MOBBS OCD

AUG 0 5 2013

30-025-41316

OXY USA Inc Corbin South Federal #1 SHL: 830 FNL & 400 FWL, Section: 9, T.18S., R.33E. BHL: 830 FNL & 400 FWL, Section: 9, T.18S., R.33E.

# RECEIVED Surface Use Plan of Operations

# Introduction

The following surface use plan of operations will be followed and carried out once the APD is approved. No other disturbance will be created other than what was submitted in this surface use plan. If any other surface disturbance is needed after the APD is approved, a BLM approved sundry notice or right of way application will be acquired prior to any new surface disturbance.

Before any surface disturbance is created, stakes or flagging will be installed to mark boundaries of permitted areas of disturbance, including soils storage areas. As necessary, slope, grade, and other construction control stakes will be placed to ensure construction in accordance with the surface use plan. All boundary markers will be maintained in place until final construction cleanup is completed. If disturbance boundary markers are disturbed or knocked down, they will be replaced before construction proceeds.

If terms and conditions are attached to the approved APD and amend any of the proposed actions in this surface use plan, we will adhere to the terms and conditions.

# **1. Existing Roads**

a. The existing access road route to the proposed project is depicted on PAP MAP. Improvements to the driving surface will be done where necessary. No new surface disturbance will be done, unless otherwise noted in the New or Reconstructed Access Roads section of this surface use plan.

b. The existing access road route to the proposed project does cross lease boundaries and a BLM road right-of-way will be acquired from the BLM prior to construction activities.

c. Existing oil and gas roads utilized to access the proposed project will be maintained by blade, water & repair as required/needed. All existing structures on the entire access route such as cattleguards, other range improvement projects, culverts, etc. will be properly repaired or replaced if they are damaged or have deteriorated beyond practical use.

c. Existing oil and gas roads utilized to access the proposed project will be maintained by blade, water & repair as required/needed. All existing structures on the entire access route such as cattleguards, other range improvement projects, culverts, etc. will be properly repaired or replaced if they are damaged or have deteriorated beyond practical use.

# 2. New or Reconstructed Access Roads

a. An access road will be needed for this proposed project. See the survey plat for the location of the access road.

b. The length of access road needed to be constructed for this proposed project is about 17 feet.

c. The maximum driving width of the access road will be 15 feet. The maximum width of surface disturbance when constructing the access road will not exceed 25 feet. All areas outside of the driving surface will be revegetated.

d. The access road will be constructed with 6 inches of compacted caliche.

e. The proposed access road will be constructed to BLM Gold Book standards and/or BLM CFO specifications.

f. The access road will be constructed with a ditch on each side of the road.

g. The maximum grade for the access road will be 1 percent.

h. No turnouts will be constructed on the proposed access road.

Page 1 of 6

# AUG 1 3 2013

i. No cattleguards will be installed for this proposed access road.

j. No BLM right-of-way grant is needed for the construction of this access road.

k. No culverts will be constructed for this proposed access road.

1. No low water crossings will be constructed for the access road.

m. Since the access road is on level ground, no lead-off ditches will be constructed for the proposed access road.

n. Newly constructed or reconstructed roads, on surface under the jurisdiction of the Bureau of Land Management, will be constructed as outlined in the BLM "Gold Book" and to meet the standards of the anticipated traffic flow and all anticipated weather requirements as needed. Construction will include ditching, draining, crowning and capping or sloping and dipping the roadbed as necessary to provide a well-constructed and safe road.

# 3. Location of Existing Wells

a. One Mile Radius map of the APD depicts all known wells within a one mile radius of the proposed well.

b. There is no other information regarding wells within a one mile radius.

### 4. Location of Existing and/or Proposed Production Facilities

a. All permanent, lasting more than 6 months, above ground structures including but not limited to pumpjacks, storage tanks, meter housing that are not subject to safety requirements will be painted a non-reflective paint color that blends in with the surrounding landscape. The paint color will be one of the colors from the BLM Standard Environmental Colors chart selected by the BLM authorized officer.

b. All proposed production facilities that are located on the well pad will be strategically placed to allow for maximum interim reclamation, recontouring, and revegetation of the well location.

c. A production facility is proposed to be installed on the proposed well location. Production from the well will be processed on site in the production facility. FLEX 3 RIG DIAGRAM depicts the location of the production facilities as they relate to the well and well pad.

d. The proposed production facility will have a secondary containment structure that is constructed to hold the capacity of 1-1/2 times the largest tank, plus freeboard to account for percipitation, unless more stringent protective requirements are deemed necessary.

If any plans change regarding the production facility or other infrastructure (pipeline, electric line, etc.), we will submit a sundry notice or right of way (if applicable) prior to installation of construction.

### Electric Line(s)

a. An electric line will be applied for through a sundry notice or BLM right of way at a later date.

# 5. Docation and Types of Water

a. The source and location of the water supply are as follows: This well will be drilled using a combination of water mud systems. It will obtained from commercial water stations in the area.

b. Water will be transported to location by truck, using existing and proposed roads.

# **6.** Construction Materials

a. Construction material that will be used to build the well pad and road will be caliche.

b. You, the operator must provide a map or plat or description depicting the location of the source of construction material.

c. The location of the source of construction material that will be used to construct the proposed project is located will be obtained from an existing BLM approved pit or from prevailing deposits found under the location.

# 7. Methods for Handling Waste

a. Drilling fluids and produced oil and water from the well during completion operations will be stored safely and disposed of properly in an NMOCD approved diposal facility.

b. Garbage and trash produced during drilling and completion operations will be collected in a trash bin and disposed of properly at a state approved site. All trash on and around the well site will be collected for disposal.

c. Human waste and grey water will be properly contained and disposed of properly at a disposal facility.

d. After drilling and completion operations, trash, chemicals, salts, frac sand and other waste material will be removed and disposed of properly at a disposal site.

e. The well will be drilled utilizing a closed loop system. Drill cutting will be properly disposed of into steel tanks and taken to an NMOCD approved disposal facility.

# 8. Ancillary Facilities

a. No ancillary facilities will be needed for this proposed project.

# 9. Well Site Layout

a. Make sure that the survey plat or other diagrams have the following necessary information for the BLM:

- i. reasonable scale (near 1":50')
- ii. well pad dimensions
- iii. well pad orientation
- iv. drilling rig components
- v. proposed access road
- vi. elevations of all points
- vii. topsoil stockpile
- viii. reserve pit location/dimensions if applicable
- ix. other disturbances needed (flare pit, stinger, frac farm pad, etc.)
- x. existing structures within a 600' x 600' area (pipelines, electric lines, well pads, etc.)

b. The proposed drilling pad was staked and surveyed by a professional surveyor. The attached survey plat of the well site depicts the drilling pad layout as staked.

c. A title of a well site diagram is FLEX 3 RIG DIAGRAM. This diagram depicts the reclaimed area, dimensions of pad.

d. Topsoil Salvaging

i. Grass, forbs, and small woody vegetation, such as sagebrush will be excavated as the topsoil is

removed.Large woody vegetation will be stripped and stored separately and respread evently on the site following topsoil respreading.Topsoil depth is defined as the top layer of soil that contains 80% of the roots. In areas to be heavily disturbed, the top 6 inches of soil material, will be stripped and stockpiled on the perimeter of the well location and along the perimeter of the access road to control run-on and run-off, to keep topsoil viable, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil should include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils. Contaminated soil will not be stockpiled, but properly treated and handled prior to topsoil salvaging.

# **10. Plans for Surface Reclamation**

#### a. Reclamation Objectives

i. The objective of interim reclamation is to restore vegetative cover and a portion of the landform sufficient to maintain healthy, biologically active topsoil; control erosion; and minimize habitat and forage loss, visual impact, and weed infestation, during the life of the well or facilities. The long-term objective of final reclamation is to return the land to a condition approximating that which existed prior to disturbance. This includes restoration of the landform and natural vegetative community, hydrologic systems, visual resources, and wildlife habitats. To ensure that the long-term objective will be reached through human and natural processes, actions will be taken to ensure standards are met for site stability, visual quality, hydrological functioning, and vegetative productivity.

ii. The BLM will be notified at least 3 days prior to commencement of any reclamation procedures.

iii. If circumstances allow, interim reclamation and/or final reclamation actions will be completed no later than 6 months from when the final well on the location has been completed or plugged. We will gain written permission from the BLM if more time is needed.

#### iv.Interim Reclamation

1. Interim reclamation will be performed on the well site after the well is drilled and completed. FLEX 3 RIG DIAGRAM depicts the location and dimensions of the planned interim reclamation for the well site.

2. Within 30 days of well completion, the well location and surrounding areas will be cleared of, and maintained free of, all materials, trash, and equipment not required for production.

3. In areas planned for interim reclamation, all the surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.

4. The areas planned for interim reclamation will then be recontoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Where applicable, the fill material of the well pad will be backfilled into the cut to bring the area back to the original contour. The interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be recontoured to the above ratios during interim reclamation.

5. Topsoil will be evenly respread and aggressively revegetated over the entire disturbed area not needed for all-weather operations including cuts & fills. To seed the area, the proper BLM seed mixture, free of noxious weeds, will be used. Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.

6. Proper erosion control methods will be used on the area to control erosion, runoff and siltation of the surrounding area.

7. The interim reclamation will be monitored periodically to ensure that vegetation has reestablished and that erosion is controlled.

#### Diffinal Reclamation (well pad, buried pipelines, etc.)

1. Prior to final reclamation procedures, the well pad, road, and surrounding area will be cleared of material, trash, and equipment.

2. All surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.

3. All disturbed areas, including roads, pipelines, pads, production facilities, and interim reclaimed areas will be recontoured to the contour existing prior to initial construction or a contour that blends indistinguishably with the surrounding landscape. Topsoil that was spread over the interim reclamation areas will be stockpiled prior to recontouring. The topsoil will be redistributed evenly over the entire disturbed site to ensure successful revegetation.

4. After all the disturbed areas have been properly prepared, the areas will be seeded with the proper BLM seed mixture, free of noxious weeds. Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.

5. Proper erosion control methods will be used on the entire area to control erosion, runoff and siltation of the surrounding area.

6. All unused equipment and structures including pipelines, electric line poles, tanks, etc. that serviced the well will be removed.

7. All reclaimed areas will be monitored periodically to ensure that revegetation occurs, that the area is not redisturbed, and that erosion is controlled.

# **11. Surface Ownership**

a. The surface ownership of the proposed project is Fee.

- 1. Surface Owner: Ross Caviness
  - **Phone Number:** (000) 000-0000

Address: 3718 NM 114 Causey, NM 88113

a. A surface use agreement was obtained from the private surface owner regarding the proposed project.

b. A good faith effort was made to provide a copy of the APD Surface Use Plan of Operations to the private surface owner.

# **12.** Other Information

a. No other information is needed at this time.

### 13. Maps and Diagrams

PAP MAP - Existing Road One Mile Radius map - Wells Within One Mile FLEX 3 RIG DIAGRAM - Production Facilities Diagram FLEX 3 RIG DIAGRAM - Well Site Diagram \_

SHL: 830 FNL & 400 FWL, Section: 9, T.18S., R.33E. BHL: 830 FNL & 400 FWL, Section: 9, T.18S., R.33E.


\_\_\_\_


FLEX 3 RIG DIAGRAM - Interim Reclamation

#### **OPERATOR CERTIFICATION**

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this

Name:Anthony D'Addieco
Position:Reservoir Management Team Leader
Address:5 Greenway Plaza, Suite 110, Houston, TX 77046
Telephone:713-350-4964
E-mail: (optional):Anthony_DAddieco@oxy.com
Company:Occidental Permian LP / OXY USA Inc / OXY USA WTP LP
Field Representative (if not above signatory):Dusty Weaver
Address (If different from above): _P.O. Box 50250 Midland, TX 79710
Telephone (if different from above):432-685-5723
E-mail (if different from above):calvin_weaver@oxy.com





.

VICINITY MAP

	······	<u>.</u>											
State of the second	5 U.S. H	Y 82	3	2	1	6	5	4	3	2		6	
	8	s at	240 K 10	11	12	7	8	5	10	11	12	7	
MA 18	LJAN 17		15	14	13 E H	2	17	16	15	14	13 et	14 17 18	
21 25 19 21	20	21 CONOCO	22	23	145 CP	19 19	HANN LIFE	NUMMIN BIRD	22	22 DERET	24	0K P. 4. 19	
30 ST. 529	29	28 1	27	26	25	30	29	ET IN	27	26	25	30	
31	32	33	34	35 ST. 529	36	31	ADIG LANK	33	34	35	36	a	
6	5	AAL JAMAS	3	2	1	5	5		3 • • 57	5	1	6	
7	ß	9	10	"	12 CORBIN S	, OUTH FE	в D. #1	9	10	1 65	DUEREGUIN	Ren ,	
ណ ល្អ 18 ភា	17	16	15	14	រេ ខ្ល	20 20 20 20 20 20 20 20 20 20 20 20 20 2	17	16	15	14	13	18	
5 MAR	92 92 14	21	22	23	24	19	20	21	22	23	24 #	स १९ २८ १९	
20 20	25	26	27	26	25	- 30	29	26	27	26	25	30	
31	35	33	34	35	36	31	32	33	34	35	36	31	
6	5	4	3	2	1	5	5	4	з	5	1	6	
SEC. 9TWP. 18-SRGE. 33-ESCALE: 1" = 2 MILESSURVEYN.M.P.M.COUNTYLEADESCRIPTION 830' FNL & 400' FWLAsel Surveying													
	TION TOR		<u>950.4'</u> USA IN	IC.		P.O. BOX 393 - 310 W. TAYLOR							

OPERATOR \_\_\_\_ OXY USA INC.

LEASE CORBIN SOUTH FED. #1

DIRECTIONS BEGINNING AT THE INTERSECTION OF HWY. #529 AND COUNTY ROAD #125 (DOG LAKE ROAD), GO SOUTHEAST ON HWY. #529 FOR 0.9 MILES, TURN RIGHT ON CALICHE ROAD AND GO SOUTH FOR 0.8 MILES, TURN LEFT AND GO EAST FOR 0.3 MILES, TURN RIGHT AND GO SOUTH FOR 0.3 MILES, TURN RIGHT AND GO WEST FOR 0.5 MILES, TURN RIGHT ON PROPOSED ROAD AND GO NORTH FOR 17.0 FEET TO LOCATION.

P.O. BOX 393 - 310 W. TAYLOR HOBBS, NEW MEXICO - 575-393-9146

