

HOBBS OCD

SEP 20 2013

OCD Hobbs

Form 3160-3  
(March 2012)FORM APPROVED  
OMB No. 1004-0137  
Expires October 31, 2014UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT


## APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		7. If Unit or CA Agreement, Name and No.
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		8. Lease Name and Well No. <b>&lt;40063&gt;</b> CORBIN SOUTH FEDERAL COM #2
2. Name of Operator OXY USA INC		9. API Well No. <b>30-025-41424</b>
3a. Address P.O. BOX 4294 HOUSTON, TX 77210	3b. Phone No. (include area code) <b>&lt;16696&gt;</b> 713-513-6640	10. Field and Pool, or Exploratory <b>&lt;13320&gt;</b> CORBIN; WOLFCAMP, SOUTH
4. Location of Well (Report location clearly and in accordance with any State requirements.) At surface 1900' FSL & 800' FWL At proposed prod. zone		11. Sec., T. R. M. or Blk. and Survey or Area L, SEC 9; T18S, R33E
14. Distance in miles and direction from nearest town or post office* 37 MILES SOUTHEAST OF LOVINGTON, NM		12. County or Parish LEA
15. Distance from proposed* location to nearest property or lease line, ft. 800' (Also to nearest drig. unit line, if any)		13. State NM
16. No. of acres in lease 280	17. Spacing Unit dedicated to this well 80.47	
18. Distance from proposed location* 1180' to nearest well, drilling, completed, applied for, on this lease, ft.	19. Proposed Depth 12000' MD / 12000' TVD	20. BLM/BIA Bond No. on file ESB000226 / NMB000862
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3926.9' GL	22. Approximate date work will start* 01/02/2014	23. Estimated duration 20 DAYS

## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification   |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

25. Signature 	Name (Printed/Typed) Jennifer Duarte (jennifer_duarte@oxy.com)	Date 04/22/2013
Title Regulatory Specialist		
Approved by (Signature) <b>JS/ STEPHEN J. CAFFEY</b>	Name (Printed/Typed)	Date <b>SEP 17 2013</b>
Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 18 U.S.C. Section 1012 make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)  
Capitan Controlled Water Basin

SEE ATTACHED FOR  
CONDITIONS OF APPROVALApproval Subject to General Requirements  
& Special Stipulations Attached

PM  
SEP 26 2013

**OXY USA Inc**  
**Corbin South Federal #2**  
**APD Data**

HOBBS OGD

SEP 20 2013

RECEIVED

OPERATOR NAME / NUMBER: OXY USA Inc

LEASE NAME / NUMBER: Corbin South Federal #2

STATE: NM

COUNTY: Lea

SURFACE LOCATION: 1900' FSL & 800' FWL, Sec 9, T18S, R33E

C-102 PLAT APPROX GR ELEV: 3926.9' EST KB ELEV: 3950.9' (24' KB)

**1. GEOLOGIC NAME OF SURFACE FORMATION**

a. Permian

**2. ESTIMATED TOPS OF GEOLOGICAL MARKERS & DEPTHS OF ANTICIPATED FRESH WATER, OIL OR GAS**

Formation Tops	TV Depth To	Expected Fluid
Rustler	1502	--
Salado (T. Salt)	1597	--
Tansill (B. Salt)	2692	--
T. Yates	3057	--
T. Seven Rivers	3422	Poss Oil
T. Queen	4232	Poss Oil
Cherry Canyon	5297	Oil/Gas
Brushy Canyon	5847	Oil/Gas
T. BSPG1 Limestone	6802	Oil/Gas
T. BSPG 1st Sand	8407	Oil/Gas
T. BSPG2 Limestone	8702	Oil/Gas
T. BSPG 2nd Sand	9077	Oil/Gas
T. BSPG3 Limestone	9602	Oil/Gas
T. BSPG 3rd Sand	9862	Oil/Gas
T. Wolfcamp	10167	Oil/Gas
T. WFMP Upper Interval	10902	Oil/Gas
T. WFMP Lower Interval	11427	Oil/Gas
TD	12000	Oil/Gas

Fresh water may be encountered above the Rustler formation. Surface casing will be set below the top of the Rustler to protect it.

**GREATEST PROJECTED TD** 12000' MD/ 12000' TVD **OBJECTIVE:** Wolfcamp

**3. CASING PROGRAM**

Surface Casing: 13.375" casing set at ± 1535' MD/1535' TVD in a 17.5" hole filled with 8.90 ppg mud

Interval	Length	Wt	Gr	Cplg	Coll Rating (psi)	Burst Rating (psi)	Jt Str (M-lbs)	ID (in)	Drift (in)	SF Coll	SF Burst	SF Ten
0'-1535'	1535'	48	H-40	ST&C	770	1730	322	12.715	12.557	1.21	1.66	1.85

Intermediate Casing: 9.625" casing set at 3100' MD / 3100' TVD in a 12.25" hole filled with 10 ppg mud

Interval	Length	Wt	Gr	Cplg	Coll Rating (psi)	Burst Rating (psi)	Jt Str (M-lbs)	ID (in)	Drift (in)	SF Coll	SF Burst	SF Ten
0'-3100'	3100'	36	J-55	LT&C	2020	3520	453	8.84	8.75	1.35	1.29	2.14

Production Casing: 5.5" casing set at  $\pm$  12000' MD / 12000' TVD in a 8.75" hole filled with 9.0 ppg mud

Interval	Length	Wt	Gr	Cplg	Coll Rating (psi)	Burst Rating (psi)	Jt Str (M-lbs)	ID (in)	Drift (in)	SF Coll	SF Burst	SF Ten
0' - 12000'	12000'	17	L-80	BT&C	6290	7740	338	4.892	4.767	1.18	1.41	1.69

Note: All Casing is in new condition

### **Casing Design Assumptions:**

#### **Burst Loads**

##### **CSG Test (Surface)**

- Internal: Displacement fluid + 70% CSG Burst rating
- External: Pore Pressure from section TD to surface

##### **CSG Test (Intermediate)**

- Internal: Displacement fluid + 70% CSG Burst rating
- External: Pore Pressure from the Intermediate hole TD to Surface CSG shoe and MW of the drilling mud that was in the hole when the CSG was run to surface

##### **CSG Test (Production)**

- Internal: Displacement fluid + 80% CSG Burst rating
- External: Pore Pressure from the well TD the Intermediate CSG shoe and MW of the drilling mud that was in the hole when the CSG was run to surface

##### **Gas Kick (Surface/Intermediate)**

- Internal: Gas Kick based on Pore Pressure or Fracture Gradient @ CSG shoe with a gas 0.115psi/ft Gas gradient to surface while drilling the next hole section (e.g. Gas kick while drilling the production hole section is a burst load used to design the intermediate CSG)
- External: Pore Pressure from section TD to previous CSG shoe and MW of the drilling mud that was in the hole when the CSG was run to surface

##### **Stimulation (Production)**

- Internal: Displacement fluid + Max Frac treating pressure (not to exceed 80% CSG Burst rating)
- External: Pore Pressure from the well TD to the Intermediate CSG shoe and 8.5 ppg MWE to surface

#### **Collapse Loads**

##### **Lost Circulation (Surface/Intermediate)**

- Internal: Losses experienced while drilling the next hole section (e.g. losses while drilling the production hole section are used as a collapse load to design the intermediate CSG). After losses there will be a column of mud inside the CSG with an equivalent weight to the Pore Pressure of the lost circulation zone
- External: MW of the drilling mud that was in the hole when the CSG was run

##### **Cementing (Surface/Intermediate/Production)**

- Internal: Displacement Fluid
- External: Cement Slurries to TOC, MW to surface

##### **Full Evacuation (Production)**

- Internal: Atmospheric Pressure
- External: MW of the drilling mud that was in the hole when the CSG was run

## Tension Loads

### Running CSG (Surface/Intermediate/Production)

- Axial load of the buoyant weight of the string plus either 100 klb over-pull or string weight in air, whichever is less

### Green Cement (Surface/Intermediate/Production)

- Axial load of the buoyant weight of the string plus the cement plug bump pressure (Final displacement + 500 psi)

Burst, Collapse and Tensile SF are calculated using Landmark's Stress Check (Casing Design) software.

## 4. CEMENT PROGRAM:

### Surface Interval

Interval	Amount sx	Ft of Fill	Type	Gal/Sk	PPG	Ft <sup>3</sup> /sk	24 Hr Comp
<b>Surface (TOC: 0' - 1535') See COA</b>							
<b>Lead:</b> 0' - 1408' (165% Excess)	1520	1408	Premium Plus cement with 2% Calcium Chloride, 4% Bentonite, 0.125 lbm/sl Poly-E-Flake	9.18	13.5	1.75	589 psi
<b>Tail:</b> 1408' - 1535' (165 % Excess)	200	127	Premium Plus cement with 94 lbm/sk Premium Plus Cement, 2% Calcium Chloride	6.39	14.80	1.35	1608 psi

### Intermediate Interval

Interval	Amount sx	Ft of Fill	Type	Gal/Sk	PPG	Ft <sup>3</sup> /sk	24 Hr Comp
<b>Intermediate (TOC: 0' - 3100') See COA</b>							
<b>Lead:</b> 0' - 2710' (105% Excess)	880	2710'	Light Premium Plus Cement, with 5% Salt, 3lb-sk Kol Seal, 0.125 lb/sk Poly-E-Flake	9.68	12.9	1.87	840 psi
<b>Tail:</b> 2710' - 3100' (105 % Excess)	200	390'	Premium Plus cement with 1% Calcium Chloride	6.36	14.80	1.34	2125 psi

### Production Interval

Interval	Amount sx	Ft of Fill	Type	Gal/Sk	PPG	Ft <sup>3</sup> /sk	24 Hr Comp
<b>Production (TOC: 2600' - 11500') Single Stage See COA</b>							
<b>Lead:</b> 2600' - 6800' (100% Excess)	800	4200'	Premium Cement, 14.8 lb/sk Silicalite 50/50 Blend, 16 lb/sk Scotchlite HGS-6000, 2 lb/sk Kol-Seal, 0.5 lb/sk CFR-3, 0.15 lb/sk WG-17, 1 lb/sk Cal-Seal 60, 1.5 lb/sk Salt.	9.79	10.80	2.39	520 psi
<b>Tail:</b> 6800' - 12000' (50% Excess)	1090	5200'	Super H Cement, 3 lbm/sk Kol-Seal, 3 lbm/sk Salt, 0.125 lbm/sk Poly-E-Flake, 0.2 % and HR-601, & 0.5% Halad-344, 0.4% CFR 3.	8.40	13.2	1.66	1750 psi

**Cement Additives:** \*Bentonite (light weight additive), Calcium Chloride (accelerator), Halad-344 (low fluid loss control), HR-601 (retarder), Kol-Seal (lost circulation additive), Salt (salt), Poly-E-Flake (lost circulation additive), Silicalite (Additive Material), CFR-3 (Dispersant), Scotchlite HGS 6000 (Light Weight Additive), WG-17 (Gelling Agent), Cal-Seal 60 (Accelerator)

## 5. PRESSURE CONTROL EQUIPMENT

Surface: 1535'. None.

Intermediate and Production: 3100' -- 12000'. Intermediate and Production hole will be drilled with a 13-5/8" 10M three ram stack with a 5M annular preventer and a 5M Choke Manifold.

- See COA
- All BOP's and associated equipment will be tested in accordance with Onshore Order #2 (250/5000 psi on rams for 10 minutes each and 250/3500 for 10 minutes for annular preventer, equal to 70% of working pressure) with a third party BOP testing service before drilling out the surface casing shoe. A Multibowl wellhead system will be used in this well therefore the BOPE test will cover the test requirements for the Intermediate and Production sections.
  - The Surface and Intermediate casings strings will be tested to 70% of their burst rating for 30 minutes. This will also test the seals of the lock down pins that hold the pack-off in place in the Multibowl wellhead system.
  - Pipe rams will be function tested every 24 hours and blind rams will be tested each time the drill pipe is out of the hole. These functional tests will be documented on the daily driller's log. A 2" kill line and 3" choke line will be accommodated on the drilling spool below the ram-type BOP.
  - The BOPE test will be repeated within 21 days of the original test, on the first trip, if drilling the intermediate or production section takes more time than planned.
  - Other accessory BOP equipment will include a Kelly cock, floor safety valve, choke lines, and choke manifold having a 5000 psi working pressure rating and tested to 5000 psi.
  - The Operator also requests a variance to connect the BOP choke outlet to the choke manifold using a co-flex hose manufactured by Contitech Rubber Industrial KFT. It is a 3" ID x 35' flexible hose with a 10,000 psi working pressure. It has been tested to 15,000 psi and is built to API Spec 16C. Once the flex line is installed it will be tied down with safety clamps (certifications attached).
  - BOP & Choke manifold diagrams attached.
- See COA

## 6. MUD PROGRAM:

See COA

Depth	Mud Wt ppg	Vis Sec	Fluid Loss	Type System
0 - 1535' <sup>1560'</sup> <del>2950'</del>	8.4 - 8.9	32 - 34	NC	Fresh Water /Spud Mud
1535' - 3100'	10.0-10.2	28 - 29	NC	Brine Water
3100' - 8000'	8.6 - 8.8	28 - 29	NC	Fresh Water
8000' - TD'	9.0 - 9.2	40 - 50	8 - 15	Salt Gel/Duo Vis

Remarks: Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times.

Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal isolation.

## 7. AUXILIARY WELL CONTROL AND MONITORING EQUIPMENT

- A full opening drill pipe stabbing valve having the appropriate connections will be on the rig floor unobstructed and readily accessible at all times.

## 8. POTENTIAL HAZARDS:

- See COA
- H2S detection equipment will be in operation after drilling out the surface casing shoe until the production casing has been cemented. Breathing equipment will be on location from drilling out the surface shoe until production casing is cemented. If H2S is encountered the operator will comply with Onshore Order #6.

- b. No abnormal temperatures or pressures are anticipated. The highest anticipated pressure gradient is 0.46 psi/ft. Maximum anticipated bottom hole pressure is between 5300 and 5400 psi.
- c. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. Adequate flare lines will be installed off the mud/gas separator where gas may be flared safely.

## **9. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS**


Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon as possible after BLM approval and as soon as a rig will be available. Move in operations and drilling is expected to take 35 days. If production casing is run, then an additional 30 days will be needed to complete the well and construct surface facilities and/or lay flow lines in order to place well on production.

## **10. WIRELINE LOGGING / MUD LOGGING / LWD**

- a. Run wireline – Triple Combo
  - 1. GR, Den, Neu, Res, Sonic from TD to base of intermediate casing.
  - 2. GR, Neutron from TD to surface
- b. Mud loggers to be rigged up from base of intermediate casing to TD

## **COMPANY PERSONNEL:**

<b><u>Name</u></b>	<b><u>Title</u></b>	<b><u>Office Phone</u></b>	<b><u>Mobile Phone</u></b>
Carlos Mercado	Drilling Engineer	(713)366-5418	(281) 455-3481
Sebastian Millan	Drilling Engineer Supervisor	(713)350-4950	(832)528-3268
Roger Allen	Drilling Superintendent	(713)215-7617	(281)682-3919
Oscar Quintero	Drilling Manager	(713)985-6343	(713)689-4946



#### LEGEND

- ① - 13 5/8\"-10M FLANGED END DATE VALVE
- ② - 13 5/8\"-10M FLANGED END DATE VALVE WITH 1\"-5/8\" NPT ADAPTER
- ③ - 13 5/8\"-10M FLANGED END DATE VALVE
- ④ - 13 5/8\"-10M FLANGED END CHECK VALVE
- ⑤ - 13 5/8\"-10M FLANGED END CHECK VALVE

SHAFER ROTATED-COVER SPHERICAL  
ANNULAR PREVENTER (API 16A  
MONOGRAMMED, 13 5/8\"-10M W-2),  
10M BOTTOM FLANGE & 5V  
STUDDED TOP (WEIGHT = 4,200  
LBS WITH SHAFER API 16A HOT  
OIL RESISTANT ADAPTOR/STILE  
ELEVATOR)

CAMERON 10M DOUBLE  
RAM-TYPE PREVENTER (API 16A  
MONOGRAMMED, 13 5/8\"-10M W-2)  
WITH 5\" CAMERON PIPE  
RAMS (CAMERON FRONT PADLOCKS  
& TOP SEALS) IN TOP CAVITY  
AND CAMERON 25 SHEARING  
RAMS IN BOTTOM CAVITY.  
BOTTOM FLANGE & STUDDED  
TOP (WEIGHT = 21,100 LBS.  
WITH RAMS)

13 5/8\"-10M W-2  
CAMERON DRILLING SPOOL  
(API 16A MONOGRAMMED)  
STUDDED TOP & FLANGED BOTTOM  
WITH 4 1/16\"-10M W-2 FLANGED OUTLETS  
(WEIGHT APPROXIMATELY 8,000 LBS.)


CAMERON 10M DOUBLE RAM-TYPE  
PREVENTER (API 16A  
MONOGRAMMED, 13 5/8\"-10M W-2)  
WITH 5\" CAMERON PIPE RAMS  
(CAMERON FRONT PADLOCKS & TOP  
SEALS) BOTTOM FLANGE &  
STUDDED TOP  
(WEIGHT = 10,000 LBS.)

H&P FURNISHED  
13 5/8\"-10M x 13 5/8\"-5M  
ADAPTER SPOOL 2\"-0\" LONG

### 13 5/8\"-10M BOP STACK WITH 13 5/8\"-5M ANNULAR

#### PROPRIETARY

THIS DRAWING AND THE LEGEND AND INFORMATION PROVIDED  
HEREIN ARE THE PROPERTY OF HELMERICH & PAYNE INTERNATIONAL  
DRILLING CO. AND ARE NOT TO BE REPRODUCED OR TRANSMITTED  
IN ANY FORM OR BY ANY MEANS, WITHOUT THE PRIOR WRITTEN  
CONSENT OF A SUFFICIENTLY AUTHORIZED REPRESENTATIVE OF  
HELMERICH & PAYNE INTERNATIONAL DRILLING CO.











ISSUED FOR  
FABRICATION  
December-18-2007  
DRAFTSMAN  
ENGINEER


API 16A MONOGRAMMED ANNULAR, CHECK AND KILL  
VALVE ASSEMBLIES ARE NOT SHOWN FOR  
CLARITY

WEIGHTS DO NOT INCLUDE HOSES, ADAPTER SPOOLS  
OR GUY CONNECT FITTINGS

**HELMERICH & PAYNE**  
INTERNATIONAL DRILLING CO.


EXCISEMENT INVOICES			DATE	TITLE		
				13 5/8"-10M BOP 3 RAM STACK		
				FLEXRIGS		
	12-12-07	ISSUED SHEET 01	JAV	CUSTOMER: H&M		
	12-12-07	REVISIONS: 1. 13 5/8"-10M BOP 3 RAM STACK	JRC	PROJECT: FLEXRIGS		
	12-12-07	2. 13 5/8"-10M BOP 3 RAM STACK	JRC	PERSON: MTS		
	12-12-07	3. 13 5/8"-10M BOP 3 RAM STACK	JRC	DATE: 12-12-07	ISS: 01	REV: 01
	12-12-07	4. 13 5/8"-10M BOP 3 RAM STACK	JRC	SCALE: 1/4"=1'		
	12-12-07	5. 13 5/8"-10M BOP 3 RAM STACK	JRC	SHEET: 01 OF 1		
	12-12-07	6. 13 5/8"-10M BOP 3 RAM STACK	JRC	210-P1-07		
	12-12-07	7. 13 5/8"-10M BOP 3 RAM STACK	JRC	E		

# FLEX3 STD CHOKE MANIFOLD (COMPREHENSIVE)







10M REMOTE  
KILL LINE SCHEMATIC




**Choke Manifold – Gas Separator (Top View)**



**Choke Manifold – Gas Separator (Side View)**



# **Gas Separator Routing** **Flex III Rigs**





# Coflex Hose Certification



Fluid Technology

Quality Document

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. N°: 746	
PURCHASER: Phoenix Beattie Co.			P.O. N°: 002491		
CONTITECH ORDER N°: 412638		HOSE TYPE: 3" ID Choke and Kill Hose			
HOSE SERIAL N°: 52777		NOMINAL / ACTUAL LENGTH: 10,67 m			
W.P. 68,96 MPa 10000 psi		T.P. 103,4 MPa 15000 psi		Duration: 60 min.	
<p>Pressure test with water at ambient temperature</p> <p style="text-align: center;">See attachment. (1 page)</p> <p>↑ 10 mm = 10 Min. → 10 mm = 25 MPa</p>					
COUPLINGS					
Type	Serial N°		Quality	Heat N°	
3" coupling with 4 1/16" Flange end	917	913	AISI 4130	T7998A	
			AISI 4130	26984	
INFOCHIP INSTALLED				API Spec 16 C Temperature rate: "B"	
All metal parts are flawless					
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.					
Date:  04. April. 2008	Inspector		Quality Control   Contitech Rubber Industrial Kft. Quality Control Dept. (1)		

## Coflex Hose Certification

Form No 100/12

**Phoenix Beattie Corp**

11535 Brittmoore Park Drive  
Houston, TX 77041  
Tel: (832) 327-0141  
Fax: (832) 327-0148  
E-mail: mail@phoenixbeattie.com  
www.phoenixbeattie.com

## Delivery Note

<b>Customer Order Number</b>	370-369-001	<b>Delivery Note Number</b>	003078	<b>Page</b>	1
<b>Customer / Invoice Address</b> HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		<b>Delivery / Address</b> HELMERICH & PAYNE IDC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD HOUSTON, TX 77015			

<b>Customer Acc No</b>	<b>Phoenix Beattie Contract Manager</b>	<b>Phoenix Beattie Reference</b>	<b>Date</b>
H01	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
1	HP10CK3A-35-4F1 3" 10K 16C C&K HOSE x 35ft OAL CW 4.1/16" API SPEC FLANGE E/ End 1: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange End 2: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange c/w BX155 Standard ring groove at each end Suitable for H2S Service Working pressure: 10,000psi Test pressure: 15,000psi Standard: API 16C Full specification Armor Guarding: Included Fire Rating: Not Included Temperature rating: -20 Deg C to +100 Deg C	1	1	0
2	SECK3-HPF3 LIFTING & SAFETY EQUIPMENT TO SUIT HP10CK3-35-F1 2 x 160mm ID Safety Clamps 2 x 244mm ID Lifting Collars & element C's 2 x 7ft Stainless Steel wire rope 3/4" OD 4 x 7.75t Shackles	1	1	0
3	SC725-200CS SAFETY CLAMP 200MM 7.25T C/S GALVANISED	1	1	0

Continued...

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days.  
Returns may be subject to a handling charge.

# Coflex Hose Certification

Form No 100/12



## Phoenix Beattie Corp

11535 Brittonmoore Park Drive  
Houston, TX 77041  
Tel: (832) 327-0141  
Fax: (832) 327-0148  
E-mail: [es11@phoenixbeattie.com](mailto:es11@phoenixbeattie.com)  
[www.phoenixbeattie.com](http://www.phoenixbeattie.com)

## Delivery Note

Customer Order Number	370-369-001	Delivery Note Number	003078	Page	2
Customer / Invoice Address HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		Delivery / Address HELMERICH & PAYNE IDC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD HOUSTON, TX 77015			

Customer Acc No	Phoenix Beattie Contract Manager	Phoenix Beattie Reference	Date
H01	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
4	SC725-132CS SAFETY CLAMP 132MM 7.25T C/S GALVANIZED C/W BOLTS	1	1	0
5	00CERT-HYDRO HYDROSTATIC PRESSURE TEST CERTIFICATE	1	1	0
6	00CERT-LOAD LOAD TEST CERTIFICATES	1	1	0
7	00FREIGHT INBOUND / OUTBOUND FREIGHT PRE-PAY & ADD TO FINAL INVOICE NOTE: MATERIAL MUST BE ACCOMPANIED BY PAPERWORK INCLUDING THE PURCHASE ORDER, RIG NUMBER TO ENSURE PROPER PAYMENT	1	1	0

Phoenix Beattie Inspection Signature :

Received In Good Condition : Signature


Print Name

Date


All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days. Returns may be subject to a handling charge.

Coflex Hose Certification

Page: 1/1



Conf Tech Rubber  
Industrial Kft.  
Quality Control Dept.  
(2)

[illegible][illegible][illegible][illegible][illegible][illegible][illegible]




CERTIFICATE OF CONFORMITY

**Supplier** : CONTITECH RUBBER INDUSTRIAL KFT.  
**Equipment** : 6 pcs. Choke and Kill Hose with installed couplings  
**Type** : 3" x 10,67 m WP: 10000 psi  
**Supplier File Number** : 412638  
**Date of Shipment** : April. 2008  
**Customer** : Phoenix Beattie Co.  
**Customer P.o.** : 002491  
**Referenced Standards**  
**/ Codes / Specifications** : API Spec 16 C  
**Serial No.:** 52754,52755,52776,52777,52778,52782

STATEMENT OF CONFORMITY

We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.

COUNTRY OF ORIGIN HUNGARY/EU


Signed : 

ContiTech Rubber  
Industrial Kft.  
Quality Control Dept.  
(1)

Date: 04. April. 2008


Position: Q.C. Manager

Closed Loop  
System



# OXY FLEX III PAD ( SCOMI Closed Loop System)


Level Area-No Caliche-For Offices and Living Quarters



100 ft



BILL OF MATERIAL			
ITEM	QTY	DESCRIPTION	LENGTH WEIGHT



				1. ALL STRUCTURAL MATERIAL SHALL BE ASTM - A36. 2. ALL PIPE SCH. 40 MATERIAL, SA 105 DR. B. 3. ALL FLANGES SHALL BE SCH. 150F & MATERIAL SA 105. 4. ALL FITTINGS SCH. 40 MATERIAL SHALL BE SA 105 DR. B. 5. TACK FABRICATION SHALL BE IN ACCORDANCE WITH JUNE-88.		TITLE: <b>CLOSED LOOP SYSTEM BASIC LAYOUT AND TIE IN OXY - H&amp;P - FLEX RIGS / PG 1 OF 2</b>		<b>Scom1</b> 821 N. State Street Parkway East, Suite 500, Houston, Texas 77058 PHONE: (281)-280-6515, FAX: (281)-280-6969	
THE CONTENT, INFORMATION AND DESCRIPTION ON THE DRAWING OR EXCERPT ARE THE EXCLUSIVE PROPRIETARY PROPERTY OF SCOM1 INTERNATIONAL. IT SHALL NOT BE REPRODUCED OR DISCLOSED IN ANY MANNER, IN ANY FORM, OR BY ANY MEANS, OR BY ANY INFORMATION, OR BY ANY MEANS, OR BY									