

HOBBS OCD

OCD Hobbs

14-944

Form 3160-3  
(March 2012)

AUG 22 2016

RECEIVED

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED  
OMB No. 1004-0137  
Expires October 31, 2014

5. Lease Serial No.  
SHL: NMLC071985 BHL: E066220006

6. If Indian, Allottee or Tribe Name

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.  
War Hammer 25 Federal COM 6H

9. API Well No.  
30-025- 43392

10. Field and Pool, or Exploratory  
Wolfcamp

11. Sec., T. R. M. or Blk. and Survey or Area  
Sect. 25, 26S, 32E

12. County or Parish  
Lea

13. State  
NM

1a. Type of work: ☒ DRILL ☐ REENTER

1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

2. Name of Operator

ConocoPhillips Company

3a. Address P.O. Box 51810 Midland, TX  
79710

3b. Phone No. (include area code)  
(432)688-6938

4. Location of Well (Report location clearly and in accordance with any State requirements.)\*

At surface 396' FNL & 603' FEL (NENE), Sect 25-26S- 32E

At proposed prod. zone 50' FSL & 1040' FEL (Lot 1), Sect. 36- 26S- 32E

14. Distance in miles and direction from nearest town or post office\*  
~35.6 mile SW from Jal, NM

15. Distance from proposed\*  
location to nearest  
property or lease line, ft.  
(Also to nearest drig. unit line, if any)

SHL: 396'  
BHL: 50'

16. No. of acres in lease  
NMLC 071985: 209.82  
NMLC 069515: 1080.00

17. Spacing Unit dedicated to this well  
E2E2 SEC. 25 & NENE & LOT 1 SECT. 36=  
224.99 acres

18. Distance from proposed location\*  
to nearest well, drilling, completed,  
applied for, on this lease, ft.

33'

19. Proposed Depth  
19,397' MD

20. BLM/BIA Bond No. on file  
ES0085

21. Elevations (Show whether DR, KDB, RT, GL, etc.)  
3134'

22. Approximate date work will start\*  
01/01/2016

23. Estimated duration  
30 Days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the BLM.

25. Signature

*CVB*

Name (Printed/Typed)  
Ashley Bergen

Date

7/24/15

Title

Regulatory Specialist

Approved by (Signature) *Is/George MacDone*

Name (Printed/Typed)

Date

AUG 19 2016

Title

FIELD MANAGER

Office

CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

*KX*  
*08/22/16*

Carlsbad Controlled Water Basin

Approval Subject to General Requirements  
& Special Stipulations Attached

SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

## ConocoPhillips, WAR HAMMER 25 FEDERAL COM 5H

### 1. Geologic Formations

TVD of target	12,171	Pilot hole depth	N/A
MD at TD:	19,450	Deepest expected fresh water:	300

### Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface	Water	
Base of Fresh Water	300	Water	
Rustler	736	Water	
Top of Salt / Salado	1,181	Salt	
Castile	2,981	Salt	
Delaware Top / Base Salt	4,649	Oil/Gas	Loss of Circulation
Ford Shale	4,769	Oil/Gas	
Cherry Canyon	5,652	Oil/Gas	Loss of Circulation
Brushy Canyon	7,310	Oil/Gas	Loss of Circulation
Bone Springs	8,666	Oil/Gas	Loss of Circulation
Bone Springs 3 <sup>rd</sup> Carb	10,844	Oil/Gas	
WolfCamp	11,960	Oil/Gas	
WolfCamp 1	12,171	Target Zone	
WolfCamp 2	12,891	Oil/Gas	

\*H<sub>2</sub>S, water flows, loss of circulation, abnormal pressures, etc.

### 2. Casing Program

ConocoPhillips Company respectfully requests the option to not run 10-3/4" 45.5# J-55 W511 (Flushed Connection) Casing and spare it as a contingency if the next hole section failed to support the hydrostatic column of the previous mud weight OR to Preset the 10-3/4" casing should a spudder rig become available. The intent for the casing and cementing program – Not Run 10-3/4" Casing Option is to:

- Drill the 12-3/4" or 9-7/8" hole sections with the same density mud (OBM or Saturated Brine).
- Case and cement the well with 13-3/8" surface, 7-5/8" intermediate and 5" production casing (3-strings).
- Isolate the Salt & Delaware utilizing Annulus Casing Packer and Stage Tool if necessary.
- Bring cement from 7-5/8" casing shoe to surface.
- Provided that if the hole can no longer support the hydrostatic column of the previous mud weight, a contingency plan to run the 10-3/4" casing will be the preferred if severe losses occurs during drilling the well.



**ConocoPhillips, WAR HAMMER 25 FEDERAL COM 5H**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
17.50"	0	810	13.375"	54.5	J55	BTC	2.88	6.97	19.3
12.25"	0	4,650	10.75"	45.5	J55	TenW511	**2.82	1.41	3.38
9.875"	0	11,960	7.625"	29.7	P110	BTC	1.52	1.57	3.13
6.75"	0	19,450	5.0"	18	P110	TenBLUE / TXPBTC	1.52	1.57	2.65
BLM Minimum Safety Factor							1.125	1.00	1.6 Dry 1.8 Wet

**\*\*COP Collapse Design: Mud drop to hydrostatic column equilibrium with pore pressure of the lost circulation zone.**

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	Y
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?	Y
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	



## ConocoPhillips, WAR HAMMER 25 FEDERAL COM 5H

### 3. Cementing Program

Casing	# Sk	Wt. lb/ gal	Yld ft <sup>3</sup> / sack	H <sub>2</sub> O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surf.	530	13.6	1.73	10.88	7	Lead: Class C + 4.0% Bentonite + 0.2% Anti-Foam + 2.0% CaCl <sub>2</sub> + 0.125lb/sk LCM + 0.1% Dispersant.
	310	14.8	1.35	6.39	7	Tail: Class C + 0.2% Anti-Foam + 0.1% Lost Circ Control + 2 lbs/bbl CemNET (losses Control)
Inter. 1	900	11.9	1.91	11.85	7	Lead: Class C + 8.0% Bentonite + 0.2% Anti-Foam + 0.125lb/sk LCM + 0.2% Dispersant + 0.2% Retarder + 2 lbs/bbl CemNET (losses Control).
	140	14.8	1.33	8.23	5	Tail: Class C + 0.2% Anti-Foam + 0.3% Retarder + 0.5% Extender + 2 lbs/bbl CemNET (losses Control).
DV/ECP Tool: NO						
Inter. 2	900	11.5	2.576	14.21	17	Lead: Class 'C' + 4.00% MPA-5 + 10.00 lb/sk BA-90 + 0.50% BA-10A + 0.30% CD-32 + 1.00% SMS + 1.30% R-3 + 5.00 lb/sk LCM-1 + 0.25 lb/sk Cello Flake + 0.005 gps FP-13L + 0.005 lb/sk Static Free
	115	13.5	1.41	6.337	7	Tail: Class 'C' + 0.25% MPA250 + 0.20% CD-32 + 0.20% R-3 + 5.00 lb/sk LCM-1 + 0.005 gps FP-13L + 0.005 lb/sk Static Free
	DV/ECP Tool: 4,800' (OPTIONAL)					
	410	11.5	2.576	14.21	17	Lead: Class 'C' + 4.00% MPA-5 + 10.00 lb/sk BA-90 + 0.50% BA-10A + 0.30% CD-32 + 1.00% SMS + 1.30% R-3 + 5.00 lb/sk LCM-1 + 0.25 lb/sk Cello Flake + 0.005 gps FP-13L + 0.005 lb/sk Static Free
Prod.	900	16.4	1.10	4.26	5	Tail: Class H + 1.800 gal/sk Gas Control Agent + 0.025 gal/sk Dispersant + 0.080 gal/sk Retarder + 0.030 gal/sk Anti-Foam.
	DV/ECP Tool NO'					

DV tool depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing String	TOC	% Excess
Surface	0'	>100%
Intermediate 1	0'	>100%
Intermediate 2	0'	>30%
Production	11,400'	>25%

Include Pilot Hole Cementing specs: NO PILOT HOLE.

Pilot hole depth **N/A**

KOP



## ConocoPhillips, WAR HAMMER 25 FEDERAL COM 5H

Plug top	Plug Bottom	% Excess	No. Sacks	Wt. lb/gal	Yld ft <sup>3</sup> /sack	Water gal/sk	Slurry Description and Cement Type

### 4. Pressure Control Equipment

	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
--	--

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
12-1/4"	13-5/8"	3M	Annular	x	50% of working pressure
			Blind Ram		± 1,500 psi
			Pipe Ram		
			Double Ram	x	
			Other*		
9-7/8"	13-5/8"	5M	Annular	x	50% of working pressure
			Blind Ram	x	5M
			Pipe Ram	x	
			Double Ram	x	
			Other*		
6-3/4"	13-5/8"	5M/10M	Annular	x	5M
			Blind Ram	x	10M
			Pipe Ram	x	
			Double Ram	x	
			Other*		

\*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

## ConocoPhillips, WAR HAMMER 25 FEDERAL COM 5H

<b>X</b>	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
<b>X</b>	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
<b>Y / N</b>	Are anchors required by manufacturer?
<b>X</b>	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.  <div style="text-align: center;"> <ul style="list-style-type: none"> <li>Provide description here</li> </ul> </div> See attached schematic.

### 5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	810	Spud Mud	8.6-9.3	32-36	N/C
0	4,650	Brine or OBM	8.6-10.2	28-30	≤5
0	11,960	Cut-Brine or OBM	8.6-9.2	30-40	≤5
0	19,450	Oil Base Mud	9.5-12.0	30-40	≤5

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

### 6. Logging and Testing Procedures

Logging, Coring and Testing.	
x	GR from 200' above KOP to TD (GR as part of the BHA while drilling). Not log in the lateral.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain
x	Dry samples taken 30' from intermediate 1 casing point to TD. GC Tracers KOP to TD.

Additional logs planned	Interval
Resistivity	
Density	
CBL	
Mud log	
PEX	



## ConocoPhillips, WAR HAMMER 25 FEDERAL COM 5H

### 7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	4.918 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. **Lost circulation material/sweeps/mud scavengers.**

Hydrogen Sulfide (H<sub>2</sub>S) monitors will be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

N	H <sub>2</sub> S is present
Y	H <sub>2</sub> S Plan attached

### 8. Other facets of operation

Is this a walking operation? If yes, describe. Yes, please see below.

Will be pre-setting casing? If yes, describe. Yes, please see below.

**Spudder Rig and Batch Drilling Operations:** Depending on rig availability, ConocoPhillips may pre-set the surface and the contingency intermediate casing. The reasons would be to improve time and cost savings.

Precision Drilling #822 Rig will be used to drill the surface hole and intermediate hole (to set 1st intermediate casing string). BLM will be contacted / notified 24 hours prior to commencing spudder rig operations and expected to take 10-12 days for a dual pad.

Surface casing and intermediate casing will be preset on all the wells on the same pad. Both hole sections will be drilled, cased and cemented according to casing program based on the approved permit. All casing strings will be tested in accordance to the rules and regulations per Onshore Order.

The wellhead will be nipped up and tested as soon as 13-3/8" surface casing is cut off after the applicable WOC time has been reached. Prior to drilling out the 13-3/8" surface casing, ConocoPhillips shall nipple up a 3M BOPE & choke arrangement with 5M components and test to the rated working pressure of a 3M BOPE system as it is subjected to the maximum anticipated surface pressure 1,500 psi (0.33 psi/ft pressure gradient assuming fully evacuated) per Onshore Order 2. The pressure test to MASP and 50% for annular shall be performed with a test plug after installing the 13-5/8" casing head and nipping up the 3M BOPE system prior to drilling out the 13-3/8" surface casing.

A blind flange cap of the same pressure rating as the wellhead will be secured to seal the wellbore on all casing strings. Pressure will be monitored via flanged port tied to a needle valve and pressure gauge to monitor pressures on each wellhead section and a means for intervention will be maintained while the drilling rig is not over the well.

## **ConocoPhillips, WAR HAMMER 25 FEDERAL COM 5H**

The drilling operation will re-commence with a big Drilling Rig (H&P Flex 3 rig type) and a BOP stack based on the approved permit will be nipped up and tested on the wellhead before drilling operations resumes on each well. The rig will skid between each well until each well's section has been drilled in this possible order:

1. Move-in PD822 to War Hammer 25 Federal COM 5H
2. Drill and pre-set Surface & Intermediate Casing
3. Skid to War Hammer 25 Federal COM 6H
4. Drill and pre-set Surface & Intermediate Casing
5. Move-in H&P Flex 3 rig to War Hammer 25 Federal COM 5H
6. Drill, Set & Cement Intermediate2 Casing
7. Skid to War Hammer 25 Federal COM 6H
8. Drill, Set & Cement Intermediate2 Casing
9. Drill, Set & Cement Production Casing
10. Skid to War Hammer 25 Federal COM 5H
11. Drill, Set & Cement Production Casing

Rig move in to drill will depend on rig availability and APD approval date. Once "Spudder Rigs" has performed pre-set surface and intermediate, the "Big Drilling Rig" shall return to each well to drill the remain sections per conditions of approval.



## ConocoPhillips, WAR HAMMER 25 FEDERAL COM 5H

### Attachments:

- Attachment#1: Directional Plan.
- Attachment#2: Wellbore Casing & Cementing Schematic.
- Attachment#3: Wellhead Schematic.
- Attachment #4: BOP Schematic.
- Attachment #5: Choke Schematic.
- Attachment #6: Special (Premium) Connections.
- Attachment #7: Flex Hose Documentation.
- Attachment #8: Spudder Rig Specifications.

13-5/8" 5M

13-5/8" 5M

2-1/16" 5M


2-1/16" 5M

26" OD Baseplate

20" Conductor

13-3/8" Casing

10-3/4" Casing






# Attachment #4

## BLOWOUT PREVENTER ARRANGEMENT - H&P486

5M System per Onshore Oil and Gas Order No. 2 utilizing 10M Rated Equipment




Item	Description
1	Rotating Head
2A	Fill up Line and Valve
2B	Flow Line (8")
2C	Shale Shakers and Centrifuges
2D	Cuttings Bins for Zero Discharge
2E	Mud Gas Separator with vent line to flare and return line to mud system
3	Annular Preventer (13-5/8", 5M)
4	Double Ram (13-5/8", 10M, Blind Ram bottom x Pipe Ram top)
5	Drilling Spool (13-5/8" 10M)
4C	Single Ram (13-5/8", 10M, Pipe Rams)
6	Kill Line Gate Valve, Inner (4-1/16", 10k psi WP)
7	Kill Line Gate Valve, Outer (4-1/16", 10k psi WP)
8	Kill Line Check Valve (4-1/16", 10k psi WP)
9	CoFlex Choke Line (4-1/16", 10k psi WP)
10	Choke Line Gate Valve, Inner (4-1/16", 10k psi WP)
11	Choke Line Hydraulically Operated Gate Valve, Outer, (4-1/6" 10k psi WP HCR)
12	Drilling Spool Adapter (13-5/8", 10M)

Drawn by:  
James Chen P.E.  
Drilling Engineer, ConocoPhillips Company  
Date: September 23rd, 2014

## BLOWOUT PREVENTER ARRANGEMENT

3M System per Onshore Oil and Gas Order No. 2 utilizing 3M and 5M Rated Equipment




Item	Description
1	Rotating Head, 13-5/8"
2A	Fill up Line and Valve
2B	Flow Line (10")
2C	Shale Shakers and Solids Settling Tank
2D	Cuttings Bins for Zero Discharge
2E	Rental Mud Gas Separator with vent line to flare and return line to mud system
3	Annular BOP (13-5/8", 5M)
4	Double Ram (13-5/8", 5M, equipped with Blind Rams and Pipe Rams)
5	Kill Line (2" flexible hose, 3000 psi WP)
6	Kill Line Valve, Inner (3-1/8", 3000 psi WP)
7	Kill Line Valve, Outer (3-1/8", 3000 psi WP)
8	Kill Line Check Valve (2-1/16", 3000 psi WP)
9	Choke Line (5M Stainless Steel Coflex Line, 3-1/8" 3M API Type 6B, 3000 psi WP)
10	Choke Line Valve, Inner (3-1/8", 3000 psi WP)
11	Choke Line Valve, Outer, (Hydraulically operated, 3-1/8", 3000 psi WP)
12	Spacer Spool (13-5/8", 5M)
13	Casing Head (13-5/8" 5M)
14	Ball Valve and Threaded Nipple on Casing Head Outlet, 2" 5M
15	Surface Casing

James Chen, P.E.  
 Drilling Engineer | ConocoPhillips Permian Shale  
 Office Phone 281.206.5244  
 Cell Phone 832.768.1647



# BOP LAYOUT

# RIG 822SSE



NOTE: STACK SHOWN IN VERTICAL POSITION FOR CLARITY

STACK COMPONENTS REPRESENTED ARE SUBJECT TO AVAILABILITY, PLEASE CONFIRM WITH WELL CONTROL DEPARTMENT MANAGER.



EQUIPMENT REPRESENTATION ONLY  
NOT DRAWN TO SCALE


## PRECISION DRILLING

DATE: 2015/10/05  
DWG No.: BOP-822-006  
DWG BY : CTJ

# Attachment #5

## CHOKE MANIFOLD ARRANGEMENT - HP486

10M System per Onshore Oil and Gas Order No. 2 utilizing 5M/10M Equipment



Item	Description
1	Pressure Gauge
2	2 Gate Valves, 3-1/16" 10M
3	2 Gate Valves, 3-1/16" 10M
4	2 Gate Valves, 3-1/16" 10M
5	2 Gate Valves, 3-1/16" 10M
6	Upper Manual Adjustable Choke, 4-1/16", 10M
7	Lower Manual Adjustable Choke, 4-1/16", 10M
8	Gate Valve, 3-1/16" 10M
9	Gate Valve, 3-1/16" 10M
10	Remote Controlled Hydraulic Adjustable Choke, 4-1/16", 10M
11	Gate Valve, 3-1/8" 5M
12	Gate Valve, 3-1/8" 5M
13	Gate Valve, 3-1/16" 10M


The 10M Choke Manifold & Valves will be tested to rated working pressure.

Drawn by:  
James Chen, P.E.  
Drilling Engineer, ConocoPhillips Company  
Date: June 25th-2014



## CHOKE MANIFOLD ARRANGEMENT

3M System per Onshore Oil and Gas Order No. 2 utilizing 3M and 5M Equipment



All Tees must be targeted

Item	Description
1	Manual Adjustable Choke, 2-1/16", 3M
2	Remote Controlled Hydraulically Operated Adjustable Choke, 2-1/16", 3M
3	Gate Valve, 2-1/16" 5M
4	Gate Valve, 2-1/16" 5M
5	Gate Valve, 2-1/16" 5M
6	Gate Valve, 2-1/16" 5M
7	Gate Valve, 3-1/8" 3M
8	Gate Valve, 2-1/16" 5M
9	Gate Valve, 2-1/16" 5M
10	Gate Valve, 2-1/16" 5M
11	Gate Valve, 3-1/8" 3M
12	Gate Valve, 2-1/16" 5M
13	Pressure Gauge
14	2" hammer union tie-in point for BOP Tester

We will test each valve to 3000 psi from the upstream side.

Submitted by:

James Chen

Drilling Engineer, Mid-Continent Business Unit, ConocoPhillips Company

Date: 21-March-2013

## Attachment #6

For the latest performance data, always visit our website: [www.tenaris.com](http://www.tenaris.com)

October 12 2015



**Connection:** Wedge 511™  
**Casing/Tubing:** CAS

**Size:** 10.750 in.  
**Wall:** 0.400 in.  
**Weight:** 45.50 lbs/ft  
**Grade:** J55  
**Min. Wall Thickness:** 87.5 %

## PIPE BODY DATA

GEOMETRY			
Nominal OD	10.750 in.	Nominal Weight	45.50 lbs/ft
Nominal ID	9.950 in.	Wall Thickness	0.400 in.
Plain End Weight	44.26 lbs/ft	Standard Drift Diameter	9.794 in.
		Special Drift Diameter	9.875 in.

## PERFORMANCE

Body Yield Strength	715 x 1000 lbs	Internal Yield	3580 psi
Collapse	2090 psi	SMYS	55000 psi

## WEDGE 511™ CONNECTION DATA

GEOMETRY			
Connection OD	10.750 in.	Connection ID	9.922 in.
Critical Section Area	7.671 sq. in.	Threads per in.	3.28
		Make-Up Loss	3.700 in.

## PERFORMANCE

Tension Efficiency	59.0 %	Joint Yield Strength	422 x 1000 lbs
Compression Strength	505 x 1000 lbs	Compression Efficiency	70.6 %
External Pressure Capacity	2090 psi	Internal Pressure Capacity	3360 psi
		Bending	14 °/100 ft

## MAKE-UP TORQUES

Minimum	11000 ft-lbs	Optimum	13200 ft-lbs
		Maximum (☺)	19300 ft-lbs

## OPERATIONAL LIMIT TORQUES

Operating Torque	49000 ft-lbs	Yield Torque	74000 ft-lbs
------------------	--------------	--------------	--------------

## BLANKING DIMENSIONS



October 21 2014



**Connection:** Blue®  
**Casing/Tubing:** CAS  
**Coupling Option:** REGULAR

**Size:** 5.000 in.  
**Wall:** 0.362 in.  
**Weight:** 18.00 lbs/ft  
**Grade:** P110  
**Min. Wall Thickness:** 87.5 %

**PIPE BODY DATA**

GEOMETRY			
Nominal OD	5.000 in.	Nominal Weight	18.00 lbs/ft
Nominal ID	4.276 in.	Wall Thickness	0.362 in.
Plain End Weight	17.95 lbs/ft	Standard Drift Diameter	4.151 in.
		Special Drift Diameter	N/A
PERFORMANCE			
Body Yield Strength	580 x 1000 lbs	Internal Yield	13940 psi
Collapse	13470 psi	SMYS	110000 psi

**BLUE® CONNECTION DATA**

GEOMETRY			
Connection OD	5.630 in.	Coupling Length	10.551 in.
Critical Section Area	5.275 sq. in.	Make-Up Loss	4.579 in.
		Connection ID	4.264 in.
		Threads per in.	5.00
PERFORMANCE			
Tension Efficiency	100 %	Joint Yield Strength	580 x 1000 lbs
Compression Efficiency	100 %	Compression Strength	580 x 1000 lbs
External Pressure Capacity	13470 psi	Internal Pressure Capacity	13940 psi
		Bending	101 °/100 ft

**MAKE-UP TORQUES**

Minimum	6400 ft-lbs	Target	7110 ft-lbs	Maximum	7820 ft-lbs
---------	-------------	--------	-------------	---------	-------------

**OPERATIONAL LIMIT TORQUES**

Operating Torque	ASK	Yield Torque	17600 ft-lbs
------------------	-----	--------------	--------------

**SHOULDER TORQUES**

Minimum	1070 ft-lbs	Maximum	6040 ft-lbs
---------	-------------	---------	-------------

December 18 2014



**Connection:** TenarisXP™ BTC  
**Casing/Tubing:** CAS  
**Coupling Option:** REGULAR

**Size:** 5.000 in.  
**Wall:** 0.362 in.  
**Weight:** 18.00 lbs/ft  
**Grade:** P110  
**Min. Wall Thickness:** 87.5 %

PIPE BODY DATA					
GEOMETRY					
Nominal OD	5.000 in.	Nominal Weight	18.00 lbs/ft	Standard Drift Diameter	4.151 in.
Nominal ID	4.276 in.	Wall Thickness	0.362 in.	Special Drift Diameter	N/A
Plain End Weight	17.95 lbs/ft				
PERFORMANCE					
Body Yield Strength	580 x 1000 lbs	Internal Yield	13940 psi	SMYS	110000 psi
Collapse	13470 psi				
TENARISXP™ BTC CONNECTION DATA					
GEOMETRY					
Connection OD	5.720 in.	Coupling Length	9.325 in.	Connection ID	4.264 in.
Critical Section Area	5.275 sq. in.	Threads per in.	5.00	Make-Up Loss	4.141 in.
PERFORMANCE					
Tension Efficiency	100 %	Joint Yield Strength	580 x 1000 lbs	Internal Pressure Capacity <sup>(1)</sup>	13940 psi
Structural Compression Efficiency	100 %	Structural Compression Strength	580 x 1000 lbs	Structural Bending <sup>(2)</sup>	101 °/100 ft
External Pressure Capacity	13470 psi				
ESTIMATED MAKE-UP TORQUES <sup>(3)</sup>					
Minimum	N/A ft-lbs	Target	N/A ft-lbs	Maximum	N/A ft-lbs
OPERATIONAL LIMIT TORQUES					
Operating Torque	ASK	Yield Torque	N/A ft-lbs		
BLANKING DIMENSIONS					



**RELIANCE**

Industrial Products USA, Ltd.

2030 E. 8th Street, Suite B • Greeley, CO 80631



Ph: (970) 346-3751 • Fax: (970) 353-3168 • Toll Free: (866) 771-9739

## Attachment #7

## T E S T C E R T I F I C A T E

Customer: PERCISION DRILLING  
P.O. #: 73011111  
Invoice #: 25279  
Material: 3 1/2" FIRE GUARD  
Description: 2" X 30'  
Coupling 1: FLOATING FLANGE  
" Serial:  
" Quality:  
Coupling 2: FLANGE  
" Serial:  
" Quality:  
Working Pressure : 3000  
Test Pressure: 4500  
Duration (mins): 10

Cert No.: 25279TO1  
Date: 6/29/2012



Conducted By: FLORES M.

Test Technician

- ☒ Acceptable  
☐ Not Acceptable

# Attachment #8



## Rig Inventory and Layout

**RIG 822SSE**

**Active**

Rig #	822	Rig Type	Super Single™ Electric
Superintendent	Johnny Ison	Operation Centre	Mid Continent
Category	Electric	Rig Type Code	SSE
Loads Winter (include boiler)	21	Class	Super Singles
Rated Vertical Depth (ft)	10000	Horse Power Range	1000 - 1200
Region	US Operations Group 1	Rig Locator Status	
Company	PDOS	Rig Phone Number	817-694-6797
		Plant Code	1505
Rated with Drill Pipe (in)	4 1/2		

### DRAWWORKS

Mechanical/Electric	VFD	Auxiliary Brake	N/A
Drawworks	Alta-Rig ARS-1201-AC	Rated Power (hp)	1200
Drawworks Capacity (lbs)	320000	Number of lines	8
Drawworks Drive (Quantity)	Baylor CM628TUT (AC) (1)	Rating (hp) - Each Motor	1230

### MAST

Mast Type	Single	Manufacturer	
Static Hook Load (lbs)	299000	Mast Clear Height (ft)	75'
Drill Line Size (in)	1	Number of lines	8
Drill Line SF=2 (lbs)	348300	Drill Line SF=3 (lbs)	232200

### SUBSTRUCTURE

Substructure Type	Trailer	Manufacturer	
Floor Height (ft)	10' 10" - 12' 6"	Kelly Bushing to Ground (ft)	
Clear Height (ft)	8' 6" - 10' 2"		
Rotary Capacity (lbs)	299000	Setback Capacity (lbs)	No Limitation

This Rig Type is Equipped with a Pipe Arm

### HOISTING AND ROTATING EQUIPMENT

Top Drive Model	Precision/Rostel PDCA50/70	Top Drive Capacity (tons)	150
Rotary Table Model	Slip Table	Rotary Table Capacity (lbs)	200000
		Rotary Table Clearance (in)	20-1/2
Power Wrench Model	W-N Apache 90-70	Maximum Diameter (in)	11-3/4



RIG 822SSE

## MUD PUMPS AND MUD SYSTEM

### MUD PUMP 1

Manufacturer & Model	BPMMP - BSF-1000 (Triplex)	Rated Power (hp)	1000
Stroke (in)	10		
Mud Pump Drive (Quantity)	Baylor CM628TUT (AC) (1)	Rating (hp) - Each Motor	1230

### MUD PUMP 2

Manufacturer & Model	BPMMP - BSF-1000 (Triplex)	Rated Power (hp)	1000
Stroke (in)	10		
Mud Pump Drive (Quantity)	Baylor CM628TUT (AC) (1)	Rating (hp) - Each Motor	1230

### MUD SYSTEM

Mud Tank Total Volume (bbl)	360	# of Mud Tanks	1
Premix Tank Volume (bbl)		Pill Tank Volume (bbl)	9.4
Trip Tank Volume (bbl)	15.7	TripTank Surface Area (ft <sup>2</sup> )	18.3
Centrifugal Pump Quantity:	2	Centrifugal Pump Size	5 x 6
Shale Shaker Quantity	1	Shale Shaker	Brandt King Cobra Linear Motion
Atmospheric Degasser	Single - 30 in OD 3 in Inlet 8 in Vent Line		
Additional Information			

### WELL CONTROL SYSTEM

Annular	Townsend Type-90	Pressure Rating (psi)	3000
		Size (in)	11
Rams			
Ram 1	Townsend T-82 - Single	Pressure Rating (psi)	3000
		Size (in)	11
Ram 2	Townsend T-82 - Single	Pressure Rating (psi)	3000
		Size (in)	11
Trim Type	Nace	BOP Additional Information	
Accumulator Manufacturer	E.C.S.	Remote Panel Type	Electric
Accumulator Volume (gal-US)	84	# of Stations:	5
Accumulator Pumps			
Choke Manifold Style (in)	2 x 3 x 2	Pressure Rating (psi)	3000

Well control equipment listed is rig's normal inventory. Well control equipment is subject to change; Operator should confirm current configuration and specific requirements with the Precision Drilling Contracts Representative.

RIG 822SSE

### ELECTRICAL POWER

Power Distribution Type 3 Diesel Electric Generators, each with Ross Hill 1402 Generator Bays powering 4 ABB ASC800 Drive Bays & Allen Bradley MCC

### POWER GENERATION

Power Generators					
Quantity	2	Generator Drive	CAT C-32	Generator Rating (kW)	810
Quantity	1	Generator Drive	CAT C-18	Generator Rating (kW)	545

### MISCELLANEOUS EQUIPMENT

Winterization	N/A	Boiler Rating (hp)	
Fuel Tank Qty	1	Total Fuel Tank Capacity (gal-US)	5200
Water Tank Qty	1	Total Water Tank Capacity (bbl)	375
Special Equipment	Hydraulic BOP Handler, Hydraulic Catheads, Hydraulic Catwalk, Hydraulic Pipe Arm, Power Tong, Substructure Leveling Jacks		

--	--


### NOTES

#### TUBULARS

As the selection of tubulars is dependant on the planned well program, specific requirements are to be discussed with the contracts representative of Precision Drilling. Exact quantities and descriptions of the selected tubulars are available upon request.

# RIG LAYOUT

# RIG 822SSE



**PRECISION DRILLING**

CALGARY, ALBERTA, CANADA



## Closed Loop System Design, Operating and Maintenance, and Closure Plan

ConocoPhillips Company  
Well: WAR HAMMER 25 FEDERAL COM W2 6H  
Location: Sec. 25, T26S, R32E  
Date: 7/3/2014

ConocoPhillips proposes the following plan for design, operating and maintenance, and closure of our proposed closed loop system for the above named well:

1. We propose to use a closed loop system with steel pits, haul-off bins, and frac tanks for containing all cuttings, solids, mud, water, brine, and liquids. We will not dig a pit, nor will we use a drying pad, nor will we build an earth pit above ground level, nor will we dispose of or bury any waste on location.

All drilling waste and all drilling fluids (fresh water, brine, mud, cuttings, drill solids, cement returns, and any other liquid or solid that may be involved) will be contained on location in the rig's steel pits or in haul-off bins or in frac tanks as needed. The intent is as follows:

- We propose to use the rigs' steel pits for containing and maintaining the drilling fluids.
- We propose to remove cuttings and drilled solids from the mud by using solids control equipment and to contain such cuttings and drilled solids on location in haul-off bins.
- We propose that any excess water that may need to be stored on location will be stored in tanks.

**The closed loop system components will be inspected daily by each tour and any needed repairs will be made immediately. Any leak in the system will be repaired immediately, and any spilled liquids and/or solids will be cleaned immediately, and the area where any such spill occurred will be remediated immediately.**

2. Cuttings and solids will be removed from location in haul-off bins by an authorized contractor and disposed of at an authorized facility. For this well, we propose the following disposal facility:

R-360 Inc.  
4507 West Carlsbad Hwy, Hobbs, NM 88240,  
P.O. Box 388; Hobbs, New Mexico 88241  
Toll Free Phone: 877.505.4274, Local Phone Number: 432.638.4076


The physical address for the plant where the disposal facility is located is Highway 62/180 at mile marker 66 (33 miles East of Hobbs, NM and 32 miles West of Carlsbad, NM).

The Permit Number for R-360 is NM-01-0006.

A photograph showing the type of haul-off bins that will be used is attached.

3. Mud will be transported by vacuum truck and disposed of at R-360 Inc. at the facility described above.
4. Fresh Water and Brine will be hauled off by vacuum truck and disposed of at an authorized salt water disposal well. We propose the following for disposal of fresh water and brine as needed:
  - Nabors Well Services Company, 3221 NW County Rd; Hobbs, NM 88240, PO 5208 Hobbs, NM, 88241, Permit SWD 092. (Well Location: **Section 3, T19S R37E**)
  - Basic Energy Services, P.O. Box 1869; Eunice, NM 88231 Phone Number: 575.394.2545, Facility located at Hwy 18, Mile Marker 19; Eunice, NM.

Jason Levinson  
Drilling Engineer  
Office: 281-206-5334  
Cell: 281-682-2783



**NOTES:**

- Contours shown at 2' intervals.
- May have different number of Pump Houses and Combination Buildings.

ConocoPhillips

**ConocoPhillips Company**

**WAR HAMMER 25 FEDERAL COM 6H & COM 5H  
SECTION 25, T26S, R32E, N.M.P.M.  
NE 1/4 NE 1/4**

DRAWN BY: S.F.

SCALE: 1" = 100'

REVISED: 06-25-15 T.E.

DATE: 01-27-14

REVISED: 05-23-14

**TYPICAL RIG LAYOUT**

**FIGURE #3**



Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017