

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENTNMOCD  
HobbsFORM APPROVED  
OMB NO. 1004-0135  
Expires: July 31, 2010

AUG 22 2016

**SUNDRY NOTICES AND REPORTS ON WELLS**  
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.***SUBMIT IN TRIPLICATE - Other instructions on reverse side.**5. Lease Serial No.  
NMLC063798

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.  
BOOMSLANG 14-23 FED 4H9. API Well No.  
30-025-42933-00-X110. Field and Pool, or Exploratory  
RED HILLS11. County or Parish, and State  
LEA COUNTY, NM

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator  
DEVON ENERGY PRODUCTION CO LP  
Contact: DAVID H COOK  
Email: david.cook@dvn.com3a. Address  
333 WEST SHERIDAN AVE  
OKLAHOMA CITY, OK 731023b. Phone No. (include area code)  
Ph: 405-552-78484. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
Sec 14 T24S R33E NWNE 200FNL 1930FEL

## 12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomple in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Devon Energy Production Co., L.P. respectfully requests approval to change the bottom hole location from 330 FSL & 1700 FEL, Unit O, Section 23, T24S, R33E to 330 FSL & 1895 FEL, Unit O, Section 23, T24S, R33E.

Please see the attached revised C-102, Drill Plan & Directional Survey.

**SEE ATTACHED FOR  
CONDITIONS OF APPROVAL**


14. I hereby certify that the foregoing is true and correct. <b>Electronic Submission #343587 verified by the BLM Well Information System For DEVON ENERGY PRODUCTION CO LP, sent to the Hobbs Committed to AFMSS for processing by PRISCILLA PEREZ on 07/08/2016 (16PP0873SE)</b>	
Name (Printed/Typed) DAVID H COOK	Title REGULATORY SPECIALIST
Signature (Electronic Submission)	Date 06/30/2016
<b>THIS SPACE FOR FEDERAL OR STATE OFFICE USE</b>	
Approved By	Title
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.	

**\*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\***



**SECTION 14, TOWNSHIP 24 SOUTH, RANGE 33 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
SITE MAP**

NOTE: LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1983 (NAD83). LISTED NEW MEXICO STATE PLANE EAST COORDINATES ARE GRID (NAD83). BASIS OF BEARING AND DISTANCES USED ARE NEW MEXICO STATE PLANE EAST COORDINATES MODIFIED TO THE SURFACE.



010 50 100 200

SCALE 1" = 100'

**DIRECTIONS TO LOCATION**

FROM STATE HWY. 128 AND CR. J2 (BRININSTOOL) GO NORTH ON J2 0.85 MILES, TURN RIGHT AND GO EAST 0.5 MILES, BEND LEFT AND GO NORTH 0.25 MILES, TURN RIGHT AND GO EAST 1.15 MILES TO A PROPOSED ROAD SURVEY AND FOLLOW FLAGS SOUTH 370' THEN SOUTH-SOUTHWEST 51' TO THE PROPOSED NORTHEAST PAD CORNER FOR THIS LOCATION

**DEVON ENERGY PRODUCTION COMPANY, L.P.**

**BOOMSLANG 14-23 FED 4H**


**LOCATED 200 FT. FROM THE NORTH LINE  
AND 1930 FT. FROM THE EAST LINE OF  
SECTION 14, TOWNSHIP 24 SOUTH,  
RANGE 33 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO**

**JUNE 8, 2016**

**SURVEY NO. 3463D**

**MADRON SURVEYING, INC.** 301 SOUTH CANAL (575) 234-3341 **CARLSBAD, NEW MEXICO**

SECTION 14, TOWNSHIP 24 SOUTH, RANGE 33 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
LOCATION VERIFICATION MAP



USGS QUAD MAP:  
BELL LAKE

NOT TO SCALE

DEVON ENERGY PRODUCTION COMPANY, L.P.  
**BOOMSLANG 14-23 FED 4H**  
LOCATED 200 FT. FROM THE NORTH LINE  
AND 1930 FT. FROM THE EAST LINE OF  
SECTION 14, TOWNSHIP 24 SOUTH,  
RANGE 33 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO


JUNE 8, 2016

SURVEY NO. 3463D

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO



SECTION 14, TOWNSHIP 24 SOUTH, RANGE 33 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

**DIRECTIONS TO LOCATION**

FROM STATE HWY. 128 AND CR. J2 (BRININSTOOL) GO NORTH ON J2 0.85 MILES, TURN RIGHT AND GO EAST 0.5 MILES, BEND LEFT AND GO NORTH 0.25 MILES, TURN RIGHT AND GO EAST 1.15 MILES TO A PROPOSED ROAD SURVEY AND FOLLOW FLAGS SOUTH 370' THEN SOUTH-SOUTHWEST 51' TO THE PROPOSED NORTHEAST PAD CORNER FOR THIS LOCATION

**DEVON ENERGY PRODUCTION COMPANY, L.P.**

**BOOMSLANG 14-23 FED 4H**

LOCATED 200 FT. FROM THE NORTH LINE  
AND 1930 FT. FROM THE EAST LINE OF

SECTION 14, TOWNSHIP 24 SOUTH,  
RANGE 33 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO

JUNE 8, 2016


SURVEY NO. 3463D

MADRON SURVEYING, INC. 301 SOUTH CANAL  
(575) 234-3341

CARLSBAD, NEW MEXICO



SECTION 14, TOWNSHIP 24 SOUTH, RANGE 33 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
AERIAL PHOTO



NOT TO SCALE  
AERIAL PHOTO:  
GOOGLE EARTH  
FEB. 2014

DEVON ENERGY PRODUCTION COMPANY, L.P.  
**BOOMSLANG 14-23 FED 4H**  
LOCATED 200 FT. FROM THE NORTH LINE  
AND 1930 FT. FROM THE EAST LINE OF  
SECTION 14, TOWNSHIP 24 SOUTH,  
RANGE 33 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO


JUNE 8, 2016

SURVEY NO. 3463D

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO



SECTION 14, TOWNSHIP 24 SOUTH, RANGE 33 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
AERIAL ACCESS ROUTE MAP



NOT TO SCALE  
AERIAL PHOTO:  
GOOGLE EARTH  
FEB. 2014

DEVON ENERGY PRODUCTION COMPANY, L.P.  
**BOOMSLANG 14-23 FED 4H**  
LOCATED 200 FT. FROM THE NORTH LINE  
AND 1930 FT. FROM THE EAST LINE OF  
SECTION 14, TOWNSHIP 24 SOUTH,  
RANGE 33 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO

JUNE 8, 2016

SURVEY NO. 3463D

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO



# Devon Energy, Boomslang 14-23 Fed 4H

## 1. Geologic Formations

TVD of target	11,166'	Pilot hole depth	N/A
MD at TD:	20,828'	Deepest expected fresh water:	100'

## Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Rustler	1284		
Top of Salt	1805		
Base of Salt	5231		
Delaware	5231		
Cherry Canyon	6144		
Brushy Canyon	7504		
Madera	8774		
Lower Brushy Canyon	8881		
1st BSPG Lime	9044		
Leonard	9168		
1st BSPG Sand	10103		
2nd BSPG Lime	10363		
2nd BSPG Sand	10788		
2nd BSPG Sand Target Top	11011		
2nd BSPG Sand Target Base	11116		
3rd BSPG Lime	11291		

\*H2S, water flows, loss of circulation, abnormal pressures, etc.



2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
17.5"	0	1,315' / 1,400'	13.375"	54.5	J-55	BTC	1.81	1.97	5.59
12.25"	0	4,300'	9.625"	40	J-55	LTC	1.38	1.15	1.88
12.25"	4,300'	5,190'	9.625"	40	HCK-55	BTC	2.02	1.15	8.43
8.75"	0	20,828'	5.5"	17	P-110RY	DWC/C	1.18	1.34	2.11
BLM Minimum Safety Factor							1.125	1.00	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	



**Devon Energy, Boomslang 14-23 Fed 4H**

**3. Cementing Program**

Casing	# Sks	Wt. lb/ gal	H <sub>2</sub> O gal/sk	Yld ft <sup>3</sup> / sack	500# Comp. Strength (hours)	Slurry Description
13-3/8" Surface	660	13.5	9.28	1.74	10	Lead: Class C Cement + 4% Gel + 1% Calcium Chloride + 0.125 lbs/sack Poly-E-Flake
	550	14.8	6.32	1.33	6	Tail: Class C Cement + 0.125 lbs/sack Poly-E-Flake
13-3/8" Surface Two Stage Option	260	13.5	9.28	1.74	10	1 <sup>st</sup> Stage Lead: Class C Cement + 4% Gel + 1% Calcium Chloride + 0.125 lbs/sack Poly-E-Flake
	550	14.8	6.32	1.33	6	1 <sup>st</sup> Stage Tail: Class C Cement + 0.125 lbs/sack Poly-E-Flake
	DV Tool = 500ft					
	530	14.8	6.32	1.33	6	2 <sup>nd</sup> Stage Primary: Class C Cement + 0.125 lbs/sack Poly-E-Flake
9-5/8" Inter.	1090	12.9	9.81	1.85	14	Lead: (65:35) Class C Cement: Poz (Fly Ash): 6% BWOC Bentonite + 5% BWOW Sodium Chloride + 0.125 lbs/sack Poly-E-Flake
	430	14.8	6.32	1.33	6	Tail: Class C Cement + 0.125 lbs/sack Poly-E-Flake
9-5/8" Inter. Two Stage Option	250	12.9	9.81	1.85	14	1 <sup>st</sup> Stage Lead: (65:35) Class C Cement: Poz (Fly Ash): 6% BWOC Bentonite + 5% BWOW Sodium Chloride + 0.125 lbs/sack Poly-E-Flake
	220	14.8	6.32	1.33	6	1 <sup>st</sup> Stage Tail: Class C Cement + 0.125 lbs/sack Poly-E-Flake
	DV Tool = 3850ft					
	850	12.9	9.81	1.85	14	2 <sup>nd</sup> Stage Lead: (65:35) Class C Cement: Poz (Fly Ash): 6% BWOC Bentonite + 5% BWOW Sodium Chloride + 0.125 lbs/sack Poly-E-Flake
	210	14.8	6.32	1.33	6	2 <sup>nd</sup> Stage Tail: Class C Cement + 0.125 lbs/sack Poly-E-Flake
5-1/2" Prod Single Stage	710	11.9	12.89	2.31	n/a	Lead: (50:50) Class H Cement: Poz (Fly Ash) + 10% BWOC Bentonite + 1 lb/sk of Kol-Seal + 0.3% BWOC HR-601 + 0.5lb/sk D-Air 5000
	2730	14.5	5.31	1.2	25	Tail: (50:50) Class H Cement: Poz (Fly Ash) + 0.5% bwoc HALAD-344 + 0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2% bwoc Bentonite
5-1/2" Prod Two Stage Option	510	11.9	12.89	2.31	n/a	1 <sup>st</sup> Stage Lead: (50:50) Class H Cement: Poz (Fly Ash) + 10% BWOC Bentonite + 1 lb/sk of Kol-Seal + 0.3% BWOC HR-601 + 0.5lb/sk D-Air 5000
	2730	14.5	5.31	1.2	25	1 <sup>st</sup> Stage Tail: (50:50) Class H Cement: Poz (Fly Ash) + 0.5% bwoc HALAD-344 + 0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2% bwoc Bentonite
	DV Tool = 6500ft					
	160	11	14.81	2.55	22	2 <sup>nd</sup> Stage Lead: Tuned Light® Cement + 0.125 lb/sk Pol-E-Flake
	50	14.8	6.32	1.33	6	2 <sup>nd</sup> Stage Tail: Class C Cement + 0.125 lbs/sack Poly-E-Flake



## Devon Energy, Boomslang 14-23 Fed 4H

If a DV tool is used, depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing String	TOC	% Excess
13-3/8" Surface Single Stage Option	0'	100%
13-3/8" Surface Two Stage Option	1 <sup>st</sup> Stage = 500' / 2 <sup>nd</sup> Stage = 0'	100%
9-5/8" Intermediate Single Stage Option	0'	75%
9-5/8" Intermediate Casing Two Stage Option	1 <sup>st</sup> Stage = 3850' / 2 <sup>nd</sup> Stage = 0'	75%
5-1/2" Production Casing Single Stage Option	4990'	25%
5-1/2" Production Casing Two Stage Option	1 <sup>st</sup> Stage = 6500' / 2 <sup>nd</sup> Stage = 4990'	25%

### 4. Pressure Control Equipment

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	------------------------------------------------------------------------------------------------------

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
12-1/4"	13-5/8"	5M 3M	Annular	x	50% of working pressure  3M 5M
			Blind Ram		
			Pipe Ram		
			Double Ram	x	
			Other*		
8-3/4"	13-5/8"	5M 3M	Annular	x	50% testing pressure  5M 3M per David cox 8/1/2011
			Blind Ram		
			Pipe Ram		
			Double Ram	x	
			Other*		
			Annular		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		

\*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a



## Devon Energy, Boomslang 14-23 Fed 4H

higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

Y	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
Y	Are anchors required by manufacturer?
Y	<p>A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.</p> <p>Devon proposes the option of using a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be <del>3,000 (3M)</del> <sup>5,000 (5M)</sup> psi. <b>5,000 (5M) BOP Required.</b></p> <ul style="list-style-type: none"> <li>Wellhead will be installed by wellhead representatives.</li> <li>If the welding is performed by a third party, the wellhead representative will monitor the temperature to verify that it does not exceed the maximum temperature of the seal.</li> <li>Wellhead representative will install the test plug for the initial BOP test.</li> <li>Wellhead will install a solid steel body pack-off to completely isolate the lower head after cementing intermediate casing. After installation of the pack-off, the pack-off and the lower flange will be tested to <del>3M</del> <sup>5M</sup>, as shown on the attached schematic. Everything above the pack-off will not have been altered whatsoever from the initial nipple up. Therefore the BOP components will not be retested at that time.</li> <li>If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head will be cut and top out operations will be conducted.</li> <li>Devon will pressure test all seals above and below the mandrel (but still above the casing) to full working pressure rating.</li> <li>Devon will test the casing to 0.22 psi/ft or 1500 psi, whichever is greater, as per Onshore Order #2.</li> </ul> <p>After running the 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of <del>3M</del> <sup>5M</sup> will be installed on the Uni-head wellhead system and will undergo a 250 psi low pressure test followed by a 3,000 psi high pressure test. The <del>3,000</del> <sup>5,000</sup> psi high and</p>



## Devon Energy, Boomslang 14-23 Fed 4H

<p>250 psi low test will cover testing requirements a maximum of 30 days, as per Onshore Order #2. If the well is not complete within 30 days of this BOP test, another full BOP test will be conducted, as per Onshore Order #2.</p> <p>After running the 9-5/8" intermediate casing with a mandrel hanger, the 13-5/8" BOP/BOPE system with a minimum rating of 3M will already be installed on the Uni-head.</p> <p>The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 3,000 psi WP.</p> <p>Devon requests a variance to use a flexible line with flanged ends between the BOP and the choke manifold (choke line). The line will be kept as straight as possible with minimal turns</p> <p>See attached schematic.</p>
--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

### 5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	1,315' 1400	FW Gel	8.6-8.8	28-34	N/C
1,315'	5,190'	Saturated Brine	10.0-10.2	28-34	N/C
5,190'	20,828'	Cut Brine	8.5-9.3	28-34	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---------------------------------------------------------	-----------------------------

### 6. Logging and Testing Procedures

Logging, Coring and Testing.	
x	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain



**Devon Energy, Boomslang 14-23 Fed 4H**

Additional logs planned		Interval
	Resistivity	Int. shoe to KOP
	Density	Int. shoe to KOP
X	CBL	Production casing
X	Mud log	Intermediate shoe to TD
	PEX	

**7. Drilling Conditions**

Condition	Specify what type and where?
BH Pressure at deepest TVD	5400 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H<sub>2</sub>S) monitors will be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

N	H <sub>2</sub> S is present
Y	H <sub>2</sub> S Plan attached

**8. Other facets of operation**

Is this a walking operation? No.

Will be pre-setting casing? No.


Attachments

  x   Directional Plan

       Other, describe



# 13-5/8" 5M BOPE & Closed Loop Equipment Schematic









Project: Lea County, NM (NAD-83)  
 Site: Boomslang 14-23 Fed  
 Well: 4H  
 Wellbore: OH  
 Design: Plan #1



Azimuths to Grid North  
 True North: -0.42°  
 Magnetic North: 6.51°

Magnetic Field  
 Strength: 48232.6snT  
 Dip Angle: 60.02°  
 Date: 6/28/2016  
 Model: HDGM





# **DEVON ENERGY**

Lea County, NM (NAD-83)

Boomslang 14-23 Fed

4H

OH

Plan: Plan #1

## **Standard Planning Report**

28 June, 2016

# LEAM Drilling Systems LLC

## Planning Report

Database: EDM 5000.1 Single User Db  
 Company: DEVON ENERGY  
 Project: Lea County, NM (NAD-83)  
 Site: Boomslang 14-23 Fed  
 Well: 4H  
 Wellbore: OH  
 Design: Plan #1

Local Co-ordinate Reference: Well 4H  
 TVD Reference: 3601.9' GL + 25' RKB @ 3626.90usft  
 MD Reference: 3601.9' GL + 25' RKB @ 3626.90usft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

Project: Lea County, NM (NAD-83)  
 Map System: US State Plane 1983  
 Geo Datum: North American Datum 1983  
 Map Zone: New Mexico Eastern Zone  
 System Datum: Mean Sea Level

Site: Boomslang 14-23 Fed  
 Site Position: Northing: 446,243.13 usft Latitude: 32° 13' 27.535 N  
 From: Map Easting: 786,353.47 usft Longitude: 103° 32' 27.617 W  
 Position Uncertainty: 0.00 usft Slot Radius: 13-3/16 " Grid Convergence: 0.42 °

Well: 4H, 2nd BS SS  
 Well Position: +N/-S 0.30 usft Northing: 446,243.43 usft Latitude: 32° 13' 27.534 N  
 +E/-W 49.94 usft Easting: 786,403.41 usft Longitude: 103° 32' 27.036 W  
 Position Uncertainty: 0.00 usft Wellhead Elevation: 3,626.90 usft Ground Level: 3,601.90 usft

Wellbore: OH  
 Magnetics: Model Name Sample Date Declination (°) Dip Angle (°) Field Strength (nT)  
 HDGM 6/28/2016 6.93 60.02 48,233

Design: Plan #1  
 Audit Notes:  
 Version: Phase: PLAN Tie On Depth: 0.00  
 Vertical Section: Depth From (TVD) +N/-S +E/-W Direction  
 (usft) (usft) (usft) (°)  
 0.00 0.00 0.00 179.34

Plan Sections

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
10,474.20	0.00	0.00	10,474.20	0.00	0.00	0.00	0.00	0.00	0.00	
11,367.00	89.28	179.34	11,047.11	-565.72	6.48	10.00	10.00	0.00	179.34	
20,828.28	89.28	179.34	11,166.00	-10,025.64	114.77	0.00	0.00	0.00	0.00	PBHL (B1423F 4H)



# LEAM Drilling Systems LLC

## Planning Report

Database: EDM 5000.1 Single User Db  
Company: DEVON ENERGY  
Project: Lea County, NM (NAD-83)  
Site: Boomsiang 14-23 Fed  
Well: 4H  
Wellbore: OH  
Design: Plan #1

Local Co-ordinate Reference: Well 4H  
TVD Reference: 3601.9' GL + 25' RKB @ 3626.90usft  
MD Reference: 3601.9' GL + 25' RKB @ 3626.90usft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,284.90	0.00	0.00	1,284.90	0.00	0.00	0.00	0.00	0.00	0.00
<b>Rustler</b>									
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,805.90	0.00	0.00	1,805.90	0.00	0.00	0.00	0.00	0.00	0.00
<b>Top of Salt</b>									
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00
4,400.00	0.00	0.00	4,400.00	0.00	0.00	0.00	0.00	0.00	0.00
4,500.00	0.00	0.00	4,500.00	0.00	0.00	0.00	0.00	0.00	0.00
4,600.00	0.00	0.00	4,600.00	0.00	0.00	0.00	0.00	0.00	0.00
4,700.00	0.00	0.00	4,700.00	0.00	0.00	0.00	0.00	0.00	0.00
4,800.00	0.00	0.00	4,800.00	0.00	0.00	0.00	0.00	0.00	0.00
4,900.00	0.00	0.00	4,900.00	0.00	0.00	0.00	0.00	0.00	0.00

# LEAM Drilling Systems LLC

## Planning Report

Database: EDM 5000.1 Single User Db  
 Company: DEVON ENERGY  
 Project: Lea County, NM (NAD-83)  
 Site: Boomslang 14-23 Fed  
 Well: 4H  
 Wellbore: OH  
 Design: Plan #1

Local Co-ordinate Reference: Well 4H  
 TVD Reference: 3601.9' GL + 25' RKB @ 3626.90usft  
 MD Reference: 3601.9' GL + 25' RKB @ 3626.90usft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,000.00	0.00	0.00	5,000.00	0.00	0.00	0.00	0.00	0.00	0.00
5,100.00	0.00	0.00	5,100.00	0.00	0.00	0.00	0.00	0.00	0.00
5,200.00	0.00	0.00	5,200.00	0.00	0.00	0.00	0.00	0.00	0.00
5,231.90	0.00	0.00	5,231.90	0.00	0.00	0.00	0.00	0.00	0.00
<b>Base of Salt - Delaware</b>									
5,300.00	0.00	0.00	5,300.00	0.00	0.00	0.00	0.00	0.00	0.00
5,400.00	0.00	0.00	5,400.00	0.00	0.00	0.00	0.00	0.00	0.00
5,500.00	0.00	0.00	5,500.00	0.00	0.00	0.00	0.00	0.00	0.00
5,600.00	0.00	0.00	5,600.00	0.00	0.00	0.00	0.00	0.00	0.00
5,700.00	0.00	0.00	5,700.00	0.00	0.00	0.00	0.00	0.00	0.00
5,800.00	0.00	0.00	5,800.00	0.00	0.00	0.00	0.00	0.00	0.00
5,900.00	0.00	0.00	5,900.00	0.00	0.00	0.00	0.00	0.00	0.00
6,000.00	0.00	0.00	6,000.00	0.00	0.00	0.00	0.00	0.00	0.00
6,100.00	0.00	0.00	6,100.00	0.00	0.00	0.00	0.00	0.00	0.00
6,144.90	0.00	0.00	6,144.90	0.00	0.00	0.00	0.00	0.00	0.00
<b>Cherry Canyon</b>									
6,200.00	0.00	0.00	6,200.00	0.00	0.00	0.00	0.00	0.00	0.00
6,300.00	0.00	0.00	6,300.00	0.00	0.00	0.00	0.00	0.00	0.00
6,400.00	0.00	0.00	6,400.00	0.00	0.00	0.00	0.00	0.00	0.00
6,500.00	0.00	0.00	6,500.00	0.00	0.00	0.00	0.00	0.00	0.00
6,600.00	0.00	0.00	6,600.00	0.00	0.00	0.00	0.00	0.00	0.00
6,700.00	0.00	0.00	6,700.00	0.00	0.00	0.00	0.00	0.00	0.00
6,800.00	0.00	0.00	6,800.00	0.00	0.00	0.00	0.00	0.00	0.00
6,900.00	0.00	0.00	6,900.00	0.00	0.00	0.00	0.00	0.00	0.00
7,000.00	0.00	0.00	7,000.00	0.00	0.00	0.00	0.00	0.00	0.00
7,100.00	0.00	0.00	7,100.00	0.00	0.00	0.00	0.00	0.00	0.00
7,200.00	0.00	0.00	7,200.00	0.00	0.00	0.00	0.00	0.00	0.00
7,300.00	0.00	0.00	7,300.00	0.00	0.00	0.00	0.00	0.00	0.00
7,400.00	0.00	0.00	7,400.00	0.00	0.00	0.00	0.00	0.00	0.00
7,500.00	0.00	0.00	7,500.00	0.00	0.00	0.00	0.00	0.00	0.00
7,504.90	0.00	0.00	7,504.90	0.00	0.00	0.00	0.00	0.00	0.00
<b>Brushy Canyon</b>									
7,600.00	0.00	0.00	7,600.00	0.00	0.00	0.00	0.00	0.00	0.00
7,700.00	0.00	0.00	7,700.00	0.00	0.00	0.00	0.00	0.00	0.00
7,800.00	0.00	0.00	7,800.00	0.00	0.00	0.00	0.00	0.00	0.00
7,900.00	0.00	0.00	7,900.00	0.00	0.00	0.00	0.00	0.00	0.00
8,000.00	0.00	0.00	8,000.00	0.00	0.00	0.00	0.00	0.00	0.00
8,100.00	0.00	0.00	8,100.00	0.00	0.00	0.00	0.00	0.00	0.00
8,200.00	0.00	0.00	8,200.00	0.00	0.00	0.00	0.00	0.00	0.00
8,300.00	0.00	0.00	8,300.00	0.00	0.00	0.00	0.00	0.00	0.00
8,400.00	0.00	0.00	8,400.00	0.00	0.00	0.00	0.00	0.00	0.00
8,500.00	0.00	0.00	8,500.00	0.00	0.00	0.00	0.00	0.00	0.00
8,600.00	0.00	0.00	8,600.00	0.00	0.00	0.00	0.00	0.00	0.00
8,700.00	0.00	0.00	8,700.00	0.00	0.00	0.00	0.00	0.00	0.00
8,774.90	0.00	0.00	8,774.90	0.00	0.00	0.00	0.00	0.00	0.00
<b>Madera</b>									
8,800.00	0.00	0.00	8,800.00	0.00	0.00	0.00	0.00	0.00	0.00
8,881.90	0.00	0.00	8,881.90	0.00	0.00	0.00	0.00	0.00	0.00
<b>Lower Brushy Canyon</b>									
8,900.00	0.00	0.00	8,900.00	0.00	0.00	0.00	0.00	0.00	0.00
9,000.00	0.00	0.00	9,000.00	0.00	0.00	0.00	0.00	0.00	0.00
9,044.90	0.00	0.00	9,044.90	0.00	0.00	0.00	0.00	0.00	0.00
<b>1st BSPG Lime</b>									



# LEAM Drilling Systems LLC

## Planning Report

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well 4H
Company:	DEVON ENERGY	TVD Reference:	3601.9' GL + 25' RKB @ 3626.90usft
Project:	Lea County, NM (NAD-83)	MD Reference:	3601.9' GL + 25' RKB @ 3626.90usft
Site:	Boomsiang 14-23 Fed	North Reference:	Grid
Well:	4H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Plan #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
9,100.00	0.00	0.00	9,100.00	0.00	0.00	0.00	0.00	0.00	0.00	
9,168.90	0.00	0.00	9,168.90	0.00	0.00	0.00	0.00	0.00	0.00	
<b>Leonard</b>										
9,200.00	0.00	0.00	9,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
9,300.00	0.00	0.00	9,300.00	0.00	0.00	0.00	0.00	0.00	0.00	
9,400.00	0.00	0.00	9,400.00	0.00	0.00	0.00	0.00	0.00	0.00	
9,500.00	0.00	0.00	9,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
9,600.00	0.00	0.00	9,600.00	0.00	0.00	0.00	0.00	0.00	0.00	
9,700.00	0.00	0.00	9,700.00	0.00	0.00	0.00	0.00	0.00	0.00	
9,800.00	0.00	0.00	9,800.00	0.00	0.00	0.00	0.00	0.00	0.00	
9,900.00	0.00	0.00	9,900.00	0.00	0.00	0.00	0.00	0.00	0.00	
10,000.00	0.00	0.00	10,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
10,100.00	0.00	0.00	10,100.00	0.00	0.00	0.00	0.00	0.00	0.00	
10,103.90	0.00	0.00	10,103.90	0.00	0.00	0.00	0.00	0.00	0.00	
<b>1st BSPG Sand</b>										
10,200.00	0.00	0.00	10,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
10,300.00	0.00	0.00	10,300.00	0.00	0.00	0.00	0.00	0.00	0.00	
10,363.90	0.00	0.00	10,363.90	0.00	0.00	0.00	0.00	0.00	0.00	
<b>2nd BSPG Lime</b>										
10,400.00	0.00	0.00	10,400.00	0.00	0.00	0.00	0.00	0.00	0.00	
10,474.20	0.00	0.00	10,474.20	0.00	0.00	0.00	0.00	0.00	0.00	
<b>KOP 10° DLS</b>										
10,500.00	2.58	179.34	10,499.99	-0.58	0.01	0.58	10.00	10.00	0.00	
10,550.00	7.58	179.34	10,549.78	-5.01	0.06	5.01	10.00	10.00	0.00	
10,600.00	12.58	179.34	10,598.99	-13.75	0.16	13.76	10.00	10.00	0.00	
10,650.00	17.58	179.34	10,647.25	-26.76	0.31	26.76	10.00	10.00	0.00	
10,700.00	22.58	179.34	10,694.20	-43.92	0.50	43.92	10.00	10.00	0.00	
10,750.00	27.58	179.34	10,739.47	-65.11	0.75	65.11	10.00	10.00	0.00	
10,800.00	32.58	179.34	10,782.72	-90.16	1.03	90.16	10.00	10.00	0.00	
10,808.79	33.46	179.34	10,790.09	-94.95	1.09	94.95	10.00	10.00	0.00	
<b>2nd BSPG Sand</b>										
10,850.00	37.58	179.34	10,823.63	-118.88	1.36	118.89	10.00	10.00	0.00	
10,900.00	42.58	179.34	10,861.87	-151.06	1.73	151.07	10.00	10.00	0.00	
10,950.00	47.58	179.34	10,897.17	-186.45	2.13	186.47	10.00	10.00	0.00	
11,000.00	52.58	179.34	10,929.24	-224.79	2.57	224.80	10.00	10.00	0.00	
11,050.00	57.58	179.34	10,957.86	-265.77	3.04	265.79	10.00	10.00	0.00	
11,100.00	62.58	179.34	10,982.79	-309.09	3.54	309.11	10.00	10.00	0.00	
11,150.00	67.58	179.34	11,003.85	-354.42	4.06	354.44	10.00	10.00	0.00	
11,186.82	71.26	179.34	11,016.79	-388.88	4.45	388.90	10.00	10.00	0.00	
<b>2nd BSPG Sand Target Top</b>										
11,200.00	72.58	179.34	11,020.88	-401.41	4.60	401.43	10.00	10.00	0.00	
11,250.00	77.58	179.34	11,033.75	-449.70	5.15	449.73	10.00	10.00	0.00	
11,300.00	82.58	179.34	11,042.36	-498.94	5.71	498.97	10.00	10.00	0.00	
11,350.00	87.58	179.34	11,046.64	-548.73	6.28	548.77	10.00	10.00	0.00	
11,367.00	89.28	179.34	11,047.11	-565.72	6.48	565.76	10.00	10.00	0.00	
<b>LP</b>										
11,400.00	89.28	179.34	11,047.52	-598.72	6.85	598.76	0.00	0.00	0.00	
11,500.00	89.28	179.34	11,048.78	-698.71	8.00	698.75	0.00	0.00	0.00	
11,600.00	89.28	179.34	11,050.04	-798.69	9.14	798.74	0.00	0.00	0.00	
11,700.00	89.28	179.34	11,051.29	-898.68	10.29	898.74	0.00	0.00	0.00	
11,800.00	89.28	179.34	11,052.55	-998.66	11.43	998.73	0.00	0.00	0.00	
11,900.00	89.28	179.34	11,053.81	-1,098.65	12.58	1,098.72	0.00	0.00	0.00	
12,000.00	89.28	179.34	11,055.06	-1,198.63	13.72	1,198.71	0.00	0.00	0.00	



# LEAM Drilling Systems LLC

## Planning Report

Database: EDM 5000.1 Single User Db  
 Company: DEVON ENERGY  
 Project: Lea County, NM (NAD-83)  
 Site: Boomslang 14-23 Fed  
 Well: 4H  
 Wellbore: OH  
 Design: Plan #1

Local Co-ordinate Reference: Well 4H  
 TVD Reference: 3601.9' GL + 25' RKB @ 3626.90usft  
 MD Reference: 3601.9' GL + 25' RKB @ 3626.90usft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
12,100.00	89.28	179.34	11,056.32	-1,298.62	14.87	1,298.70	0.00	0.00	0.00
12,200.00	89.28	179.34	11,057.58	-1,398.60	16.01	1,398.70	0.00	0.00	0.00
12,300.00	89.28	179.34	11,058.83	-1,498.59	17.16	1,498.69	0.00	0.00	0.00
12,400.00	89.28	179.34	11,060.09	-1,598.58	18.30	1,598.68	0.00	0.00	0.00
12,500.00	89.28	179.34	11,061.35	-1,698.56	19.44	1,698.67	0.00	0.00	0.00
12,600.00	89.28	179.34	11,062.60	-1,798.55	20.59	1,798.66	0.00	0.00	0.00
12,700.00	89.28	179.34	11,063.86	-1,898.53	21.73	1,898.66	0.00	0.00	0.00
12,800.00	89.28	179.34	11,065.12	-1,998.52	22.88	1,998.65	0.00	0.00	0.00
12,900.00	89.28	179.34	11,066.37	-2,098.50	24.02	2,098.64	0.00	0.00	0.00
13,000.00	89.28	179.34	11,067.63	-2,198.49	25.17	2,198.63	0.00	0.00	0.00
13,100.00	89.28	179.34	11,068.89	-2,298.47	26.31	2,298.62	0.00	0.00	0.00
13,200.00	89.28	179.34	11,070.14	-2,398.46	27.46	2,398.62	0.00	0.00	0.00
13,300.00	89.28	179.34	11,071.40	-2,498.45	28.60	2,498.61	0.00	0.00	0.00
13,400.00	89.28	179.34	11,072.66	-2,598.43	29.75	2,598.60	0.00	0.00	0.00
13,500.00	89.28	179.34	11,073.91	-2,698.42	30.89	2,698.59	0.00	0.00	0.00
13,600.00	89.28	179.34	11,075.17	-2,798.40	32.04	2,798.59	0.00	0.00	0.00
13,700.00	89.28	179.34	11,076.43	-2,898.39	33.18	2,898.58	0.00	0.00	0.00
13,800.00	89.28	179.34	11,077.68	-2,998.37	34.32	2,998.57	0.00	0.00	0.00
13,900.00	89.28	179.34	11,078.94	-3,098.36	35.47	3,098.56	0.00	0.00	0.00
14,000.00	89.28	179.34	11,080.20	-3,198.34	36.61	3,198.55	0.00	0.00	0.00
14,100.00	89.28	179.34	11,081.45	-3,298.33	37.76	3,298.55	0.00	0.00	0.00
14,200.00	89.28	179.34	11,082.71	-3,398.32	38.90	3,398.54	0.00	0.00	0.00
14,300.00	89.28	179.34	11,083.97	-3,498.30	40.05	3,498.53	0.00	0.00	0.00
14,400.00	89.28	179.34	11,085.22	-3,598.29	41.19	3,598.52	0.00	0.00	0.00
14,500.00	89.28	179.34	11,086.48	-3,698.27	42.34	3,698.51	0.00	0.00	0.00
14,600.00	89.28	179.34	11,087.74	-3,798.26	43.48	3,798.51	0.00	0.00	0.00
14,700.00	89.28	179.34	11,088.99	-3,898.24	44.63	3,898.50	0.00	0.00	0.00
14,800.00	89.28	179.34	11,090.25	-3,998.23	45.77	3,998.49	0.00	0.00	0.00
14,900.00	89.28	179.34	11,091.51	-4,098.21	46.91	4,098.48	0.00	0.00	0.00
15,000.00	89.28	179.34	11,092.76	-4,198.20	48.06	4,198.47	0.00	0.00	0.00
15,100.00	89.28	179.34	11,094.02	-4,298.19	49.20	4,298.47	0.00	0.00	0.00
15,200.00	89.28	179.34	11,095.28	-4,398.17	50.35	4,398.46	0.00	0.00	0.00
15,300.00	89.28	179.34	11,096.53	-4,498.16	51.49	4,498.45	0.00	0.00	0.00
15,400.00	89.28	179.34	11,097.79	-4,598.14	52.64	4,598.44	0.00	0.00	0.00
15,500.00	89.28	179.34	11,099.04	-4,698.13	53.78	4,698.44	0.00	0.00	0.00
15,600.00	89.28	179.34	11,100.30	-4,798.11	54.93	4,798.43	0.00	0.00	0.00
15,700.00	89.28	179.34	11,101.56	-4,898.10	56.07	4,898.42	0.00	0.00	0.00
15,800.00	89.28	179.34	11,102.81	-4,998.08	57.22	4,998.41	0.00	0.00	0.00
15,900.00	89.28	179.34	11,104.07	-5,098.07	58.36	5,098.40	0.00	0.00	0.00
16,000.00	89.28	179.34	11,105.33	-5,198.06	59.51	5,198.40	0.00	0.00	0.00
16,100.00	89.28	179.34	11,106.58	-5,298.04	60.65	5,298.39	0.00	0.00	0.00
16,200.00	89.28	179.34	11,107.84	-5,398.03	61.79	5,398.38	0.00	0.00	0.00
16,300.00	89.28	179.34	11,109.10	-5,498.01	62.94	5,498.37	0.00	0.00	0.00
16,400.00	89.28	179.34	11,110.35	-5,598.00	64.08	5,598.36	0.00	0.00	0.00
16,500.00	89.28	179.34	11,111.61	-5,697.98	65.23	5,698.36	0.00	0.00	0.00
16,600.00	89.28	179.34	11,112.87	-5,797.97	66.37	5,798.35	0.00	0.00	0.00
16,700.00	89.28	179.34	11,114.12	-5,897.95	67.52	5,898.34	0.00	0.00	0.00
16,800.00	89.28	179.34	11,115.38	-5,997.94	68.66	5,998.33	0.00	0.00	0.00
16,900.00	89.28	179.34	11,116.64	-6,097.93	69.81	6,098.32	0.00	0.00	0.00
17,000.00	89.28	179.34	11,117.89	-6,197.91	70.95	6,198.32	0.00	0.00	0.00
17,100.00	89.28	179.34	11,119.15	-6,297.90	72.10	6,298.31	0.00	0.00	0.00
17,200.00	89.28	179.34	11,120.41	-6,397.88	73.24	6,398.30	0.00	0.00	0.00
17,300.00	89.28	179.34	11,121.66	-6,497.87	74.39	6,498.29	0.00	0.00	0.00
17,400.00	89.28	179.34	11,122.92	-6,597.85	75.53	6,598.29	0.00	0.00	0.00



# LEAM Drilling Systems LLC

## Planning Report

Database: EDM 5000.1 Single User Db  
 Company: DEVON ENERGY  
 Project: Lea County, NM (NAD-83)  
 Site: Boomslang 14-23 Fed  
 Well: 4H  
 Wellbore: OH  
 Design: Plan #1

Local Co-ordinate Reference: Well 4H  
 TVD Reference: 3601.9' GL + 25' RKB @ 3626.90usft  
 MD Reference: 3601.9' GL + 25' RKB @ 3626.90usft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
17,500.00	89.28	179.34	11,124.18	-6,697.84	76.67	6,698.28	0.00	0.00	0.00
17,600.00	89.28	179.34	11,125.43	-6,797.82	77.82	6,798.27	0.00	0.00	0.00
17,700.00	89.28	179.34	11,126.69	-6,897.81	78.96	6,898.26	0.00	0.00	0.00
17,800.00	89.28	179.34	11,127.95	-6,997.80	80.11	6,998.25	0.00	0.00	0.00
17,900.00	89.28	179.34	11,129.20	-7,097.78	81.25	7,098.25	0.00	0.00	0.00
18,000.00	89.28	179.34	11,130.46	-7,197.77	82.40	7,198.24	0.00	0.00	0.00
18,100.00	89.28	179.34	11,131.72	-7,297.75	83.54	7,298.23	0.00	0.00	0.00
18,200.00	89.28	179.34	11,132.97	-7,397.74	84.69	7,398.22	0.00	0.00	0.00
18,300.00	89.28	179.34	11,134.23	-7,497.72	85.83	7,498.21	0.00	0.00	0.00
18,400.00	89.28	179.34	11,135.49	-7,597.71	86.98	7,598.21	0.00	0.00	0.00
18,500.00	89.28	179.34	11,136.74	-7,697.69	88.12	7,698.20	0.00	0.00	0.00
18,600.00	89.28	179.34	11,138.00	-7,797.68	89.27	7,798.19	0.00	0.00	0.00
18,700.00	89.28	179.34	11,139.26	-7,897.67	90.41	7,898.18	0.00	0.00	0.00
18,800.00	89.28	179.34	11,140.51	-7,997.65	91.55	7,998.17	0.00	0.00	0.00
18,900.00	89.28	179.34	11,141.77	-8,097.64	92.70	8,098.17	0.00	0.00	0.00
19,000.00	89.28	179.34	11,143.03	-8,197.62	93.84	8,198.16	0.00	0.00	0.00
19,100.00	89.28	179.34	11,144.28	-8,297.61	94.99	8,298.15	0.00	0.00	0.00
19,200.00	89.28	179.34	11,145.54	-8,397.59	96.13	8,398.14	0.00	0.00	0.00
19,300.00	89.28	179.34	11,146.80	-8,497.58	97.28	8,498.14	0.00	0.00	0.00
19,400.00	89.28	179.34	11,148.05	-8,597.56	98.42	8,598.13	0.00	0.00	0.00
19,500.00	89.28	179.34	11,149.31	-8,697.55	99.57	8,698.12	0.00	0.00	0.00
19,600.00	89.28	179.34	11,150.57	-8,797.54	100.71	8,798.11	0.00	0.00	0.00
19,700.00	89.28	179.34	11,151.82	-8,897.52	101.86	8,898.10	0.00	0.00	0.00
19,800.00	89.28	179.34	11,153.08	-8,997.51	103.00	8,998.10	0.00	0.00	0.00
19,900.00	89.28	179.34	11,154.34	-9,097.49	104.14	9,098.09	0.00	0.00	0.00
20,000.00	89.28	179.34	11,155.59	-9,197.48	105.29	9,198.08	0.00	0.00	0.00
20,100.00	89.28	179.34	11,156.85	-9,297.46	106.43	9,298.07	0.00	0.00	0.00
20,200.00	89.28	179.34	11,158.11	-9,397.45	107.58	9,398.06	0.00	0.00	0.00
20,300.00	89.28	179.34	11,159.36	-9,497.43	108.72	9,498.06	0.00	0.00	0.00
20,400.00	89.28	179.34	11,160.62	-9,597.42	109.87	9,598.05	0.00	0.00	0.00
20,500.00	89.28	179.34	11,161.88	-9,697.41	111.01	9,698.04	0.00	0.00	0.00
20,600.00	89.28	179.34	11,163.13	-9,797.39	112.16	9,798.03	0.00	0.00	0.00
20,700.00	89.28	179.34	11,164.39	-9,897.38	113.30	9,898.02	0.00	0.00	0.00
20,800.00	89.28	179.34	11,165.64	-9,997.36	114.45	9,998.02	0.00	0.00	0.00
20,828.28	89.28	179.34	11,166.00	-10,025.64	114.77	10,026.30	0.00	0.00	0.00
TD - PBHL (B1423F 4H)									

### Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
SHL (B1423F 4H) - plan hits target center - Point	0.00	0.00	0.00	0.00	0.00	446,243.43	786,403.41	32° 13' 27.534 N	103° 32' 27.036 W
PBHL (B1423F 4H) - plan hits target center - Point	0.00	0.00	11,166.00	-10,025.64	114.77	436,217.79	786,518.18	32° 11' 48.321 N	103° 32' 26.560 W

# LEAM Drilling Systems LLC

## Planning Report

Database: EDM 5000.1 Single User Db  
 Company: DEVON ENERGY  
 Project: Lea County, NM (NAD-83)  
 Site: Boomslang 14-23 Fed  
 Well: 4H  
 Wellbore: OH  
 Design: Plan #1

Local Co-ordinate Reference:  
 TVD Reference:  
 MD Reference:  
 North Reference:  
 Survey Calculation Method:

Well 4H  
 3601.9' GL + 25' RKB @ 3626.90usft  
 3601.9' GL + 25' RKB @ 3626.90usft  
 Grid  
 Minimum Curvature

### Formations

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,284.90	1,284.90	Rustler		0.72	179.34
1,805.90	1,805.90	Top of Salt		0.72	179.34
5,231.90	5,231.90	Base of Salt		0.72	179.34
5,231.90	5,231.90	Delaware		0.72	179.34
6,144.90	6,144.90	Cherry Canyon		0.72	179.34
7,504.90	7,504.90	Brushy Canyon		0.72	179.34
8,774.90	8,774.90	Madera		0.72	179.34
8,881.90	8,881.90	Lower Brushy Canyon		0.72	179.34
9,044.90	9,044.90	1st BSPG Lime		0.72	179.34
9,168.90	9,168.90	Leonard		0.72	179.34
10,103.90	10,103.90	1st BSPG Sand		0.72	179.34
10,363.90	10,363.90	2nd BSPG Lime		0.72	179.34
10,808.79	10,790.09	2nd BSPG Sand		0.72	179.34
11,186.82	11,016.79	2nd BSPG Sand Target Top		0.72	179.34

### Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
10,474.20	10,474.20	0.00	0.00	KOP 10" DLS
11,367.00	11,047.11	-565.72	6.48	LP
20,828.28	11,166.00	-10,025.64	114.77	TD



## PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Devon Energy Production Company, L.P.
LEASE NO.:	NMLC-063798
WELL NAME & NO.:	Boomslang 14-23 Fed 4H
SURFACE HOLE FOOTAGE:	0200' FNL & 1930' FEL
BOTTOM HOLE FOOTAGE:	0330' FSL & 1895' FEL Sect. 23, T. 24 S., R 33 E.
LOCATION:	Section 14, T. 24 S., R 33 E., NMPM
COUNTY:	Lea County, New Mexico

**The original COAs still stand with the following drilling modifications:**

### I. DRILLING

#### A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Lea County**

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240,  
(575) 393-3612

1. A Hydrogen Sulfide (H<sub>2</sub>S) Drilling Plan shall be activated 500 feet prior to drilling into the **Delaware** formation. **As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.

4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

## **B. CASING**

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

**Centralizers required on surface casing per Onshore Order 2.III.B.1.f.**

### **Wait on cement (WOC) for Water Basin:**

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

**No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.**

**Possibility of water flows in the Salado and Castile.**

**Possibility of lost circulation in the Red Beds, Rustler, and Delaware.**

1. The 13-3/8 inch surface casing shall be set at approximately 1400 feet (in a competent bed below the Magenta Dolomite, which is a Member of the Rustler, and if salt is encountered, set casing at least 25 feet above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.



- b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
- c. **Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.**
- d. **If cement falls back, remedial cementing will be done prior to drilling out that string.**

**Option #1 (Single Stage):**

- ☒ **Cement to surface. If cement does not circulate see B.1.a, c-d above.**

**Option #2:**

**Operator has proposed DV tool at depth of 500', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range.**

- a. **First stage to DV tool:**
  - ☒ **Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve approved top of cement on the next stage.**
- b. **Second stage above DV tool:**
  - ☒ **Cement to surface. If cement does not circulate see B.1.a, c-d above.**

**Formation below the 13-3/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe and the mud weight for the bottom of the hole. Report results to BLM office.**

- 2. **The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:**

**Option #1 (Single Stage):**

- ☒ **Cement as proposed by operator. Operator shall provide method of verification.**

**Option #2:**

**Operator has proposed DV tool at depth of 3850', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range.**

a. First stage to DV tool:

- ☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

b. Second stage above DV tool:

- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.

**Formation below the 9-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.**

**Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.**

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:

**Option #1 (Single Stage):**

- ☒ Cement as proposed by operator. Operator shall provide method of verification. **Excess calculates to 23% - Additional cement may be required.**



**Option #2:**

Operator has proposed DV tool at depth of 6500', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range.

a. First stage to DV tool:

- ☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve approved top of cement on the next stage. **Excess calculates to 23% - Additional cement may be required.**

b. Second stage above DV tool:

- ☒ Cement as proposed by operator. Operator shall provide method of verification. **Excess calculates to 24% - Additional cement may be required.**

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

**C. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).

3. **Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 5000 (5M) psi.**
  - a. **Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.**
  - b. **If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.**
  - c. **Manufacturer representative shall install the test plug for the initial BOP test.**
  - d. **Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.**
  - e. **If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.**

**5M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.**

4. **The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.**
  - a. **In a water basin, for all-casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).**
  - b. **The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer.**
  - c. **The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.**



- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

#### **D. DRILL STEM TEST**

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

#### **E. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**JAM 080116**