Form			
(Augu	ISL	200	) / ,

UNITED STATES			
DEPARTMENT OF THE INTERIOR			
BUREAU OF LAND MANAGEMENT			

INDRY NOTICES AND REPORTS ON WELLS

OCD Hobbs

FORM APPROVED OMB NO. 1004-0135 Expires: July 31, 2010

٥.	NMNM7488			
6	If Indian Allottee or Tribe Name			

LEA COUNTY, NM

Do not use this form for proposals to SE abandone well. Use form 3160-3 (APL	If Indian, Allottee or Tribe Name  7. If Unit or CA/Agreement, Name and/or No. 8910138170	
SUBMITINE PLICATE - Other instructions on reverse side.		
Type of Well		8. Well Name and No. MLMU 184
2. Name of Operator Contact: DAVID STEWART OXY USA INCORPORATED E-Mail: david_stewart@oxy.com		9. API Well No. 30-025-27483-00-S1
3a. Address P O BOX 4294 HOUSTON, TX 77210-4294	3b. Phone No. (include area code) Ph: 432-685-5717 Fx: 432-685-5742	10. Field and Pool, or Exploratory LANGLIE
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)		11. County or Parish, and State

## 12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<ul> <li>☑ Notice of Intent</li> <li>☐ Subsequent Report</li> <li>☐ Final Abandonment Notice</li> </ul>	☐ Acidize ☐ Alter Casing ☐ Casing Repair ☐ Change Plans ☐ Convert to Injection	☐ Deepen ☐ Fracture Treat ☐ New Construction ☑ Plug and Abandon ☐ Plug Back	Production (Star Reclamation Recomplete Temporarily Ab	INT TO PA PMX P&A NR P&A R

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

TD-3755' PBTD-3715' Perfs-3411-3667'

Sec 4 T24S R37E SESE 660FSL 660FEL

8-5/8" 24# csg @ 501' w/ 350sx, 12-1/4" hole, TOC-Surf-Circ 5-1/2" 14# csg @ 3753' w/ 1100sx, 7-7/8" hole, TOC-Surf-Circ

1. RIH & set CIBP @ 3361', M&P 25sx cmt 2. M&P 35sx cmt @ 2730-2450' WOC-Tag 3. M&P 25sx cmt @ 1150-1000' WOC-Tag 4. M&P 70sx cmt @ 501' to surface 557 1250-1100

10# MLF between plugs

Above ground steel tanks will be utilized

SEE ATTACHED FOR CONDITIONS OF APPROVAL

14. I hereby certify that the	ne foregoing is true and correct.  Electronic Submission #346918 verifie  For OXY USA INCORPOR  Committed to AFMSS for processing by DEBO	ATÉD,	sent to the Hobbs	
Name (Printed/Typed)	DAVID STEWART	Title	SR. REGULATORY ADVISOR	
Signature	(Electronic Submission)	Date	08/04/2016	
THIS SPACE FOR FEDERAL OR STATE OFFICE USE				
Approved By	Walls	Title	Eng	Date 9/7/16
certify that the applicant hole	by, are attached. Approval of this notice does not warrant or ds legal or equitable title to those rights in the subject lease icant to conduct operations thereon.	Office	CFO	

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

OXY USA WTP LP - Proposed Myers Langlie Mattix Unit #184 API No. 30-025-27483


70sx @ 551'-Surface

12-1/4" hole @ 501' 8-5/8" csg @ 501' w/ 350sx-TOC-Surf-Circ

/250-1100 25sx @ 1150-1600' WOC-Tag TOS 1190'


35sx @ 2730-2450' WOC-Tag

CIBP @ 3361' w/ 25sx to 3210'



Perfs @ 3411-3667'

7-7/8" hole @ 3755' 5-1/2" csg @ 3753' w/ 1100sx-TOC-Surf-Circ OXY USA WTP LP - Current Myers Langlie Mattix Unit #184 API No. 30-025-27483



## BUREAU OF LAND MANAGEMENT Carlsbad Field Office 620 East Greene Street Carlsbad, New Mexico 88220 575-234-5972

## Permanent Abandonment of Federal Wells Conditions of Approval

Failure to comply with the following Conditions of Approval may result in a Notice of Incidents of Noncompliance (INC) in accordance with 43 CFR 3163.1.

1. Plugging operations shall commence within <u>ninety (90)</u> days from the approval date of this Notice of Intent to Abandon.

If you are unable to plug the well by the 90<sup>th</sup> day provide this office, prior to the 90<sup>th</sup> day, with the reason for not meeting the deadline and a date when we can expect the well to be plugged. Failure to do so will result in enforcement action.

The rig used for the plugging procedure cannot be released and moved off without the prior approval of the authorized officer. Failure to do so may result in enforcement action.

- 2. <u>Notification:</u> Contact the appropriate BLM office at least 24 hours prior to the commencing of any plugging operations. For wells in Chaves and Roosevelt County, call 575-627-0272; Eddy County, call 575-361-2822; Lea County, call 575-393-3612.
- 3. <u>Blowout Preventers</u>: A blowout preventer (BOP), as appropriate, shall be installed before commencing any plugging operation. The BOP must be installed and maintained as per API and manufacturer recommendations. The minimum BOP requirement is a 2M system for a well not deeper than 9,090 feet; a 3M system for a well not deeper than 13,636 feet; and a 5M system for a well not deeper than 22,727 feet.
- 4. <u>Mud Requirement:</u> Mud shall be placed between all plugs. Minimum consistency of plugging mud shall be obtained by mixing at the rate of 25 sacks (50 pounds each) of gel per 100 barrels of **brine** water. Minimum nine (9) pounds per gallon.
- 5. <u>Cement Requirement</u>: Sufficient cement shall be used to bring any required plug to the specified depth and length. Any given cement volumes on the proposed plugging procedure are merely estimates and are not final. Unless specific approval is received, no plug except the surface plug shall be less than 25 sacks of cement. Any plug that requires a tag will have a minimum WOC time of 4 hours.

In lieu of a cement plug across perforations in a cased hole (not for any other plugs), a bridge plug set within 50 feet to 100 feet above the perforations shall be capped with 25 sacks of cement. If a bailer is used to cap this plug, 35 feet of cement shall be sufficient. Before pumping or bailing cement on top of CIBP, tag will be required to verify depth. Based on depth, a tag of the cement may be deemed necessary.

Unless otherwise specified in the approved procedure, the cement plug shall consist of either Neat Class "C", for up to 7,500 feet of depth or Neat Class "H", for deeper than 7,500 feet plugs.

6. <u>Dry Hole Marker</u>: All casing shall be cut-off at the base of the cellar or 3 feet below final restored ground level (whichever is deeper). The BLM is to be notified a minimum of 4 hours prior to the wellhead being cut off to verify that cement is to surface in the casing and all annuluses. Wellhead cut off shall commence within ten (10) calendar days of the well being plugged. If the cut off cannot be done by the 10<sup>th</sup> day, the BLM is to be contacted with justification to receive an extension for completing the cut off.

The well bore shall then be capped with a 4-inch pipe, 10-feet in length, 4 feet above ground and embedded in cement, unless otherwise noted in COA (requirements will be attached). The following information shall be permanently inscribed on the dry hole marker: well name and number, name of the operator, lease serial number, surveyed location (quarter-quarter section, section, township and range or other authorized survey designation acceptable to the authorized officer such as metes and bounds).

- 7. <u>Subsequent Plugging Reporting:</u> Within 30 days after plugging work is completed, file one original and three copies of the Subsequent Report of Abandonment, Form 3160-5 to BLM. The report should give in detail the manner in which the plugging work was carried out, the extent (by depths) of cement plugs placed, and the size and location (by depths) of casing left in the well. **Show date well was plugged.**
- 8. <u>Trash</u>: All trash, junk and other waste material shall be contained in trash cages or bins to prevent scattering and will be removed and deposited in an approved sanitary landfill. Burial on site is not permitted.

Following the submission and approval of the Subsequent Report of Abandonment, surface restoration will be required. See attached reclamation objectives.