HOBBS OCD

DEC 27 2016

RECEIVED

**Surface Use & Operating Plan** 

# Windward Federal #8H

- Surface Tenant: Mark and Annette McCloy Trust, P O Box 795, Tatum, NM 88267
- New Road: No new road will be necessary
- Flow Line: Will follow the road to the existing Windward Central Tank Battery
- Facilities: Will utilize facilities at the Windward Central Tank Battery location.

Well Site Information
V Door: East
Topsoil: North
Interim Reclamation: North and East

Notes

<u>Onsite</u>: On-site was done by Chad Young (BLM); Gerald Herrera (COG) on November 24, 2015. At the time on the on-site, this location was called the Windward Federal #7H.

Surface Use Plan

# SURFACE USE AND OPERATING PLAN

## 1. Existing & Proposed Access Roads

- A. The well site survey and elevation plat for the proposed well is attached with this application. It was staked by Harcrow Surveying, Artesia, NM.
- B. All roads to the location are shown on the Location Verification Map Exhibit 2. The existing lease roads are illustrated and are adequate for travel during drilling and production operations. Upgrading existing roads prior to drilling the well will be done where necessary. The road route to the well site is depicted in Exhibit #2. The road shown in Exhibit #2 will be used to access the well.
- C. Directions to location: See 600 x 600 plat
- D. Based on current road maintenance performed on other roads serving existing wells, we anticipate maintaining the lease roads leading to the proposed well pad at least once a year on dry conditions and twice a year in wetter conditions.

#### 2. Proposed Access Road:

The Location Verification Map shows that no new access road will be required for this location. If any road is required it will be constructed as follows:

The maximum width of the running surface will be 14'. The road will be crowned, ditched and constructed of 6" rolled and compacted caliche. Ditches will be at 3:1 slope and 4 feet wide. Water will be diverted where necessary to avoid ponding, prevent erosion, maintain good drainage, and to be consistent with local drainage patterns.

- A. The average grade will be less than 1%.
- B. No turnouts are planned.
- C. No cattleguard, culvert, gates, low water crossings or fence cuts are necessary.
- D. Surfacing material will consist of native caliche. Caliche will be obtained from the actual well site if available. If not available onsite, caliche will be hauled from the nearest BLM approved caliche pit in Section 1, T25S, R31E. Alternate source will be caliche pit from Mark McCloy (806) 683-6990.

Surface Use Plan

#### 3. Location of Existing Well:

The One-Mile Radius Map Exhibit 4 shows existing wells within a one-mile radius of the proposed wellbore.

# 4. Location of Existing and/or Proposed Facilities:

- A. COG Production LLC does operate an oil production facility on this lease.
- B. If the well is productive, contemplated facilities will be as follows:
  - 1) Will utilize tank battery and facilities at the existing Windward Central Tank Battery.
  - 2) Production will be sent to the Windward Central Tank Battery facility. A surface flow line of approximately 335.4' of 3" steel pipe carrying oil, gas and water under a maximum pressure of 125 psi will follow the road to the facility at the Windward Central Tank Battery location. We plan to install a 4" surface polyethylene pipe transporting Gas Lift Gas from the Windward Central Tank Battery to the Windward Federal #8H. The surface Gas Lift Gas pipe of approximately 335.4' under a maximum pressure of 125 psi will be installed no farther than 10 feet from the edge of the road.
- C. Any additional caliche will be obtained from the actual well site. If caliche does not exist or is not plentiful from the well site, the caliche will be hauled from a BLM approved caliche pit in Section 1, T25S, R31E. Alternate source will be caliche pit from Mark McCloy (806) 683-6990. Any additional construction materials will be purchased from contractors.
  - 3) It will be necessary to run electric power if this well is productive. Power will be provided by Xcel Energy and they will submit a separate plan and ROW for service to the well location.
  - 4) If the well is productive, rehabilitation plans will include the following:
  - The original topsoil from the well site will be returned to the location, and the site will be re-contoured as close as possible to the original site.

# 5. Location and Type of Water Supply:

The well will be drilled with combination brine and fresh water mud system as outlined in the drilling program. The water will be obtained from a private source, Rock House Ranch (575) 885-4195 or Mesquite Services (575) 887-4847. No water well will be drilled on the location.

#### 6. Source of Construction Materials and Location "Turn-Over" Procedure:

Obtaining caliche: One primary way of obtaining caliche to build locations and roads will be by "turning over" the location. This means, caliche will be obtained from the actual well site. Amount will vary for each pad. The procedure below has been approved by BLM personnel:

- A. Equipment that is needed to construct the proposed location will be as follows: Two dozers to flip the site for caliche and to move topsoil, one blade to level the surface, one morograder to roll and compact this site, one backhoe to dig the cellar, one water truck to water location and dust abatement and two dump trucks to haul surface material. If caliche is not available onsite and have to haul caliche from a private pit, in addition to equipment mentioned above we will have 10 belly dumps and one front end loader.
- B. The time line to complete construction will be approximately 10 days.
- C. The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
- D. An approximate 160' X 160' area is used within the proposed well site to remove caliche.
- E. Subsoil is removed and stockpiled within the surveyed well pad.
- F. When caliche is found, material will be stock piled within the pad site to build the location and road.
- G. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
- H. Once well is drilled, the stock piled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced.
- I. Neither caliche, nor subsoil will be stock piled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in the Well Site Layout or survey plat.

In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit or other established mineral pit in Section 1, T25S, R31E. Alternate source will be caliche pit from Mark McCLoy (806) 683-6990.

#### 7. Methods of Handling Water Disposal:

- A. The well will be drilled utilizing a closed loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to R360's disposal site located at 4507 West Carlsbad Highway, Hobbs, NM 88240.
- B. Drilling fluids will be contained in steel mud pits and taken to R360's disposal site located at 4507 West Carlsbad Highway, Hobbs, NM 88240.
- C. Water produced from the well during completion will be held temporarily in steel tanks and then taken to an NMOCD approved commercial disposal facility. R360's disposal site located at 4507 West Carlsbad Highway, Hobbs, NM 88240.
- D. It is anticipated that the disposal of produced water will be trucked to the Turquoise 30 Federal 1 SWD (30-24S-32E) or Gold Coast 26 Federal SWD 1 (26-24S-32E). Might also be trucked to unspecified commercial SWD wells in this area.
- E. Garbage and trash produced during drilling or completion operations will be collected in a trash bin and hauled to an approved landfill-Lea Landfill LLC. Located at Mile Marker 64, Highway 62-180 East, P O Box 3247, Carlsbad, NM 88221. No toxic waste or hazardous chemicals will be produced by this operation.
- F. Human waste and grey water will need to be properly contained and disposed of. Proper disposal and elimination of waste and grey water may include but are not limited to portable septic systems and/or portable waste gathering systems (i.e. portable toilets).
- G. After the rig is moved out and the well is either completed or abandoned, all waste materials will be cleaned up within 30 days. In the event of a dry hole only a dry hole marker will remain.

# 8. Ancillary Facilities:

No airstrip, campsite or other facilities will be built as a result of the operation on this well.

# 9. Well Site Layout:

A. The drill pad layout, with elevations staked by Harcrow Surveying, is shown in the Elevation Plat. Dimensions of the pad and pits are shown on the Rig Layout. V door direction is East. Topsoil, if available, will be stockpiled per BLM specifications. Because the pad is almost level no major cuts will be required.

B. The Rig Layout Closed-Loop exhibit shows the proposed orientation of closed loop system and access road. No permanent living facilities are planned, but a temporary foreman/toolpusher's trailer will be on location during the drilling operations.

#### 10. Plans for Restoration of the Surface:

- A. Interim Reclamation will take place within six months after the well has been completed. The pad will be downsized by reclaiming the areas not needed for production operations. The portions of the pad that are not needed for production operations will be recontoured to its original state as much as possible. The caliche that is removed will be reused to either build another pad site or for road repairs within the lease. The stockpiled topsoil will then be spread out reclaimed area and reseeded with a BLM approved seed mixture. In the event that the well must be worked over or maintained, it may be necessary to drive, park, and/or operate machinery on reclaimed land. This area will be repaired or reclaimed after work is complete.
- B. Final Reclamation: Upon plugging and abandoning the well all caliche for well pad and lease road will be removed and surface will be recountoured to reflect its surroundings as much as possible within six months. Caliche will be recycled for road repair or reused for another well pad within the lease. If any topsoil remains, it will be spread out and the area will be re-seeded with a BLM approved mixture and re-vegetated as per BLM orders. When required by BLM, the well pad site will be restored to match preconstruction grades.

#### 11. Sedimentation and Erosion Control

Immediately following pad construction approximately 970' of straw waddles will be placed on the top edge of the South and East sides of the location to reduce sediment impacts to fragile/sensitive soils.

# 12. Surface Ownership:

- A. The surface is owned U.S. Government and is administered by the Bureau of Land Management. The surface is multiple uses with the primary uses of the region for grazing of livestock and the production of oil and gas.
- B. The surface tenant is Mark and Annette McCloy Trust, P O Box 795, Tatum, NM 88267.
- C. The proposed road routes and surface location will be restored as directed by the BLM.

#### 13. Other Information:

- A. The area around the well site is grassland and the topsoil is sandy. The vegetation is moderately sparse with native prairie grasses, some mesquite and shinnery oak. No wildlife was observed but it is likely that mule deer, rabbits, coyotes and rodents traverse the area.
- B. There is no permanent or live water in the immediate area.
- C. There are no dwellings within 2 miles of this location.
- D. If needed, a Cultural Resources Examination is being prepared by Boone Arch Services of NM, LLC., 2030 North Canal, Carlsbad, New Mexico, 88220, phone # 575-885-1352 and the results will be forwarded to your office in the near future. Otherwise, COG will be participating in the Permian Basin MOA Program.

#### 14. Bond Coverage:

Bond Coverage is Statewide Bonds # NMB000860 and NMB000845

## 15. Lessee's and Operator's Representative:

The COG Production LLC representative responsible for assuring compliance with the surface use plan is as follows:

Sheryl Baker Drilling Superintendent COG Production LLC 2208 West Main Street Artesia, NM 88210 Phone (575) 748-6940 (office) (432) 934-1873 (cell) Ray Peterson Drilling Manager COG Production LLC One Concho Center 600 W Illinois Ave Midland, TX 79701 Phone (432) 685-4304 (office) (432) 818-2254 (business)

Page 7