

17-728

HOBBS OCD  
Form 3160-3  
(March 2010)  
NOV 29 2017  
RECEIVED

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED  
OMB No. 1004-0137  
Expires October 31, 2014

5. Lease Serial No.  
NMLC062749B

6. If Indian, Allottee or Tribe Name

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No. **320074**  
ZIA HILLS 19 FEDERAL COM 109H

9. API Well No.  
**30-025-44236**  
10. Field and Pool, or Exploratory **(98065)**  
WOLFCAMP / WOLFCAMP

11. Sec., T. R. M. or Blk. and Survey or Area  
SEC 19 / T26S / R32E / NMP

12. County or Parish  
LEA

13. State  
NM

1a. Type of work: ☒ DRILL ☐ REENTER

1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

2. Name of Operator  
CONOCOPHILLIPS COMPANY **(217817)**

3a. Address  
600 N. Dairy Ashford Rd Houston TX 77079

3b. Phone No. (include area code)  
(281)293-1748

4. Location of Well (Report, location clearly and in accordance with any State requirements.)  
At surface LOT 2 / 2498 FNL / 1600 FWL / LAT 32.028667 / LONG -103.717881  
At proposed prod. zone LOT 3 / 2618 FSL / 1320 FWL / LAT 32.057406 / LONG -103.718808

14. Distance in miles and direction from nearest town or post office\*  
44.9 miles

15. Distance from proposed\*  
location to nearest  
property or lease line, ft.  
171 feet  
(Also to nearest drig. unit line, if any)

16. No. of acres in lease  
321.45

17. Spacing Unit dedicated to this well  
363.93

18. Distance from proposed location\*  
to nearest well, drilling, completed, 33 feet  
applied for, on this lease, ft.

19. Proposed Depth  
11619 feet / 22124 feet

20. BLM/BIA Bond No. on file  
FED: ES0085

21. Elevations (Show whether DF, KDB, RT, GL, etc.)  
3182 feet

22. Approximate date work will start\*  
11/01/2017

23. Estimated duration  
90 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, must be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the BLM.

25. Signature  
(Electronic Submission)

Name (Printed/Typed)  
Ashley Bergen / Ph: (432)688-6938

Date  
08/02/2017

Title  
Associate, Regulatory MCBU

Approved by (Signature)  
(Electronic Submission)

Name (Printed/Typed)  
Cody Layton / Ph: (575)234-5959

Date  
11/10/2017

Title  
Supervisor Multiple Resources

Office  
CARLSBAD

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

APPROVED WITH CONDITIONS  
Approval Date: 11/10/2017

Double-sided  
X

K2  
12/10/17  
Requires NGL order  
from Santa Fe  
need to move BLT 10' EAST



OCD Hobbs

17-728

U.S. Department of the Interior

Bureau of Land Management

## Application for Permit to Drill

## APD Package Report

Date Printed: 11/20/2017 09:58 AM

APD ID: 10400017293

Well Status: AAPD

APD Received Date: 08/02/2017 08:45 AM

Well Name: ZIA HILLS 19 FEDERAL COM

Operator: CONOCOPHILLIPS COMPANY

Well Number: 109H

## APD Package Report Contents

Pooled 98065

RECEIVED  
NOV 29 2017  
HOBBS OCD

- Form 3160-3
- Operator Certification Report
- Application Report
- Application Attachments
  - Well Plat: 1 file(s)
- Drilling Plan Report
- Drilling Plan Attachments
  - Blowout Prevention Choke Diagram Attachment: 1 file(s)
  - Blowout Prevention BOP Diagram Attachment: 1 file(s)
  - Casing Design Assumptions and Worksheet(s): 4 file(s)
  - Hydrogen sulfide drilling operations plan: 2 file(s)
  - Proposed horizontal/directional/multi-lateral plan submission: 2 file(s)
  - Other Facets: 4 file(s)
  - Other Variances: 3 file(s)
- SUPO Report
- SUPO Attachments
  - Existing Road Map: 1 file(s)
  - New Road Map: 1 file(s)
  - Attach Well map: 1 file(s)
  - Water source and transportation map: 1 file(s)
  - Well Site Layout Diagram: 2 file(s)
  - Existing Vegetation at the well pad attachment: 1 file(s)
  - ROW Applications: 1 file(s)
  - Other SUPO Attachment: 9 file(s)
- PWD Report
- PWD Attachments
  - None



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Application Data Report

11/20/2017

APD ID: 10400017293

Submission Date: 08/02/2017

Highlighted data  
reflects the most  
recent changes

Operator Name: CONOCOPHILLIPS COMPANY

Well Name: ZIA HILLS 19 FEDERAL COM

Well Number: 109H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - General

APD ID: 10400017293

Tie to previous NOS?

Submission Date: 08/02/2017

BLM Office: CARLSBAD

User: Ashley Bergen

Title: Associate, Regulatory MCBU

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMLC062749B

Lease Acres: 321.45

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? NO

Permitting Agent? NO

APD Operator: CONOCOPHILLIPS COMPANY

Operator letter of designation:

### Operator Info

Operator Organization Name: CONOCOPHILLIPS COMPANY

Operator Address: 600 N. Dairy Ashford Rd

Zip: 77079

Operator PO Box:

Operator City: Houston

State: TX

Operator Phone: (281)293-1748

Operator Internet Address:

### Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: ZIA HILLS 19 FEDERAL COM

Well Number: 109H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: WOLFCAMP

Pool Name: WOLFCAMP

Is the proposed well in an area containing other mineral resources? NONE

Operator Name: CONOCOPHILLIPS COMPANY

Well Name: ZIA HILLS 19 FEDERAL COM

Well Number: 109H

Describe other minerals:

Is the proposed well in a Helium production area? N Use Existing Well Pad? NO New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: ZIA Number: 2

Well Class: HORIZONTAL

HILLS 19 PAD

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 44.9 Miles

Distance to nearest well: 33 FT

Distance to lease line: 171 FT

Reservoir well spacing assigned acres Measurement: 363.93 Acres

Well plat: ZIA\_HILLS\_19\_FEDERAL\_COM\_109H\_C\_102\_07-26-2017.pdf

Well work start Date: 11/01/2017

Duration: 90 DAYS

### Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	249 8	FNL	160 0	FWL	26S	32E	19	Lot 2	32.02866 7	- 103.7178 81	LEA	NEW MEXI CO	NEW MEXI CO	F	NMLC0 62749B	318 2	0	0
KOP Leg #1	283 8	FNL	140 0	FWL	26S	32E	19	Aliquot SENW	32.02773 2	- 103.7185 24	LEA	NEW MEXI CO	NEW MEXI CO	F	NMLC0 62749B	- 781 8	110 00	110 00
PPP Leg #1	233 7	FNL	132 0	FWL	26S	32E	19	Aliquot SENW	32.02909 7	- 103.7187 86	LEA	NEW MEXI CO	NEW MEXI CO	F	NMLC0 62749B	- 826 8	114 50	114 50



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Drilling Plan Data Report

11/20/2017

APD ID: 10400017293

Submission Date: 08/02/2017

Highlighted data  
reflects the most  
recent changes

Operator Name: CONOCOPHILLIPS COMPANY

Well Name: ZIA HILLS 19 FEDERAL COM

Well Number: 109H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	QUATERNARY	3182	0	0		NONE	No
2	RUSTLER	2063	1119	1119	DOLOMITE, ANHYDRITE	NONE	No
3	SALADO	1893	1289	1289	SALT	NONE	No
4	CASTILE	903	2279	2279	SALT	NONE	No
5	DELAWARE	-1077	4259	4259	SANDSTONE	NATURAL GAS, OIL	No
6	CHERRY CANYON	-1987	5169	5169	SANDSTONE	NATURAL GAS, OIL	No
7	BRUSHY CANYON	-3467	6649	6649	SANDSTONE	NATURAL GAS, OIL	No
8	BONE SPRING	-4867	8049	8049	SANDSTONE	NATURAL GAS, OIL	No
9	BONE SPRING 1ST	-6022	9204	9204	SANDSTONE	NATURAL GAS, OIL	No
10	BONE SPRING 2ND	-6697	9879	9879	SANDSTONE	NATURAL GAS, OIL	No
11	BONE SPRING 3RD	-7167	10349	10349	LIMESTONE	NATURAL GAS, OIL	No
12	WOLFCAMP	-8197	11379	11379	LIMESTONE, SHALE, SANDSTONE	NATURAL GAS, OIL	Yes

### Section 2 - Blowout Prevention

Pressure Rating (PSI): 10M

Rating Depth: 22124

Equipment: Rotating Head, Annular Preventer, Pipe/Blind Rams, Kill Lines, Choke Lines, Adapter Spool

Requesting Variance? YES

**Variance request:** A variance to use flexible choke line(s) from the BOP to Choke Manifold. Testing certificate is attached in "Flexhose Variance data" document. A variance to use a multibowl wellhead system. Please see attached in section 8 of drilling plan.

**Testing Procedure:** BOP/BOPE will be isolated from the casing and tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. BOPE controls will be installed prior to drilling

**Operator Name:** CONOCOPHILLIPS COMPANY

**Well Name:** ZIA HILLS 19 FEDERAL COM

**Well Number:** 109H

under the surface casing and will be used until the completion of drilling operations. The intermediate interval and the production interval will be tested per 10M working system requirements. See attached "Drill Plan" document.

**Choke Diagram Attachment:**

Zia\_Hills\_19\_Pad\_2\_Choke\_Manifold\_07-26-2017.pdf

**BOP Diagram Attachment:**

Zia\_Hills\_19\_Pad\_2\_BOPE\_07-26-2017.pdf

### Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	14.75	11.75	NEW	API	N	0	1170	0	1170	-7818	-8988	1170	J-55	47	BUTT	2.89	5.87	DRY	15.4	DRY	15.4
2	INTERMEDIATE	10.875	8.625	NEW	API	N	0	11400	0	11400	-7818	-19218	11400	P-110	32	BUTT	1.48	1.55	DRY	3.53	DRY	3.53
3	PRODUCTION	7.875	5.5	NEW	API	N	0	22124	0	22124	-7818	-29942	22124	P-110	23	OTHER - TXP	1.5	1.71	DRY	2.29	DRY	2.29

**Casing Attachments**

**Casing ID:** 1      **String Type:** SURFACE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

ZIA\_HILLS\_19\_FEDERAL\_COM\_109H\_csg\_design\_07-26-2017.pdf

Operator Name: CONOCOPHILLIPS COMPANY

Well Name: ZIA HILLS 19 FEDERAL COM

Well Number: 109H

#### Casing Attachments

Casing ID: 2 String Type: INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

ZIA\_HILLS\_19\_FEDERAL\_COM\_109H\_csg\_design\_07-26-2017.pdf

Casing ID: 3 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

ZIA\_HILLS\_19\_FEDERAL\_COM\_109H\_csg\_design\_07-26-2017.pdf

Zia\_Hills\_19\_Pad\_2\_Production\_csg\_specification\_07-26-2017.pdf

#### Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1170	470	1.68	13.5	789.6	100	Class C	+ 4.0% Bentonite + 0.2% Anti-Foam + 2.0% CaCl2 + 0.125lb/sk LCM + 0.1% Dispersant.
SURFACE	Tail				240	1.35	14.8	324	100	Class C	0.2% Anti-Foam + 0.1% Lost Circ Control
INTERMEDIATE	Lead		0	1140 0	800	2.7	11	2160	30	Class C	75.00 lb/sk BWOB D049 + 1.00 % BWOB D013 Retarder + 10.00

**Operator Name:** CONOCOPHILLIPS COMPANY

**Well Name:** ZIA HILLS 19 FEDERAL COM

**Well Number:** 109H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
											% BWOB D020 Extender + 0.02 gal/sk VBWOB D047 Anti foam + 2.00 % BWOB D154 Extender + 0.15 % BWOB D208 Viscosifier
INTERMEDIATE	Tail				670	1.29	13.5	864	30	Class C	75.00 lb/sk BWOB D049 + 0.50 % BWOB D013 Retarder + 1.00 % BWOB D020 Extender + 3.00 lb/sk WBWOB D042 Extender + 0.02 gal/sk VBWOB D047Anti foam + 0.10 % BWOB D065 Dispersant + 0.13 lb/sk WBWOB D130 Lost Circulation + 0.30 % BWOB D238 Fluid loss
PRODUCTION	Lead		0	2212 4	0	0	0	0	0	no lead	no lead
PRODUCTION	Tail				2300	1.08	16.4	2484	15	Class H	1.00 % BWOB D020 Extender + 0.02 gal/sk VBWOB D047 Anti Foam + 0.10 % BWOB D065 Dispersant + 0.15 % BWOB D255 Fluid loss + 0.30 % BWOB D800 Retarder

## Section 5 - Circulating Medium

**Mud System Type:** Closed

**Will an air or gas system be Used?** NO

**Description of the equipment for the circulating system in accordance with Onshore Order #2:**

**Diagram of the equipment for the circulating system in accordance with Onshore Order #2:**

**Describe what will be on location to control well or mitigate other conditions:** Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times. See attached "Drill Plan" for additional information.

**Describe the mud monitoring system utilized:** Closed-loop mud system using steel mud containers will be on location. Mud monitoring of any changes in levels (gains or losses) will use Pressure Volume Temperature, Pason, Visual Observations. See attached "Drill Plan" for additional information.



**Operator Name:** CONOCOPHILLIPS COMPANY

**Well Name:** ZIA HILLS 19 FEDERAL COM

**Well Number:** 109H

### Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	1140 0	OIL-BASED MUD	8.6	9.4							
0	2212 4	OIL-BASED MUD	9.5	13.5							
0	1170	SPUD MUD	8.34	8.6							

### Section 6 - Test, Logging, Coring

**List of production tests including testing procedures, equipment and safety measures:**

Production tests will be conducted multiple times per week, through a test separator, during first months following completion. Thereafter, tests will be less frequently. See attached "Drill Plan" for additional information

**List of open and cased hole logs run in the well:**

GR

**Coring operation description for the well:**

No coring operation is planned, at this time.

### Section 7 - Pressure

**Anticipated Bottom Hole Pressure:** 8157

**Anticipated Surface Pressure:** 5600.82

**Anticipated Bottom Hole Temperature(F):** 203

**Anticipated abnormal pressures, temperatures, or potential geologic hazards?** NO

**Describe:**

**Contingency Plans geohazards description:**

**Contingency Plans geohazards attachment:**

**Hydrogen Sulfide drilling operations plan required?** YES

**Hydrogen sulfide drilling operations plan:**

ZIA\_HILLS\_19\_PAD\_2\_H2S\_C\_Plan\_07-26-2017.pdf

ZIA\_HILLS\_19\_PAD\_2\_Rig\_Layout\_07-26-2017.pdf

**Operator Name:** CONOCOPHILLIPS COMPANY

**Well Name:** ZIA HILLS 19 FEDERAL COM

**Well Number:** 109H

## **Section 8 - Other Information**

**Proposed horizontal/directional/multi-lateral plan submission:**

ZIA\_HILLS\_19\_Federal\_COM\_109H\_Directional\_plan\_08-02-2017.pdf

ZIA\_HILLS\_19\_FEDERAL\_COM\_109H\_Wellbore\_Schematic\_20170830141132.pdf

**Other proposed operations facets description:**

**Other proposed operations facets attachment:**

Zia\_Hills\_19\_Pad\_2\_Drill\_Waste\_Containment\_07-26-2017.pdf

Zia\_Hills\_19\_Pad\_2\_Gas\_Capture\_Plan\_07-26-2017.pdf

ZIA\_HILLS\_19\_Federal\_COM\_109H\_Drilling\_plan\_20170915103117.pdf

Option\_2\_for\_cement\_plan\_20170915103130.pdf

**Other Variance attachment:**


Zia\_Hills\_19\_Pad\_2\_Generic\_WH\_07-26-2017.pdf

Zia\_Hills\_19\_Pad\_2\_Flexhose\_Variance\_07-26-2017.pdf

Zia\_Hills\_19\_Pad\_2\_Running\_Procedure\_2\_20170915103141.pdf

**CHOKE MANIFOLD ARRANGEMENT - 10M Choke**

per Onshore Oil and Gas Order No. 2 utilizing 5M/10M Equipment




Item	Description
1	Pressure Gauge
2	2 Gate Valves, 3-1/16" 10M
3	2 Gate Valves, 3-1/16" 10M
4	2 Gate Valves, 3-1/16" 10M
5	2 Gate Valves, 3-1/16" 10M
6	Upper Manual Adjustable Choke, 4-1/16", 10M
7	Lower Manual Adjustable Choke, 4-1/16", 10M
8	Gate Valve, 3-1/16" 10M
9	Gate Valve, 3-1/16" 10M
10	Remote Controlled Hydraulic Adjustable Choke, 4-1/16", 10M
11	Gate Valve, 3-1/8" 5M
12	Gate Valve, 3-1/8" 5M
13	Gate Valve, 3-1/16" 10M

The 10M Choke Manifold & Valves will be tested to rated working pressure.

\*Choke manifold will have one remotely operated valve and a manual adjustable valve in front of the choke manifold, as detailed in the Onshore Order 2. It currently contains one 10M hydraulic choke for a total of three choke branches (two manual and one hydraulic).

**BLOWOUT PREVENTER ARRANGEMENT - 13-5/8" 5M BOPE**


per Onshore Oil and Gas Order No. 2 utilizing 5M Rated Equipment



Item	Description
1	Rotating Head, 13-5/8"
2A	Fill up Line and Valve
2B	Flow Line (10")
2C	Shale Shakers and Solids Settling Tank
2D	Cuttings Bins for Zero Discharge
2E	Rental Mud Gas Separator with vent line to flare and return line to mud system
3	Annular BOP (13-5/8", 5M)
4	Double Ram (13-5/8", 5M, Blind Ram top x Pipe Ram bottom)
5	Kill Line (2" flexible hose, 5M)
6	Kill Line Valve, Inner (2-1/16", 5M)
7	Kill Line Valve, Outer (2-1/16", 5M)
8	Kill Line Check Valve (2-1/16", 5M)
9	Choke Line (3-1/8", 5M Stainless Steel Coflex Line)
10	Choke Line Valve, Inner (3-1/8", 5M)
11	Choke Line Valve, Outer (3-1/8", Hydraulically operated, 5M)
12	Spacer Spool (13-5/8", 5M)
13	Casing Head (13-5/8" 5M)
14	Ball Valve and Threaded Nipple on Casing Head Outlet, 2" 5M
15	Surface Casing

**BLOWOUT PREVENTER ARRANGEMENT - 11" 10M BOPE**


per Onshore Oil and Gas Order No. 2 utilizing 10M Rated Equipment



Item	Description
1	Rotating Head
2A	Fill up Line and Valve
2B	Flow Line (10")
2C	Shale Shakers and Centrifuges
2D	Cuttings Bins for Zero Discharge
2E	Mud Gas Separator with vent line to flare and return line to mud system
3	Annular Preventer (11", 10M)
4	Double Ram (11", 10M, Pipe Ram top x Blind Ram bottom)
5	Drilling Spool (11" 10M)
4C	Single Ram (11", 10M, Pipe Rams)
6	Kill Line Gate Valve, Inner (2-1/16", 10M)
7	Kill Line Gate Valve, Outer (2-1/16", 10M)
8	Kill Line Check Valve (2-1/16", 10M)
9	CoFlex Choke Line (4-1/16", 10M)
10	Choke Line Gate Valve, Inner (4-1/16", 10M)
11	Choke Line Hydraulically Operated Gate Valve, Outer, (4-1/6" 10M w/ Double Acting HCR) Drilling Spool Adapter (11", 10M)
12	

**BLOWOUT PREVENTER ARRANGEMENT - 13-5/8" 10M BOPE**

per Onshore Oil and Gas Order No. 2 utilizing 10M Rated Equipment



Item	Description
1	Rotating Head
2A	Fill up Line and Valve
2B	Flow Line (10")
2C	Shale Shakers and Centrifuges
2D	Cuttings Bins for Zero Discharge
2E	Mud Gas Separator with vent line to flare and return line to mud system
3	Annular Preventer (13-5/8", 10M)
4	Double Ram (13-5/8", 10M, Pipe Ram top x Blind Ram bottom)
5	Drilling Spool (13-5/8" 10M)
4C	Single Ram (13-5/8", 10M, Pipe Rams)
6	Kill Line Gate Valve, Inner (2-1/16", 10M)
7	Kill Line Gate Valve, Outer (2-1/16", 10M)
8	Kill Line Check Valve (2-1/16", 10M)
9	CoFlex Choke Line (4-1/16", 10M)
10	Choke Line Gate Valve, Inner (4-1/16", 10M)
11	Choke Line Hydraulically Operated Gate Valve, Outer, (4-1/6" 10M w/ Double Acting HCR)
12	Drilling Spool Adapter (13-5/8", 10M)

Type	Depth	Csg	Wt	WY	Col	Tensile	Drill Fluid
Surface Casing	MD	Length ft					
Intermediate 1 Casing	1170	1170	1170	47	3070	1510	737000
Intermediate 2 Casing	11400	11380	11400	32	7860	3420	1006000
Production 1 Casing	0	0	0				
Production 2 Casing	22124	11650	22124	23	12630	11100	641000
							12

Uses TVD!!!

#### Burst Design (Safety) Factors = BLM Criteria

Burst Design Safety Factor SF<sub>B</sub>

BLM = P<sub>i</sub> / SFE

Where

P<sub>i</sub> = The internal pressure (lb/inch<sup>2</sup>) (bursting pressure) (psi) (maximum pressure per section)

SFE = The minimum acceptable burst design factor SF<sub>B</sub> = 1.0

#### Collapse Design (Safety) Factors = BLM Criteria

Collapse Design Safety Factor SFC

SFC = P<sub>c</sub> / (DWT + 0.01 \* L)

Where

P<sub>c</sub> = The external pressure (lb/inch<sup>2</sup>) (collapse pressure) (psi) (maximum pressure per section)

L = The length of the pipe (ft)

DWT = The weight of the pipe (lb/ft)

#### Joint Strength Design (Safety) Factors = BLM Criteria

Joint Strength Design Safety Factor SFI

SFI = T<sub>j</sub> / W<sub>j</sub>

Where

T<sub>j</sub> = The joint strength (lb/inch<sup>2</sup>) (bursting pressure) (psi)

W<sub>j</sub> = The weight of the joint (lb/ft)

Surface Casing	SFE =	3070	/	523	=	5.87
Intermediate 1 Casing	SFE =	7860	/	5557	=	1.41
Intermediate 2 Casing	SFE =	0	/	0	=	#DIV/0!
Production 1 Casing	SFE =	12630	/	7241	=	1.74
Production 2 Casing	SFE =	0	/	0	=	#DIV/0!

Surface Casing	SFC =	1510	/	523	=	2.88
Intermediate 1 Casing	SFC =	3420	/	5557	=	0.62 *
Intermediate 2 Casing	SFC =	0	/	0	=	#DIV/0!
Production 1 Casing	SFC =	11100	/	7241	=	1.53
Production 2 Casing	SFC =	0	/	0	=	#DIV/0!

Surface Casing	SFI Dry =	737000	/	54590	=	13.4
Intermediate 1 Casing	SFI Dry =	1006000	/	34480	=	2.92
Intermediate 2 Casing	SFI Dry =	0	/	0	=	#DIV/0!
Production 1 Casing	SFI Dry =	641000	/	26882	=	2.40
Production 2 Casing	SFI Dry =	0	/	0	=	#DIV/0!

\* SFE = 1.48 is based on internal Casing/Drill pipe casing design assuming 1/3 casing execution

# Production Casing Specification Sheet

For the latest performance data, always visit our website: [www.tenaris.com](http://www.tenaris.com)

August 29 2016



**Connection:** TenarisXP® BTC  
**Casing/Tubing:** CAS  
**Coupling Option:** REGULAR

**Size:** 5.500 in.  
**Wall:** 0.361 in.  
**Weight:** 20.00 lbs/ft  
**Grade:** P110  
**Min. Wall Thickness:** 87.5 %

PIPE BODY DATA			
GEOMETRY			
Nominal OD	5.500 in.	Nominal Weight	20.00 lbs/ft
Nominal ID	4.778 in.	Wall Thickness	0.361 in.
Plain End Weight	19.83 lbs/ft	Standard Drift Diameter	4.653 in.
		Special Drift Diameter	N/A
PERFORMANCE			
Body Yield Strength	641 x 1000 lbs	Internal Yield	12630 psi
Collapse	11100 psi	SMYS	110000 psi
TENARISXP® BTC CONNECTION DATA			
GEOMETRY			
Connection OD	6.100 in.	Coupling Length	9.450 in.
Critical Section Area	5.828 sq. in.	Threads per in.	5.00
		Connection ID	4.766 in.
		Make-Up Loss	4.204 in.
PERFORMANCE			
Tension Efficiency	100 %	Joint Yield Strength	641 x 1000 lbs
Structural Compression Efficiency	100 %	Structural Compression Strength	641 x 1000 lbs
External Pressure Capacity	11100 psi	Internal Pressure Capacity <sup>(1)</sup>	12630 psi
		Structural Bending <sup>(2)</sup>	92 °/100 ft
ESTIMATED MAKE-UP TORQUES <sup>(3)</sup>			
Minimum	11270 ft-lbs	Optimum	12520 ft-lbs
		Maximum	13770 ft-lbs
OPERATIONAL LIMIT TORQUES			
Operating Torque	21500 ft-lbs	Yield Torque	23900 ft-lbs



# Bill of Materials

**NOTE** Contact your Cameron representative for replacement part inquiries. Cameron personnel can check the latest revision of the assembly bill-of-material to obtain the appropriate and current replacement part number.

MN-DS HOUSING			MN-DS HOUSING			MN-DS HOUSING		
Item	Qty	Description	Item	Qty	Description	Item	Qty	Description
A1	1	Conversion; Casing Head Housing, Type 'Mn-Ds', 10K, 13-5/8 Nom 10K Oec BX-159w/20.500-4TPI LH Stub Acme Top f/ Thded Flg and Prep f/ Internal Snap Ring x 13-3/8 SOW Btm w/ Four Grout Ports, w/ (2) Upper 1-13/16 API 10K BX-151 Outlets w/1-1/4 API Vr Thds Part# 2031060-48-02	A7	1	Assy; Seal Packoff f/ 11 Nom Type 'Mn-Ds', w/ 9.875-4TPI LH Stub Acme Thd w/ 7.75 Dbl 'T' Seals At ID and Dovetails At OD Part# 2217588-05-03	A20	1	VR Plug 1-1/4 LP Thd, 1-13/16 2K - 10K Part# 2222164-01-01
A2	1	Body, Bushing Reducer, 13-3/8 SOW x 11-3/4 SOW Part# 2310058-03-01	A8	1	Gate Valve, Manual, Model M Pow-R-Seal, 2-1/16 Bore, 5K Psi Psi, 2-1/16 API Flg x Flg Part# 2148451-31-22	A21	1	Gate Valve, Manual, Model FLS, 1-13/16 Bore, 10K Psi, 1-13/16 API Flg x Flg Part# 141510-41-91-01
A3	1	Body, Load Ring f/ 20 Casing (.375 C.S. Casing) To Accept Low Pressure Adapter Part# 2329761-07-01	A9	2	Companion Flange, 2-1/16 API 5K x 2" API LP Thd Part# 142362-01-03-02	A22	2	Companion Flange, 1-13/16 API 10K w/ 2" API Line Pipe, 5000 Psi WP Part# 142359-01-03-02
A4	1	Casing Hanger, Mandrel, Type 'Mn-Ds', 13-5/8 Nom x 8-5/8 API BC Box Thd Btm x 10.000-4TPI L.H Stub Acme Running Thd, Min Bore: 8.000, 10,000 Psi Max Working Pressure, 700,000 Lbs Max Hanging Load Part# 2345509-17	A10	4	Bull Plug 2" LP w/ 1/2 NPT x 3.750" Lg Part# 007481-01	A23	1	Ring Gasket, BX-159 Part# 702003-15-92
A5	1	Assy; Packoff Support Bushing, Type MN-DS', 13-5/8 10K, w/ 13-5/8 Nom Dovetail Seal, and 9-5/8 Nom 'T' Seal and w/ Internal and External Lock Ring Prep, Min. Bore 8.835 Part# 2161673-01-01	A11	2	Bleeder Fitting, Plug 1/2 NPT 4140 Nace Part# 2738068-02			
A6	1	Rotating Mandrel Hanger, Type 'MN-DS', 11 Nom, 5-1/2 20 Lb/Ft Tenaris XP Buttress Box Thd Btm X 7.500- 4 TPI Stub ACME Running Thd w/ 5.010 OD type 'H' BPV Thd w/ 7 Nom Slick Neck Top, w/ FLOW-by Slots; Min Bore: 4.754 Part# 2345649-49-01	A12	2	Needle Valve, 1/2 NPT 10000 Psi Part# 006818-23			
			A13	1	Pressure Gauge 0-5M Liquid Filled Part# Y52100-00300791			
			A14	3	Ring Gasket, R-24 Part# 702001-24-02			
			A15	8	Stud w/(2) Nuts 7/8" x 6" Lg Part# Y51201-20220301			
			A16	1	VR Plug 1-1/2 In 11-1/2 TPI -3/4 TPF 'Vee' Tubing Thd, 2-1/16 2K - 10K Part# 2222164-02-01			
			A17	3	Ring Gasket, BX-151 Part# 702003-15-12			
			A18	8	Stud w/(2) Nuts, 3/4"-10 x 5-1/4" Lg Part# Y51201-20120201			
			A19	1	Pressure Gauge 0-10M Liquid Filled Part# Y52100-00301391			

**RP-003766**

Rev 01  
Page 10

**13-5/8" 10K MN-DS System**  
20" x 11-3/4" x 8-5/8" x 5-1/2" Casing Program

 **CAMERON**  
A Schlumberger Company

# Bill of Materials

**NOTE** Contact your Cameron representative for replacement part inquiries. Cameron personnel can check the latest revision of the assembly bill-of-material to obtain the appropriate and current replacement part number.

SERVICE TOOLS			SERVICE TOOLS			EMERGENCY EQUIPMENT		
Item	Qty	Description	Item	Qty	Description	Item	Qty	Description
ST1	1	Conversion Assy; Casing Head Torque Tool, f/ 'MN-DS' w/ Lift Plate, 13-3/8 In API 8Rnd Short Thread Casing Box Thread Top X .750-10UNC (16) Bolt Pattern Btm, (8) Torque Pins, Min Bore: 12.605 Part# 2143701-75	ST7	1	Running Tool, 'MN-DS' Type f/ 13-5/8" Nom Pack-off Support Bushing w/ 4-1/2" API IF Thd Top x 4-1/2" API IF Thd Btm and 12.375" 4-TPI LH Stub Acme Thd, Safe Working Load: 275K Lbf Part# 2017712-10-01	E1	1	Assy; MN-DS-IC-1 Casing Slip, 13-5/8 Nom X 8-5/8 Casing; w/ Holes F/ Antirotation Pins, (Control Height) Part# 2161741-09-01
ST1A	1	Conversion Body; Lift Plate for Casing Head Torque Tool w/ Exrt 14.75 Stub ACME Rng Thd and (2) OD O-ring Seals Part# 2143700-76	ST8	1	Assy; Test Plug, Type 'IC', 11" Nom 4-1/2" IF Box X Pin Btm, w/ Weep Hole On Top Portion Of Test Plug, w/(2) Dovetail Seal Grooves Part# 2247042-07-01	E2	1	Assy; Emergency Bushing Packoff Support, 'MN-DS', 13-5/8, w/ 13-5/8 Dovetail; 8-5/8 'T' Seals, w/ Internal and External Locking Prep; 10K Service Part# 2161673-20-01
ST2	1	Assy; Test Plug, Type "C" 13-5/8" Nom f/ Use In Cactus Head w/ WQ Seal 4-1/2" IF Box X 4-1/2" IF Pin Btm, w/ Weep Hole On Top Portion Of Test Plug Part# 2247044-01-01	ST9	1	Weldment and Assembly, Retrieving Tool, 11" In Nom x 4-1/2" IF Box Btm x Top, Min Bore: 4.19" Part# 2367902-01-01	E3	1	Assy; Casing Hanger, IC-2, 11" x 5-1/2", (f/ 10K Above and Below) Part# 2357372-01-01
ST3	1	Weldment and Assy; Wear Bushing Running & Retrieving Tool IC-2, 13-5/8" Nom x 4-1/2" IF Box Btm x Top Part# 2301310-02	ST10	1	Assy; Wear Bushing, f/ 11" Nom Type 'MN-DS', Min Bore: 8.910" Part# 2125720-06	E4	1	Assy; 'NX' Bushing Nom 11" x 5-1/2" OD Csg w/ Integral Bit Guide Part# 2161829-02-01
ST4	1	Assy; Wear Bushing, f/ 13-5/8" Nom 10K Type 'Mn-Ds' Housing, Installed w/ (4) O-Rings & (4) Welded Stop Lugs Min Bore: 12.615 Part# 2367788-02	ST11	1	Assy; Rotating Fluted Mandrel Hanger Running Tool, TSDS-S; 11 Nom X 7.500-4TPI Stub ACME Thd Btm X 5-1/2 23 Lb/Ft TSH Blue Box Thd Top, w/ 1/8-27 NPT Test Port Part# 2161757-83-01	<b>CAPPING FLANGE</b>		
ST5	1	Assy; Running Tool, 13-5/8" Nom, w/ 8-5/8 BC Box Thd Top x 10.000-4TPI LH Stub Acme Running Thd Btm, C/ W Single O-Ring and (3) Centralizing Ribs, Min Bore: 8.00 Part# 2161757-98-01	ST12	1	Running Tool; F/ 11 Nom Seal Assembly w/ 4-1/2 API IF Thd Top X 2-7/8 API IF Thd Btm and 9.875-4 TPI LH Stub ACME Thd Part# 2017712-15-01	TA1	1	Assy; Capping Flg, 7-1/16" API 10K BX-156 Std'd Blind Top x 13-5/8" API 10K BX-159 Std'd Btm, w/ One 1-13/16" API 10K BX-151 Std'd Side Outlet, w/ 1-13/16" API Vr Thd, w/ 11" 'NX' Btm Prep, Oal: 12" Part# 2392883-03-01
ST6	1	Assy; Jetting Tool, 13-5/8" Nom Compact Housing, Type 'SSMC' Part# 2125914-01	ST13	1	Assy; Casing Head Running Tool; 14.750-4 TPI LH Internal Stub ACME Thd Btm X 11-3/4 API 8Rnd Short Thd Casing Box Thd Top; Min Bore: 11.359 Part# 2254468-04-01	TA2	1	Assy 'NX' Bushing Nom 11" w/ 7" OD Csg Part# 608783-17
			ST14	1	Assy; Low Pressure Adapter; 24.00 OD X 22.740 ID Part# 2222008-06-01	TA3	1	Gate Valve, Manual, Model FLS, 1-13/16 Bore, 10K Psi, 1-13/16 API Flg x Flg Part# 141510-41-91-01

BEGINNING AT THE INTERSECTION OF HIGHWAY 18 AND HIGHWAY 128, PROCEED IN A WESTERLY, THEN NORTHWESTERLY DIRECTION FROM JAL, NEW MEXICO ALONG HIGHWAY 128 APPROXIMATELY 30.0 MILES TO THE JUNCTION OF THIS ROAD AND J-1/ORLA ROAD TO THE SOUTH; TURN LEFT AND PROCEED IN A SOUTHERLY , THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 13.6 MILES TO THE JUNCTION OF THIS ROAD AND BATTLE AXE ROAD/CR J-2 TO THE WEST; TURN RIGHT AND PROCEED IN A WESTERLY DIRECTION APPROXIMATELY 1.1 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTH; TURN RIGHT AND PROCEED IN A NORTHERLY DIRECTION APPROXIMATELY 0.1 MILES THE BEGINNING OF THE PROPOSED ACCESS TO THE EAST; FOLLOW ROAD FLAGS IN A EASTERLY DIRECTION APPROXIMATELY 582' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM JAL, NEW MEXICO TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 44.9 MILES.

REV: 1 06-19-17 V.L.D. (PAD NAME CHANGE)


**ConocoPhillips Company**

**ZIA HILLS 19 FEDERAL PAD 2  
SE 1/4 NW 1/4, SECTION 19, T26S, R32E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

SURVEYED BY	J.A.V., R.D.	04-19-17	
DRAWN BY	V.L.D.	05-03-17	
ROAD DESCRIPTION			



# **LEGEND:**

○ PROPOSED LOCATION



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



**ConocoPhillips Company**

**ZIA HILLS 19 FEDERAL PAD 2**  
SE 1/4 NW 1/4, SECTION 19, T26S, R32E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

SURVEYED BY	J.A.V., R.D.	04-19-17	SCALE
DRAWN BY	V.L.D.	05-03-17	1:100,000
<b>ACCESS ROAD MAP</b>			<b>TOPO A</b>

REV: 1 06-19-17 V.L.D. (PAD NAME CHANGE)

# ConocoPhillips, ZIA HILLS 19 FEDERAL COM 109H

## 1. Geologic Formations

TVD of target	11,619'	Pilot hole depth	N/A
MD at TD:	22,124'	Deepest expected fresh water:	300

## Basin

Formation	Depth (TVD) from KB	SSTVD (ft.)	Water/Mineral Bearing/Target Zone	Hazards *
Quaternary Fill	Surface	0	Water	
Base of Fresh Water	300	300	Water	
Rustler	1,119	2060	Water	
Top of Salt / Salado	1,279	1900	Mineral	
Castile	2,629	550	Mineral	
Delaware Top / Base Salt	4,229	-1050	O & G	
Ford Shale	4,354	-1175	O & G	
Cherry Canyon	5,154	-1975	O & G	
Brushy Canyon	6,629	-3450	O & G	
Bone Springs	8,029	-4850	O & G	
Bone Springs 3 <sup>rd</sup> Carb	10,339	-1760	O & G	
WolfCamp	11,379	-8200	O & G	
WolfCamp 1	11,604	-8425	O & G	

\*H<sub>2</sub>S, water flows, loss of circulation, abnormal pressures, etc.

## 2. Casing Program

ConocoPhillips Company respectfully requests to approve the following 3-string casing and cementing program with the 8-5/8" casing set in the Wolfcamp formation. The intent for the casing and cementing program:

- Drill 14-3/4" surface hole to Rustler.
- Drill 10-5/8" hole from Rustler to Top of Wolfcamp formation with the same density mud (OBM or Saturated Brine).
- Case and cement the well with 11-3/4" surface, 10-5/8" intermediate and 5-1/2" production casing (3-strings).
- Isolate the Salt & Delaware utilizing Annulus Casing Packer and Stage Tool with 2-Stage Cement or Remediate with Bradenhead Squeeze if necessary.
- Bring cement for 11-3/4" casing and 8-5/8" casing to surface. Cement 5-1/2" casing to lap inside 8-5/8" casing shoe.
- 5-1/2" TXP buttress Casing Connection in 7-7/8" OH for minimum of 0.422 in clearance per Onshore Oil and Gas Order #2 III.B.

**ConocoPhillips, ZIA HILLS 19 FEDERAL COM 109H**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
14.75"	0	1170	11.75"	47.0	J55	BTC	2.89	5.87	15.4
10.875"	0	11400	8.625"	32.0	P110	BTC	**1.48	1.55	3.53
7.875"	0	22124	5.5"	23.0	P110	TXP	1.50	1.71	2.29
BLM Minimum Safety Factor							1.125	1.00	1.6 Dry 1.8 Wet

**\*\*COP Collapse Design:** 1/3 Partial Evacuation to the next casing depth (TVD).

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	Y
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?	Y
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

**ConocoPhillips, ZIA HILLS 19 FEDERAL COM 109H**

**3. Cementing Program**

**Option 1:**

Casing	# Sks	Wt. lb/ gal	Yld ft3/ sack	H <sub>2</sub> O gal/sk	500# Comp. Strength (Estimated hours)	Slurry Description
Surf.	470	13.5	1.68	8.94	8	<b>Lead:</b> Class C + 4.0% Bentonite + 0.2% Anti-Foam + 2.0% CaCl <sub>2</sub> + 0.125lb/sk LCM + 0.1% Dispersant.
	240	14.8	1.35	6.38	7	<b>Tail:</b> Class C + 0.2% Anti-Foam + 0.1% Lost Circ Control
Inter.	800	11.0	2.7	16.5	18	<b>Lead:</b> Class C 75.00 lb/sk BWOB D049 + 1.00 % BWOB D013 Retarder + 10.00 % BWOB D020 Extender + 0.02 gal/sk VBWOB D047 Anti foam + 2.00 % BWOB D154 Extender + 0.15 % BWOB D208 Viscosifier
	570	13.5	1.29	6.02	7	<b>Tail:</b> Class C 75.00 lb/sk BWOB D049 + 0.50 % BWOB D013 Retarder + 1.00 % BWOB D020 Extender + 3.00 lb/sk WBWOB D042 Extender + 0.02 gal/sk VBWOB D047 Anti foam + 0.10 % BWOB D065 Dispersant + 0.13 lb/sk WBWOB D130 Lost Circulation + 0.30 % BWOB D238 Fluid loss
Prod.	2290	16.4	1.08	4.38	10	<b>Tail:</b> Class H + 1.00 % BWOB D020 Extender + 0.02 gal/sk VBWOB D047 Anti Foam + 0.10 % BWOB D065 Dispersant + 0.15 % BWOB D255 Fluid loss + 0.30 % BWOB D800 Retarder
	DV/ACP Tool: NO					

**Option 2:**

Casing	# Sks	Wt. lb/ gal	Yld ft3/ sack	H <sub>2</sub> O gal/sk	500# Comp. Strength (Estimated hours)	Slurry Description
Surf.	470	13.5	1.68	8.94	8	<b>Lead:</b> Class C + 4.0% Bentonite + 0.2% Anti-Foam + 2.0% CaCl <sub>2</sub> + 0.125lb/sk LCM + 0.1% Dispersant.
	240	14.8	1.35	6.38	7	<b>Tail:</b> Class C + 0.2% Anti-Foam + 0.1% Lost Circ Control
Inter.	370	11.0	2.7	16.5	18	<b>Lead:</b> Class C 75.00 lb/sk BWOB D049 + 1.00 % BWOB D013 Retarder + 10.00 % BWOB D020 Extender + 0.02 gal/sk VBWOB D047 Anti foam + 2.00 % BWOB D154 Extender + 0.15 % BWOB D208 Viscosifier
	570	13.5	1.29	6.02	7	<b>Tail:</b> Class C 75.00 lb/sk BWOB D049 + 0.50 % BWOB D013 Retarder + 1.00 % BWOB

**ConocoPhillips, ZIA HILLS 19 FEDERAL COM 109H**

						D020 Extender + 3.00 lb/sk WBWOB D042 Extender + 0.02 gal/sk VBWOB D047 Anti foam + 0.10 % BWOB D065 Dispersant + 0.13 lb/sk WBWOB D130 Lost Circulation + 0.30 % BWOB D238 Fluid loss
	<b>DV/ACP Tool: 4,200'</b>					
	420	11.0	3.10	19.03	15	<b>2nd Stage Lead:</b> Class 'C' + 2.00 % BWOB Extender + 3.40 lb/sk WBWOB D042 Extender + 0.02 gal/sk VBWOB D047 Anti Foam + 2.00 % BWOB D079 Extender + 5.00 % BWOB D154 Extender + 1.00 % BWOB S001 CaCl2
Prod.	2290	16.4	1.08	4.38	10	<b>Tail:</b> Class H + 1.00 % BWOB D020 Extender + 0.02 gal/sk VBWOB D047 Anti Foam + 0.10 % BWOB D065 Dispersant + 0.15 % BWOB D255 Fluid loss + 0.30 % BWOB D800 Retarder
	<b>DV/ACP Tool: NO</b>					

DV tool depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. If it cannot be set below the shoe, a CBL shall be run to verify cement coverage.

Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing String	TOC	% Excess in OH
Surface	0'	>100%
Intermediate	0'	>30%
Production	10,400'	>15%



# **ConocoPhillips, ZIA HILLS 19 FEDERAL COM 109H**

Include Pilot Hole Cementing specs: NO PILOT HOLE.

**Pilot hole depth**

**N/A KOP**

Plug top	Plug Bottom	% Excess	No. Sacks	Wt. lb/gal	Yld ft3/sack	Water gal/sk	Slurry Description and Cement Type

## **3. Pressure Control Equipment**

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	--

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
10-5/8"	11" or 13-5/8"	10M	Annular	x	50% of working pressure
			Blind Ram	x	100% of working pressure
			Pipe Ram	x	
			Double Ram	x	
			Other*		
7-7/8"	11" or 13-5/8"	10M	Annular	x	50% of working pressure
			Blind Ram	x	100% of working pressure
			Pipe Ram	x	
			Double Ram	x	
			Other*		

\*Specify if additional ram is utilized.

Note: A 11" or 13-5/8" BOPE will be utilize depending on availability and Rig Substructure Clearance.

BOP/BOPE will be isolated from the casing and tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. BOPE controls will be installed prior to drilling under the surface casing and will be used until the completion of drilling operations. The intermediate interval and the production interval will be tested per 10M working system requirements.

Pipe rams will be operationally checked each 24-hour period. Choke manifold will have one remotely operated valve and a manual adjustable valve in front of the choke manifold, as detailed in the Onshore Order 2. It currently contains one 10M hydraulic choke for a total of three choke branches (two manual and one hydraulic). Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

## ConocoPhillips, ZIA HILLS 19 FEDERAL COM 109H

A Spudder Rig may be used to drill the surface and/or intermediate hole for economical reason depending on availability.

The wellhead will be installed and tested as soon as the surface casing is cemented. Prior to drilling out the surface casing, ConocoPhillips shall nipple up a 10M BOPE & choke arrangement with 10M components and test to the rated working pressure of a 10M BOPE system as it is subjected to the maximum anticipated surface pressure 5600 psi. The pressure test to MASP and 50% for annular shall be performed with a test plug after installing the casing head and nipping up the 5M BOPE system prior to drilling out the surface casing.

However, ConocoPhillips shall nipple up a 10M BOPE with 5M Annular Preventer if drilling out surface casing with Primary Rig.

Y	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart. <ul style="list-style-type: none"><li>• See attached data sheet &amp; certification.</li></ul>
N	Are anchors required by manufacturer?
Y	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. <ul style="list-style-type: none"><li>• See attached schematic.</li></ul>

#### 4. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	1,170	Spud Mud	8.34 - 8.6	32-36	N/C
0	11,400	Cut-Brine or OBM	8.6-9.4	30-40	≤5
0	22,124	Oil Base Mud	9.5-13.5	30-40	≤5

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/MDTotco/Visual Monitoring
---	-------------------------------

## ConocoPhillips, ZIA HILLS 19 FEDERAL COM 109H

### 5. Logging and Testing Procedures

Logging, Coring and Testing.	
x	GR from 200' above KOP to TD (GR as part of the BHA while drilling).
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain
x	Dry samples taken 30' from intermediate 1 casing point to TD.

Additional logs planned	Interval
	Resistivity
	Density
	CBL
x	Mud log
	PEX

### 6. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	8157 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H<sub>2</sub>S) monitors will be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

N	H <sub>2</sub> S is present
Y	H <sub>2</sub> S Plan attached

### 7. Other facets of operation

Is this a walking operation? If yes, describe. Yes, please see below.

Will be pre-setting casing? If yes, describe. Yes, please see below.

### Spudder Rig and Batch Drilling Operations:

A blind flange cap of the same pressure rating as the wellhead will be secured to seal the wellbore on all casing strings. Pressure will be monitored via flanged port tied to a needle valve and pressure gauge to monitor pressures on each wellhead section and a means for intervention will be maintained while the drilling rig is not over the well.

## **ConocoPhillips, ZIA HILLS 19 FEDERAL COM 109H**

### **Attachments:**


- Attachment#1: Directional Plan.
- Attachment#2: Wellbore Casing & Cementing Schematic.
- Attachment #3: Special (Premium) Connections.
- Attachment#4: Wellhead Schematic.
- Attachment #5: BOP Schematic.
- Attachment #6: Choke Schematic.
- Attachment #7: Flex Hose Documentation.
- Attachment #8: Rig Layout.

**Option 2:**

Casing	# Skis	Wt. lb/ gal	Yld ft3/ sack	H <sub>2</sub> O gal/sk	500# Comp. Strength (Estimated hours)	Slurry Description
Surf.	470	13.5	1.68	8.94	8	<b>Lead:</b> Class C + 4.0% Bentonite + 0.2% Anti-Foam + 2.0% CaCl <sub>2</sub> + 0.125lb/sk LCM + 0.1% Dispersant.
	240	14.8	1.35	6.38	7	<b>Tail:</b> Class C + 0.2% Anti-Foam + 0.1% Lost Circ Control
Inter.	370	11.0	2.7	16.5	18	<b>Lead:</b> Class C 75.00 lb/sk BWOB D049 + 1.00 % BWOB D013 Retarder + 10.00 % BWOB D020 Extender + 0.02 gal/sk VBWOB D047 Anti foam + 2.00 % BWOB D154 Extender + 0.15 % BWOB D208 Viscosifier
	570	13.5	1.29	6.02	7	<b>Tail:</b> Class C 75.00 lb/sk BWOB D049 + 0.50 % BWOB D013 Retarder + 1.00 % BWOB D020 Extender + 3.00 lb/sk WBWOB D042 Extender + 0.02 gal/sk VBWOB D047 Anti foam + 0.10 % BWOB D065 Dispersant + 0.13 lb/sk WBWOB D130 Lost Circulation + 0.30 % BWOB D238 Fluid loss
	<b>DV/ACP Tool: 4,200'</b>					
	420	11.0	3.10	19.03	15	<b>2nd Stage Lead:</b> Class 'C' + 2.00 % BWOB Extender + 3.40 lb/sk WBWOB D042 Extender + 0.02 gal/sk VBWOB D047 Anti Foam + 2.00 % BWOB D079 Extender + 5.00 % BWOB D154 Extender + 1.00 % BWOB S001 CaCl <sub>2</sub>
Prod.	2290	16.4	1.08	4.38	10	<b>Tail:</b> Class H + 1.00 % BWOB D020 Extender + 0.02 gal/sk VBWOB D047 Anti Foam + 0.10 % BWOB D065 Dispersant + 0.15 % BWOB D255 Fluid loss + 0.30 % BWOB D800 Retarder
	<b>DV/ACP Tool: NO</b>					



# 13-5/8" 10M MN-DS Wellhead System with CXS Completion



ConocoPhillips

NOTE: All dimensions on this drawing are estimated measurements and should be evaluated by engineering.

C7747

CONTITECH RUBBER Industrial Kft.	No: QC-DB- 45 / 2012
	Page: 9 / 50



## Hose Data Sheet

CRI Order No.	516273
Customer	ContiTech Beattie Co.
Customer Order No	PO5438 STOCK
Item No.	3
Hose Type	Flexible Hose
<b>Standard</b>	<b>API SPEC 16 C</b>
Inside dia in inches	3
Length	35 ft
Type of coupling one end	FLANGE 4 1/16" API SPEC 6A TYPE 6BX FOR 10000 PSIBX155 RING GROOVE
Type of coupling other end	FLANGE 4 1/16" API SPEC 6A TYPE 6BX FOR 10000 PSI BX155 RING GROOVE
H2S service NACE MR0175	Yes
Working Pressure	10 000 psi
Design Pressure	10 000 psi
Test Pressure	15 000 psi
Safety Factor	2,25
Marking	USUAL PHOENIX
Cover	NOT FIRE RESISTANT
Outside protection	St. steel outer wrap
Internal stripwound tube	No
Lining	OIL RESISTANT
Safety clamp	No
Lifting collar	No
Element C	No
Safety chain	No
Safety wire rope	No
Max. design temperature [°C]	100
Min. design temperature [°C]	-20
MBR operating [m]	1,60
MBR storage [m]	1,40
Type of packing	WOODEN CRATE ISPM-15



QC-DK- 45/2012

Page: 7/50

Fluid Technology

Quality Document

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. N°: 184	
PURCHASER: ContiTech Beattie Co.				P.O. N°: 005438	
CONTITECH ORDER N°: 516273		HOSE TYPE: 3" ID		Choke and Kill Hose	
HOSE SERIAL N°: 61477		NOMINAL / ACTUAL LENGTH: 10,67 m / 10,71 m			
W.P. 68,9 MPa 10000 psi		T.P. 103,4 MPa 15000 psi		Duration: 60 min.	
<p>Pressure test with water at ambient temperature</p> <p style="text-align: center;">See attachment. ( 1 page )</p> <p>↑ 10 mm = 10 Min. → 10 mm = 20 MPa</p>					
COUPLINGS Type	Serial N°		Quality	Heat N°	
3" coupling with	10178 10173		AISI 4130	20231	
4 1/16" 10K API Flange end			AISI 4130	33051	
<b>NOT DESIGNED FOR WELL TESTING</b>				<b>API Spec 16 C</b>	
				Temperature rate: "B"	
All metal parts are flawless					
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER INSPECTED AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.					
STATEMENT OF CONFORMITY: We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated, inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.					
COUNTRY OF ORIGIN HUNGARY/EU					
Date:	Inspector:		Quality Control:		
30. January 2012.			ContiTech Rubber Industrial Kft. Quality Control Dept. (1) <i>[Signature]</i>		

Continental Rubber Hungary Kft.  
Budapest 101, Széchenyi tér 10.  
P.O. Box 162 Budapest 10701  
Hungary

Phone: +36 (0) 662 741  
Fax: +36 (0) 662 736  
e-mail: [info@contitech.hu](mailto:info@contitech.hu)  
Internet: [www.contitech.hu](http://www.contitech.hu)

For ContiTech Hungary Kft. as  
Factory Dept.  
Pressure Control: HU 02 03 000507  
E-mail: HU 02 03 000503

Business  
Representative: Dr.  
Gábor Csikós  
E-mail: [gabor.csikos@contitech.hu](mailto:gabor.csikos@contitech.hu)  
Tel: +36 (0) 662 741




## No: 132, 184, 185

Consolidated Rubber  
Industrial Kt.  
Quality Control Dept.  
(17)

24	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100											
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89											

# System Drawing





U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## PWD Data Report

11/20/2017

### Section 1 - General

Would you like to address long-term produced water disposal? NO

### Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

### **Section 3 - Unlined Pits**

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

### **Section 4 - Injection**

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

**Injection well type:**

**Injection well number:**

**Injection well name:**

**Assigned injection well API number?**

**Injection well API number:**

**Injection well new surface disturbance (acres):**

**Minerals protection information:**

**Mineral protection attachment:**

**Underground Injection Control (UIC) Permit?**

**UIC Permit attachment:**

### **Section 5 - Surface Discharge**

**Would you like to utilize Surface Discharge PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Surface discharge PWD discharge volume (bbl/day):**

**Surface Discharge NPDES Permit?**

**Surface Discharge NPDES Permit attachment:**

**Surface Discharge site facilities information:**

**Surface discharge site facilities map:**

### **Section 6 - Other**

**Would you like to utilize Other PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Other PWD discharge volume (bbl/day):**

**Other PWD type description:**

**Other PWD type attachment:**

**Have other regulatory requirements been met?**

**Other regulatory requirements attachment:**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Bond Info Data Report

11/20/2017

### Bond Information

Federal/Indian APD: FED

BLM Bond number: ES0085

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment:

**Operator Name:** CONOCOPHILLIPS COMPANY

**Well Name:** ZIA HILLS 19 FEDERAL COM


**Well Number:** 109H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
PPP Leg #1	0	FSL	132 5	FWL	26S	32E	18	Lot 4	32.03553 3	- 103.7187 92	LEA	NEW MEXI CO	NEW MEXI CO	F	NMLC0 62749C	- 826 8	114 50	114 50
PPP Leg #1	0	FSL	132 1	FWL	26S	32E	7	Lot 4	32.05021	- 103.7188 03	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 039208 2A	- 826 8	114 50	114 50
EXIT Leg #1	233 8	FSL	132 0	FWL	26S	32E	7	Lot 3	32.05663 6	- 103.7188 08	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 039208 2A	- 843 7	217 94	116 19
BHL Leg #1	261 8	FSL	132 0	FWL	26S	32E	7	Lot 3	32.05740 6	- 103.7188 08	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 039208 2A	- 843 7	221 24	116 19



# SPECIFICATIONS

FLOOR: 3/16" PL one piece  
 CROSS MEMBER: 3 x 4.1 channel 16" on center  
 WALLS: 3/16" PL solid welded with tubing top, inside liner hooks  
 DOOR: 3/16" PL with tubing frame  
 FRONT: 3/16" PL slant formed  
 PICK UP: Standard cable with 2" x 6" x 1/4" rails, gusset at each crossmember  
 WHEELS: 10 DIA x 9 long with rease fittings  
 DOOR LATCH: 3 independent ratchet binders with chains, vertical second latch  
 GASKETS: Extruded rubber seal with metal retainers  
 WELDS: All welds continuous except sub-structure crossmembers  
 FINISH: Coated inside and out with direct to metal, rust inhibiting acrylic enamel color coat  
 HYDROTESTING: Full capacity static test  
 DIMENSIONS: 22'-11" long (21'-8" inside), 99" wide (88" inside), see drawing for height  
 OPTIONS: Steel grit blast and special paint, Ampliroll, Heil and Dino pickup  
 ROOF: 3/16" PL roof panels with tubing and channel support frame  
 LIDS: (2) 68" x 90" metal rolling lids spring loaded, self raising  
 ROLLERS: 4" V-groove rollers with delrin bearings and grease fittings  
 OPENING: (2) 60" x 82" openings with 8" divider centered on container  
 LATCH: (2) independent ratchet binders with chains per lid  
 GASKETS: Extruded rubber seal with metal retainers

## Heavy Duty Split Metal Rolling Lid



CONT.	A	B
20 YD	41	53
25 YD	53	65
30 YD	65	77







U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Operator Certification Data Report

11/20/2017

### Operator Certification

*I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.*

**NAME:** Ashley Bergen

**Signed on:** 07/26/2017

**Title:** Associate, Regulatory MCBU

**Street Address:** 3300 N. A Street

**City:** Midland

**State:** TX

**Zip:** 79710

**Phone:** (432)688-6938

**Email address:** Ashley.Bergen@conocophillips.com

### Field Representative

**Representative Name:**

**Street Address:**

**City:**

**State:**

**Zip:**

**Phone:**

**Email address:**