Form 3160-5 (June 2015)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

OCD Hobbs

FORM APPROVED OMB NO. 1004-0137 Expires: January 31, 2018

5.	Lease Serial No.	
	NMLC065194	

SUNDRY NO	OTICES AND	REPORTS O	N WELLS
Do not use this	form for propo	sals to drill or	N WELLS r to re-enter and such proposals.
abandoned well.	Use form 316	0-3 (APD) for s	such proposals

abandoned wel	I. Use form 3160-3 (APD)	for such p	roposals.	Don	6. If India	an, Allottee or Tribe	e Name	
SUBMIT IN 1	RIPLICATE - Other instru	ctions on	page 22 2 20.		7. If Unit NMN	or CA/Agreement, M116756	Name and/or No.	
Type of Well Oil Well		K	ECEIVED		8. Well N PALO	ame and No. MA BLANCO 17 F	FED COM 02	V
Name of Operator DEVON ENERGY PRODUCT	Contact: ROION COME-Mail: ronnie.slack@		ACK	,	9. API W 30-02	ell No. 25-38024-00-S1		
3a. Address 6488 SEVEN RIVERS HIGHW ARTESIA, NM 88211	/AY	3b. Phone No Ph: 405-55	. (include area code) 2-4615			and Pool or Explor ELOPE RIDGE-S		
4. Location of Well (Footage, Sec., T.	, R., M., or Survey Description)				11. Coun	ty or Parish, State		_
Sec 17 T23S R34E SESW 66	DFSL 1980FWL				LEA	COUNTY, NM		
12. CHECK THE AF	PROPRIATE BOX(ES) T	O INDICA	TE NATURE O	F NOTICE,	REPOR	Γ, OR OTHER	DATA	
TYPE OF SUBMISSION			TYPE OF	ACTION			_	
Notice of Intent	☐ Acidize	☐ Dee	pen	☐ Product	tion (S1	INIT TO D	Pool	
	☐ Alter Casing	☐ Hyd	raulic Fracturing	☐ Reclam	ation	INT TO PA	1110	
☐ Subsequent Report	Casing Repair	_	Construction	□ Recom		P&A NR _		
☐ Final Abandonment Notice	☐ Change Plans		g and Abandon	☐ Tempor	-	P&AR _		
	☐ Convert to Injection	Plug	g Back	□ Water I	Dispos			
If the proposal is to deepen directions Attach the Bond under which the wor following completion of the involved testing has been completed. Final Attach the site is ready for final Attach th	k will be performed or provide th operations. If the operation resultandonment Notices must be filed that inspection. g & packer from 11,860'. 1,865'. Tag. Circulate 10#1,865' - 11,647'. Tag. 1,470' - 11,250'. (Wolfcamp 650' - 8,455'. (Bone Spring 115' - 5,935'. (dv tool @ 60 120' - 4,905'. Tag. (Shoe 5 1,900) out @ 1,905' - 1,750'. (300) out @ 1,330' - 945'. Tag.	e Bond No. o: Its in a multip only after all salt gel mu 0 @ 11419' 0 @ 8600') 013') 6050; Delaw 00' spacer (n file with BLM/BIA le completion or recorrequirements, included. (Open perfs 1) vare/B.Salt @ 50 2 1905')	a. Required submpletion in a ling reclamation 1892'-12312	bsequent renew intervalon, have bee	ports must be filed to l, a Form 3160-4 m	within 30 days ust be filed once e operator has PROCEDURE HED	
14. I hereby certify that the foregoing is Name (<i>Printed/Typed</i>) RONNIE \$	Electronic Submission #40 For DEVON ENERGY Committed to AFMSS for pro	PRODUCT	ION COM LP, ser JIM AMOS on 03	nt to the Hob	bs JA0041SE	•		
Name (17titleta 13peta) ROMME	DLACK		THE PRODU	CHON IE	CHINOLO	GIST		_
Signature (Electronic S	Submission)		Date 03/01/2	018				
	THIS SPACE FOR	R FEDERA	L OR STATE	OFFICE U	SE			
Approved By James	a. James		Title Su	epv.	AET	,	3-18-18 Date	
Conditions of approval, if any, are attached certify that the applicant holds legal or equivalent would entitle the applicant to condu-	itable title to those rights in the si		Office 4	21/16/000	[
Title 8 U.S.C. Section 1001 and Title 43 States any false, fictitious or fraudulent s	U.S.C. Section 1212, make it a creatatements or representations as to	ime for any po any matter w	erson knowingly and ithin its jurisdiction.	willfully to m	ake to any o	lepartment or agenc	cy of the United	

(Instructions on page 2)
** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED **




Additional data for EC transaction #406290 that would not fit on the form

32. Additional remarks, continued

13. Perf @ 135'. Pump 40 sx Cl C in/out to surface. Cut wellhead off 3' BGL. Set dry hole marker.

DEVON ENERG	Y PRODUCTION COMPANY LP
Well Name: PALOMA BLANCO 17 FED COM 2	Field: GAUCHO RED BULL
Location: 660' FSL & 1980' FWL; SEC 17-235-34E	County: LEA State: NM
Elevation: 3497' KB; 3474' GL	Spud Date: 8/24/06 Compl Date:
API#: 30-025-38024 Prepared by: Ronnie Slack	Date: 2/28/18 Rev:
PROPOSED PLUG & ABANDONMENT	Proposed: 3. Cut wellhead off 3' BGL. Set dry hole marker. 2. Pmp 40 sx Cl C in/out to surface. 1. Perf @ 135'
17-1/2" Hole 13-3/8", 54.5#, J55, ST&C, @ 1,007' Cmt'd w/1150 Sx. Did not circulate, topped out w/375 Sx to surface.	Proposed: 2. Pmp 110 sx (385') Cl C in/out @ 1330' - 945'. Tag 1. Perf @ 1,330'. (T.Salt @ 1279')
8	10# Mud
	Proposed: 2. Pmp 45 sx (155') Cl C in/out @ 1,905' - 1,750'. 1. Perf @ 1,905'. (3000' spacer @ 1905')
TOC @ 3350' (CBL) (11/5/06)	10# Mud
12-1/4" Hole 9-5/8", 40#, HCK-55, LT&C, @ 5,050' Cmt'd w/1600 Sx	Proposed: 1. Spot 35 sx (215') Cl C @ 5,120' - 4,905'. Tag. (Delaware/B.Salt 5019')
	10# Mud
DV Tool @ 6,01,3'	Proposed: 1. Spot 30 sx (180') Cl C @ 6,115' - 5,935'.
	10# Mud Proposed: 1. Spot 40 sx (195') Cl H @ 8,650' - 8,455'. (Bone Spring 8600')
	Proposed: 1. Spot 45 sx (220') Cl H @ 11,470' - 11,250'. (Wolfcamp 11419')
4-1/2" Liner Top @ 11,822".	Proposed: 2. Spot 40 sx (218') CI H @ 11,865' - 11,647'. Tag.
STRAWN (12/21/06) 3 spf 11,892' - 11,894' 12,048' - 12,051' 12,096' - 12,099 12,150' - 12,153'	1. Set CIBP @ 11,865'. Tag. Circ 10# salt gel mud.
8-3/4" Hole 7", 26#, P110, LTC, @ 12,175' Cmt'd 1st stage w/1300 Sx; 2nd stage 335 Sx	Add play from 12
STRAWN (12/21/06) 3 spf 12,220' - 12,222' 12,310' - 12,312' 12/23/06: acidized 11892-12312 w/4500 gals 15% HCI	
MORROW 13,148' - 13,155' 6 spf (11/18/06) 11/21/06: acidized w/1500 gals 7.5% w/20% Methanol 11/28/06: fraced w/14.5K# 18/40, Ravg 20.3 bpm, Pavg 5752 psi	35' Cement. PBD @ 13,085' CIBP @ 13,120' (12/19/06)
6-1/8" Hole 4-1/2", 13.5#, P110HC, LTC, @ 13,850' Cmt'd w/245 Sx	13,605' PBTD (CBL depth)



BUREAU OF LAND MANAGEMENT Carlsbad Field Office 620 East Greene Street Carlsbad, New Mexico 88220 575-234-5972

Permanent Abandonment of Federal Wells Conditions of Approval

Failure to comply with the following Conditions of Approval may result in a Notice of Incidents of Noncompliance (INC) in accordance with 43 CFR 3163.1.

1. Plugging operations shall commence within <u>ninety (90)</u> days from the approval date of this Notice of Intent to Abandon.

If you are unable to plug the well by the 90th day provide this office, prior to the 90th day, with the reason for not meeting the deadline and a date when we can expect the well to be plugged. Failure to do so will result in enforcement action.

The rig used for the plugging procedure cannot be released and moved off without the prior approval of the authorized officer. Failure to do so may result in enforcement action.

- 2. <u>Notification</u>: Contact the appropriate BLM office at least 24 hours prior to the commencing of any plugging operations. For wells in Chaves and Roosevelt County, call 575-627-0272; Eddy County, call 575-361-2822; Lea County, call 575-393-3612.
- 3. <u>Blowout Preventers</u>: A blowout preventer (BOP), as appropriate, shall be installed before commencing any plugging operation. The BOP must be installed and maintained as per API and manufacturer recommendations. The minimum BOP requirement is a 2M system for a well not deeper than 9,090 feet; a 3M system for a well not deeper than 13,636 feet; and a 5M system for a well not deeper than 22,727 feet.
- 4. <u>Mud Requirement:</u> Mud shall be placed between all plugs. Minimum consistency of plugging mud shall be obtained by mixing at the rate of 25 sacks (50 pounds each) of gel per 100 barrels of **brine** water. Minimum nine (9) pounds per gallon.
- 5. <u>Cement Requirement</u>: Sufficient cement shall be used to bring any required plug to the specified depth and length. Any given cement volumes on the proposed plugging procedure are merely estimates and are not final. Unless specific approval is received, no plug except the surface plug shall be less than 25 sacks of cement. Any plug that requires a tag will have a minimum WOC time of 4 hours.

In lieu of a cement plug across perforations in a cased hole (not for any other plugs), a bridge plug set within 50 feet to 100 feet above the perforations shall be capped with 25 sacks of cement. If a bailer is used to cap this plug, 35 feet of cement shall be sufficient. Before pumping or bailing cement on top of CIBP, tag will be required to verify depth. Based on depth, a tag of the cement may be deemed necessary.

Unless otherwise specified in the approved procedure, the cement plug shall consist of either Neat Class "C", for up to 7,500 feet of depth or Neat Class "H", for deeper than 7,500 feet plugs.

6. <u>Dry Hole Marker</u>: All casing shall be cut-off at the base of the cellar or 3 feet below final restored ground level (whichever is deeper). The BLM is to be notified a minimum of 4 hours prior to the wellhead being cut off to verify that cement is to surface in the casing and all annuluses. Wellhead cut off shall commence within ten (10) calendar days of the well being plugged. If the cut off cannot be done by the 10th day, the BLM is to be contacted with justification to receive an extension for completing the cut off.

The well bore shall then be capped with a 4-inch pipe, 10-feet in length, 4 feet above ground and embedded in cement, unless otherwise noted in COA (requirements will be attached). The following information shall be permanently inscribed on the dry hole marker: well name and number, name of the operator, lease serial number, surveyed location (quarter-quarter section, section, township and range or other authorized survey designation acceptable to the authorized officer such as metes and bounds).

- 7. <u>Subsequent Plugging Reporting:</u> Within 30 days after plugging work is completed, file one original and three copies of the Subsequent Report of Abandonment, Form 3160-5 to BLM. The report should give in detail the manner in which the plugging work was carried out, the extent (by depths) of cement plugs placed, and the size and location (by depths) of casing left in the well. **Show date well was plugged.**
- 8. <u>Trash:</u> All trash, junk and other waste material shall be contained in trash cages or bins to prevent scattering and will be removed and deposited in an approved sanitary landfill. Burial on site is not permitted.

Following the submission and approval of the Subsequent Report of Abandonment, surface restoration will be required. See attached reclamation objectives.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Carlsbad Field Office 620 E. Greene St. Carlsbad, New Mexico 88220-6292 www.blm.gov/nm



In Reply Refer To: 1310

Reclamation Objectives and Procedures

Reclamation Objective: Oil and gas development is one of many uses of the public lands and resources. While development may have a short- or long-term effect on the land, successful reclamation can ensure the effect is not permanent. During the life of the development, all disturbed areas not needed for active support of production operations should undergo "interim" reclamation in order to minimize the environmental impacts of development on other resources and uses. At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land and water are restored.

The long-term objective of final reclamation is to set the course for eventual ecosystem restoration, including the restoration of the natural vegetation community, hydrology, and wildlife habitats. In most cases this means returning the land to a condition approximating or equal to that which existed prior to the disturbance. The final goal of reclamation is to restore the character of the land and water to its predisturbance condition. The operator is generally not responsible for achieving full ecological restoration of the site. Instead, the operator must achieve the short-term stability, visual, hydrological, and productivity objectives of the surface management agency and take steps necessary to ensure that long-term objectives will be reached through natural processes.

To achieve these objectives, remove any and all contaminants, scrap/trash, equipment, pipelines and powerlines. Strip and remove caliche, contour the location to blend with the surrounding landscape, redistribute the native soils, provide erosion control as needed, rip and seed as specified in the original APD COA. This will apply to well pads, facilities, and access roads. Barricade access road at the starting point. If reserve pits have not reclaimed due to salts or other contaminants, submit a plan for approval, as to how you propose to provide adequate restoration of the pit area.

- The Application for Permit to Drill or Reenter (APD, Form 3160-3), Surface Use Plan of
 Operations must include adequate measures for stabilization and reclamation of disturbed lands.
 Oil and Gas operators must plan for reclamation, both interim and final, up front in the APD
 process as per Onshore Oil and Gas Order No. 1.
- 2. For wells and/or access roads not having an approved plan, or an inadequate plan for surface reclamation (either interim or final reclamation), the operator must submit a proposal describing the procedures for reclamation. For interim reclamation, the appropriate time for submittal would be when filing the Well Completion or Recompletion Report and Log (Form 3160-4). For final reclamation, the appropriate time for submittal would be when filing the Notice of Intent, or the Subsequent Report of Abandonment, Sundry Notices and Reports on Wells (Form 3160-5). Interim reclamation is to be completed within 6 months of well completion, and final reclamation is to be completed within 6 months of well abandonment.
- 3. The operator must file a Subsequent Report Plug and Abandonment (Form 3160-5) following the plugging of a well.
- 4. Previous instruction had you waiting for a BLM specialist to inspect the location and provide you with reclamation requirements. If you have an approved Surface Use Plan of Operation and/or an approved Sundry Notice, you are free to proceed with reclamation as per approved APD. If you have issues or concerns, contact a BLM specialist to assist you. It would be in your interest to have a BLM specialist look at the location and access road prior to the removal of reclamation

equipment to ensure that it meets BLM objectives. Upon conclusion submit a Form 3160-5, Subsequent Report of Reclamation. This will prompt a specialist to inspect the location to verify work was completed as per approved plans.

- 5. The approved Subsequent Report of Reclamation will be your notice that the native soils, contour and seedbed have been reestablished. If the BLM objectives have not been met the operator will be notified and corrective actions may be required.
- 6. It is the responsibility of the operator to monitor these locations and/or access roads until such time as the operator feels that the BLM objective has been met. If after two growing seasons the location and/or access roads are not showing the potential for successful revegetation, additional actions may be needed. When you feel the BLM objectives have been met submit a Final Abandonment Notice (FAN), Form 3160-5, stating that all reclamation requirements have been achieved and the location and/or access road is ready for a final abandonment inspection.
- 7. At this time the BLM specialist will inspect the location and/or access road. If the native soils and contour have been restored, and the revegetation is successful, the FAN will be approved, releasing the operator of any further liability of the location and/or access road. If the location and/or access road have not achieved the objective, you will be notified as to additional work needed or additional time being needed to achieve the objective.

If there are any questions, please feel free to contact any of the following specialists:

Jim Amos Supervisory Petroleum Engineering Tech 575-234-5909, 575-361-2648 (Cell)

Arthur Arias Environmental Protection Specialist 575-234-6230

Henryetta Price Environmental Protection Specialist 575-234-5951

Shelly Tucker Environmental Protection Specialist 575-234-5979

Trishia Bad Bear, Hobbs Field Station Natural Resource Specialist 575-393-3612