

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**SUNDRY NOTICES AND REPORTS ON WELLS**
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*FORM APPROVED
OMB NO. 1004-0137
Expires: January 31, 20185. Lease Serial No.
NMNM115421

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

SUBMIT IN TRIPLICATE - Other instructions on page 2

1. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		Carlsbad Field Office OCD Hobbs	8. Well Name and No. JENNINGS 27 B2AP FED COM 2H
2. Name of Operator MEWBOURNE OIL COMPANY			9. API Well No. 30-025-43342-00-X1
3a. Address P O BOX 5270 HOBBS, NM 88241		3b. Phone No. (include area code) Ph: 575-393-5905	10. Field and Pool or Exploratory Area WC025G08S253235G-LWR BONE SPI
4. Location of Well (Footage, Sec., T., R. M., or Survey Description) Sec 27 T25S R32E NENE 185FNL 660FEL			11. County or Parish, State LEA COUNTY, NM

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	Change to Original A
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	PD

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.

Mewbourne Oil Company has an approved APD for the above well. Mewbourne requests approval to make the following changes:

- (321382)
- 1) Change well name to Jennings 27 W0BO Fed Com #1H. *PCN 3/23/18*
 - 2) Change pool to 98203.
 - 3) Change target zone to Wolfcamp & TVD to 12,063'.
 - 4) Change SL to 275' FNL & 1310' FEL. *PCN 3/23/18*
 - 5) Change BHL to 330' FSL & 1650' FEL.
 - 6) Change csg depth and cement to suit new plan.
 - 7) Change wellhead to multi-bowl type wellhead.

**SEE ATTACHED FOR
CONDITIONS OF APPROVAL**

Please see attachments for C-102, wellhead schematic, new drilling plan, casing & cement

Engineer OK

14. I hereby certify that the foregoing is true and correct. Electronic Submission #402280 verified by the BLM Well Information System For MEWBOURNE OIL COMPANY, sent to the Hobbs Committed to AFMSS for processing by PRISCILLA PEREZ on 01/29/2018 (18PP0521SE)	
Name (Printed/Typed) ROBERT TALLEY	Title ENGINEER
Signature (Electronic Submission)	Date 01/25/2018
THIS SPACE FOR FEDERAL OR STATE OFFICE USE	
Approved By <i>Cody D. Taylor</i>	Title <i>[Signature]</i>
Conditions of approval, if any, attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office <i>[Signature]</i>

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

**** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED *****K2*

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-43342	² Pool Code 98203	³ Pool Name WC-025 S253227A; WOLFCAMP (GAS)
⁴ Property Code 316475	⁵ Property Name JENNINGS 27 WOBO FEDERAL COM	
⁷ OGRID NO. 14744	⁸ Operator Name MEWBOURNE OIL COMPANY	⁶ Well Number 1H
		⁹ Elevation 3396'

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet From the	East/West line	County
A	27	25S	32E		275	NORTH	1310	EAST	LEA

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
0	27	25S	32E		330	SOUTH	1650	EAST	LEA

¹² Dedicated Acres	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.

No allowable will be assigned to this completion until all interest have been consolidated or a non-standard unit has been approved by the division.

PROJECT AREA

GEODETIC DATA
NAD 83 GRID - NM EAST
SURFACE LOCATION
N 403670.5 - E 750287.6
LAT: 32.1079714° N
LON: 103.6584898° W
BOTTOM HOLE
N 398997.2 - E 749986.6
LAT: 32.0951309° N
LON: 103.6595559° W

PRODUCING AREA

CORNER DATA
NAD 83 GRID - NM EAST
A: CALCULATED CORNER
N 398632.9 - E 746300.4
B: FOUND BRASS CAP "1939"
N 401272.6 - E 746280.5
C: FOUND BRASS CAP "1939"
N 403912.7 - E 746257.9
D: FOUND BRASS CAP "1939"
N 403929.4 - E 748928.9
E: FOUND BRASS CAP "1939"
N 403961.0 - E 751593.2
F: FOUND BRASS CAP "1939"
N 401339.2 - E 751631.5
G: FOUND BRASS CAP "1939"
N 398686.8 - E 751636.9
H: FOUND BRASS CAP "1939"
N 398655.2 - E 748967.6

17 OPERATOR CERTIFICATION
I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.


Signature Robert Talley Date 1/25/2018
Printed Name
E-mail Address btalley@mewbourne.com

18 SURVEYOR CERTIFICATION
I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

1-16-2018
Date of Survey
Signature and Seal of Professional Surveyor
19680
Certificate Number

Job No.: LS1801041

LOCATION VERIFICATION MAP



SECTION 27, TWP. 25 SOUTH, RGE. 32 EAST,
N. M. P. M., LEA COUNTY, NEW MEXICO

OPERATOR: Mewbourne Oil Company
LEASE: Jennings 27 WOB Federal Com
WELL NO.: 1H
ELEVATION: 3396'

LOCATION: 275' FNL & 1310' FEL
CONTOUR INTERVAL: 10'
USGS TOPO. SOURCE MAP:
Paduca Breaks West, NM (P. E. 1973)

Copyright 2017 - All Rights Reserved

NO.	REVISION	DATE
JOB NO.: LS1801041		
DWG. NO.: 1801041LVM		


RRC

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 1000'
DATE: 01-16-2018
SURVEYED BY: ML/AB
DRAWN BY: AiAC
APPROVED BY: RMH
SHEET: 1 OF 1

VICINITY MAP

NOT TO SCALE



*SECTION 27, TWP. 25 SOUTH, RGE. 32 EAST,
N. M. P. M., LEA COUNTY, NEW MEXICO*

OPERATOR: Mewbourne Oil Company
LEASE: Jennings 27 W0BO Federal Com
WELL NO.: 1H

LOCATION: 275' FNL & 1310' FEL
ELEVATION: 3396'

Copyright 2017 - All Rights Reserved


NO.	REVISION	DATE
JOB NO.:	LS1801041	
DWG. NO.:	1801041VM	



308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE:	N / A
DATE:	01-16-2018
SURVEYED BY:	ML/AB
DRAWN BY:	AiAC
APPROVED BY:	RMH
SHEET:	1 OF 1

MEWBOURNE OIL COMPANY
JENNINGS 27 WOBO FEDERAL COM #1H
(275' FNL & 1310' FEL)
SECTION 27, T25S, R32E
N. M. P. M., LEA COUNTY, NEW MEXICO




DIRECTIONS TO LOCATION

From the intersection of CR-1 (Orla Hwy.) and U. S. Hwy. 128,
Go South on CR-1 approx. 6.5 miles to a lease road on the left;
Turn left and go East approx. 0.2 miles to lease road on the right;
Turn right and go South approx. 0.8 miles to lease road on the left;
Turn left and go East approx. 0.4 miles to proposed road on the right;
Turn right and go South approx. 250 feet to proposed location on the left.

I, R. M. Howett, a N. M. Professional Surveyor, hereby certify that
I prepared this unclassified survey of a well location from an
actual survey made on the ground under my direct supervision,
said survey and plat meet the Min. Stds. for Land Surveying in
the State of N. M. and are true and correct to the best of my
knowledge and belief.

Robert M. Howett NM PS 19680



Copyright 2017 - All Rights Reserved



NO.	REVISION	DATE
JOB NO.:	LS1801041	
DWG. NO.:	1801041PAD	

RRC

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 01-16-2018
SURVEYED BY: ML/AB
DRAWN BY: AiAC
APPROVED BY: RMH
SHEET : 1 OF 1

Mewbourne Oil Company, Jennings 27 W0BO Fed Com #1H
Sec 31, T24S, R29E
SL: 275' FNL & 1310' FEL
BHL: 330' FSL & 1650' FEL

1. Geologic Formations

TVD of target	12063'	Pilot hole depth	NA
MD at TD:	16682'	Deepest expected fresh water:	175'

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface		
Rustler	713		
Top of Salt	1083		
Castile			
Base of Salt	4413		
Lamar	4623	Oil/Gas	
Bell Canyon	4690	Oil/Gas	
Cherry Canyon	5658	Oil/Gas	
Manzanita Marker	5803		
Brushy Canyon	7373	Oil/Gas	
Bone Spring	8673	Oil/Gas	
1 st Bone Spring Sand	9673	Oil/Gas	
2 nd Bone Spring Sand	10198	Oil/Gas	
3 rd Bone Spring Sand	11373	Oil/Gas	
Abo			
Wolfcamp	11820	Target Zone	
Devonian			
Fusselman			
Ellenburger			
Granite Wash			

*H2S, water flows, loss of circulation, abnormal pressures, etc.

Mewbourne Oil Company, Jennings 27 W0BO Fed Com #1H
Sec 31, T24S, R29E
SL: 275' FNL & 1310' FEL
BHL: 330' FSL & 1650' FEL

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	788'	13.375"	48	H40	STC	2.09	4.69	8.51	14.30
12.25"	0'	3453'	9.625"	36	J55	LTC	1.13	1.96	2.69	4.54
12.25"	3453'	4393'	9.625"	40	J55	LTC	1.13	1.73	11.87	16.75
12.25"	4393'	4548'	9.625"	40	N80	LTC	1.31	2.43	119.00	147.90
8.75"	0'	12211'	7"	26	HCP110	LTC	1.31	1.67	2.06	2.61
6.125"	11473'	16682'	4.5"	13.5	P110	LTC	1.31	1.52	4.79	5.99
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Jennings 27 W0BO Fed Com #1H
Sec 31, T24S, R29E
SL: 275' FNL & 1310' FEL
BHL: 330' FSL & 1650' FEL

3. Cementing Program

Casing	# Sks	Wt. lb/ gal	Yld ft3/ sack	H ₂ O gal/ sk	500# Comp. Strength (hours)	Slurry Description
Surf.	400	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	200	14.8	1.34	6.3	8	Tail: Class C + Retarder
Inter.	750	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	200	14.8	1.34	6.3	8	Tail: Class C + Retarder
Prod. Stg 1	350	12.5	2.12	11	9	Lead: Class C + Gel + Retarder + Defoamer + Extender
	400	15.6	1.18	5.2	10	Tail: Class H + Retarder + Fluid Loss + Defoamer
ECP/DV Tool @ 5803'						
Prod. Stg 2	70	12.5	2.12	11	9	Lead: Class C + Gel + Retarder + Defoamer + Extender
	100	14.8	1.34	6.3	8	Tail: Class C + Retarder
Liner	220	11.2	2.97	18	16	Class C + Salt + Gel + Fluid Loss + Retarder + Dispersant + Defoamer + Anti-Settling Agent

A copy of cement test will be available on location at time of cement job providing pump times & compressive strengths.

Casing String	TOC	% Excess
Surface	0'	100%
Intermediate	0'	25%
Production	4348'	25%
Liner	11473'	25%

Mewbourne Oil Company, Jennings 27 W0BO Fed Com #1H
Sec 31, T24S, R29E
SL: 275' FNL & 1310' FEL
BHL: 330' FSL & 1650' FEL

4. Pressure Control Equipment

Y	Variance: A variance is requested for use of a 5000 psi annular BOP with the 10,000 psi BOP stack. Please see attached description and procedure.
----------	---

BOP installed and tested before drilling which hole?	Size?	System Rated WP	Type	✓	Tested to:
12-1/4"	13-5/8"	10M	Annular	X	5000#
			Blind Ram	X	10000#
			Pipe Ram	X	
			Double Ram		
			Other*		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
Y	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. <div style="text-align: center;"> <ul style="list-style-type: none"> • Provide description here: See attached schematic. </div>

Mewbourne Oil Company, Jennings 27 W0BO Fed Com #1H
Sec 31, T24S, R29E
SL: 275' FNL & 1310' FEL
BHL: 330' FSL & 1650' FEL

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0'	788'	FW Gel	8.6-8.8	28-34	N/C
788'	4548'	Saturated Brine	10.0	28-34	N/C
4548'	11473'	Cut Brine	8.6-9.5	28-34	N/C
11473'	16682'	OBM	10.0-13.0	30-40	<10cc

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	Pason/PVT/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
X	Will run GR/CNL from KOP (11473') to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned	Interval
X Gamma Ray	11473' (KOP) to TD
Density	
CBL	
Mud log	
PEX	

Mewbourne Oil Company, Jennings 27 W0BO Fed Com #1H
Sec 31, T24S, R29E
SL: 275' FNL & 1310' FEL
BHL: 330' FSL & 1650' FEL

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	8155 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. **Lost circulation material/sweeps/mud scavengers in surface hole.**

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

	H2S is present
X	H2S Plan attached

8. Other facets of operation

Is this a walking operation? If yes, describe.

Will be pre-setting casing? If yes, describe.

Attachments

☐ Directional Plan

☐ Other, describe

Mewbourne Oil Company

Lea County, New Mexico NAD 83

Jennings 27 W0BO Fed Com #1H

Sec 27, T25S, R32E

SL: 275' FNL & 1310' FEL

BHL: 330' FSL & 1650' FEL

Plan: Design #1

Standard Planning Report

24 January, 2018

Planning Report

Database: Hobbs
 Company: Mewbourne Oil Company
 Project: Lea County, New Mexico NAD 83
 Site: Jennings 27 W0BO Fed Com #1H
 Well: Sec 27, T25S, R32E
 Wellbore: BHL: 330' FSL & 1650' FEL
 Design: Design #1

Local Co-ordinate Reference: Site Jennings 27 W0BO Fed Com #1H
 TVD Reference: WELL @ 3423.0usft (Original Well Elev)
 MD Reference: WELL @ 3423.0usft (Original Well Elev)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Project	Lea County, New Mexico NAD 83		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Jennings 27 W0BO Fed Com #1H		
Site Position:	Map	Northing:	403,671.00 usft
From:		Easting:	750,288.00 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "
		Latitude:	32.1079728
		Longitude:	-103.6584883
		Grid Convergence:	0.36 °

Well	Sec 27, T25S, R32E		
Well Position	+N/-S	0.0 usft	Northing:
	+E/-W	0.0 usft	Easting:
Position Uncertainty	0.0 usft	Wellhead Elevation:	3,423.0 usft
		Latitude:	32.1079728
		Longitude:	-103.6584883
		Ground Level:	3,396.0 usft

Wellbore	BHL: 330' FSL & 1650' FEL		
Magnetics	Model Name	Sample Date	Declination
	IGRF2010	1/24/2018	6.80
			Dip Angle
			59.90
			Field Strength
			47,877

Design	Design #1		
Audit Notes:			
Version:	Phase:	PROTOTYPE	Tie On Depth:
			0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W
	(usft)	(usft)	(usft)
	0.0	0.0	0.0
			Direction
			183.68

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
4,623.0	0.00	0.00	4,623.0	0.0	0.0	0.00	0.00	0.00	0.00	
4,808.8	3.72	307.00	4,808.7	3.6	-4.8	2.00	2.00	0.00	307.00	
11,288.1	3.72	307.00	11,274.3	256.4	-340.2	0.00	0.00	0.00	0.00	
11,473.9	0.00	0.00	11,460.0	260.0	-345.0	2.00	-2.00	0.00	180.00	KOP @ 11460'
12,211.6	88.40	179.49	11,938.0	-204.8	-340.9	11.98	11.98	0.00	179.49	
16,682.8	88.40	179.49	12,063.0	-4,674.0	-301.0	0.00	0.00	0.00	0.00	BHL: 330' FSL & 1650'

Planning Report

Database: Hobbs
 Company: Mewbourne Oil Company
 Project: Lea County, New Mexico NAD 83
 Site: Jennings 27 W0BO Fed Com #1H
 Well: Sec 27, T25S, R32E
 Wellbore: BHL: 330' FSL & 1650' FEL
 Design: Design #1

Local Co-ordinate Reference: Site Jennings 27 W0BO Fed Com #1H
 TVD Reference: WELL @ 3423.0usft (Original Well Elev)
 MD Reference: WELL @ 3423.0usft (Original Well Elev)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
SL: 275' FNL & 1310' FEL									
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00
2,800.0	0.00	0.00	2,800.0	0.0	0.0	0.0	0.00	0.00	0.00
2,900.0	0.00	0.00	2,900.0	0.0	0.0	0.0	0.00	0.00	0.00
3,000.0	0.00	0.00	3,000.0	0.0	0.0	0.0	0.00	0.00	0.00
3,100.0	0.00	0.00	3,100.0	0.0	0.0	0.0	0.00	0.00	0.00
3,200.0	0.00	0.00	3,200.0	0.0	0.0	0.0	0.00	0.00	0.00
3,300.0	0.00	0.00	3,300.0	0.0	0.0	0.0	0.00	0.00	0.00
3,400.0	0.00	0.00	3,400.0	0.0	0.0	0.0	0.00	0.00	0.00
3,500.0	0.00	0.00	3,500.0	0.0	0.0	0.0	0.00	0.00	0.00
3,600.0	0.00	0.00	3,600.0	0.0	0.0	0.0	0.00	0.00	0.00
3,700.0	0.00	0.00	3,700.0	0.0	0.0	0.0	0.00	0.00	0.00
3,800.0	0.00	0.00	3,800.0	0.0	0.0	0.0	0.00	0.00	0.00
3,900.0	0.00	0.00	3,900.0	0.0	0.0	0.0	0.00	0.00	0.00
4,000.0	0.00	0.00	4,000.0	0.0	0.0	0.0	0.00	0.00	0.00
4,100.0	0.00	0.00	4,100.0	0.0	0.0	0.0	0.00	0.00	0.00
4,200.0	0.00	0.00	4,200.0	0.0	0.0	0.0	0.00	0.00	0.00
4,300.0	0.00	0.00	4,300.0	0.0	0.0	0.0	0.00	0.00	0.00
4,400.0	0.00	0.00	4,400.0	0.0	0.0	0.0	0.00	0.00	0.00
4,500.0	0.00	0.00	4,500.0	0.0	0.0	0.0	0.00	0.00	0.00
4,600.0	0.00	0.00	4,600.0	0.0	0.0	0.0	0.00	0.00	0.00
4,623.0	0.00	0.00	4,623.0	0.0	0.0	0.0	0.00	0.00	0.00
4,700.0	1.54	307.00	4,700.0	0.6	-0.8	-0.6	2.00	2.00	0.00
4,800.0	3.54	307.00	4,799.9	3.3	-4.4	-3.0	2.00	2.00	0.00
4,808.8	3.72	307.00	4,808.7	3.6	-4.8	-3.3	2.00	2.00	0.00
4,900.0	3.72	307.00	4,899.7	7.2	-9.5	-6.6	0.00	0.00	0.00
5,000.0	3.72	307.00	4,999.5	11.1	-14.7	-10.1	0.00	0.00	0.00

Planning Report

Database: Hobbs
 Company: Mewbourne Oil Company
 Project: Lea County, New Mexico NAD 83
 Site: Jennings 27 W0BO Fed Com #1H
 Well: Sec 27, T25S, R32E
 Wellbore: BHL: 330' FSL & 1650' FEL
 Design: Design #1

Local Co-ordinate Reference: Site Jennings 27 W0BO Fed Com #1H
 TVD Reference: WELL @ 3423.0usft (Original Well Elev)
 MD Reference: WELL @ 3423.0usft (Original Well Elev)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,100.0	3.72	307.00	5,099.3	15.0	-19.9	-13.7	0.00	0.00	0.00
5,200.0	3.72	307.00	5,199.0	18.9	-25.1	-17.2	0.00	0.00	0.00
5,300.0	3.72	307.00	5,298.8	22.8	-30.2	-20.8	0.00	0.00	0.00
5,400.0	3.72	307.00	5,398.6	26.7	-35.4	-24.4	0.00	0.00	0.00
5,500.0	3.72	307.00	5,498.4	30.6	-40.6	-27.9	0.00	0.00	0.00
5,600.0	3.72	307.00	5,598.2	34.5	-45.8	-31.5	0.00	0.00	0.00
5,700.0	3.72	307.00	5,698.0	38.4	-50.9	-35.0	0.00	0.00	0.00
5,800.0	3.72	307.00	5,797.8	42.3	-56.1	-38.6	0.00	0.00	0.00
5,900.0	3.72	307.00	5,897.6	46.2	-61.3	-42.2	0.00	0.00	0.00
6,000.0	3.72	307.00	5,997.4	50.1	-66.5	-45.7	0.00	0.00	0.00
6,100.0	3.72	307.00	6,097.2	54.0	-71.6	-49.3	0.00	0.00	0.00
6,200.0	3.72	307.00	6,196.9	57.9	-76.8	-52.8	0.00	0.00	0.00
6,300.0	3.72	307.00	6,296.7	61.8	-82.0	-56.4	0.00	0.00	0.00
6,400.0	3.72	307.00	6,396.5	65.7	-87.2	-60.0	0.00	0.00	0.00
6,500.0	3.72	307.00	6,496.3	69.6	-92.3	-63.5	0.00	0.00	0.00
6,600.0	3.72	307.00	6,596.1	73.5	-97.5	-67.1	0.00	0.00	0.00
6,700.0	3.72	307.00	6,695.9	77.4	-102.7	-70.6	0.00	0.00	0.00
6,800.0	3.72	307.00	6,795.7	81.3	-107.9	-74.2	0.00	0.00	0.00
6,900.0	3.72	307.00	6,895.5	85.2	-113.1	-77.8	0.00	0.00	0.00
7,000.0	3.72	307.00	6,995.3	89.1	-118.2	-81.3	0.00	0.00	0.00
7,100.0	3.72	307.00	7,095.1	93.0	-123.4	-84.9	0.00	0.00	0.00
7,200.0	3.72	307.00	7,194.8	96.9	-128.6	-88.4	0.00	0.00	0.00
7,300.0	3.72	307.00	7,294.6	100.8	-133.8	-92.0	0.00	0.00	0.00
7,400.0	3.72	307.00	7,394.4	104.7	-138.9	-95.6	0.00	0.00	0.00
7,500.0	3.72	307.00	7,494.2	108.6	-144.1	-99.1	0.00	0.00	0.00
7,600.0	3.72	307.00	7,594.0	112.5	-149.3	-102.7	0.00	0.00	0.00
7,700.0	3.72	307.00	7,693.8	116.4	-154.5	-106.2	0.00	0.00	0.00
7,800.0	3.72	307.00	7,793.6	120.3	-159.6	-109.8	0.00	0.00	0.00
7,900.0	3.72	307.00	7,893.4	124.2	-164.8	-113.4	0.00	0.00	0.00
8,000.0	3.72	307.00	7,993.2	128.1	-170.0	-116.9	0.00	0.00	0.00
8,100.0	3.72	307.00	8,092.9	132.0	-175.2	-120.5	0.00	0.00	0.00
8,200.0	3.72	307.00	8,192.7	135.9	-180.3	-124.0	0.00	0.00	0.00
8,300.0	3.72	307.00	8,292.5	139.8	-185.5	-127.6	0.00	0.00	0.00
8,400.0	3.72	307.00	8,392.3	143.7	-190.7	-131.2	0.00	0.00	0.00
8,500.0	3.72	307.00	8,492.1	147.6	-195.9	-134.7	0.00	0.00	0.00
8,600.0	3.72	307.00	8,591.9	151.5	-201.0	-138.3	0.00	0.00	0.00
8,700.0	3.72	307.00	8,691.7	155.4	-206.2	-141.8	0.00	0.00	0.00
8,800.0	3.72	307.00	8,791.5	159.3	-211.4	-145.4	0.00	0.00	0.00
8,900.0	3.72	307.00	8,891.3	163.2	-216.6	-149.0	0.00	0.00	0.00
9,000.0	3.72	307.00	8,991.1	167.1	-221.8	-152.5	0.00	0.00	0.00
9,100.0	3.72	307.00	9,090.8	171.0	-226.9	-156.1	0.00	0.00	0.00
9,200.0	3.72	307.00	9,190.6	174.9	-232.1	-159.6	0.00	0.00	0.00
9,300.0	3.72	307.00	9,290.4	178.8	-237.3	-163.2	0.00	0.00	0.00
9,400.0	3.72	307.00	9,390.2	182.7	-242.5	-166.8	0.00	0.00	0.00
9,500.0	3.72	307.00	9,490.0	186.6	-247.6	-170.3	0.00	0.00	0.00
9,600.0	3.72	307.00	9,589.8	190.5	-252.8	-173.9	0.00	0.00	0.00
9,700.0	3.72	307.00	9,689.6	194.4	-258.0	-177.4	0.00	0.00	0.00
9,800.0	3.72	307.00	9,789.4	198.3	-263.2	-181.0	0.00	0.00	0.00
9,900.0	3.72	307.00	9,889.2	202.2	-268.3	-184.6	0.00	0.00	0.00
10,000.0	3.72	307.00	9,989.0	206.1	-273.5	-188.1	0.00	0.00	0.00
10,100.0	3.72	307.00	10,088.7	210.0	-278.7	-191.7	0.00	0.00	0.00
10,200.0	3.72	307.00	10,188.5	213.9	-283.9	-195.2	0.00	0.00	0.00
10,300.0	3.72	307.00	10,288.3	217.8	-289.0	-198.8	0.00	0.00	0.00
10,400.0	3.72	307.00	10,388.1	221.7	-294.2	-202.4	0.00	0.00	0.00

Planning Report

Database: Hobbs
 Company: Mewbourne Oil Company
 Project: Lea County, New Mexico NAD 83
 Site: Jennings 27 W0BO Fed Com #1H
 Well: Sec 27, T25S, R32E
 Wellbore: BHL: 330' FSL & 1650' FEL
 Design: Design #1

Local Co-ordinate Reference: Site Jennings 27 W0BO Fed Com #1H
 TVD Reference: WELL @ 3423.0usft (Original Well Elev)
 MD Reference: WELL @ 3423.0usft (Original Well Elev)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
10,500.0	3.72	307.00	10,487.9	225.6	-299.4	-205.9	0.00	0.00	0.00
10,600.0	3.72	307.00	10,587.7	229.5	-304.6	-209.5	0.00	0.00	0.00
10,700.0	3.72	307.00	10,687.5	233.4	-309.7	-213.0	0.00	0.00	0.00
10,800.0	3.72	307.00	10,787.3	237.3	-314.9	-216.6	0.00	0.00	0.00
10,900.0	3.72	307.00	10,887.1	241.2	-320.1	-220.2	0.00	0.00	0.00
11,000.0	3.72	307.00	10,986.9	245.1	-325.3	-223.7	0.00	0.00	0.00
11,100.0	3.72	307.00	11,086.6	249.0	-330.5	-227.3	0.00	0.00	0.00
11,200.0	3.72	307.00	11,186.4	252.9	-335.6	-230.8	0.00	0.00	0.00
11,288.1	3.72	307.00	11,274.3	256.4	-340.2	-234.0	0.00	0.00	0.00
11,300.0	3.48	307.00	11,286.2	256.8	-340.8	-234.4	2.00	-2.00	0.00
11,400.0	1.48	307.00	11,386.1	259.4	-344.2	-236.8	2.00	-2.00	0.00
11,473.9	0.00	0.00	11,460.0	260.0	-345.0	-237.3	2.00	-2.00	0.00
KOP @ 11460'									
11,500.0	3.13	179.49	11,486.1	259.3	-345.0	-236.6	11.98	11.98	0.00
11,600.0	15.11	179.49	11,584.7	243.5	-344.9	-220.8	11.98	11.98	0.00
11,700.0	27.09	179.49	11,677.8	207.5	-344.5	-185.0	11.98	11.98	0.00
11,800.0	39.07	179.49	11,761.4	153.0	-344.0	-130.6	11.98	11.98	0.00
11,900.0	51.06	179.49	11,831.9	82.4	-343.4	-60.1	11.98	11.98	0.00
12,000.0	63.04	179.49	11,886.2	-1.4	-342.7	23.4	11.98	11.98	0.00
12,058.5	70.05	179.49	11,909.5	-55.0	-342.2	76.9	11.98	11.98	0.00
FTP: 330' FNL & 1650' FEL									
12,100.0	75.02	179.49	11,921.9	-94.6	-341.8	116.3	11.98	11.98	0.00
12,200.0	87.00	179.49	11,937.5	-193.2	-341.0	214.7	11.98	11.98	0.00
12,211.6	88.40	179.49	11,938.0	-204.8	-340.9	226.3	11.98	11.98	0.00
LP: 480' FNL & 1650' FEL									
12,300.0	88.40	179.49	11,940.5	-293.1	-340.1	314.4	0.00	0.00	0.00
12,400.0	88.40	179.49	11,943.3	-393.1	-339.2	414.1	0.00	0.00	0.00
12,500.0	88.40	179.49	11,946.1	-493.0	-338.3	513.7	0.00	0.00	0.00
12,600.0	88.40	179.49	11,948.9	-593.0	-337.4	613.4	0.00	0.00	0.00
12,700.0	88.40	179.49	11,951.7	-692.9	-336.5	713.1	0.00	0.00	0.00
12,800.0	88.40	179.49	11,954.4	-792.9	-335.6	812.8	0.00	0.00	0.00
12,900.0	88.40	179.49	11,957.2	-892.9	-334.7	912.5	0.00	0.00	0.00
13,000.0	88.40	179.49	11,960.0	-992.8	-333.8	1,012.2	0.00	0.00	0.00
13,100.0	88.40	179.49	11,962.8	-1,092.8	-332.9	1,111.9	0.00	0.00	0.00
13,200.0	88.40	179.49	11,965.6	-1,192.7	-332.0	1,211.6	0.00	0.00	0.00
13,300.0	88.40	179.49	11,968.4	-1,292.7	-331.2	1,311.3	0.00	0.00	0.00
13,400.0	88.40	179.49	11,971.2	-1,392.6	-330.3	1,411.0	0.00	0.00	0.00
13,500.0	88.40	179.49	11,974.0	-1,492.6	-329.4	1,510.7	0.00	0.00	0.00
13,600.0	88.40	179.49	11,976.8	-1,592.6	-328.5	1,610.4	0.00	0.00	0.00
13,700.0	88.40	179.49	11,979.6	-1,692.5	-327.6	1,710.1	0.00	0.00	0.00
13,800.0	88.40	179.49	11,982.4	-1,792.5	-326.7	1,809.8	0.00	0.00	0.00
13,900.0	88.40	179.49	11,985.2	-1,892.4	-325.8	1,909.5	0.00	0.00	0.00
14,000.0	88.40	179.49	11,988.0	-1,992.4	-324.9	2,009.1	0.00	0.00	0.00
14,100.0	88.40	179.49	11,990.8	-2,092.3	-324.0	2,108.8	0.00	0.00	0.00
14,200.0	88.40	179.49	11,993.6	-2,192.3	-323.1	2,208.5	0.00	0.00	0.00
14,300.0	88.40	179.49	11,996.4	-2,292.3	-322.2	2,308.2	0.00	0.00	0.00
14,358.8	88.40	179.49	11,998.0	-2,351.0	-321.7	2,366.8	0.00	0.00	0.00
PPP-2: 2622' FNL & 1650' FEL									
14,400.0	88.40	179.49	11,999.2	-2,392.2	-321.3	2,407.9	0.00	0.00	0.00
14,500.0	88.40	179.49	12,002.0	-2,492.2	-320.5	2,507.6	0.00	0.00	0.00
14,600.0	88.40	179.49	12,004.8	-2,592.1	-319.6	2,607.3	0.00	0.00	0.00
14,700.0	88.40	179.49	12,007.6	-2,692.1	-318.7	2,707.0	0.00	0.00	0.00
14,800.0	88.40	179.49	12,010.4	-2,792.0	-317.8	2,806.7	0.00	0.00	0.00

Planning Report

Database: Hobbs
Company: Mewbourne Oil Company
Project: Lea County, New Mexico NAD 83
Site: Jennings 27 W0BO Fed Com #1H
Well: Sec 27, T25S, R32E
Wellbore: BHL: 330' FSL & 1650' FEL
Design: Design #1

Local Co-ordinate Reference: Site Jennings 27 W0BO Fed Com #1H
TVD Reference: WELL @ 3423.0usft (Original Well Elev)
MD Reference: WELL @ 3423.0usft (Original Well Elev)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey



Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
14,900.0	88.40	179.49	12,013.2	-2,892.0	-316.9	2,906.4	0.00	0.00	0.00
15,000.0	88.40	179.49	12,016.0	-2,992.0	-316.0	3,006.1	0.00	0.00	0.00
15,100.0	88.40	179.49	12,018.7	-3,091.9	-315.1	3,105.8	0.00	0.00	0.00
15,200.0	88.40	179.49	12,021.5	-3,191.9	-314.2	3,205.5	0.00	0.00	0.00
15,300.0	88.40	179.49	12,024.3	-3,291.8	-313.3	3,305.2	0.00	0.00	0.00
15,400.0	88.40	179.49	12,027.1	-3,391.8	-312.4	3,404.8	0.00	0.00	0.00
15,500.0	88.40	179.49	12,029.9	-3,491.7	-311.5	3,504.5	0.00	0.00	0.00
15,600.0	88.40	179.49	12,032.7	-3,591.7	-310.7	3,604.2	0.00	0.00	0.00
15,700.0	88.40	179.49	12,035.5	-3,691.6	-309.8	3,703.9	0.00	0.00	0.00
15,800.0	88.40	179.49	12,038.3	-3,791.6	-308.9	3,803.6	0.00	0.00	0.00
15,900.0	88.40	179.49	12,041.1	-3,891.6	-308.0	3,903.3	0.00	0.00	0.00
16,000.0	88.40	179.49	12,043.9	-3,991.5	-307.1	4,003.0	0.00	0.00	0.00
16,100.0	88.40	179.49	12,046.7	-4,091.5	-306.2	4,102.7	0.00	0.00	0.00
16,200.0	88.40	179.49	12,049.5	-4,191.4	-305.3	4,202.4	0.00	0.00	0.00
16,300.0	88.40	179.49	12,052.3	-4,291.4	-304.4	4,302.1	0.00	0.00	0.00
16,400.0	88.40	179.49	12,055.1	-4,391.3	-303.5	4,401.8	0.00	0.00	0.00
16,500.0	88.40	179.49	12,057.9	-4,491.3	-302.6	4,501.5	0.00	0.00	0.00
16,600.0	88.40	179.49	12,060.7	-4,591.3	-301.7	4,601.2	0.00	0.00	0.00
16,682.8	88.40	179.49	12,063.0	-4,674.0	-301.0	4,683.7	0.00	0.00	0.00

BHL: 330' FSL & 1650' FEL


Design Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
SL: 275' FNL & 1310' FE - hit/miss target - Shape - plan hits target center - Point	0.00	0.00	0.0	0.0	0.0	403,671.00	750,288.00	32.1079728	-103.6584883
KOP @ 11460' - plan hits target center - Point	0.00	0.00	11,460.0	260.0	-345.0	403,931.00	749,943.00	32.1086935	-103.6595972
FTP: 330' FNL & 1650' F - plan hits target center - Point	0.00	0.00	11,909.5	-55.0	-342.2	403,616.00	749,945.81	32.1078275	-103.6595945
LP: 480' FNL & 1650' FE - plan hits target center - Point	0.00	0.00	11,938.0	-204.8	-340.9	403,466.20	749,947.14	32.1074158	-103.6595932
PPP-2: 2622' FNL & 165 - plan hits target center - Point	0.00	0.00	11,998.0	-2,351.0	-321.7	401,320.00	749,966.28	32.1015160	-103.6595747
BHL: 330' FSL & 1650' F - plan hits target center - Point	0.00	0.00	12,063.0	-4,674.0	-301.0	398,997.00	749,987.00	32.0951303	-103.6595547

Jennings 27 W0BO Fed Com #1H





Hydril "GK"
13-5/8" 10M



Hydril "GK"

Cameron Type U
13-5/8" 10M



4 1/2"x 5 7/8" VBR

BLIND RAMS


4 1/2"x 5 7/8" VBR

13 5/8" 10M

13 5/8" 10M

13 5/8" 10M

13 5/8" 10M



10,000 PSI Annular BOP Variance Request

Mewbourne Oil Company request a variance to use a 5000 psi annular BOP with a 10,000 psi BOP stack. The component and compatibility tables along with the general well control plans demonstrate how the 5000 psi annular BOP will be protected from pressures that exceed its rated working pressure (RWP). The pressure at which the control of the wellbore is transferred from the annular preventer to another available preventer will not exceed 3500 psi (70% of the RWP of the 5000 psi annular BOP).

1. Component and Preventer Compatibility Tables

The tables below outline the tubulars and the compatible preventers in use. This table, combined with the drilling fluid, documents that two barriers to flow will be maintained at all times.

12-1/4" Intermediate Hole Section 10M psi Requirement					
Component	OD	Primary Preventer	RWP	Alternate Preventer(s)	RWP
Drillpipe	5.000" or 4.500"	Annular	5M	Upper 3.5"-5.5" VBR	10M
				Lower 3.5"-5.5" VBR	10M
HWDP	5.000" or 4.500"	Annular	5M	Upper 3.5"-5.5" VBR	10M
				Lower 3.5"-5.5" VBR	10M
Jars	6.500"	Annular	5M	-	-
DCs and MWD tools	6.500"-8.000"	Annular	5M	-	-
Mud Motor	8.000"-9.625"	Annular	5M	-	-
Intermediate Casing	9.625"	Annular	5M	-	-
Open-Hole	-	Blind Rams	10M	-	-

8-3/4" Production Hole Section 10M psi Requirement					
Component	OD	Primary Preventer	RWP	Alternate Preventer(s)	RWP
Drillpipe	5.000" or 4.500"	Annular	5M	Upper 3.5"-5.5" VBR	10M
				Lower 3.5"-5.5" VBR	10M
HWDP	5.000" or 4.500"	Annular	5M	Upper 3.5"-5.5" VBR	10M
				Lower 3.5"-5.5" VBR	10M
Jars	6.500"	Annular	5M	-	-
DCs and MWD tools	6.500"-8.000"	Annular	5M	-	-
Mud Motor	6.750"-8.000"	Annular	5M	-	-
Production Casing	7"	Annular	5M	-	-
Open-Hole	-	Blind Rams	10M	-	-

6-1/8" Lateral Hole Section 10M psi Requirement					
Component	OD	Primary Preventer	RWP	Alternate Preventer(s)	RWP
Drillpipe	4.500"	Annular	5M	Upper 3.5"-5.5" VBR Lower 3.5"-5.5" VBR	10M 10M
HWDP	4.500"	Annular	5M	Upper 3.5"-5.5" VBR Lower 3.5"-5.5" VBR	10M 10M
DCs and MWD tools	4.750"-5.500"	Annular	5M	Upper 3.5"-5.5" VBR Lower 3.5"-5.5" VBR	10M 10M
Mud Motor	4.750"-5.500"	Annular	5M	Upper 3.5"-5.5" VBR Lower 3.5"-5.5" VBR	10M 10M
Production Casing	4.500"	Annular	5M	Upper 3.5"-5.5" VBR Upper 3.5"-5.5" VBR	10M 10M
Open-Hole	-	Blind Rams	10M	-	-

VBR = Variable Bore Ram

2. Well Control Procedures

Below are the minimal high-level tasks prescribed to assure a proper shut-in while drilling, tripping, running casing, pipe out of the hole (open hole), and moving the BHA through the BOPs. At least one well control drill will be performed weekly per crew to demonstrate compliance with the procedure and well control plan. The well control drill will be recorded in the daily drilling log. The type of drill will be determined by the ongoing operations, but reasonable attempts will be made to vary the type of drill conducted (pit, trip, open hole, choke, etc.). This well control plan will be available for review by rig personnel in the Mewbourne Oil Company drilling supervisor's office on location and on the rig floor. All BOP equipment will be tested as per Onshore O&G Order No. 2 with the exception of the 5000 psi annular which will be tested to 70% of its RWP.

General Procedure While Drilling

1. Sound alarm (alert crew)
2. Space out drill string
3. Shut down pumps (stop pumps and rotary)
4. Shut-in well (uppermost applicable BOP, typically annular preventer, first. HCR & choke will already be in the closed position.)
5. Confirm shut-in
6. Notify toolpusher/company representative
7. Read and record the following:
 - a. SIDPP & SICP
 - b. Pit gain
 - c. Time
8. Regroup and identify forward plan

9. If pressure has built or is anticipated during the kill to reach 70% or greater of the RWP of the annular preventer, confirm spacing and close the upper variable bore rams.

General Procedure While Tripping

1. Sound alarm (alert crew)
2. Stab full-opening safety valve & close
3. Space out drill string
4. Shut-in well (uppermost applicable BOP, typically annular preventer, first. HCR & choke will already be in the closed position.)
5. Confirm shut-in
6. Notify toolpusher/company representative
7. Read and record the following:
 - a. SIDPP & SICP
 - b. Pit gain
 - c. Time
8. Regroup and identify forward plan
9. If pressure has built or is anticipated during the kill to reach 70% of the RWP of the annular preventer, confirm spacing and close the upper variable bore rams.

General Procedure While Running Production Casing

1. Sound alarm (alert crew)
2. Stab crossover and full-opening safety valve and close
3. Space out string
4. Shut-in well (uppermost applicable BOP, typically annular preventer, first. HCR & choke will already be in the closed position.)
5. Confirm shut-in
6. Notify toolpusher/company representative
7. Read and record the following:
 - a. SIDPP & SICP
 - b. Pit gain
 - c. Time
8. Regroup and identify forward plan
9. If pressure has built or is anticipated during the kill to reach 70% or greater of the RWP of the annular preventer, confirm spacing and close the upper variable bore rams.

General Procedure With No Pipe In Hole (Open Hole)

1. Sound alarm (alert crew)
2. Shut-in with blind rams (HCR & choke will already be in the closed position)
3. Confirm shut-in
4. Notify toolpusher/company representative
5. Read and record the following:
 - a. SICP
 - b. Pit gain
 - c. Time
6. Regroup and identify forward plan


General Procedures While Pulling BHA Through Stack

1. PRIOR to pulling last joint of drillpipe through stack:
 - a. Perform flow check. If flowing, continue to (b).
 - b. Sound alarm (alert crew)
 - c. Stab full-opening safety valve and close
 - d. Space out drill string with tool joint just beneath the upper variable bore rams
 - e. Shut-in using upper variable bore rams (HCR & choke will already be in the closed position)
 - f. Confirm shut-in
 - g. Notify toolpusher/company representative
 - h. Read and record the following:
 - i. SIDPP & SICP
 - ii. Pit gain
 - iii. Time
 - i. Regroup and identify forward plan
2. With BHA in the stack and compatible ram preventer and pipe combination immediately available:
 - a. Sound alarm (alert crew)
 - b. Stab crossover and full-opening safety valve and close
 - c. Space out drill string with upset just beneath the upper variable bore rams
 - d. Shut-in using upper variable bore rams (HCR & choke will already be in the closed position)
 - e. Confirm shut-in
 - f. Notify toolpusher/company representative
 - g. Read and record the following:
 - i. SIDPP & SICP

- ii. Pit gain
 - iii. Time
- h. Regroup and identify forward plan
- 3. With BHA in the stack and NO compatible ram preventer and pipe combination immediately available:
 - a. Sound alarm (alert crew)
 - b. If possible, pull string clear of the stack and follow "Open Hole" procedure.
 - c. If impossible to pull string clear of the stack:
 - d. Stab crossover, make up one joint/stand of drillpipe and full-opening safety valve and close
 - e. Space out drill string with tooljoint just beneath the upper variable bore ram
 - f. Shut-in using upper variable bore ram (HCR & choke will already be in the closed position)
 - g. Confirm shut-in
 - h. Notify toolpusher/company representative
 - i. Read and record the following:
 - i. SIDPP & SICP
 - ii. Pit gain
 - iii. Time
 - j. Regroup and identify forward plan

RUNNING PROCEDURE

Mewbourne Oil Co



Publication Status Note:

Draft A sent to John Cortinas for review; RA 04/29/17


Surface Systems Publication



13-5/8" 10K MN-DS System
13-3/8" x 9-5/8" x 7" Casing Program

RP-003815
Rev 01 Draft A

10M BOPE & Closed Loop Equipment Schematic



Drawing not to scale



GATES E & S NORTH AMERICA, INC.
134 44TH STREET
CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807
FAX: 361-887-0812
EMAIL: Tim.Cantu@gates.com
WEB: www.gates.com

10K CEMENTING ASSEMBLY PRESSURE TEST CERTIFICATE

Customer :	AUSTIN DISTRIBUTING	Test Date:	4/30/2015
Customer Ref. :	4060578	Hose Serial No.:	D-043015-7
Invoice No. :	500506	Created By:	JUSTIN CROPPER
Product Description:	10K3.548.0CK4.1/1610KFLGE/E LE		
End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6290	Assembly Code :	L36554102914D-043015-7
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :
Date :
Signature :

QUALITY
4/30/2015
<i>Justin Cropper</i>


Production:
Date :
Signature :

PRODUCTION
4/30/2015
<i>Justin Cropper</i>

Form PTC - 01 Rev.02



60 MIN.



Hydrogen Sulfide Drilling Operations Plan
Mewbourne Oil Company

1. General Requirements

Rule 118 does not apply to this well because MOC has researched this area and no high concentrations of H₂S were found. MOC will have on location and working all H₂S safety equipment before the Delaware formation for purposes of safety and insurance requirements.

2. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will have received training from a qualified instructor in the following areas prior to entering the drilling pad area of the well:

1. The hazards and characteristics of hydrogen sulfide gas.
2. The proper use of personal protective equipment and life support systems.
3. The proper use of hydrogen sulfide detectors, alarms, warning systems, briefing areas, evacuation procedures.
4. The proper techniques for first aid and rescue operations.

Additionally, supervisory personnel will be trained in the following areas:

- 1 The effects of hydrogen sulfide on metal components. If high tensile tubular systems are utilized, supervisory personnel will be trained in their special maintenance requirements.
- 2 Corrective action and shut in procedures, blowout prevention, and well control procedures while drilling a well.
- 3 The contents of the Hydrogen Sulfide Drilling Operations Plan.

There will be an initial training session prior to encountering a known hydrogen sulfide source. The initial training session shall include a review of the site specific Hydrogen Sulfide Drilling Operations Plan.

3. Hydrogen Sulfide Safety Equipment and Systems

All hydrogen sulfide safety equipment and systems will be installed, tested, and operational prior to drilling below the 9 5/8" intermediate casing.

1. Well Control Equipment
 - A. Choke manifold with minimum of one adjustable choke/remote choke.
 - B. Blowout preventers equipped with blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
 - C. Auxiliary equipment including annular type blowout preventer.
2. Protective Equipment for Essential Personnel

Thirty minute self contained work unit located in the dog house and at briefing areas.

Additionally: If H₂S is encountered in concentrations less than 10 ppm, fans will be placed in work areas to prevent the accumulation of hazardous amounts of poisonous gas. If higher concentrations of H₂S are detected the well will be shut in and a rotating head, mud/gas separator, remote choke and flare line with igniter will be installed.

3. Hydrogen Sulfide Protection and Monitoring Equipment

Two portable hydrogen sulfide monitors positioned on location for optimum coverage and detection. The units shall have audible sirens to notify personnel when hydrogen sulfide levels exceed 20 PPM.

4. Visual Warning Systems

A. Wind direction indicators as indicated on the wellsite diagram.

B. Caution signs shall be posted on roads providing access to location. Signs shall be painted a high visibility color with lettering of sufficient size to be readable at reasonable distances from potentially contaminated areas.

4. **Mud Program**

The mud program has been designed to minimize the amount of hydrogen sulfide entrained in the mud system. Proper mud weight, safe drilling practices, and the use of hydrogen sulfide scavengers will minimize hazards while drilling the well.

5. **Metallurgy**

All tubular systems, wellheads, blowout preventers, drilling spools, kill lines, choke manifolds, and valves shall be suitable for service in a hydrogen sulfide environment when chemically treated.

6. **Communications**

State & County Officials phone numbers are posted on rig floor and supervisors trailer. Communications in company vehicles and toolpushers are either two way radios or cellular phones.

7. **Well Testing**

Drill stem testing is not an anticipated requirement for evaluation of this well. If a drill stem test is required, it will be conducted with a minimum number of personnel in the immediate vicinity. The test will be conducted during daylight hours only.

8. **Emergency Phone Numbers**

Eddy County Sheriff's Office	911 or 575-887-7551
Ambulance Service	911 or 575-885-2111
Carlsbad Fire Dept	911 or 575-885-2111
Loco Hills Volunteer Fire Dept.	911 or 575-677-3266
Closest Medical Facility - Columbia Medical Center of Carlsbad	575-492-5000

Mewbourne Oil Company	Hobbs District Office	575-393-5905
	Fax	575-397-6252
	2nd Fax	575-393-7259

District Manager	Robin Terrell	575-390-4816
Drilling Superintendent	Frosty Lathan	575-390-4103
	Bradley Bishop	575-390-6838
Drilling Foreman	Wesley Noseff	575-441-0729

PECOS DISTRICT

DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	MEWBOURNE OIL COMPANY
LEASE NO.:	NMNM115421
WELL NAME & NO.:	JENNINGS 27 W0BO FED COM 1H
SURFACE HOLE FOOTAGE:	275' FNL & 1310' FEL
BOTTOM HOLE FOOTAGE:	330' FSL & 1650' FEL
LOCATION:	Section 27, T. 25 S., R 32 E., NMPM
COUNTY:	Eddy County, New Mexico

COA

H2S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP

A. Hydrogen Sulfide

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Delaware** formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **850** feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement).
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9-5/8** inch intermediate casing is:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above. **Additional cement maybe required. Excess calculates to 24%.**
3. The minimum required fill of cement behind the **7** inch production casing is:
Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.
 - a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
 - b. Second stage above DV tool: Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification.
4. The minimum required fill of cement behind the **4-1/2** inch production liner is:
 - Cement should tie-back 100' into the previous casing. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **10,000 (10M) psi. Variance approved to use a 5M annular. The annular must be tested to full working pressure (5000 psi.).**

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. **On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.**
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. **If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:**
 - a. **Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.**
 - b. **If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.**
 - c. **Manufacturer representative shall install the test plug for the initial BOP test.**
 - d. **If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.**
 - e. **Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.**
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
 - c. The tests shall be done by an independent service company utilizing a test plug. The results of the test shall be reported to the appropriate BLM office.

- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

ZS 021218

13 3/8 Segment	surface csg in a #/ft	17 1/2 Grade	inch hole. Coupling	Joint	Design Factors		SURFACE		
"A"	48.00	H 40	ST&C	7.89	Collapse 1.98	Burst 0.73	Length 850	Weight 40,800	
"B"							0	0	
w/8.4#/g mud, 30min Sfc Csg Test psig: 840			Tail Cmt	does not	circ to sfc.	Totals:	850	40,800	
<u>Comparison of Proposed to Minimum Required Cement Volumes</u>									
Hole Size	Annular Volume	1 Stage Cmt Sx	1 Stage CuFt Cmt	Min Cu Ft	1 Stage % Excess	Drilling Mud Wt	Calc MASP	Req'd BOPE	Min Dist Hole-Cplg
17 1/2	0.6946	600	1116	645	73	8.80	1362	2M	1.56

Burst Frac Gradient(s) for Segment(s) A, B = , b All > 0.70, OK.

9 5/8 Segment	casing inside the #/ft	13 3/8 Grade	Coupling	Joint	Design Factors		INTERMEDIATE		
"A"	36.00	J 55	LT&C	2.69	Collapse 1.13	Burst 0.6	Length 3,453	Weight 124,308	
"B"	40.00	J 55	LT&C	11.87	1.13	0.67	940	37,600	
"C"	40.00	N 80	LT&C	118.87	1.31	0.98	155	6,200	
"D"							0	0	
w/8.4#/g mud, 30min Sfc Csg Test psig:							Totals:	4,548	168,108
The cement volume(s) are intended to achieve a top of					0	ft from surface or a		850	overlap.
Hole Size	Annular Volume	1 Stage Cmt Sx	1 Stage CuFt Cmt	Min Cu Ft	1 Stage % Excess	Drilling Mud Wt	Calc MASP	Req'd BOPE	Min Dist Hole-Cplg
12 1/4	0.3132	950	1858	1497	24	10.00	3265	5M	0.81

Burst Frac Gradient(s) for Segment(s): A, B, C, D = 1.02, 0.9, 1.26, d All > 0.70, OK.

ALT. BURST IS GOOD.

7 Segment	casing inside the #/ft	9 5/8 Grade	Coupling	Joint	Design Factors		PRODUCTION		
"A"	26.00	HCP 110	LT&C	2.23	Collapse 1.38	Burst 1.22	Length 11,474	Weight 298,324	
"B"	26.00	HCP 110	BUTT	5.55	1.21	1.22	737	19,162	
"C"							0	0	
"D"							0	0	
w/8.4#/g mud, 30min Sfc Csg Test psig: 2,524							Totals:	12,211 317,486	
B	would be:			68.83	1.32	if it were a vertical wellbore.			
No Pilot Hole Planned		MTD 12211	Max VTD 11938	Csg VD 11938	Curve KOP 11474	Dogleg° 88	Severity° 12	MEOC 12211	
The cement volume(s) are intended to achieve a top of				4348	ft from surface or a		200	overlap.	
Hole Size	Annular Volume	1 Stage Cmt Sx	1 Stage CuFt Cmt	Min Cu Ft	1 Stage % Excess	Drilling Mud Wt	Calc MASP	Req'd BOPE	Min Dist Hole-Cplg
8 3/4	0.1503	look ↘	0	1194		9.50	5493	10M	0.55
Setting Depths for D V Tool(s):				5803			sum of sx	Σ CuFt	Σ % excess
% excess cmt by stage:				25	27		920	1496	25

MASP is within 10% of 5000psig, need exrta equip?

Tail cmt					<u>Design Factors</u>			LINER	
4 1/2	Liner w/top @	11473							
Segment	#/ft	Grade	Coupling	Joint	Collapse	Burst	Length	Weight	
"A"	13.50	P 110	LT&C	2.96	1.21	1.52	738	9,963	
"B"	13.50	P 110	LT&C	2.21	1.31	1.52	4,471	60,359	
w/8.4#/g mud, 30min Sfc Csg Test psig: 2,654							Totals:	5,209	70,322
A Segment Design Factors would be:				2.08	1.31	if it were a vertical wellbore.			
No Pilot Hole Planned		MTD	Max VTD	Csg VD	Curve KOP	Dogleg°	Severity°	MEOC	
		16682	12063	12063	11474	88	12	12211	
The cement volume(s) are intended to achieve a top of				11473	ft from surface or a		738	overlap.	
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
6 1/8	0.0942	220	653	435	50	13.00			0.56

Class 'H' tail cmt yld > 1.20

Capitan Reef est top XXXX.

MASP is within 10% of 5000psig, need exrta equip?