

District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
811 S. First St., Artesia, NM 88210  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy, Minerals and Natural Resources Department  
Oil Conservation Division  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Submit Original  
to Appropriate  
District Office

**HOBBS OCD**  
**AUG 06 2018**  
**RECEIVED**

## GAS CAPTURE PLAN

Date: 1/2/2018

☒ Original

Operator & OGRID No.: COG Operating LLC, OGRID 229137

☐ Amended - Reason for Amendment: \_\_\_\_\_

This Gas Capture Plan outlines actions to be taken by the Operator to reduce well/production facility flaring/venting for new completion (new drill, recomple to new zone, re-frac) activity.

*Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).*

### Well(s)/Production Facility – Name of facility

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location (ULSTR)	Footages	Expected MCF/D	Flared or Vented	Comments
Bonaid Federal Com 14H	30-025-	D-17-24S-35E	210' FNL & 1110' FWL	2,587 MMCFD		Gas will connect to CTB.

### Gathering System and Pipeline Notification

Well(s) will be connected to a production facility after flowback operations are complete, if gas transporter system is in place. The gas produced from production facility is dedicated to Versado, and will be connected to Eunice low/high pressure gathering system located in Lea County, New Mexico. It will require 0' to an undetermined amount of feet of pipeline to connect the facility to low/high pressure gathering system. COG Operating LLC provides (periodically) to Versado a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, COG Operating LLC and Versado have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at Eunice Processing Plant located in Sec 3 Twn, 22S Rng, 37 E, Lea County, New Mexico. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

### Flowback Strategy

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on Versado system at that time. Based on current information, it is COG Operating LLC's belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

### Alternatives to Reduce Flaring

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease
  - Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas – On lease
  - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
  - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines

**CONCHO**  
COG Operating LLC  
2208 West Main Street  
Artesia, NM 88210

# Well Site Layout

## Production Facility Layout

Bonaid Federal Com CTB  
Section 17- T24S- R35E

# Exhibit 3

Proposed  
Bonaid Federal Com 14H and 15H  
Wellpad

Proposed Road


### Legend

**O** = 750 BBL Steel Oil Tank  
**W** = 750 BBL Steel Water Tank  
**H** = 6' x 20' Heater  
**X** = Valve  
**SEP** = Separator  
**FWKO** = Fresh Water Knockout  
**HIT** = Heater  
**CP** = Control Panel

400'  
Topsoil will be stacked pile on the west side

### Production Equipment

2 Separators (SEP)  
2 Fresh Water Knockouts (FWKO)  
2 Heater Treaters (HIT)



400'

North