

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	CIMAREX ENERGY COMPANY
LEASE NO.:	NMNM0001917
WELL NAME & NO.:	4H- DOS EQUIS 11-14 FEDERAL COM
SURFACE HOLE FOOTAGE:	470'/N & 370'/W
BOTTOM HOLE FOOTAGE	330'/S & 360'/W
LOCATION:	Section.11.,T24S., R.32E., NMP
COUNTY:	LEA County, New Mexico

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP

A. Hydrogen Sulfide

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **1235** feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Operator shall filled 1/3rd casing with fluid while running intermediate casing to maintain collapse safety factor.

- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:

- Cement to surface. If cement does not circulate see B.1.a, c-d above.

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.

- 3. The minimum required fill of cement behind the 5-1/2 inch production casing is:

- Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

- 1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M) psi**.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties
 Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.
 During office hours call (575) 627-0272.
 After office hours call (575)

☒ Eddy County
 Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
 (575) 361-2822

☒ Lea County
 Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
 393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log (one log per well pad is acceptable) run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24

hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification

matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
 - c. The tests shall be done by an independent service company utilizing a test plug. The results of the test shall be reported to the appropriate BLM office.

- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

ZS 110118

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	CIMAREX ENERGY COMPANY
LEASE NO.:	NMNM0001917
WELL NAME & NO.:	4H- DOS EQUIS 11-14 FEDERAL COM
SURFACE HOLE FOOTAGE:	470'/N & 370'/W
BOTTOM HOLE FOOTAGE	330'/S & 360'/W
LOCATION:	Section.11.,T24S., R.32E., NMP
COUNTY:	LEA County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Below Ground-level Abandoned Well Marker
 - Hydrology
 - Range
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

Timing Limitation Exceptions:

The Carlsbad Field Office will publish an annual map of where the LPC timing and noise stipulations and conditions of approval (Limitations) will apply for the identified year (between March 1 and June 15) based on the latest survey information. The LPC Timing Area map will identify areas which are Habitat Areas (HA), Isolated Population Area (IPA), and Primary Population Area (PPA). The LPC Timing Area map will also have an area in red crosshatch. The red crosshatch area is the only area where an operator is required to submit a request for exception to the LPC Limitations. If an operator is operating outside the red crosshatch area, the LPC Limitations do not apply for that year and an exception to LPC Limitations is not required.

Hydrology

Tank Battery:

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

Surface Pipeline:

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect

pressure drops, situating valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Range

The operator must contact the allotment holder prior to construction to identify the location of the pipeline. The operator must take measures to protect the pipeline from compression or other damages. If the pipeline is damaged or compromised in any way near the proposed project as a result of oil and gas activity, the operator is responsible for repairing the pipeline immediately. The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

C. ELECTRIC LINES

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

Hydrogen Sulfide Drilling Operations Plan
Dos Equis11-14 Federal Com 4H
Cimarex Energy Co.
UL: D, Sec. 11, 24S, 32E
Lea Co., NM

1 All Company and Contract personnel admitted on location must be trained by a qualified H₂S safety instructor to the following:

- A. Characteristics of H₂S
- B. Physical effects and hazards
- C. Principal and operation of H₂S detectors, warning system and briefing areas.
- D. Evacuation procedure, routes and first aid.
- E. Proper use of safety equipment & life support systems
- F. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.

H₂S Detection and Alarm Systems:

- A. H₂S sensors/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud pits in the shale shaker area. Additional H₂S detectors may be placed as deemed necessary.
- B. An audio alarm system will be installed on the derrick floor and in the top doghouse.

3 Windsock and/or wind streamers:

- A. Windsock at mudpit area should be high enough to be visible.
- B. Windsock on the rig floor and / or top doghouse should be high enough to be visible.

4 Condition Flags and Signs

- A. Warning sign on access road to location.
- B. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H₂S present in dangerous concentration). Only H₂S trained and certified personnel admitted to location.

5 Well control equipment:

- A. See exhibit "E-1"

6 Communication:

- A. While working under masks chalkboards will be used for communication.
- B. Hand signals will be used where chalk board is inappropriate.
- C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.

7 Drillstem Testing:

No DSTs or cores are planned at this time.

8 Drilling contractor supervisor will be required to be familiar with the effects H₂S has on tubular goods and other mechanical equipment.

9 If H₂S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H₂S scavengers if necessary.

H₂S Contingency Plan
Dos Equis11-14 Federal Com 4H
Cimarex Energy Co.
UL: D, Sec. 11, 24S, 32E
Lea Co., NM

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must:

- « Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- « Evacuate any public places encompassed by the 100 ppm ROE.
- « Be equipped with H₂S monitors and air packs in order to control the release.
- « Use the "buddy system" to ensure no injuries occur during the 432-620-1975
- « Take precautions to avoid personal injury during this operation.
- « Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- « Have received training in the:
 - Detection of H₂S, and
 - Measures for protection against the gas,
 - Equipment used for protection and emergency response.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

Characteristics of H₂S and SO₂

Please see attached International Chemical Safety Cards.

Contacting Authorities

Cimarex Energy Co. of Colorado's personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Cimarex Energy Co. of Colorado's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

H₂S Contingency Plan Emergency Contacts
Dos Equis11-14 Federal Com 4H
Cimarex Energy Co.
UL: D, Sec. 11, 24S, 32E
Lea Co., NM

<u>Company Office</u>			
Cimarex Energy Co. of Colorado		800-969-4789	
Co. Office and After-Hours Menu			
<u>Key Personnel</u>			
<u>Name</u>	<u>Title</u>	<u>Office</u>	<u>Mobile</u>
Larry Seigrist	Drilling Manager	432-620-1934	580-243-8485
Charlie Pritchard	Drilling Superintendent	432-620-1975	432-238-7084
Roy Shirley	Construction Superintendent		432-634-2136
<u>Artesia</u>			
Ambulance		911	
State Police		575-746-2703	
City Police		575-746-2703	
Sheriff's Office		575-746-9888	
Fire Department		575-746-2701	
Local Emergency Planning Committee		575-746-2122	
New Mexico Oil Conservation Division		575-748-1283	
<u>Carlsbad</u>			
Ambulance		911	
State Police		575-885-3137	
City Police		575-885-2111	
Sheriff's Office		575-887-7551	
Fire Department		575-887-3798	
Local Emergency Planning Committee		575-887-6544	
US Bureau of Land Management		575-887-6544	
<u>Santa Fe</u>			
New Mexico Emergency Response Commission (Santa Fe)		505-476-9600	
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs		505-827-9126	
New Mexico State Emergency Operations Center		505-476-9635	
<u>National</u>			
National Emergency Response Center (Washington, D.C.)		800-424-8802	
<u>Medical</u>			
Flight for Life - 4000 24th St.; Lubbock, TX		806-743-9911	
Aerocare - R3, Box 49F; Lubbock, TX		806-747-8923	
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM		505-842-4433	
SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM		505-842-4949	
<u>Other</u>			
Boots & Coots IWC		800-256-9688	or 281-931-8884
Cudd Pressure Control		432-699-0139	or 432-563-3356
Halliburton		575-746-2757	
B.J. Services		575-746-3569	



**Cimarex Dos Equis 11-14 Federal Com 4H Rev0 RM 28Nov17 Proposal
Geodetic Report
(Non-Def Plan)**



Report Date:	November 28, 2017 - 11:08 AM	Survey / DLS Computation:	Minimum Curvature / Lubinski
Client:	Cimarex	Vertical Section Azimuth:	180.000 ° (Grid North)
Field:	NM Lea County (NAD 83)	Vertical Section Origin:	0.000 ft, 0.000 ft
Structure / Slot:	Cimarex Dos Equis 11-14 Federal Com 4H / Cimarex Dos Equis 11-14 Federal Com 4H	TVD Reference Datum:	RKB
Well:	Cimarex Dos Equis 11-14 Federal Com 4H	TVD Reference Elevation:	3656.000 ft above MSL
Borehole:	Original Borehole	Seabed / Ground Elevation:	3632.000 ft above MSL
UWI / API#:	Unknown / Unknown	Magnetic Declination:	6.860 °
Survey Name:	Cimarex Dos Equis 11-14 Federal Com 4H Rev0 RM 28Nov17	Total Gravity Field Strength:	998.4345mgn (9.80665 Based)
Survey Date:	November 22, 2017	Gravity Model:	GARM
Tort / AHD / DDI / ERD Ratio:	90.548 ° / 9774.899 ft / 6.222 / 0.906	Total Magnetic Field Strength:	48082.484 nT
Coordinate Reference System:	NAD83 New Mexico State Plane, Eastern Zone, US Feet	Magnetic Dip Angle:	59.978 °
Location Lat / Long:	N 32° 14' 17.19187", W 103° 39' 9.93077"	Declination Date:	November 28, 2017
Location Grid N/E Y/X:	N 451024.240 ftUS, E 751762.680 ftUS	Magnetic Declination Model:	HDGM 2017
CRS Grid Convergence Angle:	0.3631 °	North Reference:	Grid North
Grid Scale Factor:	0.9999598	Grid Convergence Used:	0.3631 °
Version / Patch:	2.10.565.0	Total Corr Mag North->Grid North:	6.4965 °
		Local Coord Referenced To:	Structure Reference Point

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [470' FNL, 370' FWL]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	N/A	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	100.00	0.00	170.07	100.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	200.00	0.00	170.07	200.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	300.00	0.00	170.07	300.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	400.00	0.00	170.07	400.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	500.00	0.00	170.07	500.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	600.00	0.00	170.07	600.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	700.00	0.00	170.07	700.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	800.00	0.00	170.07	800.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	900.00	0.00	170.07	900.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	1000.00	0.00	170.07	1000.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	1100.00	0.00	170.07	1100.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
Rustler	1185.00	0.00	170.07	1185.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	1200.00	0.00	170.07	1200.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	1300.00	0.00	170.07	1300.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	1400.00	0.00	170.07	1400.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
Salado (Top Salt)	1500.00	0.00	170.07	1500.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	1600.00	0.00	170.07	1600.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	1700.00	0.00	170.07	1700.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	1800.00	0.00	170.07	1800.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	1900.00	0.00	170.07	1900.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	2000.00	0.00	170.07	2000.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	2100.00	0.00	170.07	2100.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	2200.00	0.00	170.07	2200.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	
	2300.00	0.00	170.07	2300.00	0.00	0.00	0.00	0.00	451024.24	751762.68	N 32 14 17.19 W 103 39 9.93	


[illegible]

Comments	MD	Incl	Azim Gtd	TVD	VSEC	NS	EW	DLS	Northng	Easting	Latitude	Longitude
	(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft/100ft)	(ft)	(ft)	(N/S...°)	(E/W...°)
	12900.00	89.69	180.00	10755.12	2358.66	-2358.66	48.56	0.00	448665.67	751811.24	N 32° 13' 53.85"	W 103° 39' 9.54"
	13000.00	89.69	180.00	10755.66	2458.66	-2458.66	48.56	0.00	448665.68	751811.24	N 32° 13' 52.86"	W 103° 39' 9.55"
	13100.00	89.69	180.00	10756.19	2558.66	-2558.66	48.56	0.00	448665.69	751811.24	N 32° 13' 51.87"	W 103° 39' 9.56"
	13200.00	89.69	180.00	10756.73	2658.66	-2658.66	48.56	0.00	448665.70	751811.24	N 32° 13' 50.88"	W 103° 39' 9.57"
	13300.00	89.69	180.00	10757.27	2758.66	-2758.66	48.56	0.00	448665.71	751811.24	N 32° 13' 49.89"	W 103° 39' 9.58"
	13400.00	89.69	180.00	10757.81	2858.66	-2858.66	48.56	0.00	448665.72	751811.24	N 32° 13' 48.90"	W 103° 39' 9.59"
	13500.00	89.69	180.00	10758.35	2958.66	-2958.66	48.56	0.00	448665.73	751811.24	N 32° 13' 47.91"	W 103° 39' 9.60"
	13600.00	89.69	180.00	10758.88	3058.66	-3058.66	48.56	0.00	448665.74	751811.24	N 32° 13' 46.92"	W 103° 39' 9.61"
	13700.00	89.69	180.00	10759.42	3158.65	-3158.65	48.56	0.00	447765.75	751811.24	N 32° 13' 45.93"	W 103° 39' 9.62"
	13800.00	89.69	180.00	10759.96	3258.65	-3258.65	48.56	0.00	447765.76	751811.24	N 32° 13' 44.94"	W 103° 39' 9.63"
	13900.00	89.69	180.00	10760.50	3358.65	-3358.65	48.56	0.00	447765.77	751811.24	N 32° 13' 43.95"	W 103° 39' 9.64"
	14000.00	89.69	180.00	10761.04	3458.65	-3458.65	48.56	0.00	447765.78	751811.24	N 32° 13' 42.97"	W 103° 39' 9.65"
	14100.00	89.69	180.00	10761.57	3558.65	-3558.65	48.56	0.00	447765.79	751811.24	N 32° 13' 41.98"	W 103° 39' 9.66"
	14200.00	89.69	180.00	10762.11	3658.65	-3658.65	48.56	0.00	447765.80	751811.24	N 32° 13' 40.99"	W 103° 39' 9.67"
	14300.00	89.69	180.00	10762.65	3758.64	-3758.64	48.56	0.00	447765.81	751811.24	N 32° 13' 39.00"	W 103° 39' 9.68"
	14400.00	89.69	180.00	10763.19	3858.64	-3858.64	48.56	0.00	447765.82	751811.24	N 32° 13' 38.02"	W 103° 39' 9.69"
	14500.00	89.69	180.00	10763.73	3958.64	-3958.64	48.56	0.00	447765.83	751811.24	N 32° 13' 37.03"	W 103° 39' 9.70"
	14600.00	89.69	180.00	10764.26	4058.64	-4058.64	48.56	0.00	447765.84	751811.24	N 32° 13' 36.04"	W 103° 39' 9.71"
	14700.00	89.69	180.00	10764.80	4158.64	-4158.64	48.56	0.00	447765.85	751811.24	N 32° 13' 35.05"	W 103° 39' 9.72"
	14800.00	89.69	180.00	10765.34	4258.64	-4258.64	48.56	0.00	447765.86	751811.24	N 32° 13' 34.06"	W 103° 39' 9.73"
	14900.00	89.69	180.00	10765.88	4358.64	-4358.64	48.56	0.00	447765.87	751811.24	N 32° 13' 33.07"	W 103° 39' 9.74"
	15000.00	89.69	180.00	10766.42	4458.63	-4458.63	48.56	0.00	447765.88	751811.24	N 32° 13' 32.08"	W 103° 39' 9.75"
	15100.00	89.69	180.00	10766.95	4558.63	-4558.63	48.56	0.00	447765.89	751811.24	N 32° 13' 31.09"	W 103° 39' 9.76"
	15200.00	89.69	180.00	10767.49	4658.63	-4658.63	48.56	0.00	447765.90	751811.24	N 32° 13' 30.10"	W 103° 39' 9.77"
	15300.00	89.69	180.00	10768.03	4758.63	-4758.63	48.56	0.00	447765.91	751811.24	N 32° 13' 29.11"	W 103° 39' 9.78"
	15400.00	89.69	180.00	10768.57	4858.63	-4858.63	48.56	0.00	447765.92	751811.24	N 32° 13' 28.12"	W 103° 39' 9.79"
	15500.00	89.69	180.00	10769.11	4958.63	-4958.63	48.56	0.00	447765.93	751811.24	N 32° 13' 27.13"	W 103° 39' 9.80"
	15600.00	89.69	180.00	10769.64	5058.63	-5058.63	48.56	0.00	447765.94	751811.24	N 32° 13' 26.14"	W 103° 39' 9.81"
	15700.00	89.69	180.00	10770.18	5158.62	-5158.62	48.56	0.00	447765.95	751811.24	N 32° 13' 25.15"	W 103° 39' 9.82"
	15800.00	89.69	180.00	10770.72	5258.62	-5258.62	48.56	0.00	447765.96	751811.24	N 32° 13' 24.16"	W 103° 39' 9.83"
	15900.00	89.69	180.00	10771.26	5358.62	-5358.62	48.56	0.00	447765.97	751811.24	N 32° 13' 23.17"	W 103° 39' 9.84"
	16000.00	89.69	180.00	10771.80	5458.62	-5458.62	48.56	0.00	447765.98	751811.24	N 32° 13' 22.18"	W 103° 39' 9.85"
	16100.00	89.69	180.00	10772.33	5558.62	-5558.62	48.56	0.00	447765.99	751811.24	N 32° 13' 21.19"	W 103° 39' 9.86"
	16200.00	89.69	180.00	10772.87	5658.62	-5658.62	48.56	0.00	447766.00	751811.24	N 32° 13' 20.20"	W 103° 39' 9.87"
	16300.00	89.69	180.00	10773.41	5758.62	-5758.62	48.56	0.00	447766.01	751811.24	N 32° 13' 19.21"	W 103° 39' 9.88"
	16400.00	89.69	180.00	10773.95	5858.61	-5858.61	48.56	0.00	447766.02	751811.24	N 32° 13' 18.22"	W 103° 39' 9.89"
	16500.00	89.69	180.00	10774.49	5958.61	-5958.61	48.56	0.00	447766.03	751811.24	N 32° 13' 17.23"	W 103° 39' 9.90"
	16600.00	89.69	180.00	10775.02	6058.61	-6058.61	48.56	0.00	447766.04	751811.24	N 32° 13' 16.24"	W 103° 39' 9.91"
	16700.00	89.69	180.00	10775.56	6158.61	-6158.61	48.56	0.00	447766.05	751811.24	N 32° 13' 15.25"	W 103° 39' 9.92"
	16800.00	89.69	180.00	10776.10	6258.61	-6258.61	48.56	0.00	447766.06	751811.24	N 32° 13' 14.26"	W 103° 39' 9.93"
	16900.00	89.69	180.00	10776.64	6358.61	-6358.61	48.56	0.00	447766.07	751811.24	N 32° 13' 13.27"	W 103° 39' 9.94"
	17000.00	89.69	180.00	10777.18	6458.61	-6458.61	48.56	0.00	447766.08	751811.24	N 32° 13' 12.28"	W 103° 39' 9.95"
	17100.00	89.69	180.00	10777.71	6558.60	-6558.60	48.56	0.00	447766.09	751811.24	N 32° 13' 11.29"	W 103° 39' 9.96"
	17200.00	89.69	180.00	10778.25	6658.60	-6658.60	48.56	0.00	447766.10	751811.24	N 32° 13' 10.30"	W 103° 39' 9.97"
	17300.00	89.69	180.00	10778.79	6758.60	-6758.60	48.56	0.00	447766.11	751811.24	N 32° 13' 09.31"	W 103° 39' 9.98"
	17400.00	89.69	180.00	10779.33	6858.60	-6858.60	48.56	0.00	447766.12	751811.24	N 32° 13' 08.32"	W 103° 39' 9.99"
	17500.00	89.69	180.00	10779.87	6958.60	-6958.60	48.56	0.00	447766.13	751811.24	N 32° 13' 07.33"	W 103° 39' 10.00"
	17600.00	89.69	180.00	10780.40	7058.60	-7058.60	48.56	0.00	447766.14	751811.24	N 32° 13' 06.34"	W 103° 39' 10.01"
	17700.00	89.69	180.00	10780.94	7158.60	-7158.60	48.56	0.00	447766.15	751811.24	N 32° 13' 05.35"	W 103° 39' 10.02"
	17800.00	89.69	180.00	10781.48	7258.59	-7258.59	48.56	0.00	447766.16	751811.24	N 32° 13' 04.36"	W 103° 39' 10.03"
	17900.00	89.69	180.00	10782.02	7358.59	-7358.59	48.56	0.00	447766.17	751811.24	N 32° 13' 03.37"	W 103° 39' 10.04"
	18000.00	89.69	180.00	10782.56	7458.59	-7458.59	48.56	0.00	447766.18	751811.24	N 32° 13' 02.38"	W 103° 39' 10.05"
	18100.00	89.69	180.00	10783.09	7558.59	-7558.59	48.56	0.00	447766.19	751811.24	N 32° 13' 01.39"	W 103° 39' 10.06"
	18200.00	89.69	180.00	10783.63	7658.59	-7658.59	48.56	0.00	447766.20	751811.24	N 32° 13' 00.40"	W 103° 39' 10.07"
	18300.00	89.69	180.00	10784.17	7758.59	-7758.59	48.56	0.00	447766.21	751811.24	N 32° 12' 59.41"	W 103° 39' 10.08"
	18400.00	89.69	180.00	10784.71	7858.59	-7858.59	48.56	0.00	447766.22	751811.24	N 32° 12' 58.42"	W 103° 39' 10.09"
	18500.00	89.69	180.00	10785.25	7958.59	-7958.59	48.56	0.00	447766.23	751811.24	N 32° 12' 57.43"	W 103° 39' 10.10"
	18600.00	89.69	180.00	10785.78	8058.59	-8058.59	48.56	0.00	447766.24	751811.24	N 32° 12' 56.44"	W 103° 39' 10.11"
	18700.00	89.69	180.00	10786.32	8158.59	-8158.59	48.56	0.00	447766.25	751811.24	N 32° 12' 55.45"	W 103° 39' 10.12"

Survey Error Model: ISCVSA Rev 0 *** 3-D 95.000% Confidence 2.7955 sigma									
Survey Program:									
Survey Type: Non-Def Plan									
FSL, 360' FWL] - PBHL [330' Federal Com 4H Equis 11-14 Cimarrex Dos									
MD	Incl	Azim Ghd	TVD	VSEC	NS	EW	DLS	Northng	Eastng
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(ft)	(ft)
18800.00	89.69	180.00	10786.86	8258.58	-8258.58	48.56	0.00	442766.01	751811.24
18900.00	89.69	180.00	10787.40	8358.58	-8358.58	48.56	0.00	442666.01	751811.24
19000.00	89.69	180.00	10787.94	8458.58	-8458.58	48.56	0.00	442566.02	751811.24
19100.00	89.69	180.00	10788.47	8558.58	-8558.58	48.56	0.00	442466.03	751811.24
19200.00	89.69	180.00	10789.01	8658.57	-8658.57	48.56	0.00	442366.03	751811.24
19300.00	89.69	180.00	10789.55	8758.57	-8758.57	48.56	0.00	442266.04	751811.24
19400.00	89.69	180.00	10790.09	8858.57	-8858.57	48.56	0.00	442166.04	751811.24
19500.00	89.69	180.00	10790.63	8958.57	-8958.57	48.56	0.00	442066.05	751811.24
19600.00	89.69	180.00	10791.16	9058.57	-9058.57	48.56	0.00	441966.05	751811.24
19700.00	89.69	180.00	10791.70	9158.57	-9158.57	48.56	0.00	441866.06	751811.24
19800.00	89.69	180.00	10792.24	9258.57	-9258.57	48.56	0.00	441766.07	751811.24
19900.00	89.69	180.00	10792.78	9358.56	-9358.56	48.56	0.00	441666.07	751811.24
20000.00	89.69	180.00	10793.32	9458.56	-9458.56	48.56	0.00	441566.08	751811.24
20100.00	89.69	180.00	10793.85	9558.56	-9558.56	48.56	0.00	441466.08	751811.24
20200.00	89.69	180.00	10794.39	9658.56	-9658.56	48.56	0.00	441366.09	751811.24
20300.00	89.69	180.00	10794.93	9758.56	-9758.56	48.56	0.00	441266.09	751811.24
20312.98	89.69	180.00	10795.00	9771.54	-9771.54	48.56	0.00	441253.11	751811.24
Borehole / Survey									
Original Borehole / Cimarrex Dos Equis 11-14 Federal Com 4H Rev0 RM 28Nov17									
1	0.000	24.000	24.000	1/100.000	30.000	30.000		NAL_MWDP_PLUS_0.5_DEG- Depth Only	NAL_MWDP_PLUS_0.5_DEG
1	24.000	20312.985	1/100.000	30.000	30.000	30.000		NAL_MWDP_PLUS_0.5_DEG	Original Borehole / Cimarrex Dos Equis 11-14 Federal Com 4H

Borehole: Original Borehole	Well: Cimarex Dos Equis 11-14 Federal Com 4H	Field: NM Lea County (NAD 83)	Structure: Cimarex Dos Equis 11-14 Federal Com 4H
---------------------------------------	--	---	---

Gravity & Magnetic Parameters		Surface Location NAD83 New Mexico State Plane, Eastern Zone, US Feet		Miscellaneous	
Model: HDGM 2017	Dip: 59.978°	Date: 28-Nov-2017	Lat: N 32 14 17.19	Northing: 451024.24RUS	Grid Conv: 0.3631°
MagDec: 6.86°	FS: 48082.484mT	Gravity FS: 998.434mgal (0.80995 Based)	Lon: W 103 39 9.93	Easting: 751762.88RUS	Scale Fact: 0.9999598
				TVD Ref: RKB(3858ft above MSL)	
				Plan: Cimarex Dos Equis 11-14 Federal Com 4H Rev0 RM 28Nov17	



Critical Points

Critical Point	MD	INCL	AZIM	TVD	VSEC	N(+)/S(-)	E(+)/W(-)	DLS
SHL [470' FNL, 370' FWL]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
Rustler	1185.00	0.00	170.07	1185.00	0.00	0.00	0.00	0.00
Salado (Top Salt)	1500.00	0.00	170.07	1500.00	0.00	0.00	0.00	0.00
Base of Salt	4650.00	0.00	170.07	4650.00	0.00	0.00	0.00	0.00
Delaware Sands	4920.00	0.00	170.07	4920.00	0.00	0.00	0.00	0.00
Bone Spring	8750.00	0.00	170.07	8750.00	0.00	0.00	0.00	0.00
1st Bone Spring Sand	9885.00	0.00	170.07	9885.00	0.00	0.00	0.00	0.00
KOP - Build 12°/100' DLS	10264.56	0.00	170.07	10264.56	0.00	0.00	0.00	0.00
2nd Bone Spring Sand	10350.46	10.31	170.07	10350.00	7.59	-7.59	1.33	12.00
Build & Turn 12°/100' DLS	10639.56	45.00	170.07	10602.18	137.75	-137.75	24.12	12.00
Landing Point	11019.13	89.69	180.00	10745.00	477.82	-477.82	48.56	12.00
Cimarex Dos Equis 11-14 Federal Com 4H - PBHL [330' FSL, 360' FWL]	20312.98	89.69	180.00	10795.00	9771.54	-9771.54	48.56	0.00
3rd Bone Spring Carb	NaN			10825.00				



Cimarex Dos Equis 11-14 Federal Com 4H Rev0 RM 28Nov17 Anti-Collision Summary Report

Analysis Date-24hr Time: November 28, 2017 - 13:34

Client: Cimarex

Field: NM Lea County (NAD 83)

Structure: Cimarex Dos Equis 11-14 Federal Com 4H

Slot: Cimarex Dos Equis 11-14 Federal Com 4H

Well: Cimarex Dos Equis 11-14 Federal Com 4H

Borehole: Original Borehole

Scan MD Range: 0.00ft - 20312.98ft

Analysis Method:

3D Least Distance

Reference Trajectory:

Cimarex Dos Equis 11-14 Federal Com 4H Rev0 RM 28Nov17 (Non-Def Plan)

Depth Interval:

Every 10.00 Measured Depth (ft)

Rule Set:

NAL Procedure: D&M Anti-Collision Standard S002

Min Pts:

All local minima indicated.

Version / Patch:

2.10.565.0

Database \ Project:

US1153APP452.dir.slb.com/drilling-NM Lea County 2.10

Trajectory Error Model:

ISCWSA0 3-D 95.000% Confidence 2.7955 sigma, for subject well. For offset wells, error model version is specified with each well respectively.

Offset Selection Criteria

Wellhead distance scan:

Restricted within 61323.48 ft

Selection filters:

Definitive Surveys - Definitive Plans - Definitive surveys exclude definitive plans

- All Non-Def Surveys when no Def-Survey is set in a borehole - All Non-Def Plans when no Def-Plan is set in a borehole

Offset Trajectories Summary

Offset Trajectory	Separation			Allow	Sep.	Controlling	Reference Trajectory		Risk Level			Alert	Status
	CI-CI (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		

Results highlighted: Sep-Factor separation <= 1.50 ft

Cimarex Dos Equis 11-14
Federal Com 5H Rev0 RM
28Nov17 (Non-Def Plan)

1307.37	32.81	1304.87	1304.50	N/A	MAS = 10.00 (m)	0.00	0.00						Warning Alert
1307.30	32.81	1304.80	1304.49	230615.82	MAS = 10.00 (m)	10.00	10.00						Surface
1307.30	32.81	1304.80	1304.49	N/A	MAS = 10.00 (m)	24.00	24.00						MinPt-O-SF
1307.30	94.08	1333.14	1302.31	22.82	OSF1.50	9880.00	9880.00						WRP
999.91	97.53	933.75	902.38	15.88	OSF1.50	11120.00	10745.54						MinPts
999.92	302.72	796.97	697.20	4.00	OSF1.50	15810.00	10770.77	OSF<5.00					MinPt-CICt
999.99	554.97	628.87	445.02	2.71	OSF1.50	20312.98	10795.00						Enter Alert
													MinPts

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment: