

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

HOBBS OCD

JUL 15 2019

RECEIVED

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

F/F
(H)

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM137469
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator AMEREDEV OPERATING LLC (372224)		8. Lease Name and Well No. NANDINA FED COM 25 36 31 073H (322647)
3a. Address 5707 Southwest Parkway, Building 1, Suite 275 Austin TX	3b. Phone No. (include area code) (737)300-4700	9. API Well No. 70-025-46217 (97088)
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface LOT N / 230 FSL / 1735 FWL / LAT 32.0802 / LONG -103.30712 At proposed prod. zone LOT C / 50 FNL / 1980 FWL / LAT 32.1084804 / LONG -103.3063406		10. Field and Pool, or Exploratory WC-025 G-06 S263622F / BONE SPRING
11. Sec., T. R. M. or Blk. and Survey or Area SEC 31 / T25S / R36E / NMP		
14. Distance in miles and direction from nearest town or post office* 7 miles		12. County or Parish LEA
13. State NM		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 230 feet	16. No of acres in lease 600.28	17. Spacing Unit dedicated to this well 320
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 3426 feet	19. Proposed Depth 10150 feet / 20676 feet	20. BLM/BIA Bond No. in file FED: NMB001478
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3019 feet	22. Approximate date work will start* 07/01/2019	23. Estimated duration 90 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM. |

25. Signature (Electronic Submission)	Name (Printed/Typed) Christie Hanna / Ph: (737)300-4723	Date 05/09/2019
Title Senior Engineering Technician		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Christopher Walls / Ph: (575)234-2234	Date 07/10/2019
Title Petroleum Engineer		
Office CARLSBAD		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

ocp Rec 07/15/19

APPROVED WITH CONDITIONS

KZ
07/16/19

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM connects this information to an evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

1. SHL: LOT N / 230 FSL / 1735 FWL / TWSP: 25S / RANGE: 36E / SECTION: 31 / LAT: 32.0802 / LONG: -103.30712 (TVD: 0 feet, MD: 0 feet)
PPP: SESW / 100 FSL / 1980 FWL / TWSP: 25S / RANGE: 36E / SECTION: 31 / LAT: 32.07985 / LONG: -103.30633 (TVD: 10115 feet, MD: 10272 feet)
PPP: SESW / 0 FSL / 1932 FWL / TWSP: 25S / RANGE: 36E / SECTION: 30 / LAT: 32.09408 / LONG: -103.30633 (TVD: 10150 feet, MD: 15438 feet)
BHL: LOT C / 50 FNL / 1980 FWL / TWSP: 25S / RANGE: 36E / SECTION: 30 / LAT: 32.1084804 / LONG: -103.3063406 (TVD: 10150 feet, MD: 20676 feet)

BLM Point of Contact:

Name: Deborah Ham

Title: Legal Landlaw Examiner

Phone: 5752345965

Email: dham@blm.gov

Approval Date: 07/10/2019

(Form 3160-3, page 3)

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	AMERIDEV OPERATING LLC
LEASE NO.:	NMNM137469
WELL NAME & NO.:	073H – NANDINA FED COM 25 36 31
SURFACE HOLE FOOTAGE:	230'/S & 1735'/E
BOTTOM HOLE FOOTAGE:	50'/N & 1980'/E
LOCATION:	SECTION 31, T25S, R36E, NMPM
COUNTY:	LEA

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input checked="" type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

Primary Casing Design:

1. The 13-3/8 inch surface casing shall be set at approximately 1119 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of 8 hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours

after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

❖ **Special Capitan Reef requirements.** If lost circulation (50% or greater) occurs below the Base of the Salt, the operator shall do the following:

- Switch to fresh water mud to protect the Capitan Reef and use fresh water mud until setting the intermediate casing. The appropriate BLM office is to be notified for a PET to witness the switch to fresh water.
- Daily drilling reports from the Base of the Salt to the setting of the intermediate casing are to be submitted to the BLM CFO engineering staff via e-mail by 0800 hours each morning. Any lost circulation encountered is to be recorded on these drilling reports. The daily drilling report should show mud volume per shift/tour. Failure to submit these reports will result in an Incidence of Non-Compliance being issued for failure to comply with the Conditions of Approval. If not already planned, the operator shall run a caliper survey for the intermediate well bore and submit to the appropriate BLM office.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

2. The minimum required fill of cement behind the 9-5/8 inch 1st intermediate casing is:

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
- b. Second stage above DV tool:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office. **Excess calculates to 23% - additional cement might be required.**

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:

- Cement should tie-back at least 50 feet on top of Capitan Reef Top. Operator shall provide method of verification.

Alternate Casing Design:

2nd Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

3. The minimum required fill of cement behind the 7-5/8 inch 2nd intermediate casing is:

- Cement to surface. If cement does not circulate see B.1.a, c-d above.
Excess calculates to 14% - additional cement might be required.

In the case of lost circulation, operator has proposed to pump down 9 5/8" X 7 5/8" annulus. Operator must run a CBL from TD of the 7 5/8" casing to surface. Submit results to the BLM.

Pilot hole is required to have a plug at the bottom of the hole. If two plugs are set, the BLM is to be contacted (575-361-2822) prior to tag of bottom plug, which must be a minimum of 200' in length. Operator can set one plug from bottom of pilot hole to kick-off point and save the WOC time for tagging the first plug. Note plug tops on subsequent drilling report.

4. The minimum required fill of cement behind the 5-1/2 inch production casing is:

- Cement should tie-back at least 50 feet on top of Capitan Reef Top.
Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'

2.

Option 1:

Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 10,000 (10M) psi.

Option 2:

Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 10,000 (10M) psi.

- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

Variance approved to use a 5M annular. The annular must be tested to full working pressure (5000 psi.)

D. SPECIAL REQUIREMENT(S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties

Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.

During office hours call (575) 627-0272.

After office hours call (575)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,

(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)

393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log (one log per well pad is acceptable) run from TD to surface (horizontal well – vertical portion of hole) shall

be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.

7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.

- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug. The results of the test shall be reported to the appropriate BLM office.
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

NMK6242019

253631N APD Nandina Fed Com 35 36 31 073 30015 NMNM137469 Ameredev 12-55
05302019 NMK

Cap KFC

13 3/8	surface csg in a	17 1/2	inch hole.	Design Factors			SURFACE		
Segment	#/ft	Grade	Coupling	Body	Collapse	Burst	Length	Weight	
"A"	68.00	J 55	BUTT	14.06	3.9	0.75	1,119	76,092	
"B"							0	0	
w/8.4#/g mud, 30min Sfc Csg Test psig: 1,500				Tail Cmt	does not	clrc to sfc.	Totals:	1,119 76,092	
Comparison of Proposed to Minimum Required Cement Volumes									
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
17 1/2	0.6946	1482	2524	830	204	8.60	2529	3M	1.56
Burst Frac Gradient(s) for Segment(s) A, B = , b					All > 0.70, OK.				
					Alternate Burst = 1.36 > 0.70				

9 5/8	casing inside the	13 3/8	Design Factors				INTERMEDIATE		
Segment	#/ft	Grade	Coupling	Body	Collapse	Burst	Length	Weight	
"A"	40.00	HCL 80	BUTT	2.43	0.92	0.87	9,425	377,000	
"B"							0	0	
w/8.4#/g mud, 30min Sfc Csg Test psig:							Totals:	9,425	377,000
The cement volume(s) are intended to achieve a top of				0	ft from surface or a		1119	overlap.	
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
12 1/4	0.3132	look	0	2995		9.40	4358	5M	0.81
D V Tool(s):				4993		sum of sx	Σ CuFt	Σ% excess	
by stage % :		204	23						
Class 'H' tail cmt yld > 1.20									
Burst Frac Gradient(s) for Segment(s): A, B, C, D = 0.61, b, c, d									
<0.70 a Problem!!									
Alternate Burst = 1.32 > 1 & Alternate Collapse = 1.38 > 1.125									

Tail cmt								
5 1/2	casing inside the	9 5/8	Design Factors				PRODUCTION	
Segment	#/ft	Grade	Coupling	Body	Collapse	Burst	Length	Weight
"A"	20.00	HCP 110	BUTT	3.16	1.8	1.88	9,500	190,000
"B"	20.00	HCP 110	BUTT	8.20	1.56	1.88	11,176	223,520
w/8.4#/g mud, 30min Sfc Csg Test psig: 2,090						Totals:	20,676	413,520
The cement volume(s) are intended to achieve a top of				0	ft from surface or a		9425	overlap.
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE
8 1/2	0.2291	5082	6810	5040	35	12.50		1.23
Class 'H' tail cmt yld > 1.20								

0	5 1/2				<u>Design Factors</u>				
Segment	#/ft	Grade	Coupling	Joint	Collapse	Burst	Length	Weight	
"A"							0	0	
"B"							0	0	
w/8.4#/g mud, 30min Sfc Csg Test psig:							Totals:	0	0
Cmt vol calc below includes this csg, TOC intended					0	ft from surface or a		20676	overlap.
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
0			0	0					

Cap KFC

13 3/8	surface csg in a	17 1/2	inch hole.	Design Factors			SURFACE		
Segment	#/ft	Grade	Coupling	Body	Collapse	Burst	Length	Weight	
"A"	54.50	J 55	BUTT	8.29	1.15	0.91	1,888	102,896	
"B"							0	0	
w/8.4#/g mud, 30min Sfc Csg Test psig: 1,087			Tail Cmt	does not	circ to sfc.	Totals:	1,888	102,896	
Comparison of Proposed to Minimum Required Cement Volumes									
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
17 1/2	0.6946	1537	2621	1366	92	10.00	1892	2M	1.56
Burst Frac Gradient(s) for Segment(s) A, B = , b All > 0.70, OK.									

9 5/8 casing inside the 13 3/8				Design Factors			INTERMEDIATE		
Segment	#/ft	Grade	Coupling	Body	Collapse	Burst	Length	Weight	
"A"	40.00	HCL 80	BUTT	4.57	1.41	1.04	5,013	200,520	
"B"							0	0	
w/8.4#/g mud, 30min Sfc Csg Test psig:					Totals:		5,013	200,520	
The cement volume(s) are intended to achieve a top of					0	ft from surface or a		1888	overlap.
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
12 1/4	0.3132	look ↘	0	1682		11.50	3303	5M	0.81
D V Tool(s):				2506			sum of sx	Σ CuFt	Σ%excess
t by stage % :		193	74				1357	3882	131

7 5/8	casing inside the		9 5/8	Design Factors			INTERMEDIATE	
Segment	#/ft	Grade	Coupling	Joint	Collapse	Burst	Length	Weight
"A"	29.70	HCL 80	FJM	1.85	1.29	1.71	9,500	282,150
"B"	29.70	HCL 80	FJM	3.64	1.13	1.71	1,647	48,916
w/8.4#/g mud, 30min Sfc Csg Test psig: 2,090							Totals:	11,147
The cement volume(s) are intended to achieve a top of				0	ft from surface or a		5013	overlap.
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE
8 3/4	0.1005	683	1339	1172	14	10.50	4358	5M
Class 'H' tail cmt yld > 1.20								

Tail cmt									
5 1/2		casing inside the		7 5/8		Design Factors		PRODUCTION	
Segment	#/ft	Grade		Coupling	Joint	Collapse	Burst	Length	Weight
"A"	20.00	HCP 110		TMK UPSF	3.11	2.13	2.18	9,500	190,000
"B"	20.00	HCP 110		TMK UPSF	8.08	1.84	2.18	11,176	223,520
w/8.4#/g mud, 30min Sfc Csg Test psig: 2,090							Totals:	20,676	413,520
The cement volume(s) are intended to achieve a top of					0	ft from surface or a		11147	overlap.
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg
6 3/4	0.0835	1751	2346	1836	28	12.50			0.46
Class 'H' tail cmt yld > 1.20									

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

Environmental Assessment DOI-BLM- NM-P020-2018-0799-EA

**Ameredev Operating LLC
Nandina Fed Com 25 36 31 073H
Nandina Fed Com 25 36 31 083H
Nandina Fed Com 25 36 31 093H
Nandina Fed Com 25 36 31 103H
Nandina Fed Com 25 36 31 113H
Nandina Fed Com 25 36 31 123H**

Lease No. NMNM137469

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Ground-level Abandoned Well Marker
 - Hydrology
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Timing Limitation Exceptions:

The Carlsbad Field Office will publish an annual map of where the LPC timing and noise stipulations and conditions of approval (Limitations) will apply for the identified year (between March 1 and June 15) based on the latest survey information. The LPC Timing Area map will identify areas which are Habitat Areas (HA), Isolated Population Area (IPA), and Primary Population Area (PPA). The LPC Timing Area map will also have an area in red crosshatch. The red crosshatch area is the only area where an operator is required to submit a request for exception to the LPC Limitations. If an operator is operating outside the red crosshatch area, the LPC Limitations do not apply for that year and an exception to LPC Limitations is not required.

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

Hydrology:

The entire well pad(s) will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. The compacted berm shall be constructed at a minimum of 12 inches with impermeable mineral material (e.g. caliche). Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion. Stockpiling of topsoil is required. The top soil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control. If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

Pipelines

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to

the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.

6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.

7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:

- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
- Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
- The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)

8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be

segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

<input type="checkbox"/> seed mixture 1	<input type="checkbox"/> seed mixture 3
<input type="checkbox"/> seed mixture 2	<input type="checkbox"/> seed mixture 4
<input checked="" type="checkbox"/> seed mixture 2/LPC	<input type="checkbox"/> Aplomado Falcon Mixture

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches [that are not otherwise fenced, screened, or netted] to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

19. Special Stipulations:

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

Electric Lines

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.

5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the

Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture for LPC Sand/Shinnery Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

***Pounds of pure live seed:**

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

07/10/2019

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Christie Hanna

Signed on: 05/09/2019

Title: Senior Engineering Technician

Street Address: 5707 Southwest Parkway, Building 1, Suite 275

City: Austin

State: TX

Zip: 78735

Phone: (737)300-4723

Email address: channa@ameredev.com

Field Representative

Representative Name: ZACHARY BOYD

Street Address: 5707 SOUTHWEST PARKWAY, BLDG 1, STE. 275

City: AUSTIN

State: TX

Zip: 78735

Phone: (737)300-4700

Email address: zboyd@ameredev.com



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data Report

07/10/2019

APD ID: 10400041717

Submission Date: 05/09/2019

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - General

APD ID: 10400041717

Tie to previous NOS? 10400030258 Submission Date: 05/09/2019

BLM Office: CARLSBAD

User: Christie Hanna

Title: Senior Engineering Technician

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM137469

Lease Acres: 600.28

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? NO

Permitting Agent? NO

APD Operator: AMEREDEV OPERATING LLC

Operator letter of designation:

Operator Info

Operator Organization Name: AMEREDEV OPERATING LLC

Operator Address: 5707 Southwest Parkway, Building 1, Suite 275

Zip: 78735

Operator PO Box:

Operator City: Austin

State: TX

Operator Phone: (737)300-4700

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: WC-025 G-06
S263622F

Pool Name: BONE SPRING

Is the proposed well in an area containing other mineral resources? USEABLE WATER,NATURAL GAS,CO2,OIL

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Describe other minerals:

Is the proposed well in a Helium production area? N **Use Existing Well Pad?** NO **New surface disturbance?**

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: NAN **Number:** 3N

Well Class: HORIZONTAL

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 7 Miles

Distance to nearest well: 3426 FT

Distance to lease line: 230 FT

Reservoir well spacing assigned across Measurement: 320 Acres

Well plat: JEFF_20190509075811.pdf

NANDINA_FED_COM_25_36_31_073H___BLM_LEASE_MAP_20190509075822.pdf

NANDINA_FED_COM_25_36_31_073H___C_102_SIG_20190509075823.pdf

NANDINA_FED_COM_25_36_31_073H___VICINITY_MAP_20190509075825.pdf

NANDINA_FED_COM_25_36_31_073H___EXH_2AB_20190509075825.pdf

NANDINA_FED_COM_25_36_31_073H___GAS_CAPTURE_PLAN_20190509075835.pdf

Well work start Date: 07/01/2019

Duration: 90 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number: 18329

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	230	FSL	173 5	FWL	25S	36E	31	Lot N	32.0802	- 103.3071 2	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 137469	301 9	0	0


Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
KOP Leg #1	143	FNL	205 9	FWL	26S	36E	6	Aliquot NENW	32.07917	- 103.3060 8	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 137471	- 610 6	915 0	912 5
PPP Leg #1	100	FSL	198 0	FWL	25S	36E	31	Aliquot SESW	32.07985	- 103.3063 3	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 137469	- 709 6	102 72	101 15
PPP Leg #1	0	FSL	193 2	FWL	25S	36E	30	Aliquot SESW	32.09408	- 103.3063 3	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 127450	- 713 1	154 38	101 50
EXIT Leg #1	50	FNL	198 0	FWL	25S	36E	30	Aliquot NENW	32.10848	- 103.3063 4	LEA	NEW MEXI CO	NEW MEXI CO	F	FEE	- 713 1	206 76	101 50
BHL Leg #1	50	FNL	198 0	FWL	25S	36E	30	Lot C	32.10848 04	- 103.3063 406	LEA	NEW MEXI CO	NEW MEXI CO	F	FEE	- 713 1	206 76	101 50


Ameredev Operating, LLC
 Nandina Fed Com 25 36 31 073H
 Section 31, Township 25S, Range 36E
 Lea County, New Mexico



Nandina Fed Com 25 36 31 073H SHL: 25S 36E 230' FSL 1735' FWL
 Nandina Fed Com 25 36 31 083H SHL: 25S 36E 230' FSL 1695' FWL
 Nandina Fed Com 25 36 31 093H SHL: 25S 36E 230' FSL 1715' FWL
 Nandina Fed Com 25 36 31 103H SHL: 25S 36E 230' FSL 1635' FWL
 Nandina Fed Com 25 36 31 113H SHL: 25S 36E 230' FSL 1655' FWL
 Nandina Fed Com 25 36 31 123H SHL: 25S 36E 230' FSL 1675' FWL

Exhibit 3 – Well Site Diagram

LOCATION & ELEVATION VERIFICATION MAP



AMEREDEV

AMEREDEV OPERATING, LLC

LEASE NAME & WELL NO.: NANDINA FED COM 25 36 31 073H

SECTION 31 TWP 25-S RGE 36-E SURVEY N.M.P.M.
 COUNTY LEA STATE NM ELEVATION 3019'
 DESCRIPTION 230' FSL & 1735' FWL

LATITUDE N 32.0802073 LONGITUDE W 103.3071210



SCALE: 1" = 2000'
 0' 1000' 2000'

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY AMEREDEV OPERATING LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.


ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.



TOPOGRAPHIC
 LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
 2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
 TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
 WWW.TOPOGRAPHIC.COM

EXHIBIT 2 VICINITY MAP



AMEREDEV

AMEREDEV OPERATING, LLC

LEASE NAME & WELL NO.: NANDINA FED COM 25 36 31 073H

SECTION 31 TWP 25-S RGE 36-E SURVEY N.M.P.M.

COUNTY LEA STATE NM

DESCRIPTION 230' FSL & 1735' FWL

DISTANCE & DIRECTION

FROM INT. OF 3RD ST./NM-205/FRYING PAN RD. & NM-128, HEAD SOUTH ON 3RD ST./NM-205/FRYING PAN RD. \pm 5.6 MILES, THENCE WEST (RIGHT) ON ANTHONY RD. \pm 3.4 MILES, THENCE NORTH (RIGHT) TO CONTINUE ON ANTHONY RD. \pm 0.3 MILES, THENCE EAST (RIGHT) ON PIPELINE RD. \pm 0.3 MILES, THENCE NORTH (LEFT) ON A LEASE RD. \pm 1.0 MILES, THENCE WEST (LEFT) ON A LEASE RD. \pm 8112 FEET TO A POINT \pm 287 FEET SOUTHEAST OF THE LOCATION.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY AMEREDEV OPERATING LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.

SCALE: 1" = 10000'
0' 5000' 10000'



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY



1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 787-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

AMEREDEV


AMEREDEV OPERATING, LLC

EXHIBIT 2A

SECTION 31, TOWNSHIP 25-S, RANGE 36-E, N.M.P.M.
LEA COUNTY, NEW MEXICO



NANDINA FED COM 25 36 31 073H
NANDINA FED COM 25 36 31 093H
NANDINA FED COM 25 36 31 083H
NANDINA FED COM 25 36 31 123H
NANDINA FED COM 25 36 31 113H
NANDINA FED COM 25 36 31 103H




LEASE NAME & WELL NO.: NANDINA FED COM 25 36 31 073H

SECTION 31 TWP 25-S RGE 36-E SURVEY N.M.P.M.
COUNTY LEA STATE NM
DESCRIPTION 230' FSL & 1735' FWL

DISTANCE & DIRECTION
FROM INT. OF 3RD ST./NM-205/FRYING PAN RD. & NM-128, HEAD SOUTH ON
3RD ST./NM-205/FRYING PAN RD. ±5.6 MILES, THENCE WEST (RIGHT) ON
ANTHONY RD. ±3.4 MILES, THENCE NORTH (RIGHT) TO CONTINUE ON
ANTHONY RD. ±0.3 MILES, THENCE EAST (RIGHT) ON PIPELINE RD. ±0.3 MILES,
THENCE NORTH (LEFT) ON A LEASE RD. ±1.0 MILES, THENCE WEST (LEFT) ON
A LEASE RD. ±8112 FEET TO A POINT ±287 FEET SOUTHEAST OF THE
LOCATION.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID
BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM OF 1983, EAST
ZONE, U.S. SURVEY FEET

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND
UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF
SURVEY, AND DATA PROVIDED BY AMEREDEV OPERATING LLC THIS CERTIFICATION IS MADE AND
LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS
NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.




Michael Blake Brown, P.S. No. 18329
NOVEMBER 16, 2018

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX: (817) 744-7554
2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 862-1853 OR (800) 767-1853 • FAX: (432) 862-1743
WWW.TOPOGRAPHIC.COM

AMEREDEV

DETAIL VIEW
SCALE: 1" = 100'



S:\SURVEY\AMEREDEV OPERATING LLC\NANDINA FED COM\FINAL PRODUCTS\ILO NANDINA FED COM 25 38 31 073H REV1.DWG 11/20/2018 10:16:23 AM ccaaton



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

07/10/2019

APD ID: 10400041717

Submission Date: 05/09/2019

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	RUSTLER ANHYDRITE	3019	994	994	ANHYDRITE	NONE	No
2	SALADO	1584	1434	1434	SALT	NONE	No
3	TANSILL	-364	3382	3382	LIMESTONE	NONE	No
4	CAPITAN REEF	-747	3765	3765	LIMESTONE	USEABLE WATER	No
5	LAMAR	-2009	5027	5027	LIMESTONE	NONE	No
6	BELL CANYON	-2103	5121	5121	SANDSTONE	NATURAL GAS,OIL	No
7	BRUSHY CANYON	-4259	7277	7277	SANDSTONE	NATURAL GAS,OIL	No
8	BONE SPRING LIME	-5394	8412	8412	LIMESTONE	NONE	No
9	BONE SPRING 1ST	-6752	9770	9770	SANDSTONE	NATURAL GAS,OIL	Yes

Section 2 - Blowout Prevention

Pressure Rating (PSI): 10M

Rating Depth: 15000

Equipment: 10M BOPE SYSTEM WILL BE USED AFTER THE SURFACE CASING IS SET. A KELLY COCK WILL BE KEPT IN THE DRILL STRING AT ALL TIMES. A FULL OPENING DRILL PIPE STABBING VALVE WITH PROPER DRILL PIPE CONNECTIONS WILL BE ON THE RIG FLOOR AT ALL TIMES.

Requesting Variance? YES

Variance request: Co-Flex Choke Line, 5M Annular Preventer

Testing Procedure: See attachment

Choke Diagram Attachment:

10M_Choke_Manifold_REV_20190509080619.pdf

BOP Diagram Attachment:

5M_Annular_Preventer_Variance_and_Well_Control_Plan_20190509080629.pdf

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

10M_Choke_Manifold_REV_20190509080619.pdf

5M_BOP_System_20190509080630.pdf

Pressure_Control_Plan_Single_Well_MB4_3String_Big_Hole_BLM_20190509080630.pdf

4_String_MB_Ameredev_Wellhead_Drawing_net_REV_20190509080641.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	1119	0	1119	3019		1119	J-55	68	OTHER - BTC	8.2	0.75	DRY	12.02	DRY	14.06
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	9425	0	9425	3019		9425	HCL-80	40	OTHER - BTC	1.46	1.44	DRY	2.54	DRY	2.49
3	PRODUCTION	8.5	5.5	NEW	API	N	0	20676	0	10150	3019		20676	OTHER	20	OTHER - BTC	2.09	2.18	DRY	3.23	DRY	3.59

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

13.375_68.00_J55_BTC_20190509080728.pdf

Nandina_Fed_Com_25_36_31_073H_Wellbore_Diagram_and_CDA_20190509080737.pdf

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Casing Attachments

Casing ID: 2 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Nandina_Fed_Com_25_36_31_073H__Wellbore_Diagram_and_CDA_20190509080825.pdf

9.625_40_SeAH80HC_4100_Collapse_20190509080835.pdf

Casing ID: 3 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

5.5_20_P110HP_Eagle_SFH_20190509080921.pdf

Nandina_Fed_Com_25_36_31_073H__Wellbore_Diagram_and_CDA_20190509080929.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	733	510	1.76	13.5	897.0 1	50	CLASS C	Bentonite, Accelerator, Kolseal, Defoamer, Celloflake
SURFACE	Tail		733	1119	200	1.34	14.8	268	100	CLASS C	Salt
INTERMEDIATE	Lead	5077	0	4227	696	2.47	11.9	1719. 97	25	Class C	Salt, Bentonite, Kolseal, Defoamer, Celloflake, Anti-settling Expansion

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
											Additive
INTERMEDIATE	Tail		4227	5077	200	1.33	14.8	266	25	Class C	Retarder
INTERMEDIATE	Lead	5077	0	8169	1334	2.47	11.9	3293.9	25	Class H	Bentonite, Salt, Kolseal, Defoamer, Celloflake, Retarder, Anti-settling Expansion Additive
INTERMEDIATE	Tail		8169	9425	300	1.24	14.5	371.1	25	Class H	Salt, Bentonite, Retarder, Dispersant, Fluid Loss
PRODUCTION	Lead		0	20676	4415	1.34	14.2	5915.68	25	CLASS H	Salt, Bentonite, Fluid Loss, Dispersant, Retarder, Defoamer

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: All necessary supplies (e.g. bentonite, cedar bark) for fluid control will be on site.

Describe the mud monitoring system utilized: An electronic pit volume totalizer (PVT) will be utilized on the circulating system to monitor pit volume, flow rate, pump pressure, and pump rate.

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
9425	10150	OIL-BASED MUD	10.5	12.5							

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	1119	WATER-BASED MUD	8.4	8.6							
1119	9425	OTHER : Diesel Brine Emulsion	8.5	9.4							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

A directional survey, measurement while drilling and a mudlog/geologic lithology log will all be run from surface to TD.

List of open and cased hole logs run in the well:

DS,MWD,MUDLOG

Coring operation description for the well:

No coring will be done on this well.

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 5000

Anticipated Surface Pressure: 2767

Anticipated Bottom Hole Temperature(F): 160

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

H2S_Plan_20190509081355.pdf

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Nan073_DR_20190509081408.pdf

Nan073_LLR_20190509081408.pdf

5M_Annular_Preventer_Variance_and_Well_Control_Plan_20190509081421.pdf

Pressure_Control_Plan_Single_Well_MB4_3String_Big_Hole_BLM_20190509081422.pdf

Other proposed operations facets description:

4-STRING CONTINGENCY PLAN ATTACHED

Other proposed operations facets attachment:

CAPITAN_PROTECTION_CONTINGENCY_PLAN_20190509081431.pdf

Other Variance attachment:

R616__CoC_for_hoses_12_18_17_20190509081448.pdf

Requested_Exceptions__3_String_Revised_01312019_20190509081448.pdf

5M Annular Preventer Variance Request and Well Control Procedures

Note: A copy of the Well Control Plan must be available at multiple locations on the rig for review by rig personnel, as well as review by the BLM PET/PE, and a copy must be maintained on the rig floor.

Dual Isolation Design for 5M Annular Exception

Ameredev will utilize 13-5/8" 10M (5M Annular) BOPE System consisting of:

- 13-5/8" 5M Annular
- 13-5/8" 10M Upper Pipe Rams
 - 3-1/2" – 5-1/2" Variable Bore Ram
- 13-5/8" 10M Blind Rams
- 13-5/8" 10M Drilling Spool /w 2 - 4" 10M Outlets Double 10M Isolation Valves
- 13-5/8" 10M Lower Blind Rams
 - 3-1/2" – 5-1/2" Variable Bore Ram

All drilling components and casing associated to exposure > 5000 psi BHP requiring a 10M system will have a double isolation (secondary barrier) below the 5M Annular that would provide a barrier to flow. The mud system will always be primary barrier, it will be maintained by adjusting values based on tourly mud tests and monitoring a PVT System to maintain static wellbore conditions, displacement procedures will be followed and recorded on daily drilling reports during tripping operations. Surge and swab pressure values will be calculated and maintained and static flow check will be monitored at previous casing shoe and verified static well conditions prior to tripping out of hole and again prior to pulling last joint of drill pipe through BOPE. The below table, documents that two barriers to flow can be maintained at all times, independent of the rating of the annular preventer.

Drill Components	Size	Primary Barrier	Secondary Barrier	Third Barrier
Drillpipe	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
HWDP Drillpipe	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Drill Collars	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Production Casing	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Open Hole	13-5/8	Drilling Fluid	Blind Rams	
All Drilling Components in 10M Environment will have OD that will allow full Operational RATED WORKING PRESSURE for system design. Kill line with minimum 2" ID will be available outside substructure with 10M Check Valve for OOH Kill Operations				

Well Control Procedures

Proper well control procedures are dependent to differentiating well conditions, to cover the basic well control operations there are will be standard drilling ahead, tripping pipe, tripping BHA, running casing, and pipe out of the hole/open hole scenarios that will be defined by procedures below. Initial Shut In Pressure can be taken against the Uppermost BOPE component the 5M Annular, pressure control can be transferred from the lesser 5M Annular to the 10M Upper Pipe Rams if needed. Shut In Pressures may be equal to or less than the Rated Working Pressure but at no time will the pressure on the annular preventer exceed the Rated Working Pressure of the annular. The annular will be tested to 5,000 psi. This will be the Rated Working Pressure of the annular preventer. All scenarios will be written such as shut in will be performed by closing the 10,000 psi Upper Pipe Rams for faster Accumulator pressure recovery to allow safer reaction to controlling wellbore pressure.

Shutting In While Drilling

1. Sound alarm signaling well control event to Rig Crew
2. Space out drill string to allow FOSV installation
3. Shut down pumps
4. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
5. Install open, full open safety valve and close valve, Close Chokes
6. Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure

Shutting In While Tripping

1. Sound alarm signaling well control event to Rig Crew
2. Space out drill string to allow FOSV installation
3. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
4. Install open, full open safety valve and close valve, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

Shutting In While Running Casing

1. Sound alarm signaling well control event to Rig Crew
2. Space out casing to allow circulating swedge installation
3. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
4. Install circulating swedge, Close high pressure, low torque valves, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold Pre-job safety meeting and discuss kill procedure

Shutting In while out of hole

1. Sound alarm signaling well control event to Rig Crew
2. Shut-in well: close blind rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
3. Close Chokes, Verify well is shut-in and monitor pressures
4. Notify supervisory personnel
5. Record data (SIDP, SICP, Pit Gain, and Time)
6. Hold Pre-job safety meeting and discuss kill procedure

Shutting In prior to pulling BHA through stack

Prior to pulling last joint of drill pipe thru the stack space out and check flow
If flowing see steps below.

1. Sound alarm signaling well control event to Rig Crew
2. Shut in upper pipe ram and open HCR against Open Chokes and Valves Open
to working pressure gauge
3. Install open, full open safety valve and close valve, Close Chokes
4. Verify well is shut-in and flow has stopped
5. Notify supervisory personnel
6. Record data (SIDP, SICP, Pit Gain, and Time)
7. Hold pre-job safety meeting and discuss kill procedure

Shutting in while BHA is in the stack and ram preventer and combo immediately available

1. Sound alarm signaling well control event to Rig Crew
2. Space out BHA with upset just beneath the compatible pipe ram
3. Shut in upper compatible pipe ram and open HCR against Open Chokes and Valves Open to working pressure gauge
4. Install open, full open safety valve and close valve, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

*FOSV will be on rig floor in open position with operating handle for each type of connection utilized and tested to 10,000 psi

Shutting in while BHA is in the stack and no ram preventer or combo immediately available

1. Sound alarm signaling well control event to Rig Crew
2. If possible pick up high enough, to pull string clear and follow "Open Hole" scenario

If not possible to pick up high enough:

3. Stab Crossover, make up one joint/stand of drill pipe, and install open, full open safety valve (Leave Open)
4. Space out drill string with upset just beneath the compatible pipe ram.
5. Shut in upper compatible pipe ram and open HCR against Open Chokes and Valves Open to working pressure gauge
6. Close FOSV, Close Chokes, Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure


13 5/8" 5M BOP
Configuration

CO-FLEX LINE TO
CHOKE MANIFOLD

2" KILL LINE

4" 10M VALVES &

10M Check Valve




Pressure Control Plan

Pressure Control Equipment

- Following setting of 13-3/8" Surface Casing Ameredev will install 13-5/8 MB4 Multi Bowl Casing Head by welding on a 13-5/8 SOW x 13-5/8" 5M in combination with 13-5/8 5M x 13-5/8 10M B-Sec to Land Intm #1 and a 13-5/8 10M x 13-5/8 10M shouldered to land C-Sec to Land Intm #2 (Installation procedure witnessed and verified by a manufacturer's representative).
- Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Ameredev will install a 5M System Blowout Preventer (BOPE) with a 5M Annular Preventer and related equipment (BOPE). Full testing will be performed utilizing a full isolation test plug and limited to 5,000 psi MOP of MB4 Multi Bowl Casing Head. Pressure will be held for 10 min or until provisions of test are met on all valves and rams. The 5M Annular Preventer will be tested to 50% of approved working pressure (2,500 psi). Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Setting of 9-5/8" Intermediate will be done by landing a wellhead hanger in the 13-5/8" 5M Bowl, Cementing and setting Well Head Packing seals and testing same. (Installation procedure witnessed and verified by a manufacturer's representative) Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Full testing will be performed utilizing a full isolation test plug to 10,000 psi MOP of MB4 Multi Bowl B-Section. Pressure will be held for 10 min or until provisions of test are met on all valves and rams. The 5M Annular Preventer will be tested to 100% of approved working pressure (5,000 psi).
- Before drilling >20ft of new formation under the 9-5/8" Casing Shoe a pressure integrity test of the Casing Shoe will be performed to minimum of the MWE anticipated to control formation pressure to the next casing depth.
- Following setting of 5-1/2" Production Casing and adequate WOC time Ameredev will break 10M System Blowout Preventer (BOP) from 10M DOL-2 Casing Head, install annulus casing slips and test same (Installation procedure witnessed and verified by a manufacturer's representative) and install 11" 10M x 5-1/8" 15M Tubing Head (Installation procedure witnessed and verified by a manufacturer's representative). Ameredev will test head to 70% casing design and install Dry Hole cap with needle valve and pressure gauge to monitor well awaiting completion.

Pressure Control Plan

- Slow pump speeds will be taken daily by each crew and recorded on Daily Drilling Report after mudding up.
- A choke manifold and accumulator with floor and remote operating stations will be functional and in place after installation of BOPE, as well as full functioning mud gas separator.
- Weekly BOPE pit level drills will be conducted by each crew and recorded on Daily Drilling Report.
- BOP will be fully operated when out of hole and will be documented on the daily drilling log.
- All B.O.P.s and associated equipment will be tested in accordance with Onshore Order #2
- All B.O.P. testing will be done by an independent service company.
- The B.O.P. will be tested within 21 days of the original test if drilling takes more time than planned.
- Ameredev requests a variance to connect the B.O.P. choke outlet to the choke manifold using a co-flex hose with a 10,000 psi working pressure that has been tested to 15,000psi and is built to API Spec 16C. Once the flex line is installed it will be tied down with safety clamps. (certifications will be sent to Carlsbad BLM Office prior to install)
- Ameredev requests a variance to install a 5M Annular Preventer on the 10M System to drill the Production Hole below the 9-5/8" Intermediate Section. 5M Annular will be tested to 100% working pressure (5,000 psi). A full well control procedure will be included to isolate well bore.



Quotation

Downing Wellhead Equipment

Oklahoma City,
Oklahoma - USA

Reference Data:

16925 AMEREDEV

Proprietary and Confidential

The information contained in this drawing is the sole property of Downing Wellhead Equipment, any reproduction in part or in whole without the written permission of Downing Wellhead Equipment is prohibited.

TITLE:

AMEREDEV

DRAWN

CHECKED

APPROVED

SIZE

A

DWG. NO.

Scale:

Weight:

REV.

Sheet:

PERFORMANCE DATA

API BTC

13.375 in

68.00 lbs/ft

J-55

Technical Data Sheet

Tubular Parameters

Size	13.375	in	Minimum Yield	55,000	psi
Nominal Weight	68.00	lbs/ft	Minimum Tensile	75,000	psi
Grade	J-55		Yield Load	1,069,000	lbs
PE Weight	66.10	lbs/ft	Tensile Load	1,458,000	lbs
Wall Thickness	0.480	in	Min. Internal Yield Pressure	3,500	psi
Nominal ID	12.415	in	Collapse Pressure	1,950	psi
Drift Diameter	12.259	in			
Nom. Pipe Body Area	19.445	in ²			

Connection Parameters

Connection OD	14.375	in
Coupling Length	10.625	in
Threads Per Inch	5.000	in
Standoff Thread Turns	1.000	
Make-Up Loss	4.513	in
Yield Load In Tension	---	lbs
Min. Internal Yield Pressure	3,500	psi

Printed on: February-13-2015

NOTE:

The content of this Technical Data Sheet is for general information only and does not guarantee performance or imply fitness for a particular purpose, which only a competent drilling professional can determine considering the specific installation and operation parameters. Information that is printed or downloaded is no longer controlled by TMK IPSCO and might not be the latest information. Anyone using the information herein does so at their own risk. To verify that you have the latest TMK IPSCO technical information, please contact TMK IPSCO Technical Sales toll-free at 1-888-258-2000.



Wellbore Schematic

Well: Nandina Fed Com 25-36-31 073H
SHL: Sec. 31 25S-36E 230' FSL & 1735' FWL
BHL: Sec. 30 25S-36E 50' FNL & 1980' FWL
 Lea, NM

Wellhead: A - 13-5/8" 10M x 13-5/8" SOW
 B - 13-5/8" 10M x 13-5/8" 10M
 C - 13-5/8" 10M x 13-5/8" 10M
 Tubing Spool - 5-1/8" 15M x 13-3/8" 10M

Xmas Tree: 2-9/16" 10M

Tubing: 2-7/8" L-80 6.5# 8rd EUE

Co. Well ID: xxxxxx
AFE No.: xxxx-xxx
API No.: xxxxxxxxxxxx
GL: 3,019'
Field: Delaware
Objective: First Bone Spring
TVD: 10,150'
MD: 20,676'
Rig: TBD KB: 27'
E-Mail: Wellsite2@ameredev.com

Hole Size	Formation Tops	Logs Cement	Mud Weight
17.5"	Rustler 994'	710 Sacks TOC 0'	8.4-8.6 ppg WBM
	13.375" 68# J-55 BTC 1,119'		
12.25"	Salado 1,434'		
	Tansill 3,382'		
	Capitan Reef 3,765'		
	Lamar 5,027'	896 Sacks TOC 0'	50% Excess
	DV Tool 5,077'		
	Bell Canyon 5,121'		
	Brushy Canyon 7,277'		
	Bone Spring Lime 8,412'		
	9.625" 40# L-80HC BTC 9,425'	1,723 Sacks TOC 0'	50% Excess
8.5"	First Bone Spring 9,770'		
12° Build @ 9,425' MD thru 10,458' MD	5.5" 20# P-110CYHP BTC 20,676'	4,415 Sacks TOC 0'	25% Excess
	Target First Bone Spring 10150 TVD // 20676 MD		10.5 - 12.5 ppg OBM

Casing Design and Safety Factor Check

Casing Specifications						
Segment	Hole ID	Depth	OD	Weight	Grade	Coupling
Surface	17.5	1,119'	13.375	68	J-55	BTC
Intermediate	12.25	9,425'	9.625	40	HCL-80	BTC
Prod Segment A	8.5	9,425'	5.5	20	CYHP-110	BTC
Prod Segment B	8.5	20,676'	5.5	20	CYHP-110	BTC

Check Surface Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
14.375	1,069	915	4,100	3,450
Safety Factors				
1.56	14.06	12.02	8.20	0.75
Check Intermediate Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
7.625	940	558	6700	9460
Safety Factors				
2.31	2.49	2.54	1.46	1.44
Check Prod Casing, Segment A				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
Safety Factors				
1.36	3.59	3.23	2.09	2.18
Check Prod Casing, Segment B				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
Safety Factors				
1.36	50.23	45.19	1.94	2.18



U. S. Steel Tubular Products

5 1/2 20.00 lb (0.361) P110 HP

USS-EAGLE SFH™

	PIPE	CONNECTION	
MECHANICAL PROPERTIES			
Minimum Yield Strength	125,000	125,000	psi
Maximum Yield Strength	140,000	140,000	psi
Minimum Tensile Strength	130,000	130,000	psi
DIMENSIONS			
Outside Diameter	5.500	5.830	in.
Wall Thickness	0.361		in.
Inside Diameter	4.778	4.693	in.
Drift - API	4.653	4.653	in.
Nominal Linear Weight, T&C	19.83		lbs/ft
Plain End Weight	19.83	19.83	lbs/ft
SECTION AREA			
Cross Sectional Area Critical Area	5.828	5.054	sq. in.
Joint Efficiency		86.25	%
PERFORMANCE			
Minimum Collapse Pressure	13,150	13,150	psi
External Pressure Leak Resistance		10,000	psi
Minimum Internal Yield Pressure	14,360	14,360	psi
Minimum Pipe Body Yield Strength	729,000		lbs
Joint Strength		631,750	lbs
Compression Rating		631,750	lbs
Reference Length		21,240	ft
Maximum Uniaxial Bend Rating		89.9	deg/100 ft
Minimum Make-Up Torque		14,000	ft-lbs
Maximum Make-Up Torque		16,900	ft-lbs
Maximum Operating Torque		25,000	ft-lbs
Make-Up Loss		5.92	in.

Notes:

- 1) Other than proprietary collapse and connection values, performance properties have been calculated using standard equations defined by API 5C3 and do not incorporate any additional design or safety factors. Calculations assume nominal pipe OD, nominal wall thickness, and Specified Minimum Yield Strength (SMYS).
- 2) Compressive & Tensile Connection Efficiencies are calculated by dividing the connection critical area by the pipe body area.
- 3) Uniaxial bending rating shown is structural only, and equal to compression efficiency.
- 4) Torques have been calculated assuming a thread compound friction factor of 1.0 and are recommended only. Field make-up torques may require adjustment based on actual field conditions (e.g. make-up speed, temperature, thread compound, etc.).
- 5) Reference length is calculated by joint strength divided by plain end weight with 1.5 safety factor.
- 6) Connection external pressure resistance has been verified to 10,000 psi (Application specific testing).

Legal Notice: All material contained in this publication is for general information only. This material should not therefore be used or relied upon for any specific application without independent competent professional examination and verification of accuracy, suitability, and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.

Manuel USS Product Data Sheet 2017 rev25 (April)

Wellbore Schematic

Well: Nandina Fed Com 25-36-31 073H
SHL: Sec. 31 25S-36E 230' FSL & 1735' FWL
BHL: Sec. 30 25S-36E 50' FNL & 1980' FWL
 Lea, NM

Wellhead: A - 13-5/8" 10M x 13-5/8" SOW
 B - 13-5/8" 10M x 13-5/8" 10M
 C - 13-5/8" 10M x 13-5/8" 10M
 Tubing Spool - 5-1/8" 15M x 13-3/8" 10M

Xmas Tree: 2-9/16" 10M

Tubing: 2-7/8" L-80 6.5# 8rd EUE

Co. Well ID: xxxxxx
AFE No.: xxxx-xxx
API No.: xxxxxxxxxxxx
GL: 3,019'

Field: Delaware
Objective: First Bone Spring
TVD: 10,150'

MD: 20,676'

Rig: TBD **KB:** 27'

E-Mail: Wellsite2@ameredeve.com

Hole Size	Formation Tops	Logs Cement	Mud Weight
17.5"	Rustler 994'	710 Sacks TOC 0'	8.4-8.6 ppg WBM
	13.375" 68# J-55 BTC 1,119'		
12.25"	Salado 1,434'		
	Tansill 3,382'		
	Capitan Reef 3,765'		
	Lamar 5,027'	896 Sacks TOC 0'	50% Excess
	DV Tool 5,077'		
	Bell Canyon 5,121'		
	Brushy Canyon 7,277'		
	Bone Spring Lime 8,412'		
	9.625" 40# L-80HC BTC 9,425'	1,723 Sacks TOC 0'	50% Excess
8.5"	First Bone Spring 9,770'		
12° Build @ 9,425' MD thru 10,458' MD	5.5" 20# P-110CYHP BTC 20,676'	4,415 Sacks TOC 0'	25% Excess
	Target First Bone Spring 10150 TVD // 20676 MD		
			8.5 - 9.4 ppg Diesel Brine Emulsion
			10.5 - 12.5 ppg OBM

Casing Design and Safety Factor Check

Casing Specifications						
Segment	Hole ID	Depth	OD	Weight	Grade	Coupling
Surface	17.5	1,119'	13.375	68	J-55	BTC
Intermediate	12.25	9,425'	9.625	40	HCL-80	BTC
Prod Segment A	8.5	9,425'	5.5	20	CYHP-110	BTC
Prod Segment B	8.5	20,676'	5.5	20	CYHP-110	BTC

Check Surface Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
14.375	1,069	915	4,100	3,450
Safety Factors				
1.56	14.06	12.02	8.20	0.75
Check Intermediate Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
7.625	940	558	6700	9460
Safety Factors				
2.31	2.49	2.54	1.46	1.44
Check Prod Casing, Segment A				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
Safety Factors				
1.36	3.59	3.23	2.09	2.18
Check Prod Casing, Segment B				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
Safety Factors				
1.36	50.23	45.19	1.94	2.18

Wellbore Schematic

Well: Nandina Fed Com 25-36-31 073H
 SHL: Sec. 31 25S-36E 230' FSL & 1735' FWL
 BHL: Sec. 30 25S-36E 50' FNL & 1980' FWL
 Lea, NM
 Wellhead: A - 13-5/8" 10M x 13-5/8" SOW
 B - 13-5/8" 10M x 13-5/8" 10M
 C - 13-5/8" 10M x 13-5/8" 10M
 Tubing Spool - 5-1/8" 15M x 13-3/8" 10M
 Xmas Tree: 2-9/16" 10M
 Tubing: 2-7/8" L-80 6.5# 8rd EUE

Co. Well ID: xxxxxx
 AFE No.: xxxx-xxx
 API No.: xxxxxxxxxxxx
 GL: 3,019'
 Field: Delaware
 Objective: First Bone Spring
 TVD: 10,150'
 MD: 20,676'
 Rig: TBD KB: 27'
 E-Mail: Wellsite2@ameredev.com

Hole Size	Formation Tops	Logs Cement	Mud Weight
17.5"	Rustler 994'	710 Sacks TOC 0'	8.4-8.6 ppg WBM
	13.375" 68# J-55 BTC 1,119'		
12.25"	Salado 1,434'		
	Tansill 3,382'		
	Capitan Reef 3,765'		
	Lamar 5,027'	896 Sacks TOC 0'	50% Excess
	DV Tool 5,077'		
	Bell Canyon 5,121'		
	Brushy Canyon 7,277'		
	Bone Spring Lime 8,412'		
	9.625" 40# L-80HC BTC 9,425'	1,723 Sacks TOC 0'	50% Excess
8.5"	First Bone Spring 9,770'		
12° Build @ 9,425' MD thru 10,458' MD	5.5" 20# P-110CYHP BTC 20,676'	4,415 Sacks TOC 0'	25% Excess
	Target First Bone Spring 10150 TVD // 20676 MD		10.5 - 12.5 ppg OBM

Casing Design and Safety Factor Check

Casing Specifications						
Segment	Hole ID	Depth	OD	Weight	Grade	Coupling
Surface	17.5	1,119'	13.375	68	J-55	BTC
Intermediate	12.25	9,425'	9.625	40	HCL-80	BTC
Prod Segment A	8.5	9,425'	5.5	20	CYHP-110	BTC
Prod Segment B	8.5	20,676'	5.5	20	CYHP-110	BTC

Check Surface Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
14.375	1,069	915	4,100	3,450
Safety Factors				
1.56	14.06	12.02	8.20	0.75
Check Intermediate Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
7.625	940	558	6700	9460
Safety Factors				
2.31	2.49	2.54	1.46	1.44
Check Prod Casing, Segment A				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
Safety Factors				
1.36	3.59	3.23	2.09	2.18
Check Prod Casing, Segment B				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
Safety Factors				
1.36	50.23	45.19	1.94	2.18

SeAH

9.625"

40#

.395"

SEAH-80 HIGH COLLAPSE

(SEAH-80 IS A NON HEAT TREATED PRODUCT)

Dimensions (Nominal)

Outside Diameter	9.625	in.
Wall	0.395	in.
Inside Diameter	8.835	in.
Drift	8.750	in.
Weight, T&C	40.000	lbs./ft.
Weight, PE	38.970	lbs./ft.

Performance Properties

Collapse	4100	psi
Internal Yield Pressure at Minimum Yield		
PE	5750	psi
LTC	5750	psi
BTC	5750	psi
Yield Strength, Pipe Body	916	1000 lbs.
Joint Strength		
LTC	717	1000 lbs.
BTC	915	1000 lbs.

Note: SeAH Steel has produced this specification sheet for general information only. SeAH does not assume liability or responsibility for any loss or injury resulting from the use of information or data contained herein. All applications for the material described are at the customer's own risk and responsibility.

H₂S Drilling Operation Plan

1. All Company and Contract personnel admitted on location must be trained by a qualified H₂S safety instructor to the following:

- a. Characteristics of H₂S
- b. Physical effects and hazards
- c. Principal and operation of H₂S detectors, warning system and briefing areas
- d. Evacuation procedure, routes and first aid
- e. Proper use of safety equipment and life support systems
- f. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.

2. Briefing Area:

- a. Two perpendicular areas will be designated by signs and readily accessible.
- b. Upon location entry there will be a designated area to establish all safety compliance criteria (1.) has been met.

3. H₂S Detection and Alarm Systems:

- a. H₂S sensors/detectors shall be located on the drilling rig floor, in the base of the sub structure/cellar area, and on the mud pits in the shale shaker area. Additional H₂S detectors may be placed as deemed necessary. All detectors will be set to initiate visual alarm at 10 ppm and visual with audible at 14 ppm and all equipment will be calibrated every 30 days or as needed.
- b. An audio alarm will be installed on the derrick floor and in the top doghouse.

4. Protective Equipment for Essential Personnel:

- a. **Breathing Apparatus:**
 - i. Rescue Packs (SCBA) - 1 Unit shall be placed at each briefing area.
 - ii. Two (SCBA) Units will be stored in safety trailer on location.
 - iii. Work/Escapes packs - 1 Unit will be available on rig floor in doghouse for emergency evacuation for driller.
- b. **Auxiliary Rescue Equipment:**
 - i. Stretcher
 - ii. 2 - OSHA full body harnesses
 - iii. 100 ft. 5/8" OSHA approved rope
 - iv. 1 - 20# class ABC fire extinguisher

5. Windsock and/or Wind Streamers:

- a. Windsock at mud pit area should be high enough to be visible.
- b. Windsock on the rig floor should be high enough to be visible.

6. Communication:

- a. While working under mask scripting boards will be used for communication where applicable.
- b. Hand signals will be used when script boards are not applicable.

H₂S Drilling Operation Plan

- c. Two way radios will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at Drilling Foreman's Office.

7. Drill Stem Testing: - No Planned DST at this time.

8. Mud program:

- a. If H₂S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H₂S scavengers if necessary.

9. Metallurgy:

- a. All drill strings, casing, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H₂S service.
- b. Drilling Contractor supervisor will be required to be familiar with the effect H₂S has on tubular goods and other mechanical equipment provided through contractor.



H₂S Contingency Plan

Emergency Procedures

In the event of a release of H₂S, the first responder(s) must:

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE.
- Be equipped with H₂S monitors and air packs in order to control the release.
- Use the "buddy system" to ensure no injuries occur during the response.
- Take precautions to avoid personal injury during this operation.
- Contact Operator and/or local officials the aid in operation. See list of phone numbers attached.
- Have received training in the:
 - Detection of H₂S and
 - Measures for protection against the gas,
 - Equipment used for protection and emergency response.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H ₂ S	1.189 Air=1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO ₂	2.21 Air=1	2 ppm	N/A	1000 ppm

Contacting Authorities

Ameredev Operating LLC personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including direction to site. The following call list of essential and potential responders has been prepared for use during a release. Ameredev Operating LLC's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER)

H₂S Contingency Plan

Ameredev Operating LLC – Emergency Phone 737-300-4799			
Key Personnel:			
Name	Title	Office	Mobile
Floyd Hammond	Chief Operating officer	737-300-4724	512-783-6810
Zachary Boyd	Operations Superintendent	737-300-4725	432-385-6996
Blake Estrada	Construction Foreman		432-385-5831

<u>Artesia</u>			
Ambulance			911
State Police			575-746-2703
City Police			575-746-2703
Sheriff's Office			575-746-9888
Fire Department			575-746-2701
Local Emergency Planning Committee			575-746-2122
New Mexico Oil Conservation Division			575-748-1283
<u>Carlsbad</u>			
Ambulance			911
State Police			575-885-3137
City Police			575-885-2111
Sheriff's Office			575-887-7551
Fire Department			575-887-3798
Local Emergency Planning Committee			575-887-6544
US Bureau of Land Management			575-887-6544
<u>Santa Fe</u>			
New Mexico Emergency Response Commission (Santa Fe)			505-476-9600
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs			505-827-9126
New Mexico State Emergency Operations Center			505-476-9635
<u>National</u>			
National Emergency Response Center (Washington, D.C.)			800-424-8802
<u>Medical</u>			
Flight for Life - 4000 24th St.; Lubbock, TX			806-743-9911
Aerocare - R3, Box 49F; Lubbock, TX			806-747-8923
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM			505-842-4433
'SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM			505-842-4949

AMEREDEV

Ameredev Operating, LLC.

NAN/GB

NAN/GB #3N

Nandina 073H

Wellbore #1

Plan: Design #1

Standard Planning Report

25 April, 2019

Database:	EDM5000	Local Co-ordinate Reference:	Well Nandina 073H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3046.0usft
Project:	NAN/GB	MD Reference:	KB @ 3046.0usft
Site:	NAN/GB #3N	North Reference:	Grid
Well:	Nandina 073H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	NAN/GB		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site		NAN/GB #3N			
Site Position:		Northing:	394,428.42 usft	Latitude:	32° 4' 48.746 N
From:	Lat/Long	Easting:	859,181.30 usft	Longitude:	103° 18' 25.636 W
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.55 °

Well	Nandina 073H					
Well Position	+N/-S	0.0 usft	Northing:	394,428.42 usft	Latitude:	32° 4' 48.746 N
	+E/-W	0.0 usft	Easting:	859,181.30 usft	Longitude:	103° 18' 25.636 W
Position Uncertainty	0.0 usft	Wellhead Elevation:		Ground Level:	3,019.0 usft	

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2015	12/4/2018	6.66	59.95	47,732.43010736

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	0.80

Plan Survey Tool Program	Date 4/25/2019			
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks
1	0.0	20,676.0	Design #1 (Wellbore #1)	MWD
				OWSG MWD - Standard

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,300.0	6.00	139.00	2,299.5	-11.8	10.3	2.00	2.00	0.00	139.00	
6,724.8	6.00	139.00	6,700.0	-360.9	313.7	0.00	0.00	0.00	0.00	
7,024.8	0.00	0.00	6,999.5	-372.8	324.0	2.00	-2.00	0.00	180.00	
9,425.3	0.00	0.00	9,400.0	-372.8	324.0	0.00	0.00	0.00	0.00	
9,568.0	16.98	200.20	9,540.6	-392.4	316.8	11.90	11.90	0.00	200.20	
10,457.5	90.00	359.43	10,150.0	70.0	246.2	11.90	8.21	17.90	158.37	Nan073 FTP2
20,676.0	90.00	359.43	10,150.0	10,288.0	144.3	0.00	0.00	0.00	0.00	Nan073 BHL

Database:	EDM5000	Local Co-ordinate Reference:	Well Nandina 073H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3046.0usft
Project:	NAN/GB	MD Reference:	KB @ 3046.0usft
Site:	NAN/GB #3N	North Reference:	Grid
Well:	Nandina 073H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	2.00	139.00	2,100.0	-1.3	1.1	-1.3	2.00	2.00	0.00
2,200.0	4.00	139.00	2,199.8	-5.3	4.6	-5.2	2.00	2.00	0.00
2,300.0	6.00	139.00	2,299.5	-11.8	10.3	-11.7	2.00	2.00	0.00
2,400.0	6.00	139.00	2,398.9	-19.7	17.2	-19.5	0.00	0.00	0.00
2,500.0	6.00	139.00	2,498.4	-27.6	24.0	-27.3	0.00	0.00	0.00
2,600.0	6.00	139.00	2,597.8	-35.5	30.9	-35.1	0.00	0.00	0.00
2,700.0	6.00	139.00	2,697.3	-43.4	37.7	-42.9	0.00	0.00	0.00
2,800.0	6.00	139.00	2,796.7	-51.3	44.6	-50.7	0.00	0.00	0.00
2,900.0	6.00	139.00	2,896.2	-59.2	51.4	-58.5	0.00	0.00	0.00
3,000.0	6.00	139.00	2,995.6	-67.1	58.3	-66.2	0.00	0.00	0.00
3,100.0	6.00	139.00	3,095.1	-75.0	65.2	-74.0	0.00	0.00	0.00
3,200.0	6.00	139.00	3,194.5	-82.8	72.0	-81.8	0.00	0.00	0.00
3,300.0	6.00	139.00	3,294.0	-90.7	78.9	-89.6	0.00	0.00	0.00
3,400.0	6.00	139.00	3,393.4	-98.6	85.7	-97.4	0.00	0.00	0.00
3,500.0	6.00	139.00	3,492.9	-106.5	92.6	-105.2	0.00	0.00	0.00
3,600.0	6.00	139.00	3,592.3	-114.4	99.4	-113.0	0.00	0.00	0.00
3,700.0	6.00	139.00	3,691.8	-122.3	106.3	-120.8	0.00	0.00	0.00
3,800.0	6.00	139.00	3,791.2	-130.2	113.2	-128.6	0.00	0.00	0.00
3,900.0	6.00	139.00	3,890.7	-138.1	120.0	-136.4	0.00	0.00	0.00
4,000.0	6.00	139.00	3,990.1	-146.0	126.9	-144.2	0.00	0.00	0.00
4,100.0	6.00	139.00	4,089.6	-153.8	133.7	-152.0	0.00	0.00	0.00
4,200.0	6.00	139.00	4,189.0	-161.7	140.6	-159.7	0.00	0.00	0.00
4,300.0	6.00	139.00	4,288.5	-169.6	147.4	-167.5	0.00	0.00	0.00
4,400.0	6.00	139.00	4,387.9	-177.5	154.3	-175.3	0.00	0.00	0.00
4,500.0	6.00	139.00	4,487.4	-185.4	161.2	-183.1	0.00	0.00	0.00
4,600.0	6.00	139.00	4,586.9	-193.3	168.0	-190.9	0.00	0.00	0.00
4,700.0	6.00	139.00	4,686.3	-201.2	174.9	-198.7	0.00	0.00	0.00
4,800.0	6.00	139.00	4,785.8	-209.1	181.7	-206.5	0.00	0.00	0.00
4,900.0	6.00	139.00	4,885.2	-217.0	188.6	-214.3	0.00	0.00	0.00
5,000.0	6.00	139.00	4,984.7	-224.8	195.5	-222.1	0.00	0.00	0.00
5,100.0	6.00	139.00	5,084.1	-232.7	202.3	-229.9	0.00	0.00	0.00
5,200.0	6.00	139.00	5,183.6	-240.6	209.2	-237.7	0.00	0.00	0.00
5,300.0	6.00	139.00	5,283.0	-248.5	216.0	-245.5	0.00	0.00	0.00

Database: EDM5000
Company: Ameredev Operating, LLC.
Project: NAN/GB
Site: NAN/GB #3N
Well: Nandina 073H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Nandina 073H
TVD Reference: KB @ 3046.0usft
MD Reference: KB @ 3046.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,400.0	6.00	139.00	5,382.5	-256.4	222.9	-253.2	0.00	0.00	0.00
5,500.0	6.00	139.00	5,481.9	-264.3	229.7	-261.0	0.00	0.00	0.00
5,600.0	6.00	139.00	5,581.4	-272.2	236.6	-268.8	0.00	0.00	0.00
5,700.0	6.00	139.00	5,680.8	-280.1	243.5	-276.6	0.00	0.00	0.00
5,800.0	6.00	139.00	5,780.3	-288.0	250.3	-284.4	0.00	0.00	0.00
5,900.0	6.00	139.00	5,879.7	-295.8	257.2	-292.2	0.00	0.00	0.00
6,000.0	6.00	139.00	5,979.2	-303.7	264.0	-300.0	0.00	0.00	0.00
6,100.0	6.00	139.00	6,078.6	-311.6	270.9	-307.8	0.00	0.00	0.00
6,200.0	6.00	139.00	6,178.1	-319.5	277.7	-315.6	0.00	0.00	0.00
6,300.0	6.00	139.00	6,277.5	-327.4	284.6	-323.4	0.00	0.00	0.00
6,400.0	6.00	139.00	6,377.0	-335.3	291.5	-331.2	0.00	0.00	0.00
6,500.0	6.00	139.00	6,476.4	-343.2	298.3	-339.0	0.00	0.00	0.00
6,600.0	6.00	139.00	6,575.9	-351.1	305.2	-346.8	0.00	0.00	0.00
6,700.0	6.00	139.00	6,675.3	-359.0	312.0	-354.5	0.00	0.00	0.00
6,724.8	6.00	139.00	6,700.0	-360.9	313.7	-356.5	0.00	0.00	0.00
6,800.0	4.50	139.00	6,774.9	-366.1	318.2	-361.6	2.00	-2.00	0.00
6,900.0	2.50	139.00	6,874.7	-370.7	322.2	-366.1	2.00	-2.00	0.00
7,000.0	0.50	139.00	6,974.7	-372.7	324.0	-368.1	2.00	-2.00	0.00
7,024.8	0.00	0.00	6,999.5	-372.8	324.0	-368.2	2.00	-2.00	0.00
7,100.0	0.00	0.00	7,074.7	-372.8	324.0	-368.2	0.00	0.00	0.00
7,200.0	0.00	0.00	7,174.7	-372.8	324.0	-368.2	0.00	0.00	0.00
7,300.0	0.00	0.00	7,274.7	-372.8	324.0	-368.2	0.00	0.00	0.00
7,400.0	0.00	0.00	7,374.7	-372.8	324.0	-368.2	0.00	0.00	0.00
7,500.0	0.00	0.00	7,474.7	-372.8	324.0	-368.2	0.00	0.00	0.00
7,600.0	0.00	0.00	7,574.7	-372.8	324.0	-368.2	0.00	0.00	0.00
7,700.0	0.00	0.00	7,674.7	-372.8	324.0	-368.2	0.00	0.00	0.00
7,800.0	0.00	0.00	7,774.7	-372.8	324.0	-368.2	0.00	0.00	0.00
7,900.0	0.00	0.00	7,874.7	-372.8	324.0	-368.2	0.00	0.00	0.00
8,000.0	0.00	0.00	7,974.7	-372.8	324.0	-368.2	0.00	0.00	0.00
8,100.0	0.00	0.00	8,074.7	-372.8	324.0	-368.2	0.00	0.00	0.00
8,200.0	0.00	0.00	8,174.7	-372.8	324.0	-368.2	0.00	0.00	0.00
8,300.0	0.00	0.00	8,274.7	-372.8	324.0	-368.2	0.00	0.00	0.00
8,400.0	0.00	0.00	8,374.7	-372.8	324.0	-368.2	0.00	0.00	0.00
8,500.0	0.00	0.00	8,474.7	-372.8	324.0	-368.2	0.00	0.00	0.00
8,600.0	0.00	0.00	8,574.7	-372.8	324.0	-368.2	0.00	0.00	0.00
8,700.0	0.00	0.00	8,674.7	-372.8	324.0	-368.2	0.00	0.00	0.00
8,800.0	0.00	0.00	8,774.7	-372.8	324.0	-368.2	0.00	0.00	0.00
8,900.0	0.00	0.00	8,874.7	-372.8	324.0	-368.2	0.00	0.00	0.00
9,000.0	0.00	0.00	8,974.7	-372.8	324.0	-368.2	0.00	0.00	0.00
9,100.0	0.00	0.00	9,074.7	-372.8	324.0	-368.2	0.00	0.00	0.00
9,150.3	0.00	0.00	9,125.0	-372.8	324.0	-368.2	0.00	0.00	0.00
Nan073 KOP: Sec 06 148 FNL & 2053 FWL									
9,200.0	0.00	0.00	9,174.7	-372.8	324.0	-368.2	0.00	0.00	0.00
9,300.0	0.00	0.00	9,274.7	-372.8	324.0	-368.2	0.00	0.00	0.00
9,400.0	0.00	0.00	9,374.7	-372.8	324.0	-368.2	0.00	0.00	0.00
9,425.3	0.00	0.00	9,400.0	-372.8	324.0	-368.2	0.00	0.00	0.00
Nan073 KOP									
9,500.0	8.89	200.20	9,474.4	-378.2	322.0	-373.6	11.90	11.90	0.00
9,568.0	16.98	200.20	9,540.6	-392.4	316.8	-388.0	11.90	11.90	0.00
9,600.0	13.51	206.22	9,571.5	-400.2	313.5	-395.8	11.90	-10.84	18.80
9,700.0	6.18	268.18	9,670.1	-410.9	302.9	-406.6	11.90	-7.33	61.96
9,800.0	13.27	332.09	9,768.9	-400.9	292.1	-396.7	11.90	7.09	63.92
9,900.0	24.41	345.63	9,863.4	-370.6	281.6	-366.6	11.90	11.14	13.53

Database:	EDM5000	Local Co-ordinate Reference:	Well Nandina 073H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3046.0usft
Project:	NAN/GB	MD Reference:	KB @ 3046.0usft
Site:	NAN/GB #3N	North Reference:	Grid
Well:	Nandina 073H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
10,000.0	36.03	350.87	9,949.7	-321.4	271.8	-317.5	11.90	11.61	5.24
10,100.0	47.77	353.79	10,024.0	-255.3	263.1	-251.6	11.90	11.74	2.92
10,200.0	59.56	355.78	10,083.1	-175.2	255.9	-171.6	11.90	11.79	1.99
10,271.7	68.03	356.93	10,114.8	-111.0	251.8	-107.5	11.90	11.81	1.60
Nan073 FTP									
10,300.0	71.37	357.34	10,124.6	-84.6	250.5	-81.0	11.90	11.82	1.46
10,400.0	83.20	358.69	10,146.6	12.8	247.1	16.2	11.90	11.83	1.35
10,457.5	90.00	359.43	10,150.0	70.0	246.2	73.4	11.90	11.83	1.29
Nan073 FTP2									
10,500.0	90.00	359.43	10,150.0	112.5	245.8	116.0	0.00	0.00	0.00
10,600.0	90.00	359.43	10,150.0	212.5	244.8	215.9	0.00	0.00	0.00
10,700.0	90.00	359.43	10,150.0	312.5	243.8	315.9	0.00	0.00	0.00
10,800.0	90.00	359.43	10,150.0	412.5	242.8	415.9	0.00	0.00	0.00
10,900.0	90.00	359.43	10,150.0	512.5	241.8	515.8	0.00	0.00	0.00
11,000.0	90.00	359.43	10,150.0	612.5	240.8	615.8	0.00	0.00	0.00
11,100.0	90.00	359.43	10,150.0	712.5	239.8	715.8	0.00	0.00	0.00
11,200.0	90.00	359.43	10,150.0	812.5	238.8	815.8	0.00	0.00	0.00
11,300.0	90.00	359.43	10,150.0	912.5	237.8	915.7	0.00	0.00	0.00
11,400.0	90.00	359.43	10,150.0	1,012.5	236.8	1,015.7	0.00	0.00	0.00
11,500.0	90.00	359.43	10,150.0	1,112.5	235.8	1,115.7	0.00	0.00	0.00
11,600.0	90.00	359.43	10,150.0	1,212.5	234.8	1,215.6	0.00	0.00	0.00
11,700.0	90.00	359.43	10,150.0	1,312.5	233.8	1,315.6	0.00	0.00	0.00
11,800.0	90.00	359.43	10,150.0	1,412.5	232.8	1,415.6	0.00	0.00	0.00
11,900.0	90.00	359.43	10,150.0	1,512.5	231.8	1,515.6	0.00	0.00	0.00
12,000.0	90.00	359.43	10,150.0	1,612.4	230.8	1,615.5	0.00	0.00	0.00
12,100.0	90.00	359.43	10,150.0	1,712.4	229.8	1,715.5	0.00	0.00	0.00
12,200.0	90.00	359.43	10,150.0	1,812.4	228.8	1,815.5	0.00	0.00	0.00
12,300.0	90.00	359.43	10,150.0	1,912.4	227.8	1,915.4	0.00	0.00	0.00
12,400.0	90.00	359.43	10,150.0	2,012.4	226.8	2,015.4	0.00	0.00	0.00
12,500.0	90.00	359.43	10,150.0	2,112.4	225.8	2,115.4	0.00	0.00	0.00
12,600.0	90.00	359.43	10,150.0	2,212.4	224.8	2,215.4	0.00	0.00	0.00
12,700.0	90.00	359.43	10,150.0	2,312.4	223.8	2,315.3	0.00	0.00	0.00
12,800.0	90.00	359.43	10,150.0	2,412.4	222.8	2,415.3	0.00	0.00	0.00
12,900.0	90.00	359.43	10,150.0	2,512.4	221.8	2,515.3	0.00	0.00	0.00
13,000.0	90.00	359.43	10,150.0	2,612.4	220.8	2,615.2	0.00	0.00	0.00
13,100.0	90.00	359.43	10,150.0	2,712.4	219.8	2,715.2	0.00	0.00	0.00
13,200.0	90.00	359.43	10,150.0	2,812.4	218.8	2,815.2	0.00	0.00	0.00
13,300.0	90.00	359.43	10,150.0	2,912.4	217.8	2,915.1	0.00	0.00	0.00
13,400.0	90.00	359.43	10,150.0	3,012.4	216.8	3,015.1	0.00	0.00	0.00
13,500.0	90.00	359.43	10,150.0	3,112.4	215.8	3,115.1	0.00	0.00	0.00
13,600.0	90.00	359.43	10,150.0	3,212.4	214.8	3,215.1	0.00	0.00	0.00
13,700.0	90.00	359.43	10,150.0	3,312.4	213.8	3,315.0	0.00	0.00	0.00
13,800.0	90.00	359.43	10,150.0	3,412.4	212.8	3,415.0	0.00	0.00	0.00
13,900.0	90.00	359.43	10,150.0	3,512.4	211.8	3,515.0	0.00	0.00	0.00
14,000.0	90.00	359.43	10,150.0	3,612.3	210.8	3,614.9	0.00	0.00	0.00
14,100.0	90.00	359.43	10,150.0	3,712.3	209.8	3,714.9	0.00	0.00	0.00
14,200.0	90.00	359.43	10,150.0	3,812.3	208.8	3,814.9	0.00	0.00	0.00
14,300.0	90.00	359.43	10,150.0	3,912.3	207.9	3,914.9	0.00	0.00	0.00
14,400.0	90.00	359.43	10,150.0	4,012.3	206.9	4,014.8	0.00	0.00	0.00
14,500.0	90.00	359.43	10,150.0	4,112.3	205.9	4,114.8	0.00	0.00	0.00
14,600.0	90.00	359.43	10,150.0	4,212.3	204.9	4,214.8	0.00	0.00	0.00
14,700.0	90.00	359.43	10,150.0	4,312.3	203.9	4,314.7	0.00	0.00	0.00
14,800.0	90.00	359.43	10,150.0	4,412.3	202.9	4,414.7	0.00	0.00	0.00
14,900.0	90.00	359.43	10,150.0	4,512.3	201.9	4,514.7	0.00	0.00	0.00

Database:	EDM5000	Local Co-ordinate Reference:	Well Nandina 073H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3046.0usft
Project:	NAN/GB	MD Reference:	KB @ 3046.0usft
Site:	NAN/GB #3N	North Reference:	Grid
Well:	Nandina 073H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
15,000.0	90.00	359.43	10,150.0	4,612.3	200.9	4,614.7	0.00	0.00	0.00
15,100.0	90.00	359.43	10,150.0	4,712.3	199.9	4,714.6	0.00	0.00	0.00
15,200.0	90.00	359.43	10,150.0	4,812.3	198.9	4,814.6	0.00	0.00	0.00
15,300.0	90.00	359.43	10,150.0	4,912.3	197.9	4,914.6	0.00	0.00	0.00
15,400.0	90.00	359.43	10,150.0	5,012.3	196.9	5,014.5	0.00	0.00	0.00
15,437.7	90.00	359.43	10,150.0	5,050.0	196.5	5,052.2	0.00	0.00	0.00
Nan073 into NMNM127450									
15,500.0	90.00	359.43	10,150.0	5,112.3	195.9	5,114.5	0.00	0.00	0.00
15,600.0	90.00	359.43	10,150.0	5,212.3	194.9	5,214.5	0.00	0.00	0.00
15,700.0	90.00	359.43	10,150.0	5,312.3	193.9	5,314.5	0.00	0.00	0.00
15,800.0	90.00	359.43	10,150.0	5,412.3	192.9	5,414.4	0.00	0.00	0.00
15,900.0	90.00	359.43	10,150.0	5,512.3	191.9	5,514.4	0.00	0.00	0.00
16,000.0	90.00	359.43	10,150.0	5,612.2	190.9	5,614.4	0.00	0.00	0.00
16,100.0	90.00	359.43	10,150.0	5,712.2	189.9	5,714.3	0.00	0.00	0.00
16,200.0	90.00	359.43	10,150.0	5,812.2	188.9	5,814.3	0.00	0.00	0.00
16,300.0	90.00	359.43	10,150.0	5,912.2	187.9	5,914.3	0.00	0.00	0.00
16,400.0	90.00	359.43	10,150.0	6,012.2	186.9	6,014.3	0.00	0.00	0.00
16,500.0	90.00	359.43	10,150.0	6,112.2	185.9	6,114.2	0.00	0.00	0.00
16,600.0	90.00	359.43	10,150.0	6,212.2	184.9	6,214.2	0.00	0.00	0.00
16,700.0	90.00	359.43	10,150.0	6,312.2	183.9	6,314.2	0.00	0.00	0.00
16,800.0	90.00	359.43	10,150.0	6,412.2	182.9	6,414.1	0.00	0.00	0.00
16,900.0	90.00	359.43	10,150.0	6,512.2	181.9	6,514.1	0.00	0.00	0.00
17,000.0	90.00	359.43	10,150.0	6,612.2	180.9	6,614.1	0.00	0.00	0.00
17,100.0	90.00	359.43	10,150.0	6,712.2	179.9	6,714.1	0.00	0.00	0.00
17,200.0	90.00	359.43	10,150.0	6,812.2	178.9	6,814.0	0.00	0.00	0.00
17,300.0	90.00	359.43	10,150.0	6,912.2	177.9	6,914.0	0.00	0.00	0.00
17,400.0	90.00	359.43	10,150.0	7,012.2	176.9	7,014.0	0.00	0.00	0.00
17,500.0	90.00	359.43	10,150.0	7,112.2	175.9	7,113.9	0.00	0.00	0.00
17,600.0	90.00	359.43	10,150.0	7,212.2	174.9	7,213.9	0.00	0.00	0.00
17,700.0	90.00	359.43	10,150.0	7,312.2	173.9	7,313.9	0.00	0.00	0.00
17,800.0	90.00	359.43	10,150.0	7,412.2	172.9	7,413.9	0.00	0.00	0.00
17,900.0	90.00	359.43	10,150.0	7,512.2	171.9	7,513.8	0.00	0.00	0.00
18,000.0	90.00	359.43	10,150.0	7,612.1	170.9	7,613.8	0.00	0.00	0.00
18,100.0	90.00	359.43	10,150.0	7,712.1	169.9	7,713.8	0.00	0.00	0.00
18,200.0	90.00	359.43	10,150.0	7,812.1	169.0	7,813.7	0.00	0.00	0.00
18,300.0	90.00	359.43	10,150.0	7,912.1	168.0	7,913.7	0.00	0.00	0.00
18,400.0	90.00	359.43	10,150.0	8,012.1	167.0	8,013.7	0.00	0.00	0.00
18,500.0	90.00	359.43	10,150.0	8,112.1	166.0	8,113.7	0.00	0.00	0.00
18,600.0	90.00	359.43	10,150.0	8,212.1	165.0	8,213.6	0.00	0.00	0.00
18,700.0	90.00	359.43	10,150.0	8,312.1	164.0	8,313.6	0.00	0.00	0.00
18,800.0	90.00	359.43	10,150.0	8,412.1	163.0	8,413.6	0.00	0.00	0.00
18,900.0	90.00	359.43	10,150.0	8,512.1	162.0	8,513.5	0.00	0.00	0.00
19,000.0	90.00	359.43	10,150.0	8,612.1	161.0	8,613.5	0.00	0.00	0.00
19,100.0	90.00	359.43	10,150.0	8,712.1	160.0	8,713.5	0.00	0.00	0.00
19,200.0	90.00	359.43	10,150.0	8,812.1	159.0	8,813.5	0.00	0.00	0.00
19,300.0	90.00	359.43	10,150.0	8,912.1	158.0	8,913.4	0.00	0.00	0.00
19,400.0	90.00	359.43	10,150.0	9,012.1	157.0	9,013.4	0.00	0.00	0.00
19,500.0	90.00	359.43	10,150.0	9,112.1	156.0	9,113.4	0.00	0.00	0.00
19,600.0	90.00	359.43	10,150.0	9,212.1	155.0	9,213.3	0.00	0.00	0.00
19,700.0	90.00	359.43	10,150.0	9,312.1	154.0	9,313.3	0.00	0.00	0.00
19,800.0	90.00	359.43	10,150.0	9,412.1	153.0	9,413.3	0.00	0.00	0.00
19,900.0	90.00	359.43	10,150.0	9,512.1	152.0	9,513.2	0.00	0.00	0.00
20,000.0	90.00	359.43	10,150.0	9,612.0	151.0	9,613.2	0.00	0.00	0.00
20,100.0	90.00	359.43	10,150.0	9,712.0	150.0	9,713.2	0.00	0.00	0.00

Database: EDM5000
Company: Ameredev Operating, LLC.
Project: NAN/GB
Site: NAN/GB #3N
Well: Nandina 073H
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well Nandina 073H
TVD Reference: KB @ 3046.0usft
MD Reference: KB @ 3046.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
20,200.0	90.00	359.43	10,150.0	9,812.0	149.0	9,813.2	0.00	0.00	0.00
20,300.0	90.00	359.43	10,150.0	9,912.0	148.0	9,913.1	0.00	0.00	0.00
20,400.0	90.00	359.43	10,150.0	10,012.0	147.0	10,013.1	0.00	0.00	0.00
20,500.0	90.00	359.43	10,150.0	10,112.0	146.0	10,113.1	0.00	0.00	0.00
20,600.0	90.00	359.43	10,150.0	10,212.0	145.0	10,213.0	0.00	0.00	0.00
Nan073 LTP									
20,676.0	90.00	359.43	10,150.0	10,288.0	144.3	10,289.0	0.00	0.00	0.00
Nan073 BHL									

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Nan073 KOP - plan hits target center - Point	0.00	0.00	9,400.0	-372.8	324.0	394,055.66	859,505.33	32° 4' 45.027 N	103° 18' 21.911 W
Nan073 FTP2 - plan hits target center - Point	0.00	0.00	10,150.0	70.0	246.2	394,498.42	859,427.48	32° 4' 49.416 N	103° 18' 22.767 W
Nan073 LTP - plan misses target center by 26.0usft at 20600.0usft MD (10150.0 TVD, 10212.0 N, 145.0 E) - Point	0.00	0.00	10,150.0	10,238.0	144.2	404,666.46	859,325.53	32° 6' 30.035 N	103° 18' 22.826 W
Nan073 BHL - plan misses target center by 0.5usft at 20676.0usft MD (10150.0 TVD, 10288.0 N, 144.3 E) - Point	0.00	0.00	10,150.0	10,288.0	143.8	404,716.45	859,325.06	32° 6' 30.529 N	103° 18' 22.826 W
Nan073 FTP - plan misses target center by 39.3usft at 10271.7usft MD (10114.8 TVD, -111.0 N, 251.8 E) - Point	0.00	0.00	10,150.0	-127.5	246.2	394,300.91	859,427.48	32° 4' 47.461 N	103° 18' 22.789 W

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates +N/-S (usft)	+E/-W (usft)	Comment
15,437.7	10,150.0	5,050.0	196.5	Nan073 into NMNM127450



AMEREDEV

Ameredev Operating, LLC.

NAN/GB

NAN/GB #3N

Nandina 073H

Wellbore #1

Plan: Design #1

Lease Penetration Section Line Foot

25 April, 2019

Company:	Ameredev Operating, LLC.	Local Co-ordinate Reference:	Well Nandina 073H
Project:	NAN/GB	TVD Reference:	KB @ 3046.0usft
Site:	NAN/GB #3N	MD Reference:	KB @ 3046.0usft
Well:	Nandina 073H	North Reference:	Grid
Wellbore:	Wellbore #1	Survey Calculation Method:	Minimum Curvature
Design:	Design #1	Database:	EDM5000

Project	NAN/GB		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	NAN/GB #3N		
Site Position:		Northing:	394,428.42 usft
From:	Lat/Long	Easting:	859,181.30 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16"
		Latitude:	32° 4' 48.746 N
		Longitude:	103° 18' 25.636 W
		Grid Convergence:	0.55 °

Well	Nandina 073H		
Well Position	+N/-S	0.0 usft	Northing:
	+E/-W	0.0 usft	Easting:
Position Uncertainty	0.0 usft	Wellhead Elevation:	usft
		Latitude:	32° 4' 48.746 N
		Longitude:	103° 18' 25.636 W
		Ground Level:	3,019.0 usft

Wellbore	Wellbore #1		
Magnetics	Model Name	Sample Date	Declination
			(°)
	IGRF2015	12/4/2018	6.66
			Dip Angle
			(°)
			59.95
			Field Strength
			(nT)
			47,732.43010736

Design	Design #1		
Audit Notes:			
Version:	Phase:	PROTOTYPE	Tie On Depth:
			0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W
	(usft)	(usft)	(usft)
	0.0	0.0	0.0
			Direction
			(°)
			0.80

Survey Tool Program	Date 4/25/2019		
From	To	Survey (Wellbore)	Tool Name
(usft)	(usft)		
0.0	20,676.0	Design #1 (Wellbore #1)	MWD
			Description
			OWSG MWD - Standard

Planned Survey							
MD	Inc	Azi (azimuth)	TVD	+FSL/-FNL	+FWL/-FEL	Latitude	Longitude
(usft)	(°)	(°)	(usft)	(usft)	(usft)		
0.0	0.00	0.00	0.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
100.0	0.00	0.00	100.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
200.0	0.00	0.00	200.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
300.0	0.00	0.00	300.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
400.0	0.00	0.00	400.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
500.0	0.00	0.00	500.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
600.0	0.00	0.00	600.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
700.0	0.00	0.00	700.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
800.0	0.00	0.00	800.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
900.0	0.00	0.00	900.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
1,000.0	0.00	0.00	1,000.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
1,100.0	0.00	0.00	1,100.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W

Company: Ameredev Operating, LLC.
 Project: NAN/GB
 Site: NAN/GB #3N
 Well: Nandina 073H
 Wellbore: Wellbore #1
 Design: Design #1

Local Co-ordinate Reference: Well Nandina 073H
 TVD Reference: KB @ 3046.0usft
 MD Reference: KB @ 3046.0usft
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	Latitude	Longitude
1,200.0	0.00	0.00	1,200.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
1,300.0	0.00	0.00	1,300.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
1,400.0	0.00	0.00	1,400.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
1,500.0	0.00	0.00	1,500.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
1,600.0	0.00	0.00	1,600.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
1,700.0	0.00	0.00	1,700.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
1,800.0	0.00	0.00	1,800.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
1,900.0	0.00	0.00	1,900.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
2,000.0	0.00	0.00	2,000.0	230.0	1,735.0	32° 4' 48.746 N	103° 18' 25.636 W
2,100.0	2.00	139.00	2,100.0	228.7	1,736.1	32° 4' 48.733 N	103° 18' 25.622 W
2,200.0	4.00	139.00	2,199.8	224.7	1,739.6	32° 4' 48.694 N	103° 18' 25.583 W
2,300.0	6.00	139.00	2,299.5	218.2	1,745.3	32° 4' 48.628 N	103° 18' 25.517 W
2,400.0	6.00	139.00	2,398.9	210.3	1,752.2	32° 4' 48.549 N	103° 18' 25.438 W
2,500.0	6.00	139.00	2,498.4	202.4	1,759.0	32° 4' 48.471 N	103° 18' 25.360 W
2,600.0	6.00	139.00	2,597.8	194.5	1,765.9	32° 4' 48.392 N	103° 18' 25.281 W
2,700.0	6.00	139.00	2,697.3	186.6	1,772.7	32° 4' 48.313 N	103° 18' 25.202 W
2,800.0	6.00	139.00	2,796.7	178.7	1,779.6	32° 4' 48.235 N	103° 18' 25.123 W
2,900.0	6.00	139.00	2,896.2	170.8	1,786.4	32° 4' 48.156 N	103° 18' 25.044 W
3,000.0	6.00	139.00	2,995.6	162.9	1,793.3	32° 4' 48.077 N	103° 18' 24.965 W
3,100.0	6.00	139.00	3,095.1	155.0	1,800.2	32° 4' 47.998 N	103° 18' 24.887 W
3,200.0	6.00	139.00	3,194.5	147.2	1,807.0	32° 4' 47.920 N	103° 18' 24.808 W
3,300.0	6.00	139.00	3,294.0	139.3	1,813.9	32° 4' 47.841 N	103° 18' 24.729 W
3,400.0	6.00	139.00	3,393.4	131.4	1,820.7	32° 4' 47.762 N	103° 18' 24.650 W
3,500.0	6.00	139.00	3,492.9	123.5	1,827.6	32° 4' 47.684 N	103° 18' 24.571 W
3,600.0	6.00	139.00	3,592.3	115.6	1,834.4	32° 4' 47.605 N	103° 18' 24.493 W
3,700.0	6.00	139.00	3,691.8	107.7	1,841.3	32° 4' 47.526 N	103° 18' 24.414 W
3,800.0	6.00	139.00	3,791.2	99.8	1,848.2	32° 4' 47.448 N	103° 18' 24.335 W
3,900.0	6.00	139.00	3,890.7	91.9	1,855.0	32° 4' 47.369 N	103° 18' 24.256 W
4,000.0	6.00	139.00	3,990.1	84.0	1,861.9	32° 4' 47.290 N	103° 18' 24.177 W
4,100.0	6.00	139.00	4,089.6	76.2	1,868.7	32° 4' 47.211 N	103° 18' 24.098 W
4,200.0	6.00	139.00	4,189.0	68.3	1,875.6	32° 4' 47.133 N	103° 18' 24.020 W
4,300.0	6.00	139.00	4,288.5	60.4	1,882.4	32° 4' 47.054 N	103° 18' 23.941 W
4,400.0	6.00	139.00	4,387.9	52.5	1,889.3	32° 4' 46.975 N	103° 18' 23.862 W
4,500.0	6.00	139.00	4,487.4	44.6	1,896.2	32° 4' 46.897 N	103° 18' 23.783 W
4,600.0	6.00	139.00	4,586.9	36.7	1,903.0	32° 4' 46.818 N	103° 18' 23.704 W
4,700.0	6.00	139.00	4,686.3	28.8	1,909.9	32° 4' 46.739 N	103° 18' 23.625 W
4,800.0	6.00	139.00	4,785.8	20.9	1,916.7	32° 4' 46.661 N	103° 18' 23.547 W
4,900.0	6.00	139.00	4,885.2	13.0	1,923.6	32° 4' 46.582 N	103° 18' 23.468 W
5,000.0	6.00	139.00	4,984.7	5.2	1,930.5	32° 4' 46.503 N	103° 18' 23.389 W
5,100.0	6.00	139.00	5,084.1	-2.7	1,937.3	32° 4' 46.424 N	103° 18' 23.310 W
5,200.0	6.00	139.00	5,183.6	-10.6	1,944.2	32° 4' 46.346 N	103° 18' 23.231 W
5,300.0	6.00	139.00	5,283.0	-18.5	1,951.0	32° 4' 46.267 N	103° 18' 23.153 W
5,400.0	6.00	139.00	5,382.5	-26.4	1,957.9	32° 4' 46.188 N	103° 18' 23.074 W
5,500.0	6.00	139.00	5,481.9	-34.3	1,964.7	32° 4' 46.110 N	103° 18' 22.995 W

Company: Ameredev Operating, LLC.
 Project: NAN/GB
 Site: NAN/GB #3N
 Well: Nandina 073H
 Wellbore: Wellbore #1
 Design: Design #1

Local Co-ordinate Reference: Well Nandina 073H
 TVD Reference: KB @ 3046.0usft
 MD Reference: KB @ 3046.0usft
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/FNL (usft)	+FWL/FEL (usft)	Latitude	Longitude
5,600.0	6.00	139.00	5,581.4	-42.2	1,971.6	32° 4' 46.031 N	103° 18' 22.916 W
5,700.0	6.00	139.00	5,680.8	-50.1	1,978.5	32° 4' 45.952 N	103° 18' 22.837 W
5,800.0	6.00	139.00	5,780.3	-58.0	1,985.3	32° 4' 45.873 N	103° 18' 22.758 W
5,900.0	6.00	139.00	5,879.7	-65.8	1,992.2	32° 4' 45.795 N	103° 18' 22.680 W
6,000.0	6.00	139.00	5,979.2	-73.7	1,999.0	32° 4' 45.716 N	103° 18' 22.601 W
6,100.0	6.00	139.00	6,078.6	-81.6	2,005.9	32° 4' 45.637 N	103° 18' 22.522 W
6,200.0	6.00	139.00	6,178.1	-89.5	2,012.7	32° 4' 45.559 N	103° 18' 22.443 W
6,300.0	6.00	139.00	6,277.5	-97.4	2,019.6	32° 4' 45.480 N	103° 18' 22.364 W
6,400.0	6.00	139.00	6,377.0	-105.3	2,026.5	32° 4' 45.401 N	103° 18' 22.285 W
6,500.0	6.00	139.00	6,476.4	-113.2	2,033.3	32° 4' 45.323 N	103° 18' 22.207 W
6,600.0	6.00	139.00	6,575.9	-121.1	2,040.2	32° 4' 45.244 N	103° 18' 22.128 W
6,700.0	6.00	139.00	6,675.3	-129.0	2,047.0	32° 4' 45.165 N	103° 18' 22.049 W
6,724.8	6.00	139.00	6,700.0	-130.9	2,048.7	32° 4' 45.146 N	103° 18' 22.029 W
6,800.0	4.50	139.00	6,774.9	-136.1	2,053.2	32° 4' 45.094 N	103° 18' 21.978 W
6,900.0	2.50	139.00	6,874.7	-140.7	2,057.2	32° 4' 45.048 N	103° 18' 21.932 W
7,000.0	0.50	139.00	6,974.7	-142.7	2,059.0	32° 4' 45.028 N	103° 18' 21.912 W
7,024.8	0.00	0.00	6,999.5	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
7,100.0	0.00	0.00	7,074.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
7,200.0	0.00	0.00	7,174.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
7,300.0	0.00	0.00	7,274.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
7,400.0	0.00	0.00	7,374.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
7,500.0	0.00	0.00	7,474.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
7,600.0	0.00	0.00	7,574.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
7,700.0	0.00	0.00	7,674.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
7,800.0	0.00	0.00	7,774.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
7,900.0	0.00	0.00	7,874.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
8,000.0	0.00	0.00	7,974.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
8,100.0	0.00	0.00	8,074.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
8,200.0	0.00	0.00	8,174.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
8,300.0	0.00	0.00	8,274.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
8,400.0	0.00	0.00	8,374.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
8,500.0	0.00	0.00	8,474.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
8,600.0	0.00	0.00	8,574.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
8,700.0	0.00	0.00	8,674.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
8,800.0	0.00	0.00	8,774.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
8,900.0	0.00	0.00	8,874.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
9,000.0	0.00	0.00	8,974.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
9,100.0	0.00	0.00	9,074.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
9,150.3	0.00	0.00	9,125.0	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
Nan073 KOP: Sec 06 148 FNL & 2053 FWL							
9,200.0	0.00	0.00	9,174.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
9,300.0	0.00	0.00	9,274.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
9,400.0	0.00	0.00	9,374.7	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
9,425.3	0.00	0.00	9,400.0	-142.8	2,059.0	32° 4' 45.027 N	103° 18' 21.911 W
Nan073 KOP							

Company: Ameredev Operating, LLC.
 Project: NAN/GB
 Site: NAN/GB #3N
 Well: Nandina 073H
 Wellbore: Wellbore #1
 Design: Design #1

Local Co-ordinate Reference: Well Nandina 073H
 TVD Reference: KB @ 3046.0usft
 MD Reference: KB @ 3046.0usft
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/FNL (usft)	+FWL/FEL (usft)	Latitude	Longitude
9,500.0	8.89	200.20	9,474.4	-148.2	2,057.0	32° 4' 44.974 N	103° 18' 21.935 W
9,568.0	16.98	200.20	9,540.6	-162.4	2,051.8	32° 4' 44.833 N	103° 18' 21.997 W
9,600.0	13.51	206.22	9,571.5	-170.2	2,048.5	32° 4' 44.757 N	103° 18' 22.036 W
9,700.0	6.18	268.18	9,670.1	-180.9	2,037.9	32° 4' 44.652 N	103° 18' 22.160 W
9,800.0	13.27	332.09	9,768.9	-170.9	2,027.1	32° 4' 44.752 N	103° 18' 22.285 W
9,900.0	24.41	345.63	9,863.4	-140.6	2,016.6	32° 4' 45.053 N	103° 18' 22.404 W
10,000.0	36.03	350.87	9,949.7	-91.4	2,006.8	32° 4' 45.541 N	103° 18' 22.513 W
10,100.0	47.77	353.79	10,024.0	-25.3	1,998.1	32° 4' 46.195 N	103° 18' 22.607 W
10,200.0	59.56	355.78	10,083.1	54.8	1,990.9	32° 4' 46.989 N	103° 18' 22.681 W
10,271.7	68.03	356.93	10,114.8	119.0	1,986.8	32° 4' 47.624 N	103° 18' 22.722 W
Nan073 FTP							
10,300.0	71.37	357.34	10,124.6	145.4	1,985.5	32° 4' 47.886 N	103° 18' 22.734 W
10,400.0	83.20	358.69	10,146.6	242.8	1,982.1	32° 4' 48.849 N	103° 18' 22.762 W
10,457.5	90.00	359.43	10,150.0	300.0	1,981.2	32° 4' 49.416 N	103° 18' 22.767 W
Nan073 FTP2							
10,500.0	90.00	359.43	10,150.0	342.5	1,980.8	32° 4' 49.837 N	103° 18' 22.767 W
10,600.0	90.00	359.43	10,150.0	442.5	1,979.8	32° 4' 50.826 N	103° 18' 22.768 W
10,700.0	90.00	359.43	10,150.0	542.5	1,978.8	32° 4' 51.816 N	103° 18' 22.768 W
10,800.0	90.00	359.43	10,150.0	642.5	1,977.8	32° 4' 52.805 N	103° 18' 22.769 W
10,900.0	90.00	359.43	10,150.0	742.5	1,976.8	32° 4' 53.795 N	103° 18' 22.769 W
11,000.0	90.00	359.43	10,150.0	842.5	1,975.8	32° 4' 54.784 N	103° 18' 22.770 W
11,100.0	90.00	359.43	10,150.0	942.5	1,974.8	32° 4' 55.774 N	103° 18' 22.770 W
11,200.0	90.00	359.43	10,150.0	1,042.5	1,973.8	32° 4' 56.763 N	103° 18' 22.771 W
11,300.0	90.00	359.43	10,150.0	1,142.5	1,972.8	32° 4' 57.753 N	103° 18' 22.771 W
11,400.0	90.00	359.43	10,150.0	1,242.5	1,971.8	32° 4' 58.742 N	103° 18' 22.772 W
11,500.0	90.00	359.43	10,150.0	1,342.5	1,970.8	32° 4' 59.732 N	103° 18' 22.772 W
11,600.0	90.00	359.43	10,150.0	1,442.5	1,969.8	32° 5' 0.721 N	103° 18' 22.773 W
11,700.0	90.00	359.43	10,150.0	1,542.5	1,968.8	32° 5' 1.711 N	103° 18' 22.773 W
11,800.0	90.00	359.43	10,150.0	1,642.5	1,967.8	32° 5' 2.700 N	103° 18' 22.774 W
11,900.0	90.00	359.43	10,150.0	1,742.5	1,966.8	32° 5' 3.690 N	103° 18' 22.774 W
12,000.0	90.00	359.43	10,150.0	1,842.4	1,965.8	32° 5' 4.679 N	103° 18' 22.775 W
12,100.0	90.00	359.43	10,150.0	1,942.4	1,964.8	32° 5' 5.669 N	103° 18' 22.776 W
12,200.0	90.00	359.43	10,150.0	2,042.4	1,963.8	32° 5' 6.658 N	103° 18' 22.776 W
12,300.0	90.00	359.43	10,150.0	2,142.4	1,962.8	32° 5' 7.648 N	103° 18' 22.777 W
12,400.0	90.00	359.43	10,150.0	2,242.4	1,961.8	32° 5' 8.637 N	103° 18' 22.777 W
12,500.0	90.00	359.43	10,150.0	2,342.4	1,960.8	32° 5' 9.627 N	103° 18' 22.778 W
12,600.0	90.00	359.43	10,150.0	2,442.4	1,959.8	32° 5' 10.616 N	103° 18' 22.778 W
12,700.0	90.00	359.43	10,150.0	2,542.4	1,958.8	32° 5' 11.606 N	103° 18' 22.779 W
12,800.0	90.00	359.43	10,150.0	2,642.4	1,957.8	32° 5' 12.595 N	103° 18' 22.779 W
12,900.0	90.00	359.43	10,150.0	2,742.4	1,956.8	32° 5' 13.585 N	103° 18' 22.780 W
13,000.0	90.00	359.43	10,150.0	2,842.4	1,955.8	32° 5' 14.574 N	103° 18' 22.780 W
13,100.0	90.00	359.43	10,150.0	2,942.4	1,954.8	32° 5' 15.564 N	103° 18' 22.781 W
13,200.0	90.00	359.43	10,150.0	3,042.4	1,953.8	32° 5' 16.553 N	103° 18' 22.781 W
13,300.0	90.00	359.43	10,150.0	3,142.4	1,952.8	32° 5' 17.543 N	103° 18' 22.782 W

Company: Ameredev Operating, LLC.
 Project: NAN/GB
 Site: NAN/GB #3N
 Well: Nandina 073H
 Wellbore: Wellbore #1
 Design: Design #1

Local Co-ordinate Reference: Well Nandina 073H
 TVD Reference: KB @ 3046.0usft
 MD Reference: KB @ 3046.0usft
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Database: EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	Latitude	Longitude
13,400.0	90.00	359.43	10,150.0	3,242.4	1,951.8	32° 5' 18.532 N	103° 18' 22.782 W
13,500.0	90.00	359.43	10,150.0	3,342.4	1,950.8	32° 5' 19.522 N	103° 18' 22.783 W
13,600.0	90.00	359.43	10,150.0	3,442.4	1,949.8	32° 5' 20.511 N	103° 18' 22.783 W
13,700.0	90.00	359.43	10,150.0	3,542.4	1,948.8	32° 5' 21.501 N	103° 18' 22.784 W
13,800.0	90.00	359.43	10,150.0	3,642.4	1,947.8	32° 5' 22.490 N	103° 18' 22.784 W
13,900.0	90.00	359.43	10,150.0	3,742.4	1,946.8	32° 5' 23.480 N	103° 18' 22.785 W
14,000.0	90.00	359.43	10,150.0	3,842.3	1,945.8	32° 5' 24.469 N	103° 18' 22.786 W
14,100.0	90.00	359.43	10,150.0	3,942.3	1,944.8	32° 5' 25.459 N	103° 18' 22.786 W
14,200.0	90.00	359.43	10,150.0	4,042.3	1,943.8	32° 5' 26.448 N	103° 18' 22.787 W
14,300.0	90.00	359.43	10,150.0	4,142.3	1,942.9	32° 5' 27.438 N	103° 18' 22.787 W
14,400.0	90.00	359.43	10,150.0	4,242.3	1,941.9	32° 5' 28.428 N	103° 18' 22.788 W
14,500.0	90.00	359.43	10,150.0	4,342.3	1,940.9	32° 5' 29.417 N	103° 18' 22.788 W
14,600.0	90.00	359.43	10,150.0	4,442.3	1,939.9	32° 5' 30.407 N	103° 18' 22.789 W
14,700.0	90.00	359.43	10,150.0	4,542.3	1,938.9	32° 5' 31.396 N	103° 18' 22.789 W
14,800.0	90.00	359.43	10,150.0	4,642.3	1,937.9	32° 5' 32.386 N	103° 18' 22.790 W
14,900.0	90.00	359.43	10,150.0	4,742.3	1,936.9	32° 5' 33.375 N	103° 18' 22.790 W
15,000.0	90.00	359.43	10,150.0	4,842.3	1,935.9	32° 5' 34.365 N	103° 18' 22.791 W
15,100.0	90.00	359.43	10,150.0	4,942.3	1,934.9	32° 5' 35.354 N	103° 18' 22.791 W
15,200.0	90.00	359.43	10,150.0	5,042.3	1,933.9	32° 5' 36.344 N	103° 18' 22.792 W
15,300.0	90.00	359.43	10,150.0	5,142.3	1,932.9	32° 5' 37.333 N	103° 18' 22.792 W
15,400.0	90.00	359.43	10,150.0	5,242.3	1,931.9	32° 5' 38.323 N	103° 18' 22.793 W
15,437.7	90.00	359.43	10,150.0	5,280.0	1,931.5	32° 5' 38.696 N	103° 18' 22.793 W
Nan073 into NMNM127450							
15,500.0	90.00	359.43	10,150.0	5,342.3	1,930.9	32° 5' 39.312 N	103° 18' 22.793 W
15,600.0	90.00	359.43	10,150.0	5,442.3	1,929.9	32° 5' 40.302 N	103° 18' 22.794 W
15,700.0	90.00	359.43	10,150.0	5,542.3	1,928.9	32° 5' 41.291 N	103° 18' 22.794 W
15,800.0	90.00	359.43	10,150.0	5,642.3	1,927.9	32° 5' 42.281 N	103° 18' 22.795 W
15,900.0	90.00	359.43	10,150.0	5,742.3	1,926.9	32° 5' 43.270 N	103° 18' 22.795 W
16,000.0	90.00	359.43	10,150.0	5,842.2	1,925.9	32° 5' 44.260 N	103° 18' 22.796 W
16,100.0	90.00	359.43	10,150.0	5,942.2	1,924.9	32° 5' 45.249 N	103° 18' 22.797 W
16,200.0	90.00	359.43	10,150.0	6,042.2	1,923.9	32° 5' 46.239 N	103° 18' 22.797 W
16,300.0	90.00	359.43	10,150.0	6,142.2	1,922.9	32° 5' 47.228 N	103° 18' 22.798 W
16,400.0	90.00	359.43	10,150.0	6,242.2	1,921.9	32° 5' 48.218 N	103° 18' 22.798 W
16,500.0	90.00	359.43	10,150.0	6,342.2	1,920.9	32° 5' 49.207 N	103° 18' 22.799 W
16,600.0	90.00	359.43	10,150.0	6,442.2	1,919.9	32° 5' 50.197 N	103° 18' 22.799 W
16,700.0	90.00	359.43	10,150.0	6,542.2	1,918.9	32° 5' 51.186 N	103° 18' 22.800 W
16,800.0	90.00	359.43	10,150.0	6,642.2	1,917.9	32° 5' 52.176 N	103° 18' 22.800 W
16,900.0	90.00	359.43	10,150.0	6,742.2	1,916.9	32° 5' 53.165 N	103° 18' 22.801 W
17,000.0	90.00	359.43	10,150.0	6,842.2	1,915.9	32° 5' 54.155 N	103° 18' 22.801 W
17,100.0	90.00	359.43	10,150.0	6,942.2	1,914.9	32° 5' 55.144 N	103° 18' 22.802 W
17,200.0	90.00	359.43	10,150.0	7,042.2	1,913.9	32° 5' 56.134 N	103° 18' 22.802 W
17,300.0	90.00	359.43	10,150.0	7,142.2	1,912.9	32° 5' 57.123 N	103° 18' 22.803 W
17,400.0	90.00	359.43	10,150.0	7,242.2	1,911.9	32° 5' 58.113 N	103° 18' 22.803 W
17,500.0	90.00	359.43	10,150.0	7,342.2	1,910.9	32° 5' 59.102 N	103° 18' 22.804 W
17,600.0	90.00	359.43	10,150.0	7,442.2	1,909.9	32° 6' 0.092 N	103° 18' 22.804 W

Company:	Ameredev Operating, LLC.	Local Co-ordinate Reference:	Well Nandina 073H
Project:	NAN/GB	TVD Reference:	KB @ 3046.0usft
Site:	NAN/GB #3N	MD Reference:	KB @ 3046.0usft
Well:	Nandina 073H	North Reference:	Grid
Wellbore:	Wellbore #1	Survey Calculation Method:	Minimum Curvature
Design:	Design #1	Database:	EDM5000

Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/FNL (usft)	+FWL/FEL (usft)	Latitude	Longitude
17,700.0	90.00	359.43	10,150.0	7,542.2	1,908.9	32° 6' 1.081 N	103° 18' 22.805 W
17,800.0	90.00	359.43	10,150.0	7,642.2	1,907.9	32° 6' 2.071 N	103° 18' 22.805 W
17,900.0	90.00	359.43	10,150.0	7,742.2	1,906.9	32° 6' 3.060 N	103° 18' 22.806 W
18,000.0	90.00	359.43	10,150.0	7,842.1	1,905.9	32° 6' 4.050 N	103° 18' 22.806 W
18,100.0	90.00	359.43	10,150.0	7,942.1	1,904.9	32° 6' 5.039 N	103° 18' 22.807 W
18,200.0	90.00	359.43	10,150.0	8,042.1	1,904.0	32° 6' 6.029 N	103° 18' 22.807 W
18,300.0	90.00	359.43	10,150.0	8,142.1	1,903.0	32° 6' 7.018 N	103° 18' 22.808 W
18,400.0	90.00	359.43	10,150.0	8,242.1	1,902.0	32° 6' 8.008 N	103° 18' 22.809 W
18,500.0	90.00	359.43	10,150.0	8,342.1	1,901.0	32° 6' 8.998 N	103° 18' 22.809 W
18,600.0	90.00	359.43	10,150.0	8,442.1	1,900.0	32° 6' 9.987 N	103° 18' 22.810 W
18,700.0	90.00	359.43	10,150.0	8,542.1	1,899.0	32° 6' 10.977 N	103° 18' 22.810 W
18,800.0	90.00	359.43	10,150.0	8,642.1	1,898.0	32° 6' 11.966 N	103° 18' 22.811 W
18,900.0	90.00	359.43	10,150.0	8,742.1	1,897.0	32° 6' 12.956 N	103° 18' 22.811 W
19,000.0	90.00	359.43	10,150.0	8,842.1	1,896.0	32° 6' 13.945 N	103° 18' 22.812 W
19,100.0	90.00	359.43	10,150.0	8,942.1	1,895.0	32° 6' 14.935 N	103° 18' 22.812 W
19,200.0	90.00	359.43	10,150.0	9,042.1	1,894.0	32° 6' 15.924 N	103° 18' 22.813 W
19,300.0	90.00	359.43	10,150.0	9,142.1	1,893.0	32° 6' 16.914 N	103° 18' 22.813 W
19,400.0	90.00	359.43	10,150.0	9,242.1	1,892.0	32° 6' 17.903 N	103° 18' 22.814 W
19,500.0	90.00	359.43	10,150.0	9,342.1	1,891.0	32° 6' 18.893 N	103° 18' 22.814 W
19,600.0	90.00	359.43	10,150.0	9,442.1	1,890.0	32° 6' 19.882 N	103° 18' 22.815 W
19,700.0	90.00	359.43	10,150.0	9,542.1	1,889.0	32° 6' 20.872 N	103° 18' 22.815 W
19,800.0	90.00	359.43	10,150.0	9,642.1	1,888.0	32° 6' 21.861 N	103° 18' 22.816 W
19,900.0	90.00	359.43	10,150.0	9,742.1	1,887.0	32° 6' 22.851 N	103° 18' 22.816 W
20,000.0	90.00	359.43	10,150.0	9,842.0	1,886.0	32° 6' 23.840 N	103° 18' 22.817 W
20,100.0	90.00	359.43	10,150.0	9,942.0	1,885.0	32° 6' 24.830 N	103° 18' 22.817 W
20,200.0	90.00	359.43	10,150.0	10,042.0	1,884.0	32° 6' 25.819 N	103° 18' 22.818 W
20,300.0	90.00	359.43	10,150.0	10,142.0	1,883.0	32° 6' 26.809 N	103° 18' 22.818 W
20,400.0	90.00	359.43	10,150.0	10,242.0	1,882.0	32° 6' 27.798 N	103° 18' 22.819 W
20,500.0	90.00	359.43	10,150.0	10,342.0	1,881.0	32° 6' 28.788 N	103° 18' 22.819 W
20,600.0	90.00	359.43	10,150.0	10,442.0	1,880.0	32° 6' 29.777 N	103° 18' 22.820 W
Nan073 LTP							
20,676.0	90.00	359.43	10,150.0	10,518.0	1,879.3	32° 6' 30.529 N	103° 18' 22.820 W
Nan073 BHL							

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
+N/-S (usft)	+E/-W (usft)			
15,437.7	10,150.0	5,050.0	196.5	Nan073 into NMNM127450

Checked By: _____ Approved By: _____ Date: _____

5M Annular Preventer Variance Request and Well Control Procedures

Note: A copy of the Well Control Plan must be available at multiple locations on the rig for review by rig personnel, as well as review by the BLM PET/PE, and a copy must be maintained on the rig floor.

Dual Isolation Design for 5M Annular Exception

Ameredeve will utilize 13-5/8" 10M (5M Annular) BOPE System consisting of:

- 13-5/8" 5M Annular
- 13-5/8" 10M Upper Pipe Rams
 - 3-1/2" – 5-1/2" Variable Bore Ram
- 13-5/8" 10M Blind Rams
- 13-5/8" 10M Drilling Spool /w 2 - 4" 10M Outlets Double 10M Isolation Valves
- 13-5/8" 10M Lower Blind Rams
 - 3-1/2" – 5-1/2" Variable Bore Ram

All drilling components and casing associated to exposure > 5000 psi BHP requiring a 10M system will have a double isolation (secondary barrier) below the 5M Annular that would provide a barrier to flow. The mud system will always be primary barrier, it will be maintained by adjusting values based on tourly mud tests and monitoring a PVT System to maintain static wellbore conditions, displacement procedures will be followed and recorded on daily drilling reports during tripping operations. Surge and swab pressure values will be calculated and maintained and static flow check will be monitored at previous casing shoe and verified static well conditions prior to tripping out of hole and again prior to pulling last joint of drill pipe through BOPE. The below table, documents that two barriers to flow can be maintained at all times, independent of the rating of the annular preventer.

Drill Components	Size	Primary Barrier	Secondary Barrier	Third Barrier
Drillpipe	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
HWDP Drillpipe	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Drill Collars	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Production Casing	3-1/2"-5-1/2"	Drilling Fluid	Upper Pipe Rams	Lower Pipe Rams
Open Hole	13-5/8	Drilling Fluid	Blind Rams	
All Drilling Components in 10M Environment will have OD that will allow full Operational RATED WORKING PRESSURE for system design. Kill line with minimum 2" ID will be available outside substructure with 10M Check Valve for OOH Kill Operations				

Well Control Procedures

Proper well control procedures are dependent to differentiating well conditions, to cover the basic well control operations there are will be standard drilling ahead, tripping pipe, tripping BHA, running casing, and pipe out of the hole/open hole scenarios that will be defined by procedures below. Initial Shut In Pressure can be taken against the Uppermost BOPE component the 5M Annular, pressure control can be transferred from the lesser 5M Annular to the 10M Upper Pipe Rams if needed. Shut In Pressures may be equal to or less than the Rated Working Pressure but at no time will the pressure on the annular preventer exceed the Rated Working Pressure of the annular. The annular will be tested to 5,000 psi. This will be the Rated Working Pressure of the annular preventer. All scenarios will be written such as shut in will be performed by closing the 10,000 psi Upper Pipe Rams for faster Accumulator pressure recovery to allow safer reaction to controlling wellbore pressure.

Shutting In While Drilling

1. Sound alarm signaling well control event to Rig Crew
2. Space out drill string to allow FOSV installation
3. Shut down pumps
4. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
5. Install open, full open safety valve and close valve, Close Chokes
6. Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure

Shutting In While Tripping

1. Sound alarm signaling well control event to Rig Crew
2. Space out drill string to allow FOSV installation
3. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
4. Install open, full open safety valve and close valve, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

Shutting In While Running Casing

1. Sound alarm signaling well control event to Rig Crew
2. Space out casing to allow circulating swedge installation
3. Shut in Upper Pipe Rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
4. Install circulating swedge, Close high pressure, low torque valves, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold Pre-job safety meeting and discuss kill procedure

Shutting in while out of hole

1. Sound alarm signaling well control event to Rig Crew
2. Shut-in well: close blind rams and open HCR against Open Chokes and Valves
Open to working pressure gauge
3. Close Chokes, Verify well is shut-in and monitor pressures
4. Notify supervisory personnel
5. Record data (SIDP, SICP, Pit Gain, and Time)
6. Hold Pre-job safety meeting and discuss kill procedure

Shutting In prior to pulling BHA through stack

Prior to pulling last joint of drill pipe thru the stack space out and check flow
If flowing see steps below.

1. Sound alarm signaling well control event to Rig Crew
2. Shut in upper pipe ram and open HCR against Open Chokes and Valves Open
to working pressure gauge
3. Install open, full open safety valve and close valve, Close Chokes
4. Verify well is shut-in and flow has stopped
5. Notify supervisory personnel
6. Record data (SIDP, SICP, Pit Gain, and Time)
7. Hold pre-job safety meeting and discuss kill procedure

Shutting in while BHA is in the stack and ram preventer and combo immediately available

1. Sound alarm signaling well control event to Rig Crew
2. Space out BHA with upset just beneath the compatible pipe ram
3. Shut in upper compatible pipe ram and open HCR against Open Chokes and Valves Open to working pressure gauge
4. Install open, full open safety valve and close valve, Close Chokes
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

*FOSV will be on rig floor in open position with operating handle for each type of connection utilized and tested to 10,000 psi

Shutting in while BHA is in the stack and no ram preventer or combo immediately available

1. Sound alarm signaling well control event to Rig Crew
2. If possible pick up high enough, to pull string clear and follow "Open Hole" scenario

If not possible to pick up high enough:

3. Stab Crossover, make up one joint/stand of drill pipe, and install open, full open safety valve (Leave Open)
4. Space out drill string with upset just beneath the compatible pipe ram.
5. Shut in upper compatible pipe ram and open HCR against Open Chokes and Valves Open to working pressure gauge
6. Close FOSV, Close Chokes, Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure

Pressure Control Plan

Pressure Control Equipment

- Following setting of 13-3/8" Surface Casing Ameredev will install 13-5/8 MB4 Multi Bowl Casing Head by welding on a 13-5/8 SOW x 13-5/8" 5M in combination with 13-5/8 5M x 13-5/8 10M B-Sec to Land Intm #1 and a 13-5/8 10M x 13-5/8 10M shouldered to land C-Sec to Land Intm #2 (Installation procedure witnessed and verified by a manufacturer's representative).
- Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Ameredev will install a 5M System Blowout Preventer (BOPE) with a 5M Annular Preventer and related equipment (BOPE). Full testing will be performed utilizing a full isolation test plug and limited to 5,000 psi MOP of MB4 Multi Bowl Casing Head. Pressure will be held for 10 min or until provisions of test are met on all valves and rams. The 5M Annular Preventer will be tested to 50% of approved working pressure (2,500 psi). Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Setting of 9-5/8" Intermediate will be done by landing a wellhead hanger in the 13-5/8" 5M Bowl, Cementing and setting Well Head Packing seals and testing same. (Installation procedure witnessed and verified by a manufacturer's representative) Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- Full testing will be performed utilizing a full isolation test plug to 10,000 psi MOP of MB4 Multi Bowl B-Section. Pressure will be held for 10 min or until provisions of test are met on all valves and rams. The 5M Annular Preventer will be tested to 100% of approved working pressure (5,000 psi).
- Before drilling >20ft of new formation under the 9-5/8" Casing Shoe a pressure integrity test of the Casing Shoe will be performed to minimum of the MWE anticipated to control formation pressure to the next casing depth.
- Following setting of 5-1/2" Production Casing and adequate WOC time Ameredev will break 10M System Blowout Preventer (BOP) from 10M DOL-2 Casing Head, install annulus casing slips and test same (Installation procedure witnessed and verified by a manufacturer's representative) and install 11" 10M x 5-1/8" 15M Tubing Head (Installation procedure witnessed and verified by a manufacturer's representative). Ameredev will test head to 70% casing design and install Dry Hole cap with needle valve and pressure gauge to monitor well awaiting completion.

Pressure Control Plan

- Slow pump speeds will be taken daily by each crew and recorded on Daily Drilling Report after mudding up.
- A choke manifold and accumulator with floor and remote operating stations will be functional and in place after installation of BOPE, as well as full functioning mud gas separator.
- Weekly BOPE pit level drills will be conducted by each crew and recorded on Daily Drilling Report.
- BOP will be fully operated when out of hole and will be documented on the daily drilling log.
- All B.O.P.s and associated equipment will be tested in accordance with Onshore Order #2
- All B.O.P. testing will be done by an independent service company.
- The B.O.P. will be tested within 21 days of the original test if drilling takes more time than planned.
- Ameredev requests a variance to connect the B.O.P. choke outlet to the choke manifold using a co-flex hose with a 10,000 psi working pressure that has been tested to 15,000psi and is built to API Spec 16C. Once the flex line is installed it will be tied down with safety clamps. (certifications will be sent to Carlsbad BLM Office prior to install)
- Ameredev requests a variance to install a 5M Annular Preventer on the 10M System to drill the Production Hole below the 9-5/8" Intermediate Section. 5M Annular will be tested to 100% working pressure (5,000 psi). A full well control procedure will be included to isolate well bore.

Ameredev Drilling Plan: 3 String with 4 String Contingency

- Contingency Plan If Losses Exceed 50% in Intermediate Interval
 - We will utilize a MB4 wellhead that will enable us to convert a 3 string design to a 4 string design. (Schematic Attached)
 - We will displace well with FW and drill or condition to run 9-5/8" Casing at the Lamar Limestone, we will utilize DV Tool w/ ACP @ the Tansill to Isolate Capitan Reef and cement to surface.
 - Casing will be tested to 1500 psi or .22 psi/ft whichever is greater for 30 minutes with <10% leak off, but will not exceed 70% of the burst rating per Onshore Order No. 2.
- 7.625 Casing will be Additional 4th String
 - Drill remaining hole section to 10,670'
 - Run 7.625 29.7# HCL80 FJM Casing

4-String Contingency Wellbore Schematic

Well: (Well Name)

SHL: (SHL)

BHL: (BHL)

Lea, NM

Wellhead: A - 13-5/8" 10M x 13-5/8" SOW

B - 13-5/8" 10M x 13-5/8" 10M

C - 13-5/8" 10M x 13-5/8" 10M

Tubing Spool - 5-1/8" 15M x 13-3/8" 10M

Xmas Tree: 2-9/16" 10M

Tubing: 2-7/8" L-80 6.5# 8rd EUE

Co. Well ID:

AFE No.:

API No.:

GL:

Field:

Objective:

TVD:

MD:

Rig:

E-Mail:

XXXXXX

XXXX-XXXX

XXXXXXXXXXXX

(Elevation)'

Delaware

Wolfcamp B

(TVD)'

(MD)'

TBD KB 27'

Wellsite2@ameredev.com


Hole Size	Formation Tops	Logs	Cement	Mud Weight
17.5"	Rustler 13.375" 54.5# J-55 BTC 125' below Rustler	TOC 0'	100% Excess	8.4-8.6 ppg WBM
12.25"	Salado DV Tool with ACP At Tansill Tansill Capitan Reef Lamar 50' below Lamar 9.625" 40# L-80HC BTC	TOC 0'	50% Excess	8.3-10.2 Fresh Water
8.75"	Bell Canyon Brushy Canyon Bone Spring Lime First Bone Spring Second Bone Spring Third Bone Spring Upper 7.625" 29.7# L-80HC FJM 125' below TBSG Upper	TOC 0'	25% Excess	8.5-9.4 Diesel Brine Emulsion
6.75" 12° Build @ KOP	Third Bone Spring Wolfcamp Wolfcamp B (If Applicable) 5.5" 20# P-110CYHP TMK UP SF TORQ (MD) Target Wolfcamp B TVD // MD	TOC 0'	25% Excess	10.5-14 ppg OBM

****EXAMPLE ONLY - NOT FOR CONSTRUCTION****

Contingency Casing Design and Safety Factor Check

Casing Specifications						
Segment	Hole ID	Depth	OD	Weight	Grade	Coupling
Surface	17.5	1,888'	13.375	54.5	J-55	BTC
Int #1	12.25	5,013'	9.625	40	HCL-80	BTC
Int #2	8.75	11,147'	7.625	29.7	HCL-80	FJM
Prod Segment A	6.75	11,147'	5.5	20	CYHP-110	TMK UPSF
Prod Segment B	6.75	22,496'	5.5	20	CYHP-110	TMK UPSF

Check Surface Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
14.38	853	909	1,130	2,730
Safety Factors				
1.56	8.29	8.83	1.15	0.91
Check Int #1 Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
10.625	916	1042	4230	5750
Safety Factors				
0.81	4.57	5.20	1.41	0.95
Check Int #2 Casing				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
7.625	940	558	6700	9460
Safety Factors				
0.56	2.84	1.96	1.10	1.24
Check Prod Casing, Segment A				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
Safety Factors				
0.49	3.11	2.79	1.77	1.89
Check Prod Casing, Segment B				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
Safety Factors				
0.49	63.53	57.16	1.68	1.89



Quotation

Downing Wellhead Equipment

Oklahoma City,
Oklahoma - USA

Reference Data:

16925 AMEREDEV

Proprietary and Confidential

The information contained in this drawing is the sole property of Downing Wellhead Equipment, any reproduction in part or in whole without the written permission of Downing Wellhead Equipment is prohibited.

TITLE:

AMEREDEV

DRAWN

CHECKED

APPROVED

SIZE

A

DWG. NO.

Scale:

Weight:

REV.

Sheet:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

SUPO Data Report

07/10/2019

APD ID: 10400041717

Submission Date: 05/09/2019

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

NANDINA_FED_COM_25_36_31_073H__WELL_PAD_ACCESS_MAP_20190509081533.pdf

Existing Road Purpose: ACCESS

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? NO

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

NANDINA_FED_COM_25_36_31_073H__1_MI_RADIUS_WELLS_20190509081556.pdf

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Existing Wells description:

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description: A 4" poly flowline (700 psi maximum) will be buried and run approximately 1,574' from the Nandina Fed Com 25 36 31 073H to the existing Nandina CTB northeast of the well pad. Should any type of production facilities be located on the well pad itself, they will be strategically placed to allow for maximum interim reclamation, re-contouring, and revegetation of the well location.

Production Facilities map:

NAN_GB_EXISTING_CTB_20190509081616.pdf

NAN_GB_FLOWLINE__3N_20190509081616.pdf

Section 5 - Location and Types of Water Supply

Water Source Table

Water source use type: DUST CONTROL,
INTERMEDIATE/PRODUCTION CASING, STIMULATION, SURFACE
CASING

Water source type: GW WELL

Describe type:

Source longitude:

Source latitude:

Source datum:

Water source permit type: PRIVATE CONTRACT

Source land ownership: PRIVATE

Water source transport method: PIPELINE,TRUCKING

Source transportation land ownership: FEDERAL

Water source volume (barrels): 20000

Source volume (acre-feet): 2.577862

Source volume (gal): 840000

Water source and transportation map:

NANDINA_FED_COM_25_36_31_073H__WATER_MAP_20190509081652.pdf

NANDINA_FED_COM_25_36_31_073H__WATER_WELLS_LIST_20190509081653.pdf

Water source comments: Water will be trucked or surface piped from existing water wells on private land. See attached list of available wells.

New water well? NO

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Construction Materials description: NM One Call (811) will be notified before construction start. Top 6" of soil and brush will be stockpiled north of the pad. Closed loop drilling system will be used. Caliche will be hauled from an existing caliche pit on private (Dinwiddie Cattle Company) land in W2 08-25S-36E or an existing caliche pit on private (Dinwiddie Cattle Company) land in E2 17-25S-36E.

Construction Materials source location attachment:

NANDINA_FED_COM_25_36_31_073H__CALICHE_MAP_20190509081720.pdf

Section 7 - Methods for Handling Waste

Waste type: DRILLING

Waste content description: Drill cuttings, mud, salts, and other chemicals

Amount of waste: 2000 barrels

Waste disposal frequency : Daily

Safe containment description: Steel tanks on pad

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: R360's State approved (NM-01-0006) disposal site at Halfway, NM

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Reserve pit length (ft.)

Reserve pit width (ft.)

Reserve pit depth (ft.)

Reserve pit volume (cu. yd.)

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? YES

Description of cuttings location Steel tanks on pad

Cuttings area length (ft.)

Cuttings area width (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

NANDINA_FED_COM_25_36_31_073H__WELL_SITE_DIAGRAM_20190509081758.pdf

BO_NAN_GB_3N_PAD_SITE_S_20190509081806.pdf

Comments:

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: NAN

Multiple Well Pad Number: 3N

Recontouring attachment:

NANDINA_FED_COM_25_36_31_073H__WELL_SITE_DIAGRAM_20190509081824.pdf

Drainage/Erosion control construction: Crowned and ditched

Drainage/Erosion control reclamation: Harrowed on the contour

Well pad proposed disturbance (acres): 4.59	Well pad interim reclamation (acres): 0.79	Well pad long term disturbance (acres): 3.8
Road proposed disturbance (acres): 0	Road interim reclamation (acres): 0	Road long term disturbance (acres): 0
Powerline proposed disturbance (acres): 0	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0
Pipeline proposed disturbance (acres): 0.72	Pipeline interim reclamation (acres): 0	Pipeline long term disturbance (acres): 0.72
Other proposed disturbance (acres): 0	Other interim reclamation (acres): 0	Other long term disturbance (acres): 0
Total proposed disturbance: 5.31	Total interim reclamation: 0.79	Total long term disturbance: 4.52

Disturbance Comments:

Reconstruction method: If circumstances allow, interim reclamation and/or final reclamation actions will be completed no later than 6 months from when the final well on location has been completed or plugged. Ameredev will gain written permission from the BLM if more time is needed. Interim reclamation will be completed within 6 months of completing the well. Interim reclamation will consist of shrinking the pad 17% (.79 acre) by removing caliche and reclaiming 40' wide swaths on the north and east sides of the pad. This will leave 3.8 acres for producing six wells, with tractor-trailer turn around. Disturbed areas will be contoured to match pre-construction grades. Soil and brush will be evenly spread over disturbed areas and harrowed on the contour. Disturbed areas will be seeded in accordance with the surface owner's requirements. All topsoil for the battery will be reseeded in place for the life of the battery.

Topsoil redistribution: Enough stockpiled topsoil will be retained to cover the remainder of the pad when the well is plugged. New road will be similarly reclaimed within 6 months of plugging. Noxious weeds will be controlled.

Soil treatment: None

Existing Vegetation at the well pad:

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road:

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline:

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances:

Existing Vegetation Community at other disturbances attachment:

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Seed Management

Seed Table

Seed type:

Seed source:

Seed name:

Source name:

Source address:

Source phone:

Seed cultivar:

Seed use location:

PLS pounds per acre:

Proposed seeding season:

Seed Summary

Total pounds/Acre:

Seed Type	Pounds/Acre
-----------	-------------

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

First Name: Zachary

Last Name: Boyd

Phone: (580)940-5054

Email: zboyd@ameredev.com

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: To BLM standards

Weed treatment plan attachment:

Monitoring plan description: To BLM standards

Monitoring plan attachment:

Success standards: To BLM satisfaction

Pit closure description: No pit

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: PIPELINE

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Fee Owner: EOG Resources

Fee Owner Address: PO Box 2267

Phone: (432)425-1204

Email:

Surface use plan certification:

Surface use plan certification document:

Surface access agreement or bond:

Surface Access Agreement Need description:

Surface Access Bond BLM or Forest Service:

BLM Surface Access Bond number:

USFS Surface access bond number:

Section 12 - Other Information

Right of Way needed? YES

Use APD as ROW? YES

ROW Type(s): 288100 ROW – O&G Pipeline, 289001 ROW- O&G Well Pad

ROW Applications

Operator Name: AMEREDEV OPERATING LLC

Well Name: NANDINA FED COM 25 36 31

Well Number: 073H

SUPO Additional Information:

Use a previously conducted onsite? YES

Previous Onsite information: An on-site meeting for Ameredev's Nandina Fed Com 25 36 31 073H was held on 7/23/18. Attendees included Jeff Robertson (BLM), Shane McNeely (Ameredev), and Ged Adams (Topographic). Ameredev made a donation with the MOU fund in lieu of an archaeology report. (NOS #: 10400030258)

Other SUPO Attachment

NANDINA_FED_COM_25_36_31_073H__SURFACE_USE_PLAN_20190509081957.pdf

Section 1 – Existing Roads

- A. The existing access road route to the proposed project is depicted on *Exhibit 1 – Well Pad Access*. Improvements to the driving surface will be done where necessary. No new surface disturbance will be done, unless otherwise noted in the New or Reconstructed Access Roads section of this surface use plan.
- B. Right-Of-Way will be acquired before construction begins.
- C. The operator will improve or maintain existing roads in a condition the same as or better than before operations begin. The operator will repair pot holes, clear ditches, repair the crown, etc. All existing structures on the entire access route such as cattle guards, other range improvement projects, culverts, etc. will be properly repaired or replaced if they are damaged or have deteriorated beyond practical use.
- D. Operator will prevent and abate fugitive dust as needed, whether created by vehicular traffic, equipment operations, or wind events. BLM written approval will be acquired before application of surfactants, binding agents, or other dust suppression chemicals on roadways.

Section 2 – New or Reconstructed Access Roads

- A. No new access road will be needed for this proposed project. See *Exhibit 1 – Well Pad Access*.

Section 3 – Location of Existing Wells

Exhibit 2 – One Mile Radius Existing Wells depicts all known wells within a one mile radius of the Nandina Fed Com 25 36 31 073H. See *Exhibit 2a – One Mile Radius Wells List* for a list of wells depicted.

Ameredev Operating, LLC
Nandina Fed Com 25 36 31 073H
Section 31, Township 25S, Range 36E
Lea County, New Mexico

AMEREDEV

Ameredev, LLC




Exhibit 2 – One Mile Radius Existing Wells


API	WELL NAME	STATUS	TD
30025261530000	SPOTTED TAIL FED #2	UNKNOWN	
30025260170000	SITTING BULL #1	OIL	3379
30025260090000	STANDING BEAR #1	PLUGGED OIL	3280
30025375170001	MOMENTUM 36 STATE #1	INJECTION	9702
30025445050000	USHANKA FEDERAL COM #023H	PILOT	12500
30025453360100	GOLDEN BELL 26 36 06 FED COM #125H	PERMIT	
30025453360000	GOLDEN BELL 26 36 06 FED COM #125H	PERMIT	
30025445050100	USHANKA FEDERAL COM #023H	OIL	19335
30025375170000	MOMENTUM 36 STATE #1	DRY HOLE	9702
30025268760000	STANDING BEAR FED #2	PLUGGED OIL	3311
30025260100000	SPOTTED TAIL FED #1	OIL	3336
30025260270000	SITTING BULL #1	OIL	3368
30025452430000	NANDINA 25 36 31 FEDERAL COM #105H	PERMIT	
30025452440000	NANDINA 25 36 31 FED COM #125H	DRILLING	
30025452460000	NANDINA 25 36 31 FEDERAL COM #115H	PERMIT	
30025453100000	GOLDEN BELL 26 36 06 FED COM #105H	PERMIT	
30025453110000	GOLDEN BELL 26 36 06 FED COM #115H	DRILLING	

Exhibit 2a – One Mile Radius Existing Wells List

Section 4 - Location of Existing and/or Proposed Production Facilities

- A. The multiple well pad will be located on Section 31, and will measure 400'x500'. The top 6" of soil and brush will be stockpiled north of the well pad. Should any type of production facilities be located on the well pad, they will be strategically placed to allow for maximum interim reclamation, re-contouring, and revegetation of the well location.
- B. Production from the proposed well will be transported to an existing production facility named Nandina CTB, northeast of the well pad, via a buried 4" poly flowline that runs approximately 1,574'.
- C. All permanent (lasting more than six months) above ground structures including but not limited to pump jacks, storage tanks, barrels, pipeline risers, meter housing, etc., that are not subject to safety requirements will be painted a non-reflective paint color, Shale Green, from the BLM Standard Environmental Colors chart, unless another color is required in the APD Conditions of Approval.
- D. If any plans change regarding the production facility or other infrastructure (pipeline, electrical lines, etc.), Ameredev will submit a sundry notice or right-of-way (if applicable) prior to installation or construction.

Ameredev Operating, LLC
 Nandina Fed Com 25 36 31 073H
 Section 31, Township 25S, Range 36E
 Lea County, New Mexico







-  Flowline
-  Reclaimed Area
-  Road
-  Top Soil

Exhibit 3 – Well Site Diagram

Section 5 - Location and Types of Water Supply

- A. This location will be drilled using a combination of water and mud systems (outlined in the Drilling Program). The water will be obtained from preexisting water wells, by running a pump directly to the drilling rig. See *Exhibit 4 - Water Wells*, for a list of available water wells. In cases where a polyline is used to transport water for drilling or completion purposes, the existing and proposed roads into location will be utilized.

<u>Permit #</u>	<u>Well Name</u>	<u>Location (Lat/Lon)</u>
CP 1049 POD 2	Bennett	32°04'14.32" N, 103°12'32.30" W
CP 1378	S. Eppenour	32°05'40.62" N, 103°13' 35.26" W
CP 1285	Sec. 5	32°03'56.50" N, 103°17'37.04" W
CP 857	Capped	32°04'39.70" N, 103°16'51.13" W
C 2287	#1	32°03'59.0" N, 103°33'16.8" W
C 2286	#2	32°03'59.2" N, 103°33'15.2" W
C 2290	#3	32°04'1.0" N, 103°33' 12.6" W
C 2285	#4	32°04'3.7" N, 103°33'9.7" W
C 2288	#5	32°04'0.5" N, 103°33'8.4" W
C 2294	Garden	32°03'3.2" N, 103°32'38.1" W
C 2293	House	32°03'2.3" N, 103°32'36.8" W
J-11-S-3	Farm Well #2	32°03'08.4" N, 103°16'35.2" W
J-11-S-2	Farm Well #3	32°03'11.5" N, 103°17'02.0" W
J-11-S	Farm Well #4	32°03'24.6" N, 103°17'02.1" W
CP 1170 POD 1	CB 1	32°03'57.2" N, 103°18'45.3" W
CP 1170 POD 5		32°07'17.1" N, 103°17'48.0" W
CP 1263 POD 5	CB 2	32°03'56.27" N, 103°18'27.4" W
CP 1263 POD 3	CB 3	32°03'54.90" N, 103°18'16.74" W
CP 1351 POD 1	CB 4	32°03'57.16" N, 103°17'45.13" W
CP 1351 POD 2	CB 5	32°03'30.70" N, 103°17'45.70" W
J 26	Ryan	32°01'20.41" N, 103°15'49.46" W
J 3		32°02'41.5" N, 103°18'55.8" W

Exhibit 4 – Water Wells

Section 6 – Construction/Construction Materials

- A. Caliche will be obtained from the caliche pit located at Lat: 32° 6'28.78"N, Long: 103°16'58.77"W or the caliche pit at Lat: 32° 6'33.14"N, Long: 103°18'44.16"W or the caliche pit at Lat: 32° 3'8.30"N, Long: 103°13'57.00"W.
- B. Caliche utilized for the drilling pad will be obtained either from the locations listed above, an existing approved mineral pit, or by benching into a hill, which will allow the pad to be level with existing caliche from the cut, or extracted by "flipping" the well location. A mineral material permit will be obtained from the BLM prior to excavating any caliche on Federal Lands. Amount will vary for each pad. The procedure for "flipping" a well location is as follows:
1. An adequate amount of topsoil/root zone (usually top 6 inches of soil) will be stripped from the proposed well location and stockpiled along the side of the well location as depicted on the *Exhibit 3 - Well Site Diagram*.
 2. An area will be used within the proposed well site dimensions to excavate caliche.
 3. Subsoil will be removed and stockpiled within the surveyed well pad dimensions.
 4. Once caliche/surfacing mineral is found, the mineral material will be excavated and stock piled within the approved drilling pad dimensions.
 5. Subsoil will then be pushed back in the excavated hole and caliche will be spread accordingly across the entire well pad and road (if available).
 6. Neither caliche, nor subsoil will be stockpiled outside of the well pad dimensions. Topsoil will be stockpiled along the edge of the pad as depicted in *Exhibit 5 – Enlarged Well Site Diagram*.
 7. In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit or other established mineral pit. A BLM mineral material permit will be acquired prior to obtaining any mineral material from BLM pits or federal land.




Exhibit 5 – Enlarged Well Site Diagram

Section 7 - Methods of Handling Waste

- A. Drill cuttings, mud, salts and other chemicals will be properly disposed of into steel tanks on site and hauled to a State approved commercial disposal facility.
- B. Garbage and trash produced during drilling and completion operations will be collected in a portable metal trash container and disposed of properly at a state approved disposal facility. All trash on and around the well site will be collected for disposal.
- C. Human waste and grey water will be properly contained and disposed of properly at a state approved disposal facility.
- D. After drilling and completion operations, trash, chemicals, salts, frac sand and other waste material will be removed and disposed of properly at a state approved disposal facility.

Section 8 - Ancillary Facilities

- A. No ancillary facilities will be needed for the proposed project.

Section 9 - Well Site Layout

- A. See *Exhibit 3 - Well Site Diagram* and *Exhibit 5 – Enlarged Well Site Diagram*. The following information is presented:
1. Reasonable scale
 2. Well pad dimensions/orientation
 3. Drilling rig components/layout
 4. Proposed access road
 5. Topsoil stockpile
- B. The proposed drilling pad was staked and surveyed by a professional surveyor. The attached survey plat of the well site depicts the drilling pad layout as staked.
- C. Topsoil salvaging
1. Grass, forbs, and small woody vegetation such as mesquite will be excavated as the topsoil is removed. Large woody vegetation will be stripped and stored separately and re-spread evenly on the site following topsoil re-spreading. Topsoil depth is defined as the top layer of soil that contains 80% of the roots. In areas to be heavily disturbed, the top 6 inches of soil material will be stripped and stockpiled on the perimeter of the well location and along the perimeter of the access road to control run-on and run-off, to keep topsoil viable, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil should include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils. Contaminated soil will not be stockpiled, but properly treated and handled prior to topsoil salvaging.

Section 10 - Plans for Final Surface Reclamation

Reclamation Objectives

- A. The objective of interim reclamation is to restore vegetative cover and a portion of the landform sufficient to maintain healthy, biologically active topsoil, to control erosion, and to minimize habitat and forage loss, visual impact, and weed infestation during the life of the well or facilities.
- B. The long-term objective of final reclamation is to return the land to a condition similar to what existed prior to disturbance. This includes restoration of the landform and natural vegetative community, hydrologic systems, visual resources, and wildlife habitats. To ensure that the long-term objective will be reached through human and natural processes, actions will be taken to ensure standards are met for site stability, visual quality, hydrological functioning, and vegetative productivity.
- C. The BLM will be notified at least 3 days prior to the commencement of any reclamation procedures.

- D. If circumstances allow, interim reclamation and/or final reclamation actions will be completed no later than 6 months from when the final well on location has been completed or plugged. Ameredev will gain written permission from the BLM if more time is needed.
- E. Interim reclamation will be performed on the well site after the well is drilled and completed. *Exhibit 3 – Well Site Diagram* and *Exhibit 5 – Enlarged Well Site Diagram* depict the location and dimension of the planned interim reclamation for the well site.

Interim Reclamation Procedures (if performed)

- A. Within 30 days of well completion, the well location and surrounding areas will be cleared of, and maintained free of, all materials, trash, and equipment not required for production.
- B. In areas planned for interim reclamation, all the surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.
- C. The areas planned for interim reclamation will then be contoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Where applicable, the fill material of the well pad will be backfilled into the cut to bring the area back to the original contour. The interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 Ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be re-contoured to the above ratios during interim reclamation.
- D. Topsoil will be evenly re-spread and aggressively revegetated over the entire disturbed area not needed for all-weather operations, including cuts and fills. To seed the area, the proper BLM mixture, free of noxious weeds, will be used. Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting, in order to break the soil crust and create seed germination micro-sites.
- E. Proper erosion control methods will be used on the area to control erosion, runoff, and siltation of the surrounding area.
- F. The interim reclamation will be monitored periodically to ensure that vegetation has reestablished and that erosion is controlled.

Final Reclamation Procedures (well pad, buried pipelines, etc.)

- A. Prior to final reclamation procedures, the well pad, road, and surrounding area will be cleared of material, trash, and equipment.
- B. All surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.
- C. All disturbed areas, including roads, pipelines, pads, production facilities, and interim reclaimed areas will be re-contoured to the contour existing prior to initial construction or a contour that blends indistinguishably with the surrounding landscape. Topsoil that was spread over the interim reclamation areas will be stockpiled prior to re-contouring. The topsoil will be redistributed evenly over the entire disturbed site to ensure successful revegetation.
- D. After all the disturbed areas have been properly prepared, the areas will be seeded with the proper BLM seed mixture, free of noxious weeds. Final seedbed preparation will consist of

**Ameredev Operating, LLC
Nandina Fed Com 25 36 31 073H
Section 31, Township 25S, Range 36E
Lea County, New Mexico**

AMEREDEV

contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting, in order to break the soil crust and create seed germination micro-sites.

- E. Proper erosion control methods will be used on the area to control erosion, runoff, and siltation of the surrounding area.
- F. All unused equipment and structures including pipelines, electric line poles, tanks, etc. that serviced the well will be removed.
- G. All reclaimed areas will be monitored periodically to ensure that revegetation occurs, that the area is not re-disturbed, and that erosion is controlled.

Section 11 - Surface Ownership

- A. BLM has surface ownership for proposed project area.

Section 12 - Other Information

- A. There are no dwellings within 1 mile of this location.
- B. An on-site meeting for Ameredev's Nandina Fed Com 25 36 31 073H well was held on July 23, 2018 (NOS ID#: 10400030258).
- C. The well pad described in this document - Nandina/Golden Bell (NAN/GB #3N) - will contain 6 wells that produce into an existing central tank battery (CTB) located northeast of the well pad. The wells share a common pad access road, pipeline easement, and electrical corridor. The six flowlines from the individual wells will share a common corridor that will terminate into the CTB. The wells that share the pad are:
 - Nandina Fed Com 25 36 31 073H
 - Nandina Fed Com 25 36 31 083H
 - Nandina Fed Com 25 36 31 093H
 - Nandina Fed Com 25 36 31 103H
 - Nandina Fed Com 25 36 31 113H
 - Nandina Fed Com 25 36 31 123H

Ameredev field representative:

Zac Boyd, Operations Supervisor

Cell: (432) 385-6996

Email: zboyd@ameredev.com

Ameredev office contact:

Christie Hanna, Regulatory Coordinator

Direct: (737) 300-4723

Email: channa@ameredev.com

Ameredev Operating, LLC Address: 5707 Southwest Parkway Building 1, Suite 275 Austin, Texas 78735



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

PWD Data Report

07/10/2019

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data Report

07/10/2019

Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB001478

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: