

HOBBS OCD

FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

MAR 02 2020

APPLICATION FOR PERMIT TO DRILL OR REENTER

RECEIVED

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM137470
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator AMEREDEV OPERATING LLC (772224)		8. Lease Name and Well No. HOLLY FED COM 26 36 05 114H (726926)
3a. Address 5707 Southwest Parkway, Building 1, Suite 275 Austin TX	3b. Phone No. (include area code) (737)300-4700	9. API Well No. 30-025-4674
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface LOT C / 230 FNL / 2280 FWL / LAT 32.0789462 / LONG -103.2883135 At proposed prod. zone LOT N / 50 FSL / 2440 FWL / LAT 32.05068 / LONG -103.28775		10. Field and Pool, or Exploratory JAL WOLFCAMP WEST 98234
11. Sec., T. R. M. or Blk. and Survey or Area SEC 5 / T26S / R36E / NMP		
14. Distance in miles and direction from nearest town or post office* 6.5 miles		12. County or Parish LEA
13. State NM		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 230 feet	16. No of acres in lease 440	17. Spacing Unit dedicated to this well 320
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 815 feet	19. Proposed Depth 11702 feet / 22449 feet	20. BLM/BIA Bond No. in file FED: NMB001478
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3003 feet	22. Approximate date work will start* 10/01/2019	23. Estimated duration 90 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification.  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM.            |

25. Signature (Electronic Submission)	Name (Printed/Typed) Curtis Johnson2 / Ph: (303)236-2269	Date 07/22/2019
Title Nexgen Developer		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	Date 02/26/2020
Title Assistant Field Manager Lands & Minerals		
Office CARLSBAD		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

GCP Rec 03/04/2020

K-2  
03/06/2020

APPROVED WITH CONDITIONS

## PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

<b>OPERATOR'S NAME:</b>	Ameredev Operating LLC
<b>WELL NAME &amp; NO.:</b>	Holly Fed Com 26 36 05 114
<b>SURFACE HOLE FOOTAGE:</b>	230 FNL / 2280 FWL
<b>BOTTOM HOLE FOOTAGE:</b>	50 FSL / 2440 FWL
<b>LOCATION:</b>	Sec 5 / T26S / R36E / NMP
<b>COUNTY:</b>	Lea, NM

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input type="radio"/> Multibowl	<input checked="" type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input checked="" type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

### A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

### B. CASING

1. The 13-3/8 inch surface casing shall be set at approximately \_ feet (a minimum of 25 feet (Lea County) into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of 8 hours or 500 pounds compressive strength, whichever is greater. (This is to

- include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
- a. Cement should tie-back at least **50 feet** on top of Capitan Reef top. If cement does not circulate see B.1.a, c-d above.
3. The minimum required fill of cement behind the 7-5/8 inch intermediate casing is: Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.
- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
  - b. Second stage above DV tool:
    - Cement to surface. If cement does not circulate, contact the appropriate BLM office.
- ❖ In Capitan Reef Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
- ❖ **Special Capitan Reef requirements.** If lost circulation (50% or greater) occurs below the Base of the Salt, the operator shall do the following:
- Switch to fresh water mud to protect the Capitan Reef and use fresh water mud until setting the intermediate casing. The appropriate BLM office is to be notified for a PET to witness the switch to fresh water.
  - Daily drilling reports from the Base of the Salt to the setting of the intermediate casing are to be submitted to the BLM CFO engineering staff via e-mail by 0800 hours each morning. Any lost circulation encountered is to be recorded on these drilling reports. The daily drilling report should show mud volume per shift/tour. Failure to submit these reports will result in an Incidence of Non-Compliance being issued for failure to comply with the Conditions of Approval. If not already planned, the operator shall run a caliper survey for the intermediate well bore and submit to the appropriate BLM office.

- ❖ **If alternate four-string casing design is utilized**, freshwater-based mud shall be used across the capitan interval.

4. The minimum required fill of cement behind the 5-1/2 inch production casing is:
  - Cement should tie-back at least **50 feet** on top of Capitan Reef top. If cement does not circulate see B.1.a, c-d above.

### **C. PRESSURE CONTROL**

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **10,000 (10M) psi. Variance is approved to use a 5000 (5M) Annular which shall be tested to 5000 (5M) psi.**
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

### **D. SPECIAL REQUIREMENT (S)**

#### **Communitization Agreement**

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

## GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on

which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.

7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

**B. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.

- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.



- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.



**U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT**

## Operator Certification Data Report

02/26/2020

### Operator Certification

*I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.*

**NAME:** Christie Hanna

**Signed on:** 07/22/2019

**Title:** Senior Engineering Technician

**Street Address:** 5707 SOUTHWEST PKWY BLDG 1 STE 275

**City:** AUSTIN

**State:** TX

**Zip:** 78735

**Phone:** (737)300-4723

**Email address:** channa@ameredev.com

### Field Representative

**Representative Name:**

**Street Address:** 5707 SOUTHWEST PKWY., BLDG. 1 #275

**City:** AUSTIN

**State:** TX

**Zip:** 78735

**Phone:** (580)940-5054

**Email address:** zboyd@ameredev.com



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Application Data Report

02/26/2020

APD ID: 10400043719

Submission Date: 07/22/2019

Operator Name: AMEREDEV OPERATING LLC

Well Name: HOLLY FED COM 26 36 05

Well Number: 114H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

### Section 1 - General

APD ID: 10400043719

Tie to previous NOS? N

Submission Date: 07/22/2019

BLM Office: CARLSBAD

User: Christie Hanna

Title: Senior Engineering Technician

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM137470

Lease Acres: 440

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? NO

Permitting Agent? NO

APD Operator: AMEREDEV OPERATING LLC

Operator letter of designation:

### Operator Info

Operator Organization Name: AMEREDEV OPERATING LLC

Operator Address: 5707 Southwest Parkway, Building 1, Suite 275

Zip: 78735

Operator PO Box:

Operator City: Austin

State: TX

Operator Phone: (737)300-4700

Operator Internet Address:

### Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: HOLLY FED COM 26 36 05

Well Number: 114H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: JAL

Pool Name: WOLFCAMP  
WEST

Is the proposed well in an area containing other mineral resources? USEABLE WATER NATURAL GAS CO2 OIL

**Operator Name:** AMEREDEV OPERATING LLC

**Well Name:** HOLLY FED COM 26 36 05

**Well Number:** 114H

**Is the proposed well in an area containing other mineral resources?** USEABLE WATER,NATURAL GAS,CO2,OIL

**Is the proposed well in a Helium production area?** N    **Use Existing Well Pad?** NO    **New surface disturbance?**

**Type of Well Pad:** MULTIPLE WELL

**Multiple Well Pad Name:**

**Number:** 5S

**Well Class:** HORIZONTAL

RB/HOL

**Number of Legs:** 1

**Well Work Type:** Drill

**Well Type:** OIL WELL

**Describe Well Type:**

**Well sub-Type:** INFILL

**Describe sub-type:**

**Distance to town:** 6.5 Miles

**Distance to nearest well:** 815 FT

**Distance to lease line:** 230 FT

**Reservoir well spacing assigned acres Measurement:** 320 Acres

**Well plat:** HOLLY\_FED\_COM\_26\_36\_05\_114H\_\_\_BLM\_LEASE\_MAP\_20190715155139.pdf

HOLLY\_FED\_COM\_26\_36\_05\_114H\_\_\_EXH\_2AB\_20190715155140.pdf

HOLLY\_FED\_COM\_26\_36\_05\_114H\_\_\_VICINITY\_MAP\_20190715155140.pdf

HOLLY\_FED\_COM\_26\_36\_05\_114H\_\_\_C\_102\_SIG\_20190722130236.pdf

HOLLY\_FED\_COM\_26\_36\_05\_114H\_\_\_WELLSITE\_20190722130303.pdf

HOLLY\_FED\_COM\_26\_36\_05\_114H\_\_\_GAS\_CAPTURE\_PLAN\_20190722130342.pdf

**Well work start Date:** 10/01/2019

**Duration:** 90 DAYS

### Section 3 - Well Location Table

**Survey Type:** RECTANGULAR

**Describe Survey Type:**

**Datum:** NAD83

**Vertical Datum:** NAVD88

**Survey number:** 18329

**Reference Datum:**

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
----------	---------	--------------	---------	--------------	------	-------	---------	-------------------	----------	-----------	--------	-------	----------	------------	--------------	-----------	----	-----	---

Operator Name: AMEREDEV OPERATING LLC

Well Name: HOLLY FED COM 26 36 05

Well Number: 114H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
SHL Leg #1	230	FNL	2280	FWL	26S	36E	5	Lot C	32.0789462	-103.2883135	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 137470	3003	0	0	
KOP Leg #1	401	FSL	2441	FWL	25S	36E	32	Aliquot SESW	32.08067	-103.28777	LEA	NEW MEXICO	NEW MEXICO	F	FEE	-8197	11233	11200	
PPP Leg #1-1	1320	FSL	2359	FWL	26S	36E	5	Aliquot SESW	32.06869	-103.28817	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 006727	-8699	15897	11702	
PPP Leg #1-2	2640	FSL	2318	FEL	25S	36E	31	Aliquot NWSE	32.0868361	-103.3031625	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 119762	-9422	14672	12425	
PPP Leg #1-3	1320	FSL	2318	FEL	25S	36E	31	Aliquot SWSE	32.0832079	-103.3031615	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 137469	-9422	13352	12425	
PPP Leg #1-4	1320	FSL	2318	FEL	25S	36E	30	Aliquot SWSE	32.0977169	-103.3031656	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 137469	-9422	18630	12425	
PPP Leg #1-5	0	FNL	2373	FWL	26S	36E	8	Aliquot NENW	32.06506	-103.28817	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 137473	-8699	17217	11702	
PPP Leg #1-6	100	FNL	2317	FWL	26S	36E	5	Aliquot NENW	32.0793	-103.28779	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 137470	-8699	12037	11702	
PPP Leg #1-7	0	FNL	2318	FEL	25S	36E	30	Aliquot SWSE	32.0940887	-103.3031645	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 137469	-9422	17310	12425	
PPP Leg #1-8	0	FSL	2318	FEL	25S	36E	31	Aliquot NWNE	32.0940887	-103.3031645	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 137469	-9422	17310	12425	
EXIT Leg #1	50	FSL	2440	FWL	26S	36E	8	Aliquot SESW	32.05068	-103.28775	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 137473	-8699	22449	11702	
BHL Leg #1	50	FSL	2440	FWL	26S	36E	8	Lot N	32.05068	-103.28775	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 137473	-8699	22449	11702	



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Drilling Plan Data Report

02/26/2020

APD ID: 10400043719

Submission Date: 07/22/2019

Operator Name: AMEREDEV OPERATING LLC

Well Name: HOLLY FED COM 26 36 05

Well Number: 114H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
498447	RUSTLER ANHYDRITE	3003	1172	1172	ANHYDRITE	NONE	N
498448	SALADO	1366	1637	1637	SALT	NONE	N
498449	TANSILL	-410	3413	3413	LIMESTONE	NONE	N
502743	CAPITAN REEF	-873	3876	3876	LIMESTONE	USEABLE WATER	N
498450	LAMAR	-2071	5074	5074	LIMESTONE	NONE	N
498451	BELL CANYON	-2203	5206	5206	SANDSTONE	NATURAL GAS, OIL	N
498452	BRUSHY CANYON	-4102	7105	7105	SANDSTONE	NATURAL GAS, OIL	N
498453	BONE SPRING LIME	-5151	8154	8154	LIMESTONE	NONE	N
498454	BONE SPRING 1ST	-6547	9550	9550	SANDSTONE	NATURAL GAS, OIL	N
498455	BONE SPRING 2ND	-7070	10073	10073	SANDSTONE	NATURAL GAS, OIL	N
498456	BONE SPRING 3RD	-7626	10629	10629	LIMESTONE	NATURAL GAS, NONE, OIL	N
498457	BONE SPRING 3RD	-8223	11226	11226	SANDSTONE	NATURAL GAS, OIL	N
498459	WOLFCAMP	-8499	11502	11502	SHALE	NATURAL GAS, OIL	Y

### Section 2 - Blowout Prevention

Operator Name: AMEREDEV OPERATING LLC

Well Name: HOLLY FED COM 26 36 05

Well Number: 114H

Pressure Rating (PSI): 10M

Rating Depth: 15000

Equipment: 10M BOPE SYSTEM WILL BE USED AFTER THE SURFACE CASING IS SET. A KELLY COCK WILL BE KEPT IN THE DRILL STRING AT ALL TIMES. A FULL OPENING DRILL PIPE STABBING VALVE WITH PROPER DRILL PIPE CONNECTIONS WILL BE ON THE RIG FLOOR AT ALL TIMES.

Requesting Variance? YES

Variance request: Co-Flex Choke Line, 5M Annular Preventer

Testing Procedure: See attachment

Choke Diagram Attachment:

10M\_Choke\_Manifold\_REV\_20190722140132.pdf

BOP Diagram Attachment:

5M\_Annular\_Preventer\_Variance\_and\_Well\_Control\_Plan\_20190722140144.pdf

5M\_BOP\_System\_20190722140145.pdf

Pressure\_Control\_Plan\_Single\_Well\_MB4\_3String\_Big\_Hole\_BLM\_20190722140145.pdf

4\_String\_MB\_Ameredev\_Wellhead\_Drawing\_net\_REV\_20190722140158.pdf

### Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	1297	0	1297	3003		1297	J-55	68	OTHER - BTC	7.08	0.61	DRY	10.37	DRY	12.13
2	INTERMEDIATE	9.875	7.625	NEW	API	N	0	11502	0	11502			11502	HCL-80	29.7	OTHER - BTC	1.19	1.24	DRY	1.91	DRY	2.75
3	PRODUCTION	6.75	5.5	NEW	API	N	0	22449	0	11702			22449	P-110	20	OTHER - BTC	1.75	1.89	DRY	2.8	DRY	3.11

Casing Attachments

**Operator Name:** AMEREDEV OPERATING LLC

**Well Name:** HOLLY FED COM 26 36 05

**Well Number:** 114H

### Casing Attachments

---

**Casing ID:** 1      **String Type:** SURFACE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

13.375\_68\_J55\_SEAH\_20190722140817.pdf

Holly\_Fed\_Com\_26\_36\_05\_114H\_\_Wellbore\_Diagram\_and\_CDA\_20190722140827.pdf

---

**Casing ID:** 2      **String Type:** INTERMEDIATE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

7.625\_29.70\_P110HC\_LIBERTY\_FJM\_20190722141109.pdf

Holly\_Fed\_Com\_26\_36\_05\_114H\_\_Wellbore\_Diagram\_and\_CDA\_20190722141120.pdf

---

**Casing ID:** 3      **String Type:** PRODUCTION

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

5.50\_20\_USS\_P110\_HC\_BTC\_API\_20190722141348.pdf

Holly\_Fed\_Com\_26\_36\_05\_114H\_\_Wellbore\_Diagram\_and\_CDA\_20190722141358.pdf



Operator Name: AMEREDEV OPERATING LLC

Well Name: HOLLY FED COM 26 36 05

Well Number: 114H

#### Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	911	615	1.76	13.5	1082.33	50	Class C	Bentonite, Accelerator, Kolseal, Defoamer, Celloflake
SURFACE	Tail		911	1297	200	1.34	14.8	268	100	Class C	Salt
INTERMEDIATE	Lead	3413	0	2173	263	2.47	11.9	649.47	25	Class C	Salt, Bentonite, Kolseal, Defoamer, Celloflake, Anti-Settling Expansion Additive
INTERMEDIATE	Tail		2173	3413	200	1.33	14.8	266	25	Class C	Retarder
INTERMEDIATE	Lead	3413	0	9671	1090	2.47	11.9	2692.2	25	Class H	Bentonite, Salt, Kolseal, Defoamer, Celloflake, Retarder, Anti-Settling
INTERMEDIATE	Tail		9671	11502	300	1.24	14.5	371.1	25	Class H	Salt, Bentonite, Retarder, Dispersant, Fluid Loss
PRODUCTION	Lead		0	22449	1748	1.34	14.2	2341.7	25	Class H	Salt, Bentonite, Fluid Loss, Dispersant, Retarder, Defoamer

#### Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: All necessary supplies (e.g. bentonite, cedar bark) for fluid control will be on site.

Describe the mud monitoring system utilized: An electronic pit volume totalizer (PVT) will be utilized on the circulating system to monitor pit volume, flow rate, pump pressure, and pump rate.

#### Circulating Medium Table

**Operator Name:** AMEREDEV OPERATING LLC

**Well Name:** HOLLY FED COM 26 36 05

**Well Number:** 114H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
1150 2	1170 2	OIL-BASED MUD	10.5	12.5							
0	1297	WATER-BASED MUD	8.4	8.6							
1297	1150 2	OTHER : Diesel Brine Emulsion	8.5	9.4							

### Section 6 - Test, Logging, Coring

**List of production tests including testing procedures, equipment and safety measures:**

A directional survey, measurement while drilling and a mudlog/geologic lithology log will all be run from surface to TD.

**List of open and cased hole logs run in the well:**

DS,MWD,MUDLOG

**Coring operation description for the well:**

No coring will be done on this well.

### Section 7 - Pressure

**Anticipated Bottom Hole Pressure:** 7606

**Anticipated Surface Pressure:** 4872.5

**Anticipated Bottom Hole Temperature(F):** 165

**Anticipated abnormal pressures, temperatures, or potential geologic hazards?** NO

**Describe:**

**Contingency Plans geohazards description:**

**Contingency Plans geohazards attachment:**

**Hydrogen Sulfide drilling operations plan required?** YES

**Hydrogen sulfide drilling operations plan:**

H2S\_Plan\_20190722143339.pdf

**Operator Name:** AMEREDEV OPERATING LLC

**Well Name:** HOLLY FED COM 26 36 05

**Well Number:** 114H

## **Section 8 - Other Information**

### **Proposed horizontal/directional/multi-lateral plan submission:**

Hol114\_DR\_20190722143357.pdf

Hol114\_LLRR\_20190722143357.pdf

5M\_Annular\_Preventer\_Variance\_and\_Well\_Control\_Plan\_20190722143412.pdf

Pressure\_Control\_Plan\_Single\_Well\_MB4\_3String\_Big\_Hole\_BLM\_20190722143412.pdf

### **Other proposed operations facets description:**

4-STRING CONTINGENCY PLAN AND SKID PROCEDURE ATTACHED

### **Other proposed operations facets attachment:**

CAPITAN\_PROTECTION\_CONTINGENCY\_PLAN\_WC\_PACKET\_20190606\_20190722143429.pdf

Rig\_Skid\_Procedure\_20190722143438.pdf

### **Other Variance attachment:**

R616\_\_CoC\_for\_hoses\_12\_18\_17\_20190722143502.pdf

Requested\_Exceptions\_\_3\_String\_Revised\_01312019\_20190722143503.pdf


13 5/8" 5M BOP  
Configuration

CO-FLEX LINE TO  
CHOKE MANIFOLD

2" KILL LINE

4" 10M VALVES &

10M Check Valve



**Wellbore Schematic**

**Well:** Holly Fed Com 26-36-05 114H  
**SHL:** Sec. 05 26S-36E 230' FNL & 2280' FWL  
**BHL:** Sec. 08 26S-36E 50' FSL & 2440' FWL  
 Lea, NM  
**Wellhead:** A - 13-5/8" 10M x 13-5/8" SOW  
 B - 13-5/8" 10M x 13-5/8" 10M  
 C - 13-5/8" 10M x 13-5/8" 10M  
 Tubing Spool - 5-1/8" 15M x 13-3/8" 10M  
**Xmas Tree:** 2-9/16" 10M  
**Tubing:** 2-7/8" L-80 6.5# 8rd EUE

**Co. Well ID:** xxxxxx  
**AFE No.:** xxxx-xxx  
**API No.:** xxxxxxxxxxxx  
**GL:** 3,003'  
**Field:** Delaware  
**Objective:** Wolfcamp A  
**TVD:** 11,702'  
**MD:** 22,449'  
**Rig:** TBD **KB:** 27'  
**E-Mail:** Wellsite2@ameredev.com

Hole Size	Formation Tops	Logs Cement	Mud Weight
17.5"	Rustler 1,172'	815 Sacks TOC 0' 50% Excess	8.4-8.6 ppg WBM
	13.375" 68# J-55 BTC 1,297'		
9.875"	Salado 1,637'	463 Sacks TOC 0' 25% Excess	8.5 - 9.4 ppg Diesel Brine Emulsion
	DV Tool 3,413'		
	Tansill 3,413'		
	Capitan Reef 3,876'		
	Lamar 5,074'		
	Bell Canyon 5,206'		
	Brushy Canyon 7,105'		
	Bone Spring Lime 8,154'		
	First Bone Spring 9,550'		
	Second Bone Spring 10,073'		
	Third Bone Spring Upper 10,629'	1,390 Sacks TOC 0' 25% Excess	10.5 - 12.5 ppg OBM
	Third Bone Spring 11,226'		
	7.625" 29.7# L-80HC BTC 11,502'		
	Wolfcamp A 11,502'		
6.75"			
12° Build @ 11,233' MD thru 12,037' MD	5.5" 20# P-110 USS RYS SF 22,449' Target Wolfcamp A 11702 TVD // 22449 MD	1,748 Sacks TOC 0' 25% Excess	

## Casing Design and Safety Factor Check

<b>Casing Specifications</b>						
<b>Segment</b>	<b>Hole ID</b>	<b>Depth</b>	<b>OD</b>	<b>Weight</b>	<b>Grade</b>	<b>Coupling</b>
Surface	17.5	1,297'	13.375	68	J-55	BTC
Intermediate	9.875	11,502'	7.625	40	HCL-80	BTC
Prod Segment A	6.75	11,233'	5.5	20	CYHP-110	BTC
Prod Segment B	6.75	22,449'	5.5	20	CYHP-110	BTC

<b>Check Surface Casing</b>				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
14.375	1,069	915	4,100	3,450
<b>Safety Factors</b>				
1.56	12.13	10.37	7.08	0.61
<b>Check Intermediate Casing</b>				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
7.625	940	558	6700	9460
<b>Safety Factors</b>				
1.13	2.75	1.91	1.19	1.24
<b>Check Prod Casing, Segment A</b>				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
<b>Safety Factors</b>				
0.49	3.11	2.80	1.75	1.89
<b>Check Prod Casing, Segment B</b>				
OD Cplg	Body	Joint	Collapse	Burst
<i>inches</i>	<i>1000 lbs</i>	<i>1000 lbs</i>	<i>psi</i>	<i>psi</i>
5.777	728	655	12780	14360
<b>Safety Factors</b>				
0.49	77.61	69.83	1.68	1.89

## H<sub>2</sub>S Drilling Operation Plan

1. **All Company and Contract personnel admitted on location must be trained by a qualified H<sub>2</sub>S safety instructor to the following:**
  - a. Characteristics of H<sub>2</sub>S
  - b. Physical effects and hazards
  - c. Principal and operation of H<sub>2</sub>S detectors, warning system and briefing areas
  - d. Evacuation procedure, routes and first aid
  - e. Proper use of safety equipment and life support systems
  - f. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.
2. **Briefing Area:**
  - a. Two perpendicular areas will be designated by signs and readily accessible.
  - b. Upon location entry there will be a designated area to establish all safety compliance criteria (1.) has been met.
3. **H<sub>2</sub>S Detection and Alarm Systems:**
  - a. H<sub>2</sub>S sensors/detectors shall be located on the drilling rig floor, in the base of the sub structure/cellar area, and on the mud pits in the shale shaker area. Additional H<sub>2</sub>S detectors may be placed as deemed necessary. All detectors will be set to initiate visual alarm at 10 ppm and visual with audible at 14 ppm and all equipment will be calibrated every 30 days or as needed.
  - b. An audio alarm will be installed on the derrick floor and in the top doghouse.
4. **Protective Equipment for Essential Personnel:**
  - a. **Breathing Apparatus:**
    - i. Rescue Packs (SCBA) - 1 Unit shall be placed at each briefing area.
    - ii. Two (SCBA) Units will be stored in safety trailer on location.
    - iii. Work/Escapes packs - 1 Unit will be available on rig floor in doghouse for emergency evacuation for driller.
  - b. **Auxiliary Rescue Equipment:**
    - i. Stretcher
    - ii. 2 - OSHA full body harnesses
    - iii. 100 ft. 5/8" OSHA approved rope
    - iv. 1 - 20# class ABC fire extinguisher
5. **Windsock and/or Wind Streamers:**
  - a. Windsock at mud pit area should be high enough to be visible.
  - b. Windsock on the rig floor should be high enough to be visible.
6. **Communication:**
  - a. While working under mask scripting boards will be used for communication where applicable.
  - b. Hand signals will be used when script boards are not applicable.

## H<sub>2</sub>S Drilling Operation Plan

- c. Two way radios will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at Drilling Foreman's Office.
- 7. **Drill Stem Testing:** - No Planned DST at this time.
- 8. **Mud program:**
  - a. If H<sub>2</sub>S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H<sub>2</sub>S scavengers if necessary.
- 9. **Metallurgy:**
  - a. All drill strings, casing, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H<sub>2</sub>S service.
  - b. Drilling Contractor supervisor will be required to be familiar with the effect H<sub>2</sub>S has on tubular goods and other mechanical equipment provided through contractor.



## H<sub>2</sub>S Contingency Plan

### Emergency Procedures

In the event of a release of H<sub>2</sub>S, the first responder(s) must:

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE.
- Be equipped with H<sub>2</sub>S monitors and air packs in order to control the release.
- Use the "buddy system" to ensure no injuries occur during the response.
- Take precautions to avoid personal injury during this operation.
- Contact Operator and/or local officials the aid in operation. See list of phone numbers attached.
- Have received training in the:
  - Detection of H<sub>2</sub>S and
  - Measures for protection against the gas,
  - Equipment used for protection and emergency response.

### Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

### Characteristics of H<sub>2</sub>S and SO<sub>2</sub>

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H <sub>2</sub> S	1.189 Air=1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO <sub>2</sub>	2.21 Air=1	2 ppm	N/A	1000 ppm

### Contacting Authorities

Ameredev Operating LLC personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including direction to site. The following call list of essential and potential responders has been prepared for use during a release. Ameredev Operating LLC's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER)

**H<sub>2</sub>S Contingency Plan****Ameredev Operating LLC – Emergency Phone 737-300-4799****Key Personnel:**

Name	Title	Office	Mobile
Floyd Hammond	Chief Operating officer	737-300-4724	512-783-6810
Zachary Boyd	Operations Superintendent	737-300-4725	432-385-6996
Blake Estrada	Construction Foreman		432-385-5831

**Artesia**

Ambulance	911
State Police	575-746-2703
City Police	575-746-2703
Sheriff's Office	575-746-9888
Fire Department	575-746-2701
Local Emergency Planning Committee	575-746-2122
New Mexico Oil Conservation Division	575-748-1283

**Carlsbad**

Ambulance	911
State Police	575-885-3137
City Police	575-885-2111
Sheriff's Office	575-887-7551
Fire Department	575-887-3798
Local Emergency Planning Committee	575-887-6544
US Bureau of Land Management	575-887-6544

**Santa Fe**

New Mexico Emergency Response Commission (Santa Fe)	505-476-9600
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs	505-827-9126
New Mexico State Emergency Operations Center	505-476-9635

**National**

National Emergency Response Center (Washington, D.C.)	800-424-8802
---	--------------

**Medical**

Flight for Life - 4000 24th St.; Lubbock, TX	806-743-9911
Aerocare - R3, Box 49F; Lubbock, TX	806-747-8923
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM	505-842-4433
'SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM	505-842-4949



## **Ameredev Operating, LLC.**

**RB/HOL**

**RB/HOL #5S**

**Holly 114H**

**Wellbore #1**

**Plan: Design #1**

## **Standard Planning Report**

**21 February, 2019**

Database:	EDM5000	Local Co-ordinate Reference:	Well Holly 114H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3030.0usft
Project:	RB/HOL	MD Reference:	KB @ 3030.0usft
Site:	RB/HOL #5S	North Reference:	Grid
Well:	Holly 114H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	RB/HOL		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	RB/HOL #5S				
Site Position:		Northing:	394,025.36 usft	Latitude:	32° 4' 44.206 N
From:	Lat/Long	Easting:	864,991.18 usft	Longitude:	103° 17' 18.161 W
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.56 °

Well	Holly 114H					
Well Position	+N/-S	0.2 usft	Northing:	394,025.56 usft	Latitude:	32° 4' 44.206 N
	+E/-W	20.0 usft	Easting:	865,011.18 usft	Longitude:	103° 17' 17.929 W
Position Uncertainty		0.0 usft	Wellhead Elevation:		Ground Level:	3,003.0 usft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2015	2/19/2019	6.63	59.95	47,712.02244477

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	179.16

Plan Survey Tool Program	Date	2/21/2019		
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks
1	0.0	22,448.1	Design #1 (Wellbore #1)	MWD
				OWSG MWD - Standard

<b>Database:</b>	EDM5000	<b>Local Co-ordinate Reference:</b>	Well Holly 114H
<b>Company:</b>	Ameredev Operating, LLC.	<b>TVD Reference:</b>	KB @ 3030.0usft
<b>Project:</b>	RB/HOL	<b>MD Reference:</b>	KB @ 3030.0usft
<b>Site:</b>	RB/HOL #5S	<b>North Reference:</b>	Grid
<b>Well:</b>	Holly 114H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Design #1		

**Plan Sections**

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,300.0	6.00	15.00	2,299.5	15.2	4.1	2.00	2.00	0.00	15.00	
6,724.8	6.00	15.00	6,700.0	461.9	123.8	0.00	0.00	0.00	0.00	
7,024.8	0.00	0.00	6,999.5	477.1	127.8	2.00	-2.00	0.00	180.00	
8,525.3	0.00	0.00	8,500.0	477.1	127.8	0.00	0.00	0.00	0.00	
8,825.3	6.00	12.00	8,799.5	492.4	131.1	2.00	2.00	0.00	12.00	
10,032.5	6.00	12.00	10,000.0	615.9	157.3	0.00	0.00	0.00	0.00	
10,332.5	0.00	0.00	10,299.5	631.2	160.6	2.00	-2.00	0.00	180.00	
11,233.0	0.00	0.00	11,200.0	631.2	160.6	0.00	0.00	0.00	0.00	
11,611.9	44.94	204.81	11,541.2	503.1	101.4	11.86	11.86	0.00	204.81	
12,036.6	90.00	179.38	11,702.0	130.3	36.5	11.86	10.61	-5.99	-33.89	Hol114 FTP
22,449.0	90.00	179.38	11,702.0	-10,281.5	150.1	0.00	0.00	0.00	0.00	Hol114 BHL

Database: EDM5000  
Company: Ameredev Operating, LLC.  
Project: RB/HOL  
Site: RB/HOL #5S  
Well: Holly 114H  
Wellbore: Wellbore #1  
Design: Design #1

Local Co-ordinate Reference: Well Holly 114H  
TVD Reference: KB @ 3030.0usft  
MD Reference: KB @ 3030.0usft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	2.00	15.00	2,100.0	1.7	0.5	-1.7	2.00	2.00	0.00
2,200.0	4.00	15.00	2,199.8	6.7	1.8	-6.7	2.00	2.00	0.00
2,300.0	6.00	15.00	2,299.5	15.2	4.1	-15.1	2.00	2.00	0.00
2,400.0	6.00	15.00	2,398.9	25.3	6.8	-25.2	0.00	0.00	0.00
2,500.0	6.00	15.00	2,498.4	35.4	9.5	-35.2	0.00	0.00	0.00
2,600.0	6.00	15.00	2,597.8	45.4	12.2	-45.3	0.00	0.00	0.00
2,700.0	6.00	15.00	2,697.3	55.5	14.9	-55.3	0.00	0.00	0.00
2,800.0	6.00	15.00	2,796.7	65.6	17.6	-65.4	0.00	0.00	0.00
2,900.0	6.00	15.00	2,896.2	75.7	20.3	-75.4	0.00	0.00	0.00
3,000.0	6.00	15.00	2,995.6	85.8	23.0	-85.5	0.00	0.00	0.00
3,100.0	6.00	15.00	3,095.1	95.9	25.7	-95.5	0.00	0.00	0.00
3,200.0	6.00	15.00	3,194.5	106.0	28.4	-105.6	0.00	0.00	0.00
3,300.0	6.00	15.00	3,294.0	116.1	31.1	-115.7	0.00	0.00	0.00
3,400.0	6.00	15.00	3,393.4	126.2	33.8	-125.7	0.00	0.00	0.00
3,500.0	6.00	15.00	3,492.9	136.3	36.5	-135.8	0.00	0.00	0.00
3,600.0	6.00	15.00	3,592.3	146.4	39.2	-145.8	0.00	0.00	0.00
3,700.0	6.00	15.00	3,691.8	156.5	41.9	-155.9	0.00	0.00	0.00
3,800.0	6.00	15.00	3,791.2	166.6	44.6	-165.9	0.00	0.00	0.00
3,900.0	6.00	15.00	3,890.7	176.7	47.3	-176.0	0.00	0.00	0.00
4,000.0	6.00	15.00	3,990.1	186.8	50.1	-186.1	0.00	0.00	0.00
4,100.0	6.00	15.00	4,089.6	196.9	52.8	-196.1	0.00	0.00	0.00
4,200.0	6.00	15.00	4,189.0	207.0	55.5	-206.2	0.00	0.00	0.00
4,300.0	6.00	15.00	4,288.5	217.1	58.2	-216.2	0.00	0.00	0.00
4,400.0	6.00	15.00	4,387.9	227.2	60.9	-226.3	0.00	0.00	0.00
4,500.0	6.00	15.00	4,487.4	237.3	63.6	-236.3	0.00	0.00	0.00
4,600.0	6.00	15.00	4,586.9	247.4	66.3	-246.4	0.00	0.00	0.00
4,700.0	6.00	15.00	4,686.3	257.5	69.0	-256.4	0.00	0.00	0.00
4,800.0	6.00	15.00	4,785.8	267.6	71.7	-266.5	0.00	0.00	0.00
4,900.0	6.00	15.00	4,885.2	277.7	74.4	-276.6	0.00	0.00	0.00
5,000.0	6.00	15.00	4,984.7	287.8	77.1	-286.6	0.00	0.00	0.00
5,100.0	6.00	15.00	5,084.1	297.9	79.8	-296.7	0.00	0.00	0.00
5,200.0	6.00	15.00	5,183.6	308.0	82.5	-306.7	0.00	0.00	0.00
5,300.0	6.00	15.00	5,283.0	318.1	85.2	-316.8	0.00	0.00	0.00

Database: EDM5000  
Company: Ameredev Operating, LLC.  
Project: RB/HOL  
Site: RB/HOL #5S  
Well: Holly 114H  
Wellbore: Wellbore #1  
Design: Design #1

Local Co-ordinate Reference: Well Holly 114H  
TVD Reference: KB @ 3030.0usft  
MD Reference: KB @ 3030.0usft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,400.0	6.00	15.00	5,382.5	328.2	87.9	-326.8	0.00	0.00	0.00
5,500.0	6.00	15.00	5,481.9	338.3	90.6	-336.9	0.00	0.00	0.00
5,600.0	6.00	15.00	5,581.4	348.3	93.3	-346.9	0.00	0.00	0.00
5,700.0	6.00	15.00	5,680.8	358.4	96.0	-357.0	0.00	0.00	0.00
5,800.0	6.00	15.00	5,780.3	368.5	98.8	-367.1	0.00	0.00	0.00
5,900.0	6.00	15.00	5,879.7	378.6	101.5	-377.1	0.00	0.00	0.00
6,000.0	6.00	15.00	5,979.2	388.7	104.2	-387.2	0.00	0.00	0.00
6,100.0	6.00	15.00	6,078.6	398.8	106.9	-397.2	0.00	0.00	0.00
6,200.0	6.00	15.00	6,178.1	408.9	109.6	-407.3	0.00	0.00	0.00
6,300.0	6.00	15.00	6,277.5	419.0	112.3	-417.3	0.00	0.00	0.00
6,400.0	6.00	15.00	6,377.0	429.1	115.0	-427.4	0.00	0.00	0.00
6,500.0	6.00	15.00	6,476.4	439.2	117.7	-437.5	0.00	0.00	0.00
6,600.0	6.00	15.00	6,575.9	449.3	120.4	-447.5	0.00	0.00	0.00
6,700.0	6.00	15.00	6,675.3	459.4	123.1	-457.6	0.00	0.00	0.00
6,724.8	6.00	15.00	6,700.0	461.9	123.8	-460.1	0.00	0.00	0.00
6,800.0	4.50	15.00	6,774.9	468.6	125.6	-466.7	2.00	-2.00	0.00
6,900.0	2.50	15.00	6,874.7	474.4	127.1	-472.5	2.00	-2.00	0.00
7,000.0	0.50	15.00	6,974.7	477.0	127.8	-475.1	2.00	-2.00	0.00
7,024.8	0.00	0.00	6,999.5	477.1	127.8	-475.2	2.00	-2.00	0.00
7,100.0	0.00	0.00	7,074.7	477.1	127.8	-475.2	0.00	0.00	0.00
7,200.0	0.00	0.00	7,174.7	477.1	127.8	-475.2	0.00	0.00	0.00
7,300.0	0.00	0.00	7,274.7	477.1	127.8	-475.2	0.00	0.00	0.00
7,400.0	0.00	0.00	7,374.7	477.1	127.8	-475.2	0.00	0.00	0.00
7,500.0	0.00	0.00	7,474.7	477.1	127.8	-475.2	0.00	0.00	0.00
7,600.0	0.00	0.00	7,574.7	477.1	127.8	-475.2	0.00	0.00	0.00
7,700.0	0.00	0.00	7,674.7	477.1	127.8	-475.2	0.00	0.00	0.00
7,800.0	0.00	0.00	7,774.7	477.1	127.8	-475.2	0.00	0.00	0.00
7,900.0	0.00	0.00	7,874.7	477.1	127.8	-475.2	0.00	0.00	0.00
8,000.0	0.00	0.00	7,974.7	477.1	127.8	-475.2	0.00	0.00	0.00
8,100.0	0.00	0.00	8,074.7	477.1	127.8	-475.2	0.00	0.00	0.00
8,200.0	0.00	0.00	8,174.7	477.1	127.8	-475.2	0.00	0.00	0.00
8,300.0	0.00	0.00	8,274.7	477.1	127.8	-475.2	0.00	0.00	0.00
8,400.0	0.00	0.00	8,374.7	477.1	127.8	-475.2	0.00	0.00	0.00
8,500.0	0.00	0.00	8,474.7	477.1	127.8	-475.2	0.00	0.00	0.00
8,525.3	0.00	0.00	8,500.0	477.1	127.8	-475.2	0.00	0.00	0.00
8,600.0	1.49	12.00	8,574.7	478.0	128.0	-476.1	2.00	2.00	0.00
8,700.0	3.49	12.00	8,674.6	482.3	128.9	-480.3	2.00	2.00	0.00
8,800.0	5.49	12.00	8,774.2	489.9	130.6	-488.0	2.00	2.00	0.00
8,825.3	6.00	12.00	8,799.5	492.4	131.1	-490.5	2.00	2.00	0.00
8,900.0	6.00	12.00	8,873.7	500.1	132.7	-498.1	0.00	0.00	0.00
9,000.0	6.00	12.00	8,973.2	510.3	134.9	-508.3	0.00	0.00	0.00
9,100.0	6.00	12.00	9,072.6	520.5	137.1	-518.5	0.00	0.00	0.00
9,200.0	6.00	12.00	9,172.1	530.7	139.2	-528.6	0.00	0.00	0.00
9,300.0	6.00	12.00	9,271.5	541.0	141.4	-538.8	0.00	0.00	0.00
9,400.0	6.00	12.00	9,371.0	551.2	143.6	-549.0	0.00	0.00	0.00
9,500.0	6.00	12.00	9,470.4	561.4	145.8	-559.2	0.00	0.00	0.00
9,600.0	6.00	12.00	9,569.9	571.6	147.9	-569.4	0.00	0.00	0.00
9,700.0	6.00	12.00	9,669.3	581.9	150.1	-579.6	0.00	0.00	0.00
9,800.0	6.00	12.00	9,768.8	592.1	152.3	-589.8	0.00	0.00	0.00
9,900.0	6.00	12.00	9,868.2	602.3	154.4	-600.0	0.00	0.00	0.00
10,000.0	6.00	12.00	9,967.7	612.5	156.6	-610.2	0.00	0.00	0.00
10,032.5	6.00	12.00	10,000.0	615.9	157.3	-613.5	0.00	0.00	0.00
10,100.0	4.65	12.00	10,067.2	622.0	158.6	-619.6	2.00	-2.00	0.00
10,200.0	2.65	12.00	10,167.0	628.2	160.0	-625.8	2.00	-2.00	0.00

Database:	EDM5000	Local Co-ordinate Reference:	Well Holly 114H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3030.0usft
Project:	RB/HOL	MD Reference:	KB @ 3030.0usft
Site:	RB/HOL #5S	North Reference:	Grid
Well:	Holly 114H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
10,300.0	0.65	12.00	10,267.0	631.0	160.6	-628.6	2.00	-2.00	0.00	
10,332.5	0.00	0.00	10,299.5	631.2	160.6	-628.8	2.00	-2.00	0.00	
10,400.0	0.00	0.00	10,367.0	631.2	160.6	-628.8	0.00	0.00	0.00	
10,500.0	0.00	0.00	10,467.0	631.2	160.6	-628.8	0.00	0.00	0.00	
10,600.0	0.00	0.00	10,567.0	631.2	160.6	-628.8	0.00	0.00	0.00	
10,700.0	0.00	0.00	10,667.0	631.2	160.6	-628.8	0.00	0.00	0.00	
10,800.0	0.00	0.00	10,767.0	631.2	160.6	-628.8	0.00	0.00	0.00	
10,900.0	0.00	0.00	10,867.0	631.2	160.6	-628.8	0.00	0.00	0.00	
11,000.0	0.00	0.00	10,967.0	631.2	160.6	-628.8	0.00	0.00	0.00	
11,100.0	0.00	0.00	11,067.0	631.2	160.6	-628.8	0.00	0.00	0.00	
11,200.0	0.00	0.00	11,167.0	631.2	160.6	-628.8	0.00	0.00	0.00	
11,233.0	0.00	0.00	11,200.0	631.2	160.6	-628.8	0.00	0.00	0.00	
Hol114 KOP										
11,300.0	7.94	204.81	11,266.7	627.0	158.6	-624.6	11.86	11.86	0.00	
11,400.0	19.80	204.81	11,363.7	605.3	148.6	-603.0	11.86	11.86	0.00	
11,500.0	31.66	204.81	11,453.6	565.9	130.4	-564.0	11.86	11.86	0.00	
11,600.0	43.52	204.81	11,532.7	510.7	104.9	-509.1	11.86	11.86	0.00	
11,611.9	44.94	204.81	11,541.2	503.1	101.4	-501.6	11.86	11.86	0.00	
11,700.0	53.85	197.62	11,598.5	440.8	77.5	-439.6	11.86	10.12	-8.17	
11,800.0	64.38	191.23	11,649.8	357.8	56.4	-356.9	11.86	10.53	-6.38	
11,900.0	75.14	185.90	11,684.4	265.2	42.6	-264.5	11.86	10.76	-5.33	
12,000.0	86.01	181.09	11,700.7	166.9	36.7	-166.3	11.86	10.87	-4.82	
12,036.6	90.00	179.38	11,702.0	130.3	36.5	-129.8	11.86	10.90	-4.68	
Hol114 FTP										
12,100.0	90.00	179.38	11,702.0	66.9	37.2	-66.4	0.00	0.00	0.00	
12,200.0	90.00	179.38	11,702.0	-33.1	38.3	33.6	0.00	0.00	0.00	
12,300.0	90.00	179.38	11,702.0	-133.1	39.4	133.6	0.00	0.00	0.00	
12,400.0	90.00	179.38	11,702.0	-233.1	40.5	233.6	0.00	0.00	0.00	
12,500.0	90.00	179.38	11,702.0	-333.1	41.6	333.6	0.00	0.00	0.00	
12,600.0	90.00	179.38	11,702.0	-433.1	42.7	433.6	0.00	0.00	0.00	
12,700.0	90.00	179.38	11,702.0	-533.0	43.8	533.6	0.00	0.00	0.00	
12,800.0	90.00	179.38	11,702.0	-633.0	44.9	633.6	0.00	0.00	0.00	
12,900.0	90.00	179.38	11,702.0	-733.0	46.0	733.6	0.00	0.00	0.00	
13,000.0	90.00	179.38	11,702.0	-833.0	47.0	833.6	0.00	0.00	0.00	
13,100.0	90.00	179.38	11,702.0	-933.0	48.1	933.6	0.00	0.00	0.00	
13,200.0	90.00	179.38	11,702.0	-1,033.0	49.2	1,033.6	0.00	0.00	0.00	
13,300.0	90.00	179.38	11,702.0	-1,133.0	50.3	1,133.6	0.00	0.00	0.00	
13,400.0	90.00	179.38	11,702.0	-1,233.0	51.4	1,233.6	0.00	0.00	0.00	
13,500.0	90.00	179.38	11,702.0	-1,333.0	52.5	1,333.6	0.00	0.00	0.00	
13,600.0	90.00	179.38	11,702.0	-1,433.0	53.6	1,433.6	0.00	0.00	0.00	
13,700.0	90.00	179.38	11,702.0	-1,533.0	54.7	1,533.6	0.00	0.00	0.00	
13,800.0	90.00	179.38	11,702.0	-1,633.0	55.8	1,633.6	0.00	0.00	0.00	
13,900.0	90.00	179.38	11,702.0	-1,733.0	56.9	1,733.6	0.00	0.00	0.00	
14,000.0	90.00	179.38	11,702.0	-1,833.0	58.0	1,833.6	0.00	0.00	0.00	
14,100.0	90.00	179.38	11,702.0	-1,933.0	59.0	1,933.6	0.00	0.00	0.00	
14,200.0	90.00	179.38	11,702.0	-2,033.0	60.1	2,033.6	0.00	0.00	0.00	
14,300.0	90.00	179.38	11,702.0	-2,132.9	61.2	2,133.6	0.00	0.00	0.00	
14,400.0	90.00	179.38	11,702.0	-2,232.9	62.3	2,233.6	0.00	0.00	0.00	
14,500.0	90.00	179.38	11,702.0	-2,332.9	63.4	2,333.6	0.00	0.00	0.00	
14,600.0	90.00	179.38	11,702.0	-2,432.9	64.5	2,433.6	0.00	0.00	0.00	
14,700.0	90.00	179.38	11,702.0	-2,532.9	65.6	2,533.6	0.00	0.00	0.00	
14,800.0	90.00	179.38	11,702.0	-2,632.9	66.7	2,633.6	0.00	0.00	0.00	
14,900.0	90.00	179.38	11,702.0	-2,732.9	67.8	2,733.6	0.00	0.00	0.00	
15,000.0	90.00	179.38	11,702.0	-2,832.9	68.9	2,833.6	0.00	0.00	0.00	



Database: EDM5000  
Company: Ameredev Operating, LLC.  
Project: RB/HOL  
Site: RB/HOL #5S  
Well: Holly 114H  
Wellbore: Wellbore #1  
Design: Design #1

Local Co-ordinate Reference: Well Holly 114H  
TVD Reference: KB @ 3030.0usft  
MD Reference: KB @ 3030.0usft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
15,100.0	90.00	179.38	11,702.0	-2,932.9	70.0	2,933.6	0.00	0.00	0.00
15,200.0	90.00	179.38	11,702.0	-3,032.9	71.0	3,033.6	0.00	0.00	0.00
15,300.0	90.00	179.38	11,702.0	-3,132.9	72.1	3,133.6	0.00	0.00	0.00
15,400.0	90.00	179.38	11,702.0	-3,232.9	73.2	3,233.6	0.00	0.00	0.00
15,500.0	90.00	179.38	11,702.0	-3,332.9	74.3	3,333.6	0.00	0.00	0.00
15,600.0	90.00	179.38	11,702.0	-3,432.9	75.4	3,433.6	0.00	0.00	0.00
15,700.0	90.00	179.38	11,702.0	-3,532.9	76.5	3,533.6	0.00	0.00	0.00
15,800.0	90.00	179.38	11,702.0	-3,632.9	77.6	3,633.6	0.00	0.00	0.00
15,897.0	90.00	179.38	11,702.0	-3,729.9	78.6	3,730.6	0.00	0.00	0.00
Hol114 into NMNM006727									
15,900.0	90.00	179.38	11,702.0	-3,732.9	78.7	3,733.6	0.00	0.00	0.00
16,000.0	90.00	179.38	11,702.0	-3,832.8	79.8	3,833.6	0.00	0.00	0.00
16,100.0	90.00	179.38	11,702.0	-3,932.8	80.9	3,933.6	0.00	0.00	0.00
16,200.0	90.00	179.38	11,702.0	-4,032.8	82.0	4,033.6	0.00	0.00	0.00
16,300.0	90.00	179.38	11,702.0	-4,132.8	83.0	4,133.6	0.00	0.00	0.00
16,400.0	90.00	179.38	11,702.0	-4,232.8	84.1	4,233.6	0.00	0.00	0.00
16,500.0	90.00	179.38	11,702.0	-4,332.8	85.2	4,333.6	0.00	0.00	0.00
16,600.0	90.00	179.38	11,702.0	-4,432.8	86.3	4,433.6	0.00	0.00	0.00
16,700.0	90.00	179.38	11,702.0	-4,532.8	87.4	4,533.6	0.00	0.00	0.00
16,800.0	90.00	179.38	11,702.0	-4,632.8	88.5	4,633.6	0.00	0.00	0.00
16,900.0	90.00	179.38	11,702.0	-4,732.8	89.6	4,733.6	0.00	0.00	0.00
17,000.0	90.00	179.38	11,702.0	-4,832.8	90.7	4,833.6	0.00	0.00	0.00
17,100.0	90.00	179.38	11,702.0	-4,932.8	91.8	4,933.6	0.00	0.00	0.00
17,200.0	90.00	179.38	11,702.0	-5,032.8	92.9	5,033.6	0.00	0.00	0.00
17,217.0	90.00	179.38	11,702.0	-5,049.8	93.0	5,050.6	0.00	0.00	0.00
Hol114 into NMNM137473									
17,300.0	90.00	179.38	11,702.0	-5,132.8	93.9	5,133.6	0.00	0.00	0.00
17,400.0	90.00	179.38	11,702.0	-5,232.8	95.0	5,233.6	0.00	0.00	0.00
17,500.0	90.00	179.38	11,702.0	-5,332.8	96.1	5,333.6	0.00	0.00	0.00
17,600.0	90.00	179.38	11,702.0	-5,432.8	97.2	5,433.6	0.00	0.00	0.00
17,700.0	90.00	179.38	11,702.0	-5,532.7	98.3	5,533.6	0.00	0.00	0.00
17,800.0	90.00	179.38	11,702.0	-5,632.7	99.4	5,633.6	0.00	0.00	0.00
17,900.0	90.00	179.38	11,702.0	-5,732.7	100.5	5,733.6	0.00	0.00	0.00
18,000.0	90.00	179.38	11,702.0	-5,832.7	101.6	5,833.6	0.00	0.00	0.00
18,100.0	90.00	179.38	11,702.0	-5,932.7	102.7	5,933.6	0.00	0.00	0.00
18,200.0	90.00	179.38	11,702.0	-6,032.7	103.8	6,033.6	0.00	0.00	0.00
18,300.0	90.00	179.38	11,702.0	-6,132.7	104.9	6,133.6	0.00	0.00	0.00
18,400.0	90.00	179.38	11,702.0	-6,232.7	105.9	6,233.6	0.00	0.00	0.00
18,500.0	90.00	179.38	11,702.0	-6,332.7	107.0	6,333.6	0.00	0.00	0.00
18,600.0	90.00	179.38	11,702.0	-6,432.7	108.1	6,433.6	0.00	0.00	0.00
18,700.0	90.00	179.38	11,702.0	-6,532.7	109.2	6,533.6	0.00	0.00	0.00
18,800.0	90.00	179.38	11,702.0	-6,632.7	110.3	6,633.6	0.00	0.00	0.00
18,900.0	90.00	179.38	11,702.0	-6,732.7	111.4	6,733.6	0.00	0.00	0.00
19,000.0	90.00	179.38	11,702.0	-6,832.7	112.5	6,833.6	0.00	0.00	0.00
19,100.0	90.00	179.38	11,702.0	-6,932.7	113.6	6,933.6	0.00	0.00	0.00
19,200.0	90.00	179.38	11,702.0	-7,032.7	114.7	7,033.6	0.00	0.00	0.00
19,300.0	90.00	179.38	11,702.0	-7,132.7	115.8	7,133.6	0.00	0.00	0.00
19,400.0	90.00	179.38	11,702.0	-7,232.6	116.9	7,233.6	0.00	0.00	0.00
19,500.0	90.00	179.38	11,702.0	-7,332.6	117.9	7,333.6	0.00	0.00	0.00
19,600.0	90.00	179.38	11,702.0	-7,432.6	119.0	7,433.6	0.00	0.00	0.00
19,700.0	90.00	179.38	11,702.0	-7,532.6	120.1	7,533.6	0.00	0.00	0.00
19,800.0	90.00	179.38	11,702.0	-7,632.6	121.2	7,633.6	0.00	0.00	0.00
19,900.0	90.00	179.38	11,702.0	-7,732.6	122.3	7,733.6	0.00	0.00	0.00

<b>Database:</b>	EDM5000	<b>Local Co-ordinate Reference:</b>	Well Holly 114H
<b>Company:</b>	Ameredev Operating, LLC.	<b>TVD Reference:</b>	KB @ 3030.0usft
<b>Project:</b>	RB/HOL	<b>MD Reference:</b>	KB @ 3030.0usft
<b>Site:</b>	RB/HOL #5S	<b>North Reference:</b>	Grid
<b>Well:</b>	Holly 114H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Design #1		

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
20,000.0	90.00	179.38	11,702.0	-7,832.6	123.4	7,833.6	0.00	0.00	0.00
20,100.0	90.00	179.38	11,702.0	-7,932.6	124.5	7,933.6	0.00	0.00	0.00
20,200.0	90.00	179.38	11,702.0	-8,032.6	125.6	8,033.6	0.00	0.00	0.00
20,300.0	90.00	179.38	11,702.0	-8,132.6	126.7	8,133.6	0.00	0.00	0.00
20,400.0	90.00	179.38	11,702.0	-8,232.6	127.8	8,233.6	0.00	0.00	0.00
20,500.0	90.00	179.38	11,702.0	-8,332.6	128.9	8,333.6	0.00	0.00	0.00
20,600.0	90.00	179.38	11,702.0	-8,432.6	129.9	8,433.6	0.00	0.00	0.00
20,700.0	90.00	179.38	11,702.0	-8,532.6	131.0	8,533.6	0.00	0.00	0.00
20,800.0	90.00	179.38	11,702.0	-8,632.6	132.1	8,633.6	0.00	0.00	0.00
20,900.0	90.00	179.38	11,702.0	-8,732.6	133.2	8,733.6	0.00	0.00	0.00
21,000.0	90.00	179.38	11,702.0	-8,832.6	134.3	8,833.6	0.00	0.00	0.00
21,100.0	90.00	179.38	11,702.0	-8,932.5	135.4	8,933.6	0.00	0.00	0.00
21,200.0	90.00	179.38	11,702.0	-9,032.5	136.5	9,033.6	0.00	0.00	0.00
21,300.0	90.00	179.38	11,702.0	-9,132.5	137.6	9,133.6	0.00	0.00	0.00
21,400.0	90.00	179.38	11,702.0	-9,232.5	138.7	9,233.6	0.00	0.00	0.00
21,500.0	90.00	179.38	11,702.0	-9,332.5	139.8	9,333.6	0.00	0.00	0.00
21,600.0	90.00	179.38	11,702.0	-9,432.5	140.9	9,433.6	0.00	0.00	0.00
21,700.0	90.00	179.38	11,702.0	-9,532.5	141.9	9,533.6	0.00	0.00	0.00
21,800.0	90.00	179.38	11,702.0	-9,632.5	143.0	9,633.6	0.00	0.00	0.00
21,900.0	90.00	179.38	11,702.0	-9,732.5	144.1	9,733.6	0.00	0.00	0.00
22,000.0	90.00	179.38	11,702.0	-9,832.5	145.2	9,833.6	0.00	0.00	0.00
22,100.0	90.00	179.38	11,702.0	-9,932.5	146.3	9,933.6	0.00	0.00	0.00
22,200.0	90.00	179.38	11,702.0	-10,032.5	147.4	10,033.6	0.00	0.00	0.00
22,300.0	90.00	179.38	11,702.0	-10,132.5	148.5	10,133.6	0.00	0.00	0.00
22,399.1	90.00	179.38	11,702.0	-10,231.5	149.6	10,232.6	0.00	0.00	0.00
<b>Hol114 LTP</b>									
22,400.0	90.00	179.38	11,702.0	-10,232.5	149.6	10,233.6	0.00	0.00	0.00
22,449.0	90.00	179.38	11,702.0	-10,281.5	150.1	10,282.6	0.00	0.00	0.00
<b>Hol114 BHL</b>									

### Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Hol114 KOP - plan hits target center - Point	0.00	0.00	11,200.0	631.2	160.6	394,656.77	865,171.77	32° 4' 50.436 N	103° 17' 15.991 W
Hol114 BHL - plan hits target center - Point	0.00	0.00	11,702.0	-10,281.5	150.1	383,744.05	865,161.29	32° 3' 2.460 N	103° 17' 17.341 W
Hol114 FTP - plan hits target center - Point	0.00	0.00	11,702.0	130.3	36.5	394,155.91	865,047.72	32° 4' 45.493 N	103° 17' 17.489 W
Hol114 LTP - plan hits target center - Point	0.00	0.01	11,702.0	-10,231.5	149.6	383,794.03	865,160.74	32° 3' 2.955 N	103° 17' 17.342 W

Database:	EDM5000	Local Co-ordinate Reference:	Well Holly 114H
Company:	Ameredev Operating, LLC.	TVD Reference:	KB @ 3030.0usft
Project:	RB/HOL	MD Reference:	KB @ 3030.0usft
Site:	RB/HOL #5S	North Reference:	Grid
Well:	Holly 114H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

## Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
15,897.0	11,702.0	-3,729.9	78.6	Hol114 into NMNM006727
17,217.0	11,702.0	-5,049.8	93.0	Hol114 into NMNM137473

# ***AMEREDEV***

**Ameredev Operating, LLC.**

**RB/HOL**

**RB/HOL #5S**

**Holly 114H**

**Wellbore #1**

**Plan: Design #1**

**Lease Penetration Section Line Foot**

**21 February, 2019**

<b>Company:</b>	Ameredev Operating, LLC.	<b>Local Co-ordinate Reference:</b>	Well Holly 114H
<b>Project:</b>	RB/HOL	<b>TVD Reference:</b>	KB @ 3030.0usft
<b>Site:</b>	RB/HOL #5S	<b>MD Reference:</b>	KB @ 3030.0usft
<b>Well:</b>	Holly 114H	<b>North Reference:</b>	Grid
<b>Wellbore:</b>	Wellbore #1	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	Design #1	<b>Database:</b>	EDM5000

<b>Project</b>	RB/HOL		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	New Mexico Eastern Zone		

<b>Site</b>	RB/HOL #5S		
<b>Site Position:</b>		<b>Northing:</b>	394,025.37 usft
<b>From:</b>	Lat/Long	<b>Easting:</b>	864,991.18 usft
<b>Position Uncertainty:</b>	0.0 usft	<b>Slot Radius:</b>	13-3/16"
		<b>Latitude:</b>	32° 4' 44.206 N
		<b>Longitude:</b>	103° 17' 18.161 W
		<b>Grid Convergence:</b>	0.56 °

<b>Well</b>	Holly 114H		
<b>Well Position</b>	+N/-S	0.0 usft	<b>Northing:</b> 394,025.57 usft
	+E/-W	0.0 usft	<b>Easting:</b> 865,011.18 usft
<b>Position Uncertainty</b>	0.0 usft	<b>Wellhead Elevation:</b>	usft
		<b>Latitude:</b>	32° 4' 44.206 N
		<b>Longitude:</b>	103° 17' 17.929 W
		<b>Ground Level:</b>	3,003.0 usft

<b>Wellbore</b>	Wellbore #1		
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination</b>
			(°)
	IGRF2015	2/19/2019	6.63
			Dip Angle (°)
			59.95
			Field Strength (nT)
			47,712.02244477

<b>Design</b>	Design #1		
<b>Audit Notes:</b>			
<b>Version:</b>	<b>Phase:</b>	PROTOTYPE	<b>Tie On Depth:</b> 0.0
<b>Vertical Section:</b>	<b>Depth From (TVD)</b>	<b>+N/-S</b>	<b>+E/-W</b>
	(usft)	(usft)	(usft)
	0.0	0.0	0.0
			<b>Direction</b> (°)
			179.16

<b>Survey Tool Program</b>	<b>Date</b> 2/21/2019		
<b>From</b>	<b>To</b>	<b>Survey (Wellbore)</b>	<b>Tool Name</b>
(usft)	(usft)		
0.0	22,448.1	Design #1 (Wellbore #1)	MWD
			<b>Description</b>
			OWSG MWD - Standard

<b>Planned Survey</b>							
<b>MD</b>	<b>Inc</b>	<b>Azi (azimuth)</b>	<b>TVD</b>	<b>+FSL/-FNL</b>	<b>+FWL/-FEL</b>	<b>Latitude</b>	<b>Longitude</b>
(usft)	(°)	(°)	(usft)	(usft)	(usft)		
0.0	0.00	0.00	0.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
100.0	0.00	0.00	100.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
200.0	0.00	0.00	200.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
300.0	0.00	0.00	300.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
400.0	0.00	0.00	400.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
500.0	0.00	0.00	500.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
600.0	0.00	0.00	600.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
700.0	0.00	0.00	700.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
800.0	0.00	0.00	800.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
900.0	0.00	0.00	900.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
1,000.0	0.00	0.00	1,000.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
1,100.0	0.00	0.00	1,100.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W

Company: Ameredev Operating, LLC.  
 Project: RB/HOL  
 Site: RB/HOL #5S  
 Well: Holly 114H  
 Wellbore: Wellbore #1  
 Design: Design #1

Local Co-ordinate Reference: Well Holly 114H  
 TVD Reference: KB @ 3030.0usft  
 MD Reference: KB @ 3030.0usft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature  
 Database: EDM5000

**Planned Survey**

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	Latitude	Longitude
1,200.0	0.00	0.00	1,200.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
1,300.0	0.00	0.00	1,300.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
1,400.0	0.00	0.00	1,400.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
1,500.0	0.00	0.00	1,500.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
1,600.0	0.00	0.00	1,600.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
1,700.0	0.00	0.00	1,700.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
1,800.0	0.00	0.00	1,800.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
1,900.0	0.00	0.00	1,900.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
2,000.0	0.00	0.00	2,000.0	-229.8	2,280.0	32° 4' 44.206 N	103° 17' 17.929 W
2,100.0	2.00	15.00	2,100.0	-228.1	2,280.5	32° 4' 44.223 N	103° 17' 17.923 W
2,200.0	4.00	15.00	2,199.8	-223.1	2,281.8	32° 4' 44.273 N	103° 17' 17.907 W
2,300.0	6.00	15.00	2,299.5	-214.6	2,284.1	32° 4' 44.356 N	103° 17' 17.880 W
2,400.0	6.00	15.00	2,398.9	-204.5	2,286.8	32° 4' 44.456 N	103° 17' 17.847 W
2,500.0	6.00	15.00	2,498.4	-194.4	2,289.5	32° 4' 44.555 N	103° 17' 17.815 W
2,600.0	6.00	15.00	2,597.8	-184.4	2,292.2	32° 4' 44.655 N	103° 17' 17.782 W
2,700.0	6.00	15.00	2,697.3	-174.3	2,294.9	32° 4' 44.755 N	103° 17' 17.749 W
2,800.0	6.00	15.00	2,796.7	-164.2	2,297.6	32° 4' 44.854 N	103° 17' 17.717 W
2,900.0	6.00	15.00	2,896.2	-154.1	2,300.3	32° 4' 44.954 N	103° 17' 17.684 W
3,000.0	6.00	15.00	2,995.6	-144.0	2,303.0	32° 4' 45.053 N	103° 17' 17.652 W
3,100.0	6.00	15.00	3,095.1	-133.9	2,305.7	32° 4' 45.153 N	103° 17' 17.619 W
3,200.0	6.00	15.00	3,194.5	-123.8	2,308.4	32° 4' 45.253 N	103° 17' 17.587 W
3,300.0	6.00	15.00	3,294.0	-113.7	2,311.1	32° 4' 45.352 N	103° 17' 17.554 W
3,400.0	6.00	15.00	3,393.4	-103.6	2,313.8	32° 4' 45.452 N	103° 17' 17.521 W
3,500.0	6.00	15.00	3,492.9	-93.5	2,316.5	32° 4' 45.552 N	103° 17' 17.489 W
3,600.0	6.00	15.00	3,592.3	-83.4	2,319.2	32° 4' 45.651 N	103° 17' 17.456 W
3,700.0	6.00	15.00	3,691.8	-73.3	2,321.9	32° 4' 45.751 N	103° 17' 17.424 W
3,800.0	6.00	15.00	3,791.2	-63.2	2,324.6	32° 4' 45.851 N	103° 17' 17.391 W
3,900.0	6.00	15.00	3,890.7	-53.1	2,327.3	32° 4' 45.950 N	103° 17' 17.359 W
4,000.0	6.00	15.00	3,990.1	-43.0	2,330.1	32° 4' 46.050 N	103° 17' 17.326 W
4,100.0	6.00	15.00	4,089.6	-32.9	2,332.8	32° 4' 46.150 N	103° 17' 17.293 W
4,200.0	6.00	15.00	4,189.0	-22.8	2,335.5	32° 4' 46.249 N	103° 17' 17.261 W
4,300.0	6.00	15.00	4,288.5	-12.7	2,338.2	32° 4' 46.349 N	103° 17' 17.228 W
4,400.0	6.00	15.00	4,387.9	-2.6	2,340.9	32° 4' 46.448 N	103° 17' 17.196 W
4,500.0	6.00	15.00	4,487.4	7.5	2,343.6	32° 4' 46.548 N	103° 17' 17.163 W
4,600.0	6.00	15.00	4,586.9	17.6	2,346.3	32° 4' 46.648 N	103° 17' 17.131 W
4,700.0	6.00	15.00	4,686.3	27.7	2,349.0	32° 4' 46.747 N	103° 17' 17.098 W
4,800.0	6.00	15.00	4,785.8	37.8	2,351.7	32° 4' 46.847 N	103° 17' 17.065 W
4,900.0	6.00	15.00	4,885.2	47.9	2,354.4	32° 4' 46.947 N	103° 17' 17.033 W
5,000.0	6.00	15.00	4,984.7	58.0	2,357.1	32° 4' 47.046 N	103° 17' 17.000 W
5,100.0	6.00	15.00	5,084.1	68.1	2,359.8	32° 4' 47.146 N	103° 17' 16.968 W
5,200.0	6.00	15.00	5,183.6	78.2	2,362.5	32° 4' 47.246 N	103° 17' 16.935 W
5,300.0	6.00	15.00	5,283.0	88.3	2,365.2	32° 4' 47.345 N	103° 17' 16.902 W
5,400.0	6.00	15.00	5,382.5	98.4	2,367.9	32° 4' 47.445 N	103° 17' 16.870 W
5,500.0	6.00	15.00	5,481.9	108.5	2,370.6	32° 4' 47.545 N	103° 17' 16.837 W

Company: Ameredev Operating, LLC.  
 Project: RB/HOL  
 Site: RB/HOL #5S  
 Well: Holly 114H  
 Wellbore: Wellbore #1  
 Design: Design #1

Local Co-ordinate Reference: Well Holly 114H  
 TVD Reference: KB @ 3030.0usft  
 MD Reference: KB @ 3030.0usft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature  
 Database: EDM5000

#### Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	Latitude	Longitude
5,600.0	6.00	15.00	5,581.4	118.5	2,373.3	32° 4' 47.644 N	103° 17' 16.805 W
5,700.0	6.00	15.00	5,680.8	128.6	2,376.0	32° 4' 47.744 N	103° 17' 16.772 W
5,800.0	6.00	15.00	5,780.3	138.7	2,378.8	32° 4' 47.844 N	103° 17' 16.740 W
5,900.0	6.00	15.00	5,879.7	148.8	2,381.5	32° 4' 47.943 N	103° 17' 16.707 W
6,000.0	6.00	15.00	5,979.2	158.9	2,384.2	32° 4' 48.043 N	103° 17' 16.674 W
6,100.0	6.00	15.00	6,078.6	169.0	2,386.9	32° 4' 48.142 N	103° 17' 16.642 W
6,200.0	6.00	15.00	6,178.1	179.1	2,389.6	32° 4' 48.242 N	103° 17' 16.609 W
6,300.0	6.00	15.00	6,277.5	189.2	2,392.3	32° 4' 48.342 N	103° 17' 16.577 W
6,400.0	6.00	15.00	6,377.0	199.3	2,395.0	32° 4' 48.441 N	103° 17' 16.544 W
6,500.0	6.00	15.00	6,476.4	209.4	2,397.7	32° 4' 48.541 N	103° 17' 16.512 W
6,600.0	6.00	15.00	6,575.9	219.5	2,400.4	32° 4' 48.641 N	103° 17' 16.479 W
6,700.0	6.00	15.00	6,675.3	229.6	2,403.1	32° 4' 48.740 N	103° 17' 16.446 W
6,724.8	6.00	15.00	6,700.0	232.1	2,403.8	32° 4' 48.765 N	103° 17' 16.438 W
6,800.0	4.50	15.00	6,774.9	238.8	2,405.6	32° 4' 48.831 N	103° 17' 16.417 W
6,900.0	2.50	15.00	6,874.7	244.6	2,407.1	32° 4' 48.889 N	103° 17' 16.398 W
7,000.0	0.50	15.00	6,974.7	247.2	2,407.8	32° 4' 48.914 N	103° 17' 16.390 W
7,024.8	0.00	0.00	6,999.5	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
7,100.0	0.00	0.00	7,074.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
7,200.0	0.00	0.00	7,174.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
7,300.0	0.00	0.00	7,274.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
7,400.0	0.00	0.00	7,374.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
7,500.0	0.00	0.00	7,474.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
7,600.0	0.00	0.00	7,574.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
7,700.0	0.00	0.00	7,674.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
7,800.0	0.00	0.00	7,774.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
7,900.0	0.00	0.00	7,874.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
8,000.0	0.00	0.00	7,974.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
8,100.0	0.00	0.00	8,074.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
8,200.0	0.00	0.00	8,174.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
8,300.0	0.00	0.00	8,274.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
8,400.0	0.00	0.00	8,374.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
8,500.0	0.00	0.00	8,474.7	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
8,525.3	0.00	0.00	8,500.0	247.3	2,407.8	32° 4' 48.915 N	103° 17' 16.389 W
8,600.0	1.49	12.00	8,574.7	248.2	2,408.0	32° 4' 48.924 N	103° 17' 16.387 W
8,700.0	3.49	12.00	8,674.6	252.5	2,408.9	32° 4' 48.966 N	103° 17' 16.376 W
8,800.0	5.49	12.00	8,774.2	260.1	2,410.6	32° 4' 49.042 N	103° 17' 16.356 W
8,825.3	6.00	12.00	8,799.5	262.6	2,411.1	32° 4' 49.066 N	103° 17' 16.350 W
8,900.0	6.00	12.00	8,873.7	270.3	2,412.7	32° 4' 49.142 N	103° 17' 16.330 W
9,000.0	6.00	12.00	8,973.2	280.5	2,414.9	32° 4' 49.243 N	103° 17' 16.304 W
9,100.0	6.00	12.00	9,072.6	290.7	2,417.1	32° 4' 49.343 N	103° 17' 16.277 W
9,200.0	6.00	12.00	9,172.1	300.9	2,419.2	32° 4' 49.444 N	103° 17' 16.251 W
9,300.0	6.00	12.00	9,271.5	311.2	2,421.4	32° 4' 49.545 N	103° 17' 16.224 W
9,400.0	6.00	12.00	9,371.0	321.4	2,423.6	32° 4' 49.646 N	103° 17' 16.198 W
9,500.0	6.00	12.00	9,470.4	331.6	2,425.8	32° 4' 49.747 N	103° 17' 16.172 W

Company: Ameredev Operating, LLC.  
 Project: RB/HOL  
 Site: RB/HOL #5S  
 Well: Holly 114H  
 Wellbore: Wellbore #1  
 Design: Design #1

Local Co-ordinate Reference: Well Holly 114H  
 TVD Reference: KB @ 3030.0usft  
 MD Reference: KB @ 3030.0usft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature  
 Database: EDM5000

#### Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	Latitude	Longitude
9,600.0	6.00	12.00	9,569.9	341.8	2,427.9	32° 4' 49.848 N	103° 17' 16.145 W
9,700.0	6.00	12.00	9,669.3	352.1	2,430.1	32° 4' 49.949 N	103° 17' 16.119 W
9,800.0	6.00	12.00	9,768.8	362.3	2,432.3	32° 4' 50.050 N	103° 17' 16.092 W
9,900.0	6.00	12.00	9,868.2	372.5	2,434.4	32° 4' 50.151 N	103° 17' 16.066 W
10,000.0	6.00	12.00	9,967.7	382.7	2,436.6	32° 4' 50.252 N	103° 17' 16.040 W
10,032.5	6.00	12.00	10,000.0	386.1	2,437.3	32° 4' 50.285 N	103° 17' 16.031 W
10,100.0	4.65	12.00	10,067.2	392.2	2,438.6	32° 4' 50.345 N	103° 17' 16.015 W
10,200.0	2.65	12.00	10,167.0	398.4	2,440.0	32° 4' 50.407 N	103° 17' 15.999 W
10,300.0	0.65	12.00	10,267.0	401.2	2,440.6	32° 4' 50.435 N	103° 17' 15.992 W
10,332.5	0.00	0.00	10,299.5	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
10,400.0	0.00	0.00	10,367.0	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
10,500.0	0.00	0.00	10,467.0	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
10,600.0	0.00	0.00	10,567.0	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
10,700.0	0.00	0.00	10,667.0	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
10,800.0	0.00	0.00	10,767.0	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
10,900.0	0.00	0.00	10,867.0	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
11,000.0	0.00	0.00	10,967.0	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
11,100.0	0.00	0.00	11,067.0	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
11,200.0	0.00	0.00	11,167.0	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
11,233.0	0.00	0.00	11,200.0	401.4	2,440.6	32° 4' 50.436 N	103° 17' 15.991 W
<b>Hol114 KOP</b>							
11,300.0	7.94	204.81	11,266.7	397.2	2,438.6	32° 4' 50.395 N	103° 17' 16.014 W
11,400.0	19.80	204.81	11,363.7	375.5	2,428.6	32° 4' 50.181 N	103° 17' 16.134 W
11,500.0	31.66	204.81	11,453.6	336.1	2,410.4	32° 4' 49.794 N	103° 17' 16.349 W
11,600.0	43.52	204.81	11,532.7	280.9	2,384.9	32° 4' 49.249 N	103° 17' 16.652 W
11,611.9	44.94	204.81	11,541.2	273.3	2,381.4	32° 4' 49.175 N	103° 17' 16.694 W
11,700.0	53.85	197.62	11,598.5	211.0	2,357.5	32° 4' 48.561 N	103° 17' 16.978 W
11,800.0	64.38	191.23	11,649.8	128.0	2,336.4	32° 4' 47.741 N	103° 17' 17.233 W
11,900.0	75.14	185.90	11,684.4	35.4	2,322.6	32° 4' 46.826 N	103° 17' 17.404 W
12,000.0	86.01	181.09	11,700.7	-62.9	2,316.7	32° 4' 45.854 N	103° 17' 17.484 W
12,036.6	90.00	179.38	11,702.0	-99.5	2,316.5	32° 4' 45.493 N	103° 17' 17.489 W
<b>Hol114 FTP</b>							
12,100.0	90.00	179.38	11,702.0	-162.9	2,317.2	32° 4' 44.865 N	103° 17' 17.489 W
12,200.0	90.00	179.38	11,702.0	-262.9	2,318.3	32° 4' 43.875 N	103° 17' 17.487 W
12,300.0	90.00	179.38	11,702.0	-362.9	2,319.4	32° 4' 42.886 N	103° 17' 17.486 W
12,400.0	90.00	179.38	11,702.0	-462.9	2,320.5	32° 4' 41.896 N	103° 17' 17.484 W
12,500.0	90.00	179.38	11,702.0	-562.9	2,321.6	32° 4' 40.907 N	103° 17' 17.483 W
12,600.0	90.00	179.38	11,702.0	-662.9	2,322.7	32° 4' 39.917 N	103° 17' 17.481 W
12,700.0	90.00	179.38	11,702.0	-762.8	2,323.8	32° 4' 38.928 N	103° 17' 17.480 W
12,800.0	90.00	179.38	11,702.0	-862.8	2,324.9	32° 4' 37.938 N	103° 17' 17.479 W
12,900.0	90.00	179.38	11,702.0	-962.8	2,326.0	32° 4' 36.949 N	103° 17' 17.477 W
13,000.0	90.00	179.38	11,702.0	-1,062.8	2,327.0	32° 4' 35.959 N	103° 17' 17.476 W
13,100.0	90.00	179.38	11,702.0	-1,162.8	2,328.1	32° 4' 34.970 N	103° 17' 17.474 W
13,200.0	90.00	179.38	11,702.0	-1,262.8	2,329.2	32° 4' 33.980 N	103° 17' 17.473 W
13,300.0	90.00	179.38	11,702.0	-1,362.8	2,330.3	32° 4' 32.991 N	103° 17' 17.471 W



**Company:** Ameredev Operating, LLC.  
**Project:** RB/HOL  
**Site:** RB/HOL #5S  
**Well:** Holly 114H  
**Wellbore:** Wellbore #1  
**Design:** Design #1

**Local Co-ordinate Reference:** Well Holly 114H  
**TVD Reference:** KB @ 3030.0usft  
**MD Reference:** KB @ 3030.0usft  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Database:** EDM5000

**Planned Survey**

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	Latitude	Longitude
13,400.0	90.00	179.38	11,702.0	-1,462.8	2,331.4	32° 4' 32.001 N	103° 17' 17.470 W
13,500.0	90.00	179.38	11,702.0	-1,562.8	2,332.5	32° 4' 31.012 N	103° 17' 17.469 W
13,600.0	90.00	179.38	11,702.0	-1,662.8	2,333.6	32° 4' 30.022 N	103° 17' 17.467 W
13,700.0	90.00	179.38	11,702.0	-1,762.8	2,334.7	32° 4' 29.033 N	103° 17' 17.466 W
13,800.0	90.00	179.38	11,702.0	-1,862.8	2,335.8	32° 4' 28.043 N	103° 17' 17.464 W
13,900.0	90.00	179.38	11,702.0	-1,962.8	2,336.9	32° 4' 27.054 N	103° 17' 17.463 W
14,000.0	90.00	179.38	11,702.0	-2,062.8	2,338.0	32° 4' 26.064 N	103° 17' 17.462 W
14,100.0	90.00	179.38	11,702.0	-2,162.8	2,339.0	32° 4' 25.075 N	103° 17' 17.460 W
14,200.0	90.00	179.38	11,702.0	-2,262.8	2,340.1	32° 4' 24.085 N	103° 17' 17.459 W
14,300.0	90.00	179.38	11,702.0	-2,362.7	2,341.2	32° 4' 23.096 N	103° 17' 17.457 W
14,400.0	90.00	179.38	11,702.0	-2,462.7	2,342.3	32° 4' 22.106 N	103° 17' 17.456 W
14,500.0	90.00	179.38	11,702.0	-2,562.7	2,343.4	32° 4' 21.117 N	103° 17' 17.454 W
14,600.0	90.00	179.38	11,702.0	-2,662.7	2,344.5	32° 4' 20.127 N	103° 17' 17.453 W
14,700.0	90.00	179.38	11,702.0	-2,762.7	2,345.6	32° 4' 19.138 N	103° 17' 17.452 W
14,800.0	90.00	179.38	11,702.0	-2,862.7	2,346.7	32° 4' 18.148 N	103° 17' 17.450 W
14,900.0	90.00	179.38	11,702.0	-2,962.7	2,347.8	32° 4' 17.159 N	103° 17' 17.449 W
15,000.0	90.00	179.38	11,702.0	-3,062.7	2,348.9	32° 4' 16.169 N	103° 17' 17.447 W
15,100.0	90.00	179.38	11,702.0	-3,162.7	2,350.0	32° 4' 15.180 N	103° 17' 17.446 W
15,200.0	90.00	179.38	11,702.0	-3,262.7	2,351.0	32° 4' 14.190 N	103° 17' 17.445 W
15,300.0	90.00	179.38	11,702.0	-3,362.7	2,352.1	32° 4' 13.201 N	103° 17' 17.443 W
15,400.0	90.00	179.38	11,702.0	-3,462.7	2,353.2	32° 4' 12.211 N	103° 17' 17.442 W
15,500.0	90.00	179.38	11,702.0	-3,562.7	2,354.3	32° 4' 11.222 N	103° 17' 17.440 W
15,600.0	90.00	179.38	11,702.0	-3,662.7	2,355.4	32° 4' 10.232 N	103° 17' 17.439 W
15,700.0	90.00	179.38	11,702.0	-3,762.7	2,356.5	32° 4' 9.243 N	103° 17' 17.437 W
15,800.0	90.00	179.38	11,702.0	-3,862.7	2,357.6	32° 4' 8.253 N	103° 17' 17.436 W
15,897.0	90.00	179.38	11,702.0	-3,959.7	2,358.6	32° 4' 7.293 N	103° 17' 17.435 W
<b>Hol114 into NMNM006727</b>							
15,900.0	90.00	179.38	11,702.0	-3,962.7	2,358.7	32° 4' 7.264 N	103° 17' 17.435 W
16,000.0	90.00	179.38	11,702.0	-4,062.6	2,359.8	32° 4' 6.274 N	103° 17' 17.433 W
16,100.0	90.00	179.38	11,702.0	-4,162.6	2,360.9	32° 4' 5.285 N	103° 17' 17.432 W
16,200.0	90.00	179.38	11,702.0	-4,262.6	2,362.0	32° 4' 4.295 N	103° 17' 17.430 W
16,300.0	90.00	179.38	11,702.0	-4,362.6	2,363.0	32° 4' 3.306 N	103° 17' 17.429 W
16,400.0	90.00	179.38	11,702.0	-4,462.6	2,364.1	32° 4' 2.316 N	103° 17' 17.427 W
16,500.0	90.00	179.38	11,702.0	-4,562.6	2,365.2	32° 4' 1.326 N	103° 17' 17.426 W
16,600.0	90.00	179.38	11,702.0	-4,662.6	2,366.3	32° 4' 0.337 N	103° 17' 17.425 W
16,700.0	90.00	179.38	11,702.0	-4,762.6	2,367.4	32° 3' 59.347 N	103° 17' 17.423 W
16,800.0	90.00	179.38	11,702.0	-4,862.6	2,368.5	32° 3' 58.358 N	103° 17' 17.422 W
16,900.0	90.00	179.38	11,702.0	-4,962.6	2,369.6	32° 3' 57.368 N	103° 17' 17.420 W
17,000.0	90.00	179.38	11,702.0	-5,062.6	2,370.7	32° 3' 56.379 N	103° 17' 17.419 W
17,100.0	90.00	179.38	11,702.0	-5,162.6	2,371.8	32° 3' 55.389 N	103° 17' 17.418 W
17,200.0	90.00	179.38	11,702.0	-5,262.6	2,372.9	32° 3' 54.400 N	103° 17' 17.416 W
17,217.0	90.00	179.38	11,702.0	-5,279.6	2,373.0	32° 3' 54.232 N	103° 17' 17.416 W
<b>Hol114 into NMNM137473</b>							
17,300.0	90.00	179.38	11,702.0	-5,362.6	2,373.9	32° 3' 53.410 N	103° 17' 17.415 W

<b>Company:</b>	Ameredev Operating, LLC.	<b>Local Co-ordinate Reference:</b>	Well Holly 114H
<b>Project:</b>	RB/HOL	<b>TVD Reference:</b>	KB @ 3030.0usft
<b>Site:</b>	RB/HOL #5S	<b>MD Reference:</b>	KB @ 3030.0usft
<b>Well:</b>	Holly 114H	<b>North Reference:</b>	Grid
<b>Wellbore:</b>	Wellbore #1	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	Design #1	<b>Database:</b>	EDM5000

#### Planned Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	Latitude	Longitude
17,400.0	90.00	179.38	11,702.0	-5,462.6	2,375.0	32° 3' 52.421 N	103° 17' 17.413 W
17,500.0	90.00	179.38	11,702.0	-5,562.6	2,376.1	32° 3' 51.431 N	103° 17' 17.412 W
17,600.0	90.00	179.38	11,702.0	-5,662.6	2,377.2	32° 3' 50.442 N	103° 17' 17.410 W
17,700.0	90.00	179.38	11,702.0	-5,762.5	2,378.3	32° 3' 49.452 N	103° 17' 17.409 W
17,800.0	90.00	179.38	11,702.0	-5,862.5	2,379.4	32° 3' 48.463 N	103° 17' 17.408 W
17,900.0	90.00	179.38	11,702.0	-5,962.5	2,380.5	32° 3' 47.473 N	103° 17' 17.406 W
18,000.0	90.00	179.38	11,702.0	-6,062.5	2,381.6	32° 3' 46.484 N	103° 17' 17.405 W
18,100.0	90.00	179.38	11,702.0	-6,162.5	2,382.7	32° 3' 45.494 N	103° 17' 17.403 W
18,200.0	90.00	179.38	11,702.0	-6,262.5	2,383.8	32° 3' 44.505 N	103° 17' 17.402 W
18,300.0	90.00	179.38	11,702.0	-6,362.5	2,384.9	32° 3' 43.515 N	103° 17' 17.400 W
18,400.0	90.00	179.38	11,702.0	-6,462.5	2,385.9	32° 3' 42.526 N	103° 17' 17.399 W
18,500.0	90.00	179.38	11,702.0	-6,562.5	2,387.0	32° 3' 41.536 N	103° 17' 17.398 W
18,600.0	90.00	179.38	11,702.0	-6,662.5	2,388.1	32° 3' 40.547 N	103° 17' 17.396 W
18,700.0	90.00	179.38	11,702.0	-6,762.5	2,389.2	32° 3' 39.557 N	103° 17' 17.395 W
18,800.0	90.00	179.38	11,702.0	-6,862.5	2,390.3	32° 3' 38.568 N	103° 17' 17.393 W
18,900.0	90.00	179.38	11,702.0	-6,962.5	2,391.4	32° 3' 37.578 N	103° 17' 17.392 W
19,000.0	90.00	179.38	11,702.0	-7,062.5	2,392.5	32° 3' 36.589 N	103° 17' 17.391 W
19,100.0	90.00	179.38	11,702.0	-7,162.5	2,393.6	32° 3' 35.599 N	103° 17' 17.389 W
19,200.0	90.00	179.38	11,702.0	-7,262.5	2,394.7	32° 3' 34.610 N	103° 17' 17.388 W
19,300.0	90.00	179.38	11,702.0	-7,362.5	2,395.8	32° 3' 33.620 N	103° 17' 17.386 W
19,400.0	90.00	179.38	11,702.0	-7,462.4	2,396.9	32° 3' 32.631 N	103° 17' 17.385 W
19,500.0	90.00	179.38	11,702.0	-7,562.4	2,397.9	32° 3' 31.641 N	103° 17' 17.383 W
19,600.0	90.00	179.38	11,702.0	-7,662.4	2,399.0	32° 3' 30.652 N	103° 17' 17.382 W
19,700.0	90.00	179.38	11,702.0	-7,762.4	2,400.1	32° 3' 29.662 N	103° 17' 17.381 W
19,800.0	90.00	179.38	11,702.0	-7,862.4	2,401.2	32° 3' 28.673 N	103° 17' 17.379 W
19,900.0	90.00	179.38	11,702.0	-7,962.4	2,402.3	32° 3' 27.683 N	103° 17' 17.378 W
20,000.0	90.00	179.38	11,702.0	-8,062.4	2,403.4	32° 3' 26.694 N	103° 17' 17.376 W
20,100.0	90.00	179.38	11,702.0	-8,162.4	2,404.5	32° 3' 25.704 N	103° 17' 17.375 W
20,200.0	90.00	179.38	11,702.0	-8,262.4	2,405.6	32° 3' 24.715 N	103° 17' 17.373 W
20,300.0	90.00	179.38	11,702.0	-8,362.4	2,406.7	32° 3' 23.725 N	103° 17' 17.372 W
20,400.0	90.00	179.38	11,702.0	-8,462.4	2,407.8	32° 3' 22.736 N	103° 17' 17.371 W
20,500.0	90.00	179.38	11,702.0	-8,562.4	2,408.9	32° 3' 21.746 N	103° 17' 17.369 W
20,600.0	90.00	179.38	11,702.0	-8,662.4	2,409.9	32° 3' 20.756 N	103° 17' 17.368 W
20,700.0	90.00	179.38	11,702.0	-8,762.4	2,411.0	32° 3' 19.767 N	103° 17' 17.366 W
20,800.0	90.00	179.38	11,702.0	-8,862.4	2,412.1	32° 3' 18.777 N	103° 17' 17.365 W
20,900.0	90.00	179.38	11,702.0	-8,962.4	2,413.2	32° 3' 17.788 N	103° 17' 17.364 W
21,000.0	90.00	179.38	11,702.0	-9,062.4	2,414.3	32° 3' 16.798 N	103° 17' 17.362 W
21,100.0	90.00	179.38	11,702.0	-9,162.3	2,415.4	32° 3' 15.809 N	103° 17' 17.361 W
21,200.0	90.00	179.38	11,702.0	-9,262.3	2,416.5	32° 3' 14.819 N	103° 17' 17.359 W
21,300.0	90.00	179.38	11,702.0	-9,362.3	2,417.6	32° 3' 13.830 N	103° 17' 17.358 W
21,400.0	90.00	179.38	11,702.0	-9,462.3	2,418.7	32° 3' 12.840 N	103° 17' 17.356 W
21,500.0	90.00	179.38	11,702.0	-9,562.3	2,419.8	32° 3' 11.851 N	103° 17' 17.355 W
21,600.0	90.00	179.38	11,702.0	-9,662.3	2,420.9	32° 3' 10.861 N	103° 17' 17.354 W
21,700.0	90.00	179.38	11,702.0	-9,762.3	2,421.9	32° 3' 9.872 N	103° 17' 17.352 W
21,800.0	90.00	179.38	11,702.0	-9,862.3	2,423.0	32° 3' 8.882 N	103° 17' 17.351 W

Company:	Ameredev Operating, LLC.	Local Co-ordinate Reference:	Well Holly 114H
Project:	RB/HOL	TVD Reference:	KB @ 3030.0usft
Site:	RB/HOL #5S	MD Reference:	KB @ 3030.0usft
Well:	Holly 114H	North Reference:	Grid
Wellbore:	Wellbore #1	Survey Calculation Method:	Minimum Curvature
Design:	Design #1	Database:	EDM5000

**Planned Survey**

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	+FSL/-FNL (usft)	+FWL/-FEL (usft)	Latitude	Longitude
21,900.0	90.00	179.38	11,702.0	-9,962.3	2,424.1	32° 3' 7.893 N	103° 17' 17.349 W
22,000.0	90.00	179.38	11,702.0	-10,062.3	2,425.2	32° 3' 6.903 N	103° 17' 17.348 W
22,100.0	90.00	179.38	11,702.0	-10,162.3	2,426.3	32° 3' 5.914 N	103° 17' 17.346 W
22,200.0	90.00	179.38	11,702.0	-10,262.3	2,427.4	32° 3' 4.924 N	103° 17' 17.345 W
22,300.0	90.00	179.38	11,702.0	-10,362.3	2,428.5	32° 3' 3.935 N	103° 17' 17.344 W
22,399.1	90.00	179.38	11,702.0	-10,461.3	2,429.6	32° 3' 2.955 N	103° 17' 17.342 W
<b>Hol114 LTP</b>							
22,400.0	90.00	179.38	11,702.0	-10,462.3	2,429.6	32° 3' 2.945 N	103° 17' 17.342 W
22,449.0	90.00	179.38	11,702.0	-10,511.3	2,430.1	32° 3' 2.460 N	103° 17' 17.341 W
<b>Hol114 BHL</b>							

**Plan Annotations**

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
15,897.0	11,702.0	-3,729.9	78.6	Hol114 into NMNM006727
17,217.0	11,702.0	-5,049.8	93.0	Hol114 into NMNM137473

Checked By: _____	Approved By: _____	Date: _____
-------------------	--------------------	-------------



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## PWD Data Report

02/26/2020

APD ID: 10400043719

Submission Date: 07/22/2019

Operator Name: AMEREDEV OPERATING LLC

Well Name: HOLLY FED COM 26 36 05

Well Number: 114H

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - General

Would you like to address long-term produced water disposal? NO

### Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

**Operator Name:** AMEREDEV OPERATING LLC

**Well Name:** HOLLY FED COM 26 36 05

**Well Number:** 114H

**Lined pit Monitor description:**

**Lined pit Monitor attachment:**

**Lined pit: do you have a reclamation bond for the pit?**

**Is the reclamation bond a rider under the BLM bond?**

**Lined pit bond number:**

**Lined pit bond amount:**

**Additional bond information attachment:**

### **Section 3 - Unlined Pits**

**Would you like to utilize Unlined Pit PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD disturbance (acres):**

**PWD surface owner:**

**Unlined pit PWD on or off channel:**

**Unlined pit PWD discharge volume (bbl/day):**

**Unlined pit specifications:**

**Precipitated solids disposal:**

**Describe precipitated solids disposal:**

**Precipitated solids disposal permit:**

**Unlined pit precipitated solids disposal schedule:**

**Unlined pit precipitated solids disposal schedule attachment:**

**Unlined pit reclamation description:**

**Unlined pit reclamation attachment:**

**Unlined pit Monitor description:**

**Unlined pit Monitor attachment:**

**Do you propose to put the produced water to beneficial use?**

**Beneficial use user confirmation:**

**Estimated depth of the shallowest aquifer (feet):**

**Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?**

**TDS lab results:**

**Geologic and hydrologic evidence:**

**State authorization:**

**Unlined Produced Water Pit Estimated percolation:**

**Unlined pit: do you have a reclamation bond for the pit?**

**Operator Name:** AMEREDEV OPERATING LLC

**Well Name:** HOLLY FED COM 26 36 05

**Well Number:** 114H

**Is the reclamation bond a rider under the BLM bond?**

**Unlined pit bond number:**

**Unlined pit bond amount:**

**Additional bond information attachment:**

#### **Section 4 - Injection**

**Would you like to utilize Injection PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Injection PWD discharge volume (bbl/day):**

**Injection well mineral owner:**

**Injection well type:**

**Injection well number:**

**Injection well name:**

**Assigned injection well API number?**

**Injection well API number:**

**Injection well new surface disturbance (acres):**

**Minerals protection information:**

**Mineral protection attachment:**

**Underground Injection Control (UIC) Permit?**

**UIC Permit attachment:**

#### **Section 5 - Surface Discharge**

**Would you like to utilize Surface Discharge PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Surface discharge PWD discharge volume (bbl/day):**

**Surface Discharge NPDES Permit?**

**Surface Discharge NPDES Permit attachment:**

**Surface Discharge site facilities information:**

**Surface discharge site facilities map:**

#### **Section 6 - Other**

**Would you like to utilize Other PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Operator Name:** AMEREDEV OPERATING LLC

**Well Name:** HOLLY FED COM 26 36 05

**Well Number:** 114H

**Other PWD type description:**

**Other PWD type attachment:**

**Have other regulatory requirements been met?**

**Other regulatory requirements attachment:**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Bond Info Data Report

02/26/2020

APD ID: 10400043719

Submission Date: 07/22/2019

Operator Name: AMEREDEV OPERATING LLC

Well Name: HOLLY FED COM 26 36 05

Well Number: 114H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

### Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB001478

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: