# New Mexico Oil Construction In Triplicate: UNITED STATE 8625 N. English Eleverse 1960

FORM APPROVED OMB NO. 1004-0136 Expires: February 28, 1995

O		- TOL	A IN TARINA	AND BENEVALORS
DEPARTMENT				- ten tract a a l
DEPARTMENT	Ur i			~~~
	• •			2 T 2 A T 1
		- A.M.	LEANTOO TATAT	の心のます。パリ

•	BUREAU OF	LAND MANAGE	MENT	. ••	NM-24489	•
APP	LICATION FOR P	ERMIT TO DE	ILL OR DEEPE	N	6. IF INDIAN, ALLOTT	EE OR TRIBE NAME
la. TYPE OF WORK	ORILL 🖫		7. UNIT AGREEMENT	HAKE		
b. TIPE OF WELL	GAS		SINGLE TON	LTIPLE	8. FARM OR LEASE HAME	WELL NO.
2. NAME OF OPERATOR	& GAS CORP. (GRE	G WILKES 915	5-683-7443)		La RICA FEDER	
	UISIANA SUITE 41	•	TEXAS 79701	-683-7443)	10. FIELD AND POOL	36352 02 WILDCAT
4. LOCATION OF WELL At surface	(Report location clearly and	in accordance with a	by State requirements.")		TONTO-SEVEN R	
1650' FSL 8	1980' FEL SECTION	N 13 T19S-R3	33E LEA CO. NM		11. SEC., T., R., M., OI AND SUBVET OR	
At proposed prod.	zone SAME	<b>-</b>			SECTION 13	T19S-R33E
14. DISTANCE IN MILE	S AND DIRECTION FROM NEA	REST TOWN OR POST O	FFICE*		12. COUNTY OR PARIS	H 13. STATE
Approximate]	ly 35 miles South	vest of Hobbs	New Mexico		LEA CO.	NEW MEXICO
15. DISTANCE FROM PR LOCATION TO NEAR PROPERTY OR LEAS (Also to nearest of	722	330'	5. NO. OF ACRES IN LEASE 520		F ACRES ASSIGNED HIS WELL 40	
18. DISTANCE FROM PI TO NEAREST WELL OR APPLIED FOR, ON	, DRILLING, COMPLETED.	500'	4000 t	- (	RT OR CABLE TOULS	
21. ELEVATIONS (Show	whether DF, RT, GR, etc.)	3697' GR	•	2000	WHEN APPROX	
23.		PROPOSED CASING	AND CEMENTING PROG	RAM <sup>S C</sup> COP	ten Controlled Wa	fer Basin
SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH		QUASTITY OF CEN	ENT
25''	Conductor	NA	40 /5	Cement	nto surface v	vith Redi-mi
12½"	J-55 8 5/8"	32	1500 1530	850 Sx	. circulate c	ement
7 7/8"	J-55 5½"	15.5	4000' (5	70% 83	EU <sub>estimate TO</sub>	C_1000'
<del></del>			1 /6	OCD	<u> </u>	
. Drill 25" h	ole to 40'. Set 4	0' of 20" con	ductor pipe and	Cement t	o surface wit	h Redi-mix.

- 2. Drill 124" hole to 1500. Run and set 1500 of 8 5/8" 32# J-55 ST&C casing. Cement with 650 Sx. of Class "C" 35/65 POZ Class "C" cement + 6% Gel, + 2% CaCl, + 1/4# Folesle/ Sx., tail in with 200 Sx. of Class "C" cement + 2% CaCl, + 1/4 Flocele/Sx. circulate cement to surface.
- 3. Drill 7 7/8" hole to 4000'. Run and set 4000' of  $5\frac{1}{2}$ " 15.5# J-55 ST&C casing. Cement with 400 Sx. of 50/50 POZ Class "C" cement + 10% Gel, + 5% Salt, + 3# Gilsonite/Sx. + 1/4 Flocele/Sx., tail in with 300 Sx. of Class "C" cement + 5% Sxlt, + fluid loss,+ dispersant. Estimate top of cement 1000' from surface.

APPROVAL SUBJECT TO GENERAL REQUIREMENTS AND

SPECIAL STIPULATIONS

(If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or VESPACE DESCRIBE PROPOSED PRODUCTIVE proposal is to drill or Climble Description of Sanks. IN ABOVE STATES THE PROPOSED PROPOSED PROPOSED IN COMMISSION TO proposed it is to deepen, give data on present productive zone and proposed new prop

SIGNED OF JUNEA TITLE AGENT	DATE 04/21/03
(This spuce for Federal or State office use)	OPER. OGRID NO. 193407
PERMIT NO APPROVAL DATE	PROPERTY NO. 283/2
Affinding inferent account of creaty and are appropriate index in a contract of creaty and a con	POOL CODE 59470 EFF. DATE 7-3/-03
CONDITIONS OF APPROVAL. IF ANY:	APINO 30-025-36352
/s/ LESLIE A THEISS	7(11)(0

TILE FIELD MANAGER

JUL 1 7 2003

\*See Instructions On Reverse Side

APPROVAL FOR 1 YEAR

DISTRICT I 1625 N. French Dr., Hobbs, NM 88240 DISTRICT II 811 South First, Artesia, NM 88210

#### State of New Mexico

Energy, Minerals and Natural Resources Department

Form C-102 Revised March 17, 1999

Submit to Appropriate District Office

Certificate No. Gary L. Johns

BASIN SURVEYS

7977

State Lease - 4 Copies Fee Lease - 3 Copies

DISTRICT III 1000 Rio Brazos Rd., Aztec, NM 87410

#### DISTRICT IV 2040 South Pacheco, Santa Fe, NM 87505


#### OIL CONSERVATION DIVISION

2040 South Pacheco Santa Fe, New Mexico 87505

☐ AMENDED REPORT

									1121 010
		1	WELL LO	CATION	AND ACREA	AGE DEDICATI	ON PLAT		
-	Number			Pool Code			Pool Name		
50-02	15-3	6352	594	70	T	ONTO- SEVEN R	IVERS		
Property	Code	}	Property Name				Well No	mper	
<u> 2831</u>	<u>d_</u>				A RICA FED			4	
OGRID N	0.			201101	Operator Naz			Eleva	
193407		<u></u>		CONC	HO OIL & G			369	
<del></del>					Surface Loc			<del></del>	<del></del>
L or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
J	13	19 S	33 E		1650	SOUTH	1980	EAST	LEA
			Bottom	Hole Lo	cation If Diff	erent From Sur	face		
L or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	Count
edicated Acre	s Joint o	or Infill Co	nsolidation	Code Or	der No.	<u> </u>			L
40									
NO ALLO	WABLE W	VILL BE AS	SSIGNED	TO THIS	COMPLETION	UNTIL ALL INTE	RESTS HAVE BE	EN CONSOLID	ATED
		OR A N	NON-STAN	IDARD UN	IIT HAS BEEN	APPROVED BY	THE DIVISION		
	i		<del></del>	T			OPERATO	OD CEDTIFICAT	PION
	OPERATOR CERTIFICATION								
	ļ		đ		ļ		11	y certify the the in n is true and compl	•
	!		<u>.</u>	best of my trovviedge and belief.					
					1				_
	1				1		11/00	Thou	iza
	l 			L	_ <u> </u>		Signature		
	<sub>1</sub>			T			Joe T	Janica	
	, , , , , , , , , , , , , , , , , , ,			1	) [		Printed Nam	e	
	:			1	1		Agent		
	1		•	1	1		Title	/nn	
	i				i		04/21/ Date	03	
	i			1	i				
	i						SURVEYO	OR CERTIFICAT	rion
	Ì				3			y that the well local	
	)				N		11	as plotted from fiel made by me or	
	ļ			ĥ	3		11	nd that the same is	
	1			3695.6	3700.2*		correct to th	ue best of my belie	f.
	I	LAT-N32*3	9'26 9"		0-	<b>— 1980' ———</b>	AF	RIL B, 2003	
	Į.	LONG-W10					Date Surveye		
				3605-7	3597.5		Signature &	Seal of	
	l			1				Was and	
	i				-0			KINI.	A .
		EXHIB	יי איי		1650		The state of the s		<u></u>
	1	EVHTRI	LI A		1		11 (15) (W.	O. No. 3196	

## SECTION 13, TOWNSHIP 19 SOUTH, RANGE 33 EAST, N.M.P.M., LEA COUNTY. NEW MEXICO.



DIRECTIONS TO LOCATION:

FROM THE JUNCTION US HWY 62/180 AND SMITH RANCH ROAD(H-55), GO NORTHWESTERLY ON H-55 FOR 2.1 MILES TO THE END OF PAVEMENT; THENCE GO WEST/NORTHWESTERLY ON A CALICHE LEASE ROAD FOR 1.5 MILE TO A "Y", AND GO NORTHERLY ON RIGHT FORK FOR 1.3 MILE TO A LEAE ROAD RIGHT; THENCE GO EAST 1.1 MILE TO SOUTHEAST CORNER OF THE LA RICA #T PAD AND PROPOSED LEASE ROAD.

BASIN SURVEYS P.O. BOX 1786 - HOBBS, NEW MEXICO

W.O. Number: 3196 | Drawn By: **K. GOAD**Date: 04-09-2003 | Disk: KJG CD#4 - 3196A.DWG

100 0 100 200 FEET


SCALE: 1" = 100'

## CONCHO OIL & GAS CORP.

EF: LA RICA FEDERAL No. 4 / Well Pad Topo

THE LA RICA FED. No. 4 LOCATED 1650' FROM THE SOUTH LINE AND 1980' FROM THE EAST LINE OF SECTION 13, TOWNSHIP 19 SOUTH, RANGE 33 EAST, N.M.P.M., LEA COUNTY, NEW MEXICO.

Survey Date: 04-07-2003 Sheet 1 of 1 Sheets




LA RICA FEDERAL #4
Located at 1650' FSL and 1980' FEL
Section 13, Township 19 South, Range 33 East,
N.M.P.M., Lea County, New Mexico.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (505) 393-7316 - Office (505) 392-3074 - Fax basinsurveys.com

W.O. Number:	3196AA - KJG CD#5
Survey Date:	04-08-2003
Scale: 1" = 20	000,
Date: 04-09-	-2003

CONCHO
OIL & GAS
CORP.



LA RICA FEDERAL #4
Located at 1650' FSL and 1980' FEL
Section 13, Township 19 South, Range 33 East,
N.M.P.M., Lea County, New Mexico.

Date: 04-09-2003



in the oilfield

P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (505) 393-7316 - Office (505) 392-3074 - Fax basinsurveys.com

W.O. Number:	3196AA - KJG CD#5
Survey Date:	04-08-2003
Scale: 1" = 2	MILES

CONCHO OIL & GAS CORP.

#### APPLICATION TO DRILL

CONCHO OIL & GAS CORP.

La RICA FEDERAL # 4

UNIT "J" SECTION 13

T19S-R33E LEA CO. NM

In response to questions asked under Section II of Bulletin NTL-6 the following information on the above well is provided for your consideration.

- 1. Location of well: 1650' FSL & 1980' FEL SECTION 13 T19S-R33E LEA CO. NM
- 2. Ground Elevation above Sea Level: 3697' GR.
- 3. Geological age of surface formation: Quaternary
- 4. Drilling tools and associated equipment: Conventional rotary drilling rig using drilling mud as a circulating medium to remove solids from hole.
- 5. Proposed drilling depth: 4000'
- 6. Estimated tops of geological markers:

Rustler Anhydrite	1400'	Yates	3300'
Tansill	3100'	Seven Rivers	3650 <b>'</b>

#### 7. Possible mineral bearing formations:

Yates

0i1

Seven Rivers

0i1

#### 8. Casing Program:

Hole Size	Interval	OD of Casing	Weight	Thread	Collar	<u>Grade</u>
25"	0-40	20"	NA	NA	NA	Conductor
12½"	0-1500	8 5/8"	32#	8-R	ST&C	J-55
7 7/8"	0-4000	5½"	15.5	8-R	ST&C	J-55

## APPLICATION TO DRILL

CONCHO OIL & GAS CORP.

La RICA FEDERAL # 4

UNIT "J" SECTION 13

T19S-R33E LEA CO. NM

## 9. CASING CEMENTING & SETTING DEPTHS:

20"	Conductor	Set 40' of 20" canductor and cement to surface with Redi-Mix
8 5/8"	Surface	Set 1500' of 8 5/8" 32# J-55 ST&C casing. Cement with 650 Sx. of 35/65 Class "C" POZ + 6% Gel, + ½# Flocele/Sx. + 2% CaCl, tail in with 200 Sx. of Class "C" cement + 2% CaCl, circulate cement to surface.
5½"	Production	Set 4000' of $5\frac{1}{2}$ " 15.5# J-55 ST&C casing. Cement with 400 Sx. of Class "C" 50/50 POZ + 10% Gel, + 5% Salt, + 3# Gilsonite/Sx. + $\frac{1}{2}$ # Flocele/Sx., tail in with 300 Sx. of Class "C" cement + fluid loss + dispersant + 5% Salt. TOC estimate 1000' from surface.

10. PRESSURE CONTROL EQUIPMENT: Exhibit "E" shows a 900 Series 3000 PSI working pressure B.O.P. consisting of an annular bag type preventor, middle blind rams and bottom pipe rams. The B.O.P. will be nippled up on the 8 5/8" casing and tested to API specifications. The B.O.P. will be operated at least once in each 24 hour period and the blind rams will be operated when drill pipe is out of hole on trips. Full opening stabbing valve and upper kelly cock will be utilized. Exhibit "E-1" shows a hydraulically operated closing unit and a 3"3000 PSI choke manifold with dual adjustable chokes. No abnormal pressures or temperatures are expected.

#### 11. PROPOSED MUD CIRCULATING SYSTEM:

DEPTH	MUD WT.	VISC.	FLUID LOSS	TYPE MUD SYSTEM
40-1500'	8.4-8.7	29-38	NC	Fresh water Spud Mud, add paper to control seepage
1500-3600*	10.0-10.1	29-38	NC	Brine water add paper to control seepage and use high viscosity sweeps to clean hole.
3600-4000°	10.0-10.1	30–38	10 cc or less	Same as above using starch or Dris-Pac system to control water loss.

Sufficient mud materials will be kept on location at all times in order to combat lost circulation, or unexpected kicks. In order to run DST's, open hole logs, and casing viscosity and/or water loss may have to be adjusted to meet these needs.

#### APPLICATION TO DRILL

CONCHO OIL & GAS CORP.

La RICA FEDERAL # 4

UNIT "J" SECTION 13

T19S-R33E LEA CO. NM

#### 12. LOGGING, CORING, AND TESTING PROGRAM:

- A. Open hole logs: Dual Laterolog, SNP, LDT, Gamma Ray, Caliper from TD back to 8 5/8" casing shoe. Run cased hole Gamma Ray, Neutron from 8 5/8" casing shoe back to surface.
- B. No cores or DST's are planned at this time.

#### 13. POTENTIAL HAZARDS:

No abnormal pressures or temperatures are expected. There is no known presence of  $\mathrm{H}^2\mathrm{S}$  in this area. If  $\mathrm{H}^2\mathrm{S}$  is encountered the operator will comply with the provisions of Onshore Oil and Gas Order No. 6. No lost circulation is expected to occur. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. Estimated BHP 1750 PSI, and Estimated BHT 135°.

#### 14. ANTICIPATED STARTING DATE AND DURATION OF OPERATION:

Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon after BLM approval and as soon as a rig will be available. Move in operation and drilling is expected to take 8 days. If production casing is run then an additional 30 days will be needed to complete well and construct surface facilities and/or lay flowlines in order to place well on production.

#### 15. OTHER FACETS OF OPERATIONS:

After running casing, cased hole Gamma Ray, Neutron Collar logs will be run from TD back to all possible productive zones. The <u>Seven Rivers</u> formation will be perforated and stimulated in order to establish production. The well will be swab tested and potentialed as an oil well.

#### HYDROGEN SULFIDE DRILLING OPERATIONS PLAN

- 1. All Company and Contract personnel admitted on location must be trained by a qualified H<sub>2</sub>S safety instructor to the following:
  - A. Characteristics of H<sub>2</sub>S
  - B. Physical effects and hazzards
  - C. Proper use of safety equipment and life support systems.
  - D. Principle and operation of H<sub>2</sub>S detectors, warning system and briefing areas.
  - E. Evacuation procedure, routes and first aid.
  - F. Proper use of 30 minute pressure demand air pack.
- 2.  $H_2S$  Detection and Alarm Systems
  - A. H<sub>2</sub>S detectors and audio alarm system to be located at bell nipple, end of blooie line (mud pit) and on derrick floor or doghouse.
- 3. Windsock and/or wind streamers
  - A. Windsock at mudpit area should be high enough to be visible.
  - B. Windsock at briefing area should be high enough to be visible.
  - C. There should be a windsock at entrance to location.
- 4. Condition Flags and Signs
  - A. Warning sign on access road to location.
  - B. Flags to be displayed on sign at entrance to location. Green flag, normal safe condition. Yellow flag indicates potential pressure and danger. Red flag, danger, H<sub>2</sub>S present in dangerous concentration. Only emergency personnel admitted to location.
- 5. Well control equipment
  - A. See exhibit "E" & "E-1"
- 6. Communication
  - A. While working under masks chalkboards will be used for communication.
  - B. Hand signals will be used where chalk board is inappropriate.
  - C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephoned will be available at most drilling foreman's trailer or living quarters.
- 7. Drillstem Testing
  - A. Exhausts will be watered.
  - B. Flare line will be equipped with an electric ignitor or a propane pilot light in case gas reaches the surface.
  - C. If the location is near to a dwelling a closed DST will be performed.

- 8. Drilling contractor supervisor will be required to be familiar with the effects H2S has on tubular goods and other mechanical equipment.
- 9. If H<sub>2</sub>S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas seperator will be brought into service along with H<sub>2</sub>S scavengers if necessary.

CONCHO OIL & GAS CORP.

La RICA FEDERAL # 4

UNTI "J" SECTION 13

T19S-R33E LEA CO. NM

- 1. EXISTING ROADS & PROPOSED ROADS: Area maps; Exhibit "B" is a reproduction of a County General Hi-way Map. Exhibit "C" is a reproduction of a USGS Topographic Map, showing existing and proposed roads. All existing roads will be maintained in a condition equal to or better than current conditions. Any new roads will be constructed to BLM specifications.
  - A. Exhibit "A" shows the proposed well site as staked.
  - B. From Hobbs New Mexico take U.S. Hi-way 62-180 West toward Carlsbad New Mexico go 30 miles to Smith Ranch road turn North go 2.2 miles bear Left follow caliche road in a Northwesterly direction for approximately 2 miles, turn North and go 1.4 miles, turn Right (East) go 1.2 miles to well # 1 continue 2000' to well location on the south side of road
  - C. Flowlines and powerline will be constructed along existing road shown on Exhibit "F".
- 2. FLANNED ACCESS ROADS: Approximately 1000' of new road will be constructed.
  - A. The access roads will be crowned and ditched to a 12' wide travel surface with a 40' Right-of-Way.
  - 3, Gradient of all roads will be less than 5.00%.
  - C. If turn-outs are necessary they will be constructed.
  - D. If needed roads will be surfaced with a mimimum of 4" of caliche. This material will be obtained from a local source.
  - E. Center-line for new roads will be flagged. Earth-work will be will be done as field conditions require.
  - F. Culverts will be placed in the access road if they are necessary. The roads will be constructed to utilaze low water crossings for drainage as required by topography.
- 3. LOCATIONS OF EXISTING WELLS IN A ONE MILE RADIUS. EXHIBIT "A-1"
  - A. Water wells

- None known
- 3. Dispusal walls
- None known
- C. Drilling wells
- None known
- D Producing wells
- As shown on Exhibit "A-1"
- E. Abandoned wells
- As shown on Exhibit "A-1"

CONCHO OIL & GAS CORP.

La RICA FEDERAL # 4

UNTI "J" SECTION 13

T19S-R33E LEA CO. NM

4. If on completion this well is a producer the operator will lay pipelines and construct powerlines along existing road R-O-W's or other existing R-O-W's.

Possible routes of pipelines, flowlines and powerlines are shown on Exhibit "F".

## 5. LOCATION AND TYPE OF WATER SUPPLY:

Water will be purchased locally from a commercial source and trucked over the access roads or piped to location in flexible lines laid on top of the ground.

## 6. SOURCE OF CONSTRUCTION MATERIAL:

If possible construction material will be obtained from the excavation of drill site, if additional material is needed it will be obtained from a local source and transported over the access roads as shown on Exhibit "C".

## 7. METHODS OF HANDLING WASTE MATERIAL:

- A. Drill cuttings will be disposed of in the reserve pits.
- B. All trash, junk and other waste material will be contained in trash cages or trash bins to prevent scattering. When the job is completed all contents will be removed and disposed of in a approved sanitary land fill.
- C. Salts remaining after completion of well will be picked up by the supplier, including broken sacks.
- D. Waste water from living quaters will be drained into holes with a minium of 10'. These holes will be covered during drilling and will be back filled when the well is completed. A Porto-John will be provided for the rig crews. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.
- E. Remaining drilling fluids will be allowed to evaporate in the reserve pits until the pits are dry enough to be broken out for furthed drying. If the drilling fluids do not evaporate in a reasonable time they will be hauled off by transports to a state approve disposal site. Later pips will be broken out to speed drying. Water produced during completion will be put in reserve pits. Oil and condensate produced will be put in storage tanks and sold.

#### 8. ANCILLARY FACILITIES:

A. No camps or air strips will be constructed on location.

CONCHO OIL & GAS CORP.

La RICA FEDERAL # 4

UNTI "J" SECTION 13

T19S-R33E LEA CO. NM

#### 9. WELL SITE LAYOUT

- A. Exhibit "D" shows the proposed well site layout.
- B. This exhibit indicated proposed location of reserve and sump pits and living facilities.
- C. Mud pits in the active circulating system will be steel pits & the reserve pit is proposed to be unlined unless subsurface condition encountered during pit construction indicate that lining is needed for lateral containment of fluids.
- D. If needed, the reserve pit is to be lined with polyethelene. The pit liner will be 6 mils thick. Pit liner will extend a minimum 2'00" over the reserve pits dikes where the liner will be anchored down.
- E. The reserve pit will be fenced on three sides with four strands of barbed wire during drilling and completion phases. The fourth side will be fenced after all drilling operations have ceased. If the well is a producer, the reserve pit fence will be torn down. The reserve pit and those areas of the location not essential to production facilities will be reclaimed and seeded per BLM requirements.

#### 10. PLANS FOR RESTORATION OF SURFACE

Rehabilitation of the location and reserve pit will start in a timely manner after all drilling operations cease. The type of reclamation will depend on whether the well is a producer or a dry hole.

However, in either event, the reserve pit will be allowed to dry properly, and fluid removed and disposed of in accordance with Article 7.B as previously noted. The pit area will then be leveled and contoured to conform to the original and surrounding area. Drainage systems, if any, will be reshaped to the original configuration with provisions made to alleviate erosion. These may need to be modified in certain circumstances to prevent inundation of the location's pad and surface facilities. After the area has been shaped and contoured, topsoil from the spoil pile will be placed over the disturbed area to the extent possible. Revegetation procedures will comply with BLM standards.

If the well is a dry hole, the pad and road area will be contoured to match the existing terrain. Topsoil will be spread to the extent possible. Revegetation will comply with BLM standards.

Should the well be a producer, the previously noted procedures will apply to those areas which are not required for production facilities.

CONCHO OIL & GAS CORP.

La RICA FEDERAL # 4

UNTI "J" SECTION 13

T19S-R33E LEA CO. NM

#### 11. OTHER INFORMATION:

- A. Topography consists of sand dunes with a slight dip to the West. Deep sandy soil supports shinnery oak, native grasses, and an occasional mesquite tree.
- B. Surface is owned by the U.S. Government and is administered by the Bureau of Land Management. The surface is used for grazing livestock and the production of oil and gas.
- C. An archaeological survey will be conducted on the location and access roads. This report will be filed with The Bureau of Land Management in the Carlsbad field office.
- D. There are no dwellings in the near vicinity of this location.

#### 12. OPERATORS REPRESENTIVES:

Before construction:

TIERRA EXPLORATION, INC P.O. BOX 2188
HOBBS, NEW MEXICO 88241
OFFICE Ph. 505-391-8503
JOE T. JANICA

During and after construction:


CONCHO OIL & GAS CORP.
110 WEST LOUISIANA SUITE 410
MIDLAND, TEXAS 79701
OFFICE Ph. 915-683-7443
GREG WILKES


13. CERTIFICATION: I hereby certify that I, or persons under my direct supervision have inspected the proposed drill site and access roads, and that I am fimiliar with the conditions which currently exist, that the statements made in this plan are to the best of my knowledge true and correct, and that the work associated with the operations proposed herein will be performed by CONCHO OIL & GAS CORP. it's contractors/subcontractors is in compformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provision of U.S.C. 1001 for the filing of a false report.


NAME : 04/21/03


DATE : 04/21/03

TITLE : Agant










- Wind Direction Indicators (wind sock or streamers)
- △ H2S Monitors
  (alarms at bell nipple and shale shaker)
- Briefing Areas
- O Remote BOP Closing Unit
- ☐ Sign and Condition Flags

EXHIBIT "D"
RIG LAY OUT PLAT

CONCHO OIL & GAS CORP.

La RICA FEDERAL # 4
UNIT "J" SECTION 13
T19S-R33E LEA CO. NM




### ARRANGEMENT SRRA

900 Series 3000 PSI WP

EXHIBIT "E"
SKETCH OF B.O.P. TO BE USED ON

CONCHO OIL & GAS CORP.

La RICA FEDERAL # 4
UNIT "J" SECTION 13
T19S-R33E LEA CO. NM



Typical choke manifold assembly for 3M WP system




EXHIBIT "E-1"
CHOKE MANIFOLD & CLOSING UJIT

CONCHO OIL & GAS CORP.

La RICA FEDERAL # 4

UNIT "J" SECTION 13

T19S-R33E LEA CO. NM

