

9. Abnormal Conditions, Pressures, Temperatures, & Potential Hazards:

No abnormal pressures and/or temperatures are anticipated. Estimated BHP in the Morrow is 6600 psi. No hydrogen sulfide or other hazardous gases or fluids are known to exist in this area. Possible lost circulation interval from 3400' to 4300'.

10. Anticipated Starting Date and Duration of Operations:

The anticipated start date will be September 10, 2002. Once commenced, drilling operations should be completed in approximately 40 days. If the well is productive, another 30 days will be required for completion work and facility installation.

RECEIVED  
FACILITIES  
000