

6. Proposed Mud System:

The well will be drilled to TD with a combination of fresh water and 10# brine. The applicable depths and properties of this system are as follows:

<u>Depth</u>	<u>Type</u>	<u>Weight (ppg)</u>	<u>Viscosity (sec)</u>	<u>Water Loss (cc)</u>
0-1300'	Fresh water	8.4	28	NC
1300-4000'	Brine	10.0	29	NC

Sufficient mud materials to maintain mud properties and meet minimum lost circulation requirements will be kept at the wellsite at all times.

7. Auxiliary Well Control and Monitoring Equipment:

- a) A kelly cock will be kept in the string at all times.
- b) A full opening drill pipe stabbing valve (TIW/inside BOP) with proper drill pipe connections will be on the rig floor at all times.
- c) An electronic pit volume totalizer system will NOT be used.
The drilling fluids system will be visually monitored at all time

8. Logging, Testing, and Coring Program:

- a) Drillstem tests will be run on the basis of drilling shows.
- b) The electric logging program will consist of:
 - 1) 7-7/8" hole - Gamma ray, dual induction log, compensated neutron and litho-density logs.
- c) No conventional cores are planned. Selected intervals may be sidewall cored based upon shows and openhole logs.
- d) Further testing procedures will be determined after the 5-1/2" production casing has been cemented at TD.