

7. Auxiliary Well Control and Monitoring Equipment:

- a) A kelly cock will be kept in the string at all times.
- b) A full opening drill pipe stabbing valve (TIW/inside BOP) with proper drill pipe connections will be on the rig floor at all times.
- c) An electronic pit volume totalizer system will NOT be used.  
The drilling fluids system will be visually monitored at all time

8. Logging, Testing, and Coring Program:

- a) Drillstem tests will be run on the basis of drilling shows.
- b) The electric logging program will consist of:
  - 1) 7-7/8" hole - Gamma ray, dual induction log, compensated neutron and litho-density logs.
- c) No conventional cores are planned. Selected intervals may be sidewall cored based upon shows and openhole logs.
- d) Further testing procedures will be determined after the 5-1/2" production casing has been cemented at TD.

9. Abnormal Conditions, Pressures, Temperatures, and Potential Hazards:

No abnormal pressures, temperatures, or other potential hazard are anticipated.

No hydrogen sulfide or other hazardous gases or fluids have been encountered, reported, or are known to exist at this depth in this area. No major lost circulation zones have been reported in offsetting wells.

The maximum anticipated bottom hole pressure is approximately 1732 psi. (4000' x .433 psi/ft = 1732 psi.)

The maximum anticipated bottom hole temperature is 90 deg F.

10. Anticipated Starting Date and Duration of Operations:

Road and location work will not begin until approval has been received from the BLM. The anticipated spud date is July 25, 1996. Once commenced, the drilling operation should be complete in 15 days. If the well is productive, an additional 30 days will be required for completion, testing, and installation of permanent facilities.