

State of New Mexico
Energy Minerals and Natural Resources
Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-144
Revised October 11, 2022

fJMB2220051571

Pit, Below-Grade Tank, or
Proposed Alternative Method Permit or Closure Plan Application

ycon2218747524

Type of action: ☐ Below grade tank registration
☐ Permit of a pit or proposed alternative method
☒ Closure of a pit, below-grade tank, or proposed alternative method
☐ Modification to an existing permit/or registration
☐ Closure plan only submitted for an existing permitted or non-permitted pit, below-grade tank, or proposed alternative method

Instructions: Please submit one application (Form C-144) per individual pit, below-grade tank or alternative request

Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.

1.
Operator: LOGOS Operating, LLC OGRID #: 289408
Address: 2010 Afton Place, Farmington NM 87401
Facility or well name: Section 16D #001 Burial Trench #001 See list in closure report
API Number: See list in closure report OCD Permit Number: _____
U/L or Qtr/Qtr D Section 16 Township 31N Range 06A County: San Juan
Center of Proposed Design: Latitude _____ Longitude _____ NAD83
Surface Owner: ☐ Federal ☐ State ☐ Private ☐ Tribal Trust or Indian Allotment

2.
☒ **Pit:** Subsection F, G or J of 19.15.17.11 NMAC
Temporary: ☒ Drilling ☐ Workover
☐ Permanent ☐ Emergency ☐ Cavitation ☐ P&A ☐ Multi-Well Fluid Management Low Chloride Drilling Fluid ☒ yes ☐ no
☒ Lined ☐ Unlined Liner type: Thickness 30 mil ☐ LLDPE ☐ HDPE ☐ PVC ☐ Other _____
☒ String-Reinforced
Liner Seams: ☐ Welded ☐ Factory ☐ Other _____ Volume: 36,180.19 bbl Dimensions: L 150 x W 150 x D 17

3.
☐ **Below-grade tank:** Subsection I of 19.15.17.11 NMAC
Volume: _____ bbl Type of fluid: _____
Tank Construction material: _____
☐ Secondary containment with leak detection ☐ Visible sidewalls, liner, 6-inch lift and automatic overflow shut-off
☐ Visible sidewalls and liner ☐ Visible sidewalls only ☐ Other _____
Liner type: Thickness _____ mil ☐ HDPE ☐ PVC ☐ Other _____

4.
☐ **Alternative Method:**
Submittal of an exception request is required. Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

5.
Fencing: Subsection D of 19.15.17.11 NMAC (*Applies to permanent pits, temporary pits, and below-grade tanks*)
☐ Chain link, six feet in height, two strands of barbed wire at top (*Required if located within 1000 feet of a permanent residence, school, hospital, institution or church*)
☐ Four foot height, four strands of barbed wire evenly spaced between one and four feet
☐ Alternate. Please specify _____

6.

Netting: Subsection E of 19.15.17.11 NMAC (*Applies to permanent pits and permanent open top tanks*)

- ☐ Screen ☐ Netting ☐ Other _____
- ☐ Monthly inspections (If netting or screening is not physically feasible)

7.

Signs: Subsection C of 19.15.17.11 NMAC

- ☐ 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers
- ☐ Signed in compliance with 19.15.16.8 NMAC

8.

Variances and Exceptions:

Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance.

Please check a box if one or more of the following is requested, if not leave blank:

- ☐ Variance(s): Requests must be submitted to the appropriate division district for consideration of approval.
- ☐ Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

9.

Siting Criteria (regarding permitting): 19.15.17.10 NMAC***Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of acceptable source material are provided below. Siting criteria does not apply to drying pads or above-grade tanks.*****General siting****Ground water is less than 25 feet below the bottom of a low chloride temporary pit or below-grade tank.**

- ☐ NM Office of the State Engineer - iWATERS database search; ☐ USGS; ☐ Data obtained from nearby wells

☐ Yes ☒ No

☐ NA

Ground water is less than 50 feet below the bottom of a Temporary pit, permanent pit, or Multi-Well Fluid Management pit.

NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells

☐ Yes ☒ No

☐ NA

Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. **(Does not apply to below grade tanks)**

- Written confirmation or verification from the municipality; Written approval obtained from the municipality

☐ Yes ☒ No

Within the area overlying a subsurface mine. **(Does not apply to below grade tanks)**

- Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division

☐ Yes ☒ No

Within an unstable area. **(Does not apply to below grade tanks)**

- Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map

☐ Yes ☒ No

Within a 100-year floodplain. **(Does not apply to below grade tanks)**

- FEMA map

☐ Yes ☒ No

Below Grade Tanks

Within 100 feet of a continuously flowing watercourse, significant watercourse, lake bed, sinkhole, wetland or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 200 horizontal feet of a spring or a fresh water well used for public or livestock consumption;.

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Temporary Pit using Low Chloride Drilling Fluid (maximum chloride content 15,000 mg/liter)

Within 100 feet of a continuously flowing watercourse, or any other significant watercourse or within 200 feet of any lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). (Applies to low chloride temporary pits.)

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 300 feet from a occupied permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 200 horizontal feet of a spring or a private, domestic fresh water well used by less than five households for domestic or stock watering purposes, or 300feet of any other fresh water well or spring, in existence at the time of the initial application.

NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 100 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Temporary Pit Non-low chloride drilling fluid

Within 300 feet of a continuously flowing watercourse, or any other significant watercourse, or within 200 feet of any lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 500 horizontal feet of a spring or a private, domestic fresh water well used by less than five households for domestic or stock watering purposes, or 1000 feet of any other fresh water well or spring, in the existence at the time of the initial application;

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 300 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Permanent Pit or Multi-Well Fluid Management Pit

Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 500 horizontal feet of a spring or a fresh water well used for domestic or stock watering purposes, in existence at the time of initial application.

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 500 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

10.

Temporary Pits, Emergency Pits, and Below-grade Tanks Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC
- ☐ Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 NMAC
- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
- ☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
- ☐ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

☐ Previously Approved Design (attach copy of design) API Number: _____ or Permit Number: _____

11.

Multi-Well Fluid Management Pit Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
- ☐ A List of wells with approved application for permit to drill associated with the pit.
- ☐ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC
- ☐ Hydrogeologic Data - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC
- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC

☐ Previously Approved Design (attach copy of design) API Number: _____ or Permit Number: _____

12.

Permanent Pits Permit Application Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Hydrogeologic Report - based upon the requirements of Paragraph (1) of Subsection B of 19.15.17.9 NMAC
☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
☐ Climatological Factors Assessment
☐ Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Dike Protection and Structural Integrity Design - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Quality Control/Quality Assurance Construction and Installation Plan
☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
☐ Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Nuisance or Hazardous Odors, including H₂S, Prevention Plan
☐ Emergency Response Plan
☐ Oil Field Waste Stream Characterization
☐ Monitoring and Inspection Plan
☐ Erosion Control Plan
☐ Closure Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

13.

Proposed Closure: 19.15.17.13 NMAC

Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan.

- Type: ☐ Drilling ☐ Workover ☐ Emergency ☐ Cavitation ☐ P&A ☐ Permanent Pit ☐ Below-grade Tank ☐ Multi-well Fluid Management Pit
☐ Alternative
- Proposed Closure Method: ☐ Waste Excavation and Removal
☐ Waste Removal (Closed-loop systems only)
☐ On-site Closure Method (Only for temporary pits and closed-loop systems)
☐ In-place Burial ☐ On-site Trench Burial
☐ Alternative Closure Method

14.

Waste Excavation and Removal Closure Plan Checklist: (19.15.17.13 NMAC) **Instructions:** Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC
☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.13 NMAC
☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings)
☐ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

15.

Siting Criteria (regarding on-site closure methods only): 19.15.17.10 NMAC

Instructions: Each siting criteria requires a demonstration of compliance in the closure plan. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria require justifications and/or demonstrations of equivalency. Please refer to 19.15.17.10 NMAC for guidance.

Ground water is less than 25 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA
Ground water is between 25-50 feet below the bottom of the buried waste - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA
Ground water is more than 100 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA
Within 100 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within 300 horizontal feet of a private, domestic fresh water well or spring used for domestic or stock watering purposes, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input type="checkbox"/> No
Written confirmation or verification from the municipality; Written approval obtained from the municipality	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within 300 feet of a wetland. US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance	

adopted pursuant to NMSA 1978, Section 3-27-3, as amended.

- Written confirmation or verification from the municipality; Written approval obtained from the municipality

☐ Yes ☐ No

Within the area overlying a subsurface mine.

- Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division

☐ Yes ☐ No

Within an unstable area.

- Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map

☐ Yes ☐ No

Within a 100-year floodplain.

- FEMA map

☐ Yes ☐ No

16.

On-Site Closure Plan Checklist: (19.15.17.13 NMAC) *Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.*

- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
☐ Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection E of 19.15.17.13 NMAC
☐ Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of Subsection K of 19.15.17.11 NMAC
☐ Construction/Design Plan of Temporary Pit (for in-place burial of a drying pad) - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC
☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of 19.15.17.13 NMAC
☐ Waste Material Sampling Plan - based upon the appropriate requirements of 19.15.17.13 NMAC
☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings or in case on-site closure standards cannot be achieved)
☐ Soil Cover Design - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

17.

Operator Application Certification:

I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.

Name (Print): _____ Title: _____

Signature: _____ Date: _____

e-mail address: _____ Telephone: _____

18.

OCD Approval: ☐ Permit Application (including closure plan) ☐ Closure Plan (only) ☐ OCD Conditions (see attachment)

OCD Representative Signature: Joel Stone Approval Date: 11/04/2025

Title: Senior Environmental Scientist OCD Permit Number: fJMB2220051571/ycon2218747524

19.

Closure Report (required within 60 days of closure completion): 19.15.17.13 NMAC

Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.

☒ Closure Completion Date: 8/4/2025

20.

Closure Method:

- ☐ Waste Excavation and Removal ☒ On-Site Closure Method ☐ Alternative Closure Method ☐ Waste Removal (Closed-loop systems only)
☐ If different from approved plan, please explain.

21.

Closure Report Attachment Checklist: *Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check mark in the box, that the documents are attached.*

- ☒ Proof of Closure Notice (surface owner and division)
☐ Proof of Deed Notice (required for on-site closure for private land only)
☒ Plot Plan (for on-site closures and temporary pits)
☒ Confirmation Sampling Analytical Results (if applicable)
☒ Waste Material Sampling Analytical Results (required for on-site closure)
☒ Disposal Facility Name and Permit Number
☒ Soil Backfilling and Cover Installation
☒ Re-vegetation Application Rates and Seeding Technique
☐ Site Reclamation (Photo Documentation)

On-site Closure Location: Latitude 36.903881 _____ Longitude -107.476267 _____ NAD: ☐ 1927 ☒ 1983

22.

Operator Closure Certification:

I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.

Name (Print): Vanessa Fields Title: Sr. Regulatory Manager

Signature: Vanessa Fields Date: 10/28/2025

e-mail address: vfields@logosresourcesllc.com Telephone: 505-320-1243



Burial Trench and Drying Pad Closure Report

In accordance with Rule 19.15.17.13 NMAC the following plan describes the general in-place closure requirements of burial trenches/drying pad on LOGOS Operating, LLC location in the San Juan Basin of New Mexico. This is LOGOS's standard procedure for all burial trenches/drying pads to be utilized for the drilling, completion and/or workovers of oil and gas wells operated by LOGOS. For those burial trenches/drying pads which do not conform to this standard closure plan, a separate closure plan will be developed and utilized.

All closure activities will include proper documentation and will be submitted to NMOCD within 60 days of the pit closure. Closure report will be filed on C-144 and will include the following:

- Details on Capping and Covering, where applicable (See report)
- Plot plan (Pit Diagram) (included as an attachment)
- Inspection Log (included as an attachment)
- Notification Documentation (included as an attachment)
- Sampling Results (included as an attachment)
- Copy of Deed Notice will be filed with the County Clerk **(Not required on Federal, State or Federal Tribal Land as stated by FAQ dated October 30, 2008).**

General Requirements:

1. Prior to closure LOGOS shall remove all free liquids reasonably achievable from the prior drying pad and dispose of such liquids at a division approved facility.
 - **All liquids recovered through a shell shaker, blended then placed on drying pad to ensure all liquids were removed prior to placing in the trench burial.**
2. The preferred method of closure for all temporary pits will be on-site closure by in-place burial/drying pad, provided all the criteria in 19.15.17.13.D are met.
 - **On-site burial plan for this location was approved by the Division District Office on July 19, 2022, OCD permit number – (Facility ID fJMB2220051571)**
3. The surface owner shall be notified by (certified mail, return receipt or via email) requested that LOGOS's plans closure of operations.
 - **The closure process notification to the surface landowner (BLM) was sent via phone on July 29, 2025.**
4. Within 6 months of the rig-off status occurring LOGOS will ensure that the temporary pit and/or burial trench/drying pad is closed.

Rosa Unit 550H API: 30-045-38439; Rig released 7/16/2025

Rosa Unit 552H API: 30-45-38442; Rig released 7/24/2025

Rosa Unit 554H API: 30-045-38441; Rig released 7/30/2025

Rosa Unit 556H API: 30-045-38440; Rig released 8/18/2025.

5. Notice of Closure will give to the division district office verbally and/ or in writing at least 72 hours, but not more than one week, prior to closure operations. The notification of Closure will include the following: Operator's Name, Well Name and API number and Location (USTR).
 - **The Division District Office of NMOCD was notified by email. (See attached)**



6. Pit contents shall be achieved by mixing with non-waste containing, earthen material. The solidification process will be accomplished use a combination of natural drying and mechanical mixing. Pit contents will be mixed with non-waste, earthen material to a consistency that is deemed safe and stable. The mixing ratio shall not exceed 3 parts non-waste to 1 part pit contents.
- LOGOS mixed the pit/ burial contents with non-waste containing earthen material to achieve appropriate solidification and a consistency that was deemed safe and stable. The solidification process was accomplished using a combination of natural drying and mechanically mixing using a dozer and track hoe. The mixing ratio consisted of approximately 3 parts native soil to 1 part pit contents.
7. An eight-point composite sample will be taken of the pit using sampling tools and all samples tested per parameters listed in Table II of 19.15.17.13 NMAC. In the even that the criteria are not met (See Table I), all contents will be handled per 19.15.17.13 Subsection C (i.e dig and haul to a division-approved facility.) Approval to haul will be requested of the division district office prior to initiation.
- A five & eight-point composite was taken of the drying pad & burial trench area using sampling tools and all samples tested per parameters listed 19.15.17.13 NMAC Table II on August 4, 2025.


Table II Closure Criteria for Burial Trenches Waste Left in Place in Temporary Pits				
Depth below bottom of pit to GW < than 10,000 mg/l TDS	Constituent	Method *	Limit**	8/5/2025 Burial Trench Results (8pt)
➤ 51-100 feet	Chloride	EPA Method 300.0	40,000 mg/kg	4110 mg/kg
	TPH	EPA SW-846 Method 418.1	2,500 mg/kg	327.7 mg/kg
	GRO+DRO	EPA SW-846 Method 8015M	1,000 mg/kg	270 mg/kg
	BTEX	EPA SW-846 Method 8021 B or 8260B	50 mg/kg	2.0058 mg/kg
	Benzene	EPA SW-846 Method 8021B or 8015M	10 mg/kg	0.0712 mg/kg
	Paint Filter Test			

Table II Closure Criteria for Drying Pad Waste Left in Place in Temporary Pits				
Depth below bottom of pit to GW < than 10,000 mg/l TDS	Constituent	Method *	Limit**	8/5/2025 Drying Pad Results (5pt)
➤ 50-100 feet	Chloride	EPA Method 300.0	40,000 mg/kg	618 mg/kg
	TPH	EPA SW-846 Method 418.1	2,500 mg/kg	62.2 mg/kg
	GRO+DRO	EPA SW-846 Method 8015M	1,000 mg/kg	62.2 mg/kg
	BTEX	EPA SW-846 Method 8021 B or 8260B	50 mg/kg	0.20884mg/kg
	Benzene	EPA SW-846 Method 8021B or 8015M	10 mg/kg	Non-Detect mg/kg
	Paint Filter Test			



8. Upon achieving all applicable waste stabilization, fold the outer edges of the trench liner to overlap the waste material in the trench prior to the installation of the geomembrane cover, install a geomembrane cover over the waste material in the lined trench.
 - **Following stabilization, the outer edges of the trench liner were folded over the solids, then a geomembrane cover was placed over the sloping surface of the stabilized waste material on August 9, 2025.**
9. Upon completion of solidification and testing, the pit area will be backfilled with soil cover for burial in-place or burial trench/drying pad consists of four feet non-waste containing, uncontaminated earthen material. The soil cover shall include either the background thickness of topsoil or one-foot suitable material to establish vegetation at the site, whichever is greater.
 - **Upon completion of solidification and testing, the burial trench area was backfilled with non-waste earthen material compacted to native conditions. A minimum of four feet of cover was achieved and the cover included one foot of suitable material to establish vegetation at the site.**
10. Re-contouring of area will match fit, shape, line, form, and texture of the surrounding. Re-shaping will include drainage control, prevent ponding, and minimize erosion. Natural drainages will be unimpeded and stormwater Best Management Practices (BMPs) will be used to aid in soil stabilization and protection surface water quality.
 - **LOGOS covered the trench and the drying pad to match fit, shape, line form and texture of the surrounding area. Re-shaping included drainage control, to prevent ponding and erosion. Natural drainages were unimpeded and BMPs were used to aid in the soil stabilization. Will complete final closing of the area at final reclamation quarry. This area is in use for future drilling projects. Upon final reclamation LOGOS will contour the location to approximately match previous topography per the conditions of approvals (COA)s within the APD.**
11. Notification will be sent to the Division District office when the reclaimed area is seeded.
 - **LOGOS will comply with the surface owner (BLM) per the re-seeding requirements stated in the (COA)s of the APD for referenced wells. Will complete final closing of the area at final reclamation quarry.**
12. LOGOS shall seed the disturbed areas the first growing season after the pit and/or burial trench/drying pad is closed. Seeding will be accomplished vis drilling on the contour whenever practical or by other division-approved methods. BLM or Forest Service stipulated seed mixes will be used on federal lands. Vegetative cover will equal 70% of the native perennial vegetative cover (un-impacted) consisting of at least three native plant species, including at least on grass, but not including noxious weeds, and maintain the cover through two successive growing seasons. Repeat seeding or planting will be continue until successful vegetative growth occurs.
 - **LOGOS will comply with the surface owner (BLM) per the re-seeding requirements stated in the (COA)s of the APD for referenced wells. Will complete final closing of the area at final reclamation quarry.**
13. LOGOS shall place a steel marker at the center of the onsite burial/drying pad. The steel marker shall be not less than four inches in diameter and shall be cemented in a three-foot deep hole at a minimum. The marker will be flush with the ground to allow access and safety concerns. The marker will include a threaded collar to be used for future abandonment. The top of the marker will contain a welded steel 12" square plate that indicates the onsite burial/drying pad. The plate will be easily removable, and a four-foot-tall riser will be threaded into the top of the collar marker and welded around the base with the LOGOS information. The information will include Operator Name, Well Name and number, Unit, Section, Township Range, and an indicator that the marker is an onsite burial location.
 - **The burial trench was located with a steel marker per the above listed specifications. (See attached).**

PROPOSED ACCESS SURVEY FOR
LOGOS OPERATING, LLC
SECTION 16D RECYCLING CONTAINMENT
LOCATED IN THE NW/4 OF SEC. 16, T-31-N, R-6-W, N.M.P.M.
SAN JUAN COUNTY, NEW MEXICO



OWNERSHIP

LOCATION	OWNER	STATION	FT./RODS
NW/4 S16, T31N, R6W	B.L.M.	E.S. 0+00 TO E.S. 0+31.59	31.59/1.91

BASIS OF BEARING: AS MEASURED BY GPS BETWEEN FOUND MONUMENTS AT THE NORTHWEST WITNESS CORNER AND THE WEST QUARTER CORNER OF SECTION 16, TOWNSHIP 31 NORTH, RANGE 6 WEST, N.M.P.M. SAN JUAN COUNTY, NEW MEXICO. BEARS S00°12'19\"E A DISTANCE OF 2618.66' AS MEASURED BY G.P.S. LOCAL GRID NAD83.

DATE OF SURVEY:	GWR	DRAWN BY:	GWR
SURVEY CREW:	4/20/22	DATE:	4/24/22

REV. 1	
REV. 2	

I, GLEN W. RUSSELL, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

GLEN W. RUSSELL
GLEN W. RUSSELL, PLS
NEW MEXICO L.S. #15703
DATE APRIL 25, 2022


VECTOR SURVEYS, LLC

Professional Land Surveys, Mapping,
GPS Surveys & Oil Field Services
122 N Wall Avenue, Farmington, NM 87401
Phone (505) 320-9595
E-Mail: vectorg001@msn.com

WORK ORDER NO.:	LOGOS106	CAD FILE:	SEC16D RC_AR
-----------------	----------	-----------	--------------

Report to:

Richard Martin



envirotech

Practical Solutions for a Better Tomorrow

Analytical Report

Logos Resources

Project Name: Section 16D Drying Pad/Burial Trench

Work Order: E508043

Job Number: 12035-0114

Received: 8/5/2025

Revision: 1

Report Reviewed By:

Walter Hinchman
Laboratory Director
8/7/25

5796 U.S. Hwy 64
Farmington, NM 87401

Phone: (505) 632-1881
Envirotech-inc.com



Envirotech Inc. certifies the test results meet all requirements of TNI unless noted otherwise.
Statement of Data Authenticity: Envirotech Inc. attests the data reported has not been altered in any way.
Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech Inc.
Envirotech Inc. holds the Utah TNI certification NM00979 for data reported.
Envirotech Inc. holds the Texas TNI certification T104704557 for data reported.

Date Reported: 8/7/25



Richard Martin
2010 Afton Place
Farmington, NM 87401

Project Name: Section 16D Drying Pad/Burial Trench
Workorder: E508043
Date Received: 8/5/2025 8:29:00AM

Richard Martin,

Thank you for choosing Envirotech, Inc. as your analytical testing laboratory for the sample(s) received on, 8/5/2025 8:29:00AM, under the Project Name: Section 16D Drying Pad/Burial Trench.

The analytical test results summarized in this report with the Project Name: Section 16D Drying Pad/Burial Trench apply to the individual samples collected, identified and submitted bearing the project name on the enclosed chain-of-custody. Subcontracted sample analyses not conducted by Envirotech, Inc., are attached in full as issued by the subcontract laboratory.

Please review the Chain-of-Custody (COC) and Sample Receipt Checklist (SRC) for any issues regarding sample receipt temperature, containers, preservation etc. To best understand your test results, review the entire report summarizing your sample data and the associated quality control batch data.

All reported data in this analytical report were analyzed according to the referenced method(s) and are in compliance with the latest NELAC/TNI standards, unless otherwise noted. Samples or analytical quality control parameters not meeting specific QC criteria are qualified with a data flag. Data flag definitions are located in the Notes and Definitions section of this analytical report.

If you have any questions concerning this report, please feel free to contact Envirotech, Inc.

Respectfully,

Walter Hinchman
Laboratory Director
Office: 505-632-1881
Cell: 775-287-1762
whinchman@envirotech-inc.com

Raina Schwanz
Laboratory Administrator
Office: 505-632-1881
rainaschwanz@envirotech-inc.com

Field Offices:

Southern New Mexico Area

Lynn Jarboe
Laboratory Technical Representative
Office: 505-421-LABS(5227)
Cell: 505-320-4759
ljjarboe@envirotech-inc.com

Michelle Gonzales
Client Representative
Office: 505-421-LABS(5227)
Cell: 505-947-8222
mgonzaless@envirotech-inc.com

Envirotech Web Address: www.envirotech-inc.com

Table of Contents

Title Page	1
Cover Page	2
Table of Contents	3
Sample Summary	4
Sample Data	5
Section 16D Burial Trench	5
Section 16D Drying Pad	6
QC Summary Data	7
QC - Volatile Organics by EPA 8021B	7
QC - Nonhalogenated Organics by EPA 8015D - GRO	8
QC - Nonhalogenated Organics by EPA 8015D - DRO/ORO	9
QC - Anions by EPA 300.0/9056A	10
Definitions and Notes	11
Chain of Custody etc.	12

Sample Summary

Logos Resources	Project Name:	Section 16D Drying Pad/Burial Trench	Reported: 08/07/25 14:01
2010 Afton Place	Project Number:	12035-0114	
Farmington NM, 87401	Project Manager:	Richard Martin	

Client Sample ID	Lab Sample ID	Matrix	Sampled	Received	Container
Section 16D Burial Trench	E508043-01A	Soil	08/04/25	08/05/25	Glass Jar, 2 oz.
Section 16D Drying Pad	E508043-02A	Soil	08/04/25	08/05/25	Glass Jar, 2 oz.



Sample Data

Logos Resources
2010 Afton Place
Farmington NM, 87401

Project Name: Section 16D Drying Pad/Burial Trench
Project Number: 12035-0114
Project Manager: Richard Martin

Reported:
8/7/2025 2:01:54PM

Section 16D Burial Trench

E508043-01

Analyte	Result	Reporting Limit	Dilution	Prepared	Analyzed	Notes
Volatile Organics by EPA 8021B	mg/kg	mg/kg	Analyst: SL		Batch: 2532040	
Benzene	0.0712	0.0250	1	08/05/25	08/06/25	
Ethylbenzene	0.0596	0.0250	1	08/05/25	08/06/25	
Toluene	0.391	0.0250	1	08/05/25	08/06/25	
o-Xylene	0.131	0.0250	1	08/05/25	08/06/25	
p,m-Xylene	0.611	0.0500	1	08/05/25	08/06/25	
Total Xylenes	0.742	0.0250	1	08/05/25	08/06/25	
<i>Surrogate: 4-Bromochlorobenzene-PID</i>						
	97.6 %	70-130		08/05/25	08/06/25	
Nonhalogenated Organics by EPA 8015D - GRO	mg/kg	mg/kg	Analyst: SL		Batch: 2532040	
Gasoline Range Organics (C6-C10)	ND	20.0	1	08/05/25	08/06/25	
<i>Surrogate: 1-Chloro-4-fluorobenzene-FID</i>						
	100 %	70-130		08/05/25	08/06/25	
Nonhalogenated Organics by EPA 8015D - DRO/ORO	mg/kg	mg/kg	Analyst: NV		Batch: 2532051	
Diesel Range Organics (C10-C28)	270	25.0	1	08/05/25	08/06/25	
Oil Range Organics (C28-C36)	57.7	50.0	1	08/05/25	08/06/25	
<i>Surrogate: n-Nonane</i>						
	101 %	61-141		08/05/25	08/06/25	
Anions by EPA 300.0/9056A	mg/kg	mg/kg	Analyst: JM		Batch: 2532044	
Chloride	4110	100	5	08/05/25	08/05/25	



Sample Data

Logos Resources
2010 Afton Place
Farmington NM, 87401

Project Name: Section 16D Drying Pad/Burial Trench
Project Number: 12035-0114
Project Manager: Richard Martin

Reported:
8/7/2025 2:01:54PM

Section 16D Drying Pad

E508043-02

Analyte	Result	Reporting Limit	Dilution	Prepared	Analyzed	Notes
Volatile Organics by EPA 8021B						
	mg/kg	mg/kg	Analyst: SL		Batch: 2532040	
Benzene	ND	0.0250	1	08/05/25	08/06/25	
Ethylbenzene	ND	0.0250	1	08/05/25	08/06/25	
Toluene	0.0434	0.0250	1	08/05/25	08/06/25	
o-Xylene	ND	0.0250	1	08/05/25	08/06/25	
p,m-Xylene	0.0825	0.0500	1	08/05/25	08/06/25	
Total Xylenes	0.0825	0.0250	1	08/05/25	08/06/25	
<i>Surrogate: 4-Bromochlorobenzene-PID</i>						
		102 %	70-130	08/05/25	08/06/25	
Nonhalogenated Organics by EPA 8015D - GRO						
	mg/kg	mg/kg	Analyst: SL		Batch: 2532040	
Gasoline Range Organics (C6-C10)	ND	20.0	1	08/05/25	08/06/25	
<i>Surrogate: 1-Chloro-4-fluorobenzene-FID</i>						
		99.4 %	70-130	08/05/25	08/06/25	
Nonhalogenated Organics by EPA 8015D - DRO/ORO						
	mg/kg	mg/kg	Analyst: NV		Batch: 2532051	
Diesel Range Organics (C10-C28)	62.2	25.0	1	08/05/25	08/06/25	
Oil Range Organics (C28-C36)	ND	50.0	1	08/05/25	08/06/25	
<i>Surrogate: n-Nonane</i>						
		97.3 %	61-141	08/05/25	08/06/25	
Anions by EPA 300.0/9056A						
	mg/kg	mg/kg	Analyst: JM		Batch: 2532044	
Chloride	618	20.0	1	08/05/25	08/05/25	



QC Summary Data

Logos Resources	Project Name:	Section 16D Drying Pad/Burial Trench	Reported:
2010 Afton Place	Project Number:	12035-0114	
Farmington NM, 87401	Project Manager:	Richard Martin	8/7/2025 2:01:54PM

Volatile Organics by EPA 8021B

Analyst: SL

Analyte	Result mg/kg	Reporting Limit mg/kg	Spike Level mg/kg	Source Result mg/kg	Rec %	Rec Limits %	RPD %	RPD Limit %	Notes
---------	-----------------	-----------------------------	-------------------------	---------------------------	----------	--------------------	----------	-------------------	-------

Blank (2532040-BLK1)

Prepared: 08/05/25 Analyzed: 08/05/25

Benzene	ND	0.0250							
Ethylbenzene	ND	0.0250							
Toluene	ND	0.0250							
o-Xylene	ND	0.0250							
p,m-Xylene	ND	0.0500							
Total Xylenes	ND	0.0250							
Surrogate: 4-Bromochlorobenzene-PID	8.05		8.00		101	70-130			

LCS (2532040-BS1)

Prepared: 08/05/25 Analyzed: 08/05/25

Benzene	5.05	0.0250	5.00		101	70-130			
Ethylbenzene	5.11	0.0250	5.00		102	70-130			
Toluene	5.10	0.0250	5.00		102	70-130			
o-Xylene	5.10	0.0250	5.00		102	70-130			
p,m-Xylene	10.4	0.0500	10.0		104	70-130			
Total Xylenes	15.5	0.0250	15.0		103	70-130			
Surrogate: 4-Bromochlorobenzene-PID	7.46		8.00		93.2	70-130			

Matrix Spike (2532040-MS1)

Source: E508027-08

Prepared: 08/05/25 Analyzed: 08/05/25

Benzene	5.24	0.0250	5.00	ND	105	70-130			
Ethylbenzene	5.32	0.0250	5.00	ND	106	70-130			
Toluene	5.30	0.0250	5.00	ND	106	70-130			
o-Xylene	5.30	0.0250	5.00	ND	106	70-130			
p,m-Xylene	10.8	0.0500	10.0	ND	108	70-130			
Total Xylenes	16.1	0.0250	15.0	ND	107	70-130			
Surrogate: 4-Bromochlorobenzene-PID	8.54		8.00		107	70-130			

Matrix Spike Dup (2532040-MSD1)

Source: E508027-08

Prepared: 08/05/25 Analyzed: 08/05/25

Benzene	5.08	0.0250	5.00	ND	102	70-130	3.10	27	
Ethylbenzene	5.16	0.0250	5.00	ND	103	70-130	2.92	26	
Toluene	5.14	0.0250	5.00	ND	103	70-130	3.00	20	
o-Xylene	5.13	0.0250	5.00	ND	103	70-130	3.22	25	
p,m-Xylene	10.5	0.0500	10.0	ND	105	70-130	2.87	23	
Total Xylenes	15.6	0.0250	15.0	ND	104	70-130	2.98	26	
Surrogate: 4-Bromochlorobenzene-PID	8.57		8.00		107	70-130			



QC Summary Data

Logos Resources	Project Name:	Section 16D Drying Pad/Burial Trench	Reported:
2010 Afton Place	Project Number:	12035-0114	
Farmington NM, 87401	Project Manager:	Richard Martin	8/7/2025 2:01:54PM

Nonhalogenated Organics by EPA 8015D - GRO

Analyst: SL

Analyte	Result mg/kg	Reporting Limit mg/kg	Spike Level mg/kg	Source Result mg/kg	Rec %	Rec Limits %	RPD %	RPD Limit %	Notes
---------	-----------------	-----------------------------	-------------------------	---------------------------	----------	--------------------	----------	-------------------	-------

Blank (2532040-BLK1)

Prepared: 08/05/25 Analyzed: 08/05/25

Gasoline Range Organics (C6-C10)	ND	20.0							
Surrogate: 1-Chloro-4-fluorobenzene-FID	7.89		8.00		98.6	70-130			

LCS (2532040-BS2)

Prepared: 08/05/25 Analyzed: 08/05/25

Gasoline Range Organics (C6-C10)	58.3	20.0	50.0		117	70-130			
Surrogate: 1-Chloro-4-fluorobenzene-FID	7.81		8.00		97.6	70-130			

Matrix Spike (2532040-MS2)

Source: E508027-08

Prepared: 08/05/25 Analyzed: 08/05/25

Gasoline Range Organics (C6-C10)	61.8	20.0	50.0	ND	124	70-130			
Surrogate: 1-Chloro-4-fluorobenzene-FID	7.68		8.00		96.0	70-130			

Matrix Spike Dup (2532040-MSD2)

Source: E508027-08

Prepared: 08/05/25 Analyzed: 08/05/25

Gasoline Range Organics (C6-C10)	61.5	20.0	50.0	ND	123	70-130	0.433	20	
Surrogate: 1-Chloro-4-fluorobenzene-FID	7.71		8.00		96.4	70-130			



QC Summary Data

Logos Resources	Project Name:	Section 16D Drying Pad/Burial Trench	Reported:
2010 Afton Place	Project Number:	12035-0114	
Farmington NM, 87401	Project Manager:	Richard Martin	8/7/2025 2:01:54PM

Nonhalogenated Organics by EPA 8015D - DRO/ORO

Analyst: NV

Analyte	Result mg/kg	Reporting Limit mg/kg	Spike Level mg/kg	Source Result mg/kg	Rec %	Rec Limits %	RPD %	RPD Limit %	Notes
---------	-----------------	-----------------------------	-------------------------	---------------------------	----------	--------------------	----------	-------------------	-------

Blank (2532051-BLK1) Prepared: 08/05/25 Analyzed: 08/06/25

Diesel Range Organics (C10-C28)	ND	25.0							
Oil Range Organics (C28-C36)	ND	50.0							
Surrogate: n-Nonane	45.5		50.0		90.9	61-141			

LCS (2532051-BS1) Prepared: 08/05/25 Analyzed: 08/06/25

Diesel Range Organics (C10-C28)	246	25.0	250		98.3	66-144			
Surrogate: n-Nonane	46.6		50.0		93.2	61-141			

Matrix Spike (2532051-MS1) Source: E508043-01 Prepared: 08/05/25 Analyzed: 08/06/25

Diesel Range Organics (C10-C28)	521	25.0	250	270	100	56-156			
Surrogate: n-Nonane	48.4		50.0		96.9	61-141			

Matrix Spike Dup (2532051-MSD1) Source: E508043-01 Prepared: 08/05/25 Analyzed: 08/06/25

Diesel Range Organics (C10-C28)	409	25.0	250	270	55.5	56-156	24.0	20	R3
Surrogate: n-Nonane	47.9		50.0		95.7	61-141			



QC Summary Data

Logos Resources	Project Name:	Section 16D Drying Pad/Burial Trench	Reported:
2010 Afton Place	Project Number:	12035-0114	
Farmington NM, 87401	Project Manager:	Richard Martin	8/7/2025 2:01:54PM

Anions by EPA 300.0/9056A

Analyst: JM

Analyte	Result mg/kg	Reporting Limit mg/kg	Spike Level mg/kg	Source Result mg/kg	Rec %	Rec Limits %	RPD %	RPD Limit %	Notes
---------	-----------------	-----------------------------	-------------------------	---------------------------	----------	--------------------	----------	-------------------	-------

Blank (2532044-BLK1)					Prepared: 08/05/25 Analyzed: 08/05/25				
Chloride	ND	20.0							
LCS (2532044-BS1)					Prepared: 08/05/25 Analyzed: 08/05/25				
Chloride	254	20.0	250		102	90-110			
Matrix Spike (2532044-MS1)					Source: E508043-02		Prepared: 08/05/25 Analyzed: 08/05/25		
Chloride	725	20.0	250	618	42.5	80-120			M2
Matrix Spike Dup (2532044-MSD1)					Source: E508043-02		Prepared: 08/05/25 Analyzed: 08/05/25		
Chloride	910	20.0	250	618	117	80-120	22.7	20	R3

QC Summary Report Comment:
Calculations are based off of the raw (non-rounded) data. However, for reporting purposes all QC data is rounded to three significant figures.
Therefore, hand calculated values may differ slightly.



Definitions and Notes

Logos Resources	Project Name:	Section 16D Drying Pad/Burial Trench	
2010 Afton Place	Project Number:	12035-0114	Reported:
Farmington NM, 87401	Project Manager:	Richard Martin	08/07/25 14:01

- M2 Matrix spike recovery was outside quality control limits. The associated LCS spike recovery was acceptable.
- R3 The RPD exceeded the acceptance limit. LCS spike recovery met acceptance criteria.
- ND Analyte NOT DETECTED at or above the reporting limit
- NR Not Reported
- RPD Relative Percent Difference
- DNI Did Not Ignite
- DNR Did not react with the addition of acid or base.

Note (1): Methods marked with ** are non-accredited methods.

Note (2): Soil data is reported on an "as received" weight basis, unless reported otherwise.



[illegible]

Envirotech Analytical Laboratory

Printed: 8/5/2025 8:42:02AM

Sample Receipt Checklist (SRC)

Instructions: Please take note of any NO checkmarks.

If we receive no response concerning these items within 24 hours of the date of this notice, all the samples will be analyzed as requested.

Client:	Logos Resources	Date Received:	08/05/25 08:29	Work Order ID:	E508043
Phone:	(505) 320-2896	Date Logged In:	08/05/25 08:34	Logged In By:	Caitlin Mars
Email:	rmartin@logosresources.com	Due Date:	08/06/25 07:00 (1 day TAT)		

Chain of Custody (COC)

1. Does the sample ID match the COC? Yes
2. Does the number of samples per sampling site location match the COC? Yes
3. Were samples dropped off by client or carrier? Yes
4. Was the COC complete, i.e., signatures, dates/times, requested analyses? Yes
5. Were all samples received within holding time? Yes

Note: Analysis, such as pH which should be conducted in the field, i.e., 15 minute hold time, are not included in this discussion.

Carrier: Richard MartinComments/ResolutionSample Turn Around Time (TAT)

6. Did the COC indicate standard TAT, or Expedited TAT? Yes

Sample Cooler

7. Was a sample cooler received? Yes
8. If yes, was cooler received in good condition? Yes
9. Was the sample(s) received intact, i.e., not broken? Yes
10. Were custody/security seals present? No
11. If yes, were custody/security seals intact? NA
12. Was the sample received on ice? Yes

Note: Thermal preservation is not required, if samples are received within 15 minutes of sampling

13. See COC for individual sample temps. Samples outside of 0°C-6°C will be recorded in comments.

Sample Container

14. Are aqueous VOC samples present? No
15. Are VOC samples collected in VOA Vials? NA
16. Is the head space less than 6-8 mm (pea sized or less)? NA
17. Was a trip blank (TB) included for VOC analyses? NA
18. Are non-VOC samples collected in the correct containers? Yes
19. Is the appropriate volume/weight or number of sample containers collected? Yes

Field Label

20. Were field sample labels filled out with the minimum information:
 - Sample ID? Yes
 - Date/Time Collected? Yes
 - Collectors name? Yes

Sample Preservation

21. Does the COC or field labels indicate the samples were preserved? No
22. Are sample(s) correctly preserved? NA
24. Is lab filtration required and/or requested for dissolved metals? No

Multiphase Sample Matrix

26. Does the sample have more than one phase, i.e., multiphase? No
27. If yes, does the COC specify which phase(s) is to be analyzed? NA

Subcontract Laboratory

28. Are samples required to get sent to a subcontract laboratory? No
29. Was a subcontract laboratory specified by the client and if so who? NA Subcontract Lab: NA

Client Instruction

Signature of client authorizing changes to the COC or sample disposition.

Date



envirotech Inc.

From: [Vanessa Fields](#)
To: [Stone, Joel, EMNRD](#)
Cc: [Robert Bixler](#); [Randy Edgeington](#); [Bryan Lovato](#); [Richard Martin](#); [Etta Trujillo](#); [Dawn Howell](#); [Sharon Escojeda](#)
Subject: *Vanessa Fields* Section 16D #001 [fJMB2220051571] UL D, Section 16, T31N, R06W 72- Hour Notice confirmation sampling
LOGOS Closure 8/4/2025 at 9:30 am
Date: Tuesday, July 29, 2025 6:09:00 PM
Attachments: [image001.png](#)

Good morning,

LOGOS is providing 72-hour notification per NMAC 19.15.17.11 for confirmation sampling for closure on Section 16D Drying Pad/Burial Trench [fJMB2220051571] on Monday August 4, 2025, at 9:30 am.

Thank you,


Vanessa Fields


Senior Regulatory Manager


Email: vfields@logosresourcesllc.com

Mobile: 505-320-1243



LOCATION:	 Burial Trench Inspection								
Section 16D Burial Trench									
Inspector	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin
Date (weekly)	4/17/2025	4/21/2025	4/28/2025	5/5/2025	5/12/2025	5/19/2025	5/26/2025	6/2/2025	6/9/2025
	week 01	week 02	week 03	week 04	week 05	week 06	week 07	week 08	week 09
Pit Status	Open	Open	Open	Open	Open	Open	Open	Open	Open
Liner in good Condition	yes	yes	yes	yes	yes	yes	yes	yes	yes
Properly Fenced	yes	yes	yes	yes	yes	yes	yes	yes	yes
Slopes Intact	yes	yes	yes	yes	yes	yes	yes	yes	yes
Free Oil or Sheen Present	no	no	no	no	no	no	no	no	no
Fluid in Trench	no	no	no	no	no	no	no	no	no
Trash at Location	no	no	no	no	no	no	no	no	no
Comments	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted

LOCATION:	 Burial Trench Inspection								
Section 16D Burial Trench									
Inspector	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin
Date (weekly)	6/9/2025	6/16/2025	6/23/2025	6/30/2025	7/7/2025	7/14/2025	7/21/2025	7/28/2025	8/4/2025
	week 10	week 11	week 12	week 13	week 14	week 14	week 15	week 16	week 17
Pit Status	Open	Open	Open	Open	Open	Open	Open	Open	Open
Liner in good Condition	yes	yes	yes	yes	yes	yes	yes	yes	yes
Properly Fenced	yes	yes	yes	yes	yes	yes	yes	yes	yes
Slopes Intact	yes	yes	yes	yes	yes	yes	yes	yes	yes
Free Oil or Sheen Present	no	no	no	no	no	no	no	no	no
Fluid in Trench	no	no	no	no	no	no	no	no	no
Trash at Location	no	no	no	no	no	no	no	no	no
Comments	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. Do 72 hour closure test for drying pad and cutting pit

LOCATION:	 Burial Trench Inspection								
Section 16D Burial Trench									
Inspector	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin	Richard Martin
Date (weekly)	8/11/2025	8/18/2025	8/25/2025	9/1/2025	9/8/2025	9/15/2025	9/22/2025	9/29/2025	10/6/2025
	week 18	week 19	week 20	week 21	week 22	week 23	week 24	week 25	week 26
Pit Status	Open	Open	Open	Closed					
Liner in good Condition	yes	yes	yes	yes					
Properly Fenced	yes	yes	yes	yes					
Slopes Intact	yes	yes	yes	yes					
Free Oil or Sheen Present	no	no	no	no					
Fluid in Trench	no	no	no	no					
Trash at Location	no	no	no	no					
Comments	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Monitored Trench until closure. No Issues noted	Trench is closed					

Final Closure Photos



Confirmation of Sampling Photos

Burial Trench



Confirmation Sampling Area Drying Pad



Final Backfilled Cuttings Pit



Final Plate Marker



Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/ocd/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 521749

CONDITIONS

Operator: LOGOS OPERATING, LLC 2010 Afton Place Farmington, NM 87401	OGRID: 289408
	Action Number: 521749
	Action Type: [C-144] Temporary Pit Plan (C-144T)

CONDITIONS

Created By	Condition	Condition Date
joel.stone	NMOCD has reviewed the Closure Report submitted by [289408] LOGOS OPERATING, LLC for the SECTION 16D BURIAL TRENCH #1 @ D-16-31N-06W 0N 0E7 FACILITY ID [FJMB2220051571]. The closure report demonstrated that all protocols in the closure plan were followed, and the closure report has been approved. The re-vegetation and reclamation obligations imposed by other applicable federal or tribal agencies on lands managed by those agencies shall supersede these provisions and govern the obligations of any operator subject to those provisions, provided that the other requirements provide equal or better protection of fresh water, human health and the environment. The operator shall notify the division when reclamation and re-vegetation are complete.	11/4/2025