

Form 3160-3
(June 2015)FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: ☐ DRILL ☐ REENTER 1b. Type of Well: ☐ Oil Well ☐ Gas Well ☐ Other 1c. Type of Completion: ☐ Hydraulic Fracturing ☐ Single Zone ☐ Multiple Zone		5. Lease Serial No. 6. If Indian, Allottee or Tribe Name 7. If Unit or CA Agreement, Name and No. 8. Lease Name and Well No.
2. Name of Operator		9. API Well No. 30 015 48238
3a. Address	3b. Phone No. (include area code)	10. Field and Pool, or Exploratory
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface At proposed prod. zone		11. Sec., T. R. M. or Blk. and Survey or Area
14. Distance in miles and direction from nearest town or post office*		12. County or Parish
13. State		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)	16. No of acres in lease	17. Spacing Unit dedicated to this well
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.	19. Proposed Depth	20. BLM/BIA Bond No. in file
21. Elevations (Show whether DF, KDB, RT, GL, etc.)	22. Approximate date work will start*	23. Estimated duration
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|---|---|
| 1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM. |
|---|---|

25. Signature	Name (Printed/Typed)	Date
Title		
Approved by (Signature)	Name (Printed/Typed)	Date
Title		
Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
 Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



(Continued on page 2)

*(Instructions on page 2)

District I

1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

District II

811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720

District III

1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

District IV

1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico

Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION

1220 South St. Francis Dr.

Santa Fe, NM 87505

Form C-102

Revised August 1, 2011

Submit one copy to appropriate

District Office

☒ AMENDED REPORT
AMEND SHL

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30 015 48238	² Pool Code 96437	³ Pool Name HAPPY VALLEY; BONE SPRING
⁴ Property Code 330697	⁵ Property Name SHOWNUFF 18-19 FEDERAL COM 3BS	⁶ Well Number 3H
⁷ OGRID No. 372137	⁸ Operator Name CHISHOLM ENERGY OPERATING, LLC	⁹ Elevation 3697.2

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	7	22 S	26 E		670	SOUTH	1125	EAST	EDDY

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
O	19	22 S	26 E		100	SOUTH	2310	EAST	EDDY

¹² Dedicated Acres 320	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
---	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

NMSP EAST (FT) N = 514229.08 E = 541692.78 L1 SEC. 7 L2 L3 NMSP EAST (FT) N = 508971.97 E = 541683.99 L4 SHL/KOP STATE LEASE VBS123 1125' NMSP EAST (FT) N = 509005.30 E = 544335.01 L1 SEC. 18 L2 2639'FSL, 2322'FEL LAT.=32.391909 LONG.=104.331115 NMNM100540 L3 NMSP EAST (FT) N = 503673.71 E = 541671.42 L4 SEC. 19 L1 L2 L3 NMSP EAST (FT) N = 498379.07 E = 541689.22 L4 GRID AZ. = S00045.01°W HORIZ. DIST. = 10385.66 FT FTP 100' FNL, 2310' FEL LAT. = 32.3989690°N LONG. = 104.3311027°W N = 508876.29 E = 542025.96 GRID AZ. TO LP S56°29'46"W HORIZ. DIST 1422.21 FT BOTTOM OF HOLE 100' FSL, 2310' FEL LAT. = 32.3704279°N LONG. = 104.3311525°W NMSP EAST (FT) N = 498493.33 E = 542010.81 NMSP EAST (FT) N = 498495.18 E = 544320.26	¹⁷ OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division. <i>Jennifer Elrod</i> 10/25/19 Signature Date JENNIFER ELROD Printed Name jelrod@chisholmenergy.com E-mail Address ¹⁸ SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief. OCTOBER 3, 2019 Date of Survey <i>[Signature]</i> Signature and Seal of Professional Surveyor: Certificate Number: 12797 SURVEY NO. 6515C
--	--

Intent ☒ As Drilled ☐

API #

Operator Name:	Property Name:	Well Number
CHISHOLM ENERGY OPERATING, LLC	SHOWNUFF 18-19 FEDERAL COM 3BS	3H

Kick Off Point (KOP)

UL P	Section 7	Township 22S	Range 26E	Lot	Feet 670	From N/S SOUTH	Feet 1125	From E/W EAST	County EDDY
Latitude 32.4011263					Longitude 104.3272612			NAD 83	

First Take Point (FTP)

UL B	Section 18	Township 22S	Range 26E	Lot	Feet 100	From N/S NORTH	Feet 2310	From E/W EAST	County EDDY
Latitude 32.3989690					Longitude 104.3311027			NAD 83	

Last Take Point (LTP)

UL O	Section 19	Township 22S	Range 26E	Lot	Feet 100	From N/S SOUTH	Feet 2310	From E/W EAST	County EDDY
Latitude 32.3704279					Longitude 104.3311525			NAD 83	

Is this well the defining well for the Horizontal Spacing Unit?

☒ YES

Is this well an infill well?

☐

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #

Operator Name:	Property Name:	Well Number

KZ 06/29/2018

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit Original
to Appropriate
District Office

GAS CAPTURE PLAN

Date: 02/19/2019

☒ Original Operator & OGRID No.: Chisholm Energy Operating, LLC/372137
☐ Amended - Reason for Amendment: _____

This Gas Capture Plan outlines actions to be taken by the Operator to reduce well/production facility flaring/venting for new completion (new drill, recomple to new zone, re-frac) activity.

Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).

Well(s)/Production Facility – Name of facility

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location (ULSTR)	Footages	Expected MCF/D	Flared or Vented	Comments
SHOWNUFF 18-19 FED COM 3BS 3H	015-	UL-P, SECT. 7, 22S, 26E	670 FSL 1050 FEL	1900	FLARED	PIPELINE IN PLACE; FLARE ONLY WHEN NEEDED

Gathering System and Pipeline Notification

Well(s) will be connected to a production facility after flowback operations are complete, if gas transporter system is in place. The gas produced from production facility is dedicated to LUCID and will be connected to LUCID low/high pressure gathering system located in EDDY County, New Mexico. It will require FLOWLINES to connect the facility to low/high pressure gathering system. Chisholm Energy Operating, LLC provides (periodically) to LUCID a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, Chisholm Energy Operating, LLC and LUCID have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at RED HILLS Processing Plant located in Sec. 13, Twn. 24S, Rng. 33E, EDDY County, New Mexico. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

Flowback Strategy

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on LUCID system at that time. Based on current information, it is Chisholm Energy Operating, LLC belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

Alternatives to Reduce Flaring

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease
 - Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas – On lease
 - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
 - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines

Operator Name: CHISHOLM ENERGY OPERATING LLC**Well Name:** SHOWNUFF 18-19 FED COM 3BS**Well Number:** 3H**Section 3 - Casing**

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	420	0	420			420	H-40	48	ST&C	4.2	9.43	BUOY	18.3 ₂	BUOY	30.7 ₉
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	2700	0	2700			2700	J-55	40	LT&C	2.03	3.13	BUOY	4.61	BUOY	6.76
3	PRODUCTION	8.75	5.5	NEW	API	N	0	19578	0	8620			19578	P-110	20	BUTT	2.35	2.69	BUOY	4.43	BUOY	4.61

Casing Attachments**Casing ID:** 1 **String Type:** SURFACE**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**

Shownuff_18_19_Fed_Com_3BS_3H___Casing_Calculator_20190315095617.xlsx

Operator Name: CHISHOLM ENERGY OPERATING LLC**Well Name:** SHOWNUFF 18-19 FED COM 3BS**Well Number:** 3H**Casing Attachments****Casing ID:** 2 **String Type:** INTERMEDIATE**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**

Shownuff_18_19_Fed_Com_3BS_3H___Casing_Calculator_20190315095624.xlsx

Casing ID: 3 **String Type:** PRODUCTION**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**

Shownuff_18_19_Fed_Com_3BS_3H___Casing_Calculator_20190315095633.xlsx

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	420	440	1.34	14.8	590	100	Class C Premium Plus	Cellophane Flakes
INTERMEDIATE	Lead		0	560	150	3.7	11.5	555	200	CLASS C	Sodium Metasilicate, Defoamer, KCL, Kol-Seal, Cellophane Flakes, ROF SealCheck

Operator Name: CHISHOLM ENERGY OPERATING LLC**Well Name:** SHOWNUFF 18-19 FED COM 3BS**Well Number:** 3H



String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
INTERMEDIATE	Lead	560	560	2000	250	3.7	11.5	925	100	Class C Premium Plus	Sodium Metasilicate, Defoamer, KCL, Kol-Seal, Cellophane Flakes, ROF SealCheck
INTERMEDIATE	Tail		2000	2700	330	1.33	14.8	429	100	Class C Premium Plus	NA
PRODUCTION	Lead		0	8000	790	2.95	11.3	2330	10	Liteweight	Fluid Loss, Expanding Agent, Retarder, Defoamer, Dispersant, Extender, Viscosifier
PRODUCTION	Tail		8000	19578	2350	1.2	14.4	2820	10	Class H Premium	Extender, Fluid Loss, Retarder, Defoamer, Dispersant

Section 5 - Circulating Medium

Mud System Type: Closed**Will an air or gas system be Used?** NO**Description of the equipment for the circulating system in accordance with Onshore Order #2:****Diagram of the equipment for the circulating system in accordance with Onshore Order #2:****Describe what will be on location to control well or mitigate other conditions:** Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times**Describe the mud monitoring system utilized:** PVT, Pason/CanRig, Visual Monitoring

Circulating Medium Table



Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	420	SPUD MUD	8.5	9.2							38-40 VIS 8-10 PV 8-10 YP
420	2700	WATER-BASED MUD	8.5	8.8							38-40VIS 1-3 PV 1-3 YP

TVD ft-RKB	Geological Tops	Wellbore Sketch		Hole Size	Casing	Drilling Fluids	Cement	OH Evaluation/Logs	
500'				17-1/2"	Surface: 13-3/8" 48# H40 STC	FW Spud Mud 8.5 - 9.2 ppg 38 - 40 Vis 8 - 10 PV 8 - 10 YP	Top of Cement: Surface 14.8 ppg 1.34 cuft/sk 440 sks (100% XS)	N/A	
1,000'				12-1/4"	Intermediate: 9-5/8" 40# J55 LTC	FW Mud 8.5 - 8.8 ppg 38 - 40 Vis 1-3 PV 1-3 YP	Stage 1 Top of Lead: 560' 11.5 ppg 3.70 cuft/sk 250 sks (100% XS) Top of Tail: 2,000' 14.8 ppg 1.33 cuft/sk 330 sks (100% XS) Stage 2 Top of Cement: Surface 11.5 ppg 3.7 cuft/sk 150 sks (200% XS)	Mud Logging: 30 ft Samples from Surface Casing to ICP	
2,000'									
2,645	Delaware Mtn Grp			8-3/4" Curve 8-1/2" Lateral	Production: 5-1/2" 20# P110 BTC	Curve & Lateral 9.5 - 10.5 ppg OBM 25 - 30 PV, 12 - 18 YP 600 - 900 ES	Top of Lead: Surface 11.3 ppg 2.95 cuft/sk 790 sks (15% XS) Top of Tail: 8,000' 14.4 ppg 1.30 cuft/sk 2,350 sks (15% XS)	Mud Logging: 10 ft Samples from ICP through curve. Collect mud gas samples through select shows. 30 ft Samples through the lateral.	
3,000'									
4,000'									
5,000'	Bone Spring 5,053 Bone Spring								
6,000'	6,202 1st Bone Spring SS								
6,818	2nd Bone Spring SS								
7,000'									
8,000'	8,260 3rd Bone Spring SS								
	8,684 Wolfcamp								19,578' MD 8,617' TVD
9,000'									

BOREHOLE				WELL				FIELD				STRUCTURE	
Shownuff 18-19 Fed Com 3BS 3H				Shownuff 18-19 Fed Com 3BS 3H				NM Eddy County (NAD 83)				Chisholm Shownuff 18-19 Fed Com 3BS 3H	

Critical Point	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (deg/100ft)
SHL	0.00	0.00	270.00	0.00	0.00	0.00	0.00	
Nudge 1° DLS	1,000.00	0.00	270.00	1,000.00	0.00	0.00	0.00	0.00
13.375 in Casing	1,480.00	4.80	270.00	1,479.44	0.03	0.00	-20.09	1.00
Hold	1,600.00	6.00	270.00	1,598.90	0.04	0.00	-31.39	1.00
KOP, Build 10° DLS	8,086.06	6.00	270.00	8,049.43	0.99	0.00	-709.36	0.00
9.824999999999999 in Casing	8,582.00	51.92	205.02	8,475.95	189.96	-188.81	-825.16	10.00
Landing Point / Hold	8,966.99	90.20	200.58	8,598.66	520.17	-518.83	-962.10	10.00
Turn 2° DLS	9,086.99	90.20	200.58	8,598.24	632.57	-631.17	-1,004.29	0.00
Hold to TD	10,111.80	90.20	180.08	8,594.63	1,635.65	-1,634.00	-1,187.10	2.00
Chisholm Shownuff 18-19 Fed Com 3BS 3H - BHL	19,646.73	90.20	180.08	8,561.01	11,170.51	-11,168.85	-1,200.86	0.00

GRAVITY & MAGNETICS PARAMETERS				SURFACE LOCATION				NAD83 New Mexico State Plane, Eastern Zone, US Feet			
Model	HGDM 2019 GARM	Dip	60.029°	Date	27-Jan-20	Lat	32°24'4.05"N	Northing	609,661.14 ftUS	Grid Conv	0.003°
MagDec	7.201°	FS	47,844.168nT	Gravity FS	998.447mgn (9.80665 Based)	Lon	104°19'38.14"W	Easting	643,211.56 ftUS	Scale Fact	0.99990909
MISCELLANEOUS											
Slot	TVD Reference RKB (3729.200 ft above MSL)										
Plan	Chisholm Shownuff 18-19 Fed Com 3BS 3H R0 IC 27Jan20										
				Seabed / Ground Elevation 3697.200 ft above MSL							



Schlumberger

Chisholm Shownuff 18-19 Fed Com 3BS 3H R0 IC 27Jan20 Proposal

Geodetic Report

Def Plan



Report Date: January 28, 2020 - 05:55 PM (UTC 0)
Client: Chisholm
Field: NM Eddy County (NAD 83)
Structure / Slat: Chisholm Shownuff 18-19 Fed Com 3BS 3H
Well: Shownuff 18-19 Fed Com 3BS 3H
Borehole: Shownuff 18-19 Fed Com 3BS 3H
UWI / AP#: Unknown / Unknown
Survey Name: Chisholm Shownuff 18-19 Fed Com 3BS 3H R0 IC 27Jan20
Survey Date: January 28, 2020
Tort / AHD / DDI / ERD Ratio: 114.594' / 11970.732 ft / 6.496 / 1.392
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: 32°24'4.05455"N, 104°19'38.14018"W
Location Grid N/E Y/X: N 509661.140 RUS, E 543211.560 RUS
CRS Grid Convergence Angle: 0.0033°
Grid Scale Factor: 0.99990909
Version / Patch: 2019.8.0.1

Survey / DLS Computation: Minimum Curvature / Lubinski
Vertical Section Azimuth: 180.080 °(GRID North)
Vertical Section Origin: 0.000 ft, 0.000 ft
TVD Reference Datum: RKB
TVD Reference Elevation: 3729.200 ft above MSL
Seabed / Ground Elevation: 3697.200 ft above MSL
Magnetic Declination: 7.201°
Total Gravity Field Strength: 998.4469mgn (9.80665 Based)
Gravity Model: GARM
Total Magnetic Field Strength: 47844.168 nT
Magnetic Dip Angle: 60.029°
Declination Date: January 27, 2020
Magnetic Declination Model: HDGM 2019
North Reference: Grid North
Grid Convergence Used: 0.0033°
Total Corr Mag North->Grid North: 7.198°
Local Coord Referenced To: Well Head

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	Northing (ftUS)	Easting (ftUS)	Latitude (°)	Longitude (°)	DLS (°/100ft)	BR (°/100ft)	TR (°/100ft)
SHL	0.00	0.00	270.00	0.00	-3,729.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33			
Nudge 1" DLS	1,000.00	0.00	270.00	1,000.00	-2,729.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
Hold	1,600.00	6.00	270.00	1,598.90	-2,130.30	0.04	0.00	-31.39	509,661.14	543,180.18	32.40	-104.33	1.00	1.00	0.00
KOP, Build 10" DLS	8,086.06	6.00	270.00	8,049.43	4,320.23	0.99	0.00	-709.36	509,661.14	542,502.26	32.40	-104.33	0.00	0.00	0.00
Landing Point / Hold	8,966.99	90.20	200.58	8,598.66	4,869.46	520.17	-518.83	-962.10	509,142.36	542,249.55	32.40	-104.33	10.00	9.94	-1.15
Turn 2" DLS	9,086.99	90.20	200.58	8,598.24	4,869.04	632.57	-631.17	-1,004.29	509,030.03	542,207.37	32.40	-104.33	0.00	0.00	0.00
Hold to TD	10,111.80	90.20	180.08	8,594.63	4,865.43	1,635.65	-1,634.00	-1,187.10	508,027.30	542,024.57	32.40	-104.33	2.00	0.00	-2.00
Chisholm Shownuff 18-19 Fed (	19,646.73	90.20	180.08	8,561.01	4,831.81	11,170.51	-11,168.85	-1,200.86	498,493.33	542,010.81	32.37	-104.33	0.00	0.00	0.00

Survey Type: Def Plan

Survey Error Model: ISCWSA0 3 - D 95 % Confidence 2.7955 sigma

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	1,000.000	1/100.000	17.500			NAL_MWD_1.0_DEG	Shownuff 18-19 Fed Com 3BS :
	1	1,000.000	8,086.060	1/100.000	12.250			NAL_MWD_1.0_DEG	Shownuff 18-19 Fed Com 3BS :
	1	8,086.060	8,966.990	1/100.000	8.750			NAL_MWD_1.0_DEG	Shownuff 18-19 Fed Com 3BS :
	1	8,966.990	19,646.730	1/100.000	8.500			NAL_MWD_1.0_DEG	Shownuff 18-19 Fed Com 3BS :

Schlumberger-Private

Schlumberger

Chisholm Shownuff 18-19 Fed Com 3BS 3H R0 IC 27Jan20 Proposal
Geodetic Report

Survey Date:	January 28, 2020 - 05:55 PM (UTC 0)	Survey / DLS Computation:	Minimum Curvature / Lubinski
Client:	Chisholm	Vertical Section Azimuth:	180.080 (°GRD North)
Field:	NMEddy County (NAD 83)	Vertical Section Origin:	0.000 R, 0.000 I
Structure / Slot:	Chisholm Shownuff 18-19 Fed Com 3BS 3H	TVD Reference Datum:	RKB
Well:	Shownuff 18-19 Fed Com 3BS 3H	TVD Reference Elevation:	3729.200 ft above MSL
Borehole:	Shownuff 18-19 Fed Com 3BS 3H	Seabed / Ground Elevation:	3697.200 ft above MSL
UWI / AHP:	Unknown / Unknown	Magnetic Declination:	7.201°
Survey Name:	Chisholm Shownuff 18-19 Fed Com 3BS 3H R0 IC 27Jan20	Total Gravity Field Strength:	998.440mgm (0.80065 Based)
Survey Date:	January 28, 2020	Gravity Model:	GARM
Turn / AHD / DD / ERD Ratio:	114.554° / 11970.732 ft / 6.496 / 1.392	Total Magnetic Field Strength:	47844.168 nT
Coordinate Reference System:	NAD83 New Mexico State Plane, Eastern Zone, US Feet	Magnetic Dip Angle:	60.029°
Location Lat / Long:	32°24'4.05455°N, 104°19'38.14018°W	Declination Date:	January 27, 2020
Location Grid N/E/Y:	N 508661.140 RUS, E 543211.960 RUS	Magnetic Declination Model:	HQCM2019
CRS Grid Convergence Angle:	0.0033°	North Reference:	Grid North
Grid Scale Factor:	0.9999999	Grid Convergence Used:	0.0033°
Version / Patch:	2019.8.0.1	Total Corr Mag North->Grid North:	7.198°
		Local Coord Referenced To:	Well Head

Comments	MD (ft)	Incl (°)	Azin (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	AHD (ft)	NS (ft)	EW (ft)	DeltaMD (ft)	DeltaTVD (ft)	DLS (°/100ft)	BR (°/100ft)	TR (°/100ft)	GTF (°)	MTF (°)	TF (°)	Northing (ftUS)	Easting (ftUS)	Latitude (°-")	Longitude (°-")	Latitude (°)	Longitude (°)	Closure (ft)	Closure Azimuth (°)	Directional Difficulty Index	Tortuosity (°)	ERD Ratio
SHL	0.00	0.00	270.00	0.00	-3,729.20	0.00	0.00	0.00	0.00						HS	270.00	270M	509,661.14	543,211.56	2°24'4.054552°N	1938.140181°W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
Rustler	32.20	0.00	270.00	32.20	-3,697.00	0.00	0.00	0.00	0.00	32.20	32.20	0.00	0.00	0.00	HS	270.00	270M	509,661.14	543,211.56	2°24'4.054552°N	1938.140181°W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
Capitan	654.20	0.00	270.00	654.20	-3,075.00	0.00	0.00	0.00	0.00	622.00	622.00	0.00	0.00	0.00	HS	270.00	270M	509,661.14	543,211.56	2°24'4.054552°N	1938.140181°W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
Nudge 1" DLS	1,000.00	0.00	270.00	1,000.00	-2,729.20	0.00	0.00	0.00	0.00	345.80	345.80	0.00	0.00	0.00	HS	270.00	270M	509,661.14	543,211.56	2°24'4.054552°N	1938.140181°W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
13.75 in Casing	1,480.00	4.80	270.00	1,479.44	-2,249.76	0.03	20.09	0.00	-20.09	480.00	479.44	1.00	1.00	0.00	HS	270.00	270M	509,661.14	543,191.47	2°24'4.054503°N	1938.374549°W	32.40	-104.33	20.09	270.00	1.98	4.80	0.01
Hold	1,600.00	6.00	270.00	1,598.90	-2,130.30	0.04	31.39	0.00	-31.39	120.00	119.47	1.00	1.00	0.00	HS	270.00	270M	509,661.14	543,180.18	2°24'4.054609°N	1938.602690°W	32.40	-104.33	31.39	270.00	2.28	6.00	0.02
Lamar	2,309.18	6.00	270.00	2,304.20	-1,425.00	0.15	105.52	0.00	-105.52	709.18	705.30	0.00	0.00	0.00	HS	270.00	270M	509,661.14	543,106.05	2°24'4.054609°N	1939.370859°W	32.40	-104.33	105.52	270.00	2.80	6.00	0.05
Delaware Mtn Gr	2,668.15	6.00	270.00	2,661.20	-1,068.00	0.20	143.04	0.00	-143.04	358.97	357.00	0.00	0.00	0.00	HS	270.00	270M	509,661.14	543,068.53	2°24'4.054629°N	1939.809493°W	32.40	-104.33	143.04	270.00	2.93	6.00	0.05
Bone Spring	5,045.17	6.00	270.00	5,025.20	1,298.00	0.55	391.51	0.00	-391.51	2,377.02	2,384.00	0.00	0.00	0.00	HS	270.00	270M	509,661.14	542,820.09	2°24'4.054746°N	1942.705440°W	32.40	-104.33	391.51	270.00	3.37	6.00	0.08
1st Bone Spring SS	6,200.50	6.00	270.00	6,174.20	2,445.00	0.72	512.27	0.00	-512.27	1,155.33	1,149.00	0.00	0.00	0.00	HS	270.00	270M	509,661.14	542,699.34	2°24'4.054800°N	1944.114859°W	32.40	-104.33	512.27	270.00	3.49	6.00	0.08
2nd Bone Spring SS	8,819.89	6.00	270.00	8,790.20	3,061.00	0.81	577.01	0.00	-577.01	619.39	616.00	0.00	0.00	0.00	HS	270.00	270M	509,661.14	542,634.60	2°24'4.054826°N	1944.870093°W	32.40	-104.33	577.01	270.00	3.54	6.00	0.08
KOP: Build 10" DLS	8,086.06	6.00	270.00	8,040.43	4,320.23	0.99	709.36	0.00	-709.36	1,266.17	1,259.23	0.00	0.00	0.00	HS	270.00	270M	509,661.14	542,552.26	2°24'4.054870°N	1946.811374°W	32.40	-104.33	709.36	270.00	3.63	6.00	0.09
3rd Bone Spring SS	8,274.33	21.64	214.96	8,232.20	4,503.00	29.75	751.86	-28.72	-739.37	188.27	182.77	10.00	8.31	-29.24	15.39L	205.02	15.39L	509,632.43	542,472.26	2°24'3.770748°N	1946.763889°W	32.40	-104.33	739.36	267.78	4.27	24.83	0.09
9.624999999999999 in Casing	8,582.00	51.92	205.02	8,475.95	4,746.75	189.96	933.67	-168.81	-825.16	307.67	243.75	10.00	9.84	-3.23	7.15L	200.58	7.15L	509,472.35	542,386.48	2°24'2.186679°N	1947.764388°W	32.40	-104.33	846.49	257.11	4.72	55.59	0.11
Turn 2" DLS	8,969.99	90.20	200.58	8,986.66	4,969.46	520.17	1,291.06	-518.83	-982.10	384.99	122.71	10.00	9.94	-1.15	HS	200.58	HS	509,142.36	542,249.55	2°25'8.921167°N	1949.391683°W	32.40	-104.33	1,093.08	241.66	5.10	94.09	0.15
Hold to TD	10,111.80	90.20	180.08	8,594.63	4,865.43	1,635.65	2,435.87	-1,634.00	-1,187.10	1,024.81	-3.62	2.00	0.00	-2.00	90L	180.08	90L	509,030.03	542,207.37	2°25'7.809605°N	1949.853687°W	32.40	-104.33	1,186.16	237.85	5.15	94.09	0.16
Chisholm Shownuff 18-19 Fed C	19,646.73	90.20	180.08	8,561.01	4,831.81	11,170.51	11,970.73	-11,166.85	-1,200.86	9,534.92	-33.62	0.00	0.00	0.00	24.75L	180.08	24.75L	498,493.33	542,010.81	2°27'13.540471°N	1952.148888°W	32.37	-104.33	11,233.22	186.14	6.50	114.59	1.40

Survey Type: Def Plan

Survey Error Model: ISCW5A0 3 - D 95 % Confidence 2.7955 sigma

Description	Part	MD From (ft)	MD To (ft)	EDU Pres (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	1,000.000	1/100.000	17.500			NAL MWD 1.0 DEG	Shownuff 18-19 Fed Com 3BS 3
	1	1,000.000	8,086.960	1/100.000	12.250			NAL_MWD_1.0_DEG	Shownuff 18-19 Fed Com 3BS 3
	1	8,086.060	8,966.990	1/100.000	8.750			NAL_MWD_1.0_DEG	Shownuff 18-19 Fed Com 3BS 3
	1	8,966.990	19,646.730	1/100.000	8.500			NAL_MWD_1.0_DEG	Shownuff 18-19 Fed Com 3BS 3

Schlumberger



Chisholm Shownuff 18-19 Fed Com 3BS 3H R0 IC 27Jan20 Proposal

Geodetic Report

Def Plan

Report Date: January 28, 2020 - 05:55 PM (UTC 0)
 Client: Chisholm
 Field: NM Eddy County (NAD 83)
 Structure / Slot: Chisholm Shownuff 18-19 Fed Com 3BS 3H
 Well: Shownuff 18-19 Fed Com 3BS 3H
 Borehole: Shownuff 18-19 Fed Com 3BS 3H
 UWI / AP# : Unknown / Unknown
 Survey Name: Chisholm Shownuff 18-19 Fed Com 3BS 3H R0 IC 27Jan20
 Survey Date: January 28, 2020
 Tort / AHD / DDI / ERD Ratio: 114.594' / 11970.732 ft / 6.496' / 1.392
 Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
 Location Lat / Long: 32°24'4.05455"N, 104°19'38.14018"W
 Location Grid N/E Y/X: N 509661.140 RUS, E 543211.560 RUS
 CRS Grid Convergence Angle: 0.0033°
 Grid Scale Factor: 0.99990909
 Version / Patch: 2019.8.0.1

Survey / DLS Computation: Minimum Curvature / Lubinski
 Vertical Section Azimuth: 180.080 °(GRD North)
 Vertical Section Origin: 0.000 ft, 0.000 ft
 TVD Reference Datum: RKB
 TVD Reference Elevation: 3729.200 ft above MSL
 Seabed / Ground Elevation: 3697.200 ft above MSL
 Magnetic Declination: 7.201°
 Total Gravity Field Strength: 998.4469mgn (9.80665 Based)
 Gravity Model: GARM
 Total Magnetic Field Strength: 47844.168 nT
 Magnetic Dip Angle: 60.029°
 Declination Date: January 27, 2020
 Magnetic Declination Model: HDGM 2019
 North Reference: Grid North
 Grid Convergence Used: 0.0033°
 Total Corr Mag North->Grid North: 7.198°
 Local Coord Referenced To: Well Head

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	Northing (ftUS)	Easting (ftUS)	Latitude (°)	Longitude (°)	DLS (ft/100ft)	BR (ft/100ft)	TR (ft/100ft)
SHL	0.00	0.00	270.00	0.00	-3,729.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33			
Rustler	32.20	0.00	270.00	32.20	-3,697.00	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	100.00	0.00	270.00	100.00	-3,629.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	200.00	0.00	270.00	200.00	-3,529.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	300.00	0.00	270.00	300.00	-3,429.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	400.00	0.00	270.00	400.00	-3,329.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	500.00	0.00	270.00	500.00	-3,229.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	600.00	0.00	270.00	600.00	-3,129.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
Capitan	654.20	0.00	270.00	654.20	-3,075.00	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	700.00	0.00	270.00	700.00	-3,029.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	800.00	0.00	270.00	800.00	-2,929.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	900.00	0.00	270.00	900.00	-2,829.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	1,000.00	0.00	270.00	1,000.00	-2,729.20	0.00	0.00	0.00	509,661.14	543,211.56	32.40	-104.33	0.00	0.00	0.00
	1,100.00	1.00	270.00	1,099.99	-2,629.21	0.00	0.00	-0.87	509,661.14	543,210.69	32.40	-104.33	1.00	1.00	0.00
	1,200.00	2.00	270.00	1,199.96	-2,529.24	0.00	0.00	-3.49	509,661.14	543,208.07	32.40	-104.33	1.00	1.00	0.00
Nudge 1" DLS	1,300.00	3.00	270.00	1,299.86	-2,429.34	0.01	0.00	-7.85	509,661.14	543,203.71	32.40	-104.33	1.00	1.00	0.00
	1,400.00	4.00	270.00	1,399.68	-2,329.52	0.02	0.00	-13.96	509,661.14	543,197.60	32.40	-104.33	1.00	1.00	0.00
	1,500.00	5.00	270.00	1,499.37	-2,229.83	0.03	0.00	-21.80	509,661.14	543,189.76	32.40	-104.33	1.00	1.00	0.00
	1,600.00	6.00	270.00	1,598.90	-2,130.30	0.04	0.00	-31.39	509,661.14	543,180.18	32.40	-104.33	1.00	1.00	0.00
	1,700.00	6.00	270.00	1,698.36	-2,030.84	0.06	0.00	-41.84	509,661.14	543,169.72	32.40	-104.33	0.00	0.00	0.00
	1,800.00	6.00	270.00	1,797.81	-1,931.39	0.07	0.00	-52.29	509,661.14	543,159.27	32.40	-104.33	0.00	0.00	0.00
	1,900.00	6.00	270.00	1,897.26	-1,831.94	0.09	0.00	-62.75	509,661.14	543,148.82	32.40	-104.33	0.00	0.00	0.00
Hold	2,000.00	6.00	270.00	1,996.71	-1,732.49	0.10	0.00	-73.20	509,661.14	543,138.37	32.40	-104.33	0.00	0.00	0.00
	2,100.00	6.00	270.00	2,096.16	-1,633.04	0.12	0.00	-83.65	509,661.14	543,127.92	32.40	-104.33	0.00	0.00	0.00
	2,200.00	6.00	270.00	2,195.62	-1,533.58	0.13	0.00	-94.10	509,661.14	543,117.46	32.40	-104.33	0.00	0.00	0.00
	2,300.00	6.00	270.00	2,295.07	-1,434.13	0.15	0.00	-104.56	509,661.14	543,107.01	32.40	-104.33	0.00	0.00	0.00
	2,309.18	6.00	270.00	2,304.20	-1,425.00	0.15	0.00	-105.52	509,661.14	543,106.05	32.40	-104.33	0.00	0.00	0.00
	2,400.00	6.00	270.00	2,394.52	-1,334.68	0.16	0.00	-115.01	509,661.14	543,096.56	32.40	-104.33	0.00	0.00	0.00
	2,500.00	6.00	270.00	2,493.97	-1,235.23	0.18	0.00	-125.46	509,661.14	543,086.11	32.40	-104.33	0.00	0.00	0.00
Lamar	2,600.00	6.00	270.00	2,593.43	-1,135.77	0.19	0.00	-135.92	509,661.14	543,075.66	32.40	-104.33	0.00	0.00	0.00
	2,668.15	6.00	270.00	2,661.20	-1,068.00	0.20	0.00	-143.04	509,661.14	543,068.53	32.40	-104.33	0.00	0.00	0.00
	2,700.00	6.00	270.00	2,692.88	-1,036.32	0.20	0.00	-146.37	509,661.14	543,065.21	32.40	-104.33	0.00	0.00	0.00
	2,800.00	6.00	270.00	2,792.33	-936.87	0.22	0.00	-156.82	509,661.14	543,054.75	32.40	-104.33	0.00	0.00	0.00
	2,900.00	6.00	270.00	2,891.78	-837.42	0.23	0.00	-167.27	509,661.14	543,044.30	32.40	-104.33	0.00	0.00	0.00
	3,000.00	6.00	270.00	2,991.23	-737.97	0.25	0.00	-177.73	509,661.14	543,033.85	32.40	-104.33	0.00	0.00	0.00
	3,100.00	6.00	270.00	3,090.69	-638.51	0.26	0.00	-188.18	509,661.14	543,023.40	32.40	-104.33	0.00	0.00	0.00
Delaware Mtn Gr	3,200.00	6.00	270.00	3,190.14	-539.06	0.28	0.00	-198.63	509,661.14	543,012.95	32.40	-104.33	0.00	0.00	0.00
	3,300.00	6.00	270.00	3,289.59	-439.61	0.29	0.00	-209.09	509,661.14	543,002.49	32.40	-104.33	0.00	0.00	0.00
	3,400.00	6.00	270.00	3,389.04	-340.16	0.31	0.00	-219.54	509,661.14	542,992.04	32.40	-104.33	0.00	0.00	0.00
	3,500.00	6.00	270.00	3,488.50	-240.70	0.32	0.00	-229.99	509,661.14	542,981.59	32.40	-104.33	0.00	0.00	0.00
	3,600.00	6.00	270.00	3,587.95	-141.25	0.34	0.00	-240.44	509,661.14	542,971.14	32.40	-104.33	0.00	0.00	0.00
	3,700.00	6.00	270.00	3,687.40	-41.80	0.35	0.00	-250.90	509,661.14	542,960.69	32.40	-104.33	0.00	0.00	0.00
	3,800.00	6.00	270.00	3,786.85	57.65	0.36	0.00	-261.35	509,661.14	542,950.23	32.40	-104.33	0.00	0.00	0.00
Bone Spring	3,900.00	6.00	270.00	3,886.30	157.10	0.38	0.00	-271.80	509,661.14	542,939.78	32.40	-104.33	0.00	0.00	0.00
	4,000.00	6.00	270.00	3,985.76	256.56	0.39	0.00	-282.26	509,661.14	542,929.33	32.40	-104.33	0.00	0.00	0.00
	4,100.00	6.00	270.00	4,085.21	356.01	0.41	0.00	-292.71	509,661.14	542,918.88	32.40	-104.33	0.00	0.00	0.00
	4,200.00	6.00	270.00	4,184.66	455.46	0.42	0.00	-303.16	509,661.14	542,908.43	32.40	-104.33	0.00	0.00	0.00
	4,300.00	6.00	270.00	4,284.11	554.91	0.44	0.00	-313.61	509,661.14	542,897.98	32.40	-104.33	0.00	0.00	0.00
	4,400.00	6.00	270.00	4,383.57	654.37	0.45	0.00	-324.07	509,661.14	542,887.52	32.40	-104.33	0.00	0.00	0.00
	4,500.00	6.00	270.00	4,483.02	753.82	0.47	0.00	-334.52	509,661.14	542,877.07	32.40	-104.33	0.00	0.00	0.00
1st Bone Spring SS	4,600.00	6.00	270.00	4,582.47	853.27	0.48	0.00	-344.97	509,661.14	542,866.62	32.40	-104.33	0.00	0.00	0.00
	4,700.00	6.00	270.00	4,681.92	952.72	0.50	0.00	-355.43	509,661.14	542,856.17	32.40	-104.33	0.00	0.00	0.00
	4,800.00	6.00	270.00	4,781.37	1,052.17	0.51	0.00	-365.88	509,661.14	542,845.72	32.40	-104.33	0.00	0.00	0.00
	4,900.00	6.00	270.00	4,880.83	1,151.63	0.53	0.00	-376.33	509,661.14	542,835.26	32.40	-104.33	0.00	0.00	0.00
	5,000.00	6.00	270.00	4,980.28	1,251.08	0.54	0.00	-386.78	509,661.14	542,824.81	32.40	-104.33	0.00	0.00	0.00
	5,045.17	6.00	270.00	5,025.20	1,296.00	0.55	0.00	-391.51	509,661.14	542,820.09	32.40	-104.33	0.00	0.00	0.00
	5,100.00	6.00	270.00	5,079.73	1,350.53	0.55	0.00	-397.24	509,661.14	542,814.36	32.40	-104.33	0.00	0.00	0.00
2nd Bone Spring SS	5,200.00	6.00	270.00	5,179.18	1,449.98	0.57	0.00	-407.69	509,661.14	542,803.91	32.40	-104.33	0.00	0.00	0.00
	5,300.00	6.00	270.00	5,278.63	1,549.43	0.58	0.00	-418.14	509,661.14	542,793.46	32.40	-104.33	0.00	0.00	0.00
	5,400.00	6.00	270.00	5,378.09	1,648.89	0.60	0.00	-428.60	509,661.14	542,783.00	32.40	-104.33	0.00	0.00	0.00
	5,500.00	6.00	270.00	5,477.54	1,748.34	0.61	0.00	-439.05	509,661.14	542,772.55	32.40	-104.33	0.00	0.00	0.00
	5,600.00	6.00	270.00	5,576.99	1,847.79	0.63	0.00	-449.50	509,661.14	542,762.10	32.40	-104.33	0.00	0.00	0.00
	5,700.00	6.00	270.00	5,676.44	1,947.24	0.64	0.00	-459.95	509,661.14	542,751.65	32.40	-104.33	0.00	0.00	0.00
	5,800.00	6.00	270.00	5,775.90	2,046.70	0.66	0.00	-470.41	509,661.14	542,741.20	32.40	-104.33	0.00	0.00	0.00
KOP, Build 10" DLS	5,900.00	6.00	270.00	5,875.35	2,146.15	0.67	0.00	-480.86	509,661.14	542,730.75	32.40	-104.33</			

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	Northing (RUS)	Easting (RUS)	Latitude (°)	Longitude (°)	DLS (°100ft)	BR (°100ft)	TR (°100ft)
Turn 2° DLS	9,000.00	90.20	200.58	8,598.55	4,869.35	551.09	-549.73	-973.71	509,111.46	542,237.94	32.40	-104.33	0.00	0.00	0.00
	9,086.99	90.20	200.58	8,598.24	4,869.04	632.57	-631.17	-1,004.29	509,030.03	542,207.37	32.40	-104.33	0.00	0.00	0.00
	9,100.00	90.20	200.32	8,598.20	4,869.00	644.77	-643.36	-1,008.83	509,017.84	542,202.82	32.40	-104.33	2.00	0.00	-2.00
	9,200.00	90.20	198.32	8,597.85	4,868.65	739.18	-737.72	-1,041.91	508,923.48	542,169.74	32.40	-104.33	2.00	0.00	-2.00
	9,300.00	90.20	196.32	8,597.49	4,868.29	834.68	-833.18	-1,071.68	508,828.03	542,139.98	32.40	-104.33	2.00	0.00	-2.00
	9,400.00	90.20	194.32	8,597.14	4,867.94	931.16	-929.63	-1,098.10	508,731.60	542,113.56	32.40	-104.33	2.00	0.00	-2.00
	9,500.00	90.20	192.32	8,596.79	4,867.59	1,028.49	-1,026.93	-1,121.14	508,634.31	542,090.53	32.40	-104.33	2.00	0.00	-2.00
	9,600.00	90.20	190.32	8,596.43	4,867.23	1,126.57	-1,124.98	-1,140.76	508,536.27	542,070.90	32.40	-104.33	2.00	0.00	-2.00
	9,700.00	90.20	188.32	8,596.08	4,866.88	1,225.27	-1,223.65	-1,156.96	508,437.60	542,054.71	32.40	-104.33	2.00	0.00	-2.00
	9,800.00	90.20	186.32	8,595.72	4,866.52	1,324.46	-1,322.83	-1,169.70	508,338.43	542,041.97	32.40	-104.33	2.00	0.00	-2.00
Hold to TD	9,900.00	90.20	184.32	8,595.37	4,866.17	1,424.04	-1,422.40	-1,178.97	508,238.88	542,032.70	32.40	-104.33	2.00	0.00	-2.00
	10,000.00	90.20	182.32	8,595.02	4,865.82	1,523.88	-1,522.22	-1,184.76	508,139.06	542,026.91	32.40	-104.33	2.00	0.00	-2.00
	10,100.00	90.20	180.32	8,594.67	4,865.47	1,623.85	-1,622.19	-1,187.06	508,039.10	542,024.61	32.40	-104.33	2.00	0.00	-2.00
	10,111.80	90.20	180.08	8,594.63	4,865.43	1,635.65	-1,634.00	-1,187.10	508,027.30	542,024.57	32.40	-104.33	2.00	0.00	-2.00
	10,200.00	90.20	180.08	8,594.32	4,865.12	1,723.85	-1,722.19	-1,187.23	507,939.11	542,024.44	32.40	-104.33	0.00	0.00	0.00
	10,300.00	90.20	180.08	8,593.97	4,864.77	1,823.85	-1,822.19	-1,187.38	507,839.12	542,024.29	32.40	-104.33	0.00	0.00	0.00
	10,400.00	90.20	180.08	8,593.62	4,864.42	1,923.84	-1,922.19	-1,187.52	507,739.13	542,024.15	32.40	-104.33	0.00	0.00	0.00
	10,500.00	90.20	180.08	8,593.27	4,864.07	2,023.84	-2,022.19	-1,187.67	507,639.14	542,024.00	32.40	-104.33	0.00	0.00	0.00
	10,600.00	90.20	180.08	8,592.92	4,863.72	2,123.84	-2,122.19	-1,187.82	507,539.15	542,023.85	32.40	-104.33	0.00	0.00	0.00
	10,700.00	90.20	180.08	8,592.57	4,863.37	2,223.84	-2,222.19	-1,187.96	507,439.16	542,023.71	32.40	-104.33	0.00	0.00	0.00
10,800.00	90.20	180.08	8,592.22	4,863.02	2,323.84	-2,322.19	-1,188.11	507,339.17	542,023.56	32.39	-104.33	0.00	0.00	0.00	
10,900.00	90.20	180.08	8,591.87	4,862.67	2,423.84	-2,422.19	-1,188.25	507,239.18	542,023.42	32.39	-104.33	0.00	0.00	0.00	
11,000.00	90.20	180.08	8,591.52	4,862.32	2,523.84	-2,522.18	-1,188.40	507,139.19	542,023.27	32.39	-104.33	0.00	0.00	0.00	
11,100.00	90.20	180.08	8,591.17	4,861.97	2,623.84	-2,622.18	-1,188.54	507,039.20	542,023.13	32.39	-104.33	0.00	0.00	0.00	
11,200.00	90.20	180.08	8,590.82	4,861.62	2,723.84	-2,722.18	-1,188.69	506,939.21	542,022.98	32.39	-104.33	0.00	0.00	0.00	
11,300.00	90.20	180.08	8,590.47	4,861.27	2,823.84	-2,822.18	-1,188.84	506,839.22	542,022.84	32.39	-104.33	0.00	0.00	0.00	
11,400.00	90.20	180.08	8,590.12	4,860.92	2,923.84	-2,922.18	-1,188.98	506,739.23	542,022.69	32.39	-104.33	0.00	0.00	0.00	
11,500.00	90.20	180.08	8,589.77	4,860.57	3,023.84	-3,022.18	-1,189.13	506,639.24	542,022.54	32.39	-104.33	0.00	0.00	0.00	
11,600.00	90.20	180.08	8,589.42	4,860.22	3,123.84	-3,122.18	-1,189.27	506,539.25	542,022.40	32.39	-104.33	0.00	0.00	0.00	
11,700.00	90.20	180.08	8,589.07	4,859.87	3,223.84	-3,222.18	-1,189.42	506,439.26	542,022.25	32.39	-104.33	0.00	0.00	0.00	
11,800.00	90.20	180.08	8,588.72	4,859.52	3,323.84	-3,322.18	-1,189.56	506,339.27	542,022.11	32.39	-104.33	0.00	0.00	0.00	
11,900.00	90.20	180.08	8,588.37	4,859.17	3,423.84	-3,422.18	-1,189.71	506,239.28	542,021.96	32.39	-104.33	0.00	0.00	0.00	
12,000.00	90.20	180.08	8,588.02	4,858.82	3,523.84	-3,522.18	-1,189.85	506,139.29	542,021.82	32.39	-104.33	0.00	0.00	0.00	
12,100.00	90.20	180.08	8,587.67	4,858.47	3,623.83	-3,622.18	-1,190.00	506,039.30	542,021.67	32.39	-104.33	0.00	0.00	0.00	
12,200.00	90.20	180.08	8,587.32	4,858.12	3,723.83	-3,722.18	-1,190.14	505,939.31	542,021.53	32.39	-104.33	0.00	0.00	0.00	
12,300.00	90.20	180.08	8,586.97	4,857.77	3,823.83	-3,822.18	-1,190.29	505,839.32	542,021.38	32.39	-104.33	0.00	0.00	0.00	
12,400.00	90.20	180.08	8,586.62	4,857.42	3,923.83	-3,922.17	-1,190.43	505,739.33	542,021.24	32.39	-104.33	0.00	0.00	0.00	
12,500.00	90.20	180.08	8,586.27	4,857.07	4,023.83	-4,022.17	-1,190.58	505,639.34	542,021.09	32.39	-104.33	0.00	0.00	0.00	
12,600.00	90.20	180.08	8,585.92	4,856.72	4,123.83	-4,122.17	-1,190.72	505,539.35	542,020.95	32.39	-104.33	0.00	0.00	0.00	
12,700.00	90.20	180.08	8,585.57	4,856.37	4,223.83	-4,222.17	-1,190.87	505,439.36	542,020.80	32.39	-104.33	0.00	0.00	0.00	
12,800.00	90.20	180.08	8,585.22	4,856.02	4,323.83	-4,322.17	-1,191.01	505,339.37	542,020.66	32.39	-104.33	0.00	0.00	0.00	
12,900.00	90.20	180.08	8,584.86	4,855.66	4,423.83	-4,422.17	-1,191.16	505,239.38	542,020.51	32.39	-104.33	0.00	0.00	0.00	
13,000.00	90.20	180.08	8,584.51	4,855.31	4,523.83	-4,522.17	-1,191.30	505,139.39	542,020.37	32.39	-104.33	0.00	0.00	0.00	
13,100.00	90.20	180.08	8,584.16	4,854.96	4,623.83	-4,622.17	-1,191.45	505,039.40	542,020.22	32.39	-104.33	0.00	0.00	0.00	
13,200.00	90.20	180.08	8,583.81	4,854.61	4,723.83	-4,722.17	-1,191.59	504,939.41	542,020.08	32.39	-104.33	0.00	0.00	0.00	
13,300.00	90.20	180.08	8,583.46	4,854.26	4,823.83	-4,822.17	-1,191.74	504,839.42	542,019.93	32.39	-104.33	0.00	0.00	0.00	
13,400.00	90.20	180.08	8,583.11	4,853.91	4,923.83	-4,922.17	-1,191.88	504,739.43	542,019.79	32.39	-104.33	0.00	0.00	0.00	
13,500.00	90.20	180.08	8,582.76	4,853.56	5,023.83	-5,022.17	-1,192.03	504,639.44	542,019.64	32.39	-104.33	0.00	0.00	0.00	
13,600.00	90.20	180.08	8,582.41	4,853.21	5,123.83	-5,122.17	-1,192.17	504,539.45	542,019.50	32.39	-104.33	0.00	0.00	0.00	
13,700.00	90.20	180.08	8,582.05	4,852.85	5,223.82	-5,222.16	-1,192.32	504,439.46	542,019.35	32.39	-104.33	0.00	0.00	0.00	
13,800.00	90.20	180.08	8,581.70	4,852.50	5,323.82	-5,322.16	-1,192.46	504,339.47	542,019.21	32.39	-104.33	0.00	0.00	0.00	
13,900.00	90.20	180.08	8,581.35	4,852.15	5,423.82	-5,422.16	-1,192.61	504,239.48	542,019.06	32.39	-104.33	0.00	0.00	0.00	
14,000.00	90.20	180.08	8,581.00	4,851.80	5,523.82	-5,522.16	-1,192.75	504,139.49	542,018.92	32.39	-104.33	0.00	0.00	0.00	
14,100.00	90.20	180.08	8,580.65	4,851.45	5,623.82	-5,622.16	-1,192.90	504,039.50	542,018.77	32.39	-104.33	0.00	0.00	0.00	
14,200.00	90.20	180.08	8,580.29	4,851.09	5,723.82	-5,722.16	-1,193.04	503,939.51	542,018.63	32.39	-104.33	0.00	0.00	0.00	
14,300.00	90.20	180.08	8,579.94	4,850.74	5,823.82	-5,822.16	-1,193.19	503,839.52	542,018.49	32.39	-104.33	0.00	0.00	0.00	
14,400.00	90.20	180.08	8,579.59	4,850.39	5,923.82	-5,922.16	-1,193.33								

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	Northing (ftUS)	Easting (ftUS)	Latitude (°)	Longitude (°)	DLS (°/100ft)	BR (°/100ft)	TR (°/100ft)
		1	1,000.000	8,086.060	1/100.000	12.250			NAL_MWD_1.0_DEG		Shownuff 18-19 Fed Com 3BS :				
		1	8,086.060	8,966.990	1/100.000	8.750			NAL_MWD_1.0_DEG		Shownuff 18-19 Fed Com 3BS :				
		1	8,966.990	19,646.730	1/100.000	8.500			NAL_MWD_1.0_DEG		Shownuff 18-19 Fed Com 3BS :				

Schlumberger

Chisholm Shownuff 18-19 Fed Com 3BS 3H R0 IC 27Jan20 Proposal
Geodetic Report

Def Plan

Report Date:	January 28, 2020 - 05:55 PM (UTC 0)	Survey / DLS Completion:	Minimum Curvature / Lubinski
Client:	Chisholm	Vertical Section Azimuth:	180.080 / (GRID North)
Survey / Shot:	NMI Early County (NAD 83)	Vertical Section Origin:	0.000 / 0.000
Section / Shot:	Chisholm Shownuff 18-19 Fed Con 3B5 3H	V19 Reference Datum:	RKB
Section / Shot:	Shownuff 18-19 Fed Con 3B52 3H	V19 Reference Elevation:	866.270 220 above MSL
Borehole:	Shownuff 18-19 Fed Con 3B5 3H	Sealed / Ground Elevation:	3697.200 200 above MSL
Survey Name:	Unknown / Unknown	Magnetic Declination:	7.201°
UW1 / AP16:	Chisholm Shownuff 18-19 Fed Con 3B5 3H RD 32 C2 Jan20	Total Gravity Field Strength:	9.80665 Gauss (BAGS Based)
UW2 / AP17:	January 28, 2020	Gravity Model:	GAM8
Top / AHD / DSD / ERD Ratio:	114.566° / 119.072 182 D / 6.466° / 1392	Vertical Magnetic Field Strength:	4.458 mT
Location Lat / Long:	NAD83 New Mexico State Plane, Eastern Zone, US Feet	Magnetic Dip Angle:	60.029°
Location Lat / Long:	32° 24' 04.9450"N / 104° 10' 34.1401"W	Declination Date:	January 27, 2020
Location Lat / Long:	50.9661 140 BUS = 5.0251 156 BUS	Magnetic Declination Model:	IGMM15
CRS Grid Convergence Angle:	0.0003°	Total Reference:	7.198°
Grid Scale Factor:	999999.999	North Correction:	0.00033°
Projection / Patch:	2019.8.01	North Corr Mag North-Grid North:	0.00033°

Elements	MD	Incl	Asim	TVD	TVDSS	VSEC	AWD	NS	EW	DeltaMD	DeltaTVD	DLS	BR	TR	GTF	MTF	TF	(North)	(East)	(Latitude)	Longitude	Latitude	Longitude	Closure	Closure	Directional	Tortuosity	END Ratio	
	(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	
SHL Router	0.00	0.00	270.00	0.00	-3.729.20	0.00	0.00	0.00	0.00	0.00	32.20	32.20	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00		
	0.00	32.20	270.00	0.00	-3.697.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00		
	100.00	0.00	270.00	100.00	-3.629.20	0.00	0.00	0.00	0.00	67.80	67.80	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00		
	200.00	0.00	270.00	200.00	-3.559.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	300.00	0.00	270.00	300.00	-3.429.20	0.00	0.00	0.00	0.00	0.00	132.60	132.60	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	400.00	0.00	270.00	400.00	-3.329.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	500.00	0.00	270.00	500.00	-3.229.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	600.00	0.00	270.00	600.00	-3.129.20	0.00	0.00	0.00	0.00	0.00	132.60	132.60	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	700.00	0.00	270.00	700.00	-3.029.20	0.00	0.00	0.00	0.00	0.00	54.20	54.20	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	800.00	0.00	270.00	800.00	-2.929.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
Captain	1.000.00	0.00	270.00	1000.00	-2.729.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	2.000.00	0.00	270.00	2000.00	-2.629.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	3.000.00	0.00	270.00	3000.00	-2.529.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	4.000.00	0.00	270.00	4000.00	-2.429.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	5.000.00	0.00	270.00	5000.00	-2.329.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	6.000.00	0.00	270.00	6000.00	-2.229.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
	7.000.00	0.00	270.00	7000.00	-2.129.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
	8.000.00	0.00	270.00	8000.00	-2.029.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
	9.000.00	0.00	270.00	9000.00	-1.929.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
	10.000.00	0.00	270.00	10000.00	-1.829.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
Nudge 1° DLS	1.000.00	0.00	270.00	1000.00	-2.729.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	2.000.00	0.00	270.00	2000.00	-2.629.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	3.000.00	0.00	270.00	3000.00	-2.529.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	4.000.00	0.00	270.00	4000.00	-2.429.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	5.000.00	0.00	270.00	5000.00	-2.329.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	6.000.00	0.00	270.00	6000.00	-2.229.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
	7.000.00	0.00	270.00	7000.00	-2.129.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
	8.000.00	0.00	270.00	8000.00	-2.029.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
	9.000.00	0.00	270.00	9000.00	-1.929.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
	10.000.00	0.00	270.00	10000.00	-1.829.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
13.375 in Casing	1.000.00	0.00	270.00	1000.00	-2.729.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	2.000.00	0.00	270.00	2000.00	-2.629.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	3.000.00	0.00	270.00	3000.00	-2.529.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	4.000.00	0.00	270.00	4000.00	-2.429.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	5.000.00	0.00	270.00	5000.00	-2.329.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	6.000.00	0.00	270.00	6000.00	-2.229.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	7.000.00	0.00	270.00	7000.00	-2.129.20	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00	
	8.000.00	0.00	270.00	8000.00	-2.029.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24.4.054552N	1938.140181W	32.40	-104.33	0.00	0.00	0.00	0.00	0.00
	9.000.00	0.00	270.00	9000.00	-1.929.20	0.00	0.00	0.00	0.00	0.00	0.00	100.00	100.00	0.00	0.00	0.00	HS	270.00	270M	508.061.14	543.211.56 *24								

Schlumberger-Private

Comments	MD	Incl	Azim	TYD	TVSS	VSEC	AHD	NS	EW	DeltaMD	DeltaTYD	DLS	BR	TR	GTF	MTF	TF	Northing	Easting	Latitude	Longitude	Latitude	Longitude	Closure	Closure Azim	Directional Difficulty Index	Tortuosity	END Ratio
9.824999999999999 in Casing	8,500.00	43.79	206.49	8,420.98	4,891.78	135.19	872.83	-134.08	-798.81	100.00	77.78	10.00	9.88	-2.52	8.13L	205.02	8.13L	509.507	542.412.82	2342.728268N	1947.457038W	32.40	-104.33	809.99	260.47	4.62	47.39	0.10
	8,500.00	51.82	201.82	8,470.75	4,748.71	186.06	833.67	-189.81	-824.16	100.00	84.98	10.00	9.91	-1.79	7.15L	204.74	7.15L	509.472	542.386.48	2342.188709N	1947.764388W	32.40	-104.33	848.49	257.11	4.72	55.59	0.11
	8,600.00	53.71	204.74	8,486.83	4,757.63	202.98	948.01	-201.82	-831.19	18.00	10.88	10.00	9.92	-1.54	6.98L	203.29	6.98L	509.459.34	542.380.44	2342.057965N	1947.834574W	32.40	-104.33	855.34	256.35	4.74	57.39	0.11
	8,700.00	53.64	203.39	8,539.76	4,809.66	280.94	1,033.33	-279.73	-865.94	100.00	51.93	10.00	9.93	-1.35	6.27L	202.66	6.27L	509.381.43	542.345.70	2341.287019N	1948.240010W	32.40	-104.33	910.00	252.10	4.85	67.39	0.12
Landing Point / Hold	8,800.00	53.64	202.26	8,585.99	4,844.50	341.91	1,126.19	-341.91	-844.50	100.00	36.42	10.00	9.94	-1.13	5.86L	201.24	5.86L	509.389.18	542.340.43	2340.438872N	1948.850488W	32.40	-104.33	921.11	247.94	4.85	77.39	0.13
	8,900.00	83.53	201.24	8,595.00	4,865.80	457.69	1,224.21	-456.38	-938.25	100.00	19.81	10.00	9.95	-1.02	5.66L	200.58	5.66L	509.240.80	542.293.40	2339.591277N	1948.083405W	32.40	-104.33	1,043.35	244.06	5.04	87.39	0.14
	8,966.99	90.20	200.58	8,596.66	4,869.46	520.17	1,291.06	-518.83	-962.10	66.99	3.66	10.00	9.95	-0.98	HS	200.58	HS	509.142.86	542.245.65	2338.911951N	1949.361863W	32.40	-104.33	1,093.08	241.66	5.10	94.09	0.15
	8,900.00	90.20	200.58	8,596.66	4,869.46	520.17	1,291.06	-518.83	-962.10	66.99	3.66	10.00	9.95	-0.98	HS	200.58	HS	509.142.86	542.245.65	2338.911951N	1949.361863W	32.40	-104.33	1,093.08	241.66	5.10	94.09	0.15
Turn 2° DLS	9,096.99	90.20	200.58	8,598.24	4,869.04	632.57	1,411.06	-631.17	-1,004.29	86.99	-0.30	0.00	0.00	0.00	89.96L	200.32	89.96L	509.000.03	542.207.37	2337.808904N	1949.853677W	32.40	-104.33	1,186.16	237.85	5.15	94.09	0.16
	9,096.99	90.20	200.58	8,598.24	4,869.04	632.57	1,411.06	-631.17	-1,004.29	86.99	-0.30	0.00	0.00	0.00	89.96L	200.32	89.96L	509.017.84	542.202.82	2337.688944N	1949.853677W	32.40	-104.33	1,196.52	237.47	5.15	94.09	0.16
	9,200.00	108.32	188.32	8,597.86	4,868.65	730.18	1,524.01	-733.72	-1,041.91	100.00	-0.35	0.00	0.00	0.00	89.97L	198.32	89.97L	508.923.48	542.189.14	2336.756207N	1950.202572W	32.40	-104.33	1,276.64	234.70	5.20	10.35	0.16
	9,300.00	108.32	188.32	8,597.86	4,868.65	730.18	1,524.01	-733.72	-1,041.91	100.00	-0.35	0.00	0.00	0.00	89.98L	198.32	89.98L	508.836.03	542.176.81	2335.810250N	1950.039744W	32.40	-104.33	1,339.74	233.44	5.24	98.35	0.19
Holt to TD	9,400.00	90.20	194.32	8,597.14	4,867.94	931.16	1,724.07	-929.63	-1,068.10	100.00	-0.35	0.00	0.00	0.00	89.99L	198.32	89.99L	508.731.60	542.113.56	2334.856403N	1950.947947W	32.40	-104.33	1,438.76	229.75	5.28	100.35	0.20
	9,500.00	90.20	192.32	8,596.79	4,867.99	1,028.49	1,824.04	-1,028.93	-1,121.14	100.00	-0.35	0.00	0.00	0.00	89.99L	194.32	89.99L	508.634.31	542.080.33	2333.895641N	1951.216657W	32.40	-104.33	1,520.37	227.51	5.31	102.35	0.21
	9,600.00	90.20	190.32	8,596.43	4,867.23	1,126.57	1,924.07	-1,126.57	-1,140.76	100.00	-0.35	0.00	0.00	0.00	90L	198.32	90L	508.536.27	542.070.90	2332.924759N	1951.445997W	32.40	-104.33	1,602.16	225.40	5.35	104.35	0.22
	9,700.00	90.20	188.32	8,596.08	4,866.88	1,225.27	2,024.07	-1,225.65	-1,156.96	100.00	-0.35	0.00	0.00	0.00	90.01L	186.32	90.01L	508.437.60	542.054.71	2331.947108N	1951.634483W	32.40	-104.33	1,684.01	223.40	5.39	106.35	0.24
Holt to TD	9,800.00	90.20	186.32	8,595.72	4,866.52	1,324.46	2,124.07	-1,322.83	-1,169.70	100.00	-0.35	0.00	0.00	0.00	90.01L	184.32	90.01L	508.338.05	542.041.97	2330.965743N	1951.783652W	32.40	-104.33	1,765.81	221.48	5.42	108.35	0.25
	9,900.00	90.20	184.32	8,595.37	4,865.17	1,424.04	2,224.07	-1,422.40	-1,178.97	100.00	-0.35	0.00	0.00	0.00	90.02L	182.32	90.02L	508.238.68	542.032.70	2329.980276N	1951.891417W	32.40	-104.33	1,847.48	219.65	5.45	110.35	0.26
	10,000.00	90.20	182.32	8,595.02	4,864.82	1,523.88	2,324.07	-1,522.22	-1,184.76	100.00	-0.35	0.00	0.00	0.00	90.03L	180.32	90.03L	508.139.06	542.026.91	2328.992608N	1951.956788W	32.40	-104.33	1,926.94	217.89	5.48	112.35	0.27
	10,100.00	90.20	180.32	8,594.67	4,863.47	1,623.85	2,424.07	-1,622.19	-1,187.06	100.00	-0.35	0.00	0.00	0.00	90.04L	178.32	90.04L	508.039.10	542.024.61	2328.003631N	1951.969691W	32.40	-104.33	2,010.13	216.20	5.51	114.35	0.28
Holt to TD	10,200.00	90.20	180.08	8,594.32	4,862.12	1,723.85	2,524.07	-1,722.19	-1,187.23	88.20	-0.31	0.00	0.00	0.00	HS	180.08	HS	507.939.11	542.024.44	2327.014158N	1951.967880W	32.40	-104.33	2,095.69	214.58	5.54	114.59	0.29
	10,300.00	90.20	180.08	8,593.97	4,861.77	1,823.85	2,624.06	-1,822.19	-1,187.38	100.00	-0.35	0.00	0.00	0.00	HS	180.08	HS	507.839.12	542.024.29	2326.024678N	1951.968416W	32.40	-104.33	2,174.91	213.09	5.56	114.59	0.31
	10,400.00	90.20	180.08	8,593.62	4,861.42	1,923.84	2,724.06	-1,922.19	-1,187.52	100.00	-0.35	0.00	0.00	0.00	HS	180.08	HS	507.739.13	542.024.15	2325.035197N	1951.969114W	32.40	-104.33	2,259.43	211.71	5.58	114.59	0.32
	10,500.00	90.20	180.08	8,593.27	4,861.07	2,023.84	2,824.06	-2,022.19	-1,187.67	100.00	-0.35	0.00	0.00	0.00	HS	180.08	HS	507.639.14	542.024.00	2324.045717N	1951.962886W	32.40	-104.33	2,345.17	210.43	5.60	114.59	0.33
Holt to TD	10,600.00	90.20	180.08	8,592.92	4,860.72	2,123.84	2,924.06	-2,122.19	-1,187.82	100.00	-0.35	0.00	0.00	0.00	HS	180.08	HS	507.539.15	542.023.85	2323.056236N	1951.964590W	32.40	-104.33	2,431.99	209.24	5.62	114.59	0.34
	10,700.00	90.20	180.08	8,592.57	4,860.37	2,223.84	3,024.06	-2,222.19	-1,187.96	100.00	-0.35	0.00	0.00	0.00	HS	180.08	HS	507.439.16	542.023.70	2322.065756N	1951.966314W	32.40	-104.33	2,519.78	207.93	5.63	114.59	0.35
	10,800.00	90.20	180.08	8,592.22	4,860.02	2,323.84	3,124.06	-2,322.19	-1,188.11	100.00	-0.35	0.00	0.00	0.00	HS	180.08	HS	507.339.17	542.023.56	2321.077276N	1951.968037W	32.39	-104.33	2,608.48	207.10	5.65	114.59	0.36
	10,900.00	90.20	180.08	8,591.87	4,859.67	2,423.84	3,224.06	-2,422.19	-1,188.25	100.00	-0.35	0.00	0.00	0.00	HS	180.08	HS	507.239.18	542.023.42	2320.087794N	1951.969760W	32.39	-104.33	2,697.95	206.13	5.67	114.59	0.38
Holt to TD	11,000.00	90.20	180.08	8,591.52	4,859.32	2,523.84	3,324.06	-2,522.18	-1,188.40	100.00	-0.35	0.00	0.00	0.00	HS	180.08	HS	507.139.19	542.023.28	2319.098314N	1952.003205W	32.39	-104.33	2,787.42	205.16	5.68	114.59	0.39
	11,100.00	90.20	180.08	8,591.17	4,858.97	2,623.84	3,424.06	-2,622.18	-1,188.54	100.00	-0.35	0.00	0.00	0.00	HS	180.08	HS	507.039.20	542.023.13									

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	AHD (ft)	NS (ft)	EW (ft)	DeltaMD (ft)	DeltaTVD (ft)	DLS (°/100ft)	BR (°/100ft)	TR (°/100ft)	GTF (°)	MTF (°)	TF (°)	Northing (ftUS)	Easting (ftUS)	Latitude (°°')	Longitude (°°')	Latitude (°)	Longitude (°)	Closure (ft)	Closure Azimuth (°)	Directional Difficulty Index	Tortuosity (°)	ERD Ratio	
Survey Type:	Def Plan																												
Survey Error Model:	ISCWSA0 3 - D 95 % Confidence 2.7955 sigma																												
Survey Program:																													
Description	Part	MD From (ft)	MD To (ft)	EDU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (den)	Survey Tool Type	Borehole / Survey																				
	1	0.000	1,000.000	1/100.000	17.500			NAL_MWD_1.0_DEG	Shownuff 18-19 Fed Com 3BS 3																				
	1	1,000.000	8,086.060	1/100.000	12.250			NAL_MWD_1.0_DEG	Shownuff 18-19 Fed Com 3BS 3																				
	1	8,086.060	8,966.990	1/100.000	8.750			NAL_MWD_1.0_DEG	Shownuff 18-19 Fed Com 3BS 3																				
	1	8,966.990	19,646.730	1/100.000	8.500			NAL MWD 1.0 DEG	Shownuff 18-19 Fed Com 3BS 3																				

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	CHISHOLM ENERGY OPERATING LLC
LEASE NO.:	NMLC0064528A
WELL NAME & NO.:	SHOWNUFF 18-19 FED COM 3BS 3H
SURFACE HOLE FOOTAGE:	670'/S & 1125'/E
BOTTOM HOLE FOOTAGE:	100'/S & 2310'/E
LOCATION:	Section 7, T.22 S., R.26 E., NMPM
COUNTY:	Eddy County, New Mexico

COA

H2S	☐ Yes	☒ No	
Potash	☒ None	☐ Secretary	☐ R-111-P
Cave/Karst Potential	☐ Low	☐ Medium	☒ High
Cave/Karst Potential	☐ Critical		
Variance	☐ None	☒ Flex Hose	☐ Other
Wellhead	☐ Conventional	☒ Multibowl	☐ Both
Other	☐ 4 String Area	☒ Capitan Reef	☐ WIPP
Other	☐ Fluid Filled	☐ Cement Squeeze	☐ Pilot Hole
Special Requirements	☐ Water Disposal	☒ COM	☐ Unit

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **420 feet** (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8**

hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The 9-5/8 inch intermediate casing shall be set at approximately **2700 feet**. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:

Option 1 (Single Stage):

- Cement to surface. If cement does not circulate see B.1.a, c-d above.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.

Option 2:

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
 - b. Second stage above DV tool:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.
- ❖ In High Cave/Karst Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
 - ❖ In Capitan Reef Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
 - ❖ **Special Capitan Reef requirements.** If lost circulation (50% or greater) occurs below the Base of the Salt, the operator shall do the following:

- Switch to fresh water mud to protect the Capitan Reef and use fresh water mud until setting the intermediate casing. The appropriate BLM office is to be notified for a PET to witness the switch to fresh water.
 - Daily drilling reports from the Base of the Salt to the setting of the intermediate casing are to be submitted to the BLM CFO engineering staff via e-mail by 0800 hours each morning. Any lost circulation encountered is to be recorded on these drilling reports. The daily drilling report should show mud volume per shift/tour. Failure to submit these reports will result in an Incidence of Non-Compliance being issued for failure to comply with the Conditions of Approval. If not already planned, the operator shall run a caliper survey for the intermediate well bore and submit to the appropriate BLM office.
3. The minimum required fill of cement behind the 5-1/2 inch production casing is:

Option 1 (Single Stage):

- Cement should tie-back at least **50 feet** on top of Capitan Reef top **or 200 feet** into the previous casing, whichever is greater. If cement does not circulate see B.1.a, c-d above.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst, potash or capitan reef.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
2. **BOP REQUIREMENTS**

Option 1:

- a. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
- b. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the intermediate casing shoe shall be **5000 (5M)** psi.

Option 2:

Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**.

- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

D. SPECIAL REQUIREMENT (S)**Communitization Agreement**

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including

lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

RI03252021

Chisholm Energy Operating, LLC

801 Cherry St., Suite 1200-Unit 20

Fort Worth, TX 76102

H2S Contingency Plan

Eddy County, NM

Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crew should then block entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are NO homes or buildings in or near the ROE.

Assumed 100 ppm ROE = 3000'

100 ppm H₂S concentration shall trigger activation of this plan

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must:

- « Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- « Evacuate any public places encompassed by the 100 ppm ROE.
- « Be equipped with H₂S monitors and air packs in order to control the release.
- « Use the "buddy system" to ensure no injuries occur during the response.
- « Take precautions to avoid personal injury during this operation.
- « Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- « Have received training
 - in the: Detection of
 - H₂S, and
 - Measures for protection against the gas,
 - Equipment used for protection and emergency response.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H ₂ S	1.189 Air=1	10 ppm	100 ppm/hr	600 ppm

Sulfur Dioxide	SO ₂	2.21 Air=1	2 ppm	N/A	1000 ppm
----------------	-----------------	------------	-------	-----	----------

Contacting Authorities

Chisholm Energy Operating personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Chisholm Energy Operating, LLC response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMERP).

Hydrogen Sulfide Drilling Operations Plan

- 1 All Company and Contract personnel admitted on location must be trained by a qualified H₂S safety instructor to the following:
 - A. Characteristics of H₂S
 - B. Physical effects and hazards
 - C. Principal and operation of H₂S detectors, warning system and briefing areas.
 - D. Evacuation procedure, routes and first aid.
 - E. Proper use of safety equipment & life support systems
 - F. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30-minute pressure demand air packs.
- 2 H₂S Detection and Alarm Systems:
 - A. H₂S sensors/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud pits in the shale shaker area. Additional H₂S detectors may be placed as deemed necessary.
 - B. An audio alarm system will be installed on the derrick floor and in the top doghouse.
- 3 Windsock and/or wind streamers:
 - A. Windsock at mudpit area should be high enough to be visible.
 - B. Windsock on the rig floor and/ or top doghouse should be high enough to be visible.
- 4 Condition Flags and Signs
 - A. Warning sign on access road to location.
 - B. Flags to be displayed on sign at entrance to location. Green flag

indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H2S present in dangerous concentration). Only H2S trained and certified personnel admitted to location.

5 Well control equipment:

A. See exhibit BOP and Choke Diagrams

6 Communication:

- A. While working under masks chalkboards will be used for communication.
- B. Hand signals will be used where chalk board is inappropriate.
- C. Two-way radio will be used to communicate off location in case of emergency help is required. In most cases, cellular telephones will be available at most drilling foreman's trailer or living quarters.

7 Drill stem Testing:

No DSTs are planned at this time.

8 Drilling contractor supervisor will be required to be familiar with the effects H2S has on tubular goods and other mechanical equipment.

9 If H2S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H2S scavengers if necessary.

Emergency Assistance Telephone List

Chisholm Energy Holdings, LLC

Chisholm Energy Operating, LLC
Vice President of Operations-Brad Grandstaff

Office: (817)953-6063

Office: (817)953-3150

Cell: (972)977-9221

Drilling Superintendent-Russell Simons

Cell: (830)285-7501

Production Superintendent-Paul Martinez

Cell: (325)206-1722

Public Safety:		911 or
Eddy County Sheriff's Department	Number:	(575)887-7551
Eddy County Emergency Management	Number:	(575)628-5450
Lea County Fire Service	Number:	(575)628-5450
Fire Department:		
Artesia Fire Department	Number:	(575)746-5060
Sun Country Volunteer Fire Department	Number:	(505)484-3599
Riverside Volunteer Fire Department	Number:	(505)365-7900
Cottonwood Volunteer Fire Department	Number:	(505)748-7344
Atoka Fire Department	Number:	(505)746-9562
Queen Volunteer Fire Department	Number:	(505)981-2498
Joel Volunteer Fire Department	Number:	(505)885-4966
Otis Fire Rescue	Number:	(575)236-6113
La Huerta Volunteer Fire Department	Number:	(505)887-6353
Carlsbad Fire Department	Number:	(575)885-3125
Hope Volunteer Fire Department	Number:	(505)484-3351
Loco Hills Fire Department	Number:	(505)677-2349
Loving Fire Department	Number:	(505)745-3600
White's City Fire Department	Number:	(505)785-2219
Hospital:		
Artesia General Hospital	Number:	(575)748-3333
Carlsbad Medical Center	Number:	(575)887-4100
AirMed: Medevac	Number:	(888)303-9112
Dept. of Public Safety	Number:	(505)827-9000
New Mexico OCD-Dist. 2-Artesia	Office	Number: (575)748-1283
	Emergency	Number: (575)626-0830
Eddy County Road Department-South	Number:	(575)885-4835
Eddy County Road Department-North	Number:	(575)746-9540
NMDOT	Number:	(505)827-5100

Chisholm Energy Operating, LLC plans to operate a Closed Loop System.



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

04/13/2021

APD ID: 10400039537

Submission Date: 03/15/2019

Highlighted data
reflects the most
recent changes

Operator Name: CHISHOLM ENERGY OPERATING LLC

Well Name: SHOWNUFF 18-19 FED COM 3BS

Well Number: 3H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
418402	RUSTLER	3700	0	0	SANDSTONE, SHALE, SILTSTONE	NONE	N
418404	CAPITAN REEF	3049	651	651	LIMESTONE, SHALE	NONE	N
418405	LAMAR	1399	2301	2301	LIMESTONE, SHALE	NATURAL GAS, OIL	N
418406	DELAWARE	1042	2658	2658	SANDSTONE, SHALE, SILTSTONE	NATURAL GAS, OIL	N
418407	BONE SPRING	-1353	5053	5053	LIMESTONE, SHALE	NATURAL GAS, OIL	N
573648	BONE SPRING 1ST	-2502	6202	6202	SANDSTONE, SHALE	NATURAL GAS, OIL	N
573649	BONE SPRING 2ND	-3118	6818	6818	SANDSTONE, SHALE, SILTSTONE	NATURAL GAS, OIL	N
573650	BONE SPRING 3RD	-4560	8260	8260	SANDSTONE, SHALE, SILTSTONE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M

Rating Depth: 12500

Equipment: Rotating head, Mud Gas Separator, Flare Line, Remote Kill Line

Requesting Variance? YES

Variance request: WE PROPOSE UTILIZING A CACTUS SPEED HEAD MULTI-BOWL WELLHEAD FOR THIS WELL. PLEASE SEE ATTACHED DIAGRAM AND PRESSURE TESTING STATEMENT. ALSO WE REQUEST TO USE A FLEX CHOKE HOSE; PLEASE SEE ATTACHMENT.

Testing Procedure: As per Onshore Order #2 BOP testing procedure -N/U the rig's BOP. Use 3rd party testers to perform the following: -Test the pipe rams, blind rams, floor valves (IBOP and/or upper Kelly valve), choke lines and manifold to 250 psi/5,000 psi with a test plug and a test pump. -Test the Hyrdil annular to 250 psi/2,500 psi with same as above.

Choke Diagram Attachment:

5M_Choke_Manifold_Diagram_20190315094229.pdf

BOP Diagram Attachment:

5m_BOP_Diagram_2_20191028123344.pdf

Patriot Drilling, LLC

RIG NO. 5

Annular Preventer

13-3/8 5,000 PSI WP


Ram Preventers

13-3/8" 5,000 PSI WP Double Ram

13-3/8" 5,000 PSI WP Single Ram

Test the pipe rams, blind rams, floor valves (IBOP and/or upper Kelly valve), choke lines and manifold to 250 psi/5,000 psi with a test plug and a test pump.

Test the annular to 250 psi/2,500 psi with same as above.





District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

COMMENTS

Action 23959

COMMENTS

Operator: CHISHOLM ENERGY OPERATING, LLC 801 Cherry Street Fort Worth, TX76102			OGRID: 372137	Action Number: 23959	Action Type: FORM 3160-3
Created By	Comment			Comment Date	
kpickford	KP GEO Review 4/22/2021			04/23/2021	

District I

1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720

District II

811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720

District III

1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170

District IV

1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 23959

CONDITIONS OF APPROVAL

Operator:	CHISHOLM ENERGY OPERATING, LLC	801 Cherry Street	Fort Worth, TX76102	OGRID:	372137	Action Number:	23959	Action Type:	FORM 3160-3
-----------	--------------------------------	-------------------	---------------------	--------	--------	----------------	-------	--------------	-------------

OCD Reviewer	Condition
kpickford	Notify OCD 24 hours prior to casing & cement
kpickford	Will require a File As Drilled C-102 and a Directional Survey with the C-104
kpickford	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string
kpickford	Cement is required to circulate on both surface and intermediate1 strings of casing
kpickford	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system