

Form 3160-3  
(June 2015)FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
**APPLICATION FOR PERMIT TO DRILL OR REENTER**

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		5. Lease Serial No. <b>NMNM95642</b> 6. If Indian, Allottee or Tribe Name  7. If Unit or CA Agreement, Name and No.  8. Lease Name and Well No. <b>GRUMPY CAT 15-22 FED COM</b> <b>[325133]</b> <b>331H</b> 9. API Well No. <b>30-025-49133</b>
2. Name of Operator <b>DEVON ENERGY PRODUCTION COMPANY LP [6137]</b> 3a. Address <b>333 WEST SHERIDAN AVE, OKLAHOMA CITY, OK 7310</b> 3b. Phone No. (include area code) <b>(405) 235-3611</b>		10. Field and Pool, or Exploratory <b>[17644]</b> <b>DIAMONDTAIL; BONE SPRING/BONE SF</b> 11. Sec., T. R. M. or Blk. and Survey or Area <b>SEC 15/T23S/R32E/NMP</b>
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface <b>NWNW / 176 FNL / 1204 FWL / LAT 32.3114245 / LONG -103.6671721</b> At proposed prod. zone <b>SWSW / 20 FSL / 990 FWL / LAT 32.2829197 / LONG -103.6678444</b>		12. County or Parish <b>LEA</b> 13. State <b>NM</b>
14. Distance in miles and direction from nearest town or post office*  15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) <b>176 feet</b> 16. No of acres in lease  17. Spacing Unit dedicated to this well <b>320.0</b>		18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. <b>254 feet</b> 19. Proposed Depth <b>12050 feet / 22306 feet</b> 20. BLM/BIA Bond No. in file <b>FED: NMB000801</b>
21. Elevations (Show whether DF, KDB, RT, GL, etc.) <b>3695 feet</b> 22. Approximate date work will start* <b>08/31/2021</b> 23. Estimated duration <b>45 days</b>		24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- |   |   |
|---|---|
| 1. Well plat certified by a registered surveyor.<br>2. A Drilling Plan.<br>3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).<br>5. Operator certification.<br>6. Such other site specific information and/or plans as may be requested by the BLM. |
|---|---|

25. Signature (Electronic Submission)	Name (Printed/Typed) <b>JENNY HARMS / Ph: (800) 583-3866</b>	Date <b>09/07/2020</b>
Title <b>Regulatory Compliance Professional</b>		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) <b>Cody Layton / Ph: (575) 234-5959</b>	Date <b>03/23/2021</b>
Title <b>Assistant Field Manager Lands &amp; Minerals</b> <b>Carlsbad Field Office</b>		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
 Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

GCP Rec 05/14/2021

SL

(Continued on page 2)



Approval Date: 03/23/2021

**KZ**  
**07/02/2021**

\*(Instructions on page 2)

## PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

<b>OPERATOR'S NAME:</b>	<b>Devon Energy Production Company LP</b>
<b>LEASE NO.:</b>	<b>NMNM095642</b>
<b>LOCATION:</b>	Section 15, T.23 S., R.32 E., NMPM
<b>COUNTY:</b>	Lea County, New Mexico

<b>WELL NAME &amp; NO.:</b>	Grumpy Cat 15-22 Fed Com 331H
<b>SURFACE HOLE FOOTAGE:</b>	176'/N & 1204'/W
<b>BOTTOM HOLE FOOTAGE:</b>	20'/S & 990'/W

<b>WELL NAME &amp; NO.:</b>	Grumpy Cat 15-22 Fed Com 332H
<b>SURFACE HOLE FOOTAGE:</b>	175'/N & 2055'/W
<b>BOTTOM HOLE FOOTAGE:</b>	20'/S & 2310'/W

<b>WELL NAME &amp; NO.:</b>	Grumpy Cat 15-22 Fed Com 611H
<b>SURFACE HOLE FOOTAGE:</b>	176'/N & 1144'/W
<b>BOTTOM HOLE FOOTAGE:</b>	20'/S & 330'/W

<b>WELL NAME &amp; NO.:</b>	Grumpy Cat 15-22 Fed Com 612H
<b>SURFACE HOLE FOOTAGE:</b>	175'/N & 1995'/W
<b>BOTTOM HOLE FOOTAGE:</b>	20'/S & 1650'/W

<b>WELL NAME &amp; NO.:</b>	Grumpy Cat 15-22 Fed Com 711H
<b>SURFACE HOLE FOOTAGE:</b>	176'/N & 1174'/W
<b>BOTTOM HOLE FOOTAGE:</b>	20'/S & 790'/W

<b>WELL NAME &amp; NO.:</b>	Grumpy Cat 15-22 Fed Com 712H
<b>SURFACE HOLE FOOTAGE:</b>	175'/N & 2025'/W
<b>BOTTOM HOLE FOOTAGE:</b>	20'/S & 2110'/W

COA

H2S	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	
Potash	<input checked="" type="checkbox"/> None	<input type="checkbox"/> Secretary	<input type="checkbox"/> R-111-P
Cave/Karst Potential	<input checked="" type="checkbox"/> Low	<input type="checkbox"/> Medium	<input type="checkbox"/> High
Cave/Karst Potential	<input type="checkbox"/> Critical		
Variance	<input type="checkbox"/> None	<input checked="" type="checkbox"/> Flex Hose	<input type="checkbox"/> Other
Wellhead	<input type="checkbox"/> Conventional	<input type="checkbox"/> Multibowl	<input checked="" type="checkbox"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input checked="" type="checkbox"/> Fluid Filled	<input checked="" type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

**A. HYDROGEN SULFIDE**

A Hydrogen Sulfide (H<sub>2</sub>S) Drilling Plan shall be activated 500 feet prior to drilling into the **Diamondtail and Sand Dunes East pools of the Delaware Mountain Group**. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

**B. CASING**

1. The **13-3/8** inch surface casing shall be set at approximately **1291 feet** (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

**Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.**

2. The minimum required fill of cement behind the **8-5/8** inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above.  
**Cement excess is less than 25%, more cement might be required.**

**Operator has proposed to pump down 13-3/8" X 8-5/8" annulus. Operator must run a CBL from TD of the 8-5/8" casing to surface. Submit results to BLM.**

3. The minimum required fill of cement behind the **5-1/2** inch production casing is:
  - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.  
**Cement excess is less than 25%, more cement might be required.**

### C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
- 2.

#### Option 1:

- a. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**.
- b. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the intermediate casing shoe shall be **10,000 (10M) psi**. **Variance is approved to use a 5000 (5M) Annular which shall be tested to 5000 (5M) psi.**

#### Option 2:

1. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **10,000 (10M) psi**. **Variance is approved to use a 5000 (5M) Annular which shall be tested to 5000 (5M) psi.**
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

### D. SPECIAL REQUIREMENT (S)

#### Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New

Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

## GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

## A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

## B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not

hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

**D. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

District I  
1625 N. French Dr., Hobbs, NM 88240  
Phone: (575) 393-6161 Fax: (575) 393-0720  
District II  
811 S. First St., Artesia, NM 88210  
Phone: (575) 748-1283 Fax: (575) 748-9720  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources Department  
OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-102  
Revised August 1, 2011  
Submit one copy to appropriate  
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

<sup>1</sup> API Number <b>30-025-49133</b>	<sup>2</sup> Pool Code <b>[17644]</b>	<sup>3</sup> Pool Name <b>DIAMONDTAIL;BONE SPRING</b>
<sup>4</sup> Property Code <b>325133</b>	<sup>5</sup> Property Name <b>GRUMPY CAT 15-22 FED COM</b>	<sup>6</sup> Well Number <b>331H</b>
<sup>7</sup> OGRID No. <b>6137</b>	<sup>8</sup> Operator Name <b>DEVON ENERGY PRODUCTION COMPANY, L.P.</b>	<sup>9</sup> Elevation <b>3695.3</b>

<sup>10</sup> Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
<b>D</b>	<b>15</b>	<b>23 S</b>	<b>32 E</b>		<b>176</b>	<b>NORTH</b>	<b>1204</b>	<b>WEST</b>	<b>LEA</b>

<sup>11</sup> Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
<b>M</b>	<b>22</b>	<b>23 S</b>	<b>32 E</b>		<b>20</b>	<b>SOUTH</b>	<b>990</b>	<b>WEST</b>	<b>LEA</b>

<sup>12</sup> Dedicated Acres <b>320</b>	<sup>13</sup> Joint or Infill	<sup>14</sup> Consolidation Code	<sup>15</sup> Order No.
---	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

	<p><sup>17</sup> OPERATOR CERTIFICATION</p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p><i>Jenny Harms</i> 9-4-2020 Signature Date</p> <p><b>JENNY HARMS</b> Printed Name</p> <p><b>JENNY.HARMS@DVN.COM</b> E-mail Address</p>
<p><sup>18</sup> SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>JULY 20, 2020 Date of Survey</p> <p><i>[Signature]</i> Signature and Seal of Professional Surveyor:</p> <p>Certificate Number: <b>12797</b> Survey No. 8337</p>	<p><b>12797</b> Professional Surveyor</p>

Intent ☒ As Drilled ☐

API #		
Operator Name: DEVON ENERGY PRODUCTION COMPANY, L.P.	Property Name: GRUMPY CAT 15-22 FED COM	Well Number 331H

## Kick Off Point (KOP)

UL	Section 15	Township 23S	Range 32E	Lot	Feet 50 FNL	From N/S	Feet 990 FWL	From E/W	County LEA
Latitude 32.31177500					Longitude -103.66786200				NAD 83

## First Take Point (FTP)

UL D	Section 15	Township 23S	Range 32E	Lot	Feet 100	From N/S NORTH	Feet 990	From E/W WEST	County LEA
Latitude 32.3116317					Longitude 103.6678646				NAD 83

## Last Take Point (LTP)

UL M	Section 22	Township 23S	Range 32E	Lot	Feet 100	From N/S SOUTH	Feet 990	From E/W WEST	County LEA
Latitude 32.2831396					Longitude 103.6678446				NAD 83

Is this well the defining well for the Horizontal Spacing Unit? ☐ NOIs this well an infill well? ☐ YES


If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name:	Property Name:	Well Number

KZ 06/29/2018

(A) EXISTING GRUMPY CAT 15-22 FED COM 211H  
 (B) EXISTING GRUMPY CAT 15-22 FED COM 212H  
 (C) GRUMPY CAT 15-22 FED COM 521H  
 (D) GRUMPY CAT 15-22 FED COM 121H

(E) GRUMPY CAT 15-22 FED COM 531H  
 (F) GRUMPY CAT 15-22 FED COM 611H  
 (G) GRUMPY CAT 15-22 FED COM 711H  
 (H) GRUMPY CAT 15-22 FED COM 331H



### DIRECTIONS TO LOCATION

FROM INTERSECTION OF RED ROAD AND STATE HIGHWAY 128 GO EAST ON STATE HIGHWAY 128 APPROX. 1.2 MILES TO A PIPELINE ROAD ON LEFT (NORTH) TURN NORTHEAST ON PIPELINE ROAD AND GO NORTHEAST APPROX. 5.4 MILES TO A LEASE ROAD ON LEFT (NORTH) TURN NORTH GO APPROX. 1.0 MILE TO A LEASE ROAD ON LEFT (WEST) TURN WEST GO APPROX. 0.7 OF A MILE, ROAD TURNS RIGHT (NORTH) GO NORTH APPROX. 0.5 OF A MILE TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

I, FILMON F. JARAMILLA, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND IS SOMEWHAT LESS THAN THE MINIMUM STANDARDS FOR SUCH A SURVEY IN NEW MEXICO.

7 FILIMON F. JARAMILLO BUSTAMANTE 1979

**MADRON SURVEYING, INC.**

301 SOUTH CANAL  
(575) 234-3341

DEVON ENERGY PRODUCTION COMPANY, L.P.  
GRUMPY CAT 15-22 FED COM 331H  
LOCATED 176 FT. FROM THE NORTH LINE  
AND 1204 FT. FROM THE WEST LINE OF  
SECTION 15, TOWNSHIP 23 SOUTH,  
RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO


*JULY 20, 2020*

*SURVEY NO. 8337*

CARLSBAD, NEW MEXICO

**SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
INTERIM SITE BUILD PLAN**

- |  |                                   |
|--|-----------------------------------|
| (A) EXISTING GRUMPY CAT 15-22 FED COM 211H | (E) GRUMPY CAT 15-22 FED COM 531H |
| (B) EXISTING GRUMPY CAT 15-22 FED COM 212H | (F) GRUMPY CAT 15-22 FED COM 611H |
| (C) GRUMPY CAT 15-22 FED COM 521H          | (G) GRUMPY CAT 15-22 FED COM 711H |
| (D) GRUMPY CAT 15-22 FED COM 121H          | (H) GRUMPY CAT 15-22 FED COM 331H |



1.974± ACRES INTERIM PAD RECLAMATION AREA  
6.295± ACRES NON-RECLAIMED AREA  
8.269± ACRES GRUMPY CAT 15 WELLPAD 1

**DEVON ENERGY PRODUCTION COMPANY, L.P.  
GRUMPY CAT 15-22 FED COM 331H  
LOCATED 176 FT. FROM THE NORTH LINE  
AND 1204 FT. FROM THE WEST LINE OF  
SECTION 15, TOWNSHIP 23 SOUTH,  
RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO**

JULY 20, 2020


SURVEY NO. 8337

**MADRON SURVEYING, INC.**

301 SOUTH CANAL  
(575) 234-3341

**CARLSBAD, NEW MEXICO**

SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
LOCATION VERIFICATION MAP



USGS QUAD MAP:  
BOOTLEG RIDGE

NOT TO SCALE

DEVON ENERGY PRODUCTION COMPANY, L.P.  
**GRUMPY CAT 15-22 FED COM 331H**  
LOCATED 176 FT. FROM THE NORTH LINE  
AND 1204 FT. FROM THE WEST LINE OF  
SECTION 15, TOWNSHIP 23 SOUTH,  
RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO


JULY 20, 2020

MADRON SURVEYING, INC.

301 SOUTH CANAL  
(575) 234-3341

SURVEY NO. 8337  
CARLSBAD, NEW MEXICO

SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

**DIRECTIONS TO LOCATION**

FROM INTERSECTION OF RED ROAD AND STATE HIGHWAY 128 GO EAST ON STATE HIGHWAY 128 APPROX. 1.2 MILES TO A PIPELINE ROAD ON LEFT (NORTH) TURN NORTHEAST ON PIPELINE ROAD AND GO NORTHEAST APPROX. 5.4 MILES TO A LEASE ROAD ON LEFT (NORTH) TURN NORTH GO APPROX. 1.0 MILE TO A LEASE ROAD ON LEFT (WEST) TURN WEST GO APPROX. 0.7 OF A MILE, ROAD TURNS RIGHT (NORTH) GO NORTH APPROX. 0.5 OF A MILE TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

**DEVON ENERGY PRODUCTION COMPANY, L.P.****GRUMPY CAT 15-22 FED COM 331H**


LOCATED 176 FT. FROM THE NORTH LINE  
AND 1204 FT. FROM THE WEST LINE OF  
SECTION 15, TOWNSHIP 23 SOUTH,  
RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO

JULY 20, 2020

MADRON SURVEYING, INC.

301 SOUTH CANAL  
(575) 234-3341SURVEY NO. 8337  
CARLSBAD, NEW MEXICO

SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
AERIAL PHOTO



NOT TO SCALE  
AERIAL PHOTO:  
GOOGLE EARTH  
NOV. 2017

DEVON ENERGY PRODUCTION COMPANY, L.P.  
**GRUMPY CAT 15-22 FED COM 331H**  
LOCATED 176 FT. FROM THE NORTH LINE  
AND 1204 FT. FROM THE WEST LINE OF  
SECTION 15, TOWNSHIP 23 SOUTH,  
RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO


JULY 20, 2020

SURVEY NO. 8337

MADRON SURVEYING, INC. 301 SOUTH CANAL  
(575) 234-3341

CARLSBAD, NEW MEXICO

SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
**AERIAL ACCESS ROUTE MAP**



NOT TO SCALE  
AERIAL PHOTO:  
GOOGLE EARTH  
NOV. 2017

**DEVON ENERGY PRODUCTION COMPANY, L.P.**  
**GRUMPY CAT 15-22 FED COM 331H**  
LOCATED 176 FT. FROM THE NORTH LINE  
AND 1204 FT. FROM THE WEST LINE OF  
SECTION 15, TOWNSHIP 23 SOUTH,  
RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO

JULY 20, 2020





SURVEY NO. 8337

MADRON SURVEYING, INC. 301 SOUTH CANAL  
(575) 234-3341

CARLSBAD, NEW MEXICO



# CROSS SECTIONS



I, FILMON F. JARAMA, NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFICATE NO. 12291, AM RESPONSIBLE FOR THIS SURVEY, THAT THE SURVEY WAS CONDUCTED TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THE PLAT MEET THE MINIMUM STANDARDS FOR A SURVEY IN NEW MEXICO.

DEVON ENERGY PRODUCTION COMPANY, L.P.  
GRADING PLAN AND CROSS SECTIONS  
FOR GRUMPY CAT 15-22 FED COM 331H  
SECTION 15, TOWNSHIP 23 SOUTH,  
RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO

CUT	FILL	NET
36710 CU. YD	13690 CU. YD	23020 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED

012 60 120 240  
SCALE 1" = 120' - 1" = 20' VER


JULY 20, 2020  
301 SOUTH CANAL  
(575) 234-3341  
CARLSBAD, NEW MEXICO

SHEET 2-2  
SURVEY NO. 8337


**ACCESS ROAD PLAT (AA000111184)**

EXISTING ROAD FOR ACCESS TO GRUMPY CAT 15 WELLPAD 1  
(GRUMPY CAT 15-22 FED COM 521H, 121H, 531H, 611H, 711H, 331H, 211H, & 212H)

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING  
SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M.  
LEA COUNTY, STATE OF NEW MEXICO  
JULY 20, 2020



SEE NEXT SHEET (2-2) FOR DESCRIPTION

**GENERAL NOTES**

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-2

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (575) 234-3341

**SURVEYOR CERTIFICATE**

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 23rd DAY OF JULY 2020

FILMON F. JARAMILLO, PLS  
12797  
NEW MEXICO PROFESSIONAL SURVEYOR

MADRON SURVEYING, INC.  
301 SOUTH CANAL  
CARLSBAD, NEW MEXICO 88220  
Phone (575) 234-3341

SURVEY NO. 8337

**ACCESS ROAD PLAT (AA000111184)**

EXISTING ROAD FOR ACCESS TO GRUMPY CAT 15 WELLPAD 1  
(GRUMPY CAT 15-22 FED COM 521H, 121H, 531H, 611H, 711H, 331H, 211H, & 212H)

**DEVON ENERGY PRODUCTION COMPANY, L.P.**  
**CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING**  
**SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M.**  
**LEA COUNTY, STATE OF NEW MEXICO**  
**JULY 20, 2020**

**DESCRIPTION**

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M., LEA COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE NW/4 NW/4 OF SAID SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M., WHENCE THE WEST QUARTER CORNER OF SAID SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M. BEARS S21°26'08"W, A DISTANCE OF 2112.56 FEET;  
THENCE N12°22'06"E A DISTANCE OF 62.36 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE NORTHWEST CORNER OF SAID SECTION 15, TOWNSHIP 23 SOUTH, RANGE 32 EAST, N.M.P.M. BEARS N52°30'18"W, A DISTANCE OF 1010.84 FEET;

SAID STRIP OF LAND BEING 62.36 FEET OR 3.78 RODS IN LENGTH, CONTAINING 0.043 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

NW/4 NW/4    62.36 L.F.    3.78 RODS    0.043 ACRES

**SURVEYOR CERTIFICATE**

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 28<sup>TH</sup> DAY OF JULY 2020

FILIMON F. JARAMILLO, PLS. 12797  
MADRON SURVEYING, INC.  
301 SOUTH CANAL  
CARLSBAD, NEW MEXICO 88220  
Phone (575) 234-3341

**GENERAL NOTES**

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-2

**MADRON SURVEYING, INC.** 301 SOUTH CANAL CARLSBAD, NEW MEXICO  
(575) 234-3341

SURVEY NO. 8337

District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
811 S. First St., Artesia, NM 88210  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy, Minerals and Natural Resources Department  
Oil Conservation Division  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Submit Original  
to Appropriate  
District Office

## GAS CAPTURE PLAN

Date: August 24, 2020

☒ Original Devon & OGRID No.: Devon Energy Production Co., L.P. 6137  
☐ Amended - Reason for Amendment: \_\_\_\_\_

This Gas Capture Plan outlines actions to be taken by the Devon to reduce well/production facility flaring/venting for new completion (new drill, recomple to new zone, re-frac) activity.

*Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).*

### Well(s)/Production Facility – Name of facility

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	SHL FOOTAGES					Expected MCF/D	Flared or Vented	CTB
GRUMPY CAT 15-22 FED COM 521H		15-23S-32E	964	FWL	476	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 121H		15-23S-32E	994	FWL	476	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 531H		15-23S-32E	1024	FWL	476	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 611H		15-23S-32E	1144	FWL	176	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 711H		15-23S-32E	1174	FWL	176	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 331H	<b>30-025-49133</b>	15-23S-32E	1204	FWL	176	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 522H		15-23S-32E	1815	FWL	475	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 122H		15-23S-32E	1845	FWL	475	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 532H		15-23S-32E	1875	FWL	475	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 612H		15-23S-32E	1995	FWL	175	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 712H		15-23S-32E	2025	FWL	175	FNL			GRUMPY CAT 15 CTB 2
GRUMPY CAT 15-22 FED COM 332H		15-23S-32E	2055	FWL	175	FNL			GRUMPY CAT 15 CTB 2

### Gathering System and Pipeline Notification

Well(s) will be connected to a production facility after flowback operations are complete, if DCP system is in place. The gas produced from production facility is dedicated to DCP and will be connected to DCP low/high pressure gathering system located in Lea County, New Mexico. It will require 0' of pipeline to connect the facility to low/high pressure gathering system. Devon provides (periodically) to DCP a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, Devon and DCP have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at DCP Processing Plant located in the reference table. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

**Flowback Strategy**

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on DCP system at that time. Based on current information, it is Devon's belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

**Alternatives to Reduce Flaring**

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease
  - Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas – On lease
  - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
  - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines

**Reference Table:**

DCP Plant locations

Artesia Sec. 7, T18S, R28E,

Eunice Sec. 5, T21S, R36E

Linam Sec. 6, T19S, R37E

Zia II Sec. 19, T19S, R32E

## GRUMPY CAT 15-22 FED COM 331H

**1. Geologic Formations**

TVD of target	12050	Pilot hole depth	N/A
MD at TD:	22321	Deepest expected fresh water	

**Basin**

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone?	Hazards*
Rustler	1208		
Salt	1548		
Base of Salt	4536		
Lamar	4788		
Delaware	4830		
Cherry Canyon	5715		
Brushy Canyon	7010		
1st Bone Spring Lime	8690		
Bone Spring 1st	9840		
Bone Spring 2nd	10440		
3rd Bone Spring Lime	10965		
Bone Spring 3rd	11725		

\*H2S, water flows, loss of circulation, abnormal pressures, etc.

## GRUMPY CAT 15-22 FED COM 331H

**2. Casing Program (Primary Design)**

Hole Size	Csg. Size	Wt (PPF)	Grade	Conn	Casing Interval		Casing Interval	
					From (MD)	To (MD)	From (TVD)	To (TVD)
17 1/2	13 3/8	48	H40	STC	0	1233	0	1233
9 7/8	8 5/8	32	P110	TLW	0	10465	0	10465
7 7/8	5 1/2	17	P110	BTC	0	22321	0	12050

• All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 IILB.1.h Must have table for contingency casing.

**3. Cementing Program (Primary Design)**

Casing	# Sks	TOC	Wt. ppg	Yld (ft3/sack)	Slurry Description
Surface	931	Surf	13.2	1.44	Lead: Class C Cement + additives
Int 1	617	Surf	9	3.27	Lead: Class C Cement + additives
	67	4000' above	13.2	1.44	Tail: Class H / C + additives
Int 1 Intermediate Squeeze	As Needed	Surf	13.2	1.44	Squeeze Lead: Class C Cement + additives
	617	Surf	9	3.27	Lead: Class C Cement + additives
	67	4000' above	13.2	1.44	Tail: Class H / C + additives
Production	89	9965	9	3.27	Lead: Class H / C + additives
	1433	11496	13.2	1.44	Tail: Class H / C + additives

Casing String	% Excess
Surface	50%
Intermediate 1	30%
Intermediate 1 (Two Stage)	25%
Prod	10%

## GRUMPY CAT 15-22 FED COM 331H

**4. Pressure Control Equipment (Three String Design)**

BOP installed and tested before drilling which hole?		Size?	Min. Required WP	Type	✓	Tested to:
Int 1	13-5/8"	5M	Annular		X	50% of rated working pressure
			Blind Ram		X	5M
			Pipe Ram			
			Double Ram		X	
			Other*			
Production	13-5/8"	5M	Annular (5M)		X	100% of rated working pressure
			Blind Ram		X	10M
			Pipe Ram			
			Double Ram		X	
			Other*			
			Annular (5M)			
			Blind Ram			
			Pipe Ram			
			Double Ram			
			Other*			
N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.					
Y	A variance is requested to run a 5 M annular on a 10M system					

## GRUMPY CAT 15-22 FED COM 331H

**5. Mud Program (Three String Design)**

Section	Type	Weight (ppg)
Surface	FW Gel	8.5-9
Intermediate	DBE / Cut Brine	10-10.5
Production	OBM	8.5-9

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

**6. Logging and Testing Procedures**

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well - vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain.
	Coring? If yes, explain.

Additional logs planned		Interval
	Resistivity	Int. shoe to KOP
	Density	Int. shoe to KOP
X	CBL	Production casing
X	Mud log	Intermediate shoe to TD
	PEX	

**7. Drilling Conditions**

Condition	Specify what type and where?
BH pressure at deepest TVD	5639
Abnormal temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H<sub>2</sub>S) monitors will be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered measured values and formations will be provided to the BLM.

N	H <sub>2</sub> S is present
Y	H <sub>2</sub> S plan attached.

**8. Other facets of operation**

Is this a walking operation? Potentially

- 1 If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
- 2 The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
- 3 The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed

## GRUMPY CAT 15-22 FED COM 331H

from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially

- 1 Spudder rig will move in and batch drill surface hole.
  - a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.,
- 2 After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
- 3 The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
- 4 A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
- 5 Spudder rig operations is expected to take 4-5 days per well on a multi-well pa.
- 6 The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 7 Drilling operations will be performed with drilling rig. A that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
  - a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

## Attachments

X Directional Plan  
           Other, describe


Bent Tree 9-11 Fed Com 333H



**Well:** GRUMPY CAT 15-22 FED COM 331H  
**County:** Lea  
**Wellbore:** Permit Plan  
**Design:** Permit Plan #1

**Geodetic System:** US State Plane 1983  
**Datum:** North American Datum 1927  
**Ellipsoid:** Clarke 1866  
**Zone:** 3001 - NM East (NAD83)

MD (ft)	INC (°)	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL
2000.00	0.00	300.00	2000.00	0.00	0.00	0.00	0.00	Start Tangent
2500.00	10.00	300.00	2497.47	21.76	-37.69	-21.24	1.00	Hold Tangent
3427.27	10.00	300.00	3410.65	102.27	-177.14	-99.81	0.00	Drop to Vertical
3927.27	0.00	300.00	3908.11	124.03	-214.83	-121.05	2.00	Hold Vertical
11496.20	0.00	179.61	11477.04	124.03	-214.83	-121.05	0.00	KOP
12396.20	90.00	179.61	12050.00	-448.91	-210.93	451.79	10.00	Landing Point
22321.00	90.00	179.61	12050.00	-10373.48	-143.37	10374.47	0.00	BHL



Key Depths	MD (ft)	TVD (ft)
Rustler	0.00	0.00
Salt	1548.00	1548.00
Base of Salt	4555.16	4536.00
Lamar	4807.16	4788.00
Delaware	4849.16	4830.00
Cherry Canyon	5734.16	5715.00
Brushy Canyon	7029.16	7010.00
1st Bone Spring Lime	8709.16	8690.00
Bone Spring 1st	9859.16	9840.00
Bone Spring 2nd	10459.16	10440.00
3rd Bone Spring Lime	10984.16	10965.00
Bone Spring 3rd / Point of Penetration	11752.63	11725.00
Exit	22241.00	12050.01

**SHL**  
**KOP**  
**Point of Penetration**  
**Exit**  
**BHL**

MD (ft)	TVD (ft)	Lat (°)	Long (°)	Section Footages
0.00	0.00	32.3113	-103.6672	176' FNL, 1204' FWL of Sec 15 in T23S, R32E
11496.20	11477.04	32.3117	-103.6679	50' FNL, 990' FWL of Sec 15 in T23S, R32E
11752.63	11725.00	32.3116	-103.6679	100' FNL, 990' FWL of Sec 15 in T23S, R32E
22241.00	12050.01	32.2832	-103.6678	100' FSL, 990' FWL of Sec 22 in T23S, R32E
22321.00	12050.00	32.2828	-103.6679	20' FSL, 990' FWL of Sec 22 in T23S, R32E

Bent Tree 9-11 Fed Com 333H



**Well:** GRUMPY CAT 15-22 FED COM 331H  
**County:** Lea  
**Wellbore:** Permit Plan  
**Design:** Permit Plan #1

**Geodetic System:** US State Plane 1983  
**Datum:** North American Datum 1927  
**Ellipsoid:** Clarke 1866  
**Zone:** 3001 - NM East (NAD83)

MD (ft)	INC (°)	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL
100.00	0.00	300.00	100.00	0.00	0.00	0.00	0.00	
200.00	0.00	300.00	200.00	0.00	0.00	0.00	0.00	
300.00	0.00	300.00	300.00	0.00	0.00	0.00	0.00	
400.00	0.00	300.00	400.00	0.00	0.00	0.00	0.00	
500.00	0.00	300.00	500.00	0.00	0.00	0.00	0.00	
600.00	0.00	300.00	600.00	0.00	0.00	0.00	0.00	
700.00	0.00	300.00	700.00	0.00	0.00	0.00	0.00	
800.00	0.00	300.00	800.00	0.00	0.00	0.00	0.00	
900.00	0.00	300.00	900.00	0.00	0.00	0.00	0.00	
1000.00	0.00	300.00	1000.00	0.00	0.00	0.00	0.00	
1100.00	0.00	300.00	1100.00	0.00	0.00	0.00	0.00	
1200.00	0.00	300.00	1200.00	0.00	0.00	0.00	0.00	
1208.00	0.00	300.00	1208.00	0.00	0.00	0.00	0.00	Rustler
1300.00	0.00	300.00	1300.00	0.00	0.00	0.00	0.00	
1400.00	0.00	300.00	1400.00	0.00	0.00	0.00	0.00	
1500.00	0.00	300.00	1500.00	0.00	0.00	0.00	0.00	
1548.00	0.00	300.00	1548.00	0.00	0.00	0.00	0.00	Salt
1600.00	0.00	300.00	1600.00	0.00	0.00	0.00	0.00	
1700.00	0.00	300.00	1700.00	0.00	0.00	0.00	0.00	
1800.00	0.00	300.00	1800.00	0.00	0.00	0.00	0.00	
1900.00	0.00	300.00	1900.00	0.00	0.00	0.00	0.00	
2000.00	0.00	300.00	2000.00	0.00	0.00	0.00	0.00	Start Tangent
2100.00	2.00	300.00	2099.98	0.87	-1.51	-0.85	2.00	
2200.00	4.00	300.00	2199.84	3.49	-6.04	-3.41	2.00	
2300.00	6.00	300.00	2299.45	7.85	-13.59	-7.66	2.00	
2400.00	8.00	300.00	2398.70	13.94	-24.14	-13.60	2.00	
2500.00	10.00	300.00	2497.47	21.76	-37.69	-21.24	1.00	Hold Tangent
2600.00	10.00	300.00	2595.95	30.44	-52.73	-29.71	0.00	
2700.00	10.00	300.00	2694.43	39.13	-67.77	-38.19	0.00	
2800.00	10.00	300.00	2792.91	47.81	-82.81	-46.66	0.00	
2900.00	10.00	300.00	2891.39	56.49	-97.85	-55.13	0.00	
3000.00	10.00	300.00	2989.87	65.17	-112.88	-63.61	0.00	
3100.00	10.00	300.00	3088.35	73.86	-127.92	-72.08	0.00	
3200.00	10.00	300.00	3186.83	82.54	-142.96	-80.55	0.00	
3300.00	10.00	300.00	3285.31	91.22	-158.00	-89.03	0.00	
3400.00	10.00	300.00	3383.79	99.90	-173.04	-97.50	0.00	
3427.27	10.00	300.00	3410.65	102.27	-177.14	-99.81	0.00	Drop to Vertical
3500.00	8.55	300.00	3482.43	108.13	-187.29	-105.53	2.00	
3600.00	6.55	300.00	3581.55	114.70	-198.66	-111.94	2.00	
3700.00	4.55	300.00	3681.08	119.53	-207.03	-116.65	2.00	
3800.00	2.55	300.00	3780.89	122.62	-212.38	-119.67	2.00	
3900.00	0.55	300.00	3880.84	123.97	-214.72	-120.99	2.00	
3927.27	0.00	300.00	3908.11	124.03	-214.83	-121.05	2.00	Hold Vertical
4000.00	0.00	179.61	3980.84	124.03	-214.83	-121.05	0.00	
4100.00	0.00	179.61	4080.84	124.03	-214.83	-121.05	0.00	
4200.00	0.00	179.61	4180.84	124.03	-214.83	-121.05	0.00	
4300.00	0.00	179.61	4280.84	124.03	-214.83	-121.05	0.00	
4400.00	0.00	179.61	4380.84	124.03	-214.83	-121.05	0.00	
4500.00	0.00	179.61	4480.84	124.03	-214.83	-121.05	0.00	
4555.16	0.00	179.61	4536.00	124.03	-214.83	-121.05	0.00	Base of Salt
4600.00	0.00	179.61	4580.84	124.03	-214.83	-121.05	0.00	
4700.00	0.00	179.61	4680.84	124.03	-214.83	-121.05	0.00	
4800.00	0.00	179.61	4780.84	124.03	-214.83	-121.05	0.00	
4807.16	0.00	179.61	4788.00	124.03	-214.83	-121.05	0.00	Lamar
4849.16	0.00	179.61	4830.00	124.03	-214.83	-121.05	0.00	Delaware
4900.00	0.00	179.61	4880.84	124.03	-214.83	-121.05	0.00	
5000.00	0.00	179.61	4980.84	124.03	-214.83	-121.05	0.00	
5100.00	0.00	179.61	5080.84	124.03	-214.83	-121.05	0.00	
5200.00	0.00	179.61	5180.84	124.03	-214.83	-121.05	0.00	
5300.00	0.00	179.61	5280.84	124.03	-214.83	-121.05	0.00	
5400.00	0.00	179.61	5380.84	124.03	-214.83	-121.05	0.00	
5500.00	0.00	179.61	5480.84	124.03	-214.83	-121.05	0.00	
5600.00	0.00	179.61	5580.84	124.03	-214.83	-121.05	0.00	
5700.00	0.00	179.61	5680.84	124.03	-214.83	-121.05	0.00	
5734.16	0.00	179.61	5715.00	124.03	-214.83	-121.05	0.00	Cherry Canyon
5800.00	0.00	179.61	5780.84	124.03	-214.83	-121.05	0.00	
5900.00	0.00	179.61	5880.84	124.03	-214.83	-121.05	0.00	
6000.00	0.00	179.61	5980.84	124.03	-214.83	-121.05	0.00	
6100.00	0.00	179.61	6080.84	124.03	-214.83	-121.05	0.00	

Bent Tree 9-11 Fed Com 333H



**Well:** GRUMPY CAT 15-22 FED COM 331H  
**County:** Lea  
**Wellbore:** Permit Plan  
**Design:** Permit Plan #1

**Geodetic System:** US State Plane 1983  
**Datum:** North American Datum 1927  
**Ellipsoid:** Clarke 1866  
**Zone:** 3001 - NM East (NAD83)

MD (ft)	INC (")	AZI (")	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
6200.00	0.00	179.61	6180.84	124.03	-214.83	-121.05	0.00	
6300.00	0.00	179.61	6280.84	124.03	-214.83	-121.05	0.00	
6400.00	0.00	179.61	6380.84	124.03	-214.83	-121.05	0.00	
6500.00	0.00	179.61	6480.84	124.03	-214.83	-121.05	0.00	
6600.00	0.00	179.61	6580.84	124.03	-214.83	-121.05	0.00	
6700.00	0.00	179.61	6680.84	124.03	-214.83	-121.05	0.00	
6800.00	0.00	179.61	6780.84	124.03	-214.83	-121.05	0.00	
6900.00	0.00	179.61	6880.84	124.03	-214.83	-121.05	0.00	
7000.00	0.00	179.61	6980.84	124.03	-214.83	-121.05	0.00	
7029.16	0.00	179.61	7010.00	124.03	-214.83	-121.05	0.00	Brushy Canyon
7100.00	0.00	179.61	7080.84	124.03	-214.83	-121.05	0.00	
7200.00	0.00	179.61	7180.84	124.03	-214.83	-121.05	0.00	
7300.00	0.00	179.61	7280.84	124.03	-214.83	-121.05	0.00	
7400.00	0.00	179.61	7380.84	124.03	-214.83	-121.05	0.00	
7500.00	0.00	179.61	7480.84	124.03	-214.83	-121.05	0.00	
7600.00	0.00	179.61	7580.84	124.03	-214.83	-121.05	0.00	
7700.00	0.00	179.61	7680.84	124.03	-214.83	-121.05	0.00	
7800.00	0.00	179.61	7780.84	124.03	-214.83	-121.05	0.00	
7900.00	0.00	179.61	7880.84	124.03	-214.83	-121.05	0.00	
8000.00	0.00	179.61	7980.84	124.03	-214.83	-121.05	0.00	
8100.00	0.00	179.61	8080.84	124.03	-214.83	-121.05	0.00	
8200.00	0.00	179.61	8180.84	124.03	-214.83	-121.05	0.00	
8300.00	0.00	179.61	8280.84	124.03	-214.83	-121.05	0.00	
8400.00	0.00	179.61	8380.84	124.03	-214.83	-121.05	0.00	
8500.00	0.00	179.61	8480.84	124.03	-214.83	-121.05	0.00	
8600.00	0.00	179.61	8580.84	124.03	-214.83	-121.05	0.00	
8700.00	0.00	179.61	8680.84	124.03	-214.83	-121.05	0.00	
8709.16	0.00	179.61	8690.00	124.03	-214.83	-121.05	0.00	1st Bone Spring Lime
8800.00	0.00	179.61	8780.84	124.03	-214.83	-121.05	0.00	
8900.00	0.00	179.61	8880.84	124.03	-214.83	-121.05	0.00	
9000.00	0.00	179.61	8980.84	124.03	-214.83	-121.05	0.00	
9100.00	0.00	179.61	9080.84	124.03	-214.83	-121.05	0.00	
9200.00	0.00	179.61	9180.84	124.03	-214.83	-121.05	0.00	
9300.00	0.00	179.61	9280.84	124.03	-214.83	-121.05	0.00	
9400.00	0.00	179.61	9380.84	124.03	-214.83	-121.05	0.00	
9500.00	0.00	179.61	9480.84	124.03	-214.83	-121.05	0.00	
9600.00	0.00	179.61	9580.84	124.03	-214.83	-121.05	0.00	
9700.00	0.00	179.61	9680.84	124.03	-214.83	-121.05	0.00	
9800.00	0.00	179.61	9780.84	124.03	-214.83	-121.05	0.00	
9859.16	0.00	179.61	9840.00	124.03	-214.83	-121.05	0.00	Bone Spring 1st
9900.00	0.00	179.61	9880.84	124.03	-214.83	-121.05	0.00	
10000.00	0.00	179.61	9980.84	124.03	-214.83	-121.05	0.00	
10100.00	0.00	179.61	10080.84	124.03	-214.83	-121.05	0.00	
10200.00	0.00	179.61	10180.84	124.03	-214.83	-121.05	0.00	
10300.00	0.00	179.61	10280.84	124.03	-214.83	-121.05	0.00	
10400.00	0.00	179.61	10380.84	124.03	-214.83	-121.05	0.00	
10459.16	0.00	179.61	10440.00	124.03	-214.83	-121.05	0.00	Bone Spring 2nd
10500.00	0.00	179.61	10480.84	124.03	-214.83	-121.05	0.00	
10600.00	0.00	179.61	10580.84	124.03	-214.83	-121.05	0.00	
10700.00	0.00	179.61	10680.84	124.03	-214.83	-121.05	0.00	
10800.00	0.00	179.61	10780.84	124.03	-214.83	-121.05	0.00	
10900.00	0.00	179.61	10880.84	124.03	-214.83	-121.05	0.00	
10984.16	0.00	179.61	10965.00	124.03	-214.83	-121.05	0.00	3rd Bone Spring Lime
11000.00	0.00	179.61	10980.84	124.03	-214.83	-121.05	0.00	
11100.00	0.00	179.61	11080.84	124.03	-214.83	-121.05	0.00	
11200.00	0.00	179.61	11180.84	124.03	-214.83	-121.05	0.00	
11300.00	0.00	179.61	11280.84	124.03	-214.83	-121.05	0.00	
11400.00	0.00	179.61	11380.84	124.03	-214.83	-121.05	0.00	
11496.20	0.00	179.61	11477.04	124.03	-214.83	-121.05	0.00	KOP
11500.00	0.38	179.61	11480.84	124.02	-214.83	-121.04	10.00	
11600.00	10.38	179.61	11580.28	114.65	-214.77	-111.68	10.00	
11700.00	20.38	179.61	11676.57	88.17	-214.59	-85.19	10.00	
11752.63	25.64	179.61	11725.00	67.60	-214.45	-64.63	10.00	Bone Spring 3rd / Point of Penetration
11800.00	30.38	179.61	11766.81	45.36	-214.29	-42.39	10.00	
11900.00	40.38	179.61	11848.24	-12.47	-213.90	15.42	10.00	
12000.00	50.38	179.61	11918.39	-83.55	-213.42	86.49	10.00	
12100.00	60.38	179.61	11975.13	-165.74	-212.86	168.67	10.00	
12200.00	70.38	179.61	12016.73	-256.53	-212.24	259.44	10.00	
12300.00	80.38	179.61	12041.94	-353.17	-211.58	356.06	10.00	
12396.20	90.00	179.61	12050.00	-448.91	-210.93	451.79	10.00	Landing Point

Bent Tree 9-11 Fed Com 333H



**Well:** GRUMPY CAT 15-22 FED COM 331H  
**County:** Lea  
**Wellbore:** Permit Plan  
**Design:** Permit Plan #1

**Geodetic System:** US State Plane 1983  
**Datum:** North American Datum 1927  
**Ellipsoid:** Clarke 1866  
**Zone:** 3001 - NM East (NAD83)

MD (ft)	INC (")	AZI (")	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
12400.00	90.00	179.61	12050.00	-452.72	-210.90	455.59	0.00	
12500.00	90.00	179.61	12050.00	-552.71	-210.22	555.57	0.00	
12600.00	90.00	179.61	12050.00	-652.71	-209.54	655.54	0.00	
12700.00	90.00	179.61	12050.00	-752.71	-208.86	755.52	0.00	
12800.00	90.00	179.61	12050.00	-852.71	-208.18	855.50	0.00	
12900.00	90.00	179.61	12050.00	-952.70	-207.50	955.48	0.00	
13000.00	90.00	179.61	12050.00	-1052.70	-206.82	1055.46	0.00	
13100.00	90.00	179.61	12050.00	-1152.70	-206.14	1155.44	0.00	
13200.00	90.00	179.61	12050.00	-1252.70	-205.46	1255.42	0.00	
13300.00	90.00	179.61	12050.00	-1352.69	-204.78	1355.40	0.00	
13400.00	90.00	179.61	12050.00	-1452.69	-204.09	1455.37	0.00	
13500.00	90.00	179.61	12050.00	-1552.69	-203.41	1555.35	0.00	
13600.00	90.00	179.61	12050.00	-1652.69	-202.73	1655.33	0.00	
13700.00	90.00	179.61	12050.00	-1752.68	-202.05	1755.31	0.00	
13800.00	90.00	179.61	12050.00	-1852.68	-201.37	1855.29	0.00	
13900.00	90.00	179.61	12050.00	-1952.68	-200.69	1955.27	0.00	
14000.00	90.00	179.61	12050.00	-2052.68	-200.01	2055.25	0.00	
14100.00	90.00	179.61	12050.00	-2152.68	-199.33	2155.22	0.00	
14200.00	90.00	179.61	12050.00	-2252.67	-198.65	2255.20	0.00	
14300.00	90.00	179.61	12050.00	-2352.67	-197.97	2355.18	0.00	
14400.00	90.00	179.61	12050.00	-2452.67	-197.28	2455.16	0.00	
14500.00	90.00	179.61	12050.00	-2552.67	-196.60	2555.14	0.00	
14600.00	90.00	179.61	12050.00	-2652.66	-195.92	2655.12	0.00	
14700.00	90.00	179.61	12050.00	-2752.66	-195.24	2755.10	0.00	
14800.00	90.00	179.61	12050.00	-2852.66	-194.56	2855.08	0.00	
14900.00	90.00	179.61	12050.00	-2952.66	-193.88	2955.05	0.00	
15000.00	90.00	179.61	12050.00	-3052.65	-193.20	3055.03	0.00	
15100.00	90.00	179.61	12050.00	-3152.65	-192.52	3155.01	0.00	
15200.00	90.00	179.61	12050.00	-3252.65	-191.84	3254.99	0.00	
15300.00	90.00	179.61	12050.00	-3352.65	-191.16	3354.97	0.00	
15400.00	90.00	179.61	12050.00	-3452.65	-190.48	3454.95	0.00	
15500.00	90.00	179.61	12050.00	-3552.64	-189.79	3554.93	0.00	
15600.00	90.00	179.61	12050.00	-3652.64	-189.11	3654.91	0.00	
15700.00	90.00	179.61	12050.00	-3752.64	-188.43	3754.88	0.00	
15800.00	90.00	179.61	12050.00	-3852.64	-187.75	3854.86	0.00	
15900.00	90.00	179.61	12050.00	-3952.63	-187.07	3954.84	0.00	
16000.00	90.00	179.61	12050.00	-4052.63	-186.39	4054.82	0.00	
16100.00	90.00	179.61	12050.00	-4152.63	-185.71	4154.80	0.00	
16200.00	90.00	179.61	12050.00	-4252.63	-185.03	4254.78	0.00	
16300.00	90.00	179.61	12050.00	-4352.62	-184.35	4354.76	0.00	
16400.00	90.00	179.61	12050.00	-4452.62	-183.67	4454.74	0.00	
16500.00	90.00	179.61	12050.00	-4552.62	-182.99	4554.71	0.00	
16600.00	90.00	179.61	12050.00	-4652.62	-182.30	4654.69	0.00	
16700.00	90.00	179.61	12050.00	-4752.62	-181.62	4754.67	0.00	
16800.00	90.00	179.61	12050.01	-4852.61	-180.94	4854.65	0.00	
16900.00	90.00	179.61	12050.01	-4952.61	-180.26	4954.63	0.00	
17000.00	90.00	179.61	12050.01	-5052.61	-179.58	5054.61	0.00	
17100.00	90.00	179.61	12050.01	-5152.61	-178.90	5154.59	0.00	
17200.00	90.00	179.61	12050.01	-5252.60	-178.22	5254.57	0.00	
17300.00	90.00	179.61	12050.01	-5352.60	-177.54	5354.54	0.00	
17400.00	90.00	179.61	12050.01	-5452.60	-176.86	5454.52	0.00	
17500.00	90.00	179.61	12050.01	-5552.60	-176.18	5554.50	0.00	
17600.00	90.00	179.61	12050.01	-5652.59	-175.49	5654.48	0.00	
17700.00	90.00	179.61	12050.01	-5752.59	-174.81	5754.46	0.00	
17800.00	90.00	179.61	12050.01	-5852.59	-174.13	5854.44	0.00	
17900.00	90.00	179.61	12050.01	-5952.59	-173.45	5954.42	0.00	
18000.00	90.00	179.61	12050.01	-6052.59	-172.77	6054.39	0.00	
18100.00	90.00	179.61	12050.01	-6152.58	-172.09	6154.37	0.00	
18200.00	90.00	179.61	12050.01	-6252.58	-171.41	6254.35	0.00	
18300.00	90.00	179.61	12050.01	-6352.58	-170.73	6354.33	0.00	
18400.00	90.00	179.61	12050.01	-6452.58	-170.05	6454.31	0.00	
18500.00	90.00	179.61	12050.01	-6552.57	-169.37	6554.29	0.00	
18600.00	90.00	179.61	12050.01	-6652.57	-168.69	6654.27	0.00	
18700.00	90.00	179.61	12050.01	-6752.57	-168.00	6754.25	0.00	
18800.00	90.00	179.61	12050.01	-6852.57	-167.32	6854.22	0.00	
18900.00	90.00	179.61	12050.01	-6952.56	-166.64	6954.20	0.00	
19000.00	90.00	179.61	12050.01	-7052.56	-165.96	7054.18	0.00	
19100.00	90.00	179.61	12050.01	-7152.56	-165.28	7154.16	0.00	
19200.00	90.00	179.61	12050.01	-7252.56	-164.60	7254.14	0.00	
19300.00	90.00	179.61	12050.01	-7352.56	-163.92	7354.12	0.00	

Bent Tree 9-11 Fed Com 333H



**Well:** GRUMPY CAT 15-22 FED COM 331H  
**County:** Lea  
**Wellbore:** Permit Plan  
**Design:** Permit Plan #1

**Geodetic System:** US State Plane 1983  
**Datum:** North American Datum 1927  
**Ellipsoid:** Clarke 1866  
**Zone:** 3001 - NM East (NAD83)

MD	INC	AZI	TVD	NS	EW	VS	DLS	Comment
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	
19400.00	90.00	179.61	12050.01	-7452.55	-163.24	7454.10	0.00	
19500.00	90.00	179.61	12050.01	-7552.55	-162.56	7554.08	0.00	
19600.00	90.00	179.61	12050.01	-7652.55	-161.88	7654.05	0.00	
19700.00	90.00	179.61	12050.01	-7752.55	-161.20	7754.03	0.00	
19800.00	90.00	179.61	12050.01	-7852.54	-160.51	7854.01	0.00	
19900.00	90.00	179.61	12050.01	-7952.54	-159.83	7953.99	0.00	
20000.00	90.00	179.61	12050.01	-8052.54	-159.15	8053.97	0.00	
20100.00	90.00	179.61	12050.01	-8152.54	-158.47	8153.95	0.00	
20200.00	90.00	179.61	12050.01	-8252.53	-157.79	8253.93	0.00	
20300.00	90.00	179.61	12050.01	-8352.53	-157.11	8353.91	0.00	
20400.00	90.00	179.61	12050.01	-8452.53	-156.43	8453.88	0.00	
20500.00	90.00	179.61	12050.01	-8552.53	-155.75	8553.86	0.00	
20600.00	90.00	179.61	12050.01	-8652.52	-155.07	8653.84	0.00	
20700.00	90.00	179.61	12050.01	-8752.52	-154.39	8753.82	0.00	
20800.00	90.00	179.61	12050.01	-8852.52	-153.70	8853.80	0.00	
20900.00	90.00	179.61	12050.01	-8952.52	-153.02	8953.78	0.00	
21000.00	90.00	179.61	12050.01	-9052.52	-152.34	9053.76	0.00	
21100.00	90.00	179.61	12050.01	-9152.51	-151.66	9153.74	0.00	
21200.00	90.00	179.61	12050.01	-9252.51	-150.98	9253.71	0.00	
21300.00	90.00	179.61	12050.01	-9352.51	-150.30	9353.69	0.00	
21400.00	90.00	179.61	12050.01	-9452.51	-149.62	9453.67	0.00	
21500.00	90.00	179.61	12050.01	-9552.50	-148.94	9553.65	0.00	
21600.00	90.00	179.61	12050.01	-9652.50	-148.26	9653.63	0.00	
21700.00	90.00	179.61	12050.01	-9752.50	-147.58	9753.61	0.00	
21800.00	90.00	179.61	12050.01	-9852.50	-146.90	9853.59	0.00	
21900.00	90.00	179.61	12050.01	-9952.49	-146.21	9953.57	0.00	
22000.00	90.00	179.61	12050.01	-10052.49	-145.53	10053.54	0.00	
22100.00	90.00	179.61	12050.01	-10152.49	-144.85	10153.52	0.00	
22200.00	90.00	179.61	12050.01	-10252.49	-144.17	10253.50	0.00	
22241.00	90.00	179.61	12050.01	-10293.49	-143.89	10294.49	0.00	Exit
22300.00	90.00	179.61	12050.01	-10352.49	-143.49	10353.48	0.00	
22321.00	90.00	179.61	12050.00	-10373.48	-143.37	10374.47	0.00	BHL



**Devon Energy Center  
333 West Sheridan Avenue  
Oklahoma City, Oklahoma 73102-5015**

# **Hydrogen Sulfide (H<sub>2</sub>S) Contingency Plan**

**For**



**Grumpy Cat 15-22 Fed Com 331H**

**Sec-15 T-23S R-32E  
176' FNL & 1204' FWL  
LAT. = 32.3114245' N (NAD83)  
LONG = 103.6671721' W**

**Lea County NM**

## Grumpy Cat 15-22 Fed Com 331H

This is an open drilling site. H<sub>2</sub>S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H<sub>2</sub>S, including warning signs, wind indicators and H<sub>2</sub>S monitor.



Assumed 100 ppm **ROE = 3000'** (Radius of Exposure)  
100 ppm H<sub>2</sub>S concentration shall trigger activation of this plan.

### Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crews should then block the entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are no homes or buildings in or near the ROE.

**Assumed 100 ppm ROE = 3000'**

## 100 ppm H<sub>2</sub>S concentration shall trigger activation of this plan.

### Emergency Procedures

In the event of a release of gas containing H<sub>2</sub>S, the first responder(s) must

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE.
- Be equipped with H<sub>2</sub>S monitors and air packs in order to control the release.
- Use the “buddy system” to ensure no injuries occur during the response
- Take precautions to avoid personal injury during this operation.
- Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- Have received training in the
  - Detection of H<sub>2</sub>S, and
  - Measures for protection against the gas,
  - Equipment used for protection and emergency response.

### **Ignition of Gas Source**

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

### **Characteristics of H<sub>2</sub>S and SO<sub>2</sub>**

<b>Common Name</b>	<b>Chemical Formula</b>	<b>Specific Gravity</b>	<b>Threshold Limit</b>	<b>Hazardous Limit</b>	<b>Lethal Concentration</b>
<b>Hydrogen Sulfide</b>	H <sub>2</sub> S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
<b>Sulfur Dioxide</b>	SO <sub>2</sub>	2.21 Air = 1	2 ppm	N/A	1000 ppm

### **Contacting Authorities**

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER)

## Hydrogen Sulfide Drilling Operation Plan

### I. HYDROGEN SULFIDE (H<sub>2</sub>S) TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H<sub>2</sub>S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H<sub>2</sub>S metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H<sub>2</sub>S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H<sub>2</sub>S zone (within 3 days or 500 feet) and weekly H<sub>2</sub>S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan.

### II. HYDROGEN SULFIDE TRAINING

Note: All H<sub>2</sub>S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H<sub>2</sub>S.

**1. Well Control Equipment**

- A. Flare line
- B. Choke manifold – Remotely Operated
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
- D. Auxiliary equipment may include if applicable: annular preventer and rotating head.
- E. Mud/Gas Separator

**2. Protective equipment for essential personnel:**

30-minute SCBA units located at briefing areas, as indicated on well site diagram, with escape units available in the top doghouse. As it may be difficult to communicate audibly while wearing these units, hand signals shall be utilized.

**3. H<sub>2</sub>S detection and monitoring equipment:**

Portable H<sub>2</sub>S monitors positioned on location for best coverage and response. These units have warning lights which activate when H<sub>2</sub>S levels reach 10 ppm and audible sirens which activate at 15 ppm. Sensor locations:

- Bell nipple
- Possum Belly/Shale shaker
- Rig floor
- Choke manifold
- Cellar

**Visual warning systems:**

- A. Wind direction indicators as shown on well site diagram
- B. Caution/ Danger signs shall be posted on roads providing direct access to locations. Signs will be painted a high visibility yellow with black lettering of sufficient size to be reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

**4. Mud program:**

The mud program has been designed to minimize the volume of H<sub>2</sub>S circulated to surface. Proper mud weight, safe drilling practices and the use of H<sub>2</sub>S scavengers will minimize hazards when penetrating H<sub>2</sub>S bearing zones.

**5. Metallurgy:**

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold lines, and valves shall be H<sub>2</sub>S trim.
- B. All elastomers used for packing and seals shall be H<sub>2</sub>S trim.

**6. Communication:**

- A. Company personnel have/use cellular telephones in the field.
- B. Land line (telephone) communications at Office

**7. Well testing:**



- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safety and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H<sub>2</sub>S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

<b><u>Devon Energy Corp. Company Call List</u></b>		
Drilling Supervisor – Basin – Mark Kramer		405-823-4796
EHS Professional – Laura Wright		405-439-8129
<b><u>Agency Call List</u></b>		
<b><u>Lea County (575)</u></b>	<b>Hobbs</b>	
	Lea County Communication Authority	393-3981
	State Police	392-5588
	City Police	397-9265
	Sheriff's Office	393-2515
	<b>Ambulance</b>	<b>911</b>
	Fire Department	397-9308
	LEPC (Local Emergency Planning Committee)	393-2870
	NMOCD	393-6161
	US Bureau of Land Management	393-3612
<b><u>Eddy County (575)</u></b>	<b>Carlsbad</b>	
	State Police	885-3137
	City Police	885-2111
	Sheriff's Office	887-7551
	<b>Ambulance</b>	<b>911</b>
	Fire Department	885-3125
	LEPC (Local Emergency Planning Committee)	887-3798
	US Bureau of Land Management	887-6544
	NM Emergency Response Commission (Santa Fe)	(505) 476-9600
	24 HR	(505) 827-9126
	National Emergency Response Center	(800) 424-8802
	National Pollution Control Center: Direct	(703) 872-6000
	For Oil Spills	(800) 280-7118
	<b>Emergency Services</b>	
	Wild Well Control	(281) 784-4700
	Cudd Pressure Control	(915) 699-0139 (915) 563-3356
	Halliburton	(575) 746-2757
	B. J. Services	(575) 746-3569
<b><u>Give GPS position:</u></b>	Native Air – Emergency Helicopter – Hobbs	(575) 392-6429
	Flight For Life - Lubbock, TX	(806) 743-9911
	Aerocare - Lubbock, TX	(806) 747-8923
	Med Flight Air Amb - Albuquerque, NM	(575) 842-4433
	Lifeguard Air Med Svc. Albuquerque, NM	(800) 222-1222
	Poison Control (24/7)	(575) 272-3115
	Oil & Gas Pipeline 24 Hour Service	(800) 364-4366
	NOAA – Website - <a href="http://www.nhc.noaa.gov">www.nhc.noaa.gov</a>	

Prepared in conjunction with  
Dave Small



# Devon Energy - Well Pad Rig Location Layout Safety Equipment Location







Commitment Runs Deep



Design Plan  
Operation and Maintenance Plan  
Closure Plan

SENM - Closed Loop Systems  
June 2010

## I. Design Plan

Devon uses MI SWACO closed loop system (CLS). The MI SWACO CLS is designed to maintain drill solids at or below 5%. The equipment is arranged to progressively remove solids from the largest to the smallest size. Drilling fluids can thus be reused and savings is realized on mud and disposal costs. Dewatering may be required with the centrifuges to insure removal of ultra fine solids.

The drilling location is constructed to allow storm water to flow to a central sump normally the cellar. This insures no contamination leaves the drilling pad in the event of a spill. Storm water is reused in the mud system or stored in a reserve fluid tank farm until it can be reused. All lubricants, oils, or chemicals are removed immediately from the ground to prevent the contamination of storm water. An oil trap is normally installed on the sump if an oil spill occurs during a storm.

A tank farm is utilized to store drilling fluids including fresh water and brine fluids. The tank farm is constructed on a 20 ml plastic lined, bermed pad to prevent the contamination of the drilling site during a spill. Fluids from other sites may be stored in these tanks for processing by the solids control equipment and reused in the mud system. At the end of the well the fluids are transported from the tank farm to an adjoining well or to the next well for the rig.

Prior to installing a closed-loop system on site, the topsoil, if present, will be stripped and stockpiled for use as the final cover or fill at the time of closure.

Signs will be posted on the fence surrounding the closed-loop system unless the closed-loop system is located on a site where there is an existing well, that is operated by Devon.


## II. Operations and Maintenance Plan

**Primary Shakers:** The primary shakers make the first removal of drill solids from the drilling mud as it leaves the well bore. The shakers are sized to handle maximum drilling rate at optimal screen size. The shakers normally remove solids down to 74 microns.

**Mud Cleaner:** The Mud Cleaner cleans the fluid after it leaves the shakers. A set of hydrocyclones are sized to handle 1.25 to 1.5 times the maximum circulating rate. This ensures all the fluid is being processed to an average cut point of 25 microns. The wet discharged is dewatered on a shaker equipped with ultra fine mesh screens and generally cut at 40 microns.



## Closed Loop Schematic



**Centrifuges:** The centrifuges can be one or two in number depending on the well geometry or depth of well. The centrifuges are sized to maintain low gravity solids at 5% or below. They may or may not need a dewatering system to enhance the removal rates. The centrifuges can make a cut point of 8-10 microns depending on bowl speed, feed rate, solids loading and other factors.

The centrifuge system is designed to work on the active system and be flexible to process incoming fluids from other locations. This set-up is also dependant on well factors.

**Dewatering System:** The dewatering system is a chemical mixing and dosing system designed to enhance the solids removal of the centrifuge. Not commonly used in shallow wells. It may contain pH adjustment, coagulant mixing and dosing, and polymer mixing and dosing. Chemical flocculation binds ultra fine solids into a mass that is within the centrifuge operating design. The

dewatering system improves the centrifuge cut point to infinity or allows for the return of clear water or brine fluid. This ability allows for the ultimate control of low gravity solids.

*Cuttings Boxes:* Cuttings boxes are utilized to capture drill solids that are discarded from the solids control equipment. These boxes are set upon a rail system that allows for the removal and replacement of a full box of cuttings with an empty one. They are equipped with a cover that insures no product is spilled into the environment during the transportation phase.

*Process Tank:* (Optional) The process tank allows for the holding and process of fluids that are being transferred into the mud system. Additionally, during times of lost circulation the process tank may hold active fluids that are removed for additional treatment. It can further be used as a mixing tank during well control conditions.

*Sump and Sump Pump:* The sump is used to collect storm water and the pump is used to transfer this fluid to the active system or to the tank for to hold in reserve. It can also be used to collect fluids that may escape during spills. The location contains drainage ditches that allow the location fluids to drain to the sump.

*Reserve Fluids (Tank Farm):* A series of frac tanks are used to replace the reserve pit. These are steel tanks that are equipped with a manifold system and a transfer pump. These tanks can contain any number of fluids used during the drilling process. These can include fresh water, cut brine, and saturated salt fluid. The fluid can be from the active well or reclaimed fluid from other locations. A 20 ml liner and berm system is employed to ensure the fluids do not migrate to the environment during a spill.

If a leak develops, the appropriate division district office will be notified within 48 hours of the discovery and the leak will be addressed. Spill prevention is accomplished by maintaining pump packing, hoses, and pipe fittings to insure no leaks are occurring. During an upset condition the source of the spill is isolated and repaired as soon as it is discovered. Free liquid is removed by a diaphragm pump and returned to the mud system. Loose topsoil may be used to stabilize the spill and the contaminated soil is excavated and placed in the cuttings boxes. After the well is finished and the rig has moved, the entire location is scrapped and testing will be performed to determine if a release has occurred.

All trash is kept in a wire mesh enclosure and removed to an approved landfill when full. All spent motor oils are kept in separate containers and they are removed and sent to an approved recycling center. Any spilled lubricants, pipe

dope, or regulated chemicals are removed from soil and sent to landfills approved for these products.

These operations are monitored by Mi Swaco service technicians. Daily logs are maintained to ensure optimal equipment operation and maintenance. Screen and chemical use is logged to maintain inventory control. Fluid properties are monitored and recorded and drilling mud volumes are accounted for in the mud storage farm. This data is kept for end of well review to insure performance goals are met. Lessons learned are logged and used to help with continuous improvement.

A MI SWACO field supervisor manages from 3-5 wells. They are responsible for training personnel, supervising installations, and inspecting sites for compliance of MI SWACO safety and operational policy.

### **III. Closure Plan**

A maximum 340' X 340' caliche pad is built per well. All of the trucks and steel tanks fit on this pad. All fluid cuttings go to the steel tanks to be hauled by various trucking companies to an agency approved disposal.


# 10M BOPE & Closed Loop Equipment Schematic


10M Remote Kill Line Schematic

Outside Remote Kill Line Valve



Fill Up Line Valve





**District I**

1625 N. French Dr., Hobbs, NM 88240  
 Phone:(575) 393-6161 Fax:(575) 393-0720

**District II**

811 S. First St., Artesia, NM 88210  
 Phone:(575) 748-1283 Fax:(575) 748-9720

**District III**

1000 Rio Brazos Rd., Aztec, NM 87410  
 Phone:(505) 334-6178 Fax:(505) 334-6170

**District IV**

1220 S. St Francis Dr., Santa Fe, NM 87505  
 Phone:(505) 476-3470 Fax:(505) 476-3462

**State of New Mexico**  
**Energy, Minerals and Natural Resources**  
**Oil Conservation Division**  
**1220 S. St Francis Dr.**  
**Santa Fe, NM 87505**

CONDITIONS

Action 28265

**CONDITIONS**

Operator: DEVON ENERGY PRODUCTION COMPANY, LP 333 West Sheridan Ave. Oklahoma City, OK 73102	OGRID: 6137
	Action Number: 28265
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

**CONDITIONS**

Created By	Condition	Condition Date
pkautz	Will require a File As Drilled C-102 and a Directional Survey with the C-104	7/2/2021
pkautz	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	7/2/2021