

I. REQUEST FOR ALLOWABLE MINERAL AUTHORIZATION TO TRANSPORT

¹ Operator name and Address EOG RESOURCES INC PO BOX 2267 MIDLAND, TEXAS 79702		² OGRID Number 7377	
		³ Reason for Filing Code/ Effective Date NW 09/17/2021	
⁴ API Number 30 - 025-47187	⁵ Pool Name RED HILLS; BONE SPRING, NORTH		⁶ Pool Code 96434
⁷ Property Code 327233	⁸ Property Name YUKON 20 FED COM		⁹ Well Number 311H

II. ¹⁰ Surface Location

UI or lot no. C	Section 20	Township 24S	Range 34E	Lot Idn	Feet from the 492'	North/South Line NORTH	Feet from the 1537'	East/West line WEST	County LEA
--------------------	---------------	-----------------	--------------	---------	-----------------------	---------------------------	------------------------	------------------------	---------------

¹¹ Bottom Hole Location

UL or lot no. M	Section 29	Township 24S	Range 34E	Lot Idn	Feet from the 110'	North/South line SOUTH	Feet from the 338'	East/West line WEST	County LEA
¹² Lse Code F	¹³ Producing Method Code FLOWING	¹⁴ Gas Connection Date 09/17/2021	¹⁵ C-129 Permit Number		¹⁶ C-129 Effective Date		¹⁷ C-129 Expiration Date		

III. Oil and Gas Transporters

¹⁸ Transporter OGRID	¹⁹ Transporter Name and Address	²⁰ O/G/W
372812	EOGRM	OIL
151618	ENTERPRISE FIELD SERVICES	GAS
298751	REGENCY FIELD SERVICES	GAS
36785	DCP MIDSTREAM	GAS

IV. Well Completion Data

²¹ Spud Date 03/02/2021	²² Ready Date 09/17/2021	²³ TD 20,342'	²⁴ PBTD 20,319'	²⁵ Perforations 10,302- 20,319'	²⁶ DHC, MC	
²⁷ Hole Size		²⁸ Casing & Tubing Size		²⁹ Depth Set		³⁰ Sacks Cement
16"		13 3/8"		1348'		1255 SXS CL C/CIRC
12 1/4"		9 5/8"		5184'		1475 SXS CL C/CIRC
8 1/2"		5 1/2"		20,327'		2840 SXS CL H TOC 5656' CBL

V. Well Test Data

³¹ Date New Oil 09/17/2021	³² Gas Delivery Date 09/17/2021	³³ Test Date 10/03/2021	³⁴ Test Length 24 HRS	³⁵ Tbg. Pressure	³⁶ Csg. Pressure 796
³⁷ Choke Size 94	³⁸ Oil 3923	³⁹ Water 8117	⁴⁰ Gas 4856		⁴¹ Test Method
⁴² I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief. Signature: Kay Maddox			OIL CONSERVATION DIVISION Approved by: <i>PATRICIA MARATINEZ</i> Title: <i>PETROLEUM SPECIALIST</i> Approval Date: <i>3/21/2022</i>		
Printed name: Kay Maddox					
Title: SENIOR REGULATORY SPECIALIST					
E-mail Address: kay_maddox@eogresources.com					
Date: 10/05/2021		Phone: 432-638-8475			

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources
Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

FORM C-102

Revised August 1, 2011

Submit one copy to appropriate

District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-47187	² Pool Code 96434	³ Pool Name RED HILLS; BONE SPRING, NORTH
⁴ Property Code 327233	⁵ Property Name YUKON 20 FED COM	⁶ Well Number #311H
⁷ OGRID No. 7377	⁸ Operator Name EOG RESOURCES, INC.	⁹ Elevation 3543'

¹⁰Surface Location


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
C	20	24-S	34-E	-	492'	NORTH	1537'	WEST	LEA


¹¹Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	29	24-S	34-E	-	110'	SOUTH	338'	WEST	LEA

¹² Dedicated Acres 640.00	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
---	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.






eo resources, Inc.

YUKON 20 FED COM 311H AS-COMPLETED	REVISION:		NOTES:
DATE: 09/01/2021			1. ORIGINAL DOCUMENT SIZE: 8.5" X 11" 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET. 3. THIS WELL LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY. 4. ADJOINER INFORMATION SHOWN FOR INFORMATIONAL PURPOSES ONLY.
FILE:AD_YUKON_20_FED_COM_311H			
DRAWN BY: GJU			
SHEET: 1 OF 1			

Z:\SURVEY\EOG_MIDLAND\YUKON_20_FED_COM\FINAL_PRODUCTS\AD_YUKON_20_FED_COM_311H.DWG 9/7/2021 9:19:40 AM eochao





EOG Resources - Midland

Lea County, NM (NAD 83 NME)

Yukon 20 Fed Com

#311H

OH

Design: OH

Final PVA

14 April, 2021



EOG Resources

Final PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #311H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 25' @ 3568.0usft
Site:	Yukon 20 Fed Com	MD Reference:	KB = 25' @ 3568.0usft
Well:	#311H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.14

Project		Lea County, NM (NAD 83 NME)	
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site		Yukon 20 Fed Com								
Site Position:		Northing:		440,613.00	usft	Latitude:	32° 12' 30.615 N			
From:	Map	Easting:		802,407.00	usft	Longitude:	103° 29' 21.259 W			
Position Uncertainty:		0.0	usft	Slot Radius:		13-3/16	"	Grid Convergence:	0.45	°

Well		#311H				
Well Position	+N/-S	0.0 usft	Northing:	440,766.00 usft	Latitude:	32° 12' 32.279 N
	+E/-W	0.0 usft	Easting:	800,471.00 usft	Longitude:	103° 29' 43.778 W
Position Uncertainty	0.0 usft		Wellhead Elevation:	usft	Ground Level:	3,543.0 usft

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2020	12/8/2020	6.57	59.92	47,545.79743163

Design		OH			
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)		+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0		0.0	0.0	186.52

Survey Program		Date	4/14/2021		
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description	
140.0	20,342.0	Pro MWD (OH)	EOG MWD+IFR1	MWD + IFR1	



EOG Resources

Final PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #311H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 25' @ 3568.0usft
Site:	Yukon 20 Fed Com	MD Reference:	KB = 25' @ 3568.0usft
Well:	#311H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.14

Survey											
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)	
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.0	0.0	
140.0	0.75	218.64	140.0	-0.7	-0.6	0.54	0.54	0.00	-0.9	0.0	
231.0	0.97	68.79	231.0	-0.9	-0.2	1.83	0.24	-164.67	0.5	-0.8	
322.0	1.14	68.96	322.0	-0.3	1.3	0.19	0.19	0.19	-1.1	-0.8	
414.0	0.53	75.29	414.0	0.1	2.6	0.67	-0.66	6.88	-2.6	-0.5	
597.0	0.48	84.87	597.0	0.4	4.2	0.05	-0.03	5.23	-4.2	0.0	
692.0	0.40	97.70	692.0	0.4	4.9	0.13	-0.08	13.51	-4.8	1.1	
882.0	0.57	65.36	881.9	0.7	6.4	0.17	0.09	-17.02	-6.1	-2.0	
977.0	0.48	81.18	976.9	1.0	7.2	0.18	-0.09	16.65	-7.3	-0.1	
1,072.0	0.66	106.49	1,071.9	0.9	8.2	0.32	0.19	26.64	-7.6	3.2	
1,166.0	0.53	123.19	1,165.9	0.5	9.0	0.23	-0.14	17.77	-7.3	5.4	
1,261.0	0.66	148.41	1,260.9	-0.2	9.7	0.30	0.14	26.55	-5.3	8.2	
1,284.0	0.40	154.83	1,283.9	-0.4	9.8	1.16	-1.13	27.91	-4.5	8.7	
1,447.0	1.27	259.61	1,446.9	-1.2	8.3	0.87	0.53	64.28	8.2	3.0	
1,542.0	2.50	279.39	1,541.9	-1.1	5.2	1.45	1.29	20.82	8.6	1.4	
1,636.0	4.09	284.49	1,635.7	0.1	-0.1	1.72	1.69	5.43	9.3	2.3	
1,731.0	6.42	290.73	1,730.3	2.8	-8.3	2.52	2.45	6.57	9.0	2.7	
1,826.0	6.46	293.19	1,824.7	6.8	-18.2	0.29	0.04	2.59	6.7	3.3	
1,921.0	5.93	296.33	1,919.1	11.1	-27.5	0.66	-0.56	3.31	4.9	3.5	
2,016.0	5.45	295.65	2,013.7	15.2	-36.0	0.51	-0.51	-0.72	3.7	3.9	
2,111.0	5.14	296.44	2,108.3	19.0	-43.9	0.34	-0.33	0.83	3.2	4.2	
2,205.0	5.41	296.62	2,201.9	22.9	-51.6	0.29	0.29	0.19	2.8	4.5	
2,300.0	5.05	297.49	2,296.5	26.8	-59.3	0.39	-0.38	0.92	2.5	4.7	
2,394.0	4.88	298.81	2,390.1	30.7	-66.5	0.22	-0.18	1.40	2.6	4.6	
2,584.0	4.04	301.71	2,579.5	38.1	-79.3	0.46	-0.44	1.53	4.6	4.0	
2,679.0	3.87	303.56	2,674.3	41.6	-84.8	0.22	-0.18	1.95	6.5	3.2	
2,774.0	3.65	303.74	2,769.1	45.1	-90.0	0.23	-0.23	0.19	8.5	2.4	



EOG Resources

Final PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #311H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 25' @ 3568.0usft
Site:	Yukon 20 Fed Com	MD Reference:	KB = 25' @ 3568.0usft
Well:	#311H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.14

Survey										
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
2,964.0	9.14	304.53	2,957.9	57.0	-107.4	2.89	2.89	0.42	3.8	0.6
3,059.0	9.14	305.93	3,051.7	65.7	-119.8	0.23	0.00	1.47	-3.1	-0.4
3,154.0	8.53	308.31	3,145.5	74.5	-131.4	0.75	-0.64	2.51	-9.6	-1.4
3,249.0	8.13	308.48	3,239.5	83.0	-142.2	0.42	-0.42	0.18	-15.2	-2.8
3,344.0	7.56	309.45	3,333.6	91.2	-152.3	0.62	-0.60	1.02	-20.1	-4.0
3,439.0	6.94	312.79	3,427.9	99.1	-161.3	0.79	-0.65	3.52	-24.3	-4.5
3,533.0	6.90	315.07	3,521.2	106.9	-169.5	0.30	-0.04	2.43	-28.0	-5.6
3,628.0	6.90	315.69	3,615.5	115.0	-177.5	0.08	0.00	0.65	-31.5	-7.7
3,818.0	5.84	318.94	3,804.3	130.5	-191.8	0.59	-0.56	1.71	-37.5	-11.1
3,912.0	4.97	311.21	3,897.9	136.8	-198.0	1.20	-0.93	-8.22	-36.5	-18.5
4,007.0	5.05	293.80	3,992.6	141.2	-204.9	1.60	0.08	-18.33	-29.2	-29.1
4,102.0	4.88	290.73	4,087.2	144.3	-212.5	0.33	-0.18	-3.23	-27.6	-29.7
4,197.0	4.09	289.06	4,181.9	146.8	-219.5	0.84	-0.83	-1.76	-26.0	-29.3
4,292.0	3.74	290.64	4,276.7	149.0	-225.6	0.39	-0.37	1.66	-25.0	-27.3
4,386.0	3.43	288.79	4,370.5	151.0	-231.1	0.35	-0.33	-1.97	-21.9	-26.9
4,481.0	2.81	282.90	4,465.4	152.5	-236.1	0.73	-0.65	-6.20	-16.2	-27.0
4,576.0	1.93	277.37	4,560.3	153.2	-240.0	0.96	-0.93	-5.82	-9.7	-25.7
4,671.0	1.01	273.15	4,655.2	153.4	-242.4	0.97	-0.97	-4.44	-2.7	-23.0
4,766.0	0.97	283.08	4,750.2	153.7	-244.0	0.19	-0.04	10.45	-0.3	-19.8
4,861.0	0.48	168.12	4,845.2	153.5	-244.7	1.32	-0.52	-121.01	12.7	13.7
4,955.0	1.32	223.32	4,939.2	152.3	-245.4	1.19	0.89	58.72	19.3	5.6
5,050.0	1.10	207.93	5,034.2	150.7	-246.5	0.41	-0.23	-16.20	15.1	18.5
5,117.0	1.01	210.84	5,101.2	149.6	-247.1	0.16	-0.13	4.34	15.0	23.6
5,240.0	0.83	227.51	5,224.2	148.1	-248.4	0.26	-0.15	13.55	23.4	30.4
5,335.0	3.34	226.90	5,319.1	145.7	-250.9	2.64	2.64	-0.64	24.7	44.4
5,430.0	4.61	225.84	5,413.9	141.2	-255.6	1.34	1.34	-1.12	23.6	63.0
5,524.0	8.35	238.41	5,507.3	135.0	-264.2	4.23	3.98	13.37	38.9	76.7



EOG Resources

Final PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #311H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 25' @ 3568.0usft
Site:	Yukon 20 Fed Com	MD Reference:	KB = 25' @ 3568.0usft
Well:	#311H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.14

Survey										
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
5,619.0	11.51	255.90	5,600.8	129.0	-279.2	4.56	3.33	18.41	62.4	80.2
5,714.0	13.54	256.17	5,693.6	124.1	-299.2	2.14	2.14	0.28	61.0	96.2
5,809.0	16.26	255.20	5,785.4	118.0	-322.9	2.88	2.86	-1.02	53.8	113.5
5,904.0	19.03	253.97	5,875.9	110.3	-350.7	2.94	2.92	-1.29	41.4	131.2
5,998.0	18.24	255.90	5,965.0	102.5	-379.7	1.07	-0.84	2.05	33.4	146.9
6,093.0	19.91	260.03	6,054.8	96.1	-410.0	2.26	1.76	4.35	32.3	160.6
6,188.0	21.23	266.10	6,143.7	92.1	-443.1	2.64	1.39	6.39	35.8	171.4
6,283.0	20.35	264.96	6,232.5	89.5	-476.7	1.02	-0.93	-1.20	19.0	185.3
6,378.0	20.74	276.64	6,321.5	90.0	-509.9	4.33	0.41	12.29	43.3	190.8
6,473.0	18.50	283.76	6,411.0	95.5	-541.3	3.44	-2.36	7.49	56.4	192.9
6,567.0	20.00	301.78	6,499.8	107.6	-569.4	6.49	1.60	19.17	104.1	171.1
6,662.0	22.76	314.70	6,588.3	129.1	-596.3	5.73	2.91	13.60	126.4	142.2
6,757.0	22.24	322.96	6,676.1	156.3	-620.2	3.37	-0.55	8.69	130.7	115.5
6,852.0	22.63	322.35	6,763.9	185.2	-642.2	0.48	0.41	-0.64	115.1	106.8
6,947.0	19.64	322.88	6,852.5	212.4	-663.0	3.15	-3.15	0.56	104.3	95.2
7,042.0	15.69	321.82	6,943.0	235.2	-680.6	4.17	-4.16	-1.12	96.7	86.5
7,136.0	14.94	325.07	7,033.7	255.1	-695.4	1.21	-0.80	3.46	98.3	70.7
7,231.0	11.51	330.35	7,126.2	273.4	-707.1	3.82	-3.61	5.56	103.6	49.5
7,326.0	10.33	335.01	7,219.4	289.4	-715.4	1.55	-1.24	4.91	108.0	27.9
7,421.0	10.20	334.48	7,312.9	304.7	-722.6	0.17	-0.14	-0.56	106.9	16.9
7,516.0	7.65	333.69	7,406.8	317.9	-729.0	2.69	-2.68	-0.83	105.7	8.4
7,610.0	6.90	331.31	7,500.0	328.5	-734.5	0.86	-0.80	-2.53	104.6	5.0
7,705.0	5.98	332.89	7,594.4	337.9	-739.5	0.99	-0.97	1.66	102.6	-3.7
7,800.0	3.21	332.19	7,689.1	344.7	-743.0	2.92	-2.92	-0.74	100.9	-6.6
7,894.0	2.77	323.76	7,783.0	348.8	-745.6	0.66	-0.47	-8.97	99.3	6.2
7,989.0	2.42	303.54	7,877.9	351.8	-748.6	1.02	-0.37	-21.28	87.7	39.3
8,084.0	2.02	290.71	7,972.8	353.5	-751.8	0.67	-0.42	-13.51	73.1	57.4



EOG Resources

Final PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #311H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 25' @ 3568.0usft
Site:	Yukon 20 Fed Com	MD Reference:	KB = 25' @ 3568.0usft
Well:	#311H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.14

Survey											
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)	
8,179.0	1.71	280.86	8,067.7	354.4	-754.8	0.47	-0.33	-10.37	59.2	68.7	
8,273.0	1.54	250.72	8,161.7	354.2	-757.4	0.92	-0.18	-32.06	14.2	88.5	
8,368.0	1.67	300.90	8,256.7	354.5	-759.8	1.44	0.14	52.82	74.8	46.7	
8,463.0	1.23	319.62	8,351.7	356.0	-761.6	0.67	-0.46	19.71	83.5	20.7	
8,558.0	0.66	305.12	8,446.6	357.1	-762.7	0.65	-0.60	-15.26	74.2	40.7	
8,653.0	0.92	306.09	8,541.6	357.8	-763.8	0.27	0.27	1.02	73.5	39.4	
8,747.0	1.01	322.79	8,635.6	358.9	-764.9	0.31	0.10	17.77	80.2	16.8	
8,842.0	1.05	314.35	8,730.6	360.2	-766.0	0.16	0.04	-8.88	75.2	28.3	
8,937.0	1.10	320.85	8,825.6	361.5	-767.2	0.14	0.05	6.84	76.1	19.7	
9,032.0	1.05	348.63	8,920.6	363.1	-768.0	0.55	-0.05	29.24	74.9	-17.6	
9,126.0	1.14	9.72	9,014.5	364.9	-768.0	0.44	0.10	22.44	61.8	-43.1	
9,221.0	1.01	29.94	9,109.5	366.5	-767.4	0.42	-0.14	21.28	41.3	-61.4	
9,316.0	1.14	25.89	9,204.5	368.1	-766.6	0.16	0.14	-4.26	43.8	-58.4	
9,411.0	2.46	356.89	9,299.5	371.0	-766.3	1.65	1.39	-30.53	63.8	-30.3	
9,452.0	2.77	357.77	9,340.4	372.8	-766.4	0.76	0.76	2.15	61.4	-31.3	
9,510.0	1.52	19.53	9,398.4	375.0	-766.2	2.53	-2.15	37.52	43.4	-51.3	
KOP, MD:9510.0', TVD:9398.4', N/S:375.0', E/W:-766.2', INC:1.52											
9,522.0	1.32	28.79	9,410.4	375.2	-766.0	2.53	-1.67	77.17	34.3	-57.6	
9,617.0	8.13	177.33	9,505.1	369.5	-765.2	9.77	7.17	156.36	-64.3	32.4	
9,711.0	18.50	183.04	9,596.5	347.9	-765.7	11.11	11.03	6.07	-69.8	45.3	
9,807.0	30.50	201.50	9,683.8	309.8	-775.5	14.69	12.50	19.23	-61.3	72.7	
9,901.0	42.32	210.99	9,759.3	260.3	-800.6	13.90	12.57	10.10	-62.7	81.1	
9,996.0	45.35	210.90	9,827.9	203.9	-834.4	3.19	3.19	-0.09	-70.9	75.9	
10,090.0	46.36	214.24	9,893.3	147.0	-870.8	2.77	1.07	3.55	-61.2	70.9	
10,185.0	52.03	212.13	9,955.4	86.9	-910.0	6.20	5.97	-2.22	-44.1	60.1	
10,280.0	56.51	208.44	10,010.9	20.3	-948.9	5.67	4.72	-3.88	-18.9	53.1	
10,375.0	71.76	205.63	10,052.2	-55.7	-987.5	16.27	16.05	-2.96	5.2	52.1	



EOG Resources

Final PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #311H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 25' @ 3568.0usft
Site:	Yukon 20 Fed Com	MD Reference:	KB = 25' @ 3568.0usft
Well:	#311H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.14

Survey										
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
10,406.0	79.10	204.40	10,060.0	-82.9	-1,000.1	23.99	23.68	-3.97	11.0	53.0
10,491.0	89.43	203.17	10,068.5	-160.2	-1,034.2	12.24	12.15	-1.45	17.0	54.8
10,586.0	88.81	202.11	10,069.9	-247.8	-1,070.8	1.29	-0.65	-1.12	15.3	52.6
10,681.0	88.59	201.15	10,072.1	-336.1	-1,105.8	1.04	-0.23	-1.01	14.3	45.6
10,776.0	89.03	200.88	10,074.1	-424.8	-1,139.8	0.54	0.46	-0.28	13.1	33.1
10,871.0	88.46	198.16	10,076.2	-514.3	-1,171.6	2.92	-0.60	-2.86	11.9	16.8
10,966.0	87.58	196.23	10,079.4	-605.0	-1,199.6	2.23	-0.93	-2.03	11.9	-1.8
11,061.0	86.44	188.93	10,084.4	-697.5	-1,220.3	7.77	-1.20	-7.68	13.8	-18.9
11,155.0	85.61	183.22	10,090.9	-790.7	-1,230.2	6.12	-0.88	-6.07	17.2	-29.4
11,250.0	88.37	180.40	10,095.9	-885.5	-1,233.2	4.15	2.91	-2.97	19.2	-33.0
11,345.0	89.43	177.86	10,097.7	-980.5	-1,231.8	2.90	1.12	-2.67	18.0	-32.2
11,440.0	90.13	176.89	10,098.1	-1,075.4	-1,227.4	1.26	0.74	-1.02	15.2	-28.5
11,535.0	90.22	176.54	10,097.8	-1,170.2	-1,222.0	0.38	0.09	-0.37	11.8	-23.7
11,630.0	90.53	176.10	10,097.2	-1,265.0	-1,215.9	0.57	0.33	-0.46	8.1	-18.2
11,725.0	90.70	177.07	10,096.2	-1,359.9	-1,210.2	1.04	0.18	1.02	4.0	-13.2
11,819.0	88.77	177.68	10,096.6	-1,453.8	-1,205.9	2.15	-2.05	0.65	1.4	-9.6
11,914.0	86.62	179.53	10,100.4	-1,548.6	-1,203.6	2.98	-2.26	1.95	2.1	-7.9
12,009.0	87.06	179.35	10,105.7	-1,643.5	-1,202.7	0.50	0.46	-0.19	4.3	-7.6
12,104.0	86.75	178.65	10,110.8	-1,738.3	-1,201.0	0.80	-0.33	-0.74	6.3	-6.6
12,198.0	86.44	178.12	10,116.4	-1,832.1	-1,198.4	0.65	-0.33	-0.56	8.8	-4.6
12,293.0	86.79	177.77	10,122.0	-1,926.9	-1,195.0	0.52	0.37	-0.37	11.3	-1.8
12,388.0	87.76	177.07	10,126.5	-2,021.7	-1,190.7	1.26	1.02	-0.74	12.6	1.8
12,483.0	88.29	176.98	10,129.8	-2,116.5	-1,185.8	0.57	0.56	-0.09	12.7	6.1
12,578.0	88.29	176.71	10,132.6	-2,211.3	-1,180.5	0.28	0.00	-0.28	12.4	10.7
12,673.0	84.99	176.89	10,138.2	-2,306.0	-1,175.2	3.48	-3.47	0.19	14.7	15.4
12,768.0	87.98	179.53	10,144.0	-2,400.8	-1,172.3	4.19	3.15	2.78	17.4	17.6
12,862.0	88.81	180.23	10,146.6	-2,494.7	-1,172.1	1.15	0.88	0.74	16.9	17.2



EOG Resources

Final PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #311H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 25' @ 3568.0usft
Site:	Yukon 20 Fed Com	MD Reference:	KB = 25' @ 3568.0usft
Well:	#311H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.14

Survey										
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
12,957.0	88.55	179.70	10,148.8	-2,589.7	-1,172.0	0.62	-0.27	-0.56	15.9	16.6
13,052.0	88.02	180.40	10,151.7	-2,684.6	-1,172.1	0.92	-0.56	0.74	15.6	15.9
13,147.0	88.64	180.32	10,154.4	-2,779.6	-1,172.7	0.66	0.65	-0.08	15.1	14.7
13,242.0	88.59	179.70	10,156.7	-2,874.6	-1,172.7	0.65	-0.05	-0.65	14.2	14.0
13,337.0	89.82	181.37	10,158.0	-2,969.6	-1,173.6	2.18	1.29	1.76	12.4	12.5
13,431.0	87.85	180.14	10,160.0	-3,063.5	-1,174.9	2.47	-2.10	-1.31	11.1	10.6
13,526.0	87.45	179.97	10,163.8	-3,158.4	-1,174.9	0.46	-0.42	-0.18	11.9	9.9
13,621.0	86.35	179.09	10,169.0	-3,253.3	-1,174.2	1.48	-1.16	-0.93	13.8	10.0
13,715.0	85.34	178.38	10,175.8	-3,347.0	-1,172.1	1.31	-1.07	-0.76	17.5	11.5
13,810.0	87.89	177.07	10,181.4	-3,441.8	-1,168.3	3.02	2.68	-1.38	20.3	14.6
13,905.0	89.82	177.07	10,183.3	-3,536.6	-1,163.5	2.03	2.03	0.00	19.6	18.8
13,999.0	90.40	178.21	10,183.1	-3,630.5	-1,159.6	1.36	0.62	1.21	16.9	22.1
14,094.0	90.48	180.14	10,182.4	-3,725.5	-1,158.2	2.03	0.08	2.03	13.6	22.8
14,189.0	89.25	180.14	10,182.6	-3,820.5	-1,158.5	1.29	-1.29	0.00	11.2	21.9
14,284.0	87.54	181.11	10,185.3	-3,915.5	-1,159.5	2.07	-1.80	1.02	11.3	20.2
14,378.0	84.90	179.79	10,191.5	-4,009.3	-1,160.2	3.14	-2.81	-1.40	14.9	18.9
14,474.0	88.37	178.56	10,197.1	-4,105.1	-1,158.9	3.83	3.61	-1.28	17.9	19.6
14,569.0	89.74	178.82	10,198.7	-4,200.0	-1,156.7	1.47	1.44	0.27	16.9	21.1
14,664.0	91.10	181.63	10,198.0	-4,295.0	-1,157.1	3.29	1.43	2.96	13.6	20.1
14,758.0	89.12	180.76	10,197.8	-4,389.0	-1,159.0	2.30	-2.11	-0.93	10.9	17.5
14,853.0	92.02	180.49	10,196.9	-4,484.0	-1,160.1	3.07	3.05	-0.28	7.4	15.9
14,948.0	92.29	180.32	10,193.3	-4,578.9	-1,160.7	0.34	0.28	-0.18	1.2	14.5
15,043.0	91.63	180.67	10,190.0	-4,673.8	-1,161.5	0.79	-0.69	0.37	-4.6	13.1
15,138.0	87.19	179.79	10,191.0	-4,768.8	-1,161.9	4.76	-4.67	-0.93	-6.2	12.1
15,233.0	89.65	180.84	10,193.6	-4,863.8	-1,162.5	2.82	2.59	1.11	-6.2	10.9
15,327.0	87.21	181.73	10,196.2	-4,957.7	-1,164.6	2.76	-2.60	0.95	-6.2	8.2
15,422.0	84.62	180.49	10,203.0	-5,052.4	-1,166.4	3.02	-2.73	-1.31	-2.0	5.7



EOG Resources

Final PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #311H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 25' @ 3568.0usft
Site:	Yukon 20 Fed Com	MD Reference:	KB = 25' @ 3568.0usft
Well:	#311H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.14

Survey										
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
15,517.0	85.54	178.21	10,211.1	-5,147.1	-1,165.3	2.58	0.97	-2.40	3.6	6.1
15,612.0	88.88	179.26	10,215.7	-5,241.9	-1,163.2	3.68	3.52	1.11	5.8	7.6
15,707.0	89.27	179.18	10,217.3	-5,336.9	-1,161.9	0.42	0.41	-0.08	5.3	8.2
15,801.0	89.36	179.09	10,218.4	-5,430.9	-1,160.5	0.14	0.10	-0.10	4.4	9.0
15,896.0	89.89	179.44	10,219.0	-5,525.9	-1,159.3	0.67	0.56	0.37	3.0	9.6
15,991.0	90.95	179.53	10,218.3	-5,620.9	-1,158.4	1.12	1.12	0.09	0.2	9.8
16,085.0	92.04	179.88	10,215.9	-5,714.8	-1,158.0	1.22	1.16	0.37	-4.3	9.7
16,180.0	88.48	179.53	10,215.4	-5,809.8	-1,157.5	3.77	-3.75	-0.37	-6.7	9.5
16,275.0	89.05	179.97	10,217.5	-5,904.8	-1,157.1	0.76	0.60	0.46	-6.7	9.3
16,370.0	86.81	179.79	10,220.9	-5,999.7	-1,156.9	2.37	-2.36	-0.19	-5.3	8.9
16,465.0	86.73	179.44	10,226.3	-6,094.6	-1,156.2	0.38	-0.08	-0.37	-2.0	8.9
16,559.0	86.90	179.18	10,231.5	-6,188.4	-1,155.1	0.33	0.18	-0.28	1.1	9.4
16,654.0	88.84	179.44	10,235.0	-6,283.3	-1,153.9	2.06	2.04	0.27	2.6	9.9
16,749.0	88.75	179.18	10,237.0	-6,378.3	-1,152.8	0.29	-0.09	-0.27	2.6	10.4
16,843.0	87.43	178.21	10,240.2	-6,472.2	-1,150.7	1.74	-1.40	-1.03	3.7	11.9
16,938.0	88.57	179.18	10,243.5	-6,567.1	-1,148.5	1.58	1.20	1.02	5.0	13.4
17,033.0	90.02	180.06	10,244.6	-6,662.1	-1,147.9	1.79	1.53	0.93	4.1	13.4
17,127.0	90.42	179.35	10,244.3	-6,756.1	-1,147.4	0.87	0.43	-0.76	1.7	13.2
17,222.0	90.33	178.74	10,243.7	-6,851.1	-1,145.8	0.65	-0.09	-0.64	-1.0	14.2
17,317.0	92.53	179.97	10,241.3	-6,946.1	-1,144.7	2.65	2.32	1.29	-5.4	14.6
17,412.0	92.57	179.53	10,237.1	-7,041.0	-1,144.3	0.46	0.04	-0.46	-11.6	14.4
17,507.0	92.09	178.91	10,233.2	-7,135.9	-1,143.0	0.82	-0.51	-0.65	-17.6	15.1
17,602.0	89.93	180.41	10,231.5	-7,230.9	-1,142.5	2.77	-2.27	1.58	-21.3	15.0
17,697.0	89.41	179.79	10,232.1	-7,325.9	-1,142.6	0.85	-0.55	-0.65	-22.8	14.2
17,791.0	89.45	179.53	10,233.0	-7,419.8	-1,142.1	0.28	0.04	-0.28	-23.9	14.1
17,886.0	87.69	178.30	10,235.4	-7,514.8	-1,140.3	2.26	-1.85	-1.29	-23.6	15.2
17,981.0	90.99	179.97	10,236.5	-7,609.8	-1,138.8	3.89	3.47	1.76	-24.4	16.1



EOG Resources

Final PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #311H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 25' @ 3568.0usft
Site:	Yukon 20 Fed Com	MD Reference:	KB = 25' @ 3568.0usft
Well:	#311H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.14

Survey											
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)	
18,076.0	91.25	179.97	10,234.6	-7,704.7	-1,138.8	0.27	0.27	0.00	-28.2	15.5	
18,171.0	91.03	179.97	10,232.7	-7,799.7	-1,138.7	0.23	-0.23	0.00	-32.0	14.9	
18,266.0	90.20	181.55	10,231.7	-7,894.7	-1,140.0	1.88	-0.87	1.66	-35.0	13.0	
18,361.0	85.58	180.67	10,235.2	-7,989.6	-1,141.8	4.95	-4.86	-0.93	-33.4	10.5	
18,455.0	85.05	180.14	10,242.9	-8,083.3	-1,142.5	0.80	-0.56	-0.56	-27.6	9.2	
18,550.0	84.13	179.97	10,251.8	-8,177.9	-1,142.6	0.98	-0.97	-0.18	-20.6	8.5	
18,645.0	86.73	180.14	10,259.4	-8,272.5	-1,142.7	2.74	2.74	0.18	-15.0	7.8	
18,740.0	89.89	180.41	10,262.2	-8,367.5	-1,143.1	3.34	3.33	0.28	-14.1	6.7	
18,835.0	90.07	180.32	10,262.2	-8,462.5	-1,143.7	0.21	0.19	-0.09	-16.0	5.4	
18,930.0	88.79	179.00	10,263.2	-8,557.5	-1,143.2	1.94	-1.35	-1.39	-17.0	5.4	
19,024.0	88.75	178.74	10,265.2	-8,651.4	-1,141.3	0.28	-0.04	-0.28	-16.9	6.6	
19,120.0	89.36	178.82	10,266.8	-8,747.4	-1,139.3	0.64	0.64	0.08	-17.3	8.0	
19,215.0	88.79	178.12	10,268.3	-8,842.4	-1,136.8	0.95	-0.60	-0.74	-17.7	9.9	
19,310.0	90.68	179.09	10,268.8	-8,937.3	-1,134.4	2.24	1.99	1.02	-19.2	11.6	
19,405.0	90.37	180.32	10,267.9	-9,032.3	-1,134.0	1.34	-0.33	1.29	-22.0	11.4	
19,499.0	86.24	182.96	10,270.7	-9,126.2	-1,136.6	5.21	-4.39	2.81	-21.1	8.1	
19,594.0	90.18	179.79	10,273.6	-9,221.1	-1,138.9	5.32	4.15	-3.34	-20.1	5.2	
19,689.0	88.09	180.85	10,275.1	-9,316.1	-1,139.4	2.47	-2.20	1.12	-20.6	4.0	
19,784.0	87.16	180.58	10,279.0	-9,411.0	-1,140.6	1.02	-0.98	-0.28	-18.6	2.2	
19,879.0	86.55	180.14	10,284.2	-9,505.8	-1,141.2	0.79	-0.64	-0.46	-15.3	1.0	
19,974.0	85.41	179.88	10,290.9	-9,600.6	-1,141.2	1.23	-1.20	-0.27	-10.6	0.3	
20,069.0	87.08	178.65	10,297.1	-9,695.4	-1,140.0	2.18	1.76	-1.29	-6.3	0.9	
20,164.0	86.81	178.30	10,302.2	-9,790.2	-1,137.5	0.46	-0.28	-0.37	-3.2	2.8	
20,258.0	86.51	177.68	10,307.6	-9,884.0	-1,134.2	0.73	-0.32	-0.66	0.4	5.5	
20,284.0	86.37	177.51	10,309.3	-9,909.9	-1,133.1	0.85	-0.54	-0.65	1.5	6.4	
Final MWD Survey (MD=20284.0')											



EOG Resources

Final PVA

Company:	EOG Resources - Midland	Local Co-ordinate Reference:	Well #311H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 25' @ 3568.0usft
Site:	Yukon 20 Fed Com	MD Reference:	KB = 25' @ 3568.0usft
Well:	#311H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.14

Survey										
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)
20,342.0	86.37	177.51	10,312.9	-9,967.8	-1,130.6	0.00	0.00	0.00	4.0	8.5
Final Projection to Bit (MD=20342.0')										

Design Annotations				
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
9,510.0	9,398.4	375.0	-766.2	KOP, MD:9510.0', TVD:9398.4', N/S:375.0', E/W:-766.2', INC:1.52
20,284.0	10,309.3	-9,909.9	-1,133.1	Final MWD Survey (MD=20284.0')
20,342.0	10,312.9	-9,967.8	-1,130.6	Final Projection to Bit (MD=20342.0')

Checked By: _____ Approved By: _____ Date: _____

I CERTIFY THIS SURVEY TO BE TRUE AND CORRECT TO THE BEST OF MY BELIEF AND KNOWLEDGE
KAY MADDOX 09/21/2021

Intent ☐ As Drilled ☐

API #		
Operator Name:	Property Name:	Well Number

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
Latitude					Longitude				NAD

First Take Point (FTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
Latitude					Longitude				NAD

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
Latitude					Longitude				NAD

Is this well the defining well for the Horizontal Spacing Unit? ☐Is this well an infill well? ☐

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name:	Property Name:	Well Number

KZ 06/29/2018

Submit To Appropriate District Office Two Copies <u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 <u>District II</u> 811 S. First St., Artesia, NM 88210 <u>District III</u> 1000 Rio Brazos Rd., Aztec, NM 87410 <u>District IV</u> 1220 S. St. Francis Dr., Santa Fe, NM 87505		State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505			Form C-105 Revised August 1, 2011					
WELL COMPLETION OR RECOMPLETION REPORT AND LOG								1. WELL API NO. 30-025-47187		
4. Reason for filing: ☒ COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) ☐ C-144 CLOSURE ATTACHMENT (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)								5. Lease Name or Unit Agreement Name YUKON 20 FED COM		
								6. Well Number: 311H		
7. Type of Completion: ☒ NEW WELL ☐ WORKOVER ☐ DEEPENING ☐ PLUGBACK ☐ DIFFERENT RESERVOIR ☐ OTHER _____										
8. Name of Operator EOG RESOURCES INC						9. OGRID 7377				
10. Address of Operator PO BOX 2267 MIDLAND, TEXAS 79702						11. Pool name or Wildcat RED HILLS; BONE SPRING, NORTH				
12. Location	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County
Surface:	C	20	24S	34E		492	NORTH	1537	WEST	LEA
BH:	M	29	24S	34E		110	SOUTH	338	WEST	LEA
13. Date Spudded 03/02/2021	14. Date T.D. Reached 03/28/2021		15. Date Rig Released 03/30/2021			16. Date Completed (Ready to Produce) 09/17/2021		17. Elevations (DF and RKB, RT, GR, etc.) 3543'		
18. Total Measured Depth of Well MD 20,342' TVD 10,312'			19. Plug Back Measured Depth MD 20,319' TVD 10,312'			20. Was Directional Survey Made? YES		21. Type Electric and Other Logs Run None		
22. Producing Interval(s), of this completion - Top, Bottom, Name BONE SPRING 10,302 - 20,319'										
23. CASING RECORD (Report all strings set in well)										
CASING SIZE		WEIGHT LB./FT.		DEPTH SET		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED
13 3/8"		54.5# J-55		1348'		16"		1255 CL C/CIRC		
12 1/4"		40# J-55		5184'		12 1/4"		1475 CL C/CIRC		
5 1/2"		20# HCP 110		20,327'		8 1/2"		2840 CL H TOC 5656' CBL		
24. LINER RECORD						25. TUBING RECORD				
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN		SIZE	DEPTH SET	PACKER SET		
26. Perforation record (interval, size, and number) 10,302 - 20,319' 3 1/8", 1980 holes						27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC.				
						DEPTH INTERVAL		AMOUNT AND KIND MATERIAL USED		
						10,302 -20,319'		FRAC W/24,693,341 lbs proppant, 435,949 bbls load fld		
28. PRODUCTION										
Date First Production 09/17/2021		Production Method (<i>Flowing, gas lift, pumping - Size and type pump</i>) Flowing				Well Status (<i>Prod. or Shut-in</i>) Producing				
Date of Test 10/03/2021	Hours Tested 24	Choke Size 94	Prod'n For Test Period	Oil - Bbl 3923	Gas - MCF 4856	Water - Bbl. 8117	Gas - Oil Ratio 1238			
Flow Tubing Press.	Casing Pressure 796	Calculated 24-Hour Rate	Oil - Bbl.	Gas - MCF	Water - Bbl.	Oil Gravity - API - (<i>Corr.</i>) 41				
29. Disposition of Gas (<i>Sold, used for fuel, vented, etc.</i>) SOLD								30. Test Witnessed By		
31. List Attachments C-102, C-104, C-103, Directional Survey, H spacing										
32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.										
33. If an on-site burial was used at the well, report the exact location of the on-site burial:										
Latitude _____ Longitude _____ NAD 1927 1983										
I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief Printed Signature Kay Maddox E-mail Address kay_maddox@eogresources.com Name Kay Maddox Title Senior Regulatory Specialist Date 10/05/2021										

This form is to be filed with the appropriate District Office of the Division not later than 20 days after the completion of any newly-drilled or deepened well and not later than 60 days after completion of closure. When submitted as a completion report, this shall be accompanied by one copy of all electrical and radio-activity logs run on the well and a summary of all special tests conducted, including drill stem tests. All depths reported shall be measured depths. In the case of directionally drilled wells, true vertical depths shall also be reported. For multiple completions, items 11, 12 and 26-31 shall be reported for each zone.

Southeastern New Mexico			Northwestern New Mexico				
T. Anhy	Rustler	1185'	T. Canyon	Brushy	7549'	T. Ojo Alamo	T. Penn A "
T. Salt		1744'	T. Strawn			T. Kirtland	T. Penn. "B"
B. Salt		5036'	T. Atoka			T. Fruitland	T. Penn. "C"
T. Yates			T. Miss			T. Pictured Cliffs	T. Penn. "D"
T. 7 Rivers			T. Devonian			T. Cliff House	T. Leadville
T. Queen			T. Silurian			T. Menefee	T. Madison
T. Grayburg			T. Montoya			T. Point Lookout	T. Elbert
T. San Andres			T. Simpson			T. Mancos	T. McCracken
T. Glorieta			T. McKee			T. Gallup	T. Ignacio Otzte
T. Paddock			T. Ellenburger			Base Greenhorn	T. Granite
T. Blinebry			T. Gr. Wash			T. Dakota	
T. Tubb			T. Delaware Sand			T. Morrison	
T. Drinkard			T. Bone Springs			T. Todilto	
T. Abo			T. 1st BS Sand	10,014'		T. Entrada	
T. Wolfcamp			T.			T. Wingate	
T. Penn			T.			T. Chinle	
T. Cisco (Bough C)			T.			T. Permian	

No. 1, from.....to.....
No. 2, from.....to.....
No. 3, from.....to.....
No. 4, from.....to.....

Include data on rate of water inflow and elevation to which water rose in hole.

No. 1, from.....to.....feet.....
 No. 2, from.....to.....feet.....
 No. 3, from.....to.....feet.....

From	To	Thickness In Feet	Lithology

From	To	Thickness In Feet	Lithology

District I

1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720

District II

811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720

District III

1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170

District IV

1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 54321

ACKNOWLEDGMENTS

Operator: EOG RESOURCES INC P.O. Box 2267 Midland, TX 79702	OGRID: 7377
	Action Number: 54321
	Action Type: [C-104] Completion Packet (C-104C)

ACKNOWLEDGMENTS

☒	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
☒	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 54321

CONDITIONS

Operator: EOG RESOURCES INC P.O. Box 2267 Midland, TX 79702	OGRID: 7377
	Action Number: 54321
	Action Type: [C-104] Completion Packet (C-104C)

CONDITIONS

Created By	Condition	Condition Date
plmartinez	File 3160-4 Completion Report within 10 days to NMOCD after BLM approval.	3/21/2022