Form 3160-3 FORM APPROVED OMB No. 1004-0137 (June 2015) Expires: January 31, 2018 **UNITED STATES** DEPARTMENT OF THE INTERIOR 5. Lease Serial No. BUREAU OF LAND MANAGEMENT APPLICATION FOR PERMIT TO DRILL OR REENTER 6. If Indian, Allotee or Tribe Name 7. If Unit or CA Agreement, Name and No. DRILL REENTER 1a. Type of work: 1b. Type of Well: Oil Well Gas Well Other 8. Lease Name and Well No. 1c. Type of Completion: Hydraulic Fracturing Single Zone Multiple Zone 2. Name of Operator 9. API Well No. 30-025-52503 3a. Address 3b. Phone No. (include area code) 10. Field and Pool, or Exploratory 4. Location of Well (Report location clearly and in accordance with any State requirements.*) 11. Sec., T. R. M. or Blk. and Survey or Area At surface At proposed prod. zone 14. Distance in miles and direction from nearest town or post office* 12. County or Parish 13. State 15. Distance from proposed* 16. No of acres in lease 17. Spacing Unit dedicated to this well location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 18. Distance from proposed location* 19. Proposed Depth 20. BLM/BIA Bond No. in file to nearest well, drilling, completed, applied for, on this lease, ft. 21. Elevations (Show whether DF, KDB, RT, GL, etc.) 22. Approximate date work will start* 23. Estimated duration 24. Attachments The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable) 1. Well plat certified by a registered surveyor. 4. Bond to cover the operations unless covered by an existing bond on file (see 2. A Drilling Plan. Item 20 above). 3. A Surface Use Plan (if the location is on National Forest System Lands, the 5. Operator certification. SUPO must be filed with the appropriate Forest Service Office). 6. Such other site specific information and/or plans as may be requested by the 25. Signature Name (Printed/Typed) Date Title Approved by (Signature) Name (Printed/Typed) Date Title Office Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction



(Continued on page 2)

*(Instructions on page 2)

Received by OCD: 1/29/2024 9:52:55 AM

<u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 Phone: (575) 393-6161 Fax: (575) 393-0720 District II 811 S. First St., Artesia, NM 88210

Phone: (575) 748-1283 Fax: (575) 748-9720 District III 1000 Rio Brazos Road, Aztec, NM 87410 Phone: (505) 334-6178 Fax: (505) 334-6170

District IV 1220 S. St. Francis Dr., Santa Fe, NM 87505 Phone: (505) 476-3460 Fax: (505) 476-3462

UL or lot no. Section Township Range

State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION 1220 South St. Francis Dr. Santa Fe, NM 87505

Form C-102 Revised August 1, 2011 Submit one copy to appropriate District Office

X AMENDED REPORT

County

Released to Imaging: 2/6/2024 11:16:34 AM

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-52503	•	² Pool Code 50461	IG, SOUTH			
⁴ Property Code 335232			operty Name OOSEY 4-9 FED COM	⁶ Well Number 303H		
⁷ OGRID No. 215099		⁸ O _F CIMARE	⁹ Elevation 3659.9'			

¹⁰ Surface Location

ı	О	33	19S	34Ĕ		194	SOUTH	1448	EAST	LEA	
_				11	Bottom H	ole Location I	f Different From	Surface			

North/South line

Feet from the


East/West line

UL or lot no. Township Lot Idn Feet from the Feet from the SOUTH 20S 34E 100 1744 **EAST** LEA Joint or Infil 14 Consolidation 15 Order No

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

Feet from the

Lot Idn



State of New Mexico Energy, Minerals and Natural Resources Department

Submit Electronically Via E-permitting

Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description Effective May 25, 2021

1. Operator: _	Cimarex En	ergy Company		_ OGRID: _2	15099	Date: _	1/29/24
II. Тўрё: ⊠ (Original	□ Amendmer	nt due to □ 19.15.27	.9.D(6)(a) NMA	AC □ 19.15.27.9.D	(6)(b) NMAC □	Other.
If Other, please	describe	:					
			nformation for each ad or connected to a			wells proposed t	o be drilled or proposed
Well Nam	ne	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
Loosey Goosey 4-9 I	Fed Com 3	03H	O, Sec 33 T19S, R34E	194 FSL/ 1448	FEL 1589	1455	2845
i							
	e recom		e following informa single well pad or c	TD Reached Date	Completion Commencement	t. Initial F Date Back D	Date Date
Loosey Goosey 4-9 l	Fed Com 3	03H	11/10/2024	1/14/2025	1/20/2025	3/1/202:	5 3/1/2025
VII. Operation Subsection A th	al Pract	ices: ☑ Attac of 19.15.27.8 t Practices: □	ch a complete descr NMAC.	iption of the ac	tions Operator will	take to comply	t to optimize gas capture. with the requirements of ices to minimize venting

Section 2 – Enhanced Plan

			E APRIL 1, 2022		
Beginning April 1, 2 reporting area must c			with its statewide natural g	s capture requirement for	the applicable
Operator certifies capture requirement	-	-	tion because Operator is in	ompliance with its statew	ide natural gas
IX. Anticipated Nat	ural Gas Producti	on:			
We	11	API	Anticipated Average Natural Gas Rate MCF/E	Anticipated Volum Gas for the First	
X. Natural Gas Gat	hering System (NC	GGS):			
Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Da of System Segment	
production operations the segment or portion XII. Line Capacity. production volume fr	s to the existing or point of the natural gas. The natural gas gas from the well prior to	blanned interconnect of the gathering system will the the date of first product		em(s), and the maximum danceted. ather 100% of the anticipa	aily capacity of
			at its existing well(s) connect meet anticipated increases in		
☐ Attach Operator's	plan to manage pro	oduction in response to the	ne increased line pressure.		
Section 2 as provided	l in Paragraph (2) o		uant to Section 71-2-8 NMS 27.9 NMAC, and attaches a f ion.		

Section 3 - Certifications <u>Effective May 25, 2021</u>

Operator certifies that, after reasonable inquiry and based on the available information at the time of sublintial.
© Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or
□ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system. <i>If Operator checks this box, Operator will select one of the following:</i>
Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or
Venting and Flaring Plan. □ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- power generation on lease; (a)
- power generation for grid; (b)
- (c) compression on lease;
- (d) liquids removal on lease;
- reinjection for underground storage; (e)
- **(f)** reinjection for temporary storage;
- **(g)** reinjection for enhanced oil recovery;
- fuel cell production; and (h)
- other alternative beneficial uses approved by the division. (i)

Section 4 - Notices

- 1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:
- Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become (a) unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or
- Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.
- 2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

From State of New Mexico, Natural Gas Management Plan

VI. Separation Equipment: Attach a complete description of how Operator will size separation equipment to optimize gas capture.

XEC Standard Response

Standard facility gas process flow begins at the inlet separator. These vessels are designed based off of forecasted rates and residence times in accordance with, and often greater than, API 12J. The separated gas is then routed to an additional separation vessel (ie sales scrubber) in order to extract liquids that may have carried over or developed due to the decrease in pressure. The sales scrubber is sized based on API 521. From the sales scrubber, the gas leaves the facility and enters the gas midstream gathering network.

Cimarex

VII. Operational Practices

Cimarex values the sustainable development of New Mexico's natural resources. Venting and flaring of natural gas is a source of waste in the industry, and Cimarex will ensure that its values are aligned with those of NMOCD. As such, Cimarex plans to take pointed steps to ensure compliance with Subsection A through F of 19.15.27.8 NMAC.

Specifically, below are the steps Cimarex will plan to follow under routine well commissioning and operations.

- 1. Capture or combust natural gas during drilling operations where technically feasible, using the best industry practices and control technologies.
 - a. All flares during these operations will be a minimum of 100ft away from the nearest surface-hole location.
- 2. All gas present during post-completion drill-out and flow back will be routed through separation equipment, and, if technically feasible, flare unsellable vapors rather than vent. Lastly, formal sales separator commissioning to process well-stream fluids and send gas to a gas flow line/collection system or use the gas for on-site fuel or beneficial usage, gas as soon as is safe and technically feasible.
- 3. Cimarex will ensure the flare or combustion equipment is properly sized to handle expected flow rates, ensure this equipment is equipped with an automatic or continuous ignition source, and ensure this equipment is designed for proper combustion efficiency.
- 4. If Cimarex must flare because gas is not meeting pipeline specifications, Cimarex will limit flaring to <60 days, analyze gas composition at least twice per week, and route gas into a gathering pipeline as soon as pipeline specifications are met.
- 5. Under routine production operations, Cimarex will not flare/vent unless:
 - a. Venting or flaring occurs due to an emergency or equipment malfunction.
 - b. Venting or flaring occurs as a result of unloading practices, and an operator is onsite (or within 30 minutes of drive time and posts contact information at the wellsite) until the end of unloading practice.
 - c. The venting or flaring occurs during automated plungerlift operations, in which case the Cimarex operator will work to optimize the plungerlift system to minimize venting/flaring.
 - d. The venting or flaring occurs during downhole well maintenance, in which case Cimarex will work to minimize venting or flaring operations to the extent that it does not pose a risk to safe operations.
 - e. The well is an exploratory well, the division has approved the well as an exploratory well, venting or flaring is limited to 12 months, as approved by the division, and venting/flaring does not cause Cimarex to breach its State-wide 98% gas capture requirement.
 - f. Venting or flaring occurs because the stock tanks or other low-pressure vessels are being gauged, sampled, or liquids are being loaded out.
 - g. The venting or flaring occurs because pressurized vessels are being maintained and are being blown-down or depressurized.
 - h. Venting or flaring occurs as a result of normal dehydration unit operations.

- i. Venting or flaring occurs as a result of bradenhead testing.
- j. Venting or flaring occurs as a result of normal compressor operations, including general compressor operations, compressor engines and turbines.
- k. Venting or flaring occurs as a result of a packer leakage test.
- l. Venting or flaring occurs as a result of a production test lasting less than 24 hours unless otherwise approved by the division.
- m. Venting or flaring occurs as a result of new equipment commissioning and is necessary to purge impurities from the pipeline or production equipment.
- 6. Cimarex will maintain its equipment in accordance with its Operations and Maintenance Program, to ensure venting or flaring events are minimized and that equipment is properly functioning.
- 7. Cimarex will install automatic tank gauging equipment on all production facilities constructed after May 25, 2021, to ensure minimal emissions from tank gauging practices.
- 8. By November 25, 2022, all Cimarex facilities equipped with flares or combustors will be equipped with continuous pilots or automatic igniters, and technology to ensure proper function, i.e. thermocouple, fire-eye, etc...
- 9. Cimarex will perform AVO (audio, visual, olfactory) facility inspections in accordance with NMOCD requirements. Specifically, Cimarex will:
 - a. Perform weekly inspections during the first year of production, and so long as production is greater than 60 MCFD.
 - b. If production is less than 60 MCFD, Cimarex will perform weekly AVO inspections when an operator is present on location, and inspections at least once per calendar month with at least 20 calendar days between inspections.
- 10. Cimarex will measure or estimate the volume of vented, flared or beneficially used natural gas, regardless of the reason or authorization for such venting or flaring.
- 11. On all facilities constructed after May 25, 2021, Cimarex will install metering where feasible and in accordance with available technology and best engineering practices, in an effort to measure how much gas could have been vented or flared.
 - a. In areas where metering is not technically feasible, such as low-pressure/low volume venting or flaring applications, engineering estimates will be used such that the methodology could be independently verified.
- 12. Cimarex will fulfill the division's requirements for reporting and filing of venting or flaring that exceeds 50 MCF in volume or last eight hours or more cumulatively within any 24-hour period.

VIII. Best Management Practices to minimize venting during active and planned maintenance

Cimarex strives to ensure minimal venting occurs during active and planned maintenance activities. Below is a description of common maintenance practices, and the steps Cimarex takes to limit venting exposure.

• Workovers:

- o Always strive to kill well when performing downhole maintenance.
- o If vapors or trapped pressure is present and must be relieved then:
 - Initial blowdown to production facility:
 - Route vapors to LP flare if possible/applicable
 - Blowdown to portable gas buster tank:
 - Vent to existing or portable flare if applicable.

• Stock tank servicing:

- o Minimize time spent with thief hatches open.
- When cleaning or servicing via manway, suck tank bottoms to ensure minimal volatiles exposed to atmosphere.
 - Connect vacuum truck to low pressure flare while cleaning bottoms to limit venting.
- o Isolate the vent lines and overflows on the tank being serviced from other tanks.

• Pressure vessel/compressor servicing and associated blowdowns:

- o Route to flare where possible.
- o Blow vessel down to minimum available pressure via pipeline, prior to venting vessel.
- Preemptively changing anodes to reduce failures and extended corrosion related servicing.
- When cleaning or servicing via manway, suck vessel bottoms to ensure minimal volatiles exposed to atmosphere.

• Flare/combustor maintenance:

- Minimize downtime by coordinating with vendor and Cimarex staff travel logistics.
- Utilizing preventative and predictive maintenance programs to replace high wear components before failure.
- Because the flare/combustor is the primary equipment used to limit venting practices, ensure flare/combustor is properly maintained and fully operational at all times via routine maintenance, temperature telemetry, onsite visual inspections.

The Cimarex expectation is to limit all venting exposure. Equipment that may not be listed on this document is still expected to be maintained and associated venting during such maintenance minimized.

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Cimarex
LEASE NO.:	NMLC065607
LOCATION:	Section 33, T. 19 S, R.34 E., NMPM
COUNTY:	Lea County, New Mexico
WELL NAME & NO.:	Loosey Goosey 4-9 Fed Com 303H
SURFACE HOLE FOOTAGE:	194'/S & 1448'/E
BOTTOM HOLE FOOTAGE:	100'/S & 1744'/E

COA

H ₂ S	Yes	O No		
Potash / WIPP	None	Secretary	C R-111-P	□ WIPP
Cave / Karst	• Low	C Medium	C High	Critical
Wellhead	Conventional	Multibowl	O Both	Diverter
Cementing	☐ Primary Squeeze	☐ Cont. Squeeze	☐ EchoMeter	□ DV Tool
Special Req	☐ Break Testing	☐ Water Disposal	▼ COM	□ Unit
Variance	▼ Flex Hose	☐ Casing Clearance	☐ Pilot Hole	Capitan Reef
Variance	☐ Four-String	Offline Cementing	▼ Fluid-Filled	☐ Open Annulus
		Batch APD / Sundry		

A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Delaware Group and Morrow** formation. As a result, the Hydrogen Sulfide area must meet all requirements from 43 CFR 3176, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING

Surface and Intermediate casings must be kept fluid filled to meet BLM minimum collapse requirement.

- 1. The 13-3/8 inch surface casing shall be set at approximately 1820 feet (a minimum of 25 feet (Lea County) into the Rustler Anhydrite, above the salt, and below usable fresh water) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8** hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing shall be set at 5600ft:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above. **Excess calculates to 12%. Additional cement maybe required.**

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst, and Capitan Reef.

- ❖ In <u>Capitan Reef Areas</u> if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
- ❖ Special Capitan Reef requirements. If lost circulation (50% or greater) occurs below the Base of the Salt, the operator shall do the following: (Use this for 3 string wells in the Capitan Reef, if 4 string well ensure FW based mud used across the Capitan interval)
 - Switch to fresh water mud to protect the Capitan Reef and use fresh water mud until setting the intermediate casing. The appropriate BLM office is to be notified for a PET to witness the switch to fresh water.
 - Daily drilling reports from the Base of the Salt to the setting of the intermediate casing are to be submitted to the BLM CFO engineering staff via e-mail by 0800 hours each morning. Any lost circulation encountered is to be recorded on these drilling reports. The daily drilling report should show mud volume per shift/tour. Failure to submit these reports will result in an Incidence of Non-Compliance being issued for failure to comply with the Conditions of Approval. If not already planned, the operator shall run a caliper survey for the intermediate well bore and submit to the appropriate BLM office.
- 3. The minimum required fill of cement behind the 7 inch production casing is:
 - Cement should tie-back at least **50 feet(4950ft)** on top of Capitan Reef top. If cement does not circulate see B.1.a, c-d above.

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst, and Capitan Reef.

- 4. The minimum required fill of cement behind the **4-1/2** inch production liner is:
 - Cement should tie-back 100 feet into the previous casing. Operator shall provide method of verification. Excess calculates to 11%. Additional cement maybe required.

C. PRESSURE CONTROL

- 1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
- 2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the casing shoe shall be **5000** (**5M**) psi. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - a. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - b. Manufacturer representative shall install the test plug for the initial BOP test.
 - c. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - d. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172 must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- The operator will submit an as-drilled survey well plat of the well completion, but are not limited to, those specified in 43 CFR 3171 and 3172.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

Offline Cementing

Contact the BLM prior to the commencement of any offline cementing procedure.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)
 - Eddy County
 Email or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, BLM_NM_CFO_DrillingNotifications@BLM.GOV (575) 361-2822
 - Lea County
 Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 689-5981
- 1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per **43 CFR part 3170 Subpart 3172** as soon as 2nd Rig is rigged up on well.
- 2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
- 3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a

digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

- 1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
- 2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing intergrity test can be done (prior to the cement setting up) immediately after bumping the plug.
- 3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
- 4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
- 5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
- 6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
- 7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

- 8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.
- B. PRESSURE CONTROL
- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in 43 CFR part 3170 Subpart 3172 and API STD 53 Sec. 5.3.
- 2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
- 3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
- 4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR part 3170 Subpart 3172 must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- 5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after

installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR part 3170 Subpart 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR**

part 3170 Subpart 3172.

C. **DRILLING MUD**

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

ZS 9/14/2023



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

NAME: AMITHY CRAWFORD

Operator Certification Data Report

Signed on: 03/15/2022

Operator

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

		•
Title: Regulatory Analyst		
Street Address: 600 N M	ARIENFELD STE 600	
City: MIDLAND	State: TX	Zip: 79701
Phone: (432)620-1909		
Email address: AMITHY.	CRAWFORD@COTERRA.COM	
Field		
Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		



U.S. Department of the Interior

Application Data

BUREAU OF LAND MANAGEMENT

APD ID: 10400083867 Submission Date: 03/17/2022

Operator Name: CIMAREX ENERGY COMPANY

Well Name: LOOSEY GOOSEY 4-9 FED COM

Well Type: OIL WELL

Well Number: 303H

Well Work Type: Drill

Highlighted data reflects the most recent changes **Show Final Text**

Section 1 - General

APD ID: 10400083867 Tie to previous NOS? N Submission Date: 03/17/2022

BLM Office: Carlsbad **User: AMITHY CRAWFORD** Title: Regulatory Analyst

Federal/Indian APD: FED Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMLC065607 Lease Acres:

Allotted? Reservation: Surface access agreement in place?

Agreement in place? NO Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? Y

Permitting Agent? NO APD Operator: CIMAREX ENERGY COMPANY

Operator letter of

Operator Info

Operator Organization Name: CIMAREX ENERGY COMPANY

Operator Address: 6001 DEAUVILLE BLVD STE 300N

Operator PO Box:

Operator City: MIDLAND State: TX

Operator Phone: (303)295-3995

Operator Internet Address: hknauls@cimarex.com

Section 2 - Well Information

Well in Master Development Plan? NO **Master Development Plan name:**

Well in Master SUPO? NO Master SUPO name:

Well in Master Drilling Plan? NO Master Drilling Plan name:

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H Well API Number:

Field/Pool or Exploratory? Field and Pool Field Name: QUAIL RIDGE Pool Name: [50460] BONE

SPRING

Zip: 79706

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Is the proposed well in an area containing other mineral resources? USEABLE WATER, NATURAL GAS, OIL

Is the proposed well in a Helium production area? N Use Existing Well Pad? N New surface disturbance?

Type of Well Pad: MULTIPLE WELL Multiple Well Pad Name: Loosey Number: W2E2

Well Class: HORIZONTAL Goosey 4-9 Fed Com
Number of Legs: 1

Well Work Type: Drill
Well Type: OIL WELL
Describe Well Type:
Well sub-Type: INFILL

Describe sub-type:

Distance to town: 26 Miles Distance to nearest well: 20 FT Distance to lease line: 194 FT

Reservoir well spacing assigned acres Measurement: 321 Acres

Well plat: Loosey_Goosey_4_9_Fed_Com_303H_C102_20230814_20230814144110.pdf

Well work start Date: 10/31/2022 Duration: 30 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83 Vertical Datum: NAVD88

Survey number: Reference Datum: GROUND LEVEL

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	DVT	Will this well produce from this
SHL	194	FSL	144 8	FEL	19S	34E	33	Aliquot	32.60999 4	- 103.5613	LEA	1	NEW MEXI	F	NMNM 94622	365 9	0	0	N
Leg #1			0					SWSE	7	08		CO	CO		34022	9			
KOP	194	FSL	144	FEL	19S	34E	33	Aliquot	32.60999		LEA	1		F	NMNM	-	102	102	N
Leg			8					SWSE	4	103.5613 08		MEXI	MEXI		94622	657 8	58	37	
#1										00									
PPP	100	FNL	174	FEL	20S	34E	4	Aliquot	32.60918		LEA	l .	114-44	F	NMLC0	-	113	108	Υ
Leg			4					NWNE	2	103.5622		1	MEXI		65607	717	08	30	
#1-1										69		СО	СО			1			

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
PPP Leg #1-2	264 9	FNL	174 7	FEL	20S	34E		Aliquot NWSE	32.60205 3	- 103.5617 91	LEA	1	NEW MEXI CO	F	NMLC0 64194	- 717 1	131 36	108 30	Y
EXIT Leg #1	100	FSL	174 4	FEL	20\$	34E		Aliquot SWSE	32.58065 6	- 103.5623 22	LEA	NEW MEXI CO	NEW MEXI CO	F	NMLC0 64194		209 66	108 30	Y
BHL Leg #1	100	FSL	174 4	FEL	20S	34E	_	Aliquot SWSE	32.58065 6	- 103.5623 22	LEA		NEW MEXI CO	F	NMLC0 64194	- 717 1	209 66	108 30	Y

Intent	:	As Drill	led											
API#]											
Oper	rator Nar	ne:	<u>I</u>			Prop	perty N	Name:						Well Number
Kick C	Off Point ((KOP)												,
UL	Section	Township	Range	Lot	Feet		From I	N/S	Feet		From	n E/W	County	
Latitu	de		<u> </u>		Longitu	ude	<u> </u>						NAD	
First T	Take Poin	nt (FTP)												
UL	Section	Township	Range	Lot	Feet		From I	N/S	Feet		From	n E/W	County	
Latitu	de				Longitu	abu							NAD	
Last T	ake Poin	t (LTP)												
UL	Section	Township	Range	Lot	Feet	Fron	m N/S	Feet		From E	/W	Count	:y	
Latitu	de	<u> </u>	<u> </u>		Longitu	Longitude NAD								
		e defining winfill well?		he Hori	izontal Sp	pacin	g Unit?	?						
	ng Unit.	lease provi	ide API if	i availa	ble, Opei	rator	Name	and w	/ell ni	umber	for [Definir	ng well fo	r Horizontal
Oper	rator Nar	me:				Prop	perty l	Name:						Well Number
Estima	ated Forr	mation Top)S											<u> </u>
Forma	ation:				Тор:		Fo	rmation	า:					Тор:
							1							
					+									
							+							



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report 01/25/2024

APD ID: 10400083867 Submission Date: 03/17/2022

Operator Name: CIMAREX ENERGY COMPANY

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Show Final Text Well Type: OIL WELL Well Work Type: Drill

Highlighted data reflects the most recent changes

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
12144279	RUSTLER	0	1543	1543	ANHYDRITE, SANDSTONE	USEABLE WATER	N
12144280	TOP SALT	-1632	1632	1632	ANHYDRITE	NONE	N
12144281	BASE OF SALT	-3225	3225	3225	ANHYDRITE	NONE	N
12144282	LAMAR	-5214	5214	5214	SANDSTONE	NONE	N
12144283	BELL CANYON	-5286	5286	5286	SANDSTONE	NONE	N
12144284	CHERRY CANYON	-5740	5740	5740	SANDSTONE	NONE	N
12144285	BRUSHY CANYON	-6672	6672	6672	SANDSTONE	NATURAL GAS, OIL	N
12144286	BONE SPRING	-8200	8200	8200	LIMESTONE	NATURAL GAS, OIL	N
12144287	BONE SPRING 1ST	-9376	9376	9376	SHALE	NATURAL GAS, OIL	N
12144288	BONE SPRING 2ND	-9928	9928	9928	SANDSTONE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 2M Rating Depth: 5236

Equipment: A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

Requesting Variance? YES

Variance request: Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only.

Testing Procedure: A multi-bowl wellhead system will be utilized. After running the 13 3/8" surface casing, a 13 3/8" BOP/BOPE system with a minimum working pressure of 2000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 2000 psi test. Annular will be tested to 100%

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendors representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder, monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 2000 psi. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing strings utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Choke Diagram Attachment:

Loosey_Goosey_4_9_Fed_Com_303H_Choke_2M_3M_20220315131822.pdf

BOP Diagram Attachment:

Loosey_Goosey_4_9_Fed_Com_303H_BOP_2M_20220315131832.pdf

Pressure Rating (PSI): 3M Rating Depth: 11009

Equipment: A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

Requesting Variance? YES

Variance request: Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only.

Testing Procedure: A multi-bowl wellhead system will be utilized. After running the 13 3/8" surface casing, a 13 3/8 BOP/BOPE system with a minimum working pressure of 3000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 3000 psi test. Annular will be tested to 100% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendors representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder, monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 3000 psi. Slips will be utilized after running and cementing the production casing. After installation of the slips and wellhead on the production casing, a 13 5/8 BOP/BOPE system with a minimum working pressure of 3000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 3000 psi test. Annular will be tested to 100% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing string utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Choke Diagram Attachment:

Loosey Goosey 4 9 Fed Com 303H Choke 2M 3M 20220315131854.pdf

BOP Diagram Attachment:

Loosey Goosey 4 9 Fed Com 303H BOP 3M 20220315131903.pdf

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Pressure Rating (PSI): 5M Rating Depth: 20966

Equipment: A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

Requesting Variance? YES

Variance request: Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only.

Testing Procedure: A multi-bowl wellhead system will be utilized. After running the 13 3/8" surface casing, a 13 3/8 BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to 100% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendors representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder, monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi. Slips will be utilized after running and cementing the production casing. After installation of the slips and wellhead on the production casing, a 13 5/8 BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to 100% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing string utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Choke Diagram Attachment:

Loosey_Goosey_4_9_Fed_Com_303H_Choke_5M_20220315131928.pdf

BOP Diagram Attachment:

Loosey_Goosey_4_9_Fed_Com_303H_BOP_5M_20220315131936.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	1593	0	1593	3659	2066	1593	H-40	48	ST&C	1.12	2.51	BUOY	4.21	BUOY	4.21
- 1	INTERMED IATE	12.2 5	9.625	NEW	API	N	0	5236	0	5236	3750	-1577	5236	HCK -55	40	LT&C	1.36	1.41	BUOY	2.68	BUOY	2.68
3	PRODUCTI ON	8.75	7.0	NEW	API	N	0	10258	0	10258	3750	-6599	10258	L-80	29	LT&C	1.46	1.7	BUOY	1.88	BUOY	1.88

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
4	PRODUCTI ON	8.75	7.0	NEW	API	N	10258	11009	10258	10791	-6599	-7132	751	P- 110	29	BUTT	1.69	2.22	BUOY	60.1	BUOY	60.1
5	COMPLETI ON SYSTEM	6	4.5	NEW	API	N	9258	20966	9258	10830	-5599	-7171	11708	P- 110	11.6	BUTT	1.5	2.11	BUOY	20.1 3	BUOY	20.1 3

Casing A	Attachments
----------	-------------

Casing ID: 1 String SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Loosey_Goosey_4_9_Fed_Com_303H_Casing_Assumptions_20220315132007.pdf

Casing ID: 2 String INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

 $Loosey_Goosey_4_9_Fed_Com_303H_Casing_Assumptions_20220315132219.pdf$

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Casing	Attachments
--------	--------------------

Casing ID: 3

String

PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Loosey_Goosey_4_9_Fed_Com_303H_Casing_Assumptions_20220315132118.pdf

Casing ID: 4

String

PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Loosey_Goosey_4_9_Fed_Com_303H_Casing_Assumptions_20220315132157.pdf

Casing ID: 5

String

COMPLETION SYSTEM

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Loosey_Goosey_4_9_Fed_Com_303H_Casing_Assumptions_20220315132302.pdf

Section 4 - Cement

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

String Type	Lead/Tail	Stage Tool Depth	Тор МD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Lead		0	0	0	0	0	0	0	0	0

SURFACE	Lead		0	1593	772	1.72	13.5	1327	45	Class C	Bentonite
SURFACE	Tail		0	1593	207	1.34	14.8	277	45	Class C	LCM
INTERMEDIATE	Lead		0	5236	980	1.88	12.9	1842	53	35:65 (Poz:C)	Salt, Bentonite
INTERMEDIATE	Tail		0	5236	292	1.34	14.8	391	53	Class C	LCM
PRODUCTION	Lead		0	1100 9	320	3.64	10.3	1164	25	Tuned Light	LCM
PRODUCTION	Tail		0	1100 9	127	1.34	14.8	170	25	Class C	LCM
COMPLETION SYSTEM	Lead	92	258	2096 6	739	1.3	14.2	960	10	50:50 (Poz:H)	Salt + Bentonite + Fluid Loss + Dispersant + SMS

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials will be kept on location at all times in order to combat lost circulation or unexpected kicks. In order to run DSTs, open hole logs, and casing, the viscosity and water loss may have to be adjusted in order to meet these needs.

Describe the mud monitoring system utilized: PVT/Pason/Visual Monitoring

Circulating Medium Table

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	РН	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	1593	OTHER : Fresh Water	7.83	8.33							
1593	5236	SALT SATURATED	9.8	10.3							
5236	1100 9	OTHER : Cut Brine or OBM	8.5	9							
1100 9	2096 6	OIL-BASED MUD	8.5	9							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

No DST Planned

List of open and cased hole logs run in the well:

COMPENSATED NEUTRON LOG, DIRECTIONAL SURVEY, GAMMA RAY LOG,

Coring operation description for the well:

N/A

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 5068 Anticipated Surface Pressure: 2685

Anticipated Bottom Hole Temperature(F): 177

Anticipated abnormal pressures, temperatures, or potential geologic hazards? YES

Describe:

Lost circulation may be encountered in the Delaware mountain group. Abnormal pressure as well as hole stability issues may be encountered in the Wolfcamp.

Contingency Plans geoharzards description:

Lost circulation material will be available, as well as additional drilling fluid along with the fluid volume in the drilling rig pit system. Drilling fluid can be mixed on location or mixed in vendor mud plant and trucked to location if needed. Sufficient barite will be available to maintain appropriate mud weight for the Wolfcamp interval.

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

Loosey_Goosey_4_9_Fed_Com_303H_H2S_Plan_20220315132721.pdf

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Loosey_Goosey_4_9_Fed_Com_303H_Prelim_Directional___AC_Report_20220315132736.pdf


Other proposed operations facets description:


Other proposed operations facets attachment:

 $Loosey_Goosey_4_9_Fed_Com_303H_Drilling_Plan_20220315132749.pdf$

Other Variance attachment:

Offline_Cement_Procedure_20220315132801.pdf
Loosey_Goosey_4_9_Fed_Com_303H_Flex_Hose_20220315132811.pdf
Loosey_Goosey_4_9_Fed_Com_303H_Multibowl_20220315132818.pdf





13-5/8" 3000# psi x 13-3/8" SOW Casing Head

5-(X)-

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1593	1593	13-3/8"	48.00	H-40	ST&C	1.12	2.51	4.21
12 1/4	0	5236	5236	9-5/8"	40.00	HCK-55	LT&C	1.36	1.41	2.68
8 3/4	0	10258	10258	7"	29.00	L-80	LT&C	1.46	1.70	1.88
8 3/4	10258	11009	10791	7"	29.00	P-110	BT&C	1.69	2.22	60.10
6	9258	20966	10830	4-1/2"	11.60	P-110	BT&C	1.50	2.11	20.13
					BLM	Minimum	Safety Factor	1.125	1	1.6 Dry 1.8 Wet

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1593	1593	13-3/8"	48.00	H-40	ST&C	1.12	2.51	4.21
12 1/4	0	5236	5236	9-5/8"	40.00	HCK-55	LT&C	1.36	1.41	2.68
8 3/4	0	10258	10258	7"	29.00	L-80	LT&C	1.46	1.70	1.88
8 3/4	10258	11009	10791	7"	29.00	P-110	BT&C	1.69	2.22	60.10
6	9258	20966	10830	4-1/2"	11.60	P-110	BT&C	1.50	2.11	20.13
					BLM	Minimum	Safety Factor	1.125	1	1.6 Dry 1.8 Wet

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1593	1593	13-3/8"	48.00	H-40	ST&C	1.12	2.51	4.21
12 1/4	0	5236	5236	9-5/8"	40.00	HCK-55	LT&C	1.36	1.41	2.68
8 3/4	0	10258	10258	7"	29.00	L-80	LT&C	1.46	1.70	1.88
8 3/4	10258	11009	10791	7"	29.00	P-110	BT&C	1.69	2.22	60.10
6	9258	20966	10830	4-1/2"	11.60	P-110	BT&C	1.50	2.11	20.13
					BLM	Minimum	Safety Factor	1.125	1	1.6 Dry 1.8 Wet

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1593	1593	13-3/8"	48.00	H-40	ST&C	1.12	2.51	4.21
12 1/4	0	5236	5236	9-5/8"	40.00	HCK-55	LT&C	1.36	1.41	2.68
8 3/4	0	10258	10258	7"	29.00	L-80	LT&C	1.46	1.70	1.88
8 3/4	10258	11009	10791	7"	29.00	P-110	BT&C	1.69	2.22	60.10
6	9258	20966	10830	4-1/2"	11.60	P-110	BT&C	1.50	2.11	20.13
					BLM	Minimum	Safety Factor	1.125	1	1.6 Dry 1.8 Wet

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1593	1593	13-3/8"	48.00	H-40	ST&C	1.12	2.51	4.21
12 1/4	0	5236	5236	9-5/8"	40.00	HCK-55	LT&C	1.36	1.41	2.68
8 3/4	0	10258	10258	7"	29.00	L-80	LT&C	1.46	1.70	1.88
8 3/4	10258	11009	10791	7"	29.00	P-110	BT&C	1.69	2.22	60.10
6	9258	20966	10830	4-1/2"	11.60	P-110	BT&C	1.50	2.11	20.13
,					BLM	Minimum	Safety Factor	1.125	1	1.6 Dry 1.8 Wet

Hydrogen Sulfide Drilling Operations Plan Loosey Goosey 4-9 Fed Com 303H

Cimarex Energy Co. Lea Co., NM

1 All Company and Contract personnel admitted on location must be trained by a qualified H2S safety instructor to the following:

- A. Characteristics of H₂S
- B. Physical effects and hazards
- C. Principal and operation of H2S detectors, warning system and briefing areas.
- D. Evacuation procedure, routes and first aid.
- E. Proper use of safety equipment & life support systems
- F. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.

H₂S Detection and Alarm Systems:

- A. H2S sensors/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud pits in the shale shaker area. Additional H2S detectors may play placed as deemed necessary.
- B. An audio alarm system will be installed on the derrick floor and in the top doghouse.

3 Windsock and/or wind streamers:

- A. Windsock at mudpit area should be high enough to be visible.
- B.

Windsock on the rig floor and / or top doghouse should be high enough to be visible.

4 Condition Flags and Signs

- A. Warning sign on access road to location.
- B. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H₂S present in dangerous concentration). Only H2S trained and certified personnel admitted to location.

5 Well control equipment:

A. See exhibit "E-1"

6 Communication:

- A. While working under masks chalkboards will be used for communication.
- B. Hand signals will be used where chalk board is inappropriate.
- C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.

7 Drillstem Testing:

No DSTs r cores are planned at this time.

- 8 Drilling contractor supervisor will be required to be familiar with the effects H₂S has on tubular goods and other mechanical equipment.
- 9 If H2S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H2S scavengers if necessary.

H₂S Contingency Plan

Loosey Goosey 4-9 Fed Com 303H

Cimarex Energy Co.

Lea Co., NM

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must:

- « Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- « Evacuate any public places encompassed by the 100 ppm ROE.
- « Be equipped with H₂S monitors and air packs in order to control the release.
- « Use the "buddy system" to ensure no injuries occur during the 432-620-1975
- « Take precautions to avoid personal injury during this operation.
- « Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- « Have received training in the:
 - Detection of H₂S, and
 - · Measures for protection against the gas,
 - · Equipment used for protection and emergency response.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO_2). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

Characteristics of H₂S and SO₂

Please see attached International Chemical Safety Cards.

Contacting Authorities

Cimarex Energy Co. of Colorado's personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Cimarex Energy Co. of Colorado's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

H₂S Contingency Plan Emergency Contacts

Loosey Goosey 4-9 Fed Com 303H

Cimarex Energy Co. Lea Co., NM

Cimarex Energy Co. of Color	ado	800-969-4789		
Co. Office and After-Hours N	Menu			
Key Personnel				
Name	Title	Office		Mobile
Larry Seigrist	Drilling Manager	432-620-1934		580-243-8485
Charlie Pritchard	Drilling Superintendent	432-620-1975		432-238-7084
Roy Shirley	Construction Superintendent			432-634-2136
				· - · - · - · - · - · - ·
<u>Artesia</u>		044		
Ambulance		911		
State Police		575-746-2703		
City Police		575-746-2703		
Sheriff's Office		575-746-9888		
Fire Department	- C:th	575-746-2701		
Local Emergency Planning		575-746-2122		
New Mexico Oil Conserva	tion division	575-748-1283		
<u>Carlsbad</u>				
Ambulance		911		
State Police		575-885-3137		
City Police		575-885-2111		
Sheriff's Office		575-887-7551		
Fire Department		575-887-3798		
Local Emergency Planning		575-887-6544		
US Bureau of Land Manag	gement	575-887-6544		
Santa Fe				
New Mexico Emergency P	Response Commission (Santa Fe)	505-476-9600		
New Mexico Emergency R	Response Commission (Santa Fe) 24 Hrs	505-827-9126		
New Mexico State Emerge	ency Operations Center	505-476-9635		
National				
	onse Center (Washington, D.C.)	800-424-8802		
<u>Medical</u>				
Flight for Life - 4000 24th	St.; Lubbock, TX	806-743-9911		
Aerocare - R3, Box 49F; Lu	ubbock, TX	806-747-8923		
Med Flight Air Amb - 2301	1 Yale Blvd S.E., #D3; Albuquerque, NM	505-842-4433		
SB Air Med Service - 2505	Clark Carr Loop S.E.; Albuquerque, NM	505-842-4949		
<u>Other</u>				
Boots & Coots IWC		800-256-9688	or	281-931-8884
Cudd Pressure Control		432-699-0139	or	432-563-3356
Halliburton		575-746-2757		
B.J. Services		575-746-3569		

Schlumberger

Coterra Loosey Goosey 4-9 Fed Com 303H Rev0 kFc 04Feb22 Proposal **Geodetic Report**



(Def Plan)

Report Date: Client: February 07, 2022 - 10:02 AM COTERRA

Field: NM Lea County (NAD 83) Coterra Loosey Goosey 4-9 Pad (east) / 303H Loosey Goosey 4-9 Fed Com 303H Structure / Slot:

Borehole: Loosey Goosey 4-9 Fed Com 303H Unknown / Unknown UWI / API#:

Survey Name: Coterra Loosey Goosey 4-9 Fed Com 303H Rev0 kFc 04Feb22 Survey Date:

February 04, 2022 Tort / AHD / DDI / ERD Ratio:

102.000 ° / 10797.209 ft / 6.329 / 0.997 Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet

Location Lat / Long: N 32° 36' 35.97894", W 103° 33' 40.70962" Location Grid N/E Y/X: N 586509.800 ftUS, E 779061.150 ftUS

0.4161 ° CRS Grid Convergence Angle: Grid Scale Factor: 0.99997381 Version / Patch: 2.10.829.1

Survey / DLS Computation: Vertical Section Azimuth: Minimum Curvature / Lubinski 179.670 ° (Grid North) Vertical Section Origin: 0.000 ft, 0.000 ft

TVD Reference Datum: RKB = 22ft TVD Reference Elevation: 3681.900 ft above MSL Seabed / Ground Elevation: 3659,900 ft above MSL Magnetic Declination: 6.360°

998.5086mgn (9.80665 Based) GARM Total Gravity Field Strength: **Gravity Model:**

Total Magnetic Field Strength: 47852.214 nT Magnetic Dip Angle: 60.457° Declination Date: February 04, 2022 Magnetic Declination Model: HDGM 2022 North Reference: Grid North Grid Convergence Used: Total Corr Mag North->Grid 0.4161° North:

5.9438° Local Coord Referenced To: Well Head

Comments	MD (ft)	Incl	Azim Grid	TVD (ff)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S °)	Longitude (E/W °)
SHL [194' FSL, 1448' FEL]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	N/A	586509.80	779061.15	N 32.609994	W 103.561308
1440 1 22	100.00	0.00	224.65	100.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	200.00	0.00	224.65	200.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	300.00	0.00	224.65	300.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	400.00	0.00	224.65	400.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	500.00	0.00	224.65	500.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	600.00	0.00	224.65	600.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	700.00 800.00	0.00	224.65 224.65	700.00 800.00	0.00	0.00	0.00	0.00	586509.80 586509.80	779061.15 779061.15	N 32.609994 N 32.609994	W 103.561308 W 103.561308
	900.00	0.00	224.65	900.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	1000.00	0.00	224.65	1000.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	1100.00	0.00	224.65	1100.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	1200.00	0.00	224.65	1200.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	1300.00	0.00	224.65	1300.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	1400.00	0.00	224.65	1400.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	1500.00	0.00	224.65	1500.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
Rustler	1543.00	0.00	224.65	1543.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	1600.00	0.00	224.65	1600.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
Top Salt	1632.00	0.00	224.65	1632.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
Nudge, Build 2°/100ft	1700.00	0.00	224.65	1700.00	0.00	0.00	0.00	0.00	586509.80	779061.15	N 32.609994	W 103.561308
	1800.00	2.00	224.65	1799.98	1.23	-1.24	-1.23	2.00	586508.56	779059.92	N 32.609991	W 103.561312
	1900.00	4.00	224.65	1899.84	4.94	-4.96	-4.90	2.00	586504.84	779056.25	N 32.609981	W 103.561324
Hold	2000.01	6.00	224.65	1999.46	11.10	-11.17	-11.03	2.00	586498.63	779050.12	N 32.609964	W 103.561344
	2100.00	6.00	224.65	2098.90	18.50	-18.60	-18.37	0.00	586491.20	779042.78	N 32.609943	W 103.561368
	2200.00 2300.00	6.00 6.00	224.65 224.65	2198.36 2297.81	25.89 33.29	-26.04 -33.48	-25.72 -33.07	0.00	586483.76 586476.32	779035.43 779028.09	N 32.609923 N 32.609903	W 103.561392 W 103.561416
	2400.00	6.00	224.65	2397.26	40.68	-33.46 -40.91	-33.07 -40.41	0.00	586468.89	779028.09	N 32.609883	W 103.561440
	2500.00	6.00	224.65	2496.71	48.07	-48.35	-47.76	0.00	586461.45	779013.39	N 32.609862	W 103.561464
	2600.00	6.00	224.65	2596.16	55.47	-55.79	-55.10	0.00	586454.01	779006.05	N 32.609842	W 103.561488
	2700.00	6.00	224.65	2695.62	62.86	-63.22	-62.45	0.00	586446.58	778998.70	N 32.609822	W 103.561513
	2800.00	6.00	224.65	2795.07	70.26	-70.66	-69.79	0.00	586439.14	778991.36	N 32.609801	W 103.561537
	2900.00	6.00	224.65	2894.52	77.65	-78.10	-77.14	0.00	586431.70	778984.01	N 32.609781	W 103.561561
	3000.00	6.00	224.65	2993.97	85.05	-85.53	-84.49	0.00	586424.27	778976.67	N 32.609761	W 103.561585
	3100.00	6.00	224.65	3093.43	92.44	-92.97	-91.83	0.00	586416.83	778969.32	N 32.609740	W 103.561609
D O. #	3200.00	6.00	224.65	3192.88	99.84	-100.41	-99.18	0.00	586409.39	778961.98	N 32.609720	W 103.561633
Base Salt (Tansil)	3232.30	6.00	224.65	3225.00	102.22	-102.81	-101.55	0.00	586406.99	778959.60	N 32.609714	W 103.561640
	3300.00	6.00	224.65	3292.33	107.23	-107.85	-106.52	0.00	586401.96	778954.63	N 32.609700	W 103.561657
	3400.00	6.00	224.65	3391.78	114.62	-115.28	-113.87	0.00	586394.52	778947.29	N 32.609680	W 103.561681
	3500.00 3600.00	6.00 6.00	224.65 224.65	3491.23 3590.69	122.02 129.41	-122.72 -130.16	-121.21 -128.56	0.00	586387.08 586379.65	778939.94 778932.59	N 32.609659 N 32.609639	W 103.561705 W 103.561729
	3700.00	6.00	224.65	3690.14	136.81	-137.59	-135.90	0.00	586372.21	778925.25	N 32.609619	W 103.561729 W 103.561753
	3800.00	6.00	224.65	3789.59	144.20	-145.03	-143.25	0.00	586364.77	778917.90	N 32.609598	W 103.561777
	3900.00	6.00	224.65	3889.04	151.60	-152.47	-150.60	0.00	586357.34	778910.56	N 32.609578	W 103.561801
	4000.00	6.00	224.65	3988.50	158.99	-159.90	-157.94	0.00	586349.90	778903.21	N 32.609558	W 103.561825
	4100.00	6.00	224.65	4087.95	166.39	-167.34	-165.29	0.00	586342.46	778895.87	N 32.609538	W 103.561849
	4200.00	6.00	224.65	4187.40	173.78	-174.78	-172.63	0.00	586335.03	778888.52	N 32.609517	W 103.561873
	4300.00	6.00	224.65	4286.85	181.18	-182.21	-179.98	0.00	586327.59	778881.18	N 32.609497	W 103.561897
Section 33-4	4400.00	6.00	224.65	4386.30	188.57	-189.65	-187.32	0.00	586320.15	778873.83	N 32.609477	W 103.561921
Line NMLC0065607	4491.55	6.00	224.65	4477.35	195.34	-196.46	-194.05	0.00	586313.35	778867.11	N 32.609458	W 103.561943
Lease Crossing	4500.00	6.00	224.65	4485.76	195.96	-197.09	-194.67	0.00	586312.72	778866.49	N 32.609456	W 103.561945
	4600.00	6.00	224.65	4585.21	203.36	-204.53	-202.02	0.00	586305.28	778859.14	N 32.609436	W 103.561969
	4700.00	6.00	224.65	4684.66	210.75	-211.96	-209.36	0.00	586297.84	778851.79	N 32.609416	W 103.561993
	4800.00	6.00	224.65	4784.11	218.15	-219.40	-216.71	0.00	586290.41	778844.45	N 32.609395	W 103.562017
Capitan	4854.18	6.00	224.65	4838.00	222.15	-223.43	-220.69	0.00	586286.38	778840.47	N 32.609384	W 103.562030
	4900.00	6.00	224.65	4883.56	225.54	-226.84	-224.05	0.00	586282.97	778837.10	N 32.609375	W 103.562041
	5000.00	6.00	224.65	4983.02	232.94	-234.27	-231.40	0.00	586275.53	778829.76	N 32.609355	W 103.562065
	5100.00	6.00	224.65	5082.47	240.33	-241.71	-238.74	0.00	586268.10	778822.41	N 32.609335	W 103.562089
	5200.00	6.00	224.65	5181.92	247.73	-249.15	-246.09	0.00	586260.66	778815.07	N 32.609314	W 103.562113
Lamar	5232.26	6.00	224.65	5214.00	250.11	-251.55	-248.46	0.00	586258.26	778812.70	N 32.609308	W 103.562121
Bell Canyon	5300.00 5304.65	6.00 6.00	224.65 224.65	5281.37 5286.00	255.12 255.46	-256.58 -256.93	-253.44 -253.78	0.00 0.00	586253.22 586252.88	778807.72 778807.38	N 32.609294 N 32.609293	W 103.562137 W 103.562138
Dell Carly0f1	5400.00	6.00	224.65 224.65	5286.00	262.51	-264.02	-253.78 -260.78	0.00	586252.88 586245.79	778807.38 778800.38	N 32.609293 N 32.609274	W 103.562138 W 103.562161
	5500.00	6.00	224.65	5480.28	262.51	-264.02 -271.46	-268.13	0.00	586238.35	778793.03	N 32.609253	W 103.562185
	5600.00	6.00	224.65	5579.73	277.30	-271.46	-275.47	0.00	586230.91	778785.69	N 32.609233	W 103.562209
Drop 2°/100ft	5699.88	6.00	224.65	5679.06	284.69	-286.32	-282.81	0.00	586223.49	778778.35	N 32.609213	W 103.562233
op _ ,.oon	5700.00	6.00	224.65	5679.18	284.70	-286.33	-282.82	2.00	586223.48	778778.34	N 32.609213	W 103.562233
Cherry Canyon	5761.09	4.78	224.65	5740.00	288.75	-290.41	-286.85	2.00	586219.40	778774.31	N 32.609202	W 103.562247
	5800.00	4.00	224.65	5778.80	290.86	-292.53	-288.94	2.00	586217.28	778772.22	N 32.609196	W 103.562253
	5900.00	2.00	224.65	5878.65	294.56	-296.25	-292.61	2.00	586213.56	778768.54	N 32.609186	W 103.562265
Hold	5999.89	0.00	224.65	5978.52	295.79	-297.49	-293.84	2.00	586212.32	778767.32	N 32.609182	W 103.562269
	6000.00	0.00	224.65	5978.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	6100.00	0.00	224.65	6078.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269

Drilling Office 2.10.829.1

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S °)	Longitude (E/W °)
· · · · · · · · · · · · · · · · · · ·	6200.00 6300.00	0.00 0.00	224.65 224.65	6178.63 6278.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
	6400.00	0.00	224.65	6378.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	6500.00 6600.00	0.00	224.65 224.65	6478.63 6578.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
Brushy Canyon	6693.37	0.00	224.65	6672.00	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	6700.00	0.00	224.65	6678.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32 778767.32	N 32.609182	W 103.562269
	6800.00 6900.00	0.00	224.65 224.65	6778.63 6878.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 0.00	586212.32 586212.32	778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
	7000.00	0.00	224.65	6978.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	7100.00 7200.00	0.00	224.65 224.65	7078.63 7178.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
	7300.00	0.00	224.65	7278.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	7400.00 7500.00	0.00	224.65 224.65	7378.63 7478.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
	7600.00	0.00	224.65	7578.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	7700.00 7800.00	0.00	224.65 224.65	7678.63 7778.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269
	7900.00	0.00	224.65	7878.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269 W 103.562269
	8000.00	0.00	224.65	7978.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	8100.00 8200.00	0.00	224.65 224.65	8078.63 8178.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
Bone Spring	8221.37	0.00	224.65	8200.00	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	8300.00 8400.00	0.00	224.65 224.65	8278.63 8378.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
	8500.00	0.00	224.65	8478.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	8600.00 8700.00	0.00	224.65 224.65	8578.63 8678.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
	8800.00	0.00	224.65	8778.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	8900.00	0.00	224.65	8878.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	9000.00 9100.00	0.00 0.00	224.65 224.65	8978.63 9078.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
	9200.00	0.00	224.65	9178.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
1st BS Sand	9300.00 9397.37	0.00 0.00	224.65 224.65	9278.63 9376.00	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
ist bo sand	9400.00	0.00	224.65	9378.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	9500.00	0.00	224.65	9478.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	9600.00 9700.00	0.00	224.65 224.65	9578.63 9678.63	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 0.00	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
	9800.00	0.00	224.65	9778.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
and BC Cond	9900.00 9949.37	0.00 0.00	224.65 224.65	9878.63 9928.00	295.79 295.79	-297.49 -297.49	-293.84 -293.84	0.00 <i>0.00</i>	586212.32 586212.32	778767.32 778767.32	N 32.609182 N 32.609182	W 103.562269 W 103.562269
2nd BS Sand	10000.00	0.00	224.65	9978.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	10100.00	0.00	224.65	10078.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
KOP, Build	10200.00	0.00	224.65	10178.63	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
10°/100ft	10258.89	0.00	224.65	10237.52	295.79	-297.49	-293.84	0.00	586212.32	778767.32	N 32.609182	W 103.562269
	10300.00 10400.00	4.11 14.11	179.67 179.67	10278.60 10377.21	297.27 313.08	-298.96 -314.78	-293.83 -293.74	10.00 10.00	586210.85 586195.03	778767.33 778767.42	N 32.609178 N 32.609135	W 103.562269 W 103.562269
	10500.00	24.11	179.67	10471.58	345.78	-347.48	-293.55	10.00	586162.33	778767.60	N 32.609045	W 103.562270
3rd BS Sand	10600.00 10622.23	34.11 36.33	179.67 179.67	10558.84 10577.00	394.37 407.19	-396.07 -408.89	-293.28 -293.20	10.00 <i>10.00</i>	586113.75 586100.92	778767.88 778767.95	N 32.608911 N 32.608876	W 103.562270 W 103.562270
SIU BS Saliu	10700.00	44.11	179.67	10636.33	457.37	-459.07	-292.92	10.00	586050.75	778768.24	N 32.608738	W 103.562270
	10800.00	54.11	179.67	10701.71	532.88	-534.57	-292.49	10.00	585975.25	778768.67	N 32.608531	W 103.562271
	10900.00 11000.00	64.11 74.11	179.67 179.67	10752.98 10788.59	618.58 711.89	-620.28 -713.58	-292.00 -291.47	10.00 10.00	585889.54 585796.24	778769.16 778769.69	N 32.608295 N 32.608039	W 103.562271 W 103.562272
Build 5°/100ft	11008.89	75.00	179.67	10790.95	720.46	-722.15	-291.42	10.00	585787.67	778769.74	N 32.608015	W 103.562272
	11100.00 11200.00	79.56 84.56	179.67 179.67	10811.02 10824.83	809.31 908.32	-811.00 -910.01	-290.92 -290.35	5.00 5.00	585698.82 585599.82	778770.24 778770.80	N 32.607771 N 32.607499	W 103.562272 W 103.562273
	11300.00	89.56	179.67	10829.97	1008.16	-1009.84	-289.79	5.00	585499.99	778771.37	N 32.607224	W 103.562273
Landing Point	11308.89 11400.00	90.00 90.00	179.67 179.67	10830.00 10830.00	1017.04 1108.16	-1018.73 -1109.84	-289.74 -289.22	5.00 0.00	585491.10 585399.99	778771.42 778771.94	N 32.607200 N 32.606950	W 103.562273 W 103.562274
	11500.00	90.00	179.67	10830.00	1208.16	-1209.84	-288.65	0.00	585300.00	778772.51	N 32.606675	W 103.562274
	11600.00 11700.00	90.00 90.00	179.67	10830.00 10830.00	1308.16 1408.16	-1309.84 -1409.84	-288.08	0.00 0.00	585200.00	778773.08	N 32.606400 N 32.606125	W 103.562275
	11800.00	90.00	179.67 179.67	10830.00	1508.16	-1509.83	-287.51 -286.94	0.00	585100.00 585000.01	778773.64 778774.21	N 32.605850	W 103.562275 W 103.562276
	11900.00	90.00	179.67	10830.00	1608.16	-1609.83	-286.38	0.00	584900.01	778774.78	N 32.605575	W 103.562276
	12000.00 12100.00	90.00 90.00	179.67 179.67	10830.00 10830.00	1708.16 1808.16	-1709.83 -1809.83	-285.81 -285.24	0.00 0.00	584800.02 584700.02	778775.35 778775.92	N 32.605301 N 32.605026	W 103.562277 W 103.562277
	12200.00	90.00	179.67	10830.00	1908.16	-1909.83	-284.67	0.00	584600.03	778776.49	N 32.604751	W 103.562278
	12300.00 12400.00	90.00 90.00	179.67 179.67	10830.00 10830.00	2008.16 2108.16	-2009.83 -2109.82	-284.10 -283.54	0.00	584500.03 584400.04	778777.05 778777.62		W 103.562278 W 103.562279
	12500.00	90.00	179.67	10830.00	2208.16	-2209.82	-282.97	0.00	584300.04	778778.19	N 32.603926	W 103.562279
	12600.00 12700.00	90.00 90.00	179.67 179.67	10830.00 10830.00	2308.16 2408.16	-2309.82 -2409.82	-282.40 -281.83	0.00 0.00	584200.04 584100.05	778778.76 778779.33	N 32.603651 N 32.603377	W 103.562280 W 103.562280
	12800.00	90.00	179.67	10830.00	2508.16	-2509.82	-281.26	0.00	584000.05	778779.90	N 32.603102	W 103.562281
	12900.00	90.00	179.67	10830.00	2608.16	-2609.82	-280.69	0.00	583900.06	778780.46	N 32.602827	W 103.562281 W 103.562282
	13000.00 13100.00	90.00 90.00	179.67 179.67	10830.00 10830.00	2708.16 2808.16	-2709.81 -2809.81	-280.13 -279.56	0.00 0.00	583800.06 583700.07	778781.03 778781.60	N 32.602552 N 32.602277	W 103.562282 W 103.562282
NMLC0065607												
to NMLC0064194 Lease Crossing	13136.67	90.00	179.67	10830.00	2844.82	-2846.48	-279.35	0.00	583663.40	778781.81	N 32.602176	W 103.562282
	13200.00	90.00	179.67	10830.00	2908.16	-2909.81	-278.99	0.00	583600.07	778782.17		W 103.562283
	13300.00 13400.00	90.00 90.00	179.67 179.67	10830.00 10830.00	3008.16 3108.16	-3009.81 -3109.81	-278.42 -277.85	0.00 0.00	583500.08 583400.08	778782.74 778783.30	N 32.601728 N 32.601453	W 103.562283 W 103.562284
	13500.00	90.00	179.67	10830.00	3208.16	-3209.81	-277.29	0.00	583300.08	778783.87	N 32.601178	W 103.562284
	13600.00 13700.00	90.00 90.00	179.67 179.67	10830.00 10830.00	3308.16 3408.16	-3309.80 -3409.80	-276.72 -276.15	0.00 0.00	583200.09 583100.09	778784.44 778785.01	N 32.600903 N 32.600628	W 103.562285 W 103.562285
	13800.00	90.00	179.67	10830.00	3508.16	-3509.80	-275.58	0.00	583000.10	778785.58		W 103.562286
	13900.00	90.00	179.67	10830.00	3608.16	-3609.80	-275.01	0.00	582900.10	778786.15	N 32.600078	W 103.562286
	14000.00 14100.00	90.00 90.00	179.67 179.67	10830.00 10830.00	3708.16 3808.16	-3709.80 -3809.80	-274.44 -273.88	0.00 0.00	582800.11 582700.11	778786.71 778787.28	N 32.599804 N 32.599529	W 103.562287 W 103.562287
	14200.00	90.00	179.67	10830.00	3908.16	-3909.79	-273.31	0.00	582600.12	778787.85	N 32.599254	W 103.562288
	14300.00 14400.00	90.00 90.00	179.67 179.67	10830.00 10830.00	4008.16 4108.16	-4009.79 -4109.79	-272.74 -272.17	0.00 0.00	582500.12 582400.12	778788.42 778788.99	N 32.598979 N 32.598704	W 103.562288 W 103.562289
	14500.00	90.00	179.67	10830.00	4208.16	-4209.79	-271.60	0.00	582300.13	778789.55	N 32.598429	W 103.562289
	14600.00	90.00	179.67	10830.00	4308.16	-4309.79	-271.03	0.00	582200.13	778790.12	N 32.598154	W 103.562290
	14700.00 14800.00	90.00 90.00	179.67 179.67	10830.00 10830.00	4408.16 4508.16	-4409.79 -4509.79	-270.47 -269.90	0.00 0.00	582100.14 582000.14	778790.69 778791.26	N 32.597880 N 32.597605	W 103.562290 W 103.562291
	14900.00	90.00	179.67	10830.00	4608.16	-4609.78	-269.33	0.00	581900.15	778791.83	N 32.597330	W 103.562291
	15000.00 15100.00	90.00 90.00	179.67 179.67	10830.00 10830.00	4708.16 4808.16	-4709.78 -4809.78	-268.76 -268.19	0.00 0.00	581800.15 581700.16	778792.40 778792.96	N 32.597055 N 32.596780	W 103.562292 W 103.562292
	15200.00	90.00	179.67	10830.00	4908.16	-4809.78 -4909.78	-268.19 -267.63	0.00	581600.16 581600.16	778792.96	N 32.596780 N 32.596505	W 103.562292 W 103.562293
	15300.00	90.00	179.67	10830.00	5008.16	-5009.78	-267.06	0.00	581500.16	778794.10	N 32.596231	W 103.562293
	15400.00 15500.00	90.00 90.00	179.67 179.67	10830.00 10830.00	5108.16 5208.16	-5109.78 -5209.77	-266.49 -265.92	0.00	581400.17 581300.17	778794.67 778795.24	N 32.595956 N 32.595681	W 103.562294 W 103.562294
	15600.00	90.00	179.67	10830.00	5308.16	-5309.77	-265.35	0.00	581200.18	778795.81	N 32.595406	W 103.562295
	15700.00	90.00	179.67	10830.00	5408.16	-5409.77	-264.78	0.00	581100.18	778796.37	N 32.595131	W 103.562295

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S °)	Longitude (E/W°)
Section 4-9 Line Crossing	15786.33	90.00	179.67	10830.00	5494.49	-5496.10	-264.29	0.00	581013.85	778796.86	N 32.594894	W 103.562296
	15800.00	90.00	179.67	10830.00	5508.16	-5509.77	-264.22	0.00	581000.19	778796.94	N 32.594856	W 103.562296
	15900.00	90.00	179.67	10830.00	5608.16	-5609.77	-263.65	0.00	580900.19	778797.51	N 32.594581	W 103.562296
	16000.00	90.00	179.67	10830.00	5708.16	-5709.77	-263.08	0.00	580800.20	778798.08	N 32.594307	W 103.562297
	16100.00	90.00	179.67	10830.00	5808.16	-5809.76	-262.51	0.00	580700.20	778798.65	N 32.594032	W 103.562297
	16200.00	90.00	179.67	10830.00	5908.16	-5909.76	-261.94	0.00	580600.20	778799.21	N 32.593757	W 103.562298
	16300.00	90.00	179.67	10830.00	6008.16	-6009.76	-261.37	0.00	580500.21	778799.78	N 32.593482	W 103.562298
	16400.00	90.00	179.67	10830.00	6108.16	-6109.76	-260.81	0.00	580400.21	778800.35	N 32.593207	W 103.562299
	16500.00	90.00	179.67	10830.00	6208.16	-6209.76	-260.24	0.00	580300.22	778800.92	N 32.592932	W 103.562299
	16600.00	90.00	179.67	10830.00	6308.16	-6309.76	-259.67	0.00	580200.22	778801.49	N 32.592658	W 103.562300
	16700.00	90.00	179.67	10830.00	6408.16	-6409.75	-259.10	0.00	580100.23	778802.06	N 32.592383	W 103.562301
	16800.00	90.00	179.67	10830.00	6508.16	-6509.75	-258.53	0.00	580000.23	778802.62	N 32.592108	W 103.562301
	16900.00	90.00	179.67	10830.00	6608.16	-6609.75	-257.97	0.00	579900.23	778803.19	N 32.591833	W 103.562302
	17000.00	90.00	179.67	10830.00	6708.16	-6709.75	-257.40	0.00	579800.24	778803.76	N 32.591558	W 103.562302
	17100.00	90.00	179.67	10830.00	6808.16	-6809.75	-256.83	0.00	579700.24	778804.33	N 32.591283	W 103.562303
	17200.00	90.00	179.67	10830.00	6908.16	-6909.75	-256.26	0.00	579600.25	778804.90	N 32.591008	W 103.562303
	17300.00	90.00	179.67	10830.00	7008.16	-7009.74	-255.69	0.00	579500.25	778805.47	N 32.590734	W 103.562304
	17400.00	90.00	179.67	10830.00	7108.16	-7109.74 -7209.74	-255.12 -254.56	0.00	579400.26	778806.03	N 32.590459 N 32.590184	W 103.562304
	17500.00	90.00	179.67	10830.00	7208.16			0.00	579300.26	778806.60		W 103.562305
	17600.00 17700.00	90.00 90.00	179.67 179.67	10830.00 10830.00	7308.16 7408.16	-7309.74 -7409.74	-253.99 -253.42	0.00	579200.27 579100.27	778807.17 778807.74	N 32.589909 N 32.589634	W 103.562305
	17700.00	90.00	179.67	10830.00	7508.16	-7409.74 -7509.74	-252.85	0.00	579100.27	778808.31	N 32.589359	W 103.562306 W 103.562306
	17900.00	90.00	179.67	10830.00	7608.16	-7609.74	-252.28	0.00	578900.28	778808.87	N 32.589084	W 103.562307
	18000.00	90.00	179.67	10830.00	7708.16	-7709.73	-251.71	0.00	578800.28	778809.44	N 32.588810	W 103.562307 W 103.562307
	18100.00	90.00	179.67	10830.00	7808.16	-7809.73	-251.71	0.00	578700.29	778810.01	N 32.588535	W 103.562307 W 103.562308
	18200.00	90.00	179.67	10830.00	7908.16	-7909.73	-250.58	0.00	578600.29	778810.58	N 32.588260	W 103.562308
	18300.00	90.00	179.67	10830.00	8008.16	-8009.73	-250.01	0.00	578500.30	778811.15	N 32.587985	W 103.562309
	18400.00	90.00	179.67	10830.00	8108.16	-8109.73	-249.44	0.00	578400.30	778811.72	N 32.587710	W 103.562309
	18500.00	90.00	179.67	10830.00	8208.16	-8209.73	-248.87	0.00	578300.31	778812.28	N 32.587435	W 103.562310
	18600.00	90.00	179.67	10830.00	8308.16	-8309.72	-248.31	0.00	578200.31	778812.85	N 32.587161	W 103.562310
	18700.00	90.00	179.67	10830.00	8408.16	-8409.72	-247.74	0.00	578100.31	778813.42	N 32.586886	W 103.562311
	18800.00	90.00	179.67	10830.00	8508.16	-8509.72	-247.17	0.00	578000.32	778813.99	N 32.586611	W 103.562311
	18900.00	90.00	179.67	10830.00	8608.16	-8609.72	-246.60	0.00	577900.32	778814.56	N 32.586336	W 103.562312
	19000.00	90.00	179.67	10830.00	8708.16	-8709.72	-246.03	0.00	577800.33	778815.12	N 32.586061	W 103.562312
	19100.00	90.00	179.67	10830.00	8808.16	-8809.72	-245.46	0.00	577700.33	778815.69	N 32.585786	W 103.562313
	19200.00	90.00	179.67	10830.00	8908.16	-8909.71	-244.90	0.00	577600.34	778816.26	N 32.585511	W 103.562313
	19300.00	90.00	179.67	10830.00	9008.16	-9009.71	-244.33	0.00	577500.34	778816.83	N 32.585237	W 103.562314
	19400.00	90.00	179.67	10830.00	9108.16	-9109.71	-243.76	0.00	577400.35	778817.40	N 32.584962	W 103.562314
	19500.00	90.00	179.67	10830.00	9208.16	-9209.71	-243.19	0.00	577300.35	778817.97	N 32.584687	W 103.562315
	19600.00	90.00	179.67	10830.00	9308.16	-9309.71	-242.62	0.00	577200.35	778818.53	N 32.584412	W 103.562315
	19700.00	90.00	179.67	10830.00	9408.16	-9409.71	-242.05	0.00	577100.36	778819.10	N 32.584137	W 103.562316
	19800.00	90.00	179.67	10830.00	9508.16	-9509.70	-241.49	0.00	577000.36	778819.67	N 32.583862	W 103.562316
	19900.00	90.00	179.67	10830.00	9608.16	-9609.70	-240.92	0.00	576900.37	778820.24	N 32.583587	W 103.562317
	20000.00	90.00	179.67	10830.00	9708.16	-9709.70	-240.35	0.00	576800.37	778820.81	N 32.583313	W 103.562317
	20100.00	90.00	179.67	10830.00	9808.16	-9809.70	-239.78	0.00	576700.38	778821.38	N 32.583038	W 103.562318
	20200.00	90.00	179.67	10830.00	9908.16	-9909.70	-239.21	0.00	576600.38	778821.94	N 32.582763	W 103.562318
	20300.00	90.00	179.67	10830.00	10008.16	-10009.70	-238.65	0.00	576500.39	778822.51	N 32.582488	W 103.562319
	20400.00	90.00	179.67	10830.00	10108.16	-10109.69	-238.08	0.00	576400.39	778823.08	N 32.582213	W 103.562319
	20500.00	90.00	179.67	10830.00	10208.16	-10209.69	-237.51	0.00	576300.39	778823.65	N 32.581938	W 103.562320
	20600.00	90.00	179.67	10830.00	10308.16	-10309.69	-236.94	0.00	576200.40	778824.22	N 32.581664	W 103.562320
	20700.00	90.00	179.67	10830.00	10408.16	-10409.69	-236.37	0.00	576100.40	778824.78	N 32.581389	W 103.562321
	20800.00	90.00	179.67	10830.00	10508.16	-10509.69	-235.80	0.00	576000.41	778825.35	N 32.581114	W 103.562321
1	20900.00	90.00	179.67	10830.00	10608.16	-10609.69	-235.24	0.00	575900.41	778825.92	N 32.580839	W 103.562322
Loosey Goosey												
4-9 Fed Com	00000 74	00.00	470.07	10000 00	10071.00	10070.00	004.00	0.00	575000 7:	770000 65	N 00 500555	14/ 400 500000
303H - BHL [100' FSL, 1744' FEL]	20966.71	90.00	179.67	10830.00	10674.86	-10676.39	-234.86	0.00	575833.71	778826.30	N 32.580656	W 103.562322

Survey Type:

Def Plan

Survey Error Model:

ISCWSA Rev 3 *** 3-D 95.000% Confidence 2.7955 sigma

Survey Program:									
Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size Casi (in)	ing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	22.000	1/100.000	30.000	30.000	1==21	A001Mb_MWD-Depth Only	Loosey Goosey 4-9 Fed Com 303H / Coterra Loosey Goosey 4-9
	1	22.000	20966.705	1/100.000	30.000	30.000		A001Mb_MWD	Loosey Goosey 4-9 Fed Com 303H / Coterra Loosey Goosey 4-9


Schlumberger

COTERRA





EW (ft) Scale = 1:500.00(ft)



Vertical Section (ft) Azim = 179.67° Scale = 1:700.00(ft) Origin = 0N/-S, 0E/-W

Schlumberger



Coterra Loosey Goosey 4-9 Fed Com 303H Rev0 kFc 04Feb22 Anti-Collision Summary Report

Analysis Method: Reference Trajectory: Depth Interval:

Min Pts:

Offset Trajectories Summary

Version / Patch: Database \ Project: 3D Least Distance

All local minima indicated.

2.10.829.1 localhost\drilling-project1

Coterra Loosey Goosey 4-9 Fed Com 303H Rev0 kFc 04Feb22 (Def Plan) Every 10.00 Measured Depth (ft)

NAL Procedure: D&M AntiCollision Standard S002

 Analysis Date-24hr Time:
 February 07, 2022 - 10:02

 Client:
 COTERRA

 Field:
 NM Lea County (NAD 83)

Coterra Loosey Goosey 4-9 Pad (east) 303H Structure

Slot: Well:

Loosey Goosey 4-9 Fed Com 303H Loosey Goosey 4-9 Fed Com 303H 0.00ft ~ 20966.71ft Borehole:

Scan MD Range:

Trajectory Error Model: ISCWSA0 3-D 95.000% Confidence 2.7955 sigma

Offset Selection Criteria								s Summary					
Wellhead distance scan: Selection filters:	Not perform Definitive S		finitive Plar	ns - Definitiv	e survevs ex	clude definitive pla	ans						
						hole - All Non-Def		o Def-Plan is	set in a borehole				
Offset Trajectory	l 9	Separation		Allow	Sep.	Controlling	Reference	Trajectory		Risk Level		Alert	Status
Choos majoriory			EOU (ft)	Dev. (ft)	Fact.	Rule	MD (ft)	TVD (ft)	Alert	Minor	Major	74011	
30-025-26272 - Union Federal													ail Major
	8847.44 8847.42	32.81 32.81	8844.94 8844.91	8814.63 8814.61	N/A N/A	MAS = 10.00 (m) MAS = 10.00 (m)	0.00 10.00	0.00 10.00				Surface MinPt-O-SF	
	8847.40	32.81	8844.90	8814.60	N/A	MAS = 10.00 (m)	22.00	22.00				WRP	
	8845.47 8845.68	32.81 67.39	8834.69 8799.92	8812.66 8778.29	1068.07 204.42	MAS = 10.00 (m) OSF1.50	320.00 1320.00	320.00 1320.00				MinPts MinPt-CtCt	
	8542.68	353.52	8306.16	8189.15	36.49	OSF1.50	6760.00	6738.63				MinPt-CtCt	
	8544.29 8548.99	456.23 535.57	8239.30 8191.11	8088.06 8013.42	28.24 24.05	OSF1.50 OSF1.50	8700.00 10200.00	8678.63 10178.63				MinPt-CtCt MinPt-CtCt	
	1894.07	571.04	1512.54	1323.03	4.99	OSF1.50	17250.00	10830.00	OSF<5.00			Enter Alert	
	572.30	576.17	187.35	-3.87	1.49	OSF1.50	18580.00	10830.00		OSF<1.50	00544.00	Enter Minor	
	388.07 115.10	582.71 716.86	-1.23 -363.64	-194.64 - 601.76	1.00 0.24	OSF1.50 OSF1.50	18770.00 19140.00	10830.00 10830.00			OSF<1.00	Enter Major MinPts	
	386.89	591.55	-8.32	-204.67	0.98	OSF1.50	19510.00	10830.00			OSF>1.00	Exit Major	
	580.88 1829.66	582.66 576.30	191.60 1444.63	-1.78 1253.36	1.50 4.78	OSF1.50 OSF1.50	19710.00 20966.71	10830.00 10830.00		OSF>1.50		Exit Minor TD	
00.005.00400.0: 15.1													
30-025-02402 - Signal-Federal 1 Blind to 3899ft - P (Def Survey)												F	ail Major
	698.94	43.08	669.39	655.86	25.75	OSF1.50	0.00	0.00				Surface	
	698.94 698.94	65.91 230.58	654.17 544.39	633.03 468.36	16.48 4.58	OSF1.50 OSF1.50	22.00 120.00	22.00 120.00	OSF<5.00			WRP Enter Alert	
	698.94	707.96	226.13	-9.02	1.48	OSF1.50	350.00	350.00		OSF<1.50		Enter Minor	
	698.94 594.29	1060.80 7992.03	-9.10 -4734.56	-361.86 -7397.74	0.99 0.11	OSF1.50 OSF1.50	520.00 3880.00	520.00 3869.15			OSF<1.00	Enter Major MinPts	
	594.15	7988.82	-4732.56	-7394.67	0.11	OSF1.50	3890.00	3879.10				MinPt-CtCt	
	1722.64 2103.24	2583.42 2110.53	-0.47 695.39	-860.78 -7.28	1.00 1.49	OSF1.50 OSF1.50	5510.00 5910.00	5490.22 5888.65		OSF>1.50	OSF>1.00	Exit Major Exit Minor	
	3839.03	1157.98	3066.22	2681.06	4.98	OSF1.50	7680.00	7658.63	OSF>5.00	001 - 1.50		Exit Alert	
	7243.14 8040.89	2177.06 3987.98	5790.93	5066.08 4052.92	4.99 3.03	OSF1.50 OSF1.50	12130.00 14190.00	10830.00 10830.00	OSF<5.00			Enter Alert MINPT-O-EOU	
	8675.09	4761.25	5500.08	3913.83	2.73	OSF1.50	15350.00	10830.00				MinPt-O-ADP	
	9857.70	5654.71	6087.06	4202.99	2.62	OSF1.50	17160.00	10830.00				MinPt-O-SF	
	12831.62	6713.57	8355.07	6118.05	2.87	OSF1.50	20966.71	10830.00				TD	
Coterra Loosey Goosey 4-9 Fer Com 204H Rev0 kFc 04Feb22 (Def Plan)	d											F	ail Minor
	20.00	16.50	17.50	3.50	N/A	MAS = 5.03 (m)	0.00	0.00	CtCt<=15m<15.00			Enter Alert	
	20.00 20.00	16.50 20.07	17.50 5.79	3.50 -0.07	N/A 1.49	MAS = 5.03 (m) OSF1.50	22.00 1230.00	22.00 1230.00		OSF<1.50		WRP Enter Minor	
	20.00	24.13	3.08	-4.13	1.21	OSF1.50	1500.00	1500.00				MinPt-CtCt	
	20.15 20.27	24.57 24.72	2.93 2.95	-4.42 -4.45	1.20 1.20	OSF1.50 OSF1.50	1530.00 1540.00	1530.00 1540.00				MINPT-O-EOU MinPts	
	26.69	27.01	7.85	-0.33	1.48	OSF1.50	1700.00	1700.00		OSF>1.50		Exit Minor	
	72.04 101.95	30.98 32.57	50.55 79.40	41.06 69.38	3.66 4.96	OSF1.50 OSF1.50	2000.01 2120.00	1999.46 2118.79	OSF>5.00			MinPts Exit Alert	
	1080.31	91.71_	1018.34	988.61	18.12	OSF1.50	5999.89	5978.52	001 = 3.00			MinPt-O-SF	
	1262.98 1263.09	147.78 147.90	1163.63	1115.20 1115.18	13.01 13.00	OSF1.50 OSF1.50	9750.00 9760.00	9728.63 9738.63				MINPT-O-EOU MinPt-O-ADP	
	1274.37	150.68	1163.65 1173.08	1123.68	12.87	OSF1.50	10000.00	9978.63				MinPt-O-SF	
	1509.81	454.94	1205.69	1054.88	5.00	OSF1.50	16750.00	10830.00	OSF<5.00			Enter Alert	
	1509.84	723.92	1026.40	785.92	3.13	OSF1.50	20966.71	10830.00				MinPts	
Coterra Loosey Goosey 4-9 Fer Corn 304H Rev0 kFc 04Feb22 (Def Plan)												W	/arning Alert
	40.00	32.49	37.50	7.50	N/A	MAS = 9.90 (m)	0.00	0.00	CtCt<=15m<15.00			Enter Alert	
	39.99 39.99	32.49 32.49	37.49 25.08	7.50 7.50	N/A 3.02	MAS = 9.90 (m) MAS = 9.90 (m)	22.00 1300.00	22.00 1300.00				WRP MinPts	
	40.14	32.49	24.93	7.64	2.96	MAS = 9.90 (m)	1330.00	1330.00				MINPT-O-EOU	
	41.33 88.88	32.49 32.49	25.53 69.06	8.83 56.38	2.92 4.99	MAS = 9.90 (m) MAS = 9.90 (m)	1390.00 1830.00	1390.00 1829.96	OSF>5.00			MinPt-O-SF Exit Alert	
	131.27	32.49	110.01	98.78	6.86	MAS = 9.90 (m)	2000.01	1999.46	00.10.00			MinPts	
	1413.79	176.54	1295.26	1237.25	12.16	OSF1.50	11308.89	10830.00	005<5.00			MinPt-CtCt Enter Alert	
	1413.80 1413.80	426.10 759.30	1128.90 906.77	987.70 654.50	5.00 2.80	OSF1.50 OSF1.50	15970.00 20966.71	10830.00 10830.00	OSF<5.00			Enter Alert MinPts	
30-025-33247 - Hudson Federa 5 INC Only to 8300ft - A (Def	al	_											
Survey)													arning Alert
	970.54 970.35	32.81 32.81	968.04 967.80	937.73 937.55	N/A 17465.63	MAS = 10.00 (m) MAS = 10.00 (m)	0.00 22.00	0.00 22.00				Surface WRP	
	967.41	32.81	946.60	934.60	52.70	MAS = 10.00 (m)	560.00	560.00				MinPts	
	975.18 968.70	56.14 72.63	936.92 919.45	919.03 896.08	27.20 20.67	OSF1.50 OSF1.50	1030.00 1370.00	1030.00 1370.00				MINPT-O-EOU MinPt-CtCt	
		. 2.00	2.10.10	200.00	_0.01	33. 1.00	. 5. 0.00					0.01	

Offset Trajectory		Separation		Allow	Sep.	Controlling	Reference			Risk Level			Alert	Status
	732.66	221.57	EOU (ft) 584.11	Dev. (ft) 511.09	Fact. 5.00	Rule OSF1.50	MD (ft) 4220.00	TVD (ft) 4207.29	Alert OSF<5.00	Minor		Major	Enter Alert	
	561.33 563.88	312.89 406.69	351.91 291.92	248.44 157.19	2.70 2.08	OSF1.50 OSF1.50	5960.00 7740.00	5938.64 7718.63					MinPt-CtCt MinPt-CtCt	
	568.96 928.21	438.43 282.07	275.84 739.33	130.53 646.14	1.95 4.97	OSF1.50 OSF1.50	8340.00 9070.00	8318.63 9048.63	OSF>5.00				MinPts Exit Alert	
	3457.11	319.39	3243.35	3137.72	16.35	OSF1.50	13450.00	10830.00	001 - 0.00				MinPt-O-SF	
	10192.95	440.84	9898.22	9752.11	34.87	OSF1.50	20966.71	10830.00					TD	
30-025-32819 - Hudson Feder 1 INC Only to 13750ft - A (Def Survey)														Warning Alert
ou.voy)	2401.43	32.81	2398.93	2368.63	N/A	MAS = 10.00 (m)	0.00	0.00					Surface	Training / tion
	2401.36 2401.32	32.81 32.81	2398.84 2398.81	2368.55 2368.51	200825.33 357869.99	MAS = 10.00 (m) MAS = 10.00 (m)	10.00 20.00	10.00 20.00					MinPt-O-SF MINPT-O-EOU	
	2401.32 2399.26	32.81 32.81	2398.81 2378.95	2368.51 2366.45	667794.33 134.60	MAS = 10.00 (m) MAS = 10.00 (m)	22.00 580.00	22.00 580.00					WRP MinPts	
	2265.03 2265.63	327.45 329.29	2045.90	1937.58 1936.34	10.44 10.39	OSF1.50 OSF1.50	6240.00 6310.00	6218.63 6288.63					MinPt-CtCt MINPT-O-EOU	
	2265.12	416.66	1986.52	1848.46	8.19	OSF1.50	7940.00	7918.63					MinPt-CtCt	
	2261.16 2261.87	484.90 487.05	1937.06 1936.34	1776.26 1774.82	7.02 6.99	OSF1.50 OSF1.50	9230.00 9310.00	9208.63 9288.63					MinPt-CtCt MINPT-O-EOU	
	2259.44 2260.67	518.83 522.55	1912.71 1911.47	1740.60 1738.12	6.56 6.51	OSF1.50 OSF1.50	9870.00 9990.00	9848.63 9968.63					MinPt-CtCt MINPT-O-EOU	
	1883.38 1208.41	568.27 579.49	1503.70 821.25	1315.12 628.92	4.99 3.14	OSF1.50 OSF1.50	11050.00 12500.00	10800.88 10830.00	OSF<5.00				Enter Alert MinPts	
	1208.46	579.57	821.25	628.90	3.13	OSF1.50	12510.00	10830.00					MinPt-O-ADP	
	1208.61 1919.93	579.64 579.71	821.34 1532.62	628.96 1340.21	3.13 4.98	OSF1.50 OSF1.50	12520.00 13990.00	10830.00 10830.00	OSF>5.00				MinPt-O-SF Exit Alert	
	8554.19	577.73	8168.21	7976.46	22.30	OSF1.50	20966.71	10830.00					TD	
30-025-32971 - Hudson Feder 2 INC Only to 8369ft - A (Def	ral													
Survey)	1364.48	32.81	1361.98	1331.67	N/A	MAS = 10.00 (m)	0.00	0.00					Surface	Warning Alert
	1364.35	32.81 47.70	1361.79 1324.70	1331.54 1309.63	21307.31	MAS = 10.00 (m) OSF1.50	22.00 940.00	22.00 940.00					WRP MinPt-CtCt	
	1357.33 1324.80	147.68	1225.51	1177.12	13.66	OSF1.50	2900.00	2894.52					MinPt-CtCt	
	1315.09 1305.01	182.56 205.13	1192.55 1167.43	1132.53 1099.88	10.93 9.64	OSF1.50 OSF1.50	3590.00 4020.00	3580.74 4008.39					MinPt-CtCt MinPt-CtCt	
	1305.41 1292.60	206.48 237.00	1166.93 1133.77	1098.93 1055.61	9.58 8.25	OSF1.50 OSF1.50	4070.00 4610.00	4058.11 4595.15					MINPT-O-EOU MinPt-CtCt	
	1279.40 1288.92	321.46	1064.26	957.94	6.01	OSF1.50	6200.00	6178.63	005.500				MinPt-CtCt	
	1283.52	388.86 425.31	1028.85 999.15	900.06 858.21	4.99 4.54	OSF1.50 OSF1.50	7480.00 8180.00	7458.63 8158.63	OSF<5.00				Enter Alert MinPt-CtCt	
	1284.65 1368.93	437.27 412.57	992.30 1093.05	847.38 956.36	4.42 5.00	OSF1.50 OSF1.50	8420.00 8880.00	8398.63 8858.63	OSF>5.00				MinPts Exit Alert	
	2599.46 2599.48	182.27 182.30	2477.12 2477.12	2417.20 2417.19	21.67 21.67	OSF1.50 OSF1.50	11520.00 11530.00	10830.00 10830.00					MinPt-CtCt MinPts	
	3361.01	318.98	3147.52	3042.03	15.92 33.65	OSF1.50	13650.00	10830.00					MinPt-O-SF	
Coterra Loosey Goosey 4-9 Fe	9798.34	439.15	9504.75	9359.20	33.05	OSF1.50	20966.71	10830.00					TD	
Com 302H Rev0 kFc 04Feb22 (Def Plan)														Warning Alert
	2588.41 2588.41	32.81 32.81	2585.91 2585.91	2555.60 2555.60	N/A N/A	MAS = 10.00 (m) MAS = 10.00 (m)	0.00 22.00	0.00 22.00					Surface WRP	
	1416.34	166.58	1304.45	1249.75	12.92	OSF1.50	10260.00	10238.63					MinPt-CtCt	
	1426.27 1437.32	429.86 793.85	1138.87 907.25	996.41 643.47	5.00 2.72	OSF1.50 OSF1.50	15510.00 20966.71	10830.00 10830.00	OSF<5.00				Enter Alert MinPts	
30-025-40328 - Chapparal 33														
Federal Com 4H MWD to 15306ft - A (Def Survey)														Pass
	4726.51 4726.60	32.81 32.81	4723.94 4723.98	4693.71 4693.79	62881.13 38089.45	MAS = 10.00 (m) MAS = 10.00 (m)	0.00 22.00	0.00 22.00					MinPts WRP	
	4788.06 4788.38	32.81 32.81	4775.04 4768.39	4755.26 4755.57	454.58 273.70	MAS = 10.00 (m) MAS = 10.00 (m)	1190.00 1760.00	1190.00 1760.00					MINPT-O-EOU MinPts	
	4788.49 4797.09	32.81 32.81	4768.28 4775.25	4755.68 4764.28	270.29 247.91	MAS = 10.00 (m) MAS = 10.00 (m)	1790.00 2000.01	1789.99 1999.46					MINPT-O-EOU MINPT-O-EOU	
	5017.54	78.80	4964.17 462.97	4938.74	98.59	OSF1.50	5130.00	5112.30					MinPt-O-ADP	
	578.52 578.80	172.06 172.42	463.02	406.45 406.38	5.10 5.09	OSF1.50 OSF1.50	10570.00 10580.00	10533.57 10542.09					MinPts MinPt-O-ADP	
	580.38 10771.19	173.06 176.59	464.17 10652.63	407.32 10594.60	5.08 92.79	OSF1.50 OSF1.50	10600.00 20966.71	10558.84 10830.00					MinPt-O-SF TD	
30-025-40253 - Chaparral `33 Federal Com St01 3 MWD to 15302ft - A (Def Survey)														Pass
.300Zit - A (Dei Sulvey)	4855.30	32.81	4852.75	4822.50	93383.03	MAS = 10.00 (m)	0.00	0.00					Surface	. 400
	4855.30 4823.43	32.81 32.81	4852.67 4803.69	4822.49 4790.63	36472.18 279.58	MAS = 10.00 (m) MAS = 10.00 (m)	22.00 1740.00	22.00 1740.00					WRP MinPts	
	4823.50 4834.63	32.81 32.81	4803.59 4812.65	4790.69 4801.82	276.98 247.98	MAS = 10.00 (m) MAS = 10.00 (m)	1760.00 2000.01	1760.00 1999.46					MINPT-O-EOU MINPT-O-EOU	
	1300.52	269.51	1120.01	1031.01	7.29	OSF1.50	10580.00	10542.09					MinPt-CtCt	
	1300.54 1300.72	269.61 269.70	1119.97 1120.08	1030.93 1031.02	7.29 7.29	OSF1.50 OSF1.50	10590.00 10600.00	10550.51 10558.84					MinPts MinPt-O-SF	
	10813.31	183.59	10690.09	10629.73	89.55	OSF1.50	20966.71	10830.00					TD	
30-025-33511 - Hudson Feder 8 INC Only to 8286ft - P (Def	ral													Pass
Survey)	2257.21	32.81	2254.71	2224.40	N/A	MAS = 10.00 (m)	0.00	0.00					Surface	1 600
	2257.16 2253.32	32.81 32.81	2254.46 2237.80	2224.35 2220.51	11177.98 172.91	MAS = 10.00 (m) MAS = 10.00 (m)	22.00 460.00	22.00 460.00					WRP MinPts	
	2252.92 1922.61	62.35 332.62	2210.52 1700.02	2190.57 1589.98	56.40 8.72	OSF1.50 OSF1.50	1240.00 6380.00	1240.00 6358.63					MinPt-CtCt MinPt-CtCt	
	1921.75 1921.76	415.55	1643.88 1643.34	1506.20 1505.37	6.97	OSF1.50	7970.00	7948.63					MinPt-CtCt	
	2868.25	416.39 113.00	2792.08	2755.25	38.90	OSF1.50 OSF1.50	7990.00 12510.00	7968.63 10830.00					MinPts MinPt-CtCt	
	2868.34 2868.75	113.23 113.72	2792.02 2792.10	2755.11 2755.03	38.82 38.66	OSF1.50 OSF1.50	12530.00 12560.00	10830.00 10830.00					MINPT-O-EOU MinPt-O-ADP	
	3893.97 8933.34	307.60 414.59	3688.07 8656.12	3586.37 8518.75	19.13 32.51	OSF1.50 OSF1.50	15140.00 20966.71	10830.00 10830.00					MinPt-O-SF TD	
													·=	

Offset Trajectory		Separation		Allow	Sep.	Controlling	Reference	Trajectory		Risk Level		Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)	Dev. (ft)	Fact.	Rule	MD (ft)	TVD (ft)	Alert	Minor	Major		
coterra Loosey Goosey 4-9 Fed com 301H Rev0 kFc 04Feb22 Def Plan)													Pass
	2569.94	32.81	2567.44	2537.13	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
_	2569.94	32.81	2567.44	2537.13	N/A	MAS = 10.00 (m)	22.00	22.00				WRP	
	2544.52	37.80	2518.49	2506.72	108.01	OSF1.50	2460.00	2456.93				MinPt-CtCt	
-	2556.08	71.43	2507.63	2484.66	55.57	OSF1.50	4370.00	4356.47				MINPT-O-EOU	
_	2570.74	89.00	2510.57	2481.74	44.54	OSF1.50	5340.00	5321.15				MinPt-O-ADP	
	2830.21	166.61	2718.30	2663.60	25.85	OSF1.50	10260.00	10238.63				MinPt-CtCt	
•	2851.14	793.16	2321.53	2057.98	5.40	OSF1.50	20966.71	10830.00				MinPts	
coterra Chapadoniz 33-28 Fed com 1H Rev0 kFc 04Feb22 Def Plan)													Pass
	2551.50	32.81	2549.00	2518.69	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
	2551.50	32.81	2549.00	2518.69	N/A	MAS = 10.00 (m)	22.00	22.00				WRP	
	2546.23	34.37	2522.48	2511.86	119.72	OSF1.50	2260.00	2258.03				MinPt-CtCt	
•	2546.80	36.12	2521.88	2510.67	113.51	OSF1.50	2390.00	2387.32				MINPT-O-EOU	
	2547.48	36.94	2522.02	2510.53	110.83	OSF1.50	2450.00	2446.99				MinPt-O-ADP	
	2882.47	164.46	2772.00	2718.02	26.67	OSF1.50	10300.00	10278.60				MINPT-O-EOU	
	2882.69	164.70	2772.05	2717.99	26.64	OSF1.50	10320.00	10298.52				MinPt-O-ADP	
	2950.77	172.17	2835.16	2778.61	26.07	OSF1.50	10930.00	10765.36				MinPt-O-SF	
	10968.77	233.51	10812.26	10735.26	71.21	OSF1.50	20966.71	10830.00				TD	

1. Geological Formations

MD at TD 20,966 Deepest expected fresh water

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone	Hazards
Rustler	1543	Useable Water	
Top Salt	1632	N/A	
Base Salt	3225	N/A	
Capitan	4838	N/A	
Lamar	5214	N/A	
Bell Canyon	5286	N/A	
Cherry Canyon	5740	N/A	
Brushy Canyon	6672	Hydrocarbons	
Bone Spring	8200	Hydrocarbons	
1st Bone Spring	9376	Hydrocarbons	
2nd Bone Spring	9928	Hydrocarbons	
3rd Bone Spring	10577	Hydrocarbons	

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	1593	1593	13-3/8"	48.00	H-40	ST&C	1.12	2.51	4.21
12 1/4	0	5236	5236	9-5/8"	40.00	HCK-55	LT&C	1.36	1.41	2.68
8 3/4	0	10258	10258	7"	29.00	L-80	LT&C	1.46	1.70	1.88
8 3/4	10258	11009	10791	7"	29.00	P-110	BT&C	1.69	2.22	60.10
6	9258	20966	10830	4-1/2"	11.60	P-110	BT&C	1.50	2.11	20.13
					BLM	Minimum Sa	afety Factor	1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Cimarex Energy Co., Loosey Goosey 4-9 Fed Com 303H

	Y or N
ls casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
s premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Υ
s well located within Capitan Reef?	N
f yes, does production casing cement tie back a minimum of 50' above the Reef?	N
s well within the designated 4 string boundary.	N
s well located in SOPA but not in R-111-P?	N
f yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
s well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
s 2nd string set 100' to 600' below the base of salt?	N
s well located in high Cave/Karst?	N
f yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
s well located in critical Cave/Karst?	N
f yes, are there three strings cemented to surface?	N
s AC Report included?	N

3. Cementing Program

Casing	# Sks	Wt. lb/gal	Yld ft3/sack	H2O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surface	772	13.50	1.72	9.15	15.5	Lead: Class C + Bentonite
	207	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Intermediate	980	12.90	1.88	9.65	12	Lead: 35:65 (Poz:C) + Salt + Bentonite
	292	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Production	320	10.30	3.64	22.18		Lead: Tuned Light + LCM
	127	14.80	1.34	6.32	9.5	Tail: Class C + LCM
			_			
Completion System	739	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS
			•			

Casing String	тос	% Excess
Surface	0	45
Intermediate	0	53
Production	5036	25
Completion System	10809	10

Cimarex request the ability to perform casing integrity tests after plug bump of cement job.

4. Pressure Control Equipment

A variance is requested for the use of a diverter on the surface casing. See attached for schematic.

BOP installed and tested before drilling which hole?	Size	Min Required WP	Туре		Tested To
12 1/4	13 5/8	2М	Annular	Х	
			Blind Ram		
			Pipe Ram		2M
			Double Ram	Х	
			Other		
8 3/4	13 5/8	3M	Annular	Х	
			Blind Ram		
			Pipe Ram		3M
			Double Ram	Х	
			Other		
6	13 5/8	5M	Annular	Х	
			Blind Ram		
			Pipe Ram		5M
			Double Ram	Х	
			Other		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

- X Formation integrity test will be performed per Onshore Order #2.
 On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed.
 Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
- X A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
 - Y Are anchors required by manufacturer?

5. Mud Program

Depth	Туре	Weight (ppg)	Viscosity	Water Loss
0' to 1593'	Fresh Water	7.83 - 8.33	28	N/C
1593' to 5236'	Brine Water	9.80 - 10.30	30-32	N/C
5236' to 11009'	Cut Brine or OBM	8.50 - 9.00	27-70	N/C
11009' to 20966'	ОВМ	8.50 - 9.00	50-70	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring

6. Logging and Testing Procedures

Logg	Logging, Coring and Testing								
	Will run GR/CNL fromTD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.								
Х	No logs are planned based on well control or offset log information.								
	Drill stem test?								
	Coring?								

Additional Laws Dlaws of	l Indonesia.
Additional Logs Planned	l Interval

7. Drilling Conditions

Condition	
BH Pressure at deepest TVD	5068 psi
Abnormal Temperature	No

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

X H2S is present

X H2S plan is attached

8. Other Facets of Operation

9. Wellhead

A multi-bowl wellhead system will be utilized.

After running the 13-3/8" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to working pressure, or a maximum test pressure of 5000 psi. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2.

The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office.

The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi.

A solid steel body pack-off will be utilized after running and cementing the production casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi.

All casing strings will be tested as per Onshore Order No.2 to atleast 0.22 psi/ft or 1,500 whichever is greater and not to exceed 70% of casing burst.

If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

10. Other Variances

Cimarex requests to perform offline cementing. OLC procedure as follows: 1.Land casing on solid body mandrel hanger. Engage packoff and lockring 2. Install BPV 3. Skid rig 4. Check for pressure and remove BPV 5. Circulate down casing, taking returns through casing valves 6. Pump lead and tail cement 7. Displace cement and bump the plug 8. Ensure floats are holding pressure 9. RD cement crew 10. Install BPV and TA cap.

Cimarex requests permission to skid the rig to the next well on the pad to begin operations instead of waiting 8 hours for surface cement to harden on this 303H well. Surface cement will be pumped, we will ensure floats hold, do a green cement test and then Skid to the next well on pad. We will not perform any operations on this 303H well until at least 8 hours and when both tail and lead slurry reach 500psi. The mandrel hanger is made up on the last joint of 13 3/8" casing and then lowered down with and landing joint. It is then lowered down until the mandrel contacts the landing ring which is prewelded to the conductor pipe. At this point the 13 3/8" casing is entirely supported by the conductor pipe via the landing ring / mandrel and is independent from the rig. This allows us to walk the rig away from the 303H well and begin work on the next well while the cement is hardening. There is no way for the casing to be moved or knocked off center since it is hanging from the landing ring.

Received by OCD: 1/29/2024 9:52:55 AM

Page 59 of 91

Cementing Operational Workflow

Conventional Cementing

- 1. Land casing on fluted mandrel hanger
- Circulate down casing, taking returns through BOP stack
- 3. Pump lead and tail cement
- 4. Displace cement and bump the plug
- 5. Ensure floats are holding pressure
- 6. RD cement crew
- 7. Install packoff to isolate pressure
- 8. Install BPV and skid rig


Offline Cementing

- 1. Land casing on **solid body** mandrel hanger
 - a) Engage packoff and lockring
- 2. Install BPV
- 3. Skid rig
- 4. Check for pressure and remove BPV
- 5. Circulate down casing, taking returns through casing valves
- 6. Pump lead and tail cement
- 7. Displace cement and bump the plug
- 8. Ensure floats are holding pressure
- 9. RD cement crew
- 10. Install BPV and TA cap

Received by OCD: 1/29/2024 9:52:55 AM Page 60 of 91

Conventional Cementing Equipment-Fluted Mandrel


- Fluted Hanger allows returns up past the hanger body
- Returns throughout cement job flow up through BOP stack and into flowline
- Packoff is installed <u>after</u> cement job to isolate pressure above and below hanger
- Lockring engaged during packoff installation



Page 61 of 91 Received by OCD: 1/29/2024 9:52:55 AM

Offline Cementing Equipment-Solid Body Mandrel Hanger


- Solid Body Mandrel Hanger allows for casing to be landed and pressure isolated in one step, prior to cementing
- Lockring is engaged to lock casing in place
- Casing is isolated and returns throughout cement job flow through the casing valves and through flowback iron independent of rig



Received by OCD: 1/29/2024 9:52:55 AM

Page 62 of 91

Conventional Cementing Flow Diagram






Received by OCD: 1/29/2024 9:52:55 AM

Page 63 of 91


Conventional Cementing Flow Diagram






CIMAREX ENERGY CO. NYSE LISTED: XEC

Offline Cementing -- Intermediate Casing



Released to Imaging: 2/6/2024 11:16:34 AM


Offline Cementing -- Intermediate Casing



Released to Imaging: 2/6/2024 11:16:34 AM

Received by OCD: 1/29/2024 9:52:55 AM Page 66 of 91

- Run 7" casing
- Land 11" nominal x 7" hanger
- Test casing hanger
- Energize 11" nom x 7" hanger lock ring and pull test
- Re-test casing hanger
- Barriers & Procedures after landing casing before setting packoff
 - 10K BOP & 5K Annular-Internal and Annular barrier
 - Kill Weight Fluid in annulus and casing (ensure well is static before setting solid body packoff) Internal and Annular barrier
 - If well is not static we WILL NOT set solid body packoff.
 - 10K float collar-Internal Barrier
 - 10k float Shoe-Internal Barrier
 - After circulating a 1.5 casing capacities to ensure full column of mud and no entrained gas pumps will be shut off and floats checked for flow






Received by OCD: 1/29/2024 9:52:55 AM

Page 67 of 91


- Pick up running tool with 6-1/2" nominal Back Pressure valve run into well and set
- Barriers and procedures <u>BEFORE</u> removing BOP's
 - Kill weight Fluid in annulus-Annular Barrier
 - Solid Body Packoff-Annular Barrier
 - 10K Float Equipment-Internal Barrier
 - 10K Back pressure valve installed with BOP still on well-Internal Barrier
 - BPV will be tested before it arrives on location by Cactus




Received by OCD: 1/29/2024 9:52:55 AM

Page 68 of 91

- Nipple down BOP
- Nipple up TA Cap and test
- Skid Drilling Rig
- Barriers and procedures <u>AFTER</u> removing BOP's
 - Kill weight Fluid in annulus-Annular Barrier
 - Solid Body Packoff-Annular Barrier
 - 10K Float Equipment-Internal Barrier
 - 10K Back pressure valve-Internal Barrier
 - 10K rated TA cap with Valve-Internal Barrier



- Check Pressure on TA Cap and remove
- Install adaptor with Gate valve for off line cementing and test
- Rig up flowback iron independent of rig
- Retrieve Back Pressure Valve
- Shut in well
- Rig up to cement and pump job
- NU 10K TA cap after cement job
- Barriers and procedures before rigging up cementing equipment
 - Address well and ensure no pressure on TA cap
 - Ability to pump into well through casing valves on backside to kill if needed
 - Kill weight Fluid in annulus-Annular barrier
 - Solid Body Packoff-Annular barrier
 - 10K Float Equipment-Internal Barrier
 - 10K Back pressure valve-Internal Barrier






Received by OCD: 1/29/2024 9:52:55 AM

Page 70 of 91

Offline Cementing Risk and COA Compliance

- All testing and breaks tested in accordance with Onshore Order # 2 and COA's
- If no cement to surface, bradenhead squeeze still possible with offline cementing equipment
- Time from skid rig to offline cementing ops typically 24 hours
- Conditions where we would not Offline Cement
 - Well is flowing
- All wellhead equipment equipment rated to 10K maintaining APD compliant
 - 10K flowback iron independent of rig circulating system
 - 10K Back Pressure Valve
 - 10K Gate Valve & TA combo for second barrier during operations
 - 10K 1-13/16 Valve coming off TA cap
 - 10K TA Cap

Co-Flex Hose Loosey Goosey 4-9 Fed Com 303H Cimarex Energy Co.





U.S. Department of the Interior BUREAU OF LAND MANAGEMENT SUPO Data Report

APD ID: 10400083867

Operator Name: CIMAREX ENERGY COMPANY

Well Name: LOOSEY GOOSEY 4-9 FED COM

Well Type: OIL WELL

Submission Date: 03/17/2022

Highlighted data reflects the most recent changes

Show Final Text

Well Number: 303H

Well Work Type: Drill

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

Loosey_Goosey_4_9_Fed_Com_W2E2_Existing_Acess_Road_20220315092108.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT Row(s) Exist? NO

ROW ID(s)

ID: NM137119

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

Loosey_Goosey_4_9_Fed_Com_W2E2_New_Access_Road_ROW_20220315092237.pdf

New road type: COLLECTOR

Length: 810 Feet

Width (ft.): 30

Max slope (%): 2

Max grade (%): 6

Army Corp of Engineers (ACOE) permit required? N

ACOE Permit Number(s):

New road travel width: 18

New road access erosion control: Water will be diverted where necessary to avoid ponding, prevent erosion, maintain good drainage, and to be consistent with local drainage patterns.

New road access plan or profile prepared? N

New road access plan

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Access road engineering design? N

Access road engineering design

Turnout? N

Access surfacing type: OTHER

Access topsoil source: ONSITE

Access surfacing type description: Caliche

Access onsite topsoil source depth: 6

Offsite topsoil source description:

Onsite topsoil removal process: Push off and stockpile alongside the location

Access other construction information: The operator will prevent and abate fugitive dust as needed created by vehicular

traffic, equipment operations or other events. Access miscellaneous information: N/a

Number of access turnouts: Access turnout map:

Drainage Control

New road drainage crossing: CULVERT,LOW WATER

Drainage Control comments: To control and prevent potentially contaminated precipitation from leaving the pad site, a perimeter berm and settlement pond will be installed. Contaminated water will be removed from pond, stored in waste tanks, and disposed of at a state approved facility. Standing water or puddles will not be allowed. Drainage ditches would be established and maintained on the pad and along access roads to divert water away from operations. Natural drainage areas disturbed during construction would be re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fiber rolls, water bars, silt fences, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be obliterated, re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fiber rolls, water bars, silt fences, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be obliterated, re-contoured, and reclaimed to near original condition to re-establish natural drainage.

Road Drainage Control Structures (DCS) description: N/A

Road Drainage Control Structures (DCS) attachment:

Access Additional Attachments

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

Loosey_Goosey_4_9_Fed_Com_W2E2_One_Mile_Radius_20220315092305.pdf

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description: Production from this well pad will be routed to the proposed Loosey Goosey 4-9 E2W2 Battery located in the SW of section 33 19S 34E .810' of new access road will be built. 9460' of offlease 3phase 4wire 40v overhead powerline will be built. 10325' of offlease bulklines will be built. 75' ROW width. Bulklines/Flowlines will consist of 1 12" Steel flowline carrying oil gas and water. 4 12" steel lines carrying oil gas or water. 1 4" fiber optic cable. 1 12" air poly line. We will also be utilitizing a temporary fresh water line. 1- 12" temporary layflat poly Fresh water line. 5 miles in length.

Production Facilities map:

Mighty_Loosey_Chap_Bulkline_ROW_20220301143616.pdf
Mighty_Loosey_Chap_Power_ROW_20220301143624.pdf
Loosey_Goosey_4_9_Fed_Com_W2E2_Temp_Water_Route_20220315095022.pdf
Mighty_Chapadoniz_and_Loosey_Goosey_E2W2_On_Pad_Battery_20220317082240.pdf
Loosey_Goosey_4_9_Fed_Com_W2E2_SUPO_20220317082248.pdf

Section 5 - Location and Types of Water Supply

Water Source Table

Water source type: MUNICIPAL

Water source use type: SURFACE CASING

INTERMEDIATE/PRODUCTION

CASING

Source latitude: Source longitude:

Source datum:

Water source permit type: WATER RIGHT

Permit Number:

Water source transport method: TRUCKING

Source land ownership: FEDERAL

Source transportation land ownership: FEDERAL

Water source volume (barrels): 5000 Source volume (acre-feet): 0.64446548

Source volume (gal): 210000

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Water source and transportation

Loosey_Goosey_4_9_Drilling_Water_Route_20220315095044.pdf

Water source comments:

New water well? N

New Water Well Info

Well latitude: Well Longitude: Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft): Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft): Well casing type:

Well casing outside diameter (in.): Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method: Drill material:

Grout material: Grout depth:

Casing length (ft.): Casing top depth (ft.):

Well Production type: Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Using any construction materials: YES

Construction Materials description: Caliche will be obtained from the actual well site if available. If not available onsite caliche will be obtained for a pit located in SESW SWSE of Sec. 25 19S 33E & SW of Sec 13 19S 33E

Construction Materials source location

Section 7 - Methods for Handling

Waste type: DRILLING

Waste content description: Drilling Fluids, drill cuttings, water and other waste produced from the well during drilling

operations.

Amount of waste: 15000 barrels

Waste disposal frequency: Weekly Safe containment description: N/A

Safe containment attachment:

Received by OCD: 1/29/2024 9:52:55 AM

Page 76 of 91

Operator Name: CIMAREX ENERGY COMPANY

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Waste disposal type: HAUL TO COMMERCIAL Disposal location ownership: COMMERCIAL

FACILITY

Disposal type description:

Disposal location description: Haul to R360 Environmental Solutions, 4507 Carlsbad Hwy, Hobbs, NM 88240

Waste type: SEWAGE

Waste content description: Human Waste

Amount of waste: 300 gallons

Waste disposal frequency: Weekly

Safe containment description: Waste will be properly contained and disposed of properly at a state approved disposal

facility.

Safe containment attachment:

Waste disposal type: HAUL TO COMMERCIAL Disposal location ownership: PRIVATE

FACILITY

Disposal type description:

Disposal location description: A licensed 3rd party contractor will be used to haul and dispose human waste to City of

Toyah TX waste water facility.

Waste type: GARBAGE

Waste content description: Garbage and trash produced during drilling and completion operations

Amount of waste: 32500 pounds

Waste disposal frequency: Weekly
Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL Disposal location ownership: COMMERCIAL

FACILITY

Disposal type description:

Disposal location description: A licensed 3rd party hauls trash to Lea County Landfill

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit? NO

Reserve pit length (ft.) Reserve pit width (ft.)

Reserve pit depth (ft.)

Reserve pit volume (cu. yd.)

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? N

Description of cuttings location

Cuttings area length (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Section 8 - Ancillary

Are you requesting any Ancillary Facilities?: N

Ancillary Facilities

Comments:

Section 9 - Well Site

Well Site Layout Diagram:

Loosey_Goosey_4_9_W2E2_Well_List_20220315095530.docx

Loosey_Goosey_4_9_Fed_Com_303H_Wellsite_Layout_20220315132933.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance Multiple Well Pad Name: Loosey Goosey 4-9 Fed Com

Multiple Well Pad Number: W2E2

Cuttings area width (ft.)

Recontouring

Loosey_Goosey_4_9_Fed_Com_W2E2_Interim_reclaim_20220315095553.pdf

Drainage/Erosion control construction: To control and prevent potentially contaminated precipitation from leaving the pad site, a perimeter berm and settlement pond will be installed. Contaminated water will be removed from pond, stored in waste tanks, and disposed of at a state approved facility. Standing water or puddles will not be allowed. Drainage ditches would be established and maintained on the pad and along access roads to divert water away from operations. Natural drainage areas disturbed during construction would be re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fiber rolls, water bars, silt fences, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be obliterated, re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fiber rolls, water bars, silt

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

fences, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be obliterated, re-contoured, and reclaimed to near original condition to re-establish natural drainage.

Drainage/Erosion control reclamation: All disturbed and re-contoured areas would be reseeded according to specifications. Approved seed mixtures would be certified weed free and consist of grasses, forbs, or shrubs similar to the surrounding area. Compacted soil areas may need to be obliterated and reclaimed to near natural conditions by recontouring all slopes to facilitate and re-establish natural drainage.

Well pad proposed disturbance

(acres): 7.449

Road proposed disturbance (acres):

Powerline proposed disturbance

Pipeline proposed disturbance

(acres): 17.78

(acres): 6.512

Pipeline interim reclamation (acres): 0 Pipeline long term disturbance

Road interim reclamation (acres): 0

Other proposed disturbance (acres): 0 Other interim reclamation (acres): 0

Well pad interim reclamation (acres): Well pad long term disturbance

(acres): 4.223

Road long term disturbance (acres):

0.558

Powerline interim reclamation (acres): Powerline long term disturbance

(acres): 6.512

(acres): 17.78

Other long term disturbance (acres): 0

Total proposed disturbance: 32.299 Total interim reclamation: 2.668 Total long term disturbance: 29.073

2.668

Disturbance Comments:

Reconstruction method: After well plugging, all disturbed areas would be returned to the original contour or a contour that blends with the surrounding landform including roads unless the surface owner requests that they be left intact. In consultation with the surface owners it will be determined if any gravel or similar materials used to reinforce an area are to be removed, buried, or left in place during final reclamation. Salvaged topsoil, if any, would be re-spread evenly over the surfaces to be re-vegetated. As necessary, the soil surface would be prepared to provide a seedbed for re-establishment of desirable vegetation. Site preparation may include gouging, scarifying, dozer track-walking, mulching, or fertilizing. Reclamation, Re-vegetation, and Drainage: All disturbed and re-contoured areas would be reseeded using techniques outlined under Phase I and II of this plan or as specified by the land owner. Approved seed mixtures would be certified weed free and consist of grasses, forbs, or shrubs similar to the surrounding area. Compacted soil areas may need to be obliterated and reclaimed to near natural conditions by re-contouring all slopes to facilitate and re-establish natural drainage.

Topsoil redistribution: The original stock piled topsoil, if any, will be spread evenly over the areas being reclaimed and the original landform will be restored for all disturbed areas including well pad, production facilities, roads, pipelines, and power line corridors as close as possible to the original topography. The location will then be seeded

Soil treatment: The soil surface would be prepared to provide a seedbed for reestablishment of desirable vegetation. Establish control of erosion and invasion of non-native plants to reestablish plant community.

Existing Vegetation at the well pad: N/A

Existing Vegetation at the well pad

Existing Vegetation Community at the road: N/A

Existing Vegetation Community at the road

Existing Vegetation Community at the pipeline: N/A

Existing Vegetation Community at the pipeline

Existing Vegetation Community at other disturbances: N/A

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Existing Vegetation Community at other disturbances

Non native seed used? N

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? N

Seedling transplant description

Will seed be harvested for use in site reclamation? N

Seed harvest description:

Seed harvest description attachment:

Seed

Seed Table

Seed Summary
Seed Type Pounds/Acre

Total pounds/Acre:

Seed reclamation

Operator Contact/Responsible Official

First Name: Amithy Last Name: Crawford

Phone: (432)620-1909 Email: amithy.crawford@coterra.com

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? N

Existing invasive species treatment description:

Existing invasive species treatment

Weed treatment plan description: N/A

Weed treatment plan

Monitoring plan description: N/A

Monitoring plan

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Success standards: N/A

Pit closure description: N/A

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: PIPELIN	ΙE
---------------------------	----

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT, STATE GOVERNMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office: NMSLO

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland: USFS Ranger District:

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Operator Name: CIMAREX ENERGY COMPANY	
Well Name: LOOSEY GOOSEY 4-9 FED COM	Well Number: 303H
Military Local Office:	
USFWS Local Office:	
Other Local Office:	
USFS Region:	
USFS Forest/Grassland:	USFS Ranger District:
Disturbance type: TRANSMISSION LINE	
Describe:	
Surface Owner: BUREAU OF LAND MANAGEMENT, STATE	GOVERNMENT
Other surface owner description:	
BIA Local Office:	
BOR Local Office:	
COE Local Office:	
DOD Local Office:	
NPS Local Office:	
State Local Office: NMSLO	
Military Local Office:	
USFWS Local Office:	
Other Local Office:	
USFS Region:	
USFS Forest/Grassland:	USFS Ranger District:
Disturbance type: NEW ACCESS ROAD	
Describe:	
Surface Owner: BUREAU OF LAND MANAGEMENT	
Other surface owner description:	
BIA Local Office:	

BOR Local Office: COE Local Office:

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Section 12 - Other

Right of Way needed? Y

Use APD as ROW? Y

ROW Type(s): 281001 ROW - ROADS,288100 ROW - O&G Pipeline,289001 ROW- O&G Well Pad,FLPMA (Powerline)

ROW

SUPO Additional Information:

Use a previously conducted onsite? N

Previous Onsite information:

Other SUPO

Cimarex Loosey Goosey 4-9 Fed Com W2E2 Surface Use Plan

Upon approval of the Application for Permit to Drill (APD) the following surface use plan of operations will be followed and carried out. The surface use plan outlines the proposed surface disturbance. If any other disturbance is needed after the APD is approved, a BLM sundry notice or right of way application will be submitted for approval prior to any additional surface disturbance.

Existing Roads

- Directions to location Exhibit A.
- Public access route Exhibit B.
- Existing access road for the proposed project. Please see Exhibit B and C.
- Cimarex Energy will:
 - Improve and/or maintain existing road(s) condition the same as or better than before the operations began.
 - Provide plans for improvement and /or maintenance of existing roads if requested.
 - Repair or replace damaged or deteriorated structures as needed. Including cattle guards and culverts.
 - Prevent and abate fugitive dust as needed, whether created by vehicular traffic, equipment operations, or other events.
 - Obtain written BLM approval prior to the application of surfactants, binding agents, or other dust suppression chemicals on the roadways.
- The maximum width of the driving surface will be 18'. The road will be crowned and ditched with a 2% slope from the tip of the
 crown to the edge of the driving surface. The ditches will be 1' deep with 3:1 slopes. The driving surface will be made of 6"
 rolled and compacted caliche.

New or Reconstructed Access Roads

Cimarex Energy plans to construct a new off-lease access road

- Length: 810'
- Width: 30'
- Road Plat Exhibit D.
- A ROW will be submitted to the BLM for approval.
- Cimarex Energy will complete improvements to the driving surface as needed.
- The maximum width of the driving surface for all roads above will be 18'.
- The road will be crowned and ditched with a 2% slope from the tip of the crown to the edge of the driving surface.
- The ditches will be 1' deep with 3:1 slopes.
- The driving surface will be made of 6" rolled and compacted caliche.
- Cimarex Energy will prevent and abate fugitive dust as needed, whether created by vehicular traffic, equipment operations, or other events.

Well Radius Map

Please see Exhibit E for wells within one mile or proposed well SHL and BHL.

Proposed or Existing Production Facility

A new facility will be constructed for this project if the well is productive.

- Loosey Goosey 4-9 E2W2 CTB Exhibit F
 - Direction to facility
 - Facility pad location layout and cut and fill
 - Facility pad archeological boundary
 - Facility pad flowline corridor
 - Facility pad access road

Gas Pipeline Specifications

• No new gas pipelines are required for this project.

Salt Water Disposal Specifications

· No new SWD pipelines are required for this project.

Power Lines

Cimarex Loosey Goosey 4-9 Fed Com W2E2 Surface Use Plan

- Cimarex plans to construct an off-lease power line to service the Mighty Pheasant wells.
- Overhead power line from an existing power source located in the .
- Length: 9,460'.
- Poles: 34
- Specifications: 480 volt, 4 wire, 3 phase.
- Please see Exhibit I for proposed route.
- A ROW application will be submitted to the BLM for the proposed route.

Well Site Location

- Proposed well pad/location layout Exhibit J.
- Proposed Rig layout Exhibit K
 - The rig layout, including V-door and flare line may change depending on rig availability. The pad dimensions and
 orientation will remain the same. No additional disturbance is anticipated if a rig layout change is necessary to
 accommodate the drilling rig. If additional disturbance is required a sundry notice will be submitted to the BLM for
 approval.
 - Mud pits in the closed circulation system will be steel pits and the cuttings will be stored in the steel containment pits.
 - Cuttings will be stored in steel pits until they are hauled to a state-approved disposal facility.
- Archeological boundary Exhibit L
- Multi well pad: 204H 303H 304H 104H 203H 103H
- Pad Size: 500 x 560
- · Construction Material
 - If possible, native caliche will be obtained from the excavation of drill site. The primary way of obtaining caliche will be by "turning over" the location. This means caliche will be obtained from the actual well site. A caliche permit will be obtained from BLM prior to pushing up any caliche. 2,400 cu yds is the max amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:
 - The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
 - An approximate 120' x 120' area is used within the proposed well site to remove caliche.
 - Subsoil is removed and piled alongside the 120' x 120' area within the pad site.
 - When caliche is found, material will be stockpiled within the pad site to build the location and road.
 - Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
 - Once well is drilled, the stockpiled top soil will be used for interim reclamation and spread along areas where
 caliche is picked up and the location size is reduced. Neither caliche nor subsoil will be stockpiled outside of the
 well pad. Topsoil will be stockpiled along the edge of the pad as depicted in Exhibit J Layout Diagram.
 - Caliche will be obtained from the actual well site if available. If not available onsite caliche will be obtained for a pit located in SESW SWSE of Sec. 25 19S 33E & SW of Sec 13 19S 33E
 - Mud pits in the closed circulation system will be steel pits and the cuttings will be stored in steel containment pits.
- Cuttings will be stored in steel pits until they are hauled to a state-approved disposal facility.
- If the well is a producer, those areas of the location not essential to production facilities will be reclaimed and seeded per BLM requirements. Exhibit P: Interim Reclamation Diagram.
- There are no known dwellings within 1.5 miles of this location.

Bulkline/Flowline Pipelines

All proposed pipelines will be constructed in a 75' ROW corridor.

- Bulklines/Flowlines
- Cimarex Energy plans to construct off-lease Bulklines to service the well.
- 1 12" Steel Flowline carrying oil gas and water
- 4 12" steel bulklines carrying oil gas or water
- 1 4" fiber optic cable
- 1 12" Air poly line
- Length: 10,325'.
- MAOP: 1,500 psi; Anticipated working pressure: 200-300 psi.
- Please see Exhibit M for proposed off-lease route.
- A ROW application will be submitted to the BLM for the proposed route.

Cimarex Loosey Goosey 4-9 Fed Com W2E2 Surface Use Plan

Water Resources

1- 12" temporary layflat poly fresh water line. 5 miles in length.

Methods of Handling Waste

- Drilling fluids, produced oil, and water from the well during drilling and completion operations will be stored safely and disposed of properly in a NMOCD approved disposal facility.
- Garbage and trash produced during drilling and completion operations will be collected in a trash container and disposed of properly at a state approved disposal facility. All trash on and around well site will be collected for disposal.
- · Human waste and grey water will be contained and disposed of properly at a state approved disposal site.
- After drilling and completion operations, trash, chemicals, salts, frac sand and other waste will be removed and disposed of properly at a state approved disposal site.
- The well will be drilled utilizing a closed loop system. Drill cuttings will be properly disposed of into steel tanks and taken to an NMOCD approved disposal facility.

Ancillary Facilities

No camps or airstrips to be constructed.

Interim and Final Reclamation

- Rehabilitation of the location will start in a timely manner after all proposed drilling wells have been drilled from the pad or if drilling operations have ceased as outlined below:
 - No approved or pending drill permits for wells located on the drill pad
 - No drilling activity for 5 years from the drill pad
- Surfacing materials will be removed and returned to a mineral pit or recycled to repair or build roads and well pads.
- Drainage systems, if any, will be reshaped to the original configuration with provisions made to alleviate erosion. These may need to be modified in certain circumstances to prevent inundation of the location's pad and surface facilities. After the area has been shaped and contoured, topsoil from the spoil pile will be placed over the disturbed area to the extent possible. Revegetation procedures will comply with BLM standards.
- Exhibit P illustrates the proposed Surface Reclamation plans after cessation of drilling operations as outlined above.
 - The areas of the location not essential to production facilities and operations will be reclaimed and seeded per BLM requirements.
- Operator will amend the surface reclamation plan if well is a dry hole and/or a single well pad.

Surface Ownership

- The wellsite is on surface owned by NMSLO.
- A copy of Surface Use Agreement has been given to the surface owner.
- The land is used mainly for farming, cattle ranching, recreational use, and oil and gas production.

Cultural Resource Survey - Archeology

 Cultural Resources Survey will be conducted for the entire project as proposed in the APD and submitted to the BLM for review and approval.

On Site Notes and Information:

Location was droned



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

PWD Data Report

APD ID: 10400083867 **Submission Date:** 03/17/2022

Operator Name: CIMAREX ENERGY COMPANY

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Well Type: OIL WELL Well Work Type: Drill

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined

Would you like to utilize Lined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit

Pit liner description:

Pit liner manufacturers

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule

Lined pit reclamation description:

Lined pit reclamation

Leak detection system description:

Leak detection system

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Lined pit Monitor description:

Lined pit Monitor

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information

Section 3 - Unlined

Would you like to utilize Unlined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD disturbance (acres):

PWD surface owner:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule

Unlined pit reclamation description:

Unlined pit reclamation

Unlined pit Monitor description:

Unlined pit Monitor

Do you propose to put the produced water to beneficial use?

Beneficial use user

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic

State

Unlined Produced Water Pit Estimated

Unlined pit: do you have a reclamation bond for the pit?

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information

Section 4 -

Would you like to utilize Injection PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner: PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number: Injection well name:

Assigned injection well API number? Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection

Underground Injection Control (UIC) Permit?

UIC Permit

Section 5 - Surface

Would you like to utilize Surface Discharge PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner: PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 -

Would you like to utilize Other PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner: PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Well Name: LOOSEY GOOSEY 4-9 FED COM Well Number: 303H

Other PWD type description:

Other PWD type

Have other regulatory requirements been met?

Other regulatory requirements



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Bond Info Data

APD ID: 10400083867

Operator Name: CIMAREX ENERGY COMPANY

Well Name: LOOSEY GOOSEY 4-9 FED COM

Well Type: OIL WELL

Submission Date: 03/17/2022

Highlighted data reflects the most recent changes Show Final Text

Well Number: 303H

Well Work Type: Drill

Bond

Federal/Indian APD: FED

BLM Bond number: NMB001188

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

District II 811 S. First St., Artesia, NM 88210 Phone:(575) 748-1283 Fax:(575) 748-9720

District III 1000 Rio Brazos Rd., Aztec, NM 87410 Phone:(505) 334-6178 Fax:(505) 334-6170

1220 S. St Francis Dr., Santa Fe, NM 87505 Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. **Santa Fe, NM 87505**

CONDITIONS

Action 308878

CONDITIONS

Operator:	OGRID:
CIMAREX ENERGY CO.	215099
6001 Deauville Blvd Midland, TX 79706	Action Number: 308878
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
pkautz	Will require a File As Drilled C-102 and a Directional Survey with the C-104	2/6/2024
pkautz	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	2/6/2024
pkautz	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system	2/6/2024
pkautz	Cement is required to circulate on both surface and intermediate1 strings of casing	2/6/2024
pkautz	If cement does not circulate on any string, a CBL is required for that string of casing	2/6/2024