

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit one copy to appropriate District Office

☐ AMENDED REPORT

I. REQUEST FOR ALLOWABLE AND AUTHORIZATION TO TRANSPORT

¹ Operator name and Address OXY USA INC. PO BOX 50250 MIDLAND, TX 79710				² OGRID Number 16696	
				³ Reason for Filing Code/ Effective Date NW - 10/02/2023	
⁴ API Number 30 - 025-48939		⁵ Pool Name ANTELOPE RIDGE; WOLFCAMP			⁶ Pool Code 2220
⁷ Property Code 330848		⁸ Property Name SAKER 6 7 FEDERAL COM			⁹ Well Number 038H

II. ¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South Line	Feet from the	East/West line	County
1	6	24S	35E		180	North	850	East	Lea

¹¹ Bottom Hole Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	7	24S	35E		29	South	526	East	Lea
¹² Lse Code F	¹³ Producing Method Code F	¹⁴ Gas Connection Date 10/2/2023	¹⁵ C-129 Permit Number		¹⁶ C-129 Effective Date		¹⁷ C-129 Expiration Date		

III. Oil and Gas Transporters


¹⁸ Transporter OGRID	¹⁹ Transporter Name and Address	²⁰ O/G/W
237722	Centerion Pipeline L.P.	O
248749	DCP Midstream, LP	G

IV. Well Completion Data

²¹ Spud Date 06/06/2023	²² Ready Date 10/02/2023	²³ TD 22020' MD, 12074' TVD	²⁴ PBTD 21976' MD, 12066' TVD	²⁵ Perforations 11945'-21761', Wolfcamp	²⁶ DHC, MC
²⁷ Hole Size		²⁸ Casing & Tubing Size		²⁹ Depth Set	³⁰ Sacks Cement
17 1/2"		13 3/8" 54.5# J-55		1111'	1620sx Class C - TOC 0'
12 1/4"		7 5/8" 29.7# HCL80		11010'	5862sx Class H - TOC 0'
6 3/4"		5 1/2" 20# P110		22000'	793sx Class H- TOC 0'

V. Well Test Data

³¹ Date New Oil 11/15/2023	³² Gas Delivery Date 11/15/2023	³³ Test Date 11/19/2023	³⁴ Test Length 24 hours	³⁵ Tbg. Pressure 0	³⁶ Csg. Pressure 966
³⁷ Choke Size 0	³⁸ Oil 2692	³⁹ Water 4225	⁴⁰ Gas 2347		⁴¹ Test Method Flowing

⁴² I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief. Signature: 		OIL CONSERVATION DIVISION	
Printed name: Sarah McKinney		Approved by:	
Title: Regulatory Analyst Sr.		Title:	
E-mail Address: sarah_mckinney@oxy.com		Approval Date:	
Date: 12/07/2023	Phone: 713-215-7295		

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☒ AMENDED REPORT

As-Drilled Plat

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-48939	² Pool Code 2220	³ Pool Name Antelope Ridge; Wolfcamp
⁴ Property Code 330848	⁵ Property Name SAKER 6 7 FED COM	⁶ Well Number 38H
⁷ OGRID No. 16696	⁸ Operator Name OXY USA INC.	⁹ Elevation 3450.8' (NAVD 88)

¹⁰ Surface Location

UL or lot no. 1	Section 6	Township 24S	Range 35E	Lot Idn	Feet from the 180	North/South line NORTH	Feet from the 850	East/West line EAST	County LEA
--------------------	--------------	-----------------	--------------	---------	----------------------	---------------------------	----------------------	------------------------	---------------

¹¹ Bottom Hole Location If Different From Surface

UL or lot no. P	Section 7	Township 24S	Range 35E	Lot Idn	Feet from the 29	North/South line SOUTH	Feet from the 526	East/West line EAST	County LEA
¹² Dedicated Acres 640.06	¹³ Joint or Infill Infill	¹⁴ Consolidation Code	¹⁵ Order No.						

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

¹⁶ NAD 83 (SURFACE HOLE LOCATION) LATITUDE = 32°15'11.97" (32.253324°) LONGITUDE = -103°24'03.22" (-103.400894°) NAD 27 (SURFACE HOLE LOCATION) LATITUDE = 32°15'11.52" (32.253199°) LONGITUDE = -103°24'01.51" (-103.400420°) STATE PLANE NAD 83 (N.M. EAST) N: 457144.47' E: 829590.65' STATE PLANE NAD 27 (N.M. EAST) N: 457085.08' E: 788406.07'	NAD 83 (AS-DRILLED KOP) LATITUDE = 32°15'13.55" (32.253765°) LONGITUDE = -103°24'00.12" (-103.400033°) NAD 27 (AS-DRILLED KOP) LATITUDE = 32°15'13.10" (32.253640°) LONGITUDE = -103°23'58.42" (-103.399560°) STATE PLANE NAD 83 (N.M. EAST) N: 457307.09' E: 829855.34' STATE PLANE NAD 27 (N.M. EAST) N: 457247.70' E: 788670.74'	NAD 83 (AS-DRILLED FTP) LATITUDE = 32°15'08.69" (32.252413°) LONGITUDE = -103°23'59.57" (-103.399879°) NAD 27 (AS-DRILLED FTP) LATITUDE = 32°15'08.24" (32.252288°) LONGITUDE = -103°23'57.86" (-103.399406°) STATE PLANE NAD 83 (N.M. EAST) N: 456815.69' E: 829907.15' STATE PLANE NAD 27 (N.M. EAST) N: 456756.31' E: 788722.54'
NAD 83 (AS-DRILLED LPP) LATITUDE = 32°14'21.48" (32.239300°) LONGITUDE = -103°23'59.47" (-103.399853°) NAD 27 (AS-DRILLED LPP) LATITUDE = 32°14'21.03" (32.239175°) LONGITUDE = -103°23'57.77" (-103.399380°) STATE PLANE NAD 83 (N.M. EAST) N: 452045.23' E: 829956.72' STATE PLANE NAD 27 (N.M. EAST) N: 451985.98' E: 788771.93'	NAD 83 (AS-DRILLED LTP) LATITUDE = 32°13'32.04" (32.225566°) LONGITUDE = -103°23'59.44" (-103.399845°) NAD 27 (AS-DRILLED LTP) LATITUDE = 32°13'31.59" (32.225440°) LONGITUDE = -103°23'57.74" (-103.399373°) STATE PLANE NAD 83 (N.M. EAST) N: 447048.68' E: 830002.68' STATE PLANE NAD 27 (N.M. EAST) N: 446989.56' E: 788817.66'	NAD 83 (AS-DRILLED BHL) LATITUDE = 32°13'29.51" (32.224863°) LONGITUDE = -103°23'59.16" (-103.399767°) NAD 27 (AS-DRILLED BHL) LATITUDE = 32°13'29.05" (32.224737°) LONGITUDE = -103°23'57.46" (-103.399295°) STATE PLANE NAD 83 (N.M. EAST) N: 446793.08' E: 830028.97' STATE PLANE NAD 27 (N.M. EAST) N: 446733.97' E: 788843.94'

17 OPERATOR
CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Sarah McKinney

Signature

12/6/23

Date

Sarah McKinney

Printed Name

sarah_mckinney@oxy.com

E-mail Address

18 SURVEYOR
CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

December 12, 2019

Date of Survey

Signature and Seal of Professional Surveyor:

PAUL BUCHELE
NEW MEXICO
23782
10-16-23
PROFESSIONAL SURVEYOR

Certificate Number:

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S89°41'56"W	2640.30'
L2	S89°45'26"W	2646.85'

APPROXIMATE WELL BORE DISTANCE FROM FTP TO LTP	
TRACT	DISTANCE
FEE	4,780.63'
NMNM 014164	5,017.42'
TOTAL	9,798.05'

NOTE:

- Distances referenced on plat to section lines are perpendicular.
- Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD 83)
- As-Drilled well head has not been field verified.
- Well Bore data provided by Oxy USA Inc.

SCALE
DRAWN BY: Z.L. 10-03-23
REV: 1 Z.L. 10-16-23 (UPDATE HSU)

Received by OCD: 12/14/2023 9:56:27 AM

Released to Imaging: 3/6/2024 10:34:45 AM



Oxy Saker 6-7 Fed Com 38H HRGM+IFR1 to 22020ft Survey Geodetic Report



DefinitiveSurvey

Report Date: August 16, 2023 - 03:36 PM (UTC 0)
Client: OXY
Field: NM Lea County (NAD 83)
Structure / Slot: Oxy Saker 6-7 Fed Com Pad Lot 1 / Saker 6-7 Fed Com Pad 38H
Well: Saker 6-7 Fed Com 38H
Borehole: Saker 6-7 Fed Com 38H
UBHI / API / JobNumber: Unknown / Unknown / Unknown
Survey Name / Version: Oxy Saker 6-7 Fed Com 38H HRGM+IFR1 to 22020ft / 9
Survey Date: August 11, 2023
Tort / AHD / DDI / ERD Ratio: 329.867 ' / 10962.379 ft / 6.819 / 0.908
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: N 32°15'11.96755" , W 103°24'3.21724"
Location Grid N/E Y/X: N 457144.470 ftUS , E 829590.650 ftUS
CRS Grid Convergence Angle: 0.498°
Grid Scale Factor: 1.00000425
Engine Version: 2023.1.0.1

Survey / DLS Computation: Minimum Curvature / Lubinski
Vertical Section Azimuth: 177.575 °(Grid North)
Vertical Section Origin: 0.000 ft, 0.000 ft
TVD Reference Datum: RKB
TVD Reference Elevation: 3474.800 ft above MSL
Seabed / Ground Elevation: 3450.800 ft above MSL
Magnetic Declination: 6.299°
Total Gravity Field Strength: 998.4648mgn (9.80665 Based)
Gravity Model: GARM
Total Magnetic Field Strength: 47518.5 nT
Magnetic Dip Angle: 59.827°
Declination Date: July 27, 2023
Magnetic Declination Model: IFR1
North Reference: Grid
Total Corr Mag 5.801°
Local Coord Referenced To: Well Head

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	TVDSS (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")	Closure (ft)	Closure Azimuth (°)
WRP	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-3,474.80		457,144.47	829,590.65	N 32°15'11.97"	W 103°24'3.22"		
SHL	24.00	0.00	0.00	24.00	0.00	0.00	0.00	-3,450.80	0.00	457,144.47	829,590.65	N 32°15'11.97"	W 103°24'3.22"	0.00	0.00
First 3rd Party Survey	163.00	0.30	27.27	163.00	-0.32	0.32	0.17	-3,311.80	0.22	457,144.79	829,590.82	N 32°15'11.97"	W 103°24'3.22"	0.36	27.27
	250.00	0.37	6.85	250.00	-0.79	0.80	0.30	-3,224.80	0.16	457,145.27	829,590.95	N 32°15'11.98"	W 103°24'3.21"	0.86	20.73
	345.00	0.40	18.98	345.00	-1.40	1.42	0.45	-3,129.80	0.09	457,145.89	829,591.10	N 32°15'11.98"	W 103°24'3.21"	1.49	17.51
	439.00	0.57	5.63	438.99	-2.17	2.20	0.60	-3,035.81	0.22	457,146.67	829,591.25	N 32°15'11.99"	W 103°24'3.21"	2.28	15.30
	533.00	0.56	20.09	532.99	-3.06	3.10	0.81	-2,941.81	0.15	457,147.57	829,591.46	N 32°15'12.00"	W 103°24'3.21"	3.20	14.58
	628.00	0.36	10.49	627.98	-3.78	3.82	1.02	-2,846.82	0.22	457,148.29	829,591.67	N 32°15'12.01"	W 103°24'3.20"	3.96	14.92
	722.00	0.34	24.88	721.98	-4.31	4.37	1.19	-2,752.82	0.10	457,148.84	829,591.84	N 32°15'12.01"	W 103°24'3.20"	4.53	15.24
	816.00	0.15	5.24	815.98	-4.68	4.74	1.32	-2,658.82	0.22	457,149.21	829,591.97	N 32°15'12.01"	W 103°24'3.20"	4.92	15.54
Last 3rd Party Survey	911.00	0.12	204.26	910.98	-4.72	4.78	1.29	-2,563.82	0.28	457,149.25	829,591.94	N 32°15'12.01"	W 103°24'3.20"	4.95	15.10
	1,004.00	0.17	118.14	1,003.98	-4.56	4.62	1.37	-2,470.82	0.22	457,149.09	829,592.02	N 32°15'12.01"	W 103°24'3.20"	4.82	16.52
	1,156.00	0.43	139.24	1,155.98	-4.00	4.08	1.94	-2,318.82	0.18	457,148.55	829,592.59	N 32°15'12.01"	W 103°24'3.19"	4.52	25.43
	1,250.00	0.58	117.76	1,249.98	-3.48	3.60	2.59	-2,224.82	0.25	457,148.07	829,593.24	N 32°15'12.00"	W 103°24'3.19"	4.43	35.80
	1,440.00	0.62	124.46	1,439.97	-2.38	2.57	4.29	-2,034.83	0.04	457,147.04	829,594.94	N 32°15'11.99"	W 103°24'3.17"	5.00	59.12
	1,535.00	0.69	127.37	1,534.96	-1.71	1.93	5.17	-1,939.84	0.08	457,146.40	829,595.82	N 32°15'11.99"	W 103°24'3.16"	5.52	69.55
	1,630.00	0.74	132.15	1,629.95	-0.91	1.17	6.08	-1,844.85	0.08	457,145.64	829,596.73	N 32°15'11.98"	W 103°24'3.15"	6.19	79.11
	1,725.00	0.80	131.37	1,724.94	-0.02	0.32	7.03	-1,749.86	0.06	457,144.79	829,597.68	N 32°15'11.97"	W 103°24'3.14"	7.04	87.40
First SLB Survey	1,820.00	0.72	130.75	1,819.94	0.85	-0.51	7.98	-1,654.86	0.08	457,143.96	829,598.63	N 32°15'11.96"	W 103°24'3.12"	8.00	93.65
	1,915.00	0.74	133.17	1,914.93	1.69	-1.32	8.88	-1,559.87	0.04	457,143.15	829,599.53	N 32°15'11.95"	W 103°24'3.11"	8.98	98.44
	2,010.00	0.76	125.96	2,009.92	2.52	-2.11	9.84	-1,464.88	0.10	457,142.36	829,600.49	N 32°15'11.95"	W 103°24'3.10"	10.06	102.09
	2,106.00	0.68	121.37	2,105.91	3.23	-2.78	10.84	-1,368.89	0.10	457,141.69	829,601.49	N 32°15'11.94"	W 103°24'3.09"	11.19	104.37
	2,201.00	0.68	113.20	2,200.91	3.79	-3.29	11.84	-1,273.89	0.10	457,141.18	829,602.49	N 32°15'11.93"	W 103°24'3.08"	12.29	105.54
	2,296.00	0.76	115.48	2,295.90	4.33	-3.79	12.93	-1,178.90	0.09	457,140.68	829,603.58	N 32°15'11.93"	W 103°24'3.07"	13.47	106.33
	2,391.00	0.74	91.82	2,390.89	4.67	-4.08	14.11	-1,083.91	0.32	457,140.39	829,604.76	N 32°15'11.93"	W 103°24'3.05"	14.69	106.12
	2,486.00	0.83	80.11	2,485.88	4.63	-3.98	15.40	-988.92	0.19	457,140.49	829,606.05	N 32°15'11.93"	W 103°24'3.04"	15.91	104.49
	2,581.00	0.81	68.74	2,580.87	4.32	-3.62	16.70	-893.93	0.17	457,140.85	829,607.35	N 32°15'11.93"	W 103°24'3.02"	17.09	102.22
	2,676.00	0.94	73.28	2,675.86	3.91	-3.15	18.08	-798.94	0.15	457,141.32	829,608.73	N 32°15'11.93"	W 103°24'3.01"	18.35	99.88
	2,771.00	1.03	71.41	2,770.85	3.48	-2.65	19.63	-703.95	0.10	457,141.82	829,610.28	N 32°15'11.94"	W 103°24'2.99"	19.81	97.70
	2,961.00	1.19	65.05	2,960.81	2.25	-1.28	23.04	-513.99	0.11	457,143.19	829,613.69	N 32°15'11.95"	W 103°24'2.95"	23.07	93.17
	3,055.00	1.41	63.80	3,054.79	1.41	-0.35	24.96	-420.01	0.24	457,144.12	829,615.61	N 32°15'11.96"	W 103°24'2.93"	24.96	90.81
	3,150.00	1.61	65.86	3,149.75	0.44	0.71	27.23	-325.05	0.22	457,145.18	829,617.88	N 32°15'11.97"	W 103°24'2.90"	27.24	88.51
	3,246.00	1.67	61.33	3,245.71	-0.67	1.93	29.69	-229.09	0.15	457,146.40	829,620.34	N 32°15'11.98"	W 103°24'2.87"	29.75	86.28
	3,340.00	1.89	59.27	3,339.67	-2.01	3.38	32.22	-135.13	0.24	457,147.85	829,622.87	N 32°15'12.00"	W 103°24'2.84"	32.40	84.01
	3,435.00	2.00	57.30	3,434.61	-3.59	5.08	34.96	-40.19	0.14	457,149.55	829,625.61	N 32°15'12.01"	W 103°24'2.81"	35.33	81.74
	3,529.00	2.00	58.06	3,528.56	-5.23	6.83	37.73	53.76	0.03	457,151.30	829,628.38	N 32°15'12.03"	W 103°24'2.78"	38.35	79.74
	3,719.00	2.26	65.54	3,718.43	-8.27	10.14	43.96	243.63	0.20	457,154.61	829,634.61	N 32°15'12.06"	W 103°24'2.70"	45.11	77.02
	3,908.00	2.24	77.78	3,907.28	-10.29	12.46	50.96	432.48	0.25	457,156.93	829,641.61	N 32°15'12.09"	W 103°24'2.62"	52.46	76.26
	4,002.00	2.28	84.09	4,001.21	-10.72	13.04	54.62	526.41	0.27	457,157.51	829,645.27	N 32°15'12.09"	W 103°24'2.58"	56.15	76.57
	4,097.00	2.08	90.14	4,096.14	-10.76	13.23	58.22	621.34	0.32	457,157.70	829,648.87	N 32°15'12.09"	W 103°24'2.54"	59.70	77.20
	4,191.00	2.07	96.15	4,190.08	-10.43	13.05	61.61	715.28	0.23	457,157.52	829,652.26	N 32°15'12.09"	W 103°24'2.50"	62.98	78.05
	4,380.00	2.02	104.54	4,378.96	-8.95	11.84	68.23	904.16	0.16	457,156.31	829,658.88	N 32°15'12.08"	W 103°24'2.42"	69.25	80.15
	4,475.00	2.00	117.38	4,473.90	-7.63	10.66	71.32	999.10	0.47	457,155.13	829,661.97	N 32°15'12.07"	W 103°24'2.39"	72.12	81.50
	4,569.00	1.85	117.32	4,567.85	-6.07	9.21	74.13	1,093.05	0.16	457,153.68	829,664.78	N 32°15'12.05"	W 103°24'2.35"	74.70	82.92
	4,664.00	2.08	102.28	4,662.79	-4.87	8.14	77.17	1,187.99	0.59	457,152.61	829,667.83	N 32°15'12.04"	W 103°24'2.32"	77.60	83.98
	4,759.00	2.28	93.16	4,757.72	-4.25	7.67	80.75	1,282.92	0.42	457,152.14	829,671.40	N 32°15'12.04"	W 103°24'2.28"	81.11	84.57
	4,853.00	2.35	92.60	4,851.65	-3.90	7.48	84.54	1,376.85	0.08	457,151.95	829,675.19	N 32°15'12.03"	W 103°24'2.23"	84.87	84.94
	4,948.00	2.57	90.74	4,946.56	-3.61	7.36	88.61	1,471.76	0.25	457,151.83	829,679.26	N 32°15'12.03"	W 103°24'2.18"	88.92	85.25
	5,042.00	2.07	76.02	5,040.48	-3.83	7.75	92.37	1,565.68	0.82	457,152.22	829,683.02	N 32°15'12.04"	W 103°24'2.14"	92.69	85.21
	5,137.00	1.86	42.73	5,135.43	-5.26	9.29	95.08	1,660.63	1.20	457,153.76	829,685.73	N 32°15'12.05"	W 103°24'2.11"	95.53	84.42
	5,232.00	1.84	44.17	5,230.38	-7.40	11.52	97.19	1,755.58	0.05	457,155.99	829,687.84	N 32°15'12.07"	W 103°24'2.08"	97.87	83.24
	5,326.00	1.63	42.18	5,324.34	-9.39	13.59	99.14	1,849.54	0.23	457,158.06	829,689.79	N 32°15'12.09"	W 103°24'2.06"	100.07	82.19
	5,421.00	1.82	28.72	5,419.29	-11.64	15.92	100.77	1,944.49	0.47	457,160.39	829,691.42	N 32°15'12.12"	W 103°24'2.04"	102.02	81.02
	5,516.00	3.54	10.04	5,514.19	-15.79	20.13	102.01	2,039.39	2.01	457,167					

Actual KOP	8,736.00	1.79	77.62	8,725.65	-119.40	130.91	269.38	5,250.85	0.29	457,275.39	829,860.03	N 32°15'13.24"	W 103°24'0.07"	299.50	64.08
	8,831.00	1.63	77.85	8,820.61	-119.89	131.52	272.15	5,345.81	0.17	457,275.99	829,862.80	N 32°15'13.25"	W 103°24'0.04"	302.26	64.21
	8,926.00	1.33	68.56	8,915.58	-120.47	132.20	274.49	5,440.78	0.40	457,276.68	829,865.15	N 32°15'13.25"	W 103°24'0.01"	304.67	64.28
	9,021.00	1.34	62.31	9,010.55	-121.31	133.12	276.50	5,535.75	0.15	457,277.59	829,867.16	N 32°15'13.26"	W 103°23'59.98"	306.88	64.29
	9,116.00	1.31	60.54	9,105.53	-122.27	134.17	278.43	5,630.73	0.05	457,278.64	829,869.08	N 32°15'13.27"	W 103°23'59.96"	309.08	64.27
	9,211.00	1.47	66.42	9,200.50	-123.21	135.20	280.50	5,725.70	0.23	457,279.67	829,871.15	N 32°15'13.28"	W 103°23'59.94"	311.38	64.27
	9,306.00	1.34	75.71	9,295.47	-123.88	135.96	282.69	5,820.67	0.28	457,280.43	829,873.34	N 32°15'13.29"	W 103°23'59.91"	313.68	64.32
	9,400.00	1.28	76.41	9,389.44	-124.31	136.48	284.77	5,914.64	0.07	457,280.95	829,875.43	N 32°15'13.29"	W 103°23'59.89"	315.79	64.39
	9,496.00	1.34	69.41	9,485.42	-124.86	137.12	286.87	6,010.62	0.18	457,281.59	829,877.52	N 32°15'13.30"	W 103°23'59.86"	317.96	64.45
	9,591.00	1.49	68.60	9,580.39	-125.61	137.96	289.06	6,105.59	0.16	457,282.43	829,879.71	N 32°15'13.31"	W 103°23'59.84"	320.29	64.49
	9,686.00	1.46	65.68	9,675.36	-126.46	138.91	291.31	6,200.56	0.09	457,283.38	829,881.96	N 32°15'13.32"	W 103°23'59.81"	322.74	64.51
	9,773.00	1.26	65.71	9,762.33	-127.23	139.76	293.19	6,287.53	0.23	457,284.23	829,883.84	N 32°15'13.33"	W 103°23'59.79"	324.80	64.51
	9,868.00	0.96	55.71	9,857.32	-128.04	140.64	294.80	6,382.52	0.37	457,285.11	829,885.45	N 32°15'13.33"	W 103°23'59.77"	326.63	64.50
	9,963.00	0.83	53.32	9,952.31	-128.85	141.50	296.01	6,477.51	0.14	457,285.97	829,886.66	N 32°15'13.34"	W 103°23'59.76"	328.09	64.45
	10,058.00	0.49	356.44	10,047.30	-129.64	142.32	296.54	6,572.50	0.73	457,286.79	829,887.19	N 32°15'13.35"	W 103°23'59.75"	328.92	64.36
FTP / 100ft FNL Cross	10,153.00	0.83	320.56	10,142.29	-130.60	143.25	296.08	6,667.49	0.55	457,287.72	829,886.73	N 32°15'13.36"	W 103°23'59.76"	328.91	64.18
	10,247.00	1.12	304.59	10,236.28	-131.70	144.30	294.89	6,761.48	0.42	457,288.77	829,885.54	N 32°15'13.37"	W 103°23'59.77"	328.30	63.93
	10,342.00	1.57	290.36	10,331.25	-132.76	145.28	292.90	6,856.45	0.59	457,289.75	829,883.55	N 32°15'13.38"	W 103°23'59.79"	326.95	63.62
	10,437.00	1.74	279.67	10,426.21	-133.56	145.98	290.26	6,951.41	0.37	457,290.45	829,880.91	N 32°15'13.39"	W 103°23'59.82"	324.90	63.30
	10,531.00	1.85	282.49	10,520.17	-134.25	146.54	287.37	7,045.37	0.15	457,291.01	829,878.02	N 32°15'13.39"	W 103°23'59.86"	322.58	62.98
	10,626.00	2.41	297.49	10,615.10	-135.65	147.80	284.10	7,140.30	0.83	457,292.27	829,874.75	N 32°15'13.41"	W 103°23'59.89"	320.25	62.52
	10,721.00	2.72	306.67	10,710.01	-138.06	150.06	280.52	7,235.21	0.54	457,294.54	829,871.17	N 32°15'13.43"	W 103°23'59.94"	318.14	61.86
	10,826.00	2.99	314.91	10,814.88	-141.65	153.49	276.59	7,340.08	0.47	457,297.96	829,867.24	N 32°15'13.46"	W 103°23'59.98"	316.32	60.97
	10,920.00	3.36	314.66	10,908.73	-145.47	157.15	272.89	7,433.93	0.39	457,301.62	829,863.54	N 32°15'13.50"	W 103°24'0.02"	314.91	60.06
	10,956.00	3.36	311.95	10,944.67	-146.98	158.60	271.35	7,469.87	0.44	457,303.07	829,862.01	N 32°15'13.51"	W 103°24'0.04"	314.30	59.69
	11,025.00	3.54	311.48	11,013.55	-149.87	161.36	268.26	7,538.75	0.26	457,305.83	829,858.91	N 32°15'13.54"	W 103°24'0.08"	313.05	58.97
	11,120.00	1.67	244.68	11,108.46	-151.37	162.71	264.81	7,633.66	3.44	457,307.18	829,855.46	N 32°15'13.55"	W 103°24'0.12"	310.80	58.43
	11,125.00	1.89	225.74	11,113.46	-151.28	162.62	264.68	7,638.66	12.49	457,307.10	829,855.33	N 32°15'13.55"	W 103°24'0.12"	310.65	58.43
	11,215.00	12.29	173.12	11,202.69	-140.71	152.05	264.77	7,727.89	12.49	457,296.52	829,855.42	N 32°15'13.45"	W 103°24'0.12"	305.32	60.13
	11,310.00	22.53	173.72	11,293.22	-112.39	123.84	267.98	7,818.42	10.78	457,268.31	829,858.63	N 32°15'13.17"	W 103°24'0.08"	295.21	65.20
Exit Lateral Window	11,404.00	26.15	169.41	11,378.85	-73.91	85.56	273.76	7,904.05	4.29	457,230.03	829,864.41	N 32°15'12.79"	W 103°24'0.02"	286.82	72.64
	11,411.00	27.07	169.62	11,385.11	-70.80	82.48	274.33	7,910.31	13.17	457,226.95	829,864.98	N 32°15'12.76"	W 103°24'0.01"	286.46	73.27
	11,499.00	38.62	171.45	11,458.92	-23.50	35.47	282.04	7,984.12	13.17	457,179.94	829,872.69	N 32°15'12.29"	W 103°23'59.93"	284.26	82.83
	11,594.00	48.47	174.62	11,527.71	41.65	-29.42	289.80	8,052.91	10.62	457,115.05	829,880.46	N 32°15'11.65"	W 103°23'59.85"	291.29	95.80
	11,688.00	53.32	172.83	11,586.98	114.40	-101.89	297.81	8,112.18	5.37	457,042.58	829,888.46	N 32°15'10.93"	W 103°23'59.76"	314.76	108.89
	11,783.00	61.03	176.06	11,638.45	194.04	-181.28	305.44	8,163.65	8.60	456,963.19	829,896.09	N 32°15'10.15"	W 103°23'59.68"	355.18	120.69
	11,878.00	67.21	175.90	11,679.90	279.44	-266.50	311.43	8,205.10	6.51	456,877.97	829,902.08	N 32°15'9.30"	W 103°23'59.62"	409.89	130.56
	11,973.00	71.85	174.38	11,713.11	368.33	-355.16	318.98	8,238.31	5.11	456,789.31	829,909.64	N 32°15'8.43"	W 103°23'59.54"	477.38	138.07
	12,068.00	80.12	174.52	11,736.10	460.29	-446.82	327.89	8,261.30	8.71	456,697.65	829,918.54	N 32°15'7.52"	W 103°23'59.44"	554.22	143.73
	12,162.00	91.47	177.84	11,742.98	553.84	-540.19	334.10	8,268.18	12.58	456,604.28	829,924.75	N 32°15'6.59"	W 103°23'59.38"	635.16	148.26
	12,215.00	92.32	177.08	11,741.23	606.81	-593.11	336.45	8,266.43	2.15	456,551.36	829,927.10	N 32°15'6.07"	W 103°23'59.36"	681.89	150.44
	12,311.00	90.40	176.42	11,738.95	702.77	-688.92	341.89	8,264.15	2.11	456,455					

Enter Lateral Window	19,322.00	85.29	173.73	11,801.11	7,683.69	-7,680.76	231.96	8,326.31	2.02	449,463.70	829,822.61	N 32°13'55.95"	W 103°24'1.29"	7,684.26	178.27	
	19,417.00	91.52	177.24	11,803.75	7,778.53	-7,775.36	239.43	8,328.95	7.53	449,369.09	829,830.08	N 32°13'55.01"	W 103°24'1.22"	7,779.05	178.24	
	19,511.00	86.03	172.16	11,805.76	7,872.32	-7,868.87	248.10	8,330.96	7.95	449,275.58	829,838.75	N 32°13'54.09"	W 103°24'1.12"	7,872.78	178.19	
	19,606.00	84.50	169.20	11,813.61	7,966.30	-7,962.29	263.43	8,338.81	3.50	449,182.17	829,854.08	N 32°13'53.16"	W 103°24'0.96"	7,966.64	178.11	
	19,700.00	83.46	169.28	11,823.47	8,058.80	-8,054.12	280.88	8,348.67	1.11	449,090.33	829,871.53	N 32°13'52.25"	W 103°24'0.76"	8,059.02	178.00	
	19,795.00	84.18	169.45	11,833.69	8,152.27	-8,146.95	298.31	8,358.89	0.78	448,997.50	829,888.96	N 32°13'51.33"	W 103°24'0.57"	8,152.41	177.90	
	19,890.00	83.10	169.55	11,844.22	8,245.75	-8,239.78	315.51	8,369.42	1.14	448,904.67	829,906.17	N 32°13'50.41"	W 103°24'0.38"	8,245.82	177.81	
	19,985.00	82.99	169.33	11,855.72	8,339.10	-8,332.48	332.80	8,380.92	0.26	448,811.97	829,923.45	N 32°13'49.49"	W 103°24'0.19"	8,339.13	177.71	
	20,053.00	83.40	172.74	11,863.78	8,406.18	-8,399.17	343.32	8,388.98	5.01	448,745.28	829,933.97	N 32°13'48.83"	W 103°24'0.07"	8,406.18	177.66	
	20,079.00	83.56	174.04	11,866.73	8,431.94	-8,424.83	346.29	8,391.93	5.01	448,719.62	829,936.94	N 32°13'48.58"	W 103°24'0.04"	8,431.94	177.65	
	20,174.00	83.78	174.42	11,877.21	8,526.20	-8,518.77	355.78	8,402.41	0.46	448,625.68	829,946.43	N 32°13'47.65"	W 103°23'59.94"	8,526.20	177.61	
	20,268.00	83.14	176.40	11,887.92	8,619.51	-8,611.86	363.26	8,413.12	2.20	448,532.59	829,953.91	N 32°13'46.72"	W 103°23'59.86"	8,619.51	177.58	
	20,363.00	85.02	177.06	11,897.71	8,713.99	-8,706.19	368.65	8,422.91	2.10	448,438.26	829,959.30	N 32°13'45.79"	W 103°23'59.81"	8,713.99	177.58	
	20,458.00	84.39	176.50	11,906.48	8,808.58	-8,800.63	373.96	8,431.68	0.89	448,343.82	829,964.61	N 32°13'44.86"	W 103°23'59.75"	8,808.58	177.57	
	20,552.00	84.28	178.23	11,915.76	8,902.11	-8,894.07	378.26	8,440.96	1.84	448,250.38	829,968.91	N 32°13'43.93"	W 103°23'59.71"	8,902.11	177.56	
	20,646.00	84.19	178.14	11,925.20	8,995.63	-8,987.55	381.22	8,450.40	0.14	448,156.90	829,971.87	N 32°13'43.01"	W 103°23'59.69"	8,995.63	177.57	
	20,741.00	84.69	179.00	11,934.41	9,090.17	-9,082.07	383.58	8,459.61	1.04	448,062.38	829,974.23	N 32°13'42.07"	W 103°23'59.67"	9,090.17	177.58	
	20,836.00	84.00	178.44	11,943.77	9,184.69	-9,176.59	385.69	8,468.97	0.93	447,967.86	829,976.34	N 32°13'41.13"	W 103°23'59.65"	9,184.69	177.59	
	20,930.00	83.58	177.64	11,953.94	9,278.13	-9,269.98	388.89	8,479.14	0.96	447,874.47	829,979.54	N 32°13'40.21"	W 103°23'59.63"	9,278.13	177.60	
	21,024.00	84.03	178.41	11,964.08	9,371.58	-9,363.37	392.11	8,489.28	0.94	447,781.08	829,982.76	N 32°13'39.29"	W 103°23'59.60"	9,371.58	177.60	
	21,119.00	83.06	178.20	11,974.76	9,465.97	-9,457.73	394.90	8,499.96	1.04	447,686.72	829,985.55	N 32°13'38.35"	W 103°23'59.58"	9,465.97	177.61	
	21,214.00	83.61	179.51	11,985.79	9,560.30	-9,552.07	396.79	8,510.99	1.49	447,592.38	829,987.44	N 32°13'37.42"	W 103°23'59.56"	9,560.30	177.62	
	21,403.00	84.98	176.81	12,004.58	9,748.33	-9,740.01	402.83	8,529.78	1.60	447,404.44	829,993.48	N 32°13'35.56"	W 103°23'59.51"	9,748.34	177.63	
	21,498.00	84.52	180.51	12,013.27	9,842.90	-9,834.57	405.04	8,538.47	3.91	447,309.88	829,995.69	N 32°13'34.62"	W 103°23'59.50"	9,842.91	177.64	
	21,559.00	84.57	180.46	12,019.07	9,903.55	-9,895.29	404.53	8,544.27	0.12	447,249.16	829,995.18	N 32°13'34.02"	W 103°23'59.51"	9,903.56	177.66	
	21,603.00	83.32	179.07	12,023.71	9,947.27	-9,939.04	404.71	8,548.91	4.24	447,205.41	829,995.36	N 32°13'33.59"	W 103°23'59.51"	9,947.28	177.67	
	21,792.00	83.27	174.90	12,045.79	10,134.92	-10,126.45	414.58	8,570.99	2.19	447,018.00	830,005.23	N 32°13'31.73"	W 103°23'59.41"	10,134.93	177.66	
	21,887.00	82.10	174.02	12,057.89	10,229.01	-10,220.23	423.67	8,583.09	1.54	446,924.22	830,014.32	N 32°13'30.80"	W 103°23'59.32"	10,229.01	177.63	
LTP / 100 ft FSL Cross	21,948.00	82.95	173.53	12,065.82	10,289.35	-10,280.36	430.23	8,591.02	1.61	446,864.09	830,020.88	N 32°13'30.21"	W 103°23'59.25"	10,289.35	177.60	
Final Survey	21,952.00	83.01	173.50	12,066.31	10,293.31	-10,284.30	430.68	8,591.51	1.61	446,860.15	830,021.33	N 32°13'30.17"	W 103°23'59.24"	10,293.31	177.60	
Projection to Total Depth		22,020.00	83.01	173.50	12,074.58	10,360.64	-10,351.36	438.32	8,599.78	0.00	446,793.08	830,028.97	N 32°13'29.51"	W 103°23'59.16"	10,360.64	177.58

Survey Type: DefinitiveSurvey

Survey Error Model: ISCWSA0 2.795 sigma

Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Expected Max Inclination (deg)	Survey Tool Code	Borehole / Survey
	1	0.000	1,004.000	Act Stns		B005Mb_MWD+HRGM+SAG+MS	Saker 6-7 Fed Com 38H / Oxy Saker 6-7 Fed Com 38H HRGM+IFR1 to 22020ft
	1	1,004.000	22,020.000	Act Stns		A010Mb_MWD+IFR1+SAG+MS	Saker 6-7 Fed Com 38H / Oxy Saker 6-7 Fed Com 38H HRGM+IFR1 to 22020ft

EOU Geometry:

End MD (ft)	Hole Size (in)	Casing Size (in)	Name
22,020.000	26.400	26.400	

Intent ☐ As Drilled ☒

API # 30-025-48939		
Operator Name: OXY USA INC.	Property Name: Saker 6 7 Federal Com	Well Number 038H

Kick Off Point (KOP)

UL A	Section 6	Township 24S	Range 35E	Lot 1	Feet 20	From N/S North	Feet 583	From E/W East	County Lea
Latitude 32.253765					Longitude -103.400033			NAD Nad83	

First Take Point (FTP)

UL A	Section 6	Township 24S	Range 35E	Lot 1	Feet 512	From N/S North	Feet 537	From E/W East	County Lea
Latitude 32.252413					Longitude -103.399879			NAD Nad83	

Last Take Point (LTP)

UL P	Section 7	Township 24S	Range 35E	Lot	Feet 285	From N/S South	Feet 550	From E/W East	County Lea
Latitude 32.225566					Longitude -103.399845			NAD Nad83	

Is this well the defining well for the Horizontal Spacing Unit? ☐ NoIs this well an infill well? ☐ Yes

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API # 30-025-48934		
Operator Name: OXY USA INC.	Property Name: Saker 6 7 Fed Com	Well Number 33H

KZ 06/29/2018

Submit To Appropriate District Office Two Copies <u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 <u>District II</u> 811 S. First St., Artesia, NM 88210 <u>District III</u> 1000 Rio Brazos Rd., Aztec, NM 87410 <u>District IV</u> 1220 S. St. Francis Dr., Santa Fe, NM 87505		State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505			Form C-105 Revised April 3, 2017					
WELL COMPLETION OR RECOMPLETION REPORT AND LOG								1. WELL API NO. 30-025-48939		
4. Reason for filing: ☒ COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) ☐ C-144 CLOSURE ATTACHMENT (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)								2. Type of Lease ☐ STATE ☐ FEE ☒ FED/INDIAN		
								3. State Oil & Gas Lease No.		
7. Type of Completion: ☒ NEW WELL ☐ WORKOVER ☐ DEEPENING ☐ PLUGBACK ☐ DIFFERENT RESERVOIR ☐ OTHER _____								5. Lease Name or Unit Agreement Name Saker 6-7 Fed Com		
8. Name of Operator OXY USA INC.								6. Well Number: 38H		
10. Address of Operator PO Box 50250, MIDLAND, TX 79710								11. Pool name or Wildcat Antelope Ridge; Wolfcamp		
12. Location	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County
Surface:	1	6	24S	35E		180	North	850	East	Lea
BH:	P	7	24S	35E		29	South	526	East	Lea
13. Date Spudded 06/06/2023	14. Date T.D. Reached 8/15/2023		15. Date Rig Released 8/18/2023		16. Date Completed (Ready to Produce) 10/02/2023			17. Elevations (DF and RKB, RT, GR, etc.) 3450 GR		
18. Total Measured Depth of Well 22020' MD, 12074' TVD			19. Plug Back Measured Depth 21976' MD, 12066' TVD		20. Was Directional Survey Made? Yes			21. Type Electric and Other Logs Run CBL/Gamma		
22. Producing Interval(s), of this completion - Top, Bottom, Name 11945'-21761', Wolfcamp										
23. CASING RECORD (Report all strings set in well)										
CASING SIZE		WEIGHT LB./FT.		DEPTH SET		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED
13 3/8"		54.5# J-55		1111'		17 1/2"		1620sx Class C		
7 5/8"		29.7# HCL80		11010'		12 1/4"		5862sx Class H		
5 1/2"		20# P110		22000'		6 3/4"		793sx Class H		
24. LINER RECORD										
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN		25. TUBING RECORD				
						SIZE	DEPTH SET	PACKER SET		
26. Perforation record (interval, size, and number) 11945'-21761', 0.42", 1200 holes						27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC.				
						DEPTH INTERVAL		AMOUNT AND KIND MATERIAL USED		
						11945'-21761'		26,851,800 #'s sand and 510,009 bbls		
								produced water, 1312 bbls brackish water.		
28. PRODUCTION										
Date First Production 11/15/2023		Production Method (<i>Flowing, gas lift, pumping - Size and type pump</i>) Flowing				Well Status (<i>Prod. or Shut-in</i>) Producing				
Date of Test 11/19/2023	Hours Tested 24 hours	Choke Size 0	Prod'n For Test Period	Oil - Bbl 2692	Gas - MCF 2347	Water - Bbl. 4225	Gas - Oil Ratio 871			
Flow Tubing Press.	Casing Pressure 966	Calculated 24-Hour Rate	Oil - Bbl. 2692	Gas - MCF 2347	Water - Bbl. 4225	Oil Gravity - API - (<i>Corr.</i>)				
29. Disposition of Gas (<i>Sold, used for fuel, vented, etc.</i>) Sold								30. Test Witnessed By		
31. List Attachments C104c, C102, WBD, Directional Survey, CBL										
32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.								33. Rig Release Date:		
34. If an on-site burial was used at the well, report the exact location of the on-site burial:										
Latitude _____ Longitude _____ NAD83										
I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief										
Signature 		Printed Name Sarah McKinney			Title Regulatory Analyst Sr.			Date 12/07/2023		
E-mail Address sarah_mckinney@oxy.com										

This form is to be filed with the appropriate District Office of the Division not later than 20 days after the completion of any newly-drilled or deepened well and not later than 60 days after completion of closure. When submitted as a completion report, this shall be accompanied by one copy of all electrical and radio-activity logs run on the well and a summary of all special tests conducted, including drill stem tests. All depths reported shall be measured depths. In the case of directionally drilled wells, true vertical depths shall also be reported. For multiple completions, items 11, 12 and 26-31 shall be reported for each zone.

Southeastern New Mexico		Northwestern New Mexico	
T. Rustler 734'	T. Bell Canyon	T. Ojo Alamo	T. Penn A"
T. Salado 1170'	T. Strawn	T. Kirtland	T. Penn. "B"
T. Castile 3903'	T. Atoka	T. Fruitland	T. Penn. "C"
T. Delaware 5275'	T. Miss	T. Pictured Cliffs	T. Penn. "D"
T. Cherry Canyon 6236'	T. Devonian	T. Cliff House	T. Leadville
T. Brushy Canyon 7535'	T. Silurian	T. Menefee	T. Madison
T. Grayburg	T. Montoya	T. Point Lookout	T. Elbert
T. San Andres	T. Simpson	T. Mancos	T. McCracken
T. Glorieta	T. McKee	T. Gallup	T. Ignacio Otzte
T. Paddock	T. Ellenburger	Base Greenhorn	T. Granite
T. Blinebry	T. Gr. Wash	T. Dakota	
T. Tubb	T. Delaware Sand	T. Morrison	
T. Drinkard	T. Bone Springs 8850'	T. Todilto	
T. Abo	T. 1 st Bone Springs 9953'	T. Entrada	
T. Wolfcamp	T. 2 nd Bone Springs 10403'	T. Wingate	
T. Penn	T. 3 rd Bone Springs 11444'	T. Chinle	
T. Cisco (Bough C)	T. Wolfcamp 11931'	T. Permian	


No. 1, from.....to.....
No. 2, from.....to.....
No. 3, from.....to.....
No. 4, from.....to.....

Include data on rate of water inflow and elevation to which water rose in hole.

No. 1, from.....to.....feet.....
 No. 2, from.....to.....feet.....
 No. 3, from.....to.....feet.....

From	To	Thickness In Feet	Lithology

OXY USA Inc.
SAKER 6 7 FEDERAL COM 38H
API No. 30-025-48939



District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 294610

ACKNOWLEDGMENTS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 294610
	Action Type: [C-104] Completion Packet (C-104C)

ACKNOWLEDGMENTS

☒	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
☒	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 294610

CONDITIONS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 294610
	Action Type: [C-104] Completion Packet (C-104C)

CONDITIONS

Created By	Condition	Condition Date
smcgrath	File 3160-4 within 10 days of BLM Approval.	3/6/2024