

Well Name: BOLL WEEVIL 27-34 FED COM	Well Location: T26S / R34E / SEC 27 / NWNW / 32.02107 / -103.462534	County or Parish/State: LEA / NM
Well Number: 1H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM100569	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002547948	Well Status: Approved Application for Permit to Drill	Operator: DEVON ENERGY PRODUCTION COMPANY LP

Notice of Intent

Sundry ID: 2771006

Type of Submission: Notice of Intent

Type of Action: APD Change

Date Sundry Submitted: 01/22/2024

Time Sundry Submitted: 12:50

Date proposed operation will begin: 01/22/2024

Procedure Description: Devon Energy Production Company L.P. respectfully requests the following changes to the approved APD: SHL change from 225 FNL & 1161 FWL to 210 FNL & 1321 FWL, both 27-26S-34E TVD/MD change from 12,600'/20,144' to 12,600'/20,155' Casing program change: Intermediate casing depth change, from 11,963 ' to 12,009'. Cement volume changes to accommodate casing change. Please see attached revised C-102 and drilling & directional plans.

NOI Attachments

Procedure Description

- BOLL_WEEVIL_27_34_FED_COM_1H_Directional_Plan_01_22_24_20240122124211.pdf
- BOLL_WEEVIL_27_34_FED_COM_1H_R2_20240122124211.pdf
- BOLL_WEEVIL_27_34_FED_COM_1H_C_102_SHL_NOI_20240122124213.pdf

Received by OCD: 2/21/2024 10:30:39 AM

Page 2 of 18

Well Name: BOLL WEEVIL 27-34 FED COM	Well Location: T26S / R34E / SEC 27 / NWNW / 32.02107 / -103.462534	County or Parish/State: LEA / NM
Well Number: 1H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM100569	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002547948	Well Status: Approved Application for Permit to Drill	Operator: DEVON ENERGY PRODUCTION COMPANY LP

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: REBECCA DEAL	Signed on: JAN 22, 2024 12:46 PM
Name: DEVON ENERGY PRODUCTION COMPANY LP	
Title: Regulatory Analyst	
Street Address: 333 W SHERIDAN AVE	
City: OKLAHOMA CITY	State: OK
Phone: (303) 299-1406	
Email address: REBECCA.DEAL@DVN.COM	

Field

Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		

BLM Point of Contact

BLM POC Name: CHRISTOPHER WALLS	BLM POC Title: Petroleum Engineer
BLM POC Phone: 5752342234	BLM POC Email Address: cwalls@blm.gov
Disposition: Approved	Disposition Date: 02/20/2024
Signature: Chris Walls	

Form 3160-5
(June 2019)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: October 31, 2021

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No. **NMNM100569**
6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2		7. If Unit of CA/Agreement, Name and/or No.
1. Type of Well ☒ Oil Well ☐ Gas Well ☐ Other	8. Well Name and No. BOLL WEEVIL 27-34 FED COM/1H	
2. Name of Operator DEVON ENERGY PRODUCTION COMPANY LP	9. API Well No. 3002547948	
3a. Address 333 WEST SHERIDAN AVE, OKLAHOMA CITY,	3b. Phone No. (include area code) (405) 235-3611	10. Field and Pool or Exploratory Area WC-025 G-08 S263412K; Bone Spring/BONE SPRING
4. Location of Well (Footage, Sec., T.,R.,M., or Survey Description) SEC 27/T26S/R34E/NMP		11. Country or Parish, State LEA/NM

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA				
TYPE OF SUBMISSION	TYPE OF ACTION			
☒ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off
☐ Subsequent Report	☐ Alter Casing	☐ Hydraulic Fracturing	☐ Reclamation	☐ Well Integrity
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☐ Other
	☒ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon	
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be perfonned or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has detennined that the site is ready for final inspection.)

Devon Energy Production Company L.P. respectfully requests the following changes to the approved APD:

SHL change from 225 FNL & 1161 FWL to 210 FNL & 1321 FWL, both 27-26S-34E

TVD/MD change from 12,600'/20,144 to 12,600'/20,155

Casing program change: Intermediate casing depth change, from 11,963 to 12,009. Cement volume changes to accommodate casing change.

Please see attached revised C-102 and drilling & directional plans.

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed) REBECCA DEAL / Ph: (303) 299-1406	Title Regulatory Analyst
Signature (Electronic Submission)	Date 01/22/2024

THE SPACE FOR FEDERAL OR STATE OFFICE USE		
Approved by CHRISTOPHER WALLS / Ph: (575) 234-2234 / Approved	Title Petroleum Engineer	Date 02/20/2024
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office CARLSBAD	

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

GENERAL INSTRUCTIONS

This form is designed for submitting proposals to perform certain well operations and reports of such operations when completed as indicated on Federal and Indian lands pursuant to applicable Federal law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local area or regional procedures and practices, are either shown below, will be issued by or may be obtained from the local Federal office.

SPECIFIC INSTRUCTIONS

Item 4 - Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult the local Federal office for specific instructions.

Item 13: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by the local Federal office. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to the top of any tubing left in the hole; method of closing top of well and date well site conditioned for final inspection looking for approval of the abandonment. If the proposal will involve **hydraulic fracturing operations**, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The privacy Act of 1974 and the regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 351 et seq., 25 U.S.C. 396; 43 CFR 3160.

PRINCIPAL PURPOSE: The information is used to: (1) Evaluate, when appropriate, approve applications, and report completion of subsequent well operations, on a Federal or Indian lease; and (2) document for administrative use, information for the management, disposal and use of National Resource lands and resources, such as: (a) evaluating the equipment and procedures to be used during a proposed subsequent well operation and reviewing the completed well operations for compliance with the approved plan; (b) requesting and granting approval to perform those actions covered by 43 CFR 3162.3-2, 3162.3-3, and 3162.3-4; (c) reporting the beginning or resumption of production, as required by 43 CFR 3162.4-1(c) and (d) analyzing future applications to drill or modify operations in light of data obtained and methods used.

ROUTINE USES: Information from the record and/or the record will be transferred to appropriate Federal, State, local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecutions in connection with congressional inquiries or to consumer reporting agencies to facilitate collection of debts owed the Government.

EFFECT OF NOT PROVIDING THE INFORMATION: Filing of this notice and report and disclosure of the information is mandatory for those subsequent well operations specified in 43 CFR 3162.3-2, 3162.3-3, 3162.3-4.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to evaluate proposed and/or completed subsequent well operations on Federal or Indian oil and gas leases.

Response to this request is mandatory.

The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C St., N.W., Mail Stop 401 LS, Washington, D.C. 20240

Additional Information

Location of Well

0. SHL: NWNW / 225 FNL / 1161 FWL / TWSP: 26S / RANGE: 34E / SECTION: 27 / LAT: 32.02107 / LONG: -103.462534 (TVD: 0 feet, MD: 0 feet)

PPP: NWNW / 100 FNL / 360 FWL / TWSP: 26S / RANGE: 34E / SECTION: 27 / LAT: 32.0214 / LONG: -103.4651 (TVD: 12200 feet, MD: 12272 feet)

BHL: SWSW / 20 FSL / 360 FWL / TWSP: 26S / RANGE: 34E / SECTION: 34 / LAT: 32.0002 / LONG: -103.4652 (TVD: 12600 feet, MD: 20144 feet)


CONFIDENTIAL



Well: BOLL WEEVIL 27-34 FED COM 1H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD (ft)	INC (°)	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL
2000.00	0.00	279.00	2000.00	0.00	0.00	0.00	0.00	Start Tangent
2500.00	10.00	279.00	2497.47	6.81	-42.99	-1.70	2.00	Hold Tangent
7616.63	10.00	279.00	7536.37	145.80	-920.54	-36.34	0.00	Drop to Vertical
8116.63	0.00	279.00	8033.83	152.61	-963.53	-38.03	2.00	Hold Vertical
12109.84	0.00	179.51	12027.04	152.61	-963.53	-38.03	0.00	KOP
13009.84	90.00	179.51	12600.00	-420.33	-958.63	530.34	10.00	Landing Point
20155.43	90.00	179.51	12600.00	-7565.65	-897.52	7618.70	0.00	BHL



Key Depths	MD (ft)	TVD (ft)
Rustler	860.00	860.00
Salt	1200.00	1200.00
Base of Salt	5112.22	5070.00
Delaware	5376.23	5330.00
Cherry Canyon	6437.35	6375.00
Brushy Canyon	8062.80	7980.00
Bone Spring 1st	10672.80	10590.00
Bone Spring 2nd	11222.80	11140.00
Bone Spring 3rd / Point of Penetratic exit	12285.54 20075.43	12200.00 12600.01

SHL
KOP
Point of Penetration
Exit
BHL

MD (ft)	TVD (ft)	Lat (°)	Long (°)	Section Footages
0.00	0.00	32.0210	-103.4621	210' FNL, 1321' FWL of Sec 27 in T26S, R34E
12109.84	12027.04	32.0215	-103.4652	51' FNL, 359' FWL of Sec 27 in T26S, R34E
12285.54	12200.00	32.0214	-103.4651	100' FNL, 360' FWL of Sec 27 in T26S, R34E
20075.43	12600.01	32.0006	-103.4651	100' FSL, 360' FWL of Sec 34 in T26S, R34E
20155.43	12600.00	32.0002	-103.4652	20' FSL, 360' FWL of Sec 34 in T26S, R34E

	Y	X	MD
KOP	372660	810414	12109.84

BOLL WEEVIL 27-34 FED COM 1H



Well: BOLL WEEVIL 27-34 FED COM 1H
 County: Lea
 Wellbore: Permit Plan
 Design: Permit Plan #1

Geodetic System: US State Plane 1983
 Datum: North American Datum 1927
 Ellipsoid: Clarke 1866
 Zone: 3001 - NM East (NAD83)

MD (ft)	INC (")	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL
100.00	0.00	279.00	100.00	0.00	0.00	0.00	0.00	
200.00	0.00	279.00	200.00	0.00	0.00	0.00	0.00	
300.00	0.00	279.00	300.00	0.00	0.00	0.00	0.00	
400.00	0.00	279.00	400.00	0.00	0.00	0.00	0.00	
500.00	0.00	279.00	500.00	0.00	0.00	0.00	0.00	
600.00	0.00	279.00	600.00	0.00	0.00	0.00	0.00	
700.00	0.00	279.00	700.00	0.00	0.00	0.00	0.00	
800.00	0.00	279.00	800.00	0.00	0.00	0.00	0.00	
860.00	0.00	279.00	860.00	0.00	0.00	0.00	0.00	Rustler
900.00	0.00	279.00	900.00	0.00	0.00	0.00	0.00	
1000.00	0.00	279.00	1000.00	0.00	0.00	0.00	0.00	
1100.00	0.00	279.00	1100.00	0.00	0.00	0.00	0.00	
1200.00	0.00	279.00	1200.00	0.00	0.00	0.00	0.00	Salt,
1300.00	0.00	279.00	1300.00	0.00	0.00	0.00	0.00	
1400.00	0.00	279.00	1400.00	0.00	0.00	0.00	0.00	
1500.00	0.00	279.00	1500.00	0.00	0.00	0.00	0.00	
1600.00	0.00	279.00	1600.00	0.00	0.00	0.00	0.00	
1700.00	0.00	279.00	1700.00	0.00	0.00	0.00	0.00	
1800.00	0.00	279.00	1800.00	0.00	0.00	0.00	0.00	
1900.00	0.00	279.00	1900.00	0.00	0.00	0.00	0.00	
2000.00	0.00	279.00	2000.00	0.00	0.00	0.00	0.00	Start Tangent
2100.00	2.00	279.00	2099.98	0.27	-1.72	-0.07	2.00	
2200.00	4.00	279.00	2199.84	1.09	-6.89	-0.27	2.00	
2300.00	6.00	279.00	2299.45	2.45	-15.50	-0.61	2.00	
2400.00	8.00	279.00	2398.70	4.36	-27.54	-1.09	2.00	
2500.00	10.00	279.00	2497.47	6.81	-42.99	-1.70	2.00	Hold Tangent
2600.00	10.00	279.00	2595.95	9.52	-60.14	-2.37	0.00	
2700.00	10.00	279.00	2694.43	12.24	-77.29	-3.05	0.00	
2800.00	10.00	279.00	2792.91	14.96	-94.44	-3.73	0.00	
2900.00	10.00	279.00	2891.39	17.67	-111.59	-4.40	0.00	
3000.00	10.00	279.00	2989.87	20.39	-128.74	-5.08	0.00	
3100.00	10.00	279.00	3088.35	23.11	-145.89	-5.76	0.00	
3200.00	10.00	279.00	3186.83	25.82	-163.04	-6.44	0.00	
3300.00	10.00	279.00	3285.31	28.54	-180.19	-7.11	0.00	
3400.00	10.00	279.00	3383.79	31.26	-197.35	-7.79	0.00	
3500.00	10.00	279.00	3482.27	33.97	-214.50	-8.47	0.00	
3600.00	10.00	279.00	3580.75	36.69	-231.65	-9.14	0.00	
3700.00	10.00	279.00	3679.23	39.41	-248.80	-9.82	0.00	
3800.00	10.00	279.00	3777.72	42.12	-265.95	-10.50	0.00	
3900.00	10.00	279.00	3876.20	44.84	-283.10	-11.17	0.00	
4000.00	10.00	279.00	3974.68	47.55	-300.25	-11.85	0.00	
4100.00	10.00	279.00	4073.16	50.27	-317.40	-12.53	0.00	
4200.00	10.00	279.00	4171.64	52.99	-334.55	-13.21	0.00	
4300.00	10.00	279.00	4270.12	55.70	-351.71	-13.88	0.00	
4400.00	10.00	279.00	4368.60	58.42	-368.86	-14.56	0.00	
4500.00	10.00	279.00	4467.08	61.14	-386.01	-15.24	0.00	
4600.00	10.00	279.00	4565.56	63.85	-403.16	-15.91	0.00	
4700.00	10.00	279.00	4664.04	66.57	-420.31	-16.59	0.00	
4800.00	10.00	279.00	4762.52	69.29	-437.46	-17.27	0.00	
4900.00	10.00	279.00	4861.00	72.00	-454.61	-17.94	0.00	
5000.00	10.00	279.00	4959.48	74.72	-471.76	-18.62	0.00	
5100.00	10.00	279.00	5057.97	77.43	-488.91	-19.30	0.00	
5112.22	10.00	279.00	5070.00	77.77	-491.01	-19.38	0.00	Base of Salt
5200.00	10.00	279.00	5156.45	80.15	-506.06	-19.98	0.00	
5300.00	10.00	279.00	5254.93	82.87	-523.22	-20.65	0.00	
5376.23	10.00	279.00	5330.00	84.94	-536.29	-21.17	0.00	Delaware
5400.00	10.00	279.00	5353.41	85.58	-540.37	-21.33	0.00	
5500.00	10.00	279.00	5451.89	88.30	-557.52	-22.01	0.00	
5600.00	10.00	279.00	5550.37	91.02	-574.67	-22.68	0.00	
5700.00	10.00	279.00	5648.85	93.73	-591.82	-23.36	0.00	
5800.00	10.00	279.00	5747.33	96.45	-608.97	-24.04	0.00	
5900.00	10.00	279.00	5845.81	99.17	-626.12	-24.71	0.00	
6000.00	10.00	279.00	5944.29	101.88	-643.27	-25.39	0.00	
6100.00	10.00	279.00	6042.77	104.60	-660.42	-26.07	0.00	
6200.00	10.00	279.00	6141.25	107.31	-677.57	-26.74	0.00	
6300.00	10.00	279.00	6239.73	110.03	-694.73	-27.42	0.00	
6400.00	10.00	279.00	6338.22	112.75	-711.88	-28.10	0.00	
6437.35	10.00	279.00	6375.00	113.76	-718.28	-28.35	0.00	Cherry Canyon
6500.00	10.00	279.00	6436.70	115.46	-729.03	-28.78	0.00	

BOLL WEEVIL 27-34 FED COM 1H



Well: BOLL WEEVIL 27-34 FED COM 1H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD (ft)	INC (°)	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
6600.00	10.00	279.00	6535.18	118.18	-746.18	-29.45	0.00	
6700.00	10.00	279.00	6633.66	120.90	-763.33	-30.13	0.00	
6800.00	10.00	279.00	6732.14	123.61	-780.48	-30.81	0.00	
6900.00	10.00	279.00	6830.62	126.33	-797.63	-31.48	0.00	
7000.00	10.00	279.00	6929.10	129.05	-814.78	-32.16	0.00	
7100.00	10.00	279.00	7027.58	131.76	-831.93	-32.84	0.00	
7200.00	10.00	279.00	7126.06	134.48	-849.08	-33.51	0.00	
7300.00	10.00	279.00	7224.54	137.19	-866.24	-34.19	0.00	
7400.00	10.00	279.00	7323.02	139.91	-883.39	-34.87	0.00	
7500.00	10.00	279.00	7421.50	142.63	-900.54	-35.55	0.00	
7600.00	10.00	279.00	7519.99	145.34	-917.69	-36.22	0.00	
7616.63	10.00	279.00	7536.37	145.80	-920.54	-36.34	0.00	Drop to Vertical
7700.00	8.33	279.00	7618.66	147.88	-933.66	-36.86	2.00	
7800.00	6.33	279.00	7717.84	149.87	-946.26	-37.35	2.00	
7900.00	4.33	279.00	7817.40	151.33	-955.44	-37.72	2.00	
8000.00	2.33	279.00	7917.23	152.24	-961.18	-37.94	2.00	
8062.80	1.08	279.00	7980.00	152.53	-963.03	-38.02	2.00	Brushy Canyon
8100.00	0.33	279.00	8017.20	152.60	-963.48	-38.03	2.00	
8116.63	0.00	279.00	8033.83	152.61	-963.53	-38.03	2.00	Hold Vertical
8200.00	0.00	179.51	8117.20	152.61	-963.53	-38.04	0.00	
8300.00	0.00	179.51	8217.20	152.61	-963.53	-38.04	0.00	
8400.00	0.00	179.51	8317.20	152.61	-963.53	-38.04	0.00	
8500.00	0.00	179.51	8417.20	152.61	-963.53	-38.04	0.00	
8600.00	0.00	179.51	8517.20	152.61	-963.53	-38.04	0.00	
8700.00	0.00	179.51	8617.20	152.61	-963.53	-38.04	0.00	
8800.00	0.00	179.51	8717.20	152.61	-963.53	-38.04	0.00	
8900.00	0.00	179.51	8817.20	152.61	-963.53	-38.04	0.00	
9000.00	0.00	179.51	8917.20	152.61	-963.53	-38.04	0.00	
9100.00	0.00	179.51	9017.20	152.61	-963.53	-38.04	0.00	
9200.00	0.00	179.51	9117.20	152.61	-963.53	-38.04	0.00	
9300.00	0.00	179.51	9217.20	152.61	-963.53	-38.04	0.00	
9400.00	0.00	179.51	9317.20	152.61	-963.53	-38.04	0.00	
9500.00	0.00	179.51	9417.20	152.61	-963.53	-38.04	0.00	
9600.00	0.00	179.51	9517.20	152.61	-963.53	-38.04	0.00	
9700.00	0.00	179.51	9617.20	152.61	-963.53	-38.04	0.00	
9800.00	0.00	179.51	9717.20	152.61	-963.53	-38.04	0.00	
9900.00	0.00	179.51	9817.20	152.61	-963.53	-38.04	0.00	
10000.00	0.00	179.51	9917.20	152.61	-963.53	-38.04	0.00	
10100.00	0.00	179.51	10017.20	152.61	-963.53	-38.04	0.00	
10200.00	0.00	179.51	10117.20	152.61	-963.53	-38.04	0.00	
10300.00	0.00	179.51	10217.20	152.61	-963.53	-38.04	0.00	
10400.00	0.00	179.51	10317.20	152.61	-963.53	-38.04	0.00	
10500.00	0.00	179.51	10417.20	152.61	-963.53	-38.04	0.00	
10600.00	0.00	179.51	10517.20	152.61	-963.53	-38.04	0.00	
10672.80	0.00	179.51	10590.00	152.61	-963.53	-38.04	0.00	Bone Spring 1st
10700.00	0.00	179.51	10617.20	152.61	-963.53	-38.04	0.00	
10800.00	0.00	179.51	10717.20	152.61	-963.53	-38.04	0.00	
10900.00	0.00	179.51	10817.20	152.61	-963.53	-38.04	0.00	
11000.00	0.00	179.51	10917.20	152.61	-963.53	-38.04	0.00	
11100.00	0.00	179.51	11017.20	152.61	-963.53	-38.04	0.00	
11200.00	0.00	179.51	11117.20	152.61	-963.53	-38.04	0.00	
11222.80	0.00	179.51	11140.00	152.61	-963.53	-38.04	0.00	Bone Spring 2nd
11300.00	0.00	179.51	11217.20	152.61	-963.53	-38.04	0.00	
11400.00	0.00	179.51	11317.20	152.61	-963.53	-38.04	0.00	
11500.00	0.00	179.51	11417.20	152.61	-963.53	-38.04	0.00	
11600.00	0.00	179.51	11517.20	152.61	-963.53	-38.04	0.00	
11700.00	0.00	179.51	11617.20	152.61	-963.53	-38.04	0.00	
11800.00	0.00	179.51	11717.20	152.61	-963.53	-38.04	0.00	
11900.00	0.00	179.51	11817.20	152.61	-963.53	-38.04	0.00	
12000.00	0.00	179.51	11917.20	152.61	-963.53	-38.04	0.00	
12100.00	0.00	179.51	12017.20	152.61	-963.53	-38.04	0.00	
12109.84	0.00	179.51	12027.04	152.61	-963.53	-38.03	0.00	KOP
12200.00	9.02	179.51	12116.83	145.53	-963.47	-31.01	10.00	
12285.54	17.57	179.51	12200.00	125.88	-963.30	-11.52	10.00	Bone Spring 3rd / Point of Penetration
12300.00	19.02	179.51	12213.73	121.34	-963.26	-7.02	10.00	
12400.00	29.02	179.51	12304.95	80.70	-962.91	33.30	10.00	
12500.00	39.02	179.51	12387.74	24.83	-962.44	88.72	10.00	
12600.00	49.02	179.51	12459.56	-44.57	-961.84	157.57	10.00	
12700.00	59.02	179.51	12518.24	-125.38	-961.15	237.73	10.00	
12800.00	69.02	179.51	12562.00	-215.15	-960.38	326.79	10.00	

BOLL WEEVIL 27-34 FED COM 1H



Well: BOLL WEEVIL 27-34 FED COM 1H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD (ft)	INC (°)	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
12900.00	79.02	179.51	12589.50	-311.16	-959.56	422.04	10.00	
13000.00	89.02	179.51	12599.92	-410.49	-958.71	520.57	10.00	
13009.84	90.00	179.51	12600.00	-420.33	-958.63	530.34	10.00	Landing Point
13100.00	90.00	179.51	12600.00	-510.48	-957.86	619.77	0.00	
13200.00	90.00	179.51	12600.00	-610.48	-957.00	718.97	0.00	
13300.00	90.00	179.51	12600.00	-710.47	-956.15	818.17	0.00	
13400.00	90.00	179.51	12600.00	-810.47	-955.29	917.37	0.00	
13500.00	90.00	179.51	12600.00	-910.47	-954.44	1016.57	0.00	
13600.00	90.00	179.51	12600.00	-1010.46	-953.58	1115.76	0.00	
13700.00	90.00	179.51	12600.00	-1110.46	-952.72	1214.96	0.00	
13800.00	90.00	179.51	12600.00	-1210.46	-951.87	1314.16	0.00	
13900.00	90.00	179.51	12600.00	-1310.45	-951.01	1413.36	0.00	
14000.00	90.00	179.51	12600.00	-1410.45	-950.16	1512.56	0.00	
14100.00	90.00	179.51	12600.00	-1510.44	-949.30	1611.76	0.00	
14200.00	90.00	179.51	12600.00	-1610.44	-948.45	1710.96	0.00	
14300.00	90.00	179.51	12600.00	-1710.44	-947.59	1810.16	0.00	
14400.00	90.00	179.51	12600.00	-1810.43	-946.74	1909.36	0.00	
14500.00	90.00	179.51	12600.00	-1910.43	-945.88	2008.56	0.00	
14600.00	90.00	179.51	12600.00	-2010.43	-945.03	2107.76	0.00	
14700.00	90.00	179.51	12600.00	-2110.42	-944.17	2206.96	0.00	
14800.00	90.00	179.51	12600.00	-2210.42	-943.31	2306.16	0.00	
14900.00	90.00	179.51	12600.00	-2310.42	-942.46	2405.35	0.00	
15000.00	90.00	179.51	12600.00	-2410.41	-941.60	2504.55	0.00	
15100.00	90.00	179.51	12600.00	-2510.41	-940.75	2603.75	0.00	
15200.00	90.00	179.51	12600.00	-2610.40	-939.89	2702.95	0.00	
15300.00	90.00	179.51	12600.00	-2710.40	-939.04	2802.15	0.00	
15400.00	90.00	179.51	12600.00	-2810.40	-938.18	2901.35	0.00	
15500.00	90.00	179.51	12600.00	-2910.39	-937.33	3000.55	0.00	
15600.00	90.00	179.51	12600.00	-3010.39	-936.47	3099.75	0.00	
15700.00	90.00	179.51	12600.00	-3110.39	-935.62	3198.95	0.00	
15800.00	90.00	179.51	12600.00	-3210.38	-934.76	3298.15	0.00	
15900.00	90.00	179.51	12600.00	-3310.38	-933.90	3397.35	0.00	
16000.00	90.00	179.51	12600.00	-3410.38	-933.05	3496.55	0.00	
16100.00	90.00	179.51	12600.00	-3510.37	-932.19	3595.75	0.00	
16200.00	90.00	179.51	12600.00	-3610.37	-931.34	3694.94	0.00	
16300.00	90.00	179.51	12600.00	-3710.36	-930.48	3794.14	0.00	
16400.00	90.00	179.51	12600.00	-3810.36	-929.63	3893.34	0.00	
16500.00	90.00	179.51	12600.00	-3910.36	-928.77	3992.54	0.00	
16600.00	90.00	179.51	12600.00	-4010.35	-927.92	4091.74	0.00	
16700.00	90.00	179.51	12600.00	-4110.35	-927.06	4190.94	0.00	
16800.00	90.00	179.51	12600.01	-4210.35	-926.21	4290.14	0.00	
16900.00	90.00	179.51	12600.01	-4310.34	-925.35	4389.34	0.00	
17000.00	90.00	179.51	12600.01	-4410.34	-924.49	4488.54	0.00	
17100.00	90.00	179.51	12600.01	-4510.34	-923.64	4587.74	0.00	
17200.00	90.00	179.51	12600.01	-4610.33	-922.78	4686.94	0.00	
17300.00	90.00	179.51	12600.01	-4710.33	-921.93	4786.14	0.00	
17400.00	90.00	179.51	12600.01	-4810.32	-921.07	4885.34	0.00	
17500.00	90.00	179.51	12600.01	-4910.32	-920.22	4984.54	0.00	
17600.00	90.00	179.51	12600.01	-5010.32	-919.36	5083.73	0.00	
17700.00	90.00	179.51	12600.01	-5110.31	-918.51	5182.93	0.00	
17800.00	90.00	179.51	12600.01	-5210.31	-917.65	5282.13	0.00	
17900.00	90.00	179.51	12600.01	-5310.31	-916.80	5381.33	0.00	
18000.00	90.00	179.51	12600.01	-5410.30	-915.94	5480.53	0.00	
18100.00	90.00	179.51	12600.01	-5510.30	-915.08	5579.73	0.00	
18200.00	90.00	179.51	12600.01	-5610.29	-914.23	5678.93	0.00	
18300.00	90.00	179.51	12600.01	-5710.29	-913.37	5778.13	0.00	
18400.00	90.00	179.51	12600.01	-5810.29	-912.52	5877.33	0.00	
18500.00	90.00	179.51	12600.01	-5910.28	-911.66	5976.53	0.00	
18600.00	90.00	179.51	12600.01	-6010.28	-910.81	6075.73	0.00	
18700.00	90.00	179.51	12600.01	-6110.28	-909.95	6174.93	0.00	
18800.00	90.00	179.51	12600.01	-6210.27	-909.10	6274.13	0.00	
18900.00	90.00	179.51	12600.01	-6310.27	-908.24	6373.32	0.00	
19000.00	90.00	179.51	12600.01	-6410.27	-907.38	6472.52	0.00	
19100.00	90.00	179.51	12600.01	-6510.26	-906.53	6571.72	0.00	
19200.00	90.00	179.51	12600.01	-6610.26	-905.67	6670.92	0.00	
19300.00	90.00	179.51	12600.01	-6710.25	-904.82	6770.12	0.00	
19400.00	90.00	179.51	12600.01	-6810.25	-903.96	6869.32	0.00	
19500.00	90.00	179.51	12600.01	-6910.25	-903.11	6968.52	0.00	
19600.00	90.00	179.51	12600.01	-7010.24	-902.25	7067.72	0.00	
19700.00	90.00	179.51	12600.01	-7110.24	-901.40	7166.92	0.00	

BOLL WEEVIL 27-34 FED COM 1H



Well: BOLL WEEVIL 27-34 FED COM 1H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD	INC	AZI	TVD	NS	EW	VS	DLS	Comment
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	
19800.00	90.00	179.51	12600.01	-7210.24	-900.54	7266.12	0.00	
19900.00	90.00	179.51	12600.01	-7310.23	-899.69	7365.32	0.00	
20000.00	90.00	179.51	12600.01	-7410.23	-898.83	7464.52	0.00	
20075.43	90.00	179.51	12600.01	-7485.65	-898.19	7539.34	0.00	exit
20100.00	90.00	179.51	12600.01	-7510.23	-897.97	7563.72	0.00	
20155.43	90.00	179.51	12600.00	-7565.65	-897.52	7618.70	0.00	BHL

BOLL WEEVIL 27-34 FED COM 1H

1. Geologic Formations

TVD of target	12600	Pilot hole depth	N/A
MD at TD:	20155	Deepest expected fresh water	

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone?	Hazards*
Rustler	860		
Salt	1200		
Base of Salt	5070		
Delaware	5330		
Cherry Canyon	6375		
Brushy Canyon	7980		
Bone Spring 1st	10590		
Bone Spring 2nd	11140		
Bone Spring 3rd	12200		

*H2S, water flows, loss of circulation, abnormal pressures, etc.

BOLL WEEVIL 27-34 FED COM 1H

2. Casing Program (Primary Design)

Hole Size	Csg. Size	Wt (PPF)	Grade	Conn	Casing Interval		Casing Interval	
					From (MD)	To (MD)	From (TVD)	To (TVD)
14 3/4	10 3/4	45 1/2	J-55	BTC	0	885	0	885
9 7/8	8 5/8	32	P110	Sprint FJ	0	12009	0	12009
7 7/8	5 1/2	20	P110	DWC / C-IS+	0	20155	0	12600

•All casing strings will be tested in accordance with 43 CFR 3172. Must have table for contingency casing.

3. Cementing Program (Primary Design)

Assuming no returns are established while drilling, Devon requests to pump a two stage cement job on the intermediate casing string with the first stage being pumped conventionally with the calculated top of cement at the Brushy Canyon and the second stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. The final cement top will be verified by Echo-meter. Devon will include the Echo-meter verified fluid top and the volume of displacement fluid above the cement slurry in the annulus in all post-drill sundries on wells utilizing this cement program. Devon will report to the BLM the volume of fluid (limited to 1 bbls) used to flush intermediate casing valves following backside cementing procedures.

Casing	# Sks	TOC	Wt. ppg	Yld (ft3/sack)	Slurry Description
Surface	537	Surf	13.2	1.44	Lead: Class C Cement + additives
Int 1	568	Surf	13.0	2.3	2nd State: Bradenhead Squeeze - Lead: Class C Cement + additives
	459	8062	13.2	1.44	Tail: Class H / C + additives
Production	35	11509	9	3.27	Lead: Class H / C + additives
	1065	12110	13.2	1.44	Tail: Class H / C + additives

Casing String	% Excess
Surface	50%
Intermediate 1	30%
Prod	10%

BOLL WEEVIL 27-34 FED COM 1H

4. Pressure Control Equipment (Three String Design)

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
Int 1	13-5/8"	5M	Annular	X	50% of rated working pressure
			Blind Ram	X	5M
			Pipe Ram		
			Double Ram	X	
			Other*		
Production	13-5/8"	5M	Annular (5M)	X	50% of rated working pressure
			Blind Ram	X	5M
			Pipe Ram		
			Double Ram	X	
			Other*		
			Annular (5M)		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		
N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.				
Y	A variance is requested to run a 5 M annular on a 10M system				

BOLL WEEVIL 27-34 FED COM 1H

5. Mud Program (Three String Design)

Section	Type	Weight (ppg)
Surface	FW Gel	8.5-9
Intermediate	DBE / Cut Brine	10-10.5
Production	OBM	8.5-9

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well - vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain.
	Coring? If yes, explain.

Additional logs planned		Interval
	Resistivity	Int. shoe to KOP
	Density	Int. shoe to KOP
X	CBL	Production casing
X	Mud log	Intermediate shoe to TD
	PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH pressure at deepest TVD	5897
Abnormal temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of 43 CFR 3176. If Hydrogen Sulfide is encountered measured values and formations will be provided to the BLM.

N	H ₂ S is present
Y	H ₂ S plan attached.

BOLL WEEVIL 27-34 FED COM 1H

8. Other facets of operation

Is this a walking operation? Potentially

- 1 If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
- 2 The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
- 3 The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially

- 1 Spudder rig will move in and batch drill surface hole.
 - a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.,
- 2 After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (43 CFR 3172, all COAs and NMOCD regulations).
- 3 The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
- 4 A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
- 5 Spudder rig operations is expected to take 4-5 days per well on a multi-well pa.
- 6 The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 7 Drilling operations will be performed with drilling rig. A that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

Attachments

X Directional Plan
 Other, describe

DISTRICT I
1625 N. FRENCH DR., HOBBS, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

DISTRICT II
811 S. FIRST ST., ARTESIA, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720

DISTRICT III
1000 RIO BRAZOS RD., AZTEC, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

DISTRICT IV
1220 S. ST. FRANCIS DR., SANTA FE, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 SOUTH ST. FRANCIS DR.
Santa Fe, New Mexico 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☒ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-025-47948	Pool Code 96672	Pool Name WC-025 G-08 S263412K;BONE SPRING
Property Code 329772	Property Name BOLL WEEVIL 27-34 FED COM	Well Number 1H
OGRID No. 6137	Operator Name DEVON ENERGY PRODUCTION COMPANY, L.P.	Elevation 3266.2'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
C	27	26-S	34-E		210	NORTH	1321	WEST	LEA

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
4	34	26-S	34-E		20	SOUTH	360	WEST	LEA

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
235.99			

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

BOLL WEEVIL 27-34 FED COM 1H
EL: 3266.2'
GEODETIC COORDINATES NAD 83
NMSP EAST SURFACE LOCATION
N: 372507.67
E: 811377.79
LAT: 32.021111
LON: 103.462017

KICK OFF POINT
CALLS: S1° FNL, 359° FWL
N: 372660
E: 810414
LAT: 32.0215
LON: -103.4652

FIRST TAKE POINT (PPP 1)
100' FNL 360° FWL SEC. 27
N: 372611.69
E: 810415.66
LAT: 32.021418
LON: 103.465119

LAST TAKE POINT
100' FSL 360° FWL SEC. 34
N: 365022.01
E: 810479.60
LAT: 32.000555
LON: 103.465109

BOTTOM OF HOLE
N: 364942.02
E: 810480.27
LAT: 32.000335
LON: 103.465109

(PPP 2)
0' FSL 360° FWL SEC. 27
N: 367432.17
E: 810459.29
LAT: 32.007180
LON: 103.465112

OPERATOR CERTIFICATION

I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Rebecca Deal 1/22/2024
Signature Date

Rebecca Deal, Regulatory Analyst
Printed Name


rebecca.deal@dm.com
E-mail Address

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

01/2024
Date of Survey

Signature & Seal of Professional Surveyor



1/16/2024
Certificate No. 23261 A.DeHoyos
DRAWN BY: CM

A = N:372709.44 E:810054.86
B = N:372725.87 E:812693.37
C = N:372740.00 E:815333.32
D = N:370101.40 E:815354.84
E = N:367462.64 E:815376.57
F = N:364961.74 E:815396.18
G = N:364919.11 E:810120.45
H = N:367429.47 E:810099.25
I = N:370071.47 E:810076.10
J = N:367449.27 E:812738.00

Intent ☒ As Drilled ☐

API #		
Operator Name: DEVON ENERGY PRODUCTION COMPANY, LP.	Property Name: BOLL WEEVIL 27-34 FED COM	Well Number 1H

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
	27	26S	34E		51	FNL	359	FWL	LEA
Latitude 32.0215					Longitude -103.4652				NAD 83

First Take Point (FTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
D	27	26-S	34-E		100	NORTH	360	WEST	LEA
Latitude 32.021418					Longitude 103.465119				NAD 83

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
	34	26-S	34-E	4	100	SOUTH	360	WEST	LEA
Latitude 32.000555					Longitude 103.465109				NAD 83

Is this well the defining well for the Horizontal Spacing Unit? ☐ YIs this well an infill well? ☐ N

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name:	Property Name:	Well Number

KZ 06/29/2018

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 316286

CONDITIONS

Operator: DEVON ENERGY PRODUCTION COMPANY, LP 333 West Sheridan Ave. Oklahoma City, OK 73102	OGRID: 6137
	Action Number: 316286
	Action Type: [C-103] NOI Change of Plans (C-103A)

CONDITIONS

Created By	Condition	Condition Date
pkautz	None	3/18/2024