

Form 3160-3
(June 2015)FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input type="checkbox"/> DRILL <input type="checkbox"/> REENTER 1b. Type of Well: <input type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		5. Lease Serial No. 6. If Indian, Allottee or Tribe Name 7. If Unit or CA Agreement, Name and No. 8. Lease Name and Well No. 9. API Well No. <div style="color: red; text-align: center;">30-045-38434</div>
2. Name of Operator 3a. Address 3b. Phone No. (include area code)		10. Field and Pool, or Exploratory 11. Sec., T. R. M. or Blk. and Survey or Area 12. County or Parish 13. State
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface At proposed prod. zone		14. Distance in miles and direction from nearest town or post office* 15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 16. No of acres in lease 17. Spacing Unit dedicated to this well 18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 19. Proposed Depth 20. BLM/BIA Bond No. in file 21. Elevations (Show whether DF, KDB, RT, GL, etc.) 22. Approximate date work will start* 23. Estimated duration
24. Attachments The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)		

- | | |
|---|---|
| 1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM. |
|---|---|

25. Signature	Name (Printed/Typed)	Date
Title		
Approved by (Signature)	Name (Printed/Typed)	Date
Title		Office

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
 Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)



Approval Date: 01/27/2025

Additional Operator Remarks

Location of Well

0. SHL: NWSE / 1788 FSL / 1670 FEL / TWSP: 23N / RANGE: 9W / SECTION: 6 / LAT: 36.253568 / LONG: -107.826866 (TVD: 0 feet, MD: 0 feet)

PPP: SWSE / 1093 FSL / 2397 FEL / TWSP: 23N / RANGE: 9W / SECTION: 6 / LAT: 36.25167 / LONG: -107.829323 (TVD: 4669 feet, MD: 4936 feet)

PPP: LOT 1 / 1316 FNL / 1 FEL / TWSP: 23N / RANGE: 10W / SECTION: 1 / LAT: 36.259632 / LONG: -107.839154 (TVD: 4795 feet, MD: 10782 feet)

PPP: NESW / 1334 FSL / 2651 FWL / TWSP: 23N / RANGE: 9W / SECTION: 6 / LAT: 36.252333 / LONG: -107.830141 (TVD: 4795 feet, MD: 10782 feet)

BHL: LOT 1 / 232 FNL / 1074 FEL / TWSP: 23N / RANGE: 10W / SECTION: 1 / LAT: 36.262589 / LONG: -107.842806 (TVD: 4795 feet, MD: 10782 feet)

BLM Point of Contact

Name: CHRISTOPHER P WENMAN

Title: Natural Resource Specialist

Phone: (505) 564-7727

Email: cwenman@blm.gov

CONFIDENTIAL

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024	
		Submittal Type:	<input checked="" type="checkbox"/> Initial Submittal <input type="checkbox"/> Amended Report <input type="checkbox"/> As Drilled

WELL LOCATION INFORMATION

API Number 30-045-38434	Pool Code 5860	Pool Name BISTI; S-GALLUP (0)
Property Code 336968	Property Name PONDEROSA UNIT	Well Number 119H
OGRID No. 371838	Operator Name DJR OPERATING, LLC	Ground Level Elevation 6711'
Surface Owner: <input type="checkbox"/> State <input type="checkbox"/> Fee <input type="checkbox"/> Tribal <input checked="" type="checkbox"/> Federal		Mineral Owner: <input type="checkbox"/> State <input type="checkbox"/> Fee <input type="checkbox"/> Tribal <input checked="" type="checkbox"/> Federal

Surface Location (SHL)

UL	Section	Township	Range	Lot	Ft from the N/S	Ft from the E/W	Latitude	Longitude	County
J	6	23N	9W		1788' SOUTH	1670' EAST	36.253568° N	107.826866° W	SAN JUAN

Bottom Hole Location (BHL)

UL	Section	Township	Range	Lot	Ft from the N/S	Ft from the E/W	Latitude	Longitude	County
A	1	23N	10W	1	232' NORTH	1074' EAST	36.262589° N	107.842806° W	SAN JUAN

Dedicated Acres PENETRATED SPACING UNIT; SEC 6: NW/SE, SW/SE, SE/SW, NE/SW, LOT 6, SE/NW, LOT 5 & LOT 4 (321.94 AC.); SEC 1: SE/NE, LOT 1 & LOT 2 (119.72 AC.) = 441.66 ACRES	Infill or Defining Well	Defining Well API	Overlapping Spacing Unit (Y/N)	Consolidation Code
			N	UNIT
Order Numbers: R-14194		Well Setbacks are under Common Ownership: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Ft from the N/S	Ft from the E/W	Latitude	Longitude	County
O	6	23N	9W		1093' SOUTH	2397' EAST	36.251670° N	107.829323° W	SAN JUAN

Fist Take Point (FTP)

UL	Section	Township	Range	Lot	Ft from the N/S	Ft from the E/W	Latitude	Longitude	County
O	6	23N	9W		1093' SOUTH	2397' EAST	36.251670° N	107.829323° W	SAN JUAN

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Ft from the N/S	Ft from the E/W	Latitude	Longitude	County
A	1	23N	10W	1	232' NORTH	1074' EAST	36.262589° N	107.842806° W	SAN JUAN

Unitized Area or Area of Uniform Interest PONDEROSA UNIT	Spacing Unit Type <input checked="" type="checkbox"/> Horizontal <input type="checkbox"/> Vertical	Ground Floor Elevation
--	--	------------------------

OPERATOR CERTIFICATIONS

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, **and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest or unleased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.**

If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.

Shaw-Marie Ford
Signature


12/4/2024
Date

Shaw-Marie Ford
Printed Name

sford@enduringresources.com
E-mail Address

SURVEYOR CERTIFICATIONS

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.



Signature and Seal of Professional Surveyor:

Certificate Number

11393


Date of Survey

JULY 3, 2024


Note: No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

● FND 2 1/2" BC
GLO 1947

● FND 2 1/2" BC
GLO 1942



DETAIL



SURFACE LOCATION (SHL) ●
1788' FSL 1670' FEL
SEC. 6, T23N, R9W
LAT. 36.253568° N (NAD83)
LONG. 107.826866° W (NAD83)

FIRST TAKE POINT (FTP) ◇
1093' FSL 2397' FEL
SEC. 6, T23N, R9W
LAT. 36.251670° N (NAD83)
LONG. 107.829323° W (NAD83)

BOTTOM HOLE LOCATION (BHL) ○
232' FNL 1074' FEL
SEC. 1, T23N, R10W
LAT. 36.262589° N (NAD83)
LONG. 107.842806° W (NAD83)

KICK OFF POINT (KOP) △
1093' FSL 2397' FEL
SEC. 6, T23N, R9W
LAT. 36.251670° N (NAD83)
LONG. 107.829323° W (NAD83)

LAST TAKE POINT (LTP) □
232' FNL 1074' FEL
SEC. 1, T23N, R10W
LAT. 36.262589° N (NAD83)
LONG. 107.842806° W (NAD83)

State of New Mexico
Energy, Minerals and Natural Resources Department

Submit Electronically
Via E-permitting

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description

Effective May 25, 2021

I. Operator: DJR Operating, LLC **OGRID:** 371838 **Date:** 01/13/2025

II. Type: ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
Ponderosa J06 2309 FED COM 118H	TBD	J-06-23N-09W	1768' FSL x 1668' FEL	406	914	162
Ponderosa J06 2309 FED COM 121H	TBD	J-06-23N-09W	1729' FSL x 1663' FEL	260	65	104
Ponderosa J06 2309 FED COM 123H	TBD	J-06-23N-09W	1748' FSL x 1665' FEL	439	988	176
Ponderosa Unit 100H	TBD	J-06-23N-09W	1807' FSL x 1673 FEL	265	69	107
Ponderosa Unit 119H	TBD	J-06-23N-09W	1788' FSL x 1670 FEL	403	907	157
Ponderosa Unit 122H	TBD	J-06-23N-09W	1827' FSL x 1676' FEL	444	867	114

IV. Central Delivery Point Name: Chaco Processing Plant [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Ponderosa J06 2309 FED COM 118H	TBD	3/21/2025	3/29/2025	5/17/2025	5/29/2025	6/1/2025
Ponderosa J06 2309 FED COM 121H	TBD	3/30/2025	4/8/2025	5/17/2025	6/3/2025	6/6/2025
Ponderosa J06 2309 FED COM 123H	TBD	4/9/2025	4/18/2025	5/17/2025	6/8/2025	6/11/2025
Ponderosa Unit 100H	TBD	4/18/2025	4/27/2025	5/17/2025	6/13/2025	6/16/2025
Ponderosa Unit 119H	TBD	4/27/2025	5/6/2025	5/17/2025	6/18/2025	6/21/2025
Ponderosa Unit 122H	TBD	5/6/2024	5/15/2025	5/17/2025	6/23/2025	6/26/2025

VI. Separation Equipment: ☒ Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan**EFFECTIVE APRIL 1, 2022**

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☒ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. ☐ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system ☐ will ☐ will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator ☐ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

XIV. Confidentiality: ☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☒ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature: <i>Shaw-Marie Ford</i>
Printed Name: Shaw-Marie Ford
Title: Regulatory Specialist
E-mail Address: sford@enduringresources.com
Date: 01/13/2025
Phone: 505-716-3297
OIL CONSERVATION DIVISION (Only applicable when submitted as a standalone form)
Approved By:
Title:
Approval Date:
Conditions of Approval:



DJR OPERATING, LLC.
OGRID NO: 371838
NATURAL GAS MANAGEMENT PLAN
Ponderosa J06 2309 FED COM 118H, 121H, 123H and
Ponderosa Unit 100H, 119H, 122H
NWSE J-06-23N-09W

SEPARATION EQUIPMENT

DJR Operating, LLC (DJR) has pulled representative pressurized samples from wells in the same producing formation. DJR has utilized these samples in process simulations to determine the amount of gas anticipated in each stage of the process and utilized this information with a safety factor to size the equipment listed below:

Separation equipment will be set as follows:

- Individual 3-phase separator will be set for the individual well.
- The separator will be sized based on the anticipated volume of the well and the pressure of the lines utilized for oil, gas, and water takeaway.
- The 3-phase production separator will be equipped with a 0.75 MMBtu/hr indirect fired heater.

Heater treaters will be set as follows:

- Individual heater treaters will be set for the individual well.
- The heater treaters are sized based on the anticipated combined volume of oil and produced water predicted to come from the initial 3-phase separator.
- Oil will be separated from the produced water and the oil/produced water will be sent to its respective tanks.
- The combined oil and natural gas stream is routed to the Vapor Recovery Tower.

Vapor Recovery Equipment will be set as follows:

- The Vapor Recovery Tower has been sized, based on the anticipated volume of gas from the heater treater and oil and water tanks.
- The Vapor Recovery Unit has been sized, based on the anticipated volume of gas from the heater treater and oil and water tanks. The Vapor Recovery Unit is utilized to push the recovered gas into the sales pipeline.

Production storage tanks will be set as follows:

- The oil and produced water tanks utilize a closed vent capture system to ensure all breathing, working, and flashing losses are routed to the Vapor Recovery Tower and Vapor Recovery Unit.
- Each of the production storage tanks will be equipped with a 0.5 MMBtu/hr indirect heater.



DJR OPERATING, LLC.
OGRID NO: 371838
NATURAL GAS MANAGEMENT PLAN
Ponderosa J06 2309 FED COM 118H, 121H, 123H and
Ponderosa Unit 100H, 119H, 122H
NWSE J-06-23N-09W

VENTING and FLARING

DJR Operating, LLC (DJR) has a natural gas system available prior to startup of completion operations. DJR utilizes a Vapor Recovery Unit System and sells all natural gas except during periods of startup, shutdown, maintenance, or malfunction for the gas capturing equipment, including the vapor recovery tower, vapor recovery unit, storage tanks, and pipelines.

Currently, DJR utilizes the following from list A-I of Section 3 for its operations to minimize flaring:

- a) DJR utilizes natural gas-powered generators to power its leases where grid power isn't available.
- b) When electrical grid power is unavailable, natural gas generators will be used for major equipment onsite.
- c) DJR's in service compression will be natural gas powered.
- d) Should liquids removal, such as dehydration be required, units will be powered by natural gas.

DJR will only flare gas during the following times:

- Scheduled maintenance for gas capturing equipment including:
 - Vapor Recovery Tower
 - Vapor Recovery Unit
 - Storage tanks
 - Pipelines
 - Emergency flaring



DJR OPERATING, LLC.
OGRID NO: 371838
NATURAL GAS MANAGEMENT PLAN
Ponderosa J06 2309 FED COM 118H, 121H, 123H and
Ponderosa Unit 100H, 119H, 122H
NWSE J-06-23N-09W

OPERATIONAL PRACTICES

19.15.27.8 A. Venting and Flaring of Natural Gas

DJR Operating, LLC (DJR) understands the requirements of NMAC 19.15.27.8 which states that the venting and flaring of natural gas during drilling, completion or production that constitutes waste as defined in 19.15.2 are prohibited.

19.15.27.8 B. Venting and flaring during drilling operations

- DJR shall capture or combust natural gas if technically feasible during drilling operations using best industry practices.
- A flare stack with a 100% capacity for expected volumes will be set on location of the facility at least 100 feet from the nearest surface hole location, well heads, and storage tanks.
- In the event of an emergency, DJR will vent natural gas in order to avoid substantial impact. DJR shall report the vented or flared gas to the NMOCD.

19.15.27.8 E. Venting and flaring during completion or recompletion operations

During Completion Operations, DJR utilizes the following:

- DJR facilities are built and ready from day 1 of Flowback.
- Individual well test separators will be set to properly separate gas and liquids. Temporary test separator will be utilized initially to process volumes. In addition, separators will be tied into flowback tanks which will be tied into the gas processing equipment for sales down a pipeline. See Separation Equipment for details.
- Should the facility not yet be capable of processing gas, or the gas does not meet quality standards, then storage tanks will be set that are tied into gas busters or temporary flare to manage natural gas. This flare would meet the following requirements:
 - 1) An appropriately sized flare stack with an automatic igniter.
 - 2) DJR analyzes the natural gas samples twice per week.
 - 3) DJR routes the natural gas into a gathering pipeline as soon as the pipeline specifications are met.
 - 4) DJR provides the NMOCD with pipeline specifications and natural gas data.



19.15.27.8 D. Venting and flaring during production operations

During Production Operations DJR will not vent or flare natural gas except under the following circumstances:

1. During an emergency or malfunction
2. To unload or clean-up liquid holdup in a well to atmospheric pressure, provided:
 - a. DJR does not vent after the well achieves a stabilized rate and pressure.
 - b. DJR will remain present on-site during liquids unloading by manual purging and take all reasonable actions to achieve a stabilized rate and pressure at the earliest practical time.
 - c. DJR will optimize the system to minimize natural gas venting on any well equipped with a plunger lift or auto control system.
 - d. Best Management Practices will be used during downhole well maintenance.
3. During the first year of production from an exploratory well provided:
 - a. DJR receives approval from the NMOCD.
 - b. DJR remains in compliance with the NM gas capture requirements.
 - c. DJR submits an updated C-129 form to the NMOCD.
4. During the following activities unless prohibited:
 - a. Gauging or sampling a storage tank or low-pressure production vessel.
 - b. Loading out liquids from a storage tank.
 - c. Repair and maintenance.
 - d. Normal operation of gas activated pneumatic controller or pump.
 - e. Normal operation of a storage tank but not including venting from a thief hatch.
 - f. Normal operation of dehydration units.
 - g. Normal operations of compressors, compressor engines, turbines, valves, flanges, and connectors.
 - h. During a bradenhead, packer leakage test, or production test lasting less than 24-hours.
 - i. When natural gas does not meet the gathering pipeline specifications.
 - j. Commissioning of pipelines, equipment, or facilities only for as long as necessary to purge introduced impurities.

19.15.27.8 E. Performance standards

1. DJR has utilized process simulations with a safety factor to design all separation and storage equipment. The equipment is routed to a Vapor Recovery System and utilizes a flare as back up for periods of startup, shutdown, maintenance, or malfunction of the VRU System.
2. DJR will install a flare that designed to handle the full volume of vapors from the facility in case of the VRU failure and it is designed with an auto ignition system.
3. Flare stacks will appropriately sized and designed to ensure proper combustion efficiency.



- a. Flare stacks installed or replaced will be equipped with an automatic ignitor or continuous pilot.
 - b. Previously installed flare stacks will be retrofitted with an automatic ignitor, continuous pilot, or technology that alerts DJR of flare malfunction within 18 months after May 25, 2021.
 - c. Flare stacks replaced after May 25, 2021, will be equipped with an automatic ignitor or continuous pilot if located at a well or facility with average daily production of 60,000 cubic feet of natural gas or less.
 - d. Flare stacks will be located at least 100 feet from the well and storage tanks and securely anchored.
4. DJR will conduct an AVO inspection on all components for leaks and defects on a weekly basis.
 5. DJR will make and keep records of AVO inspections which will be available to the NMOCD for at least 5 years.
 6. DJR may use a remote or automated monitoring technology to detect leaks and releases in lieu of AVO inspections with prior NMOCD approval.
 7. Facilities will be designed to minimize waste.
 8. DJR will resolve emergencies as promptly as possible.

19.15.27.8 F. Measurement or estimation of vented and flared natural gas

1. DJR will have meters on both the low- and high-pressure sides of the flares and the volumes will be recorded in DJR's SCADA system.
2. DJR will install equipment to measure the volume of flared natural gas that has an average daily production of 60,000 cubic feet or greater of natural gas.
3. DJR's measuring equipment will conform to the industry standards.
4. The measurement system is designed such that it cannot be bypassed except for inspections and servicing meters.
5. DJR will estimate the volume of vented or flared natural gas using a methodology that can be independently verified if metering is not practicable due to low flow rate or pressure.
6. DJR will estimate the volume of flared and vented natural gas based on the results of an annual GOR test for wells that do not require measuring equipment reported on Form C-116.
7. DJR will install measuring equipment whenever the NMOCD determines that metering is necessary.



DJR OPERATING, LLC.
OGRID NO: 371838
NATURAL GAS MANAGEMENT PLAN
Ponderosa J06 2309 FED COM 118H, 121H, 123H and
Ponderosa Unit 100H, 119H, 122H
NWSE J-06-23N-09W

BEST MANAGEMENT PRACTICES

DJR Operating, LLC (DJR) utilizes the following Best Management Practices to minimize venting during active and planned maintenance.

DJR has a closed vent capture system to route emissions from the heater treater, tanks, and vapor recovery to the vapor recovery unit with an enclosed combustion device (ECD) for backup. The system is designed such that if the vapor recovery unit is taken out of service for any reason, the vapors will be routed to the ECD for combustion.

DJR will isolate and attempt to route all vapors to the vapor recovery unit or ECD prior to opening any lines for maintenance to minimize venting from the equipment.

DJR shall notify the NMOCD of venting or flaring that exceeds 50 MCF but less than 500 MCF in volume that either resulted from an emergency or malfunction, or an event lasting over eight hours or more cumulatively within any 24-hour period from a single event by filing a form C-129 no later than 15 days following the discovery or commencement of venting or flaring.

DJR shall notify the NMOCD verbally or by e-mail within 24-hours following discovery or commencement of venting or flaring that exceeds 500 MCF in volume or otherwise qualifies as a major release as defined in 19.15.29.7 NMAC from a single event and provide the information required in form C-129 to the NMOCD no later than 15 days that verifies, updates, or corrects the verbal or e-mail notification.

DJR will install measuring equipment to conform to industry standards such as American Petroleum Institute (API) Manual of Petroleum Measurement Standards (MPMS) Chapter 14.10 Measurement of Flow to Flares.

DJR's measuring equipment shall not be designed or equipped with a manifold that allows the diversion of natural gas around the metering element except for the sole purpose of inspecting and servicing the measurement equipment.

DJR shall report the volume of vented and flared natural gas for each well or facility at which venting or flaring occurred on a monthly basis.



ENDURING RESOURCES IV, LLC
6300 S SYRACUSE WAY, SUITE 525
CENTENNIAL, COLORADO 80211

DRILLING PLAN: Drill, complete, and equip single lateral in the Mancos-Gallup formation

WELL INFORMATION:

Name: Ponderosa J06 2309 Federal Com 119H

API Number: Not yet assigned

AFE Number: Not yet assigned

ER Well Number: Not yet assigned

State: New Mexico

County: San Juan

Surface Elevation: 6,711 ft ASL (GL) 6,735 ft ASL (KB)

Surface Location: 6-23-9 Sec-Twn-Rng 1,788 ft FSL 1,670 ft FEL

36.253568 ° N latitude 107.826866 ° W longitude (NAD 83)

BH Location: 1-23-10 Sec-Twn-Rng 232 ft FNL 1,074 ft FEL

36.262589 ° N latitude 107.842806 ° W longitude (NAD 83)

Driving Directions: FROM THE INTERSECTION OF US HWY 550 & US HWY 64 IN BLOOMFIELD, NM:

South on US Hwy 550 for 36.8 miles to Nageezi Post Office; Right (SouthWest) on Cty Road 7800/7786 for 5.2 miles to 3-way intersection; Right (NorthWest) on Cty Road 7825 for 0.3 mi location access on right side to Ponderosa Unit 100H PAD. There are 6 wells staked on this pad, from South to North: Ponderosa Unit 121H, 123H, 118H, 119H, 100H, 122H.

GEOLOGIC AND RESERVOIR INFORMATION:

Prognosis:	Formation Tops	TVD (ft ASL)	TVD (ft KB)	MD (ft KB)	O / G / W	Pressure
	Ojo Alamo	6,375	360	360	W	normal
	Kirtland	6,265	470	470	W	normal
	Fruitland	6,030	705	705	G, W	sub
	Pictured Cliffs	5,645	1,090	1,091	G, W	sub
	Lewis	5,465	1,270	1,275	G, W	normal
	Chacra	5,275	1,460	1,474	G, W	normal
	Cliff House	4,221	2,514	2,612	G, W	sub
	Menefee	4,211	2,524	2,623	G, W	normal
	Point Lookout	3,207	3,528	3,703	G, W	normal
	Mancos	3,052	3,683	3,862	O,G	sub (~0.38)
	Gallup (MNCS_A)	2,697	4,038	4,219	O,G	sub (~0.38)
	MNCS_B	2,597	4,138	4,319	O,G	sub (~0.38)
	MNCS_C	2,507	4,228	4,409	O,G	sub (~0.38)
	MNCS_Cms	2,467	4,268	4,449	O,G	sub (~0.38)
	MNCS_D	2,317	4,418	4,605	O,G	sub (~0.38)
	MNCS_E	2,207	4,528	4,732	O,G	sub (~0.38)
	MNCS_F	2,126	4,609	4,839	O,G	sub (~0.38)
	MNCS_G	2,066	4,669	4,936	O,G	sub (~0.38)
	MNCS_H	2,026	4,709	5,018	O,G	sub (~0.38)
	MNCS_I	1,980	4,755	5,163	O,G	sub (~0.38)
	FTP TARGET	2,066	4,669	4,936	O,G	sub (~0.38)
	PROJECTED TD	1,940	4,795	10,782	O,G	sub (~0.38)

Surface: Nacimiento

Oil & Gas Zones: Several gas bearing zones will be encountered; target formation is the Gallup

Pressure: Normal (0.43 psi/ft) or sub-normal pressure gradients anticipated in all formations

Max. pressure gradient: 0.43 psi/ft Evacuated hole gradient: 0.22 psi/ft

Maximum anticipated BH pressure, assuming maximum pressure gradient: 2,070 psi

Maximum anticipated surface pressure, assuming partially evacuated hole: 1,020 psi

Temperature: Maximum anticipated BHT is 125° F or less

H₂S INFORMATION:

H₂S Zones: Encountering hydrogen-sulfide bearing zones is **NOT** anticipated.

Safety: Sensors and alarms will be placed in the substructure, on the rig floor, above the pits, and at the shakers.

LOGGING, CORING, AND TESTING:

Mud Logs: None planned; remote geo-steering from drill out of 7" casing to TD; gas detection from drillout of 9-5/8" casing to TD.

MWD / LWD: Gamma Ray from drillout of 9-5/8" casing to TD

Open Hole Logs: None planned

Testing: None planned

Coring: None planned

Cased Hole Logs: CBL on 7" casing from deepest free-fall depth to surface

DRILLING RIG INFORMATION:

Contractor: Ensign

Rig No.: 140

Draw Works: Pacific Rim 1500AC (1,500 hp)

Mast: Process MFG Corp Swing Up Triple (136 ft, 750,000 lbs)

Top Drive: Tesco 400-EXI-600 (400 ton)

Prime Movers: 3 - CAT 3512C (1,350 hp)

Pumps: 2 - Gardner Denver PZ-11 (7,500 psi)

BOPE 1: T3 Annular & Shaffer double gate ram (11", 5,000 psi)

BOPE 2: T3 annular(11", 5,000 psi)

Choke 3", 5,000 psi

KB-GL (ft): 23.5

Note: Actual drilling rig may vary depending on availability at time the well is scheduled to be drilled.

BOPE REQUIREMENTS:

See attached diagram for details regarding BOPE specifications and configuration.

- 1) Rig will be equipped with upper and lower kelly cocks with handles available.
- 2) Inside BOP and TIW valves will be available to use on all sizes and threads of drill pipe used while drilling the well.
- 3) BOP accumulator will have enough capacity to open the HCR valve, close all rams and annular preventer, and retain minimum of 200 psi above precharge on the closing manifold without the use of closing pumps. The fluid reservoir capacity shall be at least double the usable fluid volume of the accumulator system capacity, and the fluid level shall be maintained at manufacturer's recommendation. There will be two additional sources of power for the closing pumps (electric and air). Sufficient nitrogen bottles will be available and will be recharged when pressure falls below manufacturer's recommended minimum.

- 4) BOP testing shall be conducted (a) when initially installed, (b) whenever any seal is broken or repaired, (c) if the time since the previous test exceeds 30 days. Tests will be conducted using a test plug. BOP ram preventers will be tested to 3,000 psig for 10 minutes, and the annular preventer will be tested to 1,500 psi for 10 minutes. Ram and annular preventers will be tested to 250 psi for 5 minutes. Additionally, BOP and casing strings will be tested to .22 psi/ft or 1,500 psi, whichever is greater but not exceeding 70% of yield strength of the casing, for 30 minutes, prior to drilling out 13-3/8" and 9-5/8" casing. Rams and hydraulically operated remote choke line valve will be function tested daily at a minimum.
- 5) Remote valve for BOP rams, HCR, and choke shall be placed in a location that is readily available to the driller. The remote BOP valve shall be capable of closing and opening the rams.
- 6) Manual locking devices (hand wheels) shall be intalled on rams. A valve will be installed on the annular preventer's closing line as close as possible to the preventer to act as a locking device. The valve will be maintained in the open position and shall only be closed when there is no power to the accumulator.

FLUIDS AND SOLIDS CONTROL PROGRAM:

Fluid Measurement:

Pumps shall be equipped with stroke counters with displays in the dog-house. Slow pump speed shall be recorded daily and after mudding up, at a minimum, on the drilling report. A Pit Volume Totalizer will be installed and the readout will be displayed in the dog-house. Gas-detecting equipment will be installed at the shakers, and readouts will be available in the dog-house and the in the geologist's work-station (if geologist or mud-logger is on-site).

Closed-Loop System: A fully, closed-loop system will be utilized. The system will consist of above-ground piping and above-ground storage tanks and bins. The system will not entail any earthen pits, below-grade storage, or drying pads. All equipment will be disassembled and removed from the site when drilling operations cease. The system will be capable of storing all fluids and generated cuttings and of preventing uncontrolled releases of the same. The system will be operated in an efficient manner to allow the recycling and reuse of as much fluid as possible and to minimize the amount of fluids and solids that require disposal.

Fluid Disposal: Fluids that cannot be reused, recycled, or returned to the supplier will be hauled to and disposed of at an approved disposal site (Industrial Ecosystem, Inc. or Envirotech, Inc.).

Solids Disposal: Drilling solids will be stored (until haul-off) on-site in separate containers with no other waste, debris, or garbage products. Waste solids will be hauled to and disposed of at an approved disposal site (Industrial Ecosystem, Inc. or Envirotech, Inc.).

Fluid Program: See "Detailed Drilling Plan" section and attached Newpark mud program for additional details.

DETAILED DRILLING PLAN:

SURFACE: Drill vertically to casing setting depth (plus necessary rathole), run casing, cement casing to surface.

0 ft (MD)	to	350 ft (MD)	Hole Section Length:	350 ft
0 ft (TVD)	to	350 ft (TVD)	Casing Required:	350 ft

Note: Surface hole may be drilled, cased, and cemented with a smaller rig in advance of the drilling rig.

Fluid:	Type	MW (ppg)	FL (mL/30 min)	PV (cp)	YP (lb/100 sqft)	pH	Comments
	Fresh Water	8.4	N/C	2 - 8	2 - 12	9.0	Spud mud

Hole Size: 12-1/4"

Bit / Motor: Mill Tooth or PDC, no motor

MWD / Survey: No MWD, deviation survey

Logging: None

Casing Specs: Specs								
		Wt (lb/ft)	Grade	Conn.	Collapse (psi)	Burst (psi)	Tens. Body (lbs)	Tens. Conn (lbs)
	9.625	36.0	K-55	STC	2,020	3,520	564,000	423,000

Loading		153	1,020	110,988	110,988
Min. S.F.		13.21	3.45	5.08	3.81

Assumptions: Collapse: fully evacuated casing with 8.4 ppg equivalent external pressure gradient
 Burst: maximum anticipated surface pressure with 9.5 ppg fluid inside casing while drilling
 intermediate hole and 8.4 ppg equivalent external pressure gradient
 Tension: buoyed weight in 8.4 ppg fluid with 100,000 lbs over-pull

MU Torque (ft lbs): Minimum: 3,400 Optimum: 4,530 Maximum: 5,660

Casing Summary: Float shoe, 1 jt casing, float collar, casing to surface

Centralizers: 2 centralizers per jt stop-banded 10' from each collar on bottom 3 jts, 1 centralizer per 2 jts to surface

Cement:	Type	Weight (ppg)	Yield (cuft/sk)	Water (gal/sk)	Hole Cap. (cuft/ft)	% Excess	Planned TOC (ft MD)	Total Cmt (sx)	Total Cmt (cu ft)
Redi-Mix	TYPE I-II	14.5	1.61	7.41	0.3132	50%	0	114	184

Calculated cement volumes assume gauge hole and the excess noted in table Csg ID 8.921

Mesa Ready Mix or first available

Shoe Track L 44

Notify NMOCD & BLM if cement is not circulated to surface. Cement must achieve 500 psi compressive strength before drilling out.

INTERMEDIATE: Drill as per directional plan to casing setting depth, run casing, cement casing to surface.

350 ft (MD)	to	5,224 ft (MD)	Hole Section Length:	4,874 ft
350 ft (TVD)	to	4,764 ft (TVD)	Casing Required:	5,224 ft

Fluid:	Type	MW (ppg)	FL (mL/30 min)	PV (cp)	YP (lb/100 sqft)	pH	Comments
	LSND (KCI)	8.8 - 9.2	15	8 - 14	6 - 12	10.8 - 11.2	No OBM

Hole Size (inches): 8.75

Bit / Motor: 8-3/4" PDC bit w/mud motor

MWD / Survey: MWD Survey with inclination and azimuth survey (every 100' at a minimum), GR optional

Logging: None

Pressure Test: NU BOPE and test (as noted above); pressure test 9-5/8" casing to 1,500 psi for 30 minutes.

Casing Specs:								
		Wt (lb/ft)	Grade	Conn.	Collapse (psi)	Burst (psi)	Tens. Body (lbs)	Tens. Conn (lbs)
	7	26.0	K-55	LTC	4,320	4,980	415,000	367,000
					2,081	1,293	218,445	218,445
				2.08	3.85	1.90	1.68	

Assumptions: Collapse: fully evacuated casing with 8.4 ppg equivalent external pressure gradient
 Burst: maximum anticipated surface pressure with 9.5 ppg fluid inside casing while drilling production
 hole and 8.4 ppg equivalent external pressure gradient
 Tension: buoyed weight in 8.4 ppg fluid with 100,000 lbs over-pull

MU Torque (ft lbs): Minimum: 3,400 Optimum: 4,530 Maximum: 5,660

Centralizers: 1 per joint in non-vertical hole; 1 per 2-joints in vertical hole

Cement:	Type	Weight (ppg)	Yield (cuft/sk)	Water (gal/sk)	% Excess	Planned TOC (ft MD)	Total Cmt (sx)	Total Cmt (cu ft)
Lead	III:POZ Blend	12.5	2.150	12.05	70%	0	433	930
Tail	Type III	13.5	1.710	8.88	30%	3,762	173	295

Annular Capacity	0.16681	cuft/ft	7" casing x 9-5/8" casing annulus	Shoe Track L	44
	0.1503	cuft/ft	7" casing x 8-3/4" hole annulus	Casing ID	6.276
	0.2148	cuft/ft	7" casing casing volume		

Calculated cement volumes assume gauge hole and the excess noted in table

Spacer	10 bbls water f/b	10 bbls D-Mud Breaker (SAPP)	10 bbls water f/b						
			D-MPA-2 .4%						
Lead	ASTM Type III 90/10 Poz	D-CSE 1 5.0% BWOC Strength Enhancer	BWOC Fluid Loss & Gas Migration Control	D-SA 1 1.4% BWOC Na Metasilicate	D-CD 2 .4% BWOC Dispersant	Cello Flace LCM .25 lb/sx	D-FP 1 .5% BWOC Defoamer	D-R1 1.2% Retarder	
			D-MPA-2 1.2%						
Tail	ASTM Type III 90/10 Poz	D-CSE 1 5.0% BWOC Strength Enhancer	BWOC Fluid Loss & Gas Migration Control	Cello Flace LCM .25 lb/sx	D-FP 1 .5% BWOC Defoamer	D-R1 1.2% Retarder			

Drake Intermediate Cementing Program

Notify NMOCD & BLM if cement is not circulated to surface. Cement must achieve 500 psi compressive strength before drilling out.

PRODUCTION: Drill to TD following directional plan, run casing, cement casing to surface.

5,224 ft (MD)	to	10,782 ft (MD)	Hole Section Length:	5,558 ft
4,764 ft (TVD)	to	4,795 ft (TVD)	Casing Required:	5,708 ft
Estimated KOP:		4,374 ft (MD)	4,193 ft (TVD)	
Estimated Liner Top:		5,074 ft (MD)	4,729 ft (TVD)	
Estimated Landing Point (FTP):		4,936 ft (MD)	4,669 ft (TVD)	
Estimated Lateral Length:		5,846 ft (MD)		

Fluid:	Type	MW (ppg)	FL (mL/30')	PV (cp)	YP (lb/100 sqft)	pH	Comments	Comments
	WBM	8.7 - 9.0	NC	+20	±2	9-9.5	prod water	OBM as contingency

Hole Size: 6.125

Bit / Motor: 6-1/8" PDC bit w/mud motor

MWD / Survey: MWD with GR, inclination, and azimuth (survey every joint from KOP to Landing Point and survey every 100' minimum before KOP and after Landing Point)

Logging: GR MWD for entire section, no mud-log or cuttings sampling, no OH WL logs

Pressure Test: NU BOPE and test (as noted above); pressure test 7" casing to **1,500** psi for 30 minutes.

Liner/Casing Specs:	Size (in)	Wt (lb/ft)	Grade	Conn.	Collapse (psi)	Burst (psi)	Tens. Body (lbs)	Tens. Conn (lbs)
Specs	4.500	11.6	P-110	BTC	7,560	10,690	367,000	385,000
Loading					2,369	8,774	207,925	207,925
Min. S.F.					3.19	1.22	1.77	1.85

Assumptions: Collapse: fully evacuated casing with 9.5 ppg fluid in the annulus (floating casing during running)

Burst: 8,500 psi maximum surface treating pressure with 10.2 ppg equivalent mud weight sand laden fluid with 8.4 ppg equivalent external pressure gradient.

Tension: buoyed weight in 9.0 ppg fluid with 100,000 lbs over-pull. Tension calculations assume vertical hole to approximate drag in lateral.

MU Torque (ft lbs): Minimum: BTC Optimum: BTC Maximum: BTC

Centralizers: Centralizer count and placement may be adjusted based on well conditions and as-drilled surveys.

Cement:	Type	Weight (ppg)	Yield	Water	% Excess	Planned TOC	Total Cmt	Total Cmt (cu)
Spacer	IntegraGuard Star	11		31.6		0	40 bbls	
Tail	G:POZ blend	13.3	1.520	7.50	25%	5,074	475	722
Displacement	139	est bbls						

Annular Capacities 0.1044 cu/ft 4-1/2" casing x 7" casing annulus
0.09417 cu/ft 4-1/2" casing x 6-1/8" hole annulus

0.0873 cuft/ft 4-1/2" casing volume est shoe jt ft 100
 0.0102 bbls/ft 4" DP capacity

Calculated cement volumes assume gauge hole and the excess noted in table
 American Cementing Liner & Production Blend

Spacer	S-8 Silica Flour	Avis 616 viscosifier	FP24 Defoamer .5	IntegraGuard Star	Plus 3K LCM 15	SS201 Surfactant 1		
	163.7 lbs/bbl	11.6 lb/bbl	lb/bbl	lb/bbl	gal/bbl			
Lead/Tail		Bentonite		IntegraGuard			FP24 Defoamer	
		BA90 Bonding	Viscosifier 8%	FL24 Fluid Loss .5%	GW86 Viscosifier	R7C Retarder .2%	0.3% BWOB, Anti-	
	ASTM Type I/II	Agent 5.0 lb/sx	BWOB	BWOB	.1% BWOB	BWOB	Static .01 lb/sx	
				Bentonite		IntegraGuard		FP24 Defoamer
		Pozzolan Fly Ash	BA90 Bonding	Viscosifier 4%	FL24 Fluid Loss .4%	GW86 Viscosifier	R3 Retarder .5%	.3% BWOB,
	Type G 50%	Extender 50%	Agent 3.0 lb/sx	BWOB	BWOB	.1% BWOB	BWOB	IntegraSeal 0.25
								lb/sx

Notify NMOCD & BLM if cement is not circulated to surface.

Note: This well will not be considered an unorthodox well location as defined by NMAC 19.15.16.15.C.5. As defined in NMAC 19.15.16.15.C.1.a and 19.15.16.15.C.1.b, no point in the completed interval shall be closer to the unit boundary than 100' measured along the azimuth of the well or 330' measured perpendicular to the azimuth well. The boundaries of the completed interval, as defined by NMAC 19.15.16.7.B, are the last take point and first take point, as defined by NMAC 19.15.16.7.E and NMAC 19.15.16.7.J, respectively. In the case of this well, the last take point will be the bottom toe-initiation sleeve, and the first take point will be the top perforation. **Neither the toe-initiation sleeve nor the top perforation shall be closer to the unit boundary than 100' measured along the azimuth of the well or 330' measured perpendicular to the azimuth of the well.**

FINISH WELL: ND BOP, cap well, RDMO.

COMPLETION AND PRODUCTION PLAN:

Est Lateral Length: 5,746
Est Frac Inform: 24 Frac Stages 92,000 bbls slick water 7,470,000 lbs proppant
Flowback: Flow back through production tubing as pressures allow
Production: Produce through production tubing via gas-lift into permanent production and storage facilities

ESTIMATED START DATES:

Drilling: 12/16/2024
Completion: 2/14/2025
Production: 3/31/2025

Prepared by: Greg Olson 7/18/2024
Updated: Greg Olson 11/15/2024

WELL NAME: **Ponderosa J06 2309 Federal Com 119H**
OBJECTIVE: **Drill, complete, and equip single lateral in the Mancos-Gallup formation**

API Number: *Not yet assigned*
AFE Number: *Not yet assigned*
ER Well Number: *Not yet assigned*

State: **New Mexico**
County: **San Juan**

Surface Elev.: **6,711** ft ASL (GL) **6,735** ft ASL (KB)
Surface Location: **6-23-9** Sec-Twn- Rng **1,788** ft FSL **1,670** ft FEL
BH Location: **1-23-10** Sec-Twn- Rng **232** ft FNL **1074** ft FEL

Driving Directions: **FROM THE INTERSECTION OF US HWY 550 & US HWY 64 IN BLOOMFIELD, NM:**

South on US Hwy 550 for 36.8 miles to Nageezi Post Office; Right (SouthWest) on Cty Road 7800/7786 for 5.2 miles to 3-way intersection;
Right (NorthWest) on Cty Road 7825 for 0.3 mi location access on right side to Ponderosa Unit 100H PAD. There are 6 wells staked on this pad,
from South to North: Ponderosa Unit 121H, 123H, 118H, 119H, 100H, 122H.

QUICK REFERENCE	
Sur TD (MD)	350 ft
Int TD (MD)	5,224 ft
KOP (MD)	4,374 ft
KOP (TVD)	4,193 ft
Target (TVD)	4,669 ft
Curve BUR	10 °/100 ft
POE (MD)	4,936 ft
TD (MD)	10,782 ft
Lat Len (ft)	5,846 ft

WELL CONSTRUCTION SUMMARY:

	Hole (in)	TD MD (ft)	Csg (in)	Csg (lb/ft)	Csg (grade)	Csg (conn)	Csg Top (ft)	Csg Bot (ft)
Surface	12.250	350	9.625	36	K-55	STC	0	350
Intermediate	8.750	5,224	7	26.0	K-55	LTC	0	5,224
Production	6.125	10,782	4.500	11.6	P-110	BTC	5,074	10,782

CEMENT PROPERTIES SUMMARY:

	Type	Wt (ppg)	Yd (cuft/sk)	Wtr (gal/sk)	Hole Cap. (cuft/ft)	% Excess	TOC (ft MD)	Total (sx)
Surface	TYPE I-II	14.5	1.61	7.41	0.3132	50%	0	114
Inter. (Lead)	III:POZ Blend	12.5	2.15	12.05	0.1668	70%	0	433
Inter. (Tail)	Type III	13.5	1.71	8.88	0.1503	30%	3,762	173
Prod. (Lead)	0	0	0.000	0	0.1044	0%	0	0
Prod. (Tail)	G:POZ blend	13.3	1.520	7.5	0.0873	25%	5,074	475

COMPLETION / PRODUCTION SUMMARY:


Frac: 39 plug-and-perf stages with 150,000 bbls slickwater fluid and 12,100,000 lbs of proppant (estimated)
Flowback: Flow back through production tubing as pressures allow
Production: Produce through production tubing via gas-lift into permanent production and storage facilities

Tops	TVD (ft KB)	MD (ft KB)
Ojo Alamo	360	360
Kirtland	470	470
Fruitland	705	705
Pictured Cliffs	1,090	1,091
Lewis	1,270	1,275
Chacra	1,460	1,474
Cliff House	2,514	2,612
Menefee	2,524	2,623
Point Lookout	3,528	3,703
Mancos	3,683	3,862
Gallup (MNCS_A)	4,038	4,219
MNCS_B	4,138	4,319
MNCS_C	4,228	4,409
MNCS_Cms	4,268	4,449
MNCS_D	4,418	4,605
MNCS_E	4,528	4,732
MNCS_F	4,609	4,839
MNCS_G	4,669	4,936
MNCS_H	4,709	5,018
MNCS_I	4,755	5,163
FTP TARGET	4,669	4,936
PROJECTED TD	4,795	10,782

PONDEROSA UNIT 119H

NOTE: EXACT BOPE AND CHOKE CONFIGURATION AND COMPONENTS MAY DIFFER FROM WHAT IS DEPICTED IN THE DIGRAMS BELOW DEPENDING ON THE RIG AND ITS ASSOCIATED EQUIPMENT. RAM PREVENTERS, ANNULAR PREVENTERS, AND CHOKE MANIFOLD AND COMPONENTS WILL BE RATED TO 3,000 PSI MINIMUM.


CHOKE MANIFOLD




PONDEROSA UNIT 119H

NOTE: EXACT BOPE AND CHOKE CONFIGURATION AND COMPONENTS MAY DIFFER FROM WHAT IS DEPICTED IN THE DIGRAMS BELOW DEPENDING ON THE RIG AND ITS ASSOCIATED EQUIPMENT. RAM PREVENTERS, ANNULAR PREVENTERS, AND CHOKE MANIFOLD AND COMPONENTS WILL BE RATED TO 3,000 PSI MINIMUM.

BOPE





Name	TVD	+N/-S	+E/-W	North	East	Latitude	Longitude
ponderosa 119 FTP 1093 FSL 2397 FEL	4765.00	-690.96	-724.39	19108906.46	2724274.09	36.25167000	-107.82933200
ponderosa 119 vs0	4765.00	-707.68	-707.66	1910889.73	2724290.82	36.25162406	-107.82926626
ponderosa 119 FTP 232 FNL 1074 FEL 330 ppd	4795.00	3283.93	-4699.40	1914881.34	2702029.99	36.26258900	-107.84280600


Magnetic Field
Strength: 48965.4nT
Dip Angle: 62.68°
Date: 11/11/2024
Model: IGRF2020


Total Corr (M=>G): To convert a Magnetic Direction to a Grid Direction, Add 8.469°

ASING DETAILS




Section Details										
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Annotation
1	0.00	0.00	0.000	0.00	0.00	0.00	0.00	0.000	0.00	
2	800.00	0.00	0.000	800.00	0.00	0.00	0.00	0.000	0.00	KOP Begin 3°/100' build
3	1541.02	22.23	199.963	1522.57	-133.43	-48.47	3.00	199.963	-60.08	Begin 22.23° tangent
4	3483.25	22.23	199.963	3320.43	-824.10	-299.34	0.00	0.000	-371.04	Begin 3°/100' drop
5	4224.28	0.00	0.000	4043.00	-957.53	-347.81	3.00	180.000	-431.12	Begin vertical hold
6	4374.28	0.00	0.000	4193.00	-957.53	-347.81	0.00	0.000	-431.12	Begin 10°/100' build
7	5271.28	89.70	308.830	4765.95	-600.16	-791.81	10.00	308.830	135.54	Begin 2°/100' turn
8	5579.76	89.70	315.000	4767.57	-394.19	-1021.25	2.00	90.036	443.42	Begin 89.70° lateral
9	10781.50	89.70	315.000	4795.00	3283.93	-4699.40	0.00	0.000	5645.09	PBHL/TD





Well: Ponderosa Unit 119H
Site: Ponderosa (100,118,119,121,122 & 123)
Project: San Juan County, New Mexico NAD83 NM V
Design: rev0
Rig:



13:37, November 12 2024



Planning Report

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Project	San Juan County, New Mexico NAD83 NM W		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Western Zone		

Site	Ponderosa (100,118,119,121,122 & 123)				
Site Position:		Northing:	1,911,577.39 usft	Latitude:	36.25351300
From:	Lat/Long	Easting:	2,725,001.43 usft	Longitude:	-107.82685600
Position Uncertainty:	0.00 ft	Slot Radius:	13-3/16 "		

Well	Ponderosa Unit 119H, Surf loc: 1788 FSL 1670 FEL Section 06-T23N-R09W						
Well Position	+N/-S	0.00 ft	Northing:	1,911,597.41	usft	Latitude:	36.25356800
	+E/-W	0.00 ft	Easting:	2,724,998.48	usft	Longitude:	-107.82686600
Position Uncertainty		0.00 ft	Wellhead Elevation:		ft	Ground Level:	6,711.00 ft
Grid Convergence:		0.004 °					

Wellbore	Original Hole				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2020	11/11/2024	8.473	62.676	48,965.36627143

Design	rev0				
Audit Notes:					
Version:		Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.00	0.00	0.00	314.999	

Plan Survey Tool Program	Date	11/12/2024			
Depth From (ft)	Depth To (ft)	Survey (Wellbore)	Tool Name	Remarks	
1	0.00	10,781.50	rev0 (Original Hole)	MWD	
				OWSG MWD - Standard	



Planning Report

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.000	
800.00	0.00	0.000	800.00	0.00	0.00	0.00	0.00	0.00	0.000	
1,541.02	22.23	199.963	1,522.57	-133.43	-48.47	3.00	3.00	0.00	199.963	
3,483.25	22.23	199.963	3,320.43	-824.10	-299.34	0.00	0.00	0.00	0.000	
4,224.28	0.00	0.000	4,043.00	-957.53	-347.81	3.00	-3.00	0.00	180.000	
4,374.28	0.00	0.000	4,193.00	-957.53	-347.81	0.00	0.00	0.00	0.000	
5,271.28	89.70	308.830	4,765.95	-600.16	-791.81	10.00	10.00	0.00	308.830	
5,579.76	89.70	315.000	4,767.57	-394.19	-1,021.25	2.00	0.00	2.00	90.036	
10,781.50	89.70	315.000	4,795.00	3,283.93	-4,699.40	0.00	0.00	0.00	0.000	Ponderosa 119 LTP 2



Planning Report

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.000	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.000	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.000	300.00	0.00	0.00	0.00	0.00	0.00	0.00
350.00	0.00	0.000	350.00	0.00	0.00	0.00	0.00	0.00	0.00
9-5/8" Surface Casing									
360.00	0.00	0.000	360.00	0.00	0.00	0.00	0.00	0.00	0.00
Ojo Alamo									
400.00	0.00	0.000	400.00	0.00	0.00	0.00	0.00	0.00	0.00
470.00	0.00	0.000	470.00	0.00	0.00	0.00	0.00	0.00	0.00
Kirtland									
500.00	0.00	0.000	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.000	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.000	700.00	0.00	0.00	0.00	0.00	0.00	0.00
705.00	0.00	0.000	705.00	0.00	0.00	0.00	0.00	0.00	0.00
Fruitland									
800.00	0.00	0.000	800.00	0.00	0.00	0.00	0.00	0.00	0.00
KOP Begin 3°/100' build									
900.00	3.00	199.963	899.95	-2.46	-0.89	-1.11	3.00	3.00	0.00
1,000.00	6.00	199.963	999.63	-9.83	-3.57	-4.43	3.00	3.00	0.00
1,091.08	8.73	199.963	1,089.95	-20.81	-7.56	-9.37	3.00	3.00	0.00
Pictured Cliffs									
1,100.00	9.00	199.963	1,098.77	-22.10	-8.03	-9.95	3.00	3.00	0.00
1,200.00	12.00	199.963	1,197.08	-39.23	-14.25	-17.66	3.00	3.00	0.00
1,274.74	14.24	199.963	1,269.87	-55.17	-20.04	-24.84	3.00	3.00	0.00
Lewis									
1,300.00	15.00	199.963	1,294.31	-61.17	-22.22	-27.54	3.00	3.00	0.00
1,400.00	18.00	199.963	1,390.18	-87.86	-31.91	-39.56	3.00	3.00	0.00
1,473.62	20.21	199.963	1,459.74	-110.50	-40.14	-49.75	3.00	3.00	0.00
Chacra									
1,500.00	21.00	199.963	1,484.43	-119.23	-43.31	-53.68	3.00	3.00	0.00
1,541.02	22.23	199.963	1,522.57	-133.43	-48.47	-60.08	3.00	3.00	0.00
Begin 22.23° tangent									
1,600.00	22.23	199.963	1,577.16	-154.41	-56.09	-69.52	0.00	0.00	0.00
1,700.00	22.23	199.963	1,669.73	-189.97	-69.00	-85.53	0.00	0.00	0.00
1,800.00	22.23	199.963	1,762.30	-225.53	-81.92	-101.54	0.00	0.00	0.00
1,900.00	22.23	199.963	1,854.86	-261.09	-94.84	-117.55	0.00	0.00	0.00
2,000.00	22.23	199.963	1,947.43	-296.65	-107.75	-133.56	0.00	0.00	0.00
2,100.00	22.23	199.963	2,040.00	-332.21	-120.67	-149.57	0.00	0.00	0.00
2,200.00	22.23	199.963	2,132.56	-367.77	-133.59	-165.58	0.00	0.00	0.00
2,300.00	22.23	199.963	2,225.13	-403.33	-146.50	-181.60	0.00	0.00	0.00
2,400.00	22.23	199.963	2,317.70	-438.89	-159.42	-197.61	0.00	0.00	0.00
2,500.00	22.23	199.963	2,410.26	-474.45	-172.34	-213.62	0.00	0.00	0.00
2,600.00	22.23	199.963	2,502.83	-510.01	-185.25	-229.63	0.00	0.00	0.00
2,611.84	22.23	199.963	2,513.79	-514.22	-186.78	-231.52	0.00	0.00	0.00
Cliff House									
2,622.63	22.23	199.963	2,523.78	-518.06	-188.18	-233.25	0.00	0.00	0.00
Menefee									
2,700.00	22.23	199.963	2,595.40	-545.57	-198.17	-245.64	0.00	0.00	0.00
2,800.00	22.23	199.963	2,687.97	-581.13	-211.09	-261.65	0.00	0.00	0.00
2,900.00	22.23	199.963	2,780.53	-616.69	-224.00	-277.66	0.00	0.00	0.00
3,000.00	22.23	199.963	2,873.10	-652.25	-236.92	-293.67	0.00	0.00	0.00
3,100.00	22.23	199.963	2,965.67	-687.81	-249.84	-309.68	0.00	0.00	0.00



Planning Report

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,200.00	22.23	199.963	3,058.23	-723.37	-262.75	-325.69	0.00	0.00	0.00
3,300.00	22.23	199.963	3,150.80	-758.93	-275.67	-341.70	0.00	0.00	0.00
3,400.00	22.23	199.963	3,243.37	-794.49	-288.59	-357.71	0.00	0.00	0.00
3,483.25	22.23	199.963	3,320.43	-824.10	-299.34	-371.04	0.00	0.00	0.00
Begin 3°/100' drop									
3,500.00	21.73	199.963	3,335.96	-829.99	-301.48	-373.70	3.00	-3.00	0.00
3,600.00	18.73	199.963	3,429.78	-862.48	-313.29	-388.33	3.00	-3.00	0.00
3,700.00	15.73	199.963	3,525.28	-890.32	-323.40	-400.86	3.00	-3.00	0.00
3,702.72	15.65	199.963	3,527.90	-891.01	-323.65	-401.17	3.00	-3.00	0.00
Point Lookout									
3,800.00	12.73	199.963	3,622.21	-913.42	-331.79	-411.26	3.00	-3.00	0.00
3,861.92	10.87	199.963	3,682.82	-925.32	-336.11	-416.62	3.00	-3.00	0.00
Mancos									
3,900.00	9.73	199.963	3,720.28	-931.72	-338.43	-419.50	3.00	-3.00	0.00
4,000.00	6.73	199.963	3,819.24	-945.17	-343.32	-425.55	3.00	-3.00	0.00
4,100.00	3.73	199.963	3,918.81	-953.73	-346.43	-429.41	3.00	-3.00	0.00
4,200.00	0.73	199.963	4,018.73	-957.39	-347.76	-431.06	3.00	-3.00	0.00
4,219.02	0.16	199.963	4,037.74	-957.52	-347.81	-431.12	3.00	-3.00	0.00
MNCS_A									
4,224.28	0.00	0.000	4,043.00	-957.53	-347.81	-431.12	3.00	-3.00	0.00
Begin vertical hold									
4,300.00	0.00	0.000	4,118.72	-957.53	-347.81	-431.12	0.00	0.00	0.00
4,319.02	0.00	0.000	4,137.74	-957.53	-347.81	-431.12	0.00	0.00	0.00
MNCS_B									
4,374.28	0.00	0.000	4,193.00	-957.53	-347.81	-431.12	0.00	0.00	0.00
Begin 10°/100' build									
4,400.00	2.57	308.830	4,218.72	-957.17	-348.26	-430.55	10.00	10.00	0.00
4,409.05	3.48	308.830	4,227.75	-956.87	-348.63	-430.07	10.00	10.00	0.00
MNCS_C									
4,449.26	7.50	308.830	4,267.77	-954.46	-351.63	-426.25	10.00	10.00	0.00
MNCS_Cms									
4,450.00	7.57	308.830	4,268.50	-954.40	-351.70	-426.15	10.00	10.00	0.00
4,500.00	12.57	308.830	4,317.72	-948.92	-358.51	-417.46	10.00	10.00	0.00
4,550.00	17.57	308.830	4,365.98	-940.77	-368.64	-404.54	10.00	10.00	0.00
4,600.00	22.57	308.830	4,412.93	-930.01	-382.00	-387.48	10.00	10.00	0.00
4,605.48	23.12	308.830	4,417.98	-928.68	-383.66	-385.37	10.00	10.00	0.00
MNCS_D									
4,650.00	27.57	308.830	4,458.21	-916.73	-398.50	-366.42	10.00	10.00	0.00
4,700.00	32.57	308.830	4,501.46	-901.02	-418.01	-341.52	10.00	10.00	0.00
4,732.46	35.82	308.830	4,528.31	-889.59	-432.22	-323.39	10.00	10.00	0.00
MNCS_E									
4,750.00	37.57	308.830	4,542.37	-883.02	-440.39	-312.97	10.00	10.00	0.00
4,800.00	42.57	308.830	4,580.62	-862.84	-465.46	-280.98	10.00	10.00	0.00
4,839.37	46.51	308.830	4,608.67	-845.53	-486.96	-253.53	10.00	10.00	0.00
MNCS_F									
4,850.00	47.57	308.830	4,615.92	-840.65	-493.02	-245.79	10.00	10.00	0.00
4,900.00	52.57	308.830	4,648.00	-816.62	-522.88	-207.68	10.00	10.00	0.00
4,936.18	56.19	308.830	4,669.07	-798.18	-545.79	-178.45	10.00	10.00	0.00
MNCS_G									
4,950.00	57.57	308.830	4,676.62	-790.92	-554.81	-166.94	10.00	10.00	0.00
5,000.00	62.57	308.830	4,701.55	-763.76	-588.55	-123.87	10.00	10.00	0.00
5,017.63	64.34	308.830	4,709.43	-753.87	-600.84	-108.19	10.00	10.00	0.00



Planning Report

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
MNCS_H									
5,050.00	67.57	308.830	4,722.62	-735.34	-623.86	-78.81	10.00	10.00	0.00
5,100.00	72.57	308.830	4,739.66	-705.87	-660.47	-32.09	10.00	10.00	0.00
5,150.00	77.57	308.830	4,752.53	-675.59	-698.10	15.93	10.00	10.00	0.00
5,158.82	78.45	308.830	4,754.36	-670.18	-704.82	24.51	10.00	10.00	0.00
7" Intermediate Casing									
5,162.81	78.85	308.830	4,755.15	-667.73	-707.86	28.39	10.00	10.00	0.00
MNCS_I									
5,200.00	82.57	308.830	4,761.15	-644.72	-736.45	64.88	10.00	10.00	0.00
5,250.00	87.57	308.830	4,765.44	-613.50	-775.24	114.39	10.00	10.00	0.00
5,271.28	89.70	308.830	4,765.95	-600.16	-791.81	135.54	10.00	10.00	0.00
Begin 2°/100' turn									
5,300.00	89.70	309.404	4,766.10	-582.04	-814.10	164.11	2.00	0.00	2.00
5,400.00	89.70	311.405	4,766.63	-517.22	-890.24	263.78	2.00	0.00	2.00
5,500.00	89.70	313.405	4,767.15	-449.79	-964.08	363.67	2.00	0.00	2.00
5,579.76	89.70	315.000	4,767.57	-394.19	-1,021.25	443.42	2.00	0.00	2.00
Begin 89.70° lateral									
5,600.00	89.70	315.000	4,767.68	-379.87	-1,035.57	463.66	0.00	0.00	0.00
5,700.00	89.70	315.000	4,768.21	-309.17	-1,106.28	563.66	0.00	0.00	0.00
5,800.00	89.70	315.000	4,768.73	-238.46	-1,176.99	663.66	0.00	0.00	0.00
5,900.00	89.70	315.000	4,769.26	-167.75	-1,247.70	763.66	0.00	0.00	0.00
6,000.00	89.70	315.000	4,769.79	-97.04	-1,318.41	863.66	0.00	0.00	0.00
6,100.00	89.70	315.000	4,770.32	-26.33	-1,389.12	963.65	0.00	0.00	0.00
6,200.00	89.70	315.000	4,770.84	44.38	-1,459.83	1,063.65	0.00	0.00	0.00
6,300.00	89.70	315.000	4,771.37	115.09	-1,530.53	1,163.65	0.00	0.00	0.00
6,400.00	89.70	315.000	4,771.90	185.80	-1,601.24	1,263.65	0.00	0.00	0.00
6,500.00	89.70	315.000	4,772.42	256.51	-1,671.95	1,363.65	0.00	0.00	0.00
6,600.00	89.70	315.000	4,772.95	327.22	-1,742.66	1,463.65	0.00	0.00	0.00
6,700.00	89.70	315.000	4,773.48	397.93	-1,813.37	1,563.65	0.00	0.00	0.00
6,800.00	89.70	315.000	4,774.01	468.64	-1,884.08	1,663.64	0.00	0.00	0.00
6,900.00	89.70	315.000	4,774.53	539.35	-1,954.79	1,763.64	0.00	0.00	0.00
7,000.00	89.70	315.000	4,775.06	610.06	-2,025.50	1,863.64	0.00	0.00	0.00
7,100.00	89.70	315.000	4,775.59	680.77	-2,096.21	1,963.64	0.00	0.00	0.00
7,200.00	89.70	315.000	4,776.12	751.48	-2,166.92	2,063.64	0.00	0.00	0.00
7,300.00	89.70	315.000	4,776.64	822.19	-2,237.63	2,163.64	0.00	0.00	0.00
7,400.00	89.70	315.000	4,777.17	892.90	-2,308.34	2,263.64	0.00	0.00	0.00
7,500.00	89.70	315.000	4,777.70	963.60	-2,379.05	2,363.63	0.00	0.00	0.00
7,600.00	89.70	315.000	4,778.22	1,034.31	-2,449.76	2,463.63	0.00	0.00	0.00
7,700.00	89.70	315.000	4,778.75	1,105.02	-2,520.47	2,563.63	0.00	0.00	0.00
7,800.00	89.70	315.000	4,779.28	1,175.73	-2,591.18	2,663.63	0.00	0.00	0.00
7,900.00	89.70	315.000	4,779.81	1,246.44	-2,661.89	2,763.63	0.00	0.00	0.00
8,000.00	89.70	315.000	4,780.33	1,317.15	-2,732.60	2,863.63	0.00	0.00	0.00
8,100.00	89.70	315.000	4,780.86	1,387.86	-2,803.31	2,963.63	0.00	0.00	0.00
8,200.00	89.70	315.000	4,781.39	1,458.57	-2,874.02	3,063.62	0.00	0.00	0.00
8,300.00	89.70	315.000	4,781.92	1,529.28	-2,944.73	3,163.62	0.00	0.00	0.00
8,400.00	89.70	315.000	4,782.44	1,599.99	-3,015.44	3,263.62	0.00	0.00	0.00
8,500.00	89.70	315.000	4,782.97	1,670.70	-3,086.15	3,363.62	0.00	0.00	0.00
8,600.00	89.70	315.000	4,783.50	1,741.41	-3,156.86	3,463.62	0.00	0.00	0.00
8,700.00	89.70	315.000	4,784.02	1,812.12	-3,227.57	3,563.62	0.00	0.00	0.00
8,800.00	89.70	315.000	4,784.55	1,882.83	-3,298.28	3,663.62	0.00	0.00	0.00
8,900.00	89.70	315.000	4,785.08	1,953.54	-3,368.99	3,763.61	0.00	0.00	0.00
9,000.00	89.70	315.000	4,785.61	2,024.25	-3,439.70	3,863.61	0.00	0.00	0.00
9,100.00	89.70	315.000	4,786.13	2,094.96	-3,510.41	3,963.61	0.00	0.00	0.00
9,200.00	89.70	315.000	4,786.66	2,165.67	-3,581.12	4,063.61	0.00	0.00	0.00



Planning Report

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
9,300.00	89.70	315.000	4,787.19	2,236.37	-3,651.83	4,163.61	0.00	0.00	0.00
9,400.00	89.70	315.000	4,787.72	2,307.08	-3,722.54	4,263.61	0.00	0.00	0.00
9,500.00	89.70	315.000	4,788.24	2,377.79	-3,793.25	4,363.61	0.00	0.00	0.00
9,600.00	89.70	315.000	4,788.77	2,448.50	-3,863.96	4,463.61	0.00	0.00	0.00
9,700.00	89.70	315.000	4,789.30	2,519.21	-3,934.67	4,563.60	0.00	0.00	0.00
9,800.00	89.70	315.000	4,789.82	2,589.92	-4,005.38	4,663.60	0.00	0.00	0.00
9,900.00	89.70	315.000	4,790.35	2,660.63	-4,076.09	4,763.60	0.00	0.00	0.00
10,000.00	89.70	315.000	4,790.88	2,731.34	-4,146.80	4,863.60	0.00	0.00	0.00
10,100.00	89.70	315.000	4,791.41	2,802.05	-4,217.51	4,963.60	0.00	0.00	0.00
10,200.00	89.70	315.000	4,791.93	2,872.76	-4,288.22	5,063.60	0.00	0.00	0.00
10,300.00	89.70	315.000	4,792.46	2,943.47	-4,358.93	5,163.60	0.00	0.00	0.00
10,400.00	89.70	315.000	4,792.99	3,014.18	-4,429.64	5,263.59	0.00	0.00	0.00
10,500.00	89.70	315.000	4,793.52	3,084.89	-4,500.35	5,363.59	0.00	0.00	0.00
10,600.00	89.70	315.000	4,794.04	3,155.60	-4,571.06	5,463.59	0.00	0.00	0.00
10,700.00	89.70	315.000	4,794.57	3,226.31	-4,641.77	5,563.59	0.00	0.00	0.00
10,781.50	89.70	315.000	4,795.00	3,283.93	-4,699.40	5,645.09	0.00	0.00	0.00
PBHL/TD @ 10781.50 MD 4795.00 TVD									

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (")	Hole Diameter (")	
350.00	350.00	9-5/8" Surface Casing	9-5/8	12-1/4	
5,158.82	4,754.36	7" Intermediate Casing	7	8-3/4	



Planning Report

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Formations						
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
360.00	360.00	Ojo Alamo		0.300	314.999	
470.00	470.00	Kirtland		0.300	314.999	
705.00	705.00	Fruitland		0.300	314.999	
1,091.08	1,089.95	Pictured Cliffs		0.300	314.999	
1,274.74	1,269.87	Lewis		0.300	314.999	
1,473.62	1,459.74	Chacra		0.300	314.999	
2,611.84	2,513.79	Cliff House		0.300	314.999	
2,622.63	2,523.78	Menefee		0.300	314.999	
3,702.72	3,527.90	Point Lookout		0.300	314.999	
3,861.92	3,682.82	Mancos		0.300	314.999	
4,219.02	4,037.74	MNCS_A		0.300	314.999	
4,319.02	4,137.74	MNCS_B		0.300	314.999	
4,409.05	4,227.75	MNCS_C		0.300	314.999	
4,449.26	4,267.77	MNCS_Cms		0.300	314.999	
4,605.48	4,417.98	MNCS_D		0.300	314.999	
4,732.46	4,528.31	MNCS_E		0.300	314.999	
4,839.37	4,608.67	MNCS_F		0.300	314.999	
4,936.18	4,669.07	MNCS_G		0.300	314.999	
5,017.63	4,709.43	MNCS_H		0.300	314.999	
5,162.81	4,755.15	MNCS_I		0.300	314.999	

Plan Annotations					
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates			
		+N/-S (ft)	+E/-W (ft)	Comment	
800.00	800.00	0.00	0.00	KOP Begin 3°/100' build	
1,541.02	1,522.57	-133.43	-48.47	Begin 22.23° tangent	
3,483.25	3,320.43	-824.10	-299.34	Begin 3°/100' drop	
4,224.28	4,043.00	-957.53	-347.81	Begin vertical hold	
4,374.28	4,193.00	-957.53	-347.81	Begin 10°/100' build	
5,271.28	4,765.95	-600.16	-791.81	Begin 2°/100' turn	
5,579.76	4,767.57	-394.19	-1,021.25	Begin 89.70° lateral	
10,781.50	4,795.00	3,283.93	-4,699.40	PBHL/TD @ 10781.50 MD 4795.00 TVD	



Planning Report - Geographic

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Project	San Juan County, New Mexico NAD83 NM W		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Western Zone		

Site		Ponderosa (100,118,119,121,122 & 123)			
Site Position:		Northing:	1,911,577.39 usft	Latitude:	36.25351300
From:	Lat/Long	Easting:	2,725,001.43 usft	Longitude:	-107.82685600
Position Uncertainty:	0.00 ft	Slot Radius:	13-3/16 "		

Well	Ponderosa Unit 119H, Surf loc: 1788 FSL 1670 FEL Section 06-T23N-R09W					
Well Position	+N/-S	0.00 ft	Northing:	1,911,597.41 usft	Latitude:	36.25356800
	+E/-W	0.00 ft	Easting:	2,724,998.48 usft	Longitude:	-107.82686600
Position Uncertainty		0.00 ft	Wellhead Elevation:	ft	Ground Level:	6,711.00 ft
Grid Convergence:		0.004 °				

Wellbore	Original Hole				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2020	11/11/2024	8.473	62.676	48,965.36627143

Design	rev0			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	314.999

Plan Survey Tool Program	Date	11/12/2024		
Depth From (ft)	Depth To (ft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	10,781.50 rev0 (Original Hole)	MWD	
			OWSG MWD - Standard	



Planning Report - Geographic

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.000	0.00	0.00	0.00	0.00	0.00	0.00	0.000	
800.00	0.00	0.000	800.00	0.00	0.00	0.00	0.00	0.00	0.000	
1,541.02	22.23	199.963	1,522.57	-133.43	-48.47	3.00	3.00	0.00	199.963	
3,483.25	22.23	199.963	3,320.43	-824.10	-299.34	0.00	0.00	0.00	0.000	
4,224.28	0.00	0.000	4,043.00	-957.53	-347.81	3.00	-3.00	0.00	180.000	
4,374.28	0.00	0.000	4,193.00	-957.53	-347.81	0.00	0.00	0.00	0.000	
5,271.28	89.70	308.830	4,765.95	-600.16	-791.81	10.00	10.00	0.00	308.830	
5,579.76	89.70	315.000	4,767.57	-394.19	-1,021.25	2.00	0.00	2.00	90.036	
10,781.50	89.70	315.000	4,795.00	3,283.93	-4,699.40	0.00	0.00	0.00	0.000	Ponderosa 119 LTP 2



Planning Report - Geographic

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.000	0.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
100.00	0.00	0.000	100.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
200.00	0.00	0.000	200.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
300.00	0.00	0.000	300.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
350.00	0.00	0.000	350.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
9-5/8" Surface Casing									
360.00	0.00	0.000	360.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
Ojo Alamo									
400.00	0.00	0.000	400.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
470.00	0.00	0.000	470.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
Kirtland									
500.00	0.00	0.000	500.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
600.00	0.00	0.000	600.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
700.00	0.00	0.000	700.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
705.00	0.00	0.000	705.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
Fruitland									
800.00	0.00	0.000	800.00	0.00	0.00	1,911,597.41	2,724,998.48	36.25356800	-107.82686600
KOP Begin 3°/100' build									
900.00	3.00	199.963	899.95	-2.46	-0.89	1,911,594.95	2,724,997.59	36.25356124	-107.82686903
1,000.00	6.00	199.963	999.63	-9.83	-3.57	1,911,587.58	2,724,994.91	36.25354099	-107.82687811
1,091.08	8.73	199.963	1,089.95	-20.81	-7.56	1,911,576.61	2,724,990.92	36.25351084	-107.82689164
Pictured Cliffs									
1,100.00	9.00	199.963	1,098.77	-22.10	-8.03	1,911,575.31	2,724,990.45	36.25350729	-107.82689323
1,200.00	12.00	199.963	1,197.08	-39.23	-14.25	1,911,558.19	2,724,984.23	36.25346024	-107.82691433
1,274.74	14.24	199.963	1,269.87	-55.17	-20.04	1,911,542.24	2,724,978.44	36.25341644	-107.82693398
Lewis									
1,300.00	15.00	199.963	1,294.31	-61.17	-22.22	1,911,536.25	2,724,976.26	36.25339998	-107.82694137
1,400.00	18.00	199.963	1,390.18	-87.86	-31.91	1,911,509.55	2,724,966.57	36.25332665	-107.82697426
1,473.62	20.21	199.963	1,459.74	-110.50	-40.14	1,911,486.91	2,724,958.34	36.25326444	-107.82700216
Chacra									
1,500.00	21.00	199.963	1,484.43	-119.23	-43.31	1,911,478.18	2,724,955.17	36.25324047	-107.82701291
1,541.02	22.23	199.963	1,522.57	-133.43	-48.47	1,911,463.98	2,724,950.01	36.25320146	-107.82703041
Begin 22.23° tangent									
1,600.00	22.23	199.963	1,577.16	-154.41	-56.09	1,911,443.01	2,724,942.39	36.25314385	-107.82705626
1,700.00	22.23	199.963	1,669.73	-189.97	-69.00	1,911,407.45	2,724,929.48	36.25304616	-107.82710007
1,800.00	22.23	199.963	1,762.30	-225.53	-81.92	1,911,371.89	2,724,916.56	36.25294848	-107.82714389
1,900.00	22.23	199.963	1,854.86	-261.09	-94.84	1,911,336.33	2,724,903.64	36.25285079	-107.82718771
2,000.00	22.23	199.963	1,947.43	-296.65	-107.75	1,911,300.77	2,724,890.73	36.25275311	-107.82723152
2,100.00	22.23	199.963	2,040.00	-332.21	-120.67	1,911,265.21	2,724,877.81	36.25265542	-107.82727534
2,200.00	22.23	199.963	2,132.56	-367.77	-133.59	1,911,229.65	2,724,864.89	36.25255774	-107.82731916
2,300.00	22.23	199.963	2,225.13	-403.33	-146.50	1,911,194.09	2,724,851.98	36.25246005	-107.82736297
2,400.00	22.23	199.963	2,317.70	-438.89	-159.42	1,911,158.53	2,724,839.06	36.25236237	-107.82740679
2,500.00	22.23	199.963	2,410.26	-474.45	-172.34	1,911,122.97	2,724,826.14	36.25226468	-107.82745061
2,600.00	22.23	199.963	2,502.83	-510.01	-185.25	1,911,087.41	2,724,813.23	36.25216700	-107.82749442
2,611.84	22.23	199.963	2,513.79	-514.22	-186.78	1,911,083.20	2,724,811.70	36.25215544	-107.82749961
Cliff House									
2,622.63	22.23	199.963	2,523.78	-518.06	-188.18	1,911,079.36	2,724,810.30	36.25214489	-107.82750434
Menefee									
2,700.00	22.23	199.963	2,595.40	-545.57	-198.17	1,911,051.84	2,724,800.31	36.25206932	-107.82753824
2,800.00	22.23	199.963	2,687.97	-581.13	-211.09	1,911,016.28	2,724,787.39	36.25197163	-107.82758206
2,900.00	22.23	199.963	2,780.53	-616.69	-224.00	1,910,980.72	2,724,774.48	36.25187395	-107.82762587
3,000.00	22.23	199.963	2,873.10	-652.25	-236.92	1,910,945.16	2,724,761.56	36.25177626	-107.82766969
3,100.00	22.23	199.963	2,965.67	-687.81	-249.84	1,910,909.60	2,724,748.64	36.25167858	-107.82771350



Planning Report - Geographic

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude	
3,200.00	22.23	199.963	3,058.23	-723.37	-262.75	1,910,874.04	2,724,735.73	36.25158089	-107.827775732	
3,300.00	22.23	199.963	3,150.80	-758.93	-275.67	1,910,838.48	2,724,722.81	36.25148321	-107.82780114	
3,400.00	22.23	199.963	3,243.37	-794.49	-288.59	1,910,802.92	2,724,709.89	36.25138552	-107.82784495	
3,483.25	22.23	199.963	3,320.43	-824.10	-299.34	1,910,773.32	2,724,699.14	36.25130420	-107.82788143	
Begin 3°/100' drop										
3,500.00	21.73	199.963	3,335.96	-829.99	-301.48	1,910,767.43	2,724,697.00	36.25128801	-107.82788869	
3,600.00	18.73	199.963	3,429.78	-862.48	-313.29	1,910,734.93	2,724,685.20	36.25119875	-107.82792873	
3,700.00	15.73	199.963	3,525.28	-890.32	-323.40	1,910,707.10	2,724,675.09	36.25112229	-107.82796302	
3,702.72	15.65	199.963	3,527.90	-891.01	-323.65	1,910,706.41	2,724,674.83	36.25112039	-107.82796387	
Point Lookout										
3,800.00	12.73	199.963	3,622.21	-913.42	-331.79	1,910,684.00	2,724,666.69	36.25105883	-107.82799148	
3,861.92	10.87	199.963	3,682.82	-925.32	-336.11	1,910,672.10	2,724,662.37	36.25102614	-107.82800615	
Mancos										
3,900.00	9.73	199.963	3,720.28	-931.72	-338.43	1,910,665.70	2,724,660.05	36.25100856	-107.82801403	
4,000.00	6.73	199.963	3,819.24	-945.17	-343.32	1,910,652.25	2,724,655.16	36.25097161	-107.82803060	
4,100.00	3.73	199.963	3,918.81	-953.73	-346.43	1,910,643.68	2,724,652.05	36.25094809	-107.82804116	
4,200.00	0.73	199.963	4,018.73	-957.39	-347.76	1,910,640.03	2,724,650.72	36.25093805	-107.82804566	
4,219.02	0.16	199.963	4,037.74	-957.52	-347.81	1,910,639.89	2,724,650.67	36.25093767	-107.82804583	
MNCS_A										
4,224.28	0.00	0.000	4,043.00	-957.53	-347.81	1,910,639.89	2,724,650.67	36.25093765	-107.82804584	
Begin vertical hold										
4,300.00	0.00	0.000	4,118.72	-957.53	-347.81	1,910,639.89	2,724,650.67	36.25093765	-107.82804584	
4,319.02	0.00	0.000	4,137.74	-957.53	-347.81	1,910,639.89	2,724,650.67	36.25093765	-107.82804584	
MNCS_B										
4,374.28	0.00	0.000	4,193.00	-957.53	-347.81	1,910,639.89	2,724,650.67	36.25093765	-107.82804584	
Begin 10°/100' build										
4,400.00	2.57	308.830	4,218.72	-957.17	-348.26	1,910,640.25	2,724,650.22	36.25093865	-107.82804736	
4,409.05	3.48	308.830	4,227.75	-956.87	-348.63	1,910,640.55	2,724,649.85	36.25093947	-107.82804862	
MNCS_C										
4,449.26	7.50	308.830	4,267.77	-954.46	-351.63	1,910,642.96	2,724,646.85	36.25094609	-107.82805878	
MNCS_Cms										
4,450.00	7.57	308.830	4,268.50	-954.40	-351.70	1,910,643.02	2,724,646.78	36.25094626	-107.82805904	
4,500.00	12.57	308.830	4,317.72	-948.92	-358.51	1,910,648.50	2,724,639.97	36.25096132	-107.82808213	
4,550.00	17.57	308.830	4,365.98	-940.77	-368.64	1,910,656.65	2,724,629.84	36.25098371	-107.82811647	
4,600.00	22.57	308.830	4,412.93	-930.01	-382.00	1,910,667.41	2,724,616.48	36.25101326	-107.82816180	
4,605.48	23.12	308.830	4,417.98	-928.68	-383.66	1,910,668.74	2,724,614.82	36.25101692	-107.82816742	
MNCS_D										
4,650.00	27.57	308.830	4,458.21	-916.73	-398.50	1,910,680.69	2,724,599.98	36.25104975	-107.82821776	
4,700.00	32.57	308.830	4,501.46	-901.02	-418.01	1,910,696.39	2,724,580.47	36.25109289	-107.82828393	
4,732.46	35.82	308.830	4,528.31	-889.59	-432.22	1,910,707.83	2,724,566.26	36.25112431	-107.82833212	
MNCS_E										
4,750.00	37.57	308.830	4,542.37	-883.02	-440.39	1,910,714.40	2,724,558.09	36.25114236	-107.82835981	
4,800.00	42.57	308.830	4,580.62	-862.84	-465.46	1,910,734.58	2,724,533.03	36.25119779	-107.82844482	
4,839.37	46.51	308.830	4,608.67	-845.53	-486.96	1,910,751.89	2,724,511.52	36.25124535	-107.82851776	
MNCS_F										
4,850.00	47.57	308.830	4,615.92	-840.65	-493.02	1,910,756.76	2,724,505.46	36.25125875	-107.82853832	
4,900.00	52.57	308.830	4,648.00	-816.62	-522.88	1,910,780.80	2,724,475.60	36.25132478	-107.82863959	
4,936.18	56.19	308.830	4,669.07	-798.18	-545.79	1,910,799.24	2,724,452.69	36.25137543	-107.82871728	
MNCS_G										
4,950.00	57.57	308.830	4,676.62	-790.92	-554.81	1,910,806.49	2,724,443.67	36.25139537	-107.82874786	
5,000.00	62.57	308.830	4,701.55	-763.76	-588.55	1,910,833.66	2,724,409.93	36.25146999	-107.82886231	
5,017.63	64.34	308.830	4,709.43	-753.87	-600.84	1,910,843.54	2,724,397.64	36.25149716	-107.82890398	
MNCS_H										



Planning Report - Geographic

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude	
5,050.00	67.57	308.830	4,722.62	-735.34	-623.86	1,910,862.08	2,724,374.62	36.25154807	-107.82898206	
5,100.00	72.57	308.830	4,739.66	-705.87	-660.47	1,910,891.54	2,724,338.01	36.25162901	-107.82910621	
5,150.00	77.57	308.830	4,752.53	-675.59	-698.10	1,910,921.82	2,724,300.39	36.25171221	-107.82923382	
5,158.82	78.45	308.830	4,754.36	-670.18	-704.82	1,910,927.23	2,724,293.67	36.25172707	-107.82925661	
7" Intermediate Casing										
5,162.81	78.85	308.830	4,755.15	-667.73	-707.86	1,910,929.68	2,724,290.62	36.25173380	-107.82926693	
MNCS_I										
5,200.00	82.57	308.830	4,761.15	-644.72	-736.45	1,910,952.69	2,724,262.03	36.25179702	-107.82936390	
5,250.00	87.57	308.830	4,765.44	-613.50	-775.24	1,910,983.92	2,724,223.24	36.25188280	-107.82949547	
5,271.28	89.70	308.830	4,765.95	-600.16	-791.81	1,910,997.25	2,724,206.67	36.25191943	-107.82955166	
Begin 2°/100' turn										
5,300.00	89.70	309.404	4,766.10	-582.04	-814.10	1,911,015.38	2,724,184.38	36.25196922	-107.82962724	
5,400.00	89.70	311.405	4,766.63	-517.22	-890.24	1,911,080.19	2,724,108.24	36.25214727	-107.82988548	
5,500.00	89.70	313.405	4,767.15	-449.79	-964.08	1,911,147.62	2,724,034.40	36.25233252	-107.83013590	
5,579.76	89.70	315.000	4,767.57	-394.19	-1,021.25	1,911,203.23	2,723,977.23	36.25248528	-107.83032982	
Begin 89.70° lateral										
5,600.00	89.70	315.000	4,767.68	-379.87	-1,035.57	1,911,217.54	2,723,962.92	36.25252459	-107.83037835	
5,700.00	89.70	315.000	4,768.21	-309.17	-1,106.28	1,911,288.25	2,723,892.21	36.25271884	-107.83061817	
5,800.00	89.70	315.000	4,768.73	-238.46	-1,176.99	1,911,358.96	2,723,821.50	36.25291309	-107.83085799	
5,900.00	89.70	315.000	4,769.26	-167.75	-1,247.70	1,911,429.67	2,723,750.79	36.25310734	-107.83109780	
6,000.00	89.70	315.000	4,769.79	-97.04	-1,318.41	1,911,500.38	2,723,680.08	36.25330159	-107.83133762	
6,100.00	89.70	315.000	4,770.32	-26.33	-1,389.12	1,911,571.09	2,723,609.37	36.25349584	-107.83157745	
6,200.00	89.70	315.000	4,770.84	44.38	-1,459.83	1,911,641.79	2,723,538.66	36.25369009	-107.83181727	
6,300.00	89.70	315.000	4,771.37	115.09	-1,530.53	1,911,712.50	2,723,467.95	36.25388433	-107.83205709	
6,400.00	89.70	315.000	4,771.90	185.80	-1,601.24	1,911,783.21	2,723,397.24	36.25407858	-107.83229692	
6,500.00	89.70	315.000	4,772.42	256.51	-1,671.95	1,911,853.92	2,723,326.53	36.25427282	-107.83253674	
6,600.00	89.70	315.000	4,772.95	327.22	-1,742.66	1,911,924.63	2,723,255.82	36.25446707	-107.83277657	
6,700.00	89.70	315.000	4,773.48	397.93	-1,813.37	1,911,995.34	2,723,185.11	36.25466131	-107.83301640	
6,800.00	89.70	315.000	4,774.01	468.64	-1,884.08	1,912,066.05	2,723,114.40	36.25485556	-107.83325623	
6,900.00	89.70	315.000	4,774.53	539.35	-1,954.79	1,912,136.76	2,723,043.69	36.25504980	-107.83349606	
7,000.00	89.70	315.000	4,775.06	610.06	-2,025.50	1,912,207.47	2,722,972.98	36.25524405	-107.83373589	
7,100.00	89.70	315.000	4,775.59	680.77	-2,096.21	1,912,278.18	2,722,902.27	36.25543829	-107.83397572	
7,200.00	89.70	315.000	4,776.12	751.48	-2,166.92	1,912,348.89	2,722,831.56	36.25563253	-107.83421556	
7,300.00	89.70	315.000	4,776.64	822.19	-2,237.63	1,912,419.60	2,722,760.85	36.25582677	-107.83445539	
7,400.00	89.70	315.000	4,777.17	892.90	-2,308.34	1,912,490.31	2,722,690.14	36.25602102	-107.83469523	
7,500.00	89.70	315.000	4,777.70	963.60	-2,379.05	1,912,561.02	2,722,619.43	36.25621526	-107.83493507	
7,600.00	89.70	315.000	4,778.22	1,034.31	-2,449.76	1,912,631.73	2,722,548.72	36.25640950	-107.83517490	
7,700.00	89.70	315.000	4,778.75	1,105.02	-2,520.47	1,912,702.43	2,722,478.01	36.25660374	-107.83541474	
7,800.00	89.70	315.000	4,779.28	1,175.73	-2,591.18	1,912,773.14	2,722,407.30	36.25679798	-107.83565459	
7,900.00	89.70	315.000	4,779.81	1,246.44	-2,661.89	1,912,843.85	2,722,336.59	36.25699222	-107.83589443	
8,000.00	89.70	315.000	4,780.33	1,317.15	-2,732.60	1,912,914.56	2,722,265.88	36.25718645	-107.83613427	
8,100.00	89.70	315.000	4,780.86	1,387.86	-2,803.31	1,912,985.27	2,722,195.17	36.25738069	-107.83637412	
8,200.00	89.70	315.000	4,781.39	1,458.57	-2,874.02	1,913,055.98	2,722,124.46	36.25757493	-107.83661396	
8,300.00	89.70	315.000	4,781.92	1,529.28	-2,944.73	1,913,126.69	2,722,053.75	36.25776917	-107.83685381	
8,400.00	89.70	315.000	4,782.44	1,599.99	-3,015.44	1,913,197.40	2,721,983.04	36.25796340	-107.83709366	
8,500.00	89.70	315.000	4,782.97	1,670.70	-3,086.15	1,913,268.11	2,721,912.33	36.25815764	-107.83733351	
8,600.00	89.70	315.000	4,783.50	1,741.41	-3,156.86	1,913,338.82	2,721,841.62	36.25835188	-107.83757336	
8,700.00	89.70	315.000	4,784.02	1,812.12	-3,227.57	1,913,409.53	2,721,770.91	36.25854611	-107.83781321	
8,800.00	89.70	315.000	4,784.55	1,882.83	-3,298.28	1,913,480.24	2,721,700.20	36.25874034	-107.83805306	
8,900.00	89.70	315.000	4,785.08	1,953.54	-3,368.99	1,913,550.95	2,721,629.49	36.25893458	-107.83829292	
9,000.00	89.70	315.000	4,785.61	2,024.25	-3,439.70	1,913,621.66	2,721,558.78	36.25912881	-107.83853277	
9,100.00	89.70	315.000	4,786.13	2,094.96	-3,510.41	1,913,692.37	2,721,488.07	36.25932305	-107.83877263	
9,200.00	89.70	315.000	4,786.66	2,165.67	-3,581.12	1,913,763.07	2,721,417.36	36.25951728	-107.83901249	
9,300.00	89.70	315.000	4,787.19	2,236.37	-3,651.83	1,913,833.78	2,721,346.65	36.25971151	-107.83925235	



Planning Report - Geographic

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude	
9,400.00	89.70	315.000	4,787.72	2,307.08	-3,722.54	1,913,904.49	2,721,275.94	36.25990574	-107.83949221	
9,500.00	89.70	315.000	4,788.24	2,377.79	-3,793.25	1,913,975.20	2,721,205.24	36.26009997	-107.83973207	
9,600.00	89.70	315.000	4,788.77	2,448.50	-3,863.96	1,914,045.91	2,721,134.53	36.26029420	-107.83997193	
9,700.00	89.70	315.000	4,789.30	2,519.21	-3,934.67	1,914,116.62	2,721,063.82	36.26048843	-107.84021180	
9,800.00	89.70	315.000	4,789.82	2,589.92	-4,005.38	1,914,187.33	2,720,993.11	36.26068266	-107.84045166	
9,900.00	89.70	315.000	4,790.35	2,660.63	-4,076.09	1,914,258.04	2,720,922.40	36.26087689	-107.84069153	
10,000.00	89.70	315.000	4,790.88	2,731.34	-4,146.80	1,914,328.75	2,720,851.69	36.26107112	-107.84093139	
10,100.00	89.70	315.000	4,791.41	2,802.05	-4,217.51	1,914,399.46	2,720,780.98	36.26126535	-107.84117126	
10,200.00	89.70	315.000	4,791.93	2,872.76	-4,288.22	1,914,470.17	2,720,710.27	36.26145958	-107.84141113	
10,300.00	89.70	315.000	4,792.46	2,943.47	-4,358.93	1,914,540.88	2,720,639.56	36.26165381	-107.84165100	
10,400.00	89.70	315.000	4,792.99	3,014.18	-4,429.64	1,914,611.59	2,720,568.85	36.26184803	-107.84189088	
10,500.00	89.70	315.000	4,793.52	3,084.89	-4,500.35	1,914,682.30	2,720,498.14	36.26204226	-107.84213075	
10,600.00	89.70	315.000	4,794.04	3,155.60	-4,571.06	1,914,753.00	2,720,427.43	36.26223649	-107.84237062	
10,700.00	89.70	315.000	4,794.57	3,226.31	-4,641.77	1,914,823.71	2,720,356.72	36.26243071	-107.84261050	
10,781.50	89.70	315.000	4,795.00	3,283.93	-4,699.40	1,914,881.34	2,720,299.09	36.26258900	-107.84280600	
PBHL/TD @ 10781.50 MD 4795.00 TVD										

Design Targets										
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude	
Ponderosa 119 FTP 109 - plan misses target center by 30.16ft at 5162.81ft MD (4755.15 TVD, -667.73 N, -707.86 E) - Point	0.00	0.000	4,765.00	-690.96	-724.39	1,910,906.46	2,724,274.09	36.25167000	-107.82932300	
Ponderosa 119 vs=0 - plan misses target center by 34.43ft at 5140.97ft MD (4750.52 TVD, -681.11 N, -691.24 E) - Point	0.00	0.000	4,765.00	-707.68	-707.66	1,910,889.73	2,724,290.82	36.25162406	-107.82926626	
Ponderosa 119 LTP 232 - plan hits target center - Point	0.00	0.000	4,795.00	3,283.93	-4,699.40	1,914,881.34	2,720,299.09	36.26258900	-107.84280600	

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (")	Hole Diameter (")	
350.00	350.00	9-5/8" Surface Casing	9-5/8	12-1/4	
5,158.82	4,754.36	7" Intermediate Casing	7	8-3/4	



Planning Report - Geographic

Database:	DT_Jul1724_v17	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Company:	Enduring Resources LLC	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Project:	San Juan County, New Mexico NAD83 NM W	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site:	Ponderosa (100,118,119,121,122 & 123)	North Reference:	Grid
Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev0		

Formations						
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
360.00	360.00	Ojo Alamo		0.300	314.999	
470.00	470.00	Kirtland		0.300	314.999	
705.00	705.00	Fruitland		0.300	314.999	
1,091.08	1,089.95	Pictured Cliffs		0.300	314.999	
1,274.74	1,269.87	Lewis		0.300	314.999	
1,473.62	1,459.74	Chacra		0.300	314.999	
2,611.84	2,513.79	Cliff House		0.300	314.999	
2,622.63	2,523.78	Menefee		0.300	314.999	
3,702.72	3,527.90	Point Lookout		0.300	314.999	
3,861.92	3,682.82	Mancos		0.300	314.999	
4,219.02	4,037.74	MNCS_A		0.300	314.999	
4,319.02	4,137.74	MNCS_B		0.300	314.999	
4,409.05	4,227.75	MNCS_C		0.300	314.999	
4,449.26	4,267.77	MNCS_Cms		0.300	314.999	
4,605.48	4,417.98	MNCS_D		0.300	314.999	
4,732.46	4,528.31	MNCS_E		0.300	314.999	
4,839.37	4,608.67	MNCS_F		0.300	314.999	
4,936.18	4,669.07	MNCS_G		0.300	314.999	
5,017.63	4,709.43	MNCS_H		0.300	314.999	
5,162.81	4,755.15	MNCS_I		0.300	314.999	

Plan Annotations					
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates			
		+N/-S (ft)	+E/-W (ft)	Comment	
800.00	800.00	0.00	0.00	KOP Begin 3°/100' build	
1,541.02	1,522.57	-133.43	-48.47	Begin 22.23° tangent	
3,483.25	3,320.43	-824.10	-299.34	Begin 3°/100' drop	
4,224.28	4,043.00	-957.53	-347.81	Begin vertical hold	
4,374.28	4,193.00	-957.53	-347.81	Begin 10°/100' build	
5,271.28	4,765.95	-600.16	-791.81	Begin 2°/100' turn	
5,579.76	4,767.57	-394.19	-1,021.25	Begin 89.70° lateral	
10,781.50	4,795.00	3,283.93	-4,699.40	PBHL/TD @ 10781.50 MD 4795.00 TVD	



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Reference	rev0		
Filter type:	GLOBAL FILTER APPLIED: All wellpaths within 200'+ 100/1000 of reference		
Interpolation Method:	MD Interval 100.00ft	Error Model:	ISCWSA
Depth Range:	Unlimited	Scan Method:	Closest Approach 3D
Results Limited by:	Maximum centre distance of 1,278.15ft	Error Surface:	Ellipsoid Separation
Warning Levels Evaluated at:	2.00 Sigma	Casing Method:	Not applied

Survey Tool Program		Date	11/12/2024		
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
0.00	10,781.50	rev0 (Original Hole)	MWD	OWSG MWD - Standard	

Summary						
	Reference Measured Depth (ft)	Offset Measured Depth (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Separation Factor	Warning
Site Name Offset Well - Wellbore - Design						
Ponderosa (100,118,119,121,122 & 123)						
Ponderosa #100H - Original Hole - rev0	800.00	800.00	19.84	14.27	3.563	CC, ES
Ponderosa #100H - Original Hole - rev0	900.00	899.95	22.19	15.92	3.540	SF
Ponderosa J06 2309 FED COM 121H - Original Hole - re	1,235.74	1,230.13	28.72	20.28	3.402	CC, ES, SF
Ponderosa J06 2309 FED COM 123H - Original Hole - re	1,169.44	1,167.14	19.22	11.06	2.355	CC, ES, SF
Ponderosa J06 2309 FED COM 118H - Original Hole - re	500.00	500.00	20.24	16.82	5.924	CC, ES
Ponderosa J06 2309 FED COM 118H - Original Hole - re	5,012.17	5,021.52	59.95	23.18	1.631	Level 3<2.00, SF
Ponderosa Unit 122H - Original Hole - rev0	800.00	800.00	40.07	34.51	7.198	CC, ES
Ponderosa Unit 122H - Original Hole - rev0	10,000.00	9,721.67	1,199.99	965.70	5.122	SF
Ponderosa (99, 111,112,114-117,120,136)						
Ponderosa 099H - Original Hole - rev0	4,242.40	4,400.00	688.04	652.49	19.356	CC
Ponderosa 099H - Original Hole - rev0	10,781.50	10,391.71	720.43	503.71	3.324	ES, SF
Ponderosa 117H - Original Hole - rev0	10,781.50	10,548.04	1,199.85	932.32	4.485	CC, ES, SF

Offset Design:		Ponderosa (100,118,119,121,122 & 123) - Ponderosa #100H - Original Hole - rev0											Offset Site Error:		0.00 ft		
Survey Program:		0-MWD						Rule Assigned:						Offset Well Error:		0.00 ft	
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (ft)	Separation Factor	Warning				
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)							
0.00	0.00	0.00	0.00	0.00	0.00	-7.692	19.66	-2.65	19.84								
100.00	100.00	100.00	100.00	0.27	0.27	-7.692	19.66	-2.65	19.84	19.29	0.55	36.166					
200.00	200.00	200.00	200.00	0.63	0.63	-7.692	19.66	-2.65	19.84	18.57	1.27	15.675					
300.00	300.00	300.00	300.00	0.99	0.99	-7.692	19.66	-2.65	19.84	17.85	1.98	10.006					
400.00	400.00	400.00	400.00	1.35	1.35	-7.692	19.66	-2.65	19.84	17.14	2.70	7.348					
500.00	500.00	500.00	500.00	1.71	1.71	-7.692	19.66	-2.65	19.84	16.42	3.42	5.806					
600.00	600.00	600.00	600.00	2.07	2.07	-7.692	19.66	-2.65	19.84	15.70	4.13	4.799					
700.00	700.00	700.00	700.00	2.43	2.43	-7.692	19.66	-2.65	19.84	14.99	4.85	4.090					
800.00	800.00	800.00	800.00	2.78	2.78	-7.692	19.66	-2.65	19.84	14.27	5.57	3.563 CC, ES					
900.00	899.95	899.95	899.95	3.13	3.14	155.454	19.66	-2.65	22.19	15.92	6.27	3.540 SF					
1,000.00	999.63	999.63	999.63	3.46	3.50	161.725	19.66	-2.65	29.51	22.55	6.96	4.240					
1,100.00	1,098.77	1,098.77	1,098.77	3.80	3.85	167.217	19.66	-2.65	42.10	34.45	7.66	5.499					
1,200.00	1,197.08	1,197.08	1,197.08	4.17	4.21	170.982	19.66	-2.65	60.01	51.66	8.36	7.182					
1,300.00	1,294.31	1,298.33	1,298.29	4.58	4.55	172.989	17.47	-3.92	80.83	71.79	9.04	8.939					
1,400.00	1,390.18	1,400.81	1,400.44	5.03	4.89	173.628	10.52	-7.93	101.78	92.07	9.71	10.482					

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (100,118,119,121,122 & 123) - Ponderosa #100H - Original Hole - rev0													Offset Site Error:	0.00 ft
Survey Program: 0-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (ft)	Separation Factor	Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)				
1,500.00	1,484.43	1,504.43	1,503.14	5.53	5.25	173.578	-1.31	-14.76	122.76	112.38	10.38	11.831		
1,600.00	1,577.16	1,609.01	1,605.89	6.09	5.62	173.136	-18.12	-24.44	142.83	131.78	11.05	12.931		
1,700.00	1,669.73	1,710.78	1,705.29	6.69	6.01	173.662	-38.36	-32.48	159.94	148.20	11.74	13.623		
1,800.00	1,762.30	1,812.88	1,804.56	7.30	6.42	175.743	-61.90	-36.17	175.08	162.63	12.44	14.069		
1,900.00	1,854.86	1,914.22	1,902.37	7.94	6.84	179.001	-88.36	-35.56	188.69	175.52	13.17	14.326		
2,000.00	1,947.43	2,012.67	1,997.10	8.59	7.27	-177.761	-115.13	-33.49	202.31	188.37	13.95	14.508		
2,100.00	2,040.00	2,111.13	2,091.82	9.25	7.72	-174.934	-141.90	-31.42	216.49	201.74	14.75	14.680		
2,200.00	2,132.56	2,209.58	2,186.54	9.92	8.19	-172.457	-168.67	-29.34	231.13	215.55	15.58	14.837		
2,300.00	2,225.13	2,308.04	2,281.27	10.59	8.66	-170.276	-195.43	-27.27	246.15	229.71	16.44	14.977		
2,400.00	2,317.70	2,406.49	2,375.99	11.27	9.15	-168.347	-222.20	-25.20	261.47	244.16	17.32	15.100		
2,500.00	2,410.26	2,504.95	2,470.71	11.96	9.65	-166.631	-248.97	-23.12	277.06	258.84	18.22	15.208		
2,600.00	2,502.83	2,603.40	2,565.44	12.65	10.15	-165.098	-275.73	-21.05	292.86	273.72	19.14	15.301		
2,700.00	2,595.40	2,701.86	2,660.16	13.34	10.66	-163.723	-302.50	-18.98	308.85	288.77	20.08	15.382		
2,800.00	2,687.97	2,800.31	2,754.89	14.04	11.18	-162.482	-329.27	-16.90	324.99	303.96	21.03	15.452		
2,900.00	2,780.53	2,898.77	2,849.61	14.74	11.70	-161.359	-356.03	-14.83	341.27	319.27	22.00	15.512		
3,000.00	2,873.10	2,997.22	2,944.33	15.44	12.23	-160.338	-382.80	-12.75	357.67	334.69	22.98	15.564		
3,100.00	2,965.67	3,095.67	3,039.06	16.14	12.76	-159.407	-409.57	-10.68	374.17	350.19	23.97	15.608		
3,200.00	3,058.23	3,186.73	3,126.84	16.85	13.24	-158.687	-433.67	-8.81	391.30	366.39	24.92	15.705		
3,300.00	3,150.80	3,272.00	3,209.91	17.56	13.66	-158.423	-452.82	-7.33	411.34	385.59	25.75	15.972		
3,400.00	3,243.37	3,356.13	3,292.63	18.26	14.05	-158.544	-468.07	-6.15	434.45	407.95	26.50	16.392		
3,500.00	3,335.96	3,438.83	3,374.52	18.97	14.40	-159.030	-479.51	-5.26	460.51	433.34	27.17	16.952		
3,600.00	3,429.78	3,520.67	3,455.99	19.64	14.71	-159.876	-487.34	-4.66	486.49	458.74	27.75	17.532		
3,700.00	3,525.28	3,600.00	3,535.19	20.24	14.99	-160.723	-491.61	-4.33	510.76	482.53	28.23	18.092		
3,800.00	3,622.21	3,687.03	3,622.21	20.79	15.25	-161.642	-492.65	-4.24	533.22	504.49	28.73	18.559		
3,900.00	3,720.28	3,785.10	3,720.28	21.26	15.52	-162.449	-492.65	-4.24	551.78	522.44	29.34	18.805		
4,000.00	3,819.24	3,882.74	3,817.91	21.67	15.80	-163.037	-492.44	-4.49	565.48	535.54	29.94	18.887		
4,100.00	3,918.81	3,974.00	3,908.49	22.01	16.02	-164.392	-485.69	-12.31	575.15	544.86	30.29	18.985		
4,200.00	4,018.73	4,059.92	3,991.26	22.29	16.18	-166.768	-470.84	-29.53	582.02	551.64	30.38	19.157		
4,300.00	4,118.72	4,137.81	4,062.61	22.51	16.28	30.170	-450.52	-53.08	589.13	558.93	30.20	19.506		
4,400.00	4,218.72	4,206.37	4,121.41	22.72	16.35	77.658	-427.55	-79.71	601.73	571.93	29.80	20.191		
4,500.00	4,317.72	4,270.74	4,172.44	22.90	16.40	73.099	-401.95	-109.38	618.34	589.05	29.29	21.114		
4,600.00	4,412.93	4,333.49	4,217.65	23.03	16.43	68.948	-373.55	-142.30	636.58	607.87	28.71	22.174		
4,700.00	4,501.46	4,400.00	4,260.07	23.11	16.47	65.183	-340.13	-181.04	655.00	626.80	28.21	23.220		
4,800.00	4,580.62	4,450.00	4,287.90	23.14	16.50	62.405	-313.00	-212.48	672.31	644.80	27.51	24.440		
4,900.00	4,648.00	4,515.68	4,318.77	23.13	16.58	59.885	-275.16	-256.35	687.47	660.16	27.30	25.179		
5,000.00	4,701.55	4,575.20	4,340.85	23.11	16.78	58.117	-239.07	-298.18	699.80	672.50	27.31	25.628		
5,100.00	4,739.66	4,634.43	4,357.02	23.10	17.19	56.979	-201.87	-341.30	708.73	681.01	27.72	25.565		
5,200.00	4,761.15	4,700.00	4,367.96	23.14	17.81	56.463	-159.66	-390.22	713.97	685.26	28.71	24.872		
5,300.00	4,766.10	4,752.57	4,371.36	23.34	18.40	56.516	-125.40	-429.93	715.49	685.53	29.96	23.884		
5,400.00	4,766.63	4,832.86	4,372.03	23.79	19.42	56.602	-72.24	-490.08	716.82	685.05	31.78	22.557		
5,500.00	4,767.15	4,915.55	4,372.70	24.60	20.57	56.660	-15.75	-550.47	717.68	683.87	33.81	21.225		
5,600.00	4,767.68	5,004.26	4,373.41	25.73	21.91	56.689	46.62	-613.55	717.94	681.83	36.11	19.882		
5,700.00	4,768.21	5,104.26	4,374.21	27.08	23.53	56.708	117.32	-684.26	717.79	678.96	38.83	18.487		
5,800.00	4,768.73	5,204.26	4,375.02	28.61	25.25	56.726	188.03	-754.96	717.64	675.92	41.72	17.201		
5,900.00	4,769.26	5,304.26	4,375.82	30.26	27.06	56.744	258.74	-825.67	717.49	672.73	44.76	16.029		
6,000.00	4,769.79	5,404.26	4,376.62	31.99	28.93	56.763	329.45	-896.38	717.34	669.42	47.92	14.970		
6,100.00	4,770.32	5,504.26	4,377.42	33.80	30.86	56.781	400.16	-967.09	717.19	666.02	51.17	14.017		
6,200.00	4,770.84	5,604.26	4,378.23	35.67	32.84	56.800	470.87	-1,037.80	717.04	662.55	54.49	13.159		
6,300.00	4,771.37	5,704.26	4,379.03	37.58	34.85	56.818	541.57	-1,108.51	716.89	659.01	57.87	12.387		
6,400.00	4,771.90	5,804.26	4,379.83	39.53	36.90	56.836	612.28	-1,179.21	716.74	655.43	61.31	11.690		
6,500.00	4,772.42	5,904.26	4,380.63	41.52	38.97	56.855	682.99	-1,249.92	716.59	651.80	64.79	11.061		
6,600.00	4,772.95	6,004.26	4,381.44	43.54	41.07	56.873	753.70	-1,320.63	716.44	648.14	68.29	10.490		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design:		Ponderosa (100,118,119,121,122 & 123) - Ponderosa #100H - Original Hole - rev0											Offset Site Error:		0.00 ft	
Survey Program:		0-MWD						Rule Assigned:				Offset Well Error:		0.00 ft		
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (ft)	Separation Factor	Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)						
6,700.00	4,773.48	6,104.26	4,382.24	45.59	43.18	56.892	824.41	-1,391.34	716.29	644.46	71.83	9.972				
6,800.00	4,774.01	6,204.26	4,383.04	47.66	45.32	56.910	895.11	-1,462.05	716.14	640.75	75.39	9.499				
6,900.00	4,774.53	6,304.26	4,383.84	49.74	47.47	56.929	965.82	-1,532.75	715.99	637.02	78.97	9.067				
7,000.00	4,775.06	6,404.26	4,384.64	51.85	49.63	56.947	1,036.53	-1,603.46	715.84	633.28	82.56	8.670				
7,100.00	4,775.59	6,504.26	4,385.45	53.97	51.80	56.966	1,107.24	-1,674.17	715.69	629.52	86.17	8.306				
7,200.00	4,776.12	6,604.26	4,386.25	56.10	53.98	56.984	1,177.95	-1,744.88	715.54	625.76	89.78	7.970				
7,300.00	4,776.64	6,704.26	4,387.05	58.24	56.17	57.003	1,248.65	-1,815.59	715.39	621.98	93.41	7.659				
7,400.00	4,777.17	6,804.26	4,387.85	60.40	58.37	57.021	1,319.36	-1,886.29	715.24	618.20	97.04	7.371				
7,500.00	4,777.70	6,904.26	4,388.66	62.56	60.58	57.040	1,390.07	-1,957.00	715.09	614.42	100.67	7.103				
7,600.00	4,778.22	7,004.26	4,389.46	64.74	62.79	57.058	1,460.78	-2,027.71	714.94	610.63	104.31	6.854				
7,700.00	4,778.75	7,104.25	4,390.26	66.92	65.01	57.077	1,531.49	-2,098.42	714.79	606.85	107.94	6.622				
7,800.00	4,779.28	7,204.25	4,391.06	69.11	67.24	57.095	1,602.20	-2,169.13	714.64	603.06	111.58	6.404				
7,900.00	4,779.81	7,304.25	4,391.87	71.31	69.47	57.114	1,672.90	-2,239.83	714.49	599.27	115.22	6.201				
8,000.00	4,780.33	7,404.25	4,392.67	73.51	71.70	57.132	1,743.61	-2,310.54	714.34	595.48	118.86	6.010				
8,100.00	4,780.86	7,504.25	4,393.47	75.71	73.93	57.151	1,814.32	-2,381.25	714.20	591.69	122.50	5.830				
8,200.00	4,781.39	7,604.25	4,394.27	77.93	76.17	57.169	1,885.03	-2,451.96	714.05	587.91	126.14	5.661				
8,300.00	4,781.92	7,704.25	4,395.08	80.14	78.42	57.188	1,955.74	-2,522.67	713.90	584.13	129.77	5.501				
8,400.00	4,782.44	7,804.25	4,395.88	82.36	80.66	57.207	2,026.44	-2,593.38	713.75	580.35	133.40	5.351				
8,500.00	4,782.97	7,904.25	4,396.68	84.59	82.91	57.225	2,097.15	-2,664.08	713.60	576.58	137.02	5.208				
8,600.00	4,783.50	8,004.25	4,397.48	86.82	85.16	57.244	2,167.86	-2,734.79	713.45	572.81	140.64	5.073				
8,700.00	4,784.02	8,104.25	4,398.29	89.05	87.42	57.262	2,238.57	-2,805.50	713.30	569.04	144.26	4.945				
8,800.00	4,784.55	8,204.25	4,399.09	91.28	89.67	57.281	2,309.28	-2,876.21	713.15	565.28	147.87	4.823				
8,900.00	4,785.08	8,304.25	4,399.89	93.52	91.93	57.300	2,379.99	-2,946.92	713.01	561.53	151.48	4.707				
9,000.00	4,785.61	8,404.25	4,400.69	95.76	94.19	57.318	2,450.69	-3,017.62	712.86	557.78	155.08	4.597				
9,100.00	4,786.13	8,504.25	4,401.50	98.01	96.45	57.337	2,521.40	-3,088.33	712.71	554.04	158.67	4.492				
9,200.00	4,786.66	8,604.25	4,402.30	100.25	98.72	57.355	2,592.11	-3,159.04	712.56	550.30	162.26	4.391				
9,300.00	4,787.19	8,704.25	4,403.10	102.50	100.98	57.374	2,662.82	-3,229.75	712.41	546.57	165.84	4.296				
9,400.00	4,787.72	8,804.25	4,403.90	104.75	103.25	57.393	2,733.53	-3,300.46	712.27	542.85	169.42	4.204				
9,500.00	4,788.24	8,904.25	4,404.71	107.00	105.51	57.411	2,804.23	-3,371.16	712.12	539.13	172.98	4.117				
9,600.00	4,788.77	9,004.25	4,405.51	109.25	107.78	57.430	2,874.94	-3,441.87	711.97	535.43	176.54	4.033				
9,700.00	4,789.30	9,104.25	4,406.31	111.51	110.05	57.449	2,945.65	-3,512.58	711.82	531.73	180.10	3.952				
9,800.00	4,789.82	9,204.25	4,407.11	113.76	112.32	57.467	3,016.36	-3,583.29	711.67	528.04	183.64	3.875				
9,900.00	4,790.35	9,304.25	4,407.92	116.02	114.59	57.486	3,087.07	-3,654.00	711.53	524.35	187.17	3.801				
10,000.00	4,790.88	9,404.25	4,408.72	118.28	116.86	57.505	3,157.78	-3,724.70	711.38	520.68	190.70	3.730				
10,100.00	4,791.41	9,504.25	4,409.52	120.54	119.14	57.524	3,228.48	-3,795.41	711.23	517.01	194.22	3.662				
10,160.80	4,791.73	9,564.03	4,410.00	121.92	120.50	57.535	3,270.76	-3,837.69	711.14	514.83	196.31	3.622				
10,200.00	4,791.93	9,564.03	4,410.00	122.80	120.50	57.535	3,270.76	-3,837.69	712.22	516.51	195.71	3.639				
10,300.00	4,792.46	9,564.03	4,410.00	125.07	120.50	57.535	3,270.76	-3,837.69	724.63	533.76	190.87	3.796				
10,400.00	4,792.99	9,564.03	4,410.00	127.33	120.50	57.535	3,270.76	-3,837.69	750.28	568.05	182.24	4.117				
10,500.00	4,793.52	9,564.03	4,410.00	129.60	120.50	57.535	3,270.76	-3,837.69	787.88	616.53	171.35	4.598				
10,600.00	4,794.04	9,564.03	4,410.00	131.86	120.50	57.535	3,270.76	-3,837.69	835.82	676.16	159.65	5.235				
10,700.00	4,794.57	9,564.03	4,410.00	134.13	120.50	57.535	3,270.76	-3,837.69	892.42	744.27	148.15	6.024				
10,781.50	4,795.00	9,564.03	4,410.00	135.98	120.50	57.535	3,270.76	-3,837.69	943.90	804.57	139.33	6.775				

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (100,118,119,121,122 & 123) - Ponderosa J06 2309 FED COM 121H - Original Hole - rev1												Offset Site Error:	0.00 ft
Survey Program: 0-MWD												Offset Well Error:	0.00 ft
Reference	Offset	Semi Major Axis	Highside	Rule Assigned:				Warning					
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Toolface (°)	+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	
0.00	0.00	0.00	0.00	0.00	0.00	171.846	-59.70	8.55	60.31				
100.00	100.00	100.00	100.00	0.27	0.27	171.846	-59.70	8.55	60.31	59.76	0.55	109.960	
200.00	200.00	200.00	200.00	0.63	0.63	171.846	-59.70	8.55	60.31	59.04	1.27	47.660	
300.00	300.00	300.00	300.00	0.99	0.99	171.846	-59.70	8.55	60.31	58.33	1.98	30.423	
400.00	400.00	400.00	400.00	1.35	1.35	171.846	-59.70	8.55	60.31	57.61	2.70	22.343	
500.00	500.00	500.00	500.00	1.71	1.71	171.846	-59.70	8.55	60.31	56.89	3.42	17.654	
600.00	600.00	600.00	600.00	2.07	2.07	171.846	-59.70	8.55	60.31	56.18	4.13	14.591	
700.00	700.00	700.00	700.00	2.43	2.43	171.846	-59.70	8.55	60.31	55.46	4.85	12.435	
800.00	800.00	800.00	800.00	2.78	2.78	171.846	-59.70	8.55	60.31	54.74	5.57	10.833	
900.00	899.95	900.13	900.09	3.13	3.13	-26.780	-59.90	5.94	57.84	51.58	6.26	9.240	
1,000.00	999.63	999.78	999.41	3.46	3.48	-22.003	-60.48	-1.86	50.68	43.74	6.94	7.302	
1,100.00	1,098.77	1,098.47	1,097.26	3.80	3.84	-10.466	-61.45	-14.66	39.93	32.30	7.63	5.233	
1,200.00	1,197.08	1,195.78	1,192.95	4.17	4.21	17.212	-62.77	-32.19	29.89	21.63	8.26	3.619	
1,235.74	1,231.97	1,230.13	1,226.51	4.32	4.35	32.770	-63.32	-39.54	28.72	20.28	8.44	3.402 CC, ES, SF	
1,300.00	1,294.31	1,292.25	1,287.02	4.58	4.61	61.903	-64.38	-53.51	32.29	23.42	8.87	3.640	
1,400.00	1,390.18	1,388.28	1,380.58	5.03	5.03	93.024	-66.00	-75.12	49.36	39.58	9.79	5.045	
1,500.00	1,484.43	1,483.20	1,473.05	5.53	5.46	109.747	-67.61	-96.48	74.97	64.24	10.74	6.982	
1,600.00	1,577.16	1,577.01	1,564.44	6.09	5.89	119.857	-69.20	-117.59	105.85	94.18	11.67	9.071	
1,700.00	1,669.73	1,670.70	1,655.71	6.69	6.33	125.728	-70.79	-138.67	138.75	126.17	12.58	11.028	
1,800.00	1,762.30	1,764.39	1,746.99	7.30	6.78	129.350	-72.38	-159.75	172.47	158.97	13.50	12.777	
1,900.00	1,854.86	1,858.08	1,838.26	7.94	7.23	131.790	-73.97	-180.83	206.60	192.18	14.42	14.326	
2,000.00	1,947.43	1,951.77	1,929.53	8.59	7.69	133.539	-75.56	-201.91	240.97	225.62	15.35	15.694	
2,100.00	2,040.00	2,045.46	2,020.80	9.25	8.15	134.853	-77.14	-222.99	275.49	259.20	16.29	16.907	
2,200.00	2,132.56	2,139.14	2,112.07	9.92	8.62	135.874	-78.73	-244.07	310.11	292.87	17.24	17.985	
2,300.00	2,225.13	2,232.83	2,203.35	10.59	9.09	136.691	-80.32	-265.16	344.80	326.60	18.20	18.948	
2,400.00	2,317.70	2,326.52	2,294.62	11.27	9.56	137.358	-81.91	-286.24	379.54	360.38	19.16	19.813	
2,500.00	2,410.26	2,420.21	2,385.89	11.96	10.03	137.913	-83.50	-307.32	414.31	394.19	20.12	20.591	
2,600.00	2,502.83	2,513.90	2,477.16	12.65	10.50	138.383	-85.09	-328.40	449.12	428.03	21.09	21.296	
2,700.00	2,595.40	2,607.59	2,568.44	13.34	10.98	138.785	-86.67	-349.48	483.95	461.89	22.06	21.935	
2,800.00	2,687.97	2,701.28	2,659.71	14.04	11.45	139.133	-88.26	-370.56	518.80	495.76	23.04	22.519	
2,900.00	2,780.53	2,794.97	2,750.98	14.74	11.93	139.438	-89.85	-391.64	553.66	529.64	24.02	23.052	
3,000.00	2,873.10	2,888.65	2,842.25	15.44	12.41	139.706	-91.44	-412.72	588.53	563.53	25.00	23.542	
3,100.00	2,965.67	2,982.34	2,933.53	16.14	12.89	139.944	-93.03	-433.80	623.41	597.43	25.98	23.993	
3,200.00	3,058.23	3,076.03	3,024.80	16.85	13.37	140.157	-94.62	-454.89	658.31	631.34	26.97	24.410	
3,300.00	3,150.80	3,169.72	3,116.07	17.56	13.85	140.349	-96.20	-475.97	693.20	665.25	27.96	24.795	
3,400.00	3,243.37	3,267.45	3,211.42	18.26	14.34	140.580	-97.82	-497.36	727.99	699.01	28.98	25.124	
3,500.00	3,335.96	3,369.90	3,312.28	18.97	14.81	141.271	-99.16	-515.18	761.80	731.83	29.97	25.418	
3,600.00	3,429.78	3,473.36	3,414.96	19.64	15.23	142.625	-100.10	-527.68	792.09	761.23	30.87	25.660	
3,700.00	3,525.28	3,577.92	3,519.28	20.24	15.60	143.957	-100.63	-534.67	817.49	785.82	31.66	25.817	
3,800.00	3,622.21	3,680.87	3,622.21	20.79	15.91	145.256	-100.74	-536.17	837.98	805.64	32.34	25.908	
3,900.00	3,720.28	4,903.01	4,367.01	21.26	20.80	-159.838	-575.66	7.98	815.50	787.43	28.07	29.050	
4,000.00	3,819.24	4,909.25	4,366.97	21.67	20.88	-158.249	-579.98	12.49	748.31	717.98	30.33	24.670	
4,100.00	3,918.81	4,912.97	4,366.94	22.01	20.94	-156.931	-582.56	15.17	685.09	652.44	32.65	20.982	
4,200.00	4,018.73	4,914.12	4,366.93	22.29	20.95	-155.958	-583.35	15.99	627.27	592.36	34.90	17.972	
4,300.00	4,118.72	4,913.41	4,366.94	22.51	20.94	44.116	-582.86	15.48	577.90	541.00	36.90	15.662	
4,400.00	4,218.72	4,911.92	4,366.95	22.72	20.92	95.907	-581.82	14.41	542.57	504.22	38.35	14.148	
4,500.00	4,317.72	4,895.10	4,367.06	22.90	20.69	95.836	-570.20	2.26	525.37	486.84	38.54	13.633	
4,538.50	4,354.99	4,883.06	4,367.14	22.95	20.53	94.704	-561.91	-6.49	523.97	485.79	38.18	13.724	
4,600.00	4,412.93	4,857.55	4,367.30	23.03	20.19	91.749	-544.49	-25.11	527.33	490.15	37.18	14.183	
4,700.00	4,501.46	4,800.31	4,367.67	23.11	19.47	84.517	-506.01	-67.48	544.80	510.12	34.69	15.705	
4,800.00	4,580.62	4,738.15	4,367.75	23.14	18.78	76.606	-465.14	-114.31	571.65	539.62	32.04	17.843	
4,900.00	4,648.00	4,690.15	4,364.44	23.13	18.32	69.881	-433.84	-150.54	604.62	574.76	29.86	20.252	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (100,118,119,121,122 & 123) - Ponderosa J06 2309 FED COM 121H - Original Hole - rev1												Offset Site Error:	0.00 ft
Survey Program: 0-MWD												Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (ft)	Separation Factor	Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)			
5,000.00	4,701.55	4,650.00	4,358.61	23.11	17.99	63.929	-407.88	-180.59	640.86	612.57	28.29	22.652	
5,100.00	4,739.66	4,600.00	4,347.48	23.10	17.67	58.106	-376.02	-217.47	677.39	650.24	27.16	24.945	
5,200.00	4,761.15	4,550.00	4,332.14	23.14	17.45	53.213	-344.93	-253.47	712.18	685.54	26.64	26.735	
5,300.00	4,766.10	4,500.00	4,312.72	23.34	17.30	50.073	-314.82	-288.33	743.91	717.25	26.66	27.903	
5,400.00	4,766.63	4,450.00	4,289.35	23.79	17.20	49.107	-285.94	-321.77	777.46	750.60	26.87	28.937	
5,500.00	4,767.15	4,400.00	4,262.23	24.60	17.13	47.978	-258.49	-353.54	815.05	787.93	27.11	30.060	
5,600.00	4,767.68	4,370.58	4,244.59	25.73	17.10	47.383	-243.10	-371.36	856.45	828.61	27.84	30.766	
5,700.00	4,768.21	4,350.00	4,231.55	27.08	17.08	46.614	-232.70	-383.40	903.55	874.80	28.75	31.425	
5,800.00	4,768.73	4,300.00	4,197.54	28.61	17.04	44.702	-208.75	-411.12	955.87	926.81	29.06	32.892	
5,900.00	4,769.26	4,277.49	4,181.22	30.26	17.03	43.829	-198.62	-422.85	1,013.47	983.58	29.89	33.906	
6,000.00	4,769.79	4,250.00	4,160.48	31.99	17.00	42.761	-186.83	-436.50	1,075.68	1,045.11	30.56	35.195	
6,100.00	4,770.32	4,229.53	4,144.48	33.80	16.99	41.967	-178.48	-446.17	1,141.92	1,110.63	31.29	36.500	
6,200.00	4,770.84	4,200.00	4,120.63	35.67	16.96	40.829	-167.11	-459.33	1,211.81	1,180.01	31.80	38.109	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (100,118,119,121,122 & 123) - Ponderosa J06 2309 FED COM 123H - Original Hole - rev1												Offset Site Error:	0.00 ft
Survey Program: 0-MWD												Offset Well Error:	0.00 ft
Reference	Offset	Semi Major Axis	Highside	Rule Assigned:		Distance		Warning					
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Toolface (°)	+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	
0.00	0.00	0.00	0.00	0.00	0.00	171.619	-40.04	5.90	40.47				
100.00	100.00	100.00	100.00	0.27	0.27	171.619	-40.04	5.90	40.47	39.93	0.55	73.796	
200.00	200.00	200.00	200.00	0.63	0.63	171.619	-40.04	5.90	40.47	39.21	1.27	31.985	
300.00	300.00	300.00	300.00	0.99	0.99	171.619	-40.04	5.90	40.47	38.49	1.98	20.417	
400.00	400.00	400.00	400.00	1.35	1.35	171.619	-40.04	5.90	40.47	37.78	2.70	14.994	
500.00	500.00	500.00	500.00	1.71	1.71	171.619	-40.04	5.90	40.47	37.06	3.42	11.848	
600.00	600.00	600.00	600.00	2.07	2.07	171.619	-40.04	5.90	40.47	36.34	4.13	9.793	
700.00	700.00	700.00	700.00	2.43	2.43	171.619	-40.04	5.90	40.47	35.62	4.85	8.345	
800.00	800.00	800.00	800.00	2.78	2.78	171.619	-40.04	5.90	40.47	34.91	5.57	7.270	
900.00	899.95	899.95	899.95	3.13	3.14	-30.243	-40.04	5.90	38.19	31.92	6.27	6.094	
1,000.00	999.63	999.63	999.63	3.46	3.50	-37.523	-40.04	5.90	31.66	24.70	6.96	4.550	
1,100.00	1,098.77	1,098.77	1,098.77	3.80	3.85	-58.103	-40.04	5.90	22.71	15.05	7.66	2.966	
1,169.44	1,167.14	1,167.14	1,167.14	4.06	4.10	-89.998	-40.04	5.90	19.22	11.06	8.16	2.355 CC, ES, SF	
1,200.00	1,197.08	1,197.08	1,197.08	4.17	4.21	-107.284	-40.04	5.90	20.16	11.79	8.38	2.407	
1,300.00	1,294.31	1,292.66	1,292.63	4.58	4.55	-146.966	-38.10	7.02	37.28	28.22	9.06	4.115	
1,400.00	1,390.18	1,383.79	1,383.50	5.03	4.88	-161.275	-32.39	10.32	70.03	60.33	9.70	7.216	
1,500.00	1,484.43	1,469.40	1,468.51	5.53	5.19	-166.916	-23.61	15.38	113.32	103.01	10.31	10.992	
1,600.00	1,577.16	1,554.20	1,552.32	6.09	5.49	-170.183	-12.09	21.17	163.83	152.89	10.94	14.979	
1,700.00	1,669.73	1,641.12	1,638.18	6.69	5.82	-173.183	1.11	23.76	214.73	203.15	11.58	18.545	
1,800.00	1,762.30	1,727.77	1,723.61	7.30	6.15	-176.000	15.50	22.60	265.55	253.32	12.23	21.722	
1,900.00	1,854.86	1,813.81	1,808.10	7.94	6.48	-178.710	30.98	17.77	316.50	303.63	12.87	24.588	
2,000.00	1,947.43	1,898.87	1,891.21	8.59	6.82	178.741	47.29	9.81	367.80	354.28	13.52	27.203	
2,100.00	2,040.00	1,983.63	1,973.93	9.25	7.16	176.735	63.69	1.40	419.52	405.34	14.18	29.587	
2,200.00	2,132.56	2,068.38	2,056.66	9.92	7.51	175.164	80.08	-7.00	471.55	456.69	14.85	31.748	
2,300.00	2,225.13	2,153.14	2,139.39	10.59	7.87	173.902	96.48	-15.41	523.78	508.25	15.54	33.714	
2,400.00	2,317.70	2,237.89	2,222.12	11.27	8.23	172.867	112.88	-23.81	576.17	559.94	16.23	35.504	
2,500.00	2,410.26	2,322.65	2,304.84	11.96	8.61	172.003	129.27	-32.21	628.67	611.74	16.93	37.139	
2,600.00	2,502.83	2,407.40	2,387.57	12.65	8.98	171.271	145.67	-40.62	681.26	663.63	17.63	38.635	
2,700.00	2,595.40	2,492.15	2,470.30	13.34	9.36	170.644	162.07	-49.02	733.92	715.58	18.34	40.007	
2,800.00	2,687.97	2,576.91	2,553.03	14.04	9.75	170.100	178.46	-57.43	786.64	767.58	19.06	41.268	
2,900.00	2,780.53	2,661.66	2,635.75	14.74	10.13	169.624	194.86	-65.83	839.40	819.62	19.78	42.430	
3,000.00	2,873.10	2,746.42	2,718.48	15.44	10.52	169.205	211.26	-74.24	892.20	871.69	20.51	43.504	
3,100.00	2,965.67	2,831.17	2,801.21	16.14	10.92	168.832	227.65	-82.64	945.02	923.79	21.24	44.499	
3,200.00	3,058.23	2,915.93	2,883.94	16.85	11.31	168.498	244.05	-91.05	997.88	975.91	21.97	45.423	
3,300.00	3,150.80	3,000.68	2,966.66	17.56	11.71	168.198	260.44	-99.45	1,050.76	1,028.05	22.70	46.282	
3,400.00	3,243.37	3,085.44	3,049.39	18.26	12.11	167.927	276.84	-107.86	1,103.65	1,080.21	23.44	47.082	
3,500.00	3,335.96	3,170.23	3,132.15	18.97	12.51	167.745	293.24	-116.27	1,156.50	1,132.32	24.18	47.829	
3,600.00	3,429.78	3,256.69	3,216.55	19.64	12.92	167.845	309.97	-124.84	1,206.49	1,181.57	24.92	48.411	
3,700.00	3,525.28	3,367.25	3,324.55	20.24	13.44	167.800	330.98	-135.61	1,251.85	1,225.99	25.87	48.399	
4,400.00	4,218.72	5,364.49	4,762.59	22.72	22.73	97.579	-166.16	447.72	1,247.03	1,209.35	37.68	33.092	
4,500.00	4,317.72	5,352.27	4,762.67	22.90	22.56	101.095	-157.52	439.08	1,208.49	1,169.88	38.61	31.302	
4,600.00	4,412.93	5,301.85	4,763.00	23.03	21.86	101.658	-122.13	403.16	1,179.70	1,140.96	38.74	30.452	
4,700.00	4,501.46	5,224.87	4,763.50	23.11	20.88	100.251	-69.34	347.14	1,160.09	1,121.80	38.29	30.299	
4,800.00	4,580.62	5,125.30	4,763.95	23.14	19.75	97.574	-3.30	272.63	1,147.69	1,110.26	37.43	30.659	
4,900.00	4,648.00	5,035.58	4,755.24	23.13	18.89	94.917	55.03	205.13	1,140.73	1,103.91	36.82	30.983	
4,983.15	4,693.58	4,969.47	4,739.95	23.11	18.37	92.671	97.05	156.50	1,138.97	1,102.45	36.52	31.186	
5,000.00	4,701.55	4,956.75	4,736.17	23.11	18.28	92.207	104.99	147.31	1,139.04	1,102.58	36.46	31.237	
5,100.00	4,739.66	4,884.68	4,709.71	23.10	17.86	89.376	148.79	96.62	1,142.16	1,105.79	36.37	31.401	
5,200.00	4,761.15	4,817.05	4,677.42	23.14	17.57	86.438	187.61	51.69	1,149.33	1,112.79	36.54	31.453	
5,300.00	4,766.10	4,750.00	4,638.72	23.34	17.37	83.688	223.38	10.30	1,159.55	1,122.63	36.92	31.404	
5,400.00	4,766.63	4,700.00	4,605.84	23.79	17.27	82.084	248.00	-18.19	1,171.28	1,133.73	37.54	31.197	
5,500.00	4,767.15	4,650.00	4,569.81	24.60	17.20	80.351	270.65	-44.40	1,184.81	1,146.60	38.21	31.006	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design:	Ponderosa (100,118,119,121,122 & 123) - Ponderosa J06 2309 FED COM 123H - Original Hole - rev1											Offset Site Error:	0.00 ft
Survey Program:	0-MWD											Offset Well Error:	0.00 ft
Reference	Offset	Rule Assigned:										Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	
5,600.00	4,767.68	4,610.09	4,538.97	25.73	17.14	78.891	287.20	-63.56	1,200.87	1,161.94	38.93	30.843	
5,700.00	4,768.21	4,576.65	4,511.82	27.08	17.10	77.585	299.96	-78.33	1,222.07	1,182.40	39.67	30.806	
5,800.00	4,768.73	4,550.00	4,489.40	28.61	17.07	76.516	309.37	-89.22	1,249.55	1,209.15	40.40	30.931	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (100,118,119,121,122 & 123) - Ponderosa J06 2309 FED COM 118H - Original Hole - rev1												Offset Site Error:	0.00 ft
Survey Program: 0-MWD												Offset Well Error:	0.00 ft
Reference	Offset	Semi Major Axis	Highside	Rule Assigned:				Warning					
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Toolface (°)	+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	
0.00	0.00	0.00	0.00	0.00	0.00	171.619	-20.02	2.95	20.24				
100.00	100.00	100.00	100.00	0.27	0.27	171.619	-20.02	2.95	20.24	19.69	0.55	36.898	
200.00	200.00	200.00	200.00	0.63	0.63	171.619	-20.02	2.95	20.24	18.97	1.27	15.993	
300.00	300.00	300.00	300.00	0.99	0.99	171.619	-20.02	2.95	20.24	18.25	1.98	10.209	
400.00	400.00	400.00	400.00	1.35	1.35	171.619	-20.02	2.95	20.24	17.54	2.70	7.497	
500.00	500.00	500.00	500.00	1.71	1.71	171.619	-20.02	2.95	20.24	16.82	3.42	5.924 CC, ES	
600.00	600.00	599.50	599.46	2.07	2.05	178.036	-21.36	0.73	21.38	17.26	4.12	5.191	
700.00	700.00	698.46	698.11	2.43	2.40	-166.975	-25.35	-5.87	26.09	21.28	4.81	5.420	
800.00	800.00	796.37	795.18	2.78	2.75	-152.389	-31.90	-16.69	36.32	30.82	5.50	6.606	
900.00	899.95	893.10	890.33	3.13	3.13	18.448	-40.89	-31.54	50.09	43.95	6.14	8.158	
1,000.00	999.63	988.76	983.44	3.46	3.55	27.231	-52.22	-50.27	65.11	58.37	6.74	9.655	
1,100.00	1,098.77	1,083.23	1,074.21	3.80	4.01	34.712	-65.76	-72.65	81.77	74.42	7.34	11.136	
1,200.00	1,197.08	1,176.97	1,162.90	4.17	4.51	41.195	-81.47	-98.61	100.35	92.38	7.97	12.597	
1,300.00	1,294.31	1,274.56	1,254.61	4.58	5.09	47.369	-98.72	-127.13	118.30	109.55	8.74	13.532	
1,400.00	1,390.18	1,372.21	1,346.39	5.03	5.68	53.535	-116.00	-155.68	134.27	124.65	9.62	13.955	
1,500.00	1,484.43	1,469.67	1,437.99	5.53	6.29	59.949	-133.23	-184.17	148.98	138.35	10.63	14.015	
1,600.00	1,577.16	1,566.78	1,529.25	6.09	6.91	66.644	-150.41	-212.56	163.69	151.91	11.78	13.891	
1,700.00	1,669.73	1,663.84	1,620.47	6.69	7.54	72.461	-167.57	-240.93	180.24	167.22	13.02	13.839	
1,800.00	1,762.30	1,760.90	1,711.69	7.30	8.17	77.286	-184.74	-269.30	198.33	184.02	14.31	13.859	
1,900.00	1,854.86	1,857.97	1,802.91	7.94	8.81	81.299	-201.90	-297.67	217.59	201.96	15.62	13.927	
2,000.00	1,947.43	1,955.03	1,894.13	8.59	9.46	84.659	-219.07	-326.05	237.72	220.77	16.95	14.026	
2,100.00	2,040.00	2,052.09	1,985.35	9.25	10.11	87.495	-236.24	-354.42	258.52	240.24	18.28	14.142	
2,200.00	2,132.56	2,149.15	2,076.57	9.92	10.76	89.908	-253.40	-382.79	279.85	260.24	19.61	14.268	
2,300.00	2,225.13	2,246.21	2,167.80	10.59	11.41	91.981	-270.57	-411.16	301.59	280.64	20.95	14.396	
2,400.00	2,317.70	2,343.27	2,259.02	11.27	12.06	93.776	-287.74	-439.54	323.66	301.38	22.28	14.525	
2,500.00	2,410.26	2,440.34	2,350.24	11.96	12.72	95.343	-304.90	-467.91	345.99	322.38	23.62	14.650	
2,600.00	2,502.83	2,537.40	2,441.46	12.65	13.38	96.720	-322.07	-496.28	368.55	343.60	24.95	14.772	
2,700.00	2,595.40	2,634.46	2,532.68	13.34	14.04	97.938	-339.23	-524.65	391.28	365.00	26.28	14.889	
2,800.00	2,687.97	2,731.52	2,623.90	14.04	14.70	99.024	-356.40	-553.03	414.16	386.55	27.61	15.000	
2,900.00	2,780.53	2,828.58	2,715.12	14.74	15.36	99.996	-373.57	-581.40	437.17	408.23	28.94	15.106	
3,000.00	2,873.10	2,925.64	2,806.34	15.44	16.02	100.870	-390.73	-609.77	460.29	430.02	30.27	15.207	
3,100.00	2,965.67	3,022.71	2,897.56	16.14	16.68	101.662	-407.90	-638.14	483.50	451.90	31.60	15.303	
3,200.00	3,058.23	3,119.77	2,988.79	16.85	17.34	102.381	-425.06	-666.52	506.79	473.87	32.92	15.394	
3,300.00	3,150.80	3,216.83	3,080.01	17.56	18.01	103.037	-442.23	-694.89	530.15	495.90	34.25	15.480	
3,400.00	3,243.37	3,313.89	3,171.23	18.26	18.67	103.638	-459.40	-723.26	553.57	517.99	35.57	15.561	
3,500.00	3,335.96	3,410.96	3,262.46	18.97	19.34	104.300	-476.56	-751.64	577.02	540.12	36.90	15.639	
3,600.00	3,429.78	3,508.33	3,353.97	19.64	20.00	105.153	-493.78	-780.10	599.67	561.49	38.18	15.707	
3,700.00	3,525.28	3,609.55	3,449.17	20.24	20.69	105.473	-511.57	-809.51	620.92	581.48	39.44	15.745	
3,800.00	3,622.21	3,721.75	3,556.21	20.79	21.39	105.576	-528.95	-838.23	639.26	598.55	40.71	15.704	
3,900.00	3,720.28	3,835.34	3,666.40	21.26	22.00	105.628	-543.20	-861.78	654.02	612.19	41.83	15.636	
4,000.00	3,819.24	3,950.05	3,779.14	21.67	22.53	105.627	-554.13	-879.84	665.11	622.32	42.79	15.542	
4,100.00	3,918.81	4,065.63	3,893.80	22.01	22.97	105.574	-561.57	-892.14	672.47	628.87	43.60	15.425	
4,200.00	4,018.73	4,181.77	4,009.68	22.29	23.32	105.466	-565.42	-898.50	676.05	631.81	44.24	15.282	
4,300.00	4,118.72	5,346.50	4,746.34	22.51	24.19	-139.027	-1,016.88	-399.35	632.52	617.02	15.50	40.810	
4,400.00	4,218.72	5,345.33	4,746.35	22.72	24.19	-104.412	-1,016.07	-400.19	533.44	518.00	15.44	34.549	
4,500.00	4,317.72	5,331.96	4,746.43	22.90	24.18	-139.249	-1,006.83	-409.86	435.64	420.34	15.31	28.460	
4,600.00	4,412.93	5,302.10	4,746.62	23.03	24.18	-149.038	-986.38	-431.61	342.03	326.93	15.10	22.652	
4,700.00	4,501.46	5,256.58	4,746.90	23.11	24.17	-150.990	-955.63	-465.17	255.83	240.86	14.97	17.094	
4,800.00	4,580.62	5,173.65	4,742.38	23.14	24.19	-143.545	-900.36	-526.75	177.01	160.96	16.05	11.027	
4,900.00	4,648.00	5,098.02	4,727.93	23.13	24.22	-127.308	-850.83	-581.97	105.12	85.31	19.81	5.307	
5,000.00	4,701.55	5,029.52	4,706.51	23.11	24.24	-91.906	-807.40	-630.36	60.64	26.18	34.46	1.760 Level 3<2.00	
5,012.17	4,707.04	5,021.52	4,703.51	23.10	24.24	-86.227	-802.45	-635.88	59.95	23.18	36.76	1.631 Level 3<2.00, SF	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (100,118,119,121,122 & 123) - Ponderosa J06 2309 FED COM 118H - Original Hole - rev1													Offset Site Error:	0.00 ft
Survey Program: 0-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Rule Assigned:		Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
5,100.00	4,739.66	4,965.38	4,679.56	23.10	24.25	-49.569	-768.56	-673.65	87.84	54.77	33.07	2.656		
5,200.00	4,761.15	4,900.00	4,645.57	23.14	24.25	-27.162	-731.29	-715.19	145.96	115.13	30.83	4.734		
5,300.00	4,766.10	4,850.00	4,615.41	23.34	24.24	-18.711	-704.67	-744.86	206.25	172.05	34.20	6.031		
5,400.00	4,766.63	4,800.00	4,581.89	23.79	24.22	-13.506	-679.90	-772.46	272.88	236.20	36.68	7.439		
5,500.00	4,767.15	4,750.00	4,545.27	24.60	24.20	-9.376	-657.18	-797.78	346.26	308.04	38.22	9.061		
5,600.00	4,767.68	4,712.38	4,515.84	25.73	24.18	-6.665	-641.54	-815.22	424.79	384.85	39.95	10.634		
5,700.00	4,768.21	4,680.90	4,490.07	27.08	24.15	-6.246	-629.47	-828.67	506.97	465.63	41.34	12.264		
5,800.00	4,768.73	4,650.00	4,463.85	28.61	24.13	-5.872	-618.56	-840.83	591.97	549.68	42.29	13.998		
5,900.00	4,769.26	4,630.71	4,447.05	30.26	24.11	-5.655	-612.23	-847.89	679.14	635.86	43.28	15.691		
6,000.00	4,769.79	4,600.00	4,419.67	31.99	24.08	-5.333	-602.94	-858.24	768.29	724.56	43.73	17.568		
6,100.00	4,770.32	4,600.00	4,419.67	33.80	24.08	-5.333	-602.94	-858.24	858.64	813.99	44.65	19.229		
6,200.00	4,770.84	4,577.33	4,399.01	35.67	24.05	-5.111	-596.72	-865.17	950.21	905.23	44.98	21.125		
6,300.00	4,771.37	4,550.00	4,373.63	37.58	24.02	-4.861	-589.96	-872.71	1,043.09	997.91	45.18	23.089		
6,400.00	4,771.90	4,550.00	4,373.63	39.53	24.02	-4.861	-589.96	-872.71	1,136.30	1,090.64	45.66	24.887		
6,500.00	4,772.42	4,550.00	4,373.63	41.52	24.02	-4.861	-589.96	-872.71	1,230.59	1,184.55	46.03	26.733		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (100,118,119,121,122 & 123) - Ponderosa Unit 122H - Original Hole - rev0												Offset Site Error:	0.00 ft
Survey Program: 0-MWD												Offset Well Error:	0.00 ft
Reference	Offset	Rule Assigned:										Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	
0.00	0.00	0.00	0.00	0.00	0.00	-8.040	39.68	-5.60	40.07				
100.00	100.00	100.00	100.00	0.27	0.27	-8.040	39.68	-5.60	40.07	39.52	0.55	73.063	
200.00	200.00	200.00	200.00	0.63	0.63	-8.040	39.68	-5.60	40.07	38.81	1.27	31.667	
300.00	300.00	300.00	300.00	0.99	0.99	-8.040	39.68	-5.60	40.07	38.09	1.98	20.214	
400.00	400.00	400.00	400.00	1.35	1.35	-8.040	39.68	-5.60	40.07	37.37	2.70	14.845	
500.00	500.00	500.00	500.00	1.71	1.71	-8.040	39.68	-5.60	40.07	36.66	3.42	11.730	
600.00	600.00	600.00	600.00	2.07	2.07	-8.040	39.68	-5.60	40.07	35.94	4.13	9.695	
700.00	700.00	700.00	700.00	2.43	2.43	-8.040	39.68	-5.60	40.07	35.22	4.85	8.262	
800.00	800.00	800.00	800.00	2.78	2.78	-8.040	39.68	-5.60	40.07	34.51	5.57	7.198 CC, ES	
900.00	899.95	900.48	900.43	3.13	3.13	157.131	39.24	-3.00	41.75	35.49	6.26	6.670	
1,000.00	999.63	999.98	999.62	3.46	3.48	169.818	37.92	4.71	48.47	41.53	6.94	6.985	
1,100.00	1,098.77	1,097.59	1,096.38	3.80	3.83	-176.349	35.80	17.21	63.21	55.57	7.63	8.281	
1,200.00	1,197.08	1,192.44	1,189.69	4.17	4.20	-165.643	32.94	34.01	87.13	78.81	8.32	10.467	
1,300.00	1,294.31	1,285.77	1,280.78	4.58	4.58	-158.635	29.54	54.01	119.26	110.23	9.03	13.209	
1,400.00	1,390.18	1,378.17	1,370.91	5.03	4.98	-155.033	26.13	74.07	156.83	147.08	9.76	16.074	
1,500.00	1,484.43	1,468.79	1,459.31	5.53	5.38	-153.241	22.79	93.74	198.95	188.45	10.51	18.939	
1,600.00	1,577.16	1,557.77	1,546.11	6.09	5.78	-152.706	19.51	113.05	244.57	233.31	11.27	21.710	
1,700.00	1,669.73	1,646.58	1,632.73	6.69	6.19	-152.577	16.23	132.32	290.55	278.52	12.03	24.155	
1,800.00	1,762.30	1,735.38	1,719.36	7.30	6.61	-152.484	12.95	151.60	336.52	323.71	12.81	26.274	
1,900.00	1,854.86	1,824.18	1,805.98	7.94	7.03	-152.413	9.67	170.87	382.50	368.89	13.60	28.120	
2,000.00	1,947.43	1,912.99	1,892.61	8.59	7.46	-152.357	6.40	190.15	428.47	414.06	14.41	29.738	
2,100.00	2,040.00	2,001.79	1,979.23	9.25	7.89	-152.312	3.12	209.42	474.45	459.22	15.22	31.164	
2,200.00	2,132.56	2,090.60	2,065.86	9.92	8.32	-152.275	-0.16	228.70	520.42	504.37	16.05	32.429	
2,300.00	2,225.13	2,179.40	2,152.48	10.59	8.76	-152.244	-3.43	247.97	566.40	549.52	16.88	33.556	
2,400.00	2,317.70	2,268.20	2,239.11	11.27	9.20	-152.217	-6.71	267.25	612.37	594.66	17.72	34.565	
2,500.00	2,410.26	2,357.01	2,325.73	11.96	9.64	-152.195	-9.99	286.52	658.35	639.79	18.56	35.473	
2,600.00	2,502.83	2,445.81	2,412.36	12.65	10.08	-152.175	-13.26	305.80	704.33	684.92	19.41	36.294	
2,700.00	2,595.40	2,534.62	2,498.98	13.34	10.52	-152.158	-16.54	325.07	750.30	730.04	20.26	37.038	
2,800.00	2,687.97	2,625.69	2,587.83	14.04	10.98	-152.143	-19.90	344.82	796.27	775.13	21.13	37.680	
2,900.00	2,780.53	2,745.29	2,705.35	14.74	11.53	-152.390	-23.60	366.60	840.37	818.13	22.23	37.799	
3,000.00	2,873.10	2,868.45	2,827.56	15.44	12.03	-153.061	-26.12	381.40	881.16	857.88	23.27	37.864	
3,100.00	2,965.67	2,994.27	2,953.16	16.14	12.47	-154.115	-27.32	388.47	918.61	894.38	24.23	37.909	
3,200.00	3,058.23	3,099.34	3,058.23	16.85	12.79	-155.198	-27.41	389.02	953.50	928.50	25.00	38.135	
3,300.00	3,150.80	3,191.91	3,150.80	17.56	13.06	-156.107	-27.41	389.02	988.40	962.69	25.70	38.453	
3,400.00	3,243.37	3,284.48	3,243.37	18.26	13.34	-156.956	-27.41	389.02	1,023.50	997.10	26.40	38.762	
3,500.00	3,335.96	3,377.07	3,335.96	18.97	13.62	-157.818	-27.41	389.02	1,058.73	1,031.63	27.10	39.061	
3,600.00	3,429.78	3,470.89	3,429.78	19.64	13.91	-158.872	-27.41	389.02	1,091.13	1,063.33	27.80	39.250	
3,700.00	3,525.28	3,566.40	3,525.28	20.24	14.20	-159.719	-27.41	389.02	1,118.99	1,090.50	28.49	39.280	
3,800.00	3,622.21	3,663.32	3,622.21	20.79	14.50	-160.387	-27.41	389.02	1,142.17	1,113.00	29.17	39.156	
3,900.00	3,720.28	3,761.39	3,720.28	21.26	14.81	-160.893	-27.41	389.02	1,160.58	1,130.74	29.84	38.890	
4,000.00	3,819.24	3,860.35	3,819.24	21.67	15.12	-161.254	-27.41	389.02	1,174.13	1,143.63	30.50	38.491	
4,100.00	3,918.81	3,959.92	3,918.81	22.01	15.43	-161.479	-27.41	389.02	1,182.77	1,151.62	31.15	37.967	
4,200.00	4,018.73	4,059.84	4,018.73	22.29	15.75	-161.573	-27.41	389.02	1,186.46	1,154.67	31.79	37.327	
4,300.00	4,118.72	4,159.84	4,118.72	22.51	16.07	38.386	-27.41	389.02	1,186.61	1,154.21	32.39	36.635	
4,378.97	4,197.68	4,238.51	4,197.40	22.68	16.32	89.622	-27.40	389.00	1,186.60	1,153.73	32.87	36.100	
4,400.00	4,218.72	4,258.20	4,217.08	22.72	16.38	89.556	-27.09	388.64	1,186.62	1,153.64	32.98	35.980	
4,500.00	4,317.72	4,351.85	4,309.91	22.90	16.63	89.566	-19.64	379.85	1,186.92	1,153.47	33.45	35.481	
4,600.00	4,412.93	4,445.70	4,399.82	23.03	16.83	89.586	-2.49	359.60	1,187.62	1,153.81	33.82	35.119	
4,700.00	4,501.46	4,539.90	4,484.51	23.11	17.01	89.615	24.04	328.30	1,188.70	1,154.58	34.12	34.837	
4,800.00	4,580.62	4,634.62	4,561.72	23.14	17.18	89.655	59.38	286.60	1,190.14	1,155.69	34.45	34.546	
4,900.00	4,648.00	4,729.98	4,629.32	23.13	17.40	89.703	102.77	235.40	1,191.90	1,156.98	34.92	34.132	
5,000.00	4,701.55	4,826.14	4,685.26	23.11	17.74	89.759	153.25	175.84	1,193.93	1,158.26	35.67	33.474	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (100,118,119,121,122 & 123) - Ponderosa Unit 122H - Original Hole - rev0												Offset Site Error:	0.00 ft
Survey Program: 0-MWD												Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (ft)	Separation Factor	Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)			
5,100.00	4,739.66	4,923.23	4,727.71	23.10	18.28	89.822	209.61	109.33	1,196.18	1,159.37	36.81	32.498	
5,200.00	4,761.15	5,021.35	4,755.06	23.14	19.07	89.891	270.46	37.53	1,198.60	1,160.20	38.40	31.215	
5,300.00	4,766.10	5,120.63	4,765.99	23.34	20.07	90.000	334.17	-37.65	1,200.96	1,160.56	40.40	29.727	
5,400.00	4,766.63	5,200.00	4,766.58	23.79	21.00	89.997	386.12	-97.66	1,201.76	1,159.30	42.46	28.305	
5,500.00	4,767.15	5,264.50	4,766.99	24.60	21.85	89.990	429.54	-145.35	1,201.47	1,156.95	44.53	26.983	
5,600.00	4,767.68	5,334.96	4,767.43	25.73	22.84	89.985	478.18	-196.32	1,200.24	1,153.41	46.83	25.629	
5,660.68	4,768.00	5,382.35	4,767.73	26.52	23.53	89.987	511.56	-229.95	1,199.99	1,151.64	48.36	24.816	
5,700.00	4,768.21	5,421.67	4,767.97	27.08	24.14	89.989	539.37	-257.76	1,199.99	1,150.38	49.62	24.184	
5,800.00	4,768.73	5,521.67	4,768.60	28.61	25.75	89.994	610.07	-328.47	1,199.99	1,147.12	52.88	22.694	
5,900.00	4,769.26	5,621.67	4,769.23	30.26	27.46	89.999	680.78	-399.18	1,199.99	1,143.67	56.32	21.306	
6,000.00	4,769.79	5,721.67	4,769.86	31.99	29.25	90.003	751.49	-469.89	1,199.99	1,140.08	59.92	20.027	
6,100.00	4,770.32	5,821.67	4,770.49	33.80	31.11	90.008	822.20	-540.60	1,199.99	1,136.35	63.64	18.855	
6,200.00	4,770.84	5,921.67	4,771.11	35.67	33.02	90.013	892.91	-611.31	1,199.99	1,132.52	67.48	17.784	
6,300.00	4,771.37	6,021.67	4,771.74	37.58	34.98	90.018	963.62	-682.02	1,199.99	1,128.59	71.40	16.807	
6,400.00	4,771.90	6,121.67	4,772.37	39.53	36.98	90.023	1,034.33	-752.73	1,199.99	1,124.60	75.40	15.916	
6,500.00	4,772.42	6,221.67	4,773.00	41.52	39.01	90.027	1,105.04	-823.44	1,199.99	1,120.53	79.46	15.102	
6,600.00	4,772.95	6,321.67	4,773.63	43.54	41.07	90.032	1,175.74	-894.15	1,199.99	1,116.42	83.58	14.358	
6,700.00	4,773.48	6,421.67	4,774.25	45.59	43.16	90.037	1,246.45	-964.85	1,199.99	1,112.25	87.74	13.676	
6,800.00	4,774.01	6,521.67	4,774.88	47.66	45.26	90.042	1,317.16	-1,035.56	1,199.99	1,108.05	91.95	13.051	
6,900.00	4,774.53	6,621.67	4,775.51	49.74	47.38	90.047	1,387.87	-1,106.27	1,199.99	1,103.80	96.19	12.476	
7,000.00	4,775.06	6,721.67	4,776.14	51.85	49.52	90.051	1,458.58	-1,176.98	1,199.99	1,099.53	100.46	11.945	
7,100.00	4,775.59	6,821.67	4,776.77	53.97	51.67	90.056	1,529.29	-1,247.69	1,199.99	1,095.24	104.76	11.455	
7,200.00	4,776.12	6,921.67	4,777.39	56.10	53.84	90.061	1,600.00	-1,318.40	1,199.99	1,090.91	109.08	11.001	
7,300.00	4,776.64	7,021.67	4,778.02	58.24	56.01	90.066	1,670.71	-1,389.11	1,199.99	1,086.57	113.42	10.580	
7,400.00	4,777.17	7,121.67	4,778.65	60.40	58.19	90.071	1,741.41	-1,459.82	1,199.99	1,082.21	117.78	10.188	
7,500.00	4,777.70	7,221.67	4,779.28	62.56	60.38	90.075	1,812.12	-1,530.53	1,199.99	1,077.83	122.16	9.823	
7,600.00	4,778.22	7,321.67	4,779.91	64.74	62.58	90.080	1,882.83	-1,601.24	1,199.99	1,073.43	126.56	9.482	
7,700.00	4,778.75	7,421.67	4,780.53	66.92	64.79	90.085	1,953.54	-1,671.95	1,199.99	1,069.03	130.96	9.163	
7,800.00	4,779.28	7,521.67	4,781.16	69.11	67.00	90.090	2,024.25	-1,742.66	1,199.99	1,064.61	135.38	8.864	
7,900.00	4,779.81	7,621.67	4,781.79	71.31	69.22	90.095	2,094.96	-1,813.37	1,199.99	1,060.18	139.81	8.583	
8,000.00	4,780.33	7,721.67	4,782.42	73.51	71.44	90.099	2,165.67	-1,884.08	1,199.99	1,055.73	144.25	8.319	
8,100.00	4,780.86	7,821.67	4,783.04	75.71	73.67	90.104	2,236.38	-1,954.79	1,199.99	1,051.28	148.70	8.070	
8,200.00	4,781.39	7,921.67	4,783.67	77.93	75.90	90.109	2,307.09	-2,025.50	1,199.99	1,046.83	153.16	7.835	
8,300.00	4,781.92	8,021.67	4,784.30	80.14	78.13	90.114	2,377.79	-2,096.21	1,199.99	1,042.36	157.63	7.613	
8,400.00	4,782.44	8,121.67	4,784.93	82.36	80.37	90.119	2,448.50	-2,166.92	1,199.99	1,037.89	162.10	7.403	
8,500.00	4,782.97	8,221.67	4,785.56	84.59	82.61	90.123	2,519.21	-2,237.63	1,199.99	1,033.41	166.58	7.204	
8,600.00	4,783.50	8,321.67	4,786.18	86.82	84.85	90.128	2,589.92	-2,308.34	1,199.99	1,028.92	171.07	7.015	
8,700.00	4,784.02	8,421.67	4,786.81	89.05	87.10	90.133	2,660.63	-2,379.05	1,199.99	1,024.43	175.56	6.835	
8,800.00	4,784.55	8,521.67	4,787.44	91.28	89.35	90.138	2,731.34	-2,449.76	1,199.99	1,019.93	180.05	6.665	
8,900.00	4,785.08	8,621.67	4,788.07	93.52	91.60	90.143	2,802.05	-2,520.47	1,199.99	1,015.43	184.55	6.502	
9,000.00	4,785.61	8,721.67	4,788.70	95.76	93.86	90.147	2,872.76	-2,591.18	1,199.99	1,010.93	189.06	6.347	
9,100.00	4,786.13	8,821.67	4,789.32	98.01	96.11	90.152	2,943.46	-2,661.89	1,199.99	1,006.42	193.57	6.199	
9,200.00	4,786.66	8,921.67	4,789.95	100.25	98.37	90.157	3,014.17	-2,732.60	1,199.99	1,001.91	198.08	6.058	
9,300.00	4,787.19	9,021.67	4,790.58	102.50	100.63	90.162	3,084.88	-2,803.31	1,199.99	997.39	202.60	5.923	
9,400.00	4,787.72	9,121.67	4,791.21	104.75	102.89	90.167	3,155.59	-2,874.02	1,199.99	992.87	207.12	5.794	
9,500.00	4,788.24	9,221.67	4,791.84	107.00	105.15	90.172	3,226.30	-2,944.73	1,199.99	988.35	211.64	5.670	
9,600.00	4,788.77	9,321.67	4,792.46	109.25	107.42	90.176	3,297.01	-3,015.44	1,199.99	983.82	216.17	5.551	
9,700.00	4,789.30	9,421.67	4,793.09	111.51	109.68	90.181	3,367.72	-3,086.15	1,199.99	979.29	220.69	5.437	
9,704.45	4,789.32	9,426.12	4,793.12	111.61	109.78	90.181	3,370.86	-3,089.29	1,199.99	979.09	220.89	5.432	
9,800.00	4,789.82	9,521.67	4,793.72	113.76	111.95	90.186	3,438.43	-3,156.86	1,199.99	974.76	225.22	5.328	
9,900.00	4,790.35	9,621.67	4,794.35	116.02	114.22	90.191	3,509.13	-3,227.57	1,199.99	970.23	229.76	5.223	
10,000.00	4,790.88	9,721.67	4,794.97	118.28	116.48	90.196	3,579.84	-3,298.28	1,199.99	965.70	234.29	5.122 SF	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (100,118,119,121,122 & 123) - Ponderosa Unit 122H - Original Hole - rev0													Offset Site Error:	0.00 ft
Survey Program: 0-MWD													Offset Well Error:	0.00 ft
Reference	Offset	Semi Major Axis		Offset Wellbore Centre		Rule Assigned:			Distance		Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
10,100.00	4,791.41	9,725.70	4,795.00	120.54	116.58	90.196	3,582.70	-3,301.13	1,203.82	969.03	234.79	5.127		
10,200.00	4,791.93	9,725.70	4,795.00	122.80	116.58	90.196	3,582.70	-3,301.13	1,215.88	982.65	233.24	5.213		
10,300.00	4,792.46	9,725.70	4,795.00	125.07	116.58	90.196	3,582.70	-3,301.13	1,235.95	1,006.00	229.95	5.375		
10,400.00	4,792.99	9,725.70	4,795.00	127.33	116.58	90.196	3,582.70	-3,301.13	1,263.63	1,038.44	225.19	5.611		



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (99, 111,112,114-117,120,136) - Ponderosa 099H - Original Hole - rev0													Offset Site Error: 0.00 ft
Survey Program: 0-MWD													Offset Well Error: 0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (ft)	Separation Factor	Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)			
3,100.00	2,965.67	3,716.45	3,520.37	16.14	21.78	34.476	-1,456.35	-1,081.84	1,223.32	1,197.00	26.32	46.470	
3,200.00	3,058.23	3,791.07	3,588.90	16.85	22.35	34.993	-1,444.38	-1,054.83	1,157.25	1,130.17	27.08	42.730	
3,300.00	3,150.80	3,865.69	3,657.43	17.56	22.93	35.572	-1,432.41	-1,027.82	1,091.24	1,063.39	27.84	39.190	
3,400.00	3,243.37	3,940.31	3,725.95	18.26	23.50	36.225	-1,420.43	-1,000.82	1,025.30	996.69	28.61	35.834	
3,500.00	3,335.96	4,000.91	3,781.60	18.97	23.97	36.563	-1,410.71	-978.88	959.59	930.15	29.45	32.588	
3,600.00	3,429.78	4,059.21	3,835.72	19.64	24.39	35.889	-1,399.81	-960.24	897.51	867.20	30.31	29.613	
3,700.00	3,525.28	4,111.29	3,884.78	20.24	24.71	35.602	-1,387.53	-947.85	841.69	810.47	31.22	26.960	
3,800.00	3,622.21	4,165.30	3,935.89	20.79	24.99	35.808	-1,372.36	-939.36	792.91	760.77	32.14	24.670	
3,900.00	3,720.28	4,220.25	3,987.69	21.26	25.23	36.506	-1,354.54	-935.36	752.12	719.06	33.06	22.752	
4,000.00	3,819.24	4,275.07	4,038.69	21.67	25.42	37.666	-1,334.50	-936.05	720.44	686.49	33.95	21.224	
4,100.00	3,918.81	4,328.71	4,087.49	22.01	25.56	39.231	-1,312.90	-941.27	699.02	664.28	34.75	20.118	
4,200.00	4,018.73	4,380.27	4,132.96	22.29	25.67	41.129	-1,290.45	-950.46	688.95	653.57	35.38	19.475	
4,242.40	4,061.12	4,400.00	4,149.92	22.38	25.70	41.974	-1,281.46	-955.04	688.04	652.49	35.55	19.356 CC	
4,300.00	4,118.72	4,428.74	4,174.10	22.51	25.74	-116.788	-1,268.00	-962.77	689.89	654.15	35.74	19.303	
4,400.00	4,218.72	4,473.32	4,210.30	22.72	25.79	-63.212	-1,246.35	-977.16	699.52	663.69	35.82	19.527	
4,500.00	4,317.72	4,517.60	4,244.48	22.90	25.82	-60.195	-1,224.02	-994.27	712.28	676.78	35.49	20.067	
4,600.00	4,412.93	4,562.84	4,277.37	23.03	25.83	-57.564	-1,200.49	-1,014.55	724.77	690.00	34.77	20.845	
4,700.00	4,501.46	4,600.00	4,302.69	23.11	25.84	-55.628	-1,180.74	-1,033.23	735.91	702.36	33.55	21.933	
4,800.00	4,580.62	4,650.00	4,334.16	23.14	25.83	-53.953	-1,153.70	-1,061.10	744.50	711.94	32.56	22.866	
4,900.00	4,648.00	4,700.00	4,362.43	23.13	25.81	-52.941	-1,126.32	-1,091.91	750.10	718.40	31.69	23.669	
5,000.00	4,701.55	4,750.00	4,387.28	23.11	25.77	-52.600	-1,098.80	-1,125.43	752.30	721.12	31.18	24.128	
5,100.00	4,739.66	4,800.00	4,408.54	23.10	25.74	-52.928	-1,071.37	-1,161.41	750.98	719.74	31.25	24.033	
5,200.00	4,761.15	4,850.00	4,426.04	23.14	25.69	-53.913	-1,044.00	-1,199.39	746.05	714.00	32.05	23.275	
5,300.00	4,766.10	4,932.89	4,446.79	23.34	25.63	-55.655	-994.49	-1,262.46	735.35	701.50	33.85	21.726	
5,400.00	4,766.63	5,016.26	4,456.98	23.79	25.57	-56.309	-939.37	-1,324.08	726.74	690.95	35.79	20.308	
5,500.00	4,767.15	5,110.22	4,458.35	24.60	25.50	-56.255	-873.23	-1,390.78	722.78	684.97	37.82	19.114	
5,600.00	4,767.68	5,210.21	4,458.92	25.73	25.43	-56.228	-802.52	-1,461.48	721.83	681.69	40.14	17.981	
5,700.00	4,768.21	5,310.21	4,459.50	27.08	25.44	-56.230	-731.81	-1,532.19	721.80	679.09	42.72	16.898	
5,800.00	4,768.73	5,410.21	4,460.07	28.61	26.42	-56.233	-661.10	-1,602.90	721.78	676.37	45.41	15.896	
5,900.00	4,769.26	5,510.21	4,460.64	30.26	28.11	-56.236	-590.39	-1,673.60	721.75	673.45	48.30	14.942	
6,000.00	4,769.79	5,610.21	4,461.22	31.99	29.90	-56.239	-519.68	-1,744.31	721.72	670.40	51.32	14.064	
6,100.00	4,770.32	5,710.21	4,461.79	33.80	31.75	-56.242	-448.97	-1,815.02	721.70	667.26	54.43	13.259	
6,200.00	4,770.84	5,810.21	4,462.36	35.67	33.66	-56.245	-378.26	-1,885.73	721.67	664.05	57.62	12.524	
6,300.00	4,771.37	5,910.21	4,462.94	37.58	35.60	-56.248	-307.55	-1,956.44	721.64	660.76	60.89	11.852	
6,400.00	4,771.90	6,010.21	4,463.51	39.53	37.59	-56.251	-236.84	-2,027.15	721.62	657.41	64.20	11.240	
6,500.00	4,772.42	6,110.21	4,464.08	41.52	39.61	-56.254	-166.13	-2,097.86	721.59	654.02	67.56	10.680	
6,600.00	4,772.95	6,210.21	4,464.66	43.54	41.66	-56.257	-95.42	-2,168.56	721.56	650.60	70.96	10.168	
6,700.00	4,773.48	6,310.21	4,465.23	45.59	43.73	-56.260	-24.71	-2,239.27	721.53	647.14	74.40	9.698	
6,800.00	4,774.01	6,410.21	4,465.80	47.66	45.82	-56.263	46.00	-2,309.98	721.51	643.65	77.85	9.267	
6,900.00	4,774.53	6,510.21	4,466.37	49.74	47.92	-56.266	116.71	-2,380.69	721.48	640.15	81.33	8.871	
7,000.00	4,775.06	6,610.21	4,466.95	51.85	50.05	-56.269	187.42	-2,451.40	721.45	636.62	84.83	8.505	
7,100.00	4,775.59	6,710.21	4,467.52	53.97	52.19	-56.272	258.13	-2,522.11	721.43	633.08	88.34	8.166	
7,200.00	4,776.12	6,810.21	4,468.09	56.10	54.34	-56.275	328.85	-2,592.81	721.40	629.53	91.87	7.853	
7,300.00	4,776.64	6,910.21	4,468.67	58.24	56.50	-56.278	399.56	-2,663.52	721.37	625.97	95.40	7.561	
7,400.00	4,777.17	7,010.21	4,469.24	60.40	58.67	-56.281	470.27	-2,734.23	721.34	622.40	98.94	7.291	
7,500.00	4,777.70	7,110.21	4,469.81	62.56	60.85	-56.284	540.98	-2,804.94	721.32	618.83	102.49	7.038	
7,600.00	4,778.22	7,210.21	4,470.39	64.74	63.04	-56.287	611.69	-2,875.65	721.29	615.25	106.04	6.802	
7,700.00	4,778.75	7,310.21	4,470.96	66.92	65.23	-56.290	682.40	-2,946.36	721.26	611.67	109.59	6.581	
7,800.00	4,779.28	7,410.21	4,471.53	69.11	67.43	-56.293	753.11	-3,017.07	721.24	608.09	113.15	6.374	
7,900.00	4,779.81	7,510.21	4,472.11	71.31	69.64	-56.296	823.82	-3,087.77	721.21	604.51	116.70	6.180	
8,000.00	4,780.33	7,610.21	4,472.68	73.51	71.85	-56.299	894.53	-3,158.48	721.18	600.93	120.26	5.997	
8,100.00	4,780.86	7,710.21	4,473.25	75.71	74.07	-56.302	965.24	-3,229.19	721.16	597.35	123.81	5.825	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design:		Ponderosa (99, 111,112,114-117,120,136) - Ponderosa 099H - Original Hole - rev0											Offset Site Error:		0.00 ft		
Survey Program:		0-MWD		Offset		Semi Major Axis		Offset Wellbore Centre		Rule Assigned:				Offset Well Error:		0.00 ft	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning				
8,200.00	4,781.39	7,810.21	4,473.83	77.93	76.29	-56.304	1,035.95	-3,299.90	721.13	593.77	127.36	5.662					
8,300.00	4,781.92	7,910.21	4,474.40	80.14	78.52	-56.307	1,106.66	-3,370.61	721.10	590.19	130.91	5.508					
8,400.00	4,782.44	8,010.21	4,474.97	82.36	80.75	-56.310	1,177.37	-3,441.32	721.07	586.62	134.45	5.363					
8,500.00	4,782.97	8,110.21	4,475.55	84.59	82.98	-56.313	1,248.08	-3,512.03	721.05	583.06	137.99	5.225					
8,600.00	4,783.50	8,210.21	4,476.12	86.82	85.22	-56.316	1,318.79	-3,582.73	721.02	579.49	141.53	5.095					
8,700.00	4,784.02	8,310.21	4,476.69	89.05	87.46	-56.319	1,389.50	-3,653.44	720.99	575.94	145.06	4.970					
8,800.00	4,784.55	8,410.21	4,477.27	91.28	89.70	-56.322	1,460.21	-3,724.15	720.97	572.39	148.58	4.852					
8,900.00	4,785.08	8,510.21	4,477.84	93.52	91.95	-56.325	1,530.92	-3,794.86	720.94	568.84	152.10	4.740					
9,000.00	4,785.61	8,610.21	4,478.41	95.76	94.19	-56.328	1,601.63	-3,865.57	720.91	565.30	155.61	4.633					
9,100.00	4,786.13	8,710.21	4,478.99	98.01	96.44	-56.331	1,672.35	-3,936.28	720.89	561.77	159.11	4.531					
9,200.00	4,786.66	8,810.21	4,479.56	100.25	98.69	-56.334	1,743.06	-4,006.98	720.86	558.25	162.61	4.433					
9,300.00	4,787.19	8,910.21	4,480.13	102.50	100.95	-56.337	1,813.77	-4,077.69	720.83	554.73	166.10	4.340					
9,400.00	4,787.72	9,010.21	4,480.71	104.75	103.20	-56.340	1,884.48	-4,148.40	720.81	551.22	169.58	4.251					
9,500.00	4,788.24	9,110.21	4,481.28	107.00	105.46	-56.343	1,955.19	-4,219.11	720.78	547.72	173.05	4.165					
9,600.00	4,788.77	9,210.21	4,481.85	109.25	107.72	-56.346	2,025.90	-4,289.82	720.75	544.23	176.52	4.083					
9,700.00	4,789.30	9,310.21	4,482.43	111.51	109.98	-56.349	2,096.61	-4,360.53	720.72	540.75	179.97	4.005					
9,800.00	4,789.82	9,410.21	4,483.00	113.76	112.24	-56.352	2,167.32	-4,431.24	720.70	537.28	183.42	3.929					
9,900.00	4,790.35	9,510.21	4,483.57	116.02	114.50	-56.355	2,238.03	-4,501.94	720.67	533.81	186.86	3.857					
10,000.00	4,790.88	9,610.21	4,484.15	118.28	116.77	-56.358	2,308.74	-4,572.65	720.64	530.36	190.29	3.787					
10,100.00	4,791.41	9,710.21	4,484.72	120.54	119.03	-56.361	2,379.45	-4,643.36	720.62	526.91	193.70	3.720					
10,200.00	4,791.93	9,810.21	4,485.29	122.80	121.30	-56.364	2,450.16	-4,714.07	720.59	523.48	197.11	3.656					
10,300.00	4,792.46	9,910.21	4,485.87	125.07	123.56	-56.367	2,520.87	-4,784.78	720.56	520.05	200.51	3.594					
10,400.00	4,792.99	10,010.21	4,486.44	127.33	125.83	-56.370	2,591.58	-4,855.49	720.54	516.64	203.90	3.534					
10,500.00	4,793.52	10,110.21	4,487.01	129.60	128.10	-56.373	2,662.29	-4,926.20	720.51	513.23	207.28	3.476					
10,600.00	4,794.04	10,210.21	4,487.59	131.86	130.37	-56.376	2,733.00	-4,996.90	720.48	509.84	210.64	3.420					
10,700.00	4,794.57	10,310.21	4,488.16	134.13	132.64	-56.379	2,803.71	-5,067.61	720.45	506.46	214.00	3.367					
10,781.50	4,795.00	10,391.71	4,488.63	135.98	134.49	-56.381	2,861.34	-5,125.24	720.43	503.71	216.72	3.324 ES, SF					

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (99, 111,112,114-117,120,136) - Ponderosa 117H - Original Hole - rev0													Offset Site Error: 0.00 ft
Survey Program: 0-MWD													Offset Well Error: 0.00 ft
Reference	Offset	Rule Assigned:											
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference	Offset	Highside Toolface (°)	Offset Wellbore Centre	Distance	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
5,100.00	4,739.66	5,050.00	4,813.04	23.10	18.92	-84.719	-1,459.78	-1,673.41	1,262.85	1,225.22	37.63	33.559	
5,200.00	4,761.15	5,100.00	4,826.22	23.14	19.04	-87.090	-1,421.33	-1,702.51	1,239.82	1,201.37	38.44	32.250	
5,300.00	4,766.10	5,150.00	4,835.65	23.34	19.39	-88.857	-1,383.47	-1,733.75	1,220.08	1,180.48	39.60	30.811	
5,400.00	4,766.63	5,200.00	4,841.27	23.79	19.86	-89.121	-1,346.49	-1,766.91	1,206.88	1,165.76	41.12	29.353	
5,500.00	4,767.15	5,266.57	4,843.18	24.60	20.57	-89.206	-1,298.94	-1,813.42	1,201.13	1,158.04	43.09	27.876	
5,600.00	4,767.68	5,366.55	4,843.94	25.73	21.78	-89.225	-1,228.24	-1,884.12	1,200.02	1,154.37	45.65	26.287	
5,700.00	4,768.21	5,466.55	4,844.70	27.08	23.14	-89.235	-1,157.53	-1,954.83	1,200.01	1,151.50	48.51	24.737	
5,800.00	4,768.73	5,566.55	4,845.45	28.61	24.64	-89.246	-1,086.82	-2,025.54	1,200.01	1,148.39	51.62	23.247	
5,900.00	4,769.26	5,666.55	4,846.21	30.26	26.24	-89.257	-1,016.12	-2,096.25	1,200.00	1,145.07	54.94	21.843	
6,000.00	4,769.79	5,766.55	4,846.96	31.99	27.93	-89.268	-945.41	-2,166.95	1,200.00	1,141.57	58.43	20.537	
6,100.00	4,770.32	5,866.55	4,847.72	33.80	29.71	-89.279	-874.70	-2,237.66	1,200.00	1,137.93	62.07	19.334	
6,200.00	4,770.84	5,966.55	4,848.47	35.67	31.55	-89.290	-803.99	-2,308.37	1,199.99	1,134.17	65.82	18.230	
6,300.00	4,771.37	6,066.55	4,849.23	37.58	33.44	-89.301	-733.28	-2,379.08	1,199.99	1,130.31	69.68	17.221	
6,400.00	4,771.90	6,166.55	4,849.98	39.53	35.38	-89.312	-662.57	-2,449.78	1,199.98	1,126.36	73.62	16.299	
6,500.00	4,772.42	6,266.55	4,850.74	41.52	37.36	-89.323	-591.86	-2,520.49	1,199.98	1,122.34	77.64	15.456	
6,600.00	4,772.95	6,366.55	4,851.49	43.54	39.37	-89.333	-521.15	-2,591.20	1,199.98	1,118.26	81.71	14.686	
6,700.00	4,773.48	6,466.55	4,852.25	45.59	41.42	-89.344	-450.44	-2,661.91	1,199.97	1,114.13	85.84	13.980	
6,800.00	4,774.01	6,566.55	4,853.00	47.66	43.48	-89.355	-379.73	-2,732.62	1,199.97	1,109.96	90.01	13.332	
6,900.00	4,774.53	6,666.55	4,853.76	49.74	45.57	-89.366	-309.02	-2,803.32	1,199.96	1,105.74	94.22	12.736	
7,000.00	4,775.06	6,766.55	4,854.51	51.85	47.68	-89.377	-238.31	-2,874.03	1,199.96	1,101.49	98.47	12.186	
7,100.00	4,775.59	6,866.55	4,855.27	53.97	49.80	-89.388	-167.61	-2,944.74	1,199.96	1,097.21	102.74	11.679	
7,200.00	4,776.12	6,966.55	4,856.02	56.10	51.94	-89.399	-96.90	-3,015.45	1,199.95	1,092.91	107.04	11.210	
7,300.00	4,776.64	7,066.55	4,856.78	58.24	54.09	-89.410	-26.19	-3,086.16	1,199.95	1,088.58	111.37	10.775	
7,400.00	4,777.17	7,166.55	4,857.54	60.40	56.25	-89.421	44.52	-3,156.86	1,199.95	1,084.23	115.71	10.370	
7,500.00	4,777.70	7,266.55	4,858.29	62.56	58.42	-89.431	115.23	-3,227.57	1,199.94	1,079.87	120.08	9.993	
7,600.00	4,778.22	7,366.55	4,859.05	64.74	60.60	-89.442	185.94	-3,298.28	1,199.94	1,075.48	124.46	9.641	
7,700.00	4,778.75	7,466.55	4,859.80	66.92	62.79	-89.453	256.65	-3,368.99	1,199.93	1,071.08	128.85	9.313	
7,800.00	4,779.28	7,566.55	4,860.56	69.11	64.99	-89.464	327.36	-3,439.69	1,199.93	1,066.67	133.26	9.005	
7,900.00	4,779.81	7,666.55	4,861.31	71.31	67.19	-89.475	398.07	-3,510.40	1,199.93	1,062.25	137.68	8.715	
8,000.00	4,780.33	7,766.55	4,862.07	73.51	69.40	-89.486	468.78	-3,581.11	1,199.92	1,057.81	142.11	8.444	
8,100.00	4,780.86	7,866.55	4,862.82	75.71	71.62	-89.497	539.49	-3,651.82	1,199.92	1,053.37	146.55	8.188	
8,200.00	4,781.39	7,966.55	4,863.58	77.93	73.83	-89.508	610.20	-3,722.53	1,199.92	1,048.92	151.00	7.946	
8,300.00	4,781.92	8,066.55	4,864.33	80.14	76.06	-89.519	680.90	-3,793.23	1,199.91	1,044.46	155.46	7.719	
8,400.00	4,782.44	8,166.55	4,865.09	82.36	78.29	-89.529	751.61	-3,863.94	1,199.91	1,039.99	159.92	7.503	
8,500.00	4,782.97	8,266.55	4,865.84	84.59	80.52	-89.540	822.32	-3,934.65	1,199.91	1,035.51	164.40	7.299	
8,600.00	4,783.50	8,366.55	4,866.60	86.82	82.75	-89.551	893.03	-4,005.36	1,199.91	1,031.03	168.87	7.105	
8,700.00	4,784.02	8,466.55	4,867.35	89.05	84.99	-89.562	963.74	-4,076.06	1,199.90	1,026.54	173.36	6.921	
8,800.00	4,784.55	8,566.55	4,868.11	91.28	87.23	-89.573	1,034.45	-4,146.77	1,199.90	1,022.05	177.85	6.747	
8,900.00	4,785.08	8,666.55	4,868.86	93.52	89.48	-89.584	1,105.16	-4,217.48	1,199.90	1,017.55	182.35	6.580	
9,000.00	4,785.61	8,766.55	4,869.62	95.76	91.72	-89.595	1,175.87	-4,288.19	1,199.89	1,013.05	186.85	6.422	
9,100.00	4,786.13	8,866.55	4,870.38	98.01	93.97	-89.606	1,246.58	-4,358.90	1,199.89	1,008.54	191.35	6.271	
9,200.00	4,786.66	8,966.55	4,871.13	100.25	96.22	-89.617	1,317.29	-4,429.60	1,199.89	1,004.03	195.86	6.126	
9,300.00	4,787.19	9,066.55	4,871.89	102.50	98.48	-89.627	1,388.00	-4,500.31	1,199.88	999.51	200.37	5.988	
9,400.00	4,787.72	9,166.54	4,872.64	104.75	100.73	-89.638	1,458.71	-4,571.02	1,199.88	995.00	204.89	5.856	
9,500.00	4,788.24	9,266.54	4,873.40	107.00	102.99	-89.649	1,529.41	-4,641.73	1,199.88	990.47	209.40	5.730	
9,600.00	4,788.77	9,366.54	4,874.15	109.25	105.25	-89.660	1,600.12	-4,712.43	1,199.88	985.95	213.93	5.609	
9,700.00	4,789.30	9,466.54	4,874.91	111.51	107.51	-89.671	1,670.83	-4,783.14	1,199.87	981.42	218.45	5.493	
9,800.00	4,789.82	9,566.54	4,875.66	113.76	109.77	-89.682	1,741.54	-4,853.85	1,199.87	976.89	222.98	5.381	
9,900.00	4,790.35	9,666.54	4,876.42	116.02	112.03	-89.693	1,812.25	-4,924.56	1,199.87	972.36	227.51	5.274	
10,000.00	4,790.88	9,766.54	4,877.17	118.28	114.29	-89.704	1,882.96	-4,995.27	1,199.87	967.82	232.04	5.171	
10,100.00	4,791.41	9,866.54	4,877.93	120.54	116.56	-89.714	1,953.67	-5,065.97	1,199.86	963.29	236.58	5.072	
10,200.00	4,791.93	9,966.54	4,878.68	122.80	118.83	-89.725	2,024.38	-5,136.68	1,199.86	958.75	241.11	4.976	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Offset Design: Ponderosa (99, 111,112,114-117,120,136) - Ponderosa 117H - Original Hole - rev0														Offset Site Error:	0.00 ft
Survey Program: 0-MWD														Offset Well Error:	0.00 ft
Reference	Offset	Semi Major Axis		Distance		Rule Assigned:		Warning							
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor			
10,300.00	4,792.46	10,066.54	4,879.44	125.07	121.09	-89.736	2,095.09	-5,207.39	1,199.86	954.21	245.65	4.884			
10,400.00	4,792.99	10,166.54	4,880.19	127.33	123.36	-89.747	2,165.80	-5,278.10	1,199.86	949.66	250.19	4.796			
10,500.00	4,793.52	10,266.54	4,880.95	129.60	125.63	-89.758	2,236.51	-5,348.81	1,199.85	945.12	254.74	4.710			
10,600.00	4,794.04	10,366.54	4,881.70	131.86	127.90	-89.769	2,307.21	-5,419.51	1,199.85	940.57	259.28	4.628			
10,700.00	4,794.57	10,466.54	4,882.46	134.13	130.17	-89.780	2,377.92	-5,490.22	1,199.85	936.02	263.83	4.548			
10,781.50	4,795.00	10,548.04	4,883.08	135.98	132.02	-89.789	2,435.55	-5,547.85	1,199.85	932.32	267.53	4.485 CC, ES, SF			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Reference Depths are relative to RKB=6711+23.5 @ 6734.50ft

Offset Depths are relative to Offset Datum


Central Meridian is -107.83333333

Coordinates are relative to: Ponderosa Unit 119H

Coordinate System is US State Plane 1983, New Mexico Western Zone

Grid Convergence at Surface is: 0.004°

Ladder Plot



LEGEND

Ponderosa_06 2309 FEDDOM 121H Original Hole, rev0 V0	Ponderosa_06 2309 FEDDOM 123H Original Hole, rev0 V0	Ponderosa 117H Original Hole, rev0 V0
Ponderosa_06 2309 FEDDOM 100H Original Hole, rev0 V0	Ponderosa_06 2309 FEDDOM 118H Original Hole, rev0 V0	
Ponderosa Unit 122H Original Hole, rev0 V0	Ponderosa 099H Original Hole, rev0 V0	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Anticollision Report

Company:	Enduring Resources LLC	Local Co-ordinate Reference:	Well Ponderosa Unit 119H
Project:	San Juan County, New Mexico NAD83 NM W	TVD Reference:	RKB=6711+23.5 @ 6734.50ft
Reference Site:	Ponderosa (100,118,119,121,122 & 123)	MD Reference:	RKB=6711+23.5 @ 6734.50ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Ponderosa Unit 119H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DT_Jul1724_v17
Reference Design:	rev0	Offset TVD Reference:	Offset Datum

Reference Depths are relative to RKB=6711+23.5 @ 6734.50ft

Offset Depths are relative to Offset Datum


Central Meridian is -107.8333333

Coordinates are relative to: Ponderosa Unit 119H

Coordinate System is US State Plane 1983, New Mexico Western Zone

Grid Convergence at Surface is: 0.004°

Separation Factor Plot



LEGEND

Ponderosa.062309 FEEDDOM 121H Original Hole, rev 0	Ponderosa.062309 FEEDDOM 123H Original Hole, rev 0	Ponderosa.117H Original Hole, rev 0
Ponderosa.1100H Original Hole, rev 0	Ponderosa.062309 FEEDDOM 118H Original Hole, rev 0	
Ponderosa Unit 122H Original Hole, rev 0	Ponderosa.099H Original Hole, rev 0	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Farmington District Office
6251 College Blvd, Suite A
Farmington, New Mexico 87402



In Reply Refer To:
3162.3-1(NMF0110)

* DJR OPERATING LLC
#119H PONDEROSA UNIT
Lease: NMNM137056 Agreement: NMNM106318743

SH: NW¼SE¼ Section 6, T. 23N., R. 9W.
San Juan County, New Mexico
BH: Lot 1 Section 1, T. 23N., R. 10W.
San Juan County, New Mexico
***Above Data Required on Well Sign**

GENERAL REQUIREMENTS FOR OIL AND GAS OPERATIONS ON FEDERAL AND INDIAN LEASES

The following special requirements apply and are effective when **checked**:

- A. ☒ Note all surface/drilling conditions of approval attached.
- B. ☒ The required wait on cement (WOC) time will be a minimum of 500 psi compressive strength at 60 degrees. Blowout preventor (BOP) nipple-up operations may then be initiated
- C. ☒ Test all casing strings below the conductor casing to .22 psi/ft. of casing string length or 1500 psi, whichever is greater, but not to exceed 70% of the minimum internal yield (burst) for a minimum of 30 minutes. If pressure declines more than 10 percent in 30 minutes, corrective action shall be taken.
- D. ☐ Communitization Agreement covering the acreage dedicated to this well must be filed for approval with the Bureau of Land Management, New Mexico State Office, Reservoir Management Group, 301 Dinosaur Trail, Santa Fe, New Mexico 87508.
The effective date of the agreement must be **prior** to any sales.
- E. ☐ The use of co-flex hose is authorized contingent upon the following:
 1. From the BOP to the choke manifold: the co-flex hose must be hobbled on both ends and saddle to prevent whip.
 2. From the choke manifold to the discharge tank: the co-flex hoses must be as straight as practical, hobbled on both ends and anchored to prevent whip.
 3. The co-flex hose pressure rating must be at least commensurate with approved BOPE.

INTERIOR REGION 7 • UPPER COLORADO BASIN

COLORADO, NEW MEXICO, UTAH, WYOMING

I. GENERAL

- A. Full compliance with all applicable laws and regulations, with the approved Permit to drill, and with the approved Surface Use and Operations Plan is required. Lessees and/or operators are fully accountable for the actions of their contractors and subcontractors. Failure to comply with these requirements and the filing of required reports will result in strict enforcement pursuant to 43 CFR 3163.1 or 3163.2.
- B. Each well shall have a well sign in legible condition from spud date to final abandonment. The sign should show the operator's name, lease serial number, or unit name, well number, location of the well, and whether lease is Tribal or Allotted, (See 43 CFR 3162.6(b)).
- C. A complete copy of the approved Application for Permit to Drill, along with any conditions of approval, shall be available to authorized personnel at the drill site whenever active drilling operations are under way.
- D. For Wildcat wells only, a drilling operations progress report is to be submitted, to the BLM-Field Office, weekly from the spud date until the well is completed and the Well Completion Report is filed. The report should be on 8-1/2 x 11 inch paper, and each page should identify the well by; operator's name, well number, location and lease number.
- E. As soon as practical, notice is required of all blowouts, fires and accidents involving life-threatening injuries or loss of life. (See NTL-3A).
- F. BOP equipment (except the annular preventer) shall be tested utilizing a test plug to full working pressure for 10 minutes. No bleed-off of pressure is acceptable. (See 43 CFR 3172.6(b)(9)(ii)).
- G. The operator shall have sufficient weighting materials and lost circulation materials on location in the event of a pressure kick or in the event of lost circulation. (See 43 CFR 3172.8(a)).
- H. The flare line(s) discharge shall be located not less than 100 feet from the well head, having straight lines unless turns are targeted with running tees, and shall be positioned downwind of the prevailing wind direction and shall be anchored. The flare system shall have an effective method for ignition. Where noncombustible gas is likely or expected to be vented, the system shall be provided supplemental fuel for ignition and to maintain a continuous flare. (See 43 CFR 3172.8(b)(7)).
- I. Prior approval by the BLM-Authorized Office (Drilling and Production Section) is required for variance from the approved drilling program and before commencing plugging operations, plug back work, casing repair work, corrective cementing operations, or suspending drilling operations indefinitely. Emergency approval may be obtained orally, but such approval is contingent upon filing of a Notice of Intent sundry within three business days. **Any changes to the approved plan or any questions regarding drilling operations should be directed to BLM during regular business hours at 505-564-7600. Emergency program changes after hours should be directed to Virgil Lucero at 505-793-1836.**
- J. **The Inspection and Enforcement Section (I&E), phone number (505-564-7750) is to be notified at least 24 hours in advance of BOP test, spudding, cementing, or plugging operations so that a BLM representative may witness the operations.**
- K. Unless drilling operations are commenced within three years according to 43 CFR 3171.14, approval of the Application for Permit to Drill will expire. No extensions will be granted.

- L. From the time drilling operations are initiated and until drilling operations are completed, a member of the drilling crew or the tool pusher shall maintain rig surveillance at all times, unless the well is secured with blowout preventers or cement plugs.
- M. If for any reason, drilling operations are suspended for more than 90 days, a written notice must be provided to this office outlining your plans for this well.
- N. **Commingling:** No production (oil, gas, and water) from the subject well should start until Sundry Notices (if necessary) granting variances from applicable regulations as related to commingling and off-lease measurement are approved by this office. (See 43 CFR 3173.14)

II. REPORTING REQUIREMENTS

- A. For reporting purposes, all well Sundry notices, well completion and other well actions shall be referenced by the appropriate lease, communitization agreement and/or unit agreement numbers.
- B. The following reports shall be filed with the BLM-Authorized Officer online through AFMSS 2 within 30 days after the work is completed.
 - 1. Provide complete information concerning.
 - a. Setting of each string of casing. Show size and depth of hole, grade and weight of casing, depth set, depth of all cementing tools that are used, amount (in cubic feet) and types of cement used, whether cement circulated to surface and all cement tops in the casing annulus, casing test method and results, and the date work was done. Show spud date on first report submitted.
 - b. Intervals tested, perforated (include size, number and location of perforations), acidized, or fractured; and results obtained. Provide date work was done on well completion report and completion sundry notice.
 - c. Subsequent Report of Abandonment, show the way the well was plugged, including depths where casing was cut and pulled, intervals (by depths) where cement plugs were replaced, and dates of the operations.
 - 2. Well Completion Report will be submitted with 30 days after well has been completed.
 - a. Initial Bottom Hole Pressure (BHP) for the producing formations. Show the BHP on the completion report. The pressure may be: 1) measured with a bottom hole bomb, or; 2) calculated based on shut in surface pressures (minimum seven day buildup) and fluid level shot.
 - 3. Submit a cement evaluation log if cement is not circulated to surface.
- C. Production Startup Notification is required no later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site or resumes production in the case of a well which has been off production for more than 90 days. The operator shall notify the Authorized Officer by letter or Sundry Notice, Form 3160-5, or orally to be followed by a letter or Sundry Notice, of the date on which such production has begun or resumed. CFR 43 3162.4-1(c).

III. DRILLER'S LOG

The following shall be entered in the daily driller's log: 1) Blowout preventer pressures tests, including test pressures and results, 2) Blowout preventer tests for proper functioning, 3) Blowout prevention drills conducted, 4) Casing run, including size, grade, weight, and depth set, 5) How pipe was cemented, including amount of cement, type, whether cement circulated to surface, location of cementing tools, etc., 6) Waiting on cement time for each casing string, 7) Casing pressure tests after cementing, including test pressure and results, and 8) Estimated amounts of oil and gas recovered and/or produced during drill stem test.

IV. GAS FLARING

Gas produced from this well may not be vented or flared beyond an initial, authorized test period of * Days, 20 MMCF following its (completion)(recompletion), or flowback has been routed to the production separator, whichever first occurs, without the prior, written approval of the authorized officer in accordance with 43 CFR 3179.81. Should gas be vented or flared without approval beyond the test period authorized above, you may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted. You shall be required to compensate the lessor for the portion of the gas vented or flared without approval which is determined to have been avoidably lost.

**30 days, unless a longer test period is specifically approved by the authorized officer. The 30-day period will commence upon the beginning of flowback following completion or recompletion.*

V. SAFETY

- A. All rig heating stoves are to be of the explosion-proof type.
- B. Rig safety lines are to be installed.
- C. Hard hats and other Personal Protective Equipment (PPE) must be utilized.

VI. CHANGE OF PLANS OR ABANDONMENT

- A. Any changes of plans required to mitigate unanticipated conditions encountered during drilling operations, will require approval as set forth in Section 1.I.
- B. If the well is dry, it is to be plugged in accordance with 43 CFR 3162.3-4, approval of the proposed plugging program is required as set forth in Section 1.I. The report should show the total depth reached, the reason for plugging, and the proposed intervals, by depths, where cement plugs are to be placed, type of plugging mud, etc. A Subsequent Report of Abandonment is required as set forth in Section II.B.1c.
- C. Unless a well has been properly cased and cemented, or properly plugged, the drilling rig must not be moved from the drill site without prior approval from the BLM-Authorized Officer.

VII. PHONE NUMBERS

- A. For BOPE tests, cementing, and plugging operations the phone number is 505-564-7750 and must be called 24 hours in advance in order that a BLM representative may witness the operations.
- B. Emergency program changes after hours contact:

Virgil Lucero (505) 793-1836
Dustin Porch (505) 386-9876
Kenneth Rennick (505) 564-7742
Matthew Kade (505) 564-7736

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/oed/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 426358

CONDITIONS

Operator: DJR OPERATING, LLC 200 Energy Court Farmington, NM 87401	OGRID: 371838
	Action Number: 426358
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
scrues76	Cement is required to circulate on both surface and intermediate1 strings of casing.	1/29/2025
scrues76	If cement does not circulate on any string, a Cement Bond Log (CBL) is required for that string of casing.	1/29/2025
ward.rikala	Notify the OCD 24 hours prior to casing & cement.	2/14/2025
ward.rikala	File As Drilled C-102 and a directional Survey with C-104 completion packet.	2/14/2025
ward.rikala	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string.	2/14/2025
ward.rikala	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.	2/14/2025