

Form 3160-3
(June 2015)FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input type="checkbox"/> DRILL <input type="checkbox"/> REENTER 1b. Type of Well: <input type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		5. Lease Serial No. 6. If Indian, Allottee or Tribe Name 7. If Unit or CA Agreement, Name and No. 8. Lease Name and Well No. 9. API Well No. <div style="text-align: right; color: red;">30-005-64403</div>			
2. Name of Operator 3a. Address 3b. Phone No. (include area code)		10. Field and Pool, or Exploratory 11. Sec., T. R. M. or Blk. and Survey or Area 12. County or Parish 13. State			
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface At proposed prod. zone		14. Distance in miles and direction from nearest town or post office* 15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 16. No of acres in lease 17. Spacing Unit dedicated to this well 18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 19. Proposed Depth 20. BLM/BIA Bond No. in file 21. Elevations (Show whether DF, KDB, RT, GL, etc.) 22. Approximate date work will start* 23. Estimated duration			
24. Attachments The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable) <table style="width: 100%;"> <tr> <td style="width: 50%; vertical-align: top;"> 1. Well plat certified by a registered surveyor. 2. A Drilling Plan. 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). </td> <td style="width: 50%; vertical-align: top;"> 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). 5. Operator certification. 6. Such other site specific information and/or plans as may be requested by the BLM. </td> </tr> </table>				1. Well plat certified by a registered surveyor. 2. A Drilling Plan. 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).	4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). 5. Operator certification. 6. Such other site specific information and/or plans as may be requested by the BLM.
1. Well plat certified by a registered surveyor. 2. A Drilling Plan. 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).	4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). 5. Operator certification. 6. Such other site specific information and/or plans as may be requested by the BLM.				
25. Signature Title		Name (Printed/Typed) Date			
Approved by (Signature) Title		Name (Printed/Typed) Office			
Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.					

(Continued on page 2)

*(Instructions on page 2)



C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024	
		Submittal Type:	<input checked="" type="checkbox"/> Initial Submittal
			<input type="checkbox"/> Amended Report
			<input type="checkbox"/> As Drilled

WELL LOCATION INFORMATION

API Number 30-005-64403	Pool Code 52770	Pool Name Round Tank; San Andres
Property Code 337207	Property Name BROCKVILLE FEDERAL	Well Number 1H
OGRID No. 13837	Operator Name MACK ENERGY CORPORATION	Ground Level Elevation 3731.3
Surface Owner: <input type="checkbox"/> State <input type="checkbox"/> Fee <input type="checkbox"/> Tribal <input checked="" type="checkbox"/> Federal		Mineral Owner: <input type="checkbox"/> State <input type="checkbox"/> Fee <input type="checkbox"/> Tribal <input checked="" type="checkbox"/> Federal

Surface Location

UL N	Section 7	Township 15 S	Range 29 E	Lot	Ft. from N/S 667 SOUTH	Ft. from E/W 1650 WEST	Latitude 33.0250625°N	Longitude 104.0713791°W	County CHAVES
---------	--------------	------------------	---------------	-----	---------------------------	---------------------------	--------------------------	----------------------------	------------------

Bottom Hole Location

UL N	Section 18	Township 15 S	Range 29 E	Lot	Ft. from N/S 1 SOUTH	Ft. from E/W 1650 WEST	Latitude 33.0085945°N	Longitude 104.0712955°W	County CHAVES
---------	---------------	------------------	---------------	-----	-------------------------	---------------------------	--------------------------	----------------------------	------------------

Dedicated Acres 160	Infill or Defining Well	Defining Well API	Overlapping Spacing Unit (Y/N)	Consolidation Code
Order Numbers.			Well setbacks are under Common Ownership: <input type="checkbox"/> Yes <input type="checkbox"/> No	

Kick Off Point (KOP)

UL N	Section 7	Township 15 S	Range 29 E	Lot	Ft. from N/S 667 SOUTH	Ft. from E/W 1650 WEST	Latitude 33.0250625°N	Longitude 104.0713791°W	County CHAVES
---------	--------------	------------------	---------------	-----	---------------------------	---------------------------	--------------------------	----------------------------	------------------

First Take Point (FTP)

UL C	Section 18	Township 15 S	Range 29 E	Lot	Ft. from N/S 100 NORTH	Ft. from E/W 1650 WEST	Latitude 33.0229548°N	Longitude 104.0713810°W	County CHAVES
---------	---------------	------------------	---------------	-----	---------------------------	---------------------------	--------------------------	----------------------------	------------------

Last Take Point (LTP)

UL N	Section 18	Township 15 S	Range 29 E	Lot	Ft. from N/S 100 SOUTH	Ft. from E/W 1650 WEST	Latitude 33.0088665°N	Longitude 104.0712976°W	County CHAVES
---------	---------------	------------------	---------------	-----	---------------------------	---------------------------	--------------------------	----------------------------	------------------

Unitized Area or Area of Uniform Interest	Spacing Unit Type <input type="checkbox"/> Horizontal <input type="checkbox"/> Vertical	Ground Floor Elevation:
---	---	-------------------------

OPERATOR CERTIFICATIONS

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest run leased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order here to fore entered by the division.

If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.

Deana Weaver

8/26/2024

Signature

Date

Deana Weaver


Printed Name

dweaver@mec.com

Email Address

SURVEYOR CERTIFICATIONS

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.



Signature and Seal of Professional Surveyor

FILIMON F. JARAMILLO

Certificate Number

PLS 12797

Date of Survey

JUNE 13, 2024

SURVEY NO. 9919A

Note: No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

This grid represents a standard section. You may superimpose a non-standard section, or larger area, over this grid. Operators must outline the dedicated acreage in a red box, clearly show the well surface location and bottom hole location, if it is directionally drilled, with the dimensions from the section lines in the cardinal directions. If this is a horizontal wellbore show on this plat the location of the First Take Point and Last Take Point, and the point within the Completed interval (other than the First Take Point or Last Take Point) that is closest to any outer boundary of the tract.

Surveyors shall use the latest United States government survey or dependent resurvey. Well locations will be in reference to the New Mexico Principal Meridian. If the land is not surveyed, contact the OCD Engineering Bureau. Independent subdivision surveys will not be acceptable.

BROCKVILLE FEDERAL 1H
EL. = 3731.3

GEODETIC COORDINATES
NAD 83 NMSP EAST
SURFACE LOCATION
N.= 736754.90
E.= 621623.91
LAT. = 33.0250625°N
LONG. = 104.0713791°W

KICK OFF POINT 667' FSL, 1650' FWL N.= 736754.90 E.= 621623.91 LAT. = 33.0250625°N LONG. = 104.0713791°W	FIRST TAKE POINT (PPP 1) 100' FNL, 1650' FWL N.= 735988.04 E.= 621625.26 LAT. = 33.0229548°N LONG. = 104.0713810°W
---	---


LAST TAKE POINT 100' FSL, 1650' FWL N.= 730862.41 E.= 621663.58 LAT. = 33.0088665°N LONG. = 104.0712976°W	BOTTOM OF HOLE 1' FSL, 1650' FWL N.= 730763.43 E.= 621664.48 LAT. = 33.0085945°N LONG. = 104.0712955°W
--	---

CORNER COORDINATES TABLE
NAD 83 NMSP EAST


A - N.= 741431.31	E.= 619969.62
B - N.= 741268.76	E.= 622730.72
C - N.= 741361.02	E.= 625366.62
D - N.= 738718.89	E.= 625368.32
E - N.= 736082.33	E.= 625373.48
F - N.= 733444.71	E.= 625371.40
G - N.= 730802.99	E.= 625370.10
H - N.= 730773.68	E.= 622692.56
I - N.= 730744.38	E.= 620015.02
J - N.= 733421.99	E.= 619990.60
K - N.= 736105.72	E.= 619974.98
L - N.= 738768.51	E.= 619972.30
M - N.= 736076.12	E.= 622735.35

LEGEND

--- SECTION LINE
--- QUARTER LINE
--- LEASE LINE
--- WELL PATH



SECTION 7, TOWNSHIP 15 SOUTH, RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO
SITE MAP



010 50 100 200

SCALE 1" = 100'

DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF ST. HWY. 249 & CO. RD. 217
(HAGERMAN CUTOFF) GO WEST ON ST. HWY. 249 APPROX. 3.4 MILES,
TURN LEFT ON 20' CALICHE ROAD AND GO SOUTH APPROX. 2.9
MILES, TURN RIGHT ON 20' CALICHE ROAD AND GO WEST APPROX.
0.9 MILES TO THE NORTHEAST PAD CORNER FOR THIS LOCATION.

I, FILMON F. JARAMILLO, A NEW MEXICO REGISTERED PROFESSIONAL
SURVEYOR CERTIFY THAT I DIRECTED AND SUPERVISED THIS
SURVEY, THAT THIS MAP IS A TRUE AND CORRECT REPRESENTATION OF MY
KNOWLEDGE AND BELIEFS, AND THAT I HAVE MET THE MINIMUM
STANDARDS FOR SURVEYING PRACTICE.

FILMON F. JARAMILLO, REGISTERED PROFESSIONAL SURVEYOR NO. 7891

MADRON SURVEYING, INC.

301 SOUTH CANAL
(575) 234-3327

MACK ENERGY CORPORATION
BROCKVILLE FEDERAL 1H


LOCATED 667 FT. FROM THE SOUTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 15 SOUTH,
RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO

JUNE 13, 2024

SURVEY NO. 9919A

CARLSBAD, NEW MEXICO

SECTION 7, TOWNSHIP 15 SOUTH, RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO
INTERIM SITE RECLAMATION



 DENOTES
RECLAMATION AREA
0.634± ACRES RECLAMATION AREA



010 50 100 200
SCALE 1" = 100'

MACK ENERGY CORPORATION
BROCKVILLE FEDERAL 1H
LOCATED 667 FT. FROM THE SOUTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 15 SOUTH,
RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO


JUNE 13, 2024

SURVEY NO. 9919A

MADRON SURVEYING, INC. 301 SOUTH CANAL
(575) 234-3327

CARLSBAD, NEW MEXICO

SECTION 7, TOWNSHIP 15 SOUTH, RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO
LOCATION VERIFICATION MAP



USGS QUAD MAP:
KING CAMP

NOT TO SCALE

MACK ENERGY CORPORATION
BROCKVILLE FEDERAL 1H
LOCATED 667 FT. FROM THE SOUTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 15 SOUTH,
RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO


JUNE 13, 2024

MADRON SURVEYING, INC.

301 SOUTH CANAL
(575) 234-3327

SURVEY NO. 9919A
CARLSBAD, NEW MEXICO

SECTION 7, TOWNSHIP 15 SOUTH, RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO
VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF ST. HWY. 249 & CO. RD. 217
(HAGERMAN CUTOFF) GO WEST ON ST. HWY. 249 APPROX. 3.4 MILES,
TURN LEFT ON 20' CALICHE ROAD AND GO SOUTH APPROX. 2.9
MILES, TURN RIGHT ON 20' CALICHE ROAD AND GO WEST APPROX.
0.9 MILES TO THE NORTHEAST PAD CORNER FOR THIS LOCATION.

MACK ENERGY CORPORATION
BROCKVILLE FEDERAL 1H
LOCATED 667 FT. FROM THE SOUTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 15 SOUTH,
RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO

JUNE 13, 2024

MADRON SURVEYING, INC. 301 SOUTH CANAL

(575) 234-3327

SURVEY NO. 9919A
CARLSBAD, NEW MEXICO

SECTION 7, TOWNSHIP 15 SOUTH, RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO
AERIAL PHOTO



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
APRIL 2023

MACK ENERGY CORPORATION
BROCKVILLE FEDERAL 1H
LOCATED 667 FT. FROM THE SOUTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 15 SOUTH,
RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO


JUNE 13, 2024

SURVEY NO. 9919A

MADRON SURVEYING, INC. 301 SOUTH CANAL
(575) 234-3327

CARLSBAD, NEW MEXICO

SECTION 7, TOWNSHIP 15 SOUTH, RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
APRIL 2023

MACK ENERGY CORPORATION
BROCKVILLE FEDERAL 1H
LOCATED 667 FT. FROM THE SOUTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 15 SOUTH,
RANGE 29 EAST, N.M.P.M.
CHAVES COUNTY, STATE OF NEW MEXICO

JUNE 13, 2024

SURVEY NO. 9919A

MADRON SURVEYING, INC. 301 SOUTH CANAL
(575) 234-3327

CARLSBAD, NEW MEXICO

State of New Mexico
Energy, Minerals and Natural Resources Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit Electronically
Via E-permitting

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description

Effective May 25, 2021

I. Operator: Mack Energy Corporation **OGRID:** 013837 **Date:** 8 / 26 / 2024

II. Type: ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
Brockville Federal #1H		SESW Sec 7 T15S R29E	667 FSL 1650 FWL	100	100	1,000

IV. Central Delivery Point Name: DCP Midstream Linam Ranch Processing Plant / Durango Midstream [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Brockville Federal #1H		1/1/2025	1/20/2025	03/31/2025	03/31/2025	4/1/2025

VI. Separation Equipment: ☒ Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan

EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☒ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. ☐ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system ☐ will ☐ will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator ☐ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

XIV. Confidentiality: ☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☒ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature:	<i>Deana Weaver</i>
Printed Name:	Deana Weaver
Title:	Regulatory Technician II
E-mail Address:	dweaver@mec.com
Date:	8/26/2024
Phone:	575-748-1288
OIL CONSERVATION DIVISION (Only applicable when submitted as a standalone form)	
Approved By:	
Title:	
Approval Date:	
Conditions of Approval:	

VI. Separation Equipment:

Mack Energy Corporation(MEC) production facilities include separation equipment designed to efficiently separate gas from liquid phases to optimize gas capture based on projected and estimated volumes from the targeted pool of our completion project. MEC will utilize flowback separation equipment and production separation equipment designed and built to industry specifications after the completion to optimize gas capture and send gas to sales or flare based on analytical composition. MEC operates facilities that are typically multi-well facilities. Production separation equipment is upgraded prior to new wells being completed, if determined to be undersized or inadequate. This equipment is already on-site and tied into our sales gas lines prior to the new drill operations.

VII. Operational Practices:

1. Subsection (A) Venting and Flaring of Natural Gas. MEC understands the requirements of NMAC 19.15.27.8 which outlines that the venting and flaring of natural gas during drilling, completion or production operations that constitutes waste as defined in 19.15.2 are prohibited.
2. Subsection (B) Venting and Flaring during drilling operations. This gas capture plan isn't for a well being drilled.
3. Subsection (C) Venting and flaring during completion or recompletion. Flowlines will be routed for flowback fluids into a completion or storage tank and if feasible under well conditions, flare rather than vent and commence operation of a separator as soon as it is technically feasible for a separator to function.
 - At any point in the well life (completion, production, inactive) an audio, visual and olfactory inspection be performed at prescribed intervals (weekly or monthly) pursuant to Subsection D of 19.15.27.8 NMAC, to confirm that all production equipment is operating properly and there are no leaks or releases.
4. Subsection (D) Venting and flaring during production operations
 - At any point in the well life (completion, production, inactive) an audio, visual and olfactory inspection be performed at prescribed intervals (weekly or monthly) pursuant to Subsection D of 19.15.27.8 NMAC, to confirm that all production equipment is operating properly and there are no leaks or releases.
 - Monitor manual liquid unloading for wells on-site or in close proximity (<30 minutes' drive time), take reasonable actions to achieve a stabilized rate and pressure at the earliest practical time, and take reasonable actions to minimize venting to the maximum extent practicable.
 - MEC will not vent or flare except during the approved activities listed in NMAC 19.15.27.8 (D) 14.
5. Subsection (E) Performance standards
 - All tanks and separation equipment are designed for maximum throughput and pressure to minimize waste.
 - If a flare is utilized during production operations it will have a continuous pilot and is located more than 100 feet from any known well or storage tanks.
 - At any point in the well life (completion, production, inactive) an audio, visual and olfactory inspection be performed at prescribed intervals (weekly or monthly) pursuant to Subsection D of 19.15.27.8 NMAC, to confirm that all production equipment is operating properly and there are no leaks or releases.

6. Subsection (F) Measurement or estimation of vented and flared natural gas
 - Measurement equipment is installed to measure the volume of natural gas flared from process piping.
 - When measurement isn't practicable, estimation of vented and flared natural gas will be completed as noted in 19.15.27.8 (F) 5-6.

VIII. Best Management Practices:

1. MEC has adequate storage and takeaway capacity for wells it chooses to complete as the flowlines at the sites are already in place and tied into a gathering system.
2. MEC will flare rather than vent vessel blowdown gas when technically feasible during active and/or planned maintenance to equipment on-site.
3. MEC combusts natural gas that would otherwise be vented or flared, when technically feasible.
4. MEC will shut in wells in the event of a takeaway disruption, emergency situation, or other operations where venting or flaring may occur due to equipment failures.
5. MEC has a gas gathering system in place(CTB-887)a with multiple purchaser's to limit venting or flaring, due to purchaser shut downs.

Month	Gas (MCF)
1	10550
2	8917
3	7769
4	6913
5	6247
6	5712
7	5273
8	4904
9	4589
10	4317
11	4080
12	3871
13	3685
14	3518
15	3368
16	3231
17	3107
18	2993
19	2889
20	2792
21	2702
22	2619
23	2542
24	2469
25	2402
26	2338
27	2278
28	2221
29	2168
30	2118
31	2070
32	2024
33	1981
34	1940
35	1900
36	1863
37	1827
38	1793
39	1760
40	1729
41	1698
42	1669
43	1641

44	1615
45	1589
46	1564
47	1540
48	1516
49	1494
50	1472
51	1451
52	1431
53	1411
54	1392
55	1374
56	1356
57	1339
58	1322
59	1305
60	1289
61	1274
62	1259
63	1244
64	1230
65	1216
66	1202
67	1189
68	1176
69	1164
70	1151
71	1140
72	1128
73	1116
74	1105
75	1094
76	1084
77	1073
78	1063
79	1053
80	1043
81	1034
82	1024
83	1015
84	1006
85	998
86	989
87	980

88	972
89	964
90	956
91	948
92	941
93	933
94	926
95	918
96	911
97	904
98	897
99	891
100	884
101	877
102	871
103	865
104	858
105	852
106	846
107	840
108	835
109	829
110	823
111	818
112	812
113	807
114	801
115	796
116	791
117	786
118	781
119	776
120	771
121	766
122	762
123	757
124	753
125	748
126	744
127	739
128	735
129	731
130	726
131	722

132	718
133	714
134	710
135	706
136	702
137	698
138	694
139	691
140	687
141	683
142	680
143	676
144	673
145	669
146	666
147	662
148	659
149	655
150	652
151	649
152	646
153	642
154	639
155	636
156	633
157	630
158	627
159	624
160	621
161	618
162	615
163	613
164	610
165	607
166	604
167	601
168	599
169	596
170	593
171	591
172	588
173	586
174	583
175	581

176	578
177	576
178	573
179	571
180	568
181	566
182	564
183	561
184	559
185	557
186	554
187	552
188	550
189	548
190	546
191	543
192	541
193	539
194	537
195	535
196	533
197	531
198	529
199	527
200	525
201	523
202	521
203	519
204	517
205	515
206	513
207	511
208	509
209	508
210	506
211	504
212	502
213	500
214	499
215	497
216	495
217	493
218	492
219	490

220	488
221	487
222	485
223	483
224	482
225	480
226	478
227	477
228	475
229	474
230	472
231	470
232	469
233	467
234	466
235	464
236	463
237	461
238	460
239	458
240	457
241	456
242	454
243	453
244	451
245	450
246	448
247	447
248	446
249	444
250	443
251	442
252	440
253	439
254	438
255	436
256	435
257	434
258	433
259	431
260	430
261	429
262	428
263	426

264	425
265	424
266	423
267	421
268	420
269	419
270	418
271	417
272	416
273	414
274	413
275	412
276	411
277	410
278	409
279	408
280	406
281	405
282	404
283	403
284	402
285	401
286	400
287	399
288	398
289	397
290	396
291	395
292	394
293	393
294	392
295	391
296	390
297	389
298	388
299	387
300	386
301	385
302	384
303	383
304	382
305	381
306	380
307	379

308	378
309	377
310	376
311	375
312	374
313	373
314	373
315	372
316	371
317	370
318	369
319	368
320	367
321	366
322	365
323	365
324	364
325	363
326	362
327	361
328	360
329	359
330	359
331	358
332	357
333	356
334	355
335	355
336	354
337	353
338	352
339	351
340	351
341	350
342	349
343	348
344	347
345	347
346	346
347	345
348	344
349	344
350	343
351	342

352	341
353	341
354	340
355	339
356	339
357	338
358	337
359	336
360	336
361	335
362	334
363	334
364	333
365	332
366	331
367	331
368	330
369	329
370	329
371	328
372	327
373	327
374	326
375	325
376	325
377	324
378	323
379	323
380	322
381	321
382	321
383	320
384	320
385	319
386	318
387	318
388	317
389	316
390	316
391	315
392	315
393	314
394	313
395	313

396	312
397	312
398	311
399	310
400	310
401	309
402	309
403	308
404	307
405	307
406	306
407	306
408	305
409	305
410	304
411	303
412	303
413	302
414	302
415	301
416	301
417	300
418	299
419	299
420	298
421	298
422	297
423	297
424	296
425	296
426	295
427	295
428	294
429	294
430	293
431	293
432	292
433	292
434	291
435	291
436	290
437	289
438	289
439	288

440	288
441	287
442	287
443	286
444	286
445	286
446	285
447	285
448	284
449	284
450	283
451	283
452	282
453	282
454	281
455	281
456	280
457	280
458	279
459	279
460	278
461	278
462	277
463	277
464	277
465	276
466	276
467	275
468	275
469	274
470	274
471	273
472	273
473	273
474	272
475	272
476	271
477	271
478	270
479	270
480	269
481	269
482	269
483	268

484	268
485	267
486	267
487	266
488	266
489	266
490	265
491	265
492	264
493	264
494	264
495	263
496	263
497	262
498	262
499	262
500	261
501	261
502	260
503	260
504	260
505	259
506	259
507	258
508	258
509	258
510	257
511	257
512	256
513	256
514	256
515	255
516	255
517	255
518	254
519	254
520	253
521	253
522	253
523	252
524	252
525	252
526	251
527	251

528	251
529	250
530	250
531	249
532	249
533	249
534	248
535	248
536	248
537	247
538	247
539	247
540	246
541	246
542	246
543	245
544	245
545	245
546	244
547	244
548	244
549	243
550	243
551	242
552	242
553	242
554	241
555	241
556	241
557	240
558	240
559	240
560	239
561	239
562	239
563	239
564	238
565	238
566	238
567	237
568	237
569	237
570	236
571	236

572	236
573	235
574	235
575	235
576	234
577	234
578	234
579	233
580	233
581	233
582	233
583	232
584	232
585	232
586	231
587	231
588	231
589	230
590	230
591	230
592	230
593	229
594	229
595	229
596	228
597	228
598	228
599	227
600	227
601	227
602	227
603	226
604	226
605	226
606	225
607	225
608	225
609	225
610	224
611	224
612	224
613	223
614	223
615	223

616	223
617	222
618	222
619	222
620	222
621	221
622	221
623	221
624	220
625	220
626	220
627	220
628	219
629	219
630	219
631	219
632	218
633	218
634	218
635	218
636	217
637	217
638	217
639	216
640	216
641	216
642	216
643	215
644	215
645	215
646	215
647	214
648	214
649	214
650	214
651	213
652	213
653	213
654	213
655	212
656	212
657	212
658	212
659	211

660	211
661	211
662	211
663	210
664	210
665	210
666	210
667	210
668	209
669	209
670	209
671	209
672	208
673	208
674	208
675	208
676	207
677	207
678	207
679	207
680	206
681	206
682	206
683	206
684	206
685	205
686	205
687	205
688	205
689	204
690	204
691	204
692	204
693	203
694	203
695	203
696	203
697	203
698	202
699	202
700	202
701	202
702	201
703	201

704	201
705	201
706	201
707	200
708	200
709	200
710	200
711	200
712	199
713	199
714	199
715	199
716	198
717	198
718	198
719	198
720	198
721	197
722	197
723	197
724	197
725	197
726	196
727	196
728	196
729	196
730	196
731	195
732	195
733	195
734	195
735	194
736	194
737	194
738	194
739	194
740	193
741	193
742	193
743	193
744	193
745	192
746	192
747	192

748	192
749	192
750	192
751	191
752	191
753	191
754	191
755	191
756	190
757	190
758	190
759	190
760	190
761	189
762	189
763	189
764	189
765	189
766	188
767	188
768	188
769	188
770	188
771	187
772	187
773	187
774	187
775	187
776	187
777	186
778	186
779	186
780	186
781	186
782	185
783	185
784	185
785	185
786	185
787	185
788	184
789	184
790	184
791	184

792	184
793	183
794	183
795	183
796	183
797	183
798	183
799	182
800	182
801	182
802	182
803	182
804	182
805	181
806	181
807	181
808	181
809	181
810	181
811	180
812	180
813	180
814	180
815	180
816	180
817	179
818	179
819	179
820	179
821	179
822	179
823	178
824	178
825	178
826	178
827	178
828	178
829	177
830	177
831	177
832	177
833	177
834	177
835	176

836	176
837	176
838	176
839	176
840	176
841	175
842	175
843	175
844	175
845	175
846	175
847	174
848	174
849	174
850	174
851	174
852	174
853	174
854	173
855	173
856	173
857	173
858	173
859	173
860	172
861	172
862	172
863	172
864	172
865	172
866	172
867	171
868	171
869	171
870	171
871	171
872	171
873	170
874	170
875	170
876	170
877	170
878	170
879	170

880	169
881	169
882	169
883	169
884	169
885	169
886	169
887	168
888	168
889	168
890	168
891	168
892	168
893	168
894	167
895	167
896	167
897	167
898	167
899	167
900	167
901	166
902	166
903	166
904	166
905	166
906	166
907	166
908	165
909	165
910	165
911	165
912	165
913	165
914	165
915	164
916	164
917	164
918	164
919	164
920	164
921	164
922	163
923	163

924	163
925	163
926	163
927	163
928	163
929	163
930	162
931	162
932	162
933	162
934	162
935	162
936	162
937	161
938	161
939	161
940	161
941	161
942	161
943	161
944	161
945	160
946	160
947	160
948	160
949	160
950	160
951	160
952	160
953	159
954	159
955	159
956	159
957	159
958	159
959	159
960	158
961	158
962	158
963	158
964	158
965	158
966	158
967	158

968	157
969	157
970	157
971	157
972	157
973	157
974	157
975	157
976	156
977	156
978	156
979	156
980	156
981	156
982	156
983	156
984	156
985	155
986	155
987	155
988	155
989	155
990	155
991	155
992	155
993	154
994	154
995	154
996	154
997	154
998	154
999	154
1000	154
1001	153
1002	153
1003	153
1004	153
1005	153
1006	153
1007	153
1008	153
1009	153
1010	152
1011	152

1012	152
1013	152
1014	152
1015	152
1016	152
1017	152
1018	152
1019	151
1020	151
1021	151
1022	151
1023	151
1024	151
1025	151
1026	151
1027	151
1028	150
1029	150
1030	150
1031	150
1032	150
1033	150
1034	150
1035	150
1036	149
1037	149
1038	149
1039	149
1040	149
1041	149
1042	149
1043	149
1044	149
1045	149
1046	148
1047	148
1048	148
1049	148
1050	148
1051	148
1052	148
1053	148
1054	148
1055	147

1056	147
1057	147
1058	147
1059	147
1060	147
1061	147
1062	147
1063	147
1064	146
1065	146
1066	146
1067	146
1068	146
1069	146
1070	146
1071	146
1072	146
1073	146
1074	145
1075	145
1076	145
1077	145
1078	145
1079	145
1080	145
1081	145
1082	145
1083	144
1084	144
1085	144
1086	144
1087	144
1088	144
1089	144
1090	144
1091	144
1092	144
1093	143
1094	143
1095	143
1096	143
1097	143
1098	143
1099	143

1100	143
1101	143
1102	143
1103	142
1104	142
1105	142
1106	142
1107	142
1108	142
1109	142
1110	142
1111	142
1112	142
1113	142
1114	141
1115	141
1116	141
1117	141
1118	141
1119	141
1120	141
1121	141
1122	141
1123	141
1124	140
1125	140
1126	140
1127	140
1128	140
1129	140
1130	140
1131	140
1132	140
1133	140
1134	139
1135	139
1136	139
1137	139
1138	139
1139	139
1140	139
1141	139
1142	139
1143	139

1144	139
1145	138
1146	138
1147	138
1148	138
1149	138
1150	138
1151	138
1152	138
1153	138
1154	138
1155	138
1156	137
1157	137
1158	137
1159	137
1160	137
1161	137
1162	137
1163	137
1164	137
1165	137
1166	137
1167	136
1168	136
1169	136
1170	136
1171	136
1172	136
1173	136
1174	136
1175	136
1176	136
1177	136
1178	135
1179	135
1180	135
1181	135
1182	135
1183	135
1184	135
1185	135
1186	135
1187	135

1188	135
1189	135
1190	134
1191	134
1192	134
1193	134
1194	134
1195	134
1196	134
1197	134
1198	134
1199	134



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

03/31/2025

APD ID: 10400096625

Submission Date: 02/15/2024

Highlighted data
reflects the most
recent changes

Operator Name: MACK ENERGY CORPORATION

Well Name: BROCKVILLE FEDERAL

Well Number: 1H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
15317013	RUSTLER	3731	175	175	ALLUVIUM	NONE	N
15317014	TOP OF SALT	3323	408	408	SALT	NONE	N
15317015	BASE OF SALT	3071	660	660	SALT	NONE	N
15317016	YATES	2925	806	806	ANHYDRITE, SILTSTONE	NATURAL GAS, OIL	N
15317017	SEVEN RIVERS	2691	1040	1040	ANHYDRITE, SILTSTONE	NATURAL GAS, OIL	N
15317018	QUEEN	2194	1537	1537	ANHYDRITE, SILTSTONE	NATURAL GAS, OIL	N
15317019	GRAYBURG	1803	1928	1928	ANHYDRITE, DOLOMITE, SILTSTONE	NATURAL GAS, OIL	N
15317020	SAN ANDRES	1483	2248	2248	ANHYDRITE, DOLOMITE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 3M

Rating Depth: 8724

Equipment: Rotating Head, Mud Gas Separator

Requesting Variance? NO

Variance request:

Testing Procedure: The BOP/BOPE test shall include a low pressure test of 250 to 300psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 mins without a test plug. The estimated bottom hole at TD is 120 degrees and estimated maximum bottom hole pressure is 1482psig (0.052*3097*TVD*9.2) less than 2900 bottom hole pressure. Well test to 2000psi for 30 mins.

Choke Diagram Attachment:

NEW_Choke_Manifold_3M_20240109111922.pdf

BOP Diagram Attachment:

NEW_BOP_3M_20240109111930.pdf

Operator Name: MACK ENERGY CORPORATION

Well Name: BROCKVILLE FEDERALWell Number: 1H

NEW_Choke_Manifold_3M_20240109111922.pdf

NEW_BOP_3M_20240109111930.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	200	0	200	3731	3531	200	J-55	48	ST&C	7.412	4.701	BUOY	52.87	BUOY	4.74
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	1200	0	1200	0	2531	1200	J-55	36	LT&C	3.237	7.04	BUOY	10.768	BUOY	7.04
3	PRODUCTION	8.75	7.0	NEW	API	N	0	3200	0	2992	0	739	3200	HCP-110	26	BUTT	4.551	3.317	BUOY	5.686	BUOY	3.317
4	PRODUCTION	8.75	5.5	NEW	API	N	3200	8724	2992	3097	739	634	5524	HCP-110	17	BUTT	5.375	3.547	BUOY	7.141	BUOY	3.547

Casing Attachments

Casing ID: 1StringSURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Surface_20240827112618.pdf

Operator Name: MACK ENERGY CORPORATION

Well Name: BROCKVILLE FEDERAL

Well Number: 1H

Casing Attachments

Casing ID: 2

String

INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Intermediate_20240827112830.pdf

Casing ID: 3

String

PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Production_20240827113007.pdf

Casing ID: 4

String

PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Production_20240827113324.pdf

Section 4 - Cement

Operator Name: MACK ENERGY CORPORATION**Well Name:** BROCKVILLE FEDERAL**Well Number:** 1H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Lead		0	0	0	0	0	0		0	0

SURFACE	Lead		0	200	100	2.31	14.4	139		RFC+12% PF53+2%PF1+5p psPF42+.125pps PF29	20bbls Gelled Water 50sx of 11# Scavenger Cement
SURFACE	Tail		0	200	200	1.34	14.8	139	100	Class C+1% PF1	20bbls Gelled Water 50sx of 11# Scavenger Cement
INTERMEDIATE	Lead		0	1200	225	1.72	13.5	417	100	Class C+ 45 PF20+.4pps PF45+.125 PF29	20bbls Gelled Water 50sx of 11# Scavenger Cement
INTERMEDIATE	Tail		0	1200	200	1.34	14.8	417	100	Class C + 1% PF 1	20bbls Gelled Water 50sx of 11# Scavenger Cement
PRODUCTION	Lead		0	8724	250	2.82	13.5	2228	35	Class C 4% PF20 + 4pps PF 45+125pps PF 29	20bbls Gelled Water 20bbls Chemical Wash 50sx of 11# Scavenger Cement
PRODUCTION	Tail		0	8824	1740	1.34	14.2	2228	35	50/50 Poz C + 5% (BWOW) PF44 +2% PF204+.2% PF606+.1% PF153+.4ppsPF4 4	20bbls Chemical Wash 50sx of 11# Scavenger Cement

Section 5 - Circulating Medium

Mud System Type: Open**Will an air or gas system be Used?** NO**Description of the equipment for the circulating system in accordance with 43 CFR 3172:****Diagram of the equipment for the circulating system in accordance with 43 CFR 3172:****Describe what will be on location to control well or mitigate other conditions:** Bope Brine Water**Describe the mud monitoring system utilized:** Parson PVT with PVT Volume Recorder

Circulating Medium Table

Operator Name: MACK ENERGY CORPORATION**Well Name:** BROCKVILLE FEDERAL**Well Number:** 1H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	400	SPUD MUD	8.5	10	74.8	0.1	11		12000	15	
400	1200	LSND/GEL	8.3	9.2	74.8	0.1	11		12000	15	
1200	8723	LSND/GEL	8.3	9.2	74.8	0.1	11		12000	15	The estimated bottom hole at TD is 120 degrees and estimated bottom hole pressure is 1482 (0.052*3097' TVD*9.2)

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

None

List of open and cased hole logs run in the well:

CNL/FDC,COMPENSATED DENSILOG,GAMMA RAY LOG,DUAL LATERAL LOG/MICRO-SPHERICALLY FOCUSED,

Coring operation description for the well:

None

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 1482

Anticipated Surface Pressure: 800

Anticipated Bottom Hole Temperature(F): 95

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? NO

Hydrogen sulfide drilling operations

Operator Name: MACK ENERGY CORPORATION

Well Name: BROCKVILLE FEDERAL

Well Number: 1H

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Brockville_Federal__1H_Preliminary_Horizontal_Well_Plan_1_20240826121936.pdf

Natural_Gas_Management_Plan_20240826122001.pdf

Escape_Route_20240826122022.pdf

KOP_20240826122114.pdf

Drilling_Plan_20240905085002.pdf

H2S_Plan_20240905085013.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

Other Variance attachment:


Variance_request_20240109143945.pdf

Cactus_Wellhead_installation_Procedure_20240109143956.pdf

Flex_Hose_Cert_20240109144017.pdf


Choke Manifold

3000 PSI WP



BOP Diagram

Dual Ram BOP
3000 PSI WP



Casing Design

Well:

Brockville Federal #1H

String Size & Function:

7"x 5 1/2" in

Production

x

Total Depth:

8724 ft

TVD:

3070 ft

Pressure Gradient for Calculations

(While drilling)

Mud weight, collapse:

10 #/gal

Safety Factor Collapse:

1.125

Mud weight, burst:

10 #/gal

Safety Factor Burst:

1.25

Mud weight for joint strength:

10 #/gal

Safety Factor Joint Strength

1.8

BHP @ TD for:

collapse:

1596.4 psi

Burst:

1596.4 psi,

joint strength:

1596.4 psi

Partially evacuated hole?

Pressure gradient remaining:

10 #/gal

Max. Shut in surface pressure:

3000 psi

1st segment	8724 ft	to	3200 ft	Make up Torque ft-lbs	Total ft =	5524
O.D.	Weight	Grade	Threads	opt.	min.	mx.
5.5 inches	17 #/ft	HCP-110	Buttress	4,620	3,470	5,780
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
8,580 psi	10,640 psi-lrcr	568 ,000 #	546 ,000 #	4.767		

2nd segment	3200 ft	to	0 ft	Make up Torque ft-lbs	Total ft =	3200
O.D.	Weight	Grade	Threads	opt.	min.	mx.
7 inches	26 #/ft	HCP-110	Buttress	6,930	5,200	8,660
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
7,800 psi	9,950 psi-lrcr	853 ,000 #	830 ,000 #	6.151		

3rd segment	0 ft	to	0 ft	Make up Torque ft-lbs	Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.
0 inches	0 #/ft	0	0	0	0	0
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
0 psi	0 psi	0 ,000 #	0 ,000 #	0		

4th segment	0 ft	to	0 ft	Make up Torque ft-lbs	Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.
inches	#/ft					
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
psi	psi	,000 #	,000 #			

5th segment	0 ft	to	0 ft	Make up Torque ft-lbs	Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.
inches	#/ft					
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
psi	psi	,000 #	,000 #			

6th segment	0 ft	to	0 ft	Make up Torque ft-lbs	Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.
inches	#/ft					
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
psi	psi	,000 #	,000 #			

Select	1st segment bottom	8724	S.F.	Actual	Desire
			collapse	5.374593	>= 1.125
	8724 ft to 3200 ft		burst-b	3.546667	>= 1.25
	5.5 0 HCP-110 Buttress		burst-t	3.546667	
	Top of segment 1 (ft)	3200	S.F.	Actual	Desire
Select	2nd segment from bottom		collapse	4.550593	>= 1.125
			burst-b	3.316667	>= 1.25
	3200 ft to 0 ft		burst-t	3.316667	
	7 26 HCP-110 Buttress		jnt strngth	7.141054	>= 1.8

Top of segment 2 (ft)				0	S.F.	Actual		Desire
Select	3rd segment from bottom				collapse	#DIV/0!	>=	1.125
					burst-b	0	>=	1.25
	0 ft	to	0 ft		burst-t	0		
	0	0	0	0	jnt strngth	5.68627	>=	1.8
Top of segment 3 (ft)				0	S.F.	Actual		Desire
Select	4th segment from bottom				collapse	#DIV/0!	>=	1.125
					burst-b	0	>=	1.25
	0 ft	to	0 ft		burst-t	0		
	0	0	0	0	jnt strngth	0	>=	1.8
Top of segment 4 (ft)					S.F.	Actual		Desire
Select	5th segment from bottom				collapse	#DIV/0!	>=	1.125
					burst-b	0	>=	1.25
	0 ft	to	ft		burst-t	0		
	0	0	0	0	jnt strngth	0	>=	1.8
Top of segment 5 (ft)					S.F.	Actual		Desire
Select	6th segment from bottom				collapse	#DIV/0!	>=	1.125
					burst-b	0	>=	1.25
	0 ft	to	ft		burst-t	0		
	0	0	0	0	jnt strngth	0	>=	1.8
Top of segment 6 (ft)					jnt strngth		>=	1.8

use in colapse calculations across different pressured formations

Three gradient pressure function

Depth of evaluation:

1,200 ft

516

psi @

1,200 ft

Top of salt:

2,400 ft

fx #1

516

Base of salt:

3,700 ft

fx #2

900

TD of intermediate:

4,600 ft

fx #3

540

Pressure gradient to be used above each top to be used as a function of depth. ex. psi/ft

fx #1

fx #2

fx #3

0.43

0.75

0.45

- 1) Calculate neutral point for buckling with temperature affects computed also
- 2) Surface burst calculations & kick tolerance in surface pressure for burst
- 3) Do a comparison test to determine which value is lower joint strength or body yield to use in tensile strength calculations
- 4) Raise joint strength safety factor up to next level on page #2
- 5) Sour service what pipe can be used with proper degrading of strength factors and as function of temp

Adjust for best combination of safety factors

		Secondary
S.F. Collapse bottom of segment:		
S.F. Collapse top of segment:		4.90968
S.F. Burst bottom of segment:		
S.F. Burst top of segment		
S.F. Joint strength bottom of segment:		795.518
S.F. Joint strength top of segment:		
S.F. Body yield strength bottom of segment:		764.706
S.F. Body yield strength top of segment:		6.86446

Collapse calculations for 1st segment - casing evacuated

Buoyancy factor collapse:	0.847	
calculations for bottom of segment @	3070 ft	
hydrostatic pressure collapse - backside:	1596.4 psi	
Axial load @ bottom of section	0 lbs	previous segments
Axial load factor:	0	load/(pipe body yield strength)
Collapse strength reduction factor:	1	Messrs, Westcott, Dunlop, Kemler,1940
Adjusted collapse rating of segment:	8580 psi	
Actual safety factor	5.37459	adjusted casing rating / actual pressure

Casing Design

Well: Brockville Federal #1H

String Size & Function:

7"x 5 1/2" in

Production

x

Total Depth:

8724 ft

TVD:

3070 ft

Pressure Gradient for Calculations

(While drilling)

Mud weight, collapse:

10 #/gal

Safety Factor Collapse:

1.125

Mud weight, burst:

10 #/gal

Safety Factor Burst:

1.25

Mud weight for joint strength:

10 #/gal

Safety Factor Joint Strength

1.8

BHP @ TD for:

collapse:

1596.4 psi

Burst:

1596.4 psi

joint strength:

1596.4 psi

Partially evacuated hole?

Pressure gradient remaining:

10 #/gal

Max. Shut in surface pressure:

3000 psi

1st segment	8724 ft	to	3200 ft	Make up Torque ft-lbs	Total ft =	5524
O.D.	Weight	Grade	Threads	opt.	min.	mx.
5.5 inches	17 #/ft	HCP-110	Buttress	4,620	3,470	5,780
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
8,580 psi	10,640 psi-lrcr	568 ,000 #	546 ,000 #	4.767		

2nd segment	3200 ft	to	0 ft	Make up Torque ft-lbs	Total ft =	3200
O.D.	Weight	Grade	Threads	opt.	min.	mx.
7 inches	26 #/ft	HCP-110	Buttress	6,930	5,200	8,660
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
7,800 psi	9,950 psi-lrcr	853 ,000 #	830 ,000 #	6.151		

3rd segment	0 ft	to	0 ft	Make up Torque ft-lbs	Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.
0 inches	0 #/ft	0	0	0	0	0
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
0 psi	0 psi	0 ,000 #	0 ,000 #	0		

4th segment	0 ft	to	0 ft	Make up Torque ft-lbs	Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.
inches	#/ft					
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
psi	psi	,000 #	,000 #			

5th segment	0 ft	to	0 ft	Make up Torque ft-lbs	Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.
inches	#/ft					
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
psi	psi	,000 #	,000 #			

6th segment	0 ft	to	0 ft	Make up Torque ft-lbs	Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.
inches	#/ft					
Collapse Resistance	Internal Yield	Joint Strength	Body Yield	Drift		
psi	psi	,000 #	,000 #			

Select	1st segment bottom	8724	S.F.	Actual	Desire
			collapse	5.374593	>= 1.125
	8724 ft to 3200 ft		burst-b	3.546667	>= 1.25
	5.5 0 HCP-110 Buttress		burst-t	3.546667	
	Top of segment 1 (ft)	3200	S.F.	Actual	Desire
Select	2nd segment from bottom		collapse	4.550593	>= 1.125
			burst-b	3.316667	>= 1.25
	3200 ft to 0 ft		burst-t	3.316667	
	7 26 HCP-110 Buttress		jnt strngth	7.141054	>= 1.8

Top of segment 2 (ft)				0	S.F.	Actual		Desire
Select	3rd segment from bottom				collapse	#DIV/0!	>=	1.125
					burst-b	0	>=	1.25
	0 ft	to	0 ft		burst-t	0		
	0	0	0	0	jnt strngth	5.68627	>=	1.8
Top of segment 3 (ft)				0	S.F.	Actual		Desire
Select	4th segment from bottom				collapse	#DIV/0!	>=	1.125
					burst-b	0	>=	1.25
	0 ft	to	0 ft		burst-t	0		
	0	0	0	0	jnt strngth	0	>=	1.8
Top of segment 4 (ft)					S.F.	Actual		Desire
Select	5th segment from bottom				collapse	#DIV/0!	>=	1.125
					burst-b	0	>=	1.25
	0 ft	to	ft		burst-t	0		
	0	0	0	0	jnt strngth	0	>=	1.8
Top of segment 5 (ft)					S.F.	Actual		Desire
Select	6th segment from bottom				collapse	#DIV/0!	>=	1.125
					burst-b	0	>=	1.25
	0 ft	to	ft		burst-t	0		
	0	0	0	0	jnt strngth	0	>=	1.8
Top of segment 6 (ft)					jnt strngth		>=	1.8

use in colapse calculations across different pressured formations

Three gradient pressure function

Depth of evaluation:

1,200 ft

516

psi @

1,200 ft

Top of salt:

2,400 ft

fx #1

516

Base of salt:

3,700 ft

fx #2

900

TD of intermediate:

4,600 ft

fx #3

540

Pressure gradient to be used above each top to be used as a function of depth. ex. psi/ft

fx #1

fx #2

fx #3

0.43

0.75

0.45

- 1) Calculate neutral point for buckling with temperature affects computed also
- 2) Surface burst calculations & kick tolerance in surface pressure for burst
- 3) Do a comparison test to determine which value is lower joint strength or body yield to use in tensile strength calculations
- 4) Raise joint strength safety factor up to next level on page #2
- 5) Sour service what pipe can be used with proper degrading of strength factors and as function of temp

Adjust for best combination of safety factors

		Secondary
S.F. Collapse bottom of segment:		
S.F. Collapse top of segment:		4.90968
S.F. Burst bottom of segment:		
S.F. Burst top of segment		
S.F. Joint strength bottom of segment:		795.518
S.F. Joint strength top of segment:		
S.F. Body yield strength bottom of segment:		764.706
S.F. Body yield strength top of segment:		6.86446

Collapse calculations for 1st segment - casing evacuated

Buoyancy factor collapse:	0.847	
calculations for bottom of segment @	3070 ft	
hydrostatic pressure collapse - backside:	1596.4 psi	
Axial load @ bottom of section	0 lbs	previous segments
Axial load factor:	0	load/(pipe body yield strength)
Collapse strength reduction factor:	1	Messrs, Westcott, Dunlop, Kemler,1940
Adjusted collapse rating of segment:	8580 psi	
Actual safety factor	5.37459	adjusted casing rating / actual pressure

Casing DesignWell: Brockville Federal #1H

String Size & Function:13 3/8 in surface x intermediate

Total Depth:200 ft

Pressure Gradient for Calculations(While drilling)

Mud weight, collapse:9.6 #/gal Safety Factor Collapse:1.125

Mud weight, burst:9.6 #/gal Safety Factor Burst:1.25

Mud weight for joint strength:9.6 #/gal Safety Factor Joint Strength1.8

BHP @ TD for:collapse:99.84 psi Burst:99.84 psi, joint strength:99.84 psi

Partially evacuated hole? Pressure gradient remaining:10 #/gal

Max. Shut in surface pressure:500 psi

1st segment	200 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	200
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
13.375 inches	48 #/ft	J-55	ST&C	3,220	2,420	4,030		
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
740	2,370 psi	433 ,000 #		744 ,000 #		12.559		

2nd segment	0 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
inches	#/ft							
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
psi	psi	,000 #		,000 #				

3rd segment	0 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
inches	#/ft							
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
psi	psi	,000 #		,000 #				

4th segment	0 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
inches	#/ft							
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
psi	psi	,000 #		,000 #				

5th segment	0 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
inches	#/ft							
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
psi	psi	,000 #		,000 #				

6th segment	0 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
inches	#/ft							
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
psi	psi	,000 #		,000 #				

Select	1st segment bottom	200	S.F.	Actual	Desire
			collapse	7.411859	>= 1.125
	200 ft to 0 ft		burst-b	4.700889	>= 1.25
	13.375 0 J-55 ST&C		burst-t	4.74	
	Top of segment 1 (ft)	0	S.F.	Actual	Desire
Select	2nd segment from bottom		collapse	#DIV/0!	>= 1.125
			burst-b	0	>= 1.25
	0 ft to 0 ft		burst-t	0	
	0 0 0 0		jnt strngth	52.86966	>= 1.8

Casing DesignWell: Brockville Federal #1H

String Size & Function:9 5/8 in surface intermediate x

Total Depth:1,200 ft TVD:1,200 ft

Pressure Gradient for Calculations(While drilling)

Mud weight, collapse:10 #/gal Safety Factor Collapse:1.125

Mud weight, burst:10 #/gal Safety Factor Burst:1.25

Mud weight for joint strength:10 #/gal Safety Factor Joint Strength1.8

BHP @ TD for:collapse:624 psi Burst:624 psi, joint strength:624 psi

Partially evacuated hole? Pressure gradient remaining:10 #/gal

Max. Shut in surface pressure:500 psi

1st segment	1200 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	1200
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
9.625 inches	36 #/ft	J-55	LT&C	3,940	2,960	4,930		
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
2,020 psi	3,520 psi	394 ,000 #		564 ,000 #		8.765		

2nd segment	ft	to	ft	Make up Torque ft-lbs			Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
inches	#/ft							
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
psi	psi	,000 #		,000 #				

3rd segment	0 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
inches	#/ft							
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
psi	psi	,000 #		,000 #				

4th segment	0 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
inches	#/ft							
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
psi	psi	,000 #		,000 #				

5th segment	0 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
inches	#/ft							
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
psi	psi	,000 #		,000 #				

6th segment	0 ft	to	0 ft	Make up Torque ft-lbs			Total ft =	0
O.D.	Weight	Grade	Threads	opt.	min.	mx.		
inches	#/ft							
Collapse Resistance	Internal Yield	Joint Strength		Body Yield		Drift		
psi	psi	,000 #		,000 #				

Select	1st segment bottom	1200	S.F.	Actual	Desire
			collapse	3.237179	>= 1.125
	1200 ft to 0 ft		burst-b	7.04	>= 1.25
	9.625 0 J-55 LT&C		burst-t	7.04	
	Top of segment 1 (ft)	0	S.F.	Actual	Desire
Select	2nd segment from bottom		collapse	#DIV/0!	>= 1.125
			burst-b	0	>= 1.25
	0 ft to 0 ft		burst-t	0	
	0 0 0 0		jnt strngth	10.76785	>= 1.8

Attached to Form 3160-3
Mack Energy Corporation
Brockville Federal #1H NM-105294478
SHL : 667 FSL & 1650 FWL, SESW, Sec. 7 T15S R29E
BHL : 1 FSL & 1650 FWL, SESW, Sec. 18 T15S R29E
Chaves County, NM

DRILLING PROGRAM

1. Geologic Name of Surface Formation

Quaternary

2. Estimated Tops of Important Geologic Markers:

Rustler	175'
Top Salt	408'
Base of Salt	660'
Yates	806'
Seven Rivers	1,040'
Queen	1,537'
Grayburg	1,928'
San Andres	2,248'

3. Estimated Depths of Anticipated Fresh Water, Oil and Gas:

Water Sand	150'	Fresh Water
Yates	806'	Oil/Gas
Seven Rivers	1,040'	Oil/Gas
Queen	1,537'	Oil/Gas
Grayburg	1,928'	Oil/Gas
San Andres	2,248'	Oil/Gas

No other formations are expected to give up oil, gas or fresh water in measurable quantities. Setting 13 3/8" casing to 200' and circulating cement back to surface will protect the surface fresh water sand. Salt section and shallower zones above TD, which contain commercial quantities of oil and/or gas, will have cement circulated across them by cementing 5 1/2" production casing, sufficient cement will be pumped to circulate back to surface.

4. Casing Program:

Hole Size	Interval	OD Casing	Wt, Grade, Jt, cond, collapse/burst/tension
17 1/2"	0-200'	13 3/8"	48#, J-55, ST&C, New, 7.411859/4.700889/4.74
12 1/4"	0-1200'	9 5/8"	36#, J-55, LT&C, New, 3.237179/7.04/7.04
8 3/4"	0-3200'	7"	26#,HCP-110, Buttress, New, 4.550593/3.316667/3.316667
8 3/4"	3200-8724'	5 1/2"	17#, HCP-110 Buttress, New, 5.374593/3.546667/3.546667

Variance request: A variance is requested to use a Multi Bowl System and Flex Hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturer's certification and pressure test will be kept on the rig.

5. Cement Program:

Attached to Form 3160-3
Mack Energy Corporation
Brockville Federal #1H NM-105294478
SHL : 667 FSL & 1650 FWL, SESW, Sec. 7 T15S R29E
BHL : 1 FSL & 1650 FWL, SESW, Sec. 18 T15S R29E
Chaves County, NM

13 3/8" Surface Casing: Lead 100sx, RFC+12%PF53+2%PF1+5ppsPF42+.125ppsPF29, yld 2.31, wt 14.4 ppg, 7.357gals/sx. Tail: 200sx, Class C+1% PF1, yld 1.34, wt 14.8 ppg, 6.323 gals/sx, excess 100%

9 5/8" Intermediate Casing: Lead 225sx Class C + 45 PF20+.4ppsPF45+.125pps PF29, yld 1.72, wt 13.5 ppg, 9.102gal/sx, excess 100%, Slurry Top Surface. Tail: 200sx Class C+1%PF1, yld 1.34, wt 14.8 ppg, 6.323 gals/sx, excess 100%, Slurry Top Surface.

7" & 5 1/2" Production Casing: Lead 250sx Class C 4% PF20 +4 pps PF45+125pps PF29, yld 2.82, wt 13.5 ppg, 16.421gals/sx, excess 35%, Slurry Top Surface. Tail 1,740sx, 50/50 POZ/C 5% PF44+2%PF204+.2%PF606+.1%PF153+4ppsPF44, yld 1.34, wt 14.2, 6.091gals/sx, 35% excess, Slurry top 2,000'.

6. Minimum Specifications for Pressure Control:

The blowout preventer equipment (BOP) shown in Exhibit #10 will consist of a double ram-type (3000 psi WP) minimum preventer. This unit will be hydraulically operated and the ram type preventer will be equipped with blind rams on top of 4 1/2" drill pipe rams on bottom. The 11" BOP will be nipped up on the 8 5/8" surface casing and tested by a 3rd party to 2000 psi used continuously until TD is reached. All BOP's and accessory equipment will be tested to 2000 psi before drilling out of intermediate casing. Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment (Exhibit #10) will include a Kelly cock and floor safety valve and choke lines and choke manifold (Exhibit #11) with a minimum 3000 psi WP rating

7. Types and Characteristics of the Proposed Mud System:

The well will be drilled to TD with a combination of fresh and cut brine mud system. The applicable depths and properties of this system are as follows:

DEPTH	TYPE	WEIGHT	VISCOSITY	WATERLOSS
0-200'	Fresh Water	8.5	28	N.C.
200-1200'	Cut Brine	9.1	29	N.C.
1200'-TD	Cut Brine	9.1	29	N.C.

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept at the well site at all times.

8. Auxiliary Well Control and Monitoring Equipment:

- A. Kelly cock will be kept in the drill string at all times.
- B. A full opening drill pipe-stabbing valve with proper drill pipe connections will be on the rig floor at all times.

9. Logging, Testing and Coring Program:

Attached to Form 3160-3
Mack Energy Corporation
Brockville Federal #1H NM-105294478
SHL : 667 FSL & 1650 FWL, SESW, Sec. 7 T15S R29E
BHL : 1 FSL & 1650 FWL, SESW, Sec. 18 T15S R29E
Chaves County, NM

- A. The electric logging program will consist of GR-Dual Laterolog, Spectral Density, Dual Spaced Neutron, CSNG Log from T.D. to 8 5/8 casing shoe.
- B. Drill Stem test is not anticipated.
- C. No conventional coring is anticipated.
- D. Further testing procedures will be determined at TD.

10. Abnormal Conditions, Pressures, Temperatures and Potential Hazards:

No abnormal pressures or temperatures are anticipated. The estimated bottom hole at TD is 120 degrees and estimated maximum bottom hole pressure is 1482 psig (0.052*3,097'TVD*9.2). Low levels of Hydrogen sulfide have been monitors in producing wells in the area, so H2S may be present while drilling of the well; a plan is attached to the Drilling program. No major loss of circulation zones has been reported in offsetting wells.

11. Anticipated Starting Date and Duration of Operations:

Road and location work will not begin until approval has been received from the BLM. The anticipated spud date is January 1, 2025. Once commenced, the drilling operation should be finished in approximately 20 days. If the well is productive, an additional 30 days will be required for completion and testing before a decision is made to install permanent facilities.

Attachment to Exhibit #10
NOTES REGARDING THE BLOWOUT PREVENTERS
Brockville Federal #1H
Chaves County, New Mexico

- 1. Drilling nipple to be so constructed that it can be removed without use of a welder through rotary table opening, with minimum I.D. equal to preventer bore.
- 2. Wear ring to be properly installed in head.
- 3. Blow out preventer and all fittings must be in good condition, 2000 psi WP minimum.
- 4. All fittings to be flanged.
- 5. Safety valve must be available on rig floor at all times with proper connections, valve to be full 2000 psi WP minimum.
- 6. All choke and fill lines to be securely anchored especially ends of choke lines.
- 7. Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
- 8. Kelly cock on Kelly.
- 9. Extension wrenches and hands wheels to be properly installed.

Attached to Form 3160-3

Mack Energy Corporation

Brockville Federal #1H NM-105294478

SHL : 667 FSL & 1650 FWL, SESW, Sec. 7 T15S R29E


BHL : 1 FSL & 1650 FWL, SESW, Sec. 18 T15S R29E

Chaves County, NM

-
10. Blow out preventer control to be located as close to driller's position as feasible.
 11. Blow out preventer closing equipment to include minimum 40-gallon accumulator, two independent sources of pump power on each closing unit installation all API specifications.

Choke Manifold


3000 PSI WP



BOP Diagram

Dual Ram BOP

3000 PSI WP



Brockville Federal #1H, Plan 1

Operator	Mack Energy Corp	Units	feet, °/100ft	07:45 Monday, August 26, 2024	Page 1 of 4
Field	Round Tank	County	Chaves	Vertical Section Azimuth	179.57
Well Name	Brockville Federal #1H	State	New Mexico	Survey Calculation Method	Minimum Curvature
Plan	1	Country	USA	Database	Access

Location	SL: 667 FSL & 1650 FWL Sec 7-T15S-R29E BHL: 1 FSL & 1650 FWL Sec 18-T15S-R29E			Map Zone	UTM	Lat Long Ref	
Site				Surface X	1925103.1	Surface Long	
Slot Name		UWI		Surface Y	11989020.5	Surface Lat	
Well Number	#1H	API		Surface Z	3748.8	Global Z Ref	KB
Project		MD/TVD Ref	KB	Ground Level	3731.3	Local North Ref	Grid

DIRECTIONAL WELL PLAN

MD*	INC*	AZI*	TVD*	N*	E*	DLS*	V. S.*	MapE*	MapN*	SysTVD*
ft	deg	deg	ft	ft	ft	°/100ft	ft	ft	ft	ft
*** TIE (at MD = 2165.00)										
2165.00	0.00	0.0	2165.00	0.00	0.00		0.00	1925103.10	11989020.50	1583.80
2200.00	0.00	0.0	2200.00	0.00	0.00	0.00	0.00	1925103.10	11989020.50	1548.80
2250.00	0.00	0.0	2250.00	0.00	0.00	0.00	0.00	1925103.10	11989020.50	1498.80
*** KOP 8 DEGREE (at MD = 2265.00)										
2265.00	0.00	0.0	2265.00	0.00	0.00	0.00	0.00	1925103.10	11989020.50	1483.80
2300.00	2.80	179.6	2299.99	-0.86	0.01	8.00	0.86	1925103.11	11989019.65	1448.81
2350.00	6.80	179.6	2349.80	-5.04	0.04	8.00	5.04	1925103.14	11989015.46	1399.00
2400.00	10.80	179.6	2399.20	-12.69	0.10	8.00	12.69	1925103.20	11989007.81	1349.60
2450.00	14.80	179.6	2447.95	-23.76	0.18	8.00	23.76	1925103.28	11988996.74	1300.85
2500.00	18.80	179.6	2495.81	-38.21	0.29	8.00	38.21	1925103.39	11988982.29	1252.99
2550.00	22.80	179.6	2542.54	-55.96	0.42	8.00	55.96	1925103.52	11988964.54	1206.26
2600.00	26.80	179.6	2587.92	-76.93	0.58	8.00	76.93	1925103.68	11988943.57	1160.88
2650.00	30.80	179.6	2631.72	-101.01	0.76	8.00	101.01	1925103.86	11988919.49	1117.08
2700.00	34.80	179.6	2673.74	-128.09	0.96	8.00	128.09	1925104.06	11988892.41	1075.06
2750.00	38.80	179.6	2713.77	-158.03	1.19	8.00	158.04	1925104.29	11988862.47	1035.03
2800.00	42.80	179.6	2751.61	-190.70	1.43	8.00	190.70	1925104.53	11988829.80	997.19
2850.00	46.80	179.6	2787.09	-225.92	1.70	8.00	225.93	1925104.80	11988794.58	961.71
2900.00	50.80	179.6	2820.01	-263.53	1.98	8.00	263.54	1925105.08	11988756.97	928.79
2950.00	54.80	179.6	2850.24	-303.35	2.28	8.00	303.36	1925105.38	11988717.15	898.56
*** 55 DEGREE TANGENT (at MD = 2952.50)										
2952.50	55.00	179.6	2851.67	-305.39	2.29	8.00	305.40	1925105.39	11988715.11	897.13
3000.00	55.00	179.6	2878.92	-344.30	2.58	0.00	344.31	1925105.68	11988676.20	869.88
3050.00	55.00	179.6	2907.60	-385.26	2.89	0.00	385.27	1925105.99	11988635.24	841.20
3100.00	55.00	179.6	2936.28	-426.22	3.20	0.00	426.23	1925106.30	11988594.28	812.52
3150.00	55.00	179.6	2964.96	-467.17	3.51	0.00	467.19	1925106.61	11988553.33	783.84
*** 10 DEGREE BUILD (at MD = 3152.50)										
3152.50	55.00	179.6	2966.39	-469.22	3.52	0.00	469.23	1925106.62	11988551.28	782.41
3200.00	59.75	179.6	2991.99	-509.21	3.82	10.00	509.23	1925106.92	11988511.29	756.81
3250.00	64.75	179.6	3015.26	-553.45	4.15	10.00	553.46	1925107.25	11988467.05	733.54
3300.00	69.75	179.6	3034.59	-599.54	4.50	10.00	599.56	1925107.60	11988420.96	714.21
3350.00	74.75	179.6	3049.83	-647.14	4.86	10.00	647.16	1925107.96	11988373.36	698.97
3400.00	79.75	179.6	3060.86	-695.90	5.22	10.00	695.91	1925108.32	11988324.60	687.94
3450.00	84.75	179.6	3067.60	-745.42	5.59	10.00	745.44	1925108.69	11988275.08	681.20
*** LANDING POINT (at MD = 3499.50)										
3499.50	89.70	179.6	3070.00	-794.85	5.97	10.00	794.87	1925109.07	11988225.65	678.80
3500.00	89.70	179.6	3070.00	-795.35	5.97	0.00	795.37	1925109.07	11988225.15	678.80
3550.00	89.70	179.6	3070.26	-845.34	6.34	0.00	845.37	1925109.44	11988175.16	678.54
3600.00	89.70	179.6	3070.53	-895.34	6.72	0.00	895.37	1925109.82	11988125.16	678.27

Brockville Federal #1H, Plan 1										
Operator	Mack Energy Corp			Units	feet, °/100ft		07:45 Monday, August 26, 2024 Page 2 of 4			
Field	Round Tank			County	Chaves		Vertical Section Azimuth 179.57			
Well Name	Brockville Federal #1H			State	New Mexico		Survey Calculation Method Minimum Curvature			
Plan	1			Country	USA		Database Access			
Location	SL: 667 FSL & 1650 FWL Sec 7-T15S-R29E BHL: 1 FSL & 1650 FWL Sec 18-T15S-R29E					Map Zone	UTM		Lat Long Ref	
Site						Surface X	1925103.1		Surface Long	
Slot Name						Surface Y	11989020.5		Surface Lat	
Well Number	#1H					Surface Z	3748.8		Global Z Ref KB	
Project						Ground Level	3731.3		Local North Ref Grid	
MD/TVD Ref KB										
DIRECTIONAL WELL PLAN										
MD*	INC*	AZI*	TVD*	N*	E*	DLS*	V. S.*	MapE*	MapN*	SysTVD*
ft	deg	deg	ft	ft	ft	°/100ft	ft	ft	ft	ft
3650.00	89.70	179.6	3070.79	-945.34	7.09	0.00	945.37	1925110.19	11988075.16	678.01
3700.00	89.70	179.6	3071.05	-995.34	7.47	0.00	995.37	1925110.57	11988025.16	677.75
3750.00	89.70	179.6	3071.31	-1045.34	7.85	0.00	1045.37	1925110.95	11987975.16	677.49
3800.00	89.70	179.6	3071.57	-1095.33	8.22	0.00	1095.36	1925111.32	11987925.17	677.23
3850.00	89.70	179.6	3071.84	-1145.33	8.60	0.00	1145.36	1925111.70	11987875.17	676.96
3900.00	89.70	179.6	3072.10	-1195.33	8.97	0.00	1195.36	1925112.07	11987825.17	676.70
3950.00	89.70	179.6	3072.36	-1245.33	9.35	0.00	1245.36	1925112.45	11987775.17	676.44
4000.00	89.70	179.6	3072.62	-1295.33	9.72	0.00	1295.36	1925112.82	11987725.17	676.18
4050.00	89.70	179.6	3072.88	-1345.32	10.10	0.00	1345.36	1925113.20	11987675.18	675.92
4100.00	89.70	179.6	3073.14	-1395.32	10.47	0.00	1395.36	1925113.57	11987625.18	675.66
4150.00	89.70	179.6	3073.41	-1445.32	10.85	0.00	1445.36	1925113.95	11987575.18	675.39
4200.00	89.70	179.6	3073.67	-1495.32	11.22	0.00	1495.36	1925114.32	11987525.18	675.13
4250.00	89.70	179.6	3073.93	-1545.32	11.60	0.00	1545.36	1925114.70	11987475.18	674.87
4300.00	89.70	179.6	3074.19	-1595.31	11.97	0.00	1595.36	1925115.07	11987425.19	674.61
4350.00	89.70	179.6	3074.45	-1645.31	12.35	0.00	1645.36	1925115.45	11987375.19	674.35
4400.00	89.70	179.6	3074.72	-1695.31	12.72	0.00	1695.36	1925115.82	11987325.19	674.08
4450.00	89.70	179.6	3074.98	-1745.31	13.10	0.00	1745.36	1925116.20	11987275.19	673.82
4500.00	89.70	179.6	3075.24	-1795.30	13.47	0.00	1795.36	1925116.57	11987225.20	673.56
4550.00	89.70	179.6	3075.50	-1845.30	13.85	0.00	1845.35	1925116.95	11987175.20	673.30
4600.00	89.70	179.6	3075.76	-1895.30	14.22	0.00	1895.35	1925117.32	11987125.20	673.04
4650.00	89.70	179.6	3076.02	-1945.30	14.60	0.00	1945.35	1925117.70	11987075.20	672.78
4700.00	89.70	179.6	3076.29	-1995.30	14.97	0.00	1995.35	1925118.07	11987025.20	672.51
4750.00	89.70	179.6	3076.55	-2045.29	15.35	0.00	2045.35	1925118.45	11986975.21	672.25
4800.00	89.70	179.6	3076.81	-2095.29	15.73	0.00	2095.35	1925118.83	11986925.21	671.99
4850.00	89.70	179.6	3077.07	-2145.29	16.10	0.00	2145.35	1925119.20	11986875.21	671.73
4900.00	89.70	179.6	3077.33	-2195.29	16.48	0.00	2195.35	1925119.58	11986825.21	671.47
4950.00	89.70	179.6	3077.59	-2245.29	16.85	0.00	2245.35	1925119.95	11986775.21	671.21
5000.00	89.70	179.6	3077.86	-2295.28	17.23	0.00	2295.35	1925120.33	11986725.22	670.94
5050.00	89.70	179.6	3078.12	-2345.28	17.60	0.00	2345.35	1925120.70	11986675.22	670.68
5100.00	89.70	179.6	3078.38	-2395.28	17.98	0.00	2395.35	1925121.08	11986625.22	670.42
5150.00	89.70	179.6	3078.64	-2445.28	18.35	0.00	2445.35	1925121.45	11986575.22	670.16
5200.00	89.70	179.6	3078.90	-2495.28	18.73	0.00	2495.35	1925121.83	11986525.22	669.90
5250.00	89.70	179.6	3079.17	-2545.27	19.10	0.00	2545.34	1925122.20	11986475.23	669.63
5300.00	89.70	179.6	3079.43	-2595.27	19.48	0.00	2595.34	1925122.58	11986425.23	669.37
5350.00	89.70	179.6	3079.69	-2645.27	19.85	0.00	2645.34	1925122.95	11986375.23	669.11
5400.00	89.70	179.6	3079.95	-2695.27	20.23	0.00	2695.34	1925123.33	11986325.23	668.85
5450.00	89.70	179.6	3080.21	-2745.26	20.60	0.00	2745.34	1925123.70	11986275.24	668.59

Page 2 of 4

SES v5.79

www.makinhole.com

Brockville Federal #1H, Plan 1										
Operator	Mack Energy Corp			Units	feet, °/100ft		07:45 Monday, August 26, 2024 Page 3 of 4			
Field	Round Tank			County	Chaves		Vertical Section Azimuth 179.57			
Well Name	Brockville Federal #1H			State	New Mexico		Survey Calculation Method Minimum Curvature			
Plan	1			Country	USA		Database Access			
Location	SL: 667 FSL & 1650 FWL Sec 7-T15S-R29E BHL: 1 FSL & 1650 FWL Sec 18-T15S-R29E					Map Zone	UTM		Lat Long Ref	
Site						Surface X	1925103.1		Surface Long	
Slot Name	UWI					Surface Y	11989020.5		Surface Lat	
Well Number	#1H					Surface Z	3748.8		Global Z Ref KB	
Project	MD/TVD Ref KB					Ground Level	3731.3		Local North Ref Grid	
DIRECTIONAL WELL PLAN										
MD*	INC*	AZI*	TVD*	N*	E*	DLS*	V. S.*	MapE*	MapN*	SysTVD*
ft	deg	deg	ft	ft	ft	°/100ft	ft	ft	ft	ft
5500.00	89.70	179.6	3080.47	-2795.26	20.98	0.00	2795.34	1925124.08	11986225.24	668.33
5550.00	89.70	179.6	3080.74	-2845.26	21.35	0.00	2845.34	1925124.45	11986175.24	668.06
5600.00	89.70	179.6	3081.00	-2895.26	21.73	0.00	2895.34	1925124.83	11986125.24	667.80
5650.00	89.70	179.6	3081.26	-2945.26	22.10	0.00	2945.34	1925125.20	11986075.24	667.54
5700.00	89.70	179.6	3081.52	-2995.25	22.48	0.00	2995.34	1925125.58	11986025.25	667.28
5750.00	89.70	179.6	3081.78	-3045.25	22.85	0.00	3045.34	1925125.95	11985975.25	667.02
5800.00	89.70	179.6	3082.05	-3095.25	23.23	0.00	3095.34	1925126.33	11985925.25	666.75
5850.00	89.70	179.6	3082.31	-3145.25	23.61	0.00	3145.34	1925126.71	11985875.25	666.49
5900.00	89.70	179.6	3082.57	-3195.25	23.98	0.00	3195.34	1925127.08	11985825.25	666.23
5950.00	89.70	179.6	3082.83	-3245.24	24.36	0.00	3245.34	1925127.46	11985775.26	665.97
6000.00	89.70	179.6	3083.09	-3295.24	24.73	0.00	3295.33	1925127.83	11985725.26	665.71
6050.00	89.70	179.6	3083.35	-3345.24	25.11	0.00	3345.33	1925128.21	11985675.26	665.45
6100.00	89.70	179.6	3083.62	-3395.24	25.48	0.00	3395.33	1925128.58	11985625.26	665.18
6150.00	89.70	179.6	3083.88	-3445.24	25.86	0.00	3445.33	1925128.96	11985575.26	664.92
6200.00	89.70	179.6	3084.14	-3495.23	26.23	0.00	3495.33	1925129.33	11985525.27	664.66
6250.00	89.70	179.6	3084.40	-3545.23	26.61	0.00	3545.33	1925129.71	11985475.27	664.40
6300.00	89.70	179.6	3084.66	-3595.23	26.98	0.00	3595.33	1925130.08	11985425.27	664.14
6350.00	89.70	179.6	3084.93	-3645.23	27.36	0.00	3645.33	1925130.46	11985375.27	663.87
6400.00	89.70	179.6	3085.19	-3695.23	27.73	0.00	3695.33	1925130.83	11985325.27	663.61
6450.00	89.70	179.6	3085.45	-3745.22	28.11	0.00	3745.33	1925131.21	11985275.28	663.35
6500.00	89.70	179.6	3085.71	-3795.22	28.48	0.00	3795.33	1925131.58	11985225.28	663.09
6550.00	89.70	179.6	3085.97	-3845.22	28.86	0.00	3845.33	1925131.96	11985175.28	662.83
6600.00	89.70	179.6	3086.23	-3895.22	29.23	0.00	3895.33	1925132.33	11985125.28	662.57
6650.00	89.70	179.6	3086.50	-3945.21	29.61	0.00	3945.33	1925132.71	11985075.29	662.30
6700.00	89.70	179.6	3086.76	-3995.21	29.98	0.00	3995.33	1925133.08	11985025.29	662.04
6750.00	89.70	179.6	3087.02	-4045.21	30.36	0.00	4045.32	1925133.46	11984975.29	661.78
6800.00	89.70	179.6	3087.28	-4095.21	30.73	0.00	4095.32	1925133.83	11984925.29	661.52
6850.00	89.70	179.6	3087.54	-4145.21	31.11	0.00	4145.32	1925134.21	11984875.29	661.26
6900.00	89.70	179.6	3087.81	-4195.20	31.49	0.00	4195.32	1925134.59	11984825.30	661.00
6950.00	89.70	179.6	3088.07	-4245.20	31.86	0.00	4245.32	1925134.96	11984775.30	660.73
7000.00	89.70	179.6	3088.33	-4295.20	32.24	0.00	4295.32	1925135.34	11984725.30	660.47
7050.00	89.70	179.6	3088.59	-4345.20	32.61	0.00	4345.32	1925135.71	11984675.30	660.21
7100.00	89.70	179.6	3088.85	-4395.20	32.99	0.00	4395.32	1925136.09	11984625.30	659.95
7150.00	89.70	179.6	3089.11	-4445.19	33.36	0.00	4445.32	1925136.46	11984575.31	659.69
7200.00	89.70	179.6	3089.38	-4495.19	33.74	0.00	4495.32	1925136.84	11984525.31	659.42
7250.00	89.70	179.6	3089.64	-4545.19	34.11	0.00	4545.32	1925137.21	11984475.31	659.16
7300.00	89.70	179.6	3089.90	-4595.19	34.49	0.00	4595.32	1925137.59	11984425.31	658.90

Page 3 of 4

SES v5.79

www.makinhole.com

Brockville Federal #1H, Plan 1										
Operator	Mack Energy Corp			Units	feet, °/100ft		07:45 Monday, August 26, 2024 Page 4 of 4			
Field	Round Tank			County	Chaves		Vertical Section Azimuth 179.57			
Well Name	Brockville Federal #1H			State	New Mexico		Survey Calculation Method Minimum Curvature			
Plan	1			Country	USA		Database Access			
Location	SL: 667 FSL & 1650 FWL Sec 7-T15S-R29E BHL: 1 FSL & 1650 FWL Sec 18-T15S-R29E					Map Zone	UTM		Lat Long Ref	
Site						Surface X	1925103.1		Surface Long	
Slot Name	UWI					Surface Y	11989020.5		Surface Lat	
Well Number	#1H			API			Surface Z	3748.8		Global Z Ref KB
Project				MD/TVD Ref	KB		Ground Level	3731.3		Local North Ref Grid
DIRECTIONAL WELL PLAN										
MD*	INC*	AZI*	TVD*	N*	E*	DLS*	V. S.*	MapE*	MapN*	SysTVD*
ft	deg	deg	ft	ft	ft	°/100ft	ft	ft	ft	ft
7350.00	89.70	179.6	3090.16	-4645.19	34.86	0.00	4645.32	1925137.96	11984375.31	658.64
7400.00	89.70	179.6	3090.42	-4695.18	35.24	0.00	4695.32	1925138.34	11984325.32	658.38
7450.00	89.70	179.6	3090.68	-4745.18	35.61	0.00	4745.31	1925138.71	11984275.32	658.12
7500.00	89.70	179.6	3090.95	-4795.18	35.99	0.00	4795.31	1925139.09	11984225.32	657.85
7550.00	89.70	179.6	3091.21	-4845.18	36.36	0.00	4845.31	1925139.46	11984175.32	657.59
7600.00	89.70	179.6	3091.47	-4895.17	36.74	0.00	4895.31	1925139.84	11984125.33	657.33
7650.00	89.70	179.6	3091.73	-4945.17	37.11	0.00	4945.31	1925140.21	11984075.33	657.07
7700.00	89.70	179.6	3091.99	-4995.17	37.49	0.00	4995.31	1925140.59	11984025.33	656.81
7750.00	89.70	179.6	3092.26	-5045.17	37.86	0.00	5045.31	1925140.96	11983975.33	656.54
7800.00	89.70	179.6	3092.52	-5095.17	38.24	0.00	5095.31	1925141.34	11983925.33	656.28
7850.00	89.70	179.6	3092.78	-5145.16	38.61	0.00	5145.31	1925141.71	11983875.34	656.02
7900.00	89.70	179.6	3093.04	-5195.16	38.99	0.00	5195.31	1925142.09	11983825.34	655.76
7950.00	89.70	179.6	3093.30	-5245.16	39.37	0.00	5245.31	1925142.47	11983775.34	655.50
8000.00	89.70	179.6	3093.56	-5295.16	39.74	0.00	5295.31	1925142.84	11983725.34	655.24
8050.00	89.70	179.6	3093.83	-5345.16	40.12	0.00	5345.31	1925143.22	11983675.34	654.97
8100.00	89.70	179.6	3094.09	-5395.15	40.49	0.00	5395.31	1925143.59	11983625.35	654.71
8150.00	89.70	179.6	3094.35	-5445.15	40.87	0.00	5445.31	1925143.97	11983575.35	654.45
8200.00	89.70	179.6	3094.61	-5495.15	41.24	0.00	5495.30	1925144.34	11983525.35	654.19
8250.00	89.70	179.6	3094.87	-5545.15	41.62	0.00	5545.30	1925144.72	11983475.35	653.93
8300.00	89.70	179.6	3095.14	-5595.15	41.99	0.00	5595.30	1925145.09	11983425.35	653.66
8350.00	89.70	179.6	3095.40	-5645.14	42.37	0.00	5645.30	1925145.47	11983375.36	653.40
8400.00	89.70	179.6	3095.66	-5695.14	42.74	0.00	5695.30	1925145.84	11983325.36	653.14
8450.00	89.70	179.6	3095.92	-5745.14	43.12	0.00	5745.30	1925146.22	11983275.36	652.88
8500.00	89.70	179.6	3096.18	-5795.14	43.49	0.00	5795.30	1925146.59	11983225.36	652.62
8550.00	89.70	179.6	3096.44	-5845.14	43.87	0.00	5845.30	1925146.97	11983175.37	652.36
8600.00	89.70	179.6	3096.71	-5895.13	44.24	0.00	5895.30	1925147.34	11983125.37	652.09
8650.00	89.70	179.6	3096.97	-5945.13	44.62	0.00	5945.30	1925147.72	11983075.37	651.83
8700.00	89.70	179.6	3097.23	-5995.13	44.99	0.00	5995.30	1925148.09	11983025.37	651.57
*** TD (at MD = 8723.50)										
8723.50	89.70	179.6	3097.35	-6018.63	45.17	0.00	6018.80	1925148.27	11983001.87	651.45

Page 4 of 4

SES v5.79

www.makinhole.com

PECOS DISTRICT DRILLING OPERATIONS CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Mack Energy Corporation
LEASE NO.:	NMNM-105294478
WELL NAME & NO.:	Brockville Federal 1H
SURFACE HOLE FOOTAGE:	0707' FNL & 1650' FWL
BOTTOM HOLE FOOTAGE:	0001' FNL & 1650' FWL Sec. 18, T. 15 S., R 29 E.
LOCATION:	Section 19, T. 15 S., R 29 E., NMPM
COUNTY:	Chaves County, New Mexico

The Gamma Ray and Neutron well logs must be run from total depth to surface and e-mailed to McKitric Wier at mwier@blm.gov or hard copy mailed to 2909 West Second Street Roswell, NM 88201 to his attention.

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Chaves and Roosevelt Counties**

Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.

During office hours call (575) 627-0272.

After hours cll (575) 627-0205.

A. Hydrogen Sulfide

1. **Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.

4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least **8 hours**. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

High Cave/Karst

Possibility of water flows in the Rustler, Queen, Salado, and Artesia Group.

Possibility of lost circulation in the Rustler, Artesia Group, and San Andres.

1. The **13-3/8** inch surface casing shall be set at approximately **400** feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9-5/8** inch intermediate casing is:
- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

3. The minimum required fill of cement behind the **7 X 5-1/2** inch production casing is:
- ☒ Cement to surface. If cement does not circulate, contact the appropriate BLM office.
4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).

2. **Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 3000 (3M) psi (testing to 2,000 psi).**
 - a. **Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.**
 - b. **If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.**
 - c. **Manufacturer representative shall install the test plug for the initial BOP test.**
 - d. **Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.**
 - e. **If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.**
3. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer.**
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - d. The results of the test shall be reported to the appropriate BLM office.
 - e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**

- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 05152024

Attached to Form 3160-3
Mack Energy Corporation
Brockville Federal #1H NM-105294478
SHL : 667 FSL & 1650 FWL, SESW, Sec. 7 T15S R29E
BHL : 1 FSL & 1650 FWL, SESW, Sec. 18 T15S R29E
Chaves County, NM

Mack Energy Corporation Onshore Order #6 Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H₂S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H₂S detectors alarms warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S on metal components. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan. **The concentrations of H₂S of wells in this area from surface to TD are low enough that a contingency plan is not required.**

II. H₂S SAFETY EQUIPMENT AND SYSTEMS

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonable expected to contain H₂S.

1. Well Control Equipment:

- A. Flare line.
- B. Choke manifold.
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
- D. Auxiliary equipment may include if applicable: annular preventer & rotating head.

Attached to Form 3160-3
Mack Energy Corporation
Brockville Federal #1H NM-105294478
SHL : 667 FSL & 1650 FWL, SESW, Sec. 7 T15S R29E
BHL : 1 FSL & 1650 FWL, SESW, Sec. 18 T15S R29E
Chaves County, NM

2. Protective equipment for essential personnel:

- A. Mark II Survive air 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

3. H2S detection and monitoring equipment:

- A. 1 portable H2S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 PPM are reached.

4. Visual warning systems:

- A. Wind direction indicators as shown on well site diagram (Exhibit #8).
- B. Caution/Danger signs (Exhibit #7) shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.

5. Mud program:

- A. The mud program has been designed to minimize the volume of H2S circulated to surface. Proper mud weight, safe drilling practices and the use of H2S scavengers will minimize hazards when penetrating H2S bearing zones.

6. Metallurgy:

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- B. All elastomers used for packing and seals shall be H2S trim.

7. Communication:

- A. Radio communications in company vehicles including cellular telephone and 2-way radio.
- B. Land line (telephone) communication at Office.

8. Well testing:

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safely and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H2S environment will use the closed chamber method of testing.

Attached to Form 3160-3
Mack Energy Corporation
Brockville Federal #1H NM-105294478
SHL : 667 FSL & 1650 FWL, SESW, Sec. 7 T15S R29E
BHL : 1 FSL & 1650 FWL, SESW, Sec. 18 T15S R29E
Chaves County, NM

B. There will be no drill stem testing.

EXHIBIT #7


WARNING

**YOU ARE ENTERING AN H2S
AUTHORIZED PERSONNEL ONLY**

1. BEARDS OR CONTACT LENSES NOT ALLOWED
2. HARD HATS REQUIRED
3. SMOKING IN DESIGNATED AREAS ONLY
4. BE WIND CONSCIOUS AT ALL TIMES
5. CHECK WITH MACK ENERGY FOREMAN AT OFFICE

MACK ENERGY CORPORATION


1-575-748-1288



DRILLING LOCATION H2S SAFTY EQUIPMENT

Exhibit # 8

Location Layout



Silver Oak Drilling ~ 10 Bilco Road, Artesia, NM 88210 ~ 575.746.4405
info@silveroakdrilling.com ~ www.silveroakdrilling.com

Mack Energy Corporation Call List, Chaves County

Artesia (575)	Cellular	Office
Jim Krogman.....	432-934-1596.....	748-1288
Emilio Martinez.....	432-934-7586.....	748-1288

Agency Call List (575)**Roswell**

State Police.....	622-7200
City Police.....	624-6770
Sheriff's Office.....	624-7590
Ambulance.....	624-7590
Fire Department.....	624-7590
LEPC (Local Emergency Planning Committee.....	624-6770
NMOCD.....	748-1283
Bureau of Land Management.....	627-0272

Emergency Services

Boots & Coots IWC.....	1-800-256-9688 or (281)931-8884
Cudd pressure Control.....	(915)699-0139 or (915)563-3356
Halliburton.....	746-2757
Par Five.....	748-9539
Flight For Life-Lubbock, TX.....	(806)743-9911
Aerocare-Lubbock, TX.....	(806)747-8923
Med Flight Air Amb-Albuquerque, NM.....	(505)842-4433
Lifeguard Air Med Svc. Albuquerque, NM.....	(505)272-3115

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024	
		Submittal Type:	<input checked="" type="checkbox"/> Initial Submittal
			<input type="checkbox"/> Amended Report
			<input type="checkbox"/> As Drilled

WELL LOCATION INFORMATION

API Number	Pool Code 52770	Pool Name Round Tank; San Andres
Property Code	Property Name BROCKVILLE FEDERAL	Well Number 1H
OGRID No. 13837	Operator Name MACK ENERGY CORPORATION	Ground Level Elevation 3731.3
Surface Owner: <input type="checkbox"/> State <input type="checkbox"/> Fee <input type="checkbox"/> Tribal <input checked="" type="checkbox"/> Federal		Mineral Owner: <input type="checkbox"/> State <input type="checkbox"/> Fee <input type="checkbox"/> Tribal <input checked="" type="checkbox"/> Federal

Surface Location

UL N	Section 7	Township 15 S	Range 29 E	Lot	Ft. from N/S 667 SOUTH	Ft. from E/W 1650 WEST	Latitude 33.0250625°N	Longitude 104.0713791°W	County CHAVES
---------	--------------	------------------	---------------	-----	---------------------------	---------------------------	--------------------------	----------------------------	------------------

Bottom Hole Location

UL N	Section 18	Township 15 S	Range 29 E	Lot	Ft. from N/S 1 SOUTH	Ft. from E/W 1650 WEST	Latitude 33.0085945°N	Longitude 104.0712955°W	County CHAVES
---------	---------------	------------------	---------------	-----	-------------------------	---------------------------	--------------------------	----------------------------	------------------

Dedicated Acres 160	Infill or Defining Well	Defining Well API	Overlapping Spacing Unit (Y/N)	Consolidation Code
Order Numbers.			Well setbacks are under Common Ownership: <input type="checkbox"/> Yes <input type="checkbox"/> No	

Kick Off Point (KOP)

UL N	Section 7	Township 15 S	Range 29 E	Lot	Ft. from N/S 667 SOUTH	Ft. from E/W 1650 WEST	Latitude 33.0250625°N	Longitude 104.0713791°W	County CHAVES
---------	--------------	------------------	---------------	-----	---------------------------	---------------------------	--------------------------	----------------------------	------------------

First Take Point (FTP)

UL C	Section 18	Township 15 S	Range 29 E	Lot	Ft. from N/S 100 NORTH	Ft. from E/W 1650 WEST	Latitude 33.0229548°N	Longitude 104.0713810°W	County CHAVES
---------	---------------	------------------	---------------	-----	---------------------------	---------------------------	--------------------------	----------------------------	------------------

Last Take Point (LTP)

UL N	Section 18	Township 15 S	Range 29 E	Lot	Ft. from N/S 100 SOUTH	Ft. from E/W 1650 WEST	Latitude 33.0088665°N	Longitude 104.0712976°W	County CHAVES
---------	---------------	------------------	---------------	-----	---------------------------	---------------------------	--------------------------	----------------------------	------------------

Unitized Area or Area of Uniform Interest	Spacing Unit Type <input type="checkbox"/> Horizontal <input type="checkbox"/> Vertical	Ground Floor Elevation:
---	---	-------------------------

OPERATOR CERTIFICATIONS

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest run leased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order here to fore entered by the division.

If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.

Deana Weaver

8/26/2024

Signature

Date

Deana Weaver

Printed Name

dweaver@mec.com

Email Address

SURVEYOR CERTIFICATIONS

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.



Signature and Seal of Professional Surveyor

FILIMON F. JARAMILLO

Certificate Number

Date of Survey

PLS 12797

JUNE 13, 2024

SURVEY NO. 9919A

Note: No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

03/31/2025

APD ID: 10400096625

Submission Date: 02/15/2024

Highlighted data
reflects the most
recent changes

Operator Name: MACK ENERGY CORPORATION

Well Name: BROCKVILLE FEDERAL

Well Number: 1H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
15317013	RUSTLER	3731	175	175	ALLUVIUM	NONE	N
15317014	TOP OF SALT	3323	408	408	SALT	NONE	N
15317015	BASE OF SALT	3071	660	660	SALT	NONE	N
15317016	YATES	2925	806	806	ANHYDRITE, SILTSTONE	NATURAL GAS, OIL	N
15317017	SEVEN RIVERS	2691	1040	1040	ANHYDRITE, SILTSTONE	NATURAL GAS, OIL	N
15317018	QUEEN	2194	1537	1537	ANHYDRITE, SILTSTONE	NATURAL GAS, OIL	N
15317019	GRAYBURG	1803	1928	1928	ANHYDRITE, DOLOMITE, SILTSTONE	NATURAL GAS, OIL	N
15317020	SAN ANDRES	1483	2248	2248	ANHYDRITE, DOLOMITE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 3M

Rating Depth: 8724

Equipment: Rotating Head, Mud Gas Separator

Requesting Variance? NO

Variance request:

Testing Procedure: The BOP/BOPE test shall include a low pressure test of 250 to 300psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 mins without a test plug. The estimated bottom hole at TD is 120 degrees and estimated maximum bottom hole pressure is 1482psig (0.052*3097*TVD*9.2) less than 2900 bottom hole pressure. Well test to 2000psi for 30 mins.

Choke Diagram Attachment:


NEW_Choke_Manifold_3M_20240109111922.pdf

BOP Diagram Attachment:

NEW_BOP_3M_20240109111930.pdf

Choke Manifold


3000 PSI WP



BOP Diagram

Dual Ram BOP

3000 PSI WP



Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/oed/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 447538

CONDITIONS

Operator: MACK ENERGY CORP P.O. Box 960 Artesia, NM 882110960	OGRID: 13837
	Action Number: 447538
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
dweaver	Cement is required to circulate on both surface and intermediate1 strings of casing.	4/1/2025
dweaver	If cement does not circulate on any string, a Cement Bond Log (CBL) is required for that string of casing.	4/1/2025
ward.rikala	Notify the OCD 24 hours prior to casing & cement.	5/16/2025
ward.rikala	File As Drilled C-102 and a directional Survey with C-104 completion packet.	5/16/2025
ward.rikala	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string.	5/16/2025
ward.rikala	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.	5/16/2025