

Santa Fe Main Office Phone: (505) 476-3441 Fax: (55) 476-3462 General Information Phone: (505) 629-6116 Online Phone Directory Visit: https://www.emnrd.nm.gov/ocd/contact-us/	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	C-104 Revised July 9, 2024 Submit Electronically Via OCD Permitting
--	--	---

REQUEST FOR ALLOWABLE AND AUTHORIZATION TO TRANSPORT**Section 1 - Operator and Well Information**

Submittal Type: ☐ Test Allowable (C-104RT) ☒ New Well (C-104NW) ☐ Recomplete (C-104RC) ☐ Pay Add (C-104RC) ☐ Amended	
Operator Name: Permian Resources Operating, LLC	OGRID: 372165
Property Name and Well Number: klondike 9 State Com 133H	Property Code: 334778
Mineral Owner: ☒ State ☐ Fee ☐ Tribal ☐ Federal	API Number: 30-0 15-54318
Pool Name: Winchester; Bone Spring, West	Pool Code: 97569

Section 2 – Surface Location

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
I	9	19S	28E		1473 South	458 East	32.671953	-104.174059	Eddy

Section 3 – Completion Information

Producing Method	Ready Date	Perforations MD	Perforations TVD
Gas Lift	9/24/24	8908 - 18,640	8547 - 8309

Section 4 – Action IDs for Submissions and Order Numbers

List Action IDs for Drilling Sundries	Was an Order required / needed (Y/N), if yes list Order number:
C-104 RT Action ID (if C-104NW):	Communitization Agreement ☒ Yes ☐ No, Order No. Pending
Surface Casing Action ID: 365600	Unit: ☐ Yes ☒ No, Order No.
Intermediate 1 Casing Action ID: 366566	Compulsory Pooling: ☒ Yes ☐ No, Order No. R-23050
Intermediate 2 Casing Action ID:	Down Hole Commingling: ☐ Yes ☒ No, Order No.
Production Casing Action ID: 376295	Surface Commingling: ☐ Yes ☒ No, Order No.
All casing was pressure tested in accordance with NMAC ☒ Yes ☐ No	Non-standard Location: ☐ Yes ☒ No ☒ Common ownership Order No.
Liner 1 Action ID:	Non-standard Proration: ☐ Yes ☒ No, Order No.
Casing was installed prior to OCD's Action ID system (Y/N):	Simultaneous Dedication: ☐ Yes ☒ No, Order No.

Section 5 - Operator Signature and Certification

☒ I hereby certify that the required Water Use Report has been, or will be, submitted for this well's completion.	
☒ I hereby certify that the required Fracfocus disclosure has been, or will be, submitted for this well's completion.	
☒ I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.	
Name Kanicia Schlichting	PH 432-400-0185
Title Regulatory Specialist	Date 11/7/24

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024	
		Submittal Type:	☐ Initial Submittal
			☒ Amended Report
			☒ As Drilled

WELL LOCATION INFORMATION

API Number 30-015-54318	Pool Code 97569	Pool Name WINCHESTER; BONE SPRING, WEST
Property Code 334778	Property Name KLONDIKE 9 STATE COM	Well Number 133H
OGRID No. 372165	Operator Name PERMIAN RESOURCES OPERATING, LLC	Ground Level Elevation 3,540.0'
Surface Owner: ☒ State ☐ Fee ☐ Tribal ☐ Federal		Mineral Owner: ☒ State ☐ Fee ☐ Tribal ☐ Federal

Surface Location

UL I	Section 9	Township 19S	Range 28E	Lot	Ft. from N/S 1,473 SOUTH	Ft. from E/W 458 EAST	Latitude (NAD 83) 32.671953°	Longitude (NAD 83) -104.174059°	County EDDY
---------	--------------	-----------------	--------------	-----	-----------------------------	--------------------------	---------------------------------	------------------------------------	----------------

Bottom Hole Location

UL L	Section 8	Township 19S	Range 28E	Lot	Ft. from N/S 2,297 SOUTH	Ft. from E/W 56 WEST	Latitude (NAD 83) 32.673953°	Longitude (NAD 83) -104.206142°	County EDDY
---------	--------------	-----------------	--------------	-----	-----------------------------	-------------------------	---------------------------------	------------------------------------	----------------

Dedicated Acres 320	Infill or Defining Well Infill	Defining Well API 30-015-54316	Overlapping Spacing Unit (Y/N) N	Consolidation Code C, F
Order Numbers. R-23050		Well setbacks are under Common Ownership: ☒ Yes ☐ No		

Kick Off Point (KOP)

UL I	Section 9	Township 19S	Range 28E	Lot	Ft. from N/S 2,282 SOUTH	Ft. from E/W 44 EAST	Latitude (NAD 83) 32.674188°	Longitude (NAD 83) -104.172713°	County EDDY
---------	--------------	-----------------	--------------	-----	-----------------------------	-------------------------	---------------------------------	------------------------------------	----------------


First Take Point (FTP)

UL I	Section 9	Township 19S	Range 28E	Lot	Ft. from N/S 2,342 SOUTH	Ft. from E/W 552 EAST	Latitude (NAD 83) 32.674338°	Longitude (NAD 83) -104.174362°	County EDDY
---------	--------------	-----------------	--------------	-----	-----------------------------	--------------------------	---------------------------------	------------------------------------	----------------

Last Take Point (LTP)


UL L	Section 8	Township 19S	Range 28E	Lot	Ft. from N/S 2,299 SOUTH	Ft. from E/W 117 WEST	Latitude (NAD 83) 32.673960°	Longitude (NAD 83) -104.205944°	County EDDY
---------	--------------	-----------------	--------------	-----	-----------------------------	--------------------------	---------------------------------	------------------------------------	----------------

Unitized Area or Area of Uniform Interest	Spacing Unit Type ☒ Horizontal ☐ Vertical	Ground Floor Elevation: 3570
---	--	------------------------------

OPERATOR CERTIFICATIONS <i>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest or unleased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</i> <i>If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.</i> K. Schlichting 11/7/24	SURVEYOR CERTIFICATIONS <i>I hereby certify that the well location shown on this plat was plotted from the field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</i>  Signature and Seal of Professional Surveyor 23782 July 10, 2023 Certificate Number Date of Survey
Signature Kanicia Schlichting Printed Name kanicia.schlichting@permianres.com Email Address	

Note: No allowable will be assigned to this completion until all interest have been consolidated or a non-standard unit has been approved by the division.

Property Name KLONDIKE 9 STATE COM	Well Number 133H	Drawn By N.R. 10-21-24	Revised By
---------------------------------------	---------------------	---------------------------	------------



NAD 83 (SURFACE HOLE LOCATION)	FOOTAGE
LATITUDE = 32°40'19.03" (32.671953°)	1,473' FSL
LONGITUDE = -104°10'26.61" (-104.174059°)	458' FEL
NAD 27 (SURFACE HOLE LOCATION)	
LATITUDE = 32°40'18.61" (32.671836°)	
LONGITUDE = -104°10'24.78" (-104.173550°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 608224.27' E: 590347.17'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 608162.10' E: 549167.50'	


NAD 83 (AS-COMPLETED KOP)	FOOTAGE
LATITUDE = 32°40'27.08" (32.674188°)	2,282' FSL
LONGITUDE = -104°10'21.77" (-104.172713°)	44' FEL
NAD 27 (AS-COMPLETED KOP)	
LATITUDE = 32°40'26.66" (32.674072°)	
LONGITUDE = -104°10'19.93" (-104.172204°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 609038.17' E: 590760.02'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 608975.98' E: 549580.37'	

NAD 83 (AS-COMPLETED FTP)	FOOTAGE
LATITUDE = 32°40'27.62" (32.674338°)	2,342' FSL
LONGITUDE = -104°10'27.70" (-104.174362°)	552' FEL
NAD 27 (AS-COMPLETED FTP)	
LATITUDE = 32°40'27.20" (32.674222°)	
LONGITUDE = -104°10'25.87" (-104.173853°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 609092.05' E: 590252.57'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 609029.86' E: 549072.92'	

NAD 83 (AS-COMPLETED LTP)	FOOTAGE
LATITUDE = 32°40'26.26" (32.673960°)	2,299' FSL
LONGITUDE = -104°12'21.40" (-104.205944°)	117' FWL
NAD 27 (AS-COMPLETED LTP)	
LATITUDE = 32°40'25.84" (32.673844°)	
LONGITUDE = -104°12'19.56" (-104.205434°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 608941.29' E: 580535.22'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 608879.18' E: 539355.56'	

NAD 83 (AS-COMPLETED BHL)	FOOTAGE
LATITUDE = 32°40'26.23" (32.673953°)	2,297' FSL
LONGITUDE = -104°12'22.11" (-104.206142°)	56' FWL
NAD 27 (AS-COMPLETED BHL)	
LATITUDE = 32°40'25.81" (32.673837°)	
LONGITUDE = -104°12'20.27" (-104.205632°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 608938.77' E: 580474.33'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 608876.66' E: 539294.66'	

APPROXIMATE WELLBORE MEASURED DEPTH DISTANCE FROM FTP TO LTP	
TRACT	DISTANCE
SECTION 9	4,655.08'
SECTION 8	5,076.92'
TOTAL	9,732.00'



- = SURFACE HOLE LOCATION
 - ◆ = AS-COMPLETED KICK OFF POINT/TAKE POINT
 - = AS-COMPLETED BOTTOM HOLE LOCATION
 - ▲ = SECTION CORNER LOCATED
 - = HORIZONTAL SPACING UNIT
 - = AS-COMPLETED WELLBORE
- N.O.W. = NORTH OF WELL
E.O.W. = EAST OF WELL
W.O.W. = WEST OF WELL

NOTE:

- Distances referenced on plat to section lines are perpendicular.
- Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD 83)
- As-Completed well head has not been field verified.
- Wellbore data provided by Permian Resources Operating, LLC.





Permian Resources Operating, LLC

Eddy County, NM (NAD 83 NME)

Klondike 9 State Com Pad - S9 T19S R28E

Klondike 9 State Com 133H

ST01

Design: ST01 AWB

Standard Survey Report

15 August, 2024



Company:	Permian Resources Operating, LLC	Local Co-ordinate Reference:	Well Klondike 9 State Com 133H
Project:	Eddy County, NM (NAD 83 NME)	TVD Reference:	KB @ 3566.0usft (H&P 602)
Site:	Klondike 9 State Com Pad - S9 T19S R28E	MD Reference:	KB @ 3566.0usft (H&P 602)
Well:	Klondike 9 State Com 133H	North Reference:	Grid
Wellbore:	ST01	Survey Calculation Method:	Minimum Curvature
Design:	ST01 AWB	Database:	EDM 5000.15 Single User Db

Project	Eddy County, NM (NAD 83 NME)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site						Klondike 9 State Com Pad - S9 T19S R28E											
Site Position:			Northing:			608,356.24 usft			Latitude:			32° 40' 20.336 N					
From:			Map			Easting:			590,346.78 usft			Longitude:			104° 10' 26.615 W		
Position Uncertainty:			0.0 usft			Slot Radius:			13-3/16 "			Grid Convergence:			0.09 °		

Well	Klondike 9 State Com 133H					
Well Position	+N/-S	0.0 usft	Northing:	608,224.27 usft	Latitude:	32° 40' 19.030 N
	+E/-W	0.0 usft	Easting:	590,347.17 usft	Longitude:	104° 10' 26.613 W
Position Uncertainty		0.0 usft	Wellhead Elevation:	usft	Ground Level:	3,540.0 usft

Wellbore	ST01				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM	07/15/24	6.82	60.26	47,413.16312706

Design	ST01 AWB				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	8,091.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)	
	0.0	0.0	0.0	269.36	

Survey Program	Date	08/15/24			
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description	
175.0	8,091.0	Intrepid MWD (OWB)	MWD+IFR1+MS	OWSG MWD + IFR1 + Multi-Station Correction	
8,154.0	18,701.0	MWD (ST01)	MWD	OWSG MWD - Standard	

Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
175.0	0.70	193.50	175.0	-1.0	-0.2	0.3	0.40	0.40	0.00
273.0	0.78	212.47	273.0	-2.2	-0.7	0.8	0.26	0.08	19.36
367.0	0.89	247.44	367.0	-3.0	-1.8	1.8	0.55	0.12	37.20
457.0	0.83	259.27	457.0	-3.4	-3.1	3.1	0.21	-0.07	13.14
548.0	0.63	220.41	548.0	-3.9	-4.0	4.1	0.57	-0.22	-42.70
637.0	0.80	243.52	637.0	-4.5	-4.9	4.9	0.37	0.19	25.97
727.0	0.77	225.97	726.9	-5.2	-5.9	6.0	0.27	-0.03	-19.50
818.0	0.95	257.32	817.9	-5.8	-7.1	7.1	0.55	0.20	34.45
908.0	1.18	250.79	907.9	-6.3	-8.7	8.7	0.29	0.26	-7.26



Intrepid Survey Report



Company:	Permian Resources Operating, LLC	Local Co-ordinate Reference:	Well Klondike 9 State Com 133H
Project:	Eddy County, NM (NAD 83 NME)	TVD Reference:	KB @ 3566.0usft (H&P 602)
Site:	Klondike 9 State Com Pad - S9 T19S R28E	MD Reference:	KB @ 3566.0usft (H&P 602)
Well:	Klondike 9 State Com 133H	North Reference:	Grid
Wellbore:	ST01	Survey Calculation Method:	Minimum Curvature
Design:	ST01 AWB	Database:	EDM 5000.15 Single User Db

Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
998.0	0.73	219.05	997.9	-7.1	-9.9	10.0	0.75	-0.50	-35.27
1,088.0	0.44	188.09	1,087.9	-7.8	-10.3	10.4	0.47	-0.32	-34.40
1,182.0	0.88	204.11	1,181.9	-8.9	-10.7	10.8	0.50	0.47	17.04
1,277.0	0.57	208.02	1,276.9	-9.9	-11.2	11.3	0.33	-0.33	4.12
1,371.0	0.51	197.98	1,370.9	-10.8	-11.5	11.7	0.12	-0.06	-10.68
1,465.0	0.33	41.95	1,464.9	-11.0	-11.5	11.6	0.88	-0.19	-165.99
1,560.0	2.23	42.30	1,559.9	-9.4	-10.1	10.2	2.00	2.00	0.37
1,654.0	3.70	32.37	1,653.7	-5.5	-7.2	7.3	1.65	1.56	-10.56
1,749.0	5.79	27.18	1,748.4	1.4	-3.4	3.4	2.24	2.20	-5.46
1,843.0	7.79	25.65	1,841.7	11.3	1.6	-1.7	2.14	2.13	-1.63
1,937.0	8.71	26.49	1,934.8	23.5	7.5	-7.7	0.99	0.98	0.89
2,032.0	8.34	26.63	2,028.7	36.1	13.8	-14.2	0.39	-0.39	0.15
2,126.0	9.17	26.80	2,121.6	48.8	20.2	-20.8	0.88	0.88	0.18
2,221.0	10.28	29.39	2,215.2	63.0	27.8	-28.5	1.26	1.17	2.73
2,315.0	9.88	29.19	2,307.8	77.3	35.8	-36.7	0.43	-0.43	-0.21
2,409.0	9.58	29.47	2,400.4	91.2	43.6	-44.6	0.32	-0.32	0.30
2,504.0	9.65	29.83	2,494.1	105.0	51.5	-52.6	0.10	0.07	0.38
2,598.0	10.08	28.04	2,586.7	119.1	59.3	-60.6	0.56	0.46	-1.90
2,693.0	9.67	28.22	2,680.3	133.4	66.9	-68.4	0.43	-0.43	0.19
2,787.0	9.25	27.87	2,773.0	147.1	74.2	-75.8	0.45	-0.45	-0.37
2,823.0	9.10	27.53	2,808.6	152.2	76.9	-78.6	0.44	-0.42	-0.94
2,953.0	9.01	27.49	2,937.0	170.3	86.3	-88.2	0.07	-0.07	-0.03
3,050.0	10.67	24.29	3,032.5	185.2	93.5	-95.6	1.80	1.71	-3.30
3,144.0	11.32	23.00	3,124.8	201.6	100.7	-103.0	0.74	0.69	-1.37
3,238.0	11.14	23.47	3,217.0	218.5	107.9	-110.4	0.21	-0.19	0.50
3,333.0	11.07	22.93	3,310.2	235.3	115.1	-117.8	0.13	-0.07	-0.57
3,427.0	10.76	24.25	3,402.5	251.6	122.3	-125.1	0.42	-0.33	1.40
3,521.0	10.48	24.90	3,494.9	267.4	129.5	-132.4	0.32	-0.30	0.69
3,616.0	10.11	24.42	3,588.4	282.8	136.5	-139.7	0.40	-0.39	-0.51
3,710.0	9.52	25.51	3,681.0	297.3	143.3	-146.6	0.66	-0.63	1.16
3,804.0	8.88	26.63	3,773.8	310.8	149.9	-153.4	0.71	-0.68	1.19
3,898.0	8.70	23.61	3,866.7	323.8	156.0	-159.6	0.53	-0.19	-3.21
3,993.0	9.01	21.10	3,960.6	337.3	161.6	-165.3	0.52	0.33	-2.64
4,087.0	9.57	28.41	4,053.3	351.1	167.9	-171.8	1.39	0.60	7.78
4,181.0	11.01	32.96	4,145.8	365.5	176.5	-180.6	1.76	1.53	4.84
4,275.0	10.76	33.78	4,238.1	380.3	186.3	-190.5	0.31	-0.27	0.87
4,370.0	10.54	27.06	4,331.5	395.4	195.2	-199.6	1.33	-0.23	-7.07
4,464.0	10.57	24.79	4,423.9	410.9	202.7	-207.3	0.44	0.03	-2.41
4,558.0	10.18	25.92	4,516.4	426.2	209.9	-214.7	0.47	-0.41	1.20
4,653.0	9.85	27.32	4,609.9	441.0	217.3	-222.3	0.43	-0.35	1.47
4,747.0	9.74	29.70	4,702.5	455.0	225.0	-230.0	0.45	-0.12	2.53
4,842.0	9.29	31.05	4,796.2	468.6	232.9	-238.1	0.53	-0.47	1.42
4,936.0	8.81	32.06	4,889.1	481.2	240.6	-246.0	0.54	-0.51	1.07

Company:	Permian Resources Operating, LLC	Local Co-ordinate Reference:	Well Klondike 9 State Com 133H
Project:	Eddy County, NM (NAD 83 NME)	TVD Reference:	KB @ 3566.0usft (H&P 602)
Site:	Klondike 9 State Com Pad - S9 T19S R28E	MD Reference:	KB @ 3566.0usft (H&P 602)
Well:	Klondike 9 State Com 133H	North Reference:	Grid
Wellbore:	ST01	Survey Calculation Method:	Minimum Curvature
Design:	ST01 AWB	Database:	EDM 5000.15 Single User Db

Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,031.0	9.09	28.88	4,982.9	493.9	248.1	-253.6	0.60	0.29	-3.35
5,125.0	9.40	24.70	5,075.7	507.4	254.9	-260.6	0.79	0.33	-4.45
5,220.0	9.32	24.07	5,169.4	521.4	261.3	-267.1	0.14	-0.08	-0.66
5,314.0	10.34	24.95	5,262.0	536.0	268.0	-273.9	1.10	1.09	0.94
5,408.0	10.52	26.99	5,354.5	551.3	275.4	-281.6	0.44	0.19	2.17
5,502.0	9.72	26.55	5,447.0	566.1	282.9	-289.2	0.86	-0.85	-0.47
5,596.0	10.38	22.14	5,539.6	581.0	289.6	-296.1	1.08	0.70	-4.69
5,690.0	10.37	21.58	5,632.1	596.7	295.9	-302.6	0.11	-0.01	-0.60
5,785.0	9.48	21.96	5,725.6	611.9	302.0	-308.8	0.94	-0.94	0.40
5,879.0	9.25	27.33	5,818.4	625.8	308.3	-315.3	0.96	-0.24	5.71
5,973.0	9.91	32.10	5,911.1	639.4	316.1	-323.2	1.10	0.70	5.07
6,068.0	8.24	35.98	6,004.9	651.8	324.4	-331.7	1.87	-1.76	4.08
6,162.0	10.36	28.13	6,097.6	664.7	332.4	-339.8	2.62	2.26	-8.35
6,256.0	8.67	27.96	6,190.3	678.5	339.7	-347.3	1.80	-1.80	-0.18
6,351.0	8.89	23.66	6,284.2	691.5	346.0	-353.7	0.73	0.23	-4.53
6,445.0	8.09	21.64	6,377.2	704.3	351.4	-359.2	0.91	-0.85	-2.15
6,539.0	8.58	24.36	6,470.2	716.8	356.7	-364.7	0.67	0.52	2.89
6,634.0	7.97	25.24	6,564.2	729.3	362.4	-370.5	0.66	-0.64	0.93
6,728.0	6.42	29.67	6,657.5	739.7	367.8	-376.0	1.75	-1.65	4.71
6,917.0	7.21	24.50	6,845.1	759.7	377.9	-386.4	0.53	0.42	-2.74
7,011.0	7.08	22.50	6,938.4	770.4	382.6	-391.2	0.30	-0.14	-2.13
7,106.0	6.21	24.09	7,032.8	780.5	387.0	-395.6	0.94	-0.92	1.67
7,200.0	4.63	27.84	7,126.3	788.5	390.8	-399.6	1.72	-1.68	3.99
7,294.0	3.77	31.83	7,220.1	794.5	394.2	-403.0	0.97	-0.91	4.24
7,389.0	3.34	41.14	7,314.9	799.2	397.7	-406.6	0.76	-0.45	9.80
7,483.0	3.33	6.02	7,408.8	804.0	399.8	-408.7	2.14	-0.01	-37.36
7,577.0	2.83	5.66	7,502.6	809.0	400.3	-409.3	0.53	-0.53	-0.38
7,672.0	1.90	28.28	7,597.5	812.8	401.2	-410.3	1.37	-0.98	23.81
7,733.0	2.02	61.49	7,658.5	814.2	402.7	-411.7	1.85	0.20	54.44
7,861.0	3.33	76.97	7,786.4	816.1	408.3	-417.4	1.16	1.02	12.09
7,954.0	2.58	96.07	7,879.3	816.5	413.0	-422.1	1.32	-0.81	20.54
8,003.0	2.52	101.25	7,928.2	816.1	415.1	-424.2	0.49	-0.12	10.57
8,091.0	2.12	204.78	8,016.2	814.3	416.4	-425.4	4.15	-0.45	117.65
8,154.0	8.97	275.64	8,078.9	813.7	411.0	-420.0	13.51	10.87	112.48
8,186.0	12.23	297.45	8,110.3	815.5	405.5	-414.6	15.98	10.19	68.16
8,280.0	30.85	300.38	8,197.4	832.4	375.6	-384.9	19.84	19.81	3.12
8,319.9	33.87	297.32	8,231.1	842.7	356.9	-366.3	8.61	7.56	-7.68
FTP @ 8319.9'MD, 2309.9'FSL & 100'FEL									
8,374.0	38.06	293.86	8,274.9	856.4	328.2	-337.8	8.61	7.75	-6.39
8,469.0	41.95	274.91	8,347.9	871.0	269.6	-279.3	13.42	4.09	-19.95
8,563.0	46.73	270.76	8,415.1	874.2	204.0	-213.7	5.95	5.09	-4.41
8,658.0	52.14	270.86	8,476.9	875.2	131.8	-141.6	5.70	5.69	0.11
8,752.0	62.15	268.73	8,527.8	874.8	53.0	-62.8	10.82	10.65	-2.27



Intrepid Survey Report



Company:	Permian Resources Operating, LLC	Local Co-ordinate Reference:	Well Klondike 9 State Com 133H
Project:	Eddy County, NM (NAD 83 NME)	TVD Reference:	KB @ 3566.0usft (H&P 602)
Site:	Klondike 9 State Com Pad - S9 T19S R28E	MD Reference:	KB @ 3566.0usft (H&P 602)
Well:	Klondike 9 State Com 133H	North Reference:	Grid
Wellbore:	ST01	Survey Calculation Method:	Minimum Curvature
Design:	ST01 AWB	Database:	EDM 5000.15 Single User Db

Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,846.0	73.26	266.81	8,563.4	871.4	-33.8	24.0	11.97	11.82	-2.04
8,940.0	86.95	266.43	8,579.5	865.9	-126.0	116.3	14.57	14.56	-0.40
9,039.0	91.49	263.75	8,580.9	857.4	-224.6	215.0	5.32	4.59	-2.71
9,134.0	93.25	265.40	8,577.0	848.5	-319.1	309.6	2.54	1.85	1.74
9,228.0	94.99	265.23	8,570.2	840.8	-412.5	403.1	1.86	1.85	-0.18
9,322.0	95.78	264.66	8,561.4	832.6	-505.7	496.4	1.03	0.84	-0.61
9,417.0	95.39	264.87	8,552.1	823.9	-599.9	590.6	0.47	-0.41	0.22
9,511.0	95.16	264.83	8,543.5	815.5	-693.1	684.0	0.25	-0.24	-0.04
9,605.0	91.54	268.14	8,538.0	809.8	-786.7	777.6	5.21	-3.85	3.52
9,699.0	90.45	267.17	8,536.4	806.0	-880.6	871.6	1.55	-1.16	-1.03
9,794.0	90.62	269.16	8,535.5	802.9	-975.6	966.6	2.10	0.18	2.09
9,888.0	91.68	269.78	8,533.6	802.0	-1,069.6	1,060.5	1.31	1.13	0.66
9,983.0	89.94	268.33	8,532.3	800.5	-1,164.5	1,155.5	2.38	-1.83	-1.53
10,077.0	90.25	267.19	8,532.1	796.8	-1,258.5	1,249.5	1.26	0.33	-1.21
10,171.0	91.29	267.21	8,530.8	792.2	-1,352.3	1,343.4	1.11	1.11	0.02
10,266.0	91.40	268.86	8,528.6	789.0	-1,447.3	1,438.4	1.74	0.12	1.74
10,361.0	90.95	271.18	8,526.7	789.0	-1,542.2	1,533.3	2.49	-0.47	2.44
10,455.0	93.06	271.28	8,523.4	791.0	-1,636.1	1,627.2	2.25	2.24	0.11
10,549.0	90.45	271.86	8,520.5	793.6	-1,730.1	1,721.1	2.84	-2.78	0.62
10,644.0	91.40	271.74	8,519.0	796.6	-1,825.0	1,816.0	1.01	1.00	-0.13
10,738.0	89.63	271.12	8,518.1	798.9	-1,919.0	1,909.9	2.00	-1.88	-0.66
10,832.0	92.02	271.38	8,516.8	801.0	-2,012.9	2,003.8	2.56	2.54	0.28
10,926.0	92.64	271.27	8,512.9	803.1	-2,106.8	2,097.7	0.67	0.66	-0.12
11,021.0	90.95	270.46	8,510.0	804.6	-2,201.8	2,192.6	1.97	-1.78	-0.85
11,112.0	89.89	269.96	8,509.3	804.9	-2,292.7	2,283.6	1.29	-1.16	-0.55
11,206.0	87.76	269.73	8,511.2	804.6	-2,386.7	2,377.6	2.28	-2.27	-0.24
11,300.0	87.45	269.19	8,515.1	803.8	-2,480.6	2,471.5	0.66	-0.33	-0.57
11,395.0	86.81	268.63	8,519.9	801.9	-2,575.5	2,566.4	0.89	-0.67	-0.59
11,489.0	85.88	268.85	8,525.9	799.9	-2,669.3	2,660.2	1.02	-0.99	0.23
11,584.0	88.38	268.31	8,530.7	797.5	-2,764.1	2,755.0	2.69	2.63	-0.57
11,678.0	91.85	268.31	8,530.5	794.8	-2,858.1	2,849.0	3.69	3.69	0.00
11,772.0	92.91	268.04	8,526.6	791.8	-2,951.9	2,942.9	1.16	1.13	-0.29
11,867.0	93.61	267.94	8,521.2	788.4	-3,046.7	3,037.7	0.74	0.74	-0.11
11,961.0	90.81	270.13	8,517.5	786.9	-3,140.6	3,131.6	3.78	-2.98	2.33
12,055.0	90.92	271.05	8,516.1	787.8	-3,234.6	3,225.6	0.99	0.12	0.98
12,149.0	91.29	271.08	8,514.3	789.6	-3,328.6	3,319.6	0.39	0.39	0.03
12,244.0	91.40	271.28	8,512.1	791.5	-3,423.5	3,414.5	0.24	0.12	0.21
12,338.0	91.54	271.14	8,509.7	793.5	-3,517.5	3,508.4	0.21	0.15	-0.15
12,432.0	92.16	271.73	8,506.6	795.9	-3,611.4	3,602.3	0.91	0.66	0.63
12,527.0	91.76	272.25	8,503.4	799.2	-3,706.3	3,697.1	0.69	-0.42	0.55
12,621.0	91.79	272.30	8,500.5	802.9	-3,800.2	3,791.0	0.06	0.03	0.05
12,716.0	91.99	272.53	8,497.3	806.9	-3,895.0	3,885.8	0.32	0.21	0.24
12,810.0	92.30	270.08	8,493.8	809.0	-3,988.9	3,979.7	2.63	0.33	-2.61
12,905.0	92.86	269.98	8,489.5	809.1	-4,083.8	4,074.5	0.60	0.59	-0.11



Intrepid Survey Report



Company:	Permian Resources Operating, LLC	Local Co-ordinate Reference:	Well Klondike 9 State Com 133H
Project:	Eddy County, NM (NAD 83 NME)	TVD Reference:	KB @ 3566.0usft (H&P 602)
Site:	Klondike 9 State Com Pad - S9 T19S R28E	MD Reference:	KB @ 3566.0usft (H&P 602)
Well:	Klondike 9 State Com 133H	North Reference:	Grid
Wellbore:	ST01	Survey Calculation Method:	Minimum Curvature
Design:	ST01 AWB	Database:	EDM 5000.15 Single User Db

Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
13,000.0	93.50	270.15	8,484.3	809.2	-4,178.7	4,169.4	0.70	0.67	0.18
13,094.0	94.17	270.10	8,478.0	809.4	-4,272.5	4,263.2	0.71	0.71	-0.05
13,188.0	93.58	268.62	8,471.6	808.4	-4,366.3	4,357.0	1.69	-0.63	-1.57
13,282.0	94.26	267.26	8,465.2	805.0	-4,460.0	4,450.7	1.61	0.72	-1.45
13,377.0	96.28	267.53	8,456.5	800.7	-4,554.5	4,545.2	2.15	2.13	0.28
13,471.0	93.47	267.56	8,448.5	796.7	-4,648.0	4,638.8	2.99	-2.99	0.03
13,565.0	94.06	267.63	8,442.3	792.7	-4,741.7	4,732.6	0.63	0.63	0.07
13,660.0	91.74	267.89	8,437.5	789.0	-4,836.5	4,827.4	2.46	-2.44	0.27
13,754.0	92.83	268.01	8,433.8	785.7	-4,930.4	4,921.3	1.17	1.16	0.13
13,848.0	94.40	267.99	8,427.8	782.4	-5,024.2	5,015.1	1.67	1.67	-0.02
13,943.0	92.21	268.76	8,422.4	779.7	-5,119.0	5,109.9	2.44	-2.31	0.81
14,037.0	90.59	269.13	8,420.1	778.0	-5,212.9	5,203.9	1.77	-1.72	0.39
14,131.0	92.10	269.05	8,417.9	776.5	-5,306.9	5,297.9	1.61	1.61	-0.09
14,226.0	89.83	268.89	8,416.3	774.8	-5,401.8	5,392.8	2.40	-2.39	-0.17
14,320.0	90.36	268.88	8,416.1	772.9	-5,495.8	5,486.8	0.56	0.56	-0.01
14,415.0	91.76	268.92	8,414.3	771.1	-5,590.8	5,581.8	1.47	1.47	0.04
14,509.0	89.97	268.89	8,412.9	769.3	-5,684.8	5,675.8	1.90	-1.90	-0.03
14,603.0	91.01	269.04	8,412.1	767.6	-5,778.7	5,769.8	1.12	1.11	0.16
14,697.0	89.86	269.18	8,411.4	766.2	-5,872.7	5,863.8	1.23	-1.22	0.15
14,792.0	91.12	269.25	8,410.6	764.9	-5,967.7	5,958.8	1.33	1.33	0.07
14,886.0	92.63	268.91	8,407.5	763.4	-6,061.6	6,052.7	1.65	1.61	-0.36
14,981.0	90.64	268.79	8,404.8	761.5	-6,156.6	6,147.7	2.10	-2.09	-0.13
15,075.0	91.79	268.75	8,402.8	759.4	-6,250.5	6,241.7	1.22	1.22	-0.04
15,169.0	93.56	268.69	8,398.4	757.3	-6,344.4	6,335.5	1.88	1.88	-0.06
15,263.0	95.35	268.40	8,391.1	755.0	-6,438.1	6,429.2	1.93	1.90	-0.31
15,357.0	93.53	269.80	8,383.8	753.5	-6,531.8	6,523.0	2.44	-1.94	1.49
15,451.0	94.32	269.53	8,377.4	752.9	-6,625.6	6,616.7	0.89	0.84	-0.29
15,545.0	92.13	268.90	8,372.1	751.7	-6,719.4	6,710.6	2.42	-2.33	-0.67
15,640.0	91.65	268.29	8,369.0	749.3	-6,814.3	6,805.5	0.82	-0.51	-0.64
15,734.0	91.40	267.27	8,366.5	745.7	-6,908.2	6,899.5	1.12	-0.27	-1.09
15,829.0	91.60	267.41	8,364.0	741.3	-7,003.1	6,994.4	0.26	0.21	0.15
15,923.0	93.11	266.52	8,360.1	736.3	-7,096.9	7,088.2	1.86	1.61	-0.95
16,017.0	92.38	268.54	8,355.6	732.3	-7,190.7	7,182.0	2.28	-0.78	2.15
16,111.0	91.48	271.69	8,352.5	732.5	-7,284.6	7,276.0	3.48	-0.96	3.35
16,206.0	91.34	271.79	8,350.1	735.3	-7,379.5	7,370.8	0.18	-0.15	0.11
16,300.0	91.29	270.49	8,348.0	737.2	-7,473.5	7,464.8	1.38	-0.05	-1.38
16,394.0	92.27	269.33	8,345.1	737.1	-7,567.4	7,558.7	1.62	1.04	-1.23
16,489.0	92.66	270.25	8,341.0	736.7	-7,662.3	7,653.6	1.05	0.41	0.97
16,583.0	93.53	270.47	8,335.9	737.3	-7,756.2	7,747.5	0.95	0.93	0.23
16,677.0	91.09	270.98	8,332.1	738.5	-7,850.1	7,841.4	2.65	-2.60	0.54
16,771.0	90.64	270.68	8,330.7	739.8	-7,944.1	7,935.3	0.58	-0.48	-0.32
16,865.0	91.54	269.37	8,328.9	739.9	-8,038.1	8,029.3	1.69	0.96	-1.39
16,960.0	90.17	269.40	8,327.5	738.9	-8,133.0	8,124.3	1.44	-1.44	0.03



Intrepid Survey Report



Company:	Permian Resources Operating, LLC	Local Co-ordinate Reference:	Well Klondike 9 State Com 133H
Project:	Eddy County, NM (NAD 83 NME)	TVD Reference:	KB @ 3566.0usft (H&P 602)
Site:	Klondike 9 State Com Pad - S9 T19S R28E	MD Reference:	KB @ 3566.0usft (H&P 602)
Well:	Klondike 9 State Com 133H	North Reference:	Grid
Wellbore:	ST01	Survey Calculation Method:	Minimum Curvature
Design:	ST01 AWB	Database:	EDM 5000.15 Single User Db

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
17,054.0	89.61	269.47	8,327.7	737.9	-8,227.0	8,218.3	0.60	-0.60	0.07	
17,148.0	88.77	268.89	8,329.0	736.6	-8,321.0	8,312.3	1.09	-0.89	-0.62	
17,242.0	87.87	268.67	8,331.7	734.6	-8,415.0	8,406.2	0.99	-0.96	-0.23	
17,337.0	87.59	267.20	8,335.5	731.2	-8,509.8	8,501.1	1.57	-0.29	-1.55	
17,432.0	89.55	268.50	8,337.9	727.6	-8,604.7	8,596.1	2.48	2.06	1.37	
17,526.0	89.64	268.31	8,338.5	725.0	-8,698.7	8,690.0	0.22	0.10	-0.20	
17,620.0	89.83	268.44	8,339.0	722.3	-8,792.6	8,784.0	0.24	0.20	0.14	
17,714.0	90.64	269.92	8,338.6	721.0	-8,886.6	8,878.0	1.79	0.86	1.57	
17,808.0	92.16	269.53	8,336.3	720.5	-8,980.6	8,972.0	1.67	1.62	-0.41	
17,902.0	92.44	269.44	8,332.5	719.7	-9,074.5	9,065.9	0.31	0.30	-0.10	
17,996.0	93.31	268.84	8,327.8	718.3	-9,168.4	9,159.8	1.12	0.93	-0.64	
18,091.0	92.33	269.06	8,323.1	716.5	-9,263.3	9,254.7	1.06	-1.03	0.23	
18,185.0	90.98	271.10	8,320.4	716.7	-9,357.2	9,348.6	2.60	-1.44	2.17	
18,279.0	90.84	271.19	8,318.9	718.6	-9,451.2	9,442.6	0.18	-0.15	0.10	
18,374.0	90.51	270.82	8,317.8	720.2	-9,546.2	9,537.5	0.52	-0.35	-0.39	
18,469.0	91.90	269.87	8,315.8	720.8	-9,641.1	9,632.5	1.77	1.46	-1.00	
18,563.0	92.21	268.61	8,312.4	719.5	-9,735.1	9,726.4	1.38	0.33	-1.34	
18,640.0	92.46	267.63	8,309.3	717.0	-9,812.0	9,803.3	1.31	0.32	-1.27	
LAST SVY @ 18640.0										
18,657.2	92.46	267.63	8,308.6	716.3	-9,829.1	9,820.5	0.00	0.00	0.00	
LTP @ 18657.2'MD, 2297.7'FSL & 100'FWL										
18,701.0	92.46	267.63	8,306.7	714.5	-9,872.8	9,864.2	0.00	0.00	0.00	
Projection to TD @ 18701'MD, 56.3'FSL & 2296.3'FWL										

Design Targets										
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude	
PBHL (Klondike 9 Stat	0.00	0.00	8,575.0	717.8	-9,919.1	608,942.03	580,428.07	32° 40' 26.265 N	104° 12' 22.651 W	
- hit/miss target										
- Shape										
- Point										
- actual wellpath misses target center by 272.3usft at 18701.0usft MD (8306.7 TVD, 714.5 N, -9872.8 E)										
LTP (Klondike 9 State	0.00	0.00	8,575.0	718.7	-9,829.1	608,942.94	580,518.05	32° 40' 26.273 N	104° 12' 21.598 W	
- hit/miss target										
- Shape										
- Point										
- actual wellpath misses target center by 266.2usft at 18645.7usft MD (8309.1 TVD, 716.8 N, -9817.6 E)										
FTP (Klondike 9 State	0.00	0.00	8,575.0	832.0	356.9	609,056.30	590,704.10	32° 40' 27.258 N	104° 10' 22.422 W	
- hit/miss target										
- Shape										
- Point										
- actual wellpath misses target center by 225.2usft at 8563.0usft MD (8415.1 TVD, 874.2 N, 204.0 E)										



Company:	Permian Resources Operating, LLC	Local Co-ordinate Reference:	Well Klondike 9 State Com 133H
Project:	Eddy County, NM (NAD 83 NME)	TVD Reference:	KB @ 3566.0usft (H&P 602)
Site:	Klondike 9 State Com Pad - S9 T19S R28E	MD Reference:	KB @ 3566.0usft (H&P 602)
Well:	Klondike 9 State Com 133H	North Reference:	Grid
Wellbore:	ST01	Survey Calculation Method:	Minimum Curvature
Design:	ST01 AWB	Database:	EDM 5000.15 Single User Db

Design Annotations				
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
8,319.9	8,231.1	842.7	356.9	FTP @ 8319.9'MD, 2309.9'FSL & 100'FEL
18,640.0	8,309.3	717.0	-9,812.0	LAST SVY @ 18640.0
18,657.2	8,308.6	716.3	-9,829.1	LTP @ 18657.2'MD, 2297.7'FSL & 100'FWL
18,701.0	8,306.7	714.5	-9,872.8	Projection to TD @ 18701'MD, 56.3'FSL & 2296.3'FWL

Checked By: _____

Approved By: _____

Date: _____

Santa Fe Main Office Phone: (505) 476-3441 Fax: (55) 476-3462 General Information Phone: (505) 629-6116 Online Phone Directory Visit: https://www.emnrd.nm.gov/ocd/contact-us/	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	C-105 Revised July 9, 2024 Submit Electronically Via OCD Permitting
---	--	---

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

Section 1 - Operator and Well Information

Submittal Type: ☒ New Well ☐ Workover ☐ Deepening ☐ Plugback ☐ Different Reservoir ☐ C-144 Closure Attachment ☐ Other	
Operator Name: Permian Resources Operating, LLC	OGRID: 372165
Property Name and Well Number: Klondike 9 State Com 133H	Property Code: 334778
Mineral Owner: ☒ State ☐ Fee ☐ Tribal ☐ Federal	API Number: 30-015-54318
Pool Name: Winchester; Bone Spring, West	Pool Code: 97569

Section 2 – Well Location

	Ul or lot no.	Section	Township	Range	Lot Id	Feet from	N/S Line	Feet from	E/W Line	County
SHL:	I	9	19S	28E		1473	South	458	East	Eddy
BHL	L	8	19S	28E		2297	South	56	West	Eddy

Section 3 – Completion Information

Date T.D. Reached 8/14/24	Total Measured Depth of Well 18,701	Acid Volume (bbls) N/A	☒ Directional Survey Submitted ☐ Deviation Survey Submitted
Date Rig Released 8/16/24	Plug-Back Measured Depth 18,644	Completion Fluid Used (bbls) 427,075	Were Logs Ran (Y/N) Yes
Completion Date 9/24/24	Perforations (MD and TVD) 8908 - 18,640 MD 8547 - 8309 TVD	Completion Proppant Used (lbs) 21,762,781	List Type of Logs Ran if applicable: Gamma Ray

Section 4 – Action IDs for Submissions and Order Numbers

Surface Casing Action ID: 365600	UIC Permit/Order (UIC wells only) ☐ Yes ☒ No, Order No.
Intermediate 1 Casing Action ID: 366566	NOI Recomplete Action ID (if applicable):
Intermediate 2 Casing Action ID:	NOI Plugback Action ID (if applicable):
Production Casing Action ID: 376295	Cement Squeeze Action ID (if applicable):
Tubing Action ID:	All casing was pressure tested in accordance with NMAC ☒ Yes ☐ No
Liner 1 Action ID:	Casing was installed prior to Action ID system (Y/N): No

Section 5 – Test Data

Date First Production 9/24/24	Production Method Gas Lift	Well Status Producing	Gas – Oil Ratio 2397
Date of Test 10/2/24	Choke Size .9	Flowing Tubing Pressure N/A	Casing Pressure 426
24 hr Oil (bbls) 288	24 hr Gas (MCF) 691	24 hr Water (bbls) 2778	Oil Gravity - API 41.8
Disposition of Gas: Sold			


Section 6 – Pits

☐ A temporary pit was used at the well. If so, attach a plat with the location of the temporary pit.
☒ A Closed Loop System was used.
☐ If an on-site burial was used at the well, report the exact location of the on-site burial: LAT: _____ LONG: _____

Section 7 - Operator Signature and Certification

☒ I hereby certify that the required Water Use Report has been, or will be, submitted for this well’s completion.	
☒ I hereby certify that the required Fracfocus disclosure has been, or will be, submitted for this well’s completion.	
☒ I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.	
Name Kanicia Schlichting	PH 432-400-0185
Title Regulatory Specialist	Date 11/7/24

South Formations				North Formations			
Formation/Zone	MD	TVD	W/O/G	Formation/Zone	MD	TVD	W/O/G
Base Salt	401	401		T. San Jose			
Tansil	629	629		T. Nacimiento			
Yates	750	750		T. Ojo Alamo			
Seven Rivers	1113	1113		T. Kirtland			
Queen	1663	1663		T. Fruitland			
Brushy Canyon	2989	2973	O/G	T. Pictured Cliffs			
Bone Spring Lime	3494	3469	O/G	T. Lewis Shale			
1st Bone Spring Sand	6115	6052	O/G	T. Chacra			
2nd Bone Spring Sand	7159	7086	O/G	T. Cliff House			
3rd Bone Spring Sand	8356	8256	O/G	T. Menefee			
T. Paddock				T. Point Lookout			
T. Blinebry				T. Mancos			
T.Tubb				T. Gallup			
T. Drinkard				T. Greenhorn			
T. Abo				T. Graneros			
T. Wolfcamp				T. Dakota			
T. Penn				T. Morrison			
T. Cisco				T. Bluff			
T. Canyon				T.Todilto			
T. Strawn				T. Entrada			
T. Atoka				T. Wingate			
T. Morrow				T. Chinle			
T. Barnett Shale				T. Permian			
T. Miss				T. Penn A"			
T. Woodford Shale				T. Penn. "B"			
T. Devonian				T. Penn. "C"			
T. Silurian				T. Penn. "D"			
T. Fusselman				T. Leadville			
T. Montoya				T. Madison			
T. Simpson				T. Elbert			
T. McKee				T. McCracken			
T. Waddell				T. Ignacio Otzte			
T. Connel				T. Granite			
T. Ellenburger				T. Hermosa			
T. Gr. Wash				T. De Chelly			
T. Delaware Sand				T. Pinkerton			
T. Lamar Lime							
T. Bell Canyon							
T. Cherry Canyon							
T. Brushy Canyon							
T. Bone Springs							
T. 1st BS Sand							
T. 2nd BS Carbonate							
T. 2nd BS Sand							
T. 3rd BS Carbonate							
T. 3rd BS Sand							



Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/ocd/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 400412

ACKNOWLEDGMENTS

Operator: Permian Resources Operating, LLC 300 N. Marienfeld St Ste 1000 Midland, TX 79701	OGRID: 372165
	Action Number: 400412
	Action Type: [C-104] Completion Packet - New Well (C-104NW)

ACKNOWLEDGMENTS

☒	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
☒	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.
☒	I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/oed/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 400412

CONDITIONS

Operator: Permian Resources Operating, LLC 300 N. Marienfeld St Ste 1000 Midland, TX 79701	OGRID: 372165
	Action Number: 400412
	Action Type: [C-104] Completion Packet - New Well (C-104NW)

CONDITIONS

Created By	Condition	Condition Date
plmartinez	None	11/20/2025