Form 3160-3
(October 2024)

FORM APPROVED
OMB No. 1004-0220
Expires: October 31, 2027

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No.: NMNM108027

6. If Indian, Allotee or Tribe Name:

1a. Type of work: ☑ DRILL ☐ REENTER

1b. Type of Well: ☐ Oil Well ☑ Gas Well ☐ Other

1c. Type of Completion: ☐ Hydraulic Fracturing ☑ Single Zone ☐ Multiple Zone

7. If Unit or CA Agreement, Name and No.:

8. Lease Name and Well No.: PABST FED COM 213H

2. Name of Operator: TAP ROCK OPERATING LLC

9. API Well No.: 30-015-57535

3a. Address: 1700 LINCOLN ST SUITE 4700, DENVER, CO 80203

3b. Phone No. *(include area code)*: (720) 460-3316

10. Field and Pool, or Exploratory: PURPLE SAGE/WOLFCAMP (GAS)

4. Location of Well *(Report location clearly and in accordance with any State requirements.*)*

At surface: NWNE / 753 FNL / 2349 FEL / LAT 32.0769949 / LONG -104.3825667

At proposed prod. zone: SWSE / 5 FSL / 2360 FEL / LAT 32.0499368 / LONG -104.3830832

11. Sec., T. R. M. or Blk. and Survey or Area: SEC 3/T26S/R25E/NMP

14. Distance in miles and direction from nearest town or post office*: 7 miles

12. County or Parish: EDDY

13. State: NM

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any): 753 feet

16. No of acres in lease:

17. Spacing Unit dedicated to this well: 1280.0

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.: 25 feet

19. Proposed Depth: 8103 feet / 18708 feet

20. BLM/BIA Bond No. in file: FED: NMB105800930

21. Elevations (Show whether DF, KDB, RT, GL, etc.): 3631 feet

22. Approximate date work will start*: 03/01/2026

23. Estimated duration: 60 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM.

25. Signature	Name *(Printed/Typed)*	Date
(Electronic Submission)	CORY WALK / Ph: (720) 460-3316	10/06/2025

Title: Permitting Agent

Approved by *(Signature)*	Name *(Printed/Typed)*	Date
(Electronic Submission)	CODY LAYTON / Ph: (575) 234-5959	11/21/2025

Title	Office
Assistant Field Manager Lands & Minerals	Carlsbad Field Office

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

APPROVED WITH CONDITIONS

(Continued on page 2)

*(Instructions on page 2)

Approval Date: 11/21/2025

C-102	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024
Submit Electronically Via OCD Permitting		Submittal Type: [X] Initial Submittal [ ] Amended Report [ ] As Drilled

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number	Pool Code	Pool Name
30-015- 57535	98220	PURPLE SAGE; WOLFCAMP (GAS)

Property Code	Property Name	Well Number
338228	PABST FED COM	213H

OGRID No.	Operator Name	Ground Level Elevation
372043	TAP ROCK OPERATING, LLC	3631'

Surface Owner: [ ] State [ ] Fee [ ] Tribal [X] Federal
Mineral Owner: [ ] State [ ] Fee [ ] Tribal [X] Federal

Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the N/S	Feet from the E/W	Latitude	Longitude	County
B	3	26-S	25-E	-	753' N	2349' E	N 32.0769949	W 104.3825667	EDDY

Bottom Hole Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the N/S	Feet from the E/W	Latitude	Longitude	County
O	10	26-S	25-E	-	5' S	2360' E	N 32.0499368	W 104.3830832	EDDY

Dedicated Acres	Infill or Defining Well	Defining Well API	Overlapping Spacing Unit (Y/N)	Consolidated Code
1280	Defining	30-015-xxxxx (213H)	N	C

Order Numbers: will file NSP
Well Setbacks are under Common Ownership: [X] Yes [ ] No

Kick Off Point (KOP)

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the N/S	Feet from the E/W	Latitude	Longitude	County
B	3	26-S	25-E	-	50' N	2360' E	N 32.0789266	W 104.3826036	EDDY

First Take Point (FTP)

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the N/S	Feet from the E/W	Latitude	Longitude	County
B	3	26-S	25-E	-	330' N	2360' E	N 32.0781569	W 104.3826033	EDDY

Last Take Point (LTP)

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the N/S	Feet from the E/W	Latitude	Longitude	County
O	10	26-S	25-E	-	330' S	2360' E	N 32.0508306	W 104.3830537	EDDY

Unitized Area or Area of Uniform Interest	Spacing Unity Type	Ground Floor Elevation
Y	[X] Horizontal [ ] Vertical	3631'

OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief; and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest or unleased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

If this well is a horizontal well, I further certify that this organization has received The consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.

Signature: Cory Walk — Date: 10-03-2025

Print Name: Cory Walk

E-mail Address: cory@permitswest.com

SURVEYORS CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

RAMON DOMINGUEZ — NEW MEXICO — 24508 — PROFESSIONAL SURVEYOR

9/9/2025 2:47:19 PM

Signature and Seal of Professional Surveyor — Date

Certificate Number

Date of Survey: 08/25/2025

S:\SURVEY\TAP ROCK\PABST_UNIT\FINAL_PRODUCTS\ALO_PABST_FED_COM_213H.dwg ADISABELLA 9/9/2025 2:47 PM

C-102

Submit Electronically
Via OCD Permitting

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION

Revised July 9, 2024

Submittal Type:
- [X] Initial Submittal
- [ ] Amended Report
- [ ] As Drilled

Property Name and Well Number

PABST FED COM 213H

SURFACE LOCATION (SHL)
NEW MEXICO EAST
NAD 1983
X=526089 Y=391751
LAT.: N 32.0769949
LONG.: W 104.3825667
NAD 1927
X=484906 Y=391695
LAT.: N 32.0768768
LONG.: W 104.3820642
753' FNL 2349' FEL

KICK OFF POINT (KOP)
NEW MEXICO EAST
NAD 1983
X=526077 Y=392454
LAT.: N 32.0789266
LONG.: W 104.3826036
NAD 1927
X=484895 Y=392398
LAT.: N 32.0788086
LONG.: W 104.3821011
50' FNL 2360' FEL

FIRST TAKE POINT (FTP)
NEW MEXICO EAST
NAD 1983
X=526077 Y=392174
LAT.: N 32.0781569
LONG.: W 104.3826033
NAD 1927
X=484895 Y=392118
LAT.: N 32.0780388
LONG.: W 104.3821007
330' FNL 2360' FEL



BLM PERF. POINT (BPP1)
NEW MEXICO EAST
NAD 1983
X=526005 Y=387206
LAT.: N 32.0645000
LONG.: W 104.3828284
NAD 1927
X=484823 Y=387150
LAT.: N 32.0643818
LONG.: W 104.3823263
0' FSL 2431' FEL

LAST TAKE POINT (LTP)
NEW MEXICO EAST
NAD 1983
X=525933 Y=382234
LAT.: N 32.0508306
LONG.: W 104.3830537
NAD 1927
X=484751 Y=382178
LAT.: N 32.0507122
LONG.: W 104.3825521
330' FSL 2360' FEL

BOTTOM HOLE LOCATION (BHL)
NEW MEXICO EAST
NAD 1983
X=525924 Y=381909
LAT.: N 32.0499368
LONG.: W 104.3830832
NAD 1927
X=484742 Y=381853
LAT.: N 32.0498184
LONG.: W 104.3825816
5' FSL 2360' FEL

SURVEYORS CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

08/25/2025
Date of Survey

Signature and Seal of Professional Surveyor:

RAMON DOMINGUEZ NEW MEXICO 24508 PROFESSIONAL SURVEYOR

9/9/2025 2:47:20 PM

S:\SURVEY\APROCK\PABST_UNIT\FINAL_PRODUCTS\LO_PABST_FED_COM_213H.dwg ADSHELLA 9/9/2025 2:47 PM

TAP ROCK

SECTION 3, TOWNSHIP 26-S, RANGE 25-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



SURFACE LOCATION (SHL)
NEW MEXICO EAST
NAD 1983
X=526089 Y=391751
LAT.: N 32.0769949
LONG.: W 104.3825667
753' FNL 2349' FEL

KICK OFF POINT (KOP)
NEW MEXICO EAST
NAD 1983
X=526077 Y=392454
LAT.: N 32.0789266
LONG.: W 104.3826036
50' FNL 2360' FEL

FIRST TAKE POINT (FTP)
NEW MEXICO EAST
NAD 1983
X=526077 Y=392174
LAT.: N 32.0781569
LONG.: W 104.3826033
330' FNL 2360' FEL

BLM PERF. POINT (BPP1)
NEW MEXICO EAST
NAD 1983
X=526005 Y=387206
LAT.: N 32.0645000
LONG.: W 104.3828284
0' FSL 2431' FEL

LAST TAKE POINT (LTP)
NEW MEXICO EAST
NAD 1983
X=525933 Y=382234
LAT.: N 32.0508306
LONG.: W 104.3830537
330' FSL 2360' FEL

BOTTOM HOLE LOCATION (BHL)
NEW MEXICO EAST
NAD 1983
X=525924 Y=381909
LAT.: N 32.0499368
LONG.: W 104.3830832
5' FSL 2360' FEL



DETAIL VIEW
SCALE: 1" = 100'

SCALE: 1" = 2000'
0' 1000' 2000'

LEASE NAME & WELL NO.: PABST FED COM 213H

SECTION 3 TWP 26-S RGE 25-E SURVEY N.M.P.M.
COUNTY EDDY STATE NM
DESCRIPTION 753' FNL & 2349' FEL

DISTANCE & DIRECTION
FROM INT. OF CARLSBAD CAVERN HWY., & US-180/US-62 W, GO SOUTHWEST ON US-180/US-62 W ±6.7 MILES, THENCE EAST (LEFT) ON DILLAHUNTY RD. ±3.2 MILES, THENCE NORTH (LEFT) ON A PROPOSED RD. ±0.86 MILES, TO A POINT ±379 FEET SOUTH OF THE LOCATION.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

AS OF THE DATE OF SURVEY, ALL ABOVE GROUND APPURTENANCES WITHIN 300' OF THE STAKED LOCATION ARE SHOWN HEREON.

RAMON DOMINGUEZ NEW MEXICO 24508 PROFESSIONAL SURVEYOR

9/9/2025 2:47:21 PM

Ramon A. Dominguez, P.S. No. 24508

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
481 WINSCOTT ROAD, Ste. 200 • BENBROOK, TEXAS 76126
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

S:\SURVEY\TAPROCK\PABST_UNIT\FINAL_PRODUCTS\LO_PABST_FED_COM_213H.DWG 9/9/2025 2:47:21 PM adisabella

State of New Mexico
Energy, Minerals and Natural Resources Department

Submit Electronically
Via E-permitting

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description
Effective May 25, 2021

I. Operator: _____Tap Rock Operating LLC_____ **OGRID:** _____372043_____ **Date:** 9/29/2025

II. Type: ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
Pabst Fed Com 202H		B, 3, 26S, 25E	753' FNL, 2374' FEL	940	3571	5149
Pabst Fed Com 204H		B, 3, 26S, 25E	778' FNL, 2349' FEL	940	3571	5149
Pabst Fed Com 211H		B, 3, 26S, 25E	778' FNL, 2374' FEL	940	3571	5149
Pabst Fed Com 213H		B, 3, 26S, 25E	753' FNL, 2349' FEL	940	3571	5149

IV. Central Delivery Point Name: _____ Pabst Fed Com CDP_____ [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Pabst Fed Com 202H		2/1/2026	3/1/2026	4/1/2026	5/1/2026	5/1/2026
Pabst Fed Com 204H		2/1/2026	3/1/2026	4/1/2026	5/1/2026	5/1/2026
Pabst Fed Com 211H		2/1/2026	3/1/2026	4/1/2026	5/1/2026	5/1/2026
Pabst Fed Com 213H		2/1/2026	3/1/2026	4/1/2026	5/1/2026	5/1/2026

VI. Separation Equipment: ☒ Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan
EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☒ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. ☐ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system ☐ will ☐ will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator ☐ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

XIV. Confidentiality: ☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☒ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system. ***If Operator checks this box, Operator will select one of the following:***

Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- **(a)** power generation on lease;
- **(b)** power generation for grid;
- **(c)** compression on lease;
- **(d)** liquids removal on lease;
- **(e)** reinjection for underground storage;
- **(f)** reinjection for temporary storage;
- **(g)** reinjection for enhanced oil recovery;
- **(h)** fuel cell production; and
- **(i)** other alternative beneficial uses approved by the division.

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature: 
Printed Name: Bill Ramsey
Title: Sr. Environmental and Regulatory Specialist
E-mail Address: brmasey@taprk.com
Date: 9/29/2025
Phone: 720-238-2787

OIL CONSERVATION DIVISION **(Only applicable when submitted as a standalone form)**
Approved By:
Title:
Approval Date:
Conditions of Approval:

Tap Rock Operating Natural Gas Management Plan

VI. **Separation Equipment:**

Each surface facility design includes the following process equipment: 3-phase separators (1 separator per well), a sales gas scrubber, one or two 3-phase heater treaters, a vapor recovery tower (VRT), a VRU compressor, multiple water and oil tanks, as well as flare knockouts (HP & LP), and flares (HP & LP). All process vessels will be sized to separate oil, water, gas based upon typical/historical & predicted well performance. Each process vessel will be fitted with an appropriately sized PSV as per ASME code requirements to mitigate vessel rupture and loss of containment. Additionally, the process vessels will be fitted with pressure transmitters tied to the facility control system which will allow operations to monitor pressures and when necessary, shut-in the facility to avoid vessel over-pressure and the potential vent of natural gas. Natural gas will preferentially be sold to pipeline, and only during upset/emergency conditions will gas be directed to the HP flare system. Flash gas from both the 3-phase heater treater and the VRT will be recompressed using a VRU compressor and this gas will also preferentially be directed to the gas sales pipeline. Oil tanks & water tanks will be fitted with 16 oz thief hatches as well as PVRVs to protect the tanks from rupture/collapse. Additionally, the tank vapor outlets and tank vapor capture system will be sized to keep tank pressures below 12 oz. The tank vapor capture system will include a tank vapor blower & knockout as well as a low-pressure flare and knockout. Tank vapors will preferentially be directed to the VRU and the sales gas pipeline. Only during process upsets/emergency conditions will tank vapors be directed to the LP flare system.

VII. **Operational Practices:**

- During drilling operations- Gas meters will be installed at the shakers and Volume Totalizers will be installed on the pits. In the event that elevated gas levels, or a pit gain are observed, returns will be diverted to a gas buster. Gas coming off the gas buster will be combusted at the flare stack. A 10’ or taller flare will be located at least 100’ from the SHL.

- During completions operations, including stimulation and frac plug drill out operations, hydrocarbon production to surface is minimized. When gas production does occur, gas will be combusted at a flare stack. A 10’ or taller flare will be located at least 100’ from the SHL.

- During production operations, all process vessels (separators, heater treaters, VRTs, Tanks) will recompress (where necessary) and route gas outlets into the natural gas gathering pipeline. Gas will preferentially be routed to natural gas gathering pipeline and the flare system will be used only during emergency, malfunction, or if the gas does not meet pipeline specifications. In the event of flaring off-specification gas, operations will pull gas samples twice a week and will also route gas back to pipeline as soon as the gas meets specification. Exceptions to this will include only those qualified emergencies as mentioned in the BLM Waste Prevention Rule.

- To comply with state performance standards, separation and storage equipment will be designed to handle the maximum anticipated throughput and pressure to minimize waste and reduce the likelihood of venting gas to atmosphere. Additionally, each storage atmospheric tank (Oil & Water) will be fitted with a level transmitter to facilitate gauging of the tank without opening of the thief hatch. Any gas collected through the tank vent system is expected to be recompressed and routed to sales. However, in the event of an emergency, the tank vapor capture system will be designed to combust the gas using a flare stack fitted with a continuous or automatic ignitor. The flare stack will be properly anchored and will be located a minimum of 100 feet from the well and storage tanks. Operators will conduct weekly AVO inspections. These AVO inspection records will be stored for the required 5-year period and will be made available upon Division request.

VIII. **Best Management Practices:**

- When performing routine or preventive maintenance on a vessel or tank, initially all inlet valves are closed, and the vessel or tank is allowed to depressurize through the normal outlet connections to gas sales and/or liquid tanks. Once the vessel or tank is depressurized to lowest acceptable sales outlet pressure, usually around 20 psig, a temporary low-pressure flowline is connected from the vessel or tank to the Vapor Recovery Unit (VRU) for further pressure reduction. Once depressurized to less than 1-2 psig, the remaining natural gas in the vessel or tank is vented to atmosphere through a controlled pressure relief valve. Once the vessel or tank is depressurized to atmospheric pressure, the vessel or tank can be safely opened, and maintenance performed.

AFMSS
U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report
11/21/2025

APD ID: 10400107655
Submission Date: 10/06/2025
Operator Name: TAP ROCK OPERATING LLC
Well Name: PABST FED COM
Well Number: 213H
Well Type: CONVENTIONAL GAS WELL
Well Work Type: Drill

Highlighted data reflects the most recent changes

Show Final Text

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
16838852	QUATERNARY	3631	0	0	OTHER : None	NONE	N
16838832	RUSTLER ANHYDRITE	3592	39	39	ANHYDRITE	NONE	N
16838833	TOP SALT	3321	310	310	SALT	OTHER : Salt	N
16838834	BASE OF SALT	2276	1355	1358	SALT	OTHER : Salt	N
16838835	DELAWARE	2054	1577	1581	OTHER, SANDSTONE : Moutain Group	NONE	N
16838836	LAMAR	2047	1584	1588	SANDSTONE	NATURAL GAS, OIL	N
16838837	BELL CANYON	2013	1618	1622	SANDSTONE	NATURAL GAS, OIL	N
16838838	RAMSEY SAND	2002	1629	1633	SANDSTONE	NATURAL GAS, OIL	N
16838839	CHERRY CANYON	1154	2477	2486	LIMESTONE	NATURAL GAS, OIL	N
16838840	BRUSHY CANYON	161	3470	3484	SANDSTONE	NATURAL GAS, OIL	N
16838841	BONE SPRING LIME	-1295	4926	4949	OTHER : Carbonate	NATURAL GAS, OIL	N
16838842	AVALON SAND	-1554	5185	5209	OTHER : Upper - Carbonate	NATURAL GAS, OIL	N
16838843	AVALON SAND	-1857	5488	5514	OTHER : Middle - Carbonate	NATURAL GAS, OIL	N
16838844	AVALON SAND	-2200	5831	5859	OTHER : Lower - Carbonate	NATURAL GAS, OIL	N
16838845	BONE SPRING 1ST	-2340	5971	6000	SANDSTONE	NATURAL GAS, OIL	N
16838846	BONE SPRING 2ND	-2634	6265	6295	OTHER : Carbonate	NATURAL GAS, OIL	N
16838847	BONE SPRING 2ND	-3107	6738	6771	SANDSTONE	NATURAL GAS, OIL	N

Operator Name: TAP ROCK OPERATING LLC

Well Name: PABST FED COM **Well Number:** 213H

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
16838848	BONE SPRING 3RD	-3257	6888	6922	OTHER : Carbonate	NATURAL GAS, OIL	N
16838849	BONE SPRING 3RD	-4207	7838	7874	SANDSTONE	NATURAL GAS, OIL	N
16838850	BONE SPRING 3RD	-4471	8102	8153	OTHER : W Sandstone	NATURAL GAS, OIL	N
16838851	WOLFCAMP	-4561	8192	8269	OTHER : A	NATURAL GAS, OIL	N
16838831	WOLFCAMP	-4681	8312	8492	OTHER : A Lower	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M **Rating Depth:** 10000

Equipment: At 18,708', a 5M pressure control system is required. The BOP stack consisting of 3 rams with 2 pipe rams, 1 blind ram, and 1 annular preventer will be used below surface casing to TD. See attachments for BOP and choke manifold diagrams. Also present will be an accumulator that meets the requirements of 43 CFR 3172 for the pressure rating of the BOP stack. A rotating head will also be installed as needed. BOP will be inspected and operated as recommended in 43 CFR 3172. A top drive check valve and sub equipped with a full opening valve sized to fit the drill pipe and collars will be available on the rig floor in the open position. The wellhead will be a multi-bowl speed head.

Requesting Variance? YES

Variance request: Tap Rock requests a variance to run a multi-bowl speed head for setting the Intermediate and Production Strings. Tap Rock requests a variance to drill this well using a co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Tap Rock requests a variance to have the option of batch drilling this well with other wells on the same pad. If this well is batch drilled, after cementing a casing string, a 5M dry hole cap with bleed off valve will be installed. The rig will then walk to another well on the pad. Tap Rock Operating requests to only test BOP connection breaks after rig walks per the procedures and stipulations set forth in the “BOP Shell Test Procedure” document emailed to the BLM on 8/11/22.

Testing Procedure: After surface casing is set and the BOP is nippled up, the BOP pressure tests will be made with a third party tester to 250 psi low, 5000 psi high, and the annular preventer will be tested to 250 psi low, 2500 psi high.

Choke Diagram Attachment:

5M_Choke_Diagram_20251004155132.pdf

BOP Diagram Attachment:

5M_BOP_Diagram_20251004155138.pdf

Operator Name: TAP ROCK OPERATING LLC

Well Name: PABST FED COM **Well Number:** 213H

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	14.75	11.75	NEW	API	N	0	350	0	350	3631	3281	350	J-55	42	BUTT	1.13	1.15	DRY	1.6	DRY	1.6
2	INTERMEDIATE	11	8.625	NEW	API	N	0	1638	0	1634	3631	1997	1638	J-55	32	BUTT	1.13	1.15	DRY	1.6	DRY	1.6
3	PRODUCTION	7.875	5.5	NEW	NON API	N	0	18708	0	7824	3631	-4193	18708	P-110	20	OTHER - TPN	1.13	1.15	DRY	1.6	DRY	1.6

Casing Attachments

Casing ID: 1 **String** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Design_Assumptions_20251004155226.pdf

Operator Name: TAP ROCK OPERATING LLC

Well Name: PABST FED COM **Well Number:** 213H

Casing Attachments

Casing ID: 2 **String** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Design_Assumptions_20251004155249.pdf

Casing ID: 3 **String** PRODUCTION

Inspection Document:

Spec Document:

5.5in_TPN_Casing_Spec_20251004155309.pdf

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Design_Assumptions_20251004155318.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	0	0	0	0	0	0	None	None
SURFACE	Tail		0	350	228	1.33	14.8	304	100	Class C	5% NCl + LCM
INTERMEDIATE	Lead		0	1138	164	2.7	11	443	75	Class C	Bentonite + 1% CaCL2 + 8% NaCl + LCM
INTERMEDIATE	Tail		1138	1638	124	1.33	14.8	165	30	Class C	5% NaCl + LCM
PRODUCTION	Lead		0	7860	473	3.35	10.5	1586	20	Class C	Fluid Loss + Dispersant +

Operator Name: TAP ROCK OPERATING LLC

Well Name: PABST FED COM **Well Number:** 213H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
											Retarder + LCM
PRODUCTION	Tail		7860	18708	1386	1.63	13.2	2259	20	Class H	Fluid Loss + Dispersant + Retarder + LCM

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with 43 CFR 3172:

Diagram of the equipment for the circulating system in accordance with 43 CFR 3172:

Describe what will be on location to control well or mitigate other conditions: All necessary mud products (i.e., barite, pac) for weight addition and fluid loss control will always be on site. Mud program is subject to change due to hole conditions.

Describe the mud monitoring system utilized: Electronic Pason mud monitor system complying with 43 CFR 3172 will be used.

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	350	OTHER : Fresh Water Spud Mud	8.4	8.4							
350	1638	SALT SATURATED	10	10							
1638	18708	OIL-BASED MUD	9	9							

Operator Name: TAP ROCK OPERATING LLC

Well Name: PABST FED COM **Well Number:** 213H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Electric Logging Program: No open-hole logs are planned at this time. GR will be collected while drilling through the MWD tools from KOP to TD. A 2-person mud logging program will be used from KOP to TD. CBL w/ CCL from as far as gravity will let it fall to TOC.

List of open and cased hole logs run in the well:

MUD LOG/GEOLOGICAL LITHOLOGY LOG,GAMMA RAY LOG,CEMENT BOND LOG,

Coring operation description for the well:

No DSTs or cores are planned at this time.

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 3661 **Anticipated Surface Pressure:** 1825

Anticipated Bottom Hole Temperature(F): 170

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

Pabst_H2S_Plan_20251004155521.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Pabst_213H_Directional_Plan_20251004155533.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

Pabst_213H_Drill_Plan_20251004155542.pdf
Pabst_213H_Anticollision_Report_20251004155556.pdf
CoFlex_Certs_20251004155605.pdf
BOP_Shell_Test_Procedure_20251004155612.pdf
Wellhead_Diagram_3T_20251004155624.pdf
Pabst_WMP_20251004155625.pdf

Other Variance request(s)?: N

Other Variance attachment:

Operator Name: TAP ROCK OPERATING LLC

Well Name: PABST FED COM **Well Number:** 213H

Company: Tap Rock Operating
Well: Pabst Fed Com 213H
County: Eddy County, New Mexico (NAD 83)
Rig: H&P 466
Wellbore: Wellbore #1
Design: Design #1
Date: 12:07, September 25 2025

Geodetic System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone: New Mexico Eastern Zone
System Datum: Mean Sea Level

WELL DETAILS: Pabst Fed Com 213H

GL @ 3631.00 Well @ 3657.00usft (H&P 466)

+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
-0.05	24.90	391751.47	526088.51	32° 4' 37.182 N	104° 22' 57.240 W

SURVEY PROGRAM

Depth From	Depth To	Survey/Plan	Tool
0.00	18708.28	Design #1 (Wellbore #1)	MWD+IFR1+SAG+FDIR

DESIGN TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
BPP1_Pabst Fed Com 213H	0.00	-4545.31	-58.24	387206.21	526005.37	32° 3' 52.200 N	104° 22' 58.182 W
FTP_Pabst Fed Com 213H	0.00	422.66	13.76	392174.18	526077.37	32° 4' 41.365 N	104° 22' 57.372 W
KOP_Pabst Fed Com 213H	0.00	702.66	13.79	392454.17	526077.40	32° 4' 44.136 N	104° 22' 57.373 W
LTP_Pabst Fed Com 213H	0.00	-9517.81	-130.32	382233.70	525933.29	32° 3' 2.990 N	104° 22' 58.993 W
PBHL_Pabst Fed Com 213H	8102.89	-9842.95	-139.61	381908.57	525924.00	32° 2' 59.772 N	104° 22' 59.100 W
T1-1000' VS_Pabst Fed Com 213H	8340.76	-999.64	-10.97	390751.88	526052.64	32° 4' 27.289 N	104° 22' 57.652 W
T2-4000' VS_Pabst Fed Com 213H	8304.11	-3999.32	-54.61	387752.20	526009.00	32° 3' 57.603 N	104° 22' 58.143 W
T3-6500' VS_Pabst Fed Com 213H	8251.74	-6499.05	-90.97	385252.47	525972.64	32° 3' 32.865 N	104° 22' 58.552 W
T4-7000' VS_Pabst Fed Com 213H	8236.90	-6999.00	-98.24	384752.52	525965.37	32° 3' 27.917 N	104° 22' 58.634 W

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Annotation
0.00	0.00	0.00	0.00	-0.05	24.90	0.00	0.000	0.00	
500.00	0.00	0.00	500.00	-0.05	24.90	0.00	0.000	0.00	KOP, 1.00°/100' Build
1106.25	6.06	359.09	1105.12	31.99	24.40	1.00	359.094	-32.03	Begin 6.06° Tangent
7153.84	6.06	359.09	7118.89	670.62	14.30	0.00	0.000	-670.44	Begin 1.00°/100' Drop
7760.09	0.00	0.00	7724.01	702.66	13.79	1.00	180.000	-702.47	Begin Vertical Hold
7860.09	0.00	0.00	7824.01	702.66	13.79	0.00	0.000	-702.47	KOP, 11.00°/100' Build
8680.09	90.20	180.83	8344.88	180.02	6.19	11.00	180.833	-179.78	Begin 90.20° Lateral
9859.89	90.20	180.83	8340.76	-999.64	-10.97	0.00	0.000	1000.00	Begin 2.00°/100' Build
9884.99	90.70	180.83	8340.56	-1024.74	-11.33	2.00	0.013	1025.11	Hold 90.70° Inc, 180.83° Azm
12860.11	90.70	180.83	8304.11	-3999.32	-54.61	0.00	0.000	4000.00	Begin 2.00°/100' Build
12885.13	91.20	180.83	8303.69	-4024.33	-54.97	2.00	-0.018	4025.02	Hold 91.20° Inc, 180.83° Azm
15360.65	91.20	180.83	8251.74	-6499.05	-90.97	0.00	0.000	6500.00	Begin 2.00°/100' Build
15386.18	91.71	180.83	8251.09	-6524.56	-91.34	2.00	-0.027	6525.52	Hold 91.71° Inc, 180.83° Azm
15860.87	91.71	180.83	8236.90	-6999.00	-98.24	0.00	0.000	7000.00	Begin 2.00°/100' Build
15910.53	92.71	180.83	8234.98	-7048.61	-98.96	2.00	0.020	7049.62	Hold 92.71° Inc, 180.83° Azm
18708.28	92.71	180.83	8102.89	-9842.95	-139.61	0.00	0.000	9844.25	PBHL

MS Directional



Azimuths to Grid North
True North: 0.03°
Magnetic North: 6.84°

Magnetic Field
Strength: 47004.8nT
Dip Angle: 59.43°
Date: 9/25/2025
Model: HDGM2025

To convert a Magnetic Direction to a Grid Direction, Add 6.843°
To convert a Magnetic Direction to a True Direction, Add 6.817° East
To convert a True Direction to a Grid Direction, Add 0.026°









Tap Rock Operating
Pabst Fed Com 213H
H&P 466

Tap Rock Operating

Eddy County, New Mexico (NAD 83)
Pabst Fed Com (202H, 204H, 211H, 213H)
Pabst Fed Com 213H

Wellbore #1

Plan: Design #1

Standard Planning Report

25 September, 2025

Planning Report

Database:	TRG_EDMConroe	**Local Co-ordinate Reference:**	Well Pabst Fed Com 213H
Company:	Tap Rock Operating	**TVD Reference:**	Well @ 3657.00usft (H&P 466)
Project:	Eddy County, New Mexico (NAD 83)	**MD Reference:**	Well @ 3657.00usft (H&P 466)
Site:	Pabst Fed Com (202H, 204H, 211H, 213H)	**North Reference:**	Grid
Well:	Pabst Fed Com 213H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project Eddy County, New Mexico (NAD 83)

Map System:	US State Plane 1983	**System Datum:**	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site Pabst Fed Com (202H, 204H, 211H, 213H)

Site Position:		**Northing:**	391,751.51 usft	**Latitude:**	32° 4' 37.182 N
From:	Lat/Long	**Easting:**	526,063.61 usft	**Longitude:**	104° 22' 57.530 W
Position Uncertainty:	0.00 usft	**Slot Radius:**	13-3/16 "		

Well Pabst Fed Com 213H

Well Position	**+N/-S**	0.00 usft	**Northing:**	391,751.47 usft	**Latitude:**	32° 4' 37.182 N
	+E/-W	0.00 usft	**Easting:**	526,088.51 usft	**Longitude:**	104° 22' 57.240 W
Position Uncertainty		0.00 usft	**Wellhead Elevation:**	usft	**Ground Level:**	3,631.00 usft
Grid Convergence:		-0.026 °				

Wellbore Wellbore #1

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM2025	9/25/2025	6.817	59.433	47,004.80

Design Design #1

Audit Notes:

Version:		**Phase:**	PLAN	**Tie On Depth:**	0.00

Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.00	0.00	0.00	180.83

Plan Survey Tool Program **Date** 9/25/2025

	Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	18,708.28	Design #1 (Wellbore #1)	MWD+IFR1+SAG+FDIR OWSG MWD + IFR1 + Sag	

Planning Report

Database:	TRG_EDMConroe	**Local Co-ordinate Reference:**	Well Pabst Fed Com 213H
Company:	Tap Rock Operating	**TVD Reference:**	Well @ 3657.00usft (H&P 466)
Project:	Eddy County, New Mexico (NAD 83)	**MD Reference:**	Well @ 3657.00usft (H&P 466)
Site:	Pabst Fed Com (202H, 204H, 211H, 213H)	**North Reference:**	Grid
Well:	Pabst Fed Com 213H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Plan Sections

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.000	
1,106.25	6.06	359.09	1,105.12	32.04	-0.51	1.00	1.00	0.00	359.094	
7,153.85	6.06	359.09	7,118.89	670.66	-10.60	0.00	0.00	0.00	0.000	
7,760.09	0.00	0.00	7,724.01	702.70	-11.11	1.00	-1.00	0.00	180.000	
7,860.09	0.00	0.00	7,824.01	702.70	-11.11	0.00	0.00	0.00	0.000	
8,680.09	90.20	180.83	8,344.88	180.07	-18.71	11.00	11.00	0.00	180.833	
9,859.89	90.20	180.83	8,340.76	-999.59	-35.87	0.00	0.00	0.00	0.000	T1-1000' VS_Pabst
9,884.99	90.70	180.83	8,340.56	-1,024.69	-36.24	2.00	2.00	0.00	0.013	
12,860.11	90.70	180.83	8,304.11	-3,999.27	-79.51	0.00	0.00	0.00	0.000	T2-4000' VS_Pabst
12,885.13	91.20	180.83	8,303.69	-4,024.29	-79.87	2.00	2.00	0.00	-0.018	
15,360.65	91.20	180.83	8,251.74	-6,499.00	-115.87	0.00	0.00	0.00	0.000	T3-6500' VS_Pabst
15,386.18	91.71	180.83	8,251.09	-6,524.52	-116.24	2.00	2.00	0.00	-0.027	
15,860.87	91.71	180.83	8,236.90	-6,998.95	-123.14	0.00	0.00	0.00	0.000	T4-7000' VS_Pabst
15,910.53	92.71	180.83	8,234.98	-7,048.56	-123.86	2.00	2.00	0.00	0.020	
18,708.28	92.71	180.83	8,102.89	-9,842.90	-164.51	0.00	0.00	0.00	0.000	PBHL_Pabst Fed C

Planning Report

Database:	TRG_EDMConroe	**Local Co-ordinate Reference:**	Well Pabst Fed Com 213H
Company:	Tap Rock Operating	**TVD Reference:**	Well @ 3657.00usft (H&P 466)
Project:	Eddy County, New Mexico (NAD 83)	**MD Reference:**	Well @ 3657.00usft (H&P 466)
Site:	Pabst Fed Com (202H, 204H, 211H, 213H)	**North Reference:**	Grid
Well:	Pabst Fed Com 213H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
39.00	0.00	0.00	39.00	0.00	0.00	0.00	0.00	0.00	0.00
Rustler									
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
310.00	0.00	0.00	310.00	0.00	0.00	0.00	0.00	0.00	0.00
Top Salt									
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
KOP, 1.00°/100' Build									
600.00	1.00	359.09	599.99	0.87	-0.01	-0.87	1.00	1.00	0.00
700.00	2.00	359.09	699.96	3.49	-0.06	-3.49	1.00	1.00	0.00
800.00	3.00	359.09	799.86	7.85	-0.12	-7.85	1.00	1.00	0.00
900.00	4.00	359.09	899.68	13.96	-0.22	-13.95	1.00	1.00	0.00
1,000.00	5.00	359.09	999.37	21.80	-0.34	-21.79	1.00	1.00	0.00
1,106.25	6.06	359.09	1,105.12	32.04	-0.51	-32.03	1.00	1.00	0.00
Begin 6.06° Tangent									
1,200.00	6.06	359.09	1,198.35	41.94	-0.66	-41.93	0.00	0.00	0.00
1,300.00	6.06	359.09	1,297.79	52.50	-0.83	-52.48	0.00	0.00	0.00
1,357.54	6.06	359.09	1,355.00	58.58	-0.93	-58.56	0.00	0.00	0.00
Base Salt									
1,400.00	6.06	359.09	1,397.23	63.06	-1.00	-63.04	0.00	0.00	0.00
1,500.00	6.06	359.09	1,496.67	73.62	-1.16	-73.60	0.00	0.00	0.00
1,580.78	6.06	359.09	1,577.00	82.15	-1.30	-82.12	0.00	0.00	0.00
Delaware Mountain Gp									
1,587.82	6.06	359.09	1,584.00	82.89	-1.31	-82.87	0.00	0.00	0.00
Lamar									
1,600.00	6.06	359.09	1,596.11	84.18	-1.33	-84.15	0.00	0.00	0.00
1,622.02	6.06	359.09	1,618.00	86.50	-1.37	-86.48	0.00	0.00	0.00
Bell Canyon									
1,633.08	6.06	359.09	1,629.00	87.67	-1.39	-87.64	0.00	0.00	0.00
Ramsey Sand									
1,700.00	6.06	359.09	1,695.55	94.74	-1.50	-94.71	0.00	0.00	0.00
1,800.00	6.06	359.09	1,794.99	105.30	-1.66	-105.26	0.00	0.00	0.00
1,900.00	6.06	359.09	1,894.43	115.86	-1.83	-115.82	0.00	0.00	0.00
2,000.00	6.06	359.09	1,993.87	126.42	-2.00	-126.38	0.00	0.00	0.00
2,100.00	6.06	359.09	2,093.31	136.98	-2.17	-136.93	0.00	0.00	0.00
2,200.00	6.06	359.09	2,192.75	147.54	-2.33	-147.49	0.00	0.00	0.00
2,300.00	6.06	359.09	2,292.19	158.10	-2.50	-158.05	0.00	0.00	0.00
2,400.00	6.06	359.09	2,391.63	168.66	-2.67	-168.60	0.00	0.00	0.00
2,485.85	6.06	359.09	2,477.00	177.73	-2.81	-177.67	0.00	0.00	0.00
Cherry Canyon									
2,500.00	6.06	359.09	2,491.07	179.22	-2.83	-179.16	0.00	0.00	0.00
2,600.00	6.06	359.09	2,590.52	189.78	-3.00	-189.72	0.00	0.00	0.00
2,700.00	6.06	359.09	2,689.96	200.34	-3.17	-200.27	0.00	0.00	0.00
2,800.00	6.06	359.09	2,789.40	210.90	-3.33	-210.83	0.00	0.00	0.00
2,900.00	6.06	359.09	2,888.84	221.46	-3.50	-221.39	0.00	0.00	0.00
3,000.00	6.06	359.09	2,988.28	232.02	-3.67	-231.94	0.00	0.00	0.00
3,100.00	6.06	359.09	3,087.72	242.58	-3.83	-242.50	0.00	0.00	0.00
3,200.00	6.06	359.09	3,187.16	253.14	-4.00	-253.06	0.00	0.00	0.00
3,300.00	6.06	359.09	3,286.60	263.70	-4.17	-263.61	0.00	0.00	0.00
3,400.00	6.06	359.09	3,386.04	274.26	-4.34	-274.17	0.00	0.00	0.00

Planning Report

Database:	TRG_EDMConroe	**Local Co-ordinate Reference:**	Well Pabst Fed Com 213H
Company:	Tap Rock Operating	**TVD Reference:**	Well @ 3657.00usft (H&P 466)
Project:	Eddy County, New Mexico (NAD 83)	**MD Reference:**	Well @ 3657.00usft (H&P 466)
Site:	Pabst Fed Com (202H, 204H, 211H, 213H)	**North Reference:**	Grid
Well:	Pabst Fed Com 213H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
3,484.43	6.06	359.09	3,470.00	283.18	-4.48	-283.08	0.00	0.00	0.00
Brushy Canyon									
3,500.00	6.06	359.09	3,485.48	284.82	-4.50	-284.72	0.00	0.00	0.00
3,600.00	6.06	359.09	3,584.92	295.38	-4.67	-295.28	0.00	0.00	0.00
3,700.00	6.06	359.09	3,684.36	305.94	-4.84	-305.84	0.00	0.00	0.00
3,800.00	6.06	359.09	3,783.80	316.50	-5.00	-316.39	0.00	0.00	0.00
3,900.00	6.06	359.09	3,883.24	327.06	-5.17	-326.95	0.00	0.00	0.00
4,000.00	6.06	359.09	3,982.69	337.62	-5.34	-337.51	0.00	0.00	0.00
4,100.00	6.06	359.09	4,082.13	348.18	-5.50	-348.06	0.00	0.00	0.00
4,200.00	6.06	359.09	4,181.57	358.74	-5.67	-358.62	0.00	0.00	0.00
4,300.00	6.06	359.09	4,281.01	369.30	-5.84	-369.18	0.00	0.00	0.00
4,400.00	6.06	359.09	4,380.45	379.86	-6.00	-379.73	0.00	0.00	0.00
4,500.00	6.06	359.09	4,479.89	390.42	-6.17	-390.29	0.00	0.00	0.00
4,600.00	6.06	359.09	4,579.33	400.98	-6.34	-400.85	0.00	0.00	0.00
4,700.00	6.06	359.09	4,678.77	411.54	-6.51	-411.40	0.00	0.00	0.00
4,800.00	6.06	359.09	4,778.21	422.10	-6.67	-421.96	0.00	0.00	0.00
4,900.00	6.06	359.09	4,877.65	432.66	-6.84	-432.51	0.00	0.00	0.00
4,948.62	6.06	359.09	4,926.00	437.79	-6.92	-437.65	0.00	0.00	0.00
Bone Spring Lime									
5,000.00	6.06	359.09	4,977.09	443.22	-7.01	-443.07	0.00	0.00	0.00
5,100.00	6.06	359.09	5,076.53	453.78	-7.17	-453.63	0.00	0.00	0.00
5,200.00	6.06	359.09	5,175.97	464.34	-7.34	-464.18	0.00	0.00	0.00
5,209.08	6.06	359.09	5,185.00	465.30	-7.36	-465.14	0.00	0.00	0.00
Upper Avalon									
5,300.00	6.06	359.09	5,275.42	474.90	-7.51	-474.74	0.00	0.00	0.00
5,400.00	6.06	359.09	5,374.86	485.46	-7.67	-485.30	0.00	0.00	0.00
5,500.00	6.06	359.09	5,474.30	496.02	-7.84	-495.85	0.00	0.00	0.00
5,513.78	6.06	359.09	5,488.00	497.47	-7.86	-497.31	0.00	0.00	0.00
Middle Avalon									
5,600.00	6.06	359.09	5,573.74	506.58	-8.01	-506.41	0.00	0.00	0.00
5,700.00	6.06	359.09	5,673.18	517.14	-8.17	-516.97	0.00	0.00	0.00
5,800.00	6.06	359.09	5,772.62	527.70	-8.34	-527.52	0.00	0.00	0.00
5,858.71	6.06	359.09	5,831.00	533.90	-8.44	-533.72	0.00	0.00	0.00
Lower Avalon									
5,900.00	6.06	359.09	5,872.06	538.26	-8.51	-538.08	0.00	0.00	0.00
5,999.50	6.06	359.09	5,971.00	548.77	-8.67	-548.58	0.00	0.00	0.00
1st Bone Spring Sand									
6,000.00	6.06	359.09	5,971.50	548.82	-8.68	-548.64	0.00	0.00	0.00
6,100.00	6.06	359.09	6,070.94	559.38	-8.84	-559.19	0.00	0.00	0.00
6,200.00	6.06	359.09	6,170.38	569.94	-9.01	-569.75	0.00	0.00	0.00
6,295.15	6.06	359.09	6,265.00	579.99	-9.17	-579.79	0.00	0.00	0.00
2nd Bone Spring Carb									
6,300.00	6.06	359.09	6,269.82	580.50	-9.18	-580.31	0.00	0.00	0.00
6,400.00	6.06	359.09	6,369.26	591.06	-9.34	-590.86	0.00	0.00	0.00
6,500.00	6.06	359.09	6,468.70	601.62	-9.51	-601.42	0.00	0.00	0.00
6,600.00	6.06	359.09	6,568.14	612.18	-9.68	-611.97	0.00	0.00	0.00
6,700.00	6.06	359.09	6,667.59	622.74	-9.84	-622.53	0.00	0.00	0.00
6,770.81	6.06	359.09	6,738.00	630.22	-9.96	-630.01	0.00	0.00	0.00
2nd Bone Spring Sand									
6,800.00	6.06	359.09	6,767.03	633.30	-10.01	-633.09	0.00	0.00	0.00
6,900.00	6.06	359.09	6,866.47	643.86	-10.18	-643.64	0.00	0.00	0.00
6,921.65	6.06	359.09	6,888.00	646.15	-10.21	-645.93	0.00	0.00	0.00
3rd Bone Spring Carb									

Planning Report

Database:	TRG_EDMConroe	**Local Co-ordinate Reference:**	Well Pabst Fed Com 213H
Company:	Tap Rock Operating	**TVD Reference:**	Well @ 3657.00usft (H&P 466)
Project:	Eddy County, New Mexico (NAD 83)	**MD Reference:**	Well @ 3657.00usft (H&P 466)
Site:	Pabst Fed Com (202H, 204H, 211H, 213H)	**North Reference:**	Grid
Well:	Pabst Fed Com 213H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
7,000.00	6.06	359.09	6,965.91	654.42	-10.34	-654.20	0.00	0.00	0.00
7,100.00	6.06	359.09	7,065.35	664.98	-10.51	-664.76	0.00	0.00	0.00
7,153.85	6.06	359.09	7,118.89	670.66	-10.60	-670.44	0.00	0.00	0.00
Begin 1.00°/100' Drop									
7,200.00	5.60	359.09	7,164.81	675.35	-10.68	-675.13	1.00	-1.00	0.00
7,300.00	4.60	359.09	7,264.41	684.24	-10.82	-684.02	1.00	-1.00	0.00
7,400.00	3.60	359.09	7,364.15	691.39	-10.93	-691.16	1.00	-1.00	0.00
7,500.00	2.60	359.09	7,464.01	696.80	-11.01	-696.57	1.00	-1.00	0.00
7,600.00	1.60	359.09	7,563.94	700.47	-11.07	-700.23	1.00	-1.00	0.00
7,700.00	0.60	359.09	7,663.92	702.39	-11.10	-702.16	1.00	-1.00	0.00
7,760.09	0.00	0.00	7,724.01	702.70	-11.11	-702.47	1.00	-1.00	0.00
Begin Vertical Hold									
7,800.00	0.00	0.00	7,763.92	702.70	-11.11	-702.47	0.00	0.00	0.00
7,860.09	0.00	0.00	7,824.01	702.70	-11.11	-702.47	0.00	0.00	0.00
KOP, 11.00°/100' Build									
7,874.09	1.54	180.83	7,838.00	702.52	-11.11	-702.28	11.00	11.00	0.00
3rd Bone Spring Sand									
7,900.00	4.39	180.83	7,863.88	701.18	-11.13	-700.94	11.00	11.00	0.00
7,950.00	9.89	180.83	7,913.47	694.97	-11.22	-694.73	11.00	11.00	0.00
8,000.00	15.39	180.83	7,962.24	684.03	-11.38	-683.79	11.00	11.00	0.00
8,050.00	20.89	180.83	8,009.74	668.47	-11.61	-668.23	11.00	11.00	0.00
8,100.00	26.39	180.83	8,055.52	648.43	-11.90	-648.19	11.00	11.00	0.00
8,150.00	31.89	180.83	8,099.18	624.10	-12.25	-623.85	11.00	11.00	0.00
8,153.33	32.26	180.83	8,102.00	622.33	-12.28	-622.09	11.00	11.00	0.00
3rd BS W Sand									
8,200.00	37.39	180.83	8,140.30	595.69	-12.66	-595.44	11.00	11.00	0.00
8,250.00	42.89	180.83	8,178.51	563.47	-13.13	-563.22	11.00	11.00	0.00
8,268.73	44.95	180.83	8,192.00	550.48	-13.32	-550.23	11.00	11.00	0.00
Wolfcamp A X Sand									
8,300.00	48.39	180.83	8,213.45	527.74	-13.65	-527.49	11.00	11.00	0.00
8,350.00	53.89	180.83	8,244.81	488.83	-14.22	-488.57	11.00	11.00	0.00
8,374.90	56.63	180.83	8,259.00	468.37	-14.52	-468.11	11.00	11.00	0.00
Wolfcamp A Y Sand									
8,400.00	59.39	180.83	8,272.30	447.09	-14.83	-446.82	11.00	11.00	0.00
8,450.00	64.89	180.83	8,295.65	402.90	-15.47	-402.64	11.00	11.00	0.00
8,492.21	69.53	180.83	8,312.00	364.00	-16.03	-363.73	11.00	11.00	0.00
Wolfcamp A Lower									
8,500.00	70.39	180.83	8,314.67	356.69	-16.14	-356.41	11.00	11.00	0.00
8,550.00	75.89	180.83	8,329.17	308.86	-16.84	-308.58	11.00	11.00	0.00
8,600.00	81.39	180.83	8,339.01	259.86	-17.55	-259.58	11.00	11.00	0.00
8,650.00	86.89	180.83	8,344.11	210.15	-18.27	-209.86	11.00	11.00	0.00
8,680.09	90.20	180.83	8,344.88	180.07	-18.71	-179.78	11.00	11.00	0.00
Begin 90.20° Lateral									
8,700.00	90.20	180.83	8,344.81	160.17	-19.00	-159.87	0.00	0.00	0.00
8,800.00	90.20	180.83	8,344.46	60.18	-20.45	-59.88	0.00	0.00	0.00
8,900.00	90.20	180.83	8,344.11	-39.81	-21.91	40.12	0.00	0.00	0.00
9,000.00	90.20	180.83	8,343.76	-139.80	-23.36	140.12	0.00	0.00	0.00
9,100.00	90.20	180.83	8,343.41	-239.79	-24.82	240.12	0.00	0.00	0.00
9,200.00	90.20	180.83	8,343.06	-339.78	-26.27	340.12	0.00	0.00	0.00
9,300.00	90.20	180.83	8,342.71	-439.77	-27.73	440.12	0.00	0.00	0.00
9,400.00	90.20	180.83	8,342.36	-539.76	-29.18	540.12	0.00	0.00	0.00
9,500.00	90.20	180.83	8,342.02	-639.74	-30.64	640.12	0.00	0.00	0.00
9,600.00	90.20	180.83	8,341.67	-739.73	-32.09	740.12	0.00	0.00	0.00

Planning Report

Database:	TRG_EDMConroe	**Local Co-ordinate Reference:**	Well Pabst Fed Com 213H
Company:	Tap Rock Operating	**TVD Reference:**	Well @ 3657.00usft (H&P 466)
Project:	Eddy County, New Mexico (NAD 83)	**MD Reference:**	Well @ 3657.00usft (H&P 466)
Site:	Pabst Fed Com (202H, 204H, 211H, 213H)	**North Reference:**	Grid
Well:	Pabst Fed Com 213H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,700.00	90.20	180.83	8,341.32	-839.72	-33.54	840.12	0.00	0.00	0.00
9,800.00	90.20	180.83	8,340.97	-939.71	-35.00	940.12	0.00	0.00	0.00
9,859.89	90.20	180.83	8,340.76	-999.59	-35.87	1,000.00	0.00	0.00	0.00
Begin 2.00°/100' Build									
9,884.99	90.70	180.83	8,340.56	-1,024.69	-36.24	1,025.11	2.00	2.00	0.00
Hold 90.70° Inc, 180.83° Azm									
9,900.00	90.70	180.83	8,340.38	-1,039.70	-36.45	1,040.12	0.00	0.00	0.00
10,000.00	90.70	180.83	8,339.15	-1,139.68	-37.91	1,140.11	0.00	0.00	0.00
10,100.00	90.70	180.83	8,337.93	-1,239.66	-39.36	1,240.10	0.00	0.00	0.00
10,200.00	90.70	180.83	8,336.70	-1,339.64	-40.82	1,340.09	0.00	0.00	0.00
10,300.00	90.70	180.83	8,335.48	-1,439.63	-42.27	1,440.09	0.00	0.00	0.00
10,400.00	90.70	180.83	8,334.25	-1,539.61	-43.73	1,540.08	0.00	0.00	0.00
10,500.00	90.70	180.83	8,333.03	-1,639.59	-45.18	1,640.07	0.00	0.00	0.00
10,600.00	90.70	180.83	8,331.80	-1,739.57	-46.64	1,740.06	0.00	0.00	0.00
10,700.00	90.70	180.83	8,330.57	-1,839.55	-48.09	1,840.06	0.00	0.00	0.00
10,800.00	90.70	180.83	8,329.35	-1,939.53	-49.54	1,940.05	0.00	0.00	0.00
10,900.00	90.70	180.83	8,328.12	-2,039.52	-51.00	2,040.04	0.00	0.00	0.00
11,000.00	90.70	180.83	8,326.90	-2,139.50	-52.45	2,140.03	0.00	0.00	0.00
11,100.00	90.70	180.83	8,325.67	-2,239.48	-53.91	2,240.03	0.00	0.00	0.00
11,200.00	90.70	180.83	8,324.45	-2,339.46	-55.36	2,340.02	0.00	0.00	0.00
11,300.00	90.70	180.83	8,323.22	-2,439.44	-56.82	2,440.01	0.00	0.00	0.00
11,400.00	90.70	180.83	8,322.00	-2,539.43	-58.27	2,540.00	0.00	0.00	0.00
11,500.00	90.70	180.83	8,320.77	-2,639.41	-59.73	2,640.00	0.00	0.00	0.00
11,600.00	90.70	180.83	8,319.55	-2,739.39	-61.18	2,739.99	0.00	0.00	0.00
11,700.00	90.70	180.83	8,318.32	-2,839.37	-62.64	2,839.98	0.00	0.00	0.00
11,800.00	90.70	180.83	8,317.10	-2,939.35	-64.09	2,939.97	0.00	0.00	0.00
11,900.00	90.70	180.83	8,315.87	-3,039.34	-65.54	3,039.97	0.00	0.00	0.00
12,000.00	90.70	180.83	8,314.65	-3,139.32	-67.00	3,139.96	0.00	0.00	0.00
12,100.00	90.70	180.83	8,313.42	-3,239.30	-68.45	3,239.95	0.00	0.00	0.00
12,200.00	90.70	180.83	8,312.19	-3,339.28	-69.91	3,339.94	0.00	0.00	0.00
12,300.00	90.70	180.83	8,310.97	-3,439.26	-71.36	3,439.94	0.00	0.00	0.00
12,400.00	90.70	180.83	8,309.74	-3,539.25	-72.82	3,539.93	0.00	0.00	0.00
12,500.00	90.70	180.83	8,308.52	-3,639.23	-74.27	3,639.92	0.00	0.00	0.00
12,600.00	90.70	180.83	8,307.29	-3,739.21	-75.73	3,739.91	0.00	0.00	0.00
12,700.00	90.70	180.83	8,306.07	-3,839.19	-77.18	3,839.91	0.00	0.00	0.00
12,800.00	90.70	180.83	8,304.84	-3,939.17	-78.64	3,939.90	0.00	0.00	0.00
12,860.11	90.70	180.83	8,304.11	-3,999.27	-79.51	4,000.00	0.00	0.00	0.00
Begin 2.00°/100' Build									
12,885.13	91.20	180.83	8,303.69	-4,024.29	-79.87	4,025.02	2.00	2.00	0.00
Hold 91.20° Inc, 180.83° Azm									
12,900.00	91.20	180.83	8,303.38	-4,039.15	-80.09	4,039.89	0.00	0.00	0.00
13,000.00	91.20	180.83	8,301.28	-4,139.12	-81.54	4,139.87	0.00	0.00	0.00
13,100.00	91.20	180.83	8,299.18	-4,239.09	-83.00	4,239.84	0.00	0.00	0.00
13,200.00	91.20	180.83	8,297.08	-4,339.05	-84.45	4,339.82	0.00	0.00	0.00
13,300.00	91.20	180.83	8,294.98	-4,439.02	-85.91	4,439.80	0.00	0.00	0.00
13,400.00	91.20	180.83	8,292.89	-4,538.99	-87.36	4,539.78	0.00	0.00	0.00
13,500.00	91.20	180.83	8,290.79	-4,638.96	-88.81	4,639.76	0.00	0.00	0.00
13,600.00	91.20	180.83	8,288.69	-4,738.92	-90.27	4,739.73	0.00	0.00	0.00
13,700.00	91.20	180.83	8,286.59	-4,838.89	-91.72	4,839.71	0.00	0.00	0.00
13,800.00	91.20	180.83	8,284.49	-4,938.86	-93.18	4,939.69	0.00	0.00	0.00
13,900.00	91.20	180.83	8,282.39	-5,038.83	-94.63	5,039.67	0.00	0.00	0.00
14,000.00	91.20	180.83	8,280.29	-5,138.79	-96.09	5,139.65	0.00	0.00	0.00
14,100.00	91.20	180.83	8,278.19	-5,238.76	-97.54	5,239.62	0.00	0.00	0.00

Planning Report

Database:	TRG_EDMConroe	**Local Co-ordinate Reference:**	Well Pabst Fed Com 213H
Company:	Tap Rock Operating	**TVD Reference:**	Well @ 3657.00usft (H&P 466)
Project:	Eddy County, New Mexico (NAD 83)	**MD Reference:**	Well @ 3657.00usft (H&P 466)
Site:	Pabst Fed Com (202H, 204H, 211H, 213H)	**North Reference:**	Grid
Well:	Pabst Fed Com 213H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
14,200.00	91.20	180.83	8,276.10	-5,338.73	-98.99	5,339.60	0.00	0.00	0.00
14,300.00	91.20	180.83	8,274.00	-5,438.69	-100.45	5,439.58	0.00	0.00	0.00
14,400.00	91.20	180.83	8,271.90	-5,538.66	-101.90	5,539.56	0.00	0.00	0.00
14,500.00	91.20	180.83	8,269.80	-5,638.63	-103.36	5,639.54	0.00	0.00	0.00
14,600.00	91.20	180.83	8,267.70	-5,738.60	-104.81	5,739.51	0.00	0.00	0.00
14,700.00	91.20	180.83	8,265.60	-5,838.56	-106.26	5,839.49	0.00	0.00	0.00
14,800.00	91.20	180.83	8,263.50	-5,938.53	-107.72	5,939.47	0.00	0.00	0.00
14,900.00	91.20	180.83	8,261.41	-6,038.50	-109.17	6,039.45	0.00	0.00	0.00
15,000.00	91.20	180.83	8,259.31	-6,138.47	-110.63	6,139.42	0.00	0.00	0.00
15,100.00	91.20	180.83	8,257.21	-6,238.43	-112.08	6,239.40	0.00	0.00	0.00
15,200.00	91.20	180.83	8,255.11	-6,338.40	-113.53	6,339.38	0.00	0.00	0.00
15,300.00	91.20	180.83	8,253.01	-6,438.37	-114.99	6,439.36	0.00	0.00	0.00
15,360.65	91.20	180.83	8,251.74	-6,499.00	-115.87	6,500.00	0.00	0.00	0.00
Begin 2.00°/100' Build									
15,386.18	91.71	180.83	8,251.09	-6,524.52	-116.24	6,525.52	2.00	2.00	0.00
Hold 91.71° Inc, 180.83° Azm									
15,400.00	91.71	180.83	8,250.68	-6,538.33	-116.44	6,539.33	0.00	0.00	0.00
15,500.00	91.71	180.83	8,247.69	-6,638.27	-117.90	6,639.29	0.00	0.00	0.00
15,600.00	91.71	180.83	8,244.70	-6,738.22	-119.35	6,739.24	0.00	0.00	0.00
15,700.00	91.71	180.83	8,241.71	-6,838.16	-120.80	6,839.20	0.00	0.00	0.00
15,800.00	91.71	180.83	8,238.72	-6,938.11	-122.26	6,939.15	0.00	0.00	0.00
15,860.87	91.71	180.83	8,236.90	-6,998.95	-123.14	7,000.00	0.00	0.00	0.00
Begin 2.00°/100' Build									
15,900.00	92.50	180.83	8,235.46	-7,038.04	-123.71	7,039.10	2.00	2.00	0.00
15,910.53	92.71	180.83	8,234.98	-7,048.56	-123.86	7,049.62	2.00	2.00	0.00
Hold 92.71° Inc, 180.83° Azm									
16,000.00	92.71	180.83	8,230.76	-7,137.92	-125.16	7,138.99	0.00	0.00	0.00
16,100.00	92.71	180.83	8,226.04	-7,237.80	-126.61	7,238.88	0.00	0.00	0.00
16,200.00	92.71	180.83	8,221.32	-7,337.68	-128.07	7,338.76	0.00	0.00	0.00
16,300.00	92.71	180.83	8,216.60	-7,437.56	-129.52	7,438.65	0.00	0.00	0.00
16,400.00	92.71	180.83	8,211.87	-7,537.44	-130.97	7,538.54	0.00	0.00	0.00
16,500.00	92.71	180.83	8,207.15	-7,637.31	-132.43	7,638.43	0.00	0.00	0.00
16,600.00	92.71	180.83	8,202.43	-7,737.19	-133.88	7,738.32	0.00	0.00	0.00
16,700.00	92.71	180.83	8,197.71	-7,837.07	-135.33	7,838.21	0.00	0.00	0.00
16,800.00	92.71	180.83	8,192.99	-7,936.95	-136.79	7,938.10	0.00	0.00	0.00
16,900.00	92.71	180.83	8,188.27	-8,036.82	-138.24	8,037.98	0.00	0.00	0.00
17,000.00	92.71	180.83	8,183.55	-8,136.70	-139.69	8,137.87	0.00	0.00	0.00
17,100.00	92.71	180.83	8,178.82	-8,236.58	-141.14	8,237.76	0.00	0.00	0.00
17,200.00	92.71	180.83	8,174.10	-8,336.46	-142.60	8,337.65	0.00	0.00	0.00
17,300.00	92.71	180.83	8,169.38	-8,436.34	-144.05	8,437.54	0.00	0.00	0.00
17,400.00	92.71	180.83	8,164.66	-8,536.21	-145.50	8,537.43	0.00	0.00	0.00
17,500.00	92.71	180.83	8,159.94	-8,636.09	-146.96	8,637.31	0.00	0.00	0.00
17,600.00	92.71	180.83	8,155.22	-8,735.97	-148.41	8,737.20	0.00	0.00	0.00
17,700.00	92.71	180.83	8,150.50	-8,835.85	-149.86	8,837.09	0.00	0.00	0.00
17,800.00	92.71	180.83	8,145.77	-8,935.73	-151.31	8,936.98	0.00	0.00	0.00
17,900.00	92.71	180.83	8,141.05	-9,035.60	-152.77	9,036.87	0.00	0.00	0.00
18,000.00	92.71	180.83	8,136.33	-9,135.48	-154.22	9,136.76	0.00	0.00	0.00
18,100.00	92.71	180.83	8,131.61	-9,235.36	-155.67	9,236.65	0.00	0.00	0.00
18,200.00	92.71	180.83	8,126.89	-9,335.24	-157.13	9,336.53	0.00	0.00	0.00
18,300.00	92.71	180.83	8,122.17	-9,435.12	-158.58	9,436.42	0.00	0.00	0.00
18,400.00	92.71	180.83	8,117.45	-9,534.99	-160.03	9,536.31	0.00	0.00	0.00
18,500.00	92.71	180.83	8,112.72	-9,634.87	-161.49	9,636.20	0.00	0.00	0.00
18,600.00	92.71	180.83	8,108.00	-9,734.75	-162.94	9,736.09	0.00	0.00	0.00
18,708.28	92.71	180.83	8,102.89	-9,842.90	-164.51	9,844.25	0.00	0.00	0.00

Planning Report

Database:	TRG_EDMConroe	**Local Co-ordinate Reference:**	Well Pabst Fed Com 213H
Company:	Tap Rock Operating	**TVD Reference:**	Well @ 3657.00usft (H&P 466)
Project:	Eddy County, New Mexico (NAD 83)	**MD Reference:**	Well @ 3657.00usft (H&P 466)
Site:	Pabst Fed Com (202H, 204H, 211H, 213H)	**North Reference:**	Grid
Well:	Pabst Fed Com 213H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
PBHL									

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
KOP_Pabst Fed Com - plan misses target center by 702.79usft at 0.00usft MD (0.00 TVD, 0.00 N, 0.00 E) - Point	0.00	360.00	0.00	702.70	-11.11	392,454.17	526,077.40	32° 4' 44.136 N	104° 22' 57.373 W
BPP1_Pabst Fed Con - plan misses target center by 4546.02usft at 0.00usft MD (0.00 TVD, 0.00 N, 0.00 E) - Point	0.00	360.00	0.00	-4,545.26	-83.14	387,206.21	526,005.37	32° 3' 52.200 N	104° 22' 58.182 W
LTP_Pabst Fed Com - plan misses target center by 8109.42usft at 18708.28usft MD (8102.89 TVD, -9842.90 N, -164.51 E) - Point	0.00	0.00	0.00	-9,517.77	-155.22	382,233.70	525,933.29	32° 3' 2.990 N	104° 22' 58.993 W
FTP_Pabst Fed Com - plan misses target center by 422.86usft at 0.00usft MD (0.00 TVD, 0.00 N, 0.00 E) - Point	0.00	360.00	0.00	422.71	-11.14	392,174.17	526,077.37	32° 4' 41.365 N	104° 22' 57.372 W
PBHL_Pabst Fed Com - plan hits target center - Point	0.00	0.00	8,102.89	-9,842.90	-164.51	381,908.57	525,924.00	32° 2' 59.772 N	104° 22' 59.100 W
T4-7000' VS_Pabst F - plan hits target center - Point	0.00	360.00	8,236.90	-6,998.95	-123.14	384,752.52	525,965.37	32° 3' 27.917 N	104° 22' 58.634 W
T3-6500' VS_Pabst F - plan hits target center - Point	0.00	360.00	8,251.74	-6,499.00	-115.87	385,252.47	525,972.64	32° 3' 32.865 N	104° 22' 58.552 W
T2-4000' VS_Pabst F - plan hits target center - Point	0.00	360.00	8,304.11	-3,999.27	-79.51	387,752.20	526,009.00	32° 3' 57.603 N	104° 22' 58.143 W
T1-1000' VS_Pabst F - plan hits target center - Point	0.00	360.00	8,340.76	-999.59	-35.87	390,751.88	526,052.64	32° 4' 27.289 N	104° 22' 57.652 W

Planning Report

Database:	TRG_EDMConroe	**Local Co-ordinate Reference:**	Well Pabst Fed Com 213H
Company:	Tap Rock Operating	**TVD Reference:**	Well @ 3657.00usft (H&P 466)
Project:	Eddy County, New Mexico (NAD 83)	**MD Reference:**	Well @ 3657.00usft (H&P 466)
Site:	Pabst Fed Com (202H, 204H, 211H, 213H)	**North Reference:**	Grid
Well:	Pabst Fed Com 213H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Formations

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
39.00	39.00	Rustler			
310.00	310.00	Top Salt			
1,357.54	1,355.00	Base Salt			
1,580.78	1,577.00	Delaware Mountain Gp			
1,587.82	1,584.00	Lamar			
1,622.02	1,618.00	Bell Canyon			
1,633.08	1,629.00	Ramsey Sand			
2,485.85	2,477.00	Cherry Canyon			
3,484.43	3,470.00	Brushy Canyon			
4,948.62	4,926.00	Bone Spring Lime			
5,209.08	5,185.00	Upper Avalon			
5,513.78	5,488.00	Middle Avalon			
5,858.71	5,831.00	Lower Avalon			
5,999.50	5,971.00	1st Bone Spring Sand			
6,295.15	6,265.00	2nd Bone Spring Carb			
6,770.81	6,738.00	2nd Bone Spring Sand			
6,921.65	6,888.00	3rd Bone Spring Carb			
7,874.09	7,838.00	3rd Bone Spring Sand			
8,153.33	8,102.00	3rd BS W Sand			
8,268.73	8,192.00	Wolfcamp A X Sand			
8,374.90	8,259.00	Wolfcamp A Y Sand			
8,492.21	8,312.00	Wolfcamp A Lower			

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates +N/-S (usft)	Local Coordinates +E/-W (usft)	Comment
500.00	500.00	0.00	0.00	KOP, 1.00°/100' Build
1,106.25	1,105.12	32.04	-0.51	Begin 6.06° Tangent
7,153.85	7,118.89	670.66	-10.60	Begin 1.00°/100' Drop
7,760.09	7,724.01	702.70	-11.11	Begin Vertical Hold
7,860.09	7,824.01	702.70	-11.11	KOP, 11.00°/100' Build
8,680.09	8,344.88	180.07	-18.71	Begin 90.20° Lateral
9,859.89	8,340.76	-999.59	-35.87	Begin 2.00°/100' Build
9,884.99	8,340.56	-1,024.69	-36.24	Hold 90.70° Inc, 180.83° Azm
12,860.11	8,304.11	-3,999.27	-79.51	Begin 2.00°/100' Build
12,885.13	8,303.69	-4,024.29	-79.87	Hold 91.20° Inc, 180.83° Azm
15,360.65	8,251.74	-6,499.00	-115.87	Begin 2.00°/100' Build
15,386.18	8,251.09	-6,524.52	-116.24	Hold 91.71° Inc, 180.83° Azm
15,860.87	8,236.90	-6,998.95	-123.14	Begin 2.00°/100' Build
15,910.53	8,234.98	-7,048.56	-123.86	Hold 92.71° Inc, 180.83° Azm
18,708.28	8,102.89	-9,842.90	-164.51	PBHL

PECOS DISTRICT
DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Tap Rock Operating LLC
WELL NAME & NO.:	Pabst Fed Com 213H
LOCATION:	Sec 03-26S-25E-NMP
COUNTY:	Eddy County, New Mexico

Create COAs

H_2S	Cave / Karst	Waste Prevention Rule
Not Reported	Critical	Waste Minimization Plan

Potash	R-111-Q Design
None	

Wellhead	Casing	Cementing
Multibowl	3-String Well	☐ DV Tool ☐ Bradenhead ☐ Echometer
☑ Flex Hose	☐ Liner ☐ Fluid Filled ☐ Casing Clearance	☐ Offline Cement ☐ Open Annulus ☐ Pilot Hole
☑ Break Testing		

Special Requirements

☐ Capitan Reef ☐ Water Disposal ☑ COM ☐ Unit

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H_2S) monitors shall be installed prior to drilling out the surface shoe. If H_2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet 43 CFR 3176 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **11-3/4** inch surface casing shall be set at approximately **350** feet (a minimum of **70'** into the Rustler Anhydrite, above the salt, and below usable fresh water) and cemented to the surface.
    a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic-type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the

Approval Date: 11/21/2025

cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or **500 pounds compressive strength**, whichever is greater (including lead cement.)
c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
d. If cement falls back, remedial cementing will be done prior to drilling out that string.

2. The minimum required fill of cement behind the **8-5/8** inch intermediate casing **(set at 1600' per BLM geologist)** is **cement to surface**. If cement does not circulate, see B.1.a, c-d above.
   - **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry** due to the presence of cave/karst, Capitan Reef, or potash features.

3. The minimum required fill of cement behind the **5-1/2** inch production casing is **cement to surface**. If cement does not circulate, see B.1.a, c-d above.
   - **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry** due to the presence of cave/karst, Capitan Reef, or potash features.

C. PRESSURE CONTROL

1. Operator has proposed a multi-bowl wellhead assembly. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M)** psi.
   a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
   b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
   c. Manufacturer representative shall install the test plug for the initial BOP test.
   d. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
   e. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172 must be followed.

2. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).

3. Break testing has been approved for this well ONLY on those intervals utilizing a 5M BOPE or less. **(Annular preventer must be tested to a minimum of 70% of BOPE**

working pressure and shall be higher than the MASP.) If in the event break testing is not utilized, then a full BOPE test would be conducted.

a. Variance only pertains to the intermediate hole-sections and no deeper than the Bone Springs formation. **BOPE Break Testing is NOT permitted to drill the production hole section.**
b. While in transfer between wells, BOPE shall be secured by the hydraulic carrier or cradle.
c. A full BOPE test is required prior to drilling the first deep intermediate hole section. If any subsequent hole interval is deeper than the first, a full BOPE test will be required. (200' TVD tolerance between intermediate shoes is allowable).
d. As a minimum, a full BOPE test shall be performed at 21-day intervals.
e. In the event any repairs or replacement of the BOPE is required, the BOPE shall test as per **43 CFR 3172**. Any well control event while drilling require notification to the BLM Petroleum Engineer **(575-706-2779)** prior to the commencement of any BOPE Break Testing operations.

D. SPECIAL REQUIREMENT(S)

Communitization Agreement:

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- The operator will submit an as-drilled survey well plat of the well completion, but are not limited to, those specified in 43 CFR 3171 and 3172.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

a. Spudding well (minimum of 24 hours)
b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
c. BOPE tests (minimum of 4 hours)

Contact Eddy County Petroleum Engineering Inspection Staff:

Email or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220; **BLM_NM_CFO_DrillingNotifications@BLM.GOV**; (575) 361-2822

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
    a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
    b. When the operator proposes to set surface casing with Spudder Rig
        i. Notify the BLM when moving in and removing the Spudder Rig.
        ii. Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
        iii. BOP/BOPE test to be conducted per **43 CFR 3172** as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. For intervals in which cement to surface is required, cement to surface should be verified with a visual check and density or pH check to differentiate cement from spacer and drilling mud. The results should be documented in the driller's log and daily reports.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or

if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends of both lead and tail cement, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-Q potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in **43 CFR 3172**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible

hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
    i. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
    ii. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
    iii. Manufacturer representative shall install the test plug for the initial BOP test.
    iv. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed.
    v. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
    i. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
    ii. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
    iii. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve

open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for 8 hours or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

iv. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.

v. The results of the test shall be reported to the appropriate BLM office.

vi. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.

vii. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

viii. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR 3172**.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Hydrogen Sulfide Drilling

Operations Plan

Tap Rock Resources

1 H2S safety instructions to the following:

- Characteristics of H2S
- Physical effects and hazards
- Principal and operation of H2S detectors, warning system and briefing areas
- Evacuation procedures, routes and first aid
- Proper use of safety equipment & life support systems
- Essential personnel meeting medical evaluation criteria will receive additional training on the proper use of 30min pressure demand air packs

2 H2S Detection and Alarm Systems:

- H2S sensor/detectors to be located on the drilling rig floor, in the base of the sub structure / cellar area, on the mud pits in the shale shaker area. Additional H2S detectors may be placed as deemed necessary
- An audio alarm system will be installed on the derrick floor and in the doghouse

3 Windsocks and / Wind Streamers:

- Windsocks at mud pit area should be high enough to be visible
- Windsock on the rig floor and / top of doghouse should be high enough to be visible

4 Condition Flags and Signs:

- Warning sign on access road to location
- Flags to be displayed on sign at entrance to location
    - Green Flag – Normal Safe Operation Condition
    - Yellow Flag – Potential Pressure and Danger
    - Red Flag – Danger (H2S present in dangerous concentrations) Only H2S trained personnel admitted on location

5 Well Control Equipment:

- See Drilling Operations Plan Schematics

6 Communication:

- While working under masks chalkboards will be used for communications
- Hand signals will be used where chalk board is inappropriate
- Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.

7 Drilling Stem Testing:

- No DST cores are planned at this time

8 Drilling contractor supervisor will be required to be familiar with the effects H2S has on tubulars good and other mechanical equipment

9 If H2S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H2S scavengers if necessary

11 Emergency Contacts

Emergency Contacts		
Carlsbad Police Department	575.887.7551	911
Carlsbad Medical Center	575.887.4100	911
Eddy County Fire Service	575.628.5450	911
Eddy County Sherriff	575.887.7551	911
Lea County Fire Service	575.391.2983	911
Lea County Sherriff	575.396.3611	911
Jal Police Department	575.395.2121	911
Jal Fire Department	575.395.2221	911
Tap Rock Resources	720.772.5090	

Rig Diagram
Pabst Fed Com
Tap Rock Operating, LLC
3-26S-25E
Eddy County, NM

N

- Briefing Area
- Current Well
- Flare Stack
- H2S Monitor
- Wind Indicator
- Mud Gas Separator



Tap Rock Operating LLC

Pabst Fed Com Well Pad
H2S Contingency Plan:
2 Mile Radius Map

Sec. 3, Township 26S, Range 25E
Eddy County, New Mexico

Well Pad Location

1:27,000

0 0.25 0.5 1
Miles

N

NAD 1983 New Mexico State Plane East
FIPS 3001 Feet

PERMITS WEST

Prepared by Permits West, Inc., October 3, 2025
for Tap Rock Operating, LLC





Schematic Closed Loop Drilling Rig*

1. Pipe Rack
2. Drill Rig
3. House Trailers/ Offices
4. Generator/Fuel/Storage
5. Overflow-Frac Tank
6. Skids
7. Roll Offs
8. Hopper or Centrifuge
9. Mud Tanks
10. Loop Drive
11. Generator (only for use with centrifuge)

*Not drawn to scale: Closed loop system requires at least 30 feet beyond mud tanks. Ideally 60 feet would be available

Above: Centrifugal Closed Loop System

PERMITS WEST, INC.
PROVIDING PERMITS for LAND USERS
37Verano Loop, Santa Fe, New Mexico 87508 (505) 466-8120

Closed Loop Drilling System: **Mud tanks to right (1)**
Hopper in air to settle out solids (2)
Water return pipe (3)
Shaker between hopper and mud tanks (4)
Roll offs on skids (5)

Flow Chart for Drilling Fluids and Solids



Photos Courtesy of Gandy Corporation Oil Field Service

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
https://www.emnrd.nm.gov/ocd/contact-us

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Operator: TAP ROCK OPERATING, LLC 1700 Lincoln St Denver, CO 80203	OGRID: 372043
	Action Number: 529254
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

ACKNOWLEDGMENTS

☑	I hereby certify that no additives containing PFAS chemicals will be added to the completion or recompletion of this well.

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
https://www.emnrd.nm.gov/ocd/contact-us

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Operator: TAP ROCK OPERATING, LLC 1700 Lincoln St Denver, CO 80203	OGRID: 372043
	Action Number: 529254
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
permitsw	Cement is required to circulate on both surface and intermediate1 strings of casing.	11/24/2025
permitsw	If cement does not circulate on any string, a Cement Bond Log (CBL) is required for that string of casing.	11/24/2025
ward.rikala	Notify the OCD 24 hours prior to casing & cement.	12/8/2025
ward.rikala	File As Drilled C-102 and a directional Survey with C-104 completion packet.	12/8/2025
ward.rikala	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string.	12/8/2025
ward.rikala	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.	12/8/2025