

GW - 004

AGWMR

09/08/2010



Matthew P. Hudson
Remediation Project
Manager

Upstream Business Unit
Chevron Environmental
Management Company
1400 Smith St
Room 07062
Houston, TX 77002
Tel 713 372 9207
mhudson@chevron.com

September 26, 2010

Environmental Bureau Chief
Oil Conservation Division
1220 South St. Francis Drive
Santa Fe, NM 87505

Subject: Annual Reports

Dear Madam/Sir:

Please find enclosed one hardcopy and one electronic copy of the following reports:

2009 Annual Groundwater Monitoring Report and Remedial System Summary
Eunice North Gas Plant, Lea County, NM, GW-004

2009 Annual Report
Lovington Paddock Site, Lea County, NM, 1R-272

2009 Groundwater Monitoring Report
Buckeye Vacuum Unit, Lea County, NM, GW-029

2009 Groundwater Monitoring Report
Buckeye Compressor Site, Lea County, NM, GW-029

Should have you have questions or concerns, please do not hesitate to contact me at (713) 372-9207.

Sincerely,

A handwritten signature in black ink, appearing to read "Matthew P. Hudson", written over a horizontal line.

Matthew P. Hudson

Enclosure


**2009 ANNUAL GROUNDWATER MONITORING REPORT AND
REMEDIAL SYSTEMS SUMMARY
EUNICE NORTH GAS PLANT
Lea County, New Mexico**




Stantec

Prepared and Submitted By:

Stantec Consulting Corporation



Stephanie Peters, Project Engineer



Daniel Woodward, Project Manager

Reviewed By:



Chad Vowell, Senior Project Manager

September 8, 2010

Table of Contents

1.0 SITE BACKGROUND	1
1.1 Site Location and Background	1
1.2 Groundwater Monitoring and Remediation Background	1
1.3 Site Contaminants of Concern Overview	2
1.3.1 Groundwater Chromium	2
1.3.2 Groundwater Hydrocarbons	3
1.3.3 Groundwater Dissolved Solids	3
1.4 Scope of Work	4
2.0 SITE SETTING	5
2.1 Regional Physiography	5
2.2 Regional Geology	5
2.3 Regional Hydrogeology	5
3.0 HYDROGEOLOGIC ASSESSMENT	7
3.1 Groundwater Elevation Measurement	7
3.1.1 March/April 2009 Groundwater Gradient	7
3.1.2 August 2009 Groundwater Gradient	8
4.0 GROUNDWATER SAMPLING PROTOCOL AND ANALYSIS	9
4.1 Groundwater Monitor Well Sampling Protocol	9
4.2 Sampling Schedule Protocol	10
4.3 March/April 2009 Sampling Schedule	10
4.4 August 2009 Sampling Schedule	11
4.5 Sample Handling and Analysis	11
4.6 Investigation Derived Waste Management	12
4.7 Analytical Results	12
4.8 Total Chromium and Hexavalent Chromium Analysis	12
4.8.1 March/April 2009 Total Chromium and Hexavalent Chromium Metals Analysis	12
4.8.2 August 2009 Total Chromium and Hexavalent Chromium Metals Analysis	14
4.9 Chloride Analysis	15
4.9.1 March/April 2009 Chloride Analysis	15
4.9.2 August 2009 Chloride Analysis	16
4.10 Benzene, Toluene, Ethylbenzene, and Xylene Analysis	17
4.10.1 March/April 2009 Benzene, Toluene, Ethylbenzene, and Xylene Analysis	17
4.10.2 August 2009 Benzene, Toluene, Ethylbenzene, and Xylene Analysis	18
4.11 TPH-DRO and TPH-GRO Analysis	19
4.11.1 March/April 2009 TPH-DRO and TPH-GRO Analysis	19
4.11.2 August 2009 TPH-DRO and TPH-GRO Analysis	20
4.12 Inorganic Metals Analysis	20
4.12.1 March/April 2009 Inorganic Metals Analysis	21
4.12.2 August 2009 Inorganic Metals Analysis	22
4.13 Total Dissolved Solids Analysis	22
4.13.1 March/April 2009 Total Dissolved Solids Analysis	23
4.13.2 August 2009 Total Dissolved Solids Analysis	24
4.14 Additional Analysis	24

4.14.1	March/April 2009 Additional Analysis	25
4.14.2	August 2009 Total Dissolved Solids Analysis	26
5.0	OPERATION AND MAINTENANCE ACTIVITIES.....	27
6.0	QUALITY ASSURANCE/QUALITY CONTROL PROGRAM.....	28
6.1	Field Duplicate Samples	28
6.2	Trip Blank Samples.....	29
6.3	Decontamination Procedures.....	29
7.0	CONCLUSIONS AND RECOMMENDATIONS	30
7.1	Conclusions.....	30
7.1.1	Total Chromium and Hexavalent Chromium.....	30
7.1.2	Chloride and TDS.....	31
7.1.3	Benzene, Toluene, Ethylbenzene, and Xylene	32
7.1.4	TPH-DRO and TPH-GRO	32
7.1.5	Inorganic Metals.....	32
7.1.6	Sulfate.....	33
7.2	Recommendations.....	33
7.2.1	Additional Evaluation.....	33
7.2.2	Sampling Schedule	33
7.2.3	Phase-Separated Hydrocarbon Remediation	34
8.0	STATEMENT OF LIMITATIONS.....	35
9.0	REFERENCES.....	36

LIST OF FIGURES

Figure 1	Site Location Map
Figure 2	Site Details Map
Figure 2A	Geologic Cross-Section
Figure 3	Potentiometric Surface Map – Shallow Wells (March/April 2009)
Figure 4	Potentiometric Surface Map – Deep Wells (March/April 2009)
Figure 5	Potentiometric Surface Map – Shallow Wells (August 2009)
Figure 6	Potentiometric Surface Map – Deep Wells (August 2009)
Figure 7	Total Chromium mg/L – Shallow Wells (March/April 2009)
Figure 8	Hexavalent Chromium mg/L – Shallow Wells (March/April 2009)
Figure 9	Total Chromium mg/L – Deep Wells (March/April 2009)
Figure 10	Hexavalent Chromium mg/L – Deep Wells (March/April 2009)
Figure 11	Total Chromium mg/L – Shallow Wells (August 2009)
Figure 12	Hexavalent Chromium mg/L – Shallow Wells (August 2009)
Figure 13	Total Chromium mg/L – Deep Wells (August 2009)
Figure 14	Hexavalent Chromium mg/L – Deep Wells (August 2009)
Figure 15	Chloride mg/L – Shallow Wells (March/April 2009)
Figure 16	Chloride mg/L – Deep Wells (March/April 2009)
Figure 17	Chloride mg/L – Shallow Wells (August 2009)
Figure 18	Chloride mg/L – Deep Wells (August 2009)
Figure 19	Benzene mg/L – Shallow Wells (March/April 2009)
Figure 20	Benzene mg/L – Deep Wells (March/April 2009)
Figure 21	Benzene mg/L – Shallow Wells (August 2009)
Figure 22	Benzene mg/L – Deep Wells (August 2009)
Figure 23	TPH-GRO and TPH-DRO mg/L – Shallow Wells (March/April 2009)
Figure 24	TPH-GRO and TPH-DRO mg/L – Deep Wells (March/April 2009)
Figure 25	TPH-GRO and TPH-DRO mg/L – Shallow Wells (August 2009)
Figure 26	TPH-GRO and TPH-DRO mg/L – Deep Wells (August 2009)

LIST OF TABLES

Table 1	CUMULATIVE GROUNDWATER ELEVATION DATA
Table 2	SUMMARY OF 2009 GROUNDWATER ANALYTICAL RESULTS
Table 3	SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
Table 4	SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS

LIST OF APPENDICES

APPENDIX A	CUMULATIVE GROUNDWATER FIELD PARAMETERS
APPENDIX B	LABORATORY ANALYTICAL REPORTS
APPENDIX C	2009 OPERATIONS AND MAINTENANCE FIELD REPORTS

1.0 SITE BACKGROUND

This report summarizes the 2009 semi-annual groundwater monitoring program by Stantec Consulting Corporation (Stantec) on behalf of Chevron Environmental Management Company (CEMC) at the Eunice North Gas Plant (OGRID No. 4323). For the purpose of this report, the monitored area consists of the original gas plant property and surrounding areas (Site) included in the groundwater monitoring program. Site activities for 2009 included:

- Two semi-annual groundwater sampling events conducted in March/April and August ; and
- Monthly operation and maintenance (O&M) Site visits to gauge two (2) monitor wells for phase separated hydrocarbon (PSH) thickness.

1.1 Site Location and Background

The Eunice North Gas Plant (Plant) is located in the southeast corner of New Mexico, in Lea County. The Site is approximately 0.25 miles north of the town of Eunice in the south half (S/2) of the southeast quarter (SE/4) of the northeast quarter (NE/4) of Section 28, Township 21 South (T-21-S), Range 37 East (R-37-E). The approximate latitude/longitude coordinates are 32° 27' 01.46" N and 103° 09' 42.71" W. A Site Location Map is presented as **Figure 1**.

The Plant was originally constructed in the 1940s, and was owned and operated by Texaco from the 1940s through 1998. In 1998, plant ownership was transferred to Versado LLP (Versado), a partnership between Texaco and Dynegy Midstream Services (Dynegy). Dynegy operated the Plant for Versado. The Plant has not operated as a gas plant since Versado assumed ownership in 1998. Gas plant operations ceased and the operational equipment has been partially dismantled with much of the equipment shut-in. In 2005, Dynegy was purchased by Targa Midstream Services (Targa), and Targa became the Plant operator for Versado. The Plant is currently operated by Targa as a natural gas compressor station under an agreement with Chevron. Targa has also operated two compressors in the northwest portion of the Site since 2005. A Site Details Map is presented as **Figure 2**.

1.2 Groundwater Monitoring and Remediation Background

Dissolved benzene and chromium concentrations were detected in the soil and groundwater within the plant boundaries in the early 1990s during Texaco's renewal process of the plant Groundwater Discharge Permit with the New Mexico Oil Conservation Division (NMOCD). In August 1996, the NMOCD required an initial investigation to evaluate the integrity of process area sumps at the Plant. Dissolved benzene and dissolved chromium were detected in groundwater above the State of New Mexico Water Quality Control Commission (WQCC) Human Health standards, which was documented in the *Subsurface Environmental Assessment Report* (Highlander, 1996). The possible source of the chromium was defined as cooling tower blowdown discharged to the surface southwest of the plant.

Several soil and groundwater investigations were conducted between 1996 and 2003, with semi-annual groundwater monitoring beginning in 2004. Based on the groundwater investigations, the three primary groups of dissolved-phase groundwater constituents of concern (COCs) for this Site are: chromium, petroleum hydrocarbons, and dissolved solids (chloride concentrations have been monitored as representative of the dissolved solids). Additionally,

PSH was observed in two wells (MW005 and MW006). PSH recovery and remediation activities were initiated in 2004. Currently, neither well exhibits measurable PSH accumulations.

Beginning in 2003, remedial efforts for chromium concentrations exceeding regulatory action levels began through In-Situ Reactive Zone (IRZ) treatment at a "study area" consisting of three injection wells near the area of the highest chromium concentrations. The study was followed by the addition of an array of 14 injection wells at the distal end of the chromium plume. The IRZ process used a carbohydrate-based electron donor (molasses) to stimulate reducing conditions in the subsurface to reduce hexavalent chromium to trivalent chromium. IRZ was discontinued in September 2005 based on bench-scale test results which suggested a more effective technology was available.

The remedial approach selected for future in-situ treatment of the dissolved-phase hexavalent chromium groundwater is anticipated to be injection of an inorganic reducing agent (calcium polysulfide or sodium sulfide) along with an electron donor (sodium acetate). The calcium polysulfide will provide rapid reduction of hexavalent chromium within the injection area, while the sodium acetate will create a reducing zone through biological activity capable of treating hexavalent chromium migrating into the injection area.

In 2006, a sampling reduction proposal was submitted and approved by the NMOCD. This reduced the number of wells in each event and removed analytes from the sampling program.

1.3 Site Contaminants of Concern Overview

There are three COCs remaining at the Site affecting groundwater quality: chromium (total chromium and hexavalent chromium species), petroleum hydrocarbons, and dissolved solids. Significant reductions in the chromium concentrations have been noted in areas where the chromate and hydrocarbon intermix in the groundwater. Therefore, previous and planned remediation strategies have been designed to utilize this naturally occurring process.

1.3.1 Groundwater Chromium

The primary source of fresh water at the Site is the Ogallala Aquifer (as described in **Section 2.3**). Active remediation of the groundwater affected by dissolved-phase chromium at the Site has been suspended due to concerns with the aquifer geochemistry. The Ogallala Aquifer at the Site has poor but definite hydraulic continuity, resulting in stratified concentrations of chromium within the aquifer. The chromium impact within the aquifer has been divided into two zones, designated as the "shallow" and "deep" zones.

Historically, the highest chromium concentrations in the deep zone of the aquifer occur on the eastern and southeastern edge of the Plant. The plume appears to move with the hydraulic gradient northeastward and eastward. The deep zone hydraulically merges with the shallow zone as the aquifer thins in gross saturated thickness east of the Plant. The aquifer is considered, hydrogeologically, to be part of the deep zone east of the Plant.

The chromium concentrations exceeding regulatory action levels are fully defined in all but the north and northeastern most direction in the deep zone. The shallow zones are fully defined to the south and west. Data gathered through previous assessment events indicate that

chromium, most likely originating from surface sources, has percolated into the groundwater. The potential chromium source is thought to have originated to the south and southwest of the plant and possibly within the plant site itself.

Chromium concentrations in the shallow zone are, historically, the greatest to the southwest, south, and along the eastern edge of the Plant. Chromium exceeding regulatory action levels appears to move with the hydraulic gradient northeastward and then eastward.

Hydrocarbon concentrations above regulatory action levels have been previously observed in the plant area. The hydrocarbon plume consists of dissolved and light phase separated components. Chromium concentrations appear to have been reduced in areas where the hydrocarbon and chromium plumes intersect.

1.3.2 Groundwater Hydrocarbons

PSH accumulations have historically been observed in two wells, MW005 and MW006. The wells are located near the eastern edge of the Plant. These wells were historically gauged and product was recovered from one of the wells on a weekly basis. However, product levels have fallen dramatically over the last few years and have been consistently below measurable limits in 2009. Based on these observations, it was proposed to NMOCD, in a letter dated June 14, 2006, and again in a letter dated March 20, 2008, to discontinue the weekly monitoring and PSH removal to be replaced by a mutually agreed upon form of passive PSH collection in the wells that would achieve similar results. NMOCD acceptance of the modification was not received; therefore, weekly monitoring was continued through December of 2008 and monitoring was reduced to a monthly frequency in 2009.

As noted in the chromium section above, the dissolved hydrocarbons are in a near ideal location to assist in the remediation of the chromium plume. The hydrocarbon acts as a food source promoting the proliferation of naturally occurring bacteria. This bacterial growth in turn produces a reducing environment within the aquifer resulting in the chemical reduction of the chromium.

1.3.3 Groundwater Dissolved Solids

Dissolved solids concentrations above regulatory action levels have been identified at the Site. Brine water produced during regional oil and gas production activities is believed to have percolated into the Ogallala Aquifer. Laboratory analysis was conducted to quantify several of the dissolved major minerals whose sum is commonly referred to as Total Dissolved Solids (TDS).

Chloride distribution and historical process knowledge of plant operations suggest elevated chlorides are unrelated to plant operation. The highest concentrations are located to the south and southwest of the plant (hydraulically up-gradient) and to the east of the plant (hydraulically down-gradient). The sources of the chloride impact have not been determined with any certainty. However, on December 7 through December 12, 2009, soil assessment activities were conducted in suspected chloride source areas in and surrounding the former Eunice North Gas Plant. The results of this analysis will be submitted under a separate letter report.

1.4 Scope of Work

The 2009 Site activities included semi-annual groundwater gauging and sampling in March/April and August, and monthly PSH monitoring at two well locations. The scope of work described in this report consisted of:

- Semi-annual collection of groundwater samples for analysis of petroleum constituents (benzene, toluene, ethylbenzene, and xylenes [BTEX], Gasoline Range Organics [GRO], Diesel Range Organics [DRO]), chromium, hexavalent chromium, and chloride Concentrations] from each available well location identified in the Sampling and Analysis Plan using a submersible pump; and
- Monthly O&M at the Site involving the gauging of monitor wells MW005 and MW006 using an oil-water interface probe to determine the PSH thickness.

2.0 SITE SETTING

A file review of previously submitted soil boring and groundwater monitor well completion logs indicates the following geology at the Site:

- Interbedded sand and sandstone from the ground surface to approximately twenty (20) feet below ground surface (bgs).
- A caliche strata layer extends from twenty (20) feet bgs to a sand layer found at approximately sixty-five (65) feet bgs.
- The sand layer overlays a layer of clay found at approximately sixty-five (65) to ninety (90) feet bgs.
- The clay overlays a second sand and gravel stratum that extends to approximately one-hundred fifteen (115) feet bgs.
- Clay beds are encountered at approximately one-hundred fifteen (115) feet bgs and define the total depth of the Site wells.

A geologic cross-section of the Site, including pertinent COC analytical results, is presented as **Figure 2A**.

2.1 Regional Physiography

The Site is located in the southeast corner of New Mexico near the northern edge of the City of Eunice in the southern half of Lea County. The Site lies in the Pecos River Basin of the Great Plains physiographic province. The Site also lies in the Eunice Plain, which is bounded on the south by the South Plain, on the east by Rattlesnake Ridge, on the northeast by the High Plains, on the northwest by the Laguna Valley and Gramma Ridge Area, on the west by the San Simone Ridge and San Simone Swale, and to the west by Antelope Ridge Area.

2.2 Regional Geology

The geologic formations of interest at the Site include (from the oldest to the youngest): Triassic Chinle; Cretaceous undifferentiated; Tertiary Ogallala; and Quaternary windblown (eolian) sediments, designated as the Blackwater Draw Formation. Of particular interest with regard to the groundwater impact at the Site are the Tertiary Ogallala and the Blackwater Draw which together make up the Ogallala Aquifer.

2.3 Regional Hydrogeology

The primary source of fresh water at the Site is the Ogallala Aquifer. The Ogallala Aquifer at the Site consists of the fluvial and eolian sediments of the Tertiary Ogallala Formation and the eolian sediments of the Quaternary Blackwater Draw Formation. The Ogallala aquifer is bounded unconformably upon the erosional surface of the claystones, sandstones, and siltstones of the Triassic Chinle Formation. The Chinle forms the base of the fresh groundwater in the area because of the Chinle's low vertical permeability.

The base of the Ogallala Aquifer is composed of five to ten feet of gravel, sand, and clay. This gravel unit is overlain by alternating layers of loose and well consolidated red and yellow sandstones. Previous investigators termed the gravel unit as the "deep" water-bearing zone

and the overlying sandstones as the "shallow" water bearing zone. Overall depth to groundwater roughly varies with topography across the Site, ranging from roughly 30 to 90 feet.

3.0 HYDROGEOLOGIC ASSESSMENT

Currently, 144 wells are located at the Site and utilized to provide assessment of groundwater conditions and migration characteristics.

The primary objectives of the groundwater gauging activities at the Site are to:

- Monitor groundwater elevations;
- Determine borehole annular volume to calculate purge volumes;
- Provide data to determine hydraulic gradient; and
- Utilize this data to compare to historical data for assessment of historical groundwater trends.

3.1 Groundwater Elevation Measurement

Before groundwater sampling activities commenced, an oil-water interface probe (accurate to the nearest +0.01 feet) was used to measure the depth to groundwater, PSH thickness, and total well depth from the surveyed point on the rim of each well's top of casing. Depth to groundwater, depth to PSH, and total well depth measurements were recorded on the Groundwater Field Log. Data from the 2009 events were utilized to calculate groundwater elevations which were then utilized to determine an apparent groundwater gradient and direction of flow.

A measurable accumulation of PSH was not observed in any of the wells during the 2009 events. A Cumulative Groundwater Elevation Data table is included as **Table 1**.

3.1.1 March/April 2009 Groundwater Gradient

During the March/April 2009 event, the shallow zone (as described in **Section 4.2**) groundwater elevations ranged from 3,381.79 feet above mean sea level (AMSL) in MW026 to 3,376.90 feet AMSL in MW034. These groundwater elevations indicate a general groundwater flow from a high in the area of MW026 located south of the plant to a low in the area of MW034, located north-northeast of the plant. The groundwater appears to move radially from the southwest area wells, then to the north and northeast as it passes under the plant at an approximate gradient of 0.006 ft/ft. The March/April 2009 shallow zone groundwater elevations were used to generate the Potentiometric Surface Map – Shallow Wells (March/April 2009), depicted on **Figure 3**.

During the March/April 2009 event, the deep zone (as described in **Section 4.2**) groundwater elevations ranged from 3,381.60 feet AMSL in MW014A to 3,350.08 feet AMSL in GOPWW2. These groundwater elevations indicate a general groundwater flow from a high in the area of MW014A located south of the plant to a low in the area of GOPWW2, located north-northeast of the plant. The groundwater flow is to the northeast at an approximate gradient of 0.017 ft/ft. In the eastern portion of the Site, there is also a significant increase in gradient as the base of the aquifer mounds upward at the northeast portion of the Site in the area of IW010, IW011, IW012, and IW013, requiring the groundwater to flow to the north and south around the mound. The March/April 2009 deep zone groundwater elevations were used to generate the Potentiometric Surface Map – Deep Wells (March/April 2009), depicted on **Figure 4**.

3.1.2 August 2009 Groundwater Gradient

During the August 2009 event, the shallow zone groundwater elevations ranged from 3,381.52 feet AMSL in MW026 to 3,376.95 feet AMSL in MW021. These groundwater elevations indicate a general groundwater flow from a high in the area of MW026 located south of the plant to a low in the area of MW021 located north to northeast of the plant. The groundwater appears to move to the west, northwest, and north from the area of MW026, then gradually shift to the north and northeast as it passes under the plant at an approximate gradient of 0.004 ft/ft. The August 2009 shallow zone groundwater elevations were used to generate the Potentiometric Surface Map – Shallow Wells (August 2009), depicted on **Figure 5**.

During the August 2009 event, the deep zone groundwater elevations ranged from 3,381.28 feet AMSL in MW014A to 3,350.23 feet AMSL in GOPWW2. These groundwater elevations indicate a general groundwater flow from the western half of the Site (south of the plant and in plant area) to the northwest, north, and northeast at an approximate gradient of 0.008 ft/ft. The gradient increases to the east of the plant to an approximate gradient of 0.018 ft/ft. The somewhat radial gradient noted to the southwest of the plant shifting to the north and eventually to the north-northeast of the plant, was observed during both events and is consistent with those observed during previous events. The August 2009 deep zone groundwater elevations were used to generate the Potentiometric Surface Map – Deep Wells (August 2009), depicted on **Figure 6**.

4.0 GROUNDWATER SAMPLING PROTOCOL AND ANALYSIS

Groundwater analytical data from the Site are utilized to:

- Assess the effect of historic site activities on groundwater conditions at the Site;
- Monitor potential off-site migration of the impacted groundwater; and
- Maintain compliance with the NMOCD regulations.

4.1 Groundwater Monitor Well Sampling Protocol

Beginning with the least-impacted wells, and prior to sampling, each well was purged using low-flow techniques utilizing a submersible pump positioned two to ten feet from the bottom of the well. During well purging, water quality parameters were measured using a multi-meter with flow-through-cell and recorded on the Groundwater Sampling Field Data Sheets every three to five minutes. Purging was conducted until a minimum of three well volumes of groundwater was removed or water quality parameters stabilized for three consecutive readings within the following limits:

- Dissolved oxygen (DO) - 10%;
- Conductivity - 3%;
- Temperature - 3%;
- pH - ± 0.1 unit; and
- Oxidation reduction potential (ORP) - ± 10 millivolts.

Groundwater samples were collected before groundwater had passed through the flow-through-cell. Volatile organic compound samples were collected first and pre-preserved sample containers were filled prior to pumping water into the flow through cell. The pump rate was reduced when samples were collected for benzene, toluene, ethylbenzene, and xylene (BTEX) due to the volatility of the analyte. During the March/April 2009 sampling event, 66 wells were purged using the low-flow procedures. During the August 2009 sampling event, 8 wells were purged using low-flow procedures. The remaining wells were purged by pumping a minimum of three well volumes of groundwater or until water quality parameters stabilized for three consecutive readings.

Groundwater samples collected for metals analysis were field filtered into pre-preserved containers using high-capacity, 0.45- μ m, disposable filters. All sample containers were filled by allowing the pump discharge to flow with minimal turbulence into the sampling container. If a sample could not be filtered in the field, the chain of custody was marked "Filter at Lab" and an unpreserved bottle was used.

If a duplicate sample was collected at a location, all bottles designated for a particular analysis at that location were filled before bottles for another analysis were filled.

Indicator field parameters were recorded at the time of sample collection, and cumulative groundwater field parameters are summarized in **Appendix A**.

4.2 Sampling Schedule Protocol

As described in **Section 2.3**, the water bearing aquifer is divided into "shallow" and "deep" water bearing zones. Therefore, the well identifications of the Site well locations, summarized below, have been designated in the same manner:

Shallow zone wells:

- Forty-six shallow zone monitor wells;
- Four middle zone monitor wells (included in the "shallow" zone for simplicity);
- Two shallow zone injection wells (IW001 and IW002); and
- Two shallow zone recovery wells (RW002 and RW003).

Deep zone wells:

- Sixty-one deep zone monitor wells (identified by an A or an SA designation added to the end of the well location name; i.e.: MW002A);
- Thirteen deep zone injection wells at the distal array (IW012 is not sampled);
- Eleven deep zone medial array injection wells;
- One deep zone recovery well (RW004A); and
- Five deep zone water wells (drilled and owned by landowners).

During the March/April 2009 and August 2009 events, groundwater samples could not be collected from the following wells due to access issues:

ROLANDWW, MW001, MW003, MW007, MW026, MW027, MW047, MW069, and MW007A.

Well locations are detailed on **Figure 2**.

4.3 March/April 2009 Sampling Schedule

During the March/April 2009 sampling event, groundwater samples were collected from 136 wells, excluding any wells deemed inaccessible. The NMOCD and neighboring property owners requiring notification were notified prior to each sampling event. The well designations for the March/April 2009 sampling event are summarized below:

- **Forty-Seven shallow zone monitoring wells:** MW002, MW004, MW005, MW006, MW008, MW008M, MW009, MW010, MW011, MW011M, MW012, MW012M, MW013, MW014, MW015, MW018, MW020, MW021, MW023, MW024, MW025, MW028, MW029, MW030, MW031, MW032, MW033, MW034, MW035, MW036, MW037, MW038, MW043, MW044, MW045, MW046, MW058, MW059, MW060, MW061, MW068, MW070, MW088M, RW002, RW003, IW001, and IW002.
- **Eighty-four deep zone monitoring wells:** MW002A, MW004A, MW008A, MW009A, MW011A, MW012A, MW013A, MW014A, MW015A, MW016A, MW018A, MW019A, MW020A, MW021A, MW022A, MW023A, MW024A, MW039A, MW040A, MW041A, MW042A, MW046A, MW048SA, MW049SA, MW050SA, MW051SA, MW052SA, MW053SA, MW054SA, MW055SA, MW056SA, MW057SA, MW062A, MW063A, MW064SA, MW065SA, MW066SA, MW067SA, MW070A, MW071SA, MW072SA, MW073SA, MW074SA, MW075SA, MW076SA, MW077SA, MW078SA, MW079SA, MW080SA, MW081SA, MW082SA, MW083SA, MW084SA, MW085SA, MW086SA, MW087A, MW089SA, MW090SA, MW091SA, MW092SA, MW093SA, IW003, IW004,

IW005, IW006, IW007, IW008, IW009, IW010, IW011, IW013, IW014, IW015, IW016, IW018, IW019, IW020, IW021, IW022, IW023, IW024, IW025, IW026, IW027, and IW028, and RW004A.

- **Five privately owned water wells:** GOPWW2, LORDWW, ROLANDWW, WOODPELLWW, and EPWW1.

4.4 August 2009 Sampling Schedule

For the August 2009 sampling event, groundwater samples were collected from 74 wells, excluding any wells deemed inaccessible. The NMOCD and neighboring property owners requiring notification were notified prior to each sampling event. The well designations for the August 2009 sampling event are summarized below:

- **Twenty-Five shallow zone monitoring wells:** MW010, MW013, MW014, MW015, MW018, MW020, MW021, MW023, MW024, MW025, MW026, MW027, MW028, MW029, MW030, MW031, MW032, MW033, MW058, MW059, MW060, MW061, MW068, MW069, and MW070.
- **Forty-five deep zone monitoring wells:** MW013A, MW014A, MW015A, MW016A, MW018A, MW019A, MW020A, MW021A, MW022A, MW023A, MW024A, MW040A, MW048SA, MW053SA, MW054SA, MW055SA, MW056SA, MW057SA, MW062A, MW063A, MW064SA, MW065SA, MW066SA, MW067SA, MW070A, MW071SA, MW072SA, MW073SA, MW074SA, MW075SA, MW076SA, MW077SA, MW078SA, MW079SA, MW080SA, MW081SA, MW082SA, MW083SA, MW084SA, MW085SA, MW086SA, MW090SA, IW023, IW024, IW025, and IW026.
- **Three privately owned water wells:** GOPWW2, LORDWW, and WOODPELLWW.

4.5 Sample Handling and Analysis

Following collection, groundwater samples were labeled, logged on a laboratory chain of custody, and placed on ice in an insulated cooler to maintain a temperature of approximately 4°C. Groundwater samples were transported via FedEx to the analytical laboratory. Proper chain of custody documentation was maintained throughout the sampling and analysis process.

All groundwater samples were analyzed by Lancaster Laboratories in Lancaster, Pennsylvania. The groundwater samples collected during the March/April and August 2009 groundwater sampling events were analyzed for:

- BTEX by EPA Method 8021B;
- Total petroleum hydrocarbons (TPH) as gasoline range organics (GRO) and diesel range organics (DRO) by EPA Method 8015B;
- Total metals (arsenic, chromium, iron, manganese) by EPA Method 6010B;
- Hexavalent chromium by EPA Method 7196A;
- Chloride by EPA Method 300.0; and
- TDS by EPA Method 160.1.

Injection well locations IW023 through IW026 and monitor well location MW090SA were analyzed for the following analytes in addition to those indicated above:

- Sodium by EPA Method 6010B;
- Alkalinity (pH 4.5 and pH 8.3) by SM20 2320B;
- pH by SM20 4500-H+B;
- Sulfate by EPA Method 300.0;
- Sulfide by SM20 4500 S2 D; and
- Total Organic Carbon (TOC) by SM20 5310C.

4.6 Investigation Derived Waste Management

Purged groundwater was pumped from the wells into a 500-gallon poly tank during sampling activities, and later pumped into a disposal well located on the plant property.

4.7 Analytical Results

The analytical results of all groundwater samples collected during the two semi-annual sampling events are compared against the NMWQCC Human Health or Domestic Water Supply standards and exceedances are indicated in the tabulated data. Results for each group of analytes are discussed below. Summaries of the March/April 2009 and August 2009 groundwater sampling results have been tabulated in **Table 2** through **Table 4**. Quality control sample results are discussed in **Section 6**. The laboratory analytical reports can be found in **Appendix B**.

All analytical data is provided to the respective water well owners following each sampling event.

4.8 Total Chromium and Hexavalent Chromium Analysis

During the March/April 2009 and August 2009 events, groundwater samples were analyzed for total chromium and hexavalent chromium metals. A discussion of total chromium and hexavalent chromium metals analytical results for each event and well type is presented in the following sections. **Table 2** includes a summary of the 2009 cumulative total chromium and hexavalent chromium metals analytical results and compares the results with the NMWQCC Human Health Standards.

4.8.1 March/April 2009 Total Chromium and Hexavalent Chromium Metals Analysis

Shallow Monitor Wells

Groundwater samples were collected from 47 shallow monitor wells for total chromium and hexavalent chromium metals analysis. The regulatory limit for total chromium and hexavalent chromium concentrations is defined by the NMWQCC Human Health Standard of 0.05 mg/L. The reported total chromium and hexavalent chromium metals analytical results are presented below:

	<u>Total Chromium</u>		<u>Hexavalent Chromium</u>	
Number of Detections	20		14	
Exceedances Above Regulatory Limit	17		9	
Minimum Concentration (mg/L)	0.0219	MW009	0.033	MW010
Maximum Concentration (mg/L)	3.67	MW011	3.8	MW011

An isopleth map, Total Chromium mg/L – Shallow Wells (March/April 2009), is presented as **Figure 7**. An isopleth map, Hexavalent Chromium mg/L – Shallow Wells (March/April 2009), is presented as **Figure 8**.

Deep Monitor Wells

Groundwater samples were collected from 85 deep monitor wells for total chromium and hexavalent chromium metals analysis. The regulatory limit for total chromium and hexavalent chromium concentrations is defined by the NMWQCC Human Health Standard of 0.05 mg/L. The reported total chromium and hexavalent chromium metals analytical results are presented below:

	<u>Chromium</u>		<u>Hexavalent Chromium</u>	
Number of Detections	54		39	
Exceedances Above Regulatory Limit	40		35	
Minimum Concentration (mg/L)	0.0152	IW003	0.022	MW022A
Maximum Concentration (mg/L)	3.77	MW011A	3.7	MW011A

Water Wells

Groundwater samples were collected from four privately owned water wells for total chromium and hexavalent chromium metals analysis. The regulatory limit for total chromium and hexavalent chromium concentrations is defined by the NMWQCC Human Health Standard of 0.05 mg/L. The reported total chromium and hexavalent chromium metals analytical results are presented below:

	<u>Chromium</u>		<u>Hexavalent Chromium</u>	
Number of Detections	1		1	
Exceedances Above Regulatory Limit	--		--	
Maximum Concentration (mg/L)	0.0296	WoodellWW	0.022	WoodellWW

An isopleth map including deep monitor well and private water well locations, Total Chromium mg/L – Deep Wells (March/April 2009), is presented as **Figure 9**. An isopleth map including deep monitor well and private water well locations, Hexavalent Chromium mg/L – Deep Wells (March/April 2009), is presented as **Figure 10**.

-- indicates a numeric value of zero.

4.8.2 August 2009 Total Chromium and Hexavalent Chromium Metals Analysis

Shallow Monitor Wells

Groundwater samples were collected from 25 shallow monitor wells for total chromium and hexavalent chromium metals analysis. The regulatory limit for total chromium and hexavalent chromium concentrations is defined by the NMWQCC Human Health Standard of 0.05 mg/L. The reported total chromium and hexavalent chromium metals analytical results are presented below:

	<u>Chromium</u>		<u>Hexavalent Chromium</u>	
Number of Detections	7		7	
Exceedances Above Regulatory Limit	5		5	
Minimum Concentration (mg/L)	0.0387	MW010	0.028	MW010
Maximum Concentration (mg/L)	4.24	MW061	4.4	MW061

An isopleth map, Total Chromium mg/L – Shallow Wells (August 2009), is presented as **Figure 11**. An isopleth map, Hexavalent Chromium mg/L – Shallow Wells (August 2009), is presented as **Figure 12**.

Deep Monitor Wells

Groundwater samples were collected from 46 deep monitor wells for total chromium and hexavalent chromium metals analysis. The regulatory limit for total chromium and hexavalent chromium concentrations is defined by the NMWQCC Human Health Standard of 0.05 mg/L. The reported total chromium and hexavalent chromium metals analytical results are presented below:

	<u>Chromium</u>		<u>Hexavalent Chromium</u>	
Number of Detections	18		15	
Exceedances Above Regulatory Limit	12		12	
Minimum Concentration (mg/L)	0.0156	MW085SA	0.031	MW021A
Maximum Concentration (mg/L)	1.47	IW024	1.2	IW024

Water Wells

Groundwater samples were collected from three privately owned water wells for total chromium and hexavalent chromium metals analysis. The regulatory limit for total chromium and hexavalent chromium concentrations is defined by the NMWQCC Human Health Standard of 0.05 mg/L. The reported total chromium and hexavalent chromium metals analytical results are presented below:

	<u>Chromium</u>		<u>Hexavalent Chromium</u>	
Number of Detections	1		1	
Exceedances Above Regulatory Limit	1		1	
Maximum Concentration (mg/L)	0.0561	WoodellWW	0.058	WoodellWW

An isopleth map including deep monitor well and private water well locations, Total Chromium mg/L – Deep Wells (August 2009), is presented as **Figure 13**. An isopleth map including deep monitor well and private water well locations, Hexavalent Chromium mg/L – Deep Wells (August 2009), is presented as **Figure 14**.

4.9 Chloride Analysis

During the March/April 2009 and August 2009 events, groundwater samples were analyzed for chloride. Table 2 includes a summary of the 2009 cumulative chloride analytical results and compares the results with the NMWQCC Human Health standards.

4.9.1 March/April 2009 Chloride Analysis

Shallow Monitor Wells

Groundwater samples were collected from 47 shallow monitor wells for chloride analysis. The regulatory limit for total chloride concentrations is defined by the NMWQCC Human Health Standard of 250 mg/L. The reported chloride analytical results are presented below:

	Chloride	
Number of Detections	47	
Exceedances Above Regulatory Limit	40	
Minimum Concentration (mg/L)	121	MW031
Maximum Concentration (mg/L)	2,590	MW010

An isopleth map, Chloride mg/L – Shallow Wells (March/April 2009), is presented as Figure 15.

Deep Monitor Wells

Groundwater samples were collected from 85 deep monitor wells for chloride analysis. The regulatory limit for total chloride concentrations is defined by the NMWQCC Human Health Standard of 250 mg/L. The reported chloride analytical results are presented below:

	Chloride	
Number of Detections	85	
Exceedances Above Regulatory Limit	72	
Minimum Concentration (mg/L)	44.9	MW014A
Maximum Concentration (mg/L)	6,370	MW021A

Water Wells

Groundwater samples were collected from four privately owned water wells for chloride analysis. The regulatory limit for total chloride concentrations is defined by the NMWQCC Human Health Standard of 250 mg/L. The reported chloride analytical results are presented below:

	<u>Chloride</u>	
Number of Detections	4	
Exceedances Above Regulatory Limit	4	
Minimum Concentration (mg/L)	255	EPWW1
Maximum Concentration (mg/L)	1,610	LORDWW

An isopleth map including deep monitor well and private water well locations, Chloride mg/L – Deep Wells (March/April 2009), is presented as **Figure 16**.

4.9.2 August 2009 Chloride Analysis

Shallow Monitor Wells

Groundwater samples were collected from 25 shallow monitor wells for chloride analysis. The regulatory limit for total chloride concentrations is defined by the NMWQCC Human Health Standard of 250 mg/L. The reported chloride analytical results are presented below:

	<u>Chloride</u>	
Number of Detections	25	
Exceedances Above Regulatory Limit	17	
Minimum Concentration (mg/L)	95.9	MW031
Maximum Concentration (mg/L)	3,470	MW069

An isopleth map, Chloride mg/L – Shallow Wells (August 2009), is presented as **Figure 17**.

Deep Monitor Wells

Groundwater samples were collected from 46 deep monitor wells for chloride analysis. The regulatory limit for total chloride concentrations is defined by the NMWQCC Human Health Standard of 250 mg/L. The reported chloride analytical results are presented below:

	<u>Chloride</u>	
Number of Detections	46	
Exceedances Above Regulatory Limit	33	
Minimum Concentration (mg/L)	45.6	MW014A
Maximum Concentration (mg/L)	6,020	MW021A

Water Wells

Groundwater samples were collected from three privately owned water wells for chloride analysis. The regulatory limit for total chloride concentrations is defined by the NMWQCC Human Health Standard of 250 mg/L. The reported chloride analytical results are presented below:

	<u>Chloride</u>	
Number of Detections	3	
Exceedances Above Regulatory Limit	3	
Minimum Concentration (mg/L)	615	WOODELLWW
Maximum Concentration (mg/L)	2,040	LORDWW

An isopleth map including deep monitor well and private water well locations, Chloride mg/L – Deep Wells (August 2009), is presented as **Figure 18**.

4.10 Benzene, Toluene, Ethylbenzene, and Xylene Analysis

During the March/April 2009 and August 2009 events, groundwater samples were analyzed for BTEX analytes. **Table 2** includes a summary of the 2009 cumulative BTEX analytical results and compares the results with the NMWQCC Human Health standards.

4.10.1 March/April 2009 Benzene, Toluene, Ethylbenzene, and Xylene Analysis

Shallow Monitor Wells

Groundwater samples were collected from 47 shallow monitor wells for BTEX analysis. The regulatory limit for benzene, toluene, ethylbenzene, and xylene are defined by the NMWQCC Human Health Standards of 0.01 mg/L, 0.75 mg/L, 0.75 mg/L and 0.62 mg/L, respectively. The reported BTEX analytical results are presented below:

	<u>Benzene</u>		<u>Toluene</u>		<u>Ethylbenzene</u>		<u>Xylene</u>	
Number of Detections	18		13		15		6	
Exceedances Above Regulatory Limit	8		--		--		--	
Minimum Concentration (mg/L)	0.002	MW0461	0.0012	MW015	0.001	MW060	0.0036	MW061
Maximum Concentration (mg/L)	0.51	MW006	0.19	MW033	0.28	MW033	0.42	MW036

An isopleth map, Benzene mg/L – Shallow Wells (March/April 2009), is presented as **Figure 19**.

Deep Monitor Wells

Groundwater samples were collected from 85 deep monitor wells for BTEX analysis. The regulatory limit for benzene, toluene, ethylbenzene, and xylene are defined by the NMWQCC Human Health Standards of 0.01 mg/L, 0.75 mg/L, 0.75 mg/L and 0.62 mg/L, respectively. The reported BTEX analytical results are presented below:

	<u>Benzene</u>		<u>Toluene</u>		<u>Ethylbenzene</u>		<u>Xylene</u>	
Number of Detections	24		21		24		3	
Exceedances Above Regulatory Limit	10		--		--		--	
Minimum Concentration (mg/L)	0.002	MW0461	0.0013	MW015	0.001	MW060	0.0031	MW061
Maximum Concentration (mg/L)	0.29	MW006	0.01	MW033	0.23	MW033	0.034	MW036

Water Wells

Groundwater samples were collected from four privately owned water wells for BTEX analysis. The regulatory limit for benzene, toluene, ethylbenzene, and xylene are defined by the NMWQCC Human Health Standards of 0.01 mg/L, 0.75 mg/L, 0.75 mg/L and 0.62 mg/L, respectively. The reported BTEX analytical results are presented below:

	<u>Benzene</u>		<u>Toluene</u>		<u>Ethylbenzene</u>		<u>Xylene</u>
Number of Detections	1		1		1		--
Exceedances Above Regulatory Limit	1		--		--		--
Maximum Concentration (mg/L)	0.018	LORDWW	0.0045	LORDWW	0.0014	LORDWW	

An isopleth map including deep monitor well and private water well locations, Benzene mg/L – Deep Wells (March/April 2009), is presented as **Figure 20**.

4.10.2 August 2009 Benzene, Toluene, Ethylbenzene, and Xylene Analysis

Shallow Monitor Wells

Groundwater samples were collected from 25 shallow monitor wells for BTEX analysis. The regulatory limit for benzene, toluene, ethylbenzene, and xylene are defined by the NMWQCC Human Health Standards of 0.01 mg/L, 0.75 mg/L, 0.75 mg/L and 0.62 mg/L, respectively. The reported BTEX analytical results are presented below:

	<u>Benzene</u>		<u>Toluene</u>		<u>Ethylbenzene</u>		<u>Xylene</u>	
Number of Detections	3		2		2		2	
Exceedances Above Regulatory Limit	1		--		--		--	
Minimum Concentration (mg/L)	0.0011	MW014	0.01	MW069	0.022	MW069	0.0064	MW069
Maximum Concentration (mg/L)	0.18	MW033	0.15	MW033	0.26	MW033	0.085	MW033

An isopleth map, Benzene mg/L – Shallow Wells (August 2009), is presented as **Figure 21**.

Deep Monitor Wells

Groundwater samples were collected from 46 deep monitor wells for BTEX analysis. The regulatory limit for benzene, toluene, ethylbenzene, and xylene are defined by the NMWQCC Human Health Standards of 0.01 mg/L, 0.75 mg/L, 0.75 mg/L and 0.62 mg/L, respectively. The reported BTEX analytical results are presented below:

	<u>Benzene</u>		<u>Toluene</u>		<u>Ethylbenzene</u>		<u>Xylene</u>	
Number of Detections	1		1		1		1	
Exceedances Above Regulatory Limit	--		--		--		--	
Maximum Concentration (mg/L)	0.002	MW024A	0.0013	MW024A	0.001	IW025	0.0058	IW025

Water Wells

Groundwater samples were collected from three privately owned water wells for BTEX analysis. No groundwater BTEX concentrations were detected in analytical results.

An isopleth map including deep monitor well and private water well locations, Benzene mg/L – Deep Wells (August 2009), is presented as **Figure 22**.

4.11 TPH-DRO and TPH-GRO Analysis

During the March/April 2009 and August 2009 events, groundwater samples were analyzed for TPH-DRO and TPH-GRO analysis. The NMWQCC does not currently stipulate a regulatory standard for the presence of TPH-DRO and TPH-GRO in groundwater. Table 2 includes a summary of the 2009 cumulative TPH-DRO and TPH-GRO analytical results.

4.11.1 March/April 2009 TPH-DRO and TPH-GRO Analysis

Shallow Monitor Wells

Groundwater samples were collected from 47 shallow monitor wells for TPH-GRO and TPH-DRO analysis. The reported TPH-DRO and TPH-GRO analytical results are presented below:

	<u>TPH-DRO</u>		<u>TPH-GRO</u>	
Number of Detections	31		12	
Exceedances Above Regulatory Limit	--		--	
Minimum Concentration (mg/L)	0.096	MW068	0.062	MW070
Maximum Concentration (mg/L)	1,500	MW088M	4.9	MW088M

A shallow well concentration map, TPH-DRO and TPH-GRO mg/L – Shallow Wells (March/April 2009), is presented as Figure 23.

Deep Monitor Wells

Groundwater samples were collected from 85 deep monitor wells for TPH-DRO and TPH-GRO analysis. The reported TPH-DRO and TPH-GRO analytical results are presented below:

	<u>TPH-DRO</u>		<u>TPH-GRO</u>	
Number of Detections	36		9	
Exceedances Above Regulatory Limit	NA**		NA	
Minimum Concentration (mg/L)	0.097	MW077SA	0.1	MW070A
Maximum Concentration (mg/L)	710	RW004A	19	RW004A

Water Wells

Groundwater samples were collected from four privately owned water wells for TPH-DRO and TPH-GRO analysis. The reported TPH-DRO and TPH-GRO analytical results are presented below:

	<u>TPH-DRO</u>		<u>TPH-GRO</u>	
Number of Detections	1		1	
Exceedances Above Regulatory Limit	NA		NA	
Maximum Concentration (mg/L)	0.52	EPWW1	0.08	LORDWW

A concentration map including deep monitor well and private water well locations, TPH-DRO and TPH-GRO mg/L – Deep Wells (March/April 2009), is presented as Figure 24.

** NA indicates there is no regulatory limit for the respective constituent.

4.11.2 August 2009 TPH-DRO and TPH-GRO Analysis

Shallow Monitor Wells

Groundwater samples were collected from 25 shallow monitor wells for TPH-GRO and TPH-DRO analysis. The reported TPH-DRO and TPH-GRO analytical results are presented below:

	<u>TPH-DRO</u>		<u>TPH-GRO</u>	
Number of Detections	18		4	
Exceedances Above Regulatory Limit	--		--	
Minimum Concentration (mg/L)	0.1	MW013	0.12	MW069
Maximum Concentration (mg/L)	0.89	MW033	2	MW033

A shallow well concentration map, TPH-DRO and TPH-GRO mg/L-Shallow Wells (August 2009), is presented as **Figure 25**.

Deep Monitor Wells

Groundwater samples were collected from 46 deep monitor wells for TPH-DRO and TPH-GRO analysis. The reported TPH-DRO and TPH-GRO analytical results are presented below:

	<u>TPH-DRO</u>		<u>TPH-GRO</u>	
Number of Detections	14		3	
Exceedances Above Regulatory Limit	--		--	
Minimum Concentration (mg/L)	0.11	MW054SA	0.051	MW063A
Maximum Concentration (mg/L)	0.81	MW021A	0.11	MW062A

Water Wells

Groundwater samples were collected from three privately owned water wells for TPH-DRO and TPH-GRO analysis. No groundwater TPH-DRO and TPH-GRO concentrations were detected in analytical results.

A concentration map including deep monitor well and private water well locations, TPH-DRO and TPH-GRO mg/L – Deep Wells (August 2009), is presented as **Figure 26**.

4. 12 Inorganic Metals Analysis

During the March/April 2009 and August 2009 events, groundwater samples were analyzed for inorganic metal analytes. It should be noted that the elevated concentrations of inorganic metals recorded during the 2009 sampling events are likely related to the dissolution of metals in the natural substrata and are not indicative of any historically documented plant activities. **Table 3** summarizes the 2009 inorganic metals analytical results.

4.12.1 March/April 2009 Inorganic Metals Analysis

Shallow Monitor Wells

Groundwater samples were collected from 47 shallow monitor wells for inorganic metals analysis. The regulatory limit for arsenic, iron, and manganese are defined by the NMWQCC Human Health Standards of 0.1 mg/L, 1.0 mg/L, and 0.2 mg/L, respectively. The reported inorganic metals analytical results are presented below:

	<u>Arsenic</u>		<u>Iron</u>		<u>Manganese</u>	
Number of Detections	14		19		32	
Exceedances Above Regulatory Limit	3		16		22	
Minimum Concentration (mg/L)	0.0211	MW028	0.389	MW033	0.0058	MW069
Maximum Concentration (mg/L)	0.137	MW012M	1030	MW088M	52.7	MW033

Deep Monitor Wells

Groundwater samples were collected from 85 deep monitor wells for inorganic metals analysis. The regulatory limit for arsenic, iron, and manganese are defined by the NMWQCC Human Health Standards of 0.1 mg/L, 1.0 mg/L, and 0.2 mg/L, respectively. The reported inorganic metals analytical results are presented below:

	<u>Arsenic</u>		<u>Iron</u>		<u>Manganese</u>	
Number of Detections	18		20		45	
Exceedances Above Regulatory Limit	5		17		23	
Minimum Concentration (mg/L)	0.02	MW012A	0.2	MW012A	0.005	MW012A
Maximum Concentration (mg/L)	0.299	IW007	986	MW004A	25.9	IW009

Water Wells

Groundwater samples were collected from four privately owned water wells for inorganic metals analysis. The regulatory limit for arsenic, iron, and manganese are defined by the NMWQCC Human Health Standards of 0.1 mg/L, 1.0 mg/L, and 0.2 mg/L, respectively. The reported inorganic metals analytical results are presented below:

	<u>Iron</u>		<u>Manganese</u>	
Number of Detections	2		3	
Exceedances Above Regulatory Limit	2		2	
Minimum Concentration (mg/L)	2.18	GOPWW2	0.138	LORDWW
Maximum Concentration (mg/L)	4.2	LORDWW	0.513	GOPWW2

* Arsenic concentrations were not detected in water well analytical results.

4.12.2 August 2009 Inorganic Metals Analysis

Shallow Monitor Wells

Groundwater samples were collected from 25 shallow monitor wells for inorganic metals analysis. The regulatory limit for arsenic, iron, and manganese are defined by the NMWQCC Human Health Standards of 0.1 mg/L, 1.0 mg/L, and 0.2 mg/L, respectively. The reported inorganic metals analytical results are presented below:

	<u>Arsenic</u>		<u>Manganese</u>	
Number of Detections	6		10	
Exceedances Above Regulatory Limit	--		6	
Minimum Concentration (mg/L)	0.0218	MW023	0.0059	MW032
Maximum Concentration (mg/L)	0.0283	MW014	1.11	MW060

* Iron concentrations were not detected in shallow monitor well analytical results.

Deep Monitor Wells

Groundwater samples were collected from 46 deep monitor wells for inorganic metals analysis. The regulatory limit for arsenic, iron, and manganese are defined by the NMWQCC Human Health Standards of 0.1 mg/L, 1.0 mg/L, and 0.2 mg/L, respectively. The reported inorganic metals analytical results are presented below:

	<u>Arsenic</u>		<u>Iron</u>		<u>Manganese</u>	
Number of Detections	7		2		9	
Exceedances Above Regulatory Limit	--		--		6	
Minimum Concentration (mg/L)	0.0209	MW018A	0.52	MW083SA	0.0114	MW012A
Maximum Concentration (mg/L)	0.0304	MW040A	0.565	MW082SA	3.15	MW060

Water Wells

Groundwater samples were collected from three privately owned water wells for inorganic metals analysis. The regulatory limit for arsenic, iron, and manganese are defined by the NMWQCC Human Health Standards of 0.1 mg/L, 1.0 mg/L, and 0.2 mg/L, respectively. The reported inorganic metals analytical results are presented below:

	<u>Iron</u>		<u>Manganese</u>	
Number of Detections	1		2	
Exceedances Above Regulatory Limit	1		1	
Minimum Concentration (mg/L)	1.34	LORDWW	0.0139	LORDWW
Maximum Concentration (mg/L)			0.577	GOPWW2

4. 13 Total Dissolved Solids Analysis

During the March/April 2009 and August 2009 events, groundwater samples were analyzed for TDS. Table 4 includes a summary of the 2009 groundwater parameter results, including TDS analytical results.

4.13.2 August 2009 Total Dissolved Solids Analysis

Shallow Monitor Wells

Groundwater samples were collected from 25 shallow monitor wells for TDS analysis. The regulatory limit for TDS is defined by the NMWQCC Human Health Standards of 1,000 mg/L. The reported TDS analytical results are presented below:

	Total Dissolved Solids	
Number of Detections	18	
Exceedances Above Regulatory Limit	12	
Minimum Concentration (mg/L)	647	MW014
Maximum Concentration (mg/L)	6,690	MW69

Deep Monitor Wells

Groundwater samples were collected from 46 deep monitor wells for TDS analysis. The regulatory limit for TDS is defined by the NMWQCC Human Health Standards of 1,000 mg/L. The reported TDS analytical results are presented below:

	Total Dissolved Solids	
Number of Detections	35	
Exceedances Above Regulatory Limit	6	
Minimum Concentration (mg/L)	452	MW024A
Maximum Concentration (mg/L)	13,300	MW021A

Water Wells

Groundwater samples were collected from four deep monitor wells for TDS analysis. The regulatory limit for TDS is defined by the NMWQCC Human Health Standards of 1,000 mg/L. The reported TDS analytical results are presented below:

	Total Dissolved Solids	
Number of Detections	2	
Exceedances Above Regulatory Limit	2	
Minimum Concentration (mg/L)	1,480	WOODELLWW
Maximum Concentration (mg/L)	3,060	GOPWW2

4.14 Additional Analysis

During the March/April 2009 and August 2009 events, groundwater samples from monitor wells MW090SA, IW023, IW024, IW025, and IW026 were analyzed for sodium, pH, alkalinity, TOC, and sulfide. The regulatory limit for pH is defined by the NMWQCC Human Health Standard of 6-9 (measured as the negative logarithm (base 10) of the molar concentration of dissolved hydrogen units (H^+)). The regulatory limit for sulfate is defined by the NMWQCC Human Health Standard of 600 mg/L. The NMWQCC does not currently stipulate a regulatory standard for the presence of alkalinity, TOC, and sulfide in groundwater. Due to the alkaline nature of the local soils, alkalinity was analyzed to a pH of 4.5. Alkalinity is measured in milliequivalents per liter

(mEq/L). **Table 3** includes a summary of the 2009 groundwater parameter results, including sodium analytical results. **Table 4** includes a summary of the 2009 groundwater parameter results, including pH, alkalinity to pH 8.3, alkalinity to pH 4.5, TOC, and sulfide.

4.14.1 March/April 2009 Additional Analysis

Groundwater samples were collected from 5 shallow monitor wells for sodium, pH alkalinity, TOC, and sulfide analysis. The reported sodium, pH alkalinity, TOC, and sulfide analytical results are presented below:

	<u>Sodium</u>	
Number of Detections	5	
Exceedances Above Regulatory Limit	--	
Minimum Concentration (mg/L)	279	IW026
Maximum Concentration (mg/L)	661	IW025

	<u>pH</u>	
Number of Detections	5	
Exceedances Above Regulatory Limit	4	
Minimum pH Unit	6.6	IW025
Maximum pH Unit	7.3	IW026

	<u>Alkalinity to pH of 4.5</u>	
Number of Detections	5	
Exceedances Above Regulatory Limit	--	
Minimum Alkalinity (mEq/L)	212	IW024
Maximum Alkalinity (mEq/L)	998	IW025

	<u>Total Organic Carbon</u>		<u>Sulfide</u>	
Number of Detections	3		1	
Exceedances Above Regulatory Limit	--		--	
Minimum Concentration (mg/L)	30	MW014A	49.8	IW025
Maximum Concentration (mg/L)	14,900	RW004A		

4.14.2 August 2009 Total Dissolved Solids Analysis

Groundwater samples were collected from 5 shallow monitor wells for sodium, pH, alkalinity, TOC, and sulfide analysis. The reported sodium, pH, alkalinity, TOC, and sulfide analytical results are presented below:

	<u>Sodium</u>	
Number of Detections	5	
Exceedances Above Regulatory Limit	--	
Minimum Concentration (mg/L)	246	IW026
Maximum Concentration (mg/L)	601	IW024

	<u>pH</u>	
Number of Detections	5	
Exceedances Above Regulatory Limit	4	
Minimum Concentration (mg/L)	6.6	IW025
Maximum Concentration (mg/L)	7.2	IW026

	<u>Alkalinity to 4.5</u>	
Number of Detections	5	
Exceedances Above Regulatory Limit	--	
Minimum Concentration (mg/L)	210	IW024
Maximum Concentration (mg/L)	799	IW025

	<u>Total Organic Carbon</u>		<u>Sulfide</u>		<u>Sulfate</u>	
Number of Detections	4		1		5	
Exceedances Above Regulatory Limit	--		--		4	
Minimum Concentration (mg/L)	4.4	IW023	254	IW025	390	IW026
Maximum Concentration (mg/L)	60.8	IW025			1,670	IW024

5.0 OPERATION AND MAINTENANCE ACTIVITIES

Observed hydrocarbons have impacted soil and groundwater at the Site within a limited area inside the plant boundary; however, the source of the hydrocarbon impact is believed to have been removed. Stantec performed monthly O&M at the Plant involving the gauging of monitor wells MW005 and MW006 using an oil-water interface probe to determine the PSH thickness; which was recorded on the O&M Field Report. Since October 2005, PSH thickness has not been observed in MW005. PSH was not observed in MW005 and MW006 during the 2009 monthly O&M visits.

Stantec proposed in a letter to the NMOCD dated March 20, 2009 to utilize a mutually agreed upon form of passive PSH collection in the wells that would achieve similar results. Copies of the 2009 Operations and Maintenance Field Report are attached as **Appendix C**.

6.0 QUALITY ASSURANCE/QUALITY CONTROL PROGRAM

Quality assurance/quality control (QA/QC) objectives for groundwater monitoring data include:

- Collecting data in accordance with procedures as appropriate for its intended use;
- Maintaining sufficient quality data to meet scientific and legal scrutiny;
- Generating representative data of known and acceptable precision and accuracy; and
- Evaluating data that is consistent in content and quality.

Results for the QA/QC samples along with laboratory QA/QC results are included in the laboratory analytical reports located in **Appendix B**.

6.1 Field Duplicate Samples

A field duplicate sample is a second sample collected at the same location as the original sample. Duplicate samples are collected simultaneously, or in immediate succession, using identical recovery techniques, and treated in an identical manner during storage, transportation, and analysis. One duplicate sample is collected for every ten groundwater samples collected to assure accuracy of testing methods by the laboratory. Twelve (12) duplicate samples were collected during the March/April 2009 sampling event and seven (7) duplicate samples were collected during the August 2009 sampling event. The following table presents benzene analytical results for wells sampled during the 2009 semi-annual events compared to their respective duplicate sample results.

Date	Original Sample ID	Original Sample Analytical Results (ug/L)	Duplicate Sample ID	Duplicate Sample Analytical Result (ug/L)
03/17/09	MW040A	6.8	DUP#100	6.8
03/18/09	MW083SA	<1.0	DUP#200	<1.0
03/19/09	MW015A	9.8	DUP#101	9.3
03/23/09	IW015	7.6	DUP#201	5.6
03/25/09	IW019	<1.0	DUP#202	<1.0
03/25/09	MW024	<1.0	DUP#102	<1.0
03/26/09	MW055SA	<1.0	DUP#103	<1.0
03/30/09	MW013A	<1.0	DUP#104	<1.0
03/31/09	MW011A	<1.0	DUP#203	<1.0
03/31/09	MW002A	<1.0	DUP#105	<1.0
04/02/09	MW051SA	<1.0	DUP#106	<1.0
04/07/09	IW028	<1.0	DUP#204	<1.0
08/10/09	MW086SA	<1.0	DUP#100	<1.0
08/19/09	MW061	<1.0	DUP#101	<1.0
08/20/09	MW023A	<1.0	DUP#200	<1.0
08/20/09	MW025	<1.0	DUP#102	<1.0
08/24/09	MW075SA	<1.0	DUP#201	<1.0
08/24/09	MW033	180	DUP#103	170
08/25/09	MW022A	<1.0	DUP#104	<1.0

The following table presents chloride analytical results for wells sampled during the 2009 semi-annual events compared to their respective duplicate sample results.

Date	Original Sample ID	Original Sample Analytical Results (ug/L)	Duplicate Sample ID	Duplicate Sample Analytical Result (ug/L)
03/17/09	MW040A	54.1	DUP#100	52.1
03/18/09	MW083SA	1470	DUP#200	1540
03/19/09	MW015A	2010	DUP#101	1900
03/23/09	IW015	984	DUP#201	988
03/25/09	IW019	1730	DUP#202	1040
03/25/09	MW024	985	DUP#102	563
03/26/09	MW055SA	719	DUP#103	694
03/30/09	MW013A	68	DUP#104	66.8
03/31/09	MW011A	1420	DUP#203	1600
03/31/09	MW002A	1160	DUP#105	1270
04/02/09	MW051SA	1240	DUP#106	1260
04/07/09	IW028	583	DUP#204	569
08/10/09	MW086SA	1330	DUP#100	1500
08/19/09	MW061	716	DUP#101	836
08/20/09	MW023A	50.6	DUP#200	49.1
08/20/09	MW025	432	DUP#102	439
08/24/09	MW075SA	586	DUP#201	1250
08/24/09	MW033	915	DUP#103	909
08/25/09	MW022A	68.7	DUP#104	67.1

The duplicate samples represent acceptable laboratory precision in all but three of the duplicate sample results. The IW19, MW024, and MW075SA sample concentration results varied significantly from the respective duplicate sample concentration results. Stantec will continue to closely monitor these three well locations during 2010 sampling activities.

6.2 Trip Blank Samples

As volatiles were part of the analytical program, trip blanks were submitted to the laboratory at a rate of one trip blank per cooler. Trip blanks were analyzed for BTEX to detect potential cross-contamination of volatile organic constituents between aqueous samples during sample handling and shipment.

No constituents were detected in the March/April 2009 or August 2009 trip blanks.

6.3 Decontamination Procedures

To decontaminate sampling equipment, an Alconox-water solution was pumped from buckets through the pump and associated equipment. All equipment was then rinsed thoroughly with distilled water pumped from clean buckets. The Alconox-water solution and distilled water were changed periodically. One-time use disposable equipment was not decontaminated, but packaged for appropriate disposal.

7.0 CONCLUSIONS AND RECOMMENDATIONS

The following conclusions and recommendations are based upon reviews of historical data, evaluation of operations, past remedial techniques, and data collected during 2009.

7.1 Conclusions

The potentiometric surface of the Site is believed to be atypical for this general region, but is consistent with activities south of the Plant and well pumping at the Plant. The potentiometric surface returns to the natural gradient to the east of the Plant.

7.1.1 Total Chromium and Hexavalent Chromium

The chromium plume is fully defined in all but the northeastern most direction in the deep zone. The shallow zones are fully defined to the south and west. The shallow and deep zone plumes are illustrated on **Figure 7** through **Figure 14**.

Shallow Zone

- The shallow zone has shown relatively stable chromium concentrations;
- The areas of elevated total chromium concentrations were generally located near the southwest corner of the plant in the vicinity of MW011, MW013, and MW023, and on the east side of the plant in the vicinity of MW004; and
- Hexavalent chromium concentrations were generally located in the same areas south and west of the plant. Elevated concentrations were also observed on the east side of the plant in the vicinity of MW004.

Deep Zone

- Total chromium concentrations have generally decreased in the distal array injection wells since discontinuing IRZ, primarily due to increasing pH values;
- The results indicate the leading edge of the total chromium plume has not reached the furthest water well to the east (GOPWW2); however, the well located 600 feet west of GOPWW2 (MW086SA) continues to trend elevated concentrations;
- The areas of elevated total chromium concentrations were generally located in the southwest portion of the plant centered on MW011A, and east of the plant centered on the medial array;
- Hexavalent chromium concentrations were generally located in the southwest portion of the plant, centered on MW011A, and east of the plant centered on the medial array. Additionally, results indicate the leading edge of the hexavalent chromium plume has not reached the furthest monitoring well to the east (GOPWW2); however, elevated hexavalent chromium concentrations were located directly east of the medial array.

Water Wells

- There is an overall increase in total chromium on the southern side of the plume and a decrease on the northern side. However, an exception to the trend is the elevated hexavalent chromium concentration at the northern most water well location, WoodellWW, during August 2009; and
- All other water well locations remain below the regulatory limits for total and hexavalent chromium.

Concentrations at the distal end of the plume generally remained consistent with 2008 analytical results. Sentry wells with low or non-detectable concentrations of chromium are at the northern and eastern most extent of the plume.

7.1.2 Chloride and TDS

Chloride concentrations are elevated across the entire Site and indicate regional impact, as the plume is not fully defined in the shallow zone wells to the west and south of the Site, and to the north and northeast in the deep zone wells. The shallow and deep zone plumes are illustrated on **Figure 15** through **Figure 18**.

Shallow Zone

- Elevated chloride concentrations were generally located to the south and southwest of the plant.
- Elevated chloride concentrations were noted in the following wells: MW010, MW015, MW006, MW037, MW005, MW014, MW008M, MW011, MW002, MW060, and MW068.

Deep Zone

- Elevated chloride concentrations were generally located east, centered on the distal array, and on the northeast side of the plant, centered on MW021A and MW042A. Additionally, elevated chloride concentrations were located east of the medial array, centered on MW084SA.

Water Wells

- Elevated chloride concentrations were observed at three water well locations (WOODELLWW, GOPWW2, and LORDWW) during both the April/March and August 2009 sampling events;
- Elevated chloride concentrations at the three water well locations were generally located along the fringe of the deep zone chloride plume: WOODELLWW is located along the northern edge of the chloride plume, GOPWW2 is located at the east edge of the chloride plume, and LORDWW is located towards the southern edge of the chloride plume.

Both the shallow and deep chloride concentrations suggest multiple sources located southwest, south, and northeast of the plant. There have been no documented releases of chlorides associated with the Plant. However, there are numerous regional oilfield-related operations that may have contributed to the chloride concentrations in groundwater. During December 2009, Stantec conducted a chlorides investigation at select locations in and around the Plant; 25 soil borings were advanced from six areas of concern (AOCs) to maximum depths of 60 feet bgs (or until groundwater was encountered). Soil samples were collected from each soil boring and results will be presented in a separate letter report.

7.1.3 Benzene, Toluene, Ethylbenzene, and Xylene

The shallow benzene plume is fully defined in all directions except north of the plant. The plume is primarily contained on the plant property except for isolated exceedances south of the plant (MW033), west of the plant (MW033) and east of the plant (MW006). The deep benzene plume is fully defined to the south of the Plant. However, elevated deep plume concentrations of benzene were located at isolated locations to the west (MW070A and MW023A), northeast (MW074A), east (IW009 and MW072SA), and on the south side of the plant (RW004A).

During the April/March 2009 sampling event, an elevated benzene concentration was detected in water well location LORDWW. An elevated benzene concentration has not been historically documented in prior sampling events at the LORDWW water well location. Stantec will continue to monitor the location for additional exceedances in 2010.

The shallow and deep zone plumes for the March/April 2009 and August 2009 are illustrated on Figure 19 through Figure 22.

Toluene, ethylbenzene, and xylene concentrations were below WQCC standards; and are not considered primary COCs at the Site.

7.1.4 TPH-DRO and TPH-GRO

TPH-DRO and TPH-GRO concentrations were primarily contained on the plant property near the southwest portion of the plant, the area south-southwest of the plant, and at the distal array (with an isolated detection north of the plant at MW021) as indicated by the results from the March/April 2009 event. The elevated values are likely due to matrix interferences caused by molasses remaining from the previous injections. TPH concentrations are illustrated on Figure 23 through Figure 26.

7.1.5 Inorganic Metals

During the 2008 semi-annual groundwater sampling events, four additional metals (calcium, potassium, magnesium, and sodium) were sampled at five monitor well locations (MW090SA, IW023, IW024, IW025, and IW026) to obtain baseline concentrations prior to initiating in-situ (calcium polysulfide and sodium acetate) chromium treatment. During the 2009 sampling events, one additional metal (sodium) was collected from the five monitor well locations affected by the 2008 in-situ chromium treatment. The other three metals (arsenic, iron, manganese) are consistently part of the semi-annual groundwater monitoring schedule for all well locations sampled. Arsenic, iron, and manganese are monitored to evaluate the liberation of naturally occurring metals from the formation due to reducing conditions present. The three metals generally occur within areas of the Site previously amended with molasses for in-situ chromium treatment (study area, distal array). During the 2009 semiannual sampling events, analytical results from groundwater samples collected at several monitor well locations reported arsenic, iron, and manganese concentrations above their respective NMWQCC regulatory standards. However, as the reducing conditions dissipate, the metals will oxidize back to their insoluble state.

7.1.6 Sulfate

The 2009 sulfate data was collected from the five monitor well locations affected by the 2008 in-situ chromium treatment (MW090SA, IW023, IW024, IW025, and IW026). Sodium sulfate represents a carbon source (electron donor) for native bacteria to degrade using readily available electron acceptors (oxygen, nitrate, and sulfate). The reducing conditions convert hexavalent chromium to insoluble trivalent chromium. During August 2009, analytical results from groundwater samples collected at four monitor well locations (IW023, IW024, IW026, and MW090SA) reported sulfate concentrations above the NMWQCC standard of 600 mg/L. Sulfate will continued to be monitored, as needed, to evaluate consumption of alternate electron acceptors.

7.2 Recommendations

7.2.1 Additional Evaluation

The following activities are recommended to further delineate and provide additional information on the Site groundwater conditions:

- Additional research and investigation in the area surrounding monitoring well MW061 to delineate the source and extent of the chromium impacts;
- Conduct Site wide in-situ chromium treatment (sodium sulfate); and
- Further evaluate source locations for chloride concentrations.

7.2.2 Sampling Schedule

Semi-annual sampling events are still recommended at this time; however, it is proposed the first event continue to encompass the sampling of all accessible (138) wells at the Site, while the second sampling event in 2010 is contingent on information received on the first sampling event.

For both events, the proposed analytical program is:

- Benzene, ethylbenzene, toluene, and xylene by EPA Method 8021B;
- TPH-DRO and TPH-GRO (at all specified wells except injection wells) by EPA Method 8015B;
- RCRA metals (arsenic, chromium, iron, and manganese) by EPA Method 6010B;
- Hexavalent chromium by EPA Method 7196A;
- Chloride by EPA Method 300.0; and
- TDS by EPA Method 160.1.

Five pilot study well locations (IW-023, IW-024, IW-025, IW-026, and MW-090SA) will be analyzed for five parameters in addition to the above mentioned constituents analyzed from all groundwater samples. The additional parameters for the five pilot study well locations are listed below:

- pH by SM20 4500-H+B;
- Alkalinity by SM20 2320B;
- TOC by SM20 5310 B/C;
- Sulfide by SM20 4500 S2 D;
- Sulfate by EPA Method 300.0; and

- Sodium by EPA Method 6010B.

7.2.3 Phase-Separated Hydrocarbon Remediation

Based on the O&M observations, it has been proposed to NMOCD (in a letter dated March 20, 2009) to discontinue the weekly monitoring and PSH removal at MW005 and MW006 and instead install some form of passive PSH collection (i.e., absorbent sock or other proven technology) in MW006 that will achieve similar results.

8.0 STATEMENT OF LIMITATIONS

The conclusions and recommendations contained in this report are based upon professional opinions with regard to the subject matter. These opinions have been arrived at in accordance with currently accepted hydrogeologic and engineering standards and practices applicable to the Site. Stantec derived the data in this report primarily from visual inspections, examination of data collected from consulting professionals previously conducting site activities, examination of records in the public domain, and interviews with individuals having information about the Site.

This report is based, in part, on information supplied to Stantec by a third-party source. Efforts have been made to substantiate the third-party information; however, Stantec cannot guarantee the information completeness or accuracy. All data collected prior to October 2005 was provided by ARCADIS G&M, Inc. Descriptions and protocol presented in this report are intended to summarize activities conducted by Stantec following September 2005.

9.0 REFERENCES

ARCADIS, 2005, *Groundwater Investigation and Remediation Activities Report 2004*, dated March 2005.

Highlander, 1996, *Subsurface Environmental Assessment Report*, dated September 1996.

Borton, R. L. (1978). *Bibliography of Ground-Water Studies in New Mexico 1873-1977*. New Mexico State Engineer, Santa Fe, New Mexico. Rose Printing Company, Inc., Tallahassee, Florida.

Gustavson, T. C., et al, (1995), *Origin and Development of Playa Basins, Sources of Recharge to the Ogallala Aquifer, Southern High Plains, Texas and New Mexico*, Bureau of Economic Geology, University of Texas, Austin, Report of Investigations No.22.

Nativ, R. (1988). *Hydrogeology and Hydrochemistry of the Ogallala Aquifer, Southern High Plains, Texas Panhandle and Easter New Mexico*. (Report of Investigations No. 177). Bureau of Economic Geology. The University of Texas at Austin, Austin, Texas.

Nicholson Jr., A. Clebsch Jr., A. (1961). *Geology and Ground-Water Conditions in Southern Lea County, New Mexico*. (Groundwater Report 6). Socorro, State Bureau of Mines and Mineral Resources, New Mexico Institute of Mining and Technology.

SECOR 2006, Annual Summary of Investigation and Remediation, dated January 2007.

SECOR 2007, In-Situ Pilot Study Work Plan, dated May 14, 2007.

SECOR 2007, Pre-Pilot Study, dated October 29, 2007


SECOR 2007, Annual Summary of Investigation and Remediation, dated July 2008.

Stantec 2008, Pilot Study Report, dated February 9, 2009.

Stantec 2008, Annual Summary of Investigation and Remediation, dated August 2009.

Walker, J. R. (1978). *Baylor Geological Studies, Geomorphic Evolution of the Southern High Plains*. (Bulletin No. 35). Baylor University Department of Geology, Waco, Texas.

FIGURE 1
Site Location Map



REFERENCE: USGS 7.5 MINUTE QUADRANGLE; EUNICE AND RATTLESNAKE CANYON, NEW MEXICO

No warranty is made by Stantec as to the accuracy, reliability, or completeness of these data. Original data were compiled from various sources. This information may not meet National Map Accuracy Standards. This product was developed electronically, and may be updated without notification. Any reproduction may result in a loss of scale and/or information.



10235 West Little York
Houston, Texas 77040

PHONE: (713) 937-7973 FAX: (713) 983-8328

FOR:

CHEVRON
EUNICE NORTH GAS PLANT
EUNICE, NEW MEXICO

SITE LOCATION MAP

FIGURE:

1

JOB NUMBER:

212201135

DRAWN BY:

ARA

CHECKED BY:

DNW

APPROVED BY:

CV


DATE:

1/5/10

**FIGURE 2
Site Details Map**

FIGURE 2A
Geologic Cross Section

FIGURE 3
Potentiometric Surface Map – Shallow Wells
(March/April 2009)





Stantec
10235 WEST LITTLE YORK
HOUSTON, TEXAS
PHONE: (713) 937-7973 FAX: (713) 983-8328

FOR: **CHEVRON**
EUNICE NORTH GAS PLANT

JOB NUMBER: 212201135
DRAWN BY: ARA/JBL
CHECKED BY: DNNW
APPROVED BY: CV


FIGURE: **3**

DATE: 1/5/10

POTENTIOMETRIC SURFACE MAP
SHALLOW WELLS
MARCH/APRIL 2009

FIGURE 4
Potentiometric Surface Map – Deep Wells
(March/April 2009)

FIGURE 5
Potentiometric Surface Map – Shallow Wells
(August 2009)





10235 WEST LITTLE YORK
HOUSTON, TEXAS
PHONE: (713) 937-7973 FAX: (713) 968-8328

FOR: **CHEVRON**
EUNICE NORTH GAS PLANT
EUNICE, NEW MEXICO

JOB NUMBER: 212201135
DRAWN BY: ARA/JBL
CHECKED BY: DNW
APPROVED BY: SO

FIGURE: **5**
**POTENTIOMETRIC SURFACE MAP
SHALLOW WELLS
JULY/AUGUST 2009**

DATE: 1/5/10

FIGURE 6
Potentiometric Surface Map – Deep Wells
(August 2009)

FIGURE 7
Total Chromium mg/L – Shallow Wells (March/April 2009)

FIGURE 8
Hexavalent Chromium mg/L – Shallow Wells
(March/April 2009)

FIGURE 9
Total Chromium mg/L – Deep Wells (March/April 2009)

FIGURE 10
Hexavalent Chromium mg/L – Deep Wells (March/April 2009)

FIGURE 11
Total Chromium mg/L – Shallow Wells (August 2009)



FOR:		CHEVRON	TOTAL CHROMIUM mg/L SHALLOW WELLS JULY/AUGUST 2009		FIGURE:
EUNICE NORTH GAS PLANT					11
EUNICE, NEW MEXICO					
JOB NUMBER:	DRAWN BY:	CHECKED BY:	APPROVED BY:	DATE:	
212201135	ARA/JBL	DNW	SO	1/5/10	

Stantec
10235 WEST LITTLE YORK
HOUSTON, TEXAS
PHONE: (713) 937-7973 FAX: (713) 963-6328

FIGURE 12
Hexavalent Chromium mg/L – Shallow Wells (August 2009)

FIGURE 13
Total Chromium mg/L – Deep Wells (August 2009)

FIGURE 14
Hexavalent Chromium mg/L – Deep Wells (August 2009)





10235 WEST LITTLE YORK
HOUSTON, TEXAS
PHONE: (713) 937-7973 FAX: (713) 963-8328

FOR:

CHEVRON

EUNICE NORTH GAS PLANT

EUNICE, NEW MEXICO

JOB NUMBER: 212201135

DRAWN BY: ARA/JBL

HEXAVALENT CHROMIUM mg/L
DEEP WELLS
JULY/AUGUST 2009

FIGURE: 14

CHECKED BY: DNW

APPROVED BY: SO

DATE: 1/5/10

FIGURE 15
Chloride mg/L – Shallow Wells (March/April 2009)



Stantec
10235 WEST LITTLE YORK
HOUSTON, TEXAS
PHONE: (713) 937-7873 FAX: (713) 983-8328

FOR:

CHEVRON
EUNICE NORTH GAS PLANT
EUNICE, NEW MEXICO

JOB NUMBER: 212201135
DRAWN BY: ARA/JBL

FIGURE: **15**

CHLORIDE mg/L
SHALLOW WELLS
MARCH/APRIL 2009

CHECKED BY: DNW
APPROVED BY: CV
DATE: 1/5/10

FIGURE 16
Chloride mg/L – Deep Wells (March/April 2009)



FOR: CHEVRON EUNICE NORTH GAS PLANT EUNICE, NEW MEXICO		CHLORIDE mg/L DEEP WELLS MARCH/APRIL 2009		FIGURE:	16
JOB NUMBER: 212201135	DRAWN BY: ARA/JBL	CHECKED BY: DNW	APPROVED BY: CV	DATE:	1/5/10

Stantec
10235 WEST LITTLE YORK
HOUSTON, TEXAS
PHONE: (713) 937-7973 FAX: (713) 983-8328

FIGURE 17
Chloride mg/L – Shallow Wells (August 2009)





Stantec
10235 WEST LITTLE YORK
HOUSTON, TEXAS
PHONE: (713) 937-7973 FAX: (713) 983-8328

FOR: **CHEVRON**
EUNICE NORTH GAS PLANT
EUNICE, NEW MEXICO

JOB NUMBER: 212201135
DRAWN BY: ARAJEL

CHLORIDE mg/L
SHALLOW WELLS
JULY/AUGUST 2009

FIGURE: **17**

CHECKED BY: DNW
APPROVED BY: SO
DATE: 1/5/10

FIGURE 18
Chloride mg/L – Deep Wells (August 2009)

FIGURE 19
Benzene mg/L – Shallow Wells (March/April 2009)



10235 WEST LITTLE YORK
HOUSTON, TEXAS
PHONE: (713) 937-7973 FAX: (713) 963-8328

FOR: **CHEVRON**
EUNICE NORTH GAS PLANT
EUNICE, NEW MEXICO

JOB NUMBER: 212201135
DRAWN BY: ARA/JBL

**BENZENE (mg/L)
SHALLOW WELLS
MARCH/APRIL 2009**

FIGURE: **19**

CHECKED BY: DNW
APPROVED BY: CV
DATE: 1/5/10

FIGURE 20
Benzene mg/L – Deep Wells (March/April 2009)



FIGURE 21
Benzene mg/L – Shallow Wells (August 2009)





10235 WEST LITTLE YORK
HOUSTON, TEXAS
PHONE: (713) 937-7973 FAX: (713) 983-8328

FOR:

CHEVRON

EUNICE NORTH GAS PLANT

EUNICE, NEW MEXICO

JOB NUMBER: 212201135

DRAWN BY: ARA/JBL

FIGURE:

BENZENE (mg/L)
SHALLOW WELLS
JULY/AUGUST 2009

21

CHECKED BY: DNW

APPROVED BY: SO

DATE: 1/5/10

FIGURE 22
Benzene mg/L – Deep Wells (August 2009)

FIGURE 23
TPH-DRO and TPH-GRO mg/L – Shallow Wells
(March/April 2009)





FIGURE 24
TPH-DRO and TPH-GRO mg/L – Deep Wells
(March/April 2009)

FIGURE 25
TPH-DRO and TPH-GRO mg/L – Shallow Wells (August 2009)



 Stantec 10235 WEST LITTLE YORK HOUSTON, TEXAS PHONE: (713)937-7973 FAX: (713)993-8328	FOR: CHEVRON EUNICE NORTH GAS PLANT EUNICE, NEW MEXICO		TPH-GRO AND TPH-DRO (mg/L) SHALLOW WELLS JULY/AUGUST 2009		FIGURE: 25
	JOB NUMBER: 212201135	DRAWN BY: ARA/JBL	CHECKED BY: DNW	APPROVED BY: SO	DATE: 1/5/10

FIGURE 26
TPH-DRO and TPH-GRO mg/L – Deep Wells (August 2009)



 10235 WEST LITTLE YORK HOUSTON, TEXAS PHONE: (713)937-7973 FAX: (713)983-8328	FOR:		CHEVRON EUNICE NORTH GAS PLANT EUNICE, NEW MEXICO		TPH-GRO AND TPH-DRO (mg/L) DEEP WELLS JULY/AUGUST 2009	FIGURE: 26
	JOB NUMBER:	212201135	DRAWN BY:	ARA/JBL		
	CHECKED BY:	DNW	APPROVED BY:	SO		
					DATE:	1/5/10

TABLE 1
CUMULATIVE GROUNDWATER ELEVATION DATA

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
Shallow Zone Wells				
MW001	04/22/97	3428.57	52.34	3376.23
	12/18/97	3428.57	52.32	3376.25
	11/16/99	3428.57	*51.32	3377.25
	05/15/01	3428.57	50.33	3378.24
	08/23/01	3428.57	51.02	3377.55
	01/21/02	3428.57	50.64	3377.93
	04/04/02	3428.57	50.66	3377.91
	09/03/02	3428.57	50.44	3378.13
	12/02/02	3428.57	50.20	3378.37
	01/31/03	3428.57	50.36	3378.21
	03/28/03	3428.57	50.54	3378.03
	05/19/03	3428.57	50.36	3378.21
	09/09/03	3428.57	50.52	3378.05
	01/26/04	3428.57	50.73	3377.84
	03/30/04	3428.57	50.71	3377.86
	06/07/04	3428.57	50.76	3377.81
	09/17/04	3428.57	50.30	3378.27
	11/30/04	3428.57	49.90	3378.67
	03/31/05	3428.57	49.25	3379.32
	05/23/05	3428.57	49.15	3379.42
	01/17/06	3428.57	48.39	3380.18
	06/19/06	3428.57	48.02	3380.55
	04/19/07	3428.57	47.75	3380.82
	03/24/08	3428.57	47.83	3380.74
	03/11/09	NG	NG	NG
MW002	04/22/97	3432.17	55.95	3376.22
	12/18/97	3432.17	55.62	3376.55
	11/16/99	3432.17	*54.97	3377.20
	05/15/01	3432.17	54.15	3378.02
	08/23/01	3432.17	54.12	3378.05
	01/21/02	3432.17	54.30	3377.87
	04/04/02	3432.17	54.31	3377.86
	09/03/02	3432.17	54.14	3378.03
	12/02/02	3432.17	53.88	3378.29
	01/30/03	3432.17	53.88	3378.29
	03/28/03	3432.17	54.16	3378.01
	05/19/03	3432.17	53.97	3378.20
	09/09/03	3432.17	54.05	3378.12
	12/02/03	3432.17	53.89	3378.28
	03/30/04	3432.17	54.11	3378.06
	06/07/04	3432.17	54.21	3377.96
	09/17/04	3432.17	53.94	3378.23
	11/30/04	3432.17	53.74	3378.43
	03/31/05	3432.17	53.37	3378.80
	05/23/05	3432.17	53.06	3379.11
	01/16/06	3432.17	52.62	3379.55
	06/19/06	3432.17	52.20	3379.97
	04/12/07	3432.17	51.78	3380.39
	03/19/08	3432.17	51.69	3380.48
	03/11/09	3432.17	51.94	3380.23
MW003	04/22/97	3428.27	49.79	3378.48
	12/18/97	3428.27	49.24	3379.03
	11/16/99	3428.27	*50.49	3377.78
	05/15/01	3428.27	49.63	3378.64
	08/23/01	3428.27	49.99	3378.28
	01/21/02	3428.27	49.81	3378.46
	04/04/02	3428.27	49.92	3378.35
	09/03/02	3428.27	49.80	3378.47
	12/02/02	3428.27	49.51	3378.76
	01/31/03	3428.27	49.64	3378.63
	03/28/03	3428.27	49.61	3378.66
	05/19/03	3428.27	49.57	3378.70
	09/09/03	3428.27	49.64	3378.63
	12/03/03	3428.27	49.70	3378.57
	03/30/04	3428.27	49.78	3378.49
	06/07/04	3428.27	49.74	3378.53
	09/17/04	3428.27	49.38	3378.89
	11/30/04	3428.27	48.80	3379.47
	03/31/05	3428.27	48.40	3379.87
	05/23/05	3428.27	48.31	3379.96
	01/17/06	3428.27	47.79	3380.48
	06/19/06	3428.27	47.65	3380.62
	4/16/2007	3428.27	47.23	3381.04
	03/19/08	3428.27	47.21	3381.06
	03/11/09	3428.27	47.73	3380.54

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW004	04/22/97	3423.38	48.24	3375.14
	12/18/97	3423.38	47.69	3375.69
	11/16/99	3423.38	*46.76	3376.62
	05/15/01	3423.38	45.91	3377.47
	08/23/01	3423.38	46.12	3377.26
	01/21/02	3423.38	46.20	3377.18
	04/04/02	3423.38	46.27	3377.11
	09/03/02	3423.38	45.95	3377.43
	12/02/02	3423.38	45.85	3377.53
	01/31/03	3423.38	45.94	3377.44
	03/28/03	3423.38	45.96	3377.42
	05/19/03	3423.38	45.97	3377.41
	09/09/03	3423.38	46.14	3377.24
	12/03/03	3423.38	46.15	3377.23
	03/30/04	3423.38	46.24	3377.14
	06/07/04	3423.38	46.19	3377.19
	09/17/04	3423.38	45.90	3377.48
	11/29/04	3423.38	45.44	3377.94
	03/31/05	3423.38	42.85	3380.53
	05/23/05	3423.38	44.90	3378.48
MW005	04/22/97	3424.77	49.30	3375.47
	12/18/97	3424.77	49.52	3375.25
	11/16/99	3424.77	*48.14	3376.63
	05/15/01	3424.77	NR	NR
	08/23/01	3424.77	47.82	3376.95
	01/21/02	3424.77	47.80	3376.97
	04/09/02	3424.77	47.31	3377.46
	04/10/03	3424.77	47.27	3377.50
	05/19/03	3424.77	47.25	3377.52
	09/08/03	3424.77	49.22	3375.55
	12/03/03	3424.77	47.51	3377.26
	03/30/04	3424.77	47.56	3377.21
	06/07/04	3424.77	47.54	3377.23
	09/17/04	3424.77	47.18	3377.59
	11/30/04	3424.77	46.51	3378.26
	04/01/05	3424.77	46.26	3378.51
	05/23/05	3424.77	46.04	3378.73
	01/18/06	3424.77	45.30	3379.47
	06/15/06	3424.77	45.05	3379.72
	04/19/07	3424.77	44.82	3379.95
MW006	03/24/08	3424.77	44.92	3379.85
	03/11/09	3424.77	45.49	3379.28
	04/22/97	3425.26	49.26	3376.00
	12/18/97	3425.26	49.69	3375.57
	11/16/99	3425.26	*48.69	3376.57
	05/15/01	3425.26	49.48	3375.78
	08/23/01	3425.26	50.21	3375.05
	01/21/02	3425.26	50.11	3375.15
	04/09/02	3425.26	50.35	3374.91
	09/11/02	3425.26	49.55	3375.71
	12/05/02	3425.26	49.13	3376.13
	04/10/03	3425.26	49.61	3375.65
	05/19/03	3425.26	49.63	3375.63
	09/08/03	3425.26	49.22	3376.04
	12/03/03	3425.26	49.95	3375.31
	03/30/04	3425.26	50.63	3374.63
	06/07/04	3425.26	49.25	3376.01
	09/17/04	3425.26	48.75	3376.51
	11/30/04	3425.26	46.94	3378.32
	04/01/05	3425.26	46.70	3378.56
	05/23/05	3425.26	46.49	3378.77
	01/18/06	3425.26	45.74	3379.52
	06/15/06	3425.26	45.47	3379.79
	04/23/07	3425.26	45.25	3380.01
	03/24/08	3425.26	45.35	3379.91
	03/11/09	3425.26	45.90	3379.36

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW007	12/18/97	3428.39	49.43	3378.96
	11/16/99	3428.39	*50.57	3377.82
	05/15/01	3428.39	49.70	3378.69
	08/23/01	3428.39	50.06	3378.33
	01/21/02	3428.39	49.93	3378.46
	04/04/02	3428.39	50.03	3378.36
	09/03/02	3428.39	49.90	3378.49
	12/02/02	3428.39	49.60	3378.79
	01/31/03	3428.39	49.71	3378.68
	03/28/03	3428.39	49.70	3378.69
	05/19/03	3428.39	49.60	3378.79
	09/09/03	3428.39	49.73	3378.66
	12/03/03	3428.39	49.71	3378.68
	03/30/04	3428.39	49.89	3378.50
	06/07/04	3428.39	49.82	3378.57
	09/17/04	3428.39	49.44	3378.95
	11/30/04	3428.39	48.90	3379.49
	03/31/05	3428.39	48.50	3379.89
	05/23/05	3428.39	48.41	3379.98
	01/17/06	3428.39	47.91	3380.48
	06/19/06	3428.39	47.75	3380.64
MW008	04/16/07	3428.39	47.33	3381.06
	03/19/08	3428.39	47.35	3381.04
	03/10/09	3428.39	47.78	3380.61
	12/18/97	3430.13	50.76	3379.37
	11/16/99	3430.13	*52.25	3377.88
	05/15/01	3430.13	51.36	3378.77
	08/23/01	3430.13	51.72	3378.41
	01/21/02	3430.13	51.53	3378.60
	04/04/02	3430.13	51.60	3378.53
	09/03/02	3430.13	51.51	3378.62
	12/02/02	3430.13	51.27	3378.86
	01/31/03	3430.13	51.31	3378.82
	03/28/03	3430.13	51.31	3378.82
	05/19/03	3430.13	51.21	3378.92
	09/09/03	3430.13	51.33	3378.80
	12/03/03	3430.13	51.33	3378.80
	03/30/04	3430.13	51.40	3378.73
	06/07/04	3430.13	51.82	3378.31
	11/30/04	3430.13	50.64	3379.49
	03/31/05	3430.13	50.24	3379.89
	05/23/05	3430.13	50.14	3379.99
MW008M	01/17/06	3430.13	49.52	3380.61
	06/19/06	3430.13	49.37	3380.76
	04/03/07	3430.13	48.93	3381.20
	03/24/08	3430.13	48.80	3381.33
	03/11/09	3430.13	49.24	3380.89
	01/21/02	3430.27	51.71	3378.56
	04/04/02	3430.27	51.77	3378.50
	09/03/02	3430.27	51.68	3378.59
	12/02/02	3430.27	51.45	3378.82
	01/31/03	3430.27	51.52	3378.75
	03/28/03	3430.27	51.47	3378.80
	05/19/03	3430.27	51.44	3378.83
	09/09/03	3430.27	51.49	3378.78
	12/03/03	3430.27	51.44	3378.83
	03/30/04	3430.27	51.52	3378.75
	06/07/04	3430.27	51.56	3378.71
	11/30/04	3430.27	50.79	3379.48
	03/31/05	3430.27	50.47	3379.80
	05/23/05	3430.27	50.32	3379.95
	01/17/06	3430.27	49.77	3380.50
	06/19/06	3430.27	49.65	3380.62
	04/13/07	3430.27	49.39	3380.88
	03/24/08	3430.27	49.12	3381.15
	03/11/09	3430.27	49.44	3380.83

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW009	12/18/97	3427.63	48.98	3378.65
	11/16/99	3427.63	*50.38	3377.25
	05/15/01	3427.63	49.59	3378.04
	08/23/01	3427.63	49.85	3377.78
	01/21/02	3427.63	49.82	3377.81
	04/04/02	3427.63	49.88	3377.75
	09/03/02	3427.63	49.75	3377.88
	12/02/02	3427.63	49.55	3378.08
	01/31/03	3427.63	49.60	3378.03
	03/28/03	3427.63	49.57	3378.06
	05/19/03	3427.63	49.53	3378.10
	09/09/03	3427.63	49.66	3377.97
	12/03/03	3427.63	49.66	3377.97
	03/30/04	3427.63	49.88	3377.75
	06/07/04	3427.63	49.77	3377.86
	09/17/04	3427.63	49.60	3378.03
	11/30/04	3427.63	49.00	3378.63
	03/31/05	3427.63	48.61	3379.02
	05/23/05	3427.63	48.47	3379.16
	01/17/06	3427.63	47.90	3379.73
	06/19/06	3427.63	47.75	3379.88
	03/18/08	3427.63	47.49	3380.14
	03/11/09	3427.63	47.91	3379.72
MW010	12/18/97	3419.42	43.22	3376.20
	11/16/99	3419.42	*41.27	3378.15
	05/15/01	3419.42	40.37	3379.05
	08/23/01	3419.42	40.61	3378.81
	01/21/02	3419.42	40.71	3378.71
	04/04/02	3419.42	40.85	3378.57
	09/03/02	3419.42	40.65	3378.77
	12/02/02	3419.42	40.50	3378.92
	01/30/03	3419.42	40.51	3378.91
	03/28/03	3419.42	40.46	3378.96
	05/19/03	3419.42	40.52	3378.90
	09/09/03	3419.42	40.52	3378.90
	12/07/03	3419.42	40.59	3378.83
	03/30/04	3419.42	40.81	3378.61
	06/07/04	3419.42	40.74	3378.68
	09/17/04	3419.42	40.50	3378.92
	11/30/04	3419.42	40.11	3379.31
	03/31/05	3419.42	39.63	3379.79
	05/23/05	3419.42	39.42	3380.00
	01/16/06	3419.42	39.15	3380.27
	06/16/06	3419.42	38.97	3380.45
	04/11/07	3419.42	38.57	3380.85
	03/19/08	3419.42	39.14	3380.28
	08/04/08	3419.42	38.94	3380.48
	03/11/09	3419.42	39.16	3380.26
	07/29/09	3419.42	39.31	3380.11
MW011	11/16/99	3431.49	*53.58	3377.91
	05/15/01	3431.49	52.78	3378.71
	08/23/01	3431.49	52.96	3378.53
	01/21/02	3431.49	52.84	3378.65
	04/04/02	3431.49	52.89	3378.60
	09/03/02	3431.49	52.80	3378.69
	12/02/02	3431.49	52.56	3378.93
	01/30/03	3431.49	52.51	3378.98
	03/28/03	3431.49	52.63	3378.86
	05/19/03	3431.49	52.58	3378.91
	09/09/03	3431.49	52.60	3378.89
	12/03/03	3431.49	52.52	3378.97
	03/30/04	3431.49	52.56	3378.93
	06/07/04	3431.49	52.61	3378.88
	11/30/04	3431.49	52.16	3379.33
	03/31/05	3431.49	52.82	3378.67
	05/23/05	3431.49	51.58	3379.91
	01/16/06	3431.49	51.16	3380.33
	06/19/06	3431.49	50.92	3380.57
	03/29/07	3431.49	50.57	3380.92
	03/24/08	3431.49	50.30	3381.19
	03/11/09	3431.49	50.53	3380.96

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW011M	01/21/02	3431.21	52.68	3378.53
	04/04/02	3431.21	52.63	3378.58
	09/03/02	3431.21	52.54	3378.67
	12/02/02	3431.21	52.32	3378.89
	01/30/03	3431.21	52.25	3378.96
	03/28/03	3431.21	52.32	3378.89
	05/19/03	3431.21	52.31	3378.90
	09/09/03	3431.21	52.30	3378.91
	12/03/03	3431.21	52.25	3378.96
	03/30/04	3431.21	52.31	3378.90
	06/07/04	3431.21	52.34	3378.87
	11/30/04	3431.21	51.91	3379.30
	03/31/05	3431.21	52.62	3378.59
	05/23/05	3431.21	51.38	3379.83
	01/16/06	3431.21	50.90	3380.31
	06/19/06	3431.21	50.65	3380.56
MW012	03/29/07	3431.21	50.15	3381.06
	03/24/08	3431.21	49.97	3381.24
	03/11/09	3431.21	50.21	3381.00
	11/16/99	3429.51	*51.12	3378.39
	05/15/01	3429.51	50.50	3379.01
	08/23/01	3429.51	50.50	3379.01
	01/21/02	3429.51	50.48	3379.03
	04/05/02	3429.51	50.49	3379.02
	09/03/02	3429.51	50.40	3379.11
	12/02/02	3429.51	50.25	3379.26
	01/30/03	3429.51	50.13	3379.38
	03/28/03	3429.51	50.25	3379.26
	05/19/03	3429.51	50.15	3379.36
	09/09/03	3429.51	50.11	3379.40
	12/03/03	3429.51	50.05	3379.46
	03/30/04	3429.51	50.18	3379.33
MW012M	06/07/04	3429.51	50.13	3379.38
	11/30/04	3429.51	49.66	3379.85
	03/31/05	3429.51	49.58	3379.93
	05/23/05	3429.51	49.23	3380.28
	01/16/06	3429.51	48.88	3380.63
	06/19/06	3429.51	48.65	3380.86
	04/02/07	3429.51	48.21	3381.30
	03/21/08	3429.51	47.70	3381.81
	03/11/09	3429.51	48.26	3381.25
	01/21/02	3430.06	50.95	3379.11
	04/05/02	3430.06	51.37	3378.69
	09/03/02	3430.06	50.89	3379.17
	12/02/02	3430.06	50.75	3379.31
	01/30/03	3430.06	50.65	3379.41
	03/28/03	3430.06	50.76	3379.30
	05/19/03	3430.06	50.71	3379.35
	09/09/03	3430.06	50.63	3379.43
MW012M	12/03/03	3430.06	50.63	3379.43
	03/30/04	3430.06	50.70	3379.36
	06/07/04	3430.06	50.32	3379.74
	11/30/04	3430.06	50.30	3379.76
	03/31/05	3430.06	50.19	3379.87
	05/23/05	3430.06	49.64	3380.42
	01/16/06	3430.06	49.50	3380.56
	06/19/06	3430.06	48.41	3381.65
	04/05/07	3430.06	49.10	3380.96
	03/21/08	3430.06	48.79	3381.27
	03/11/09	3430.06	48.90	3381.16

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW013	12/18/97	3424.11	46.98	3377.13
	11/16/99	3424.11	*44.81	3378.30
	05/15/01	3424.11	45.05	3379.06
	08/23/01	3424.11	45.11	3379.00
	01/21/02	3424.11	45.14	3378.97
	04/05/02	3424.11	45.22	3378.89
	09/03/02	3424.11	45.11	3379.00
	12/02/02	3424.11	44.91	3379.20
	01/30/03	3424.11	44.84	3379.27
	03/28/03	3424.11	45.91	3378.20
	05/19/03	3424.11	44.90	3379.21
	09/09/03	3424.11	44.89	3379.22
	12/02/03	3424.11	44.75	3379.36
	03/30/04	3424.11	44.94	3379.17
	06/07/04	3424.11	44.98	3379.13
	09/17/04	3424.11	44.82	3379.29
	11/30/04	3424.11	44.53	3379.58
	03/31/05	3424.11	44.05	3380.06
	05/23/05	3424.11	43.85	3380.26
	01/16/06	3424.11	43.47	3380.64
	06/16/06	3424.11	43.21	3380.90
	04/18/07	3424.11	42.83	3381.28
	09/19/07	3424.11	42.63	3381.48
	03/18/08	3424.11	42.65	3381.46
	08/04/08	3424.11	42.96	3381.15
	03/11/09	3424.11	43.19	3380.92
	07/29/09	3424.11	43.30	3380.81
MW014	11/16/99	3424.05	45.22	3378.86
	05/15/01	3424.05	44.61	3379.44
	08/23/01	3424.05	44.48	3379.57
	01/21/02	3424.05	44.49	3379.56
	04/05/02	3424.05	44.60	3379.45
	09/03/02	3424.05	44.25	3379.80
	12/02/02	3424.05	44.24	3379.81
	01/30/03	3424.05	44.19	3379.86
	03/28/03	3424.05	44.31	3379.74
	05/19/03	3424.05	44.25	3379.80
	09/09/03	3424.05	44.18	3379.87
	12/02/03	3424.05	44.03	3380.02
	03/30/04	3424.05	44.25	3379.80
	06/07/04	3424.05	44.18	3379.87
	09/14/04	3424.05	44.16	3379.89
	11/30/04	3424.05	43.98	3380.07
	03/31/05	3424.05	43.57	3380.48
	05/23/05	3424.05	40.76	3383.29
	01/17/06	3424.05	42.89	3381.16
	06/16/06	3424.05	42.78	3381.27
	03/26/07	3424.05	42.37	3381.68
	09/19/07	3424.05	42.14	3381.91
	03/19/08	3424.05	42.22	3381.83
	03/11/09	3424.05	42.69	3381.36
	07/29/09	3424.05	42.83	3381.22
MW015	11/16/99	3420.40	41.46	3378.94
	05/15/01	3420.40	40.85	3379.55
	08/23/01	3420.40	40.85	3379.55
	01/21/02	3420.40	40.81	3379.59
	04/04/02	3420.40	40.99	3379.41
	09/03/02	3420.40	40.75	3379.65
	12/02/02	3420.40	40.53	3379.87
	01/30/03	3420.40	40.51	3379.89
	03/28/03	3420.40	40.64	3379.76
	05/19/03	3420.40	40.56	3379.84
	09/08/03	3420.40	40.57	3379.83
	12/02/03	3420.40	40.51	3379.89
	03/30/04	3420.40	40.81	3379.59
	06/07/04	3420.40	40.60	3379.80
	09/16/04	3420.40	40.55	3379.85
	11/30/04	3420.40	40.22	3380.18
	03/31/05	3420.40	39.77	3380.63
	05/23/05	3420.40	39.58	3380.82
	01/17/06	3420.40	39.17	3381.23
	06/16/06	3420.40	39.13	3381.27
	03/22/07	3420.40	38.83	3381.57
	09/18/07	3420.40	38.51	3381.89
	03/18/08	3420.40	38.59	3381.81
	08/04/08	3420.40	39.02	3381.38
	03/10/09	3420.40	39.11	3381.29
	07/28/09	3420.40	39.35	3381.05

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW018	05/15/01	3417.15	37.82	3379.33
	05/15/01	3417.15	37.90	3379.25
	08/23/01	3417.15	37.26	3379.89
	01/21/02	3417.15	37.90	3379.25
	04/04/02	3417.15	38.15	3379.00
	09/03/02	3417.15	37.34	3379.81
	12/02/02	3417.15	37.37	3379.78
	01/30/03	3417.15	37.38	3379.77
	03/28/03	3417.15	37.66	3379.49
	05/19/03	3417.15	37.81	3379.34
	09/08/03	3417.15	37.82	3379.33
	12/02/03	3417.15	37.99	3379.16
	03/30/04	3417.15	38.30	3378.85
	06/07/04	3417.15	37.86	3379.29
	09/16/04	3417.15	37.48	3379.67
	11/29/04	3417.15	36.48	3380.67
	03/31/05	3417.15	36.32	3380.83
	05/23/05	3417.15	36.18	3380.97
	01/17/06	3417.15	36.05	3381.10
	06/16/06	3417.15	36.31	3380.84
	04/02/07	3417.15	35.95	3381.20
MW020	09/13/07	3417.15	35.18	3381.97
	03/18/08	3417.15	36.19	3380.96
	03/10/09	3417.15	36.59	3380.56
	07/28/09	3417.15	36.83	3380.32
	11/16/99	3420.85	44.58	3376.27
	02/06/02	3420.85	44.02	3376.83
	09/03/02	3420.85	43.79	3377.06
	12/09/02	3420.85	43.84	3377.01
	01/30/03	3420.85	43.78	3377.07
	03/28/03	3420.85	43.86	3376.99
	06/05/03	3420.85	43.93	3376.92
	01/22/04	3420.85	44.39	3376.46
	03/30/04	3420.85	44.41	3376.44
	06/07/04	3420.85	44.16	3376.69
	09/17/04	3420.85	43.99	3376.86
	11/29/04	3420.85	43.59	3377.26
	04/01/05	3420.85	43.12	3377.73
	05/23/05	3420.85	42.99	3377.86
	01/17/06	3420.85	42.61	3378.24
	06/16/06	3420.85	42.55	3378.30
	04/04/07	3420.85	42.23	3378.62
MW021	03/18/08	3420.85	42.25	3378.60
	08/04/08	3420.85	42.57	3378.28
	03/10/09	3420.85	42.67	3378.18
	07/28/09	3420.85	42.88	3377.97
	11/16/99	3422.72	47.82	3374.90
	05/15/01	3422.72	47.09	3375.63
	08/23/01	3422.72	47.34	3375.38
	01/21/02	3422.72	47.19	3375.53
	04/04/02	3422.72	47.35	3375.37
	09/03/02	3422.72	47.25	3375.47
	12/02/02	3422.72	47.01	3375.71
	01/30/03	3422.72	46.98	3375.74
	03/28/03	3422.72	47.02	3375.70
	05/19/03	3422.72	47.09	3375.63
	09/08/03	3422.72	47.21	3375.51
	01/21/04	3422.72	47.22	3375.50
	03/30/04	3422.72	47.21	3375.51
	06/07/04	3422.72	47.45	3375.27
	09/17/04	3422.72	47.15	3375.57
	11/29/04	3422.72	46.80	3375.92
	03/31/05	3422.72	46.28	3376.44
	05/23/05	3422.72	46.22	3376.50
	01/18/06	3422.72	45.68	3377.04
	06/14/06	3422.72	45.45	3377.27
	04/09/07	3422.72	45.10	3377.62
	09/18/07	3422.72	45.81	3376.91
	03/18/08	3422.72	45.07	3377.65
	08/04/08	3422.72	46.23	3376.49
	03/10/09	3422.72	45.60	3377.12
	07/28/09	3422.72	45.77	3376.95

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW023	11/16/99	3436.44	58.42	3378.02
	05/15/01	3436.44	57.73	3378.71
	08/23/01	3436.44	57.79	3378.65
	02/07/02	3436.44	57.77	3378.67
	09/03/02	3436.44	57.69	3378.75
	12/02/02	3436.44	57.46	3378.98
	01/30/03	3436.44	57.41	3379.03
	03/28/03	3436.44	57.50	3378.94
	05/19/03	3436.44	57.41	3379.03
	09/09/03	3436.44	57.39	3379.05
	12/02/03	3436.44	57.14	3379.30
	03/30/04	3436.44	57.34	3379.10
	06/07/04	3436.44	57.21	3379.23
	09/17/04	3436.44	57.34	3379.10
	11/30/04	3436.44	57.16	3379.28
	03/31/05	3436.44	56.92	3379.52
	05/23/05	3436.44	56.68	3379.76
	01/17/06	3436.44	56.37	3380.07
	06/14/06	3436.44	56.00	3380.44
	04/18/07	3436.44	55.64	3380.80
	09/20/07	3436.44	55.46	3380.98
MW024	01/09/03	3431.32	53.76	3377.56
	01/29/03	3431.32	53.64	3377.68
	03/27/03	3431.32	53.85	3377.47
	05/19/03	3431.32	53.77	3377.55
	09/09/03	3431.32	53.93	3377.39
	12/02/03	3431.32	53.86	3377.46
	03/30/04	3431.32	54.10	3377.22
	06/07/04	3431.32	54.21	3377.11
	09/16/04	3431.32	53.71	3377.61
	11/29/04	3431.32	53.54	3377.78
	03/31/05	3431.32	53.06	3378.26
	05/23/05	3431.32	52.78	3378.54
	01/17/06	3431.32	52.11	3379.21
	06/14/06	3431.32	51.60	3379.72
	04/11/07	3431.32	51.33	3379.99
	09/13/07	3431.32	51.44	3379.88
	03/19/08	3431.32	51.45	3379.87
	08/04/08	3431.32	51.52	3379.80
	03/11/09	3431.22	51.69	3379.53
	07/29/09	3431.22	51.74	3379.48
MW025	11/16/99	3432.69	53.23	3379.41
	05/15/01	3432.69	53.24	3379.45
	08/23/01	3432.69	53.02	3379.67
	01/21/02	3432.69	53.03	3379.66
	04/05/02	3432.69	53.17	3379.52
	09/03/02	3432.69	53.01	3379.68
	12/02/02	3432.69	52.83	3379.86
	01/29/03	3432.69	52.80	3379.89
	03/28/03	3432.69	52.86	3379.83
	05/19/03	3432.69	52.59	3380.10
	09/09/03	3432.69	52.62	3380.07
	12/02/03	3432.69	52.55	3380.14
	03/30/04	3432.69	52.70	3379.99
	06/07/04	3432.69	52.62	3380.07
	09/16/04	3432.69	52.48	3380.21
	11/29/04	3432.69	52.41	3380.28
	03/31/05	3432.69	52.10	3380.59
	05/23/05	3432.69	51.88	3380.81
	01/17/06	3432.69	51.43	3381.26
	06/16/06	3432.69	51.40	3381.29
	03/22/07	3432.69	50.04	3382.65
	09/18/07	3432.69	50.89	3381.80
	03/18/08	3432.69	50.85	3381.84
	08/04/08	3432.69	51.10	3381.59
	03/10/09	3432.69	51.12	3381.57
	07/28/09	3432.69	51.31	3381.38

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW026	11/16/99	3432.04	52.95	3379.09
	05/15/01	3432.04	52.08	3379.96
	08/23/01	3432.04	52.06	3379.98
	01/21/02	3432.04	51.91	3380.13
	04/04/02	3432.04	52.00	3380.04
	09/03/02	3432.04	51.99	3380.05
	12/02/02	3432.04	51.60	3380.44
	01/30/03	3432.04	51.43	3380.61
	03/28/03	3432.04	51.62	3380.42
	05/19/03	3432.04	51.52	3380.52
	09/08/03	3432.04	51.64	3380.40
	12/02/03	3432.04	51.49	3380.55
	03/30/04	3432.04	51.70	3380.34
	06/07/04	3432.04	51.69	3380.35
	09/16/04	3432.04	51.62	3380.42
	11/30/04	3432.04	51.56	3380.48
	03/31/05	3432.04	51.03	3381.01
	05/23/05	3432.04	50.79	3381.25
	01/17/06	3432.04	50.43	3381.61
	06/15/06	3432.04	50.23	3381.81
	04/05/07	3432.04	51.12	3380.92
MW027	09/10/07	3432.04	49.84	3382.20
	03/18/08	3432.04	49.74	3382.30
	08/04/08	3432.04	49.80	3382.24
	03/10/09	3432.04	50.25	3381.79
	07/28/09	3432.04	50.52	3381.52
	11/16/99	3443.33	64.65	3378.68
	05/15/01	3443.33	64.09	3379.24
	08/23/01	3443.33	63.82	3379.51
	01/21/02	3443.33	63.87	3379.46
	04/04/02	3443.33	63.90	3379.43
	09/03/02	3443.33	63.90	3379.43
	12/02/02	3443.33	63.64	3379.69
	01/30/03	3443.33	63.59	3379.74
	03/27/03	3443.33	63.49	3379.84
	05/19/03	3443.33	63.63	3379.70
	09/08/03	3443.33	63.58	3379.75
	12/02/03	3443.33	63.48	3379.85
	03/30/04	3443.33	63.62	3379.71
	06/07/04	3443.33	63.67	3379.66
	09/16/04	3443.33	63.55	3379.78
	11/29/04	3443.33	63.48	3379.85
	03/31/05	3443.33	62.98	3380.35
MW028	05/23/05	3443.33	62.73	3380.60
	01/17/06	3443.33	62.39	3380.94
	06/16/06	3443.33	62.32	3381.01
	03/21/07	3443.33	62.13	3381.20
	09/13/07	3443.33	62.04	3381.29
	03/18/08	3443.33	61.99	3381.34
	08/04/08	3443.33	62.14	3381.19
	03/11/09	NG	NG	NG
	07/29/09	3443.33	62.52	3380.81
	11/16/99	3451.63	73.52	3378.11
	05/15/01	3451.63	72.89	3378.74
	08/23/01	3451.63	72.86	3378.77
	01/21/02	3451.63	72.75	3378.88
	04/05/02	3451.63	72.77	3378.86
	09/03/02	3451.63	72.71	3378.92
	12/02/02	3451.63	72.55	3379.08
	01/29/03	3451.63	72.51	3379.12
	03/28/03	3451.63	72.58	3379.05
	05/19/03	3451.63	72.52	3379.11
	09/09/03	3451.63	72.53	3379.10
	01/28/04	3451.63	72.53	3379.10
	03/30/04	3451.63	72.36	3379.27
	06/07/04	3451.63	72.25	3379.38
	09/17/04	3451.63	72.28	3379.35
	11/29/04	3451.63	71.89	3379.74
	04/01/05	3451.63	71.71	3379.92
	05/23/05	3451.63	71.55	3380.08
	01/17/06	3451.63	71.10	3380.53
	06/14/06	3451.63	71.16	3380.47
	03/21/07	3451.63	70.91	3380.72
	09/05/07	3451.63	70.61	3381.02
	03/18/08	3451.63	70.68	3380.95
	08/04/08	3451.63	69.96	3381.67
	03/10/09	3451.63	70.70	3380.93
	07/28/09	3451.63	70.89	3380.74

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW029	11/16/99	3446.89	68.62	3378.27
	05/15/01	3446.89	68.12	3378.77
	08/30/01	3446.89	68.47	3378.42
	02/06/02	3446.89	67.97	3378.92
	09/03/02	3446.89	67.86	3379.03
	12/02/02	3446.89	67.70	3379.19
	01/29/03	3446.89	67.73	3379.16
	03/27/03	3446.89	67.66	3379.23
	05/19/03	3446.89	67.63	3379.26
	09/09/03	3446.89	67.68	3379.21
	12/02/03	3446.89	67.59	3379.30
	03/30/04	3446.89	67.50	3379.39
	06/07/04	3446.89	67.53	3379.36
	06/16/04	3446.89	67.49	3379.40
	11/29/04	3446.89	67.58	3379.31
	03/31/05	3446.89	67.33	3379.56
	05/23/05	3446.89	67.15	3379.74
	01/17/06	3446.89	66.99	3379.90
	06/14/06	3446.89	66.75	3380.14
	03/28/07	3446.89	66.46	3380.43
	09/05/07	3446.89	66.25	3380.64
MW030	04/24/02	3439.84	61.42	3378.42
	05/07/02	3439.84	61.30	3378.54
	09/03/02	3439.84	61.39	3378.45
	12/02/02	3439.84	61.18	3378.66
	01/29/03	3439.84	61.80	3378.04
	03/27/03	3439.84	61.14	3378.70
	05/19/03	3439.84	61.16	3378.68
	09/09/03	3439.84	61.16	3378.68
	12/02/03	3439.84	61.06	3378.78
	03/30/04	3439.84	61.04	3378.80
	06/07/04	3439.84	61.03	3378.81
	09/17/04	3439.84	61.06	3378.78
	11/29/04	3439.84	61.08	3378.76
	03/31/05	3439.84	60.80	3379.04
	05/23/05	3439.84	60.60	3379.24
	01/17/06	3439.84	60.28	3379.56
	06/14/06	3439.84	59.99	3379.85
	03/28/07	3439.84	59.58	3380.26
	09/10/07	3439.84	59.40	3380.44
	03/18/08	3439.84	58.20	3381.64
	08/04/08	3439.84	59.14	3380.70
MW031	03/10/09	3439.84	59.25	3380.59
	07/28/09	3439.84	59.24	3380.60
	04/25/02	3440.68	61.80	3378.88
	05/07/02	3440.68	61.85	3378.83
	09/03/02	3440.68	61.88	3378.80
	12/02/02	3440.68	61.73	3378.95
	01/29/03	3440.68	61.71	3378.97
	03/27/03	3440.68	61.65	3379.03
	05/19/03	3440.68	61.67	3379.01
	09/09/03	3440.68	61.68	3379.00
	12/02/03	3440.68	61.50	3379.18
	03/30/04	3440.68	61.53	3379.15
	06/07/04	3440.68	61.51	3379.17
	09/16/04	3440.68	61.48	3379.19
	11/29/04	3440.68	61.43	3379.25
	03/31/05	3440.68	61.04	3379.64
	05/23/05	3440.68	60.96	3379.72
	01/17/06	3440.68	60.74	3379.94
	06/14/06	3440.68	60.53	3380.15
	03/28/07	3440.68	60.24	3380.44
	09/10/07	3440.68	60.00	3380.68
	03/18/08	3440.68	59.89	3380.79
	08/04/08	3440.68	59.90	3380.78
	03/10/09	3440.68	59.86	3380.82
	07/28/09	3440.68	59.58	3381.10

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW032	04/04/02	3442.22	62.71	3379.51
	09/03/02	3442.22	62.61	3379.61
	12/02/02	3442.22	62.40	3379.82
	01/31/03	3442.22	62.55	3379.67
	03/27/03	3442.22	62.32	3379.90
	05/19/03	3442.22	62.37	3379.85
	09/09/03	3442.22	62.38	3379.84
	12/02/03	3442.22	62.23	3379.99
	03/30/04	3442.22	62.30	3379.92
	06/07/04	3442.22	62.28	3379.94
	09/16/04	3442.22	62.14	3380.08
	03/31/05	3442.22	61.54	3380.68
	05/23/05	3442.22	61.35	3380.87
	01/17/06	3442.22	60.93	3381.29
	06/15/06	3442.22	60.92	3381.30
	04/13/07	3442.22	60.75	3381.47
	09/06/07	3442.22	60.52	3381.70
	03/19/08	3442.22	60.59	3381.63
	08/04/08	3442.22	60.85	3381.37
	03/10/09	3442.22	60.82	3381.40
	07/28/09	3442.22	61.02	3381.20
MW033	04/04/02	3428.86	48.95	3379.91
	09/03/02	3428.86	48.86	3380.00
	12/05/02	3428.86	48.76	3380.10
	01/31/03	3428.86	48.63	3380.23
	03/27/03	3428.86	48.50	3380.36
	05/19/03	3428.86	48.63	3380.23
	09/09/03	3428.86	48.59	3380.27
	12/03/03	3428.86	48.69	3380.17
	03/30/04	3428.86	49.78	3379.08
	06/07/04	3428.86	48.64	3380.22
	09/16/04	3428.86	48.51	3380.35
	11/30/04	3428.86	48.41	3380.45
	04/01/05	3428.86	48.24	3380.62
	05/23/05	3428.86	47.73	3381.13
	01/17/06	3428.86	47.27	3381.59
	06/16/06	3428.86	47.06	3381.80
	04/23/07	3428.86	46.85	3382.01
	09/20/07	3428.86	46.64	3382.22
	03/18/08	3428.86	46.62	3382.24
	08/04/08	3428.86	46.92	3381.94
	03/11/09	3428.86	47.19	3381.67
	07/29/09	3428.86	47.34	3381.52
MW034	04/04/02	3418.76	43.49	3375.27
	09/03/02	3418.76	43.43	3375.33
	12/02/02	3418.76	43.24	3375.52
	01/30/03	3418.76	43.31	3375.45
	03/28/03	3418.76	43.20	3375.56
	05/19/03	3418.76	43.24	3375.52
	09/08/03	3418.76	43.43	3375.33
	12/02/03	3418.76	43.37	3375.39
	03/30/04	3418.76	43.55	3375.21
	06/07/04	3418.76	43.50	3375.26
	09/16/04	3418.76	43.41	3375.35
	11/29/04	3418.76	43.71	3375.05
	03/31/05	3418.76	42.66	3376.10
	05/23/05	3418.76	42.52	3376.24
	01/17/06	3418.76	47.06	3371.70
	06/19/06	3418.76	41.70	3377.06
	04/09/07	3418.76	41.40	3377.36
	03/19/08	3418.76	41.35	3377.41
	03/11/09	3418.76	41.86	3376.90
MW035	08/23/01	3427.39	50.49	3376.90
	01/21/02	3427.39	50.45	3376.94
	04/04/02	3427.39	50.58	3376.81
	09/03/02	3427.39	50.04	3377.35
	12/02/02	3427.39	50.03	3377.36
	01/31/03	3427.39	50.03	3377.36
	03/28/03	3427.39	50.19	3377.20
	05/19/03	3427.39	50.24	3377.15
	09/09/03	3427.39	50.35	3377.04
	12/03/03	3427.39	50.32	3377.07
	03/30/04	3427.39	50.52	3376.87
	06/07/04	3427.39	50.51	3376.88
	09/17/04	3427.39	49.98	3377.41
	11/30/04	3427.39	49.09	3378.30
	03/31/05	3427.39	49.02	3378.37
	05/23/05	3427.39	49.06	3378.33
	01/17/06	3427.39	48.44	3378.95
	06/19/06	3427.39	48.18	3379.21
	04/02/07	3427.39	47.91	3379.48
	03/18/08	3427.39	47.94	3379.45
	03/10/09	3427.39	48.45	3378.94

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW036	08/23/01	3425.49	48.36	3377.13
	01/21/02	3425.49	48.22	3377.27
	04/04/02	3425.49	48.24	3377.25
	09/03/02	3425.49	47.75	3377.74
	12/02/02	3425.49	47.78	3377.71
	01/31/03	3425.49	47.84	3377.65
	03/28/03	3425.49	47.91	3377.58
	05/19/03	3425.49	47.96	3377.53
	09/09/03	3425.49	48.12	3377.37
	12/03/03	3425.49	48.22	3377.27
	03/30/04	3425.49	48.37	3377.12
	06/07/04	3425.49	48.32	3377.17
	09/17/04	3425.49	47.86	3377.63
	11/30/04	3425.49	47.20	3378.29
	04/01/05	3425.49	46.89	3378.60
	05/23/05	3425.49	46.80	3378.69
	01/17/06	3425.49	46.11	3379.38
	06/19/06	3425.49	45.79	3379.70
MW037	04/19/07	3425.49	45.52	3379.97
	03/24/08	3425.49	45.65	3379.84
	03/11/09	3425.49	46.18	3379.31
	08/23/01	3423.71	46.60	3377.11
	01/21/02	3423.71	46.59	3377.12
	04/04/02	3423.71	46.62	3377.09
	09/03/02	3423.71	46.07	3377.64
	12/02/02	3423.71	46.17	3377.54
	01/31/03	3423.71	46.28	3377.43
	03/28/03	3423.71	46.29	3377.42
	05/19/03	3423.71	46.39	3377.32
	09/09/03	3423.71	46.52	3377.19
	12/03/03	3423.71	46.46	3377.25
	03/30/04	3423.71	47.76	3375.95
	06/07/04	3423.71	46.64	3377.07
	09/17/04	3423.71	46.18	3377.53
	11/30/04	3423.71	45.51	3378.20
	04/01/05	3423.71	45.34	3378.37
MW038	05/23/05	3423.71	45.21	3378.50
	01/18/06	3423.71	44.46	3379.25
	06/19/06	3423.71	44.29	3379.42
	04/19/07	3423.71	44.05	3379.66
	03/24/08	3423.71	44.15	3379.56
	03/11/09	3423.71	45.74	3377.97
	08/23/01	3425.23	47.85	3377.38
	01/21/02	3425.23	47.69	3377.54
	04/04/02	3425.23	47.81	3377.42
	09/03/02	3425.23	47.43	3377.80
	12/02/02	3425.23	47.30	3377.93
	01/31/03	3425.23	47.41	3377.82
	03/28/03	3425.23	47.51	3377.72
	05/19/03	3425.23	47.42	3377.81
	09/09/03	3425.23	47.61	3377.62
	12/03/03	3425.23	47.72	3377.51
	03/30/04	3425.23	47.80	3377.43
	06/07/04	3425.23	47.76	3377.47
MW043	09/17/04	3425.23	47.44	3377.79
	11/30/04	3425.23	46.89	3378.34
	04/01/05	3425.23	46.54	3378.69
	05/23/05	3425.23	46.35	3378.88
	01/17/06	3425.23	45.61	3379.62
	06/19/06	3425.23	45.32	3379.91
	4/19/2007	3425.23	45.09	3380.14
	03/24/08	3425.23	45.20	3380.03
	03/11/09	3425.23	45.73	3379.50
	05/07/02	3423.57	47.61	3375.96
	09/03/02	3423.57	47.53	3376.04
	12/02/02	3423.57	47.42	3376.15
	01/30/03	3423.57	47.38	3376.19
	03/28/03	3423.57	47.44	3376.13
	05/19/03	3423.57	47.50	3376.07
	09/08/03	3423.57	47.64	3375.93
	12/02/03	3423.57	47.55	3376.02
	03/30/04	3423.57	47.84	3375.73
	06/07/04	3423.57	47.82	3375.75
MW043	09/14/04	3423.57	47.44	3376.13
	11/29/04	3423.57	46.55	3377.02
	03/31/05	3423.57	46.49	3377.08
	05/23/05	3423.57	46.51	3377.06
	01/17/06	3423.57	44.92	3378.65
	06/14/06	3423.57	45.45	3378.12
	04/09/07	3423.57	45.35	3378.22
	03/18/08	3423.57	45.36	3378.21
	03/10/09	3423.57	45.85	3377.72

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW044	04/04/02	3420.41	43.88	3376.55
	09/03/02	3420.41	43.52	3376.89
	12/02/02	3420.41	43.47	3376.94
	01/30/03	3420.41	43.68	3376.73
	03/28/03	3420.41	43.49	3376.92
	05/19/03	3420.41	43.58	3376.83
	09/08/03	3420.41	43.69	3376.72
	12/02/03	3420.41	43.65	3376.76
	03/30/04	3420.41	43.90	3376.51
	06/07/04	3420.41	43.88	3376.53
	09/16/04	3420.41	43.49	3376.92
	11/29/04	3420.41	43.06	3377.35
	03/31/05	3420.41	42.59	3377.82
	05/23/05	3420.41	42.55	3377.86
	01/17/06	3420.41	41.72	3378.69
	06/19/06	3420.41	41.59	3378.82
	04/06/07	3420.41	41.45	3378.96
	03/19/08	3420.41	41.35	3379.06
	03/11/09	3420.41	41.89	3378.52
MW045	04/04/02	3425.53	48.57	3376.96
	09/03/02	3425.53	48.15	3377.38
	12/02/02	3425.53	47.94	3377.59
	01/31/03	3425.53	48.08	3377.45
	03/28/03	3425.53	48.31	3377.22
	05/19/03	3425.53	48.11	3377.42
	09/09/03	3425.53	48.34	3377.19
	12/03/03	3425.53	48.37	3377.16
	03/30/04	3425.53	48.44	3377.09
	06/07/04	3425.53	48.61	3376.92
	09/17/04	3425.53	48.10	3377.43
	11/30/04	3425.53	47.60	3377.93
	03/31/05	3425.53	47.05	3378.48
	05/23/05	3425.53	46.98	3378.55
	01/17/06	3425.53	46.36	3379.17
	06/19/06	3425.53	45.87	3379.66
	04/02/07	3425.53	45.66	3379.87
	04/17/07	3425.53	45.73	3379.80
	03/18/08	3425.53	45.74	3379.79
	03/10/09	3425.53	46.16	3379.37
MW046	04/04/02	3426.81	49.93	3376.88
	09/03/02	3426.81	49.37	3377.44
	12/02/02	3426.81	49.17	3377.64
	01/31/03	3426.81	49.33	3377.48
	03/28/03	3426.81	49.66	3377.15
	05/19/03	3426.81	49.35	3377.46
	09/09/03	3426.81	49.67	3377.14
	12/03/03	3426.81	49.75	3377.06
	03/30/04	3426.81	49.82	3376.99
	06/07/04	3426.81	50.05	3376.76
	09/17/04	3426.81	49.33	3377.48
	11/30/04	3426.81	48.99	3377.82
	03/31/05	3426.81	48.36	3378.45
	05/23/05	3426.81	48.18	3378.63
	01/17/06	3426.81	47.34	3379.47
	06/19/06	3426.81	46.87	3379.94
	04/19/07	3426.81	46.75	3380.06
	03/18/08	3426.81	46.84	3379.97
	03/11/09	3426.81	47.33	3379.48
MW047	04/04/02	3427.65	49.54	3378.11
	09/03/02	3427.65	49.40	3378.25
	12/02/02	3427.65	49.16	3378.49
	01/31/03	3427.65	49.22	3378.43
	03/28/03	3427.65	49.29	3378.36
	05/19/03	3427.65	49.21	3378.44
	09/09/03	3427.65	49.36	3378.29
	12/03/03	3427.65	49.38	3378.27
	03/30/04	3427.65	49.50	3378.15
	06/07/04	3427.65	49.43	3378.22
	09/17/04	3427.65	49.20	3378.45
	11/30/04	3427.65	48.66	3378.99
	03/31/05	3427.65	47.98	3379.67
	05/23/05	3427.65	47.90	3379.75
	01/17/06	3427.65	47.38	3380.27
	06/19/06	3427.65	47.12	3380.53
	04/16/07	3427.65	46.73	3380.92
	03/19/08	3427.65	46.84	3380.81
	03/11/09	NG	NG	NG

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW058	01/31/03	3437.13	58.49	3378.64
	03/27/03	3437.13	58.49	3378.64
	05/19/03	3437.13	58.52	3378.61
	09/09/03	3437.13	58.57	3378.56
	12/02/03	3437.13	58.44	3378.69
	03/30/04	3437.13	58.51	3378.62
	06/07/04	3437.13	58.50	3378.63
	09/16/04	3437.13	58.42	3378.71
	11/29/04	3437.13	58.43	3378.70
	03/31/05	3437.13	59.08	3378.05
	05/23/05	3437.13	57.84	3379.29
	01/17/06	3437.13	57.43	3379.70
	06/14/06	3437.13	57.10	3380.03
	04/23/07	3437.13	56.20	3380.93
	09/13/07	3437.13	56.58	3380.55
	03/19/08	3437.13	56.46	3380.67
	08/04/08	3437.13	56.47	3380.66
	03/11/09	3437.13	56.52	3380.61
	07/29/09	3437.13	56.56	3380.57
MW059	01/31/03	3442.22	63.28	3378.94
	03/28/03	3442.22	63.23	3378.99
	05/19/03	3442.22	63.15	3379.07
	09/09/03	3442.22	63.15	3379.07
	12/02/03	3442.22	63.05	3379.17
	03/30/04	3442.22	63.06	3379.16
	06/07/04	3442.22	63.00	3379.22
	09/17/04	3442.22	63.03	3379.19
	11/30/04	3442.22	62.96	3379.26
	03/31/05	3442.22	62.75	3379.47
	05/23/05	3442.22	62.51	3379.71
	01/17/06	3442.22	62.28	3379.94
	06/14/06	3442.22	61.96	3380.26
	Date Missing	3442.22	61.61	3380.61
	09/11/07	3442.22	61.39	3380.83
	03/19/08	3442.22	61.30	3380.92
	08/04/08	3442.22	61.20	3381.02
	03/11/09	3442.22	61.33	3380.89
	07/29/09	3442.22	61.32	3380.90
MW060	01/08/03	3437.70	58.62	3379.08
	01/30/03	3437.70	58.38	3379.32
	03/28/03	3437.70	58.45	3379.25
	05/19/03	3437.70	58.39	3379.31
	09/09/03	3437.70	58.34	3379.36
	12/02/03	3437.70	58.15	3379.55
	03/30/04	3437.70	58.20	3379.50
	06/07/04	3437.70	58.19	3379.51
	09/16/04	3437.70	58.12	3379.58
	11/29/04	3437.70	58.11	3379.59
	03/31/05	3437.70	57.79	3379.91
	05/23/05	3437.70	57.63	3380.07
	01/17/06	3437.70	57.33	3380.37
	06/16/06	3437.70	57.13	3380.57
	03/28/07	3437.70	56.80	3380.90
	09/13/07	3437.70	56.57	3381.13
	03/18/08	3437.70	56.46	3381.24
	08/04/08	3437.70	56.57	3381.13
	03/10/09	3437.70	66.55	3371.15
	07/28/09	3437.70	56.60	3381.10
MW061	01/08/03	3439.86	60.23	3379.63
	03/27/03	3439.86	60.20	3379.66
	05/19/03	3439.86	60.26	3379.60
	09/09/03	3439.86	60.18	3379.68
	12/02/03	3439.86	60.00	3379.86
	03/30/04	3439.86	60.12	3379.74
	06/07/04	3439.86	60.06	3379.80
	09/16/04	3439.86	59.93	3379.93
	11/29/04	3439.86	59.84	3380.02
	03/31/05	3439.86	59.52	3380.34
	05/23/05	3439.86	59.32	3380.54
	01/17/06	3439.86	58.90	3380.96
	06/15/06	3439.86	58.81	3381.05
	04/18/07	3439.86	58.54	3381.32
	09/20/07	3439.86	58.39	3381.47
	03/18/08	3439.86	58.34	3381.52
	08/04/08	3439.86	58.55	3381.31
	03/11/09	3439.86	58.59	3381.27
	07/29/09	3439.86	58.65	3381.21

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW068	03/27/03	3448.08	67.61	3380.47
	05/19/03	3448.08	68.70	3379.38
	09/09/03	3448.08	68.67	3379.41
	12/02/03	3448.08	68.51	3379.57
	03/30/04	3448.08	68.52	3379.56
	06/07/04	3448.08	68.45	3379.63
	09/16/04	3448.18	68.30	3379.88
	11/29/04	3448.08	68.19	3379.89
	03/31/05	3448.08	67.90	3380.18
	05/23/05	3448.08	67.78	3380.30
	01/17/06	3448.08	67.40	3380.68
	06/14/06	3448.08	67.30	3380.78
	03/22/07	3448.08	67.04	3381.04
	09/06/07	3448.08	66.78	3381.30
	03/18/08	3448.08	66.80	3381.28
	08/04/08	3448.08	67.09	3380.99
	03/10/09	3448.08	66.94	3381.14
	07/28/09	3448.08	67.02	3381.06
MW069	03/27/03	3444.07	64.89	3379.18
	05/19/03	3444.07	64.83	3379.24
	09/09/03	3444.07	64.79	3379.28
	12/02/03	3444.07	64.63	3379.44
	03/30/04	3444.07	64.65	3379.42
	06/07/04	3444.07	64.63	3379.44
	09/16/04	3444.07	64.60	3379.47
	11/29/04	3444.07	64.51	3379.56
	03/31/05	3444.07	64.24	3379.83
	05/23/05	3444.07	64.08	3379.99
	01/17/06	3444.07	63.82	3380.25
	06/14/06	3444.07	63.66	3380.41
	03/22/09	3444.07	63.39	3380.68
	09/06/07	3444.07	63.16	3380.91
	03/18/08	3444.07	63.17	3380.90
	08/04/08	3444.07	63.10	3380.97
	03/10/09	3444.07	62.99	3381.08
	07/28/09	3444.07	63.09	3380.98
MW070	03/27/03	3439.68	61.00	3378.68
	05/19/03	3439.68	61.03	3378.65
	09/09/03	3439.68	61.02	3378.66
	12/02/03	3439.68	60.93	3378.75
	03/30/04	3439.68	61.02	3378.66
	06/07/04	3439.68	60.94	3378.74
	09/16/04	3439.68	60.90	3378.78
	11/29/04	3439.68	60.91	3378.77
	03/31/05	3439.68	60.72	3378.96
	05/23/05	3439.68	60.52	3379.16
	01/17/06	3439.68	60.20	3379.48
	06/14/06	3439.68	59.88	3379.80
	03/29/07	3439.68	59.47	3380.21
	09/10/07	3439.68	59.25	3380.43
	03/18/08	3439.68	59.18	3380.50
	08/04/08	3439.68	59.09	3380.59
	03/10/09	3439.68	59.11	3380.57
	07/28/09	3439.68	59.10	3380.58
MW088M	09/24/04	3430.63	50.65	3379.98
	03/31/05	3430.63	50.61	3380.02
	05/23/05	3430.63	50.25	3380.38
	01/16/06	3430.63	49.90	3380.73
	06/19/06	3430.63	49.67	3380.96
	04/05/07	3430.63	49.25	3381.38
	03/21/08	3430.63	49.00	3381.63
RW002	03/11/09	3430.63	49.30	3381.33
	01/21/02	3431.66	52.98	3378.68
	04/04/02	3431.66	53.05	3378.61
	09/03/02	3431.66	52.95	3378.71
	12/02/02	3431.66	52.81	3378.85
	01/30/03	3431.66	52.75	3378.91
	03/28/03	3431.66	52.76	3378.90
	05/19/03	3431.66	52.73	3378.93
	09/09/03	3431.66	52.72	3378.94
	12/03/03	3431.66	52.66	3379.00
	03/30/04	3431.66	52.77	3378.89
	06/07/04	3431.66	52.77	3378.89
	11/29/04	3431.66	52.34	3379.32
	03/31/05	3431.66	51.05	3380.61
	05/23/05	3431.66	51.77	3379.89
	01/16/06	3431.66	51.35	3380.31
	06/19/06	3431.66	51.11	3380.55
	03/29/07	3431.66	50.60	3381.06
	03/24/08	3431.66	50.45	3381.21
	03/11/09	3431.66	50.70	3380.96

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
RW003	01/21/02	3429.82	50.75	3379.07
	04/04/02	3429.82	50.78	3379.04
	09/03/02	3429.82	50.75	3379.07
	12/02/02	3429.82	50.56	3379.26
	01/30/03	3429.82	50.45	3379.37
	03/28/03	3429.82	50.55	3379.27
	05/19/03	3429.82	50.49	3379.33
	09/09/03	3429.82	50.40	3379.42
	12/03/03	3429.82	50.34	3379.48
	03/30/04	3429.82	50.53	3379.29
	06/07/04	3429.82	50.43	3379.39
	11/30/04	3429.82	50.13	3379.69
	03/31/05	3429.82	49.90	3379.92
	05/23/05	3429.82	49.55	3380.27
	01/16/06	3429.82	49.20	3380.62
	06/19/06	3429.82	48.95	3380.87
	04/02/07	3429.82	48.53	3381.29
	03/19/08	3429.82	48.30	3381.52
	03/11/09	3429.82	48.58	3381.24
IW001	08/01/02	3431.91	53.19	3378.72
	12/02/02	3431.91	52.90	3379.01
	01/30/03	3431.91	52.85	3379.06
	03/28/03	3431.91	52.94	3378.97
	05/19/03	3431.91	50.91	3381.00
	09/09/03	3431.91	52.62	3379.29
	12/03/03	3431.91	53.03	3378.88
	03/30/04	3431.91	52.98	3378.93
	06/07/04	3431.91	53.93	3377.98
	11/30/04	3431.91	53.04	3378.87
	03/31/05	3431.91	53.62	3378.29
	05/23/05	3431.91	52.58	3379.33
	01/18/06	3431.91	49.50	3382.41
	06/19/06	3431.91	51.28	3380.63
	04/16/07	3431.91	48.85	3383.06
	03/24/08	3431.91	50.70	3381.21
	03/10/09	3431.91	48.98	3382.93
IW002	09/03/02	3430.33	53.14	3377.19
	12/02/02	3430.33	50.99	3379.34
	01/30/03	3430.33	50.88	3379.45
	03/28/03	3430.33	50.99	3379.34
	05/19/03	3430.33	50.88	3379.45
	09/09/03	3430.33	51.46	3378.87
	12/03/03	3430.33	50.94	3379.39
	03/30/04	3431.00	51.62	3379.38
	06/07/04	3431.00	51.61	3379.39
	11/30/04	3431.00	51.34	3379.66
	03/31/05	3431.00	51.54	3379.46
	05/23/05	3431.00	51.36	3379.64
	01/18/06	3431.00	47.48	3383.52
	06/19/06	3431.00	48.71	3382.29
	04/11/07	3431.00	47.05	3383.95
	03/21/08	3431.00	46.19	3384.81
	03/10/09	3431.00	46.99	3384.01

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
Deep Zone Wells				
MW002A	01/07/03	3432.31	54.03	3378.28
	01/30/03	3432.31	53.89	3378.42
	03/28/03	3432.31	54.11	3378.20
	05/19/03	3432.31	53.99	3378.32
	09/09/03	3432.31	54.12	3378.19
	12/02/03	3432.31	53.97	3378.34
	03/30/04	3432.31	54.20	3378.11
	06/07/04	3432.31	54.21	3378.10
	09/17/04	3432.31	53.93	3378.38
	11/30/04	3432.31	53.74	3378.57
	03/31/05	3432.31	53.36	3378.95
	05/23/05	3432.31	53.08	3379.23
	01/17/06	3432.31	52.56	3379.75
	06/19/06	3432.31	52.18	3380.13
	04/12/07	3432.31	51.80	3380.51
	09/01/07	3432.31	NS	NS
	03/19/08	3432.31	51.72	3380.59
	03/11/09	3432.31	51.89	3380.42
MW004A	12/18/97	3423.57	48.00	3375.57
	11/16/99	3423.57	*47.00	3376.57
	05/15/01	3423.57	46.31	3377.26
	08/23/01	3423.57	46.44	3377.13
	01/21/02	3423.57	46.44	3377.13
	04/04/02	3423.57	46.52	3377.05
	09/03/02	3423.57	46.49	3377.08
	12/02/02	3423.57	46.10	3377.47
	01/31/03	3423.57	46.16	3377.41
	03/28/03	3423.57	46.20	3377.37
	05/19/03	3423.57	46.21	3377.36
	09/09/03	3423.57	46.36	3377.21
	12/03/03	3423.57	46.38	3377.19
	03/30/04	3423.57	46.45	3377.12
	06/07/04	3423.57	46.66	3376.91
	09/17/04	3423.57	46.18	3377.39
	11/30/04	3423.57	45.62	3377.95
	03/31/05	3423.57	45.61	3377.96
	05/23/05	3423.57	45.19	3378.38
	01/18/06	3423.57	44.39	3379.18
	06/19/06	3423.57	44.21	3379.36
	04/16/07	3423.57	43.95	3379.62
	03/19/08	3423.57	43.98	3379.59
	03/11/09	3423.57	44.54	3379.03
MW007A	12/18/97	3428.13	49.37	3378.76
	11/16/99	3428.13	*50.22	3377.91
	05/15/01	3428.13	49.38	3378.75
	08/23/01	3428.13	49.72	3378.41
	01/21/02	3428.13	49.64	3378.49
	04/04/02	3428.13	49.74	3378.39
	09/03/02	3428.13	49.60	3378.53
	12/02/02	3428.13	49.32	3378.81
	01/31/03	3428.13	49.43	3378.70
	03/28/03	3428.13	49.43	3378.70
	05/19/03	3428.13	49.37	3378.76
	09/09/03	3428.13	49.43	3378.70
	12/03/03	3428.13	49.49	3378.64
	03/30/04	3428.13	49.60	3378.53
	06/07/04	3428.13	49.53	3378.60
	09/17/04	3428.13	49.22	3378.91
	01/17/06	3428.13	47.66	3380.47
	06/19/06	3428.13	47.50	3380.63
	04/16/07	3428.13	47.11	3381.02
	03/19/08	3428.13	47.12	3381.01
	03/11/09	3428.13	47.64	3380.49
MW008A	12/18/97	3430.01	50.81	3379.20
	11/16/99	3430.01	*52.16	3377.85
	05/15/01	3430.01	51.34	3378.67
	08/23/01	3430.01	51.64	3378.37
	01/21/02	3430.01	51.49	3378.52
	04/04/02	3430.01	51.53	3378.48
	09/03/02	3430.01	51.41	3378.60
	12/02/02	3430.01	51.16	3378.85
	01/31/03	3430.01	51.24	3378.77
	03/28/03	3430.01	51.25	3378.76
	05/19/03	3430.01	51.21	3378.80
	09/09/03	3430.01	51.26	3378.75
	12/03/03	3430.01	51.21	3378.80
	03/30/04	3430.01	51.29	3378.72
	06/07/04	3430.01	51.32	3378.69
	11/30/04	3430.01	50.68	3379.33
	03/31/05	3430.01	50.24	3379.77
	05/23/05	3430.01	50.12	3379.89
	01/17/06	3430.01	49.58	3380.43
	06/19/06	3430.01	49.41	3380.60
	04/03/07	3430.01	48.48	3381.53
	03/24/08	3430.01	49.12	3380.89
	03/11/09	3430.01	49.18	3380.83

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW009A	12/18/97	3427.48	49.03	3378.45
	11/16/99	3427.48	*50.22	3377.26
	05/15/01	3427.48	49.42	3378.06
	08/23/01	3427.48	49.64	3377.84
	01/21/02	3427.48	49.68	3377.80
	04/04/02	3427.48	49.78	3377.70
	09/03/02	3427.48	49.55	3377.93
	12/02/02	3427.48	49.40	3378.08
	01/31/03	3427.48	49.45	3378.03
	03/28/03	3427.48	49.44	3378.04
	05/19/03	3427.48	49.43	3378.05
	09/09/03	3427.48	49.52	3377.96
	12/03/03	3427.48	49.63	3377.85
	03/30/04	3427.48	49.73	3377.75
	06/07/04	3427.48	49.65	3377.83
	09/17/04	3427.48	49.48	3378.00
	11/30/04	3427.48	48.91	3378.57
	03/31/05	3427.48	48.42	3379.06
	05/23/05	3427.48	48.33	3379.15
	01/17/06	3427.48	47.73	3379.75
MW011A	06/19/06	3427.48	47.52	3379.96
	04/04/07	3427.48	47.31	3380.17
	03/19/08	3427.48	47.29	3380.19
	03/11/09	3427.48	47.73	3379.75
	12/18/97	3431.77	51.49	3380.28
	11/16/99	3431.77	*53.49	3378.28
	05/15/01	3431.77	53.07	3378.70
	08/23/01	3431.77	53.20	3378.57
	01/21/02	3431.77	53.04	3378.73
	04/04/02	3431.77	53.13	3378.64
	09/03/02	3431.77	53.01	3378.76
	12/02/02	3431.77	52.76	3379.01
	01/30/03	3431.77	52.72	3379.05
	03/28/03	3431.77	52.85	3378.92
	05/19/03	3431.77	52.78	3378.99
	09/09/03	3431.77	52.82	3378.95
	12/03/03	3431.77	52.83	3378.94
	03/30/04	3431.77	53.04	3378.73
	06/07/04	3431.77	53.03	3378.74
	11/30/04	3431.77	53.03	3378.74
MW012A	03/31/05	3431.77	52.18	3379.59
	05/23/05	3431.77	51.94	3379.83
	01/16/06	3431.77	51.45	3380.32
	06/19/06	3431.77	51.25	3380.52
	03/29/07	3431.77	50.88	3380.89
	03/24/08	3431.77	50.69	3381.08
	03/11/09	3431.77	50.94	3380.83
	12/18/97	3429.92	49.73	3380.19
	11/16/99	3429.92	*51.50	3378.42
	05/15/01	3429.92	50.83	3379.09
	08/23/01	3429.92	50.89	3379.03
	01/21/02	3429.92	50.84	3379.08
	04/05/02	3429.92	50.90	3379.02
	09/03/02	3429.92	50.80	3379.12
	12/02/02	3429.92	50.65	3379.27
	01/30/03	3429.92	50.55	3379.37
	03/28/03	3429.92	50.66	3379.26
	05/19/03	3429.92	50.63	3379.29
	09/09/03	3429.92	50.52	3379.40
	12/03/03	3429.92	50.51	3379.41
	03/30/04	3429.92	50.67	3379.25
MW012A	06/07/04	3429.92	50.52	3379.40
	11/30/04	3429.92	50.28	3379.64
	03/31/05	3429.92	49.97	3379.95
	05/23/05	3429.92	49.77	3380.15
	01/16/06	3429.92	49.13	3380.79
	06/19/06	3429.92	49.00	3380.92
	04/02/07	3429.92	48.35	3381.57
	03/21/08	3429.92	48.37	3381.55
	03/11/09	3429.92	48.65	3381.27

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW013A	12/18/97	3424.25	46.84	3377.41
	11/16/99	3424.25	45.79	3378.46
	05/15/01	3424.25	45.06	3379.19
	08/23/01	3424.25	45.22	3379.03
	01/21/02	3424.25	45.17	3379.08
	04/05/02	3424.25	45.23	3379.02
	09/03/02	3424.25	45.15	3379.10
	12/02/02	3424.25	44.94	3379.31
	01/30/03	3424.25	44.80	3379.45
	03/28/03	3424.25	44.96	3379.29
	05/19/03	3424.25	44.91	3379.34
	09/09/03	3424.25	44.89	3379.36
	12/02/03	3424.25	44.78	3379.47
	03/30/04	3424.25	45.01	3379.24
	06/07/04	3424.25	44.96	3379.29
	09/17/04	3424.25	44.80	3379.45
	11/30/04	3424.25	44.56	3379.69
	03/31/05	3424.25	44.06	3380.19
	05/23/05	3424.25	43.82	3380.43
	01/16/06	3424.25	43.42	3380.83
	06/16/06	3424.25	43.19	3381.06
MW014A	04/16/07	3424.25	42.81	3381.44
	09/20/07	3424.25	42.62	3381.63
	03/19/08	3424.25	42.68	3381.57
	08/04/08	3424.25	42.44	3381.81
	03/10/09	3424.25	43.05	3381.20
	07/29/09	3424.25	43.30	3380.95
	12/18/97	3423.93	45.93	3378.00
	11/16/99	3423.93	44.89	3379.01
	05/15/01	3423.93	44.40	3379.53
	08/23/01	3423.93	44.27	3379.66
	01/21/02	3423.93	44.25	3379.68
	04/05/02	3423.93	44.37	3379.56
	09/03/02	3423.93	44.20	3379.73
	12/02/02	3423.93	43.99	3379.94
	01/30/03	3423.93	43.95	3379.98
	03/28/03	3423.93	44.16	3379.77
	05/19/03	3423.93	44.01	3379.92
	09/09/03	3423.93	43.93	3380.00
	12/02/03	3423.93	43.96	3379.97
	03/30/04	3423.93	44.05	3379.88
	06/07/04	3423.93	43.98	3379.95
	09/16/04	3423.93	43.89	3380.04
MW015A	11/30/04	3423.93	43.71	3380.22
	03/31/05	3423.93	43.30	3380.63
	05/23/05	3423.93	43.04	3380.89
	01/17/06	3423.93	42.65	3381.28
	06/16/06	3423.93	42.49	3381.44
	03/21/07	3423.93	42.15	3381.78
	09/12/07	3423.93	41.92	3382.01
	03/18/08	3423.93	41.31	3382.62
	03/10/09	3423.93	42.33	3381.60
	07/28/09	3423.93	42.65	3381.28
	12/18/97	3420.55	42.50	3378.05
	11/16/99	3420.55	41.33	3379.22
	05/15/01	3420.55	40.69	3379.86
	08/23/01	3420.55	40.71	3379.84
	01/21/02	3420.55	40.72	3379.83
	04/04/02	3420.55	40.89	3379.66
	09/03/02	3420.55	40.66	3379.89
	12/02/02	3420.55	40.43	3380.12
	01/30/03	3420.55	40.30	3380.25
	03/28/03	3420.55	40.54	3380.01
	05/19/03	3420.55	40.52	3380.03
	09/08/03	3420.55	40.49	3380.06
	12/02/03	3420.55	40.42	3380.13
	03/30/04	3420.55	40.72	3379.83
	06/07/04	3420.55	40.61	3379.94
	09/16/04	3420.55	40.44	3380.11
	11/30/04	3420.55	40.21	3380.34
	03/31/05	3420.55	39.70	3380.85
	05/23/05	3420.55	39.50	3381.05
	01/17/06	3420.55	39.17	3381.38
	06/16/06	3420.55	39.03	3381.52
	03/22/07	3420.55	38.74	3381.81
	09/13/07	3420.55	38.42	3382.13
	03/18/08	3420.55	38.63	3381.92
	08/04/08	3420.55	38.91	3381.64
	03/10/09	3420.55	39.05	3381.50
	07/28/09	3420.55	39.28	3381.27

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW016A	12/18/97	3419.92	41.98	3377.94
	11/16/99	3419.92	40.80	3379.12
	05/15/01	3419.92	40.34	3379.58
	08/23/01	3419.92	40.21	3379.71
	01/21/02	3419.92	40.33	3379.59
	04/04/02	3419.92	40.51	3379.41
	09/03/02	3419.92	40.16	3379.76
	12/02/02	3419.92	39.90	3380.02
	01/30/03	3419.92	39.89	3380.03
	03/28/03	3419.92	40.05	3379.87
	05/19/03	3419.92	40.15	3379.77
	09/08/03	3419.92	40.11	3379.81
	12/02/03	3419.92	40.17	3379.75
	03/30/04	3419.92	40.43	3379.49
	06/07/04	3419.92	40.26	3379.66
	09/16/04	3419.92	39.98	3379.94
	11/30/04	3419.92	39.53	3380.39
	03/31/05	3419.92	39.05	3380.87
	05/23/05	3419.92	38.96	3380.96
	01/17/06	3419.92	38.53	3381.39
	06/16/06	3419.92	38.62	3381.30
	03/22/07	3419.92	38.32	3381.60
	09/12/07	3419.92	37.98	3381.94
	03/18/08	3419.92	38.29	3381.63
	08/04/08	3419.92	38.58	3381.34
	03/10/09	3419.92	38.75	3381.17
	07/28/09	3419.92	38.96	3380.96
MW017A	12/18/97	3424.38	46.05	3378.33
	11/16/99	3424.38	45.12	3379.26
	05/15/01	3424.38	44.53	3379.85
	08/23/01	3424.38	44.49	3379.89
	01/21/02	3424.38	44.42	3379.96
	04/04/02	3424.38	44.58	3379.80
	09/03/02	3424.38	44.38	3380.00
	12/02/02	3424.38	44.15	3380.23
	01/30/03	3424.38	44.10	3380.28
	03/28/03	3424.38	44.23	3380.15
	05/19/03	3424.38	44.19	3380.19
	09/08/03	3424.38	44.13	3380.25
	12/02/03	3424.38	44.07	3380.31
	03/30/04	3424.38	44.26	3380.12
	06/07/04	3424.38	44.21	3380.17
	09/16/04	3424.38	44.14	3380.24
	11/30/04	3424.38	43.89	3380.49
	03/31/05	3424.38	43.44	3380.94
	05/23/05	3424.28	43.24	3381.04
	01/17/06	3424.28	42.80	3381.48
	06/16/06	3424.28	42.69	3381.59
	03/21/07	3424.28	42.42	3381.86
	09/13/07	3424.28	42.13	3382.15
	03/21/08	3424.28	42.42	3381.86
	09/13/08	3424.28	42.13	3382.15
Plugged and Abandoned				
MW018A	12/18/97	3416.86	39.16	3377.70
	11/16/99	3416.86	37.52	3379.34
	05/15/01	3416.86	37.62	3379.24
	08/23/01	3416.86	37.55	3379.31
	01/21/02	3416.86	37.62	3379.24
	04/04/02	3416.86	37.89	3378.97
	09/03/02	3416.86	37.03	3379.83
	12/02/02	3416.86	37.01	3379.85
	01/30/03	3416.86	37.12	3379.74
	03/28/03	3416.86	37.38	3379.48
	05/19/03	3416.86	37.54	3379.32
	09/08/03	3416.86	37.51	3379.35
	12/02/03	3416.86	37.65	3379.21
	03/30/04	3416.86	38.01	3378.85
	06/07/04	3416.86	37.56	3379.30
	09/16/04	3416.86	37.20	3379.66
	11/29/04	3416.86	36.11	3380.75
	03/31/05	3416.86	35.99	3380.87
	05/23/05	3416.86	35.86	3381.00
	01/17/06	3416.86	35.78	3381.08
	06/16/06	3416.86	36.01	3380.85
	04/02/07	3416.86	35.65	3381.21
	09/12/07	3416.86	35.51	3381.35
	03/18/08	3416.86	35.88	3380.98
	03/10/09	3416.86	36.29	3380.57
	07/28/09	3416.86	36.49	3380.37

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW019A	12/18/97	3414.74	39.83	3374.91
	11/16/99	3414.74	38.12	3376.62
	05/15/01	3414.74	38.02	3376.72
	08/23/01	3414.74	37.62	3377.12
	01/21/02	3414.74	37.92	3376.82
	04/04/02	3414.74	38.15	3376.59
	09/03/02	3414.74	37.40	3377.34
	12/02/02	3414.74	37.46	3377.28
	01/30/03	3414.74	37.61	3377.13
	03/28/03	3414.74	37.79	3376.95
	05/19/03	3414.74	37.91	3376.83
	09/08/03	3414.74	38.06	3376.68
	12/02/03	3414.74	38.22	3376.52
	03/30/04	3414.74	38.41	3376.33
	06/07/04	3414.74	37.93	3376.81
	09/16/04	3414.74	37.82	3376.92
	11/29/04	3414.74	36.70	3378.04
	03/31/05	3414.74	36.35	3378.39
	05/23/05	3414.74	36.62	3378.12
	01/17/06	3414.74	36.37	3378.37
	06/16/06	3414.74	36.61	3378.13
	04/04/07	3414.74	36.30	3378.44
	09/13/07	3414.74	35.96	3378.78
	03/18/08	3414.74	36.50	3378.24
	08/04/08	3414.74	36.82	3377.92
	03/10/09	3414.74	36.74	3378.00
	07/28/09	3414.74	37.00	3377.74
MW020A	11/16/99	3421.14	44.70	3376.44
	02/06/02	3421.14	44.14	3377.00
	09/03/02	3421.14	43.98	3377.16
	12/09/02	3421.14	44.06	3377.08
	01/30/03	3421.14	43.98	3377.16
	03/28/03	3421.14	44.05	3377.09
	06/05/03	3421.14	44.44	3376.70
	01/22/04	3421.14	44.68	3376.46
	03/30/04	3421.14	44.59	3376.55
	06/07/04	3421.14	44.33	3376.81
	09/17/04	3421.14	44.15	3376.99
	11/29/04	3421.14	43.75	3377.39
	04/01/05	3421.14	43.24	3377.90
	05/23/05	3421.14	43.16	3377.98
	01/17/06	3421.14	42.87	3378.27
	06/16/06	3421.14	42.74	3378.40
	04/04/07	3421.14	42.40	3378.74
	03/18/08	3421.14	42.41	3378.73
	08/04/08	3421.14	42.76	3378.38
	03/10/09	3421.14	42.85	3378.29
	07/28/09	3421.14	43.08	3378.06
MW021A	11/16/99	3422.94	48.41	3374.53
	05/15/01	3422.94	47.57	3375.37
	08/23/01	3422.94	47.98	3374.96
	01/21/02	3422.94	47.83	3375.11
	04/04/02	3422.94	47.98	3374.96
	09/03/02	3422.94	48.07	3374.87
	12/02/02	3422.94	47.63	3375.31
	01/30/03	3422.94	47.61	3375.33
	03/28/03	3422.94	47.71	3375.23
	05/19/03	3422.94	47.96	3374.98
	09/08/03	3422.94	48.01	3374.93
	01/21/04	3422.94	48.73	3374.21
	03/30/04	3422.94	47.94	3375.00
	06/07/04	3422.94	48.28	3374.66
	09/14/04	3422.94	47.95	3374.99
	11/29/04	3422.94	47.35	3375.59
	03/31/05	3422.94	46.93	3376.01
	05/23/05	3422.94	47.04	3375.90
	01/18/06	3422.94	46.34	3376.60
	06/14/06	3422.94	46.35	3376.59
	04/09/07	3422.94	45.80	3377.14
	09/18/07	3422.94	45.09	3377.85
	03/19/08	3422.94	45.08	3377.86
	8/4/080	3422.94	45.49	3377.45
	03/10/09	3422.94	46.28	3376.66
	07/28/09	3422.94	46.46	3376.48

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW022A	11/16/99	3431.13	57.29	3373.84
	05/15/01	3431.13	53.35	3377.78
	08/23/01	3431.13	53.96	3377.17
	01/21/02	3431.13	53.75	3377.38
	04/04/02	3431.13	66.00	3365.13
	09/03/02	3431.13	52.96	3378.17
	12/02/02	3431.13	52.95	3378.18
	01/31/03	3431.13	53.25	3377.88
	03/28/03	3431.13	53.58	3377.55
	05/19/03	3431.13	53.26	3377.87
	09/09/03	3431.13	66.99	3364.14
	12/03/03	3431.13	66.97	3364.16
	03/30/04	3431.13	64.08	3367.05
	06/07/04	3431.13	61.36	3369.77
	09/17/04	3431.13	53.22	3377.91
	11/30/04	3431.13	54.56	3376.57
	03/31/05	3431.13	52.44	3378.69
	05/23/05	3431.13	52.30	3378.83
	01/16/06	3431.13	52.56	3378.57
	06/19/06	3431.13	47.04	3384.09
	03/30/07	3431.13	50.80	3380.33
MW023A	09/13/07	3431.13	50.84	3380.29
	03/18/08	3431.13	50.78	3380.35
	08/04/08	3431.13	51.02	3380.11
	03/10/09	3431.13	51.09	3380.04
	07/28/09	3431.13	51.20	3379.93
	01/09/03	3436.26	57.70	3378.56
	01/30/03	3436.26	57.23	3379.03
	03/28/03	3436.26	57.33	3378.93
	05/19/03	3436.26	57.25	3379.01
	09/09/03	3436.26	53.23	3383.03
	12/02/03	3436.26	57.23	3379.03
	03/30/04	3436.26	57.25	3379.01
	06/07/04	3436.26	57.35	3378.91
	09/17/04	3436.26	57.14	3379.12
	11/30/04	3436.26	57.11	3379.15
	03/31/05	3436.26	56.62	3379.64
	05/23/05	3436.26	56.46	3379.80
	01/17/06	3436.26	56.09	3380.17
	06/14/06	3436.26	55.80	3380.46
	03/29/07	3436.26	53.38	3382.88
MW024A	09/11/07	3436.26	55.29	3380.97
	03/18/08	3436.26	55.11	3381.15
	08/04/08	3436.26	55.18	3381.08
	03/10/09	3436.26	55.22	3381.04
	07/28/09	3436.26	55.32	3380.94
	11/16/99	3430.77	54.30	3376.47
	05/15/01	3430.77	53.32	3377.45
	08/23/01	3430.77	53.86	3376.91
	02/06/02	3430.77	53.42	3377.35
	09/03/02	3430.77	53.26	3377.51
	12/02/02	3430.77	53.03	3377.74
	01/29/03	3430.77	53.11	3377.66
	03/27/03	3430.77	53.31	3377.46
	05/19/03	3430.77	53.22	3377.55
	09/09/03	3430.77	53.73	3377.04
	12/02/03	3430.77	53.69	3377.08
	03/30/04	3430.77	53.87	3376.90
	06/07/04	3430.77	53.89	3376.88
	09/16/04	3430.77	53.11	3377.66
	11/29/04	3430.77	53.04	3377.73
	03/31/05	3430.77	52.50	3378.27
	05/23/05	3430.77	52.26	3378.51
	01/17/06	3430.77	51.43	3379.34
	06/14/06	3430.77	50.90	3379.87
	04/11/07	3430.77	50.82	3379.95
	09/18/07	3430.77	50.88	3379.89
	03/19/08	3430.77	50.88	3379.89
	08/04/08	3430.77	50.98	3379.79
	03/11/09	3430.77	51.15	3379.62
	07/29/09	3430.77	51.17	3379.60

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW039A	08/23/01	3435.71	57.85	3377.86
	01/21/02	3435.71	57.62	3378.09
	04/04/02	3435.71	57.71	3378.00
	09/03/02	3435.71	57.47	3378.24
	12/02/02	3435.71	57.20	3378.51
	01/30/03	3435.71	57.20	3378.51
	03/28/03	3435.71	57.40	3378.31
	05/19/03	3435.71	57.27	3378.44
	09/09/03	3435.71	57.43	3378.28
	12/02/03	3435.71	57.32	3378.39
	03/30/04	3435.71	57.43	3378.28
	06/07/04	3435.71	57.52	3378.19
	09/17/04	3435.71	57.22	3378.49
	11/30/04	3435.71	57.00	3378.71
	03/31/05	3435.71	56.54	3379.17
	05/23/05	3435.71	56.29	3379.42
	01/16/06	3435.71	55.75	3379.96
	06/19/06	3435.71	55.41	3380.30
MW040A	04/04/02	3422.92	43.70	3379.22
	09/03/02	3422.92	43.90	3379.02
	12/02/02	3422.92	43.71	3379.21
	01/31/03	3422.92	43.71	3379.21
	03/28/03	3422.92	43.71	3379.21
	05/19/03	3422.92	43.69	3379.23
	09/09/03	3422.92	43.69	3379.23
	12/02/03	3422.92	43.68	3379.24
	03/30/04	3422.92	43.84	3379.08
	06/07/04	3422.92	43.97	3378.95
	09/17/04	3422.92	43.70	3379.22
	11/30/04	3422.92	43.29	3379.63
	03/31/05	3422.92	32.79	3390.13
	05/23/05	3422.92	42.55	3380.37
	01/16/06	3422.92	42.40	3380.52
	06/16/06	3422.92	42.10	3380.82
	04/02/07	3422.92	41.61	3381.31
	09/11/07	3422.92	41.73	3381.19
MW041A	04/25/02	3418.42	43.22	3375.20
	05/07/02	3418.42	43.12	3375.30
	09/03/02	3418.42	43.30	3375.12
	12/02/02	3418.42	43.04	3375.38
	01/30/03	3418.42	43.19	3375.23
	03/28/03	3418.42	43.01	3375.41
	05/19/03	3418.42	43.08	3375.34
	09/08/03	3418.42	43.23	3375.19
	12/02/03	3418.42	43.23	3375.19
	03/30/04	3418.42	43.38	3375.04
	06/07/04	3418.42	43.33	3375.09
	09/16/04	3418.42	43.24	3375.18
	11/29/04	3418.42	42.97	3375.45
	03/31/05	3418.42	42.49	3375.93
	05/23/05	3418.42	42.35	3376.07
	01/17/06	3418.42	41.90	3376.52
	06/16/06	3418.42	41.57	3376.85
	04/17/07	3418.42	41.25	3377.17
MW042A	03/19/08	3418.42	41.20	3377.22
	03/11/09	3418.42	41.70	3376.72
	08/23/01	3424.75	46.26	3378.49
	01/21/02	3424.75	48.30	3376.45
	04/04/02	3424.75	48.17	3376.58
	09/03/02	3424.75	47.86	3376.89
	12/02/02	3424.75	47.75	3377.00
	01/31/03	3424.75	47.65	3377.10
	03/28/03	3424.75	47.84	3376.91
	05/19/03	3424.75	47.84	3376.91
	09/09/03	3424.75	48.04	3376.71
	12/03/03	3424.75	48.00	3376.75
	03/30/04	3424.75	48.31	3376.44
	06/07/04	3424.75	48.42	3376.33
	09/17/04	3424.75	48.58	3376.17
	11/29/04	3424.75	47.24	3377.51
	03/31/05	3424.75	47.30	3377.45
	05/23/05	3424.75	47.05	3377.70
	01/17/06	3424.75	46.02	3378.73
MW042A	06/19/06	3424.75	45.90	3378.85
	04/17/07	3424.75	45.59	3379.16
	03/19/08	3424.75	45.71	3379.04
	03/11/09	3424.75	46.15	3378.60

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW046A	01/07/03	3426.45	50.09	3376.36
	01/31/03	3426.45	48.81	3377.64
	03/28/03	3426.45	49.06	3377.39
	05/19/03	3426.45	48.88	3377.57
	09/09/03	3426.45	50.48	3375.97
	12/03/03	3426.45	50.54	3375.91
	03/30/04	3426.45	50.33	3376.12
	06/07/04	3426.45	50.20	3376.25
	09/17/04	3426.45	48.83	3377.62
	11/30/04	3426.45	48.66	3377.79
	03/31/05	3426.45	47.92	3378.53
	05/23/05	3426.45	47.75	3378.70
	01/17/06	3426.45	46.55	3379.90
	06/19/06	3426.45	46.12	3380.33
	04/17/07	3426.45	46.35	3380.10
MW048SA	03/19/08	3426.45	46.39	3380.06
	03/11/09	3426.45	46.78	3379.67
MW048SA	08/01/02	3421.10	46.45	3374.65
	09/03/02	3421.10	46.40	3374.70
	12/02/02	3421.10	46.26	3374.84
	01/30/03	3421.10	46.18	3374.92
	03/28/03	3421.10	46.15	3374.95
	05/19/03	3421.10	46.19	3374.91
	09/08/03	3421.10	46.44	3374.66
	12/02/03	3421.10	46.45	3374.65
	03/30/04	3421.10	46.62	3374.48
	06/07/04	3421.10	46.48	3374.62
	09/16/04	3421.10	46.43	3374.67
	11/29/04	3421.10	46.17	3374.93
	03/31/05	3421.10	45.67	3375.43
	05/23/05	3421.10	45.52	3375.58
	01/17/06	3421.10	45.11	3375.99
	06/16/06	3421.10	44.96	3376.14
	04/10/07	3421.10	44.62	3376.48
	09/19/07	3421.10	44.49	3376.61
MW049SA	03/19/08	3421.10	44.60	3376.50
	08/04/08	3421.10	44.94	3376.16
	03/11/09	3421.10	45.02	3376.08
	07/29/09	3421.10	45.26	3375.84
MW049SA	07/30/02	3422.46	49.31	3373.15
	09/03/02	3422.46	49.29	3373.17
	12/02/02	3422.46	49.18	3373.28
	01/30/03	3422.46	49.13	3373.33
	03/28/03	3422.46	49.09	3373.37
	05/19/03	3422.46	49.08	3373.38
	09/08/03	3422.46	49.32	3373.14
	12/02/03	3422.46	49.32	3373.14
	03/30/04	3422.46	49.42	3373.04
	06/07/04	3422.46	48.57	3373.89
	09/16/04	3422.46	49.36	3373.10
	11/29/04	3422.46	49.16	3373.30
	03/31/05	3422.46	48.65	3373.81
	05/23/05	3422.46	48.59	3373.87
	01/17/06	3422.46	48.19	3374.27
	06/16/06	3422.46	47.97	3374.49
	04/10/07	3422.46	47.62	3374.84
	03/19/08	3422.46	47.53	3374.93
	03/11/09	3422.46	47.95	3374.51
MW050SA	07/30/02	3419.31	46.30	3373.01
	09/03/02	3419.31	46.19	3373.12
	12/02/02	3419.31	45.93	3373.38
	01/30/03	3419.31	45.92	3373.39
	03/28/03	3419.31	45.92	3373.39
	05/19/03	3419.31	46.01	3373.30
	09/08/03	3419.31	46.13	3373.18
	12/02/03	3419.31	46.05	3373.26
	03/30/04	3419.31	46.15	3373.16
	06/07/04	3419.31	46.18	3373.13
	09/14/04	3419.31	46.18	3373.13
	11/29/04	3419.31	45.80	3373.51
	03/31/05	3419.31	45.34	3373.97
	05/23/05	3419.31	45.26	3374.05
	01/17/06	3419.31	44.95	3374.36
	06/14/06	3419.31	44.71	3374.60
	04/09/07	3419.31	44.28	3375.03
	03/19/08	3419.31	44.25	3375.06
	03/11/09	3419.31	44.78	3374.53

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW051SA	10/10/02	3415.42	44.50	3370.92
	12/02/02	3415.42	44.43	3370.99
	01/30/03	3415.42	44.38	3371.04
	03/28/03	3415.42	44.39	3371.03
	05/19/03	3415.42	44.40	3371.02
	09/08/03	3415.42	44.55	3370.87
	12/02/03	3415.42	44.53	3370.89
	03/30/04	3415.42	44.59	3370.83
	06/07/04	3415.42	44.53	3370.89
	09/14/04	3415.42	44.58	3370.84
	03/31/05	3415.42	44.04	3371.38
	05/23/05	3415.42	43.95	3371.47
	01/17/06	3415.42	43.70	3371.72
	06/15/06	3415.42	43.47	3371.95
	04/17/07	3415.42	43.09	3372.33
MW052SA	03/19/08	3415.42	43.04	3372.38
	03/11/09	3415.42	43.48	3371.94
MW052SA	10/10/02	3415.23	45.45	3369.78
	12/02/02	3415.23	45.39	3369.84
	01/30/03	3415.23	45.35	3369.88
	03/28/03	3415.23	45.36	3369.87
	05/19/03	3415.23	45.28	3369.95
	09/08/03	3415.23	45.51	3369.72
	12/02/03	3415.23	45.52	3369.71
	03/30/04	3415.23	45.58	3369.65
	06/07/04	3415.23	45.85	3369.38
	09/14/04	3415.23	45.58	3369.65
	11/29/04	3415.23	45.43	3369.80
	03/31/05	3415.23	45.05	3370.18
	05/23/05	3415.23	45.02	3370.21
	01/17/06	3415.23	44.72	3370.51
	06/16/06	3415.23	44.59	3370.64
MW053SA	04/10/07	3415.23	44.34	3370.89
	03/19/08	3415.23	44.24	3370.99
	03/11/09	3415.23	44.54	3370.69
MW053SA	09/18/02	3413.86	42.93	3370.93
	12/02/02	3413.86	42.80	3371.06
	01/30/03	3413.86	42.68	3371.18
	03/28/03	3413.86	42.68	3371.18
	05/19/03	3413.86	42.65	3371.21
	09/08/03	3413.86	43.09	3370.77
	12/02/03	3413.86	43.12	3370.74
	03/30/04	3413.86	43.15	3370.71
	06/07/04	3413.86	43.04	3370.82
	09/16/04	3413.86	43.09	3370.77
	11/29/04	3413.86	42.74	3371.12
	03/31/05	3413.86	42.13	3371.73
	05/23/05	3413.86	41.97	3371.89
	01/17/06	3413.86	41.61	3372.25
	06/16/06	3413.86	41.67	3372.19
MW054SA	04/05/07	3413.86	41.32	3372.54
	09/19/07	3413.86	41.20	3372.66
	03/18/08	3413.86	41.30	3372.56
	08/04/08	3413.86	41.76	3372.10
	03/10/09	3413.86	41.60	3372.26
	07/28/09	3413.86	41.97	3371.89
MW054SA	01/30/03	3411.38	45.21	3366.17
	03/28/03	3411.38	45.09	3366.29
	05/19/03	3411.38	45.09	3366.29
	09/08/03	3411.38	45.43	3365.95
	12/02/03	3411.38	45.41	3365.97
	03/30/04	3411.38	45.46	3365.92
	06/07/04	3411.38	45.37	3366.01
	09/14/04	3411.38	42.48	3368.90
	11/29/04	3411.38	45.26	3366.12
	03/31/05	3411.38	44.90	3366.48
	05/23/05	3411.38	44.81	3366.57
	01/17/06	3411.38	44.68	3366.70
	06/16/06	3411.38	44.73	3366.65
	04/10/07	3411.38	44.57	3366.81
	09/19/07	3411.38	44.63	3366.75
	03/19/08	3411.38	44.59	3366.79
	08/04/08	3411.38	44.84	3366.54
	03/11/09	3411.38	44.74	3366.64
	07/29/09	3411.38	44.93	3366.45

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW055SA	01/06/03	3407.43	41.20	3366.23
	01/30/03	3407.43	41.00	3366.43
	03/27/03	3407.43	41.15	3366.28
	05/19/03	3407.43	41.00	3366.43
	09/08/03	3407.43	41.13	3366.30
	12/02/03	3407.43	41.09	3366.34
	03/30/04	3407.43	41.12	3366.31
	06/07/04	3407.43	41.02	3366.41
	09/14/04	3407.43	41.18	3366.25
	11/29/04	3407.43	41.08	3366.35
	03/31/05	3407.43	40.90	3366.53
	05/23/05	3407.43	40.82	3366.61
	01/17/06	3407.43	40.76	3366.67
	06/15/06	3407.43	40.68	3366.75
	04/10/07	3407.43	40.63	3366.80
	09/19/07	3407.43	40.56	3366.87
	03/19/08	3407.43	40.68	3366.75
	08/04/08	3407.43	40.75	3366.68
	03/11/09	3407.43	40.79	3366.64
	07/29/09	3407.43	40.85	3366.58
MW056SA	01/07/03	3410.71	46.32	3364.39
	01/30/03	3410.71	46.21	3364.50
	03/28/03	3410.71	46.20	3364.51
	05/19/03	3410.71	46.18	3364.53
	09/08/03	3410.71	46.31	3364.40
	12/02/03	3410.71	46.33	3364.38
	03/30/04	3410.71	46.40	3364.31
	06/07/04	3410.71	46.31	3364.40
	09/14/04	3410.71	46.38	3364.33
	11/29/04	3410.71	46.31	3364.40
	03/31/05	3410.71	46.01	3364.70
	05/23/05	3410.71	45.93	3364.78
	01/17/06	3410.71	45.62	3365.09
	06/15/06	3410.71	45.42	3365.29
	04/11/07	3410.71	44.91	3365.80
	09/20/07	3410.71	44.67	3366.04
	03/19/08	3410.71	44.69	3366.02
	08/04/08	3410.71	44.79	3365.92
	03/11/09	3410.71	44.92	3365.79
	07/29/09	3410.71	44.93	3365.78
MW057SA	01/30/03	3417.74	46.33	3371.41
	03/28/03	3417.74	46.45	3371.29
	05/19/03	3417.74	46.59	3371.15
	09/08/03	3417.74	46.72	3371.02
	12/02/03	3417.74	46.65	3371.09
	03/30/04	3417.74	46.70	3371.04
	06/07/04	3417.74	46.75	3370.99
	09/14/04	3417.74	46.58	3371.16
	11/30/04	3417.74	46.00	3371.74
	03/31/05	3417.74	45.77	3371.97
	05/23/05	3417.74	45.73	3372.01
	01/17/06	3417.74	45.53	3372.21
	06/14/06	3417.74	45.50	3372.24
	03/29/07	3417.74	44.91	3372.83
	09/11/07	3417.74	44.96	3372.78
	03/18/08	3417.74	45.05	3372.69
	08/04/08	3417.74	45.34	3372.40
	03/10/09	3417.74	45.58	3372.16
	07/28/09	3417.74	45.58	3372.16
MW062A	01/31/03	3434.19	57.13	3377.06
	03/27/03	3434.19	57.16	3377.03
	05/19/03	3434.19	57.19	3377.00
	09/09/03	3434.19	57.29	3376.90
	12/02/03	3434.19	57.17	3377.02
	03/30/04	3434.19	57.35	3376.84
	06/07/04	3434.19	57.40	3376.79
	09/16/04	3434.19	57.18	3377.01
	11/29/04	3434.19	57.08	3377.11
	03/31/05	3434.19	56.64	3377.55
	05/23/05	3434.19	56.51	3377.68
	01/17/06	3434.19	55.93	3378.26
	06/14/06	3434.19	55.52	3378.67
	04/20/07	3434.19	55.17	3379.02
	09/13/07	3434.19	55.17	3379.02
	03/18/08	3434.19	55.13	3379.06
	08/04/08	3434.19	55.25	3378.94
	03/11/09	3434.19	55.39	3378.80
	07/28/09	3434.19	55.45	3378.74

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW063A	01/31/03	3435.22	57.89	3377.33
	03/27/03	3435.22	57.80	3377.42
	05/19/03	3435.22	57.82	3377.40
	09/09/03	3435.22	57.89	3377.33
	12/02/03	3435.22	57.78	3377.44
	03/30/04	3435.22	57.97	3377.25
	06/07/04	3435.22	57.93	3377.29
	09/16/04	3435.22	57.81	3377.41
	11/29/04	3435.22	57.78	3377.44
	03/31/05	3435.22	54.53	3380.69
	05/23/05	3435.22	57.20	3378.02
	01/17/06	3435.22	56.80	3378.42
	06/14/06	3435.22	56.44	3378.78
	04/20/07	3435.22	56.02	3379.20
	09/10/07	3435.22	55.92	3379.30
	03/18/08	3435.22	55.89	3379.33
	08/04/08	3435.22	55.98	3379.24
	03/11/09	3435.22	56.02	3379.20
	07/28/09	3435.22	56.05	3379.17
MW064SA	03/27/03	3405.15	54.20	3350.95
	05/19/03	3405.15	54.22	3350.93
	09/08/03	3405.15	54.27	3350.88
	12/02/03	3405.15	54.35	3350.80
	03/30/04	3405.15	54.39	3350.76
	06/07/04	3405.15	54.40	3350.75
	09/14/04	3405.15	54.36	3350.79
	11/29/04	3405.15	54.24	3350.91
	03/24/05	3405.15	54.91	3350.24
	05/23/05	3405.15	53.69	3351.46
	01/17/06	3405.15	53.09	3352.06
	06/14/06	3405.15	52.67	3352.48
	03/21/07	3405.15	NM	NM
	09/05/07	3405.15	51.52	3353.63
	03/19/08	3405.15	51.21	3353.94
	08/04/08	3405.15	51.11	3354.04
	03/11/09	3405.15	51.16	3353.99
	07/29/09	3405.15	51.05	3354.10
MW065SA	03/27/03	3402.96	54.21	3348.75
	05/19/03	3402.96	54.23	3348.73
	09/08/03	3402.96	54.38	3348.58
	12/02/03	3402.96	54.51	3348.45
	03/30/04	3402.96	54.61	3348.35
	06/07/04	3402.96	54.32	3348.64
	09/14/04	3402.96	54.45	3348.51
	11/30/04	3402.96	54.31	3348.65
	03/31/05	3402.96	53.92	3349.04
	05/23/05	3402.96	53.66	3349.30
	01/17/06	3402.96	52.99	3349.97
	06/15/06	3402.96	52.62	3350.34
	04/10/07	3402.96	52.12	3350.84
	09/11/07	3402.96	51.59	3351.37
	03/19/08	3402.96	51.39	3351.57
	08/04/08	3402.96	51.30	3351.66
	03/11/09	3402.96	51.52	3351.44
	07/29/09	3402.96	51.32	3351.64
MW066SA	03/28/03	3404.03	52.45	3351.58
	05/19/03	3404.03	52.24	3351.79
	09/08/03	3404.03	52.71	3351.32
	12/02/03	3404.03	53.00	3351.03
	03/30/04	3404.03	53.16	3350.87
	06/07/04	3404.03	52.88	3351.15
	09/14/04	3404.03	55.30	3348.73
	11/29/04	3404.03	53.24	3350.79
	03/29/05	3404.03	52.71	3351.32
	05/23/05	3404.03	52.36	3351.67
	01/17/06	3404.03	51.15	3352.88
	06/15/06	3404.03	50.35	3353.68
	Date Missing	3404.03	49.45	3354.58
	09/19/07	3404.03	48.63	3355.40
	03/18/08	3404.03	48.25	3355.78
	08/04/08	3404.03	48.99	3355.04
	03/10/09	3404.03	49.00	3355.03
	07/29/09	3404.03	49.32	3354.71
MW067SA	03/28/03	3409.16	47.64	3361.52
	05/19/03	3409.16	47.61	3361.55
	09/08/03	3409.16	48.19	3360.97
	12/02/03	3409.16	48.25	3360.91
	03/30/04	3409.16	48.34	3360.82
	06/07/04	3409.16	48.10	3361.06
	09/14/04	3409.16	48.26	3360.90
	01/17/06	3409.16	45.90	3363.26
	06/16/06	3409.16	46.02	3363.14
	04/05/07	3409.16	45.46	3363.70
	09/12/07	3409.16	45.38	3363.78
	03/18/08	3409.16	45.34	3363.82
	08/04/08	3409.16	46.06	3363.10
	03/10/09	3409.16	45.81	3363.35
	07/28/09	3409.16	46.35	3362.81

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW070A	03/27/03	3439.67	61.08	3378.59
	05/19/03	3439.67	61.06	3378.61
	09/09/03	3439.67	61.05	3378.62
	12/02/03	3439.67	60.96	3378.71
	03/30/04	3439.67	60.96	3378.71
	06/07/04	3439.67	60.98	3378.69
	09/16/04	3439.67	60.98	3378.69
	11/30/04	3439.67	60.88	3378.79
	03/31/05	3439.67	60.68	3378.99
	05/23/05	3439.67	60.49	3379.18
	01/17/06	3439.67	60.14	3379.53
	06/14/06	3439.67	59.92	3379.75
	03/29/07	3439.67	59.45	3380.22
	09/11/07	3439.67	59.30	3380.37
	03/18/08	3439.67	59.09	3380.58
	08/04/08	3439.67	59.06	3380.61
	03/10/09	3439.67	59.11	3380.56
	07/28/09	3439.67	59.14	3380.53
MW071SA	05/02/03	3401.01	34.79	3366.22
	05/19/03	3401.01	52.61	3348.40
	09/08/03	3401.01	52.83	3348.18
	12/02/03	3401.01	52.98	3348.03
	03/30/04	3401.01	53.03	3347.98
	06/07/04	3401.01	52.78	3348.23
	09/14/04	3401.01	53.00	3348.01
	11/29/04	3401.01	53.71	3347.30
	03/31/05	3401.01	57.12	3343.89
	05/23/05	3401.01	51.90	3349.11
	01/17/06	3401.01	51.25	3349.76
	06/15/06	3401.01	50.95	3350.06
	04/03/07	3401.01	50.47	3350.54
	09/18/07	3401.01	49.94	3351.07
	03/18/08	3401.01	49.73	3351.28
	08/04/08	3401.01	49.87	3351.14
	03/10/09	3401.01	49.92	3351.09
	07/28/09	3401.01	49.83	3351.18
MW072SA	05/01/03	3401.34	53.46	3347.88
	05/19/03	3401.34	52.96	3348.38
	09/08/03	3401.34	53.24	3348.10
	12/02/03	3401.34	53.35	3347.99
	03/30/04	3401.34	53.49	3347.85
	06/07/04	3401.34	53.18	3348.16
	09/14/04	3401.34	53.39	3347.95
	11/29/04	3401.34	53.06	3348.28
	03/29/05	3401.34	52.39	3348.95
	05/23/05	3401.34	52.14	3349.20
	01/17/06	3401.34	51.49	3349.85
	06/15/06	3401.34	51.25	3350.09
	04/03/07	3401.34	50.78	3350.56
	09/13/07	3401.34	50.20	3351.14
	03/18/08	3401.34	50.06	3351.28
	08/04/08	3401.34	50.29	3351.05
	03/10/09	3401.34	50.44	3350.90
	07/28/09	3401.34	50.24	3351.10
MW073SA	05/03/03	3403.26	50.25	3353.01
	05/19/03	3403.26	50.21	3353.05
	09/08/03	3403.26	50.61	3352.65
	12/02/03	3403.26	50.74	3352.52
	03/30/04	3403.26	50.86	3352.40
	06/07/04	3403.26	50.58	3352.68
	09/14/04	3403.26	50.76	3352.50
	11/29/04	3403.26	50.40	3352.86
	03/31/05	3403.26	49.65	3353.61
	05/23/05	3403.26	49.38	3353.88
	01/17/06	3403.26	48.68	3354.58
	06/15/06	3403.26	48.52	3354.74
	04/03/07	3403.26	48.01	3355.25
	09/12/07	3403.26	47.55	3355.71
	03/18/08	3403.26	47.45	3355.81
	08/04/08	3403.26	47.78	3355.48
	03/10/09	3403.26	47.89	3355.37
	07/28/09	3403.26	47.97	3355.29
MW074SA	02/18/04	3409.97	50.22	3359.75
	03/30/04	3409.97	50.24	3359.73
	06/07/04	3409.97	50.15	3359.82
	09/14/04	3409.97	50.22	3359.75
	11/29/04	3409.97	NR	NR
	3/31/005	3409.97	49.79	3360.18
	05/23/05	3409.97	49.69	3360.28
	01/17/06	3409.97	49.31	3360.66
	06/15/06	3409.97	49.02	3360.95
	04/03/07	3409.97	48.39	3361.58
	09/05/07	3409.97	48.10	3361.87
	03/18/08	3409.97	48.03	3361.94
	08/04/08	3409.97	48.07	3361.90
	03/10/09	3409.97	48.18	3361.79
	07/28/09	3409.97	48.14	3361.83

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW075SA	02/18/04	3404.21	54.19	3350.02
	03/30/04	3404.21	54.21	3350.00
	06/07/04	3404.21	54.11	3350.10
	09/14/04	3404.21	54.08	3350.13
	11/29/04	3404.21	54.04	3350.17
	03/31/05	3404.21	53.69	3350.52
	05/23/05	3404.21	53.49	3350.72
	01/17/06	3404.21	52.89	3351.32
	06/15/06	3404.21	52.44	3351.77
	04/03/07	3404.21	51.86	3352.35
	09/05/07	3404.21	51.38	3352.83
	03/18/08	3404.21	51.07	3353.14
	08/04/08	3404.21	50.91	3353.30
	03/10/09	3404.21	50.93	3353.28
	07/28/09	3404.21	50.80	3353.41
MW076SA	02/18/04	3404.13	55.72	3348.41
	03/29/04	3404.13	55.77	3348.36
	06/07/04	3404.13	55.62	3348.51
	09/14/04	3404.13	55.64	3348.49
	11/29/04	3404.13	55.54	3348.59
	03/31/05	3404.13	55.17	3348.96
	05/23/05	3404.13	54.94	3349.19
	01/17/06	3404.13	54.39	3349.74
	06/15/06	3404.13	53.95	3350.18
	04/03/07	3404.13	53.01	3351.12
	03/18/08	3404.13	52.76	3351.37
	08/04/08	3404.13	52.60	3351.53
	03/10/09	3404.13	52.61	3351.52
	07/28/09	3404.13	52.45	3351.68
MW077SA	02/18/04	3401.71	53.71	3348.00
	03/30/04	3401.71	53.72	3347.99
	06/07/04	3401.71	53.49	3348.22
	09/14/04	3401.71	53.56	3348.15
	03/31/05	3401.71	52.99	3348.72
	05/23/05	3401.71	52.77	3348.94
	01/17/06	3401.71	57.13	3344.58
	06/15/06	3401.71	51.79	3349.92
	04/11/07	3401.71	51.34	3350.37
	09/06/07	3401.71	50.82	3350.89
	03/19/08	3401.71	50.62	3351.09
	08/04/08	3401.71	50.56	3351.15
	03/11/09	3401.71	50.71	3351.00
	07/29/09	3401.71	50.49	3351.22
MW078SA	03/30/04	3411.12	44.63	3366.49
	06/07/04	3411.12	45.45	3365.67
	09/16/04	3411.12	45.72	3365.40
	11/29/04	3411.12	45.18	3365.94
	03/31/05	3411.12	44.30	3366.82
	05/23/05	3411.12	44.08	3367.04
	01/17/06	3411.12	43.64	3367.48
	06/16/06	3411.12	43.97	3367.15
	04/05/07	3411.12	43.42	3367.70
	09/06/07	3411.12	43.47	3367.65
	03/18/08	3411.12	43.49	3367.63
	08/04/08	3411.12	44.70	3366.42
	03/10/09	3411.12	43.47	3367.65
	07/28/09	3411.12	44.50	3366.62
MW079SA	03/30/04	3408.80	48.78	3360.02
	06/07/04	3408.80	46.61	3362.19
	09/14/04	3408.80	48.73	3360.07
	11/29/04	3408.80	46.27	3362.53
	05/23/05	3408.80	47.09	3361.71
	01/17/06	3408.80	46.31	3362.49
	06/16/06	3408.80	46.33	3362.47
	03/28/07	3408.80	45.81	3362.99
	09/06/07	3408.80	45.68	3363.12
	03/21/08	3408.80	45.54	3363.26
	08/04/08	3408.80	46.31	3362.49
	03/11/09	3408.80	46.03	3362.77
	07/29/09	3408.80	46.55	3362.25
MW080SA	03/30/04	3408.92	48.82	3360.10
	06/07/04	3408.92	48.70	3360.22
	09/14/04	3408.92	48.81	3360.11
	11/29/04	3408.92	48.36	3360.56
	03/31/05	3408.92	47.56	3361.36
	05/23/05	3408.92	48.18	3360.74
	01/17/06	3408.92	46.42	3362.50
	06/16/06	3408.92	46.46	3362.46
	03/28/07	3408.92	45.85	3363.07
	09/06/07	3408.92	45.80	3363.12
	03/21/08	3408.92	45.70	3363.22
	08/04/08	3408.92	46.45	3362.47
	03/11/09	3408.92	45.70	3363.22
	07/29/09	3408.92	46.66	3362.26

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW081SA	03/30/04	3408.28	48.50	3359.78
	06/07/04	3408.28	46.80	3361.48
	09/14/04	3408.28	48.43	3359.85
	11/29/04	3408.28	47.99	3360.29
	03/16/05	3408.28	47.17	3361.11
	05/23/05	3408.28	47.12	3361.16
	01/17/06	3408.28	46.02	3362.26
	06/16/06	3408.28	46.02	3362.26
	03/28/07	3408.28	45.42	3362.86
	09/06/07	3408.28	45.34	3362.94
	03/21/08	3408.28	45.21	3363.07
	08/04/08	3408.28	45.98	3362.30
	03/11/09	3408.28	46.14	3362.14
	07/29/09	3408.28	46.23	3362.05
MW082SA	03/30/04	3406.25	55.46	3350.79
	06/07/04	3406.25	55.35	3350.90
	09/14/04	3406.25	55.22	3351.03
	11/29/04	3406.25	55.19	3351.06
	03/01/05	3406.25	54.81	3351.44
	05/23/05	3406.25	54.66	3351.59
	01/17/06	3406.25	54.00	3352.25
	06/14/06	3406.25	53.61	3352.64
	03/22/07	3406.25	52.94	3353.31
	09/05/07	3406.25	52.43	3353.82
	03/19/08	3406.25	52.12	3354.13
	08/04/08	3406.25	52.03	3354.22
	03/11/09	3406.25	52.09	3354.16
	07/29/09	3406.25	51.97	3354.28
MW083SA	03/30/04	3406.11	55.33	3350.78
	06/07/04	3406.11	55.22	3350.89
	09/14/04	3406.11	54.18	3351.93
	11/29/04	3406.11	55.19	3350.92
	03/01/05	3406.11	54.85	3351.26
	05/23/05	3406.11	54.58	3351.53
	01/17/06	3406.11	53.93	3352.18
	06/14/06	3406.11	53.51	3352.60
	03/22/07	3406.11	52.83	3353.28
	09/05/07	3406.11	52.34	3353.77
	03/19/08	3406.11	52.04	3354.07
	08/04/08	3406.11	51.94	3354.17
	03/11/09	3406.11	52.00	3354.11
	07/29/09	3406.11	51.91	3354.20
MW084SA	03/30/04	3405.98	54.83	3351.15
	06/07/04	3405.98	54.78	3351.20
	09/14/04	3405.98	54.70	3351.28
	11/29/04	3405.98	54.61	3351.37
	03/24/05	3405.98	54.27	3351.71
	05/23/05	3405.98	54.09	3351.89
	01/17/06	3405.98	53.45	3352.53
	06/14/06	3405.98	53.02	3352.96
	03/21/07	3405.98	NM	NM
	09/05/07	3405.98	51.86	3354.12
	03/19/08	3405.98	51.55	3354.43
	08/04/08	3405.98	51.47	3354.51
	03/11/09	3405.98	51.50	3354.48
	07/29/09	3405.98	51.40	3354.58
MW085SA	03/30/04	3405.98	55.24	3350.74
	06/07/04	3405.98	55.08	3350.90
	09/14/04	3405.98	55.08	3350.90
	11/29/04	3405.98	54.98	3351.00
	03/24/05	3405.98	54.66	3351.32
	05/23/05	3405.98	54.44	3351.54
	01/17/06	3405.98	53.82	3352.16
	06/14/06	3405.98	53.40	3352.58
	03/21/07	3405.98	NM	NM
	09/05/07	3405.98	52.24	3353.74
	03/19/08	3405.98	51.92	3354.06
	08/04/08	3405.98	51.84	3354.14
	03/11/09	3405.98	51.90	3354.08
	07/29/09	3405.98	51.79	3354.19
MW086SA	09/14/04	3401.86	53.74	3348.12
	03/31/05	3401.86	53.08	3348.78
	05/23/05	3401.86	52.83	3349.03
	01/17/06	3401.86	52.18	3349.68
	06/15/06	3401.86	51.86	3350.00
	04/11/07	3401.86	51.38	3350.48
	09/20/07	3401.86	50.87	3350.99
	03/19/08	3401.86	50.71	3351.15
	08/04/08	3401.86	50.72	3351.14
	03/11/09	3401.86	50.91	3350.95
	07/29/09	3401.86	50.67	3351.19

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
MW087A	09/24/04	3430.75	50.05	3380.70
	03/31/05	3430.75	50.85	3379.90
	05/23/05	3430.75	50.74	3380.01
	01/17/06	3430.75	50.15	3380.60
	06/19/06	3430.75	49.95	3380.80
	04/13/07	3430.75	49.41	3381.34
	03/24/08	3430.75	49.51	3381.24
	03/11/09	3430.75	49.84	3380.91
MW089SA	01/17/06	3428.09	48.30	3379.79
	06/20/06	3428.09	48.10	3379.99
	04/05/07	3428.09	47.87	3380.22
	03/21/08	3428.09	47.79	3380.30
	03/11/09	3428.09	48.30	3379.79
MW090SA	01/18/06	3428.33	48.76	3379.57
	06/20/06	3428.33	48.57	3379.76
	04/05/07	3428.33	48.42	3379.91
	03/21/08	3428.33	48.29	3380.04
	03/11/09	3428.33	48.79	3379.54
	07/29/09	3428.33	48.98	3379.35
MW091SA	01/17/06	3422.45	43.90	3378.55
	06/20/06	3422.45	43.86	3378.59
	04/05/07	3422.45	43.37	3379.08
	03/19/08	3422.45	43.33	3379.12
	03/11/09	3422.45	43.84	3378.61
MW092SA	01/17/06	3422.51	43.94	3378.57
	06/20/06	3422.51	43.62	3378.89
	04/05/07	3422.51	43.50	3379.01
	03/19/08	3422.51	43.38	3379.13
	03/11/09	3422.51	43.89	3378.62
MW093SA	01/17/06	3422.72	44.13	3378.59
	06/20/06	3422.72	43.60	3379.12
	04/05/07	3422.72	43.56	3379.16
	03/24/08	3422.72	43.55	3379.17
	03/11/09	3422.72	44.12	3378.60
RW001	11/16/99	3428.32	50.41	3377.91
	05/15/01	3428.32	49.65	3378.67
	08/23/01	3428.32	50.04	3378.28
	01/21/02	3428.32	49.85	3378.47
	04/04/02	3428.32	49.97	3378.35
	09/03/02	3428.32	49.88	3378.44
	12/02/02	3428.32	49.53	3378.79
	01/31/03	3428.32	49.63	3378.69
	03/28/03	3428.32	49.62	3378.70
	05/19/03	3428.32	49.51	3378.81
	09/09/03	3428.32	49.66	3378.66
	12/03/03	3428.32	49.71	3378.61
	03/30/04	3428.32	49.81	3378.51
	06/07/04	3428.32	49.75	3378.57
	09/17/04	3428.32	49.34	3378.98
	11/29/04	3428.32	48.80	3379.52
	03/31/05	3428.32	48.43	3379.89
	05/23/05	3428.32	50.25	3378.07
IW003	12/16/03	3406.68	45.47	3361.21
	02/18/04	3406.68	45.37	3361.31
	03/30/04	3406.68	45.37	3361.31
	06/03/04	3406.68	44.39	3362.29
	11/29/04	3406.68	45.95	3360.73
	03/17/05	3406.68	45.26	3361.42
	05/23/05	3406.68	45.10	3361.58
	01/17/06	3406.68	44.76	3361.92
	06/16/06	3406.68	44.77	3361.91
	04/09/07	3406.68	46.30	3360.38
	03/21/08	3406.68	44.71	3361.97
	03/10/09	3406.68	44.96	3361.72
IW004	12/16/03	3406.31	45.04	3361.27
	02/18/04	3406.31	44.95	3361.36
	03/30/04	3406.31	44.97	3361.34
	06/07/04	3406.31	45.99	3360.32
	11/29/04	3406.31	45.31	3361.00
	03/17/05	3406.31	44.83	3361.48
	05/23/05	3406.31	44.43	3361.88
	01/17/06	3406.31	44.52	3361.79
	06/16/06	3406.31	44.36	3361.95
	04/09/07	3406.31	44.15	3362.16
	03/21/08	3406.31	44.25	3362.06
	03/10/09	3406.31	44.44	3361.87

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
IW005	12/16/03	3405.36	45.85	3359.51
	02/18/04	3405.36	43.85	3361.51
	03/30/04	3405.36	43.84	3361.52
	06/07/04	3405.36	45.02	3360.34
	11/29/04	3405.36	44.52	3360.84
	03/21/05	3405.36	43.72	3361.64
	05/23/05	3405.36	42.71	3362.65
	01/17/06	3405.36	43.75	3361.61
	06/16/06	3405.36	43.62	3361.74
	04/12/07	3405.36	43.82	3361.54
	03/21/08	3405.36	43.51	3361.85
	03/10/09	3405.36	43.68	3361.68
IW006	12/16/03	3404.36	45.14	3359.22
	02/18/04	3404.36	43.24	3361.12
	03/30/04	3404.36	43.24	3361.12
	06/07/04	3404.36	44.18	3360.18
	11/29/04	3404.36	43.75	3360.61
	03/21/05	3404.36	42.86	3361.50
	05/23/05	3404.36	42.54	3361.82
	01/17/06	3404.36	42.68	3361.68
	06/16/06	3404.36	42.57	3361.79
	03/27/07	3404.36	42.49	3361.87
	04/12/07	3404.36	42.32	3362.04
	03/21/08	3404.36	42.65	3361.71
	03/10/09	3404.396	42.78	3361.62
IW007	12/16/03	3405.31	45.65	3359.66
	02/18/04	3405.31	44.09	3361.22
	03/30/04	3405.31	44.31	3361.00
	06/07/04	3405.31	43.54	3361.77
	11/29/04	3405.31	44.62	3360.69
	03/22/05	3405.31	43.24	3362.07
	05/23/05	3405.31	43.83	3361.48
	01/17/06	3405.31	43.91	3361.40
	06/16/06	3405.31	43.94	3361.37
	03/26/07	3405.31	43.48	3361.83
	03/21/08	3405.31	43.79	3361.52
	03/10/09	3405.31	44.21	3361.10
IW008	12/16/03	3405.37	50.61	3354.76
	02/18/04	3405.37	50.13	3355.24
	03/30/04	3405.37	51.08	3354.29
	06/07/04	3405.37	45.54	3359.83
	11/29/04	3405.37	43.98	3361.39
	03/22/05	3405.37	43.55	3361.82
	05/23/05	3405.37	43.85	3361.52
	01/17/06	3405.37	44.03	3361.34
	06/16/06	3405.37	44.07	3361.30
	03/23/07	3405.37	46.50	3358.87
	03/21/08	3405.37	44.80	3360.57
	03/10/09	3405.37	48.17	3357.20
IW009	12/16/03	3406.07	47.22	3358.85
	02/18/04	3406.07	47.40	3358.67
	03/30/04	3406.07	47.49	3358.58
	06/07/04	3406.07	44.55	3361.52
	11/29/04	3406.07	44.74	3361.33
	03/22/05	3406.07	44.30	3361.77
	05/23/05	3406.07	44.30	3361.77
	01/17/06	3406.07	45.02	3361.05
	06/16/06	3406.07	45.41	3360.66
	03/23/07	3406.07	46.27	3359.80
	03/21/08	3406.07	46.42	3359.65
	03/10/09	3406.07	47.12	3358.95
IW010	12/16/03	3405.82	52.88	3352.94
	02/18/04	3405.82	53.48	3352.34
	03/30/04	3405.82	53.52	3352.30
	06/07/04	3405.82	54.65	3351.17
	11/29/04	3405.82	54.45	3351.37
	03/22/05	3405.82	53.45	3352.37
	05/23/05	3405.82	53.21	3352.61
	01/17/06	3405.82	53.45	3352.37
	06/16/06	3405.82	52.93	3352.89
	03/23/07	3405.82	53.48	3352.34
	03/21/08	3405.82	53.30	3352.52
	03/10/09	3405.82	53.55	3352.27

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
IW011	12/16/03	3406.83	57.60	3349.23
	02/18/04	3406.83	57.59	3349.24
	03/30/04	3406.83	57.64	3349.19
	06/07/04	3406.83	58.79	3348.04
	11/29/04	3406.83	58.81	3348.02
	03/23/05	3406.83	58.19	3348.64
	05/23/05	3406.83	57.51	3349.32
	01/17/06	3406.83	57.79	3349.04
	06/16/06	3406.83	56.93	3349.90
	03/22/07	3406.83	56.21	3350.62
IW012	03/21/08	3406.83	55.44	3351.39
	03/10/09	3406.83	55.51	3351.32
IW012	02/18/04	3405.92	54.99	3350.93
	03/30/04	3405.92	Dry	Dry
	06/07/04	3405.92	53.24	3352.68
	11/29/04	3405.92	56.03	3349.89
	03/24/05	3405.92	55.03	3350.89
	05/23/05	3405.92	53.20	3352.72
	01/17/06	3405.92	Dry	Dry
	06/16/06	3405.92	55.44	3350.48
	03/22/07	3405.92	58.98	3346.94
	03/21/08	3405.92	54.29	3351.63
IW013	03/10/09	3405.92	54.26	3351.66
IW013	02/18/04	3406.62	56.27	3350.35
	03/30/04	3406.62	56.34	3350.28
	06/07/04	3406.62	51.56	3355.06
	11/29/04	3406.62	57.36	3349.26
	03/24/05	3406.62	56.72	3349.90
	05/23/05	3406.62	56.81	3349.81
	01/17/06	3406.62	56.15	3350.47
	06/16/06	3406.62	55.72	3350.90
	03/22/07	3406.62	NM	NM
	03/21/08	3406.62	54.13	3352.49
IW014	03/10/09	3406.62	54.12	3352.50
IW014	02/18/04	3405.48	54.55	3350.93
	03/30/04	3405.48	54.59	3350.89
	06/07/04	3405.48	NR	NR
	11/29/04	3405.48	55.88	3349.60
	03/24/05	3405.48	55.54	3349.94
	05/23/05	3405.48	55.02	3350.46
	01/17/06	3405.48	54.66	3350.82
	06/16/06	3405.48	54.25	3351.23
	03/26/07	3405.48	53.30	3352.18
	03/21/08	3405.48	52.64	3352.84
IW015	03/10/09	3405.48	52.57	3352.91
IW015	02/18/04	3406.05	45.43	3360.62
	03/30/04	3406.05	45.45	3360.60
	06/07/04	3406.05	45.91	3360.14
	11/29/04	3406.05	46.33	3359.72
	03/16/05	3406.05	44.97	3361.08
	05/23/05	3406.05	NR	NR
	01/17/06	3406.05	44.83	3361.22
	06/16/06	3406.05	44.58	3361.47
	04/09/07	3406.05	44.38	3361.67
	03/21/08	3406.05	44.20	3361.85
IW016	03/10/08	3406.05	44.58	3361.47
IW016	02/18/04	3408.29	48.16	3360.13
	03/30/04	3408.29	48.19	3360.10
	06/03/04	3408.29	49.11	3359.18
	11/29/04	3408.29	49.26	3359.03
	04/18/05	3408.29	48.50	3359.79
	05/23/05	3408.29	48.51	3359.78
	01/17/06	3408.29	47.45	3360.84
	06/16/06	3408.29	47.09	3361.20
	03/28/07	3408.29	46.33	3361.96
	03/21/08	3408.29	46.21	3362.08
IW018	03/10/08	3408.29	46.70	3361.59
IW018	01/17/06	3424.54	45.94	3378.60
	06/20/06	3424.54	45.82	3378.72
	04/09/07	3424.54	45.92	3378.62
	03/19/08	3424.54	45.59	3378.95
IW019	03/10/09	3424.54	46.05	3378.49
IW019	01/17/06	3423.78	45.13	3378.65
	06/20/06	3423.78	44.95	3378.83
	04/06/07	3423.78	44.85	3378.93
	03/19/08	3423.78	44.74	3379.04
	03/10/09	3423.78	45.23	3378.55

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
IW020	01/17/06	3423.50	44.76	3378.74
	06/20/06	3423.50	44.55	3378.95
	04/10/07	3423.50	44.33	3379.17
	04/09/08	3423.50	44.33	3379.17
	03/10/09	3423.5	44.84	3378.66
IW021	01/17/06	3423.16	44.44	3378.72
	06/20/06	3423.16	44.15	3379.01
	04/05/07	3423.16	44.04	3379.12
	03/19/08	3423.16	43.91	3379.25
	03/10/09	3423.16	44.42	3378.74
IW022	01/17/06	3423.16	44.39	3378.77
	06/20/06	3423.16	44.10	3379.06
	04/10/07	3423.16	43.87	3379.29
	04/09/08	3423.16	43.83	3379.33
	03/10/09	3423.16	44.33	3378.83
IW023	01/17/06	3426.05	47.25	3378.80
	06/20/06	3426.05	41.82	3384.23
	04/10/07	3426.05	46.65	3379.40
	03/21/08	3426.05	46.76	3379.29
	03/10/09	3426.05	47.14	3378.91
IW024	07/28/09	3426.05	47.33	3378.72
IW024	01/18/06	3426.63	47.15	3379.48
	06/20/06	3426.63	47.10	3379.53
	04/04/07	3426.63	46.85	3379.78
	03/21/08	3426.63	47.70	3378.93
	03/10/09	3426.63	47.25	3379.38
IW025	07/28/09	3426.63	47.45	3379.18
IW025	01/18/06	3427.62	48.09	3379.53
	06/20/06	3427.62	47.95	3379.67
	04/04/07	3427.62	47.72	3379.90
	03/21/08	3427.62	48.10	3379.52
	03/10/09	3427.62	47.20	3380.42
IW026	07/28/09	3427.62	48.44	3379.18
IW026	01/18/06	3428.01	48.42	3379.59
	06/20/06	3428.01	48.26	3379.75
	04/04/07	3428.01	48.10	3379.91
	03/21/08	3428.01	48.05	3379.96
	03/10/09	3428.01	48.58	3379.43
IW027	07/28/09	3428.01	48.76	3379.25
IW027	01/18/06	3428.17	48.55	3379.62
	06/20/06	3428.17	48.33	3379.84
	04/04/07	3428.17	48.17	3380.00
	03/21/08	3428.17	48.10	3380.07
	03/11/09	3428.17	48.66	3379.51
IW028	03/16/05	3428.18	48.70	3379.48
	05/23/05	3428.18	49.09	3379.09
	06/16/05	3428.18	49.10	3379.08
	01/17/06	3428.18	48.53	3379.65
	06/20/06	3428.18	48.30	3379.88
	04/04/07	3428.18	48.09	3380.09
	04/09/08	3428.18	47.99	3380.19
	03/11/09	3428.18	48.51	3379.67

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
RW004A	01/21/02	3430.11	51.51	3378.60
	04/04/02	3430.11	51.59	3378.52
	09/03/02	3430.11	51.45	3378.66
	12/02/02	3430.11	51.10	3379.01
	01/31/03	3430.11	51.14	3378.97
	03/28/03	3430.11	51.16	3378.95
	05/19/03	3430.11	51.23	3378.88
	09/09/03	3430.11	46.36	3383.75
	12/03/03	3430.11	51.53	3378.58
	03/30/04	3430.74	52.34	3378.40
	06/07/04	3430.74	51.61	3379.13
	11/30/04	3430.74	51.56	3379.18
	03/31/05	3430.74	51.97	3378.77
	05/23/05	3430.74	52.13	3378.61
	01/18/06	3430.74	47.46	3383.28
	06/19/06	3430.74	49.78	3380.96
	04/11/07	3430.74	47.15	3383.59
	03/24/08	3430.74	49.51	3381.23
	03/11/09	3430.74	47.49	3383.25
WATER WELLS				
GOPWW2	NR	3396.97	49.02	3347.95
	12/04/02	3396.97	49.54	3347.43
	01/31/03	3396.97	49.42	3347.55
	03/28/03	3396.97	49.14	3347.83
	05/19/03	3396.97	49.21	3347.76
	09/09/03	3396.97	49.37	3347.60
	12/02/03	3396.97	49.71	3347.26
	03/30/04	3396.97	49.54	3347.43
	06/07/04	3396.97	49.31	3347.66
	09/14/04	3396.97	49.45	3347.52
	11/29/04	3396.97	49.22	3347.75
	03/31/05	3396.97	48.81	3348.16
	05/23/05	3396.67	48.52	3348.15
	01/18/06	3396.67	48.00	3348.67
	06/23/06	3396.67	47.65	3349.02
	04/23/07	3396.67	47.15	3349.52
	09/10/07	3396.67	46.70	3349.97
	03/21/08	3396.67	46.46	3350.21
LordWW	08/04/08	3396.67	46.47	3350.20
	03/10/09	3396.67	46.59	3350.08
	07/28/09	3396.67	46.44	3350.23
	12/18/97	3419.97	44.00	3375.97
	11/16/99	3419.97	42.67	3377.30
	06/07/01	3419.97	41.90	3378.07
	02/06/02	3419.97	42.01	3377.96
	09/03/02	3419.97	41.88	3378.09
	12/09/02	3419.97	41.88	3378.09
	06/05/03	3419.97	41.95	3378.02
	01/22/04	3419.97	42.25	3377.72
	03/30/04	3419.97	42.34	3377.63
	06/07/04	3419.97	42.12	3377.85
	09/17/04	3419.97	41.93	3378.04
	05/23/05	3419.97	40.93	3379.04
	01/17/06	3419.97	40.59	3379.38
	06/23/06	3419.97	40.57	3379.40
	04/05/07	3419.97	40.05	3379.92
	03/18/08	3419.97	48.17	3371.80
	08/04/08	3419.97	40.43	3379.54
	03/10/09	3419.97	40.61	3379.36
	07/28/09	3419.97	40.80	3379.17

TABLE 1
SUMMARY OF 2009 GAUGING DATA
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Well ID	Date Measured	Top of Casing Elevation (feet AMSL)	Depth to Water (feet)	Groundwater Elevation (feet AMSL)
RolandWW	12/18/97	3419.47	43.12	3376.35
	11/16/99	3419.47	41.58	3377.89
	05/15/01	3419.47	41.06	3378.41
	08/23/01	3419.47	40.92	3378.55
	01/21/02	3419.47	41.09	3378.38
	04/04/02	3419.47	41.32	3378.15
	09/03/02	3419.47	40.90	3378.57
	12/02/02	3419.47	40.80	3378.67
	01/31/03	3419.47	40.79	3378.68
	03/28/03	3419.47	40.74	3378.73
	06/03/03	3419.47	40.92	3378.55
	09/09/03	3419.47	41.03	3378.44
	12/02/03	3419.47	41.14	3378.33
	03/30/04	3419.47	41.35	3378.12
	06/07/04	3419.47	41.17	3378.30
	03/31/05	3419.47	39.62	3379.85
	05/23/05	3419.47	39.81	3379.66
	06/23/06	3419.47	39.56	3379.91
	03/11/09	3419.47	39.69	3379.78
WoodellWW	05/15/01	3423.77	49.63	3374.14
	08/23/01	3423.77	49.97	3373.80
	04/05/02	3423.77	49.52	3374.25
	09/03/02	3423.77	54.07 (P)	3369.70
	12/02/02	3423.77	49.06	3374.71
	01/30/03	3423.77	49.14	3374.63
	03/28/03	3423.77	62.24 (P)	3361.53
	06/05/03	3423.77	53.76 (P)	3370.01
	09/09/03	3423.77	53.65 (P)	3370.12
	12/02/03	3423.77	49.07	3374.70
	03/30/04	3423.77	49.50	3374.27
	06/07/04	3423.77	54.24	3369.53
	11/29/04	3423.77	48.89	3374.88
	05/23/05	3423.77	52.80	3370.97
	03/10/09	NG	NG	NG
EPWW1	12/18/97	3429.95	73.12	3356.83
	04/22/97	3429.95	66.46	3363.49
	11/16/99	3429.95	65.20	3364.75
	05/15/01	3429.95	52.27	3377.68
	08/23/01	3429.95	52.86	3377.09
	01/21/02	3429.95	52.67	3377.28
	04/04/02	3429.95	93.34	3336.61
	09/03/02	3429.95	50.85	3379.10
	12/02/02	3429.95	51.59	3378.36
	01/31/03	3429.95	52.20	3377.75
	03/28/03	3429.95	52.58	3377.37
	05/19/03	3429.95	52.26	3377.69
	09/09/03	3429.95	94.08	3335.87
	12/03/03	3429.95	94.07	3335.88
	03/30/04	3429.95	86.62	3343.33
	06/07/04	3429.95	77.45	3352.50
	09/17/04	3429.95	52.22	3377.73
	11/30/04	3429.95	57.80	3372.15
	03/31/05	3429.95	51.39	3378.56
	05/23/05	3429.95	51.16	3378.79
	03/10/09	NG	NG	NG

Notes:

AMSL - Above Mean Sea Level
MW - Monitoring Well
No Suffix - Shallow/Middle Monitoring Well Completion
(Example: MW069)
A - Deep Monitoring Well Completion
(Example: MW070A)
M - Middle Monitoring Well Completion
(Example: MW008M)
SA - Fully-Penetrating, Monitoring Well Completion
(Example: MW071SA)
RW - Recovery Well
EP - Eunice Plant
WW - Water Well
GOP - Gulf Oil Corp.
IW - Injection Well
(P) - Well was pumping during water collection
NR - Not Reported
NG - Not Gauged

TABLE 2
SUMMARY OF 2009 GROUNDWATER ANALYTICAL
RESULTS

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	-----	-----	0.05	0.05	250
Shallow Zone Wells										
MW001	04/23/97	0.384	<0.001	0.075	0.049	-----	-----	-----	-----	-----
	01/20/99	0.006	0.019	0.029	0.029	-----	-----	-----	-----	-----
	11/17/99	0.008	0.018	0.140	0.042	-----	-----	-----	-----	-----
	05/31/01	0.060	0.020	0.540	0.090	-----	-----	-----	-----	-----
	02/07/02	0.002	0.009	0.059	0.084	<0.26	0.489	-----	-----	-----
	01/08/03	<0.002	0.002	0.017	0.024	<0.25	0.280	-----	-----	-----
	06/05/03	<0.002	0.004	0.052	<0.001	-----	-----	-----	-----	-----
	01/12/05	0.004	ND	0.047	ND	ND	0.220	-----	-----	200
	05/26/05	0.02	0.004	0.073	0.023	ND	0.440	-----	-----	280
	01/27/06	0.0017	<0.001	0.044	0.0033	<0.6	<0.6	0.0343	<0.02	338
	07/13/06	0.089	<0.001	0.037	0.0042	0.540	0.300	0.0308	<0.02	368
	04/19/07	0.036	<0.001	0.110	0.0095	0.500	0.380	<0.015	<0.02	327
	04/17/08	<0.001	<0.001	0.0016	<0.003	0.410	<0.05	<0.015	<0.2	112
	No Access (1st Half 2009) - Due to Construction Activity									
MW002	04/22/97	<0.001	<0.001	<0.001	<0.001	-----	-----	-----	-----	-----
	05/22/01	<0.002	<0.002	<0.002	<0.002	-----	-----	-----	-----	-----
	01/24/02	<0.002	<0.002	<0.002	<0.002	-----	<0.25	-----	-----	-----
	09/16/02	<0.002	<0.002	<0.002	<0.002	-----	<0.05	-----	-----	-----
	12/18/02	<0.002	<0.002	<0.002	<0.002	-----	<0.25	-----	-----	-----
	03/13/03	<0.002	<0.002	<0.002	<0.002	-----	<0.05	-----	-----	-----
	05/28/03	<0.002	<0.002	<0.002	<0.002	-----	<0.05	-----	-----	-----
	01/04/05	ND	ND	ND	ND	ND	ND	-----	-----	440
	06/06/05	ND	ND	ND	ND	ND	ND	-----	-----	410
	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0642	0.058	552
	07/06/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0339	0.037	553
	04/12/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.0699	0.064	817
	04/02/08	0.0045	0.0014	<0.001	<0.003	<0.097	<0.05	0.147	0.15	934
	03/31/09	<0.001	<0.001	<0.001	<0.003	0.190	<0.05	0.137	0.13	1040
MW003	04/22/97	<0.001	<0.001	<0.001	<0.001	-----	-----	-----	-----	-----
	05/24/01	<0.002	<0.002	<0.002	<0.002	-----	-----	-----	-----	-----
	01/06/05	ND	ND	ND	ND	ND	ND	-----	-----	570
	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.194	0.200	514
	07/07/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.187	0.170	530
	04/16/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.116	0.10	372
	04/03/08	0.0037	0.0012	<0.001	<0.003	<0.096	<0.05	0.085	0.052	317
	No Access (1st Half 2009) - Due to Construction Activity									
MW004	04/23/97	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	-----	-----	-----
	01/21/99	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	-----	-----	-----
	11/18/99	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	-----	-----	-----
	05/24/01	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-----	-----	-----
	01/28/02	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-----	-----	-----
	09/18/02	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-----	-----	-----
	12/30/02	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-----	-----	-----
	03/18/03	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-----	-----	-----
	06/04/03	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-----	-----	-----
	06/06/05	ND	ND	ND	ND	ND	ND	-----	-----	-----
	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	1.5	0.14	-----
	07/07/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	1.79	1.8	776
	04/17/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	1.92	0.51	1130
	04/15/08	0.0028	<0.001	<0.001	<0.003	0.140	<0.05	2.28	1.9	1030
	03/31/09	<0.001	<0.001	<0.001	<0.003	0.230	<0.05	1.46	1.5	852
MW005	04/22/97	0.54	0.31	0.093	0.245	-----	-----	-----	-----	-----
	02/11/02	0.60	<0.02	0.08	0.13	27	1.83	-----	-----	-----
	06/30/05	0.81	ND	0.07	ND	ND	ND	-----	-----	-----
	01/27/06	0.520	<0.005	0.064	<0.005	2.5	<0.6	0.0202	<0.02	1010
	07/13/06	0.440	<0.001	0.072	0.0078	2.3	1.5	0.0344	<0.02	894
	04/19/07	0.810	0.0013	0.064	0.012	3.2	2.4	<0.015	<0.02	1080
	04/17/08	0.004	<0.001	0.0012	<0.003	2.8	0.230	0.0151	<0.2	1500
	04/07/09	0.095	<0.001	0.0110	<0.003	3.2	0.290	<0.015	<0.02	1160

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	---	---	0.05	0.05	250
MW006	04/22/97	0.34	0.28	0.11	0.33	---	---	---	---	---
	02/11/02	0.68	0.67	0.11	0.26	71	3.6	---	---	---
	04/23/07	1.50	0.36	0.10	0.84	6.3	4.2	<0.015	<0.02	2970
	04/17/08	0.036	<0.001	0.0039	0.0036	3.1	0.400	<0.015	<0.20	2780
	04/07/09	0.510	<0.005	0.0420	0.1500	3.4	1.6	<0.015	<0.02	2310
MW007	08/19/97	<0.001	0.001	0.001	0.001	---	---	---	---	---
	05/24/01	<0.002	0.002	0.002	0.002	---	---	---	---	---
	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.015	<0.02	274
	07/07/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0232	<0.02	206
	04/16/07	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.0152	<0.02	193
	04/03/08	0.0027	<0.001	<0.001	<0.003	<0.096	<0.05	0.036	0.034	185
	No Access (1st Half 2009) - Due to Construction Activity									
MW008	08/20/97	<0.001	<0.001	<0.001	<0.001	---	---	---	---	---
	05/31/01	<0.002	<0.002	<0.002	<0.002	---	---	---	---	---
	09/18/02	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	---	---	---
	02/09/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0515	<0.08	702
	07/18/06	<0.001	<0.001	<0.001	<0.003	0.330	<0.05	0.0221	<0.02	802
	04/03/07	<0.001	<0.001	<0.001	<0.003	0.480	0.120	0.0391	<0.02	701
	04/15/08	<0.005	<0.005	<0.005	<0.015	0.410	<0.25	0.0162	<0.50	844
	03/30/09	<0.001	<0.001	<0.001	<0.003	0.180	<0.05	<0.015	<0.02	799
MW008M	02/10/06	<0.01	<0.01	<0.01	<0.03	<12	<66	0.215	<0.08	1300
	07/19/06	<0.005	<0.005	<0.005	<0.015	14.0	1.0	0.165	<0.02	1290
	04/13/07	<0.002	<0.001	<0.001	<0.003	18.0	1.3	0.163	<0.02	1200
	04/16/08	<0.002	<0.001	<0.001	<0.003	10.0	0.640	0.153	<1	1280
	03/31/09	<0.005	<0.005	<0.005	<0.015	2.5	<0.25	0.145	<0.2	1230
MW009	08/20/97	0.002	<0.001	<0.001	<0.001	---	---	---	---	---
	05/31/01	<0.002	<0.002	<0.002	<0.002	---	---	---	---	---
	12/19/02	<0.002	<0.002	<0.002	<0.002	0.63	<0.05	---	---	---
	06/04/03	<0.002	<0.002	<0.002	<0.002	0.3	<0.05	---	---	---
	01/04/05	ND	ND	ND	ND	ND	ND	---	---	---
	06/06/05	ND	ND	ND	ND	ND	ND	---	---	---
	02/02/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0728	0.062	253
	07/13/06	<0.001	<0.001	<0.001	<0.003	<0.094	<0.05	<0.015	<0.02	255
	04/15/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.0198	<0.02	384
	03/26/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	0.0219	<0.02	584
MW010	09/16/97	<0.001	<0.001	<0.001	<0.001	---	---	---	---	---
	05/24/01	<0.002	<0.002	<0.002	<0.002	---	---	---	---	---
	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0586	0.055	2200
	06/30/06	<0.001	<0.001	<0.001	<0.003	0.150	<0.05	0.082	0.048	2220
	04/11/07	<0.001	<0.001	<0.001	<0.003	0.100	<0.05	0.0483	0.043	2170
	09/19/07	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.0445	0.023	2430
	04/07/08	0.0041	0.0011	<0.001	<0.003	<0.1	<0.05	0.0517	<0.02*	2300
	08/13/08	0.0042	0.0055	0.013	<0.003	<0.1	0.059	0.0511	<0.02	2570
	03/26/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0412	0.033	2590
	08/19/09	<0.001	<0.001	<0.001	<0.003	0.66	<0.05	0.0387	0.028	2960
MW011	05/31/01	<0.002	<0.002	<0.002	<0.002	---	---	---	---	---
	02/09/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	3.9	3.2	1450
	07/19/06	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	3.81	3.5	1380
	03/29/07	0.0013	<0.001	<0.001	<0.003	<0.095	<0.05	4.15	3.3	1200
	04/16/08	<0.001	<0.001	<0.001	<0.003	0.10	<0.05	3.59	0.86	1660
	03/31/09	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	3.67	3.8	1380
MW011M	10/01/01	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	---	---	---
	02/10/06	<0.01	<0.01	<0.01	<0.03	<1.2	<1.2	0.319	0.08	1540
	07/19/06	<0.05	<0.05	<0.05	<0.015	<250	1.7	0.267	<0.02	1470
	03/29/07	<0.005	0.0012	<0.001	<0.003	0.860	<0.05	0.205	<0.2	1410
	04/16/08	<0.002	<0.001	<0.001	<0.003	0.560	<0.05	0.092	<1	1370
	03/31/09	<0.005	<0.005	<0.005	<0.015	0.300	<0.25	0.0672	<0.2	1330
MW012	05/30/01	<0.002	<0.002	<0.002	<0.002	---	---	---	---	---
	02/10/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.104	0.083	439
	07/20/06	<0.001	<0.001	<0.001	<0.003	0.440	0.063	0.0284	<0.02	408
	04/02/07	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.079	<0.02	436
	04/17/08	<0.005	<0.005	<0.005	<0.005	0.56	<0.25	<0.015	<0.5	848
	04/01/09	<0.001	<0.001	<0.001	<0.003	0.39	<0.05	<0.015	<0.02	447

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620			0.05	0.05	250
MW012M	02/10/06	0.050	0.050	0.050	0.150	950.0	4.90	0.255	<2	833
	07/20/06	0.050	0.050	0.050	0.150	0.160	<0.05	0.259	<0.02	906
	04/05/07	<0.005	<0.005	<0.005	<0.015	140.0	0.640	0.287	<2	871
	04/17/08	<0.02	<0.02	<0.02	<0.06	2.89	3.90	0.124	<2	781
	04/01/09	<0.005	<0.005	<0.005	<0.015	170	3.1	0.0782	<0.02	691
MW013	05/23/01	<0.002	<0.002	<0.002	<0.002					
	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.733	0.68	935
	07/05/06	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.638	0.61	946
	04/18/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.741	0.58	925
	09/20/07	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	0.673	0.62	784
	04/15/08	0.0018	<0.001	<0.001	<0.003	<0.099	<0.05	0.197	0.088	616
	08/21/08	<0.001	<0.001	0.0011	<0.003	<0.096	<0.05	0.604	0.3	819
	04/01/09	<0.001	<0.001	0.0011	<0.003	<0.096	<0.05	0.855	0.82	771
	08/10/09	<0.001	<0.001	<0.001	<0.003	0.10	<0.05	0.83	0.84	760
MW014	05/24/01	<0.002	<0.002	<0.002	<0.002					
	01/26/06	<0.001	<0.001	<0.001	<0.003	0.60	<0.6	0.325	0.29	2070
	06/29/06	<0.001	0.0011	0.0014	<0.003	1.200	<0.05	0.273	0.25	1880
	04/13/07	<0.001	<0.001	<0.001	<0.003	0.980	<0.05	0.242	0.23	1720
	09/20/07	<0.001	<0.001	<0.001	<0.003	1.100	<0.05	0.235	0.18	1630
	04/07/08	0.0019	<0.001	<0.001	<0.003	1.400	<0.05	0.231	0.11*	1600
	03/30/09	<0.001	<0.001	<0.001	<0.003	1.500	<0.05	0.201	0.2	1460
	08/10/09	0.0011	<0.001	<0.001	<0.003	0.650	<0.05	<0.015	<0.020	133
MW015	05/17/01	<0.002	<0.002	<0.002	<0.002					
	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	2720
	06/29/06	<0.001	<0.001	0.0012	<0.003	0.110	<0.05	<0.015	<0.02	2900
	03/22/07	<0.001	<0.001	<0.001	<0.003	0.130	<0.05	<0.015	<0.02	2570
	09/19/07	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	<0.015	<0.02	2380
	03/24/08	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	2230
	08/06/08	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	<0.015	<0.02	2380
	03/19/09	0.0029	0.0012	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	1850
	08/20/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	<0.015	<0.02	1590
MW018	05/17/01	<0.002	<0.002	<0.002	<0.002					
	01/23/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	284
	06/29/06	<0.001	0.0030	0.0032	<0.003	0.150	<0.05	<0.015	<0.02	318
	04/02/07	<0.001	<0.001	<0.001	<0.003	0.100	<0.05	<0.015	<0.02	283
	09/14/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	212
	03/24/08	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	<0.015	<0.02	223
	03/19/09	0.0026	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	181
	08/19/09	<0.001	<0.001	<0.001	<0.003	0.15	<0.05	<0.015	<0.02	200
MW020	06/07/01	<0.002	<0.002	<0.002	<0.002					
	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	992
	06/30/06	<0.001	0.0012	0.0015	<0.003	0.140	<0.05	<0.015	<0.02	908
	04/04/07	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	<0.015	<0.02	824
	09/18/07	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	<0.015	<0.02	826
	03/26/08	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	<0.015	<0.02	887
	08/06/08	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	<0.015	<0.02	785
	03/19/09	0.0049	0.0020	<0.001	<0.003	0.150	<0.05	<0.015	<0.02	817
	08/21/09	<0.001	<0.001	<0.001	<0.003	0.2	<0.05	<0.015	<0.02	1180

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620			0.05	0.05	250
MW021	01/18/99	<0.001	<0.001	<0.001	<0.001					
	11/17/99	<0.001	<0.001	<0.001	<0.001					
	05/18/01	<0.002	<0.002	<0.002	<0.002					
	01/23/02	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05			
	12/11/02	<0.002	<0.002	<0.002	<0.002	<0.5	<0.05			
	03/05/03	<0.002	<0.002	<0.002	<0.002	<0.25				
	05/21/03	<0.002	<0.002	<0.002	<0.002	<0.24				
	12/21/05	ND	ND	ND	ND	0.63	ND			
	05/27/05	ND	ND	0.003	ND	0.4	ND			290
	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	272
	06/30/06	<0.001	<0.001	<0.001	<0.003	0.780	<0.05	<0.015	<0.02	346
	04/09/07	<0.001	<0.001	<0.001	<0.003	0.460	<0.05	<0.015	<0.02	215
	09/19/07	<0.001	<0.001	<0.001	<0.003	0.380	<0.05	<0.015	<0.02	242
	04/01/08	0.017	0.0039	0.0015	<0.003	0.570	0.054	<0.015	<0.02	234
	08/07/08	<0.001	<0.001	<0.001	<0.003	0.510	<0.05	<0.015	<0.02	197
03/24/09	<0.001	<0.001	<0.001	<0.003	0.520	<0.05	<0.015	<0.02	216	
08/06/09	<0.001	<0.001	<0.001	<0.003	0.670	<0.05	<0.015	<0.02	193	
MW023	05/29/01	<0.002	<0.002	<0.002	<0.002					
	06/01/05	ND	ND	ND	ND	ND	ND			
	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.459	0.43	1290
	06/26/06	<0.001	<0.001	<0.001	<0.003	0.100	<0.005	0.549	0.55	1180
	04/18/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	1.33	1.2	965
	09/21/07	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	1.65	1.6	975
	04/09/08	0.0048	0.0012	<0.001	<0.003	<0.097	<0.05	1.66	1.7	862
	08/21/08	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	1.62	1.7	879
	03/31/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	1.69	1.7	949
	08/12/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	1.69	1.6	771
MW024	07/18/05	ND	ND	ND	ND	ND	ND			
	12/28/05	ND	ND	ND	ND	ND	15			
	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.184	0.18	636
	06/27/06	<0.001	0.0038	0.0047	0.0039	<0.096	<0.05	0.125	0.1	613
	04/11/07	<0.001	<0.001	<0.001	<0.003	0.14	<0.05	0.0289	0.027	577
	09/14/07	<0.001	<0.001	<0.001	<0.003	0.27	<0.05	0.0443	0.043	560
	04/07/08	0.0019	<0.001	<0.001	<0.003	0.4	<0.05	0.0399	0.046*	590
	08/13/08	0.0036	0.0043	0.0099	<0.003	0.13	<0.05	0.0547	0.026	653
	03/25/09	<0.001	<0.001	<0.001	<0.003	0.11	<0.05	0.0462	0.041	717
08/19/09	<0.001	<0.001	<0.001	<0.003	0.18	<0.05	0.0454	0.037	719	
MW025	05/29/01	<0.002	<0.002	<0.002	<0.002					
	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0403	0.036	281
	07/05/06	<0.001	0.0013	0.0012	<0.003	1.300	<0.05	<0.015	<0.02	397
	03/22/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	375
	09/19/07	<0.001	<0.001	<0.001	<0.003	0.430	<0.05	<0.015	<0.02	320
	03/24/08	<0.001	<0.001	<0.001	<0.003	0.570	<0.05	<0.015	<0.02	393
	08/07/08	<0.001	<0.001	<0.001	<0.003	0.290	<0.05	<0.015	<0.02	392
	03/19/09	0.0035	0.0014	<0.001	<0.003	0.330	<0.05	<0.015	<0.02	418
	08/20/09	<0.001	<0.001	<0.001	<0.003	0.410	<0.05	<0.015	<0.02	432
MW026	05/18/01	<0.002	<0.002	<0.002	<0.002					
	01/19/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0176	<0.02	766
	06/23/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	708
	04/05/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	737
	09/11/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	731
	03/25/08	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	805
	08/11/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	825
	No Access (1st Half 2009) - Due to Construction Activity									
	08/24/09	<0.001	<0.001	<0.001	<0.003	0.15	<0.05	<0.015	<0.02	866
	MW027	05/18/01	<0.002	<0.002	<0.002	<0.002				
01/23/06		<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0557	<0.02	355
06/23/06		<0.001	<0.001	<0.001	<0.003	0.270	<0.05	<0.015	<0.02	408
03/21/07		<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.0221	<0.02	399
09/14/07		<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0216	<0.02	370
No Access (1st Half 2009)										
08/19/09		<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	344

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	-----	-----	0.05	0.05	250
MW028	05/22/01	<0.002	<0.002	<0.002	<0.002	-----	-----	-----	<0.02	-----
	01/18/06	<0.001	<0.001	<0.001	<0.003	ND	ND	0.0301	<0.02	655
	06/20/06	<0.001	<0.001	<0.001	<0.003	0.320	<0.05	<0.015	<0.02	629
	03/21/07	<0.001	<0.001	<0.001	<0.003	0.280	<0.05	<0.015	<0.02	418
	09/06/07	<0.001	<0.001	<0.001	<0.003	0.290	<0.05	<0.015	<0.02	389
	03/19/08	<0.001	<0.001	<0.001	<0.003	0.140	<0.05	<0.015	<0.02	292
	08/12/08	<0.001	<0.001	<0.001	<0.003	0.250	<0.05	<0.015	<0.02	333
	03/19/09	0.0085	0.0028	0.0012	<0.003	<0.095	<0.05	<0.015	<0.02	253
	08/24/09	<0.001	<0.001	<0.001	<0.003	0.490	0.12	<0.015	<0.02	438
MW029	05/18/01	<0.002	<0.002	<0.002	<0.002	-----	-----	-----	<0.02	-----
	01/18/06	<0.001	<0.001	<0.001	<0.003	ND	ND	<0.015	<0.02	147
	06/20/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	155
	03/28/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	145
	09/06/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	138
	03/20/08	<0.001	<0.001	0.003	<0.003	<0.096	<0.05	<0.015	<0.02	138
	08/05/08	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	142
	03/16/09	0.0079	0.0031	0.0013	<0.003	<0.096	<0.05	<0.015	<0.02	138
	08/24/09	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	<0.015	<0.02	136
MW030	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	411
	06/22/06	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	248
	03/28/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	387
	09/11/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	360
	03/25/08	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	363
	08/05/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	328
	03/16/09	0.012	0.0043	0.0017	<0.003	<0.094	<0.05	<0.015	<0.02	346
	08/20/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	180
MW031	01/19/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	113
	06/21/06	<0.001	<0.001	<0.001	<0.003	0.360	<0.05	<0.015	<0.02	131
	03/28/07	<0.001	<0.001	<0.001	<0.003	0.210	<0.05	<0.015	<0.02	97.3
	09/11/07	<0.001	<0.001	<0.001	<0.003	0.230	<0.05	<0.015	<0.02	104
	03/20/08	<0.001	0.0011	0.0031	<0.003	0.230	<0.05	<0.015	<0.02	103
	08/05/08	<0.001	<0.001	<0.001	<0.003	0.260	<0.05	<0.015	<0.02	90.4
	03/24/09	<0.001	<0.001	<0.001	<0.003	0.150	<0.05	<0.015	<0.02	121
	08/04/09	<0.001	<0.001	<0.001	<0.003	0.170	<0.05	<0.015	<0.02	95.9
MW032	01/19/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0405	<0.02	279
	06/21/06	<0.001	<0.001	<0.001	<0.003	0.140	<0.05	0.0261	<0.02	249
	04/13/07	<0.001	<0.001	<0.001	<0.003	0.190	<0.05	0.0195	<0.02	246
	09/07/07	<0.001	<0.001	<0.001	<0.003	0.210	<0.05	<0.015	<0.02	228
	04/07/08	0.010	0.0022	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	255
	08/14/08	0.0012	0.0012	0.0023	<0.003	<0.1	<0.05	<0.015	<0.02	268
	03/30/09	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	255
	08/06/09	<0.001	<0.001	<0.001	<0.003	0.490	0.24	<0.015	<0.02	227
MW033	04/03/02	0.3	2.9	0.4	0.7	0.68	12.4	-----	-----	-----
	09/23/02	0.7	8	1	1.5	0.64	28	-----	-----	-----
	01/08/03	0.8	5.4	0.9	1.1	0.57	18	-----	-----	-----
	06/05/03	0.48	0.07	0.48	0.03	0.61	2.3	-----	-----	-----
	01/13/05	0.49	1.6	0.47	0.53	0.37	10	-----	<0.02	840
	05/25/05	0.38	1.3	0.4	0.43	0.47	9.3	-----	<0.02	770
	01/27/06	0.370	0.960	0.420	0.450	<0.6	1.4	<0.015	<0.02	795
	06/26/06	0.250	0.680	0.340	0.350	0.880	4.6	<0.015	<0.02	779
	04/23/07	0.190	0.320	0.380	0.200	1.100	3.100	<0.015	<0.02	495
	09/21/07	0.180	0.380	0.400	0.190	1.400	2.900	<0.015	<0.02	539
	03/19/08	0.170	0.380	0.420	0.200	1.30	3.40	<0.015	<0.02	723
	08/13/08	0.140	0.093	0.210	0.049	0.730	1.500	<0.015	<0.02	818
	04/01/09	0.180	0.190	0.280	0.110	0.990	2.400	<0.015	<0.02	699
	08/24/09	0.180	0.150	0.260	0.085	0.890	2.000	<0.015	<0.02	915
MW034	12/05/02	<0.002	<0.002	<0.002	<0.002	<0.5	<0.05	-----	-----	-----
	03/05/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	-----	-----	-----
	01/05/05	ND	ND	ND	ND	ND	ND	-----	-----	540
	06/07/05	ND	ND	ND	ND	ND	ND	-----	-----	480
	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0838	0.08	443
	07/07/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0533	0.045	412
	04/09/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0491	0.033	343
	04/01/08	0.008	0.0022	0.001	<0.003	<0.097	<0.05	0.0812	0.049	363
	03/25/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0883	0.078	414

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	-----	-----	0.05	0.05	250
MW035	01/29/02	<0.002	<0.002	<0.002	<0.002	<0.26	<0.05	-----	-----	-----
	09/11/02	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	-----	-----	-----
	03/05/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	-----	-----	-----
	12/21/04	ND	ND	ND	ND	ND	ND	-----	0.005	70
	05/25/05	0.002	0.018	0.011	0.01	ND	0.19	-----	-----	30
	01/23/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	33.3
	06/22/06	<0.001	<0.001	<0.001	<0.003	0.700	<0.05	<0.015	<0.02	80.3
	04/02/07	<0.001	<0.001	<0.001	<0.003	0.260	<0.05	<0.015	<0.02	59.2
	04/02/08	0.0053	0.0015	<0.001	<0.003	0.740	<0.05	<0.015	<0.02	54.9
	03/24/09	<0.001	<0.001	<0.001	<0.003	0.580	<0.05	<0.015	<0.02	225
MW036	08/29/01	<0.002	0.005	<0.002	0.047	-----	-----	-----	-----	-----
	09/19/02	<0.002	<0.002	<0.002	0.019	1.10	0.71	-----	-----	-----
	01/17/03	0.003	<0.002	<0.002	0.11	1.60	0.9	-----	-----	-----
	01/12/05	ND	ND	ND	ND	1.50	0.42	-----	<0.005	760
	05/31/05	ND	ND	0.003	0.49	2.10	0.51	-----	<0.005	610
	01/26/06	0.0019	<0.001	<0.001	0.070	1.5	0.60	0.0172	<0.02	685
	07/12/06	0.0096	0.0013	0.0026	0.098	3.200	0.850	<0.015	<0.02	663
	04/19/07	0.018	<0.001	0.030	0.400	2.000	2.300	<0.015	<0.02	460
	04/16/08	0.026	<0.001	0.0046	0.440	3.20	3.70	<0.015	<0.02	183
	04/07/09	0.014	0.001	0.0033	0.420	3.20	2.70	<0.015	<0.02	460
MW037	08/29/01	2.0	<0.1	0.4	0.7	0.56	6.48	0.05	0.005	740
	02/07/02	1.7	<0.04	0.36	0.19	0.71	3.82	0.05	0.005	770
	09/19/02	3.4	<0.08	0.32	0.1	1.3	2.5	0.05	0.01	380
	01/08/03	3.7	<0.1	0.4	0.4	1.8	11.0	-----	0.005	330
	06/05/03	2.1	<0.08	0.35	0.27	1.3	4.4	-----	0.005	350
	01/12/05	1.8	<0.02	0.56	0.23	2.3	7.0	-----	<0.005	460
	05/26/05	1.9	<0.02	0.31	0.18	3.5	8.0	0.01	<0.005	530
	01/27/06	3.0	0.017	0.42	0.079	5.8	1.3	<0.015	<0.02	605
	07/13/06	2.2	<0.005	0.14	0.020	5.30	5.7	<0.015	<0.02	585
	04/19/07	2.4	<0.005	0.25	0.033	3.90	6.5	<0.015	0.02	669
MW038	04/16/08	1.80	<0.005	0.100	0.022	6.90	4.60	<0.015	<0.08	1020
	04/07/09	0.073	<0.001	0.040	0.004	2.70	0.50	<0.015	<0.02	1810
	08/29/01	<0.002	<0.002	<0.002	<0.002	0.34	<0.05	-----	-----	-----
	02/07/02	0.003	<0.002	<0.002	<0.002	0.43	<0.05	-----	-----	-----
	09/19/02	0.088	<0.004	<0.004	<0.004	0.62	0.11	-----	-----	-----
	01/07/03	0.024	<0.002	<0.002	<0.002	0.71	0.16	-----	-----	-----
	06/05/03	0.011	<0.002	<0.002	<0.002	0.6	0.14	-----	-----	-----
	01/12/05	0.005	ND	ND	ND	0.31	ND	-----	<0.01	530
	05/31/05	0.005	ND	ND	ND	0.3	ND	-----	<0.005	-----
	01/26/06	0.0042	<0.001	<0.001	<0.003	<0.6	<0.6	0.216	<0.02	508
MW043	07/13/06	0.0084	<0.001	<0.001	<0.003	0.450	<0.05	0.121	<0.02	510
	04/19/07	0.020	<0.001	0.0029	0.0063	0.690	0.110	0.313	<0.02	414
	04/16/08	<0.001	<0.001	<0.001	<0.003	0.390	<0.05	0.179	0.13	260
	04/07/09	<0.001	<0.001	<0.001	<0.003	0.350	<0.05	0.185	0.13	301
	04/25/02	<0.002	<0.002	<0.002	<0.002	<0.26	<0.05	-----	-----	-----
	09/11/02	<0.002	<0.002	<0.002	<0.002	0.25	<0.05	-----	-----	-----
	03/19/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	-----	-----	-----
	12/28/04	ND	ND	ND	ND	0.79	0.062	-----	-----	-----
	05/27/05	ND	0.002	ND	ND	0.43	0.058	-----	-----	180
	01/23/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	746
MW044	06/30/06	<0.001	<0.001	<0.001	<0.003	0.200	<0.05	<0.015	<0.02	170
	04/09/07	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	<0.015	<0.02	103
	03/26/08	<0.001	<0.001	<0.001	<0.003	0.870	<0.05	<0.015	<0.02	212
	03/24/09	<0.001	<0.001	<0.001	<0.003	0.930	<0.05	<0.015	<0.02	240
	04/03/02	<0.002	<0.002	<0.002	<0.002	-----	<0.005	-----	-----	-----
	09/18/02	<0.002	<0.002	<0.002	<0.002	-----	<0.005	-----	-----	-----
	01/02/03	<0.002	<0.002	<0.002	<0.002	-----	<0.005	-----	-----	-----
	06/04/03	<0.002	<0.002	<0.002	<0.002	-----	<0.005	-----	-----	-----
	01/05/05	ND	ND	ND	ND	0.72	ND	-----	-----	860
	06/09/05	ND	ND	ND	ND	0.61	ND	-----	0.67	880
MW044	02/02/06	<0.001	<0.001	<0.001	<0.003	0.67	<0.6	0.242	0.18	695
	07/21/06	<0.001	<0.001	<0.001	<0.003	2.70	<0.05	<0.015	<0.02	540
	04/06/07	<0.001	<0.001	<0.001	<0.003	3.10	<0.05	<0.015	<0.02	430
	04/09/08	<0.001	<0.001	<0.001	<0.003	1.10	<0.05	0.130	0.11	448
	03/25/09	<0.001	<0.001	<0.001	<0.003	2.40	<0.05	0.108	0.084	505

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	---	---	0.05	0.05	250
MW045	04/04/02	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	---	---	---
	09/12/02	<0.002	<0.002	<0.002	<0.002	<0.24	<0.05	---	---	---
	12/19/02	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	---	---	---
	05/27/03	<0.002	<0.002	<0.002	<0.002	<0.26	<0.05	---	---	---
	05/27/05	0.003	ND	0.004	ND	0.32	0.1	---	---	330
	01/27/06	<0.001	<0.001	<0.001	<0.003	1.3	<0.6	<0.015	<0.02	328
	07/12/06	<0.001	<0.001	0.0016	0.0042	2.800	0.110	<0.015	<0.02	373
	04/02/07	<0.001	<0.001	<0.001	<0.003	2.800	---	<0.015	---	376
	04/17/07	<0.001	<0.001	<0.001	<0.003	2.400	0.170	<0.015	<0.02	340
	04/02/08	0.0068	0.0021	0.0012	0.003	3.300	0.190	<0.015	<0.02	351
	03/24/09	<0.001	<0.001	<0.001	<0.003	3.200	0.160	<0.015	<0.02	256
MW046	04/04/02	<0.002	<0.002	<0.002	0.02	0.77	0.194	---	---	---
	09/19/02	<0.002	<0.002	<0.002	0.008	0.92	0.34	---	---	---
	01/07/03	0.003	0.016	<0.002	0.018	0.66	<0.5	---	---	---
	06/04/03	0.006	<0.002	<0.002	0.012	2.4	0.4	---	---	---
	01/12/05	ND	ND	ND	ND	3.4	0.25	---	<0.005	170
	05/26/05	0.005	0.003	0.009	0.027	2.7	0.4	---	---	130
	01/26/06	0.0025	<0.001	0.0035	0.011	6.2	<0.6	<0.015	<0.02	296
	07/12/06	0.006	0.0017	0.010	0.027	4.300	0.330	<0.015	<0.02	376
	04/19/07	<0.001	<0.001	<0.001	<0.003	3.300	0.400	<0.015	<0.02	550
	04/17/08	0.021	0.0011	0.052	0.026	4.60	0.550	<0.015	<0.02	580
	04/07/09	0.022	0.0014	0.055	0.089	5.20	0.650	<0.015	<0.02	551
MW047	04/04/02	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	---	---	---
	09/17/02	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	---	---	---
	01/02/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	---	---	---
	06/02/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	---	---	---
	06/06/05	ND	ND	ND	ND	ND	ND	---	---	---
	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0854	0.077	356
	07/07/06	<0.001	<0.001	<0.001	<0.003	<0.094	<0.05	0.0573	0.043	232
	04/17/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0511	0.03	206
	04/03/08	0.0041	0.0013	<0.001	<0.003	<0.097	<0.05	0.107	0.11	212
	No Access (1st Half 2009) - Due to Construction Activity									
MW058	01/28/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.25	---	---	---
	01/03/05	ND	ND	ND	ND	ND	ND	---	0.17	580
	06/08/05	ND	ND	ND	ND	ND	ND	1.36	1.1	---
	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.581	0.54	610
	07/06/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.599	0.57	639
	09/14/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.835	0.86	694
	04/15/08	0.0023	<0.001	<0.001	<0.003	<0.095	<0.05	1.7	1.7	1040
	08/21/08	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	2.26	2.2	1140
	04/02/09	<0.001	<0.001	0.0016	<0.003	<0.094	<0.05	2	1.9	876
	08/19/09	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	2.22	1.1	1050
MW059	01/29/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.25	---	---	---
	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.101	0.095	435
	06/26/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.005	0.124	0.12	446
	09/12/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.185	0.19	255
	04/03/08	0.0032	0.001	<0.001	<0.003	<0.096	<0.05	0.200	<0.02	499
	08/14/08	0.0016	0.0016	0.0028	<0.003	<0.1	<0.05	0.546	0.45	1010
	03/31/09	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.206	0.2	517
	08/12/09	<0.001	<0.001	<0.001	<0.003	0.11	<0.05	0.210	0.22	497
MW060	01/08/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	---	---	---
	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	961
	07/06/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	842
	03/28/07	<0.001	<0.001	<0.001	<0.003	<0.098	<0.005	<0.015	<0.02	876
	09/14/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	983
	03/25/08	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	1030
	08/11/08	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	<0.015	<0.02	1130
	03/18/09	0.0052	0.0021	0.0010	<0.003	<0.098	<0.05	<0.015	<0.02	1160
	08/24/09	<0.001	<0.001	<0.001	<0.003	0.11	<0.05	<0.015	<0.02	1450
MW061	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	4.07	0.38	844
	07/05/06	<0.001	<0.001	<0.001	<0.003	<0.094	<0.05	3.91	3.6	766
	04/18/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.005	3.81	3.4	756
	09/21/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	3.45	3.1	697
	08/07/08	<0.001	<0.001	<0.001	<0.003	0.100	<0.05	2.95	2.6	707
	04/01/09	<0.002	0.013	0.0046	0.0036	0.140	0.078	2.7	2.7	651
	08/19/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	4.24	4.4	716

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	-----	-----	0.05	0.05	250
MW068	03/05/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	-----	-----	-----
	01/19/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	1910
	06/21/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	932
	03/22/07	<0.001	<0.001	<0.001	<0.003	-----	<0.05	<0.015	<0.02	128
	09/07/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	1250
	03/25/08	0.0015	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	2340
	08/11/08	0.0032	<0.001	<0.001	<0.003	0.680	<0.05	<0.015	<0.02	5690
	03/18/09	0.0053	0.0022	0.0011	<0.003	0.096	<0.05	<0.015	<0.02	1170
	08/24/09	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	<0.015	<0.02	2110
MW069	03/05/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	-----	-----	-----
	01/19/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0481	<0.02	4330
	06/21/06	<0.001	<0.001	<0.001	<0.003	0.260	<0.05	<0.015	<0.02	2400
	03/22/07	<0.001	<0.001	<0.001	<0.003	0.490	<0.05	<0.015	<0.02	1490
	09/07/07	<0.001	<0.001	<0.001	<0.003	0.500	<0.05	<0.015	<0.02	2600
	No Access (1st Half 2009) - Due to Construction Activity									
	08/24/09	0.0063	0.01	0.022	0.0064	0.610	0.12	<0.015	<0.02	3470
MW070	03/06/03	<0.002	<0.002	<0.002	<0.002	<0.25	<0.05	-----	-----	-----
	01/27/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	155
	06/22/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	163
	03/29/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	191
	09/12/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	46
	03/25/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	275
	08/05/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	237
	03/16/09	0.022	0.0068	0.0022	<0.003	<0.095	0.062	<0.015	<0.02	232
	08/20/09	<0.001	<0.001	<0.001	<0.003	0.28	<0.05	<0.015	<0.02	197
	09/13/04	ND	ND	ND	ND	39	7	-----	-----	-----
MW088M	02/06/06	<0.1	<0.1	<0.1	<0.3	<1,200	<4,000	0.691	<2	626
	07/20/06	<0.001	<0.001	<0.001	<0.003	<4.8	<0.05	0.108	<0.02	879
	04/05/07	<0.005	<0.001	<0.001	<0.003	<0.11	<0.05	0.0346	<0.02	701
	04/21/08	<0.02	<0.02	<0.02	<0.06	71.00	4.70	0.273	<2.0	801
	04/01/09	<0.05	<0.05	<0.05	<0.15	1,500	4.90	0.186	<2	720
RWO02	02/10/06	<0.01	<0.01	<0.01	<0.03	-----	-----	0.295	<0.02	1390
	07/20/06	<0.001	<0.001	<0.001	<0.003	380	50	0.0581	<0.02	1220
	03/29/07	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.205	<0.02	1080
	04/17/08	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	0.0523	<0.02	1220
	03/31/09	<0.005	<0.005	<0.005	<0.015	6.6	<0.25	0.0662	<2.00	942
RWO03	02/10/06	<0.01	<0.01	<0.01	<0.03	-----	-----	0.015	<0.02	545
	07/20/06	<0.005	<0.005	<0.005	<0.015	2400	250	0.015	<0.02	585
	04/02/07	<0.005	<0.005	<0.005	<0.015	1.10	<0.25	<0.015	<0.2	627
	04/21/08	<0.005	<0.005	<0.005	<0.0015	0.67	0.25	<0.015	<0.5	441
	04/01/09	<0.005	<0.005	<0.005	<0.0150	0.76	<0.25	<0.015	<0.2	487
IWO01	02/06/06	<0.025	<0.025	<0.025	<0.075	-----	-----	<0.015	<2	146
	07/20/06	<0.01	<0.01	<0.01	<0.03	480000	6200	0.02	<0.02	240
	04/16/07	<0.05	<0.05	<0.05	0.150	550	4,500	<0.015	<2	689
	04/17/08	<0.02	<0.02	<0.02	<0.06	230	2,800	<0.375	<2	686
	03/31/09	0.0059	0.0053	<0.005	<0.015	35	0.250	<0.015	<2	738
IWO02	02/06/06	30	<0.02	<0.02	<0.06	-----	-----	0.0166	<2	126
	07/20/06	<0.01	<0.01	<0.01	<0.05	960000	6600	0.0154	<0.02	133
	04/11/07	<0.1	<0.1	<0.1	<0.3	17	<5	<0.075	<2	317
	04/21/08	<0.02	<0.02	<0.02	<0.06	310	<0.1	<0.075	<2	371
	4/6/2009*	<0.05	<0.05	<0.05	<0.15	6	<2.5	<0.075	<2	501
Deep Zone Wells										
MW0002A	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0268	0.026	506
	07/06/06	<0.001	<0.001	<0.001	<0.003	0.460	<0.05	0.0787	0.068	848
	04/12/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.0586	0.045	729
	04/02/08	0.015	0.0032	0.0012	<0.003	0.740	<0.05	0.278	0.27	1460
	03/31/09	<0.001	<0.001	<0.001	<0.003	0.510	<0.05	0.333	0.34	1160
MW004A	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.175	0.18	483
	07/07/06	<0.001	<0.001	<0.001	<0.003	<0.094	<0.05	0.177	0.18	373
	04/16/07	<0.001	<0.001	<0.001	<0.003	0.100	<0.05	0.265	0.28	523
	04/03/08	0.012	0.0025	<0.001	<0.003	<0.096	<0.05	0.334	0.23	571
	03/30/09	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.271	0.25	465

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	---	---	0.05	0.05	250
MW007A	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.53	0.52	585
	07/07/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.367	0.38	409
	04/16/07	<0.001	<0.001	<0.001	<0.003	0.100	<0.05	0.641	0.69	710
	04/03/08	0.0099	0.0021	<0.001	<0.003	<0.096	<0.05	0.732	0.68	689
	No Access (1st Half 2009) - Due to Construction Activity									
MW008A	02/09/06	<0.025	<0.025	<0.025	<0.075	<1.2	<6	0.205	<0.08	996
	07/18/06	<0.005	<0.005	<0.005	<0.015	6.5	0.6	0.151	<0.02	1020
	04/03/07	<0.005	<0.001	<0.001	<0.003	20.0	2.2	0.204	<0.2	1010
	04/15/08	<0.025	<0.025	<0.025	<0.075	56.0	2.4	0.18	<1	1030
	03/26/09	<0.005	<0.005	<0.005	<0.015	56.0	1.2	0.149	<0.2	1130
MW009A	01/11/05	ND	ND	ND	ND	ND	ND	---	---	---
	02/02/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.938	0.9	644
	07/13/06	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.88	0.78	642
	04/04/07	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	0.916	0.84	356
	04/15/08	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.902	0.92	706
	03/26/09	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.803	0.86	683
MW011A	02/10/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	3.75	3.5	1350
	07/19/06	<0.001	<0.001	<0.001	<0.003	<0.094	<0.05	4.32	4.2	1480
	03/29/07	0.0017	<0.001	<0.001	<0.003	0.140	<0.05	3.94	3.4	1370
	04/16/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	3.88	3.8	1460
	03/31/09	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	3.77	3.7	1420
MW012A	02/10/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	72.6
	07/20/06	<0.001	<0.001	<0.001	<0.003	0.160	<0.05	<0.015	<0.02	88.1
	04/05/07	<0.001	<0.001	<0.001	<0.003	0.100	<0.05	<0.015	<0.02	99
	04/21/08	<0.001	<0.001	<0.001	<0.003	0.180	<0.05	<0.015	<0.02	81.8
	04/01/09	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	100
MW013A	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0492	0.039	111
	07/05/06	<0.001	<0.001	<0.001	<0.003	0.100	<0.05	0.0308	0.021	84
	04/16/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0626	0.043	122
	09/21/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0295	0.028	86
	04/07/08	0.0074	0.0017	<0.001	<0.003	<0.096	<0.05	0.0245	0.04*	87.5
	08/21/08	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	0.0269	0.023	85.3
	03/30/09	<0.001	<0.001	<0.001	<0.003	0.160	<0.05	<0.015	<0.020	68
	08/04/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.020	72.5
MW014A	01/23/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	45.8
	06/29/06	<0.001	0.0010	0.0014	<0.003	<0.095	<0.05	<0.015	<0.02	47.9
	03/21/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	45.6
	09/13/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	46.2
	03/24/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	47.9
	03/18/09	0.017	0.0058	0.0019	<0.003	<0.096	<0.06	<0.015	<0.02	44.9
	08/20/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	45.6
MW015A	01/23/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	1130
	06/29/06	<0.001	0.0018	0.0019	<0.003	<0.095	<0.05	<0.015	<0.02	1440
	03/22/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	1320
	09/14/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	1400
	03/24/08	<0.001	<0.001	0.0014	<0.003	<0.096	<0.05	<0.015	<0.02	1910
	08/06/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	2020
	03/19/09	0.0098	0.0027	0.0011	<0.003	<0.096	<0.05	<0.015	<0.02	2010
	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	2270
MW016A	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	255
	06/29/06	<0.001	<0.001	0.0013	<0.003	<0.096	<0.05	<0.015	<0.02	287
	03/22/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	260
	09/13/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	269
	03/19/08	<0.001	0.0053	0.014	0.0051	<0.097	0.070	<0.015	<0.02	289
	08/07/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	352
	03/17/09	0.0076	0.0030	0.0012	<0.003	<0.094	<0.05	<0.015	<0.02	368
	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	509
MW017A	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	69.7
	06/29/06	<0.001	0.0012	0.0014	<0.003	<0.095	<0.05	<0.015	<0.02	87.8
	03/21/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.005	<0.015	<0.02	83.7
WELL WAS PLUGGED AND ABANDONED										

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	-----	-----	0.05	0.05	250
MW018A	05/31/05	ND	ND	ND	ND	ND	ND	-----	-----	-----
	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	284
	06/29/06	<0.001	0.0023	0.0027	<0.003	<0.095	<0.05	<0.015	<0.02	318
	04/02/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	283
	09/13/07	<0.001	<0.001	<0.001	<0.003	0.100	<0.05	<0.015	<0.02	212
	03/24/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	233
	03/18/09	0.0079	0.0029	0.0013	<0.003	<0.094	<0.05	<0.015	<0.02	219
	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	304
MW019A	01/23/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	385
	06/30/06	<0.001	0.0023	0.0022	<0.003	<0.094	<0.05	<0.015	<0.02	360
	04/04/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	343
	09/14/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	306
	03/26/08	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	<0.015	<0.02	398
	08/07/08	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	394
	03/17/09	0.011	0.0039	0.0015	<0.003	<0.096	<0.05	<0.015	<0.02	321
	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	491
MW020A	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	521
	06/30/06	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	579
	04/04/07	<0.001	<0.001	<0.001	<0.003	0.120	<0.05	0.0185	<0.02	862
	09/18/07	<0.001	<0.001	<0.001	<0.003	0.100	<0.05	<0.015	0.024	708
	03/26/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	789
	08/06/08	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	<0.015	<0.02	867
	03/19/09	0.0056	0.0022	<0.001	<0.003	0.150	<0.05	0.0173	<0.02	1060
	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	1110
MW021A	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0307	0.026	6110
	06/30/06	<0.001	<0.001	<0.001	<0.003	0.400	<0.05	0.0326	0.033	7720
	04/09/07	<0.001	<0.001	<0.001	<0.003	1.200	<0.05	<0.015	<0.020	3350
	09/19/07	<0.001	<0.001	<0.001	<0.003	0.560	<0.05	0.0261	0.027	8180
	04/01/08	0.031	0.0057	0.0017	<0.003	0.700	0.091	0.0365	0.023	6440
	03/24/09	<0.001	<0.001	<0.001	<0.003	0.560	<0.05	0.0264	<0.020	6370
	08/06/09	<0.001	<0.001	<0.001	<0.003	0.810	0.054	0.0318	0.031	6020
MW022A	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0217	<0.02	70.5
	07/06/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	65.2
	03/30/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0181	<0.02	69
	09/14/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0211	<0.02	61.3
	04/02/08	0.024	0.0049	0.0015	<0.003	<0.095	0.068	0.0305	<0.02	67.9
	08/13/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.0306	0.026	75.3
	03/18/09	0.0036	0.0016	<0.001	<0.003	<0.097	<0.05	0.0275	0.022	61
	08/25/09	<0.001	<0.001	0.0026	<0.003	<0.096	<0.05	0.0315	0.026	68.7
MW023A	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	50.1
	06/26/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.005	<0.015	<0.02	48.5
	03/29/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	48.4
	09/12/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	46.2
	03/25/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	52.2
	08/12/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	52.3
	03/18/09	0.031	0.0073	0.002	<0.003	0.099	0.094	<0.015	<0.02	46.6
	08/20/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	50.6
MW024A	07/18/05	ND	ND	ND	ND	ND	18	-----	-----	-----
	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.043	0.04	181
	06/27/06	<0.001	0.0035	0.0043	0.0035	<0.096	<0.05	0.0446	0.02	203
	04/11/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.0242	0.021	170
	09/19/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.0254	0.023	180
	04/07/08	0.0046	0.0012	<0.001	<0.003	<0.095	<0.05	0.0279	0.044*	195
	08/13/08	0.0043	0.0047	0.010	<0.003	<0.1	<0.05	0.134	0.091	474
	03/25/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.162	0.15	530
MW039A	08/12/09	0.002	0.0013	<0.001	<0.003	0.24	<0.05	0.0307	0.034	63.5
	01/06/05	ND	ND	ND	ND	ND	ND	-----	-----	-----
	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.198	0.18	312
	07/06/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.217	0.21	324
	04/12/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.178	0.18	299
	04/03/08	0.038	0.0059	0.0015	<0.003	<0.095	0.100	0.285	0.24	405
	04/02/09	<0.001	<0.001	0.0022	<0.003	<0.096	<0.05	0.297	0.28	365

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM-WQCC Standard		0.01	0.750	0.750	0.620	---	---	0.05	0.05	250
MW040A	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	53.9
	06/28/06	<0.001	0.0021	0.0026	<0.003	<0.095	<0.005	<0.015	<0.02	52.8
	04/02/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	63.1
	09/12/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	54
	03/24/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	58.8
	08/07/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	55.3
	03/17/09	0.0068	0.0025	0.0011	<0.003	<0.098	<0.05	<0.015	<0.02	54.1
	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	54.1
MW041A	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.663	0.6	686
	07/07/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.52	0.53	616
	04/17/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.415	0.4	509
	04/15/08	0.0038	<0.001	<0.001	<0.003	1.50	<0.05	0.393	0.35	530
	04/01/09	0.0019	0.004	0.011	0.0031	<0.096	0.072	0.380	0.35	449
MW042A	01/19/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.015	0.02	5.3
	06/22/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.156	0.14	3730
	04/17/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.172	0.16	4010
	04/02/08	0.010	0.0025	<0.001	<0.003	<0.095	<0.05	0.268	0.26	3520
	03/31/09	<0.001	<0.001	<0.001	<0.003	0.120	<0.05	0.351	0.31	2990
MW046A	01/11/05	ND	ND	ND	ND	0.46	ND	---	0.005	580
	05/24/05	0.005	ND	ND	ND	0.35	ND	---	---	570
	01/26/06	0.0019	<0.001	<0.001	<0.003	<0.6	<0.6	0.387	0.38	676
	07/12/06	<0.001	<0.001	<0.001	<0.003	0.330	<0.05	0.441	0.44	637
	04/17/07	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.586	0.45	595
	04/02/08	0.0087	0.0024	<0.001	<0.003	0.097	<0.05	0.485	0.48	676
	03/31/09	<0.001	<0.001	<0.001	<0.003	0.280	<0.05	0.591	0.56	568
	06/07/05	ND	ND	ND	ND	ND	ND	---	---	540
MW048SA	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.171	0.17	437
	07/11/06	<0.001	<0.001	<0.001	<0.003	<0.094	<0.05	0.176	0.17	586
	04/10/07	<0.001	<0.001	<0.001	<0.003	NA	<0.05	0.228	0.21	453
	09/20/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.253	0.23	464
	04/01/08	0.0069	0.0019	<0.001	<0.003	<0.099	<0.05	0.272	0.26	497
	08/20/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.305	0.32	510
	03/26/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.294	0.3	589
	08/12/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.31	0.32	492
	01/06/05	ND	ND	ND	ND	ND	ND	---	0.065	3200
	06/06/05	ND	ND	ND	ND	ND	ND	---	---	2700
MW049SA	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0624	0.06	2770
	07/11/06	<0.001	<0.001	<0.001	<0.003	0.170	<0.05	0.0701	0.061	2480
	04/10/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.0823	0.078	2320
	04/08/08	0.0023	<0.001	<0.001	<0.003	<0.098	<0.05	0.0953	0.094	2260
	03/26/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.103	0.11	2210
MW050SA	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.187	0.19	1210
	07/10/06	<0.001	<0.001	<0.001	<0.003	0.690	<0.05	0.215	0.2	1500
	04/09/07	<0.001	<0.001	<0.001	<0.003	0.280	<0.05	0.285	0.22	1230
	04/01/08	0.017	0.0041	0.0015	<0.003	0.560	0.052	0.27	0.22	1500
	03/25/09	<0.001	<0.001	<0.001	<0.003	0.74	<0.05	0.262	0.24	1260
MW051SA	01/11/05	ND	ND	ND	ND	ND	ND	---	0.56	---
	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.694	0.66	1490
	07/11/06	<0.001	<0.001	<0.001	<0.003	<0.094	<0.05	0.688	0.69	1630
	04/17/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.895	0.68	1540
	04/09/08	0.0013	<0.001	<0.001	<0.003	<0.095	<0.05	0.654	0.63	1370
MW052SA	04/02/09	<0.001	<0.001	0.0023	<0.003	0.210	<0.05	0.721	0.70	1240
	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.4	0.39	2440
	07/11/06	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.373	0.36	1590
	04/10/07	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	0.378	0.36	1600
	04/08/08	0.0014	<0.001	<0.001	<0.003	0.260	<0.05	0.376	0.30	1690
MW052SA	03/26/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.34	0.35	1980

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALEN	CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	---	---	0.05	0.05	---	250
MW053SA	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	---	266
	07/11/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	---	249
	04/05/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	---	228
	09/20/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	---	193
	03/26/08	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	<0.015	<0.02	---	161
	03/18/09	0.0035	0.0015	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	---	194
	08/20/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	---	205
MW054SA	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.262	0.27	---	838
	07/11/06	<0.001	<0.001	<0.001	<0.003	<0.094	<0.05	0.148	0.15	---	807
	04/10/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.145	0.14	---	868
	09/20/07	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	0.138	0.12	---	844
	04/08/08	0.0013	<0.001	<0.001	<0.003	<0.097	<0.05	0.121	0.11	---	925
	08/20/08	<0.001	<0.001	0.0011	<0.003	<0.1*	<0.05	0.121	0.13	---	985
	03/26/09	<0.001	<0.001	<0.001	<0.003	<0.095*	<0.05	0.111	0.11	---	978
	08/10/09	<0.001	<0.001	<0.001	<0.003	0.11	<0.05	0.107	0.1	---	834
MW055SA	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.213	0.21	---	705
	06/28/06	<0.001	0.0039	0.0039	0.0032	<0.097	<0.05	0.145	0.15	---	113
	04/10/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.202	0.19	---	593
	09/20/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.227	0.19	---	576
	04/09/08	0.0016	<0.001	<0.001	<0.003	<0.095	<0.05	0.230	0.22	---	589
	08/19/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.224	0.22	---	582
	03/26/09	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.228	0.25	---	719
	08/12/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.243	0.25	---	589
MW056SA	01/26/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.432	0.4	---	1330
	07/12/06	<0.001	0.0012	0.0011	<0.003	0.220	<0.05	0.375	0.42	---	1460
	04/11/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.323	0.28	---	1320
	09/21/07	<0.001	<0.001	<0.001	<0.003	0.170	<0.05	0.445	0.41	---	1470
	04/09/08	0.0016	<0.001	<0.001	<0.003	<0.095	<0.05	0.417	0.40	---	1400
	08/19/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.365	0.35	---	1540
	03/25/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.402	0.41	---	1230
	08/12/09	<0.001	<0.001	<0.001	<0.003	0.160	<0.05	0.398	0.41	---	1330
MW057SA	06/01/05	ND	ND	ND	ND	ND	ND	---	---	---	240
	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	---	196
	06/28/06	<0.001	0.0031	0.0035	0.0031	<0.97	<0.05	<0.015	<0.02	---	139
	03/29/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	---	218
	09/12/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0201	<0.02	---	232
	03/27/08	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.0493	0.034	---	548
	08/06/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0478	0.052	---	472
	03/17/09	0.0062	0.0024	0.0011	<0.003	<0.099	<0.05	0.0404	0.03	---	324
MW062A	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0393	0.034	---	581
	01/24/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	---	64
	06/27/06	0.0019	0.011	0.010	0.0086	<0.096	0.097	<0.015	<0.02	---	64.5
	04/20/07	0.0034	<0.001	0.0023	<0.003	<0.097	<0.05	<0.015	<0.02	---	56.8
	09/14/07	0.001	0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	---	60.4
	04/09/08	0.003	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	---	62.5
	08/18/08	<0.001	<0.001	0.0013	<0.003	<0.096	<0.05	<0.015	<0.02	---	60.2
MW063A	04/02/09	<0.001	<0.001	0.0029	<0.003	<0.096	<0.05	<0.015	<0.02	---	57.2
	08/03/09	<0.001	<0.001	<0.001	<0.003	0.44	0.11	<0.015	<0.02	---	62.1
	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	---	56
	06/27/06	0.004	0.020	0.014	0.012	<0.095	0.140	<0.015	<0.02	---	55.1
	04/20/07	0.0086	<0.001	<0.003	<0.003	<0.098	<0.05	<0.015	<0.02	---	54.3
	09/11/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	---	121
	04/09/08	0.0052	0.0012	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	---	55.9
MW064SA	08/18/08	<0.001	<0.001	0.0014	<0.003	<0.096	<0.05	<0.015	<0.02	---	55.5
	04/02/09	<0.001	<0.001	0.0025	<0.003	<0.095	<0.05	<0.015	<0.02	---	66.2
	08/04/09	<0.001	<0.001	<0.001	<0.003	0.14	0.051	<0.015	<0.02	---	56.1
	02/02/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.169	0.14	---	56
	07/14/06	<0.001	<0.001	<0.001	<0.003	0.150	<0.05	0.128	0.14	---	55.1
	03/21/07	<0.001	<0.001	<0.001	<0.003	0.170	<0.005	0.179	0.16	---	1090
	09/06/07	<0.001	<0.001	<0.001	<0.003	0.220	<0.05	0.164	0.15	---	1130
MW064SA	03/25/08	<0.001	<0.001	<0.001	<0.003	0.560	<0.05	0.0393	0.066	---	1540
	08/05/08	<0.001	<0.001	<0.001	<0.003	0.730	<0.05	0.0386	0.073	---	1390
	03/17/09	<0.001	<0.001	<0.001	<0.003	0.270	<0.05	0.127	0.11	---	1190
	08/17/09	<0.001	<0.001	<0.001	<0.003	0.410	<0.05	0.097	0.098	---	1500

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	-----	-----	0.05	0.05	250
MW065SA	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0439	0.037	1400
	06/28/06	<0.001	0.0034	0.0038	0.0032	<0.096	<0.05	0.0397	0.032	1180
	04/10/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0571	0.058	1140
	09/12/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0675	0.065	599
	04/08/08	0.0014	<0.001	<0.001	<0.003	<0.099	<0.05	0.0839	0.045	1140
	08/19/08	<0.001	<0.001	0.0011	<0.003	<0.1	<0.05	0.0893	0.083	1120
	03/25/09	<0.001	<0.001	0.0011	<0.003	<0.096	<0.05	0.0884	0.079	1070
	08/06/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	0.0741	0.066	967
MW066SA	01/25/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.177	0.19	1780
	07/11/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0317	0.021	1580
	09/20/07	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	<0.015	<0.02	1160
	08/19/08	<0.001	<0.001	0.0011	<0.003	<0.1	<0.05	<0.015	<0.02	1090
	03/26/09	<0.001	<0.001	0.0011	<0.003	<0.097	<0.05	<0.015	<0.02	1160
	08/06/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	<0.015	<0.02	966
MW067SA	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	233
	07/10/06	<0.001	<0.001	<0.001	<0.003	<0.12	<0.05	<0.015	<0.02	229
	04/05/07	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	<0.015	<0.02	210
	09/13/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	187
	03/27/08	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	194
	08/11/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	199
	03/19/09	0.0032	0.0014	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	198
	08/20/09	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	186
MW070A	01/27/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	61.8
	06/22/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	45.7
	03/29/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	46.4
	09/11/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	283
	03/25/08	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	54.2
	08/05/08	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	<0.015	<0.02	45
	03/16/09	0.038	0.010	0.0032	<0.003	<0.096	0.110	<0.015	<0.02	45.6
	08/20/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	46.3
MW071SA	01/06/05	ND	ND	ND	ND	ND	ND	----	----	----
	01/25/06	0.031	0.0011	0.003	0.030	1.1	0.60	<0.015	<0.02	1050
	07/12/06	<0.001	<0.001	<0.001	<0.003	0.480	0.095	<0.015	<0.02	1080
	04/03/07	<0.001	<0.001	<0.001	<0.003	0.480	<0.05	<0.015	<0.02	998
	09/19/07	<0.001	<0.001	<0.001	<0.003	0.700	<0.05	<0.015	<0.02	1040
	03/27/08	<0.001	<0.001	<0.001	<0.003	0.200	<0.05	<0.015	<0.02	1180
	08/12/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.0193	<0.02	1170
	03/24/09	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.108	0.097	929
MW072SA	01/23/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	340
	06/28/06	<0.001	0.0025	0.0030	<0.003	<0.096	<0.05	<0.015	<0.02	389
	04/03/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	331
	09/14/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	306
	03/27/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	327
	08/12/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	344
	03/17/09	0.014	0.0044	0.0016	<0.003	<0.097	<0.05	<0.015	<0.02	301
	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	351
MW073SA	01/20/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	355
	06/28/06	<0.001	0.0024	0.0029	<0.003	<0.097	<0.05	<0.015	<0.02	376
	04/03/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	302
	09/13/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	283
	03/27/08	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	287
	08/12/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	273
	03/17/09	0.0078	0.0029	0.0013	<0.003	<0.098	<0.05	<0.015	<0.02	283
	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	732
MW074SA	12/07/04	ND	ND	ND	ND	ND	ND	----	----	----
	05/31/05	ND	ND	ND	ND	ND	ND	----	----	----
	01/18/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	623
	06/20/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	659
	04/03/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	653
	09/06/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	638
	03/20/08	<0.001	<0.001	0.0018	<0.003	<0.096	<0.05	<0.015	<0.02	607
	08/06/08	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	<0.015	<0.02	586
	03/16/09	0.023	0.0088	0.0022	<0.003	0.120	0.069	<0.015	<0.02	491
	08/24/09	<0.001	<0.001	<0.001	<0.003	<0.094	<0.05	<0.015	<0.02	634

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	---	---	0.05	0.05	250
MW075SA	01/19/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	795
	06/21/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	826
	04/03/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	641
	09/06/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	607
	03/20/08	<0.001	<0.001	0.0013	<0.003	<0.096	<0.05	<0.015	<0.02	660
	08/06/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	645
	03/16/09	0.015	0.0049	0.0018	<0.003	<0.095	<0.05	<0.015	<0.02	598
	08/24/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	586
MW076SA	06/01/05	ND	ND	ND	ND	ND	ND	---	---	---
	01/19/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	463
	06/21/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	500
	04/03/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	489
	09/07/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	506
	03/20/08	<0.001	<0.001	0.0016	<0.003	<0.098	<0.05	<0.015	<0.02	547
	08/06/08	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	533
	03/16/09	0.012	0.0041	0.0016	<0.003	<0.095	<0.05	<0.015	<0.02	536
MW077SA	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	819
	12/08/04	0.052	0.071	0.039	0.25	ND	ND	---	---	---
	06/01/05	ND	ND	ND	ND	ND	ND	---	---	---
	01/19/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.03	0.028	1760
	06/21/06	<0.001	<0.001	<0.001	<0.003	0.120	<0.05	0.0343	0.023	1660
	04/11/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.0301	0.028	1900
	09/06/07	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.0197	<0.02	1760
	04/08/08	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.0233	0.029	1680
MW078SA	08/19/08	<0.001	<0.001	0.0014	<0.003	0.110	<0.05	0.0481	0.044	1960
	03/25/09	<0.001	<0.001	<0.001	<0.003	0.097	<0.05	0.0294	0.022	1170
	08/18/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.0157	<0.02	755
	12/08/04	0.05	0.084	0.069	0.22	ND	ND	---	---	---
	01/19/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	191
	06/21/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	201
	04/05/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	191
	09/07/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	155
MW079SA	03/26/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	191
	08/11/08	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	0.005	<0.02	158
	03/18/09	0.0032	0.0013	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	172
	08/20/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	159
	02/03/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	917
	07/18/06	<0.001	<0.001	<0.001	<0.003	0.140	<0.05	<0.015	<0.02	774
	03/28/07	<0.001	<0.001	<0.001	<0.003	0.140	<0.05	<0.015	<0.02	508
	09/07/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	418
MW080SA	04/02/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	373
	08/06/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.0195	<0.02	340
	03/24/09	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	<0.015	<0.02	322
	08/18/09	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	398
	02/02/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	615
	07/18/06	<0.001	<0.001	<0.001	<0.003	0.130	<0.05	<0.015	<0.02	504
	03/28/07	<0.001	<0.001	<0.001	<0.003	0.260	0.059	<0.015	<0.02	403
	09/07/07	<0.001	<0.001	<0.001	<0.003	0.130	<0.05	<0.015	<0.02	344
MW081SA	04/02/08	<0.001	<0.001	<0.001	<0.003	0.250	0.071	<0.015	<0.02	332
	08/06/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.0195	<0.02	305
	03/23/09	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	280
	08/18/09	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	<0.015	<0.02	735
	02/02/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	<0.015	<0.02	1060
	07/18/06	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	1120
	03/28/07	<0.001	<0.001	<0.001	<0.003	0.170	<0.05	<0.015	<0.02	765
	09/07/07	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	<0.015	<0.02	582
MW082SA	04/02/08	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	<0.015	<0.02	483
	08/06/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.0195	<0.02	439
	03/23/09	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	<0.015	<0.02	510
	08/18/09	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	1340
	02/03/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.0364	<0.02	940
	07/14/06	<0.001	<0.001	<0.001	<0.003	0.480	<0.05	<0.015	<0.02	1210
	03/22/07	0.0015	<0.001	<0.001	<0.003	0.370	<0.05	<0.0151	<0.02	1120
	09/06/07	<0.001	<0.001	<0.001	<0.003	0.450	<0.05	<0.015	<0.02	1120
MW082SA	03/26/08	<0.005	<0.005	<0.005	<0.015	0.420	0.270	<0.015	<0.02	1200
	08/06/08	<0.001	<0.001	<0.001	<0.003	0.280	<0.05	0.0195	<0.02	1180
	03/18/09	<0.001	<0.001	<0.001	<0.003	0.300	0.073	<0.015	<0.02	1380
	08/17/09	<0.001	<0.001	<0.001	<0.003	0.250	<0.05	<0.015	<0.02	366

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM/VQCC Standard		0.01	0.750	0.750	0.620			0.05	0.05	250
MW083SA	02/03/06	0.011	<0.005	0.008	<0.015	<6	<45	0.0466	<0.02	1080
	07/14/06	<0.001	<0.001	<0.001	<0.003	1.000	0.055	0.0183	<0.02	1170
	03/22/07	0.0062	<0.001	<0.001	<0.003	0.430	<0.05	0.0189	0.08	1080
	09/06/07	0.0018	<0.001	<0.001	<0.003	0.510	<0.05	<0.015	<0.5	1090
	03/25/08	<0.005	<0.005	<0.005	<0.015	0.690	<0.25	<0.015	<0.2	1160
	08/06/08	<0.001	<0.001	<0.001	<0.003	0.460	<0.05	0.0195	<0.02	1710
	03/18/09	<0.001	<0.001	<0.001	<0.003	0.360	<0.05	<0.015	<0.02	1470
	08/17/09	<0.001	<0.001	<0.001	<0.003	0.420	<0.05	<0.015	<0.02	1980
MW084SA	02/03/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.103	0.16	2500
	07/14/06	<0.001	<0.001	<0.001	<0.003	0.140	<0.05	0.0191	0.13	1720
	03/21/07	<0.001	<0.001	<0.001	<0.003	0.120	<0.05	0.187	0.15	2090
	09/06/07	<0.001	<0.001	<0.001	<0.003	0.130	<0.05	0.192	0.18	2290
	03/25/08	<0.001	<0.001	<0.001	<0.003	0.150	<0.05	0.192	0.2	2720
	08/05/08	<0.001	<0.001	<0.001	<0.003	0.300	<0.05	0.18	0.17	2430
	03/17/09	<0.001	<0.001	<0.001	<0.003	0.150	<0.05	0.176	0.17	2530
	08/13/09	<0.001	<0.001	<0.001	<0.003	0.210	<0.05	0.0982	0.11	1980
MW085SA	02/03/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.103	<0.02	1480
	07/14/06	<0.001	<0.001	<0.001	<0.003	0.310	<0.05	0.0191	<0.02	1840
	03/21/07	<0.001	<0.001	<0.001	<0.003	0.480	<0.05	0.0256	<0.02	1380
	09/06/07	<0.001	<0.001	<0.001	<0.003	0.880	<0.05	0.0176	<0.02	1270
	03/25/08	<0.001	<0.001	<0.001	<0.003	0.490	<0.05	0.0266	<0.02	1740
	08/05/08	<0.001	<0.001	<0.001	<0.003	0.280	<0.05	0.0238	<0.02	1620
	03/18/09	<0.001	<0.001	<0.001	<0.003	7.2	<0.05	0.0199	<0.02	1160
	08/17/09	<0.001	<0.001	<0.001	<0.003	0.44	<0.05	0.0156	<0.02	1300
MW086SA	10/07/04	ND	ND	ND	ND	ND	ND	----	----	----
	01/27/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.058	0.052	1170
	07/12/06	<0.001	<0.001	<0.001	<0.003	<0.094	<0.05	0.115	0.13	1300
	04/11/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.0787	0.075	1220
	09/21/07	<0.001	0.0032	0.0089	<0.003	<0.095	<0.05	0.121	0.12	1010
	04/08/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0578	0.057	1090
	08/19/08	<0.001	<0.001	0.0011	<0.003	<0.1	<0.05	0.0762	0.078	1250
	03/25/09	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.0512	0.047	1390
MW087A	08/10/09	<0.001	<0.001	<0.001	<0.003	0.120	<0.05	0.0601	0.063	1330
	09/14/04	ND	ND	ND	ND	ND	ND	4.23	----	----
	02/06/06	<0.005	<0.005	<0.005	<0.15	<0.6	<0.6	0.449	<0.5	1560
	07/18/06	<0.005	<0.005	<0.005	<0.015	6.400	0.270	0.144	<0.02	1100
	04/13/07	<0.002	<0.001	<0.001	<0.003	5.100	2.400	0.173	<0.02	1160
	04/15/08	<0.005	<0.005	<0.005	<0.015	4.80	<0.25	0.187	<1	1550
	03/30/09	<0.005	<0.005	<0.005	<0.015	1.7	<0.25	0.233	<0.2	1060
MW089SA	02/09/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	1.36	0.95	709
	07/21/06	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	1.11	1.1	787
	04/04/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.591	1.0	785
	04/09/08	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	1.15	1.1	909
	03/26/09	<0.001	<0.001	<0.001	<0.003	<0.10	<0.05	1.07	1.1	1010
MW090SA	02/09/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.437	0.45	575
	07/21/06	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.42	0.52	630
	04/03/07	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	0.484	0.49	833
	04/14/08	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	0.569	0.59	850
	03/17/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	0.634	0.54	652
	08/11/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.58	0.52	648
MW091SA	02/09/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.748	0.67	679
	07/24/06	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.856	0.77	732
	04/05/07	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	1.05	1.1	864
	04/07/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	1.16	0.57	819
	03/24/09	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.821	0.88	834
MW092SA	02/09/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	1.16	1	662
	07/24/06	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.901	0.76	607
	04/05/07	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	1.3	1.4	841
	04/09/08	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	1.61	1.3	740
	03/24/09	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	1.48	1.5	905
MW093SA	02/09/06	<0.001	<0.001	<0.001	<0.003	<0.6	<0.6	0.689	0.62	684
	07/24/06	<0.001	<0.001	<0.001	<0.003	0.110	<0.05	0.477	0.42	564
	04/05/07	<0.001	<0.001	<0.001	<0.003	0.340	<0.05	0.615	0.97	732
	04/09/08	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	1.96	1.7	831
	03/24/09	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	2	2	949
IWO03	02/06/06	<0.1	<0.1	<0.1	<0.3	----	----	0.136	<2	1100
	07/25/06	<0.01	<0.01	<0.01	<0.2	720	3.2	0.0305	<2	1080
	04/09/07	<0.05	<0.05	<0.05	<0.015	2.400	<2.5	0.075	<2	1130
	04/03/08	<0.01	<0.01	<0.01	<0.03	3.100	<0.5	0.075	<2	1130
	03/23/09	<0.005	<0.005	<0.005	<0.015	2.100	<0.25	0.0152	<0.20	1050

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	-----	-----	0.05	0.05	250
IWO04	02/06/06	<0.025	<0.025	<0.025	<0.075	-----	-----	0.0693	<2	1430
	07/25/06	<0.01	<0.01	<0.01	<0.03	440	1.6	0.0216	<2	1320
	04/09/07	<0.005	<0.005	<0.005	<0.015	0.720	<0.25	0.0176	<2	1400
	04/03/08	<0.005	<0.005	<0.005	<0.015	0.350	<0.25	<0.015	NRS	1610
	03/23/09	<0.001	<0.001	<0.001	<0.003	0.390	<0.05	0.0182	<0.02	1570
IWO05	02/06/06	<0.1	<0.1	<0.1	<0.3	-----	-----	0.591	<2	781
	07/26/06	<0.01	<0.01	<0.01	<0.03	1500	24	0.252	<2	887
	03/27/07	<0.1	<0.1	<0.1	<0.3	3600	5000	0.135	<2	964
	04/12/07	<0.1	<0.1	<0.1	<0.3	3.600	<5	0.102	<2	1210
	04/01/08	<0.005	<0.005	<0.005	<0.015	3.200	<0.25	0.0781	<2	1140
IWO06	03/23/09	<0.005	<0.005	<0.005	<0.015	1.500	<0.25	0.0311	<0.1	1690
IWO06	02/07/06	<0.1	<0.1	<0.1	<0.3	-----	-----	0.286	<2	628
	07/26/06	<0.01	<0.01	<0.01	<0.03	32	2400	0.0643	<2	772
	03/27/07	<0.1	<0.1	<0.1	<0.3	2.1	5000	0.0592	<2	832
	04/12/07	<0.1	<0.1	<0.1	<0.3	2.100	<5	0.04	<2	900
IWO07	04/01/08	<0.005	<0.005	<0.005	<0.015	1.400	0.310	0.0287	<1	1000
	03/19/09	<0.005	<0.005	<0.005	<0.015	0.670	<0.25	0.016	<1	915
IWO07	02/07/06	<0.1	<0.1	<0.1	<0.3	-----	-----	0.185	<2	572
	07/26/06	<0.025	<0.025	<0.025	<0.075	3600	21000	0.118	<2	527
	03/28/07	<0.1	<0.1	<0.1	<0.3	3600	13.000	0.171	<2	837
	04/01/08	<0.01	<0.01	<0.01	<0.03	3000	8.300	0.114	<2	714
	03/19/09	0.0069	<0.005	<0.005	<0.015	6.6	0.400	0.0706	<2	880
IWO08	02/07/06	<0.1	<0.1	<0.1	<0.3	-----	-----	0.128	<2	382
	07/26/06	<0.025	<0.025	<0.025	<0.075	6100	7700	0.023	<2	572
	03/23/07	<0.001	<0.001	<0.001	<0.003	3.900	0.082	0.0249	0.1	574
	04/01/08	<0.005	<0.005	<0.005	<0.015	1.700	0.360	0.0166	<1	576
	03/19/09	<0.005	<0.005	<0.005	<0.015	0.910	<0.250	<0.015	<1	604
IWO09	02/07/06	<0.1	<0.1	<0.1	<0.3	-----	-----	0.121	<2	606
	07/27/06	<0.025	<0.025	<0.025	<0.075	2100000	3900	0.0557	<2	434
	03/23/07	<0.025	<0.001	0.0048	<0.1	<5000	14.000	-----	<0.4	-----
	03/31/08	<0.01	<0.005	<0.005	<0.015	-----	6.000	0.0438	NRS	694
	03/19/09	0.012	<0.010	0.0059	<0.030	NA	3.400	<0.075	NA	NA
IWO10	02/07/06	<0.1	<0.1	<0.1	<0.3	-----	-----	0.11	<2	970
	07/27/06	<0.025	<0.025	<0.025	<0.075	1200	1300	0.0236	<2	971
	03/23/07	<0.005	<0.001	<0.001	<0.003	0.650	<0.05	0.0198	0.2	1020
	03/31/08	<0.005	<0.005	<0.005	<0.015	<0.19	<0.025	<0.015	<0.5*	1130
	03/19/09	<0.005	<0.005	<0.005	<0.015	0.120	<0.250	<0.015	<0.02*	1150
IWO11	02/08/06	<0.1	<0.1	<0.1	<0.3	-----	-----	0.0694	<2	624
	07/26/06	<0.025	<0.025	<0.025	<0.075	1700	18000	0.0272	<2	908
	03/22/07	<0.1	<0.1	<0.1	<0.3	110	<5	0.0317	<1	980
	03/31/08	<0.005	<0.005	<0.005	<0.015	5.100	<0.025	0.0263	<2.0*	1080
	03/18/09	<0.005	<0.005	<0.005	<0.015	2.200	<0.250	<0.015	<0.002*	1000
IWO13	02/08/06	<0.1	<0.1	<0.1	<0.3	-----	-----	0.418	<2	1160
	07/27/06	<0.025	<0.025	<0.025	<0.2	190	1300	0.0585	<2	952
	03/22/07	<0.002	<0.001	0.0027	<0.02	390	0.86	0.0311	<1	890
	03/28/08	<0.005	<0.005	<0.005	<0.015	0.690	<0.025	<0.015	<0.2	1050
	03/18/09	<0.001	<0.001	<0.001	<0.003	0.120	<0.050	<0.015	<0.02	1020
IWO14	02/13/06	<0.1	<0.1	<0.1	<0.3	-----	-----	0.199	<10	666
	07/25/06	98	<0.025	<0.5	<0.03	2400	70000	0.072	<2	964
	03/26/07	<0.1	<0.1	<0.1	<0.3	1700	9.9	0.0494	<2	1080
	03/26/08	<0.05	<0.05	<0.05	<0.15	170.000	<2.5	0.075	<1	1170
	03/18/09	<0.005	<0.005	<0.005	<0.015	4.100	<0.25	0.0188	<0.002	1190
IWO15	02/09/06	<0.1	<0.1	<0.1	<0.003	-----	-----	0.301	<2	1000
	07/25/06	<0.01	<0.01	<0.01	<0.003	1600	5200	0.157	<2	1050
	04/09/07	<0.05	<0.05	<0.05	<0.003	20	<2.5	0.165	<2	1060
	04/03/08	<0.01	<0.01	<0.01	<0.003	3.100	<0.5	0.075	<2	1040
	03/23/09	0.0076	<0.005	<0.005	<0.015	2.600	<0.25	0.0566	<2	984
IWO16	02/08/06	<0.1	<0.1	<0.1	<0.003	-----	-----	0.138	<2	848
	07/25/06	<0.01	<0.01	<0.01	<0.003	2600000	4400	0.0484	<2	987
	03/28/07	<0.1	<0.1	<0.1	<0.003	19	<5	0.0293	<1	848
	04/02/08	<0.005	<0.005	<0.005	<0.015	3.500	<0.250	0.0221	<2	769
	03/24/09	<0.005	<0.005	<0.005	<0.015	4.500	<0.25	0.0202	<2	677
IWO18	02/06/06	2.2	<0.001	<0.001	<0.003	-----	-----	2.88	0.27	1340
	07/21/06	<0.001	<0.001	<0.001	<0.003	3800	50	<0.015	<0.02	400
	04/09/07	<0.001	<0.001	<0.001	<0.003	2.2	<0.05	<0.015	<0.02	175
	04/09/08	<0.001	<0.001	<0.001	<0.003	2.300	<0.05	1.08	0.29	1140
	03/24/09	<0.001	<0.001	<0.001	<0.003	3.100	<0.05	0.248	0.18	1130

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	---	---	0.05	0.05	250
IWO19	02/07/06	<0.001	<0.001	<0.001	<0.003	---	---	1.06	0.88	1780
	07/24/06	<0.001	<0.001	<0.001	<0.003	930	50	1.14	0.99	1800
	04/06/07	<0.001	<0.001	<0.001	<0.003	0.740	<0.05	1.24	1.1	1620
	04/08/08	<0.001	<0.001	<0.001	<0.003	0.47	<0.05	1.51	1.4	1680
	03/25/09	<0.001	<0.001	<0.001	<0.003	0.61	<0.05	1.57	1.4	1730
IWO20	02/07/06	<0.001	<0.001	<0.001	<0.003	---	---	0.777	0.76	999
	07/24/06	<0.001	<0.001	<0.001	<0.003	310	50	0.898	0.8	521
	04/10/07	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	1.51	1.5	1200
	04/08/08	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	1.79	1.7	1180
	03/25/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	2	1.9	1350
IWO21	02/07/06	<0.001	<0.001	<0.001	<0.003	---	---	0.701	0.68	692
	07/24/06	<0.001	<0.001	<0.001	<0.003	97	50	0.93	0.81	673
	04/05/07	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	1.14	1.2	753
	04/08/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	1.73	1.6	859
	03/25/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	1.74	1.6	1000
IWO22	02/07/06	<0.001	<0.001	<0.001	<0.003	---	---	0.526	0.5	624
	07/25/06	<0.001	<0.001	<0.001	<0.003	94	50	0.489	0.46	662
	04/10/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.505	0.52	713
	04/07/08	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	0.785	0.82	781
	03/25/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	0.525	0.53	670
IWO23	07/25/06	<0.001	<0.001	<0.001	<0.003	97	50	0.158	0.15	500
	04/10/07	0.001	<0.001	<0.001	<0.003	<0.099	<0.05	0.206	0.21	620
	04/07/08	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.248	0.20	659
	03/16/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.285	0.25	650
	08/11/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	0.3	0.28	637
IWO24	02/08/06	<0.001	<0.001	<0.001	<0.003	95	---	1.28	1.2	868
	04/03/07	<0.001	<0.001	<0.001	<0.003	0.120	<0.05	1.12	1.3	827
	04/15/08	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	1.41	1.3	808
	03/16/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	1.31	0.91	985
	08/11/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	1.47	1.2	1020
IWO25	02/08/06	<0.001	<0.001	<0.001	<0.003	---	---	0.377	0.39	584
	07/21/06	<0.001	<0.001	<0.001	<0.003	95	50	0.845	0.83	632
	04/14/08	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	1.19	1.2	801
	03/16/09	<0.001	0.0015	0.001	0.0054	<0.097	<0.05	0.0479	<0.020	502
	08/13/09	<0.001	<0.001	0.001	0.0058	0.19	<0.05	0.0387	<0.020	582
IWO26	02/08/06	<0.001	<0.001	<0.001	<0.003	---	---	0.499	0.47	612
	07/21/06	<0.001	<0.001	<0.001	<0.003	95	50	0.618	0.6	583
	04/03/07	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0403	0.035	487
	03/16/09	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	<0.015	<0.020	518
	08/13/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	<0.015	<0.020	460
IWO27	02/08/06	<0.001	<0.001	<0.001	<0.003	---	---	0.591	0.57	789
	07/21/06	<0.001	<0.001	<0.001	<0.003	95	50	0.699	0.69	732
	04/04/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.0352	0.023	197
	04/14/08	<0.001	<0.001	<0.001	<0.003	<0.11	<0.05	0.41	0.42	575
	03/25/09	<0.001	<0.001	<0.001	<0.003	<0.098	<0.05	0.383	0.38	2880
IWO28	02/08/06	<0.001	<0.001	<0.001	<0.003	---	---	0.991	0.99	682
	07/21/06	<0.001	<0.001	<0.001	<0.003	95	50	0.652	0.62	549
	04/04/07	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.526	0.67	522
	04/15/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	0.727	0.74	625
	04/07/09	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	0.354	0.35	583
RW004A	02/10/06	<0.05	<0.05	<0.05	<0.150	---	---	0.015	<0.08	138
	07/19/06	<0.01	<0.01	<0.01	<0.03	130	9900	0.0213	<0.02	147
	04/11/07	<0.1	<0.1	<0.1	<0.3	340	23	<0.075	<2.0	209
	04/16/08	<0.01	<0.005	<0.005	<0.015	890	22	0.0712	<1	258
	03/31/09	0.290	<0.01	0.230	0.034	710	19	0.0436	<0.2	291

TABLE 2
SUMMARY OF 2009 SUMMARY OF ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Sample Location	Date	Benzene	Toluene	Ethylbenzene	Xylenes	TPH-DRO	TPH-GRO	CHROMIUM	HEXAVALENT CHROMIUM	CHLORIDE
Standard Units		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard		0.01	0.750	0.750	0.620	---	---	0.05	0.05	250
WATER WELLS										
GOPWW2	01/19/06	<0.001	<0.001	<0.001	<0.003	---	---	<0.015	<0.02	1000
	06/28/06	2	7.9	5.8	4.8	82	150	<0.015	<0.02	1140
	04/23/07	0.0027	<0.001	0.0015	---	<0.098	<0.05	<0.015	<0.02	1130
	09/10/07	<0.001	<0.001	<0.001	<0.003	0.110	0.063	<0.015	<0.02	1320
	03/24/08	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	2130
	08/05/08	<0.001	<0.001	<0.001	<0.003	0.220	<0.05	<0.015	<0.02	1690
	03/17/09	<0.001	<0.001	<0.001	<0.003	<0.1	<0.05	<0.015	<0.02	1600
	08/18/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	1420
LORDWW	01/23/06	<0.001	<0.001	<0.001	<0.003	---	---	0.0677	<0.02	1260
	06/27/06	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	<0.015	<0.02	71.3
	04/05/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	0.148	<0.02	1540
	09/18/07	<0.001	<0.001	<0.001	<0.003	0.930	<0.5	<0.015	<0.02	1320
	03/26/08	<0.001	<0.001	<0.001	<0.003	0.280	<0.05	0.0664	<0.02	1470
	08/13/08	0.0083	0.0094	0.019	0.0039	<0.1	0.092	<0.015	<0.02	1380
	03/19/09	0.018	0.0045	0.0014	<0.003	<0.3	0.080	<0.015	<0.02	1610
	08/21/09	<0.001	<0.001	<0.001	<0.003	<0.095	<0.05	<0.015	<0.02	2040
ROLANDWW	04/06/09	Well is Inaccessible								
WOODELLWW	01/24/06	<0.001	<0.001	<0.001	<0.003	---	---	<0.015	<0.02	699
	06/27/06	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	602
	03/29/07	<0.001	<0.001	<0.001	<0.003	<0.097	<0.05	<0.015	<0.02	621
	04/15/08	<0.001	<0.001	<0.001	<0.003	<0.099	<0.05	0.0523	0.035	305
	08/21/08	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0254	<0.02	558
	03/24/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0296	0.022	690
	08/24/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0561	0.058	615
	08/24/09	<0.001	<0.001	<0.001	<0.003	<0.096	<0.05	0.0561	0.058	615
EPWW1	01/26/06	<0.001	<0.001	<0.001	<0.003	0.6	0.6	0.125	<0.02	79.6
	07/06/06	<0.001	<0.001	<0.001	<0.003	0.095	0.05	0.0259	<0.02	49.2
	04/06/09	<0.001	<0.001	<0.001	<0.003	0.520	<0.05	<0.015	<0.02	255

Notes:

Bold = Detections exceeding the New Mexico Water Quality Control Commission (NM WQCC)

Human Health or Domestic Water Supply Standards (if standards are available).

Sample Date followed by asterisk = Due to excessive foaming of the sample, normal reporting limits were not attained and preservation requirements were not met.

mg/L = milligrams per liter

NA = Not Analyzed

-- = Not Analyzed

< = less than - the number following the sign is the limit of quantitation, the smallest amount of analyte which can be reliably determined using the specific analytical test.

ND = Data gathered from previous report indicates the analytical result was "non-detect" with no method detection given.

* = Resampled on different date

TABLE 3
SUMMARY OF 2009 INORGANIC METALS – ANALYTICAL
RESULTS

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01	--	1.0	--	--	--	0.05	0.2	0.002	0.05	0.05	10
MW001	08/24/05	NA	NA	NA	225	0.76	NA	NA	NA	NA	0.64	NA	NA	NA	NA
	01/27/06	<0.02	0.0575	<0.005	276	2.74	NA	NA	NA	<0.02	0.832	<0.0002	<0.02	<0.005	<0.02
	07/13/06	<0.02	0.0587	<0.005	NA	2.18	NA	NA	NA	<0.015	0.766	NA	0.0252	<0.005	<0.02
	04/19/07	<0.02	NA	NA	281	4.09	NA	NA	NA	NA	0.855	NA	NA	NA	NA
	04/17/08	<0.02	NA	NA	429	0.644	98.8	15	410	NA	1.53	NA	NA	NA	NA
MW002	03/11/09	No Access (1st Half 2009) - Due to Construction Activity													
	01/24/06	<0.02	0.058	<0.005	208	0.999	NA	NA	NA	<0.02	0.0147	<0.0002	0.0222	<0.005	<0.02
	07/06/06	<0.02	0.0441	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0235	<0.005	<0.02
	04/12/07	<0.02	NA	NA	285	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/02/08	<0.02	NA	NA	355	<0.2	160	12.1	370	NA	<0.005	NA	NA	NA	NA
MW003	03/31/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/11/05	NA	NA	NA	327	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	01/25/06	<0.02	0.0297	<0.005	257	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0396	<0.005	<0.02
	07/07/06	<0.02	0.0251	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0486	<0.005	<0.02
	04/16/07	<0.02	NA	NA	216	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW004	04/03/08	<0.02	NA	NA	217	<0.2	62.4	7.27	390	NA	<0.005	NA	NA	NA	NA
	03/11/09	No Access (1st Half 2009) - Due to Construction Activity													
	08/15/05	NA	NA	NA	300	<0.4	NA	NA	NA	NA	0.04	NA	NA	NA	NA
	01/25/06	<0.02	0.0374	<0.005	422	<0.2	NA	NA	NA	<0.02	0.0209	<0.0002	0.0592	<0.005	<0.02
	07/07/06	<0.02	0.0376	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.0184	NA	0.0619	<0.005	<0.02
MW005	04/17/07	<0.02	NA	NA	482	<0.2	NA	NA	NA	NA	0.0163	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/15/08	<0.02	NA	NA	517	<0.2	136	15.2	577	NA	0.0055	NA	NA	NA	NA
	03/30/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0192	NA	NA	NA	NA
	08/25/05	NA	NA	NA	542	5.85	NA	NA	NA	NA	2.01	NA	NA	NA	NA
MW006	01/27/06	<0.02	0.484	<0.005	269	5.8	NA	NA	NA	<0.02	0.916	<0.0002	<0.02	<0.005	0.0358
	07/13/06	<0.02	0.366	<0.005	NA	5.32	NA	NA	NA	<0.015	0.807	NA	<0.02	<0.005	<0.02
	04/19/07	<0.02	NA	NA	302	9.94	NA	NA	NA	NA	0.837	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/17/08	<0.02	NA	NA	473	10.1	188	44.4	620	NA	1.88	NA	NA	NA	NA
MW007	04/07/09	<0.02	NA	NA	NA	8.04	NA	NA	NA	NA	0.807	NA	NA	NA	NA
	04/23/07	0.0264	NA	NA	375	29	NA	NA	NA	NA	3.24	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/17/08	0.0254	NA	NA	235	12.9	134	64.8	1460	NA	3.84	NA	NA	NA	NA
	04/07/09	0.0255	NA	NA	NA	16.1	NA	NA	NA	NA	2.13	NA	NA	NA	NA
MW007	08/11/05	NA	NA	NA	238	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	01/24/06	<0.02	0.0373	<0.005	200	0.287	NA	NA	NA	<0.02	0.0054	<0.0002	0.107	<0.005	<0.02
	07/07/06	<0.02	0.0247	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0764	<0.005	<0.02
	04/16/07	<0.02	NA	NA	169	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
MW007	04/03/08	<0.02	NA	NA	128	<0.2	42.6	5.69	265	NA	<0.005	NA	NA	NA	NA
	03/11/09	No Access (1st Half 2009) - Due to Construction Activity													

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01		1.0				0.05	-0.2	0.002	0.05	0.05	10
MW008	09/16/04	NA	NA	NA	646	<0.1	NA	NA	NA	NA	<0.05	NA	NA	NA	NA
	01/13/05	NA	NA	NA	449	<0.4	NA	NA	NA	NA	4.18	NA	NA	NA	NA
	07/06/05	NA	NA	NA	506	16	NA	NA	NA	NA	4.12	NA	NA	NA	NA
	02/09/06	<0.02	0.388	<0.005	414	69	NA	NA	NA	<0.02	4.12	<0.0002	<0.02	<0.005	<0.02
	07/18/06	0.0202	0.228	<0.005	NA	60.1	NA	NA	NA	<0.015	3.79	NA	<0.02	<0.005	<0.02
MW008M	04/03/07	0.0263	NA	NA	417	59.7	NA	NA	NA	NA	1.26	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	513	NA	0.508	NA	NA	NA	NA
	04/15/08	<0.02	NA	NA	405	36.3	127	14.4	NA	NA	1.36	NA	NA	NA	NA
	03/30/09	0.0363	NA	NA	NA	52.9	NA	NA	NA	NA	NA	NA	NA	NA	NA
	09/16/04	NA	NA	NA	645	2.4	NA	NA	NA	NA	<0.05	NA	NA	NA	NA
MW009	01/17/05	NA	NA	NA	841	24.2	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	07/06/05	NA	NA	NA	502	2.54	NA	NA	NA	NA	2.14	NA	NA	NA	NA
	02/10/06	0.0244	2.48	<0.005	860	17.4	NA	NA	NA	<0.02	4.99	<0.002	<0.02	<0.005	<0.02
	07/19/06	<0.02	3.07	<0.005	NA	5.26	NA	NA	NA	<0.015	3.79	NA	<0.02	<0.005	<0.02
	04/13/07	0.0261	NA	NA	465	55.8	NA	NA	NA	NA	0.869	NA	NA	NA	NA
MW009	09/01/07	NA	NA	NA	NA	NA	NA	NA	802	NA	NA	NA	NA	NA	NA
	04/16/08	0.0322	NA	NA	390	31	533	32.4	NA	NA	0.457	NA	NA	NA	NA
	03/31/09	0.0458	NA	NA	NA	22.8	NA	NA	NA	NA	0.318	NA	NA	NA	NA
	08/16/05	NA	NA	NA	281	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	02/02/06	<0.02	0.0524	<0.005	131	0.54	NA	NA	NA	<0.02	0.007	<0.002	0.0214	<0.005	<0.02
MW010	07/13/06	<0.02	0.0539	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.02	<0.005	<0.02
	09/01/07	NA	NA	NA	NA	NA	NA	NA	324	NA	NA	NA	NA	NA	NA
	04/15/08	<0.02	NA	NA	248	0.591	74.7	10.3	NA	NA	0.0085	NA	NA	NA	NA
	03/26/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/18/05	NA	NA	NA	733	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
MW011	01/24/06	<0.02	0.0573	<0.005	607	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0239	<0.005	<0.02
	06/30/06	<0.02	0.057	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/11/07	<0.02	NA	NA	641	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/18/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/07/08	<0.02	NA	NA	624	<0.2	255	20.2	703	NA	<0.005	NA	NA	NA	NA
MW011	08/13/08	0.024	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0071	NA	NA	NA	NA
	03/26/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/25/05	NA	NA	NA	490	<0.4	NA	NA	NA	NA	0.01	NA	NA	NA	NA
	07/11/05	NA	NA	NA	818	<0.4	NA	NA	NA	NA	0.04	NA	NA	NA	NA
MW011	02/09/06	<0.02	0.0666	<0.005	712	0.94	NA	NA	NA	<0.02	0.187	<0.0002	0.0665	<0.005	0.036
	07/19/06	<0.02	0.0269	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.11	NA	0.0751	<0.005	<0.02
	03/29/07	<0.02	NA	NA	543	<0.2	NA	NA	NA	NA	0.0204	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/16/08	<0.02	NA	NA	705	<0.2	195	27.7	719	NA	0.0333	NA	NA	NA	NA
MW011	03/31/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0337	NA	N	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01		1.0				0.05	0.2	0.002	0.05	0.05	10
MW011M	01/25/05	NA	NA	NA	1060	2.62	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	07/11/05	<0.02	0.733	<0.005	660	15.5	NA	NA	NA	NA	2.81	NA	NA	NA	NA
	02/10/06	0.0203	0.546	<0.005	419	6.61	NA	NA	NA	<0.02	0.985	<0.004	<0.02	<0.005	<0.02
	07/19/06	0.0327	NA	NA	209	<0.275	NA	NA	NA	<0.015	0.128	NA	<0.02	<0.005	<0.02
	03/29/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.0449	NA	NA	NA	NA
MW012	09/01/07	NA	NA	NA	343	6.71	373	39.5	691	NA	0.869	NA	NA	NA	NA
	04/16/08	<0.02	NA	NA	NA	6.21	NA	NA	NA	NA	0.628	NA	NA	NA	NA
	03/31/09	<0.02	NA	NA	416	0.1	NA	NA	NA	NA	108	NA	NA	NA	NA
	09/09/04	NA	NA	NA	393	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	01/18/05	NA	NA	NA	382	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
MW012M	07/11/05	NA	0.0612	<0.005	393	<0.2	NA	NA	NA	<0.02	0.0798	<0.0002	0.0249	<0.005	<0.02
	02/10/06	<0.02	0.737	<0.005	NA	11.1	NA	NA	NA	<0.015	0.95	NA	<0.02	<0.005	<0.02
	07/20/06	<0.02	NA	NA	327	1.54	NA	NA	NA	NA	0.0517	NA	NA	NA	NA
	04/02/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	09/01/07	NA	NA	NA	381	18.7	135	14	341	NA	4.05	NA	NA	NA	NA
MW013	04/01/09	0.0335	NA	NA	281	5.95	NA	NA	NA	NA	6.9	NA	NA	NA	NA
	04/17/08	NA	NA	NA	169	<0.4	NA	NA	NA	NA	<0.05	NA	NA	NA	NA
	07/14/04	NA	NA	NA	1590	271	NA	NA	NA	NA	1.01	NA	NA	NA	NA
	07/18/05	NA	NA	NA	NA	<0.4	NA	NA	NA	NA	0.59	NA	NA	NA	NA
	07/20/06	0.0393	2.84	<0.005	NA	514	NA	NA	NA	<0.02	50.2	<0.004	<0.02	<0.005	<0.02
MW014	07/20/06	0.0497	3.42	0.0315	2890	1130	NA	NA	NA	0.0176	72.5	NA	0.1	<0.005	<0.02
	04/05/07	0.1	NA	NA	NA	NA	NA	NA	NA	NA	92.6	NA	NA	NA	NA
	09/01/07	NA	NA	NA	2890	899	600	40.6	372	NA	44.4	NA	NA	NA	NA
	04/17/08	0.139	NA	NA	NA	91.8	NA	NA	NA	NA	2.06	NA	NA	NA	NA
	04/01/09	0.137	NA	NA	497	0.86	NA	NA	NA	NA	0.02	NA	NA	NA	NA
MW013	08/18/05	NA	NA	<0.005	467	<0.2	NA	NA	NA	<0.015	<0.005	<0.0002	0.0632	<0.005	<0.02
	01/26/06	<0.02	0.0258	<0.005	NA	<0.2	NA	NA	NA	NA	<0.005	NA	0.0626	<0.005	<0.02
	07/05/06	<0.02	0.0233	<0.005	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/18/07	<0.02	NA	NA	425	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/20/07	<0.02	NA	NA	289	0.399	92.3	11.3	384	NA	<0.005	NA	NA	NA	NA
MW014	04/15/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	4/1/2009	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	8/10/2009	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/22/05	NA	NA	NA	407	<0.4	NA	NA	NA	NA	0.01	NA	NA	NA	NA
MW014	01/26/06	<0.02	0.0614	<0.005	296	<0.2	NA	NA	NA	<0.02	0.0337	<0.0002	<0.02	<0.005	<0.02
	06/29/06	<0.02	0.0508	<0.005	NA	<0.2	NA	NA	NA	<0.02	0.037	NA	<0.02	<0.005	<0.02
	04/13/07	<0.02	NA	NA	237	<0.2	NA	NA	NA	NA	0.037	NA	NA	NA	NA
	09/19/07	<0.02	NA	NA	NA	<0.289	NA	NA	NA	NA	0.0457	NA	NA	NA	NA
	04/07/08	0.0203	NA	NA	270	<0.2	101	15.5	996	NA	0.0488	NA	NA	NA	NA
MW014	04/01/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	N	NA	NA
	08/10/09	0.0283	NA	NA	NA	<0.2	NA	NA	NA	NA	0.354	NA	N	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
MW015	01/25/06	0.1	1.0	0.01	569	<0.2	NA	NA	NA	0.05	0.2	0.002	0.05	0.05	<0.02
	06/29/06	<0.02	0.0675	<0.005	569	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0353	<0.005	<0.02
	03/22/07	<0.02	0.0701	<0.005	531	<0.2	NA	NA	NA	<0.02	<0.005	NA	0.0272	<0.005	<0.02
	09/19/07	<0.02	NA	NA	523	<0.2	186	17.3	884	NA	<0.005	NA	NA	NA	NA
	03/24/08	<0.02	NA	NA	523	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW018	08/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/23/06	<0.02	0.0483	<0.005	119	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/29/06	<0.02	0.0422	<0.005	133	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
MW020	04/02/07	<0.02	NA	NA	104	<0.2	44.8	6.29	263	NA	<0.005	NA	NA	NA	NA
	09/14/07	<0.02	NA	NA	104	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/24/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW021	01/25/06	<0.02	0.0573	<0.005	233	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/30/06	<0.02	0.0583	<0.005	200	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/04/07	0.202	NA	NA	229	<0.2	103	11.7	371	NA	<0.005	NA	NA	NA	NA
	09/18/07	<0.02	NA	NA	229	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/26/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW023	08/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/24/06	0.0202	0.0484	<0.005	71.7	<0.2	NA	NA	NA	<0.02	0.215	<0.0002	<0.02	<0.005	<0.02
	06/30/06	<0.02	0.0433	<0.005	NA	<0.2	NA	NA	NA	<0.02	0.15	NA	<0.02	<0.005	<0.02
MW023	04/09/07	<0.02	NA	NA	65.2	<0.2	NA	NA	NA	NA	0.173	NA	NA	NA	NA
	09/19/07	<0.02	NA	NA	56.4	<0.2	22.1	6.66	500	NA	0.231	NA	NA	NA	NA
	04/01/08	0.0276	NA	NA	NA	<0.2	NA	NA	NA	NA	0.198	NA	NA	NA	NA
	08/07/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.396	NA	NA	NA	NA
	03/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.172	NA	NA	NA	NA
MW023	08/06/09	<0.02	NA	NA	457	<0.2	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	06/01/05	<0.01	NA	NA	408	<0.2	NA	NA	NA	NA	<0.005	<0.0002	0.0216	<0.005	<0.02
	01/26/06	<0.02	0.0279	<0.005	398	<0.2	NA	NA	NA	<0.02	<0.005	NA	0.0227	<0.005	<0.02
	06/26/06	<0.02	0.0273	<0.005	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/18/07	<0.02	NA	NA	394	<0.2	168	14.9	527	NA	<0.005	NA	NA	NA	NA
MW023	09/21/07	0.0212	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/08/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/31/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/12/09	0.0218	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
MW024	01/24/06	0.1	1.0	0.01	189	<0.2	NA	NA	NA	0.05	0.2	<0.002	0.05	0.05	10
	06/27/06	<0.02	0.0972	<0.005	189	<0.2	NA	NA	NA	<0.02	0.0266	<0.0002	<0.02	<0.005	<0.02
	04/11/07	<0.02	0.0916	<0.005	229	<0.2	NA	NA	NA	<0.02	0.0682	NA	<0.02	<0.005	<0.02
	09/19/07	<0.02	NA	NA	256	<0.2	136	13.1	239	NA	0.0144	NA	NA	NA	NA
	04/07/08	<0.02	NA	NA	256	<0.2	136	13.1	239	NA	0.0267	NA	NA	NA	NA
	08/13/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0114	NA	NA	NA	NA
	03/25/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.007	NA	NA	NA	NA
	08/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/16/05	<0.01	NA	NA	133	<0.4	NA	NA	NA	<0.02	<0.01	<0.0002	<0.02	<0.005	<0.02
	01/24/06	<0.02	0.0508	<0.005	183	<0.2	NA	NA	NA	<0.02	0.009	<0.0002	<0.02	<0.005	<0.02
MW025	07/05/06	<0.02	0.0806	<0.005	232	<0.2	NA	NA	NA	<0.015	0.0104	NA	<0.02	<0.005	<0.02
	03/22/07	<0.02	NA	NA	226	<0.2	95.5	10	189	NA	0.011	NA	NA	NA	NA
	09/19/07	<0.02	NA	NA	226	<0.2	95.5	10	189	NA	0.0112	NA	NA	NA	NA
	03/24/08	<0.02	NA	NA	226	<0.2	95.5	10	189	NA	0.0105	NA	NA	NA	NA
	08/07/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0129	NA	NA	NA	NA
	03/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0125	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0095	<0.0002	0.0237	<0.005	<0.02
	01/19/06	<0.02	0.0873	<0.005	290	0.664	NA	NA	NA	<0.02	0.0095	<0.0002	0.0237	<0.005	<0.02
	06/23/06	<0.02	0.0537	<0.005	293	<0.2	NA	NA	NA	<0.02	<0.005	NA	0.0256	<0.005	<0.02
	04/05/07	<0.02	NA	NA	365	<0.2	126	11.1	206	NA	<0.005	NA	NA	NA	NA
MW026	09/11/07	<0.02	NA	NA	365	<0.2	126	11.1	206	NA	<0.05	NA	NA	NA	NA
	03/25/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.006	NA	NA	NA	NA
	08/11/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.006	NA	NA	NA	NA
	03/11/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.006	NA	NA	NA	NA
	08/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/23/06	<0.02	0.0578	<0.005	174	0.528	NA	NA	NA	<0.02	0.0104	<0.0002	<0.02	<0.005	<0.02
	06/23/06	<0.02	0.0493	<0.005	203	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	0.0407
	03/21/07	<0.02	NA	NA	203	1.03	NA	NA	NA	NA	0.0207	NA	NA	NA	NA
	09/14/07	<0.02	NA	NA	NA	4.24	NA	NA	NA	NA	0.0949	NA	NA	NA	NA
	03/11/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW027	08/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/18/06	<0.02	0.0571	<0.005	70.4	0.318	NA	NA	NA	<0.02	0.0079	<0.0002	<0.02	<0.005	<0.02
	06/20/06	<0.02	0.039	<0.005	50.9	<0.2	NA	NA	NA	<0.02	0.0076	NA	<0.02	<0.005	<0.02
	03/21/07	<0.02	NA	NA	44.9	<0.2	12	5.15	442	NA	<0.005	NA	NA	NA	NA
	09/06/07	<0.02	NA	NA	44.9	<0.2	12	5.15	442	NA	<0.005	NA	NA	NA	NA
	03/19/08	0.0275	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0071	NA	NA	NA	NA
	08/12/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/19/09	0.0211	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/24/09	0.0255	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/18/06	<0.02	0.0856	<0.005	111	1.27	NA	NA	NA	<0.02	0.0183	<0.0002	0.025	<0.005	<0.02
MW028	06/20/06	0.0243	0.0437	<0.005	85	0.272	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	03/28/07	0.0243	NA	NA	85	0.272	NA	NA	NA	<0.02	<0.005	NA	NA	NA	NA
	09/06/07	0.0208	NA	NA	85.8	<0.2	36.1	5.46	83.6	NA	<0.005	NA	NA	NA	NA
	03/20/08	0.021	NA	NA	85.8	<0.2	36.1	5.46	83.6	NA	<0.005	NA	NA	NA	NA
	08/05/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/24/09	0.0239	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/18/06	<0.02	0.0571	<0.005	70.4	0.318	NA	NA	NA	<0.02	0.0079	<0.0002	<0.02	<0.005	<0.02
	06/20/06	<0.02	0.039	<0.005	50.9	<0.2	NA	NA	NA	<0.02	0.0076	NA	<0.02	<0.005	<0.02
	03/21/07	<0.02	NA	NA	44.9	<0.2	12	5.15	442	NA	<0.005	NA	NA	NA	NA
MW029	09/06/07	<0.02	NA	NA	44.9	<0.2	12	5.15	442	NA	<0.005	NA	NA	NA	NA
	03/19/08	0.0275	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0071	NA	NA	NA	NA
	08/12/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/19/09	0.0211	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/24/09	0.0255	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/18/06	<0.02	0.0856	<0.005	111	1.27	NA	NA	NA	<0.02	0.0183	<0.0002	0.025	<0.005	<0.02
	06/20/06	0.0243	0.0437	<0.005	85	0.272	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	03/28/07	0.0243	NA	NA	85	0.272	NA	NA	NA	<0.02	<0.005	NA	NA	NA	NA
	09/06/07	0.0208	NA	NA	85.8	<0.2	36.1	5.46	83.6	NA	<0.005	NA	NA	NA	NA
	03/20/08	0.021	NA	NA	85.8	<0.2	36.1	5.46	83.6	NA	<0.005	NA	NA	NA	NA
	08/05/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/24/09	0.0239	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01	--	1.0	--	--	--	0.05	0.2	0.002	0.05	0.05	10
MW030	01/20/06	<0.02	0.115	<0.005	135	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/22/06	<0.02	0.112	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	03/28/07	<0.02	NA	<0.005	124	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/11/07	0.0259	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/25/08	<0.02	NA	NA	117	0.261	55.2	7.15	125	NA	0.0051	NA	NA	NA	NA
	08/05/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0072	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW031	01/19/06	<0.02	0.102	<0.005	89.6	0.205	NA	NA	NA	<0.02	0.488	<0.0002	<0.02	<0.005	<0.02
	06/21/06	0.0212	0.103	<0.005	NA	<0.2	NA	NA	NA	<0.02	0.566	NA	<0.02	<0.005	<0.02
	03/28/07	0.0227	NA	NA	87.9	0.02	NA	NA	NA	NA	0.587	NA	NA	NA	NA
	09/11/07	0.0205	NA	NA	NA	0.329	NA	NA	NA	NA	0.537	NA	NA	NA	NA
	03/20/08	<0.02	NA	NA	78.6	0.384	30.1	3.44	116	NA	0.533	NA	NA	NA	NA
	08/05/08	0.0243	NA	NA	NA	0.321	NA	NA	NA	NA	0.518	NA	NA	NA	NA
	03/24/09	0.0257	NA	NA	NA	0.482	NA	NA	NA	NA	0.513	NA	NA	NA	NA
	08/04/09	0.0253	NA	NA	NA	<0.2	NA	NA	NA	<0.02	0.532	<0.0002	<0.02	<0.005	<0.02
MW032	01/19/06	<0.02	0.0669	<0.005	167	0.354	NA	NA	NA	<0.02	<0.0051	<0.0002	<0.02	<0.005	<0.02
	06/21/06	<0.02	0.0557	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/13/07	<0.02	NA	NA	173	0.517	NA	NA	NA	NA	0.0183	NA	NA	NA	NA
	09/07/07	<0.02	NA	NA	NA	0.217	NA	NA	NA	NA	0.0059	NA	NA	NA	NA
	04/07/08	<0.02	NA	NA	152	<0.2	44.5	7.23	153	NA	<0.005	NA	NA	NA	NA
	08/14/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0114	NA	NA	NA	NA
	03/30/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/06/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0059	NA	NA	NA	NA
MW033	01/27/06	<0.02	0.281	<0.005	237	1.31	NA	NA	NA	<0.02	0.525	<0.0002	<0.02	<0.005	<0.02
	06/26/06	<0.02	0.271	<0.005	NA	1.03	NA	NA	NA	<0.02	0.5	NA	<0.02	<0.005	<0.02
	04/23/07	<0.02	NA	NA	203	0.661	NA	NA	NA	NA	0.478	NA	NA	NA	NA
	09/21/07	<0.02	NA	NA	NA	0.515	NA	NA	NA	NA	0.725	NA	NA	NA	NA
	03/19/08	<0.02	NA	NA	272	0.689	141	5.15	263	NA	1.44	NA	NA	NA	NA
	08/13/08	<0.02	NA	NA	NA	0.314	NA	NA	NA	NA	1.73	NA	NA	NA	NA
	04/01/09	<0.02	NA	NA	NA	0.389	NA	NA	NA	NA	1.15	NA	NA	NA	NA
	08/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	1.04	NA	NA	NA	NA
MW034	01/25/06	<0.02	0.03	<0.005	162	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0271	<0.005	<0.02
	07/07/06	<0.02	0.031	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0265	<0.005	<0.02
	04/09/07	<0.02	NA	NA	139	0.205	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/01/08	<0.02	NA	NA	127	<0.2	55.8	7.6	312	NA	<0.005	NA	NA	NA	NA
	03/25/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/23/06	<0.02	0.138	<0.005	110	0.288	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	09/22/06	<0.02	0.11	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
MW035	04/02/07	<0.02	NA	NA	122	<0.2	NA	NA	NA	NA	0.0052	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/02/08	<0.02	NA	NA	119	<0.2	24.6	3.97	97.5	NA	0.016	NA	NA	NA	NA
	03/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0482	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
MW036	08/11/05	0.01	NA	NA	144	2.35	NA	NA	NA	0.05	0.56	NA	NA	0.05	10
	01/26/06	<0.02	0.397	<0.005	238	3.55	NA	NA	NA	<0.02	0.643	<0.0002	NA	<0.005	NA
	07/12/06	<0.02	0.438	<0.005	NA	3.54	NA	NA	NA	<0.015	0.607	NA	<0.02	<0.005	<0.02
	04/19/07	0.0242	NA	NA	186	4.35	NA	NA	NA	NA	0.524	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
MW037	04/16/08	0.0405	NA	NA	99.8	6.17	44.6	5.58	211	NA	0.327	NA	NA	NA	NA
	04/07/09	0.0292	NA	NA	NA	5.07	NA	NA	NA	NA	0.879	NA	NA	NA	NA
	08/25/05	0.05	NA	NA	56.6	11.1	NA	NA	NA	NA	0.35	NA	NA	NA	NA
	01/27/06	0.0504	0.505	<0.005	84.6	8.41	NA	NA	NA	<0.02	-0.882	<0.0002	NA	<0.005	<0.02
	07/13/06	0.055	0.307	<0.005	NA	5.66	NA	NA	NA	<0.015	1.05	NA	<0.02	<0.005	<0.02
MW038	04/19/07	0.058	NA	NA	118	8.49	NA	NA	NA	NA	0.984	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/16/08	0.0794	NA	NA	130	10.1	101	16.9	851	NA	1.27	NA	NA	NA	NA
	04/07/09	0.0732	NA	NA	NA	13.6	NA	NA	NA	NA	1.17	NA	NA	NA	NA
	05/31/05	0.01	NA	NA	97.5	6.42	NA	NA	NA	NA	0.21	NA	NA	NA	NA
MW043	01/26/06	<0.02	0.117	<0.005	308	2.39	NA	NA	NA	<0.02	0.274	<0.0002	<0.02	<0.005	<0.02
	07/13/06	<0.02	0.102	<0.005	NA	0.841	NA	NA	NA	<0.015	0.211	NA	0.0252	<0.005	<0.02
	04/19/07	<0.02	NA	NA	250	2.63	NA	NA	NA	NA	0.209	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/16/08	<0.02	NA	NA	192	0.598	84.8	12.3	253	NA	0.177	NA	NA	NA	NA
MW044	04/07/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.163	NA	NA	NA	NA
	01/23/06	<0.02	0.0905	<0.005	362	<0.2	NA	NA	NA	<0.02	2.15	<0.0002	0.0573	<0.005	<0.02
	06/30/06	0.04	0.0718	<0.005	NA	<0.2	NA	NA	NA	<0.02	0.0452	NA	<0.02	<0.005	<0.02
	04/08/07	0.0468	NA	NA	35.2	<0.2	NA	NA	NA	NA	0.0894	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
MW045	03/26/08	0.0345	NA	NA	65.2	<0.2	23.6	16.3	353	NA	0.188	NA	NA	NA	NA
	03/24/09	0.022	NA	NA	NA	<0.2	NA	NA	NA	NA	0.311	NA	NA	NA	NA
	02/02/06	<0.02	0.0568	<0.005	233	<0.2	NA	NA	NA	<0.02	0.283	<0.0002	<0.02	<0.005	<0.02
	07/21/06	<0.02	0.0766	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.251	NA	<0.02	<0.005	<0.02
	04/06/07	<0.02	NA	NA	145	0.217	NA	NA	NA	NA	0.288	NA	NA	NA	NA
MW046	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/09/08	<0.02	NA	NA	172	<0.2	85.9	11.4	422	NA	0.548	NA	NA	NA	NA
	03/25/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.393	NA	NA	NA	NA
	01/27/06	<0.02	0.0988	<0.005	213	<0.2	NA	NA	NA	<0.02	0.332	<0.0002	<0.02	<0.005	<0.02
	07/12/06	<0.02	0.1	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.305	NA	<0.02	<0.005	<0.02
MW045	04/02/07	<0.02	NA	NA	222	<0.2	NA	NA	NA	NA	0.333	NA	NA	NA	NA
	04/17/07	<0.02	NA	NA	190	<0.2	NA	NA	NA	NA	0.227	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/02/08	<0.02	NA	NA	178	0.248	42.4	10.8	272	NA	0.312	NA	NA	NA	NA
	03/24/09	<0.02	NA	NA	NA	1.83	NA	NA	NA	NA	0.354	NA	NA	NA	NA
MW046	01/26/06	0.043	0.38	<0.005	116	2.34	NA	NA	NA	<0.02	1.22	<0.0002	<0.02	<0.005	<0.02
	07/12/06	0.0386	0.387	<0.005	NA	2.51	NA	NA	NA	<0.015	1.32	NA	<0.02	<0.005	<0.02
	04/19/07	0.0427	NA	NA	151	3.1	NA	NA	NA	NA	1.71	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/17/08	0.0388	NA	NA	164	3.31	59.5	4.33	364	NA	1.6	NA	NA	NA	NA
	04/07/09	0.0325	NA	NA	NA	2.76	NA	NA	NA	NA	1.81	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01		1.0									
MW047	08/11/05	<0.01	NA	NA	273	<0.4	NA	NA	NA	0.05	<0.01	<0.002	0.05	0.05	10
	01/25/06	<0.02	0.0424	<0.005	171	<0.2	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	07/07/06	<0.02	0.0327	<0.005	101	<0.2	NA	NA	NA	<0.015	<0.005	<0.0002	<0.02	<0.005	<0.02
	04/16/07	<0.02	NA	NA	101	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
MW058	04/03/08	<0.02	NA	NA	132	NA	29.3	5.68	215	NA	<0.005	NA	NA	NA	NA
	03/11/09	<0.01	NA	NA	520	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	08/16/05	<0.02	0.0361	<0.005	313	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0455	<0.005	<0.02
	01/24/06	<0.02	0.0381	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0455	<0.005	<0.02
	07/06/06	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW059	09/14/07	<0.02	NA	NA	487	0.338	221	18	457	NA	<0.005	NA	NA	NA	NA
	04/15/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/02/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW060	01/20/06	<0.02	0.0413	<0.005	230	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0372	<0.005	<0.02
	06/26/06	<0.02	0.0422	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	0.0353	<0.005	<0.02
	09/11/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/03/08	<0.02	NA	NA	289	<0.2	139	10.5	172	NA	<0.005	NA	NA	NA	NA
	08/14/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0091	NA	NA	NA	NA
MW061	03/31/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/12/09	0.0232	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/16/05	<0.01	NA	NA	454	<0.4	NA	NA	NA	NA	0.04	<0.0002	NA	NA	NA
	01/24/06	<0.02	0.0468	<0.005	503	0.24	NA	NA	NA	<0.02	0.0543	<0.0002	0.0332	<0.005	<0.02
	07/06/06	<0.02	0.0592	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.354	NA	<0.0225	<0.005	<0.02
MW062	03/28/07	<0.02	NA	NA	554	0.286	NA	NA	NA	NA	0.423	NA	NA	NA	NA
	09/14/07	<0.02	NA	NA	NA	0.399	NA	NA	NA	NA	0.635	NA	NA	NA	NA
	03/25/08	<0.02	NA	NA	484	0.357	220	13.6	272	NA	0.734	NA	NA	NA	NA
	08/11/08	<0.02	NA	NA	NA	0.361	NA	NA	NA	NA	0.914	NA	NA	NA	NA
	03/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.956	NA	NA	NA	NA
MW063	08/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	1.11	NA	NA	NA	NA
	01/26/06	<0.02	0.0409	<0.005	352	<0.2	NA	NA	NA	<0.02	0.295	<0.0002	0.0516	<0.005	<0.02
	07/05/06	<0.02	0.0274	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.3	NA	0.049	<0.005	<0.02
	04/18/07	<0.02	NA	NA	343	<0.2	NA	NA	NA	NA	0.29	NA	NA	NA	NA
	09/21/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.267	NA	NA	NA	NA
MW064	08/07/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.186	NA	NA	NA	NA
	04/01/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.158	NA	NA	NA	NA
	08/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0615	NA	NA	NA	NA
	01/19/06	<0.02	0.0647	<0.005	259	<0.2	NA	NA	NA	<0.02	0.819	<0.0002	<0.02	<0.005	<0.02
	06/21/06	<0.02	0.0566	<0.005	NA	<0.2	NA	NA	NA	<0.02	0.244	NA	<0.02	<0.005	<0.02
MW065	03/22/07	<0.02	NA	NA	120	<0.2	NA	NA	NA	NA	0.0894	NA	NA	NA	NA
	09/07/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.367	NA	NA	NA	<0.02
	03/25/08	<0.02	NA	NA	279	<0.2	80.9	35.8	1170	NA	1.02	NA	NA	NA	<0.02
	08/11/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	1.95	NA	NA	NA	NA
	03/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.368	NA	NA	NA	NA
MW066	08/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.588	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01	—	1.0	—	—	—	0.05	0.2	0.002	0.05	0.05	10
MW069	01/19/06	<0.02	0.167	<0.005	677	0.847	NA	NA	NA	<0.02	0.118	<0.0002	<0.02	<0.005	<0.02
	06/21/06	<0.02	0.134	<0.005	NA	<0.2	NA	NA	NA	<0.02	0.114	NA	<0.02	<0.005	<0.02
	03/22/07	<0.02	NA	NA	303	0.62	NA	NA	NA	NA	1.55	NA	NA	<0.005	<0.02
	09/07/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.208	NA	NA	NA	<0.02
	03/11/09	<0.02	NA	NA	NA	<0.2	No Access (1st Half 2009) - Due to Construction Activity	NA	NA	NA	0.208	NA	NA	NA	<0.02
MW070	08/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.288	NA	NA	NA	NA
	01/27/06	<0.02	0.0659	<0.005	68.8	<0.2	NA	NA	NA	<0.02	0.0059	<0.0002	<0.02	<0.005	<0.02
	06/22/06	<0.02	0.0606	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	03/29/07	<0.02	NA	NA	79.9	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/11/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW088M	03/25/08	<0.02	NA	NA	106	<0.2	51.3	6.71	111	NA	<0.005	NA	NA	NA	NA
	08/05/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0058	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/19/05	<0.05	NA	NA	4050	942	NA	NA	NA	NA	<0.10	NA	NA	NA	NA
RW002	07/12/05	<0.05	NA	NA	405	<2.0	NA	NA	NA	NA	43.2	0.004	0.1	0.025	0.1
	02/06/06	0.144	1.04	0.025	3480	1330	NA	NA	NA	0.1	36	0.004	0.1	0.025	0.1
	07/20/06	<0.02	0.0905	<0.005	NA	0.405	NA	NA	NA	<0.015	2.12	NA	<0.02	<0.005	<0.02
	04/05/07	<0.02	NA	NA	362	2.44	NA	NA	NA	NA	0.0385	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
RW003	04/21/08	0.154	NA	NA	3270	1420	406	624	338	NA	58.7	NA	NA	NA	NA
	04/01/09	0.117	NA	NA	1030	NA	NA	NA	NA	NA	52.7	NA	NA	NA	NA
	01/25/05	<0.01	NA	NA	597	2	NA	NA	NA	NA	0.88	NA	NA	NA	NA
	07/07/05	<0.01	NA	NA	595	8.9	NA	NA	NA	NA	1.44	NA	NA	NA	NA
	02/10/06	<0.02	0.151	<0.005	952	23.7	NA	NA	NA	<0.02	6.42	<0.0002	<0.02	<0.005	<0.02
IW001	07/20/06	<0.02	0.0733	<0.005	NA	21.8	NA	NA	NA	<0.015	1.79	NA	<0.02	<0.005	<0.02
	03/29/07	<0.02	NA	NA	554	40.7	NA	NA	NA	NA	1.51	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.23	NA	NA	NA	NA
	04/17/08	<0.02	NA	NA	547	24.6	133	16.7	539	NA	1.64	NA	NA	NA	NA
	03/31/09	<0.02	NA	NA	NA	14.8	NA	NA	NA	NA	0.06	NA	NA	NA	NA
RW003	09/09/04	<0.01	NA	NA	468	<0.1	NA	NA	NA	NA	1.9	NA	NA	NA	NA
	01/18/05	<0.01	NA	NA	590	4.2	NA	NA	NA	NA	3.71	NA	NA	NA	NA
	07/12/05	<0.01	NA	NA	408	12.6	NA	NA	NA	NA	11.7	<0.0002	<0.02	<0.005	<0.02
	02/10/06	0.0367	1.48	<0.005	476	94.9	NA	NA	NA	<0.02	1.15	NA	<0.02	<0.005	<0.02
	07/20/06	0.0656	1.47	<0.005	NA	73.8	NA	NA	NA	<0.015	0.889	NA	<0.02	<0.005	<0.02
IW001	04/02/07	0.128	NA	NA	418	44.9	NA	NA	NA	NA	0.889	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.833	NA	NA	NA	NA
	04/21/08	0.12	NA	NA	476	40.4	85.7	35.7	419	NA	0.833	NA	NA	NA	NA
	04/01/09	0.101	NA	NA	NA	53.3	NA	NA	NA	NA	0.05	NA	NA	NA	NA
	09/15/04	<0.05	NA	NA	1420	115	NA	NA	NA	NA	2.9	NA	NA	NA	NA
IW001	01/26/05	<0.1	NA	NA	679	77.8	NA	NA	NA	NA	0.4	NA	NA	NA	NA
	07/07/05	<0.05	NA	NA	1160	82.5	NA	NA	NA	NA	0.94	NA	NA	NA	NA
	02/06/06	0.0274	0.993	<0.005	1520	145	NA	NA	NA	<0.02	3.49	<0.0002	<0.02	<0.005	0.381
	07/20/06	0.0287	1.33	0.0122	NA	208	NA	NA	NA	<0.015	4.55	NA	<0.02	<0.005	0.341
	04/16/07	<0.02	NA	NA	514	71.9	NA	NA	NA	NA	1.32	NA	<0.02	<0.005	0.341
IW001	04/17/08	<0.5	NA	NA	2250	197	174	383	301	NA	5.12	NA	NA	NA	NA
	03/31/09	0.0519	NA	NA	NA	49.8	NA	NA	NA	NA	2.45	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic mg/L	Barium mg/L	Cadmium mg/L	Calcium mg/L	Iron mg/L	Magnesium mg/L	Potassium mg/L	Sodium mg/L	Lead mg/L	Manganese mg/L	Mercury mg/L	Selenium mg/L	Silver mg/L	Zinc mg/L
NW002	NM WQCC Standard	0.1	1.0	0.01	--	1.0	--	--	--	0.05	0.2	0.002	0.05	0.05	10
	09/09/04	NA	NA	NA	NA	6	NA	NA	NA	NA	0.2	NA	NA	NA	NA
	01/19/05	NA	NA	NA	542	82	NA	NA	NA	NA	0.32	NA	NA	NA	NA
	07/12/05	NA	NA	NA	NA	90.9	NA	NA	NA	NA	0.53	NA	NA	NA	NA
	02/06/06	0.0264	0.755	<0.005	1080	265	NA	NA	NA	<0.02	4.62	<0.001	<0.02	<0.005	0.589
MW002A	07/20/06	0.0314	0.888	0.0198	NA	365	NA	NA	NA	<0.015	4.58	NA	<0.02	<0.005	0.372
	04/11/07	0.1	NA	NA	1680	79.8	NA	NA	NA	NA	1.47	NA	NA	NA	NA
	04/21/08	<0.10	NA	NA	1290	37.8	85.5	250	162	NA	1.04	NA	NA	NA	NA
	4/6/2008*	<0.10	NA	NA	NA	27.9	NA	NA	NA	NA	0.993	NA	NA	NA	NA
DEEP ZONE WELLS															
MW002A	01/24/06	<0.02	0.04	<0.005	131	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	07/06/06	0.0202	0.0408	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.0051	NA	<0.02	<0.005	<0.02
	04/12/07	<0.02	NA	NA	179	<0.2	NA	NA	NA	NA	0.0115	NA	NA	NA	NA
	04/02/08	0.0222	NA	NA	340	<0.2	195	16.6	414	NA	0.0363	NA	NA	NA	NA
	03/31/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0228	NA	NA	NA	NA
MW004A	08/15/05	NA	NA	NA	29.1	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	01/25/06	<0.02	0.0282	<0.005	143	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0249	<0.005	<0.02
	07/07/06	<0.02	0.0251	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.02	<0.005	<0.02
	04/16/07	<0.02	NA	NA	173	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
MW007A	04/03/08	0.0203	NA	NA	215	<0.2	131	10.7	222	NA	<0.005	NA	NA	NA	NA
	03/31/09	0.0257	NA	NA	NA	986	NA	NA	NA	NA	13	NA	NA	NA	NA
	08/10/05	NA	NA	NA	214	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	01/26/06	<0.02	0.0338	<0.005	301	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0322	<0.005	<0.02
	07/07/06	<0.02	0.0254	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.0002	<0.005	<0.02
MW008A	04/16/07	<0.02	NA	NA	283	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/03/08	<0.02	NA	NA	339	<0.2	151	14	369	NA	NA	NA	NA	NA	NA
	03/11/09														
MW008A	09/16/04	NA	NA	NA	617	0.1	NA	NA	NA	NA	0.06	NA	NA	NA	NA
	01/06/05	NA	NA	NA	617	0.61	NA	NA	NA	NA	0.22	NA	NA	NA	NA
	07/06/05	NA	NA	NA	123	22.3	NA	NA	NA	NA	1.75	NA	NA	NA	NA
	02/09/06	0.0328	13.6	<0.005	575	29.5	NA	NA	NA	<0.02	2.36	<0.002	<0.02	<0.005	<0.02
	07/18/06	0.0236	11.2	<0.005	615	11.5	NA	NA	NA	<0.015	1.09	NA	<0.02	<0.005	<0.02
MW009A	04/03/07	0.0753	NA	NA	615	70.6	NA	NA	NA	NA	1.49	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/15/08	0.0981	NA	NA	733	113	385	31.6	582	NA	1.54	NA	NA	NA	NA
	03/26/09	0.106	NA	NA	NA	155	NA	NA	NA	NA	1.84	NA	NA	NA	NA
	08/16/05	NA	NA	NA	161	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
MW009A	02/02/06	<0.02	0.0192	<0.005	289	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0361	<0.005	<0.02
	07/13/06	<0.02	0.0185	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0451	<0.005	<0.02
	04/04/07	<0.02	NA	NA	252	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/15/08	<0.02	NA	NA	249	<0.2	128	16	373	NA	<0.005	NA	NA	NA	NA
MW009A	03/26/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01	—	1.0	—	—	—	0.05	0.2	0.002	0.05	0.05	10
MW011A	09/15/04	NA	NA	NA	398	<0.1	NA	NA	NA	NA	<0.05	NA	NA	NA	NA
	01/25/05	NA	NA	NA	NA	<0.4	NA	NA	NA	NA	0.03	NA	NA	NA	NA
	07/11/05	NA	NA	NA	620	<0.2	NA	NA	NA	<0.02	0.0263	<0.0002	0.0818	<0.005	0.168
	02/10/06	<0.02	0.0273	<0.005	589	<0.2	NA	NA	NA	<0.015	0.0299	NA	0.0761	<0.005	0.155
	07/19/06	<0.02	0.0297	<0.005	NA	<0.2	NA	NA	NA	NA	0.0407	NA	NA	NA	NA
	03/29/07	<0.02	NA	NA	551	<0.2	NA	NA	NA	NA	NA	NA	NA	NA	NA
MW012A	09/01/07	NA	NA	NA	NA	NA	247	36.7	821	NA	0.0441	NA	NA	NA	NA
	04/16/08	<0.02	NA	NA	513	<0.2	NA	NA	NA	NA	0.0151	NA	NA	NA	NA
	03/31/09	<0.02	NA	NA	281	<0.2	NA	NA	NA	NA	1.01	NA	NA	NA	NA
	07/14/04	NA	NA	NA	169	<0.4	NA	NA	NA	NA	0.59	NA	NA	NA	NA
	01/18/05	NA	NA	NA	189	<0.4	NA	NA	NA	NA	0.039	NA	NA	NA	NA
	07/12/05	NA	0.14	<0.005	49.2	<0.2	NA	NA	NA	<0.015	0.0638	NA	<0.02	<0.005	<0.02
MW013A	02/10/06	<0.02	0.174	<0.005	NA	<0.2	NA	NA	NA	NA	0.081	NA	NA	NA	NA
	04/02/07	<0.02	NA	NA	65	<0.2	NA	NA	NA	NA	NA	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0174	NA	NA	NA	NA
	04/21/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.005	NA	NA	NA	NA
	04/01/09	0.02	NA	NA	NA	<0.4	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	06/03/05	<0.02	0.0359	<0.005	53.4	<0.2	NA	NA	NA	<0.015	<0.005	<0.0002	<0.02	<0.005	<0.02
MW014A	07/05/06	<0.02	0.0325	<0.005	NA	<0.2	NA	NA	NA	NA	<0.005	NA	<0.02	<0.005	<0.02
	04/16/07	0.0204	NA	NA	53.5	<0.2	NA	NA	NA	NA	<0.005	NA	NA	<0.005	<0.02
	09/21/07	0.0259	NA	NA	NA	<0.2	23.5	5	107	NA	<0.005	NA	NA	NA	NA
	04/07/08	0.0223	NA	NA	45.2	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/08	0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/30/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW015A	08/04/09	0.0243	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/23/06	0.0261	0.0371	<0.005	33.7	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/29/06	<0.02	0.0343	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	03/21/07	0.0236	NA	NA	31.3	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/13/07	0.0207	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/24/08	0.0256	NA	NA	31.9	<0.2	19.8	6.03	121	NA	<0.005	NA	NA	NA	NA
MW016A	03/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0065	NA	NA	NA	NA
	08/20/09	0.0214	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	<0.02	<0.005	<0.02
	01/23/06	<0.02	0.126	<0.005	235	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/29/06	<0.02	0.133	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	03/22/07	<0.02	NA	NA	249	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/14/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW017A	03/24/08	<0.02	NA	NA	347	<0.2	234	20.7	550	NA	<0.005	NA	NA	NA	NA
	09/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/20/06	<0.02	0.0246	<0.005	90.1	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/29/06	<0.02	0.0248	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
MW018A	03/22/07	<0.02	NA	NA	95	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/13/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/19/08	<0.02	NA	NA	90.9	<0.2	50.8	7.5	156	NA	<0.005	NA	NA	NA	NA
	08/07/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01	NA	1.0	NA	NA	NA	0.05	0.2	<0.002	0.05	0.05	10
MW017A	01/24/06	0.0226	0.0412	<0.005	38.4	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/29/06	0.0206	0.0342	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	03/21/07	0.0226	NA	NA	48.5	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
MW018A	PLUGGED AND ABANDONED														
	01/20/06	<0.02	0.0273	<0.005	100	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/29/06	<0.02	0.0267	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	0.0241
	04/02/07	<0.02	NA	NA	105	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/13/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/24/08	<0.02	NA	NA	105	<0.2	63	8.77	171	NA	<0.005	NA	NA	NA	NA
	03/17/09	<0.02	NA	NA	105	<0.2	63	8.77	171	NA	<0.005	NA	NA	NA	NA
	08/21/09	0.0209	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW019A	01/23/06	<0.02	0.0302	<0.005	126	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/30/06	<0.02	0.0291	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/04/07	<0.02	NA	NA	118	<0.2	NA	NA	NA	NA	0.0083	NA	NA	NA	NA
	09/14/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0186	NA	NA	NA	NA
	03/26/08	<0.02	NA	NA	127	<0.2	69.7	8.88	189	NA	<0.005	NA	NA	NA	NA
	08/07/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	<0.0002	NA	NA	NA
MW020A	01/24/06	<0.02	0.0247	<0.005	181	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/30/06	<0.02	0.0242	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	0.0203	<0.005	<0.02
	04/04/07	<0.02	NA	NA	236	<0.2	NA	NA	NA	NA	0.0068	NA	NA	NA	NA
	09/18/07	<0.02	NA	NA	233	<0.2	126	12.6	248	NA	<0.005	NA	NA	NA	NA
	03/26/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0058	NA	NA	NA	NA
	09/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/19/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	<0.0002	NA	<0.005	<0.02
MW021A	01/24/06	<0.02	0.0368	<0.005	626	<0.2	NA	NA	NA	<0.02	0.0103	<0.0002	<0.02	<0.005	<0.02
	06/30/06	<0.02	0.0381	<0.005	NA	<0.2	NA	NA	NA	<0.02	0.0077	NA	<0.02	<0.005	<0.02
	04/09/07	<0.02	NA	NA	465	<0.2	NA	NA	NA	NA	0.0112	NA	<0.02	NA	NA
	09/19/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0138	NA	NA	NA	NA
	04/01/08	<0.02	NA	NA	595	<0.2	295	48.3	3520	NA	0.0158	NA	NA	NA	NA
	03/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0152	NA	NA	NA	NA
	08/06/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0114	NA	NA	NA	NA
	01/24/06	<0.02	0.0535	<0.005	65.2	<0.2	NA	NA	NA	<0.02	<0.0058	<0.0002	<0.02	<0.005	<0.02
MW022A	03/30/07	<0.02	0.0649	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.02	<0.005	<0.02
	09/14/07	<0.02	NA	NA	69.9	<0.2	NA	NA	NA	NA	0.0112	NA	NA	NA	NA
	04/02/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0219	NA	NA	NA	NA
	08/13/08	<0.02	NA	NA	70.1	<0.2	12.2	3.42	52.4	NA	0.0216	NA	NA	NA	NA
	03/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0143	NA	NA	NA	NA
	08/10/05	<0.02	NA	NA	38.6	<0.4	NA	NA	NA	NA	0.0059	NA	NA	NA	NA
	01/20/06	0.0246	0.0387	<0.005	35.8	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/26/06	<0.02	0.0372	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
MW023A	03/29/07	<0.02	NA	NA	34.1	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/11/07	0.0287	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/25/08	<0.02	NA	NA	33.8	<0.2	18.5	4.94	102	NA	<0.005	NA	NA	NA	NA
	08/12/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0073	NA	NA	NA	NA
	03/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard	01/25/06	0.1	1.0	0.01	72.1	1.0	NA	NA	NA	0.05	0.2	0.002	0.05	0.05	10
MW024A	06/27/06	<0.02	0.0377	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	04/11/07	0.0206	NA	<0.005	66.1	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	09/14/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/07/08	<0.02	NA	NA	72.8	<0.2	41.2	6.84	120	NA	<0.005	NA	NA	NA	NA
MW039A	08/13/08	0.0251	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0139	NA	NA	NA	NA
	03/25/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/12/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	06/08/05	0.01	NA	NA	84.2	<0.4	NA	NA	NA	NA	<0.01	<0.0002	NA	NA	NA
MW040A	01/25/06	0.0219	0.0333	<0.005	134	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0243	<0.005	<0.02
	07/06/06	0.0229	0.0338	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0292	<0.005	<0.02
	04/12/07	<0.02	NA	NA	117	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
MW041A	04/03/08	<0.02	NA	NA	159	<0.2	87.2	9.17	201	NA	<0.005	NA	NA	NA	NA
	04/02/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/18/05	<0.02	NA	NA	32.6	<0.4	NA	NA	NA	NA	<0.01	<0.0002	NA	NA	NA
	01/20/06	0.0234	0.0332	<0.005	35	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
MW042A	06/28/06	0.0203	0.0348	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/02/07	<0.02	NA	NA	34.8	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/11/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/24/08	0.0223	NA	NA	33	<0.2	21.6	5.52	106	NA	<0.005	NA	NA	NA	NA
MW044A	08/07/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/09	0.0304	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/26/06	<0.02	0.0181	<0.005	266	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0425	<0.005	<0.02
MW046A	07/07/06	<0.02	0.0191	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.032	<0.005	<0.02
	04/17/07	<0.02	NA	NA	185	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	<0.2	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/02/08	<0.02	NA	NA	317	<0.2	165	46.3	1840	NA	0.0094	NA	NA	NA	NA
MW048A	03/31/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0073	NA	NA	NA	NA
	01/26/06	<0.02	0.0204	<0.005	282	<0.2	NA	NA	NA	<0.02	0.0539	<0.0002	<0.02	<0.005	<0.02
	07/12/06	<0.02	0.0179	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.0339	NA	0.0318	<0.005	<0.02
	04/17/07	<0.02	NA	NA	314	<0.2	NA	NA	NA	NA	0.0257	NA	NA	<0.005	<0.02
MW048SA	09/01/07	NA	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0159	NA	NA	NA	NA
	04/02/08	<0.02	NA	NA	225	<0.2	128	13.5	333	NA	0.0167	NA	NA	NA	NA
	03/31/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	<0.02	0.0173	<0.0002	0.0256	<0.005	<0.02
	01/25/06	<0.02	0.041	<0.005	162	1.16	NA	NA	NA	<0.02	<0.005	NA	0.0228	<0.005	<0.02
MW048SA	07/11/06	<0.02	0.0255	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.0072	NA	NA	NA	NA
	04/10/07	<0.02	NA	NA	183	<0.285	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/20/07	0.0207	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/01/08	<0.02	NA	NA	181	0.264	101	13.3	194	NA	<0.005	NA	NA	NA	NA
MW048SA	08/20/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/26/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW048SA	08/12/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
	NM WQCC Standard	0.1	1.0	0.01	-	1.0	-	-	-	0.05	0.2	0.002	0.05	0.05	10
MW049SA	01/25/06	<0.02	0.0335	<0.005	488	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	07/11/06	<0.02	0.0314	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.02	<0.005	<0.02
	04/10/07	<0.02	NA	NA	419	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	368	0.303	187	23.7	1130	NA	0.0071	NA	NA	NA	NA
MW050SA	04/08/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/26/09	<0.02	NA	NA	239	<0.2	NA	NA	NA	<0.015	<0.005	<0.0002	<0.023	<0.005	<0.02
	07/10/06	<0.02	0.0466	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.03	<0.005	<0.02
	04/09/07	<0.02	NA	NA	286	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW051SA	09/01/07	NA	NA	NA	NA	<0.2	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/01/08	<0.02	NA	NA	286	<0.2	134	15	870	NA	0.0072	NA	NA	NA	NA
	03/25/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0057	NA	NA	NA	NA
	01/26/06	<0.02	0.0308	<0.005	361	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0482	<0.005	<0.02
MW052SA	07/11/06	<0.02	0.0288	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0509	<0.005	<0.02
	04/17/07	<0.02	NA	NA	450	0.272	NA	NA	NA	NA	0.007	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/09/08	<0.02	NA	NA	345	<0.2	164	17.5	754	NA	<0.005	NA	NA	NA	NA
MW053SA	04/02/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/26/06	<0.02	0.0339	<0.005	495	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.0262	<0.005	<0.02
	07/11/06	<0.02	0.0301	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.029	<0.005	<0.02
	04/10/07	<0.02	NA	NA	457	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW054SA	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/08/08	<0.02	NA	NA	471	<0.2	234	18	652	NA	<0.005	NA	NA	NA	NA
	03/26/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/26/06	<0.02	0.0307	<0.005	105	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
MW055SA	07/11/06	<0.02	0.0294	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.02	<0.005	<0.02
	04/05/07	<0.02	NA	NA	84.2	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/20/07	0.0201	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/26/08	<0.02	NA	NA	79.9	<0.2	38.1	6.41	173	NA	<0.005	NA	NA	NA	NA
MW056SA	03/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/26/06	<0.02	0.0481	<0.005	254	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0306	<0.005	<0.02
	07/11/06	<0.02	0.048	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.02	<0.005	<0.02
MW057SA	04/10/07	<0.02	NA	NA	248	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/20/07	0.0217	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/08/08	<0.02	NA	NA	270	<0.2	150	12.5	337	NA	<0.005	NA	NA	NA	NA
	08/20/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW058SA	03/26/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/10/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/25/06	<0.02	0.0206	<0.005	175	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.0225	<0.005	<0.02
	06/28/06	<0.02	0.0282	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
MW059SA	04/10/07	<0.02	NA	NA	179	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/20/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/09/08	<0.02	NA	NA	181	<0.2	110	10.4	250	NA	<0.005	NA	NA	NA	NA
	08/19/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW060SA	03/26/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/12/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
MW066SA	01/26/06	<0.02	1.0	0.01	274	<0.2	NA	NA	NA	0.05	0.2	0.002	0.05	0.05	10
	07/12/06	<0.02	0.028	<0.005	245	<0.2	NA	NA	NA	<0.015	<0.005	<0.0002	0.0379	<0.005	<0.02
	04/11/07	<0.02	0.0343	<0.005	NA	0.414	NA	NA	NA	NA	<0.005	NA	0.0338	<0.005	0.0238
	09/21/07	0.0216	NA	NA	245	0.209	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/09/08	<0.02	NA	NA	257	<0.2	131	17.4	865	NA	<0.005	NA	NA	NA	NA
	08/19/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/25/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/12/09	0.0254	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/20/06	<0.02	0.0657	<0.005	117	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/28/06	<0.02	0.0582	<0.005	NA	<0.2	NA	NA	NA	NA	<0.005	NA	<0.02	<0.005	<0.02
MW067SA	03/29/07	<0.02	NA	NA	139	0.255	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/11/07	<0.02	NA	NA	248	<0.2	98.6	7.78	304	NA	<0.005	NA	NA	NA	NA
	03/27/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/24/06	0.0277	0.0412	<0.005	39.3	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/27/06	0.0224	0.0414	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/20/07	0.0276	NA	NA	46.1	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/14/07	0.0305	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW0682A	04/09/08	0.0252	NA	NA	36.9	<0.2	22.8	5.12	88.6	NA	<0.005	NA	NA	NA	NA
	08/18/08	0.0265	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/02/09	0.0268	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0065	NA	NA	NA	NA
	08/03/09	0.0235	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/20/06	0.0239	0.0406	<0.005	36.7	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/27/06	0.0235	0.0425	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/20/07	0.0243	NA	NA	43.5	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/11/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/09/08	0.0246	NA	NA	36.7	<0.2	20.6	4.87	92.7	NA	<0.005	NA	NA	NA	NA
	08/18/08	0.0259	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW063A	04/02/09	0.0272	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/04/09	0.0264	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	07/22/04	<0.01	NA	NA	333	<0.01	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/12/05	<0.01	NA	NA	288	<0.40	NA	NA	NA	NA	1.75	NA	NA	NA	NA
	07/14/05	<0.01	NA	NA	144	1.75	NA	NA	NA	NA	0.5	NA	NA	NA	NA
	02/02/06	<0.02	0.0758	<0.005	304	2.82	NA	NA	NA	<0.02	0.0721	<0.0002	0.0248	<0.005	<0.02
	07/14/06	<0.02	0.0415	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0261	<0.005	<0.02
	03/21/07	<0.02	NA	NA	276	0.252	NA	NA	NA	NA	0.007	NA	NA	NA	NA
	09/06/07	<0.02	NA	NA	NA	220	NA	NA	NA	NA	NA	NA	NA	NA	NA
	03/25/08	<0.02	NA	NA	302	0.307	154	17.5	754	NA	0.0129	NA	NA	NA	NA
MW064SA	08/05/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0053	NA	NA	NA	NA
	08/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
MW065SA	NM WQCC Standard	0.1	1.0	0.01	-	1.0	-	-	-	0.05	0.2	0.002	0.05	0.05	10
	06/02/05	0.03	NA	NA	NA	<0.40	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	01/20/06	<0.02	0.0579	<0.005	342	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0238	<0.005	<0.02
	06/28/06	<0.02	0.0565	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	0.0249	<0.005	<0.02
	04/10/07	<0.02	NA	NA	327	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/11/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/08/08	<0.02	NA	NA	340	<0.2	192	13.3	395	NA	<0.005	NA	NA	NA	NA
	08/19/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0071	NA	NA	NA	NA
	03/26/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/06/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	NA	NA	NA
MW066SA	01/25/06	<0.02	0.0506	<0.005	482	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0283	<0.005	<0.02
	07/11/06	<0.02	0.0526	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.0061	NA	<0.02	<0.005	<0.02
	09/20/07	<0.02	NA	NA	NA	0.277	NA	NA	NA	NA	0.259	NA	NA	NA	NA
	08/19/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.345	NA	NA	NA	NA
	03/26/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.381	NA	NA	NA	NA
	08/06/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	01/20/06	0.0211	0.0317	<0.005	93.7	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.02	<0.005	<0.02
	07/10/06	<0.02	0.0283	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.02	<0.005	<0.02
	04/05/07	0.0209	NA	NA	93.5	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/13/07	0.0209	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW067SA	03/27/08	0.0201	NA	NA	96.3	0.226	48.1	6.54	227	NA	<0.005	NA	NA	NA	NA
	08/11/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/19/09	0.0202	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/27/06	<0.02	0.0347	<0.005	34.9	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	08/22/06	<0.02	0.0334	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	03/29/07	<0.02	NA	NA	32.3	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/11/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/25/08	<0.02	NA	NA	34.1	<0.2	19	4.59	108	NA	<0.005	NA	NA	NA	NA
	08/05/08	0.0236	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW070A	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0081	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/25/06	0.0242	0.308	<0.005	179	<0.2	NA	NA	NA	<0.02	4.06	<0.0002	<0.02	<0.005	<0.02
	07/12/06	<0.02	0.0931	<0.005	NA	<0.2	NA	NA	NA	<0.015	4.93	NA	<0.02	<0.005	<0.02
	04/03/07	<0.02	NA	NA	277	0.238	NA	NA	NA	NA	4.73	NA	NA	NA	NA
	09/19/07	0.022	NA	NA	NA	0.274	NA	NA	NA	NA	4.86	NA	NA	NA	NA
	03/27/08	<0.02	NA	NA	370	<0.2	190	8.73	309	NA	4.81	NA	NA	NA	NA
	08/12/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	2.44	NA	NA	NA	NA
	03/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.638	NA	NA	NA	NA
	08/10/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.668	NA	NA	NA	NA
MW072SA	01/23/06	0.0216	0.0258	<0.005	121	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	06/28/06	<0.02	0.0285	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/03/07	0.0205	NA	NA	125	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/14/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/27/08	<0.02	NA	NA	125	<0.2	60.7	8.2	274	NA	<0.005	NA	NA	NA	NA
	08/12/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0051	NA	NA	NA	NA
	03/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/21/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01		1.0				0.05	0.2	<0.002	0.05	0.05	10
MW073SA	01/20/06	<0.02	0.0444	<0.005	160	0.219	NA	NA	NA	<0.02	0.0066	<0.0002	<0.02	<0.005	<0.02
	06/28/06	<0.02	0.0403	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/03/07	<0.02	NA	NA	150	<0.2	NA	NA	NA	NA	0.0053	NA	NA	NA	NA
	09/13/05	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0077	NA	NA	NA	NA
	03/27/08	<0.02	NA	NA	144	<0.2	64.7	8.07	189	NA	0.0008	NA	NA	NA	NA
MW074SA	08/12/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	<0.0002	0.0388	<0.005	<0.02
	03/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	<0.0002	0.0347	<0.005	<0.02
	08/21/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	<0.0002	0.0347	<0.005	<0.02
	01/18/06	<0.02	0.0479	<0.005	242	<0.2	NA	NA	NA	<0.02	<0.005	NA	NA	NA	NA
	06/20/06	<0.02	0.0449	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	NA	NA	NA
MW075SA	04/03/07	<0.02	NA	NA	222	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/06/07	<0.02	NA	NA	209	<0.2	141	12	433	NA	<0.005	NA	NA	NA	NA
	03/20/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0067	NA	NA	NA	NA
	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	<0.0002	0.0456	<0.005	<0.02
MW076SA	08/24/09	<0.02	0.0273	<0.005	252	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0443	<0.005	<0.02
	01/19/06	<0.02	0.0282	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	NA	NA	NA
	06/21/06	<0.02	NA	NA	235	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/03/07	<0.02	NA	NA	NA	<0.2	136	13.2	455	NA	<0.005	NA	NA	NA	NA
	09/06/07	<0.02	NA	NA	220	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW077SA	03/20/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/19/06	<0.02	0.0198	<0.005	171	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0315	<0.005	<0.02
MW078SA	06/21/06	<0.02	0.0205	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.0289	<0.005	<0.02
	04/03/07	<0.02	NA	NA	178	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/07/07	0.015	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/20/08	<0.02	NA	NA	176	<0.2	111	11.2	449	NA	<0.005	NA	NA	NA	NA
	08/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW079SA	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0057	NA	NA	NA	NA
	01/19/06	<0.02	0.0336	<0.005	388	<0.2	NA	NA	NA	<0.02	0.0095	<0.0002	0.0332	<0.005	<0.02
	06/21/06	<0.02	0.0345	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	0.0352	<0.005	0.0239
	04/11/07	<0.02	NA	NA	402	<0.2	NA	NA	NA	NA	0.0136	NA	NA	NA	NA
	09/06/07	<0.02	NA	NA	NA	<0.2	219	18.9	856	NA	0.0156	NA	NA	NA	NA
MW078SA	04/08/08	<0.02	NA	NA	407	<0.2	NA	NA	NA	NA	0.0054	NA	NA	NA	NA
	08/19/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0051	NA	NA	NA	NA
	03/25/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/19/06	<0.02	0.0429	<0.005	98	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
MW078SA	06/21/06	<0.02	0.0437	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/05/07	<0.02	NA	NA	93.3	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/06/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/28/08	<0.02	NA	NA	86.1	<0.2	40	6.32	134	NA	<0.005	NA	NA	NA	NA
	08/11/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW078SA	03/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0069	NA	NA	NA	NA
	08/20/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01	—	1.0	—	—	—	0.05	0.2	0.002	0.05	0.05	10
MW079SA	11/22/04	0.006	NA	NA	599	8.2	NA	NA	NA	NA	2.3	NA	NA	NA	NA
	01/05/05	<0.01	NA	NA	630	4.43	NA	NA	NA	NA	1.35	NA	NA	NA	NA
	07/20/05	<0.01	NA	NA	729	1.97	NA	NA	NA	NA	0.91	NA	NA	NA	NA
	02/03/06	<0.02	0.417	<0.005	347	1.63	NA	NA	NA	<0.02	0.435	<0.0002	<0.02	<0.005	<0.02
	07/18/06	<0.02	0.226	<0.005	NA	0.3	NA	NA	NA	<0.015	0.288	NA	<0.02	<0.005	<0.02
	03/28/07	<0.02	NA	NA	220	2.21	NA	NA	NA	NA	0.176	NA	NA	NA	NA
	09/07/07	<0.02	NA	NA	NA	0.287	NA	NA	NA	NA	0.178	NA	NA	NA	NA
	04/02/08	<0.02	NA	NA	113	2.43	59.7	18.4	246	NA	0.128	NA	NA	NA	NA
	08/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.153	NA	NA	NA	NA
	03/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.146	NA	NA	NA	NA
MW080SA	08/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0893	NA	NA	NA	NA
	10/11/04	<0.01	NA	NA	244	<0.1	NA	NA	NA	NA	<0.05	NA	NA	NA	NA
	01/05/05	<0.01	NA	NA	220	<0.40	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	07/20/05	<0.01	NA	NA	206	<0.40	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	02/02/06	<0.02	0.0412	<0.005	206	<0.2	NA	NA	NA	<0.02	0.0275	<0.0002	<0.02	<0.005	<0.02
	07/18/06	<0.02	0.0419	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.0135	NA	<0.02	<0.005	<0.02
	03/28/07	<0.02	NA	NA	151	<0.2	NA	NA	NA	NA	0.0168	NA	NA	NA	NA
	09/07/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0134	NA	NA	NA	NA
	04/02/08	<0.02	NA	NA	118	<0.2	60.8	10.6	288	NA	0.0214	NA	NA	NA	NA
	08/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0246	NA	NA	NA	NA
MW081SA	03/23/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	10/10/04	<0.01	NA	NA	412	2.4	NA	NA	NA	NA	2.75	NA	NA	NA	NA
	01/05/05	<0.01	NA	NA	345	0.77	NA	NA	NA	NA	3.16	NA	NA	NA	NA
	07/20/05	<0.01	NA	NA	364	1.55	NA	NA	NA	NA	1.11	NA	NA	NA	NA
	02/02/06	<0.02	0.108	<0.005	340	2.24	NA	NA	NA	<0.02	0.386	<0.0002	<0.02	<0.005	<0.02
	07/18/06	<0.02	0.111	<0.005	NA	0.511	NA	NA	NA	<0.015	0.301	NA	<0.02	<0.005	<0.02
	03/28/07	<0.02	NA	NA	288	4.07	NA	NA	NA	NA	0.506	NA	NA	NA	NA
	09/07/07	<0.02	NA	NA	NA	1.13	69.1	12.4	286	NA	0.23	NA	NA	NA	NA
	04/02/08	<0.02	NA	NA	139	4.56	NA	NA	NA	NA	0.0919	NA	NA	NA	NA
MW082SA	08/06/08	<0.02	NA	NA	NA	1.76	NA	NA	NA	NA	0.0821	NA	NA	NA	NA
	03/23/09	<0.02	NA	NA	NA	0.297	NA	NA	NA	NA	0.0742	NA	NA	NA	NA
	08/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	94.4	NA	NA	NA	NA
	10/19/04	<0.10	NA	NA	1430	1600	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	01/12/05	<0.01	NA	NA	438	15.7	NA	NA	NA	NA	2.89	NA	NA	NA	NA
	07/14/05	<0.01	NA	NA	973	<0.40	NA	NA	NA	<0.02	1.06	<0.0002	<0.02	<0.005	<0.02
	02/03/06	0.0809	0.482	<0.005	425	2.2	NA	NA	NA	<0.015	1.15	NA	NA	NA	NA
	07/14/06	0.0226	0.323	<0.005	NA	<0.2	NA	NA	NA	NA	1.55	NA	NA	NA	NA
	03/22/07	<0.02	NA	NA	303	0.62	NA	NA	NA	NA	1.8	NA	NA	NA	NA
	09/06/07	<0.02	NA	NA	NA	1.87	NA	NA	NA	NA	2.07	NA	NA	NA	NA
MW083SA	03/26/08	<0.02	NA	NA	317	4.16	152	28.8	572	NA	2.1	NA	NA	NA	NA
	08/06/08	<0.02	NA	NA	NA	1.66	NA	NA	NA	NA	2.61	NA	NA	NA	NA
	03/18/09	<0.02	NA	NA	NA	4.56	NA	NA	NA	NA	3.15	NA	NA	NA	NA
	08/17/08	<0.02	NA	NA	NA	0.585	NA	NA	NA	NA	3.15	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01	—	1.0	—	—	—	0.05	0.2	0.002	0.05	0.05	10
MW083SA	10/19/04	<0.10	NA	NA	1720	2970	NA	NA	NA	NA	255	NA	NA	NA	NA
	01/13/05	<0.01	NA	NA	504	26.2	NA	NA	NA	NA	1.98	NA	NA	NA	NA
	07/14/05	<0.01	NA	NA	788	<0.40	NA	NA	NA	NA	3.6	NA	NA	NA	NA
	02/03/06	0.0899	0.6	<0.005	598	2.84	NA	NA	NA	<0.02	8.88	0.002	<0.02	<0.005	<0.02
	07/14/06	0.0486	0.523	<0.005	NA	<0.2	NA	NA	NA	<0.015	5.04	NA	<0.02	<0.005	<0.02
	03/22/07	0.0281	NA	NA	473	1.29	NA	NA	NA	NA	2.55	NA	NA	NA	NA
	09/06/07	0.0204	NA	NA	NA	0.2	NA	NA	NA	NA	2.01	NA	NA	NA	NA
	03/25/08	<0.02	NA	NA	337	0.456	196	29.6	631	NA	1.26	NA	NA	NA	NA
	08/06/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.103	NA	NA	NA	NA
	03/18/09	<0.02	NA	NA	NA	8.65	NA	NA	NA	NA	1.12	NA	NA	NA	NA
MW084SA	08/17/09	<0.02	NA	NA	NA	0.52	NA	NA	NA	NA	1.09	NA	NA	NA	NA
	10/20/04	<0.01	NA	NA	550	<0.2	NA	NA	NA	NA	<0.05	NA	NA	NA	NA
	01/13/05	<0.01	NA	NA	522	1.61	NA	NA	NA	NA	0.02	NA	NA	NA	NA
	07/18/05	<0.01	NA	NA	418	<0.40	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	02/03/06	<0.02	0.0679	<0.005	495	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0338	<0.005	<0.02
	07/14/06	<0.02	0.0525	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0264	<0.005	<0.02
	03/21/07	<0.02	NA	NA	452	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/06/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/25/08	<0.02	NA	NA	534	<0.2	276	24.2	999	NA	<0.005	NA	NA	NA	NA
	08/05/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW085SA	03/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/13/09	0.0229	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	10/20/04	<0.01	NA	NA	420	0.1	NA	NA	NA	NA	<0.05	NA	NA	NA	NA
	01/13/05	<0.01	NA	NA	339	0.44	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	07/18/05	<0.01	NA	NA	330	<0.40	NA	NA	NA	NA	0.03	NA	NA	NA	NA
	02/03/06	<0.02	0.224	<0.005	336	0.89	NA	NA	NA	<0.02	0.24	<0.0002	0.0238	<0.005	<0.02
	07/14/06	<0.02	0.0657	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.0221	NA	<0.02	<0.005	<0.02
	03/21/07	<0.02	NA	NA	315	1.52	NA	NA	NA	NA	0.0917	NA	NA	NA	NA
	09/06/07	<0.02	NA	NA	NA	1.31	NA	NA	NA	NA	0.111	NA	NA	NA	NA
	03/25/08	<0.02	NA	NA	309	<0.2	159	15.5	836	NA	0.0089	NA	NA	NA	NA
MW086SA	08/05/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.0061	NA	NA	NA	NA
	03/18/09	<0.02	NA	NA	NA	0.435	NA	NA	NA	NA	0.197	NA	NA	NA	NA
	08/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/14/04	<0.01	NA	NA	491	0.1	NA	NA	NA	NA	<0.05	NA	NA	NA	NA
	01/13/05	<0.01	NA	NA	460	<0.40	NA	NA	NA	NA	C	NA	NA	NA	NA
	06/02/05	<0.01	NA	NA	383	<0.40	NA	NA	NA	NA	<0.01	NA	NA	NA	NA
	01/27/06	<0.02	0.0339	<0.005	304	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	07/12/06	<0.02	0.0386	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.02	<0.005	<0.02
	04/11/07	<0.02	NA	NA	327	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/21/07	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW086SA	04/08/08	<0.02	NA	NA	313	<0.2	170	11.8	383	NA	<0.005	NA	NA	NA	NA
	08/19/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	03/25/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/10/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/10/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
MW087A	NM WQCC Standard	0.1	1.0	0.01		1.0				0.05	0.2	0.002	0.05	0.05	10
	09/14/04	<0.01	NA	NA	452	<0.2	NA	NA	NA	NA	<0.05	NA	NA	NA	NA
	01/13/05	<0.01	NA	NA	525	<0.40	NA	NA	NA	NA	0.42	NA	NA	NA	NA
	07/06/05	<0.01	NA	NA	449	0.94	NA	NA	NA	NA	1.11	NA	NA	NA	NA
	02/06/06	0.0222	4.52	<0.005	558	14.5	NA	NA	NA	<0.02	6.61	0.001	<0.02	<0.005	<0.02
	07/18/06	<0.02	2.92	<0.005	NA	<0.217	NA	NA	NA	<0.015	3.5	NA	<0.02	<0.005	<0.02
	04/13/07	<0.02	NA	NA	393	13	NA	NA	NA	NA	1.72	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/15/08	0.0276	NA	NA	378	4.27	345	17.4	737	NA	1.4	NA	NA	NA	NA
	03/30/09	0.0241	NA	NA	NA	1.23	NA	NA	NA	NA	0.786	NA	NA	NA	NA
MW089SA	02/09/06	<0.02	0.0401	<0.005	397	<0.284	NA	NA	NA	<0.02	0.0131	<0.0002	0.038	<0.005	0.0289
	07/21/06	<0.02	0.0219	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0532	<0.005	<0.02
	04/04/07	<0.02	NA	NA	277	<0.2	NA	NA	NA	NA	0.0056	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/09/08	<0.02	NA	NA	407	<0.2	193	16.5	549	NA	0.0118	NA	NA	NA	NA
	03/26/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	02/09/06	<0.02	0.0458	<0.005	327	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0383	<0.005	<0.02
	07/21/06	<0.02	0.0375	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0408	<0.005	<0.02
	04/03/07	<0.02	NA	NA	366	<0.2	NA	NA	NA	NA	0.0051	NA	NA	NA	NA
	04/14/08	<0.02	NA	NA	381	<0.2	118	11.2	461	NA	<0.005	NA	NA	NA	NA
MW090SA	03/17/09	<0.02	NA	NA	NA	<0.2	NA	NA	492	NA	<0.005	NA	NA	NA	NA
	08/11/09	<0.02	NA	NA	NA	<0.2	NA	NA	472	NA	<0.005	NA	NA	NA	NA
	02/09/06	<0.02	0.0452	<0.005	334	<0.2	NA	NA	NA	<0.02	0.0051	<0.0002	0.0325	<0.005	<0.02
	07/24/06	<0.02	0.0387	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0417	<0.005	<0.02
	04/05/07	<0.02	NA	NA	351	<0.2	NA	NA	NA	NA	0.0075	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	<0.2	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/07/08	<0.02	NA	NA	453	<0.2	133	14.3	446	NA	<0.005	NA	NA	NA	NA
	03/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	02/09/06	<0.02	0.051	<0.005	337	0.536	NA	NA	NA	<0.02	0.0102	<0.0002	0.0413	<0.005	<0.02
	07/24/06	<0.02	0.0307	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0483	<0.005	<0.02
MW092SA	04/05/07	<0.02	NA	NA	350	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	<0.2	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/08/08	<0.02	NA	NA	427	0.282	130	14.5	595	NA	<0.005	NA	NA	NA	NA
	03/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	02/09/06	<0.02	0.084	<0.005	349	1.66	NA	NA	NA	<0.02	0.0457	<0.0002	0.0399	<0.005	<0.02
	07/24/06	<0.02	0.0308	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.0053	NA	0.0387	<0.005	<0.02
	04/05/07	<0.02	NA	NA	235	0.883	NA	NA	NA	NA	0.0731	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	<0.2	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/08/08	<0.02	NA	NA	413	<0.2	120	14.9	569	NA	<0.005	NA	NA	NA	NA
	03/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
MW093SA	09/14/04	<0.01	NA	NA	452	<0.2	NA	NA	NA	NA	<0.05	NA	NA	NA	NA
	01/13/05	<0.01	NA	NA	525	<0.40	NA	NA	NA	NA	0.42	NA	NA	NA	NA
	07/06/05	<0.01	NA	NA	449	0.94	NA	NA	NA	NA	1.11	NA	NA	NA	NA
	02/06/06	0.0222	4.52	<0.005	558	14.5	NA	NA	NA	<0.02	6.61	0.001	<0.02	<0.005	<0.02
	07/18/06	<0.02	2.92	<0.005	NA	<0.217	NA	NA	NA	<0.015	3.5	NA	<0.02	<0.005	<0.02
	04/13/07	<0.02	NA	NA	393	13	NA	NA	NA	NA	1.72	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/15/08	0.0276	NA	NA	378	4.27	345	17.4	737	NA	1.4	NA	NA	NA	NA
	03/30/09	0.0241	NA	NA	NA	1.23	NA	NA	NA	NA	0.786	NA	NA	NA	NA
	02/09/06	<0.02	0.0401	<0.005	397	<0.284	NA	NA	NA	<0.02	0.0131	<0.0002	0.038	<0.005	0.0289
	07/21/06	<0.02	0.0219	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0532	<0.005	<0.02

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
RW004A	09/16/04	0.1	1.0	0.01	1580	166	NA	NA	NA	0.05	0.2	0.002	0.05	0.05	10
	01/18/05	<0.05	NA	NA	722	78.5	NA	NA	NA	NA	5.2	NA	NA	NA	NA
	07/07/05	<0.05	NA	NA	726	51.8	NA	NA	NA	NA	14.9	NA	NA	NA	NA
	02/10/06	0.0207	0.363	<0.005	430	70.3	NA	NA	NA	<0.02	7.7	0.004	<0.02	<0.005	0.281
	07/19/06	<0.02	0.565	<0.005	223	478	NA	NA	NA	<0.015	4.77	NA	<0.02	<0.005	0.376
	04/11/07	0.1	NA	NA	1840	478	NA	NA	NA	NA	7.68	NA	NA	NA	NA
IW003	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/16/08	0.0672	NA	NA	2090	697	178	384	124	NA	9.38	NA	NA	NA	NA
	03/31/09	0.0257	NA	NA	NA	886	NA	NA	NA	NA	13	NA	NA	NA	NA
	10/11/04	NA	NA	NA	5860	149	NA	NA	NA	NA	51.1	NA	NA	NA	NA
	01/27/05	NA	NA	NA	2250	61.6	NA	NA	NA	NA	24	NA	NA	NA	NA
	07/21/05	NA	NA	NA	2090	83.3	NA	NA	NA	NA	17.2	NA	NA	NA	NA
IW004	02/06/06	0.278	1.03	<0.005	3980	158	NA	NA	NA	<0.02	48.5	<0.01	0.0796	0.0131	0.252
	07/25/06	0.205	1.71	<0.005	NA	4.69	NA	NA	NA	<0.015	33.5	NA	<0.02	<0.005	<0.02
	04/09/07	0.358	NA	NA	1000	27.3	NA	NA	NA	NA	14.8	NA	NA	NA	NA
	04/03/08	0.254	NA	NA	756	26.1	256	209	306	NA	15.3	NA	NA	NA	NA
	03/23/09	0.188	NA	NA	NA	22.5	NA	NA	NA	NA	12.5	NA	NA	NA	NA
	07/21/05	NA	NA	NA	NA	71.2	NA	NA	NA	NA	11.1	NA	NA	NA	NA
IW005	02/06/06	0.0547	0.443	<0.005	1300	42.9	NA	NA	NA	<0.02	8.19	<0.001	0.0507	<0.005	0.0673
	07/25/06	0.0618	0.882	<0.005	NA	1.92	NA	NA	NA	<0.015	16.7	NA	<0.02	<0.005	<0.02
	04/09/07	0.0612	NA	NA	569	4.09	NA	NA	NA	NA	6.84	NA	NA	NA	NA
	04/03/08	0.0218	NA	NA	551	<0.2	233	87	507	NA	5.85	NA	NA	NA	NA
	03/23/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	3.83	NA	NA	NA	NA
	10/11/04	NA	NA	NA	NA	170	NA	NA	NA	NA	11.1	NA	NA	NA	NA
IW006	01/27/05	NA	NA	NA	NA	34.2	NA	NA	NA	NA	2.1	NA	NA	NA	NA
	07/13/05	NA	NA	NA	NA	95.3	NA	NA	NA	NA	3.9	NA	NA	NA	NA
	02/06/06	0.0595	0.675	<0.005	2200	197	NA	NA	NA	<0.02	15.6	<0.002	0.0636	<0.005	0.339
	07/26/06	0.096	0.675	<0.005	NA	49.3	NA	NA	NA	<0.015	19	NA	0.0428	<0.005	0.0909
	03/27/07	0.272	NA	NA	875	13.8	NA	NA	NA	NA	3.14	NA	NA	NA	NA
	04/12/07	0.329	NA	NA	726	6.33	NA	NA	NA	NA	2.15	NA	NA	NA	NA
IW006	04/01/08	0.154	NA	NA	681	23.5	302	221	277	NA	4.69	NA	NA	NA	NA
	03/23/09	0.0571	NA	NA	NA	6.21	NA	NA	NA	NA	1.8	NA	NA	NA	NA
	10/13/04	NA	NA	NA	3560	202	NA	NA	NA	NA	26.5	NA	NA	NA	NA
	01/10/05	NA	NA	NA	3110	240	NA	NA	NA	NA	35.3	NA	NA	NA	NA
	07/13/05	NA	NA	NA	1770	114	NA	NA	NA	NA	17.4	NA	NA	NA	NA
	02/07/06	0.118	1	0.0058	2720	184	NA	NA	NA	<0.0289	41.5	<0.004	0.0758	0.012	0.338
IW006	07/26/06	0.288	0.763	<0.005	NA	5.41	NA	NA	NA	<0.015	10.4	NA	<0.02	<0.005	<0.02
	03/27/07	0.203	NA	NA	784	16.4	NA	NA	NA	NA	6.21	NA	NA	NA	NA
	04/12/07	0.16	NA	NA	637	10.1	NA	NA	NA	NA	3.6	NA	NA	NA	NA
	04/01/08	0.129	NA	NA	597	8.04	219	181	264	NA	6.46	NA	NA	NA	NA
	03/19/09	0.0781	NA	NA	NA	6.9	NA	NA	NA	NA	5.59	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01		1.0				0.05	0.2	0.002	0.05	0.05	10
IW007	12/02/04	NA	NA	NA	3400	217	NA	NA	NA	NA	11.2	NA	NA	NA	NA
	01/10/05	NA	NA	NA	1930	137	NA	NA	NA	NA	7.6	NA	NA	NA	NA
	07/13/05	NA	NA	NA	1400	90.7	NA	NA	NA	NA	5.5	NA	NA	NA	NA
	02/07/06	0.125	0.756	0.0058	3930	213	NA	NA	NA	0.0425	21.5	<0.004	0.075	0.008	0.432
	07/26/06	0.0599	0.741	<0.005	NA	44.9	NA	NA	NA	<0.015	16.2	NA	0.0774	0.005	0.259
IW008	03/26/07	0.0622	NA	NA	5090	69.3	NA	NA	NA	NA	27.5	NA	NA	NA	NA
	04/01/08	0.0464	NA	NA	3410	93.5	887	303	331	NA	31.8	NA	NA	NA	NA
	03/19/09	0.299	NA	NA	NA	14	NA	NA	NA	NA	2.03	NA	NA	NA	NA
	10/13/04	NA	NA	NA	2330	221	NA	NA	NA	NA	10.3	NA	NA	NA	NA
	01/11/05	NA	NA	NA	1320	106	NA	NA	NA	NA	7.5	NA	NA	NA	NA
IW009	07/13/05	NA	NA	NA	912	88.7	NA	NA	NA	NA	1.8	NA	NA	NA	NA
	02/07/06	0.0674	0.472	<0.005	1280	156	NA	NA	NA	<0.015	10.4	<0.004	0.022	<0.005	0.287
	07/26/06	0.161	0.438	<0.005	NA	3	NA	NA	NA	<0.015	2.85	NA	<0.02	<0.005	<0.02
	03/23/07	0.287	NA	NA	623	21.2	NA	NA	NA	NA	4.09	NA	NA	NA	NA
	04/01/08	0.144	NA	NA	568	20.3	242	111	242	NA	4.17	NA	NA	NA	NA
IW010	03/19/09	0.0783	NA	NA	NA	13.3	NA	NA	NA	NA	3.7	NA	NA	NA	NA
	10/14/04	NA	NA	NA	3700	236	NA	NA	NA	NA	15.2	NA	NA	NA	NA
	01/11/05	NA	NA	NA	3470	230	NA	NA	NA	NA	13.1	NA	NA	NA	NA
	07/13/05	NA	NA	NA	1940	114	NA	NA	NA	NA	6.2	NA	NA	NA	NA
	02/07/06	0.138	0.718	<0.005	1760	180	NA	NA	NA	<0.02	18.1	<0.01	0.115	0.0087	0.414
IW011	07/27/06	0.0982	0.683	<0.005	NA	79.8	NA	NA	NA	<0.0242	13.3	NA	0.134	<0.005	0.574
	03/31/08	0.0562	NA	NA	2370	52.6	810	234	362	NA	24.3	NA	NA	NA	NA
	03/19/09	<0.1	NA	NA	NA	46.1	NA	NA	NA	NA	25.9	NA	NA	NA	NA
	10/14/04	NA	NA	NA	6590	354	NA	NA	NA	NA	<0.5	NA	NA	NA	NA
	01/11/05	NA	NA	NA	4980	344	NA	NA	NA	NA	134	NA	NA	NA	NA
IW012	07/13/05	NA	NA	NA	3310	355	NA	NA	NA	NA	81.4	NA	NA	NA	NA
	02/07/06	0.0906	1.07	<0.005	1560	117	NA	NA	NA	NA	42.4	<0.004	<0.02	0.0117	<0.02
	07/27/06	0.0605	0.754	<0.005	NA	54.3	NA	NA	NA	<0.015	9.86	NA	<0.02	<0.005	<0.02
	03/23/07	0.397	NA	NA	500	15.3	NA	NA	NA	NA	10.9	NA	NA	NA	NA
	03/31/08	0.0411	NA	NA	403	17.4	162	86	412	NA	11.7	NA	NA	NA	NA
IW013	03/19/09	0.0208	NA	NA	NA	18.1	NA	NA	NA	NA	11.7	NA	NA	NA	NA
	10/14/04	NA	NA	NA	1720	53	NA	NA	NA	NA	4.7	NA	NA	NA	NA
	01/12/05	NA	NA	NA	1830	97.8	NA	NA	NA	NA	0.38	NA	NA	NA	NA
	07/14/05	NA	NA	NA	1820	48.1	NA	NA	NA	NA	2.4	NA	NA	NA	NA
	02/08/06	0.0537	0.751	<0.005	3890	161	NA	NA	NA	<0.02	11.6	<0.004	0.0451	<0.005	0.334
IW014	07/26/06	0.0257	0.257	<0.005	NA	57	NA	NA	NA	<0.015	11.8	NA	0.0363	<0.005	<0.02
	03/22/07	0.108	NA	NA	1090	10.8	NA	NA	NA	NA	2.41	NA	NA	NA	NA
	03/31/08	0.187	NA	NA	913	8.03	204	182	239	NA	2.7	NA	NA	NA	NA
	03/18/09	0.0874	NA	NA	NA	4.3	NA	NA	NA	NA	2.18	NA	NA	NA	NA
	10/19/04	NA	NA	NA	4080	360	NA	NA	NA	NA	19.5	NA	NA	NA	NA
IW015	01/12/05	NA	NA	NA	2700	309	NA	NA	NA	NA	18.5	NA	NA	NA	NA
	07/14/05	NA	NA	NA	2300	254	NA	NA	NA	NA	6.2	NA	NA	NA	NA
	02/08/06	0.0405	0.517	<0.005	1960	295	NA	NA	NA	NA	6.2	<0.004	0.0626	<0.005	0.511
	07/27/06	0.033	0.78	<0.005	NA	47.7	NA	NA	NA	<0.015	1.35	NA	<0.02	<0.005	<0.02
	03/22/07	0.0342	NA	NA	674	10.1	NA	NA	NA	NA	1.83	NA	NA	NA	NA
IW016	03/26/08	<0.02	NA	NA	347	0.247	143	52.2	412	NA	0.315	NA	NA	NA	NA
	03/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.282	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01	—	100	—	—	—	0.05	0.2	0.002	0.05	0.05	10
IW014	10/19/04	NA	NA	NA	2150	1160	NA	NA	NA	NA	62.3	NA	NA	NA	NA
	01/13/05	NA	NA	NA	1770	147	NA	NA	NA	NA	1.1	NA	NA	NA	NA
	07/14/05	NA	NA	NA	2600	65.9	NA	NA	NA	NA	0.7	NA	NA	NA	NA
	02/13/06	0.0518	0.816	<0.005	4120	466	NA	NA	NA	<0.02	5.3	<0.004	0.068	<0.005	1.24
	07/25/06	0.047	0.304	0.0081	NA	228	NA	NA	NA	<0.015	3.34	NA	<0.02	<0.005	<0.0299
IW015	03/26/07	0.0877	NA	NA	2440	144	NA	NA	NA	NA	2.43	NA	NA	NA	NA
	03/28/07	0.0819	NA	NA	NA	141	NA	NA	NA	NA	2.4	NA	NA	NA	NA
	03/26/08	0.173	NA	NA	1590	14.9	152	284	779	NA	0.678	NA	NA	NA	NA
	03/18/09	0.229	NA	NA	NA	1.59	NA	NA	NA	NA	0.413	NA	NA	NA	NA
	10/11/04	NA	NA	NA	7160	121	NA	NA	NA	NA	11.6	NA	NA	NA	NA
IW016	01/05/05	NA	NA	NA	6360	86.2	NA	NA	NA	NA	7.1	NA	NA	NA	NA
	07/21/05	NA	NA	NA	6490	55	NA	NA	NA	NA	3.62	NA	NA	NA	NA
	02/09/06	0.0808	1.34	<0.005	8070	53.1	NA	NA	NA	<0.02	4.4	<0.01	0.0446	<0.005	0.216
	07/25/06	0.216	1.33	<0.005	NA	10.4	NA	NA	NA	<0.015	0.786	NA	<0.02	<0.005	<0.02
	04/08/07	0.485	NA	NA	1000	21	NA	NA	NA	NA	0.443	NA	NA	NA	NA
IW018	04/03/08	0.236	NA	NA	531	20.3	189	391	344	NA	0.402	NA	NA	NA	NA
	03/23/09	0.187	NA	NA	NA	14.8	NA	NA	NA	NA	0.339	NA	NA	NA	NA
	10/10/04	NA	NA	NA	3320	185	NA	NA	NA	NA	4.1	NA	NA	NA	NA
	01/04/05	NA	NA	NA	4700	211	NA	NA	NA	NA	7.6	NA	NA	NA	NA
	07/20/05	NA	NA	NA	4430	213	NA	NA	NA	NA	12	NA	NA	NA	NA
IW019	02/08/06	0.185	1.25	<0.005	5890	270	NA	NA	NA	<0.0272	13.1	<0.004	0.142	<0.005	0.524
	07/25/06	0.133	0.672	<0.005	NA	117	NA	NA	NA	<0.015	13.4	NA	<0.02	<0.005	<0.02
	03/28/07	0.06	NA	NA	926	13.4	NA	NA	NA	NA	1.42	NA	NA	NA	NA
	04/02/08	0.0586	NA	NA	551	11.5	107	377	313	NA	0.978	NA	NA	NA	NA
	03/24/09	0.0537	NA	NA	NA	14.4	NA	NA	NA	NA	0.978	NA	NA	NA	NA
IW020	02/06/06	0.112	0.147	<0.005	204	10.1	NA	NA	NA	<0.02	0.512	<0.0002	0.0274	<0.005	<0.02
	07/21/06	<0.02	0.104	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.295	NA	<0.02	<0.005	<0.02
	04/08/07	<0.02	NA	NA	108	0.705	NA	NA	NA	NA	0.5	NA	NA	NA	NA
	04/09/08	0.051	NA	NA	171	3.16	67.3	26.7	975	NA	0.438	NA	NA	NA	NA
	03/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.92	NA	NA	NA	NA
IW021	02/07/06	<0.02	0.0589	<0.005	333	<0.2	NA	NA	NA	<0.02	0.0405	<0.0002	0.0432	<0.005	<0.02
	07/24/06	<0.02	0.0498	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.0314	NA	0.0504	<0.005	<0.02
	04/08/07	<0.02	NA	NA	356	<0.2	NA	NA	NA	NA	0.0268	NA	NA	NA	NA
	04/06/08	<0.02	NA	NA	359	<0.2	163	20.8	1140	NA	0.0283	NA	NA	NA	NA
	03/25/09	<0.02	0.0368	<0.005	280	<0.2	NA	NA	NA	<0.02	0.0297	NA	NA	NA	NA
IW022	02/07/06	<0.02	0.037	<0.005	NA	<0.2	NA	NA	NA	<0.02	0.017	<0.0002	0.0362	<0.005	<0.02
	07/24/06	<0.02	0.037	<0.005	NA	<0.2	NA	NA	NA	<0.015	0.0077	NA	0.0416	<0.005	<0.02
	04/10/07	<0.02	NA	NA	456	3.23	NA	NA	NA	NA	0.124	NA	NA	NA	NA
	04/08/08	<0.02	NA	NA	415	<0.2	179	16.2	828	NA	0.0295	NA	NA	NA	NA
	03/25/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	NA	NA	NA
IW023	02/07/06	<0.02	0.0391	<0.005	300	<0.2	NA	NA	NA	<0.02	<0.0002	<0.0002	0.0441	<0.005	<0.02
	07/24/06	<0.02	0.0327	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0511	<0.005	<0.02
	04/05/07	<0.02	NA	NA	317	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/08/08	<0.02	NA	NA	434	<0.2	128	14.3	569	NA	<0.005	NA	NA	NA	NA
	03/25/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
NM WQCC Standard		0.1	1.0	0.01		1.0				0.05	0.2	0.002	0.05	0.05	10
IW022	02/07/06	<0.02	0.0515	<0.005	273	0.298	NA	NA	NA	<0.02	0.103	<0.0002	<0.0264	<0.005	<0.02
	07/25/06	<0.02	0.0451	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0324	<0.005	<0.02
	04/10/07	<0.02	NA	NA	345	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/07/08	<0.02	NA	NA	408	<0.2	108	11.2	428	NA	<0.005	NA	NA	NA	NA
IW023	03/25/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	02/07/06	<0.02	0.0654	<0.005	282	1.08	NA	NA	NA	<0.02	0.0441	<0.0002	0.0389	<0.005	<0.02
	07/25/06	<0.02	0.0347	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.031	<0.005	<0.02
	04/10/07	<0.02	NA	NA	311	0.215	NA	NA	NA	NA	0.0069	NA	NA	NA	NA
IW024	04/07/08	<0.02	NA	NA	376	2.02	104	10.5	377	NA	0.0342	NA	NA	NA	NA
	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	351	NA	<0.005	NA	NA	NA	NA
	08/11/09	<0.02	NA	NA	NA	<0.2	NA	NA	343	NA	<0.005	NA	NA	NA	NA
	02/08/06	<0.02	0.0399	<0.005	453	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0594	<0.005	<0.02
IW025	07/21/06	<0.02	0.0357	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0597	<0.005	<0.02
	04/03/07	<0.02	NA	NA	458	<0.2	NA	NA	NA	NA	0.0061	NA	NA	NA	NA
	04/15/08	<0.02	NA	NA	403	<0.2	133	15.1	518	NA	<0.005	NA	NA	NA	NA
	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	609	NA	0.847	NA	NA	NA	NA
IW026	08/11/09	<0.02	NA	NA	NA	<0.2	NA	NA	601	NA	0.398	NA	NA	NA	NA
	02/08/06	<0.02	0.0445	<0.005	284	0.4	NA	NA	NA	<0.02	0.0077	<0.0002	0.0392	<0.005	<0.02
	07/21/06	<0.02	0.0405	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0523	<0.005	<0.02
	04/03/07	<0.02	NA	NA	381	0.978	NA	NA	NA	NA	0.0146	NA	NA	NA	NA
IW027	04/14/08	<0.02	NA	NA	439	0.451	131	15.3	477	NA	0.0066	NA	NA	NA	NA
	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	661	NA	0.157	NA	NA	NA	NA
	08/13/09	<0.02	NA	NA	NA	<0.2	NA	NA	563	NA	0.263	NA	NA	NA	NA
	02/08/06	<0.02	0.0362	<0.005	348	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.049	<0.005	<0.02
IW028	07/21/06	<0.02	0.0336	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0499	<0.005	<0.02
	04/03/07	<0.02	NA	NA	216	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	04/14/08	<0.02	NA	NA	221	0.648	74.9	6.97	246	NA	0.0178	NA	NA	NA	NA
	03/16/09	<0.02	NA	NA	NA	<0.2	NA	NA	279	NA	<0.005	NA	NA	NA	NA
IW029	08/13/09	<0.02	NA	NA	NA	<0.2	NA	NA	246	NA	<0.005	NA	NA	NA	NA
	02/08/06	<0.02	0.0396	<0.005	412	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0516	<0.005	<0.02
	07/21/06	<0.02	0.0386	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.0543	<0.005	<0.02
	04/04/07	<0.02	NA	NA	114	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
IW030	04/14/08	<0.02	NA	NA	388	0.254	115	11.1	442	NA	0.008	NA	NA	NA	NA
	03/25/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	02/08/06	<0.02	0.0338	<0.005	304	<0.2	NA	NA	NA	<0.02	0.0079	<0.0002	0.0488	<0.005	<0.02
	07/21/06	<0.02	0.0352	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	0.038	<0.005	<0.02
IW031	04/04/07	<0.02	NA	NA	234	0.653	NA	NA	NA	NA	0.0202	NA	NA	NA	NA
	04/15/08	<0.02	NA	NA	255	<0.2	102	12.8	434	NA	<0.005	NA	NA	NA	NA
	04/07/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
							WATER WELLS								
GOPWW2	01/19/06	<0.02	0	<0.005	161	10.3	NA	NA	NA	<0.02	0.787	<0.0002	<0.02	<0.005	<0.02
	06/28/06	<0.02	0.0992	<0.005	NA	<0.2	NA	NA	NA	<0.02	0.597	NA	<0.02	<0.005	<0.02
	04/23/07	<0.02	NA	NA	162	6.3	NA	NA	NA	NA	0.26	NA	NA	NA	NA
	09/10/07	<0.02	NA	NA	NA	13.8	NA	NA	NA	NA	0.405	NA	NA	NA	NA
	03/24/08	<0.02	NA	NA	262	5.39	233	16.6	630	NA	0.559	NA	NA	NA	NA
	08/05/08	<0.02	NA	NA	NA	1.06	NA	NA	NA	NA	0.354	NA	NA	NA	NA
	03/17/09	<0.02	NA	NA	NA	2.18	NA	NA	NA	NA	0.513	NA	NA	NA	NA
	08/18/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.577	NA	NA	NA	NA

TABLE 3
SUMMARY OF 2009 INORGANIC METALS ANALYTICAL RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Arsenic	Barium	Cadmium	Calcium	Iron	Magnesium	Potassium	Sodium	Lead	Manganese	Mercury	Selenium	Silver	Zinc
LordWW	NM WQCC Standard	0.1	1.0	0.01	—	1.0	—	—	—	0.05	0.2	0.002	0.05	0.05	10
	01/23/06	<0.02	0.0368	<0.005	465	9.2	NA	NA	NA	<0.02	0.0465	<0.0002	0.0463	<0.005	<0.02
	06/27/06	<0.02	0.0627	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	<0.02
	04/05/07	<0.02	NA	NA	406	31.3	NA	NA	NA	NA	0.34	NA	NA	NA	NA
	09/18/07	7.32	NA	NA	NA	7.32	NA	NA	NA	NA	0.192	NA	NA	NA	NA
	03/26/08	<0.02	NA	NA	438	28.1	248	18.6	521	NA	0.272	NA	NA	NA	NA
	08/13/08	<0.02	NA	NA	NA	4.17	NA	NA	NA	NA	0.144	NA	NA	NA	NA
	03/19/09	<0.02	NA	NA	NA	4.2	NA	NA	NA	NA	0.138	NA	NA	NA	NA
ROLANDWW	08/21/09	<0.02	NA	NA	NA	1.34	NA	NA	NA	NA	0.139	NA	NA	NA	NA
	04/06/09	Well is Inaccessible													
WoodellWW	12/21/04	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	05/25/05	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	01/24/06	<0.02	0.036	<0.005	321	<0.2	NA	NA	NA	<0.02	<0.005	<0.0002	0.0226	<0.005	<0.02
	06/27/06	<0.02	0.0391	<0.005	NA	<0.2	NA	NA	NA	<0.02	<0.005	NA	<0.02	<0.005	0.184
	03/29/07	<0.02	NA	NA	317	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	09/01/07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	04/15/08	<0.02	NA	NA	<130.0	1.14	49.1	7.74	142	NA	<0.02	NA	NA	NA	NA
	08/21/08	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
EPWW1	03/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	08/24/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	<0.005	NA	NA	NA	NA
	01/26/06	<0.02	0.0683	<0.005	75.9	0.475	NA	NA	NA	<0.02	<0.005	<0.0002	<0.02	<0.005	<0.02
	07/06/06	<0.02	0.0615	<0.005	NA	<0.2	NA	NA	NA	<0.015	<0.005	NA	<0.02	<0.005	<0.02
	04/06/09	<0.02	NA	NA	NA	<0.2	NA	NA	NA	NA	0.251	NA	NA	NA	NA

Notes:
Bold = Detections exceeding the New Mexico Water Quality Control Commission (NM WQCC) Human Health or Domestic Water Supply Standards (if standards are available).
Sample Date followed by asterisk = Due to excessive foaming of the sample, normal reporting limits were not attained. Preservation requirements were not met.
mg/L = milligrams per liter
NA = Not Applicable
< = less than - the number following the sign is the limit of quantitation, the smallest amount of analyte which can be reliably determined using the specific analytical test.
-- = Not Analyzed

TABLE 4
SUMMARY OF 2009 GROUNDWATER PARAMETER
RESULTS

TABLE 4.
SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	pH	Alkalinity to pH 8.3	Alkalinity to pH 4.5	Total Dissolved Solids	Total Organic Carbon	Sulfide	Sulfate	Nitrate Nitrogen	Bicarbonate Alkalinity	Carbonate Alkalinity
	Units	NA	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM-WQCC Standard	6-9	NA	NA	NA	1000	NA	NA	600	10	NA	NA
SHALLOW ZONE WELLS											
MW001	04/17/08	7.2	<2.0	472	3050	NA	NA	1800	2.4	472	<2.0
	03/11/09					No Access (1st Half 2009) - Due to Construction Activity					
MW002	04/02/08	7.3	<2.0	188	2730	NA	NA	679	33.1	188	<2.0
	03/31/09	NA	NA	NA	3290	NA	NA	NA	NA	NA	NA
MW003	04/03/08	7.4	<2.0	262	2180	NA	NA	815	18.2	262	<2.0
	03/11/09					No Access (1st Half 2009) - Due to Construction Activity					
MW004	04/15/08	7.1	<2.0	230	3360	NA	NA	1370	7.9	230	<2.0
	03/30/09	NA	NA	NA	3940	NA	NA	NA	NA	NA	NA
MW005	04/17/08	6.9	<2.0	439	4910	NA	NA	867	0.7	439	<2.0
	04/07/09	NA	NA	NA	2680	NA	NA	NA	NA	NA	NA
MW006	04/17/08	6.8	<2.0	577	5660	NA	NA	99.8	<0.5	577	<2.0
	04/07/09	NA	NA	NA	4340	NA	NA	NA	NA	NA	NA
MW007	04/03/08	7.5	<2.0	273	1390	NA	NA	480	5.5	273	<2.0
	03/11/09					No Access (1st Half 2009) - Due to Construction Activity					
MW008	04/15/08	6.5	<2.0	905	3140	NA	NA	599	<0.5	905	<2.0
	03/30/09	NA	NA	NA	3730	NA	NA	NA	NA	NA	NA
MW008M	04/16/08	6.8	<2.0	2770	5730	NA	NA	<5.0	<0.5	2770	<2.0
	03/31/09	NA	NA	NA	5300	NA	NA	NA	NA	NA	NA
MW009	04/15/08	7.3	<2.0	268	1990	NA	NA	700	14.4	268	<2.0
	03/26/09	NA	NA	NA	2100	NA	NA	NA	NA	NA	NA
MW010	04/07/08	7	<2.0	207	5140	NA	NA	693	4.3	207	<2.0
	08/13/08	6.9	<2.0	202	5460	NA	NA	866	NA	NA	NA
	03/26/09	NA	NA	NA	5670	NA	NA	NA	NA	NA	NA
MW011	04/16/08	6.9	<2.0	201	5040	NA	NA	1470	11.3	201	<2.0
	03/31/09	NA	NA	NA	5530	NA	NA	NA	NA	NA	NA
MW011M	04/16/08	7.1	<2.0	1510	4680	NA	NA	597	<0.5	1510	<2.0
	03/31/09	NA	NA	NA	5250	NA	NA	NA	NA	NA	NA
MW012	04/17/08	6.6	<2.0	947	2640	NA	NA	93	<0.5	947	<2.0
	04/07/09	NA	NA	NA	2220	NA	NA	NA	NA	NA	NA
MW012M	04/17/08	6.4	<2.0	5770	18000	NA	NA	<5.0	<0.5	5770	<2.0
	04/07/09	NA	NA	NA	8270	NA	NA	NA	NA	NA	NA
MW013	04/15/08	7.3	<2.0	230	1990	NA	NA	1090	6.2	230	<2.0
	08/21/08	7.2	<2.0	239	3480	NA	NA	1330	NA	NA	NA
	04/07/09	NA	NA	NA	3390	NA	NA	NA	NA	NA	NA
MW014	08/10/09	NA	NA	NA	3360	NA	NA	NA	NA	NA	NA
	04/07/08	7	<2.0	400	4230	NA	NA	594	11.9	400	<2.0
	03/30/09	NA	NA	NA	4170	NA	NA	NA	NA	NA	NA
	08/10/09	NA	NA	NA	647	NA	NA	NA	NA	NA	NA

TABLE 4
SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	pH	Alkalinity to pH 8.3	Alkalinity to pH 4.5	Total Dissolved Solids	Total Organic Carbon	Sulfide	Sulfate	Nitrate Nitrogen	Bicarbonate Alkalinity	Carbonate Alkalinity
	Units	NA	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NMWQCC Standard											
	03/24/08	6.8	<2.0	252	5310	--	--	736	7.9	252	<2.0
MW015	08/06/08	7.1	<2.0	258	4730	--	--	874	--	--	--
	03/19/09	--	--	--	4840	--	--	--	--	--	--
	08/20/09	--	--	--	3930	--	--	--	--	--	--
MW018	03/24/08	7.3	<2.0	304	1240	--	--	315	5.3	304	<2.0
	03/19/09	--	--	--	1390	--	--	--	--	--	--
	03/26/08	7.2	<2.0	238	1820	--	--	--	--	--	--
MW020	08/06/08	7.2	<2.0	234	1940	--	--	382	16.5	238	<2.0
	03/19/09	--	--	--	2190	--	--	343	--	--	--
	04/07/08	7.1	<2.0	686	1540	--	--	268	4	686	<2.0
MW021	08/07/08	7.2	<2.0	682	1530	--	--	242	--	--	--
	03/24/09	--	--	--	1460	--	--	--	--	--	--
	08/06/09	--	--	--	1490	--	--	--	--	--	--
MW023	04/09/08	7.2	<2.0	251	3660	--	--	1400	5.3	251	<2.0
	08/21/08	7.1	<2.0	256	3920	--	--	1580	--	--	--
	03/31/09	--	--	--	3940	--	--	--	--	--	--
MW024	08/12/09	--	--	--	3890	--	--	--	--	--	--
	04/07/08	7	<2.0	307	2180	--	--	580	4.4	307	<2.0
	08/13/08	7.1	<2.0	274	1780	--	--	499	--	--	--
MW025	03/25/09	--	--	--	1800	--	--	--	--	--	--
	03/24/08	7.1	<2.0	401	1610	--	--	326	10.4	401	<2.0
	08/07/08	7.1	<2.0	371	1550	--	--	346	--	--	--
MW026	03/19/09	--	--	--	120	--	--	--	--	--	--
	08/20/09	--	--	--	1690	--	--	--	--	--	--
	03/25/08	7.2	<2.0	191	2240	--	--	661	2.1	191	<2.0
MW027	08/11/08	7.1	<2.0	188	2320	--	--	749	--	--	--
	03/11/09	--	--	--	No Access (1st Half 2009) - Due to Construction Activity						--
	08/24/09	--	--	--	2620	--	--	--	--	--	--
MW028	03/11/09	--	--	--	No Access (1st Half 2009)						--
	03/19/08	7.7	<2.0	353	1520	--	--	372	9.8	353	<2.0
	08/12/08	7.6	<2.0	365	1450	--	--	413	--	--	--
MW029	03/19/09	--	--	--	1450	--	--	--	--	--	--
	08/24/09	--	--	--	1470	--	--	--	--	--	--
	03/20/08	7.6	<2.0	170	749	--	--	165	1.8	170	<2.0
MW029	08/05/08	7.5	<2.0	187	767	--	--	165	--	--	--
	03/16/09	--	--	--	728	--	--	--	--	--	--
	08/24/09	--	--	--	706	--	--	--	--	--	--

TABLE 4
SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	Units	pH	Alkalinity to pH 8.3	Alkalinity to pH 4.5	Total Dissolved Solids	Total Organic Carbon	Sulfide	Sulfate	Nitrate Nitrogen	Bicarbonate Alkalinity	Carbonate Alkalinity
	mm WQCC Standard	mg/L	NA	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
MW030	03/25/08	7.4	NA	<2.0	165	964	—	—	137	1.4	165	<2.0
	08/05/08	7.4	NA	<2.0	170	962	—	—	363	—	—	—
	03/16/09	—	—	—	—	952	—	—	—	—	—	—
	08/20/09	—	—	—	—	986	—	—	—	—	—	—
MW031	03/20/08	7.4	NA	<2.0	301	724	—	—	115	<0.5	301	<2.0
	08/05/08	7.2	NA	<2.0	300	714	—	—	312	—	—	—
	03/24/09	—	—	—	—	703	—	—	—	—	—	—
	08/04/09	—	—	—	—	711	—	—	—	—	—	—
MW032	04/07/08	7.2	NA	<2.0	246	1180	—	—	271	3.2	246	<2.0
	08/14/08	7.4	NA	<2.0	255	1160	—	—	290	—	—	—
	03/30/09	—	—	—	—	1250	—	—	—	—	—	—
	08/06/09	—	—	—	—	1160	—	—	—	—	—	—
MW033	03/19/08	7.5	NA	<2.0	397	1950	—	—	422	<0.5	397	<2.0
	08/13/08	7.3	NA	<2.0	386	2050	—	—	464	—	—	—
	04/01/09	—	—	—	—	1940	—	—	—	—	—	—
	08/24/09	—	—	—	—	1870	—	—	—	—	—	—
MW034	04/01/08	7.2	NA	<2.0	328	1380	—	—	331	2.9	328	<2.0
	03/25/09	—	—	—	—	1360	—	—	—	—	—	—
MW035	04/02/08	7	NA	<2.0	477	766	—	—	86.6	1.4	477	<2.0
	03/24/09	—	—	—	—	1320	—	—	—	—	—	—
MW036	04/16/08	7	NA	<2.0	663	1040	—	—	<5.0	<0.5	663	<2.0
	04/07/09	—	—	—	—	1320	—	—	—	—	—	—
MW037	04/16/08	7	NA	<2.0	839	2950	—	—	92.6	<0.5	839	<2.0
	04/07/09	—	—	—	—	3840	—	—	—	—	—	—
MW038	04/16/08	7.2	NA	<2.0	465	2060	—	—	482	25.5	465	<2.0
	04/07/09	—	—	—	—	1760	—	—	—	—	—	—
MW043	03/26/08	7.5	NA	<2.0	552	1250	—	—	193	0.62	552	<2.0
	03/24/09	—	—	—	—	1410	—	—	—	—	—	—
MW044	04/09/08	7	NA	<2.0	518	1900	—	—	462	1.9	518	<2.0
	03/25/09	—	—	—	—	1700	—	—	—	—	—	—
MW045	04/02/08	7	NA	<2.0	563	1520	—	—	145	22.3	563	<2.0
	03/24/09	—	—	—	—	1220	—	—	—	—	—	—
MW046	04/17/08	7.1	NA	<2.0	645	1760	—	—	32	<0.5	645	<2.0
	04/03/08	—	—	—	—	1700	—	—	—	—	—	—
MW047	04/11/09	7.4	NA	<2.0	287	1190	—	—	318	2.8	287	<2.0
	03/11/09	—	—	—	—	—	—	—	—	—	—	—
MW058	No Access (1st Half 2009) - Due to Construction Activity											
	04/15/08	7.3	NA	<2.0	156	3660	—	—	1530	7	156	<2.0
	08/21/08	7.1	NA	<2.0	153	4490	—	—	1850	—	—	—
	04/02/09	—	—	—	—	3680	—	—	—	—	—	—

TABLE 4
SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	pH	Alkalinity to pH 8.3	Alkalinity to pH 4.5	Total Dissolved Solids	Total Organic Carbon	Sulfide	Sulfate	Nitrate Nitrogen	Bicarbonate Alkalinity	Carbonate Alkalinity
	Units	NA	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
MW059	04/03/08	7.9	<2.0	137	2040	—	—	728	4.9	137	<2.0
	08/14/08	7.2	<2.0	124	4140	—	—	1800	—	—	—
	03/31/09	—	—	—	2300	—	—	—	—	—	—
	08/12/09	—	—	—	2260	—	—	—	—	—	—
MW060	03/25/08	7.2	<2.0	143	3430	—	—	1270	<0.5	143	<2.0
	08/11/08	7.2	<2.0	129	3680	—	—	1500	—	—	—
	03/18/09	—	—	—	3420	—	—	—	—	—	—
	08/24/09	—	—	—	3450	—	—	—	—	—	—
MW061	08/07/08	7.3	<2.0	173	3140	—	—	1250	—	—	—
	04/01/09	—	—	—	2950	—	—	—	—	—	—
	03/25/08	7.2	<2.0	254	4550	—	—	337	4.4	254	<2.0
	08/11/08	7.1	<2.0	282	17800	—	—	404	—	—	—
MW068	03/18/09	—	—	—	2510	—	—	—	—	—	—
	08/24/09	—	—	—	3500	—	—	—	—	—	—
	03/11/09	—	—	—	—	No Access (1st Half 2009) - Due to Construction Activity					
	08/24/09	—	—	—	6590	—	—	—	—	—	—
MW070	03/25/08	7.4	<2.0	211	896	—	—	149	2.1	211	<2.0
	08/05/08	7.3	<2.0	216	912	—	—	354	—	—	—
	03/16/09	—	—	—	902	—	—	—	—	—	—
	08/20/09	—	—	—	827	—	—	—	—	—	—
MW088M	04/21/08	5.8	<2.0	6480	21000	—	—	127	<0.5	6480	<2.0
	04/01/09	—	—	—	17100	—	—	—	—	—	—
	04/17/08	6.6	<2.0	245	4590	—	—	1830	<0.5	245	<2.0
	03/31/09	—	—	—	5160	—	—	—	—	—	—
RW002	04/21/08	7.1	<2.0	1080	2700	—	—	469	<0.5	1080	<2.0
	04/01/09	—	—	—	2170	—	—	—	—	—	—
	04/17/08	6.9	<2.0	5610	11200	—	—	<20.0	<0.5	5610	<2.0
	03/31/09	—	—	—	6510	—	—	—	—	—	—
IW001	04/21/08	7.1	<2.0	5400	5700	—	—	<5.0	<0.5	5400	<2.0
	4/6/2009*	—	—	—	5090	—	—	—	—	—	—
DEEP ZONE WELLS											
MW002A	04/02/08	7.2	<2.0	165	2820	—	—	500	2.3	165	<2.0
	03/31/09	—	—	—	2750	—	—	—	—	—	—
	04/03/08	7.5	<2.0	175	1740	—	—	580	3.6	175	<2.0
	03/31/09	—	—	—	1700	—	—	—	—	—	—
MW007A	04/03/08	7.8	<2.0	155	2840	—	—	1120	4.5	155	<2.0
	03/11/09	—	—	—	—	No Access (1st Half 2009) - Due to Construction Activity					
	04/15/08	6.7	<2.0	2520	6460	—	—	<5.0	<0.5	2520	<2.0
	03/26/09	—	—	—	7330	—	—	—	—	—	—
MW008A	04/15/08	7.4	<2.0	216	2580	—	—	1100	7.3	216	<2.0
	03/26/09	—	—	—	2410	—	—	—	—	—	—
	04/16/08	7.2	<2.0	157	5640	—	—	2020	11	157	<2.0
	03/31/09	—	—	—	6130	—	—	—	—	—	—

TABLE 4
SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	pH	Alkalinity to pH 8.3	Alkalinity to pH 4.5	Total Dissolved Solids	Total Organic Carbon	Sulfide	Sulfate	Nitrate/Nitrogen	Bicarbonate Alkalinity	Carbonate Alkalinity
	Units	NA	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM-WGCC Standard		6.9	NA	NA	1000	NA	NA	600	10	NA	NA
MW012A	04/21/08	7.9	<2.0	272	517	--	--	33.2	<0.5	272	<2.0
	04/01/09	--	--	--	509	--	--	--	--	--	--
	04/07/08	7.5	<2.0	201	589	--	--	117	1.9	201	<2.0
MW013A	08/21/08	7.5	<2.0	200	588	--	--	128	--	--	--
	03/30/09	--	--	--	540	--	--	--	--	--	--
	08/04/09	--	--	--	540	--	--	--	--	--	--
MW014A	03/24/08	7.6	<2.0	219	523	--	--	107	2.1	219	<2.0
	03/18/09	--	--	--	30	--	--	--	--	--	--
	08/20/09	--	--	--	507	--	--	--	--	--	--
MW015A	03/24/08	7.1	<2.0	142	3620	--	--	160	2.2	142	<2.0
	08/06/08	7.3	<2.0	143	3140	--	--	131	--	--	--
	03/19/09	--	--	--	4190	--	--	--	--	--	--
MW016A	03/19/08	7.6	<2.0	171	976	--	--	214	2.2	171	<2.0
	08/07/08	7.5	<2.0	172	1030	--	--	206	--	--	--
	03/17/09	--	--	--	1080	--	--	--	--	--	--
MW018A	03/24/08	7.4	<2.0	189	1080	--	--	331	2.8	189	<2.0
	03/17/09	--	--	--	1050	--	--	--	--	--	--
MW019A	03/26/08	7.4	<2.0	202	1180	--	--	355	2.9	202	<2.0
	08/07/08	7.4	<2.0	216	1220	--	--	266	--	--	--
	03/17/09	--	--	--	1150	--	--	--	--	--	--
MW020A	03/26/08	7.4	<2.0	163	1570	--	--	429	4.2	163	<2.0
	08/06/08	7.3	<2.0	160	1950	--	--	534	--	--	--
	03/19/09	--	--	--	2600	--	--	--	--	--	--
MW021A	04/01/08	6.8	<2.0	354	11900	--	--	888	2.1	354	<2.0
	03/24/09	--	--	--	11300	--	--	--	--	--	--
	08/06/09	--	--	--	13300	--	--	--	--	--	--
MW022A	04/02/08	7.7	<2.0	176	449	--	--	66.6	2.7	176	<2.0
	08/13/08	7.6	<2.0	175	437	--	--	64.9	--	--	--
	03/18/09	--	--	--	445	--	--	--	--	--	--
MW023A	03/25/08	7.7	<2.0	211	524	--	--	112	2	211	<2.0
	08/12/08	7.7	<2.0	208	502	--	--	114	--	--	--
	03/18/09	--	--	--	520	--	--	--	--	--	--
	08/20/09	--	--	--	526	--	--	--	--	--	--
MW024A	04/07/08	7.6	<2.0	183	757	--	--	132	1.8	183	<2.0
	08/13/08	7.5	<2.0	190	1160	--	--	194	--	--	--
	03/25/09	--	--	--	1350	--	--	--	--	--	--
MW039A	08/12/09	--	--	--	452	--	--	--	--	--	--
	04/03/08	7.5	<2.0	150	1390	--	--	542	4.2	150	<2.0
	04/02/09	--	--	--	1660	--	--	--	--	--	--
MW040A	03/24/08	7.7	<2.0	202	509	--	--	102	2	202	<2.0
	08/07/08	7.7	<2.0	204	510	--	--	107	--	--	--
	03/17/09	--	--	--	506	--	--	--	--	--	--
MW041A	04/15/08	7.3	<2.0	224	1830	--	--	692	2.9	224	<2.0
	04/01/09	--	--	--	1880	--	--	--	--	--	--

TABLE 4
SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	pH	Alkalinity to pH 8.3	Alkalinity to pH 4.5	Total Dissolved Solids	Total Organic Carbon	Sulfide	Sulfate	Nitrate Nitrogen	Bicarbonate Alkalinity	Carbonate Alkalinity
	Units	NA	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM/WQCC Standard	8-9	7.2	<2.0	249	7040	—	—	897	4.3	249	<2.0
MW042A	04/02/08	7.2	<2.0	249	7200	—	—	897	4.3	249	<2.0
	03/31/09	—	—	—	7200	—	—	—	—	—	—
MW046A	04/02/08	7.1	<2.0	319	2330	—	—	823	4.9	319	<2.0
	03/31/09	—	—	—	2590	—	—	—	—	—	—
	04/01/08	7.3	<2.0	174	1640	—	—	509	3.6	174	<2.0
MW048SA	08/20/08	7.4	<2.0	176	1720	—	—	495	—	—	—
	03/26/09	—	—	—	1740	—	—	—	—	—	—
	08/12/09	—	—	—	1740	—	—	—	—	—	—
MW049SA	04/08/08	7.2	<2.0	219	4320	—	—	533	2.2	219	<2.0
	03/26/09	—	—	—	2210	—	—	—	—	—	—
MW050SA	04/01/08	7.1	<2.0	300	3810	—	—	1050	3.1	300	<2.0
	03/25/09	—	—	—	4130	—	—	—	—	—	—
MW051SA	04/09/08	7.1	<2.0	241	3710	—	—	1150	4.4	241	<2.0
	04/02/09	—	—	—	4140	—	—	—	—	—	—
MW052SA	04/08/08	7.2	<2.0	230	4110	—	—	908	3.2	230	<2.0
	03/26/09	—	—	—	4210	—	—	—	—	—	—
MW053SA	03/26/08	7.4	<2.0	277	816	—	—	85.3	2.3	277	<2.0
	03/18/09	—	—	—	938	—	—	—	—	—	—
	08/20/09	—	—	—	944	—	—	—	—	—	—
MW054SA	04/08/08	7.2	<2.0	210	6010	—	—	540	3.7	210	<2.0
	08/20/08	7.5	<2.0	204	2170	—	—	497	—	—	—
	03/26/09	—	—	—	2360	—	—	—	—	—	—
	08/10/09	—	—	—	2350	—	—	—	—	—	—
MW055SA	04/09/08	7.3	<2.0	185	1610	—	—	433	2.1	185	<2.0
	08/19/08	7.3	<2.0	186	1810	—	—	438	—	—	—
	03/26/09	—	—	—	1810	—	—	—	—	—	—
	08/12/09	—	—	—	1830	—	—	—	—	—	—
MW056SA	04/09/08	7.3	<2.0	244	3590	—	—	1090	4.3	244	<2.0
	08/19/08	7.2	<2.0	256	3880	—	—	804	—	—	—
	03/25/09	—	—	—	3930	—	—	—	—	—	—
	08/12/09	—	—	—	4020	—	—	—	—	—	—
MW057SA	03/27/08	7.2	<2.0	295	1990	—	—	520	18.9	295	<2.0
	08/05/08	7.3	<2.0	302	1720	—	—	490	—	—	—
	03/17/09	—	—	—	1620	—	—	—	—	—	—
MW062A	04/09/08	7.7	<2.0	190	487	—	—	93.4	1.7	190	<2.0
	08/18/08	7.7	<2.0	191	516	—	—	99.6	—	—	—
	04/02/09	—	—	—	495	—	—	—	—	—	—
	08/03/09	—	—	—	504	—	—	—	—	—	—
MW063A	04/09/08	7.7	<2.0	197	466	—	—	89.8	1.6	197	<2.0
	08/18/08	7.6	<2.0	197	503	—	—	94.2	—	—	—
	04/02/09	—	—	—	488	—	—	—	—	—	—
	08/04/08	—	—	—	502	—	—	—	—	—	—

TABLE 4
SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	pH	Alkalinity to pH 8.3	Alkalinity to pH 4.5	Total Dissolved Solids	Total Organic Carbon	Sulfide	Sulfate	Nitrate Nitrogen	Bicarbonate Alkalinity	Carbonate Alkalinity
	Units	NA	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
MW064SA	03/25/08	7	<2.0	340	3600	--	--	719	6.7	NA	<2.0
	08/05/08	7.1	<2.0	354	3890	--	--	846	--	--	--
	03/17/09	--	--	--	3200	--	--	--	--	--	--
	08/17/09	--	--	--	3320	--	--	--	--	--	--
MW065SA	04/08/08	7.2	<2.0	187	2530	--	--	510	2	187	<2.0
	08/19/08	7.2	<2.0	186	3190	--	--	495	--	--	--
	03/25/09	--	--	--	2810	--	--	--	--	--	--
	08/05/09	--	--	--	2920	--	--	--	--	--	--
MW066SA	08/19/08	7	<2.0	384	3000	--	--	684	--	--	--
	03/25/09	--	--	--	2980	--	--	--	--	--	--
	08/05/09	--	--	--	3060	--	--	--	--	--	--
	03/27/08	7.6	<2.0	321	1120	--	--	291	6	321	<2.0
MW067SA	08/11/08	7.3	<2.0	327	1170	--	--	284	--	--	--
	03/19/09	--	--	--	1120	--	--	--	--	--	--
	08/20/09	--	--	--	1050	--	--	--	--	--	--
MW070A	03/25/08	7.8	<2.0	218	515	--	--	122	2.1	218	<2.0
	08/05/08	7.7	<2.0	222	542	--	--	287	--	--	--
	03/16/09	--	--	--	510	--	--	--	--	--	--
	08/20/09	--	--	--	545	--	--	--	--	--	--
MW071SA	03/28/08	7.3	<2.0	217	2800	--	--	420	0.75	217	<2.0
	08/12/08	6.9	<2.0	286	2900	--	--	591	--	--	--
	03/24/09	--	--	--	2440	--	--	--	--	--	--
	08/10/09	--	--	--	2810	--	--	--	--	--	--
MW072SA	03/27/08	7.2	<2.0	282	1420	--	--	388	5	282	<2.0
	08/12/08	7.2	<2.0	313	1400	--	--	337	--	--	--
	03/17/09	--	--	--	1370	--	--	--	--	--	--
MW073SA	03/27/08	7.3	<2.0	325	1230	--	--	279	5	325	<2.0
	08/12/08	7.1	<2.0	318	1260	--	--	282	--	--	--
	03/17/09	--	--	--	1190	--	--	--	--	--	--
	03/20/08	7.2	<2.0	281	2560	--	--	823	11	281	<2.0
MW074SA	08/06/08	7.2	<2.0	282	2190	--	--	771	--	--	--
	03/16/09	--	--	--	2060	--	--	--	--	--	--
	08/24/09	--	--	--	2020	--	--	--	--	--	--
MW075SA	08/06/08	7.3	<2.0	251	2330	--	--	778	--	--	--
	03/16/09	--	--	--	2400	--	--	--	--	--	--
	08/24/09	--	--	--	2400	--	--	--	--	--	--
MW076SA	03/20/08	7.7	<2.0	266	2280	--	--	740	12.1	266	<2.0
	08/05/08	7.2	<2.0	261	2120	--	--	876	--	--	--
	03/16/09	--	--	--	2140	--	--	--	--	--	--
MW077SA	04/08/08	7.1	<2.0	253	3340	--	--	676	13.7	253	<2.0
	08/19/08	7.1	<2.0	255	5010	--	--	675	--	--	--
	03/25/09	--	--	--	3100	--	--	--	--	--	--
	08/18/09	--	--	--	2590	--	--	--	--	--	--

TABLE 4
SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	pH	Alkalinity to pH 8.3	Alkalinity to pH 4.5	Total Dissolved Solids	Total Organic Carbon	Sulfide	Sulfate	Nitrate Nitrogen	Bicarbonate Alkalinity	Carbonate Alkalinity
	Units	NA	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
WM0785A											
	03/26/08	7.3	<2.0	275	823	--	--	165	5.4	275	<2.0
	08/11/08	7.3	<2.0	274	855	--	--	158	--	--	--
	03/18/09	--	--	--	845	--	--	--	--	--	--
	08/20/09	--	--	--	790	--	--	--	--	--	--
WM0795A											
	04/02/08	7.1	<2.0	438	1420	--	--	231	<0.5	438	<2.0
	08/06/08	7	<2.0	384	1320	--	--	272	--	--	--
	03/24/09	--	--	--	1290	--	--	--	--	--	--
	08/18/09	--	--	--	1240	--	--	--	--	--	--
WM0805A											
	04/02/08	7.1	<2.0	455	1370	--	--	222	<0.5	455	<2.0
	08/06/08	7	<2.0	357	1220	--	--	322	--	--	--
	03/23/09	--	--	--	1250	--	--	--	--	--	--
	08/18/09	--	--	--	1160	--	--	--	--	--	--
WM0815A											
	04/02/08	7.3	<2.0	337	1640	--	--	342	<0.5	337	<2.0
	08/06/08	7.1	<2.0	367	1520	--	--	320	--	--	--
	03/23/09	--	--	--	1940	--	--	--	--	--	--
	08/18/09	--	--	--	1640	--	--	--	--	--	--
WM0825A											
	03/26/08	6.8	<2.0	457	3240	--	--	704	<0.5	457	<2.0
	08/06/08	6.9	<2.0	524	3210	--	--	790	--	--	--
	03/18/09	--	--	--	3480	--	--	--	--	--	--
	08/17/09	--	--	--	4070	--	--	--	--	--	--
WM0835A											
	03/26/08	6.7	<2.0	807	3520	--	--	590	<0.5	807	<2.0
	08/06/08	7	<2.0	353	3780	--	--	865	--	--	--
	03/18/09	--	--	--	4020	--	--	--	--	--	--
	08/17/09	--	--	--	4170	--	--	--	--	--	--
WM0845A											
	03/26/08	7	<2.0	258	4860	--	--	782	8.7	258	<2.0
	08/06/08	6.9	<2.0	261	5720	--	--	820	--	--	--
	03/17/09	--	--	--	5310	--	--	--	--	--	--
	08/13/09	--	--	--	4760	--	--	--	--	--	--
WM0855A											
	03/26/08	7	<2.0	342	4150	--	--	785	2.6	342	<2.0
	08/06/08	6.9	<2.0	357	4160	--	--	894	--	--	--
	03/18/09	--	--	--	3450	--	--	--	--	--	--
	08/17/09	--	--	--	4140	--	--	--	--	--	--
WM0865A											
	04/08/08	7.1	<2.0	208	2640	--	--	419	1.6	208	<2.0
	08/19/08	7.1	<2.0	224	2900	--	--	464	--	--	--
	03/25/09	--	--	--	3650	--	--	--	--	--	--
	08/10/09	--	--	--	4120	--	--	--	--	--	--
WM087A											
	04/15/08	7	<2.0	2150	4520	--	--	97	<0.5	2150	--
	03/30/09	--	--	--	4380	--	--	--	--	--	--
WM0895A											
	04/09/08	7.2	<2.0	206	3850	--	--	1460	7.6	206	<2.0
	03/26/09	--	--	--	3790	--	--	--	--	--	--
	04/14/08	7.3	<2.0	243	3100	--	--	1170	9.2	243	<2.0
WM0905A											
	03/17/09	7.1	<2.0	234	3230	--	--	--	--	--	--
	08/11/09	7.1	<2.0	231	3290	5.5	<0.16	1170	--	--	--
WM0915A											
	04/07/08	7	<2.0	236	2970	--	--	1050	4.1	236	<2.0
	03/24/09	--	--	--	3540	--	--	--	--	--	--

TABLE 4
SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	pH	Alkalinity to pH 8.3	Alkalinity to pH 4.5	Total Dissolved Solids	Total Organic Carbon	Sulfide	Sulfate	Nitrate Nitrogen	Bicarbonate Alkalinity	Carbonate Alkalinity
	Units	NA	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
NM WQCC Standard	8-9	7.2	<2.0	257	1000	NA	--	600	10	NA	NA
MW092SA	04/08/08	7.2	<2.0	257	2860	--	--	1020	5.1	257	<2.0
	03/24/09	--	--	--	3480	--	--	--	--	--	--
MW093SA	04/08/08	7.1	<2.0	273	3000	--	--	1040	5.3	273	<2.0
	03/24/09	--	--	--	3750	--	--	--	--	--	--
RW004A	04/16/08	4.9	<2.0	3110	13900	--	--	154	<2.0	3110	<2.0
	03/31/09	--	--	--	14900	--	--	--	--	--	--
IW003	04/03/08	7.1	<2.0	1870	4440	--	--	<5.0	<0.5	1870	<2.0
	3/23/2009*	--	--	--	4400	--	--	--	--	--	--
IW004	04/03/08	6.8	<2.0	713	3960	--	--	541	<0.5	713	<2.0
	03/23/09	--	--	--	4490	--	--	--	--	--	--
IW005	04/01/08	7	<2.0	2480	4890	--	--	<5.0	<0.5	2480	<2.0
	3/23/2009*	--	--	--	4790	--	--	--	--	--	--
IW006	04/01/08	6.9	<2.0	1760	3660	--	--	119	<0.5	1760	<2.0
	03/19/09	--	--	--	3400	--	--	--	--	--	--
IW007	04/01/08	5.8	<2.0	7270	26300	--	--	149	<2.0	7270	<2.0
	3/19/2009*	--	--	--	5550	--	--	--	--	--	--
IW008	04/01/08	7.1	<2.0	2130	3480	--	--	<5.0	<0.5	2130	<2.0
	3/19/2009*	--	--	--	3030	--	--	--	--	--	--
IW009	03/31/08	5.6	<2.0	5430	20000	--	--	149	<0.5	5430	<2.0
	3/19/2009*	--	--	--	--	--	--	--	--	--	--
IW010	03/31/08	7.2	<2.0	682	2860	--	--	523	<0.5	682	<2.0
	3/19/2009*	--	--	--	3290	--	--	--	--	--	--
IW011	03/31/08	7.1	<2.0	2520	5340	--	--	<5.0	<0.5	2520	<2.0
	3/18/2009*	--	--	--	4320	--	--	--	--	--	--
IW013	03/26/08	6.6	<2.0	531	2810	--	--	426	<0.5	531	<2.0
	03/18/09	--	--	--	2860	--	--	--	--	--	--
IW014	03/26/08	7.2	<2.0	3600	6360	--	--	<5.0	<0.5	3600	<2.0
	3/18/2009*	--	--	--	5750	--	--	--	--	--	--
IW015	04/03/08	7.1	<2.0	1820	4410	--	--	<5.0	<0.5	1820	<2.0
	03/23/09	--	--	--	4040	--	--	--	--	--	--
IW016	04/02/08	7	<2.0	2370	4150	--	--	<5.0	<0.5	2370	<2.0
	3/24/2009*	--	--	--	3240	--	--	--	--	--	--
IW018	04/09/08	7.1	<2.0	603	3260	--	--	537	2.5	603	<2.0
	3/24/2009*	--	--	--	3080	--	--	--	--	--	--
IW019	04/08/08	7	<2.0	340	4470	--	--	1400	6.5	340	<2.0
	03/25/09	--	--	--	4880	--	--	--	--	--	--
IW020	04/08/08	7.1	<2.0	260	4170	--	--	1460	8.2	260	<2.0
	03/25/09	--	--	--	4880	--	--	--	--	--	--
IW021	04/08/08	7.3	<2.0	285	3370	--	--	1100	5.4	285	<2.0
	03/25/09	--	--	--	3880	--	--	--	--	--	--
IW022	04/07/08	7	<2.0	235	2700	--	--	977	4.2	235	<2.0
	03/25/09	--	--	--	2750	--	--	--	--	--	--
	04/07/08	7.1	<2.0	250	2350	--	--	847	4.5	250	<2.0
	03/16/09	7	<2.0	246	2560	3.9	<0.16	--	--	--	--
IW023	08/11/09	7.1	<2.0	240	2700	4.4	<0.16	774	--	--	--

TABLE 4
SUMMARY OF 2009 GROUNDWATER PARAMETER RESULTS
NORTH EUNICE GAS PLANT
LEA COUNTY, NEW MEXICO

Location ID	Sample Date	pH	Alkalinity to pH 8.3	Alkalinity to pH 4.5	Total Dissolved Solids	Total Organic Carbon	Sulfide	Sulfate	Nitrate Nitrogen	Bicarbonate Alkalinity	Carbonate Alkalinity
NM WQCC Standard	Units	NA	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
IW024	04/15/08 03/16/09 08/11/09	7.2 7 7.2	<2.0 <2.0 <2.0	262 212 210	1000 3440 4080	-- -- 6.3	-- <0.16 <0.16	600 1370 1670	5.5 -- --	262 -- --	<2.0 -- --
IW025	04/14/08 03/16/09 08/13/09	7.2 6.6 6.6	<2.0 <2.0 <2.0	233 988 799	3220 3290 3220	-- 238 60.8	-- 49.8 254	1160 -- 866	5.3 -- --	233 -- --	<2.0 -- --
IW026	04/14/08 03/16/09 08/13/09	7.3 7.3 7.2	<2.0 <2.0 <2.0	257 234 256	1630 1790 1640	-- 2.7 --	-- <0.16 --	284 -- 390	2.6 -- --	257 -- --	<2.0 -- --
IW027	04/14/08 03/25/09	7.2 --	<2.0 --	239 --	3090 2880	-- --	-- --	1140 --	11.2 --	239 --	<2.0 --
IW028	04/15/08 04/07/09	7.3 --	<2.0 --	250 --	2870 2840	-- --	-- --	1010 --	9.2 --	250 --	<2.0 --
WATER WELLS											
GOPWW2	03/24/08 08/05/08 03/17/09	7.4 8.1 --	<2.0 <2.0 --	32.6 23.8 --	3880 2910 2260	-- -- --	-- -- --	118 13.8 --	<0.5 -- --	32.6 -- --	<2.0 -- --
LORDWW	08/18/09 03/26/08 08/13/08 03/19/09	-- 7 7.2 --	-- <2.0 <2.0 --	-- 141 29.7 --	3060 3600 3400 4270	-- -- -- Well is inaccessible	-- -- -- --	-- 1240 968 --	-- 6.6 -- --	-- 141 -- --	-- <2.0 -- --
ROLANDWW	04/08/09	--	--	--	--	--	--	--	--	--	--
WOODELLWW	04/15/08 08/21/08 03/24/09	7.4 7.1 --	<2.0 <2.0 --	193 243 --	1060 1820 1780	-- -- --	-- -- --	274 477 --	1.9 -- --	193 -- --	<2.0 -- --
EPWW1	08/24/09 04/05/09	-- --	-- --	-- --	1480 914	-- --	-- --	-- --	-- --	-- --	-- --

Notes:
Bold = Detections exceeding the New Mexico Water Quality Control Commission (NM WQCC) Human Health or Domestic Water Supply Standards (if standards are available).
 Sample Date followed by asterisk = Due to excessive foaming of the sample, normal reporting limits were not attained. Preservation requirements were not met.
 mg/L = milligrams per liter
 NA = Not Applicable
 < = less than - the number following the sign is the limit of quantitation, the smallest amount of analyte which can be reliably determined using the specific analytical test.
 -- = Not Analyzed

**APPENDIX A
CUMULATIVE GROUNDWATER FIELD PARAMETERS**



Where quality is a science.

Acct. #: _____ Sample #: _____

SCR#:

014215

[illegible]

Analysis Request / Environmental Services Chain of Custody



For Lancaster Laboratories use only

Acct. # _____

Group # _____

Sample # _____

COC # 196611

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chromia</u> Acct. #: _____ Project Name: <u>12.12.17.01/35</u> PWSID #: _____ Project Manager: <u>Chad Ouel</u> P.O. #: _____ Sampler: <u>Tina JBL</u> Quote #: _____ Name of state where samples were collected: <u>MD</u>		5 Analyses Requested Preservation Codes H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		6 Temperature of samples upon receipt (if requested)	
2 Sample Identification		3 Composite		4 Matrix	
Date Collected Time Collected		Grab		Soil Water Other	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	
3-17-09 1429		X		X	
Trip Blank		-		X	
3-17-09 0930		X		X	
3-17-09 1409		X		X	
3-17-09 1330		X		X	

Lancaster
Laboratories

Acct. # .

Group#

Sample #

COC # 196609

Please print. Instructions on reverse side correspond with circled numbers.

For Lab Use Only

FSF

SCR#:

Client: *Bob Jones* Acct #:

Acct. #:

Project Name/ #: *12501055, 201.0* PWSID #:

PWSID #:

Project Manager: *Chad* P.O.#: *020001*

P.O.#:

Sampler: سكس / 3M

Quote #:

Name of state where samples were collected: California

۱۳۳۳

Sample Identification	Date Collected	Time Collected	3	
			Grab	Composite
MWD 855A	3-18-09	0950	X	
MWD 835A	3-18-09	1027	X	
MWD 825A	3-18-09	1133	X	
T0004	3-18-09	1316	X	
T0003	3-18-09	1408	X	
T0001	3-18-09	1545	X	
T00 Blank	---	---	---	
DWD-900	3-18-09	---	X	

Turnaround Time Requested (TAT) (please circle): <u>Normal</u> Rush (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: _____ Rush results requested by (please circle): _____ Phone _____ Fax _____ Phone #: _____ Fax #: _____ E-mail address: _____		
Data Package Options (please circle if required)		SDG Complete?
Type I (validation/NJ Reg)	TX TRRP-13	Yes No
Type II (Tier II)	MA MCP CT RCP	
Type III (Reduced NJ)		
Type IV (CLP SOW)		
Type VI (Raw Data Only)		
Site-specific QC (MS/MSD/Dup)? Yes No (If yes, indicate QC sample and submit triplicate volumes.) Internal COC Required? Yes / No		

Relinquished by:	Date	Time	Received by:	Date	Time
	3-18-03	5:43			
Relinquished by:	Date	Time	Received by:	Date	Time
Relinquished by:	Date	Time	Received by:	Date	Time
Relinquished by:	Date	Time	Received by:	Date	Time
Relinquished by:	Date	Time	Received by:	Date	Time
Relinquished by:	Date	Time	Received by:	Date	Time

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766

Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

2102.03

Lancaster
Laboratories

Acct. #

Group#

Sample #

COC # 196603

Please print. Instructions on reverse side correspond with circled numbers.

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-8768
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

COC # 196605

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chesapeake</u> Acct. #: <u> </u> Project Name: <u>217701135.201.250</u> PWSID #: <u> </u> Project Manager: <u>Chad Ward</u> P.O. #: <u> </u> Sampler: <u>SM 153c</u> Quote #: <u> </u> Name of state where samples were collected: <u>VA</u>									
2									
3		4		5		6		7	
Composite Grab		Soil Water Other		Matrix Check if NPDES Applicable		Total # of Containers		Preservation Codes	
Date Collected Time Collected		Date Collected Time Collected		Date Collected Time Collected		Date Collected Time Collected		Date Collected Time Collected	
Sample Identification		Sample Identification		Sample Identification		Sample Identification		Sample Identification	
TW005 TW006 TW007 TW008 TW009 TW010 TW011 TW012 TW013 TW014 TW015 TW016 TW017 TW018 TW019 TW020 TW021 TW022 TW023 TW024 TW025 TW026 TW027 TW028 TW029 TW030 TW031 TW032 TW033 TW034 TW035 TW036 TW037 TW038 TW039 TW040 TW041 TW042 TW043 TW044 TW045 TW046 TW047 TW048 TW049 TW050 TW051 TW052 TW053 TW054 TW055 TW056 TW057 TW058 TW059 TW060 TW061 TW062 TW063 TW064 TW065 TW066 TW067 TW068 TW069 TW070 TW071 TW072 TW073 TW074 TW075 TW076 TW077 TW078 TW079 TW080 TW081 TW082 TW083 TW084 TW085 TW086 TW087 TW088 TW089 TW090 TW091 TW092 TW093 TW094 TW095 TW096 TW097 TW098 TW099 TW100 TW101 TW102 TW103 TW104 TW105 TW106 TW107 TW108 TW109 TW110 TW111 TW112 TW113 TW114 TW115 TW116 TW117 TW118 TW119 TW120 TW121 TW122 TW123 TW124 TW125 TW126 TW127 TW128 TW129 TW130 TW131 TW132 TW133 TW134 TW135 TW136 TW137 TW138 TW139 TW140 TW141 TW142 TW143 TW144 TW145 TW146 TW147 TW148 TW149 TW150 TW151 TW152 TW153 TW154 TW155 TW156 TW157 TW158 TW159 TW160 TW161 TW162 TW163 TW164 TW165 TW166 TW167 TW168 TW169 TW170 TW171 TW172 TW173 TW174 TW175 TW176 TW177 TW178 TW179 TW180 TW181 TW182 TW183 TW184 TW185 TW186 TW187 TW188 TW189 TW190 TW191 TW192 TW193 TW194 TW195 TW196 TW197 TW198 TW199 TW200 TW201 TW202 TW203 TW204 TW205 TW206 TW207 TW208 TW209 TW210 TW211 TW212 TW213 TW214 TW215 TW216 TW217 TW218 TW219 TW220 TW221 TW222 TW223 TW224 TW225 TW226 TW227 TW228 TW229 TW230 TW231 TW232 TW233 TW234 TW235 TW236 TW237 TW238 TW239 TW240 TW241 TW242 TW243 TW244 TW245 TW246 TW247 TW248 TW249 TW250 TW251 TW252 TW253 TW254 TW255 TW256 TW257 TW258 TW259 TW260 TW261 TW262 TW263 TW264 TW265 TW266 TW267 TW268 TW269 TW270 TW271 TW272 TW273 TW274 TW275 TW276 TW277 TW278 TW279 TW280 TW281 TW282 TW283 TW284 TW285 TW286 TW287 TW288 TW289 TW290 TW291 TW292 TW293 TW294 TW295 TW296 TW297 TW298 TW299 TW300 TW301 TW302 TW303 TW304 TW305 TW306 TW307 TW308 TW309 TW310 TW311 TW312 TW313 TW314 TW315 TW316 TW317 TW318 TW319 TW320 TW321 TW322 TW323 TW324 TW325 TW326 TW327 TW328 TW329 TW330 TW331 TW332 TW333 TW334 TW335 TW336 TW337 TW338 TW339 TW340 TW341 TW342 TW343 TW344 TW345 TW346 TW347 TW348 TW349 TW350 TW351 TW352 TW353 TW354 TW355 TW356 TW357 TW358 TW359 TW360 TW361 TW362 TW363 TW364 TW365 TW366 TW367 TW368 TW369 TW370 TW371 TW372 TW373 TW374 TW375 TW376 TW377 TW378 TW379 TW380 TW381 TW382 TW383 TW384 TW385 TW386 TW387 TW388 TW389 TW390 TW391 TW392 TW393 TW394 TW395 TW396 TW397 TW398 TW399 TW400 TW401 TW402 TW403 TW404 TW405 TW406 TW407 TW408 TW409 TW410 TW411 TW412 TW413 TW414 TW415 TW416 TW417 TW418 TW419 TW420 TW421 TW422 TW423 TW424 TW425 TW426 TW427 TW428 TW429 TW430 TW431 TW432 TW433 TW434 TW435 TW436 TW437 TW438 TW439 TW440 TW441 TW442 TW443 TW444 TW445 TW446 TW447 TW448 TW449 TW450 TW451 TW452 TW453 TW454 TW455 TW456 TW457 TW458 TW459 TW460 TW461 TW462 TW463 TW464 TW465 TW466 TW467 TW468 TW469 TW470 TW471 TW472 TW473 TW474 TW475 TW476 TW477 TW478 TW479 TW480 TW481 TW482 TW483 TW484 TW485 TW486 TW487 TW488 TW489 TW490 TW491 TW492 TW493 TW494 TW495 TW496 TW497 TW498 TW499 TW500 TW501 TW502 TW503 TW504 TW505 TW506 TW507 TW508 TW509 TW510 TW511 TW512 TW513 TW514 TW515 TW516 TW517 TW518 TW519 TW520 TW521 TW522 TW523 TW524 TW525 TW526 TW527 TW528 TW529 TW530 TW531 TW532 TW533 TW534 TW535 TW536 TW537 TW538 TW539 TW540 TW541 TW542 TW543 TW544 TW545 TW546 TW547 TW548 TW549 TW550 TW551 TW552 TW553 TW									

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

**Lancaster
Laboratories**

For Lancaster Laboratories use only

Acct. #

Group#

Sample #

COC # 196604

Please print. Instructions on reverse side correspond with circled numbers.

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

[illegible]



For Lancaster Laboratories use only

Acct. #

Group#

Sample #

COC # 201039

Please print. Instructions on reverse side correspond with circled numbers.

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766

Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only
 Acct. # _____ Group # _____ Sample # _____

COC # 171891

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chevron</u> Acct. #: _____ Project Name/ID: <u>W. E. F. W. 120001135, 201.250</u> PWSID #: _____ Project Manager: <u>Chris Cowell</u> P.O. #: _____ Sampler: <u>SC/DM</u> Quote #: _____ Name of state where samples were collected: <u>WA</u>		2 Sample Identification <table border="1"> <thead> <tr> <th>Sample Identification</th> <th>Date Collected</th> <th>Time Collected</th> <th>Grab</th> <th>Composite</th> </tr> </thead> <tbody> <tr> <td>MW002</td> <td>3-30-09</td> <td>1055</td> <td>X</td> <td></td> </tr> <tr> <td>MW007A</td> <td>3-30-09</td> <td>1235</td> <td>X</td> <td></td> </tr> <tr> <td>Top 3 Blank</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample Identification	Date Collected	Time Collected	Grab	Composite	MW002	3-30-09	1055	X		MW007A	3-30-09	1235	X		Top 3 Blank				
Sample Identification	Date Collected	Time Collected	Grab	Composite																			
MW002	3-30-09	1055	X																				
MW007A	3-30-09	1235	X																				
Top 3 Blank																							
3 Matrix ☐ Water ☐ NPDES Applicable ☐ Potable Check if ☐ Other		4 Total # of Containers <table border="1"> <thead> <tr> <th>Matrix</th> <th>Containers</th> </tr> </thead> <tbody> <tr> <td>Water</td> <td>7</td> </tr> <tr> <td>NPDES</td> <td>7</td> </tr> <tr> <td>Potable</td> <td>2</td> </tr> </tbody> </table>		Matrix	Containers	Water	7	NPDES	7	Potable	2												
Matrix	Containers																						
Water	7																						
NPDES	7																						
Potable	2																						
5 Analyses Requested <table border="1"> <thead> <tr> <th>Analyses Requested</th> <th>Containers</th> </tr> </thead> <tbody> <tr> <td>CL, HX, TDS</td> <td>1</td> </tr> <tr> <td>TPH, D20</td> <td>2</td> </tr> <tr> <td>TPH, 17PH, 670</td> <td>3</td> </tr> <tr> <td>TPH, 17PH, 670</td> <td>2</td> </tr> </tbody> </table>		Analyses Requested	Containers	CL, HX, TDS	1	TPH, D20	2	TPH, 17PH, 670	3	TPH, 17PH, 670	2	6 Preservation Codes H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other											
Analyses Requested	Containers																						
CL, HX, TDS	1																						
TPH, D20	2																						
TPH, 17PH, 670	3																						
TPH, 17PH, 670	2																						
7 Turnaround Time Requested (TAT) (please circle): Normal ☒ Rush ☐ Date results are needed: _____ Rush results requested by (please circle): Phone _____ Fax _____ E-mail _____ Phone #: _____ Fax #: _____ E-mail address: _____		8 Data Package Options (please circle if required) Type I (Validation/NJ Reg) TX TRRP-13 Yes No Type II (Tier II) MA MCP CT RCP Yes No Type III (Reduced NJ) Site-specific QC (MSMSD/Dup)? Yes No Type IV (CEG SOW) Internal QC Required? Yes No Type VI (Raw Data Only) Internal COC Required? Yes No																					
9 Relinquished by: <u>[Signature]</u> Date: <u>3-30-09</u> Time: <u>1635</u> Relinquished by: _____ Date: _____ Time: _____ Relinquished by: _____ Date: _____ Time: _____ Relinquished by: _____ Date: _____ Time: _____ Relinquished by: _____ Date: _____ Time: _____		Preservation Codes H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other																					
Remarks <u>* Note All Dis. Labels are field filled *</u> <u>121 245 micron filter *</u>		Temperature of samples upon receipt (if requested)																					

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only

COC # 201040

Acct. # _____ Group # _____ Sample # _____

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chen, Dan</u> Acct. #: _____ Project Name/ID: <u>21220133</u> PWSID #: _____ Project Manager: <u>Chad Uebel</u> P.O. #: _____ Sampler: <u>JM</u> Quote #: _____ Name of state where samples were collected: <u>MD</u>		2 Sample Identification <table border="1"> <thead> <tr> <th>Sample Identification</th> <th>Date Collected</th> <th>Time Collected</th> </tr> </thead> <tbody> <tr><td>MW000819</td><td>3-31-09</td><td>932</td></tr> <tr><td>MW000819</td><td>3-31-09</td><td>1148</td></tr> <tr><td>MW000819</td><td>3-31-09</td><td>1121</td></tr> <tr><td>MW000819</td><td>3-31-09</td><td>1252</td></tr> <tr><td>MW000819</td><td>3-31-09</td><td>1337</td></tr> <tr><td>MW000819</td><td>3-31-09</td><td>1446</td></tr> <tr><td>MW000819</td><td>3-31-09</td><td>1530</td></tr> <tr><td>Tri-Blenk</td><td></td><td></td></tr> <tr><td>Tri-Blenk</td><td></td><td></td></tr> <tr><td>Tri-Blenk</td><td></td><td></td></tr> </tbody> </table>		Sample Identification	Date Collected	Time Collected	MW000819	3-31-09	932	MW000819	3-31-09	1148	MW000819	3-31-09	1121	MW000819	3-31-09	1252	MW000819	3-31-09	1337	MW000819	3-31-09	1446	MW000819	3-31-09	1530	Tri-Blenk			Tri-Blenk			Tri-Blenk			3 Matrix <table border="1"> <thead> <tr> <th>Matrix</th> <th>Composite</th> <th>Grab</th> <th>Soil</th> <th>Water</th> <th>Other</th> </tr> </thead> <tbody> <tr><td></td><td>X</td><td>X</td><td></td><td>X</td><td></td></tr> <tr><td></td><td>X</td><td>X</td><td></td><td>X</td><td></td></tr> <tr><td></td><td>X</td><td>X</td><td></td><td>X</td><td></td></tr> <tr><td></td><td>X</td><td>X</td><td></td><td>X</td><td></td></tr> <tr><td></td><td>X</td><td>X</td><td></td><td>X</td><td></td></tr> <tr><td></td><td>X</td><td>X</td><td></td><td>X</td><td></td></tr> <tr><td></td><td>X</td><td>X</td><td></td><td>X</td><td></td></tr> <tr><td></td><td>X</td><td>X</td><td></td><td>X</td><td></td></tr> <tr><td></td><td>X</td><td>X</td><td></td><td>X</td><td></td></tr> <tr><td></td><td>X</td><td>X</td><td></td><td>X</td><td></td></tr> </tbody> </table>		Matrix	Composite	Grab	Soil	Water	Other		X	X		X			X	X		X			X	X		X			X	X		X			X	X		X			X	X		X			X	X		X			X	X		X			X	X		X			X	X		X		4 Total # of Containers <table border="1"> <thead> <tr> <th>Matrix</th> <th>Composite</th> <th>Grab</th> <th>Soil</th> <th>Water</th> <th>Other</th> </tr> </thead> <tbody> <tr><td></td><td>7</td><td>7</td><td></td><td>7</td><td></td></tr> <tr><td></td><td>7</td><td>7</td><td></td><td>7</td><td></td></tr> <tr><td></td><td>7</td><td>7</td><td></td><td>7</td><td></td></tr> <tr><td></td><td>7</td><td>7</td><td></td><td>7</td><td></td></tr> <tr><td></td><td>7</td><td>7</td><td></td><td>7</td><td></td></tr> <tr><td></td><td>7</td><td>7</td><td></td><td>7</td><td></td></tr> <tr><td></td><td>7</td><td>7</td><td></td><td>7</td><td></td></tr> <tr><td></td><td>7</td><td>7</td><td></td><td>7</td><td></td></tr> <tr><td></td><td>7</td><td>7</td><td></td><td>7</td><td></td></tr> <tr><td></td><td>7</td><td>7</td><td></td><td>7</td><td></td></tr> </tbody> </table>		Matrix	Composite	Grab	Soil	Water	Other		7	7		7			7	7		7			7	7		7			7	7		7			7	7		7			7	7		7			7	7		7			7	7		7			7	7		7			7	7		7		5 Analyses Requested <table border="1"> <thead> <tr> <th>Analyses Requested</th> <th>Preservation Codes</th> </tr> </thead> <tbody> <tr><td></td><td>H=HCl T=Thiosulfate N=HNO₃ B=NaOH S=H₂SO₄ O=Other</td></tr> <tr><td></td><td></td></tr> <tr><td></td><td></td></tr> <tr><td></td><td></td></tr> <tr><td></td><td></td></tr> <tr><td></td><td></td></tr> <tr><td></td><td></td></tr> <tr><td></td><td></td></tr> <tr><td></td><td></td></tr> <tr><td></td><td></td></tr> </tbody> </table>		Analyses Requested	Preservation Codes		H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other																			6 Preservation Codes H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other Remarks: <u>Relinquished by client</u> <u>field filled by BWS</u> <u>micron filter</u>		7 Turnaround Time Requested (TAT) (please circle) (Normal) Rush (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: _____ Rush results requested by (please circle): _____ Phone #: _____ Phone: _____ Fax: _____ E-mail: _____ E-mail address: _____		8 Data Package Options (please circle if required) Type I (Validation/NJ Reg) TX TRRP-13 Type II (Tier II) MA MCP CT RCP Type III (Reduced NJ) Site-specific QC (MS/MSD/Dup)? Yes No Type IV (CLP SOW) (if yes, indicate QC sample and submit signature volume) Type VI (Raw Data Only) Internal COC Required? Yes No		9 Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time Received by: _____ Date Time Received by: _____ Date Time Received by: _____ Date Time Received by: _____ Date Time Received by: _____	
Sample Identification	Date Collected	Time Collected																																																																																																																																																																																																												
MW000819	3-31-09	932																																																																																																																																																																																																												
MW000819	3-31-09	1148																																																																																																																																																																																																												
MW000819	3-31-09	1121																																																																																																																																																																																																												
MW000819	3-31-09	1252																																																																																																																																																																																																												
MW000819	3-31-09	1337																																																																																																																																																																																																												
MW000819	3-31-09	1446																																																																																																																																																																																																												
MW000819	3-31-09	1530																																																																																																																																																																																																												
Tri-Blenk																																																																																																																																																																																																														
Tri-Blenk																																																																																																																																																																																																														
Tri-Blenk																																																																																																																																																																																																														
Matrix	Composite	Grab	Soil	Water	Other																																																																																																																																																																																																									
	X	X		X																																																																																																																																																																																																										
	X	X		X																																																																																																																																																																																																										
	X	X		X																																																																																																																																																																																																										
	X	X		X																																																																																																																																																																																																										
	X	X		X																																																																																																																																																																																																										
	X	X		X																																																																																																																																																																																																										
	X	X		X																																																																																																																																																																																																										
	X	X		X																																																																																																																																																																																																										
	X	X		X																																																																																																																																																																																																										
	X	X		X																																																																																																																																																																																																										
Matrix	Composite	Grab	Soil	Water	Other																																																																																																																																																																																																									
	7	7		7																																																																																																																																																																																																										
	7	7		7																																																																																																																																																																																																										
	7	7		7																																																																																																																																																																																																										
	7	7		7																																																																																																																																																																																																										
	7	7		7																																																																																																																																																																																																										
	7	7		7																																																																																																																																																																																																										
	7	7		7																																																																																																																																																																																																										
	7	7		7																																																																																																																																																																																																										
	7	7		7																																																																																																																																																																																																										
	7	7		7																																																																																																																																																																																																										
Analyses Requested	Preservation Codes																																																																																																																																																																																																													
	H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other																																																																																																																																																																																																													

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
 Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster
Laboratories

COC # 171890

Please print. Instructions on reverse side correspond with circled numbers.

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Chevron Generic Analysis Request/Chain of Custody



For Lancaster Laboratories use only
 Acct. #: _____ Sample #: _____

012992
 SCR# 65073

Facility #: <u>Al. Fenner</u> Site Address: <u>Fenner, NM</u> Chevron PM: <u>Mark Hudson</u> Lead Consultant: <u>C. Vassell</u> Consultant/Office: <u>Stanley Moorhead</u> Consultant Prj. Mgr.: <u>D. Woodward</u> Consultant Phone #: <u>713-537-7893</u> Fax #: <u>713-583-8326</u> Sampler: <u>JSC, JM</u> Service Order #: _____ ☐ Non SAR: ☒				Analyses Requested <table border="1"> <tr> <th colspan="2">Preservation Codes</th> <th colspan="2">Matrix</th> <th colspan="2">Preservative Codes</th> </tr> <tr> <td>H</td><td>H</td> <td>Soil</td><td>Water</td> <td>H</td><td>H</td> </tr> <tr> <td>TPH G</td><td>TPH D</td> <td>Oil</td><td>NPDES</td> <td>N</td><td>N</td> </tr> <tr> <td>Oxygenates</td><td>Extended Rpt.</td> <td>Water</td><td>Potable</td> <td></td><td></td> </tr> <tr> <td>8260 full scan</td><td>Silica Gel Cleanup</td> <td>Soil</td><td></td> <td></td><td></td> </tr> <tr> <td></td><td>Lead Total</td> <td>Composite</td><td></td> <td></td><td></td> </tr> <tr> <td></td><td>TPH H</td> <td></td><td></td> <td></td><td></td> </tr> <tr> <td></td><td>VP/EPH</td> <td></td><td></td> <td></td><td></td> </tr> <tr> <td></td><td>NWTPH H ClO₂ quantification</td> <td></td><td></td> <td></td><td></td> </tr> </table>				Preservation Codes		Matrix		Preservative Codes		H	H	Soil	Water	H	H	TPH G	TPH D	Oil	NPDES	N	N	Oxygenates	Extended Rpt.	Water	Potable			8260 full scan	Silica Gel Cleanup	Soil					Lead Total	Composite					TPH H						VP/EPH						NWTPH H ClO ₂ quantification				
Preservation Codes		Matrix		Preservative Codes																																																									
H	H	Soil	Water	H	H																																																								
TPH G	TPH D	Oil	NPDES	N	N																																																								
Oxygenates	Extended Rpt.	Water	Potable																																																										
8260 full scan	Silica Gel Cleanup	Soil																																																											
	Lead Total	Composite																																																											
	TPH H																																																												
	VP/EPH																																																												
	NWTPH H ClO ₂ quantification																																																												
Sample Identification <u>I0002</u> <u>Tip Blank</u>				Time Date Collected: <u>4-6-05</u> Time Collected: <u>1520</u> Date: _____ Time: _____																																																									
Turnaround Time Requested (TAT) (please circle) STD. TAT 24 hour 72 hour 48 hour 5 day 4 day				Relinquished by: <u>[Signature]</u> Date: <u>9-26-08</u> Time: <u>0800</u> Relinquished by: <u>[Signature]</u> Date: <u>9-26-09</u> Time: <u>1704</u> Relinquished by: <u>[Signature]</u> Date: _____ Time: _____																																																									
Data Package Options (please circle if required) QC Summary Type I - Full Type VI (Raw Data) Disk / EDD WIP (RWOCB) Standard Format Disk Other: _____				Relinquished by Commercial Carrier: UPS FedEx Other: _____ Temperature Upon Receipt: _____ C°																																																									
Comments / Remarks <u>* Note: Duplicates were filed with 0.45 micron filter #</u>				Preservative Codes H = HCl T = Thiosulfate N = HNO ₃ B = NaOH S = H ₂ SO ₄ O = Other ☐ J value reporting needed ☐ Must meet lowest detection limits possible for 8260 compounds 8021 MTBE Confirmation ☐ Confirm MTBE + Naphthalene ☐ Confirm highest hit by 8260 ☐ Confirm all hits by 8260 ☐ Run ____ oxy's on highest hit ☐ Run ____ oxy's on all hits																																																									
Time Date: _____ Time: _____ Date: _____ Time: _____ Date: _____ Time: _____ Date: _____ Time: _____				Custody Seals Intact? Yes No																																																									

012994

For Lancaster Laboratories use only

Sample #:

Acct. #.:

SCR#:

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.



Where quality is a science.

For Lancaster Laboratories use only

SCR#: 009471
46694

[illegible]

GROUNDWATER FIELD LOG
EUNICE NORTH GAS PLANT
FIRST HALF 2009

ORDER	BLADDER PUMP WELL ID #	DATE	TIME	DEPTH TO WATER (ft.)	TOTAL WELL DEPTH (ft.)	PSH THICKNESS (ft.)
1	GOPWW2	3/10/2009	11:31	46.59	80.00	
2	IW001	3/10/2009	15:57	48.98	89.22	
3	IW002	3/10/2009	16:26	46.99	84.90	
4	IW003	3/10/2009	14:12	44.96	60.58	
5	IW004	3/10/2009	14:08	44.44	55.00	
6	IW005	3/10/2009	13:57	43.68	51.05	
7	IW006	3/10/2009	13:53	42.78	55.00	
8	IW007	3/10/2009	13:49	44.21	51.05	
9	IW008	3/10/2009	13:45	48.17	54.51	
10	IW009	3/10/2009	13:39	47.12	49.98	
11	IW010	3/10/2009	13:32	53.55	63.38	
12	IW011	3/10/2009	13:26	55.51	68.40	
13	IW013	3/10/2009	13:17	54.12	65.00	
14	IW014	3/10/2009	12:51	52.57	78.31	
15	IW015	3/10/2009	14:15	44.58	53.42	
16	IW016	3/10/2009	14:23	46.70	73.88	
17	IW018	3/10/2009	14:31	46.05	53.42	
18	IW019	3/10/2009	14:39	45.23	73.68	
19	IW020	3/10/2009	14:40	44.84	103.35	
20	IW021	3/10/2009	14:49	44.42	102.91	
21	IW022	3/10/2009	14:51	44.33	105.27	
22	IW023	3/10/2009	14:53	47.14	104.55	
23	IW024	3/10/2009	14:58	47.25	102.74	
24	IW025	3/10/2009	15:00	47.20	103.70	
25	IW026	3/10/2009	15:08	48.58	103.30	
26	IW027	3/11/2009	10:15	48.66	101.79	
27	IW028	3/11/2009	15:14	48.51	108.09	
28	MW001	3/11/2009	Unable to Access- Demo		68.46	
29	MW005	3/11/2009	10:39	45.49	67.75	
30	MW006	3/11/2009	10:38	45.90	68.38	
31	MW008	3/11/2009	15:36	49.24	66.77	
32	MW008A	3/11/2009	15:30	49.18	115.38	
33	MW008M	3/11/2009	15:41	49.44	86.30	
34	MW009	3/11/2009	15:16	47.91	69.00	
35	MW009A	3/11/2009	15:18	47.73	102.85	
36	MW011	3/11/2009	15:51	50.53	67.95	
37	MW011A	3/11/2009	15:53	50.94	117.43	
38	MW011M	3/11/2009	15:50	50.21	91.92	
39	MW012	3/11/2009	16:16	48.26	66.39	
40	MW012A	3/11/2009	16:18	48.65	115.48	
41	MW012M	3/11/2009	16:12	48.90	91.51	

ORDER	BLADDER PUMP WELL ID #	DATE	TIME	DEPTH TO WATER (ft.)	TOTAL WELL DEPTH (ft.)	PSH THICKNESS (ft.)
42	MW027	3/11/2009	No Access-Property Owner Issu		71.42	
43	MW036	3/11/2009	10:27	46.18	61.83	
44	MW037	3/11/2009	10:34	45.74	61.55	
45	MW038	3/11/2009	10:28	45.73	61.70	
46	MW044	3/11/2009	14:32	41.89	62.71	
47	MW046	3/11/2009	10:22	47.33	66.73	
48	MW064SA	3/11/2009	11:11	51.16	80.64	
49	MW079SA	3/11/2009	14:20	46.03	72.76	
50	MW080SA	3/11/2009	14:18	45.70	74.91	
51	MW081SA	3/11/2009	14:22	46.14	75.95	
52	MW082SA	3/11/2009	12:49	52.09	80.34	
53	MW083SA	3/11/2009	12:48	52.00	81.20	
54	MW084SA	3/11/2009	11:37	51.50	81.25	
55	MW085SA	3/11/2009	12:46	51.90	81.55	
56	MW087A	3/11/2009	15:37	49.84	113.18	
57	MW088M	3/11/2009	15:22	49.30	92.93	
58	MW089SA	3/11/2009	15:19	48.30	101.32	
59	MW090SA	3/11/2009	15:10	48.79	103.15	
60	MW091SA	3/11/2009	14:46	43.84	102.41	
61	MW092SA	3/11/2009	14:44	43.89	102.25	
62	MW093SA	3/11/2009	14:41	44.12	103.10	
63	RW002	3/11/2009	15:56	50.70	71.78	
64	RW003	3/11/2009	16:20	48.58	66.88	
65	RW004A	3/11/2009	15:43	47.49	115.51	

Historically Dry Wells

1	IW012	3/11/2009	13:22	54.26	59.00	
---	-------	-----------	-------	-------	-------	--

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-16-09 WELL NO. IW/023

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 59 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED* Serial No.: 076100 QD01417

Spec. Conductivity: Standard: 1413 Reading: 1413 ; pH Standard: 7 Reading 7.00 ; Standard 4 Reading: 4.00

Standard 10 Reading: 10.00 ; ORP: Standard: 240 Reading: 240 ; DO: T°C: 12.11 mmHg: 9.76 DO Conc.: NA

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 47.14 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 104.55 FT.

D. Height of Water Column in casing (h = TD - SWL): 57.41 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1010

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1014</u>	<u>6.52</u>	<u>128</u>	<u>6.47</u>	<u>16.05</u>	<u>3.60</u>	<u>N/R</u>
<u>1019</u>	<u>4.95</u>	<u>112</u>	<u>6.83</u>	<u>17.50</u>	<u>3.60</u>	<u>47.21</u>
<u>1024</u>	<u>4.75</u>	<u>110</u>	<u>6.85</u>	<u>17.75</u>	<u>3.60</u>	<u>47.19</u>
<u>1029</u>	<u>4.75</u>	<u>108</u>	<u>6.86</u>	<u>17.86</u>	<u>3.61</u>	<u>47.19</u>
<u>1034</u>	<u>4.71</u>	<u>106</u>	<u>6.87</u>	<u>17.89</u>	<u>3.61</u>	<u>NR</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTX TPH</u>	<u>1034</u>		
<u>Diss Metals</u>	<u>1034</u>		
<u>Chlorides, TDS</u>	<u>1034</u>		

COMMENTS: Purged 3/4 oz a gallon of water by hand / No odor / Clear
* multi meter was calibrated 3/11/09

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 57.41 x 0.80 = -- (Total Depth of Well) 58.62

Signature: [Signature]
 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/16/09 WELL NO. IW024

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 63 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.25 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 108.74 FT.
- D. Height of Water Column in casing (h = TD - SWL): 55.49 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 10:28 AM 1128

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1030</u>	<u>4.45</u>	<u>52</u>	<u>7.24</u>	<u>23.43</u>	<u>3.33</u>	<u>47.32</u>
<u>1137</u>	<u>2.18</u>	<u>52</u>	<u>7.16</u>	<u>22.06</u>	<u>5.25</u>	<u>47.32</u>
<u>1142</u>	<u>1.97</u>	<u>52</u>	<u>7.15</u>	<u>22.33</u>	<u>5.30</u>	<u>47.33</u>
<u>1147</u>	<u>1.89</u>	<u>53</u>	<u>7.15</u>	<u>23.50</u>	<u>5.34</u>	<u>47.31</u>
<u>1152</u>	<u>1.82</u>	<u>55</u>	<u>7.15</u>	<u>23.44</u>	<u>5.34</u>	<u>47.32</u>
<u>1157</u>	<u>1.65</u>	<u>57</u>	<u>7.16</u>	<u>24.43</u>	<u>5.34</u>	<u>47.31</u>
<u>1202</u>	<u>1.75</u>	<u>55</u>	<u>7.18</u>	<u>24.33</u>	<u>5.35</u>	<u>47.31</u>
<u>1207</u>	<u>1.79</u>	<u>58</u>	<u>7.19</u>	<u>24.69</u>	<u>5.34</u>	<u>47.30</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>TOC</u>			
<u>Sample 1</u>	<u>1207</u>		
<u>377X/TPH BRO</u>			
<u>TPH DRO</u>			
<u>Dist. Res. 1</u>			
<u>Dist. Res. 2</u>			

COMMENTS:

1st Green / 120 2nd / Clear 2/28/09

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft.
- 8-inch hole.....2.60 gal/in ft.
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 55.49 x 0.80 = -- (Total Depth of Well) 58.34

Signature: JM

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/16/09 WELL NO. IW025

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 67 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.20 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 103.70 FT.
- D. Height of Water Column in casing (h = TD - SWL): 56.50 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1327

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1322</u>	<u>3.61</u>	<u>-264</u>	<u>6.96</u>	<u>25.98</u>	<u>3.32</u>	<u>* See Comments</u>
<u>1337</u>	<u>1.02</u>	<u>-330</u>	<u>6.88</u>	<u>22.93</u>	<u>4.28</u>	
<u>1342</u>	<u>0.79</u>	<u>-338</u>	<u>6.91</u>	<u>23.00</u>	<u>4.27</u>	
<u>1347</u>	<u>0.59</u>	<u>-348</u>	<u>6.92</u>	<u>22.44</u>	<u>4.27</u>	
<u>1352</u>	<u>0.60</u>	<u>-343</u>	<u>6.93</u>	<u>22.68</u>	<u>4.27</u>	
<u>1357</u>	<u>0.57</u>	<u>-356</u>	<u>6.93</u>	<u>22.61</u>	<u>4.27</u>	

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>TOC</u>	<u>1357</u>		
<u>Sulfide</u>	<u>1357</u>		
<u>STEX</u>	<u>1357</u>		
<u>TPH</u>	<u>1357</u>		
<u>TPHD</u>			
<u>Disinfectant</u>			
<u>1,1,1-Trichloroethane</u>			

COMMENTS:

* Unable to collect SWL do to white milky Paste < 1/2 sec

White / Very Strong Odor / Milky

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 56.50 x 0.80 = -- (Total Depth of Well) 58.50

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/16/09 WELL NO. IW026

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 70 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: _____
- B. Thickness of Free Product, if present: _____ Inches
- C. Total Depth of well (TD) from top of casing/piezometer: _____
- D. Height of Water Column in casing (h = TD - SWL): _____

Well Collected
New TD

48.58
DM ~~47.88~~ FT.
49.90 103.30 FT.
1.32 DM 54.72 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1432

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1434	6.66	-121	7.41	21.68	2.82	48.68
1439	5.36	-63	7.40	21.17	2.83	48.65
1444	5.26	-43	7.41	21.11	2.81	48.64
1449	5.24	-33	7.42	21.04	2.78	48.67
1454	5.26	-23	7.42	21.03	2.76	48.66

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
TOC Salt/D BTEX OPHCE 1,1,1-TC, TDS Diss Metals	1454		

COMMENTS:

No Color / Salty / No odor 2/23/09

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft.
- 8-inch hole.....2.60 gal/in ft.
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 54.72 x 0.80 = -- (Total Depth of Well) 59.52

4m
1.32 Signature: JM 48.84

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/17/09 WELL NO. MW09054

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513

Spec. Conductivity: Standard: 1413 Reading: 1410 :pH Standard: 7 Reading: 7.01 :Standard 4 Reading: 4.00

Standard 10 Reading: 10.00 : ORP: Standard: 240 Reading: 246.3 : DO: T°C: 13.49 mmHg: 9.46 DO Conc.: 9.0

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.79 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 103.15 FT.
- D. Height of Water Column in casing (h = TD - SWL): 54.36 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 0904

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>905</u>	<u>7.09</u>	<u>247.0</u>	<u>6.61</u>	<u>18.25</u>	<u>3.457</u>	<u>48.88</u>
<u>910</u>	<u>4.77</u>	<u>216.3</u>	<u>6.90</u>	<u>19.02</u>	<u>4.366</u>	<u>48.87</u>
<u>915</u>	<u>4.27</u>	<u>208.4</u>	<u>6.94</u>	<u>19.09</u>	<u>4.467</u>	<u>48.87</u>
<u>920</u>	<u>4.19</u>	<u>202.7</u>	<u>6.97</u>	<u>19.25</u>	<u>4.486</u>	<u>48.86</u>
<u>925</u>	<u>4.14</u>	<u>199.3</u>	<u>6.97</u>	<u>19.40</u>	<u>4.488</u>	<u>48.84</u>
<u>930</u>	<u>4.05</u>	<u>197.0</u>	<u>6.95</u>	<u>19.53</u>	<u>4.495</u>	<u>48.86</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>70C Solids</u> <u>BOTEX</u> <u>10HQED</u> <u>21. Next 0.100s.</u> <u>Dissolved</u> <u>Full Solids</u>	<u>930</u>		

COMMENTS:

Lgt Green / No odor / Clear 2 1/2 gal

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 54.36 x 0.80 = 43.49 (Total Depth of Well) 59.66

Signature: JM

Stantec **GROUNDWATER SAMPLING FIELD DATA SHEET**

PROJECT NO.: 212201135 DATE: 3-17-09 WELL NO. 60P002

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 63 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.59 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 90.00 FT.
- D. Height of Water Column in casing (h = TD - SWL): 33.41 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____OBSERVATIONS: Purging Start Time: 1023

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1025	11.48	120.2	7.61	19.08	4.691	46.53
1030	1.65	24.0	7.69	18.89	4.657	46.62
1035	1.44	-5.5	7.67	N/R DM	4.666	46.66
1040	1.39	-93.7	7.62	18.29	4.651	46.71
1045	1.32	-36.9	7.62	18.20	4.654	46.75
1050	1.26	-58.0	7.65	18.26	4.651	46.79
1055	1.22	-72.6	7.65	18.31	4.650	46.83
1100	1.16	-89.3	7.69	18.49	4.645	46.86
1105	1.12	-98.4	7.70	18.60	4.650	46.87
1110	1.11	-113.4	7.70	18.74	4.650	46.87

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
DPX / 17PH 600	1402		
DPX 000			
Ch. Hx C. 5DS			

COMMENTS:

Strong Odor / Yellow Color / Silty > 1.0 gal

Using Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:Collect sample when Depth to Water measures **Less than or equal to:**Original Water Column: 33.41 x 0.80 = 26.73 (Total Depth of Well) 53.27Signature: JL

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/17/09 WELL NO. G0PWW2

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear/Caln

EQUIPMENT CALIBRATION: (YSI) QED Serial No.: _____

Spec. Conductivity: Standard: Reading: ; pH Standard: 7 Reading ; Standard 4 Reading:

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec.Cond: ;pH 7: ;pH 4: ;pH: 10 ;ORP:

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 46.59 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 20.00 FT.

D. Height of Water Column in casing ($h = TD - SWL$): 33.41 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: _____ **Purging Start Time:** _____

Time	DO ($\pm 10\%$)	ORP ($\pm 10\text{mV}$)	pH (± 0.1)	Temp ($\pm 3\%$)	Conduct ($\pm 3\%$)	SWL
1115	LOR	-125	7.71	12.83	4652	46.87
1120	1.07	-131.3	7.74	18.94	4656	47.00
1125	1.31*	-149.9	7.78	19.17	4651	47.04
1130	1.13	-161.1	7.79	19.23	4655	47.07
1135	* 1.06	-163.9	7.78	19.44	4652	47.10
1140						

well purged

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH C20	407		
TPH D20	S		
Chloro C. FDS			

COMMENTS:

* YSF meter turned OFF / well started pumping off at 1135 $\pm 0.09^{\circ}$

Using Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: $33.41 \times 0.80 = \text{-- (Total Depth of Well) } 53.27$

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

MW0845A

PROJECT NO.: 212201135 DATE: 3/17/09 WELL NO. ~~212201135~~

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 66 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 57.50 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 81.25 FT.
- D. Height of Water Column in casing (h = TD - SWL): 29.75 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1252

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1255	1524	54	6.97	19.41	6.977	57.50
1300	3.94	51.09	6.71	19.85	9.127	57.49
1305	3.14	45.10	6.74	19.91	9.384	57.49
1310	2.61	43.8	6.75	19.97	9.412	57.47
1315	2.27	43.5	6.75	20.11	9.417	57.46
1320	2.10	43.5	6.76	20.09	9.407	57.47
1325	1.96	44.0	6.78	20.07	9.387	57.47
1330	1.94	44.3	6.79	20.17	9.330	57.49

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>RTK / TPH 620</u>	<u>1330</u>	_____	_____
<u>TPH 220</u>	<u>1330</u>	_____	_____
<u>Ch. H.C. / TDS</u>	<u>1330</u>	_____	_____

COMMENTS:

No Color / No Odor / Clear 7/23/09

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft.
- 8-inch hole.....2.60 gal/in ft.
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 29.75 x 0.80 = -- (Total Depth of Well) 57.45

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-27-09 WELL NO. MW0655A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.16 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 80.64 FT.
- D. Height of Water Column in casing (h = TD - SWL): 29.48 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1347

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1349</u>	<u>7.80</u>	<u>72.0</u>	<u>6.79</u>	<u>20.12</u>	<u>5.212</u>	<u>51.12</u>
<u>1354</u>	<u>3.52</u>	<u>76.3</u>	<u>6.82</u>	<u>20.38</u>	<u>5.941</u>	<u>51.12</u>
<u>1359</u>	<u>2.20</u>	<u>75.9</u>	<u>6.82</u>	<u>20.33</u>	<u>5.991</u>	<u>51.12</u>
<u>1404</u>	<u>1.60</u>	<u>74.8</u>	<u>6.83</u>	<u>20.26</u>	<u>6.033</u>	<u>51.03</u>
<u>1409</u>	<u>1.47</u>	<u>73.3</u>	<u>6.88</u>	<u>20.31</u>	<u>5.906</u>	<u>51.12</u>
<u>1414</u>	<u>1.54</u>	<u>72.5</u>	<u>6.89</u>	<u>20.38</u>	<u>5.705</u>	<u>51.10</u>
<u>1419</u>	<u>1.64</u>	<u>71.8</u>	<u>6.91</u>	<u>20.40</u>	<u>5.562</u>	<u>51.10</u>
<u>1424</u>	<u>1.71</u>	<u>71.6</u>	<u>6.92</u>	<u>20.49</u>	<u>5.465</u>	<u>51.10</u>
<u>1429</u>	<u>1.88</u>	<u>71.4</u>	<u>6.93</u>	<u>20.51</u>	<u>5.395</u>	<u>51.10</u>
<u>1434</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH GRO</u>	<u>1429</u>		
<u>DPH DRO</u>			
<u>CI Hex G. TDS</u>			

COMMENTS: No Color / No Odor / Clear 7/2 gals

- Using Capacities:
- 2-inch hole.....0.16 gal/in ft.
 - 4-inch hole.....0.65 gal/in ft.
 - 6.5-inch hole.....1.70 gal/in ft.
 - 8-inch hole.....2.60 gal/in ft.
 - 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 29.48 x 0.80 = -- (Total Depth of Well) 57.05

Signature: [Signature] 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-18-09 WELL NO. MW0855A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 41 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear Calm

EQUIPMENT CALIBRATION:

YSI

QED

Serial No.: 3500

Spec. Conductivity: Standard: 1413 Reading: 1414 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 9.00

Standard 10 Reading: 999 ORP: Standard: 240 Reading: 240.1 DO: T°C: 15.47 mmHg: 9.06 DO Conc.: 90.6

End-of-Day Recheck: Spec. Cond.: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 51.90 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 81.55 FT.

D. Height of Water Column in casing (h = TD - SWL): 29.65 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 0900

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
900	7.30	-19.9	6.68	16.78	5375	51.90
905	2.23	-135.2	6.75	16.82	-134.7 *	51.87
910	1.32	-134.2	6.75	16.83	-134.9	51.87
915	1.19	-172.2	6.80	16.97 6.502	174.9 *	51.85
920	1.14	-248.0	6.87	17.25	6.393	51.85
925	1.00	-272.6	6.93	17.34	6.822	51.86
930	0.86	-295.0	6.94	17.44	6.063	51.87
935	0.79	-319.3	6.96	17.50	5.900	51.87
940	0.74	-327.1	6.96	17.55	5.762	51.87
945	0.71	-332.3	6.97	17.61	5.693	51.88

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH GRO	950		
TPH GRO			
Chloro C ₆ TDS			

COMMENTS:

light gray color / very strong odor / not silty 7/8 full
 Record ORP on Conductivity was not recorded for 3 readings


Using Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 29.65 x 0.80 = -- (Total Depth of Well) 57.83

Signature: 

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. MW085-5A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 41 °F

FIELD PERSONNEL: JL/JM WEATHER: Calm Clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; **pH** Standard: 7 Reading _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec.Cond: :pH 7: :pH 4: :pH: 10 :ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 51.90 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 21.55 FT.

D. Height of Water Column in casing ($h = TD - SWL$): 29.65 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: _____[illegible]

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>DTEX / TP4 B20</u>	<u>950</u>		
<u>TP4 D20</u>	<u>950</u>		
<u>Ch. Flex C., TDS</u>	<u>950</u>		

COMMENTS:

Using Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: $29.65 \times 0.80 = \text{-- (Total Depth of Well) } 57.83$

Signature: _____

8/2008

* DUP/200

Stantec **GROUNDWATER SAMPLING FIELD DATA SHEET**

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. MWO 835A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 41 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100503

Spec. Conductivity: Standard: 1413 Reading: 1414 ; pH Standard: 7 Reading 7.00 ; Standard 4 Reading: 4.00

Standard 10 Reading: 9.99 ; ORP: Standard: 240 Reading: 240.1 ; DO: T°C: 15.47 mmHg: 9.06 DO Conc.: 90.6

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 52.00 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 81.20 FT.

D. Height of Water Column in casing (h = TD - SWL): 29.20 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1005

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1007</u>	<u>7.50</u>	<u>-155.4</u>	<u>6.60</u>	<u>18.24</u>	<u>5803</u>	<u>52.05</u>
<u>1012</u>	<u>1.70</u>	<u>-142.1</u>	<u>6.53</u>	<u>18.30</u>	<u>6278</u>	<u>52.03</u>
<u>1017</u>	<u>1.11</u>	<u>-137.2</u>	<u>6.52</u>	<u>18.85</u>	<u>6379</u>	<u>51.99</u>
<u>1022</u>	<u>1.01</u>	<u>-132.8</u>	<u>6.52</u>	<u>18.65</u>	<u>6441</u>	<u>52.02</u>
<u>1027</u>	<u>0.91</u>	<u>-126.9</u>	<u>6.48</u>	<u>18.82</u>	<u>6467</u>	<u>52.00</u>
<u>1032</u>						
<u>1037</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH Q20</u>	<u>1027</u>		
<u>TPH Q20</u>			
<u>Ch. Hex Co., TDS</u>			

COMMENTS: DUP - 200 Lgt Brown Color / Very Strong Odor / Clear < 1/2 gal

Using Capacities:
2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 29.20 x 0.80 = -- (Total Depth of Well) 57.84

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. MWA 82SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 41 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 52.09 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 80.34 FT.

D. Height of Water Column in casing (h = TD - SWL): 28.25 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1101

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1103</u>	<u>4.71</u>	<u>-19.7</u>	<u>6.61</u>	<u>19.53</u>	<u>5.305</u>	<u>52.10</u>
<u>1108</u>	<u>2.19</u>	<u>-32.8</u>	<u>6.56</u>	<u>20.43</u>	<u>5.499</u>	<u>52.11</u>
<u>1113</u>	<u>1.46</u>	<u>-41.2</u>	<u>6.53</u>	<u>21.20</u>	<u>5.681</u>	<u>52.10</u>
<u>1118</u>	<u>1.24</u>	<u>-47.4</u>	<u>6.53</u>	<u>21.93</u>	<u>5.761</u>	<u>52.11</u>
<u>1123</u>	<u>1.08</u>	<u>-54.0</u>	<u>6.50</u>	<u>22.85</u>	<u>5.787</u>	<u>52.10</u>
<u>1128</u>	<u>0.99</u>	<u>-56.1</u>	<u>6.51</u>	<u>22.71</u>	<u>5.806</u>	<u>52.06</u>
<u>1133</u>	<u>0.94</u>	<u>-55.8</u>	<u>6.52</u>	<u>22.70</u>	<u>5.814</u>	<u>52.05</u>
<u>1138</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH GRO</u>	<u>1133</u>		
<u>TPH DRO</u>			
<u>Ch. Hg. Cr. TDS</u>			

COMMENTS: Lgt Brown Color / Very Strong Odor / Clear 4/28/09

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 28.25 x 0.80 = 22.60 (Total Depth of Well) 57.74

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-18-09 WELL NO. 20014

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 78 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear/Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 52.57 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 79.31 FT.
- D. Height of Water Column in casing (h = TD - SWL): 25.74 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1237

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1241	4.64	-52.7	6.91	20.57	8.511	52.54
1246	1.40	-84.3	6.94	20.48	8.503	52.79
1251	0.96	-103.5	6.94	20.28	8.511	52.91
1256	0.81	-135.3	6.98	20.30	8.509	53.06
1301	0.73	-142.8	6.95	20.29	8.506	53.18
1306	0.69	-119.4	6.96	20.47	8.493	53.33
1311	0.67	-115.2	6.95	20.24	8.533	53.50
1316	0.64	-105.2	6.96	20.36	8.518	53.67

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH 620	1316		
TPH DRO			
Ch. Hex. Co. PPS			

COMMENTS:

Dark Brown Color / Very Strong Odor / Cloudy 2/28-01

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 25.74 x 0.80 = -(Total Depth of Well) 52.71

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-18-09 WELL NO. I2013

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 77 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 52.12 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 65.00 FT.
- D. Height of Water Column in casing (h = TD - SWL): 12.88 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1341

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1343</u>	<u>6.00</u>	<u>-51.0</u>	<u>6.52</u>	<u>20.58</u>	<u>4935</u>	<u>54.18</u>
<u>1348</u>	<u>6.39</u>	<u>-79.4</u>	<u>6.35</u>	<u>20.97</u>	<u>4867</u>	<u>54.21</u>
<u>1353</u>	<u>1.02</u>	<u>-93.5</u>	<u>6.38</u>	<u>21.06</u>	<u>4856</u>	<u>54.22</u>
<u>1358</u>	<u>0.89</u>	<u>-104.9</u>	<u>6.38</u>	<u>21.03</u>	<u>4855</u>	<u>54.22</u>
<u>1403</u>	<u>0.80</u>	<u>-112.4</u>	<u>6.37</u>	<u>21.02</u>	<u>4851</u>	<u>54.24</u>
<u>1408</u>	<u>0.73</u>	<u>-117.8</u>	<u>6.37</u>	<u>20.98</u>	<u>4844</u>	<u>54.23</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH B20</u>	<u>1408</u>		
<u>TPH B20</u>	<u>S</u>		
<u>CL HexC, TDS</u>			

COMMENTS: light yellow color / strong odor - clear < 1/2 gal

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures **Less than or equal to:**

Original Water Column: 12.88 x 0.80 = -- (Total Depth of Well) 54.69

Signature: [Signature]

8/2008

Stantec **GROUNDWATER SAMPLING FIELD DATA SHEET**

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. IW011

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 78 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 55.51 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 68.40 FT.

D. Height of Water Column in casing (h = TD - SWL): 12.89 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 14:48

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1450	7.50	24.2	6.81	24.49	5.927	55.40
1455	1.25	-44.8	6.82	22.67	6.033	55.60
1500	0.88	-63.2	6.74	22.67	6.004	55.66
* 1505	0.73	-79.7	6.79	23.03	5.989	55.66
1510	0.94	-64.9	6.81	23.02	5.996	55.69
1515	1.40	-25.1	6.82	22.79	5.987	55.78
1520	1.48	-10.4	6.82	22.13	5.992	55.86
1525	0.91	-20.4	6.80	21.27	6.002	55.95
1530	0.58	-69.1	6.81	21.25	5.985	56.01
1535	0.56	-85.5	6.82	21.28	5.985	56.08

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTDX / TPH Q20	DM 1545		
TPH Q20			
Ch. Hec C, TDS			

COMMENTS:

Dark Brown color / very strong odor / cloudy 7 1/2 gal.
 @ 1505 Air in the fluid lines, possibly silencing the DO readings

Using Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 12.89 x 0.80 = -- (Total Depth of Well) 58.08

Signature: _____

Pg 2 of 2

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. IW011FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 78 °FFIELD PERSONNEL: JL/JM WEATHER: Clear calmEQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 55.51 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 68.40 FT.
- D. Height of Water Column in casing (h = TD - SWL): 12.89 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____**OBSERVATIONS:**Purging Start Time: 14.48

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1540</u>	<u>0.54</u>	<u>-82.5</u>	<u>6.82</u>	<u>21.92</u>	<u>5974</u>	<u>56.00</u>
<u>1545</u>	<u>0.53</u>	<u>-69.7</u>	<u>6.82</u>	<u>22.48</u>	<u>5969</u>	<u>56.00</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	<u>7M</u>		
	<u>1540</u>		
	<u>1545</u>		
	<u>5</u>		

COMMENTS:**Casing Capacities:**

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:Collect sample when Depth to Water measures Less than or equal to:Original Water Column: 12.89 x 0.80 = -- (Total Depth of Well) 58.08

Signature: _____

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-19-09 WELL NO. 12010

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 47 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513

Spec. Conductivity: Standard: 1413 Reading: 1413 :pH Standard: 7 Reading 7.01 :Standard 4 Reading: 4.00

Standard 10 Reading: 9.99 : ORP: Standard: 240 Reading: 240.0: DO: T°C: 16.98 mmHg: 8.91 DO Conc.: 90.7

End-of-Day Recheck: Spec. Cond: :pH 7: :pH 4: :pH 10 :ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 53.55 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 63.38 FT.
 D. Height of Water Column in casing (h = TD - SWL): 9.83 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 906

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>908</u>	<u>8.38</u>	<u>87.1</u>	<u>6.12</u>	<u>17.37</u>	<u>41802</u>	<u>53.56</u>
<u>913</u>	<u>2.93</u>	<u>10.6</u>	<u>6.35</u>	<u>17.87</u>	<u>41939</u>	<u>53.73</u>
<u>918</u>	<u>1.45</u>	<u>-12.8</u>	<u>6.43</u>	<u>17.93</u>	<u>41943</u>	<u>53.84</u>
<u>923</u>	<u>1.23</u>	<u>-23.3</u>	<u>6.40</u>	<u>18.15</u>	<u>41950</u>	<u>53.91</u>
<u>928</u>	<u>1.05</u>	<u>-31.3</u>	<u>6.40</u>	<u>18.40</u>	<u>41954</u>	<u>53.97</u>
<u>933</u>	<u>0.95</u>	<u>-36.3</u>	<u>6.39</u>	<u>18.56</u>	<u>41957</u>	<u>54.05</u>
<u>938</u>	<u>0.88</u>	<u>-37.7</u>	<u>6.41</u>	<u>18.70</u>	<u>41961</u>	<u>54.15</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH 670</u>	<u>938</u>		
<u>TPH 720</u>	<u> </u>		
<u>CL Hex C TDS</u>	<u> </u>		

COMMENTS: Slight Brown Color / Strong odor / clear < 1/2 sec.

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 9.83 x 0.80 = -- (Total Depth of Well) 55.51

Signature: JM

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 8/19/09 WELL NO. IW^{JS}009

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 47 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.12 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 49.98 FT.
- D. Height of Water Column in casing (h = TD - SWL): 2.86 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 9:58

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1000	4.25	30.6	5.61	17.79	9849	47.06
1005	1.65	17.0	5.59	18.12	9908	47.19
1010	1.01	4.6	5.59	18.53	9941	47.38
1015	0.85	-2.6	5.58	18.69	9964	47.43
1020	0.81	-5.6	5.59	18.70	9960	47.49
1025	0.75	-8.0	5.60	18.63	9972	47.56

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX</u>	<u>1025</u>		
<u>Diss. Metals</u>	<u>5</u>		

COMMENTS:

Very dark brown / strong odor / cloudy
 * Note well purged off before BTEX & Diss. Metals collected
 Flushed H₂O₂ by well meter
 (unable to filter w/ filter)
 < 1/2 inch
 Note filter in lab of

Using Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 2.86 x 0.80 = -- (Total Depth of Well) 47.69

Signature: JM

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. IW008

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 50 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 48.17 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 54.57 FT.

D. Height of Water Column in casing (h = TD - SWL): 6.34 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1052

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1055</u>	<u>6.29</u>	<u>-52.8</u>	<u>6.82</u>	<u>18.78</u>	<u>4.322</u>	<u>48.38</u>
<u>1100</u>	<u>1.28</u>	<u>-98.5</u>	<u>6.85</u>	<u>19.30</u>	<u>4.159</u>	<u>48.59</u>
<u>1105</u>	<u>0.94</u>	<u>-94.5</u>	<u>6.86</u>	<u>19.07</u>	<u>4.147</u>	<u>48.70</u>
<u>1110</u>	<u>0.80</u>	<u>-89.1</u>	<u>6.84</u>	<u>19.14</u>	<u>4.137</u>	<u>48.84</u>
<u>1115</u>	<u>0.74</u>	<u>-85.9</u>	<u>6.86</u>	<u>19.23</u>	<u>4.134</u>	<u>48.93</u>
<u>1120</u>	<u>0.69</u>	<u>-91.8</u>	<u>6.86</u>	<u>19.29</u>	<u>4.131</u>	<u>49.13</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TOH GRO</u>	<u>1120</u>		
<u>TDH DRO</u>	<u>S</u>		
<u>Chloride / TDS</u>			
<u>Chloride / TDS</u>			

COMMENTS: Dark Color / Strong Odor / Cloudy < 1/2 gal

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 6.34 x 0.80 = -- (Total Depth of Well) 49.43

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. IW007
 FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F
 FIELD PERSONNEL: JL/JM WEATHER: Clear / Windy
EQUIPMENT CALIBRATION: YSI QED Serial No.: _____
 Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____
 Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____
 End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 44.21 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 51.05 FT.
 D. Height of Water Column in casing (h = TD - SWL): 6.84 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1318

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1320</u>	<u>7.24</u>	<u>0.8</u>	<u>6.82</u>	<u>19.74</u>	<u>19.75</u>	<u>44.21</u>
<u>1325</u>	<u>1.21</u>	<u>-70.8</u>	<u>6.81</u>	<u>20.21</u>	<u>5.703</u>	<u>43.42</u>
<u>1330</u>	<u>0.84</u>	<u>-93.2</u>	<u>6.81</u>	<u>20.31</u>	<u>5.733</u>	<u>44.57</u>
<u>1335</u>	<u>0.73</u>	<u>-108.4</u>	<u>6.81</u>	<u>20.42</u>	<u>5.732</u>	<u>44.78</u>
<u>1340</u>	<u>0.69</u>	<u>-118.5</u>	<u>6.81</u>	<u>20.46</u>	<u>5.740</u>	<u>44.85</u>
<u>1345</u>	<u>0.67</u>	<u>-122.8</u>	<u>6.82</u>	<u>20.39</u>	<u>5.751</u>	<u>44.93</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH/GRO</u>	<u>1345</u>	_____	_____
<u>TPH DRO</u>	<u> </u>	_____	_____
<u>Ch, Hex, Cy, TPA</u>	<u> </u>	_____	<u>HEAT (Flushed out HNO3)</u>
<u>COMMENTS:</u>	_____	_____	_____

Dark Brown / Very Strong Odor / Cloudy
At this depth there is a lot of HNO3 flushed out of well water &

Using Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 6.84 x 0.80 = -- (Total Depth of Well) 45.57

Signature: JM

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-19-09 WELL NO. IW006

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 42.78 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 55.00 FT.
- D. Height of Water Column in casing (h = TD - SWL): 12.22 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1407

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1410</u>	<u>4.12</u>	<u>-15.3</u>	<u>6.60</u>	<u>21.03</u>	<u>4.958</u>	<u>42.79</u>
<u>1415</u>	<u>1.56</u>	<u>-27.5</u>	<u>6.60</u>	<u>20.83</u>	<u>4.958</u>	<u>42.82</u>
<u>1420</u>	<u>0.92</u>	<u>-45.1</u>	<u>6.63</u>	<u>20.52</u>	<u>4.985</u>	<u>42.83</u>
<u>1425</u>	<u>0.72</u>	<u>-54.7</u>	<u>6.61</u>	<u>20.52</u>	<u>4.988</u>	<u>42.85</u>
<u>1430</u>	<u>0.60</u>	<u>-61.3</u>	<u>6.62</u>	<u>20.96</u>	<u>4.990</u>	<u>42.82</u>
<u>1435</u>	<u>0.57</u>	<u>-60.5</u>	<u>6.59</u>	<u>21.24</u>	<u>4.990</u>	<u>42.82</u>
<u>1440</u>						
<u>1445</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH GRO</u>	<u>1435</u>		
<u>TPH DRO</u>			
<u>Ch. Hex. Sol. TPH</u>			
<u>1,2-Dichloroethane</u>			

COMMENTS: Very Dark Brown / Very Strong Odor / Cloudy < 1/2 gal

* Dry Metals Filter in Lab H2O2 Flushed out w/ used water *

- Casing Capacities:
- 2-inch hole.....0.16 gal/lin ft.
 - 4-inch hole.....0.65 gal/lin ft.
 - 6.5-inch hole.....1.70 gal/lin ft
 - 8-inch hole.....2.60 gal/lin ft
 - 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 12.22 x 0.80 = -- (Total Depth of Well) 45.82

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/23/09 WELL NO. IW005
 FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 64 °F
 FIELD PERSONNEL: JL/JM WEATHER: Clear / calm
 EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513
 Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading 7.00 Standard 4 Reading: 3.97
 Standard 10 Reading: 10.01 ORP: Standard: 240 Reading: 240.1 DO: T°C: 17.3 mmHg: 8.57 DO Conc.: 89.3
 End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 43.68 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 51.05 FT.
 D. Height of Water Column in casing (h = TD - SWL): 7.37 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 0936

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
940	6.84	111.8	6.42	19.31	5.803	43.89
945	1.89	-107.2	6.57	20.19	5.936	44.10
950	1.10	-141.9	6.64	20.33	5.964	44.44
955	.96	-152.1	6.65	20.44	5.989	44.47
1000	.86	-158.1	6.65	20.50	6.026	44.74
1005	.81	-161.0	6.65	20.84	6.032	44.64

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH/dro	1005		
TPH/dro			
Chloride, TDS			

COMMENTS:

Dark brown / strong odor / Silty Markey

4/2 80°

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 7.37 x 0.80 = -- (Total Depth of Well) 45.15

Signature: *JM*

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/23/09 WELL NO. IW004

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.44 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 55.00 FT.
- D. Height of Water Column in casing (h = TD - SWL): 10.56 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1043

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1045</u>	<u>6.19</u>	<u>-24.3</u>	<u>6.37</u>	<u>21.75</u>	<u>6019</u>	<u>44.47</u>
<u>1050</u>	<u>1.76</u>	<u>-14.6</u>	<u>6.34</u>	<u>21.98</u>	<u>5981</u>	<u>44.46</u>
<u>1055</u>	<u>1.20</u>	<u>-13.7</u>	<u>6.35</u>	<u>22.07</u>	<u>5981</u>	<u>44.48</u>
<u>1100</u>	<u>.91</u>	<u>-14.9</u>	<u>6.32</u>	<u>22.32</u>	<u>5971</u>	<u>45.45</u>
<u>1105</u>	<u>0.78</u>	<u>-15.3</u>	<u>6.34</u>	<u>22.59</u>	<u>5979</u>	<u>45.58</u>
<u>1110</u>	<u>0.73</u>	<u>-18.0</u>	<u>6.33</u>	<u>22.62</u>	<u>5978</u>	<u>45.60</u>
<u>1115</u>	<u>0.69</u>	<u>-19.1</u>	<u>6.35</u>	<u>22.58</u>	<u>5990</u>	<u>44.47</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTAK / TPA6RO</u>	<u>1115</u>		
<u>GPH DRO</u>	<u>S</u>		
<u>Chlor C. TDS</u>			

COMMENTS:

light Brown / Strong odor / Murky < 1/2 gal

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 10.56 x 0.80 = -- (Total Depth of Well) 46.55

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-23-09 WELL NO. IW003

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 67 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.96 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 84.90 FT.
D. Height of Water Column in casing (h = TD - SWL): 39.94 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1236

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1240</u>	<u>6.55</u>	<u>-88.4</u>	<u>6.86</u>	<u>20.79</u>	<u>5.426</u>	<u>45.08</u>
<u>1245</u>	<u>1.31</u>	<u>-114.5</u>	<u>6.81</u>	<u>21.54</u>	<u>5.480</u>	<u>45.15</u>
<u>1250</u>	<u>1.88</u>	<u>-131.5</u>	<u>6.80</u>	<u>21.66</u>	<u>5.444</u>	<u>45.32</u>
<u>1255</u>	<u>1.78</u>	<u>-143.6</u>	<u>6.80</u>	<u>21.58</u>	<u>5.448</u>	<u>45.43</u>
<u>1300</u>	<u>1.69</u>	<u>-152.7</u>	<u>6.78</u>	<u>21.65</u>	<u>5.437</u>	<u>45.49</u>
<u>1305</u>	<u>1.63</u>	<u>157.4</u>	<u>6.78</u>	<u>21.59</u>	<u>5.447</u>	<u>45.63</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>RTER / TDH 620</u>	<u>1305</u>	_____	_____
<u>TDH DRO</u>	<u>5</u>	_____	_____
<u>Ch. Hx Comp. TDS</u>	<u>5</u>	_____	_____

COMMENTS:

Dr. Brown / Strawn 0201 / Merkey

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.63 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 39.94 x 0.80 = -- (Total Depth of Well) 52.94

Signature: [Signature]

DUP-201

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/23/09 WELL NO. IW015
FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F
FIELD PERSONNEL: JL/JM WEATHER: Clear/Breezy
EQUIPMENT CALIBRATION: YSI QED Serial No.:
Spec. Conductivity: Standard: Reading: ; pH Standard: 7 Reading: ; Standard 4 Reading:
Standard 10 Reading: ; ORP: Standard: Reading: ; DO: T°C: mmHg: DO Conc.:
End-of-Day Recheck: Spec. Cond: ; pH 7: ; pH 4: ; pH 10: ; ORP:

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 44.58 FT.
B. Thickness of Free Product, if present: Inches FT.
C. Total Depth of well (TD) from top of casing/piezometer: 53.42 FT.
D. Height of Water Column in casing (h = TD - SWL): 8.84 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 1324

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1326	4.38	-57.3	6.82	22.09	5.371	44.50
1331	1.08	-96.6	6.82	22.74	5.348	44.78
1336	.77	-92.9	6.81	23.13	5.351	44.84
1341	.67	-111.1	6.81	23.12	5.355	44.95
1346	0.59	-119.6	6.80	23.32	5.347	N/A
1351	0.56	-99.6	6.79	23.87	5.352	45.09

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH GRD	1351		
OPH DRO			
Chloro C, TDS			

COMMENTS: Dark Brown / strong odor / Murky 1/2 gal
* DUP-201

sing Capacities:
2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
Collect sample when Depth to Water measures Less than or equal to:
Original Water Column: 8.84 x 0.80 = -- (Total Depth of Well) 46.34

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/27/09 WELL NO. MWO 81SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 70 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.14 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 75.95 FT.
D. Height of Water Column in casing (h = TD - SWL): 29.81 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1436

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1439</u>	<u>6.54</u>	<u>5.4</u>	<u>6.89</u>	<u>20.34</u>	<u>27.44</u>	<u>45.67</u>
<u>1444</u>	<u>2.10</u>	<u>-24.6</u>	<u>6.81</u>	<u>20.36</u>	<u>27.09</u>	<u>45.65</u>
<u>1449</u>	<u>1.21</u>	<u>-27.4</u>	<u>6.80</u>	<u>20.17</u>	<u>26.73</u>	<u>45.72</u>
<u>1454</u>	<u>0.97</u>	<u>-22.4</u>	<u>6.79</u>	<u>19.99</u>	<u>26.59</u>	<u>45.67</u>
<u>1459</u>	<u>0.89</u>	<u>-17.1</u>	<u>6.79</u>	<u>19.92</u>	<u>26.49</u>	<u>45.66</u>
<u>1504</u>	<u>0.82</u>	<u>-13.0</u>	<u>6.79</u>	<u>19.97</u>	<u>26.44</u>	<u>45.66</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH GRO</u>	<u>1504</u>		
<u>PH DRD</u>	<u>5</u>		
<u>Ch. Hex. C. TDS</u>			
<u>Dist. Mic. 3</u>			

COMMENTS: Clear / No odor / No Color < 1/2 gal

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 29.81 x 0.80 = (Total Depth of Well) 52.10

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/23/09 WELL NO. MW0805A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 70 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 45.70 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 74.91 FT.
- D. Height of Water Column in casing (h = TD - SWL): 29.21 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1528

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1530</u>	<u>10.62</u>	<u>42.4</u>	<u>7.05</u>	<u>20.73</u>	<u>18.73</u>	<u>46.12</u>
<u>1535</u>	<u>5.08</u>	<u>11.0</u>	<u>7.06</u>	<u>21.22</u>	<u>18.45</u>	<u>46.09</u>
<u>1540</u>	<u>4.63</u>	<u>-4.1</u>	<u>7.09</u>	<u>21.20</u>	<u>18.40</u>	<u>46.11</u>
<u>1545</u>	<u>4.64</u>	<u>-5.5</u>	<u>7.10</u>	<u>21.21</u>	<u>18.31</u>	<u>46.12</u>
<u>1550</u>	<u>4.56</u>	<u>-3.7</u>	<u>7.09</u>	<u>21.25</u>	<u>18.30</u>	<u>46.10</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>8TET 1701 620</u>	<u>1550</u>		
<u>7P4020</u>	<u>5</u>		
<u>Ch. H₂O, TDS</u>			

COMMENTS: No Color / 8/10/09 220- / Clear -1/250

- Sampling Capacities:
- 2-inch hole.....0.16 gal/lin ft.
 - 4-inch hole.....0.65 gal/lin ft.
 - 6.5-inch hole.....1.70 gal/lin ft.
 - 8-inch hole.....2.60 gal/lin ft.
 - 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
Collect sample when Depth to Water measures Less than or equal to:
Original Water Column: 29.21 x 0.80 = -- (Total Depth of Well) 51.54

Signature: [Signature] 8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 2/24/09 WELL NO. MW07984

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 50 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading 7.00; Standard 4 Reading: 4.00

Standard 10 Reading: 9.98 ; ORP: Standard: 240 Reading: 240.3 DO: T°C: 15.30 mmHg: 9.02 DO Conc.: 98.7

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.03 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 72.76 FT.
 D. Height of Water Column in casing (h = TD - SWL): 26.73 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 905

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
907	7.28	141.9	6.33	17.06	2056	46.09
912	2.13	83.7	6.74	17.12	2061	46.06
917	1.50	65.2	6.82	17.72	2056	46.05
922	1.23	47.8	6.82	17.86	2057 ²⁰⁵⁹ 17.87	46.03
927	0.97	32.8	6.87	18.27	2.057	46.05
932	0.92	25.8	6.87	18.42	2.058	46.04
0937	0.83	15.9	6.86	18.67	2.060	46.04

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>STEX / TPH 620</u>	<u>0937</u>	_____	_____
<u>TPH D10</u>	_____	_____	_____
<u>CH Hex C-TDS</u>	_____	_____	_____

COMMENTS:

Clear / Slight Odor / No Color 2/23/09

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures **Less than or equal to:**

Original Water Column: 26.73 x 0.80 = -- (Total Depth of Well) 51.37

Signature: JM

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-28-09 WELL NO. IW016

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 50 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.70 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 73.68 FT.
- D. Height of Water Column in casing (h = TD - SWL): 26.98 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 0958

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1000	7.58	39.1	6.81	18.89	5.052	46.71
1005	1.44	-49.1	6.81	18.83	5.117	46.85
1010	0.90	-72.5	6.82	18.87	5.129	46.94
1015	0.67	-82.2	6.83	19.10	5.126	47.08
1020	0.57	-85.3	6.84	19.25	5.125	47.09
1025	0.52	-90.4	6.85	19.39	5.126	47.31

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH GRD	10.25		
TPH DLO			
CHHC, TDs			

COMMENTS:

Dark Brown / Strong odor / Cloudy Mercury = 1/2 gal

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 26.98 x 0.80 = -- (Total Depth of Well) 52.09

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. MW091SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 57 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 43.84 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 102.41 FT.
- D. Height of Water Column in casing (h = TD - SWL): 58.57 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1100

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1103	6.62	-26.6	7.05	19.91	4289	43.96
1108	3.61	-26.0	6.88	19.96	4550	43.93
1113	3.28	-6.6	6.86	19.93	4606	43.91
1118	3.25	8.6	6.85	20.04	4615	43.93
1123	3.19	18.8	6.85	20.09	4626	43.92
1128	3.13	28.0	6.85	20.18	4628	43.93
1133	3.13	34.6	6.85	20.29	4621	43.92

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH / GAO	1133		
TPH DRO			
Ch, HCB, PCB, TDS			

COMMENTS: Slightly Silty / no odor / 1st Green (Needs new bonded tubing)
2/2 get

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 58.57 x 0.80 = -- (Total Depth of Well) 55.55

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-24-09 WELL NO. MW0925A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 43.89 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 102.25 FT.
- D. Height of Water Column in casing (h = TD - SWL): 58.36 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1305

	Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
	<u>1308</u>	<u>6.20</u>	<u>33.6</u>	<u>6.92</u>	<u>21.66</u>	<u>4027</u>	<u>43.92</u>
	<u>1313</u>	<u>3.65</u>	<u>48.7</u>	<u>6.85</u>	<u>21.93</u>	<u>4563</u>	<u>43.90</u>
	<u>1318</u>	<u>3.22</u>	<u>56.5</u>	<u>6.86</u>	<u>21.45</u>	<u>4829</u>	<u>43.90</u>
	<u>1323</u>	<u>3.03</u>	<u>61.1</u>	<u>6.86</u>	<u>21.54</u>	<u>4873</u>	<u>43.94</u>
	<u>1328</u>	<u>2.91</u>	<u>64.2</u>	<u>6.87</u>	<u>21.77</u>	<u>4892</u>	<u>43.95</u>
	<u>1333</u>	<u>2.92</u>	<u>66.7</u>	<u>6.88</u>	<u>21.58</u>	<u>4907</u>	<u>43.92</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX TDH 11620</u>	<u>1333</u>		
<u>TDH DLO</u>	<u>5</u>		
<u>Cl, H₂O₂, TDS</u>			
<u>Disinfectant</u>			

COMMENTS: Slightly Silty / no odor / light green < 1/2 sol.

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.

4-inch hole.....0.65 gal/lin ft.

6.5-inch hole.....1.70 gal/lin ft.

8-inch hole.....2.60 gal/lin ft.

10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 58.36 x 0.80 = 46.69 (Total Depth of Well) 55.56

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. MWO 935A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.12 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 103.10 FT.
- D. Height of Water Column in casing (h = TD - SWL): 58.98 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1356

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1359</u>	<u>6.5</u>	<u>62.1</u>	<u>6.83</u>	<u>20.54</u>	<u>4098</u>	<u>44.15</u>
<u>1404</u>	<u>2.05</u>	<u>74.1</u>	<u>6.84</u>	<u>20.86</u>	<u>4932</u>	<u>44.14</u>
<u>1409</u>	<u>1.73</u>	<u>77.9</u>	<u>6.82</u>	<u>20.79</u>	<u>5083</u>	<u>44.15</u>
<u>1414</u>	<u>1.63</u>	<u>78.5</u>	<u>6.85</u>	<u>20.72</u>	<u>5117</u>	<u>44.15</u>
<u>1419</u>	<u>1.67</u>	<u>78.2</u>	<u>6.87</u>	<u>20.73</u>	<u>5121</u>	<u>44.15</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH B20</u>	<u>1419</u>		
<u>TPH PRO</u>	<u>5</u>		
<u>ChloroC, TDS</u>			
<u>DP, Microb</u>			

COMMENTS: Clear / no odor / light green 4/23/09

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 58.98 x 0.80 = -- (Total Depth of Well) 55.91

Signature: JM 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. IWO18

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.05 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 53.40 FT.
- D. Height of Water Column in casing (h = TD - SWL): 7.37 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1455

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1459</u>	<u>3.31</u>	<u>64.3</u>	<u>6.82</u>	<u>21.19</u>	<u>3785</u>	<u>46.11</u>
<u>1504</u>	<u>1.57</u>	<u>78.4</u>	<u>6.79</u>	<u>21.61</u>	<u>4588</u>	<u>46.16</u>
<u>1509</u>	<u>1.06</u>	<u>82.7</u>	<u>6.77</u>	<u>21.28</u>	<u>4840</u>	<u>46.15</u>
<u>1514</u>	<u>0.85</u>	<u>85.6</u>	<u>6.77</u>	<u>21.39</u>	<u>4893</u>	<u>46.15</u>
<u>1519</u>	<u>0.79</u>	<u>87.2</u>	<u>6.77</u>	<u>21.60</u>	<u>4906</u>	<u>46.15</u>
<u>1524</u>	<u>0.74</u>	<u>88.8</u>	<u>6.76</u>	<u>21.58</u>	<u>4920</u>	<u>46.12</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH GRO</u>	<u>1524</u>	_____	_____
<u>TPH DRO</u>	<u> </u>	_____	_____
<u>OL, HLC, TDS</u>	<u> </u>	_____	_____
<u>Di. Metals</u>	<u> </u>	_____	_____

COMMENTS:

light green / no odor (At 1511) Water become silty and light Brown
< 1/2 gal

Using Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 7.37 x 0.80 = 5.90 (Total Depth of Well) 47.52

Signature: JM

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-25-09 WELL NO. MW0044

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: JL/JM WEATHER: Cloudy / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: 57100513

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7.18 Reading: 7.02 Standard 4 Reading: 3.99

Standard 10 Reading: 10.01 ; ORP: Standard: 240 Reading: 240.1 ; DO: T°C: 13.81 mmHg: 92.7 DO Conc.: 9.30

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.89 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 62.71 FT.
- D. Height of Water Column in casing (h = TD - SWL): 20.82 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 0915

	Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
	<u>0916</u>	<u>4.02</u>	<u>191.8</u>	<u>6.58</u>	<u>17.58</u>	<u>2.864</u>	<u>41.94</u>
	<u>0921</u>	<u>1.86</u>	<u>120.3</u>	<u>6.71</u>	<u>17.79</u>	<u>2.962</u>	<u>41.93</u>
	<u>0925</u>	<u>1.45</u>	<u>163.1</u>	<u>6.81</u>	<u>18.02</u>	<u>3.114</u>	<u>41.92</u>
	<u>0931</u>	<u>1.17</u>	<u>160.5</u>	<u>6.74</u>	<u>18.31</u>	<u>3.145</u>	<u>41.91</u>
	<u>0936</u>	<u>0.97</u>	<u>156.7</u>	<u>6.74</u>	<u>18.36</u>	<u>3.153</u>	<u>41.92</u>
	<u>0941</u>	<u>0.72</u>	<u>153.8</u>	<u>6.74</u>	<u>18.49</u>	<u>3.140</u>	<u>41.93</u>
	<u>0945</u>	<u>0.75</u>	<u>143.9</u>	<u>6.77</u>	<u>18.55</u>	<u>3.097</u>	<u>41.91</u>
	<u>0951</u>	<u>0.65</u>	<u>136.0</u>	<u>6.77</u>	<u>18.60</u>	<u>3.057</u>	<u>41.92</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH / GAO</u>	<u>0951</u>		
<u>OPH / DRO</u>			
<u>CHL / HX / C₁ / TDS</u>			

COMMENTS: No O₂ / Clear / light green > 1/2 gal

- Casing Capacities:
- 2-inch hole.....0.16 gal/lin ft.
 - 4-inch hole.....0.65 gal/lin ft.
 - 6.5-inch hole.....1.70 gal/lin ft.
 - 8-inch hole.....2.60 gal/lin ft.
 - 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 20.82 x 0.80 = — (Total Depth of Well) 46.05

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-25-09 WELL NO. T2020

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 54 °F

FIELD PERSONNEL: JL/JM WEATHER: cloudy / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.89 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 103.35 FT.
- D. Height of Water Column in casing (h = TD - SWL): 58.51 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1109

	Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL	
	<u>1111</u>	<u>4.45</u>	<u>122.6</u>	<u>6.89</u>	<u>19.21</u>	<u>4.644</u>	<u>44.95</u>	<u>X see com</u>
	<u>1116</u>	<u>2.31</u>	<u>118.5</u>	<u>6.86</u>	<u>19.10</u>	<u>6.049</u>	<u>44.91</u>	
	<u>1121</u>	<u>1.79</u>	<u>130.5</u>	<u>6.85</u>	<u>19.03</u>	<u>6.227</u>	<u>44.99</u>	
<u>Set</u>	<u>1126</u>	<u>1.60</u>	<u>130.4</u>	<u>6.85</u>	<u>19.13</u>	<u>6.768</u>	<u>44.89</u>	
<u>Com</u>	<u>1131</u>	<u>1.59</u>	<u>130.3</u>	<u>6.85</u>	<u>19.14</u>	<u>6.284</u>	<u>44.89</u>	
	<u>1136</u>							
	<u>1141</u>							

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>35EX / TPH 620</u>	<u>1131</u>		
<u>TPH 620</u>			
<u>CP, Hex C, TDS</u>			

COMMENTS: 1111
* Very silty / reddish brown color / no odor / very silty
* @ 1123 water started to clear slightly

Casing Capacities:
 1-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 58.51 x 0.80 = -- (Total Depth of Well) 58.51

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-25-09 WELL NO. 2W021

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.92 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 102.91 FT.
- D. Height of Water Column in casing (h = TD - SWL): 58.49 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1254

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1256</u>	<u>6.62</u>	<u>115.7</u>	<u>6.95</u>	<u>20.12</u>	<u>3692</u>	<u>44.45</u>
<u>1301</u>	<u>3.84</u>	<u>119.6</u>	<u>6.88</u>	<u>20.53</u>	<u>4240</u>	<u>44.40</u>
<u>1306</u>	<u>3.64</u>	<u>119.2</u>	<u>6.85</u>	<u>20.82</u>	<u>4814</u>	<u>44.41</u>
<u>1311</u>	<u>2.84</u>	<u>119.1</u>	<u>6.80</u>	<u>21.03</u>	<u>5135</u>	<u>44.36</u>
<u>1316</u>	<u>2.83</u>	<u>118.1</u>	<u>6.81</u>	<u>21.40</u>	<u>5224</u>	<u>44.40</u>
<u>1321</u>	<u>2.71</u>	<u>118.0</u>	<u>6.82</u>	<u>20.91</u>	<u>5306</u>	<u>44.41</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTX / TPH 020</u>	<u>1321</u>		
<u>TPH DAO</u>	<u> </u>		
<u>CP Hex G₂ TPS</u>	<u> </u>		
<u>TPH DAO</u>	<u> </u>		

COMMENTS:

1st Green / No odor / Clear 4.9 gal.

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 58.49 x 0.80 = (Total Depth of Well) 56.11

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-25-09 WELL NO. SW022

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.33 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 105.27 FT.
- D. Height of Water Column in casing (h = TD - SWL): 60.94 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1404

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1406</u>	<u>7.47</u>	<u>56.8</u>	<u>6.79</u>	<u>21.21</u>	<u>3724</u>	<u>44.31</u>
<u>1411</u>	<u>3.37</u>	<u>79.1</u>	<u>6.84</u>	<u>21.11</u>	<u>3934</u>	<u>44.33</u>
<u>1416</u>	<u>3.02</u>	<u>86.1</u>	<u>6.84</u>	<u>21.31</u>	<u>3959</u>	<u>44.33</u>
<u>1421</u>	<u>2.90</u>	<u>91.3</u>	<u>6.85</u>	<u>21.11</u>	<u>3975</u>	<u>44.32</u>
<u>1426</u>	<u>2.99</u>	<u>93.0</u>	<u>6.86</u>	<u>21.27</u>	<u>3956</u>	<u>44.32</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH/RO</u>	<u>1426</u>	_____	_____
<u>TPH DRO</u>	<u> </u>	_____	_____
<u>Chloro. & TDS</u>	<u> </u>	_____	_____
<u>Di/Meths</u>	<u> </u>	_____	_____

COMMENTS:

* Well needs new tubing 1/2 Banded < 1/2 inch
Clear / no odor

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 60.94 x 0.80 = 48.75 (Total Depth of Well) 56.51

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/25/09 WELL NO. ILW027

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 70 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 1

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.66 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 101.79 FT.
 D. Height of Water Column in casing (h = TD - SWL): 53.13 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1451

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1454</u>	<u>6.92</u>	<u>62.9</u>	<u>7.13</u>	<u>21.34</u>	<u>3232</u>	<u>48.58</u>
<u>1459</u>	<u>4.23</u>	<u>78.3</u>	<u>7.02</u>	<u>20.38</u>	<u>3973</u>	<u>48.57</u>
<u>1504</u>	<u>3.76</u>	<u>84.0</u>	<u>7.09</u>	<u>20.17</u>	<u>4003</u>	<u>48.57</u>
<u>1509</u>	<u>3.64</u>	<u>85.1</u>	<u>7.05</u>	<u>20.08</u>	<u>4008</u>	<u>48.54</u>
<u>1514</u>	<u>3.72</u>	<u>88.7</u>	<u>7.03</u>	<u>20.03</u>	<u>4017</u>	<u>48.56</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>ESTER / TPH GRO</u>	<u>1514</u>		
<u>TPH DCO</u>	<u>5</u>		
<u>CL, HUC, C, TDS</u>			

COMMENTS:

Slightly silty / no odor / Lgt Green < 1/2 sec

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 53.13 x 0.80 = -- (Total Depth of Well) 59.28

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

MW009

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO. ~~212201135~~

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 55 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 0700/14.62 0702/13.89 0703/14.04

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 3.99

Standard 10 Reading: 10.01 ORP: Standard: 240 Reading: 240.1 DO: T°C: 13.74 mmHg: 9.23 DO Conc.: 89.1

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer:

47.91
~~48.51~~ FT.

B. Thickness of Free Product, if present: Inches

FT.

C. Total Depth of well (TD) from top of casing/piezometer:

69.00 ~~108.09~~ FT.

D. Height of Water Column in casing (h = TD - SWL):

21.09 ~~59.58~~ FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 916

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
917	8.86	190.9	6.85	18.43	2651	48.01
922	4.76	173.3	6.99	18.36	2711	47.94
927	4.59	168.7	6.99	18.44	2726	47.93
932	4.58	166.7	7.00	18.51	2731	47.94
937	4.56	164.8	7.00	18.61	2735	47.93

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
STEX / TPH 620	0937		
TPH 220			
Cl, Hex C, TDS, Diss Metals			

COMMENTS:

1st Green / 2nd Orange / Clear < 1/2 gal

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.


Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 59.58 x 0.80 = (Total Depth of Well) 60.42

21.09

52.12

Signature: 

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO. MW0094

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 55 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.73 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 102.85 FT.
- D. Height of Water Column in casing (h = TD - SWL): 55.12 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1006

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1007	6.67	115.9	7.20	19.31	3213	47.82
1012	8.86	126.0	7.08	19.35	3205	50.12
1017	3.53	157.4	6.93	19.52	3196	50.10
1022	3.34	134.1	7.07	19.62	3205	47.97
1027	3.30	130.4	7.08	19.64	3195	48.00
1032	3.26	130.9	7.18	19.77	3191	47.99

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH 620</u>	<u>1032</u>	_____	_____
<u>TPH DRO</u>	_____	_____	_____
<u>Cl, Hx, C, TDS</u>	_____	_____	_____

COMMENTS:

Clear / no odor / 1st Green > 1/2 gal

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft
8-inch hole.....	2.60 gal/lin ft
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 55.12 x 0.80 = -- (Total Depth of Well) 58.75

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO. MW0895A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 55 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.30 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 101.32 FT.
- D. Height of Water Column in casing (h = TD - SWL): 58.02 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1056

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1058</u>	<u>7.58</u>	<u>117.4</u>	<u>7.19</u>	<u>20.01</u>	<u>3781</u>	<u>48.42</u>
<u>1103</u>	<u>3.63</u>	<u>129.1</u>	<u>6.97</u>	<u>20.41</u>	<u>4681</u>	<u>48.35</u>
<u>1109</u>	<u>2.74</u>	<u>129.0</u>	<u>6.96</u>	<u>20.74</u>	<u>4756</u>	<u>48.33</u>
<u>1113</u>	<u>2.68</u>	<u>127.9</u>	<u>6.97</u>	<u>20.94</u>	<u>4764</u>	<u>48.34</u>
<u>1118</u>	<u>2.71</u>	<u>126.9</u>	<u>6.98</u>	<u>21.00</u>	<u>4770</u>	<u>48.34</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH 6RO</u>	<u>1118</u>	_____	_____
<u>TPH DRO</u>	_____	_____	_____
<u>ChloroC, TDS</u>	_____	_____	_____
<u>Distillate</u>	_____	_____	_____

COMMENTS: light green / clear / no odor > 1/2 gal.

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft
- 8-inch hole.....2.60 gal/in ft
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 58.02 x 0.80 = 46.42 (Total Depth of Well) 58.90

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO. MW008A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 49.18 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 115.38 FT.
- D. Height of Water Column in casing (h = TD - SWL): 66.20 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1344

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL	
1349	3.07	-114.4	6.64	21.10	6838	48.96	
1354	0.72	-120.6	6.61	20.94	6837	49.12	
1359	0.65	-125.0	6.62	21.04	6848	49.12	SEE COMMENTS
1404	0.50	-127.4	6.65	21.42	6859	—	
1409	0.47	-128.4	6.67	21.17	6910	—	
1414	0.40	-131.0	6.65	20.95	6899	—	

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH G20	1414		
TPH D20			
Cl, HxC, TDS			
Disinfectant			

COMMENTS: dark Brown / Strong Odor Biomass stuck on tubing
* unable to gauge due to biomass

- Casing Capacities:
- 2-inch hole.....0.16 gal/lin ft.
 - 4-inch hole.....0.65 gal/lin ft.
 - 6.5-inch hole.....1.70 gal/lin ft
 - 8-inch hole.....2.60 gal/lin ft
 - 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 66.20 x 0.80 = -- (Total Depth of Well) 62.42

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/30/09 WELL NO. MA1008

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65° °F

FIELD PERSONNEL: JL/MDM WEATHER: Sunny Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 49.24 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 66.77 FT.
- D. Height of Water Column in casing (h = TD - SWL): 17.53 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1027-1055

OBSERVATIONS: Purging Start Time: 10:27

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>10:30</u>	<u>4.09</u>	<u>61.1</u>	<u>6.15</u>	<u>19.19</u>	<u>5.222</u>	<u>49.19</u>
<u>10:35</u>	<u>1.27</u>	<u>-13.7</u>	<u>6.31</u>	<u>19.29</u>	<u>5.767</u>	<u>49.20</u>
<u>10:40</u>	<u>0.85</u>	<u>-37.8</u>	<u>6.31</u>	<u>19.34</u>	<u>5.842</u>	<u>49.20</u>
<u>10:45</u>	<u>0.69</u>	<u>-45.7</u>	<u>6.33</u>	<u>19.39</u>	<u>5.837</u>	<u>49.22</u>
<u>10:50</u>	<u>0.63</u>	<u>-51.1</u>	<u>6.34</u>	<u>19.53</u>	<u>5.709</u>	<u>49.22</u>
<u>1055</u>	<u>0.64</u>	<u>-53.1</u>	<u>6.38</u>	<u>19.63</u>	<u>5.573</u>	<u>49.20</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX/TPH</u>	<u>1055</u>		
<u>TPH/DRO</u>	<u> </u>		
<u>Hex Chrom, CL, TDS</u>	<u> </u>		

COMMENTS: Diss. Met
White/Grey Slight odor / Slight Silty 7/12/06

Casing Capacities:
 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 17.53 x 0.80 = ^{id.02} 14.02 - (Total Depth of Well) 52.75

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

pg 1 of 2

PROJECT NO.: 212201135 DATE: B-30-09 WELL NO. MW087A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 67° °F

FIELD PERSONNEL: JL/M DM WEATHER: Sunny/Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 49.84 FT.
 B. Thickness of Free Product, if present: _____ Inches 6.33 FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 113.18 FT.
 D. Height of Water Column in casing (h = TD - SWL): 63.34 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1113 -

OBSERVATIONS: Purging Start Time: 1113

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1115</u>	<u>9.31</u>	<u>16.5</u>	<u>6.99</u>	<u>19.39</u>	<u>6.363</u>	<u>51.01</u>
<u>1120</u>	<u>0.93</u>	<u>-74.6</u>	<u>6.88</u>	<u>19.48</u>	<u>6.607</u>	<u>50.25</u>
<u>1125</u>	<u>0.66</u>	<u>-118.8</u>	<u>6.89</u>	<u>19.49</u>	<u>6.619</u>	<u>50.23</u>
<u>1130</u>	<u>0.53</u>	<u>-148.4</u>	<u>6.91</u>	<u>19.48</u>	<u>6.628</u>	<u>50.23</u>
<u>1135</u>	<u>0.48</u>	<u>-165.6</u>	<u>6.79</u>	<u>19.61</u>	<u>6.648</u>	<u>50.23</u>
<u>1140</u>	<u>0.44</u>	<u>-183.9</u>	<u>6.88</u>	<u>19.57</u>	<u>6.671</u>	<u>50.23</u>
<u>1145</u>	<u>0.42</u>	<u>-206.3</u>	<u>6.89</u>	<u>19.62</u>	<u>6.667</u>	<u>50.23</u>
<u>1150</u>	<u>0.41</u>	<u>-227.9</u>	<u>6.92</u>	<u>19.68</u>	<u>6.683</u>	<u>50.24</u>
<u>1155</u>	<u>0.40</u>	<u>-244.4</u>	<u>6.88</u>	<u>19.68</u>	<u>6.683</u>	<u>50.23</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX/TPH</u>	<u>1235</u>	_____	_____
<u>TPH/DRO</u>	<u>S</u>	_____	_____
<u>Hex Cr, CL, TDS, Diss met</u>	<u>S</u>	_____	_____

COMMENTS:

Needs new Sample tubing med Brown/Strong Odor/clear
> 1.0 gal.

Casing Capacities:

1-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft
8-inch hole.....	2.60 gal/lin ft
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 63.34 x 0.80 = -- (Total Depth of Well) 62.50

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

Pg 2 of 2

PROJECT NO.: 212201135 DATE: 3-30-09 WELL NO. MW087A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 67° °F

FIELD PERSONNEL: JL/MDM WEATHER: Sunny Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 49.84 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 113.18 FT.
D. Height of Water Column in casing (h = TD - SWL): 63.34 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1113

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1200</u>	<u>0.39</u>	<u>-254.8</u>	<u>6.90</u>	<u>19.78</u>	<u>6.695</u>	<u>50.23</u>
<u>1205</u>	<u>0.38</u>	<u>-265.9</u>	<u>6.88</u>	<u>19.70</u>	<u>6.697</u>	<u>50.24</u>
<u>1210</u>	<u>0.37</u>	<u>-274.8</u>	<u>6.91</u>	<u>19.78</u>	<u>6.709</u>	<u>50.23</u>
<u>1215</u>	<u>0.37</u>	<u>-282.0</u>	<u>6.81</u>	<u>19.74</u>	<u>6.709</u>	<u>50.23</u>
<u>1220</u>	<u>0.38</u>	<u>-286.9</u>	<u>6.87</u>	<u>19.76</u>	<u>6.705</u>	<u>50.24</u>
<u>1225</u>	<u>0.38</u>	<u>-300.0</u>	<u>6.91</u>	<u>19.80</u>	<u>6.691</u>	<u>50.25</u>
<u>1230</u>	<u>0.37</u>	<u>-304.6</u>	<u>6.88</u>	<u>19.97</u>	<u>6.689</u>	<u>50.25</u>
<u>1235</u>	<u>0.37</u>	<u>-310.0</u>	<u>6.87</u>	<u>19.83</u>	<u>6.681</u>	<u>50.23</u>
<u>1240</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX/TPH</u>	<u>1235</u>		
<u>TPH/DRO</u>	<u>5</u>		
<u>Hex Cr, Cl, TDS, Diss met</u>			

COMMENTS:

mod Brown / Strong odor / clear
7.10 gal.

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 63.34 x 0.80 = -- (Total Depth of Well) 62.50

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/31/09 WELL NO. MW008m

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 43 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading: 7.02 Standard 4 Reading: 4.00

Standard 10 Reading: 10.02 ORP: Standard: 240 Reading: 240.0 DO: T°C: 11.75 mmHg: 10.0 DO Conc.: 90.0

End-of-Day Recheck: Spec. Cond.: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 49.44 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 86.30 FT.
 D. Height of Water Column in casing (h = TD - SWL): 36.86 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 900

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
902	6.93	15.1	6.69	16.82	7508	49.79
907	1.67	-84.0	6.78	17.51	7668	49.78
912	1.19	-104.2	6.80	17.33	7682	49.75
917	1.02	-114.3	6.80	17.44	7657	49.71
922	0.89	-123.1	6.80	17.66	7677	49.73
927	0.83	-128.7	6.79	18.01	7656	49.70
932	0.79	-131.3	6.79	18.30	7642	49.72

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTR4 TPH GRD	932		
TPH GRD			
Chloride, TDS			
Diss Metals			

COMMENTS: Dark Brown / strong odor / cloudy > 1/2 gal

Casing Capacities:
 1/2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 36.86 x 0.80 = -- (Total Depth of Well) 56.81

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/31/09 WELL NO. RW004A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 45 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ : ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.49 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 115.51 FT.
- D. Height of Water Column in casing (h = TD - SWL): 47.50 FT.

PURGING METHOD: Grundfos Bladder Peristaltic/ Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 955

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
958	5.23	18.1	5.06	18.77	10.54	47.59
1003	5.18	-22.9	5.03	18.66	10.62	47.73
1008	0.92	-97.9	5.03	18.47	10.62	47.82
1013	0.82	-26.0	5.03	18.35	10.63	47.84
1018	0.76	-25.4	5.04	18.49	10.62	47.92

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTLX / TPH 000	1018		
TPH 000			
CL, H ₂ O ₂ , TDS			

COMMENTS: Dark Brown / Strong odor / Cloudy / 1/2 gal

- Casing Capacities:
- 2-inch hole.....0.16 gal/lin ft.
 - 4-inch hole.....0.65 gal/lin ft.
 - 6.5-inch hole.....1.70 gal/lin ft.
 - 8-inch hole.....2.60 gal/lin ft.
 - 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 47.50 x 0.80 = -- (Total Depth of Well) 77.51

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/31/09 WELL NO. MW011m
 FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 45 °F
 FIELD PERSONNEL: JL/JM WEATHER: Clear/Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____
 Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____
 Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____
 End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.91 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 91.92 FT.
 D. Height of Water Column in casing (h = TD - SWL): 41.71 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1054

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1056	5.99	-46.6	6.70	18.36	7.114	50.38
1101	1.89	-70.2	6.83	18.24	7.050	50.51
1106	1.28	-74.5	6.84	18.24	7.030	50.60
1111	1.02	-76.0	6.84	18.27	7.028	50.73
1116	0.93	-75.7	6.85	18.26	7.024	50.81
1121	0.86	-75.6	6.86	18.29	7.026	50.85

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH GRD	1121		
TPH PRO			
Cl, HexC, TDS			

COMMENTS:

light Brownish green / strong odor / Cloudy > 1/2 gal

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft
- 8-inch hole.....2.60 gal/lin ft
- 10-inch hole.....4.10 gal/lin ft

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 41.71 x 0.80 = (Total Depth of Well) 58.55

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/31/09 WELL NO. MW2011

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 59 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.53 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 67.95 FT.
 D. Height of Water Column in casing (h = TD - SWL): 17.42 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1230

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1232</u>	<u>6.57</u>	<u>20.7</u>	<u>7.10</u>	<u>18.80</u>	<u>6.852</u>	<u>50.54</u>
<u>1237</u>	<u>2.08</u>	<u>29.0</u>	<u>6.97</u>	<u>19.09</u>	<u>7.149</u>	<u>50.53</u>
<u>1242</u>	<u>1.40</u>	<u>35.5</u>	<u>6.96</u>	<u>18.95</u>	<u>7.203</u>	<u>50.52</u>
<u>1247</u>	<u>1.31</u>	<u>40.6</u>	<u>6.95</u>	<u>18.90</u>	<u>7.812</u>	<u>50.52</u>
<u>1252</u>	<u>1.28</u>	<u>44.4</u>	<u>6.93</u>	<u>18.87</u>	<u>7.216</u>	<u>50.52</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX TPH GLO</u>	<u>1252</u>	_____	_____
<u>TPH DRO</u>	<u> </u>	_____	_____
<u>Chloro-TPH</u>	<u> </u>	_____	_____

COMMENTS: Clear / light green / Slight odor 71/53°

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 17.42 x 0.80 = (Total Depth of Well) 54.01

Signature: [Signature]

DUP-203

Stantec **GROUNDWATER SAMPLING FIELD DATA SHEET**

PROJECT NO.: 212201135 DATE: 3/31/09 WELL NO. MW011A
 FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F
 FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy
EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.94 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 117.43 FT.
 D. Height of Water Column in casing (h = TD - SWL): 66.49 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1310

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1313</u>	<u>6.56</u>	<u>62.5</u>	<u>7.10</u>	<u>18.80</u>	<u>7157</u>	<u>51.20</u>
<u>1318</u>	<u>2.07</u>	<u>63.3</u>	<u>7.05</u>	<u>19.09</u>	<u>7252</u>	<u>51.32</u>
<u>1323</u>	<u>1.33</u>	<u>63.8</u>	<u>7.06</u>	<u>19.19</u>	<u>7274</u>	<u>51.37</u>
<u>1328</u>	<u>1.31</u>	<u>64.4</u>	<u>7.05</u>	<u>19.15</u>	<u>7287</u>	<u>51.28</u>
<u>1333</u>	<u>1.34</u>	<u>65.0</u>	<u>7.05</u>	<u>18.88</u>	<u>7290</u>	<u>51.32</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTX / TPH GRO</u>	<u>1333</u>	_____	_____
<u>TPH DAO</u>	<u> </u>	_____	_____
<u>Cl Hex Co TPS</u>	<u> </u>	_____	_____

COMMENTS:

Clear with light green color / Strong odor 2 1/5 gal
* DUP 203

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 66.49 x 0.80 = -- (Total Depth of Well) 64.23

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-31-09 WELL NO. RW002

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.70 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 71.78 FT.
- D. Height of Water Column in casing (h = TD - SWL): 21.08 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1424

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1426</u>	<u>5.26</u>	<u>-22.0</u>	<u>6.49</u>	<u>19.82</u>	<u>6.016</u>	<u>50.69</u>
<u>1431</u>	<u>1.65</u>	<u>-71.6</u>	<u>6.40</u>	<u>19.73</u>	<u>6.060</u>	<u>50.70</u>
<u>1436</u>	<u>1.93</u>	<u>-70.2</u>	<u>6.43</u>	<u>19.70</u>	<u>6.000</u>	<u>50.69</u>
<u>1441</u>	<u>2.01</u>	<u>-63.8</u>	<u>6.41</u>	<u>19.63</u>	<u>5.960</u>	<u>50.70</u>
<u>1446</u>	<u>1.97</u>	<u>-54.8</u>	<u>6.47</u>	<u>20.18</u>	<u>5.947</u>	<u>50.65</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX GPHARO</u>	<u>1446</u>		
<u>TDH DRO</u>	<u> </u>		
<u>Chloro, TDS, P, Ni, Mn, Fe</u>	<u> </u>		

COMMENTS: Dark Brown / Strong Odor / Cloudy 7/2506

Casing Capacities:
 1-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 21.08 x 0.80 = -- (Total Depth of Well) 54.91

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/31/09 WELL NO. IW 001

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 63 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.98 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 89.22 FT.
- D. Height of Water Column in casing (h = TD - SWL): 40.24 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1508

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1510	5.51	-104.8	6.90	19.99	9894	48.95
1515	1.16	-171.3	6.90	20.33	10.06	48.89
1520	.80	-195.2	6.96	20.23	10.16	48.81
1525	.71	-203.1	6.89	20.22	10.18	49.59
1530	.65	-208.1	6.95	20.08	10.19	49.69

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTX / TPH / GRO	1530		
TPH / DRO			
Cl, Hex, Cr, TDS			

COMMENTS: Disinfect
Dark Brown / Very Strong odor / Crust on top of bowl / Murky
7/23/09

Casing Capacities:
 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 40.24 x 0.80 = (Total Depth of Well) 57.02

Signature: [Signature]
 8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/1/09 WELL NO. MW012M

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 54 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: ; ORP: Standard: 240 Reading: ; DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.90 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 91.51 FT.
 D. Height of Water Column in casing (h = TD - SWL): 42.61 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 944

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
946	5.77	-30.1	6.50	18.02	7328	48.73
951	1.55	-92.5	6.63	18.02	7497	49.16
956	1.09	-105.9	6.67	18.19	7505	49.28
1001	0.91	-114.9	6.67	18.27	7531	49.33
1006	0.80	-120.7	6.67	18.26	7553	49.36
1011	0.72	-119.8	6.67	18.35	7550	49.43
1016	0.67	-122.1	6.67	18.48	7560	49.51

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____


SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTX TPH GRO	1016		
TPH GRO			
Ch, Hex C, TDS			
Diss Metals			

COMMENTS: Dark Brown / Strong Odor / Murky 7/25/09

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 42.61 x 0.80 = -- (Total Depth of Well) 57.42

Signature:  8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/1/09 WELL NO. MW062
FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F
FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION:

YSI

QED

Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.26 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 66.39 FT.
D. Height of Water Column in casing (h = TD - SWL): 18.13 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1035

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1036</u>	<u>6.42</u>	<u>-39.0</u>	<u>6.62</u>	<u>19.93</u>	<u>3646</u>	<u>48.21</u>
<u>1041</u>	<u>1.63</u>	<u>-41.4</u>	<u>6.53</u>	<u>20.60</u>	<u>3.872</u>	<u>48.21</u>
<u>1046</u>	<u>0.94</u>	<u>-42.2</u>	<u>6.52</u>	<u>21.04</u>	<u>3.896</u>	<u>48.21</u>
<u>1051</u>	<u>0.79</u>	<u>-41.1</u>	<u>6.53</u>	<u>21.28</u>	<u>3.858</u>	<u>48.21</u>
<u>1056</u>	<u>0.75</u>	<u>-38.0</u>	<u>6.56</u>	<u>21.32</u>	<u>3.783</u>	<u>48.20</u>
<u>1101</u>	<u>0.77</u>	<u>-35.4</u>	<u>6.58</u>	<u>21.36</u>	<u>3.721</u>	<u>48.21</u>
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTLA TAP BRO</u>	<u>1101</u>	_____	_____
<u>TAP BRO</u>	<u>S</u>	_____	_____
<u>CL, HCL, C, TDS</u>	<u>S</u>	_____	_____
<u>Dist Metals</u>	<u>S</u>	_____	_____

COMMENTS:

light Brown / Strong Odor / Merky 4/23/06

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft
8-inch hole.....2.60 gal/lin ft
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 18.13 x 0.80 = -- (Total Depth of Well) 51.88

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/1/09 WELL NO.: mw012A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.65 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 115.48 FT.
- D. Height of Water Column in casing (h = TD - SWL): 66.83 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1219

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1221</u>	<u>4.50</u>	<u>-1.1</u>	<u>7.88</u>	<u>20.61</u>	<u>0.975</u>	<u>48.59</u>
<u>1226</u>	<u>1.95</u>	<u>-20.6</u>	<u>7.83</u>	<u>20.50</u>	<u>0.935</u>	<u>48.95</u>
<u>1231</u>	<u>1.77</u>	<u>-39.2</u>	<u>7.81</u>	<u>20.61</u>	<u>0.921</u>	<u>48.95</u>
<u>1236</u>	<u>1.72</u>	<u>-56.7</u>	<u>7.80</u>	<u>20.70</u>	<u>0.906</u>	<u>48.96</u>
<u>1241</u>	<u>1.62</u>	<u>-71.2</u>	<u>7.80</u>	<u>20.92</u>	<u>0.900</u>	<u>48.96</u>
<u>1246</u>	<u>1.54</u>	<u>-82.9</u>	<u>7.79</u>	<u>20.86</u>	<u>0.894</u>	<u>48.94</u>
<u>1251</u>	<u>1.56</u>	<u>-92.2</u>	<u>7.80</u>	<u>20.90</u>	<u>0.891</u>	<u>48.94</u>
<u>1256</u>	<u>*N/A</u>	<u>-100.9</u>	<u>7.79</u>	<u>20.88</u>	<u>0.889</u>	<u>48.91</u>
<u>1301</u>	<u>1.84</u>	<u>-108.0</u>	<u>7.80</u>	<u>20.77</u>	<u>885</u>	<u>48.99</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH 8</u>	<u>1301</u>	_____	_____
<u>TPH D</u>	<u>1</u>	_____	_____
<u>CH₂Cl₂, TDS</u>	<u>1</u>	_____	_____
<u>DPSS Metals</u>	<u>1</u>	_____	_____

COMMENTS:

*YSI Turned off, will collect 1 more parameter

Clear / slight odor / LG + Green 0.880 > 1.30

Casing Capacities:

2-inch hole.....	0.16 gal/in ft.
4-inch hole.....	0.65 gal/in ft.
6.5-inch hole.....	1.70 gal/in ft.
8-inch hole.....	2.60 gal/in ft.
10-inch hole.....	4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 66.83 x 0.80 = 53.46 (Total Depth of Well) 62.01

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/1/09 WELL NO. R2W088M

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 64 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 078100513

Spec. Conductivity: Standard: 1.413 Reading: 1.413 pH Standard: 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 10.00 ; ORP: Standard: 240 Reading: 240.0 DO: T°C: 14.72 mmHg: 89.9 DO Conc.: 9.18

End-of-Day Recheck: Spec. Cond.: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 49.30 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 92.93 FT.
D. Height of Water Column in casing (h = TD - SWL): 43.63 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1323

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1326</u>	<u>6.26</u>	<u>-14.4</u>	<u>6.11</u>	<u>21.16</u>	<u>8.809</u>	<u>49.29</u>
<u>1331</u>	<u>1.53</u>	<u>-44.1</u>	<u>5.88</u>	<u>21.72</u>	<u>11.80</u>	<u>49.30</u>
<u>1336</u>	<u>0.91</u>	<u>-63.0</u>	<u>5.87</u>	<u>21.87</u>	<u>21.88</u>	<u>49.25</u>
<u>1341</u>	<u>0.77</u>	<u>-69.1</u>	<u>5.86</u>	<u>22.21</u>	<u>12.82</u>	<u>49.20</u>
<u>1346</u>	<u>0.71</u>	<u>-78.8</u>	<u>5.86</u>	<u>21.89</u>	<u>12.94</u>	<u>49.21</u>
<u>1351</u>	<u>0.67</u>	<u>-85.6</u>	<u>5.86</u>	<u>22.16</u>	<u>12.95</u>	<u>49.29</u>
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BT2X / OPH 6</u>	<u>1351</u>	_____	_____
<u>VT2-D</u>	<u>1</u>	_____	_____
<u>Ch, Hex Cr, TDS</u>	<u>1</u>	_____	_____

COMMENTS: Dr. Metc
Light Brown / Very Strong Odor / Mercury > 1/2 g/L

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft
8-inch hole.....2.60 gal/lin ft
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 43.63 x 0.80 = -- (Total Depth of Well) 58.02

Signature: SM

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/1/09 WELL NO. RW003
 FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F
 FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.58 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 66.88 FT.
- D. Height of Water Column in casing (h = TD - SWL): 18.30 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1424

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1425</u>	<u>5.70</u>	<u>-39.6</u>	<u>6.57</u>	<u>20.89</u>	<u>3.731</u>	<u>48.49</u>
<u>1430</u>	<u>1.58</u>	<u>-75.6</u>	<u>6.60</u>	<u>20.95</u>	<u>3.655</u>	<u>48.52</u>
<u>1435</u>	<u>0.89</u>	<u>-85.2</u>	<u>6.62</u>	<u>20.94</u>	<u>4.655</u>	<u>48.53</u>
<u>1440</u>	<u>0.71</u>	<u>-91.6</u>	<u>6.61</u>	<u>20.99</u>	<u>3.639</u>	<u>48.52</u>
<u>1445</u>	<u>0.62</u>	<u>-92.9</u>	<u>6.61</u>	<u>20.90</u>	<u>3.634</u>	<u>48.50</u>
<u>1450</u>	<u>0.52</u>	<u>-94.1</u>	<u>6.62</u>	<u>20.97</u>	<u>3.624</u>	<u>48.50</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTBx / TPA C</u>	<u>1450</u>		
<u>TPA D</u>	<u> </u>		
<u>Ch. H₂O Co. TDS</u>	<u> </u>		

COMMENTS:

Light Brown / Very Strong Odor, Cloud on top of SWL / Merck
7 1/2 gal

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft
- 8-inch hole.....2.60 gal/in ft
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 18.30 x 0.80 = (Total Depth of Well) 52.24

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/6/09 WELL NO. 4 WOOD

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513
@ 13.83 @ 14.01 @ 14.27

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7.01 Standard 4 Reading: 921

Standard 10 Reading: 10.07 ORP: Standard: 240 Reading: 240.0 DO: T°C: 14.51 mmHg: 9.34 DO Conc.: 91.2

End-of-Day Recheck: Spec. Cond.: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.99 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 84.90 FT.
- D. Height of Water Column in casing (h = TD - SWL): 37.91 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 14.42

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1445</u>	<u>5.15</u>	<u>49.5</u>	<u>6.82</u>	<u>20.33</u>	<u>7695</u>	<u>47.30</u>
<u>1450</u>	<u>2.28</u>	<u>-126.7</u>	<u>6.88</u>	<u>20.39</u>	<u>7860</u>	<u>47.47</u>
<u>1455</u>	<u>1.69</u>	<u>-141.9</u>	<u>6.93</u>	<u>20.89</u>	<u>7880</u>	<u>47.59</u>
<u>1500</u> 1460	<u>1.44</u>	<u>-154.3</u>	<u>6.94</u>	<u>21.05</u>	<u>7931</u>	<u>47.73</u>
<u>1505</u> 1465	<u>1.34</u>	<u>-152.3</u>	<u>6.94</u>	<u>20.84</u>	<u>7998</u>	<u>47.83</u>
<u>1510</u>	<u>1.26</u>	<u>-130.0</u>	<u>6.95</u>	<u>21.20</u>	<u>7976</u>	<u>47.98</u>
<u>1515</u>	<u>1.18</u>	<u>-137.4</u>	<u>6.88</u>	<u>21.56</u>	<u>8017</u>	<u>47.99</u>
<u>1520</u> *	<u>1.35</u>	<u>-129.4</u>	<u>6.94</u>	<u>21.76</u>	<u>7988</u>	<u>48.20</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH 6</u>	<u>1520</u>	_____	_____
<u>TPH D</u>	<u>1</u>	_____	_____
<u>Ch, Hcn C, TDS</u>	<u>1</u>	_____	_____

COMMENTS:

Dark Brown / Strong Odor / Merley 1/2 gal
* YSI Turned off @ 1520 Note (DO spike) (Clust on top of water)

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 37.91 x 0.80 = 30.33 (Total Depth of Well) 54.57

Signature: _____

DUP 204

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/7/09 WELL NO. #W028

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 55 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513
12.98 / 0756
Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7.00 Reading: 7.00 Standard 4 Reading: 4.00
1350 / 0903
Standard 10 Reading: 9.95 ORP: Standard: 240 Reading: 240.0 DO: T°C: 13.10 mmHg: 9.91 DO Conc.: 92.5
0808

End-of-Day Recheck: Spec. Cond.: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.57 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 108.09 FT.
D. Height of Water Column in casing (h = TD - SWL): 59.58 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 955

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
0957	7.91	222.1	6.71	17.52	2844	48.60
1002	5.17	200.1	7.05	18.14	3.355	48.57
1007	4.72	192.0	7.07	18.14	3.604	48.57
1012	4.56	186.5	7.10	18.47	3.660	48.57
1017	4.48	183.5	7.14	18.77	3.674	48.57
1022	4.46	182.4	7.04	18.87	3.685	48.60

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH 6	1022		
TPH D			
Ch, Hex C, TDS			
Orss Metals			

COMMENTS:

DUP 204 Clear / light green / no odor > 1/25.0

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft
8-inch hole.....2.60 gal/lin ft
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 59.58 x 0.80 = -- (Total Depth of Well) 60.42

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/7/09 WELL NO. MW037

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ :ORP: Standard: _____ Reading: _____ :DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH 10: _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 45.74 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 61.55 FT.
 D. Height of Water Column in casing (h = TD - SWL): 15.81 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1109

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1111</u>	<u>7.30</u>	<u>19.3</u>	<u>6.88</u>	<u>20.51</u>	<u>3.242</u>	<u>44.69</u>
<u>1116</u>	<u>2.29</u>	<u>-59.4</u>	<u>6.91</u>	<u>20.54</u>	<u>6.484</u>	<u>44.65</u>
<u>1121</u>	<u>1.44</u>	<u>-80.3</u>	<u>6.93</u>	<u>20.49</u>	<u>6.593</u>	<u>44.62</u>
<u>1126</u>	<u>1.22</u>	<u>-92.3</u>	<u>7.00</u>	<u>20.45</u>	<u>6.614</u>	<u>44.62</u>
<u>1131</u>	<u>1.15</u>	<u>-99.9</u>	<u>6.91</u>	<u>20.45</u>	<u>6.614</u>	<u>44.65</u>
<u>1136</u>	<u>1.07</u>	<u>-103.4</u>	<u>7.00</u>	<u>20.39</u>	<u>6.596</u>	<u>44.67</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH6</u>	<u>1136</u>	_____	_____
<u>TDH D</u>	<u>1</u>	_____	_____
<u>Cl, HCO₃, TDS</u>	<u>1</u>	_____	_____

COMMENTS: Disinfect
light Brown / Slight odor / Slight Salty < 1/25

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 15.81 x 0.80 = -- (Total Depth of Well) 48.90

Signature: 48.90 _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/7/09 WELL NO. MW005

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F

FIELD PERSONNEL: JL/JM WEATHER: Clear/Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 45.48 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 67.75 FT.
 D. Height of Water Column in casing (h = TD - SWL): 22.26 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1327

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1330</u>	<u>6.75</u>	<u>13.8</u>	<u>6.78</u>	<u>21.88</u>	<u>4150</u>	<u>45.50</u>
<u>1335</u>	<u>1.44</u>	<u>-42.6</u>	<u>6.83</u>	<u>21.16</u>	<u>4474</u>	<u>45.55</u>
<u>1340</u>	<u>1.20</u>	<u>-52.9</u>	<u>6.81</u>	<u>21.08</u>	<u>4518</u>	<u>45.55</u>
<u>1345</u>	<u>1.08</u>	<u>-58.4</u>	<u>6.79</u>	<u>21.11</u>	<u>4582</u>	<u>45.60</u>
<u>1350</u>	<u>1.00</u>	<u>-69.0</u>	<u>6.79</u>	<u>21.22</u>	<u>4606</u>	<u>45.50</u>
<u>1355</u>	<u>0.91</u>	<u>-66.7</u>	<u>6.80</u>	<u>21.15</u>	<u>4636</u>	<u>45.55</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH 6</u>	<u>1355</u>	_____	_____
<u>TPH D</u>	<u> </u>	_____	_____
<u>Ch. Hex Cr. PDS</u>	<u> </u>	_____	_____
<u>Disinfectants</u>	<u> </u>	_____	_____

COMMENTS:

light green / slightly silty / strong odor 2/25/1

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft
 8-inch hole.....2.60 gal/lin ft
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 22.26 x 0.80 = (Total Depth of Well) 49.94

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/7/09 WELL NO. MW006
 FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F
 FIELD PERSONNEL: JL/JM WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____
 Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____
 Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____
 End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 45.90 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 68.38 FT.
 D. Height of Water Column in casing ($h = TD - SWL$): 22.48 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1418

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1420</u>	<u>6.78</u>	<u>-21.6</u>	<u>6.94</u>	<u>22.36</u>	<u>6838</u>	<u>45.80</u>
<u>1425</u>	<u>1.69</u>	<u>-71.7</u>	<u>7.04</u>	<u>22.16</u>	<u>7.762</u>	<u>45.84</u>
<u>1430</u>	<u>1.83</u>	<u>-94.7</u>	<u>6.99</u>	<u>22.26</u>	<u>7.979</u>	<u>45.77</u>
<u>1435</u>	<u>1.06</u>	<u>-105.5</u>	<u>7.02</u>	<u>22.18</u>	<u>8021</u>	<u>45.77</u>
<u>1440</u>	<u>0.96</u>	<u>-110.5</u>	<u>7.03</u>	<u>22.13</u>	<u>8028</u>	<u>45.75</u>
<u>1445</u>	<u>0.90</u>	<u>-113.5</u>	<u>6.95</u>	<u>22.02</u>	<u>80.40</u>	<u>45.75</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BVBR 1/2H6</u>	<u>1445</u>	_____	_____
<u>TP#2</u>	<u>6</u>	_____	_____
<u>Ch. Hdr C, TDS</u>	<u>7</u>	_____	_____
<u>Drip Meas</u>	_____	_____	_____

COMMENTS: Slightly Silty / light green / Strong Oclar < 1/2 set

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 22.48 x 0.80 = -- (Total Depth of Well) 50.39

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/7/09 WELL NO. mnw1046

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: 1.413 Reading: 8.91 pH Standard: 7 Reading: 7.10 Standard 4 Reading: 4.08

Standard 10 Reading: 10.14 ; ORP: Standard: 240 Reading: 240.1 DO: T°C: 13.67 mmHg: 9.51 DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.33 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 66.73 FT.
- D. Height of Water Column in casing (h = TD - SWL): 19.40 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1017

OBSERVATIONS: Purging Start Time: 1017

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1022</u>	<u>1.44</u>	<u>-121.7</u>	<u>6.96</u>	<u>20.90</u>	<u>3169</u>	<u>47.34</u>
<u>1027</u>	<u>0.71</u>	<u>-138.4</u>	<u>6.98</u>	<u>20.96</u>	<u>3166</u>	<u>47.36</u>
<u>1032</u>	<u>0.50</u>	<u>-146.5</u>	<u>6.99</u>	<u>20.99</u>	<u>3164</u>	<u>47.37</u>
<u>1037</u>	<u>0.40</u>	<u>-150.1</u>	<u>6.99</u>	<u>21.04</u>	<u>3165</u>	<u>47.38</u>
<u>1042</u>	<u>0.36</u>	<u>-152.2</u>	<u>6.98</u>	<u>21.00</u>	<u>3170</u>	<u>47.35</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Diss. Metals</u>	<u>1042</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>Hex Cr / TDS</u>	<u>1042</u>	<u>1000 mL 1</u>	<u>-</u>
<u>BTEX / TPH-GRD</u>	<u>1042</u>	<u>40 mL 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1042</u>	<u>1000 mL 2</u>	<u>HCl</u>

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 19.40 x 0.80 = -- (Total Depth of Well) 51.21

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/7/09 WELL NO. MW036

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: _____

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.18 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 61.83 FT.
D. Height of Water Column in casing (h = TD - SWL): 15.65 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1117

OBSERVATIONS: Purging Start Time: 1117

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1122	0.50	-109.5	6.93	20.98	1598	46.24
1127	0.43	-108.2	6.87	20.99	1690	46.22
1132	0.44	-103.7	6.84	20.98	1780	46.24
1137	0.50	-102.4	6.81	21.01	1907	46.23
1142	0.59	-99.0	6.81	20.99	2030	46.23
1147	0.64	-95.5	6.80	21.01	2132	46.23
1152	0.76	-94.5	6.80	21.03	2257	46.23
1157	0.80	-92.6	6.85	20.99	2347	46.17
1202	0.91	-88.4	6.77	20.86	2391	46.24
1207	1.00	-87.5	6.79	20.87	2460	46.24

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Diss Metals	1207	500 ml 1	HNO3
Hex Cr/TDS	1207	1000 ml 1	-
BTEX / TPH-GRO	1207	400 ml 3	HCL
COMMENTS: TPH-DRO	1207	1000 ml 2	HCL

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft
8-inch hole.....2.60 gal/in ft
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 15.65 x 0.80 = 12.52 (Total Depth of Well) 49.31

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/7/09 WELL NO. mw038

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 45.73 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 61.70 FT.
 D. Height of Water Column in casing (h = TD - SWL): 15.97 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1330

OBSERVATIONS: Purging Start Time: 1330

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1335</u>	<u>0.81</u>	<u>-13.2</u>	<u>6.92</u>	<u>21.28</u>	<u>3393</u>	<u>45.21</u>
<u>1340</u>	<u>0.52</u>	<u>2.1</u>	<u>6.91</u>	<u>21.34</u>	<u>3150</u>	<u>45.73</u>
<u>1345</u>	<u>0.36</u>	<u>10.7</u>	<u>6.89</u>	<u>21.24</u>	<u>3011</u>	<u>45.73</u>
<u>1350</u>	<u>0.25</u>	<u>17.7</u>	<u>6.89</u>	<u>21.27</u>	<u>2927</u>	<u>45.75</u>
<u>1355</u>	<u>0.24</u>	<u>22.7</u>	<u>6.88</u>	<u>21.27</u>	<u>2885</u>	<u>45.73</u>
<u>1400</u>	<u>0.20</u>	<u>25.9</u>	<u>6.89</u>	<u>21.22</u>	<u>2863</u>	<u>45.72</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Diss Metals</u>	<u>1400</u>	<u>500 ml</u>	<u>HNO3</u>
<u>Hex Cr / TDS</u>	<u>1400</u>	<u>1000 ml</u>	<u> </u>
<u>BTEX / TPH-GRO</u>	<u>1400</u>	<u>40 ml</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DKO</u>	<u>1400</u>	<u>1000 ml</u>	<u>Hcl</u>

Using Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft
 8-inch hole.....2.60 gal/lin ft
 10-inch hole.....4.10 gal/lin ft

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 15.97 x 0.80 = -- (Total Depth of Well) 45.92

Signature:

Lancaster Laboratories
Where quality is a science.

For Lancaster Laboratories use only

Acct. #: _____ Sample #: _____

006197

SCR#:

Sample #:

Acct. #:

Facility #: E 06000 X-1000 Case: PMA-21321135

Site Address: 1000 X-1000, MEX. 10

Chevron PM: J. Flomay Lead Consultant: C. Vignell

Consultant/Office: Sanger. Houston

Consultant Prj. Mgr.: Darryl W. Adams, C

Consultant Phone #: 713.937.7473 Fax #: 713.983.8328

Sampler: SBS/JS

Service Order #: _____ ☐ Non SAR: _____

Service Order #: ☐ Non SAR: _____☐ Non SAR:[illegible][illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, P.O. Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the



Where quality is a science.

For Lancaster Laboratories use only

Acct. #:

Sample #:

SCR#:

007470


[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300

Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

3566 Rev. 1/31/02

004497



For Lancaster Laboratories use only

SCR#:

Sample #:

Acct. #:-

Where quality is a science.

[illegible]

Lancaster Laboratories, Inc., 2425-New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

3566 Rev. 1/31/02

004498



Lancaster Laboratories

Where quality is a science.

For Lancaster Laboratories use only

Sample #:

Acct. #:

SCR#:

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

3566 Rev: 1/31/02

Chevron Generic Analysis Request/Chain of Custody



004500

For Lancaster Laboratories use only
Acct. # _____ Sample # _____ SCR# _____

Facility #: <u>Enbridge North Gas Plant - D12201135</u> Site Address: <u>Enbridge, New Mexico</u> Chevron PM: <u>J. Hower</u> Lead Consultant: <u>C. Vowles</u> Consultant/Office: <u>Santa Fe, New Mexico</u> Consultant Proj. Mgr.: <u>D. Woodward</u> Consultant Phone #: <u>713-437-9973</u> Fax #: <u>713-783-8328</u> Sampler: <u>S.B. JZ</u> Service Order #: _____ ☐ Non SAR: _____				Analyses Requested <table border="1"> <tr> <th colspan="4">Preservation Codes</th> </tr> <tr> <th>H</th> <th>H</th> <th>H</th> <th>H</th> </tr> <tr> <td>8260 full scan</td> <td>Oxygenates</td> <td>TPH G 70</td> <td>TPH D 70</td> </tr> <tr> <td>TPH D 70</td> <td>Extended Ring</td> <td>Silica Gel Cleanup</td> <td>Lead Total</td> </tr> <tr> <td colspan="4"> ☐ Diss. ☐ Method ☐ quantification </td> </tr> <tr> <td colspan="4"> ☐ NMT/TPH HClID ☐ quantification </td> </tr> <tr> <td colspan="4"> ☐ VP/EPH </td> </tr> </table>				Preservation Codes				H	H	H	H	8260 full scan	Oxygenates	TPH G 70	TPH D 70	TPH D 70	Extended Ring	Silica Gel Cleanup	Lead Total	☐ Diss. ☐ Method ☐ quantification				☐ NMT/TPH HClID ☐ quantification				☐ VP/EPH			
Preservation Codes																																			
H	H	H	H																																
8260 full scan	Oxygenates	TPH G 70	TPH D 70																																
TPH D 70	Extended Ring	Silica Gel Cleanup	Lead Total																																
☐ Diss. ☐ Method ☐ quantification																																			
☐ NMT/TPH HClID ☐ quantification																																			
☐ VP/EPH																																			
Matrix <table border="1"> <tr> <td>Soil</td> <td>Water</td> <td>Oil</td> <td>Air</td> </tr> <tr> <td>☒</td> <td>☒</td> <td>☐</td> <td>☐</td> </tr> <tr> <td>☐</td> <td>☐</td> <td>☐</td> <td>☐</td> </tr> <tr> <td>☐</td> <td>☐</td> <td>☐</td> <td>☐</td> </tr> </table>				Soil	Water	Oil	Air	☒	☒	☐	☐	☐	☐	☐	☐	☐	☐	☐	☐	Preservative Codes H = HCl T = Thiosulfate N = HNO ₃ B = NaOH S = H ₂ SO ₄ O = Other ☐ J value reporting needed ☐ Must meet lowest detection limits possible for 8260 compounds 8021 MTBE Confirmation ☐ Confirm MTBE + Naphthalene ☐ Confirm highest hit by 8260 ☐ Confirm all hits by 8260 ☐ Run ____ oxy's on highest hit ☐ Run ____ oxy's on all hits															
Soil	Water	Oil	Air																																
☒	☒	☐	☐																																
☐	☐	☐	☐																																
☐	☐	☐	☐																																
Comments/Remarks All times O.P. Certified + no zone				Comments/Remarks All times O.P. Certified + no zone																															
Turnaround Time Requested (TAT) (please circle) 24 hour ☐ 72 hour ☐ 48 hour ☐ 5 day ☐				Data Package Options (please circle if required) QC Summary ☐ Type I - Full ☐ Type VI (Raw Data) ☐ Disk / EDD ☐ WIP (RWQCB) ☐ Standard Format ☐ Disk ☐ Other: _____																															
Relinquished by: <u>John Bell</u> Date: <u>3/20/09</u> Time: <u>1750</u>				Received by: _____ Date: _____ Time: _____																															
Relinquished by: _____ Date: _____ Time: _____				Received by: _____ Date: _____ Time: _____																															
Relinquished by: _____ Date: _____ Time: _____				Received by: _____ Date: _____ Time: _____																															
Relinquished by Commercial Carrier: UPS ☐ FedEx ☐ Other ☐				Relinquished by: _____ Date: _____ Time: _____																															
Temperature Upon Receipt _____ C°				Custody Seals Intact? Yes ☐ No ☐																															

 Lancaster Laboratories
Where quality is a science.

For Lancaster Laboratories use only

004499

SCR#:

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories
Where quality is a science.

SCR#: 008891
4365

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories
Where quality is a science.

Acct. #:-

SCR#:

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Chevron Generic Analysis Request/Chain of Custody

008868



For Lancaster Laboratories use only


SCR#:

Sample #:

Acct. #:

Facility #				Site Address				Chevron PM				Consultant/Office				Consultant Prj. Mgr.				Consultant Phone				Sampler				Service Order #				Non SAR							
Enbridge Health Gas Plant - 212201135				Enbridge, New Mexico				D. Hamer				Lead Consultant: C. Vaneil				Stanley - Houston				D. Woodward				713.437-7973				Fax # 713.437.8328				SB, JP							
Sample Identification				Date Collected				Time Collected				Grab				Composite																							
MW013A				3.30.09				0955				✓																											
MW014				3.30.09				1058				✓																											
MW032				3.30.09				1213				✓																											
MW004A				3.30.09				1443				✓																											
DUP 104				3.30.09				---				✓																											
T.O.P. Blank												✓																											
Turnaround Time Requested (TAT) (please circle)				24 hour				72 hour				48 hour				5 day																							
Data Package Options (please circle if required)				QC Summary				Type I - Full				Type VI (Raw Data)				Disk / EDD				Standard Format				WIP (RWQCB)				Disk											
Relinquished by:				Relinquished by:				Relinquished by:				Relinquished by:				Relinquished by:				Relinquished by:				Relinquished by:				Relinquished by:											
Date				Time				Date				Time				Date				Time				Date				Time											
3/30/09				10:35				3/30/09				10:35				3/30/09				10:35				3/30/09				10:35											
Received by:				Received by:				Received by:				Received by:				Received by:				Received by:				Received by:				Received by:											
Date				Time				Date				Time				Date				Time				Date				Time											
3/30/09				10:35				3/30/09				10:35				3/30/09				10:35				3/30/09				10:35											
Custody Seals Intact?				Yes				No																															

Chevron Generic Analysis Request/Chain of Custody



For Lancaster Laboratories use only

Acct. #: _____ Sample #: _____

SCR#: _____

Facility #: Enviros North Gas Plant 212201135
 Site Address: Enviros, New Mexico
 Chevron PM: James Lead Consultant: A. Vowell
 Consultant/Office: Stantec Houston
 Consultant Proj. Mgr.: D. Widdowid
 Consultant Phone #: 713.437.7973 Fax #: 713.437.8328
 Sampler: SB/DP
 Service Order #: _____ ☐ Non SAR:

Analyses Requested				Matrix		Total Number of Containers		Preservation Codes		Preservative Codes	
Sample Identification	Date Collected	Time Collected	Grab	Composite	Soil	Water	Oil	Air	TPH GRP	TPH DR	Extended Rng.
MMW002A	3-31-09	0045	✓			✓			✓		
MMW002	3-31-09	1031	✓			✓			✓		
MMW046A	3-31-09	1115	✓			✓			✓		
MMW042A	3-31-09	1306	✓			✓			✓		
MMW059	3-31-09	1419	✓			✓			✓		
MMW023	3-31-09	1500	✓			✓			✓		
MMW004	3-31-09	1545	✓			✓			✓		
Dup #105	3-31-09	—	✓			✓			✓		
TUP Blanks	3-31-09	—	✓			✓			✓		

Turnaround Time Requested (TAT) (please circle)	Relinquished by:	Date	Time	Received by:	Date	Time
STD TAT 24 hour	<u>[Signature]</u>	3/31/09	1250			
72 hour						
48 hour						
5 day						

Data Package Options (please circle if required)	Relinquished by:	Date	Time	Received by:	Date	Time
QC Summary	<u>[Signature]</u>	3/31/09	1746			
Type VI (Raw Data)						
WIP (RWQCB)						
Disk						

Temperature Upon Receipt	C°	UPS	FedEx	Other	Relinquished by Commercial Carrier:	Received by:	Date	Time

Custody Seals Intact?	Yes	No

Comments / Remarks
* Field + 1419 for Dissolved Metals
All Times are Central Time Zone

 Lancaster Laboratories
Where quality is a science.

SCR#:

3566 Rev. 1/31/02

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories
Where quality is a science.

Lancaster Laboratories
Where quality is a science.

For Lancaster Laboratories use only
Sample #: _____

Acct. #:

Sample #:

SCR#:

009280

 **Lancaster Laboratories**
Where quality is a science.

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425 Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.



Where quality is a science.

Lancaster Laboratories

For Lancaster Laboratories use only

Sample #:

Acct. #:-

SCR#:

009279

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

3566 Rev. 1/31/02

 Lancaster Laboratories
Where quality is a science.

008757
1633

Where quality is a science:

Facility #: Enviro North Gas Plant 212201135 Site Address: Enviro, New Mexico Chevron PM: J. Homer Lead Consultant: C. Vowell Consultant/Office: Stanlec Houston Consultant Prj. Mgr.: D. Woodward Consultant Phone #: 713-9377973 Fax #: 713-987-8328 Sampler: SB JI Service Order #: _____ ☐ Non SAR: _____				Matrix <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%;"> ☐ Potable ☐ NPDES </td> <td style="width:33%;"> ☐ Water ☐ Oil ☐ Air </td> <td style="width:33%;"> ☐ Total Number of Containers </td> </tr> </table>				☐ Potable ☐ NPDES	☐ Water ☐ Oil ☐ Air	☐ Total Number of Containers																																																					
☐ Potable ☐ NPDES	☐ Water ☐ Oil ☐ Air	☐ Total Number of Containers																																																													
Analyses Requested <table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th style="width:10%;">Preservation Codes</th> <th style="width:10%;">Time</th> <th style="width:10%;">Date</th> <th style="width:10%;">Received by:</th> <th style="width:10%;">Time</th> <th style="width:10%;">Date</th> <th style="width:10%;">Received by:</th> <th style="width:10%;">Time</th> </tr> <tr> <td>TPH G</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>TPH D ☐ Extended Rng.</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>TPH D ☐ Slice Gel Cleanup</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>Lead Total ☐ Diss. ☐ Method</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>VPH/EPH</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>NWTPH HClID ☐ quantification</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>				Preservation Codes	Time	Date	Received by:	Time	Date	Received by:	Time	TPH G								TPH D ☐ Extended Rng.								TPH D ☐ Slice Gel Cleanup								Lead Total ☐ Diss. ☐ Method								VPH/EPH								NWTPH HClID ☐ quantification								Preservative Codes H = HCl T = Thiosulfate N = HNO ₃ B = NaOH S = H ₂ SO ₄ O = Other ☐ J value reporting needed ☐ Must meet lowest detection limits possible for 8260 compounds 8021 MTBE Confirmation ☐ Confirm MTBE + Naphthalene ☐ Confirm highest hit by 8260 ☐ Confirm all hits by 8260 ☐ Run ____ oxy's on highest hit. ☐ Run ____ oxy's on all hits			
Preservation Codes	Time	Date	Received by:	Time	Date	Received by:	Time																																																								
TPH G																																																															
TPH D ☐ Extended Rng.																																																															
TPH D ☐ Slice Gel Cleanup																																																															
Lead Total ☐ Diss. ☐ Method																																																															
VPH/EPH																																																															
NWTPH HClID ☐ quantification																																																															
Comments/Remarks Not at ABR - 10 Field H ₂ He Please Lab 5. Hr for Dissolved Metals All time 9:11 Corral time Zone																																																															

Relinquished by: <i>[Signature]</i> Date: 6/14/07 Time: 08:57		Relinquished by: <i>[Signature]</i> Date: 4/18/09 Time: 11:00	
Relinquished by: <i>[Signature]</i> Date: 5/20/09 Time: 11:00		Relinquished by: <i>[Signature]</i> Date: 5/20/09 Time: 11:00	
Relinquished by Commercial Carrier: UPS FedEx Other _____ Temperature Upon Receipt _____ C°			

Turnaround Time Requested (TAT) (please circle) STD. TAT 72 hour 48 hour 24 hour 4 day 5 day			
Data Package Options (please circle if required) QC Summary Type I - Full Type VI (Raw Data) Disk / EDD WIP (RWQCB) Standard Format Disk Other _____			

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

GROUNDWATER FIELD LOG
EUNICE NORTH GAS PLANT
FIRST HALF 2009

ORDER	GRUNDFOS WELL ID #	DATE	TIME	DEPTH TO WATER (ft.)	TOTAL WELL DEPTH (ft.)	PSH THICKNESS (ft.)
1	LORDWW	3/10/2009	10:11	40.61	70.00	
2	MW014A	3/10/2009	10:15	42.33	105.56	
3	MW016A	3/10/2009	10:23	38.75	91.36	
4	MW018A	3/10/2009	10:34	36.29	84.45	
5	MW019A	3/10/2009	11:17	36.74	74.81	
6	MW020A	3/10/2009	11:23	42.85	83.70	
7	MW022A	3/10/2009	11:29	51.09	123.83	
8	MW023A	3/10/2009	11:35	55.22	123.30	
9	MW026	3/10/2009	12:42	50.25	66.11	
10	MW029	3/10/2009	12:48	65.97	81.01	
11	MW030	3/10/2009	12:52	59.25	77.68	
12	MW040A	3/10/2009	12:59	41.96	109.80	
13	MW053SA	3/10/2009	13:06	41.60	71.40	
14	MW057SA	3/10/2009	13:15	45.58	73.72	
15	MW060	3/10/2009	13:25	66.55	102.17	
16	MW067SA	3/10/2009	13:33	46.81	88.31	
17	MW068	3/10/2009	13:42	56.94	112.35	
18	MW070	3/10/2009	13:51	59.11	95.87	
19	MW070A	3/10/2009	13:52	59.11	127.20	
20	MW072SA	3/10/2009	14:04	50.44	97.83	
21	MW073SA	3/10/2009	14:08	47.89	71.21	
22	MW074SA	3/10/2009	14:13	48.18	70.09	
23	MW075SA	3/10/2009	14:18	50.93	69.18	
24	MW076SA	3/10/2009	14:21	52.61	98.15	
25	MW078SA	3/10/2009	14:31	43.47	71.81	
26	WOODELLWW	3/10/2009	---	---	---	
27	MW015	3/10/2009	14:37	39.11	54.10	
28	MW020	3/10/2009	11:24	42.67	62.06	
29	MW018	3/10/2009	10:38	36.59	55.35	
30	MW043	3/10/2009	14:43	45.85	67.58	
31	MW069	3/10/2009	14:50	52.99	112.35	
32	MW028	3/10/2009	14:59	70.70	85.09	
33	MW031	3/10/2009	15:03	59.86	77.02	
34	MW071SA	3/10/2009	15:14	49.92	95.72	
35	MW035	3/10/2009	15:21	48.45	65.36	
36	MW021	3/10/2009	15:25	45.60	62.20	
37	MW025	3/10/2009	15:30	51.12	62.72	
38	MW045	3/10/2009	15:37	46.16	66.29	
39	MW015A	3/10/2009	14:38	39.05	109.12	
40	MW007	3/10/2009	15:43	47.78	68.22	
41	EPWW1	3/10/2009	---	---	---	
42	MW032	3/10/2009	15:55	60.82	68.80	

ORDER	GRUNDFOS WELL ID #	DATE	TIME	DEPTH TO WATER (ft.)	TOTAL WELL DEPTH (ft.)	PSH THICKNESS (ft.)
43	MW013A	3/10/2009	16:01	43.05	106.10	
44	MW066SA	3/10/2009	16:07	49.00	72.02	
45	MW021A	3/10/2009	15:24	46.28	87.74	
46	MW002	3/11/2009	10:01	51.94	68.59	
47	MW077SA	3/11/2009	10:15	50.71	98.45	
48	MW065SA	3/11/2009	10:19	51.52	85.71	
49	MW024A	3/11/2009	10:46	51.15	101.48	
50	MW034	3/11/2009	10:56	41.86	65.25	
51	MW047	3/11/2009	Unable to Access- Demo		66.58	
52	MW010	3/11/2009	11:14	39.16	64.64	
53	MW049SA	3/11/2009	11:18	47.95	88.12	
54	MW002A	3/11/2009	10:02	51.89	103.28	
55	MW086SA	3/11/2009	11:29	50.91	97.80	
56	MW059	3/11/2009	11:37	61.33	106.41	
57	MW024	3/11/2009	10:45	51.69	89.16	
58	MW055SA	3/11/2009	11:44	40.79	54.70	
59	MW054SA	3/11/2009	12:46	44.74	61.90	
60	MW042A	3/11/2009	12:53	46.15	99.10	
61	MW048SA	3/11/2009	11:20	45.02	88.42	
62	MW004A	3/11/2009	12:55	44.54	103.70	
63	MW003	3/11/2009	12:59	47.73	70.51	
64	MW050SA	3/11/2009	13:06	44.78	83.78	
65	MW039A	3/11/2009	13:10	55.14	119.23	
66	MW014	3/11/2009	13:16	42.69	60.88	
67	MW007A	3/11/2009	13:25	47.64	106.50	
68	MW052SA	3/11/2009	13:30	44.54	68.15	
69	MW056SA	3/11/2009	13:35	44.92	56.80	
70	MW046A	3/11/2009	11:08	46.78	107.72	
71	MW041A	3/11/2009	11:16	41.70	91.08	
72	MW023	3/11/2009	11:23	55.55	69.11	
73	MW058	3/11/2009	11:32	56.52	111.32	
74	MW013	3/11/2009	11:46	43.19	80.13	
75	MW051SA	3/11/2009	12:37	43.48	69.05	
76	MW004	3/11/2009	12:56	44.33	66.50	
77	MW061	3/11/2009	13:05	58.59	110.69	
78	MW062A	3/11/2009	13:15	55.39	110.71	
79	MW063A	3/11/2009	13:21	56.02	108.56	
80	MW033	3/11/2009	13:35	47.19	63.02	
81	ROWLANDWW	3/11/2009	13:45	39.69	58.00	

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/16/09 WELL NO. MW0-745A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: SUNNY

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: 1.413 Reading: 1064 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 10.00 : ORP: Standard: 240 Reading: 240 DO: T°C: 11.28 mmHg: 9.80 DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.18 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 76.09 FT.
 D. Height of Water Column in casing (h = TD - SWL): 21.91 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0955

OBSERVATIONS: Purging Start Time: 0955

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1005</u>	<u>5.82</u>	<u>234.3</u>	<u>7.00</u>	<u>19.65</u>	<u>2327</u>	<u>48.97</u>
<u>1010</u>	<u>5.37</u>	<u>230.8</u>	<u>7.01</u>	<u>19.83</u>	<u>2334</u>	<u>48.99</u>
<u>1015</u>	<u>5.25</u>	<u>228.9</u>	<u>6.90</u>	<u>19.93</u>	<u>2338</u>	<u>49.02</u>
<u>1020</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1015</u>	<u>1000 mL 1</u>	<u>—</u>
<u>Diss. Metals</u>	<u>1015</u>	<u>500 mL 1</u>	<u>H/NO3</u>
<u>BTEX / TPH-GRO</u>	<u>1015</u>	<u>40 mL 3</u>	<u>HCL</u>
COMMENTS: <u>TPH-DRO</u>	<u>1015</u>	<u>1000 mL 2</u>	<u>HCL</u>
<u>195 H2</u>			

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft
 8-inch hole.....2.60 gal/lin ft
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 21.91 x 0.80 = -- (Total Depth of Well) 52.56

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/16/09 WELL NO. MWO-75SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: SUNNY

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.93 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 69.18 FT.
 D. Height of Water Column in casing (h = TD - SWL): 18.25 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1033

OBSERVATIONS: Purging Start Time: 1033

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1043</u>	<u>5.50</u>	<u>223.1</u>	<u>7.02</u>	<u>20.12</u>	<u>26.59</u>	<u>51.98</u>
<u>1048</u>	<u>5.33</u>	<u>219.3</u>	<u>7.01</u>	<u>20.31</u>	<u>2732</u>	<u>52.00</u>
<u>1053</u>	<u>5.32</u>	<u>216.0</u>	<u>7.00</u>	<u>20.37</u>	<u>2746</u>	<u>52.01</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1053</u>	<u>1000 mL 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1053</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1053</u>	<u>40 mL 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1053</u>	<u>1000 mL 2</u>	<u>HCl</u>
<u>195 Hz</u>			

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 18.25 x 0.80 = -- (Total Depth of Well) 54.58

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/16/09 WELL NO. MWO-76 SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 52.61 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 98.15 FT.
- D. Height of Water Column in casing (h = TD - SWL): 45.54 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1105

OBSERVATIONS: Purging Start Time: 1105

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct (±3%)	SWL
<u>1115</u>	<u>5.03</u>	<u>206.8</u>	<u>7.06</u>	<u>20.37</u>	<u>2380</u>	<u>52.81</u>
<u>1120</u>	<u>4.88</u>	<u>202.8</u>	<u>7.07</u>	<u>20.55</u>	<u>2530</u>	<u>52.81</u>
<u>1125</u>	<u>4.84</u>	<u>197.2</u>	<u>7.07</u>	<u>20.62</u>	<u>2543</u>	<u>52.82</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1125</u>	<u>1000 ml</u> <u>1</u>	<u>—</u>
<u>Diss. Metals</u>	<u>1125</u>	<u>500 ml</u> <u>1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1125</u>	<u>40 ml</u> <u>3</u>	<u>Hcl</u>
COMMENTS: <u>TPH-DRO</u>	<u>1125</u>	<u>1000 ml</u> <u>2</u>	<u>Hcl</u>
	<u>195 Hz</u>		

Using Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 45.54 x 0.80 = -- (Total Depth of Well) 61.71

Signature: _____

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/16/09 WELL NO. MW0-70

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 59.11 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 95.87 FT.
- D. Height of Water Column in casing (h = TD - SWL): 36.76 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 13/5

OBSERVATIONS: Purging Start Time: 13/5

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1325</u>	<u>6.00</u>	<u>152.7</u>	<u>7.1P</u>	<u>21.96</u>	<u>1236</u>	<u>59.50</u>
<u>1330</u>	<u>5.89</u>	<u>151.3</u>	<u>7.20</u>	<u>21.93</u>	<u>1233</u>	<u>59.50</u>
<u>1335</u>	<u>5.93</u>	<u>152.9</u>	<u>7.20</u>	<u>21.93</u>	<u>1235</u>	<u>59.50</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1335</u>	<u>1000 mL 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1335</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1335</u>	<u>40 mL 3</u>	<u>HCL</u>
<u>COMMENTS: TPH-DRO</u>	<u>1335</u>	<u>1000 mL 2</u>	<u>HCL</u>
<u>195 Hk</u>			

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft
- 8-inch hole.....2.60 gal/lin ft
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 36.76 x 0.80 = -- (Total Depth of Well) 66.46

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/16/09 WELL NO. MW0-70A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 59.11 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 127.20 FT.
 D. Height of Water Column in casing (h = TD - SWL): 68.09 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1350

OBSERVATIONS: Purging Start Time: 1350

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1400</u>	<u>5.39</u>	<u>148.0</u>	<u>7.80</u>	<u>22.27</u>	<u>695</u>	<u>63.85</u>
<u>1405</u>	<u>5.36</u>	<u>138.1</u>	<u>7.92</u>	<u>24.23</u>	<u>736</u>	<u>63.48</u>
<u>1410</u>	<u>5.25</u>	<u>140.2</u>	<u>7.83</u>	<u>23.65</u>	<u>732</u>	<u>63.94</u>
<u>1415</u>	<u>4.98</u>	<u>139.2</u>	<u>7.84</u>	<u>24.17</u>	<u>737</u>	<u>63.97</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1415</u>	<u>1000 ml</u>	<u> </u>
<u>Diss. Metals</u>	<u>1415</u>	<u>500 ml</u>	<u>1</u>
<u>BTEX / TPH-GRO</u>	<u>1415</u>	<u>40 ml</u>	<u>3</u>
<u>COMMENTS: TPH-DRO</u>	<u>1415</u>	<u>1000 ml</u>	<u>2</u>
<u>195 H₂</u>			

Sing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 68.09 x 0.80 = (Total Depth of Well) 72.72

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/16/09 WELL NO. MW0-30

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 59.25 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 77.68 FT.
 D. Height of Water Column in casing (h = TD - SWL): 18.43 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1439

OBSERVATIONS: Purging Start Time: 1439

	Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
	<u>1449</u>	<u>5.91</u>	<u>143.9</u>	<u>7.39</u>	<u>22.19</u>	<u>1115</u>	<u>60.37</u>
	<u>1454</u>	<u>5.71</u>	<u>144.0</u>	<u>7.33</u>	<u>22.09</u>	<u>1265</u>	<u>60.41</u>
	<u>1459</u>	<u>5.60</u>	<u>142.5</u>	<u>7.30</u>	<u>21.99</u>	<u>1319</u>	<u>60.42</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex C</u>	<u>1459</u>	<u>1000 ml 1</u>	<u>—</u>
<u>Diss. Metals</u>	<u>1459</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRV</u>	<u>1459</u>	<u>40 ml 3</u>	<u>HCL</u>
<u>COMMENTS: TPH-DRG</u>	<u>1459</u>	<u>1000 ml 2</u>	<u>HCL</u>
	<u>195 Hz</u>		

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 18.43 x 0.80 = -- (Total Depth of Well) 62.93

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/16/09 WELL NO. MWO-29

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 65.97 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 81.01 FT.
- D. Height of Water Column in casing (h = TD - SWL): 15.04 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1520

OBSERVATIONS: Purging Start Time: 1520

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct (±3%)	SWL
<u>1530</u>	<u>6.77</u>	<u>143.5</u>	<u>7.41</u>	<u>21.84</u>	<u>942</u>	<u>67.27</u>
<u>1535</u>	<u>6.74</u>	<u>147.8</u>	<u>7.42</u>	<u>21.69</u>	<u>945</u>	<u>67.27</u>
<u>1540</u>	<u>6.81</u>	<u>141.5</u>	<u>7.42</u>	<u>21.62</u>	<u>947</u>	<u>67.28</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1540</u>	<u>1000 mL</u>	<u> </u>
<u>Diss. Metals</u>	<u>1540</u>	<u>500 mL</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1540</u>	<u>40 mL</u>	<u>HCL</u>
<u>COMMENTS: TPH-DRO</u>	<u>1540</u>	<u>1000 mL</u>	<u>HCL</u>

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 15.04 x 0.80 = (Total Depth of Well) 68.97

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/17/09 WELL NO. MW0-72SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: 1.413 Reading: 1.159 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 9.99 ORP: Standard: 240 Reading: 240 DO: T°C: 13.86 mmHg: 9.79 DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.44 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 97.83 FT.
 D. Height of Water Column in casing (h = TD - SWL): 47.39 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0843

OBSERVATIONS: Purging Start Time: 0843

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>0853</u>	<u>3.44</u>	<u>205.0</u>	<u>7.06</u>	<u>19.20</u>	<u>1715</u>	<u>50.53</u>
<u>0858</u>	<u>2.76</u>	<u>202.1</u>	<u>7.06</u>	<u>19.51</u>	<u>1723</u>	<u>50.83</u>
<u>0903</u>	<u>2.64</u>	<u>199.8</u>	<u>7.06</u>	<u>19.68</u>	<u>1721</u>	<u>50.53</u>
<u>0908</u>	<u>2.83</u>	<u>197.7</u>	<u>7.07</u>	<u>19.65</u>	<u>1740</u>	<u>50.53</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>0908</u>	<u>1000 mL 1</u>	<u>—</u>
<u>Diss. Metals</u>	<u>0908</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>0908</u>	<u>40 mL 3</u>	<u>HCL</u>
<u>COMMENTS: TPH-DRO</u>	<u>0908</u>	<u>1000 mL 2</u>	<u>HCL</u>
<u>195 H2</u>			

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 47.39 x 0.80 = — (Total Depth of Well) 59.91

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/17/09 WELL NO. MWO-73SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.89 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 71.21 FT.
 D. Height of Water Column in casing (h = TD - SWL): 23.32 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0936

OBSERVATIONS: Purging Start Time: 0936

	Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct (±3%)	SWL
	<u>0946</u>	<u>1.41</u>	<u>165.9</u>	<u>7.00</u>	<u>20.00</u>	<u>1604</u>	<u>48.66</u>
	<u>0951</u>	<u>1.21</u>	<u>156.7</u>	<u>7.00</u>	<u>20.10</u>	<u>1610</u>	<u>48.67</u>
	<u>0956</u>	<u>1.13</u>	<u>151.1</u>	<u>7.00</u>	<u>20.44</u>	<u>1611</u>	<u>48.68</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>0956</u>	<u>1000 ml 1</u>	<u>—</u>
<u>Diss. Metals</u>	<u>0956</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>0956</u>	<u>40 ml 3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>0956</u>	<u>1000 ml 2</u>	<u>Hcl</u>

195 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 23.32 x 0.80 = -- (Total Depth of Well) 52.55

Signature: [Signature]

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/12/09 WELL NO. MW0-575A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 45.58 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 73.72 FT.
- D. Height of Water Column in casing (h = TD - SWL): 28.14 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1015

OBSERVATIONS: Purging Start Time: 1015

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1025</u>	<u>5.49</u>	<u>152.8</u>	<u>7.00</u>	<u>19.61</u>	<u>1905</u>	<u>46.28</u>
<u>1030</u>	<u>5.52</u>	<u>148.5</u>	<u>7.02</u>	<u>19.67</u>	<u>1877</u>	<u>46.29</u>
<u>1035</u>	<u>5.49</u>	<u>146.4</u>	<u>7.06</u>	<u>19.71</u>	<u>1913</u>	<u>46.29</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1035</u>	<u>1000 mL 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1035</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1035</u>	<u>40 mL 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1035</u>	<u>1000 mL 2</u>	<u>HCl</u>

195 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 28.14 x 0.80 = (Total Depth of Well) 51.20

Signature: [Signature]

Dup #100

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/17/09 WELL NO. MWD-40A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 61 °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 41.96 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 109.80 FT.
- D. Height of Water Column in casing (h = TD - SWL): 67.84 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1050

OBSERVATIONS:

Purging Start Time: 1050

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL	
1100	4.60	132.3	7.65	20.42	672	50.55	
1105	4.85	133.8	7.59	20.57	678	52.33	
1110	5.23	148.9	7.50	20.74	684	53.02	
1115	5.41	143.5	7.60	20.82	688	53.43	
1120	5.53	149.0	7.63	20.76	722	53.64	

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Hex Cr	1120	1000 mL 1	—
Diss. Metals	1120	500 mL 1	HNO3
BTEX / TPH-GR0	1120	40 mL 3	HCl
COMMENTS: TPH-DR0	1120	1000 mL 2	HCl

198 H2

DUP # 100

Using Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 67.84 x 0.80 = -- (Total Depth of Well) 55.52

Signature: _____

8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/17/09 WELL NO. MWO-16A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: _____

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 38.75 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 91.36 FT.

D. Height of Water Column in casing (h = TD - SWL): 52.61 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1250

OBSERVATIONS: Purging Start Time: 1250

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1300</u>	<u>5.06</u>	<u>157.7</u>	<u>7.32</u>	<u>21.59</u>	<u>1540</u>	<u>42.98</u>
<u>1305</u>	<u>5.04</u>	<u>165.5</u>	<u>7.32</u>	<u>21.73</u>	<u>1644</u>	<u>43.39</u>
<u>1310</u>	<u>5.13</u>	<u>164.7</u>	<u>7.27</u>	<u>21.76</u>	<u>1669</u>	<u>43.68</u>
<u>1315</u>	<u>5.19</u>	<u>657.1</u>	<u>7.35</u>	<u>21.75</u>	<u>1763</u>	<u>43.83</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1315</u>	<u>1000 mL 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1315</u>	<u>500 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRD</u>	<u>1315</u>	<u>40 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1315</u>	<u>1000 2</u>	<u>HCl</u>

1P2 H2

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 52.61 x 0.80 = (Total Depth of Well) 49.27

Signature:

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/17/09 WELL NO. MWO-18A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 36.29 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 84.45 FT.
- D. Height of Water Column in casing (h = TD - SWL): 48.16 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1330

OBSERVATIONS: Purging Start Time: 1330

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1340</u>	<u>4.63</u>	<u>153.5</u>	<u>7.85</u>	<u>21.96</u>	<u>1397</u>	<u>43.46</u>
<u>1345</u>	<u>4.57</u>	<u>149.6</u>	<u>7.86</u>	<u>22.33</u>	<u>1438</u>	<u>44.00</u>
<u>1350</u>	<u>4.62</u>	<u>154.1</u>	<u>7.34</u>	<u>22.41</u>	<u>1449</u>	<u>44.23</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1350</u>	<u>1000 mL 1</u>	<u>-</u>
<u>Diss. Metals</u>	<u>1350</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1350</u>	<u>40 mL 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-D20</u>	<u>1350</u>	<u>1000 mL 2</u>	<u>HCl</u>

170 Hz

- Casing Capacities:
- 2-inch hole.....0.16 gal/lin ft.
 - 4-inch hole.....0.65 gal/lin ft.
 - 6.5-inch hole.....1.70 gal/lin ft
 - 8-inch hole.....2.60 gal/lin ft
 - 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
Collect sample when Depth to Water measures Less than or equal to:
Original Water Column: 48.16 x 0.80 = -- (Total Depth of Well) 45.92

Signature: [Signature] 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/12/09 WELL NO. MW0-19A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:

Standard 10 Reading: ORP: Standard: Reading: DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 36.74 FT.
 B. Thickness of Free Product, if present: Inches FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 74.81 FT.
 D. Height of Water Column in casing (h = TD - SWL): 38.07 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1457

OBSERVATIONS: Purging Start Time: 1457

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1507	4.98	167.2	7.13	22.31	1707	41.36
1512	4.95	153.2	7.26	22.47	1735	41.65
1517	4.89	148.7	7.18	22.61	1763	41.75
1522	4.86	149.3	7.19	22.58	1776	41.81

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Hex Cr	1522	1000 mL 2	-
Diss. Metals	1522	500 mL 1	HNO3
BTEX / TPH - GRO	1522	40 mL 3	HCL
COMMENTS: TPH - DRD	1522	1000 mL 2	HCL

165 Hz


Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 38.07 x 0.80 = -- (Total Depth of Well) 44.35

Signature: 

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3-18-09 WELL NO. MW0-23A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 51 °F

FIELD PERSONNEL: SB/JI WEATHER: _____

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 55.22 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 123.30 FT.
 D. Height of Water Column in casing (h = TD - SWL): 68.08 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 0901

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct(±3%)	SWL
<u>0911</u>	<u>5.01</u>	<u>200.4</u>	<u>7.77</u>	<u>19.29</u>	<u>695</u>	<u>60.43</u>
<u>0916</u>	<u>4.82</u>	<u>198.4</u>	<u>7.76</u>	<u>19.77</u>	<u>705</u>	<u>60.58</u>
<u>0921</u>	<u>4.77</u>	<u>196.6</u>	<u>7.75</u>	<u>19.99</u>	<u>705</u>	<u>60.41</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>0921</u>	<u>1000 mL 1</u>	<u> </u>
<u>Diss. Metals</u>		<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 mL 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-PRO</u>		<u>1000 mL 2</u>	<u>HCl</u>

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 68.08 x 0.80 = Total Depth of Well) 68.83

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. MWO-14A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 52 °F

FIELD PERSONNEL: SB/JI WEATHER: Calm, sunny, clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 42.33 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 105.56 FT.
 D. Height of Water Column in casing (h = TD - SWL): 63.23 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 0950

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1000	9.21	116.6	7.70	20.27	695	54.51
1005	4.52	177.2	7.69	20.60	700	54.57
1010	4.54	179.4	7.69	20.84	702	54.56
1015	4.56	180.1	7.69	21.05	700	54.53

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Hex Cr	1015	1000 mL 1	-
Diss. Metals		500 mL 1	HNO3
BTEX / TPH-GRO		40 mL 3	Hcl
COMMENTS: TPH-DRO		1000 mL 2	Hcl

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 63.23 x 0.80 = 50.58 (Total Depth of Well) 54.97

Signature: [Signature]

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. MW0-68

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 55 °F

FIELD PERSONNEL: SB/JI WEATHER: Calm, clear, sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 66.94 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 112.35 FT.
- D. Height of Water Column in casing (h = TD - SWL): 55.41 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: _____

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>10481053</u>	<u>.40</u>	<u>62.6</u>	<u>7.25</u>	<u>20.94</u>	<u>2744</u>	<u>67.60</u>
<u>11031058</u>	<u>.31</u>	<u>47.4</u>	<u>7.14</u>	<u>20.91</u>	<u>4723</u>	<u>67.58</u>
<u>11081103</u>	<u>.71</u>	<u>53.7</u>	<u>7.13</u>	<u>21.12</u>	<u>3503</u>	<u>67.58</u>
<u>1108</u>	<u>1.40</u>	<u>62.2</u>	<u>7.16</u>	<u>21.17</u>	<u>3460</u>	<u>67.59</u>
<u>1113</u>	<u>1.87</u>	<u>69.6</u>	<u>7.17</u>	<u>21.21</u>	<u>3480</u>	<u>67.59</u>
<u>1118</u>	<u>1.98</u>	<u>76.4</u>	<u>7.16</u>	<u>21.21</u>	<u>3497</u>	<u>67.59</u>
<u>1123</u>	<u>1.95</u>	<u>82.0</u>	<u>7.16</u>	<u>21.20</u>	<u>3533</u>	<u>67.59</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1123</u>	<u>1000 mL 1</u>	<u> </u>
<u>Diss. Metals</u>		<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 mL 3</u>	<u>HCl</u>
COMMENTS: <u>TPH-DAO</u>		<u>1000 mL 2</u>	<u>HCl</u>

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 55.41 x 0.80 = (Total Depth of Well) 76.02

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. MW0-60
 FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 70 °F
 FIELD PERSONNEL: SB/JI WEATHER: clear, calm, sunny
EQUIPMENT CALIBRATION: YSI QED Serial No.: _____
 Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____
 Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____
 End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 56.55 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 102.17 FT.
 D. Height of Water Column in casing ($h = TD - SWL$): 45.62 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1248

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1258 1208</u>	<u>.83</u>	<u>-143.1</u>	<u>7.07</u>	<u>22.01</u>	<u>5124</u>	<u>57.19</u>
<u>1313 1303</u>	<u>.19</u>	<u>-147.3</u>	<u>7.07</u>	<u>22.08</u>	<u>5171</u>	<u>57.19</u>
<u>1318 1308</u>	<u>.15</u>	<u>-147.6</u>	<u>7.04</u>	<u>22.07</u>	<u>5163</u>	<u>57.19</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1308</u>	<u>1000 mL 1</u>	<u>-</u>
<u>Diss. Metals</u>		<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 mL 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>		<u>1000 mL 2</u>	<u>HCl</u>

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 45.62 x 0.80 = -- (Total Depth of Well) 65.67

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. MW0-22A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 74 °F

FIELD PERSONNEL: SB/JI WEATHER: Calm, clear, sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 51.09 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 123.83 FT.

D. Height of Water Column in casing (h = TD - SWL): 72.74 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1334

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1344</u>	<u>9.18</u>	<u>35.6</u>	<u>7.40</u>	<u>21.63</u>	<u>660</u>	<u>58.19</u>
<u>1349</u>	<u>4.76</u>	<u>59.3</u>	<u>7.38</u>	<u>21.57</u>	<u>663</u>	<u>58.36</u>
<u>1354</u>	<u>4.85</u>	<u>59.7</u>	<u>7.37</u>	<u>21.55</u>	<u>664</u>	<u>58.44</u>
<u>1359</u>	<u>4.91</u>	<u>64.9</u>	<u>7.37</u>	<u>21.48</u>	<u>663</u>	<u>58.48</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex C</u>	<u>1359</u>	<u>1000 mL 2</u>	<u> </u>
<u>Diss Metals</u>		<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX/TPH-GRO</u>		<u>40 mL 3</u>	<u>HCl</u>
COMMENTS: <u>TPH-DRO</u>		<u>1000 mL 2</u>	<u>HCl</u>

Using Capacities:

2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 72.74 x 0.80 = (Total Depth of Well) 65.63

Signature: [Signature]

8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. MWD-7PSA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 78 °F

FIELD PERSONNEL: SB/JI WEATHER: Calm, clear, sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 43.47 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 78.81 FT.
D. Height of Water Column in casing (h = TD - SWL): 35.34 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1423

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1433</u>	<u>1.74</u>	<u>81.7</u>	<u>7.21</u>	<u>21.16</u>	<u>1277</u>	<u>44.55</u>
<u>1438</u>	<u>1.70</u>	<u>78.1</u>	<u>7.23</u>	<u>21.13</u>	<u>1283</u>	<u>44.56</u>
<u>1443</u>	<u>1.66</u>	<u>76.7</u>	<u>7.24</u>	<u>21.20</u>	<u>1296</u>	<u>44.56</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1443</u>	<u>1000 ml 1</u>	<u> </u>
<u>Diss. Metals</u>		<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 ml 3</u>	<u>Hcl</u>
COMMENTS: <u>TPH-DRO</u>		<u>1000 ml 2</u>	<u>Hcl</u>

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 35.34 x 0.80 = (Total Depth of Well) 50.53

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/18/09 WELL NO. MWO-53 SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 77 °F

FIELD PERSONNEL: SB/JI WEATHER: Calm, clear, sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH: Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 41.60 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 71.40 FT.
D. Height of Water Column in casing (h = TD - SWL): 29.80 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1504

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1514</u>	<u>5.14</u>	<u>99.2</u>	<u>7.28</u>	<u>21.54</u>	<u>1517</u>	<u>42.88</u>
<u>1519</u>	<u>5.15</u>	<u>97.9</u>	<u>7.29</u>	<u>21.49</u>	<u>1466</u>	<u>42.91</u>
<u>1524</u>	<u>5.11</u>	<u>98.4</u>	<u>7.29</u>	<u>21.59</u>	<u>1455</u>	<u>42.92</u>
<u>1529</u>	<u>5.11</u>	<u>98.5</u>	<u>7.29</u>	<u>21.41</u>	<u>1453</u>	<u>42.92</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1529</u>	<u>1000 mL 1</u>	<u>-</u>
<u>Diss. Metals</u>		<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 mL 3</u>	<u>HCL</u>
<u>COMMENTS: TPH-DRO</u>		<u>1000 mL 2</u>	<u>HCL</u>

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 29.80 x 0.80 = -- (Total Depth of Well) 47.56

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. LOD-WW
FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 44 °F
FIELD PERSONNEL: SB/JI WEATHER: SUNNY

EQUIPMENT CALIBRATION:

YSI

QED

Serial No.: _____

Spec. Conductivity: Standard: 1,413 Reading: 1,233 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 4.02

Standard 10 Reading: 9.99 ; ORP: Standard: 240 Reading: 240 ; DO: T°C: 16.06 mmHg: 9.10 DO Conc.: _____

End-of-Day Recheck: Spec. Cond.: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 40.61 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 70.00 FT.
D. Height of Water Column in casing (h = TD - SWL): 29.39 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0847

OBSERVATIONS:

Purging Start Time: 0847

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>0857</u>	<u>0.22</u>	<u>-271.9</u>	<u>8.18</u>	<u>18.39</u>	<u>5039</u>	<u>42.75</u>
<u>0902</u>	<u>0.16</u>	<u>-259.2</u>	<u>7.90</u>	<u>18.45</u>	<u>5000</u>	<u>43.07</u>
<u>0907</u>	<u>0.13</u>	<u>-256.3</u>	<u>7.86</u>	<u>18.44</u>	<u>4971</u>	<u>43.17</u>
<u>0912</u>	<u>0.11</u>	<u>-250.3</u>	<u>7.79</u>	<u>18.40</u>	<u>4943</u>	<u>43.27</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>0912</u>	<u>1000 ml 1</u>	<u>-</u>
<u>Diss. Metals</u>	<u>0912</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>ISTEX / TPH-GRO</u>	<u>0912</u>	<u>40 ml 3</u>	<u>HCl</u>
COMMENTS: <u>TPH-DRO</u>	<u>0912</u>	<u>1000 ml 2</u>	<u>Hcl</u>

173 Hz

Lining Capacities:

2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft
8-inch hole.....2.60 gal/in ft
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 29.39 x 0.80 = -- (Total Depth of Well) 4648

Signature: [Signature]

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 01 APR 2009 WELL NO. 10A2WW

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 58 °F

FIELD PERSONNEL: SB/JP WEATHER: CLC 672

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 40.61 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 70.00 FT.

D. Height of Water Column in casing (h = TD - SWL): 29.39 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 0931

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>0941</u>	<u>0.38</u>	<u>-148.4</u>	<u>7.16</u>	<u>19.12</u>	<u>5651</u>	<u>43.74</u>
<u>0946</u>	<u>0.20</u>	<u>-140.7</u>	<u>7.08</u>	<u>19.29</u>	<u>5827</u>	<u>43.93</u>
<u>0951</u>	<u>0.41</u>	<u>-130.9</u>	<u>7.07</u>	<u>19.48</u>	<u>5882</u>	<u>43.90</u>
<u>0956</u>	<u>0.83</u>	<u>-109.2</u>	<u>7.04</u>	<u>19.55</u>	<u>5873</u>	<u>43.89</u>
<u>1001</u>	<u>1.02</u>	<u>-101.0</u>	<u>7.05</u>	<u>19.56</u>	<u>5862</u>	<u>43.88</u>
<u>1006</u>	<u>1.20</u>	<u>-90.0</u>	<u>7.03</u>	<u>19.61</u>	<u>5854</u>	<u>43.88</u>
<u>1011</u>	<u>1.26</u>	<u>-92.3</u>	<u>7.05</u>	<u>19.70</u>	<u>5857</u>	<u>43.88</u>
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
_____	<u>1011</u>	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

COMMENTS:

Re-Sample for TDS only

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 29.39 x 0.80 = -- (Total Depth of Well) 46.49

Signature: Alto Self

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. MW020A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 44 °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 42.85 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 83.70 FT.

D. Height of Water Column in casing (h = TD - SWL): 40.85 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0930

OBSERVATIONS: Purging Start Time: 0930

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>0940</u>	<u>4.40</u>	<u>45.7</u>	<u>7.04</u>	<u>19.44</u>	<u>3678</u>	<u>46.69</u>
<u>0945</u>	<u>4.40</u>	<u>54.9</u>	<u>7.02</u>	<u>19.53</u>	<u>3825</u>	<u>46.94</u>
<u>0950</u>	<u>4.42</u>	<u>58.8</u>	<u>7.01</u>	<u>19.57</u>	<u>3806</u>	<u>46.99</u>
<u>0955</u>	<u>4.42</u>	<u>62.9</u>	<u>7.01</u>	<u>19.67</u>	<u>3797</u>	<u>46.99</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>0955</u>	<u>1000 ml 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>0955</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>0955</u>	<u>40 ml 3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>0955</u>	<u>1000 ml 2</u>	<u>Hcl</u>

184.00 H2

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft
8-inch hole.....2.60 gal/lin ft
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 40.85 x 0.80 = (Total Depth of Well) 51.02

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. MW0-20

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 42.67 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 62.06 FT.

D. Height of Water Column in casing (h = TD - SWL): 19.39 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1007

OBSERVATIONS: Purging Start Time: 1007

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1017</u>	<u>4.88</u>	<u>72.2</u>	<u>6.98</u>	<u>19.68</u>	<u>3226</u>	<u>44.65</u>
<u>1022</u>	<u>4.77</u>	<u>72.5</u>	<u>6.96</u>	<u>19.72</u>	<u>3334</u>	<u>44.69</u>
<u>1027</u>	<u>4.73</u>	<u>74.4</u>	<u>6.96</u>	<u>19.85</u>	<u>3374</u>	<u>44.72</u>
<u>1032</u>	<u>4.69</u>	<u>75.0</u>	<u>6.96</u>	<u>19.86</u>	<u>3399</u>	<u>44.74</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1032</u>	<u>1000 ml 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1032</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1032</u>	<u>40 ml 3</u>	<u>HCL</u>
COMMENTS: <u>TPH-DRO</u>	<u>1032</u>	<u>1000 ml 2</u>	<u>HCL</u>

17800 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 19.39 x 0.80 = (Total Depth of Well) 46.54

Signature: [Signature]

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. MWD-67SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 45.81 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 88.31 FT.

D. Height of Water Column in casing (h = TD - SWL): 42.50 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1050

OBSERVATIONS: Purging Start Time: 1050

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1100</u>	<u>4.28</u>	<u>66.8</u>	<u>7.16</u>	<u>19.19</u>	<u>1604</u>	<u>46.36</u>
<u>1105</u>	<u>4.24</u>	<u>63.5</u>	<u>7.16</u>	<u>20.25</u>	<u>1605</u>	<u>46.36</u>
<u>1110</u>	<u>4.22</u>	<u>63.4</u>	<u>7.15</u>	<u>20.69</u>	<u>1611</u>	<u>46.37</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1110</u>	<u>1000 mL</u>	<u>1</u>
<u>Diss. Metals</u>	<u>1110</u>	<u>500 mL</u>	<u>1</u>
<u>BTEX / TPH-GRO</u>	<u>1110</u>	<u>40 mL</u>	<u>3</u>
COMMENTS: <u>TPH-DRO</u>	<u>1110</u>	<u>1000 mL</u>	<u>2</u>

195.00 H2

Using Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 42.50 x 0.80 = — (Total Depth of Well) 54.31

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. MW018

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 36.59 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 55.35 FT.
- D. Height of Water Column in casing (h = TD - SWL): 18.76 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 11:27

OBSERVATIONS: Purging Start Time: 11:27

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>11:37</u>	<u>6.01</u>	<u>82.9</u>	<u>7.13</u>	<u>19.83</u>	<u>1797</u>	<u>37.62</u>
<u>11:42</u>	<u>5.99</u>	<u>82.0</u>	<u>7.12</u>	<u>19.91</u>	<u>1824</u>	<u>37.63</u>
<u>11:47</u>	<u>5.97</u>	<u>81.8</u>	<u>7.11</u>	<u>20.05</u>	<u>1844</u>	<u>37.63</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>11:47</u>	<u>1000 ml</u>	<u>✓</u>
<u>Diss. Metals</u>	<u>11:47</u>	<u>500 ml</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>11:47</u>	<u>40 ml</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>11:47</u>	<u>1000 ml</u>	<u>Hcl</u>

195 Hz

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 18.76 x 0.80 = 15.01 (Total Depth of Well) 40.34

Signature: [Signature]

8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. MWO-15

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 39.11 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 54.10 FT.

D. Height of Water Column in casing (h = TD - SWL): 14.99 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1309

OBSERVATIONS: Purging Start Time: 1309

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1219</u>	<u>5.32</u>	<u>116.3</u>	<u>6.82</u>	<u>20.24</u>	<u>6272</u>	<u>40.44</u>
<u>1324</u>	<u>5.30</u>	<u>111.7</u>	<u>6.80</u>	<u>20.21</u>	<u>6451</u>	<u>40.45</u>
<u>1329</u>	<u>5.27</u>	<u>110.9</u>	<u>6.79</u>	<u>20.29</u>	<u>6571</u>	<u>40.47</u>
<u>1334</u>	<u>5.24</u>	<u>111.3</u>	<u>6.79</u>	<u>20.25</u>	<u>6606</u>	<u>40.47</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1334</u>	<u>1000 ml 1</u>	<u>—</u>
<u>Diss. Metals</u>	<u>1334</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-Gro</u>	<u>1334</u>	<u>40 ml 3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1334</u>	<u>1000 ml 2</u>	<u>Hcl</u>

195 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 14.99 x 0.80 = -- (Total Depth of Well) 42.10

Signature: _____

Stantec

Dup # 101

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. MW015A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: ; pH Standard: 7 Reading: ; Standard 4 Reading:

Standard 10 Reading: ; ORP: Standard: Reading: ; DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: ; pH 7: ; pH 4: ; pH: 10 ; ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 39.05 FT.
 B. Thickness of Free Product, if present: Inches FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 109.12 FT.
 D. Height of Water Column in casing (h = TD - SWL): 70.07 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1346

OBSERVATIONS: Purging Start Time: 1346

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1356	3.11	114.3	7.01	21.27	5407	45.00
1401	2.96	115.4	7.01	21.99	5511	45.05
1406	2.87	118.0	7.01	22.70	5604	45.07

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Hex Cr	1406	1000 mL 1	—
Disc. Metals	1406	500 mL 1	HNO3
BTEX / TPH-GRO	1406	40 mL 3	HCl
COMMENTS: TPH-DRO	1406	1000 mL 2	HCl

160 Hz Dup # 101

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 70.07 x 0.80 = — (Total Depth of Well) 53.06

Signature: 

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. MW025

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.12 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 62.72 FT.
- D. Height of Water Column in casing (h = TD - SWL): 11.60 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1426

OBSERVATIONS:

Purging Start Time: 1426

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1436</u>	<u>1.58</u>	<u>115.9</u>	<u>6.83</u>	<u>21.37</u>	<u>2243</u>	<u>52.01</u>
<u>1441</u>	<u>1.55</u>	<u>112.7</u>	<u>6.80</u>	<u>21.44</u>	<u>2381</u>	<u>52.03</u>
<u>1446</u>	<u>1.21</u>	<u>105.8</u>	<u>6.84</u>	<u>21.52</u>	<u>2443</u>	<u>52.03</u>
<u>1451</u>	<u>1.10</u>	<u>102.1</u>	<u>6.83</u>	<u>21.53</u>	<u>2479</u>	<u>52.03</u>
<u>1456</u>	<u>1.10</u>	<u>107.3</u>	<u>6.76</u>	<u>21.50</u>	<u>2460</u>	<u>52.03</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1456</u>	<u>1000 ml 1</u>	<u> </u>
<u>Dist. Metals</u>	<u>1456</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1456</u>	<u>40 ml 3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1456</u>	<u>1000 ml 2</u>	<u>Hcl</u>

190 Hz

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 11.60 x 0.80 = -- (Total Depth of Well) 53.44

Signature: _____

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/19/09 WELL NO. MW028

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: SUNNY

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 70.70 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 85.09 FT.
- D. Height of Water Column in casing (h = TD - SWL): 14.39 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1520

OBSERVATIONS: Purging Start Time: 1520

	Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
	<u>1530</u>	<u>3.75</u>	<u>121.9</u>	<u>7.41</u>	<u>22.51</u>	<u>1980</u>	<u>71.98</u>
	<u>1535</u>	<u>2.98</u>	<u>116.9</u>	<u>7.42</u>	<u>23.27</u>	<u>2148</u>	<u>72.06</u>
	<u>1540</u>	<u>2.28</u>	<u>110.0</u>	<u>7.47</u>	<u>23.49</u>	<u>2219</u>	<u>72.06</u>
	<u>1545</u>	<u>1.87</u>	<u>103.9</u>	<u>7.44</u>	<u>23.48</u>	<u>2237</u>	<u>72.08</u>
	<u>1550</u>	<u>1.98</u>	<u>100.9</u>	<u>7.46</u>	<u>23.49</u>	<u>2200</u>	<u>72.12</u>
	<u>1555</u>	<u>1.78</u>	<u>96.1</u>	<u>7.44</u>	<u>23.50</u>	<u>2240</u>	<u>72.14</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1555</u>	<u>1000 ml</u>	<u>1</u>
<u>Diss. Metals</u>	<u>1555</u>	<u>500 ml</u>	<u>1</u>
<u>BTEX / TPH-GRO</u>	<u>1555</u>	<u>40 ml</u>	<u>3</u>
<u>COMMENTS: TPH-DRO</u>	<u>1555</u>	<u>1000 ml</u>	<u>2</u>

197 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 14.39 x 0.80 = -- (Total Depth of Well) 73.57

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. MW045

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: 1.413 Reading: 1.252 ; pH Standard: 7 Reading 7.00 ; Standard 4 Reading: 4.01

Standard 10 Reading: 10.00 ; ORP: Standard: 240 Reading: 240 ; DO: T°C: 15.61 mmHg: 8.93 DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 46.16 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 66.29 FT.

D. Height of Water Column in casing (h = TD - SWL): 20.13 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0906

OBSERVATIONS: Purging Start Time: 0906

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>0916</u>	<u>1.03</u>	<u>-0.1</u>	<u>6.70</u>	<u>20.17</u>	<u>1739</u>	<u>47.22</u>
<u>0921</u>	<u>0.49</u>	<u>-16.0</u>	<u>6.68</u>	<u>20.35</u>	<u>1752</u>	<u>47.25</u>
<u>0926</u>	<u>0.33</u>	<u>-22.8</u>	<u>6.71</u>	<u>20.45</u>	<u>1787</u>	<u>47.27</u>
<u>0931</u>	<u>0.25</u>	<u>-22.9</u>	<u>6.70</u>	<u>20.42</u>	<u>1809</u>	<u>47.27</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>0931</u>	<u>1000 ml</u> <u>1</u>	<u> </u>
<u>Dist. Metals</u>	<u>0931</u>	<u>500 ml</u> <u>1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>0931</u>	<u>40 ml</u> <u>3</u>	<u>HCL</u>
<u>COMMENTS: TPH-DRO</u>	<u>0931</u>	<u>1000 ml</u> <u>2</u>	<u>HCL</u>

195 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 20.13 x 0.80 = (Total Depth of Well) 50.18

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. MW035

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.45 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 65.36 FT.
 D. Height of Water Column in casing (h = TD - SWL): 16.91 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0945

OBSERVATIONS: Purging Start Time: 0945

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>0955</u>	<u>0.78</u>	<u>94.1</u>	<u>6.65</u>	<u>20.69</u>	<u>1791</u>	<u>49.47</u>
<u>0000</u>	<u>0.68</u>	<u>120.1</u>	<u>6.55</u>	<u>20.71</u>	<u>1803</u>	<u>49.47</u>
<u>1005</u>	<u>0.58</u>	<u>135.4</u>	<u>6.55</u>	<u>20.76</u>	<u>1803</u>	<u>49.49</u>
<u>1010</u>	<u>0.51</u>	<u>125.7</u>	<u>6.62</u>	<u>20.74</u>	<u>1810</u>	<u>49.50</u>
<u>1015</u>	<u>0.50</u>	<u>129.9</u>	<u>6.62</u>	<u>20.78</u>	<u>1805</u>	<u>49.50</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hea Cr</u>	<u>1015</u>	<u>1000 mL 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1015</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX/TPH-GRO</u>	<u>1015</u>	<u>40 mL 3</u>	<u>Hcl</u>
COMMENTS: <u>TPH-DRO</u>	<u>1015</u>	<u>1000 mL 2</u>	<u>Hcl</u>

190 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 16.91 x 0.80 = (Total Depth of Well) 51.83

Signature: _____

8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. MW 043

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: SUNNY

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 45.85 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 67.58 FT.
D. Height of Water Column in casing (h = TD - SWL): 21.73 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1029

OBSERVATIONS: Purging Start Time: 1029

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1039</u>	<u>0.36</u>	<u>127.7</u>	<u>6.78</u>	<u>20.08</u>	<u>1889</u>	<u>46.83</u>
<u>1044</u>	<u>0.28</u>	<u>57.3</u>	<u>7.01</u>	<u>20.09</u>	<u>2020</u>	<u>46.84</u>
<u>1049</u>	<u>0.21</u>	<u>47.3</u>	<u>7.00</u>	<u>20.15</u>	<u>2060</u>	<u>46.85</u>
<u>1054</u>	<u>0.17</u>	<u>44.9</u>	<u>7.01</u>	<u>20.17</u>	<u>2082</u>	<u>46.85</u>
<u>1059</u>	<u>0.14</u>	<u>45.3</u>	<u>7.00</u>	<u>20.24</u>	<u>2108</u>	<u>46.85</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1059</u>	<u>1000 ml</u>	<u> </u>
<u>Diss. Metals</u>	<u>1059</u>	<u>500 ml</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1059</u>	<u>40 ml</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1059</u>	<u>1000 ml</u>	<u>Hcl</u>

190 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 21.73 x 0.80 = (Total Depth of Well) 50.19

Signature: _____

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. MW 031

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 59.86 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 77.02 FT.
- D. Height of Water Column in casing (h = TD - SWL): 17.16 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1120

OBSERVATIONS: Purging Start Time: 1120

	Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct (±3%)	SWL
	<u>1130</u>	<u>0.50</u>	<u>-9.9</u>	<u>6.97</u>	<u>20.53</u>	<u>1029</u>	<u>60.57</u>
	<u>1135</u>	<u>0.33</u>	<u>-48.7</u>	<u>7.02</u>	<u>20.72</u>	<u>1017</u>	<u>60.57</u>
	<u>1140</u>	<u>0.19</u>	<u>-67.9</u>	<u>7.02</u>	<u>20.70</u>	<u>1015</u>	<u>60.58</u>
	<u>1145</u>	<u>0.13</u>	<u>-78.8</u>	<u>7.05</u>	<u>20.76</u>	<u>1009</u>	<u>60.58</u>
	<u>1150</u>	<u>0.10</u>	<u>-81.3</u>	<u>7.05</u>	<u>20.74</u>	<u>1009</u>	<u>60.59</u>
	<u>1155</u>	<u>0.08</u>	<u>-80.2</u>	<u>7.06</u>	<u>20.81</u>	<u>1008</u>	<u>60.59</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1155</u>	<u>1000 ml</u>	<u>1</u>
<u>Diss. Metals</u>	<u>1155</u>	<u>500 ml</u>	<u>1</u>
<u>BTEX / TPH-GRO</u>	<u>1155</u>	<u>40 ml</u>	<u>3</u>
COMMENTS: <u>TPH-DRO</u>	<u>1155</u>	<u>1000 ml</u>	<u>2</u>

190 Hz

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 17.16 x 0.80 = -- (Total Depth of Well) 63.29

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. MW 021A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.28 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 87.74 FT.
 D. Height of Water Column in casing (h = TD - SWL): 41.46 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1313

OBSERVATIONS: Purging Start Time: 1313

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1323</u>	<u>0.51</u>	<u>115.0</u>	<u>6.70</u>	<u>21.06</u>	<u>13,298</u>	<u>50.52</u>
<u>1328</u>	<u>0.40</u>	<u>109.6</u>	<u>6.66</u>	<u>21.24</u>	<u>15,543</u>	<u>50.59</u>
<u>1333</u>	<u>0.37</u>	<u>107.8</u>	<u>6.65</u>	<u>21.35</u>	<u>16,244</u>	<u>50.64</u>
<u>1338</u>	<u>0.33</u>	<u>107.3</u>	<u>6.65</u>	<u>21.47</u>	<u>16,519</u>	<u>50.67</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1338</u>	<u>1000 ml</u>	<u>1</u>
<u>Diss. Metals</u>	<u>1338</u>	<u>500 ml</u>	<u>1</u>
<u>BTEX / TPH-GRO</u>	<u>1338</u>	<u>40 ml</u>	<u>3</u>
<u>COMMENTS: TPH-DRO</u>	<u>1338</u>	<u>1000 ml</u>	<u>2</u>

170 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 41.46 x 0.80 = -- (Total Depth of Well) 54.57

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. MW021

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 45.60 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 62.20 FT.
 D. Height of Water Column in casing (h = TD - SWL): 16.60 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1351

OBSERVATIONS: Purging Start Time: 1351

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1401</u>	<u>0.51</u>	<u>104.5</u>	<u>7.01</u>	<u>21.05</u>	<u>1551</u>	<u>46.41</u>
<u>1406</u>	<u>0.35</u>	<u>102.7</u>	<u>7.01</u>	<u>21.13</u>	<u>1798</u>	<u>46.42</u>
<u>1411</u>	<u>0.28</u>	<u>102.5</u>	<u>7.01</u>	<u>21.17</u>	<u>1934</u>	<u>46.43</u>
<u>1416</u>	<u>0.29</u>	<u>101.8</u>	<u>7.02</u>	<u>21.14</u>	<u>2014</u>	<u>46.44</u>
<u>1421</u>	<u>0.22</u>	<u>103.7</u>	<u>6.99</u>	<u>21.20</u>	<u>2093</u>	<u>46.44</u>
<u>1426</u>	<u>0.17</u>	<u>102.9</u>	<u>7.02</u>	<u>21.21</u>	<u>2135</u>	<u>46.44</u>
<u>1431</u>	<u>0.15</u>	<u>103.7</u>	<u>7.01</u>	<u>21.23</u>	<u>2155</u>	<u>46.44</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1431</u>	<u>1000 mL</u>	<u> </u>
<u>Diss. Metals</u>	<u>1431</u>	<u>500 mL</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1431</u>	<u>40 mL</u>	<u>HCL</u>
<u>COMMENTS: TPH-DRO</u>	<u>1431</u>	<u>1000 mL</u>	<u>HCL</u>

170 Hz

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 16.60 x 0.80 = (Total Depth of Well) 48.92

Signature: _____

8/2008

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. Woodell WW

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: °F

FIELD PERSONNEL: SB/JI WEATHER: SUNNY

EQUIPMENT CALIBRATION: (YSI) QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____; ORP: Standard: _____ Reading: _____; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec.Cond: ;pH 7: ;pH 4: ;pH: 10 ;ORP:

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: _____ FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: _____ FT.

D. Height of Water Column in casing ($h = TD - SWL$): _____ FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: _____

[illegible]

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Hex Cr	1445	1000 ml 1	—
Diss. Metals	1445	500 ml 1	HNO3
BTEX / TPH-GRO	1445	40 ml 3	HCl
COMMENTS: TPH-DRO	1445	1000 ml 2	HCl
Pumping Well		No Parameters	

Increasing Capacities:

2-inch hole.....0.16 gal/min ft. .

4-inch hole.....0.65 gal/in ft.

6.5-inch hole.....1.70 gal/lin ft

8-inch hole.....2.60 gal/lin ft

10-inch hole.....4.10 gal/lin. ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: _____ x 0.80 = ____ (Total Depth of Well) _____

Signature: 

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/24/09 WELL NO. MWD 71 SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 49.92 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 95.72 FT.
 D. Height of Water Column in casing (h = TD - SWL): 45.80 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1503

OBSERVATIONS: Purging Start Time: 1503

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1513</u>	<u>0.40</u>	<u>101.1</u>	<u>6.62</u>	<u>20.70</u>	<u>3731</u>	<u>49.99</u>
<u>1518</u>	<u>0.26</u>	<u>99.9</u>	<u>6.71</u>	<u>20.68</u>	<u>3802</u>	<u>49.99</u>
<u>1523</u>	<u>0.18</u>	<u>106.2</u>	<u>6.70</u>	<u>20.72</u>	<u>3856</u>	<u>49.99</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1523</u>	<u>1000 ml 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1523</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1523</u>	<u>40 ml 3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1523</u>	<u>1000 ml 2</u>	<u>Hcl</u>

200 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 45.80 x 0.80 = -- (Total Depth of Well) 59.08

Signature: [Signature]

Dup #102

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/25/09 WELL NO. MW024

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 48 °F

FIELD PERSONNEL: SB/JI WEATHER: Cloudy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 06F1362 AB

Spec. Conductivity: Standard: 1.4/3 Reading: 1.221 pH Standard: 7 Reading 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 9.99 ; ORP: Standard: 240 Reading: 240 ; DO: T°C: 12.50 mmHg: 9.21 DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH: 10 :ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.69 FT.
- B. Thickness of Free Product, if present: Inches FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 89.16 FT.
- D. Height of Water Column in casing (h = TD - SWL): 37.47 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0845

OBSERVATIONS: Purging Start Time: 0845

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
0855	1.48	219.5	6.95	19.58	2640	52.18
0900	1.27	215.7	6.95	19.61	2658	52.20
0905	1.07	212.0	6.93	19.51	2658	52.23
0910	0.85	207.5	6.93	19.64	2669	52.23
0915	0.66	204.2	6.93	19.65	2674	52.25
0920	0.50	200.2	6.93	19.70	2682	52.25

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Hex Cr	0920	1000 ml 2	
Diss. Metals	0920	500 ml 1	HNO3
BTEX / TPH-GRO	0920	40 ml 3	HCl
COMMENTS: TPH-DRO	0920	1000 ml 2	HCl

Dup #102 205 Hz

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft
- 8-inch hole.....2.60 gal/in ft
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 37.47 x 0.80 = (Total Depth of Well) 59.18

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/25/09 WELL NO. MW024A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 48 °F

FIELD PERSONNEL: SB/JI WEATHER: cloudy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH 10: _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.15 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 101.48 FT.
- D. Height of Water Column in casing (h = TD - SWL): 50.33 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0935

OBSERVATIONS: Purging Start Time: 0935

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>0945</u>	<u>3.96</u>	<u>189.9</u>	<u>7.26</u>	<u>18.55</u>	<u>2135</u>	<u>54.38</u>
<u>0950</u>	<u>3.92</u>	<u>188.3</u>	<u>7.26</u>	<u>19.44</u>	<u>2180</u>	<u>54.83</u>
<u>0955</u>	<u>3.81</u>	<u>186.7</u>	<u>7.27</u>	<u>19.67</u>	<u>2145</u>	<u>54.94</u>
<u>1000</u>	<u>3.91</u>	<u>186.1</u>	<u>7.28</u>	<u>19.65</u>	<u>2111</u>	<u>54.97</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1000</u>	<u>1000 ml 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1000</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1000</u>	<u>40 ml 3</u>	<u>HCL</u>
<u>COMMENTS: TPH-DRO</u>	<u>1000</u>	<u>1000 ml 2</u>	<u>HCL</u>

175 Hz

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 50.33 x 0.80 = (Total Depth of Well) 61.21

Signature: _____

8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/25/09 WELL NO. MW0505A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 58 °F

FIELD PERSONNEL: SB/JI WEATHER: cloudy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.78 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 83.78 FT.
D. Height of Water Column in casing (h = TD - SWL): 39.00 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1015

OBSERVATIONS: Purging Start Time: 1015

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1025</u>	<u>0.68</u>	<u>191.6</u>	<u>6.89</u>	<u>19.62</u>	<u>5271</u>	<u>46.00</u>
<u>1030</u>	<u>0.72</u>	<u>179.4</u>	<u>6.90</u>	<u>19.71</u>	<u>5362</u>	<u>46.02</u>
<u>1035</u>	<u>0.64</u>	<u>168.5</u>	<u>6.89</u>	<u>19.75</u>	<u>5541</u>	<u>46.03</u>
<u>1040</u>	<u>0.60</u>	<u>159.6</u>	<u>6.90</u>	<u>19.70</u>	<u>5648</u>	<u>46.04</u>
<u>1045</u>	<u>0.59</u>	<u>152.2</u>	<u>6.87</u>	<u>19.71</u>	<u>5730</u>	<u>46.05</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1045</u>	<u>1000 mL 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1045</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1045</u>	<u>40 mL 3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1045</u>	<u>1000 mL 2</u>	<u>Hcl</u>

190 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft
8-inch hole.....2.60 gal/lin ft
10-inch hole.....4.10 gal/lin ft

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 39.00 x 0.80 = (Total Depth of Well) 52.58

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/25/09 WELL NO. MW 034

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 58 °F

FIELD PERSONNEL: SB/JI WEATHER: cloudy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 41.86 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 65.25 FT.
- D. Height of Water Column in casing (h = TD - SWL): 23.39 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1058

OBSERVATIONS: Purging Start Time: 1058

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1108</u>	<u>3.23</u>	<u>133.5</u>	<u>7.11</u>	<u>20.16</u>	<u>2073</u>	<u>42.77</u>
<u>1113</u>	<u>3.16</u>	<u>134.7</u>	<u>7.02</u>	<u>20.31</u>	<u>2082</u>	<u>42.78</u>
<u>1118</u>	<u>3.14</u>	<u>129.1</u>	<u>7.06</u>	<u>20.36</u>	<u>2087</u>	<u>42.78</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1118</u>	<u>1000 mL 2</u>	<u> </u>
<u>Diss Metals</u>	<u>1118</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1118</u>	<u>40 mL 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1118</u>	<u>1000 mL 2</u>	<u>HCl</u>

190 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 23.39 x 0.80 = (Total Depth of Well) 46.53

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/25/09 WELL NO. MW056SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: cloudy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH 10: _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.92 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 56.80 FT.
- D. Height of Water Column in casing (h = TD - SWL): 11.88 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1304

OBSERVATIONS: Purging Start Time: 1304

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1314</u>	<u>2.73</u>	<u>189.9</u>	<u>6.99</u>	<u>21.33</u>	<u>5755</u>	<u>46.74</u>
<u>1319</u>	<u>2.55</u>	<u>157.7</u>	<u>7.09</u>	<u>21.53</u>	<u>5840</u>	<u>46.76</u>
<u>1324</u>	<u>2.56</u>	<u>161.5</u>	<u>6.97</u>	<u>21.33</u>	<u>5828</u>	<u>46.77</u>
<u>1329</u>	<u>2.49</u>	<u>152.4</u>	<u>7.00</u>	<u>21.37</u>	<u>5827</u>	<u>46.78</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1329</u>	<u>1000 ml</u> <u>1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1329</u>	<u>500 ml</u> <u>1</u>	<u>HN03</u>
<u>BTEX / TPH-GRO</u>	<u>1329</u>	<u>40 ml</u> <u>3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1329</u>	<u>1000 ml</u> <u>2</u>	<u>Hcl</u>

170.5 Hz

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft
- 8-inch hole.....2.60 gal/lin ft
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 11.88 x 0.80 = -- (Total Depth of Well) 47.29

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/25/09 WELL NO.: MW065SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Partly cloudy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.52 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 85.71 FT.
D. Height of Water Column in casing (h = TD - SWL): 34.19 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1345

OBSERVATIONS: Purging Start Time: 1345

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1355</u>	<u>6.49</u>	<u>147.6</u>	<u>7.03</u>	<u>20.76</u>	<u>4159</u>	<u>52.11</u>
<u>1400</u>	<u>6.45</u>	<u>142.9</u>	<u>7.09</u>	<u>20.83</u>	<u>4175</u>	<u>52.13</u>
<u>1405</u>	<u>6.53</u>	<u>134.6</u>	<u>7.06</u>	<u>20.84</u>	<u>4170</u>	<u>52.14</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1405</u>	<u>1000 ml 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1405</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1405</u>	<u>40 ml 3</u>	<u>HCL</u>
<u>COMMENTS: TPH-DRO</u>	<u>1405</u>	<u>1000 ml 2</u>	<u>HCL</u>

195 Hz

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 34.19 x 0.80 = -- (Total Depth of Well) 58.35

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/25/09 WELL NO. MW0775A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Partly cloudy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.71 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 98.45 FT.
 D. Height of Water Column in casing ($h = TD - SWL$): 47.74 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1419

OBSERVATIONS: Purging Start Time: 1419

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1429</u>	<u>2.52</u>	<u>136.1</u>	<u>6.92</u>	<u>20.55</u>	<u>4791</u>	<u>50.62</u>
<u>1434</u>	<u>2.51</u>	<u>128.7</u>	<u>6.92</u>	<u>20.60</u>	<u>4788</u>	<u>50.62</u>
<u>1439</u>	<u>2.48</u>	<u>124.7</u>	<u>6.92</u>	<u>20.66</u>	<u>4808</u>	<u>50.62</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1439</u>	<u>1000 mL 1</u>	<u>—</u>
<u>Diss. Metals</u>	<u>1439</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1439</u>	<u>40 mL 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1439</u>	<u>1000 mL 2</u>	<u>HCl</u>

200 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 47.74 x 0.80 = — (Total Depth of Well) 60.25

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/25/09 WELL NO. MW0865A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.91 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 97.80 FT.
- D. Height of Water Column in casing (h = TD - SWL): 46.89 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1452

OBSERVATIONS: Purging Start Time: 1452

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1502</u>	<u>1.99</u>	<u>130.5</u>	<u>6.81</u>	<u>20.72</u>	<u>5508</u>	<u>50.84</u>
<u>1507</u>	<u>1.99</u>	<u>126.3</u>	<u>6.81</u>	<u>20.73</u>	<u>5494</u>	<u>50.84</u>
<u>1512</u>	<u>1.98</u>	<u>126.4</u>	<u>6.84</u>	<u>20.70</u>	<u>5463</u>	<u>50.84</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1512</u>	<u>1000 mL</u> <u>2</u>	<u> </u>
<u>Diss. Metals</u>	<u>1512</u>	<u>500 mL</u> <u>1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1512</u>	<u>40 mL</u> <u>3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1512</u>	<u>1000 mL</u> <u>2</u>	<u>Hcl</u>

200 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 46.89 x 0.80 = (Total Depth of Well) 60.28

Signature: [Signature]

Stantec

Dup # 103

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO: MW055A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 06F1362 AB

Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:

Standard 10 Reading: ORP: Standard: Reading: DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: 1212 pH 7: 7.06 pH 4: 4.01 pH 10: 9.99 ORP: 240

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 40.79 FT.
 B. Thickness of Free Product, if present: Inches FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 54.70 FT.
 D. Height of Water Column in casing (h = TD - SWL): 13.91 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0907

OBSERVATIONS: Purging Start Time: 0907

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
0917	4.39	169.4	7.09	19.35	2508	42.69
0922	4.29	171.1	7.07	19.73	2662	42.84
0927	4.28	171.9	7.08	20.06	2706	42.94
0932	4.26	172.3	7.08	20.21	2725	43.01

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Hex Cr	0932	1000 ml 1	—
Diss. Metals	0932	500 ml 1	HNO3
BTEX / TPH-GRO	0932	40 ml 3	HCl
COMMENTS: TPH-DRO	0932	1000 ml 2	HCl

160 Hz Dup # 103

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft
8-inch hole.....	2.60 gal/lin ft
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 13.91 x 0.80 = -- (Total Depth of Well) 43.57

Signature: 

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO. MW066SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: SUNNY / WINDY

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 49.00 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 72.02 FT.
- D. Height of Water Column in casing (h = TD - SWL): 23.02 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0947

OBSERVATIONS: Purging Start Time: 0947

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>0957</u>	<u>0.32</u>	<u>174.2</u>	<u>6.71</u>	<u>20.37</u>	<u>4375</u>	<u>50.03</u>
<u>1002</u>	<u>0.26</u>	<u>116.7</u>	<u>6.73</u>	<u>20.43</u>	<u>4395</u>	<u>50.06</u>
<u>1007</u>	<u>0.20</u>	<u>90.7</u>	<u>6.73</u>	<u>20.49</u>	<u>4408</u>	<u>50.08</u>
<u>1012</u>	<u>0.14</u>	<u>77.0</u>	<u>6.73</u>	<u>20.50</u>	<u>4407</u>	<u>50.09</u>
<u>1017</u>	<u>0.11</u>	<u>66.8</u>	<u>6.72</u>	<u>20.52</u>	<u>4408</u>	<u>50.10</u>
<u>1022</u>	<u>0.09</u>	<u>60.0</u>	<u>6.73</u>	<u>20.58</u>	<u>4418</u>	<u>50.10</u>
<u>1027</u>	<u>0.08</u>	<u>54.7</u>	<u>6.73</u>	<u>20.58</u>	<u>4417</u>	<u>50.10</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1027</u>	<u>1000 mL 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1027</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1027</u>	<u>40 mL 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1027</u>	<u>1000 mL 2</u>	<u>HCl</u>

190 Hz

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft.
- 8-inch hole.....2.60 gal/in ft.
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 23.02 x 0.80 = (Total Depth of Well) 53.60

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO. MW052SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.54 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 68.15 FT.
D. Height of Water Column in casing (h = TD - SWL): 23.61 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1044

OBSERVATIONS: Purging Start Time: 1044

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1054</u>	<u>1.54</u>	<u>114.7</u>	<u>6.80</u>	<u>20.70</u>	<u>554P</u>	<u>46.67</u>
<u>1059</u>	<u>1.37</u>	<u>115.4</u>	<u>6.79</u>	<u>20.67</u>	<u>5686</u>	<u>46.71</u>
<u>1104</u>	<u>1.21</u>	<u>115.5</u>	<u>6.79</u>	<u>20.73</u>	<u>5820</u>	<u>46.73</u>
<u>1109</u>	<u>1.14</u>	<u>115.6</u>	<u>6.79</u>	<u>20.73</u>	<u>5904</u>	<u>46.73</u>
<u>1114</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1109</u>	<u>1000 ml 1</u>	<u>—</u>
<u>Diss Metals</u>	<u>1109</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-600</u>	<u>1109</u>	<u>40 ml 3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1109</u>	<u>1000 ml 2</u>	<u>Hcl</u>

190 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 23.61 x 0.80 = — (Total Depth of Well) 49.26

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO. MW054SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.74 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 61.90 FT.
 D. Height of Water Column in casing (h = TD - SWL): 17.16 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1124

OBSERVATIONS: Purging Start Time: 1124

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1134</u>	<u>4.40</u>	<u>129.7</u>	<u>7.05</u>	<u>20.74</u>	<u>3275</u>	<u>46.12</u>
<u>1139</u>	<u>4.14</u>	<u>129.1</u>	<u>7.03</u>	<u>20.77</u>	<u>3413</u>	<u>46.16</u>
<u>1144</u>	<u>4.03</u>	<u>127.6</u>	<u>7.02</u>	<u>20.74</u>	<u>3531</u>	<u>46.19</u>
<u>1149</u>	<u>3.91</u>	<u>126.8</u>	<u>7.01</u>	<u>20.78</u>	<u>3630</u>	<u>46.21</u>
<u>1154</u>	<u>3.87</u>	<u>125.7</u>	<u>7.01</u>	<u>20.82</u>	<u>3677</u>	<u>46.24</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hea Cs</u>	<u>1154</u>	<u>1000 ml</u> <u>1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1154</u>	<u>500 ml</u> <u>1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1154</u>	<u>40 ml</u> <u>3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DR0</u>	<u>1154</u>	<u>1000 ml</u> <u>2</u>	<u>Hcl</u>

185 Hz

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 17.16 x 0.80 = -- (Total Depth of Well) 48.17

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO. MW049SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.95 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 88.12 FT.
D. Height of Water Column in casing (h = TD - SWL): 40.17 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1318

OBSERVATIONS: Purging Start Time: 1318

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1328</u>	<u>0.50</u>	<u>132.9</u>	<u>6.86</u>	<u>21.02</u>	<u>6750</u>	<u>48.79</u>
<u>1333</u>	<u>0.47</u>	<u>122.7</u>	<u>6.86</u>	<u>21.05</u>	<u>6737</u>	<u>48.80</u>
<u>1338</u>	<u>0.42</u>	<u>114.3</u>	<u>6.86</u>	<u>20.99</u>	<u>6753</u>	<u>48.81</u>
<u>1343</u>	<u>0.42</u>	<u>109.1</u>	<u>6.86</u>	<u>21.01</u>	<u>6749</u>	<u>48.83</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1343</u>	<u>1000 mL 2</u>	<u> </u>
<u>Diss. Metals</u>	<u>1343</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX/TPH-GRO</u>	<u>1343</u>	<u>40 mL 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1343</u>	<u>1000 mL 2</u>	<u>HCl</u>

190 Hz

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 40.17 x 0.80 = (Total Depth of Well) 55.98

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO. MW048SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 451.02 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 88.42 FT.

D. Height of Water Column in casing (h = TD - SWL): 43.40 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1357

OBSERVATIONS: Purging Start Time: 1357

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1407</u>	<u>5.20</u>	<u>112.8</u>	<u>7.12</u>	<u>21.03</u>	<u>2572</u>	<u>45.90</u>
<u>1402</u>	<u>5.17</u>	<u>110.1</u>	<u>7.13</u>	<u>21.00</u>	<u>2573</u>	<u>45.92</u>
<u>1417</u>	<u>5.18</u>	<u>110.3</u>	<u>7.13</u>	<u>21.00</u>	<u>2582</u>	<u>45.93</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1417</u>	<u>1000 ml 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1417</u>	<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1417</u>	<u>40 ml 3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1417</u>	<u>1000 ml 2</u>	<u>Hcl</u>

190 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.3-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 43.40 x 0.80 = (Total Depth of Well) 53.70

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/26/09 WELL NO. MW 010

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: _____

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard-4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 39.16 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 64.64 FT.

D. Height of Water Column in casing (h = TD - SWL): 25.48 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1432

OBSERVATIONS: Purging Start Time: 1432

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1442</u>	<u>4.36</u>	<u>126.8</u>	<u>6.69</u>	<u>21.23</u>	<u>7828</u>	<u>39.91</u>
<u>1447</u>	<u>4.31</u>	<u>115.8</u>	<u>6.70</u>	<u>21.24</u>	<u>7750</u>	<u>39.91</u>
<u>1452</u>	<u>4.31</u>	<u>108.1</u>	<u>6.71</u>	<u>21.21</u>	<u>7744</u>	<u>39.92</u>
<u>1457</u>	<u>4.31</u>	<u>108.5</u>	<u>6.70</u>	<u>21.21</u>	<u>7776</u>	<u>39.92</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1458</u>	<u>1000 ml</u>	<u> </u>
<u>Diss. Metals</u>	<u>1457</u>	<u>500 ml</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1457</u>	<u>40 ml</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1457</u>	<u>1000 ml</u>	<u>HCl</u>

190 Hz

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 25.48 x 0.80 = -- (Total Depth of Well) 44.25

Signature: _____

8/2008

Using Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

Dup #104

PROJECT NO.: 212201135 DATE: 3/30/09 WELL NO. MW 013A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 60 °F

FIELD PERSONNEL: SB/W JP WEATHER: Clear, Sunny, Wind

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: 1413 Reading: 1152 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 10.00 : ORP: Standard: 240 Reading: 240 : DO: T°C: 17.26 mmHg: 626.5 DO Conc.: 8.70

End-of-Day Recheck: Spec. Cond.: _____ pH 7: _____ pH 4: _____ pH: 10 _____ : ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 43.05 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 106.10 FT.
 D. Height of Water Column in casing (h = TD - SWL): 63.05 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 0930

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>0940</u>	<u>5.65</u>	<u>166.1</u>	<u>7.41</u>	<u>20.25</u>	<u>788</u>	<u>53.03</u>
<u>0945</u>	<u>5.75</u>	<u>164.0</u>	<u>7.47</u>	<u>20.39</u>	<u>777</u>	<u>54.33</u>
<u>0950</u>	<u>5.75</u>	<u>162.2</u>	<u>7.50</u>	<u>20.48</u>	<u>772</u>	<u>55.00</u>
<u>0955</u>	<u>5.75</u>	<u>158.2</u>	<u>7.53</u>	<u>20.64</u>	<u>774</u>	<u>55.38</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>09:55</u>	<u>1000 ml 1</u>	<u> </u>
<u>Diss. Metals</u>		<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 ml 3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>		<u>1000 ml 2</u>	<u>Hcl</u>

Dup #104

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 63.05 x 0.80 = 50.44 (Total Depth of Well) 55.66

Signature: Alan Self

8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3.30.09 WELL NO. MW014
 FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 71 °F
 FIELD PERSONNEL: SB/JP WEATHER: Clear, Sunny, Windy
EQUIPMENT CALIBRATION: YSI QED Serial No.: _____
 Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____
 Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ /mmHg: _____ DO Conc.: _____
 End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 42.69 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 60.88 FT.
 D. Height of Water Column in casing (h = TD - SWL): 18.19 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: _____

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1043</u>	<u>0.60</u>	<u>164.2</u>	<u>6.90</u>	<u>20.99</u>	<u>5506</u>	<u>43.45</u>
<u>1048</u>	<u>0.36</u>	<u>157.0</u>	<u>6.89</u>	<u>21.09</u>	<u>5642</u>	<u>43.46</u>
<u>1053</u>	<u>0.28</u>	<u>149.0</u>	<u>6.89</u>	<u>21.10</u>	<u>5752</u>	<u>43.47</u>
<u>1058</u>	<u>0.23</u>	<u>142.8</u>	<u>6.87</u>	<u>21.09</u>	<u>5782</u>	<u>43.49</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1058</u>	<u>1000 ml 1</u>	<u> </u>
<u>Diss. Metals</u>		<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 ml 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>		<u>1000 ml 2</u>	<u>HCl</u>

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft
 8-inch hole.....2.60 gal/lin ft
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 18.19 x 0.80 = (Total Depth of Well) 46.32

Signature: [Signature] 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 30 MAR 09 WELL NO.: MW032

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 75 °F

FIELD PERSONNEL: SB/JI WEATHER: clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 60.82 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 68.80 FT.
- D. Height of Water Column in casing (h = TD - SWL): 7.98 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: _____

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1148	6.45	149.1	7.27	25.14	1495	62.96
1153	5.29	144.7	7.20	24.99	1655	63.34
1158	5.22	141.9	7.20	24.62	1713	63.12
1203	5.42	139.9	7.20	23.76	1811	63.04
1208	5.40	136.4	7.19	23.63	1803	62.98
1213	5.47	136.7	7.20	23.7	1800	62.92

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hea Cr</u>	<u>1213</u>	<u>1000 ml</u>	<u>1</u>
<u>Diss. Metals</u>		<u>500 ml</u>	<u>1</u>
<u>BTEX / TPH-GRO</u>		<u>40 ml</u>	<u>3</u>
<u>COMMENTS: TPH-DRO</u>		<u>1000 ml</u>	<u>2</u>

Sampling Capacities:
 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 7.98 x 0.80 = -- (Total Depth of Well) 62.41

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 30 MAR 09 WELL NO. MW004A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 80 °F

FIELD PERSONNEL: SB/JI WEATHER: WINDY Gust W 10-30 mph

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.54 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 103.70 FT.
 D. Height of Water Column in casing (h = TD - SWL): 59.16 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: _____

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1408	2.80	155.3	7.38	23.50	2267	56.23
1413	2.69	154.1	7.37	23.92	2285	56.30
1418	2.88	154.0	7.30	24.73	2486	56.43
1423	3.50	151.6	7.23	24.83	2630	56.23
1428	3.46	148.1	7.23	25.03	2632	55.85
1433	3.88	144.5	7.24	25.03	2613	55.77
1438	3.94	142.2	7.24	24.99	2585	55.72
1443	3.94	140.1	7.23	25.01	2579	55.70

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Hex Cr	1443	1000 mL 1	—
Diss. Metals		500 mL 1	HNO3
BTEX / TPH-GRO		40 mL 3	Hcl
COMMENTS: TPH-DRO		1000 mL 2	Hcl

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 59.16 x 0.80 = — (Total Depth of Well) 56.37

Signature: Steve Bell

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

Dwp #105

PROJECT NO.: 212201135 DATE: 31 MAR 09 WELL NO. MW002A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 57 °F

FIELD PERSONNEL: SB/JP WEATHER: clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: 1413 Reading: 1009 pH Standard: 7 Reading 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 1000 ORP: Standard: 240 Reading: 240 DO: T°C: 13.5 mmHg: 633.4 DO Conc.: 9.68

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.89 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 103.28 FT.
D. Height of Water Column in casing (h = TD - SWL): 51.39 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 0900

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>0910</u>	<u>0.25</u>	<u>171.8</u>	<u>6.34</u>	<u>20.46</u>	<u>4407</u>	<u>55.43</u>
<u>0915</u>	<u>0.20</u>	<u>154.2</u>	<u>6.89</u>	<u>20.39</u>	<u>3989</u>	<u>55.58</u>
<u>0920</u>	<u>0.15</u>	<u>145.3</u>	<u>6.88</u>	<u>20.62</u>	<u>4167</u>	<u>55.85</u>
<u>0925</u>	<u>0.15</u>	<u>138.4</u>	<u>6.85</u>	<u>20.81</u>	<u>4263</u>	<u>55.89</u>
<u>0930</u>	<u>0.16</u>	<u>132.0</u>	<u>6.86</u>	<u>20.99</u>	<u>4308</u>	<u>55.71</u>
<u>0935</u>	<u>0.18</u>	<u>127.1</u>	<u>6.85</u>	<u>21.08</u>	<u>4309</u>	<u>55.73</u>
<u>0940</u>	<u>0.20</u>	<u>119.7</u>	<u>6.86</u>	<u>21.14</u>	<u>4288</u>	<u>55.75</u>
<u>0945</u>	<u>0.21</u>	<u>117.5</u>	<u>6.86</u>	<u>21.18</u>	<u>4270</u>	<u>55.76</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>0945</u>	<u>1000 ml</u>	<u>1</u>
<u>Diss. Metals</u>		<u>500 ml</u>	<u>1</u>
<u>BTEX / TPH-GRO</u>		<u>40 ml</u>	<u>3</u>
<u>COMMENTS: TPH-DRO</u>		<u>1000 ml</u>	<u>2</u>

Dwp #105

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 51.39 x 0.80 = 41.11 (Total Depth of Well) 62.16

Signature: Alan Bell

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 31 MAR 2009 WELL NO. MW002

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: SB/IP WEATHER: Clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.94 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 68.59 FT.
- D. Height of Water Column in casing (h = TD - SWL): 16.65 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 10:26

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1016</u>	<u>2.35</u>	<u>114.3</u>	<u>6.68</u>	<u>20.89</u>	<u>4430</u>	<u>52.86</u>
<u>1021</u>	<u>2.23</u>	<u>104.6</u>	<u>6.71</u>	<u>21.10</u>	<u>4485</u>	<u>52.88</u>
<u>1026</u>	<u>2.19</u>	<u>104.7</u>	<u>6.71</u>	<u>21.18</u>	<u>4439</u>	<u>52.88</u>
<u>1031</u>	<u>2.19</u>	<u>105.2</u>	<u>6.72</u>	<u>21.47</u>	<u>4430</u>	<u>52.89</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1031</u>	<u>1000 ml</u>	<u> </u>
<u>Diss. Metals</u>		<u>500 ml</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 ml</u>	<u>HCL</u>
<u>COMMENTS: TPH-DRO</u>		<u>1000 ml</u>	<u>HCL</u>

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 16.65 x 0.80 = (Total Depth of Well) 55.27

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 31 MAR 2009 WELL NO. MW046A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: SB/JI WEATHER: CLOUDY

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.78 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 107.72 FT.
- D. Height of Water Column in casing (h = TD - SWL): 60.94 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1050

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1100</u>	<u>1.09</u>	<u>134.9</u>	<u>6.68</u>	<u>21.35</u>	<u>3044</u>	<u>49.60</u>
<u>1105</u>	<u>0.80</u>	<u>120.9</u>	<u>6.69</u>	<u>21.51</u>	<u>3046</u>	<u>49.68</u>
<u>1110</u>	<u>0.81</u>	<u>118.7</u>	<u>6.68</u>	<u>21.56</u>	<u>3096</u>	<u>49.74</u>
<u>1115</u>	<u>0.81</u>	<u>124.8</u>	<u>6.67</u>	<u>21.56</u>	<u>3151</u>	<u>49.78</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1115</u>	<u>1000 ml 2</u>	<u> </u>
<u>Diss. Metals</u>		<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX/TPH-GRO</u>		<u>40 ml 3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>		<u>1000 ml 2</u>	<u>Hcl</u>

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 60.94 x 0.80 = (Total Depth of Well) 58.96

Signature: Steve Boe

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/14/2009 WELL NO. WAW042A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: SB/JI WEATHER: Cloudy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 46.15 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 99.10 FT.

D. Height of Water Column in casing (h = TD - SWL): 52.95 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1241

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1251</u>	<u>0.38</u>	<u>129.4</u>	<u>6.77</u>	<u>21.30</u>	<u>9809</u>	<u>54.71</u>
<u>1256</u>	<u>0.30</u>	<u>118.9</u>	<u>6.76</u>	<u>21.52</u>	<u>10015</u>	<u>54.72</u>
<u>1301</u>	<u>0.36</u>	<u>106.1</u>	<u>6.75</u>	<u>21.87</u>	<u>10299</u>	<u>54.80</u>
<u>1306</u>	<u>0.35</u>	<u>98.5</u>	<u>6.75</u>	<u>21.78</u>	<u>10175</u>	<u>54.83</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>HexCr</u>	<u>1306</u>	<u>100 ml - 1</u>	
<u>Dis Metals</u>		<u>500 ml - 1</u>	<u>HNO3</u>
<u>BTEX/TPH-GP</u>		<u>40 ml - 3</u>	<u>He/</u>
COMMENTS: <u>TPH-DRO</u>		<u>100 ml - 2</u>	<u>He/</u>

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.63 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 52.95 x 0.80 = 42.36 (Total Depth of Well) 56.74

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/17/2009 WELL NO. MW059

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 68 °F

FIELD PERSONNEL: SB/JI WEATHER: Cloudy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 61.33 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 106.41 FT.

D. Height of Water Column in casing (h = TD - SWL): 45.08 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1329

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1339</u>	<u>4.23</u>	<u>108.2</u>	<u>6.89</u>	<u>20.95</u>	<u>4958</u>	<u>61.62</u>
<u>1344</u>	<u>4.01</u>	<u>104.8</u>	<u>6.94</u>	<u>20.98</u>	<u>4640</u>	<u>61.63</u>
<u>1349</u>	<u>3.27</u>	<u>100.4</u>	<u>6.98</u>	<u>21.03</u>	<u>4115</u>	<u>61.64</u>
<u>1354</u>	<u>3.04</u>	<u>97.0</u>	<u>7.02</u>	<u>21.10</u>	<u>3617</u>	<u>61.64</u>
<u>1359</u>	<u>3.20</u>	<u>96.2</u>	<u>7.07</u>	<u>21.02</u>	<u>3201</u>	<u>61.64</u>
<u>1404</u>	<u>3.19</u>	<u>98.5</u>	<u>7.08</u>	<u>21.15</u>	<u>3003</u>	<u>61.64</u>
<u>1409</u>	<u>3.48</u>	<u>99.5</u>	<u>7.09</u>	<u>21.20</u>	<u>2897</u>	<u>61.65</u>
<u>1414</u>	<u>3.77</u>	<u>101.5</u>	<u>7.09</u>	<u>21.14</u>	<u>2847</u>	<u>61.65</u>
<u>1419</u>	<u>3.92</u>	<u>103.1</u>	<u>7.09</u>	<u>21.25</u>	<u>2846</u>	<u>61.65</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1419</u>	<u>1000 mL</u>	<u>---</u>
<u>Diss. Metals</u>		<u>500 mL</u>	<u>HNO3</u>
<u>BTEX / TPH-620</u>		<u>40 mL</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>		<u>1000 mL</u>	<u>HCl</u>

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 45.08 x 0.80 = --- (Total Depth of Well) 70.34

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 31 MAR 09 WELL NO. MW023

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 70 °F

FIELD PERSONNEL: SB/JI WEATHER: CLEAR

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 55.55 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 69.11 FT.
D. Height of Water Column in casing (h = TD - SWL): 13.56 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1440

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1450</u>	<u>6.46</u>	<u>137.0</u>	<u>6.75</u>	<u>20.70</u>	<u>446.6</u>	<u>56.89</u>
<u>1455</u>	<u>6.76</u>	<u>134.6</u>	<u>6.74</u>	<u>20.71</u>	<u>435.6</u>	<u>56.93</u>
<u>1500</u>	<u>6.74</u>	<u>134.5</u>	<u>6.74</u>	<u>20.76</u>	<u>457.7</u>	<u>56.93</u>
<u>1505</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1500</u>	<u>1000 ml 1</u>	<u>—</u>
<u>Diss. Metals</u>		<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 ml 3</u>	<u>HCl</u>
<u>COMMENTS: TPH-DRO</u>		<u>1000 ml 2</u>	<u>HCl</u>

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 13.56 x 0.80 = — (Total Depth of Well) 58.26

Signature: Allen Bell

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 31 MAR 09 WELL NO. MW004

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 70 °F

FIELD PERSONNEL: SB/JI WEATHER: CLEAR

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 44.33 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 66.50 FT.

D. Height of Water Column in casing (h = TD - SWL): 22.17 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1520

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1530</u>	<u>1.65</u>	<u>141.3</u>	<u>6.57</u>	<u>21.36</u>	<u>5139</u>	<u>44.91</u>
<u>1535</u>	<u>1.11</u>	<u>136.2</u>	<u>6.53</u>	<u>21.39</u>	<u>4795</u>	<u>44.92</u>
<u>1540</u>	<u>1.05</u>	<u>133.4</u>	<u>6.53</u>	<u>21.42</u>	<u>4706</u>	<u>44.93</u>
<u>1545</u>	<u>1.03</u>	<u>131.6</u>	<u>6.53</u>	<u>21.42</u>	<u>4655</u>	<u>44.93</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1545</u>	<u>1000 ml</u>	<u>1</u>
<u>Diss. Metals</u>		<u>500 ml</u>	<u>1</u>
<u>BTEX / TPH-GRO</u>		<u>40 ml</u>	<u>3</u>
COMMENTS: <u>TPH-DRO</u>		<u>1000 ml</u>	<u>2</u>

Casing Capacities:
 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 22.17 x 0.80 = -- (Total Depth of Well) 48.76

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 01 APR 2009 WELL NO. MW013

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 65 °F

FIELD PERSONNEL: SBK SP WEATHER: CLEAR

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: 1413 Reading: 1069 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 400

Standard 10 Reading: 10.08 ; ORP: Standard: 246 Reading: 240 ; DO: T°C: 17.63 mmHg: 676.9 DO Conc.: 8.78

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 43.19 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 60.13 FT.
- D. Height of Water Column in casing (h = TD - SWL): 16.94 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1031

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1041</u>	<u>5.23</u>	<u>0.7</u>	<u>7.06</u>	<u>20.60</u>	<u>4249</u>	<u>43.54</u>
<u>1046</u>	<u>5.23</u>	<u>10.4</u>	<u>7.04</u>	<u>20.73</u>	<u>4270</u>	<u>43.54</u>
<u>1051</u>	<u>5.22</u>	<u>21.5</u>	<u>7.02</u>	<u>20.74</u>	<u>4265</u>	<u>43.55</u>
<u>1056</u>	<u>5.16</u>	<u>29.0</u>	<u>7.01</u>	<u>20.80</u>	<u>4268</u>	<u>43.55</u>
<u>1101</u>	<u>5.16</u>	<u>42.0</u>	<u>7.00</u>	<u>20.81</u>	<u>4092</u>	<u>43.55</u>
<u>1106</u>	<u>5.22</u>	<u>40.0</u>	<u>7.00</u>	<u>20.86</u>	<u>4290</u>	<u>43.55</u>
<u>1111</u>	<u>5.25</u>	<u>46.3</u>	<u>6.99</u>	<u>20.83</u>	<u>4286</u>	<u>43.55</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1111</u>	<u>1000 ml</u> <u>1</u>	<u> </u>
<u>Diss. Metals</u>		<u>500 ml</u> <u>1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 ml</u> <u>3</u>	<u>Hcl</u>
COMMENTS: <u>TPH-DRO</u>		<u>1000 ml</u> <u>2</u>	<u>Hcl</u>

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 16.94 x 0.80 = -- (Total Depth of Well) 46.57

Signature: Steve Reel

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 01 APR 09 WELL NO. MW033

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 72 °F

FIELD PERSONNEL: SB/JF WEATHER: CLEAR

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.19 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 63.02 FT.
- D. Height of Water Column in casing (h = TD - SWL): 15.83 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1217

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1227</u>	<u>0.53</u>	<u>-235.0</u>	<u>7.10</u>	<u>22.02</u>	<u>3036</u>	<u>47.92</u>
<u>1232</u>	<u>0.36</u>	<u>-250.6</u>	<u>7.10</u>	<u>22.03</u>	<u>3057</u>	<u>48.84</u>
<u>1237</u>	<u>0.27</u>	<u>-259.2</u>	<u>7.10</u>	<u>22.06</u>	<u>3100</u>	<u>48.86</u>
<u>1242</u>	<u>0.24</u>	<u>-261.8</u>	<u>7.11</u>	<u>22.05</u>	<u>3121</u>	<u>48.88</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1242</u>	<u>1000 ml 1</u>	<u> </u>
<u>Diss. Metals</u>		<u>500 ml 1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 ml 3</u>	<u>HCl</u>
COMMENTS: <u>TPH-DRO</u>		<u>1000 ml 2</u>	<u>HCl</u>

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.

4-inch hole.....0.65 gal/lin ft.

6.5-inch hole.....1.70 gal/lin ft.

8-inch hole.....2.60 gal/lin ft.

10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 15.83 x 0.80 = (Total Depth of Well) 50.35

Signature: [Signature] 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 01 APR 09 WELL NO. MW 061

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 74 °F

FIELD PERSONNEL: SB/JP WEATHER: CLEAR

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 58.59 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 110.69 FT.
- D. Height of Water Column in casing (h = TD - SWL): 52.10 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1302

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1312	1.56	-15.6	7.09	22.30	5424	58.62
1317	1.20	-0.1	7.05	22.27	5484	58.62
1322	0.88	8.3	7.04	22.42	5510	58.63
1327	0.74	15.7	7.05	22.41	5409	58.63
1332	0.91	23.9	7.07	22.30	5097	58.63
1337	2.45	67.9	7.11	22.45	4554	58.63
1342	2.01	51.6	7.14	22.49	4319	58.63
1347	1.41	46.1	7.14	22.46	4180	58.64
1352	1.13	43.1	7.14	22.44	4082	58.64
1357	1.06	41.1	7.13	22.49	4036	58.64

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>H2O CR</u>	<u>1402</u>	<u>1000 ml</u>	<u>1</u>
<u>Disc. Metals</u>		<u>500 ml</u>	<u>1</u>
<u>BTEX/TPH-GRD</u>		<u>40 ml</u>	<u>3</u>
COMMENTS: <u>TPH-PRO</u>		<u>1000 ml</u>	<u>2</u>

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft.
- 8-inch hole.....2.60 gal/in ft.
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 52.10 x 0.80 = -- (Total Depth of Well) 69.01

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 01 APR 09 WELL NO. MW041A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 75 °F

FIELD PERSONNEL: SB/JP WEATHER: Clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 41.70 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 91.08 FT.
- D. Height of Water Column in casing (h = TD - SWL): 49.38 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1426

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1436</u>	<u>3.56</u>	<u>47.7</u>	<u>7.11</u>	<u>22.67</u>	<u>2632</u>	<u>49.62</u>
<u>1441</u>	<u>3.30</u>	<u>42.8</u>	<u>7.10</u>	<u>23.48</u>	<u>2690</u>	<u>49.65</u>
<u>1446</u>	<u>3.00</u>	<u>42.3</u>	<u>7.10</u>	<u>23.70</u>	<u>2709</u>	<u>49.69</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1446</u>	<u>1000 mL</u> <u>2</u>	<u> </u>
<u>Dist. Metals</u>		<u>500 mL</u> <u>1</u>	<u>HNO3</u>
<u>BTEX/TPH-GRO</u>		<u>40 mL</u> <u>3</u>	<u>Hcl</u>
COMMENTS: <u>TPH-DRO</u>		<u>1000 mL</u> <u>2</u>	<u>Hcl</u>

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 49.38 x 0.80 = (Total Depth of Well) 51.57

Signature: [Signature]

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/2/09 WELL NO. MW0515A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny/very windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: 1.413 Reading: 1.095 pH Standard: 7 Reading: 7.00 ; Standard 4 Reading: 4.00

Standard 10 Reading: 10.00 ; ORP: Standard: 240 Reading: 240 ; DO: T°C: 14.02 mmHg: 9.22 DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 43.48 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 69.05 FT.

D. Height of Water Column in casing (h = TD - SWL): 25.57 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 0929

OBSERVATIONS: Purging Start Time: 0929

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>0939</u>	<u>1.41</u>	<u>209.8</u>	<u>6.88</u>	<u>19.03</u>	<u>4097</u>	<u>45.82</u>
<u>0944</u>	<u>1.23</u>	<u>204.6</u>	<u>6.88</u>	<u>19.14</u>	<u>4098</u>	<u>45.87</u>
<u>0949</u>	<u>1.15</u>	<u>200.4</u>	<u>6.88</u>	<u>19.30</u>	<u>4123</u>	<u>45.92</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>0949</u>	<u>1000 mL</u> <u>1</u>	<u> </u>
<u>Diss. Metals</u>	<u>0949</u>	<u>500 mL</u> <u>1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>0949</u>	<u>40 mL</u> <u>3</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>0949</u>	<u>1000 mL</u> <u>2</u>	<u>Hcl</u>

1FS H2

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 25.57 x 0.80 = (Total Depth of Well) 48.59

Signature: _____

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/2/09 WELL NO. MW062A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny / very Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 55.39 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 110.71 FT.
- D. Height of Water Column in casing (h = TD - SWL): 55.32 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1019

OBSERVATIONS: Purging Start Time: 1019

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1029</u>	<u>5.13</u>	<u>150.6</u>	<u>7.71</u>	<u>16.71</u>	<u>583</u>	<u>56.53</u>
<u>1034</u>	<u>4.99</u>	<u>151.3</u>	<u>7.70</u>	<u>17.02</u>	<u>587</u>	<u>56.59</u>
<u>1039</u>	<u>4.80</u>	<u>151.0</u>	<u>7.69</u>	<u>17.59</u>	<u>595</u>	<u>57.04</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1039</u>	<u>1000 ml</u>	<u>HNO3</u>
<u>Diss. Metals</u>	<u>1039</u>	<u>500 ml</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>	<u>1039</u>	<u>40 ml</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DRO</u>	<u>1039</u>	<u>1000 ml</u>	<u>Hcl</u>

175 H2

Ising Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft
- 8-inch hole.....2.60 gal/lin ft
- 10-inch hole.....4.10 gal/lin ft

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 55.32 x 0.80 = -- (Total Depth of Well) 66.45

Signature: _____

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/2/09 WELL NO. MW063A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny / Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 56.02 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 108.56 FT.

D. Height of Water Column in casing (h = TD - SWL): 52.54 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1100

OBSERVATIONS: Purging Start Time: 1100

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1110</u>	<u>4.12</u>	<u>144.7</u>	<u>7.61</u>	<u>20.24</u>	<u>622</u>	<u>56.91</u>
<u>1115</u>	<u>3.96</u>	<u>144.1</u>	<u>7.60</u>	<u>20.95</u>	<u>632</u>	<u>59.34</u>
<u>1120</u>	<u>3.90</u>	<u>144.3</u>	<u>7.60</u>	<u>21.33</u>	<u>638</u>	<u>59.53</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1120</u>	<u>1000 ml</u>	<u> </u>
<u>Diss. Metals</u>	<u>1120</u>	<u>500 ml</u>	<u>HNO3</u>
<u>BTEX / TPH-GR0</u>	<u>1120</u>	<u>40 ml</u>	<u>Hcl</u>
<u>COMMENTS: TPH-DR0</u>	<u>1120</u>	<u>1000 ml</u>	<u>Hcl</u>

180 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 52.54 x 0.80 = -- (Total Depth of Well) 66.52

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4/2/09 WELL NO. MW039A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: Sunny/Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 55.14 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 119.23 FT.
D. Height of Water Column in casing (h = TD - SWL): 64.09 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: 1230

OBSERVATIONS: Purging Start Time: 1230

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1240</u>	<u>3.70</u>	<u>167.0</u>	<u>7.38</u>	<u>20.94</u>	<u>2406</u>	<u>58.70</u>
<u>1245</u>	<u>3.59</u>	<u>164.7</u>	<u>7.37</u>	<u>21.43</u>	<u>2372</u>	<u>59.07</u>
<u>1250</u>	<u>3.45</u>	<u>164.3</u>	<u>7.37</u>	<u>21.61</u>	<u>2338</u>	<u>59.20</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>	<u>1250</u>	<u>1000 mL 1</u>	<u> </u>
<u>Diss. Metals</u>	<u>1250</u>	<u>500 mL 1</u>	<u>HNO3</u>
<u>BTEX / TPH-6RO</u>	<u>1250</u>	<u>40 mL 3</u>	<u>Hcl</u>
COMMENTS: <u>TPH-DR0</u>	<u>1250</u>	<u>1000 mL 2</u>	<u>Hcl</u>

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 64.09 x 0.80 = -- (Total Depth of Well) 67.95

Signature: _____

PROJECT NO.: 212201135 DATE: 4-6-09 WELL NO. EPWW1

FIELD PERSONNEL: SB/JI WEATHER: *bc*

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; **pH Standard:** 7 Reading _____ ; **Standard 4 Reading:** _____

Standard 10 Reading: _____; ORP: Standard: _____ Reading: _____; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

A. Static Water Level (SWL) below top of casing/piezometer: _____ FT.

B. Thickness of Free Product, if present: _____ Inches. _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: _____ FT.

D. Height of Water Column in casing ($h = TD - SWL$): _____ FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: _____ **Purging Start Time:** _____

[illegible]

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Hex CR	10:30	1000 ml 1	—
Diss. Metals		500 ml 1	HNO3
BTEX / TPH-GRO		40 ml 3	HCl
COMMENTS: TPH-DRO		1000 ml 2	HCl

COMMENTS: TPA-DRO 1000 ml 2 HCL
pumping water well - No Parameters, unable to find filter
for Dissolved metals. Flushed for conservative from bottle - Request
Lab filter for Dissolved metals

Expanding Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures **Less than or equal to:**

Original Water Column: _____ x 0.80 = -- (Total Depth of Well)

Signature: Lila S. S. S.

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 3/10/08 WELL NO. MW003

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: °F

FIELD PERSONNEL: SB/JI WEATHER:

EQUIPMENT CALIBRATION: (YSI) QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ;pH Standard: 7 Reading _____ ;Standard 4 Reading: _____

Standard 10 Reading: _____; ORP: Standard: _____ Reading: _____; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec.Cond: _____; pH 7: _____; pH 4: _____; pH: 10 _____; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 47.73 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 70.51 FT.

D. Height of Water Column in casing ($h = TD - SWL$): 22.78 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: _____ **Purging Start Time:** _____

[illegible]

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Hex Cr		1000 ml 2	
Diss. Metals		500 ml 1	HNO3
BTEX / TPH-GRO		40 ml 3	Hcl
COMMENTS: TPH-DRO	1 0	1000 ml 2	Hcl

COMMENTS: ^{TPH-DRO} 1000 ml 2 H2C
No Samples- unable to access due to
construction in area

Increasing Capacities:

2-inch hole.....0.16 gal/in ft. .

4-inch hole.....0.65 gal/in. ft. .

6.5-inch hole.....1.70 gal/in ft

8-inch hole.....2.60 gal/lin ft

10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to

Original Water Column: 22.78 x 0.80 = -- (Total Depth of Well) 52.28

Signature: X. M. Jell

8/2008

PROJECT NO.: 212201135 DATE: 3/10/09 WELL NO. MW007

FIELD PERSONNEL: SB/JI WEATHER: _____

Spec. Conductivity: Standard: Reading: ; pH Standard: 7 Reading ; Standard 4 Reading:

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

A. Static Water Level (SWL) below top of casing/piezometer: 47.78 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 68.22 FT.

D. Height of Water Column in casing ($h = TD - SWL$): 20.44 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

Purging Start Time:_____

[illegible]

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
------------------	------	-----------------------------	--------------

Hex Cr 1000 ml $\frac{1}{2}$ —

Diss. Metals	500 ml	1	HNO ₃
--------------	--------	---	------------------

BTEX / TPH-GRO	40	ml	3	Hcl
----------------	----	----	---	-----

COMMENTS: TPH-DRO 1000 ml 2 Hcl

COMMENTS: TPH-DRO 1000 ml 2 Hel
No samples. unable to access due to
Pine Struck in area

Increasing Capacities:

2-inch hole.....0.16 gal/lin ft. .

4-inch hole.....0.65 gal/lin ft. .

6.5-inch hole.....1.70 gal/lin ft

8-inch hole.....2.60 gal/lin ft

10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 20.44 x 0.80 = -- (Total Depth of Well) 51.86

Signature: Althea Jell

PROJECT NO.: 212201135 DATE: 3/10/28 WELL NO. mw047

FIELD PERSONNEL: SB/JI WEATHER:

Spec. Conductivity: Standard: Reading: ; **pH Standard:** 7 Reading ; **Standard 4 Reading:**

Standard 10 Reading: _____; ORP: Standard: _____ Reading: _____; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: :pH 7: :pH 4: :pH: 10 :ORP:

A. Static Water Level (SWL) below top of casing/piezometer: _____ FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: _____ FT.

D. Height of Water Column in casing ($h = TD - SWL$): _____ FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: **Purging Start Time:**_____

[illegible]

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
------------------	------	-----------------------------	--------------

Hex Cr

Diss. Metals

BTEX / TPH-GRO

COMMENTS: TPH-DRO

COMMENTS: No Access / demo work.

Increasing Capacities:

2-inch hole.....0.16 gal/min ft. .

4-inch hole.....0.65 gal/lin ft. .

6.5-inch hole.....1.70 gal/lin ft

8-inch hole.....2.60 gal/lin ft

10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: _____ x 0.80 = -- (Total Depth of Well) _____

Signature: [Signature]

8/2008

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 DATE: 4-6-09 WELL NO. Rowland WW

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: SB/JI WEATHER: _____

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 39.69 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 58.00 FT.
- D. Height of Water Column in casing (h = TD - SWL): 18.31 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: _____

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex Cr</u>		<u>1000 mL</u> <u>1</u>	
<u>Diss. Metals</u>		<u>500 mL</u> <u>1</u>	<u>HNO3</u>
<u>BTEX / TPH-GRO</u>		<u>40 mL</u> <u>3</u>	<u>Hcl</u>
		<u>1000 mL</u> <u>2</u>	<u>Hcl</u>

COMMENTS: TPH-DRO
No Sample Pump Not operatable. No Access to well

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft.
- 8-inch hole.....2.60 gal/in ft.
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 18.31 x 0.80 = -- (Total Depth of Well) 43.35

Signature: [Signature]

Groundwater Monitoring Duplicate Sample Field Log

Site: N. Conic

[illegible]

**Stantec Consulting
Midland, Texas
Purge Water Disposal**

Project Site: W. Terrace

[illegible]

Purge Water Disposal

Project Site: Enrico North

[illegible]

Groundwater Monitoring Duplicate Sample Field Log

Site: Enrico North Gas Plant

[illegible]

Acct. #

Group#

Sample #

COC # 217454

Please print. Instructions on reverse side correspond with circled numbers.

(1) Client:		<u>Chenoweth</u>		Acct. #:	<u>201750</u>
Project Name/ID:		<u>201750 / 10000115</u>		PWSID #:	<u>10000115</u>
Project Manager:		<u>C. Vassiliou / J. C. Vassiliou</u>		P.O.#:	<u> </u>
Sampler:		<u>J. Hargrett / J. C. Vassiliou</u>		Quote #:	<u> </u>
Name of state where samples were collected: <u>New York</u>					

Sample Identification	Date Collected	Time Collected	(3)				(4)		(5) Analyses Requested				Preservation Codes	Remarks	Temperature of samples upon receipt (if requested)	
			Grab	Composite	Soil	Water	Other	Matrix	Total # of Containers	H	H	H				H
MW-01A	8-24-09	1057	X				X		7	3	2	1	1	T=Thiosulfate B=NaOH O=Other	Fish Kill Pond, I.L. Lab	6
MW-01B	8-24-09	1135	X				X		7	3	2	1	1		"	
MW-01C	8-24-09	1216	X				X		7	3	2	1	1		"	
MW-01D	8-24-09	1339	X				X		7	3	2	1	1		"	
MW-01E	8-24-09	1410	X				X		7	3	2	1	1		"	
MW-01F	8-24-09	1500	X				X		7	3	2	1	1		"	
DUP-103	8-24-09	—	X				X		7	3	2	1	1		"	
Tri-03 bank	—	—	—				X		2	2					"	

(7) Turnaround Time Requested (TAT) (please circle): Normal Rush			
(Rush TAT is subject to Lancaster Laboratories approval and surcharge.)			
Date results are needed: _____			
Rush results requested by (please circle):	Phone	Fax	E-mail
Phone #:	Fax #:		
E-mail address: _____			

(8) Data Package Options (please circle if required)		SDG Complete?	
Type I (Validation/NJ Reg)	TX TRRP-13	Yes	No
Type II (Tier II)	MA MCP CT RCP		
Type III (Reduced NJ)	Site-specific QC (MS/MSD/Dup)?	Yes	No
Type IV (CLP SOW)	(If yes, indicate QC sample and submit replicate volume.)		
Type VI (Raw Data Only)	Internal COC Required? Yes / No		

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Analysis Request Environmental Services Chain of Custody



For Lancaster Laboratories use only

Acct. #

Group #


Sample #

COC # 217453

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chesapeake</u> Acct. #: <u>201250</u> Project Name/Address: <u>199901135</u> PWSID #: <u>201250</u> Project Manager: <u>Chad Powell</u> PO #: <u>201250</u> Sampler: <u>T. Lawrence / S. Gervais</u> Quote #: <u>201250</u> Name of state where samples were collected: <u>Delaware</u>		5 Analyses Requested Preservation Codes H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		6 Temperature of samples (if requested)	
2 Sample Identification <u>MWD0735A</u> <u>MWD0575A</u> <u>MWD076A</u> <u>MWD075A</u> <u>MWD075A</u> <u>MWD075A</u> <u>Trip Block</u>		4 Matrix Soil ☐ Water ☒ Composite ☒ Other: ☐		3 Date Collected Time Collected <u>7/1/09</u> <u>1035</u> <u>7/1/09</u> <u>1117</u> <u>7/1/09</u> <u>1157</u> <u>7/1/09</u> <u>1252</u> <u>7/1/09</u> <u>1325</u> <u>7/1/09</u> <u>1406</u>	
7 Turnaround Time Requested (TAT) (please circle): Normal Rush (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: _____ Rush results requested by (please circle): Phone Fax E-mail Phone #: _____ Fax #: _____ E-mail address: _____		8 Data Package Options (please circle if required) TX TRRP-13 _____ MA MCP _____ CT RCP _____ Site-specific QC (MS/MSD/Up)? Yes No (If yes, indicate QC sample and volume in separate volume) Internal COC Required? Yes No		9 Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____	
5 Analyses Requested Preservation Codes H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		4 Matrix Soil ☐ Water ☒ Composite ☒ Other: ☐		3 Date Collected Time Collected <u>7/1/09</u> <u>1035</u> <u>7/1/09</u> <u>1117</u> <u>7/1/09</u> <u>1157</u> <u>7/1/09</u> <u>1252</u> <u>7/1/09</u> <u>1325</u> <u>7/1/09</u> <u>1406</u>	
2 Sample Identification <u>MWD0735A</u> <u>MWD0575A</u> <u>MWD076A</u> <u>MWD075A</u> <u>MWD075A</u> <u>MWD075A</u> <u>Trip Block</u>		4 Matrix Soil ☐ Water ☒ Composite ☒ Other: ☐		3 Date Collected Time Collected <u>7/1/09</u> <u>1035</u> <u>7/1/09</u> <u>1117</u> <u>7/1/09</u> <u>1157</u> <u>7/1/09</u> <u>1252</u> <u>7/1/09</u> <u>1325</u> <u>7/1/09</u> <u>1406</u>	
7 Turnaround Time Requested (TAT) (please circle): Normal Rush (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: _____ Rush results requested by (please circle): Phone Fax E-mail Phone #: _____ Fax #: _____ E-mail address: _____		8 Data Package Options (please circle if required) TX TRRP-13 _____ MA MCP _____ CT RCP _____ Site-specific QC (MS/MSD/Up)? Yes No (If yes, indicate QC sample and volume in separate volume) Internal COC Required? Yes No		9 Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____	

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
 Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.



Where quality is a science.

For Lancaster Laboratories use only

Sample #:

Acct. #:-


SCR#:

0157

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300

3566 Rev. 1/31/02



Where quality is a science.

Lancaster Laboratories

For Lancaster Laboratories use only

Sample #:

Acct #:

SCR#:

013964

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

3566 Rev. 1/31/02

Lancaster Laboratories
Where quality is a science.

010311

Acct. #:

Where quality is a science.

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.



Where quality is a science.

For Lancaster Laboratories use only

010312

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

3566 Rev. 1/31/02



Lancaster Laboratories
Where quality is a science.

For Lancaster Laboratories use only

Acct. #:- _____ Sample #:- _____

SCR#:

Facility #: Envirop North Gas Plant 212201135
 Site Address: Envirop New Mexico
 Chevron PM: J. Horner Lead Consultant: C. Venable
 Consultant/Office: Satander Houston
 Consultant Proj. Mgr.: Danny Woodward
 Consultant Phone #: 213.973.9973 Fax #: 213.983.8328
 Sampler: SAB
 Service Order #: ☐ Non SAR:

☐ Non SAR:

Sample Identification	Date Collected	Time Collected	Grab
NW0758A	8-24-09	1035	✓
NW0748A	8-24-09	1125	✓
NW0611WW	8-24-09	1150	✓
NW0626	8-28-09	1410	✓
Trip Blanks	—	—	—
Dup #291	8-24-09	—	✓

[illegible]

Please print. Instructions on reverse side correspond with circled numbers.

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only

Acct. #

Group #


Sample #

COC # 217452

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>CUX</u> Acct. #: <u>217452</u> Project Name/ID: <u>217452</u> PWSID #: <u>217452</u> Project Manager: <u>John Carroll</u> P.O. #: <u>217452</u> Sampler: <u>J. Carroll</u> Quote #: <u>217452</u> Name of state where samples were collected: <u>Massachusetts</u>		2 Sample Identification <table border="1"> <thead> <tr> <th>Sample Identification</th> <th>Date Collected</th> <th>Time Collected</th> <th>Grab</th> <th>Composite</th> <th>Soil</th> <th>Water</th> <th>Other</th> <th>Total # of Containers</th> <th>Matrix</th> <th>4</th> <th>5</th> <th>6</th> </tr> </thead> <tbody> <tr> <td>MW067SA</td> <td>8-20-09</td> <td>1106</td> <td>X</td> <td></td> <td></td> <td>X</td> <td></td> <td>7</td> <td>X</td> <td></td> <td>1</td> <td></td> </tr> <tr> <td>MW053SA</td> <td>8-20-09</td> <td>1145</td> <td>X</td> <td></td> <td></td> <td>X</td> <td></td> <td>7</td> <td>X</td> <td></td> <td>1</td> <td></td> </tr> <tr> <td>MW078SA</td> <td>8-20-09</td> <td>1226</td> <td>X</td> <td></td> <td></td> <td>X</td> <td></td> <td>7</td> <td>X</td> <td></td> <td>1</td> <td></td> </tr> <tr> <td>MW015</td> <td>8-20-09</td> <td>1343</td> <td>X</td> <td></td> <td></td> <td>X</td> <td></td> <td>7</td> <td>X</td> <td></td> <td>1</td> <td></td> </tr> <tr> <td>MW025</td> <td>8-20-09</td> <td>1437</td> <td>X</td> <td></td> <td></td> <td>X</td> <td></td> <td>7</td> <td>X</td> <td></td> <td>1</td> <td></td> </tr> <tr> <td>20P-102</td> <td>8-20-09</td> <td></td> <td>X</td> <td></td> <td></td> <td>X</td> <td></td> <td>7</td> <td>X</td> <td></td> <td>1</td> <td></td> </tr> <tr> <td>Tap Blank</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>X</td> <td></td> <td>2</td> <td>X</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>55</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample Identification	Date Collected	Time Collected	Grab	Composite	Soil	Water	Other	Total # of Containers	Matrix	4	5	6	MW067SA	8-20-09	1106	X			X		7	X		1		MW053SA	8-20-09	1145	X			X		7	X		1		MW078SA	8-20-09	1226	X			X		7	X		1		MW015	8-20-09	1343	X			X		7	X		1		MW025	8-20-09	1437	X			X		7	X		1		20P-102	8-20-09		X			X		7	X		1		Tap Blank						X		2	X												55				
Sample Identification	Date Collected	Time Collected	Grab	Composite	Soil	Water	Other	Total # of Containers	Matrix	4	5	6																																																																																																												
MW067SA	8-20-09	1106	X			X		7	X		1																																																																																																													
MW053SA	8-20-09	1145	X			X		7	X		1																																																																																																													
MW078SA	8-20-09	1226	X			X		7	X		1																																																																																																													
MW015	8-20-09	1343	X			X		7	X		1																																																																																																													
MW025	8-20-09	1437	X			X		7	X		1																																																																																																													
20P-102	8-20-09		X			X		7	X		1																																																																																																													
Tap Blank						X		2	X																																																																																																															
								55																																																																																																																
7 Turnaround Time Requested (TAT) (please circle): <u>Normal</u> Rush (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: _____ Rush results requested by (please circle): _____ Phone _____ Fax _____ E-mail _____ Phone #: _____ Fax #: _____ E-mail address: _____		8 Data Package Options (please circle if required) Type I (Validation/NJ Reg) TX TRRP-13 SDG Complete? Yes No Type II (Tier II) MA MCP CT RCP Type III (Reduced NJ) Site-specific QC (MS/MSD/Dup)? Yes No Type IV (CLP SOW) (if yes, indicate QC sample and submit triplicate volume) Type VI (Raw Data Only) Internal COC Required? Yes / No																																																																																																																						
9 Relinquished by: <u>[Signature]</u> Date: <u>8-20-09</u> Time: <u>1706</u> Relinquished by: _____ Date: _____ Time: _____ Relinquished by: _____ Date: _____ Time: _____ Relinquished by: _____ Date: _____ Time: _____ Relinquished by: _____ Date: _____ Time: _____		6 Preservation Codes H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other Remarks: <u>Don't Methylate. In Lab</u> Temperature of samples upon receipt (if requested): _____																																																																																																																						

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only

COC # 217451

Acct. # _____ Group # _____ Sample # _____

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chemco</u> Acct. #: _____ Project Name/ID: <u>N. F. 217451</u> PWSID #: _____ Project Manager: <u>Chad Howell / D. Woodward</u> Sampler: <u>L. Langwell / H. P. ...</u> Quote #: _____ Name of state where samples were collected: <u>New Mexico</u>		2 Sample Identification: _____ Date Collected: _____ Time Collected: _____		3 Matrix: ☒ Soil ☒ Water ☒ Composite ☐ NPDES Applicable		4 Total # of Containers: _____ Other: _____		5 Analyses Requested: _____ Preservation Codes: _____		6 Preservation Codes: H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		7 Turnaround Time Requested (TAT) (please circle): Normal / Rush (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: _____ Rush results requested by (please circle): Phone Fax E-mail Phone #: _____ Fax #: _____ E-mail address: _____		8 Data Package Options (please circle if required) Type I (Validation/NJ Reg) TX TRRP-13 Type II (Tier II) MA MCP CT RCP Type III (Reduced NJ) Site-specific QC (MS/MSD/Dup)? Yes No Type IV (CLP SOW) (if yes, indicate QC sample and submit separate volume) Type VI (Raw Data Only) Internal COC Required? Yes / No		9 Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time 8-19-09 16:55 Date Time Date Time Date Time Date Time Date Time	
Sample ID: <u>AWD037</u> Date: <u>8-19-09</u> Time: <u>1030</u>		☒ Soil ☒ Water ☒ Composite		Matrix: ☒ Soil ☒ Water ☒ Composite		Total # of Containers: <u>7</u> Other: _____		Analyses Requested: _____		Preservation Codes: _____		Preservation Codes: H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time 8-19-09 16:55 Date Time Date Time Date Time Date Time Date Time			
Sample ID: <u>AWD038</u> Date: <u>8-19-09</u> Time: <u>1131</u>		☒ Soil ☒ Water ☒ Composite		Matrix: ☒ Soil ☒ Water ☒ Composite		Total # of Containers: <u>7</u> Other: _____		Analyses Requested: _____		Preservation Codes: _____		Preservation Codes: H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time 8-19-09 16:55 Date Time Date Time Date Time Date Time Date Time			
Sample ID: <u>AWD039</u> Date: <u>8-19-09</u> Time: <u>1244</u>		☒ Soil ☒ Water ☒ Composite		Matrix: ☒ Soil ☒ Water ☒ Composite		Total # of Containers: <u>7</u> Other: _____		Analyses Requested: _____		Preservation Codes: _____		Preservation Codes: H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time 8-19-09 16:55 Date Time Date Time Date Time Date Time Date Time			
Sample ID: <u>AWD040</u> Date: <u>8-19-09</u> Time: <u>1301</u>		☒ Soil ☒ Water ☒ Composite		Matrix: ☒ Soil ☒ Water ☒ Composite		Total # of Containers: <u>7</u> Other: _____		Analyses Requested: _____		Preservation Codes: _____		Preservation Codes: H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time 8-19-09 16:55 Date Time Date Time Date Time Date Time Date Time			
Sample ID: <u>AWD041</u> Date: <u>8-19-09</u> Time: <u>1403</u>		☒ Soil ☒ Water ☒ Composite		Matrix: ☒ Soil ☒ Water ☒ Composite		Total # of Containers: <u>7</u> Other: _____		Analyses Requested: _____		Preservation Codes: _____		Preservation Codes: H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time 8-19-09 16:55 Date Time Date Time Date Time Date Time Date Time			
Sample ID: <u>AWD042</u> Date: <u>8-19-09</u> Time: <u>1452</u>		☒ Soil ☒ Water ☒ Composite		Matrix: ☒ Soil ☒ Water ☒ Composite		Total # of Containers: <u>7</u> Other: _____		Analyses Requested: _____		Preservation Codes: _____		Preservation Codes: H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time 8-19-09 16:55 Date Time Date Time Date Time Date Time Date Time			
Sample ID: <u>DWD-101</u> Date: <u>8-19-09</u> Time: _____		☒ Soil ☒ Water ☒ Composite		Matrix: ☒ Soil ☒ Water ☒ Composite		Total # of Containers: <u>7</u> Other: _____		Analyses Requested: _____		Preservation Codes: _____		Preservation Codes: H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time 8-19-09 16:55 Date Time Date Time Date Time Date Time Date Time			
Sample ID: <u>Trip Blank</u> Date: _____ Time: _____		☒ Soil ☒ Water ☒ Composite		Matrix: ☒ Soil ☒ Water ☒ Composite		Total # of Containers: <u>4</u> Other: _____		Analyses Requested: _____		Preservation Codes: _____		Preservation Codes: H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time 8-19-09 16:55 Date Time Date Time Date Time Date Time Date Time			

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
 Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only

Acct. #

Group #

Sample #

COC # 217448

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chesapeake</u> Acct. #: <u>201250</u> Project Name/ID: <u>201250</u> PWSID #: <u>201250</u> Project Manager: <u>Chad Clowell</u> P.O. #: <u>201250</u> Sampler: <u>Thompson/Spivey Construction</u> Quote #: <u>201250</u> Name of state where samples were collected: <u>New Mexico</u>		2 Sample Identification Sample ID: <u>2025</u> Date Collected: <u>8-13-08</u> Time Collected: <u>1321</u> Sample ID: <u>2026</u> Date Collected: <u>8-13-08</u> Time Collected: <u>1313</u>		3 Matrix Soil ☒ Water ☒ Composite ☒ Other: <u>None</u>		4 Analyses Requested H ☒ H ☒ H ☒ H ☒ TDS, pH, Alk., <u>As, Cd, Cr, Cu, Fe, Pb, Zn</u> TDS, pH, Alk., <u>As, Cd, Cr, Cu, Fe, Pb, Zn</u> TDS, pH, Alk., <u>As, Cd, Cr, Cu, Fe, Pb, Zn</u>		5 Preservation Codes H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		6 Temperature of samples (if requested) Remarks: <u>See attached. Metals info.</u> <u>"</u> <u>See attached. D. Woodward.</u> <u>at Durstons &</u> <u>245-644-8583</u>	
7 Turnaround Time Requested (TAT) (please circle) (Normal) (Rush) (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: _____ Rush results requested by (please circle): Phone Fax E-mail Phone #: _____ Fax #: _____ E-mail address: _____		Relinquished by: <u>[Signature]</u> Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		Date Time Received by: Date Time Received by: Date Time Received by: Date Time Received by: Date Time Received by:		8 Data Package Options (please circle if required) Type I (validation/NJ Reg) TX TRRP-13 SDG Complete? Yes No Type II (Tier II) MA MCP CT RCP Type III (Reduced NJ) Site-specific QC (MS/MSD/Dup)? Yes No Type IV (CLP SOW) (if yes, indicate QC sample and actual replicate volume) Type VI (Raw Data Only) Internal COC Required? Yes / No					

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
 Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only


COC # 217447

Acct. # _____ Group# _____ Sample # _____

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chamon</u> Acct. #: <u>701.250</u> Project Name#: <u>112701135</u> PWSID #: _____ Project Manager: <u>Chad Cowell</u> P.O.#: _____ Sampler: <u>Thompson / S. Corridor</u> Quote #: _____ Name of state where samples were collected: <u>New Mexico</u>		5 Analyses Requested Preservation Codes H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		6 Temperature of samples upon receipt (if requested)	
2 Sample Identification <u>AW20845A</u> <u>Trip Blank</u>		3 Grab Composite ☒		4 Matrix Soil ☒ Water ☒ Other ☐ Volatile ☐ Non-Volatile ☐	
7 Turnaround Time Requested (TAT) (please circle): <u>Normal</u> Rush (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: _____ Rush results requested by (please circle): _____ Phone #: _____ Fax #: _____ E-mail address: _____		8 Data Package Options (please circle if required) Type I (Validation/NJ Reg) TX TRRP-13 Type II (Tier II) MA MCP CT RCP Type III (Reduced NJ) Site-specific QC (MS/MSD/Dup)? Yes No Type IV (CLP SOW) (if yes, indicate QC sample and submit replicate volume) Type VI (Raw Data Only) Internal COC Required? Yes / No		9 Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____	
8 Date Package Options (please circle if required) Type I (Validation/NJ Reg) TX TRRP-13 Type II (Tier II) MA MCP CT RCP Type III (Reduced NJ) Site-specific QC (MS/MSD/Dup)? Yes No Type IV (CLP SOW) (if yes, indicate QC sample and submit replicate volume) Type VI (Raw Data Only) Internal COC Required? Yes / No		9 Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____ Relinquished by: _____		9 Date Time Date Time Date Time Date Time Date Time	

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
 Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.



For Lancaster Laboratories use only

Acct. #

Group#

Sample #

COC # 217446

Please print. Instructions on reverse slide correspond with circled numbers.

[illegible]

**Lancaster
Laboratories**

Acct. #

Group#


Sample #

COC # 217444

Please print. Instructions on reverse side correspond with circled numbers.

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only

Acct. #

Group #

Sample #

COC # 217442

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chevron</u> Acct. #: <u>250</u> Project Name/ID: <u>717701135.701_PWSID #:</u> Project Manager: <u>Chad Dawell</u> P.O. #: <u></u> Sampler: <u>Terri S. Longwell</u> Quote #: <u>222</u> Name of state where samples were collected: <u>MD</u>		2 Sample Identification: <u>MD262A</u> Date Collected: <u>8-3-09</u> Time Collected: <u>1503</u>		3 Matrix: ☒ Soil ☒ Water ☐ Other ☐ Composite ☐ NPDES Applicable ☐ Potable Check		4 Total # of Containers: <u>7</u> Other: <u>3</u>		5 Analyses Requested: <u>TPH DRO</u> <u>TPH GND</u> <u>TPH DRO</u> <u>TDS, (1300.0)</u> <u>Fe, As, Cr, Mn, Pb</u>		6 Preservation Codes: <u>73579</u> H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		Preservation Codes: <u>73579</u> H=HCl T=Thiosulfate N=HNO ₃ B=NaOH S=H ₂ SO ₄ O=Other		Remarks: <u>Filter Disc. Partic. in Lab</u>		Temperature of samples upon receipt (if requested)	
7 Turnaround Time Requested (TAT) (please circle): <u>Normal</u> Rush (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: _____ Rush results requested by (please circle): Phone Fax E-mail Phone #: _____ Fax #: _____ E-mail address: _____																	
8 Data Package Options (please circle if required)																	
Type I (validation/NJ Reg) Type II (Tier II) Type III (Reduced NJ) Type IV (CLP SOW) Type VI (Raw Data Only)				TX TRRP-13 MA MCP CT RCP Site-specific QC (MS/MSD/Dup)? Yes No (If yes, indicate QC sample and submit replicate volume.) Internal COC Required? Yes / No				SDG Complete? Yes No									
9 Relinquished by: <u>[Signature]</u> Date: <u>8-3-09</u> Time: <u>0800</u> Relinquished by: <u>[Signature]</u> Date: <u>8-3-09</u> Time: <u>1707</u> Relinquished by: <u>[Signature]</u> Date: <u>8-3-09</u> Time: <u>1707</u> Relinquished by: <u>[Signature]</u> Date: <u>8-3-09</u> Time: <u>1707</u> Relinquished by: <u>[Signature]</u> Date: <u>8-3-09</u> Time: <u>1707</u> Relinquished by: <u>[Signature]</u> Date: <u>8-3-09</u> Time: <u>1707</u>																	

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only

Acct. #

Group #

Sample #

COC # 217450

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chavon</u> Acct. #: <u> </u> Project Name: <u>212201135 201 PWSID #:</u> Project Manager: <u>Chris O'Connell / 1720080#:</u> Sampler: <u>Theresa / J. Demaris</u> Quote #: <u> </u> Name of state where samples were collected: <u>Massachusetts</u>		2 Sample Identification <table border="1"> <thead> <tr> <th>Sample Identification</th> <th>Date Collected</th> <th>Time Collected</th> </tr> </thead> <tbody> <tr> <td>ANALYST SA</td> <td>8-18-09</td> <td>1117</td> </tr> <tr> <td>ANALYST SA</td> <td>8-18-09</td> <td>1154</td> </tr> <tr> <td>ANALYST SA</td> <td>8-18-09</td> <td>1235</td> </tr> <tr> <td>ANALYST SA</td> <td>8-18-09</td> <td>1343</td> </tr> <tr> <td>ANALYST SA</td> <td>8-18-09</td> <td>1509</td> </tr> <tr> <td>Tip Blank</td> <td>8-18-09</td> <td> </td> </tr> </tbody> </table>		Sample Identification	Date Collected	Time Collected	ANALYST SA	8-18-09	1117	ANALYST SA	8-18-09	1154	ANALYST SA	8-18-09	1235	ANALYST SA	8-18-09	1343	ANALYST SA	8-18-09	1509	Tip Blank	8-18-09																
Sample Identification	Date Collected	Time Collected																																					
ANALYST SA	8-18-09	1117																																					
ANALYST SA	8-18-09	1154																																					
ANALYST SA	8-18-09	1235																																					
ANALYST SA	8-18-09	1343																																					
ANALYST SA	8-18-09	1509																																					
Tip Blank	8-18-09																																						
3 Matrix ☐ Soil ☐ Water ☐ Other ☐ Composite ☐ Grab		4 Total # of Containers <table border="1"> <thead> <tr> <th>Matrix</th> <th>Containers</th> </tr> </thead> <tbody> <tr> <td>Soil</td> <td>7</td> </tr> <tr> <td>Water</td> <td>7</td> </tr> <tr> <td>Other</td> <td>7</td> </tr> </tbody> </table>		Matrix	Containers	Soil	7	Water	7	Other	7																												
Matrix	Containers																																						
Soil	7																																						
Water	7																																						
Other	7																																						
5 Analyses Requested <table border="1"> <thead> <tr> <th>Analyses Requested</th> <th>Containers</th> </tr> </thead> <tbody> <tr> <td>Asbestos</td> <td>7</td> </tr> <tr> <td>Lead</td> <td>7</td> </tr> <tr> <td>Cadmium</td> <td>7</td> </tr> <tr> <td>Chromium</td> <td>7</td> </tr> <tr> <td>Copper</td> <td>7</td> </tr> <tr> <td>Iron</td> <td>7</td> </tr> <tr> <td>Manganese</td> <td>7</td> </tr> <tr> <td>Nickel</td> <td>7</td> </tr> <tr> <td>Silver</td> <td>7</td> </tr> <tr> <td>Zinc</td> <td>7</td> </tr> </tbody> </table>		Analyses Requested	Containers	Asbestos	7	Lead	7	Cadmium	7	Chromium	7	Copper	7	Iron	7	Manganese	7	Nickel	7	Silver	7	Zinc	7	6 Preservation Codes <table border="1"> <thead> <tr> <th>Preservation Codes</th> <th>Containers</th> </tr> </thead> <tbody> <tr> <td>H=HCl</td> <td>7</td> </tr> <tr> <td>T=Thiosulfate</td> <td>7</td> </tr> <tr> <td>N=HNO₃</td> <td>7</td> </tr> <tr> <td>B=NaOH</td> <td>7</td> </tr> <tr> <td>S=H₂SO₄</td> <td>7</td> </tr> <tr> <td>O=Other</td> <td>7</td> </tr> </tbody> </table>		Preservation Codes	Containers	H=HCl	7	T=Thiosulfate	7	N=HNO ₃	7	B=NaOH	7	S=H ₂ SO ₄	7	O=Other	7
Analyses Requested	Containers																																						
Asbestos	7																																						
Lead	7																																						
Cadmium	7																																						
Chromium	7																																						
Copper	7																																						
Iron	7																																						
Manganese	7																																						
Nickel	7																																						
Silver	7																																						
Zinc	7																																						
Preservation Codes	Containers																																						
H=HCl	7																																						
T=Thiosulfate	7																																						
N=HNO ₃	7																																						
B=NaOH	7																																						
S=H ₂ SO ₄	7																																						
O=Other	7																																						
7 Turnaround Time Requested (TAT) (please circle): Normal/ Rush (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: <u>8-18-09</u> Rush results requested by (please circle): Phone Fax E-mail Phone #: <u> </u> Fax #: <u> </u> E-mail address: <u> </u>		8 Data Package Options (please circle if required) <table border="1"> <thead> <tr> <th>Options</th> <th>Yes</th> <th>No</th> </tr> </thead> <tbody> <tr> <td>Type I (validation/NJ Reg)</td> <td></td> <td></td> </tr> <tr> <td>Type II (Tier II)</td> <td></td> <td></td> </tr> <tr> <td>Type III (Reduced NJ)</td> <td></td> <td></td> </tr> <tr> <td>Type IV (CLP SOW)</td> <td></td> <td></td> </tr> <tr> <td>Type VI (Raw Data Only)</td> <td></td> <td></td> </tr> </tbody> </table>		Options	Yes	No	Type I (validation/NJ Reg)			Type II (Tier II)			Type III (Reduced NJ)			Type IV (CLP SOW)			Type VI (Raw Data Only)																				
Options	Yes	No																																					
Type I (validation/NJ Reg)																																							
Type II (Tier II)																																							
Type III (Reduced NJ)																																							
Type IV (CLP SOW)																																							
Type VI (Raw Data Only)																																							
9 Relinquished by: <u>[Signature]</u> Relinquished by: <u> </u> Relinquished by: <u> </u> Relinquished by: <u> </u> Relinquished by: <u> </u>		9 Date Time <table border="1"> <thead> <tr> <th>Date</th> <th>Time</th> </tr> </thead> <tbody> <tr> <td>8-18-09</td> <td>1710</td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> </tbody> </table>		Date	Time	8-18-09	1710																																
Date	Time																																						
8-18-09	1710																																						

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
 Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

DUP-104

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-25-09 WELL NO. MW022A
FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 85 °F.
FIELD PERSONNEL: J. LONCURE WEATHER: P. Cloudy / Slight Breeze
EQUIPMENT CALIBRATION: YSI QED Serial No.: 070100513
Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 4.00
Standard 10 Reading: 8.99 ORP: Standard: 240 Reading: 240.0 DO: T°C: 28.73 mmHg: 7.34 DO Conc.:
End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.20 FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: 103.27 FT.
D. Height of Water Column in casing (h = TD - SWL): 52.07 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1120

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct (±3%)	SWL
1123	3.71	32.1	8.32	29.71	6.637	53.50
1128	3.20	26.4	7.27	23.35	1.027	56.11
1133	3.41	29.3	7.17	23.36	0.746	56.43
1138	3.73	34.7	7.14	23.28	0.702	56.54
1143	4.04	37.8	7.13	23.29	0.687	56.54
1148	4.28	39.3	7.13	23.45	0.684	56.50
1153						
1158						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH GRO	1147	40cc VOA (3)	NCI
TPH DRO		1000cc Amber (2)	NCI
TPH, CI, C-6+		1000cc Poly (2)	
COMMENTS: Fe, As, Cr, Mn		500cc Poly (1)	
194 Hz	Do Color / No O2.0 / Clear		

DUP-104

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 52.07 x 0.80 = -- (Total Depth of Well) 61.61

Signature: DSC

2nd Sample

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-10-09 WELL NO. MW014

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 89 °F

FIELD PERSONNEL: SB WEATHER: Clear Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: 06F1362AB

Spec. Conductivity: Standard: 1.413 Reading: 1.427 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 9.99 ; ORP: Standard: 240 Reading: 240.1 DO: T°C: 28.5 mmHg: 689.7 DO Conc.: 7.12

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 42.83 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 59.91 FT.
 D. Height of Water Column in casing (h = TD - SWL): 17.08 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1252

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1302	1.00	-251.5	7.45	23.69	607	43.70
1307	0.55	-256.6	7.51	23.30	607	43.71
1312	0.33	-249.1	7.54	23.18	700	43.71
1317	0.24	-244.0	7.60	22.97	663	43.72
1322	0.21	-239.0	7.59	22.98	727	43.72
1327	0.19	-235.6	7.58	22.89	744	43.72
1332	0.18	-231.1	7.59	22.86	737	43.72

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1332		

COMMENTS:

(190.11)

Using Capacities:
 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 17.08 x 0.80 = -- (Total Depth of Well) 46.24

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-10-09 WELL NO. MW013

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 70 °F

FIELD PERSONNEL: SB WEATHER: Clear, Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 43.30 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 60.05 FT.
- D. Height of Water Column in casing (h = TD - SWL): 16.75 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1354

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1404	5.40	25.4	6.95	23.26	4232	43.65
1409	5.33	34.4	6.94	23.00	4330	43.65
1414	5.31	39.7	6.94	22.95	4341	43.65
1419	5.29	44.8	6.94	22.86	4375	43.65

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1419		

COMMENTS:

(190 H₂O)

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 16.75 x 0.80 = -- (Total Depth of Well) 46.65

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-10-09 WELL NO. MW054SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 89 °F

FIELD PERSONNEL: SB WEATHER: Clear, Sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: ; pH Standard: 7 Reading: ; Standard 4 Reading:

Standard 10 Reading: ; ORP: Standard: Reading: ; DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: ; pH 7: ; pH 4: ; pH 10: ; ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.93 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 59.90 FT.
- D. Height of Water Column in casing (h = TD - SWL): 14.97 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 1448

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1458	5.36	66.8	7.01	22.49	3391	46.14
1503	5.05	69.3	6.99	22.46	2585	46.18
1508	4.98	72.5	6.98	22.40	3663	46.19
1513	4.94	72.0	6.98	22.33	3704	46.22

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1513	3-40 ml VOA's	HCl
		2-1000 ml Amber	HCl
		1-1000 ml Poly	HOAc
		1-500 ml Poly	Meat

COMMENTS:

190 ft

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft
- 8-inch hole.....2.60 gal/in ft
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 14.97 x 0.80 = -- (Total Depth of Well) 47.92

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-12-09 WELL NO. MW024A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 73 °F

FIELD PERSONNEL: SB WEATHER: PC, 1st wind

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: 1.413 Reading: 1373 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 9.99 ORP: Standard: 240 Reading: 240 DO: T°C: 27.99 mmHg: 692.7 DO Conc.: 7.33

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.17 FT.
- B. Thickness of Free Product, if present: Inches FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 101.48 FT.
- D. Height of Water Column in casing (h = TD - SWL): 50.31 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 1015

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1025	4.58	87.0	7.32	22.33	651	54.69
1030	4.48	79.3	7.30	22.38	650	54.75
1035	4.50	73.8	7.29	22.48	651	54.81
1040	4.61	69.1	7.30	22.52	654	54.83

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1040	3-400 ml VOA's	Hel
		2-1000 ml Amber	Hel
		1-1000 ml PMX	nat
		1-500 ml Poly	nat

COMMENTS:

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 50.31 x 0.80 = (Total Depth of Well) 61.23

Signature: SB

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 10-8-12 WELL NO. MW059

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: _____ °F

FIELD PERSONNEL: _____ WEATHER: PC, LA wind

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 61.32 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 106.45 FT.
- D. Height of Water Column in casing (h = TD - SWL): 45.13 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1109

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1119</u>	<u>4.34</u>	<u>73.8</u>	<u>7.01</u>	<u>23.07</u>	<u>5271</u>	<u>61.70</u>
<u>1124</u>	<u>4.24</u>	<u>69.5</u>	<u>7.00</u>	<u>22.68</u>	<u>5262</u>	<u>61.71</u>
<u>1129</u>	<u>3.94</u>	<u>66.0</u>	<u>7.03</u>	<u>22.61</u>	<u>4829</u>	<u>61.71</u>
<u>1134</u>	<u>3.31</u>	<u>62.0</u>	<u>7.08</u>	<u>22.67</u>	<u>4248</u>	<u>61.71</u>
<u>1139</u>	<u>3.32</u>	<u>59.8</u>	<u>7.12</u>	<u>22.83</u>	<u>3837</u>	<u>61.71</u>
<u>1144</u>	<u>3.42</u>	<u>57.9</u>	<u>7.16</u>	<u>22.91</u>	<u>3496</u>	<u>61.71</u>
<u>1149</u>	<u>3.42</u>	<u>56.8</u>	<u>7.18</u>	<u>22.95</u>	<u>3277</u>	<u>✓</u>
<u>1154</u>	<u>3.50</u>	<u>57.5</u>	<u>7.19</u>	<u>23.01</u>	<u>3156</u>	<u>—</u>
<u>1159</u>	<u>3.66</u>	<u>59.0</u>	<u>7.20</u>	<u>23.02</u>	<u>3096</u>	<u>—</u>
<u>1204</u>	<u>3.78</u>	<u>66.2</u>	<u>7.20</u>	<u>23.03</u>	<u>3061</u>	<u>—</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
_____	<u>1204</u>	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

COMMENTS:

2nd try

Using Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft
- 8-inch hole.....2.60 gal/lin ft
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 45.13 x 0.80 = — (Total Depth of Well) 70.34

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-12-09 WELL NO. MW023

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 86 °F

FIELD PERSONNEL: SB WEATHER: PC, lt wind

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:

Standard 10 Reading: ORP: Standard: Reading: DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 55.55 FT.
 B. Thickness of Free Product, if present: Inches FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 69.02 FT.
 D. Height of Water Column in casing (h = TD - SWL): 13.47 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 1224

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1234	3.94	79.3	6.89	23.22	4715	56.73
1239	3.69	85.3	6.88	23.90	4783	56.74
1244	3.35	90.3	6.88	22.83	4840	56.75
1249	2.93	95.4	6.87	22.83	4866	56.76
1254	2.65	99.6	6.88	22.59	4858	56.77
1259	2.48	104.8	6.88	22.73	4892	56.78
1304	2.41	105.3	6.88	22.78	4893	56.77
1309	2.31	108.0	6.88	22.71	4887	56.77

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1309		

COMMENTS:

200 Hz

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 13.47 x 0.80 = -- (Total Depth of Well) 58.24

Signature: SB

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-12-09 WELL NO. MW0485A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 70 °F

FIELD PERSONNEL: SB WEATHER: PC, low wind

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 45.26 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 84.95 FT.
- D. Height of Water Column in casing (h = TD - SWL): 39.69 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1340

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1350</u>	<u>1.77</u>	<u>80.6</u>	<u>7.07</u>	<u>22.56</u>	<u>2709</u>	<u>45.90</u>
<u>1355</u>	<u>1.20</u>	<u>83.5</u>	<u>7.09</u>	<u>22.41</u>	<u>2615</u>	<u>45.90</u>
<u>1400</u>	<u>1.18</u>	<u>86.6</u>	<u>7.09</u>	<u>22.36</u>	<u>2615</u>	<u>45.91</u>
<u>1405</u>	<u>1.22</u>	<u>90.1</u>	<u>7.08</u>	<u>22.35</u>	<u>2638</u>	<u>45.91</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	<u>1405</u>		

COMMENTS:

190 Hc

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 39.69 x 0.80 = -- (Total Depth of Well) 63.19

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-12-08 WELL NO. MW0555A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 91 °F

FIELD PERSONNEL: SB WEATHER: PC, Wind

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 40.85 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 53.09 FT.
- D. Height of Water Column in casing (h = TD - SWL): 12.24 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1429

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1439	2.95	78.8	7.12	23.03	2663	43.87
1444	2.55	82.6	7.09	23.01	2775	43.76
1449	2.25	84.6	7.08	22.81	2813	43.70
1454	2.10	88.0	7.06	22.95	2836	43.62
1459	2.00	89.8	7.07	23.03	2849	43.52

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1459		

COMMENTS:

175 lb
191 lb

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 12.24 x 0.80 = -- (Total Depth of Well) 43.29

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-17-09 WELL NO. MW0565A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 93 °F

FIELD PERSONNEL: SAB WEATHER: PC, 1st wind

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 44.93 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 54.90 FT.
- D. Height of Water Column in casing (h = TD - SWL): 9.97 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1519

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1529</u>	<u>2.48</u>	<u>83.8</u>	<u>6.98</u>	<u>24.84</u>	<u>5960</u>	<u>46.13</u>
<u>1534</u>	<u>2.43</u>	<u>86.2</u>	<u>6.97</u>	<u>24.35</u>	<u>5955</u>	<u>46.15</u>
<u>1539</u>	<u>2.45</u>	<u>87.8</u>	<u>6.97</u>	<u>24.12</u>	<u>5960</u>	<u>46.17</u>
<u>1544</u>						
<u>1549</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	<u>1539</u>		

COMMENTS:

Casing Capacities:
 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 9.97 x 0.80 = -- (Total Depth of Well) 46.92

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8/20/09 WELL NO. NW070

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 70 °F

FIELD PERSONNEL: SB WEATHER: Clear, Wind

EQUIPMENT CALIBRATION: YSI QED Serial No.: 06F1362 AB

Spec. Conductivity: Standard: 1.113 Reading: 1.459 pH Standard: 7 Reading: 7.00 ; Standard 4 Reading: 4.01

Standard 10 Reading: 9.97 ; ORP: Standard: 240 Reading: 240 ; DO: T°C: 29.06 mmHg: 684.9 DO Conc.: 7.04

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: _____

B. Thickness of Free Product, if present: _____ Inches

C. Total Depth of well (TD) from top of casing/piezometer: _____

D. Height of Water Column in casing (h = TD - SWL): _____

59.00 FT.

_____ FT.

95.88 FT.

36.28 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1:05:20

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1102</u>	<u>5.33</u>	<u>178.4</u>	<u>7.30</u>	<u>23.01</u>	<u>1252</u>	<u>59.52</u>
<u>1107</u>	<u>5.19</u>	<u>174.4</u>	<u>7.27</u>	<u>22.96</u>	<u>1252</u>	<u>59.53</u>
<u>1112</u>	<u>5.02</u>	<u>164.7</u>	<u>7.25</u>	<u>23.01</u>	<u>1249</u>	<u>59.54</u>
<u>1117</u>	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
_____	<u>1112</u>	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

COMMENTS:

200 ft

Casing Capacities:

1-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 36.28 x 0.80 = -- (Total Depth of Well) 66.46

Signature: SB

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-20-09 WELL NO. MW070A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 91 °F

FIELD PERSONNEL: SS WEATHER: Clear, Humid

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ :ORP: Standard: _____ Reading: _____ :DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH 10: _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 58.14 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 127.17 FT.
- D. Height of Water Column in casing (h = TD - SWL): 68.03 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1133

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1143</u>	<u>4.18</u>	<u>109.5</u>	<u>7.95</u>	<u>33.14</u>	<u>705</u>	<u>65.90</u>
<u>1148</u>	<u>3.93</u>	<u>101.8</u>	<u>7.92</u>	<u>33.39</u>	<u>717</u>	<u>67.00</u>
<u>1153</u>	<u>3.41</u>	<u>93.1</u>	<u>7.84</u>	<u>34.48</u>	<u>825</u>	<u>66.75</u>
<u>1158</u>	<u>4.87</u>	<u>94.1</u>	<u>7.66</u>	<u>26.32</u>	<u>874</u>	<u>66.69</u>
<u>1203</u>	<u>4.76</u>	<u>93.8</u>	<u>7.87</u>	<u>26.28</u>	<u>874</u>	<u>66.80</u>
<u>1208</u>	<u>4.67</u>	<u>93.3</u>	<u>7.57</u>	<u>26.27</u>	<u>873</u>	<u>66.83</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	<u>1208</u>		

COMMENTS: 1034h

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 68.03 x 0.80 = 54.42 (Total Depth of Well) 72.75

Signature: SS 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-20-09 WELL NO. MW030

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 94 °F

FIELD PERSONNEL: SB/SG WEATHER: Clear to wind

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:

Standard 10 Reading: ORP: Standard: Reading: DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 59.24 FT.
- B. Thickness of Free Product, if present: Inches FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 77.68 FT.
- D. Height of Water Column in casing (h = TD - SWL): 18.44 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 1259

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1309	5.00	27.5	7.28	25.09	1370	60.23
1314	5.14	29.5	7.25	24.33	1455	60.25
1319	5.16	33.9	7.22	23.90	1545	60.27
1324	5.13	37.6	7.22	23.64	1552	60.26
1329	5.05	41.1	7.23	23.50	1565	60.27

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1329		

COMMENTS:

1954

Casing Capacities:
 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 18.44 x 0.80 = (Total Depth of Well) 62.93

Signature: SB

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

Dup #200

PROJECT NO.: 212201135 201.250 DATE: 8-20-09 WELL NO. W023A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 96 °F

FIELD PERSONNEL: _____ WEATHER: Clear & Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 55.32 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 123.23 FT.
 D. Height of Water Column in casing (h = TD - SWL): 67.91 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1352

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1402</u>	<u>4.88</u>	<u>82.7</u>	<u>7.64</u>	<u>24.03</u>	<u>798</u>	<u>62.42</u>
<u>1407</u>	<u>4.75</u>	<u>84.4</u>	<u>7.62</u>	<u>24.03</u>	<u>800</u>	<u>63.95</u>
<u>1412</u>	<u>4.59</u>	<u>86.9</u>	<u>7.61</u>	<u>24.31</u>	<u>805</u>	<u>65.02</u>
<u>1417</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Dup #200</u>	<u>1412</u>		

COMMENTS:

193 ft

- Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 67.91 x 0.80 = -- (Total Depth of Well) 68.90

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-20-09 WELL NO. MW014A
 FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 45 °F
 FIELD PERSONNEL: _____ WEATHER: P.C. 1st wind

EQUIPMENT CALIBRATION:

YSI

QED

Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 42.65 FT.
 B. Thickness of Free Product, if present: _____ Inches 708.04 FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 108.04 FT.
 D. Height of Water Column in casing (h = TD - SWL): 62.39 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1446

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1456</u>	<u>3.95</u>	<u>74.9</u>	<u>7.53</u>	<u>23.87</u>	<u>780</u>	<u>53.32</u>
<u>1501</u>	<u>3.88</u>	<u>76.4</u>	<u>7.54</u>	<u>24.70</u>	<u>800</u>	<u>53.28</u>
<u>1506</u>	<u>4.03</u>	<u>77.8</u>	<u>7.55</u>	<u>25.80</u>	<u>810</u>	<u>53.94</u>
<u>1511</u>						
<u>1516</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	<u>1506</u>		

COMMENTS:

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 62.39 x 0.80 = -- (Total Depth of Well) 55.13

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-21-09 WELL NO. mw020A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 77 °F

FIELD PERSONNEL: SB WEATHER: PC, Clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: 06F1362 AB

Spec. Conductivity: Standard: 1.413 Reading: 1.416 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 9.48 ORP: Standard: 240 Reading: 246 DO: T°C: 28.75 mmHg: 689.5 DO Conc.: 2.13

End-of-Day Recheck: Spec. Cond.: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 43.08 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 80.49 FT.
 D. Height of Water Column in casing (h = TD - SWL): 37.41 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 10:00

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1020	4.52	199.3	7.03	21.66	3912	46.96
1025	4.63	193.9	6.99	21.62	3930	46.91
1030	4.68	189.4	6.99	21.98	3921	46.96
1035						

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1030		

COMMENTS:

193 lb

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 37.41 x 0.80 = -- (Total Depth of Well) 50.56

Signature: SB

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-21-08 WELL NO: MW020

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 79 °F

FIELD PERSONNEL: SB WEATHER: PC & Wind

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 42.88 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 58.00 FT.
- D. Height of Water Column in casing (h = TD - SWL): 15.12 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1050

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1100</u>	<u>5.17</u>	<u>156.2</u>	<u>6.92</u>	<u>21.90</u>	<u>3349</u>	<u>45.06</u>
<u>1105</u>	<u>5.13</u>	<u>149.3</u>	<u>6.90</u>	<u>21.84</u>	<u>3412</u>	<u>45.09</u>
<u>1110</u>	<u>5.11</u>	<u>143.2</u>	<u>6.90</u>	<u>21.73</u>	<u>3468</u>	<u>45.11</u>
<u>1115</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	<u>1110</u>		

COMMENTS:

V93

Recharge Calculation at Time of Sample Collection:
Collect sample when Depth to Water measures Less than or equal to:
Original Water Column: 15.12 x 0.80 = 12.10 (Total Depth of Well) 45.90

- Sampling Capacities:
- 2-inch hole.....0.16 gal/lin ft.
 - 4-inch hole.....0.65 gal/lin ft.
 - 6.5-inch hole.....1.70 gal/lin ft
 - 8-inch hole.....2.60 gal/lin ft.
 - 10-inch hole.....4.10 gal/lin ft.

Signature: SB
8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-21-09 WELL NO. L-2-WW

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 72 °F

FIELD PERSONNEL: CB WEATHER: Partly Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 40.80 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 62.45 FT.
 D. Height of Water Column in casing (h = TD - SWL): 21.65 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1135

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1145	0.30	-278.4	8.10	21.65	5300	42.86
1150	0.16	-284.0	7.97	21.65	5345	43.28
1155	0.12	-282.4	7.87	21.63	5431	43.37
1200	0.10	-284.1	7.81	21.80	5481	43.42

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1200		

COMMENTS:

190

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 21.65 x 0.80 = -- (Total Depth of Well) 45.13

Signature: *sh*

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-21-09 WELL NO. MW019A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 85 °F

FIELD PERSONNEL: SB WEATHER: PC, calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 29.00 FT.
 B. Thickness of Free Product, if present: _____ Inches FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 22.05 FT.
 D. Height of Water Column in casing (h = TD - SWL): 35.05 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1254

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1304	3.34	49.4	7.16	21.89	1725	43.82
1309	3.67	52.7	7.15	22.08	1801	44.15
1314	3.76	54.9	7.15	22.29	1841	43.61
1319	3.91	57.0	7.14	22.34	1872	43.40

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1319		

COMMENTS:

145 Ha

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft
 8-inch hole.....2.60 gal/in ft
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 35.05 x 0.80 = (Total Depth of Well) 44.01

Signature: SB

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-21-09 WELL NO. WW0725A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 87 °F

FIELD PERSONNEL: SB WEATHER: PC. Clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.24 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 93.74 FT.
- D. Height of Water Column in casing (h = TD - SWL): 43.50 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1347

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1357</u>	<u>2.28</u>	<u>60.3</u>	<u>7.09</u>	<u>22.31</u>	<u>2037</u>	<u>50.38</u>
<u>1402</u>	<u>2.26</u>	<u>58.5</u>	<u>7.08</u>	<u>22.18</u>	<u>2007</u>	<u>50.38</u>
<u>1407</u>	<u>2.68</u>	<u>56.0</u>	<u>7.07</u>	<u>22.05</u>	<u>1988</u>	<u>50.38</u>
<u>1412</u>	<u>2.42</u>	<u>55.8</u>	<u>7.06</u>	<u>22.18</u>	<u>1984</u>	<u>50.38</u>
<u>1417</u>	<u>2.28</u>	<u>55.9</u>	<u>7.05</u>	<u>22.05</u>	<u>2001</u>	<u>50.38</u>
<u>1422</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	<u>1407</u>		

COMMENTS:

195 hr

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 43.50 x 0.80 = -- (Total Depth of Well) 58.86

Signature: SB

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-21-08 WELL NO. MW076 SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 80 °F

FIELD PERSONNEL: SB WEATHER: PC 6-10 wind

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:

Standard 10 Reading: ORP: Standard: Reading: DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 52.45 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 43.78 FT.
- D. Height of Water Column in casing (h = TD - SWL): 41.33 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 1440

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1450	4.28	57.1	7.05	22.27	2949	52.59
1458	4.28	57.8	7.04	22.72	3028	52.60
1500	4.19	65.4	7.02	22.48	3051	52.60
1505						

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1500		

COMMENTS:

Using Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 41.33 x 0.80 = -- (Total Depth of Well) 60.72

Signature: SB

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

Dup #201

PROJECT NO.: 212201135 201.250 DATE: 8-24-09 WELL NO. MW025SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 84°F

FIELD PERSONNEL: SB WEATHER: Clear & Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 06F1362 AB

Spec. Conductivity: Standard: 1.413 Reading: 1.49 pH Standard: 7 Reading: 7.06 Standard 4 Reading: 4.00

Standard 10 Reading: 9.98 ORP: Standard: 240 Reading: 240 DO: T°C: 24.9 mmHg: 688.7 DO Conc.: 2.63

End-of-Day Recheck: Spec. Cond.: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.80 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 65.59 FT.
- D. Height of Water Column in casing (h = TD - SWL): 14.78 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1010

Time	DQ (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1020	4.70	101.5	6.96	22.73	3086	51.61
1025	4.90	63.7	6.96	22.67	3133	51.62
1030	5.13	64.5	6.96	22.52	3186	51.63
1035	5.24	76.3	6.96	22.47	3225	51.63

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Dup #201	1035		

COMMENTS: 14.2 ft

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 14.78 x 0.80 = -- (Total Depth of Well) 53.76

Signature: SB 8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-24-08 WELL NO. MW074SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 88 °F

FIELD PERSONNEL: SB WEATHER: Clear Windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.14 FT.
 B. Thickness of Free Product, if present: _____ Inches FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 66.37 FT.
 D. Height of Water Column in casing (h = TD - SWL): 18.23 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1105

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1115	5.10	98.8	7.01	22.54	2973	48.73
1120	5.10	100.5	7.01	22.48	2959	48.75
1125	5.05	102.4	7.02	22.45	2956	48.75
1130						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1125		

COMMENTS:

1924

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft
 8-inch hole.....2.60 gal/lin ft
 10-inch hole.....4.10 gal/lin-ft

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 18.23 x 0.80 = -- (Total Depth of Well) 51.79

Signature: SB

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-24-97 WELL NO. MW026

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 9X °F

FIELD PERSONNEL: SB WEATHER: Clear, windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.52 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 102.72 FT.
- D. Height of Water Column in casing (h = TD - SWL): 12.20 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1330

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1340	3.63	85.7	6.89	25.69	3335	52.25
1345	3.87	89.6	6.86	25.88	3311	52.28
1350	4.10	93.6	6.83	25.00	3711	52.30
1355	4.47	99.4	6.81	24.18	3818	52.31
1400	4.63	106.6	6.81	23.93	3912	52.32
1405	4.55	110.4	6.81	23.81	3929	52.32
1410	4.28	114.0	6.81	23.77	2948	53.33

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1410		

COMMENTS:

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 1220 x 0.80 = -- (Total Depth of Well) 52.96

Signature: SB

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-24-09 WELL NO. Woodell/W

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 91 °F

FIELD PERSONNEL: _____ WEATHER: Clear windy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: _____ FT.
B. Thickness of Free Product, if present: _____ Inches _____ FT.
C. Total Depth of well (TD) from top of casing/piezometer: _____ FT.
D. Height of Water Column in casing ($h = TD - SWL$): _____ FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: _____

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
_____	<u>1:50</u>	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

COMMENTS:

Sampling Domestic water well, do parameters

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: _____ x 0.80 = ____ (Total Depth of Well)

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-24-09 WELL NO. MW028

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 82 °F

FIELD PERSONNEL: J. Longwell / J. Premeaux WEATHER: Clear Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: _____

B. Thickness of Free Product, if present: _____ Inches

C. Total Depth of well (TD) from top of casing/piezometer: _____

D. Height of Water Column in casing (h = TD - SWL): _____

70.59 ~~85.01~~ ⁵⁴ FT.
85.01 ~~70.59~~ ⁵⁴ FT.
14.12 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 10:15

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1017	3.87	149.6	7.01	24.21	2.346	72.60
1022	2.09	118.6	7.23	23.89	2.319	71.65
1027	2.18	104.7	7.29	24.11	2.268	71.67
1032	2.10	91.1	7.31	24.63	2.335	71.60
1037	1.46	79.2	7.33	25.31	2.405	71.59
1042	1.29	68.2	7.35	26.09	2.404	71.54
1047	1.35	59.1	7.35	26.80	2.420	71.51
1052	1.28	52.3	7.35	27.31	2.426	71.49

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH GRO	1052	40cc VOA (3)	HCl
TPH PRO		1000cc Amber (2)	HCl
Ch, TDS, 0.6µ		1000cc Poly (1)	
COMMENTS: Fe, As, Cr, Mn		560cc Poly (1)	
No Color / Clear / No Odor			

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 14.12 x 0.80 = -- (Total Depth of Well) 89.00 73.71

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-24-09 WELL NO. MW068

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90° °F

FIELD PERSONNEL: JDL WEATHER: Hot Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:

Standard 10 Reading: ORP: Standard: Reading: DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 67.02 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 112.42 FT.
- D. Height of Water Column in casing (h = TD - SWL): 45.40 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 1109

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1110	3.73	91.7	6.51	25.99	41.84	67.74
1115	0.92	73.9	6.52	24.58	39.00	67.54
1120	0.60	42.9	7.07	23.27	14.93	67.53
1125	0.61	28.5	7.06	22.92	7.314	67.53
1130	0.62	26.8	7.02	22.93	6.495	67.52
1135	0.10	25.5	7.01	23.13	6.406	67.54

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX/PAH G70	1135	40m / bag 3	HCL
TPH/DRD		1000 Amber - 2	HCL
CI/TDS/Cr6		1000 Poly	
		500ml Poly	

COMMENTS: FeAs, CI/MM VERY SLTLY

- Using Capacities:
- 2-inch hole.....0.16 gal/in ft.
 - 4-inch hole.....0.65 gal/in ft.
 - 6.5-inch hole.....1.70 gal/in ft
 - 8-inch hole.....2.60 gal/in ft
 - 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 45.40 x 0.80 = -- (Total Depth of Well) 76.10

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-24-09 WELL NO. MW060

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90 °F

FIELD PERSONNEL: SPJL WEATHER: HOT BR2024

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 56.60 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 102.16 FT.
 D. Height of Water Column in casing (h = TD - SWL): 45.56 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1150

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1151	5.81	48.6	7.01	25.20	6.318	57.00
1156	1.28	-16.3	7.45	23.88	5.432	57.13
1201	0.55	-34.5	7.01	24.24	5.370	57.12
1206	0.52	-45.5	7.04	24.36	5.374	57.13
1211	0.60	-50.4	7.01	24.52	5.397	57.13
1216	0.74	-57.7	7.01	24.33	5.416	57.14

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
B22-TPH G70	1216	40ml vial / 3	HCl
TPH G70		1000ml / 2	HCl
C1/TDS/C16		1000ml / 1	
COMMENTS: Fe / As / Cr / Mn		500ml / 1	

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 45.56 x 0.80 = -- (Total Depth of Well) 65.71

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-24-09 WELL NO. MW029

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 15 °F

FIELD PERSONNEL: SPL WEATHER: Hot Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 65.92 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 81.04 FT.
 D. Height of Water Column in casing (h = TD - SWL): 15.12 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1312

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1314	2.43	-0.7	6.94	29.14	5.405	66.54
1319	5.53	3x 23.6	8.18	27.08	1.694	66.67
1324	6.13	3x 49.7	7.45	24.74	1.183	66.70
1329	6.21	2x 48.7	7.43	24.46	1.130	66.70
1334	6.21	16.8	7.41	24.55	1.125	66.70
1339	6.17	22.5	7.39	24.38	1.126	66.70

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX-TPHGRD	1339	40mL/vial - 3	HCL
TPH-D20		1000 mL/Am/2	HCL
Cl/TDS/Co6		1000 mL/TP/1	
COMMENTS: Fe/As/Cr/Mn		500 mL/TP/1	
VERY SILTY			
* Determine Error			

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 15.12 x 0.80 = -- (Total Depth of Well) 68.94

Signature: _____

DUP-103

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-24-09 WELL NO. MW033

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 95 °F

FIELD PERSONNEL: S/L WEATHER: Hot

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.34 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 62.96 FT.
 D. Height of Water Column in casing (h = TD - SWL): 15.62 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1409

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1410</u>	<u>9.04</u>	<u>36.1</u>	<u>7.36</u>	<u>24.66</u>	<u>1.156</u>	<u>47.89</u>
<u>1415</u>	<u>0.90</u>	<u>-174.1</u>	<u>7.13</u>	<u>25.06</u>	<u>3.355</u>	<u>48.80</u>
<u>1420</u>	<u>0.28</u>	<u>-203.6</u>	<u>7.16</u>	<u>24.61</u>	<u>3.245</u>	<u>48.84</u>
<u>1425</u>	<u>0.35</u>	<u>-214.6</u>	<u>7.20</u>	<u>24.52</u>	<u>3.261</u>	<u>48.86</u>
<u>1430</u>	<u>0.33</u>	<u>-213.7</u>	<u>7.20</u>	<u>24.61</u>	<u>3.263</u>	<u>48.88</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX-TPHGR0</u>	<u>1430</u>	<u>40ml / 10A / 3</u>	<u>HCL</u>
<u>THGR0</u>		<u>1000ml / 1A / 2</u>	<u>HCL</u>
<u>CI/TDS/EC</u>		<u>1000ml / 1 / 1</u>	<u> </u>
<u>COMMENTS: Fe/As/Cr/Mn</u>		<u>500ml / 1 / 1</u>	<u> </u>

* DUP-103 * Very Silty / Very strange odor

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft
8-inch hole.....	2.60 gal/lin ft
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 15.62 x 0.80 = (Total Depth of Well) 50.46

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-24-09 WELL NO. MW069

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 95 °F

FIELD PERSONNEL: JPL WEATHER: Hot / 177 clouds

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 63.09 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 112.51 FT.
 D. Height of Water Column in casing (h = TD - SWL): 49.42 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1453

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1454</u>	<u>4.85</u>	<u>-122.1</u>	<u>7.80</u>	<u>27.30</u>	<u>5.558</u>	<u>63.64</u>
<u>1459</u>	<u>8.64</u>	<u>-49.4</u>	<u>6.60</u>	<u>23.58</u>	<u>23.80</u>	<u>63.80</u>
<u>1504</u>	<u>0.58</u>	<u>-54.6</u>	<u>6.53</u>	<u>23.56</u>	<u>15.22</u>	<u>63.78</u>
<u>1509</u>	<u>0.56</u>	<u>-53.0</u>	<u>6.51</u>	<u>24.13</u>	<u>13.05</u>	<u>63.77</u>
<u>1514</u>	<u>0.57</u>	<u>-51.9</u>	<u>6.54</u>	<u>24.33</u>	<u>11.61</u>	<u>63.77</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 168 gal

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>B701/TPH G70</u>	<u>1514</u>	<u>40ml / 100ml / 3</u>	<u>HCL</u>
<u>TPH D70</u>		<u>1000ml / 1 / 2</u>	<u>HCL</u>
<u>C1/C6/705</u>		<u>1000ml / 1 / 1</u>	
COMMENTS: <u>Fe/As/Cr/Mn</u>	<u>5:17y</u>	<u>500ml / 1 / 1</u>	

Casing Capacities:
 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 49.42 x 0.80 = -- (Total Depth of Well) 72.97

Signature: _____ 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8/21/09 WELL NO. MW0735A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 78 °F

FIELD PERSONNEL: Jerry Longwell / Sonya Gonzales WEATHER: light breeze, sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.97 FT.
- B. Thickness of Free Product, if present: _____ Inches
- C. Total Depth of well (TD) from top of casing/piezometer: 55 (685) 48.14 FT.
- D. Height of Water Column in casing (h = TD - SWL): ? 20.62 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1007

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1008</u>	<u>3.05</u>	<u>203</u>	<u>6.86</u>	<u>24.31</u>	<u>2.045</u>	<u>48.55</u>
<u>1013</u>	<u>1.69</u>	<u>179.4</u>	<u>6.72</u>	<u>21.75</u>	<u>1.827</u>	<u>48.50</u>
<u>1018</u>	<u>1.35</u>	<u>162.7</u>	<u>6.73</u>	<u>21.90</u>	<u>1.806</u>	<u>48.50</u>
<u>1023</u>	<u>1.20</u>	<u>145.1</u>	<u>6.79</u>	<u>22.11</u>	<u>1.790</u>	<u>48.50</u>
<u>1028</u>	<u>1.17</u> (12u)	<u>136.0</u>	<u>6.82</u>	<u>22.10</u>	<u>1.792</u>	<u>48.50</u>
<u>1033</u>	<u>1.15</u>	<u>128.0</u>	<u>6.84</u>	<u>22.17</u>	<u>1.795</u>	<u>48.50</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX TPH, GRO</u>	<u>1033</u>	<u>40ml Voa (3)</u>	<u>HCl</u>
<u>TPH DRO</u>		<u>1000 ml Amber (2)</u>	<u>HCl</u>
<u>IDS, Cl, Cr let</u>		<u>1000 poly (1)</u>	
<u>COMMENTS: Fe, As, Cr, Mn</u>		<u>500 ml poly (1)</u>	

177 Hz @ 1010 very silty, no color, no odor.

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 20.62 x 0.80 = -- (Total Depth of Well) 52.09

Signature: Sonya Gonzales / Jerry Longwell

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8/21/09 WELL NO. MW057SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 82 °F

FIELD PERSONNEL: Jerry Longwell / Sonya Gonzales WEATHER: slight breeze, sunny, warm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 45.58 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 70.88 FT.
 D. Height of Water Column in casing (h = TD - SWL): 25.30 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1056

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1057	5.92	91.7	6.95	22.41	2.034	46.59
1102	5.68	98.3	6.88	22.77	2.182	46.81
1107	5.26	98.9	6.88	21.91	2.196	46.19
1112	5.32	95.6	6.92	22.04	2.221	46.19
1117						
1122						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX, TPH, GRO	1112	40 ml Voa (3)	HEI
TPH, GRO	1112	1000 ml Amber (2)	HEI
TDS, Cl, Cr, Pb	1112	1000 poly (1)	—
COMMENTS: Fe, As, Cr, Mn		300 ml poly (1)	—

1112 clear, no color, no odor

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 25.30 x 0.80 = -- (Total Depth of Well) 56.70

Signature: Sonya Gonzales, Jerry Longwell

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8/21/09 WELL NO. MW018A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 84 °F

FIELD PERSONNEL: Jerry Longwell / Sonya Gonzales WEATHER: light breeze, sunny warm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 36.49 FT.

B. Thickness of Free Product, if present: _____ Inches FT.

C. Total Depth of well (TD) from top of casing/piezometer: 81.33 FT.

D. Height of Water Column in casing (h = TD - SWL): 44.84 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1131

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1132	5.90	79.1	6.94	23.42	2.301	36.88
1137	3.80	65.8	7.71	21.43	1.363	45.23
1142	4.18	64.8	7.63	21.43	1.367	+ 45.75 + see comments
1147	4.50	63.6	7.47	21.62	1.410	56.11
1152	4.68	65.1	7.34	21.63	1.478	46.32
1157	4.24	66.7	7.31	21.68	1.497	46.42 46.42 ⁵⁶
1202						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX TPH GRO	1157	40 ml Voa (3)	HCl
TPH DRO	1157	1000 ml Amber (2)	HCl
TDS, Cl, Cr, Co	1157	1000 ml poly (1)	—
COMMENTS: Fe, As, Cr, Mn	1157	500 ml poly (1)	—

173 ftz Clear, no odor

* Pump control is @ low flow rate. *

using Capacities:

2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 44.84 x 0.80 = -- (Total Depth of Well) 45.45

Signature: Sonya Gonzales / Jerry Longwell 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-21-09 WELL NO. MW016A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90 °F

FIELD PERSONNEL: Jerry Longwell / Songa Gonzalez WEATHER: Sunny, light breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 38.96 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 91.37 FT.
- D. Height of Water Column in casing (h = TD - SWL): 52.41 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1235

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1737</u>	<u>6.48</u>	<u>69.4</u>	<u>8.16</u>	<u>25.58</u>	<u>1.534</u>	<u>40.65</u>
<u>1242</u>	<u>5.35</u>	<u>67.1</u>	<u>7.21</u>	<u>22.65</u>	<u>1.826</u>	<u>42.25</u>
<u>1247</u>	<u>5.33</u>	<u>65.16</u>	<u>7.22</u>	<u>22.63</u>	<u>1.803</u>	<u>42.75</u>
<u>1252</u>	<u>5.36</u>	<u>64.0</u>	<u>7.22</u>	<u>22.71</u>	<u>1.813</u>	<u>42.93</u>
<u>1257</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX, TPH, GLO</u>	<u>1252</u>	<u>40 ml vial (3) →</u>	<u>HCl</u>
<u>TPH, GLO</u>	<u>1252</u>	<u>1000 ml Amber (2)</u>	<u>HCl</u>
<u>TA, Cl, Cr 6+</u>	<u>1252</u>	<u>1000 ml poly (1)</u>	<u>—</u>
<u>COMMENTS: Fe, As, Cr, Mn</u>	<u>1252</u>	<u>500 ml poly (1)</u>	<u>—</u>
<u>173 Hz</u>	<u>Clear, no odor</u>		

Casing Capacities:

2-inch hole.....	0.16 gal/in ft.
4-inch hole.....	0.65 gal/in ft.
6.5-inch hole.....	1.70 gal/in ft.
8-inch hole.....	2.60 gal/in ft.
10-inch hole.....	4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 52.41 x 0.80 = — (Total Depth of Well) 49.44

Signature: Songa Gonzalez, Jerry Longwell

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8/21/09 WELL NO. MW015A
 FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 94 °F
 FIELD PERSONNEL: Jerry Longwell / Sonya Gonzales WEATHER: light breeze, sunny, clear
 EQUIPMENT CALIBRATION: YSI QED Serial No.:
 Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:
 Standard 10 Reading: ORP: Standard: Reading: DO: T°C: mmHg: DO Conc.:
 End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 39.28 FT.
 B. Thickness of Free Product, if present: Inches FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 102.00 FT.
 D. Height of Water Column in casing (h = TD - SWL): 65.72 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS:

Purging Start Time: 1307

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1308	6.56	53.7	7.72	24.38	1.850	39.82
1313	3.67	65.3	6.93	22.99	5.848	46.20
1328	3.55	59.1	6.97	23.53	5.614	48.46
1323	3.38	52.4	7.02	24.27	5.656	50.43
1328	3.30	45.3	7.02	24.78	5.812	50.10
					0	49.80 SG

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX, TPH GRD	1328	40 ml Voa (3)	HCl
TPH DRD	1328	1000 ml Amber (2)	HCl
TDS, Cl, Cr 6+	1328	1000 ml poly (1)	-
COMMENTS: Fe, As, Cr, Mn	1328	500 ml poly (1)	-
173 Hz	clear, odorless		

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 65.72 x 0.80 = -- (Total Depth of Well) 49.42

Signature:

Sonya Gonzales, Jerry Longwell

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8/21/09 WELL NO. MW040 ^A ~~54~~ SC

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 94 °F

FIELD PERSONNEL: Jerry Longwell / Sergio Gonzalez WEATHER: sunny, light breeze, warm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 42.17 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 109.85 FT.
 D. Height of Water Column in casing (h = TD - SWL): 67.68 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1343

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1344	4.85	37.2	7.40	25.35	6.306	42.51
1349	5.37	16.0	7.75	22.05	0.817	418.21
1354	5.05	11.6	7.76	22.50	0.739	49.63
1359	5.33	15.4	7.75	22.79	0.740	49.80
1404	5.46	13.9	7.76	22.93	0.739	49.93
1409						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 160 gal. on-site pump in plant

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX, TPH GRO	1404	40 ml Voa (3)	HCl
TPH GRO	1404	1000 ml Ambd 2	HCl
TDS: Cl, Cr 6+	1404	1000 ml poly (1)	=
COMMENTS: Fe, As, Cr, Mn	1404	500ml poly (1)	=

195 Hz clear, odorless.

Sampling Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 67.68 x 0.80 = -- (Total Depth of Well) 55.70

Signature: Sergio Gonzalez / Jerry Longwell 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-20-09 WELL NO. MW067SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 87 °F

FIELD PERSONNEL: J. Longwell WEATHER: p. cloudy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 2.98 ; ORP: Standard: 240 Reading: 240.0 DO: T°C: 28.39 mmHg: 7.00 DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH: 10 :ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.35 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 84.20 FT.
 D. Height of Water Column in casing (h = TD - SWL): 37.85 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1045

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
1046	1.90	25.8	6.24	29.97	5.600	46.88
1051	4.43	53.8	7.01	22.26	1.710	46.84
1056	4.23	65.4	6.95	22.51	1.555	46.84
1101	4.27	67.1	6.97	22.52	1.545	46.84
1106	4.73	65.9	6.99	22.86	1.544	46.84
1111						
1116						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BUBX / TPH 620	1106	40.2. UDA (3)	HCC
TPH DRO		1000.2 Amber (2)	HCC
CI, TPS, C-64		1000.0 Poly (1)	
COMMENTS: Fe, As, Cr, Mn		500.0 Poly (1)	
No Color / No odor / @ 1448 very silty			183 H2

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 37.85 x 0.80 = --(Total Depth of Well) 53.92

Signature: 

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-20-09 WELL NO. MW053SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 87 °F

FIELD PERSONNEL: J. Langwell WEATHER: P. Cloudy / C. m

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 41.97 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 68.33 FT.
- D. Height of Water Column in casing (h = TD - SWL): 26.36 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1128

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1130</u>	<u>6.21</u>	<u>62.5</u>	<u>7.12</u>	<u>24.82</u>	<u>1.646</u>	<u>43.85</u>
<u>1135</u>	<u>4.80</u>	<u>62.5</u>	<u>7.22</u>	<u>22.43</u>	<u>1.461</u>	<u>44.05</u>
<u>1140</u>	<u>4.81</u>	<u>63.8</u>	<u>7.22</u>	<u>22.43</u>	<u>1.423</u>	<u>44.08</u>
<u>1145</u>	<u>4.80</u>	<u>64.6</u>	<u>7.22</u>	<u>22.51</u>	<u>1.414</u>	<u>44.10</u>
<u>1150</u>						
<u>1155</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX/TPH GRO</u>	<u>1145</u>	<u>40mL VOA (3)</u>	<u>HCl</u>
<u>TPH DRO</u>	<u>S</u>	<u>100mL Amber (2)</u>	<u>HCl</u>
<u>TPS, O, O, O, O</u>	<u>S</u>	<u>100mL Poly (1)</u>	<u>—</u>
<u>COMMENTS: Fe, As, Cr, Mn</u>		<u>500mL Poly (1)</u>	<u>—</u>
<u>No Color / No Odor / Clear</u>			<u>192 Hc</u>

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
- 4-inch hole.....0.65 gal/lin ft.
- 6.5-inch hole.....1.70 gal/lin ft.
- 8-inch hole.....2.60 gal/lin ft.
- 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 26.36 x 0.80 = — (Total Depth of Well) 42.24

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-20-09 WELL NO. MW0785A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 88 °F

FIELD PERSONNEL: J. Longwell WEATHER: P. Cloudy / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 44.50 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 68.15 FT.

D. Height of Water Column in casing (h = TD - SWL): 23.65 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1159

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1201	6.21	60.9	7.30	26.29	1.349	45.04
1206	3.26	59.3	7.18	22.39	1.368	45.04
1211	1.95	56.3	7.22	21.95	1.122	45.04
1216	1.76	54.6	7.21	21.90	1.166	45.04
1221	1.68	53.3	7.20	21.94	1.166	45.04
1226	1.64	52.2	7.20	22.01	1.169	45.04
1231						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BIBV 1TPH 620	1226	400c VOA (3)	HCl
TPH D120		1000c Amber (2)	HCl
ODS, CI, C, 6+		1000c Poly (1)	
COMMENTS: Fe, As, C, Mn		500c Poly (1)	
No Color / No Odor / Clear			180 Hc.

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 23.65 x 0.80 = -- (Total Depth of Well) 49.23

Signature: _____

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-20-09 WELL NO. M0015

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 88 °F

FIELD PERSONNEL: J. Longwell WEATHER: P. Cloudy / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 39.35 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 54.05 FT.
- D. Height of Water Column in casing (h = TD - SWL): 14.70 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1326

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1328</u>	<u>3.46</u>	<u>6.7</u>	<u>7.36</u>	<u>30.59</u>	<u>6.132</u>	<u>40.25</u>
<u>1333</u>	<u>4.98</u>	<u>44.3</u>	<u>6.77</u>	<u>21.98</u>	<u>5.705</u>	<u>40.33</u>
<u>1338</u>	<u>4.92</u>	<u>47.2</u>	<u>6.78</u>	<u>21.85</u>	<u>5.650</u>	<u>40.35</u>
<u>1343</u>	<u>4.89</u>	<u>52.1</u>	<u>6.78</u>	<u>21.94</u>	<u>5.641</u>	<u>40.35</u>
<u>1348</u>						
<u>1353</u>						
<u>1358</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTBY / TPN 670</u>	<u>1343</u>	<u>400cc IPA (3)</u>	<u>HCl</u>
<u>TPN DRO</u>		<u>1000cc Amber (2)</u>	<u>HCl</u>
<u>Q, TDS, C, G+</u>		<u>1000cc Poly (1)</u>	
<u>COMMENTS: Fe, As, Cr, Mn</u>		<u>500cc Poly (1)</u>	
<u>No Coloc / No Odo- / Silica</u>			<u>180 Hz</u>

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 14.70 x 0.80 = -- (Total Depth of Well) 92.25

Signature: [Signature]

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-20-09 WELL NO. MW025

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 92 °F

FIELD PERSONNEL: J. Kinswell WEATHER: Clear / Calm

EQUIPMENT CALIBRATION: (YSI) QED Serial No.: _____

Spec. Conductivity: Standard: Reading: ; **pH Standard:** 7 Reading: ; **Standard 4 Reading:**

Standard 10 Reading: _____; ORP: Standard: _____ Reading: _____; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: ; pH 7: ; pH 4: ; pH: 10 ; ORP:

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 5.31 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 66.09 FT.

D. Height of Water Column in casing ($h = TD - SWL$): 14.79 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1406

	<u>Time</u>	<u>DO ($\pm 10\%$)</u>	<u>ORP ($\pm 10\text{mV}$)</u>	<u>pH (± 0.1)</u>	<u>Temp ($\pm 3\%$)</u>	<u>Conduct ($\pm 3\%$)</u>	<u>SWL</u>
	<u>1407</u>	<u>5.05</u>	<u>46.6</u>	<u>6.86</u>	<u>28.21</u>	<u>5.180</u>	<u>52.06</u>
	<u>1412</u>	<u>2.39</u>	<u>84.2</u>	<u>6.88</u>	<u>28.63</u>	<u>2.352</u>	<u>52.88</u>
	<u>1417</u>	<u>1.21</u>	<u>30.0</u>	<u>6.85</u>	<u>29.44</u>	<u>2.300</u>	<u>51.88</u>
	<u>1429</u>	<u>4.08</u>	<u>25.6</u>	<u>6.89</u>	<u>24.39</u>	<u>2.390</u>	<u>51.88</u>
	<u>1437</u>	<u>1.02</u>	<u>15.4</u>	<u>6.97</u>	<u>24.34</u>	<u>2.422</u>	<u>51.88</u>
	<u>1432</u>	<u>1.01</u>	<u>11.3</u>	<u>6.97</u>	<u>24.13</u>	<u>2.413</u>	<u>51.88</u>
	<u>1437</u>	<u>0.99</u>	<u>10.0</u>	<u>6.99</u>	<u>24.30</u>	<u>2.406</u>	<u>51.88</u>
	<u>1447</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
------------------	------	-----------------------------	--------------

BTEX / TPH GRO 1437 40.0 UG/L (3) + (3) HCR

TPH DRD (1000.0 A/Der (2)+(2) 10C1

Cl, TDS, Cr 6+ 1000µ Poly (1) + (1) —

COMMENTS: ~~Fe A3 K, 1112~~ 500-cc Poly (1) + (1) —

(#) Noodor / Ches 180142

(DOP-102)

Backbone Calculation at Time of Sample Collection

2-inch hole..... 0.16 gal/in ft

4-inch hole.....0.65 gal/lin ft. .

Original Water Column: _____ x 0.80 = _____ (Total Depth of Well) 37.25

10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: _____ x 0.80 = -- (Total Depth of Well) 54.26

Signature: [Signature]

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-19-09 WELL NO. MW027

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 83° °F

FIELD PERSONNEL: J. Langwell / J. Premere WEATHER: Clear / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading 7.00 Standard 4 Reading: 400

Standard 10 Reading: 10.00 ORP: Standard: 290 Reading: 290.0 DO: T°C: 28.16 mmHg: 7.03 DO Conc.: 7

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 62.52 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 71.51 FT.
 D. Height of Water Column in casing (h = TD - SWL): 8.99 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 10:00

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
1015	6.59	196.2	6.71	24.01	2.445	62.72
1020	5.61	186.5	6.82	23.25	2.465	62.80
1025	5.50	178.1	6.86	23.40	2.454	62.03
1030	5.63	170.9	6.87	23.31	2.441	63.20
1035						
1040						
1045						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 1.5 gal

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH B20	1030	40.0 UOA (3)	NCI
TPH D20		1000ml Amber (2)	NCI
TD5, C1, C6+		1000ml Poly (1)	
COMMENTS: Fe, As, C, Mn		500.0 Poly (1)	

No color / 100 odor / 3.124

- Using Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 8.99 x 0.80 = (Total Depth of Well) 64.31

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-19-07 WELL NO. MW010

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 85 °F

FIELD PERSONNEL: J. Longwell / J. Francis WEATHER: Clear / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 39.31 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 64.58 FT.

D. Height of Water Column in casing (h = TD - SWL): 25.27 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1109

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1111	5.54	49.2	7.79	32.23	2.840	40.05
1116	9.00	69.8	6.45	29.88	7.807	39.89
1121	3.92	78.1	6.43	23.65	8.320	39.90
1126	3.88	85.1	6.47	23.67	8.179	39.80
1131	3.92	89.1	6.48	23.68	8.098	39.90
1136						
1141						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH/GRO	1131	40-L DRA (3)	HCl
TPH DRO		1000-ml Amber (2)	HCl
IDS, CI, C-6+		1000-ml Poly (12)	
COMMENTS: V-As, Cr, Mn		500-ml Poly (1)	

183 Hz
No Color / No Odor / Clear

Using Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 25.27 x 0.80 = -- (Total Depth of Well) 44.36

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-19-09 WELL NO. M2024

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 88 °F

FIELD PERSONNEL: J. Longwell / J. Premier WEATHER: Clear / Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 51.74 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 89.21 FT.

D. Height of Water Column in casing (h = TD - SWL): 37.97 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1700

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1704</u>	<u>4.39</u>	<u>71.5</u>	<u>6.87</u>	<u>32.88</u>	<u>2.294</u>	<u>52.07</u>
<u>1709</u>	<u>1.87</u>	<u>77.2</u>	<u>6.77</u>	<u>23.39</u>	<u>2.729</u>	<u>52.10</u>
<u>1714</u>	<u>1.37</u>	<u>78.7</u>	<u>6.77</u>	<u>22.75</u>	<u>2.823</u>	<u>52.10</u>
<u>1719</u>	<u>1.31</u>	<u>79.4</u>	<u>6.77</u>	<u>22.75</u>	<u>2.851</u>	<u>52.10</u>
<u>1724</u>	<u>1.29</u>	<u>79.5</u>	<u>6.76</u>	<u>22.75</u>	<u>2.876</u>	<u>52.10</u>
<u>1729</u>	_____	_____	_____	_____	_____	_____
<u>1734</u>	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>212X / TPA 670</u>	<u>1724</u>	<u>400cc DDA (3)</u>	<u>HCl</u>
<u>TPA DRO</u>	_____	<u>1000cc Amber (2)</u>	<u>HCl</u>
<u>TDS, Cl, Cr 6+</u>	_____	<u>1000cc Poly (1)</u>	_____
<u>COMMENTS: Fe, As, Cr, Mn</u>	_____	<u>500cc Poly (1)</u>	_____
<u>195 Hz</u>	<u>No Color / No Odor / Clear</u>	_____	_____

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 37.97 x 0.80 = — (Total Depth of Well) 58.85

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-19-09 WELL NO. MW058

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 89 °F

FIELD PERSONNEL: J. Longwell / J. Pomeroy WEATHER: Clear / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:

Standard 10 Reading: ORP: Standard: Reading: DO: °C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 56.52 FT.
 B. Thickness of Free Product, if present: Inches FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 116.8 FT.
 D. Height of Water Column in casing (h = TD - SWL): 54.62 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 1243

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1245	5.13	72.5	6.93	28.14	4765	57.02
1251	3.89	81.8	6.84	23.13	5.635	57.03
1256	3.67	83.2	6.85	22.74	5.758	57.08
1301	3.78	91.2	6.85	22.67	5.735	57.08
1306						
1311						
1316						
1321						

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH 620	1301	40cc VOA (3)	HCl
TPH DRO		1000cc Amber (2)	HCl
TDS, Cl, Cr 6+		1000cc Poly (1)	
COMMENTS: Fe, As, Cr, Mn		500cc Poly (1)	
(No Color / No Odor / Slight Silty 214 Hz) (Ag + Green @ Sample)			

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 54.62 x 0.80 = -- (Total Depth of Well) 67.48

Signature: 

DUP-101

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-19-03 WELL NO. MW061

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 92 °F

FIELD PERSONNEL: J. Langsford / J. Francis WEATHER: Clear / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:

Standard 10 Reading: ORP: Standard: Reading: DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 58.65 FT.
B. Thickness of Free Product, if present: Inches FT.
C. Total Depth of well (TD) from top of casing/piezometer: 110.66 FT.
D. Height of Water Column in casing (h = TD - SWL): 52.01 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 1345

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1348	2.33	4.7	6.80	29.93	5.810	58.89
1353	0.67	6.9	6.84	24.01	5.798	58.86
1358	0.59	12.0	6.87	23.69	5.805	58.86
1403	0.61	16.1	6.89	23.52	5.789	58.86
1408						
1413						
1418						

PURGE WATER STORED/DISPOSED OF WHERE/HOW:

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
TPH-620	1403	40-cc. NDA (3) + (3)	HCl
TPH-620		1000-ml Amber (2) + (2)	HCl
VDS, CI, C, G+		1000-ml Poly (1) + (1)	
COMMENTS: Fe, As, C, Mn		500-ml Poly (1) + (1)	

DUP-101 Lgt. Green Color / No Odor / Slight Silt

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 52.01 x 0.80 = -- (Total Depth of Well) 69.05

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-19-09 WELL NO. MW018

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 95 °F

FIELD PERSONNEL: J. Lowndes / J. Francis WEATHER: Clear / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 36.83 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 53.87 FT.
 D. Height of Water Column in casing (h = TD - SWL): 17.06 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1430

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1432</u>	<u>5.24</u>	<u>5.4</u>	<u>7.29</u>	<u>33.00</u>	<u>1.227</u>	<u>37.35</u>
<u>1437</u>	<u>6.09</u>	<u>21.9</u>	<u>6.85</u>	<u>24.14</u>	<u>2.056</u>	<u>37.49</u>
<u>1449</u>	<u>6.15</u>	<u>35.2</u>	<u>6.89</u>	<u>22.73</u>	<u>1.984</u>	<u>37.45</u>
<u>1447</u>	<u>6.22</u>	<u>40.9</u>	<u>6.90</u>	<u>22.52</u>	<u>1.989</u>	<u>37.47</u>
<u>1457</u>	<u>6.19</u>	<u>42.7</u>	<u>6.91</u>	<u>22.49</u>	<u>1.882</u>	<u>37.47</u>
<u>1457</u>						
<u>1502</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH 500</u>		<u>40-cc VOA (3)</u>	<u>HCl</u>
<u>TPH 500</u>		<u>1000-cc Amber @</u>	<u>HCl</u>
<u>DES, Cl, Cr 6+</u>		<u>1000-cc Poly (1)</u>	
<u>COMMENTS: Fe, As, Cr, Mn</u>		<u>500-cc Poly (1)</u>	
<u>No Color / No Odor / Clear</u>		<u>18.5 Hz</u>	

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 17.06 x 0.80 = -- (Total Depth of Well) 40.24

Signature: [Signature]

8/2008

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 3 April 2009 WELL NO. MW2062A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 98 °F

FIELD PERSONNEL: JPL WEATHER: Hot Clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 55.45 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 110.55 FT.

D. Height of Water Column in casing (h = TD - SWL): 55.01 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1446

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1448	7.80	60.4	7.30	26.22	0.791	58.94
1453	5.60	49.4	7.54	23.64	0.720	60.13
1458	5.48	49.3	7.52	24.57	0.722	59.21
1503	5.54	46.6	7.54	25.78	0.727	58.28

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
HEX-CI	1503	1	NONE
Metals		1	NONE
BTEX-GRO		3	HCl
TPH-DRO		2	HCl

COMMENTS: 224H2

Casing Capacities:
2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 55.01 x 0.80 = -- (Total Depth of Well) 66.54

Signature: JPL

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-4-09 WELL NO. MW263A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 95 °F

FIELD PERSONNEL: JF/SL WEATHER: Clear / HOT

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 56.05 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 108.56 FT.
 D. Height of Water Column in casing (h = TD - SWL): 52.51 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 12:40

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1242	6.22	90.4	7.28	30.12	0.781	58.03
1247	6.55	79.0	7.47	23.74	0.733	67.06
1252	5.19	77.1	7.48	24.24	0.728	67.06
1257	4.69	72.0	7.57	25.07	0.737	66.61
1302	5.07	64.9	7.57	25.11	0.735	66.50
1307	5.44	61.0	7.59	25.18	0.735	66.53
1312	5.63	64.1	7.56	25.34	0.734	59.00
1317						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
HOT-61	1312	1 1000ml / poly	NONE
METALS		1 500ml / poly	NONE
BTEX-620		3 40ml / vial	HCL
TH/PAH		2 1000ml / amber	HCL

COMMENTS: * STARTED AT 230 HZ ADJUSTED TO 195 HZ

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 52.51 x 0.80 = -- (Total Depth of Well) 66.55

Signature: JF

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-4-09 WELL NO. MW1013A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 98 °F

FIELD PERSONNEL: SP/L WEATHER: Hot / clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 43.30 FT.
 B. Thickness of Free Product, if present: _____ Inches 105.96 FT.
 C. Total Depth of well (TD) from top of casing/piezometer: _____ FT.
 D. Height of Water Column in casing (h = TD - SWL): 62.66 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1329

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1331</u>	<u>10.25</u>	<u>47.6</u>	<u>7.26</u>	<u>24.33</u>	<u>0.851</u>	<u>44.40</u>
<u>1336</u>	<u>7.26</u>	<u>56.6</u>	<u>7.32</u>	<u>23.20</u>	<u>0.883</u>	<u>51.94</u>
<u>1341</u>	<u>6.30</u>	<u>46.6</u>	<u>7.69</u>	<u>23.59</u>	<u>0.868</u>	<u>52.96</u>
<u>1346</u>	<u>6.33</u>	<u>65.4</u>	<u>7.28</u>	<u>23.77</u>	<u>0.855</u>	<u>53.49</u>
<u>1351</u>	<u>6.53</u>	<u>55.5</u>	<u>7.55</u>	<u>23.79</u>	<u>0.839</u>	<u>53.70</u>
<u>1356</u>	<u>6.55</u>	<u>52.9</u>	<u>7.58</u>	<u>23.78</u>	<u>0.828</u>	<u>53.84</u>
<u>1401</u>	<u>6.43</u>	<u>50.1</u>	<u>7.61</u>	<u>23.94</u>	<u>0.825</u>	<u>53.92</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hex</u>	<u>1401</u>	<u>1-1000ml poly</u>	<u>N/A</u>
<u>Metals</u>		<u>1-500ml poly</u>	<u>N/A</u>
<u>BTEX - TPH GTO</u>		<u>3-40ml vials</u>	<u>HCC</u>
<u>TPH - DRO</u>		<u>2-1000ml Amber</u>	<u>HCC</u>

COMMENTS: _____

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 62.66 x 0.80 = -- (Total Depth of Well) 55.83

Signature: JP

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8.4.09 WELL NO. MW031

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 100 °F

FIELD PERSONNEL: _____ WEATHER: Hot/CLEAR

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 59.58 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 76.99 FT.

D. Height of Water Column in casing (h = TD - SWL): 17.41 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1417

Time	DO (±10%)	ORP(±10mV)	pH(±0.1)	Temp.(±3%)	Conduct.(±3%)	SWL
<u>1419</u>	<u>7.87</u>	<u>34.7</u>	<u>7.29</u>	<u>26.22</u>	<u>0.887</u>	<u>60.91</u>
<u>1424</u>	<u>1.57</u>	<u>30.4</u>	<u>6.87</u>	<u>24.72</u>	<u>1.081</u>	<u>60.70</u>
<u>1429</u>	<u>0.86</u>	<u>16.9</u>	<u>6.92</u>	<u>24.78</u>	<u>1.077</u>	<u>60.68</u>
<u>1434</u>	<u>0.70</u>	<u>0.4</u>	<u>6.97</u>	<u>25.04</u>	<u>1.063</u>	<u>60.71</u>
<u>1439</u>	<u>0.69</u>	<u>-10.2</u>	<u>7.02</u>	<u>25.10</u>	<u>1.050</u>	<u>60.69</u>
<u>1444</u>	<u>0.57</u>	<u>-12.2</u>	<u>7.06</u>	<u>25.09</u>	<u>1.040</u>	<u>60.69</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 82 gal. inside plant @ seep.

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>Hotter</u>	<u>1444</u>	<u>1-1000ml P</u>	<u>N/A</u>
<u>Metals</u>		<u>1-500ml P</u>	<u>N/A</u>
<u>BTEX-TPH GRO</u>		<u>3-40ml V</u>	<u>HCL</u>
COMMENTS: <u>TPH DRO</u>		<u>2-1000ml A</u>	<u>HCL</u>

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 17.41 x 0.80 = -- (Total Depth of Well) 63.06

Signature: J.P.

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201,250 DATE: 8-6-09 WELL NO. MW021A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90 °F

FIELD PERSONNEL: ASL / AB WEATHER: Clear / Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading 7.00 ; Standard 4 Reading: 400

Standard 10 Reading: 10.06 ; ORP: Standard: 280 Reading: 239.9; DO: T°C: 35.78 mmHg: 6.12 DO Conc.: X

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.46 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 87.50 FT.
- D. Height of Water Column in casing (h = TD - SWL): 41.04 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:	Purging Start Time: <u>11:54</u>						
Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL	
<u>11:55</u>	<u>8.30</u>	<u>195.8</u>	<u>6.49</u>	<u>27.29</u>	<u>7.590</u>	<u>51.64</u>	
<u>12:00</u>	<u>2.00</u>	<u>173.6</u>	<u>6.53</u>	<u>23.33</u>	<u>11.72</u>	<u>53.95</u>	
<u>12:05</u>	<u>1.69</u>	<u>160.1</u>	<u>6.55</u>	<u>23.49</u>	<u>13.81</u>	<u>54.03</u>	
<u>12:10</u>	<u>1.15</u>	<u>149.2</u>	<u>6.53</u>	<u>24.01</u>	<u>15.71</u>	<u>54.08</u>	
<u>12:15</u>	<u>1.04</u>	<u>138.8</u>	<u>6.51</u>	<u>24.36</u>	<u>16.72</u>	<u>54.14</u>	
<u>12:20</u>	<u>0.96</u>	<u>129.1</u>	<u>6.51</u>	<u>24.63</u>	<u>17.40</u>	<u>54.19</u>	
<u>12:25</u>	<u>0.96</u>	<u>120.9</u>	<u>6.51</u>	<u>24.63</u>	<u>17.74</u>	<u>54.23</u>	
<u>12:30</u>	<u>0.88</u>	<u>113.8</u>	<u>6.52</u>	<u>24.76</u>	<u>18.00</u>	<u>54.25</u>	

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>1ST EX / TAP H GRO</u>	<u>12:30</u>	<u>400cc VOA (3)</u>	<u>HCl</u>
<u>TAP H DRO</u>	<u>12:30</u>	<u>(400cc) 2000cc Amber (2)</u>	<u>HCl</u>
<u>Fe, As, C, Mn</u>	<u>12:30</u>	<u>500cc Poly (1)</u>	<u>---</u>
<u>TD, Cl, C-6</u>	<u>12:30</u>	<u>1000cc Poly (1)</u>	<u>---</u>
COMMENTS: <u>186 Hz No Color / No Odor / Clear</u>			

Casing Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft.
- 8-inch hole.....2.60 gal/in ft.
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 46.04 x 0.80 = --- (Total Depth of Well) 54.66

Signature: DBL

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-6-09 WELL NO. Mwoz1

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90° °F

FIELD PERSONNEL: La 1 SL WEATHER: Clear Hot

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 45.77 FT.
 B. Thickness of Free Product, if present: _____ Inches 0 FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 62.38 FT.
 D. Height of Water Column in casing (h = TD - SWL): 16.61 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1243

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1243	1.32	101.4	6.48	25.18	18.58	46.37
1244	1.32	52.5	7.07	23.38	2.291	47.03
1254	1.03	53.2	7.01	23.08	2.001	47.08
1259	1.08	93.4	6.99	23.25	2.025	47.08
1304	1.06	53.1	6.97	23.36	2.060	47.09
1309	1.02	52.5	6.95	23.05	2.086	47.10

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1310		

COMMENTS:

186 1/2 on White Box

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 16.61 x 0.80 = - (Total Depth of Well) 49.1

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-6-09 WELL NO: W032

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90 °F

FIELD PERSONNEL: JLS WEATHER: Clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 62.00 FT.
- B. Thickness of Free Product, if present: _____ Inches 0 FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 68.76 FT.
- D. Height of Water Column in casing (h = TD - SWL): _____ FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 13:27

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1329	4.59	54.0	7.01	27.68	1.868	
1334	7.10	49.7	7.15	28.61	1.305	61.84
1339	7.52	54.1	7.06	30.53	1.306	61.73
1344	7.12	65.89	7.02	31.21	1.487	61.68
1349	6.74	69.5	7.02	31.50	1.571	61.64
1354						
1359						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1356		

COMMENTS: No Color/Clarity (13:53 well pumped & off) 193 1/2 on Relief Box

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 6.76 x 0.80 = -- (Total Depth of Well) 63.36

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-6-09 WELL NO: Hw066sk

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90° °F

FIELD PERSONNEL: A/SJ WEATHER: Hazy Clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ :pH Standard: 7 Reading: _____ :Standard 4 Reading: _____

Standard 10 Reading: _____ : ORP: Standard: _____ Reading: _____ : DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ :pH 7: _____ :pH 4: _____ :pH: 10 _____ :ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: _____

B. Thickness of Free Product, if present: _____ Inches

C. Total Depth of well (TD) from top of casing/piezometer: _____

D. Height of Water Column in casing (h = TD - SWL): _____

49.32
~~49.83~~ FT.
0 FT.
68.74 FT.
_____ FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 14:23

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
14:24	9.23	29.5	6.92	32.39	1.775	49.83
14:29	1.60	40.4	6.56	24.07	4.352	50.19
14:34	1.22	39.7	6.59	23.96	4.353	50.19
14:39	0.88	35.1	6.61	23.93	4.347	50.20
14:44	0.78	32.7	6.63	24.32	4.339	50.21
14:49	0.80	30.1	6.63	24.41	4.352	50.21

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	14:51		

COMMENTS: 182.70 MZ, No Color. Clear No odor

Casing Capacities:
2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 19.42 x 0.80 = (Total Depth of Well) 53.21

Signature: _____

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-6-09 WELL NO: W0655A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90°F

FIELD PERSONNEL: J. SL WEATHER: hot clear

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.32 FT.
 B. Thickness of Free Product, if present: _____ Inches 0 FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 82.27 FT.
 D. Height of Water Column in casing (h = TD - SWL): _____ FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1516

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1519	6.83	39.5	6.73	26.95	3.998	51.59
1524	8.87	54.1	6.86	27.06	4.155	51.83
1529	8.58	62.6	6.90	23.95	4.155	51.85
1534	8.29	69.8	6.93	23.95	4.132	51.87
1539	8.29	77.5	6.93	23.78	4.125	51.87
1544	8.29	79.2	6.93	23.74	4.130	51.87

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 160 gal @ pump inside plant

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
	1546		

COMMENTS: 185.2 MHz as per hole (B.V.)

Casing Capacities:

- 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 26.95 x 0.80 = 21.56 (Total Depth of Well) 57.51

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-10-09 WELL NO. MW0715A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90 °F

FIELD PERSONNEL: ISH WEATHER: Clear / Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH 10: _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 49.83 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 91.21 FT.
- D. Height of Water Column in casing (h = TD - SWL): 41.38 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1313

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct (±3%)	SWL
<u>1314</u>	<u>4.23</u>	<u>73.2</u>	<u>6.78</u>	<u>32.81</u>	<u>4.125</u>	<u>49.80</u>
<u>1319</u>	<u>0.89</u>	<u>67.2</u>	<u>6.51</u>	<u>22.91</u>	<u>3.725</u>	<u>49.80</u>
<u>1324</u>	<u>0.79</u>	<u>62.5</u>	<u>6.55</u>	<u>22.80</u>	<u>3.799</u>	<u>49.79</u>
<u>1329</u>	<u>0.93</u>	<u>57.8</u>	<u>6.58</u>	<u>22.76</u>	<u>3.872</u>	<u>49.80</u>
<u>1334</u>	<u>0.74</u>	<u>57.4</u>	<u>6.58</u>	<u>22.63</u>	<u>3.900</u>	<u>49.80</u>
<u>1339</u>	<u>0.62</u>	<u>56.7</u>	<u>6.55</u>	<u>22.70</u>	<u>3.921</u>	<u>49.80</u>
<u>1344</u>	<u>0.59</u>	<u>54.2</u>	<u>6.56</u>	<u>22.64</u>	<u>3.907</u>	<u>49.80</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH GRO</u>	<u>1344</u>	<u>40-cc VOA (3)</u>	<u>HCl</u>
<u>TPH GRO</u>	<u>S</u>	<u>1000-cc Amber (2)</u>	<u>HCl</u>
<u>Fe, As, Cu, Mn</u>	<u>S</u>	<u>500-cc Poly (1)</u>	<u>None</u>
<u>COMMENTS: TO5, Cl, C-6+</u>	<u>S</u>	<u>1000-cc Poly (1)</u>	<u>None</u>
<u>@ 1315 Shallow Entry</u>	<u>S</u>	<u>1 No Color / No ODO</u>	<u>185-Alt</u>

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 41.38 x 0.80 = -- (Total Depth of Well) 57.77

Signature: [Signature]

DUP-100

Stantec
GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-10-09 WELL NO. MW08654

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 92 °F

FIELD PERSONNEL: Jerry S. Lonswell WEATHER: Clear/Cal

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:

Standard 10 Reading: ORP: Standard: Reading: DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH 10: ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.67 FT.
- B. Thickness of Free Product, if present: Inches FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 92.79 FT.
- D. Height of Water Column in casing (h = TD - SWL): 42.12 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS: Purging Start Time: 1359

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1400	5.31	72.6	6.58	25.07	4.755	50.72
1405	3.12	74.3	6.62	22.23	5.834	50.72
1410	2.43	73.2	6.66	22.32	5.741	50.71
1415	2.41	71.6	6.68	22.34	5.683	50.71
1420						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 123 gal @ samp inside plant

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH + G20	1415	40cc VOA (3)	HCl
TPH D20	S	1,000cc A-ba (2)	HCl
Fe, Pb, Cr, Mn		500cc Poly (1)	
COMMENTS: TDS, Cl, Cr, Pb		1,000cc Poly (1)	

185 Hz No Color / No Odor / Clear

DUP-100

Casing Capacities:
2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
Collect sample when Depth to Water measures Less than or equal to:
Original Water Column: 42.12 x 0.80 = (Total Depth of Well) 59.0 ft

Signature: [Signature] 8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-11-09 WELL NO. 20023

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90°F

FIELD PERSONNEL: Steve Bell / Jerry Lowndes WEATHER: Clear / Calm

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 9.99 ; ORP: Standard: 240 Reading: 240.0 ; DO: T°C: 28.33 mmHg: 7.06 DO Conc.: X

End-of-Day Recheck: Spec. Cond.: pH 7: pH 4: pH: 10 :ORP:

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 47.33 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 100.53 FT.

D. Height of Water Column in casing (h = TD - SWL): 53.20 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1138

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1147	6.31	114.4	6.54	23.63	3.792	47.31
1147	4.07	107.5	6.65	23.44	3.768	47.30
1152	3.94	106.0	6.70	23.80	3.785	47.33
1157	3.69	103.3	6.71	23.43	3.766	47.31
1202	3.73	100.8	6.73	23.90	3.778	47.32
1207	3.71	97.7	6.74	23.41	3.778	47.32

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 1.0 gal.

SAMPLES COLLECTED: No Color / No Odor / Clear

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTX / TPH BRO	1207	40L OBP (3)	HCl
TPH BRO		1000L Amber (2)	HCl
Fe, As, Cr, Mn		300mL Poly (1)	NEAT
COMMENTS: TDS, Cl, C-6+		1000L Poly (1)	NEAT
PH, DO		1000L Poly (1)	NEAT
ALL		500L Poly (2)	NEAT
Sulfide		500L Amber (1)	Sodium Hydroxide / Zn Acet.
VOL		125L Amber (1)	HPO4

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 53.20 x 0.80 = -- (Total Depth of Well) 57.97

Signature: JBL

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-11-09 WELL NO. 22027

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 95 °F

FIELD PERSONNEL: Steve Bell & Terry S. Longwell WEATHER:

EQUIPMENT CALIBRATION: YSI QED Serial No.:

Spec. Conductivity: Standard: Reading: pH Standard: 7 Reading: Standard 4 Reading:

Standard 10 Reading: ORP: Standard: Reading: DO: T°C: mmHg: DO Conc.:

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 47.45 FT.
- B. Thickness of Free Product, if present: Inches FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 102.03 FT.
- D. Height of Water Column in casing (h = TD - SWL): 54.58 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION:

OBSERVATIONS:

Purging Start Time: 1321

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1325	3.50	93.1	6.51	27.76	4.703	47.41
1330	2.12	94.3	6.63	27.97	5.623	47.43
1335	1.91	91.2	6.71	28.36	5.770	47.46
1340	1.71	87.6	6.70	28.57	5.834	47.48
1345	1.62	86.7	6.74	28.32	5.819	47.43
1350	1.58	88.5	6.75	26.30	5.811	47.43

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 1.0 gal

SAMPLES COLLECTED:

2 1/2 Gallons / No Oils / Clear

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
Well Sediment	1350		

COMMENTS:

2 Cpm @ 15+15 50 psi

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft.
- 8-inch hole.....2.60 gal/in ft.
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 54.58 x 0.80 = (Total Depth of Well) 58.63

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-11-09 WELL NO. MW0903A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 98 °F

FIELD PERSONNEL: _____ WEATHER: Cloudy / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 48.98 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 103.49 FT.

D. Height of Water Column in casing (h = TD - SWL): 54.51 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1453

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
<u>1456</u>	<u>5.54</u>	<u>48.2</u>	<u>6.83</u>	<u>28.39</u>	<u>3.452</u>	<u>NR</u>
<u>1501</u>	<u>3.80</u>	<u>49.2</u>	<u>6.79</u>	<u>24.27</u>	<u>4.904</u>	<u>48.98</u>
<u>1506</u>	<u>3.42</u>	<u>52.6</u>	<u>6.83</u>	<u>25.48</u>	<u>4.469</u>	<u>48.95</u>
<u>1511</u>	<u>3.09</u>	<u>54.9</u>	<u>6.82</u>	<u>24.76</u>	<u>4.509</u>	<u>48.95</u>
<u>1516</u>	<u>3.88</u>	<u>56.2</u>	<u>6.83</u>	<u>25.05</u>	<u>4.500</u>	<u>48.95</u>
<u>1521</u>	<u>3.42</u>	<u>58.6</u>	<u>6.82</u>	<u>24.52</u>	<u>4.466</u>	<u>48.95</u>
<u>1526</u>	<u>4.27</u>	<u>62.1</u>	<u>6.82</u>	<u>23.52</u>	<u>4.493</u>	<u>48.98</u>
<u>1531</u>	<u>4.27</u>	<u>67.9</u>	<u>6.80</u>	<u>23.08</u>	<u>4.491</u>	<u>48.95</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 1.2 gal

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>1st Sample</u>	<u>1531</u>	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

COMMENTS:

1st Sample / No odor / Clear

Casing Capacities:

2-inch hole.....0.16 gal/in ft.
4-inch hole.....0.65 gal/in ft.
6.5-inch hole.....1.70 gal/in ft.
8-inch hole.....2.60 gal/in ft.
10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 54.51 x 0.80 = -- (Total Depth of Well) 59.48

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-13-09 WELL NO. IW025

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 88 °F

FIELD PERSONNEL: J Longwell / S Gonzales WEATHER: light breeze, sunny, warm

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.44 FT.
 B. Thickness of Free Product, if present: _____ Inches FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 99.08 FT.
 D. Height of Water Column in casing (h = TD - SWL): 50.64 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1237

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1246	1.73	-223.6	6.57	29.22	3.565	*
1251	1.86	-260.1	6.44	28.01	4.105	
1256	1.97	-283.3	6.40	27.13	4.248	
1301	3.25	-284.7	6.41	24.77	4.260	
1306	3.52	-285.7	6.40	24.67	4.255	
1311	3.61	-288.7	6.41	25.15	4.222	
1316	4.00	-291.1	6.41	24.70	4.248	
1321	3.86	-290.0	6.40	25.44	4.247	

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 10 gal

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
F ₁ , P ₁ , C ₁ , M ₁ , N ₁	1321		

COMMENTS:

* Unable gauge water level bk of milky/chalky substance on probe.

Casing Capacities:

2-inch hole.....	0.16 gal/in ft.
4-inch hole.....	0.65 gal/in ft.
6.5-inch hole.....	1.70 gal/in ft.
8-inch hole.....	2.60 gal/in ft.
10-inch hole.....	4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 50.64 x 0.80 = 58.51 (Total Depth of Well) 56

Signature: Sergio Gonzales

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8/13/09 WELL NO. MW0845A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 94 °F

FIELD PERSONNEL: J Longwell / S Gonzales WEATHER: light breeze, warm, sunny

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 48.98 FT.
 B. Thickness of Free Product, if present: _____ Inches FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 103.49 FT.
 D. Height of Water Column in casing (h = TD - SWL): 54.51 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1446

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1449	252.3	-46.3	6.69	25.53	7.121	51.38
1454	252.3	-51.8	6.65	24.08	8.114	51.38
1459	11.90	-52.2	6.67	24.62	8.190	51.39
1504	11.11	-48.6	6.68	24.85	8.238	51.38
1509	10.97	-40.7	6.69	24.77	8.202	51.38
1514	10.71	-49.0	6.70	24.93	7.967	51.38
1519	10.81	-36.5	6.74	24.49	7.583	51.40
1524	10.84	-30.3	6.74	24.63	7.477	51.40
1529	10.78	-32.7	6.75	24.85	7.377	51.39

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 1.5 gal Disposed @ pump on site

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH/GC	1529	40 ml vial (3)	HCL
TPH/DRO		1000 ml amber (2)	HCL
Fe, As, Cr, Mn, Na		500 ml poly (1)	Heat
		1000 ml poly (1)	Heat

COMMENTS: TDS, Cl, Cr 6+
Clear, odorless

* Note DO reading is in percent @ 1449

Casing Capacities:

2-inch hole.....	0.16 gal/lin ft.
4-inch hole.....	0.65 gal/lin ft.
6.5-inch hole.....	1.70 gal/lin ft.
8-inch hole.....	2.60 gal/lin ft.
10-inch hole.....	4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 54.51 x 0.80 = 43.61 (Total Depth of Well) 59.88

Signature: _____

S. Gonzales

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-17-09 WELL NO. MW064.SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 82 °F

FIELD PERSONNEL: Ferry, J. Langwell WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading: 7.00 Standard 4 Reading: 4.07

Standard 10 Reading: 998 ; ORP: Standard: 240 Reading: 240.0 DO: T°C 26.90 mmHg: 7.20 DO Conc.:

End-of-Day Recheck: Spec. Cond.: pH 7: pH 4: pH: 10 :ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: _____ FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: _____ FT.
 D. Height of Water Column in casing (h = TD - SWL): _____ FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: _____

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
0944	5.66	173.6	6.49	21.87	4.629	51.04
0949	3.86	167.2	6.59	22.63	5.126	51.04
0954	6.90	153.5	6.66	23.00	5.173	51.04
0959	6.79	143.9	6.70	23.64	5.160	51.04
1004	7.60	138.5	6.73	23.38	5.099	51.04
1009	7.89	136.5	6.74	23.08	5.082	51.04
1014						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH / GRO	1009	40cc VOA (3)	12CI
TPH / DRO		100cc TPH (2)	12CI
TPH, CI, Cr, Pb		180cc Poly (1)	
COMMENTS: Fe, As, Cr, Mn		500cc Poly (1)	

No Color / No Odor / Clear & Air pumping into flow cell &

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: _____ x 0.80 = ____ (Total Depth of Well)

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-17-09 WELL NO. MW085 SA

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 85 °F

FIELD PERSONNEL: Jerry S. Longwell WEATHER: Clear / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 51.79 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 77.80 FT.

D. Height of Water Column in casing (h = TD - SWL): 26.01 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1030

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1033</u>	<u>3.90</u>	<u>-138.2</u>	<u>6.84</u>	<u>22.45</u>	<u>4.933</u>	<u>51.84</u>
<u>1038</u>	<u>2.40</u>	<u>-122.7</u>	<u>6.74</u>	<u>23.08</u>	<u>5.613</u>	<u>51.80</u>
<u>1043</u>	<u>4.45</u>	<u>-108.2</u>	<u>6.71</u>	<u>23.51</u>	<u>5.887</u>	<u>51.81</u>
<u>1048</u>	<u>4.12</u>	<u>-99.8</u>	<u>6.71</u>	<u>23.71</u>	<u>5.932</u>	<u>51.80</u>
<u>1053</u>	<u>4.19</u>	<u>-80.0</u>	<u>6.70</u>	<u>23.19</u>	<u>5.995</u>	<u>51.79</u>
<u>1058</u>	<u>4.23</u>	<u>-73.2</u>	<u>6.70</u>	<u>23.54</u>	<u>6.018</u>	<u>51.79</u>
<u>1103</u>	<u>4.43</u>	<u>-69.7</u>	<u>6.70</u>	<u>23.84</u>	<u>6.001</u>	<u>51.79</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 0.5 gal in sample on site

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH 670</u>	<u>1103</u>	<u>40ml VOA (3)</u>	<u>HCl</u>
<u>TPH 670</u>	<u> </u>	<u>1000µl Amber (2)</u>	<u>HCl</u>
<u>TPS, CI, C, 6+</u>	<u> </u>	<u>100µl Poly (1)</u>	<u> </u>
<u>Fe, As, C, Mn</u>	<u> </u>	<u>200-µl Poly (1)</u>	<u> </u>

COMMENTS: Light Brown / Very Strong Odor / Clear
(R-01036 No Color)

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 26.01 x 0.80 = (Total Depth of Well) 56.99

Signature: _____

Stantec

PROJECT NO.: 212201135 201.250 DATE: 8-17-09 WELL NO. MW0835A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 87 °F

FIELD PERSONNEL: Ferry S. Longwell WEATHER: clear/Slight Breeze

EQUIPMENT CALIBRATION: (YSI) QED Serial No.: _____

Spec. Conductivity: Standard: Reading: ;pH Standard: 7 Reading ;Standard 4 Reading:

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec.Cond: _____; pH 7: _____; pH 4: _____; pH: 10 _____; ORP: _____

FIELD MEASUREMENTS:

A. Static Water Level (SWL) below top of casing/piezometer: 51.91 FT.

B. Thickness of Free Product, if present: _____ Inches _____ FT.

C. Total Depth of well (TD) from top of casing/piezometer: 78.01 FT.

D. Height of Water Column in casing ($h = TD - SWL$): 76.10 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS:

Purging Start Time: 1127

<u>Time</u>	<u>DO ($\pm 10\%$)</u>	<u>ORP ($\pm 10\text{mV}$)</u>	<u>pH (± 0.1)</u>	<u>Temp. ($\pm 3\%$)</u>	<u>Conduct. ($\pm 3\%$)</u>	<u>SWL</u>
1130	9.72	-3.9	6.52	23.74	5.280	51.92
1135	6.22	-30.1	6.54	24.38	5.582	51.91
1140	6.78	-32.3	6.56	25.14	5.741	51.80
1145	6.84	-34.7	6.92	24.74	5.856	51.80
1150	6.05	-35.2	6.56	25.10	5.872	51.90
1155	5.80	-38.1	6.57	25.15	5.896	51.90
1700	5.25	-38.0	6.57	25.20	5.899	51.80
1205						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX LTPH 620	1200	400.c JOP (3)	HCC
LTPH 220	S	1000.c Amber (2)	HCI
IDS, CI, Cc 6x		1000.c Poly (1)	—
COMMENTS: Fe, As, C, Mn		500.c Poly (1)	—
Lgt. Brown / Strong Odor		/ Clear	

Increasing Capacities:

2-inch hole.....0.16 gal/in ft. .

1/2-inch hole.....	0.65 gal/lin ft. .
--------------------	--------------------

5.5-inch hole.....1.70 gal/in ft

1/2-inch hole.....	2.60 gal/lin ft
--------------------	-----------------

0-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 26.10 x 0.80 = — (Total Depth of Well) 57.13

Signature: _____

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-17-09 WELL NO. MW0825A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90 °F

FIELD PERSONNEL: Terry S. Longwell WEATHER: Clear / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 51.87 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 77.91 FT.
- D. Height of Water Column in casing (h = TD - SWL): 25.94 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1237

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1241</u>	<u>7.37</u>	<u>-119.4</u>	<u>6.64</u>	<u>25.49</u>	<u>4.931</u>	<u>52.05</u>
<u>1246</u>	<u>6.24</u>	<u>-82.3</u>	<u>6.57</u>	<u>23.75</u>	<u>5.650</u>	<u>52.02</u>
<u>1251</u>	<u>4.82</u>	<u>-77.6</u>	<u>6.60</u>	<u>25.77</u>	<u>5.708</u>	<u>52.00</u>
<u>1256</u>	<u>4.56</u>	<u>-72.0</u>	<u>6.60</u>	<u>26.43</u>	<u>5.739</u>	<u>52.00</u>
<u>1301</u>	<u>4.21</u>	<u>-68.7</u>	<u>6.61</u>	<u>26.80</u>	<u>5.743</u>	<u>52.00</u>
<u>1306</u>	<u>4.50</u>	<u>-62.7</u>	<u>6.61</u>	<u>25.43</u>	<u>5.799</u>	<u>52.00</u>
<u>*Comp. 1308</u>	<u>4.12</u>	<u>-59.8</u>	<u>6.62</u>	<u>27.63</u>	<u>5.746</u>	<u>51.99</u>
<u>1315</u>	<u>4.23</u>	<u>-54.9</u>	<u>6.62</u>	<u>27.64</u>	<u>5.784</u>	<u>51.99</u>

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTX / TPH 620</u>	<u>1320</u>	<u>90ml WOA (3)</u>	<u>HCl</u>
<u>TPH D20</u>	<u>1320</u>	<u>1000-ml Amber (2)</u>	<u>HCl</u>
<u>TDS, Cl, Cr, Cu</u>	<u>1320</u>	<u>1000-ml Poly (1)</u>	<u>—</u>
<u>COMMENTS: Fe, As, C, Mn</u>	<u>1320</u>	<u>500-ml Poly (1)</u>	<u>—</u>

Lgt. Brown / Strong Odor / Clear * @ 1308 Compressor - Quilted *
it is getting less hot

Casing Capacities:

2-inch hole.....0.16 gal/lin ft.
4-inch hole.....0.65 gal/lin ft.
6.5-inch hole.....1.70 gal/lin ft.
8-inch hole.....2.60 gal/lin ft.
10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 25.94 x 0.80 = — (Total Depth of Well) 57.15

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-18-07 WELL NO. MW0795A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 85 °F

FIELD PERSONNEL: J. Longwell / J. Pomeroy WEATHER: Clear / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: 076100513

Spec. Conductivity: Standard: 1413 Reading: 1413 pH Standard: 7 Reading 7.00 Standard 4 Reading: 4.00

Standard 10 Reading: 9.99 ORP: Standard: 240 Reading: 240 DO: T°C: 28.50 mmHg: 7.02 DO Conc.: X

End-of-Day Recheck: Spec. Cond: pH 7: pH 4: pH: 10 ORP:

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.55 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 69.77 FT.
- D. Height of Water Column in casing (h = TD - SWL): 23.22 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1034

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp (±3%)	Conduct (±3%)	SWL
1037	3.70	85.1	6.53	24.30	1.900	46.62
1042	1.79	50.5	6.69	25.04	1.851	46.62
1047	1.54	34.8	6.76	26.35	1.843	46.65
1052	1.82	24.6	6.78	27.04	1.846	46.65
1057	3.89	15.4	6.79	26.36	1.839	46.65
1102	4.36	11.0	6.79	26.36	1.834	46.63
1107	3.45	6.6	6.80	26.44	1.831	46.63
1112	3.55	3.3	6.81	26.38	1.830	46.63
1117	3.41	3.0	6.82	28.57	1.825	46.64

PURGE WATER STORED/DISPOSED OF WHERE/HOW: 1.0 gal

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BIEX / TPH 600	1117	400cc 10A (3)	HCl
TPH DRO		1000cc Amber (2)	HCl
TPS, Cl, O, G+		1000cc Poly (1)	
COMMENTS: Fe, As, Cr, Mn		500cc Poly (1)	

1st Brown @ first then no color / slight odor / clear

Casing Capacities:

2-inch hole.....	0.16 gal/in ft.
4-inch hole.....	0.65 gal/in ft.
6.5-inch hole.....	1.70 gal/in ft.
8-inch hole.....	2.60 gal/in ft.
10-inch hole.....	4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 23.22 x 0.80 = -- (Total Depth of Well) 51.19

Signature: _____

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-18-09 WELL NO. MW080.5A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 87 °F

FIELD PERSONNEL: T. Longwell / J. Peemont WEATHER: Clear / B. Blue Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH 10: _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.66 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 71.85 FT.
 D. Height of Water Column in casing (h = TD - SWL): 25.19 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1137

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1139</u>	<u>8.86</u>	<u>71.9</u>	<u>6.84</u>	<u>26.78</u>	<u>1.757</u>	<u>46.72</u>
<u>1144</u>	<u>6.00</u>	<u>75.1</u>	<u>6.95</u>	<u>24.76</u>	<u>1.728</u>	<u>46.72</u>
<u>1149</u>	<u>5.45</u>	<u>79.2</u>	<u>7.03</u>	<u>25.97</u>	<u>1.733</u>	<u>46.73</u>
<u>1154</u>	<u>5.55</u>	<u>81.6</u>	<u>7.02</u>	<u>25.71</u>	<u>1.731</u>	<u>46.74</u>
<u>1159</u>						
<u>1204</u>						
<u>1209</u>						
<u>1214</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: < 0.5

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH 600</u>	<u>1154</u>	<u>40cc, CDA (3)</u>	<u>HCl</u>
<u>TPH DRO</u>	<u>5</u>	<u>1000cc Amber (2)</u>	<u>HCl</u>
<u>TPS, CI, C-6+</u>		<u>1000cc Poly (1)</u>	<u>-</u>
<u>COMMENTS: Fe, As, Cr, Mn</u>		<u>500cc Poly (1)</u>	<u>-</u>

No Color / No Odor / Clear

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 25.19 x 0.80 = -- (Total Depth of Well) 51.69

Signature: DSU

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-18-09 WELL NO. MW0815A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90 °F

FIELD PERSONNEL: Tikousue / Ti Pomico WEATHER: Clear / Slight Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ ; pH Standard: 7 Reading: _____ ; Standard 4 Reading: _____

Standard 10 Reading: _____ ; ORP: Standard: _____ Reading: _____ ; DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ ; pH 7: _____ ; pH 4: _____ ; pH: 10 _____ ; ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.23 FT.
 B. Thickness of Free Product, if present: _____ Inches _____ FT.
 C. Total Depth of well (TD) from top of casing/piezometer: 72.41 FT.
 D. Height of Water Column in casing (h = TD - SWL): 26.18 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1218

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
<u>1220</u>	<u>1.98</u>	<u>62.5</u>	<u>6.66</u>	<u>23.35</u>	<u>2.407</u>	<u>46.36</u>
<u>1225</u>	<u>1.27</u>	<u>61.0</u>	<u>6.79</u>	<u>24.96</u>	<u>2.392</u>	<u>46.31</u>
<u>1230</u>	<u>1.10</u>	<u>53.0</u>	<u>6.92</u>	<u>25.26</u>	<u>2.402</u>	<u>46.30</u>
<u>1235</u>	<u>1.07</u>	<u>47.8</u>	<u>6.83</u>	<u>26.77</u>	<u>2.415</u>	<u>46.30</u>
<u>1240</u>						
<u>1245</u>						
<u>1250</u>						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
<u>BTEX / TPH GRO</u>	<u>1235</u>	<u>400cc J09 (B)</u>	<u>HCl</u>
<u>TPH DRO</u>		<u>1000cc Amber (D)</u>	<u>HCl</u>
<u>DD, CH, C, G, +</u>		<u>1000cc Poly (L)</u>	
<u>COMMENTS: Fe, As, Cr, Mn</u>		<u>500cc Poly (L)</u>	

1st Brown, No 2nd - 1st Clear

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
 4-inch hole.....0.65 gal/in ft.
 6.5-inch hole.....1.70 gal/in ft.
 8-inch hole.....2.60 gal/in ft.
 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 26.18 x 0.80 = -- (Total Depth of Well) 51.46

Signature: [Signature]

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-18-09 WELL NO. 60PW22

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 90 °F

FIELD PERSONNEL: A. Longwell / J. Pomeroy WEATHER: Clear / Breezy

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 46.44 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 87.60 FT.
- D. Height of Water Column in casing (h = TD - SWL): 40.66 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1329

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1329	3.21	-90.8	7.36	28.83	4.254	46.38
1334	1.76	-121.8	7.42	28.02	4.203	46.43
1339	0.84	-120.6	7.41	28.29	4.206	46.49
1343	0.68	-120.1	7.40	28.37	4.211	46.50
1349						
1353						
1359						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTX / TPH GRO	1343	40cc UOA (3)	NCI
TPH DRO		100cc Amber (2)	NCI
BDS, Cl, Cr, Gr		100cc Poly (1)	—
COMMENTS: Fe, As, Cr, Mn		500cc Poly (1)	—

Light Brown / Strong Odor / No Heavy

Using Capacities:

- 2-inch hole.....0.16 gal/in ft.
- 4-inch hole.....0.65 gal/in ft.
- 6.5-inch hole.....1.70 gal/in ft.
- 8-inch hole.....2.60 gal/in ft.
- 10-inch hole.....4.10 gal/in ft.

Recharge Calculation at Time of Sample Collection:

Collect sample when Depth to Water measures Less than or equal to:

Original Water Column: 40.66 x 0.80 = -- (Total Depth of Well) 58.57

Signature: _____

8/2008

Stantec

GROUNDWATER SAMPLING FIELD DATA SHEET

PROJECT NO.: 212201135 201.250 DATE: 8-18-09 WELL NO. MW0725A

FACILITY NAME: Eunice North Gas Plant TEMPERATURE: 96 °F

FIELD PERSONNEL: J. Langwell / J. Penner WEATHER: Clear / Slight Breeze

EQUIPMENT CALIBRATION: YSI QED Serial No.: _____

Spec. Conductivity: Standard: _____ Reading: _____ pH Standard: 7 Reading: _____ Standard 4 Reading: _____

Standard 10 Reading: _____ ORP: Standard: _____ Reading: _____ DO: T°C: _____ mmHg: _____ DO Conc.: _____

End-of-Day Recheck: Spec. Cond: _____ pH 7: _____ pH 4: _____ pH: 10 _____ ORP: _____

FIELD MEASUREMENTS:

- A. Static Water Level (SWL) below top of casing/piezometer: 50.49 FT.
- B. Thickness of Free Product, if present: _____ Inches _____ FT.
- C. Total Depth of well (TD) from top of casing/piezometer: 93.60 FT.
- D. Height of Water Column in casing (h = TD - SWL): 43.11 FT.

PURGING METHOD: Grundfos Bladder Peristaltic Fultz DURATION: _____

OBSERVATIONS: Purging Start Time: 1440

Time	DO (±10%)	ORP (±10mV)	pH (±0.1)	Temp. (±3%)	Conduct. (±3%)	SWL
1443	1.37	-3.5	6.86	29.97	4.003	50.50
1448	1.93	1.7	6.88	26.01	4.234	50.48
1453	2.74	16.4	6.93	23.89	3.928	50.48
1458	2.85	29.0	6.92	23.58	3.917	50.50
1503	2.83	35.4	6.91	23.48	3.907	50.48
1508	2.86	37.0	6.93	23.51	3.904	50.48
1513						

PURGE WATER STORED/DISPOSED OF WHERE/HOW: _____

SAMPLES COLLECTED:

Sample Number(s)	Time	Size/Number of Container(s)	Preservative
BTEX / TPH 670	1508	40cc 00A (3)	HCl
TPH DRO		1000cc Amber (2)	HCl
TDS, Cl, Cr 6+		1000cc Poly (1)	
COMMENTS: Fe, As, Cr, Mn		500cc Poly (1)	

190 Hz
No Colo. / No Odor / Slight Gassy

Casing Capacities:
 2-inch hole.....0.16 gal/lin ft.
 4-inch hole.....0.65 gal/lin ft.
 6.5-inch hole.....1.70 gal/lin ft.
 8-inch hole.....2.60 gal/lin ft.
 10-inch hole.....4.10 gal/lin ft.

Recharge Calculation at Time of Sample Collection:
 Collect sample when Depth to Water measures Less than or equal to:
 Original Water Column: 43.11 x 0.80 = -- (Total Depth of Well) 39.11

Signature: [Signature]
 8/2008

**APPENDIX B
LABORATORY ANALYTICAL REPORTS**



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

August 11, 2009

SAMPLE GROUP

The sample group for this submittal is 1156062. Samples arrived at the laboratory on Tuesday, August 04, 2009. The PO# for this group is 212201135.201.250 and the release number is EUNICE NORTH GP.

Client Description

MW062A Grab Water Sample

Lancaster Labs Number

5740234

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC STANTEC International, Inc.
COPY TO
ELECTRONIC STANTEC International, Inc.
COPY TO

Attn: Chad Vowell

Attn: Steve Bell



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

A handwritten signature in black ink, appearing to read 'Robert Strocko Jr.'.

Robert Strocko Jr.
Manager



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5740234

Group No. 1156062

MW062A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/03/2009 15:03 by JSL

Account Number: 11842

Submitted: 08/04/2009 09:05

STANTEC International, Inc.

Reported: 08/11/2009 at 15:59

10235 W. Little York

Discard: 09/11/2009

Ste 400

Houston TX 77040

M062A

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	110	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	440	190	2
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	0.0235	0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	62.1	40.0	100
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	504	30.0	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	< 0.020	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.
Trip blank vials were not received by the laboratory for this sample group.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09217A53A	08/05/2009 22:06	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09217A53A	08/05/2009 22:06	Katrina T Longenecker	1
0146	GC VOA Water Prep	SW-846 5030B	1	09217A53A	08/05/2009 22:06	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092160012A	08/05/2009 14:11	Diane V Do	2



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5740234

Group No. 1156062

MW062A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/03/2009 15:03 by JSL

Account Number: 11842

Submitted: 08/04/2009 09:05
Reported: 08/11/2009 at 15:59
Discard: 09/11/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

M062A

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092160012A	08/04/2009 15:20	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092185705003	08/07/2009 16:22	John P Hook	1
07051	Chromium	SW-846 6010B	1	092185705003	08/07/2009 16:22	John P Hook	1
01754	Iron	SW-846 6010B	1	092185705003	08/07/2009 16:22	John P Hook	1
07058	Manganese	SW-846 6010B	1	092185705003	08/07/2009 16:22	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092185705003	08/06/2009 20:40	Mirit S Shenouda	1
0224	Chloride	EPA 300.0	1	09218196602B	08/06/2009 23:03	Ashley M Adams	100
0212	Total Dissolved Solids	SM20 2540 C	1	09217021201A	08/05/2009 08:04	Susan A Engle	1
00276	Hexavalent Chromium	SW-846 7196A	1	09216027601A	08/04/2009 10:00	Michelle L Lalli	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/11/09 at 03:59 PM

Group Number: 1156062

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09217A53A	Sample number(s): 5740234							
Benzene	< 1.0	1.0	ug/l	115	115	80-120	0	30
Ethylbenzene	< 1.0	1.0	ug/l	110	110	80-120	0	30
Toluene	< 1.0	1.0	ug/l	115	110	80-120	4	30
TPH-GRO water C6-C10	< 50	50.	ug/l	91	100	75-135	10	30
Total Xylenes	< 3.0	3.0	ug/l	113	113	80-120	0	30
Batch number: 092160012A	Sample number(s): 5740234							
TPH-DRO water C10-C28	< 100	100.	ug/l	96	73	56-122	28*	20
Batch number: 092185705003	Sample number(s): 5740234							
Arsenic	< 0.0200	0.0200	mg/l	101		80-120		
Chromium	< 0.0150	0.0150	mg/l	100		90-110		
Iron	< 0.200	0.200	mg/l	102		90-112		
Manganese	< 0.0050	0.0050	mg/l	100		90-110		
Batch number: 09218196602B	Sample number(s): 5740234							
Chloride	< 0.40	0.40	mg/l	99		90-110		
Batch number: 09216027601A	Sample number(s): 5740234							
Hexavalent Chromium	< 0.020	0.020	mg/l	97		90-110		
Batch number: 09217021201A	Sample number(s): 5740234							
Total Dissolved Solids	< 30.0	30.0	mg/l	98		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09217A53A	Sample number(s): 5740234 UNSPK: 5740234, P740418								
Benzene	120		70-152						
Ethylbenzene	120		75-133						
Toluene	116		78-129						
TPH-GRO water C6-C10	99		63-154						
Total Xylenes	121		67-155						
Batch number: 092185705003	Sample number(s): 5740234 UNSPK: P741668 BKG: P741668								
Arsenic	104	107	75-125	3	20	< 0.0200	< 0.0200	0 (1)	20
Chromium	101	100	81-120	1	20	< 0.0150	< 0.0150	0 (1)	20
Iron	128 (2)	100 (2)	75-125	4	20	5.51	5.68	3	20

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/11/09 at 03:59 PM

Group Number: 1156062

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Manganese	102	99	75-125	2	20	0.278	0.284	2	20
Batch number: 09218196602B Chloride	Sample number(s): 5740234 UNSPK: P740165 BKG: P740165 92 90-110 153 154 0 20								
Batch number: 09216027601A Hexavalent Chromium	Sample number(s): 5740234 UNSPK: P740200 BKG: P740200 88 89 85-115 1 5 < 0.20 < 0.20 0 (1) 5								
Batch number: 09217021201A Total Dissolved Solids	Sample number(s): 5740234 UNSPK: P740123 BKG: P740123 83 64 54-143 7 12 33,600 32,700 3 9								

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed
unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: TPH-GRO water C6-C10
Batch number: 09217A53A

Trifluorotoluene-F		Trifluorotoluene-P	
5740234	79	97	
Blank	81	96	
LCS	90	97	
LCSD	96	98	
MS	92	97	
Limits:	63-135	69-129	

Analysis Name: TPH-DRO water C10-C28
Batch number: 092160012A
Orthoterphenyl

5740234	91
Blank	116
LCS	124
LCSD	107
Limits:	54-127

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

**Lancaster
Laboratories**

Acct. # 11842

Acct. # 11842 Group#

Group# 1156062 Sample #

#5 5740234

COC# 217442

Please print. Instructions on reverse side correspond with circled numbers.

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766

Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

August 13, 2009

SAMPLE GROUP

The sample group for this submittal is 1156247. Samples arrived at the laboratory on Wednesday, August 05, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

Client Description

MW063A Grab Water Sample
MW013A Grab Water Sample
MW031A Grab Water Sample
Trip Blank Water Sample

Lancaster Labs Number

5741247
5741248
5741249
5741250

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC STANTEC International, Inc.
COPY TO
ELECTRONIC STANTEC International, Inc.
COPY TO

Attn: Chad Vowell

Attn: Steve Bell



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

A handwritten signature in black ink that reads "Robert Strocko Jr." with a stylized flourish at the end.

Robert Strocko Jr.
Manager



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5741247

Group No. 1156247

MW063A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/04/2009 13:12 by JL

Account Number: 11842

Submitted: 08/05/2009 09:35

STANTEC International, Inc.

Reported: 08/13/2009 at 07:09

10235 W. Little York

Discard: 09/13/2009

Ste 400

Houston TX 77040

EUN63

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	51	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	140	95	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	0.0264	0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	56.1	8.0	20
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	502	30.0	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	< 0.020	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09218A54A	08/07/2009 01:05	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09218A54A	08/07/2009 01:05	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09218A54A	08/07/2009 01:05	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092170024A	08/07/2009 18:30	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092170024A	08/06/2009 08:50	Denise L Trimby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5741247

Group No. 1156247

MW063A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/04/2009 13:12 by JL

Account Number: 11842

Submitted: 08/05/2009 09:35
Reported: 08/13/2009 at 07:09
Discard: 09/13/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

EUN63

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092235705003	08/13/2009 00:06	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092235705003	08/13/2009 00:06	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092235705003	08/13/2009 00:06	John W Yanzuk II	1
07058	Manganese	SW-846 6010B	1	092235705003	08/13/2009 00:06	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092235705003	08/12/2009 14:35	James L Mertz	1
00224	Chloride	EPA 300.0	1	09218196602B	08/08/2009 17:26	Ashley M Adams	20
0212	Total Dissolved Solids	SM20 2540 C	1	09218021201A	08/06/2009 08:11	Susan E Hibner	1
0276	Hexavalent Chromium	SW-846 7196A	1	09217027602A	08/05/2009 10:30	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5741248

Group No. 1156247

MW013A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/04/2009 14:01 by JL

Account Number: 11842

Submitted: 08/05/2009 09:35

STANTEC International, Inc.

Reported: 08/13/2009 at 07:09

10235 W. Little York

Discard: 09/13/2009

Ste 400

Houston TX 77040

EUN13

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	< 95	95	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	0.0243	0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	72.5	40.0	100
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	540	30.0	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	< 0.020	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09218A54A	08/07/2009 01:28	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09218A54A	08/07/2009 01:28	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09218A54A	08/07/2009 01:28	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092170024A	08/07/2009 18:51	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092170024A	08/06/2009 08:50	Denise L Trimby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5741248

Group No. 1156247

NM

MW013A Grab Water Sample
Eunice North Gas Plant

Collected: 08/04/2009 14:01 by JL

Account Number: 11842

Submitted: 08/05/2009 09:35
Reported: 08/13/2009 at 07:09
Discard: 09/13/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

EUN13

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092235705003	08/13/2009 00:09	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092235705003	08/13/2009 00:09	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092235705003	08/13/2009 00:09	John W Yanzuk II	1
07058	Manganese	SW-846 6010B	1	092235705003	08/13/2009 00:09	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092235705003	08/12/2009 14:35	James L Mertz	1
00224	Chloride	EPA 300.0	1	09218196602B	08/07/2009 00:36	Ashley M Adams	100
0212	Total Dissolved Solids	SM20 2540 C	1	09218021201A	08/06/2009 08:11	Susan E Hibner	1
0276	Hexavalent Chromium	SW-846 7196A	1	09217027602A	08/05/2009 10:30	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5741249

Group No. 1156247

MW031A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/04/2009 14:44 by JL

Account Number: 11842

Submitted: 08/05/2009 09:35

STANTEC International, Inc.

Reported: 08/13/2009 at 07:09

10235 W. Little York

Discard: 09/13/2009

Ste 400

Houston TX 77040

EUN31

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	170	96	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	0.0253	0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.532	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	95.9	40.0	100
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	711	60.0	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	< 0.020	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09218A54A	08/07/2009 01:52	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09218A54A	08/07/2009 01:52	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09218A54A	08/07/2009 01:52	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092170024A	08/07/2009 19:12	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092170024A	08/06/2009 08:50	Denise L Trimby	1

Lancaster Laboratories Sample No. WW 5741249

Group No. 1156247

MW031A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/04/2009 14:44 by JL

Account Number: 11842

Submitted: 08/05/2009 09:35

STANTEC International, Inc.

Reported: 08/13/2009 at 07:09

10235 W. Little York

Discard: 09/13/2009

Ste 400

Houston TX 77040

EUN31

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092235705003	08/13/2009 00:17	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092235705003	08/13/2009 00:17	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092235705003	08/13/2009 00:17	John W Yanzuk II	1
07058	Manganese	SW-846 6010B	1	092235705003	08/13/2009 00:17	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092235705003	08/12/2009 14:35	James L Mertz	1
00224	Chloride	EPA 300.0	1	09218196602B	08/07/2009 01:22	Ashley M Adams	100
0212	Total Dissolved Solids	SM20 2540 C	1	09218021201A	08/06/2009 08:11	Susan E Hibner	1
0276	Hexavalent Chromium	SW-846 7196A	1	09217027602A	08/05/2009 10:30	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5741250

Group No. 1156247

Trip Blank Water Sample
Eunice North Gas Plant

NM

Collected: 08/04/2009

Account Number: 11842

Submitted: 08/05/2009 09:35

STANTEC International, Inc.

Reported: 08/13/2009 at 07:09

10235 W. Little York

Discard: 09/13/2009

Ste 400

Houston TX 77040

EUNTB

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09218A54A	08/07/2009 00:18	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09218A54A	08/07/2009 00:18	Katrina T Longenecker	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/13/09 at 07:09 AM

Group Number: 1156247

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09218A54A	Sample number(s): 5741247-5741250							
Benzene	< 1.0	1.0	ug/l	110	100	80-120	10	30
Ethylbenzene	< 1.0	1.0	ug/l	100	95	80-120	5	30
Toluene	< 1.0	1.0	ug/l	105	95	80-120	10	30
TPH-GRO water C6-C10	< 50	50.	ug/l	109	109	75-135	0	30
Total Xylenes	< 3.0	3.0	ug/l	103	97	80-120	7	30
Batch number: 092170024A	Sample number(s): 5741247-5741249							
TPH-DRO water C10-C28	< 100	100.	ug/l	70	73	56-122	4	20
Batch number: 092235705003	Sample number(s): 5741247-5741249							
Arsenic	< 0.0200	0.0200	mg/l	103		80-120		
Chromium	< 0.0150	0.0150	mg/l	100		90-110		
Iron	< 0.200	0.200	mg/l	101		90-112		
Manganese	< 0.0050	0.0050	mg/l	100		90-110		
Batch number: 09218196602B	Sample number(s): 5741247-5741249							
Chloride	< 0.40	0.40	mg/l	99		90-110		
Batch number: 09217027602A	Sample number(s): 5741247-5741249							
Hexavalent Chromium	< 0.020	0.020	mg/l	102		90-110		
Batch number: 09218021201A	Sample number(s): 5741247-5741249							
Total Dissolved Solids	< 30.0	30.0	mg/l	93		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09218A54A	Sample number(s): 5741247-5741250 UNSPK: P741904, P741906								
Benzene	105		70-152						
Ethylbenzene	110		75-133						
Toluene	105		78-129						
TPH-GRO water C6-C10	127		63-154						
Total Xylenes	110		67-155						
Batch number: 092235705003	Sample number(s): 5741247-5741249 UNSPK: P741695 BKG: P741695								
Arsenic	107	107	75-125	0	20	< 0.0200	< 0.0200	0 (1)	20
Chromium	98	99	81-120	1	20	< 0.0150	< 0.0150	0 (1)	20
Iron	141 (2)	115 (2)	75-125	4	20	4.80	4.89	2	20

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/13/09 at 07:09 AM

Group Number: 1156247

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Manganese	99	100	75-125	1	20	0.269	0.276	3	20
Batch number: 09218196602B Chloride	Sample number(s): 5741247-5741249 UNSPK: P740165 BKG: P740165 92 90-110 153 154 0 20								
Batch number: 09217027602A Hexavalent Chromium	Sample number(s): 5741247-5741249 UNSPK: 5741247 BKG: 5741247 104 104 85-115 0 5 < 0.020 < 0.020 0 (1) 5								
Batch number: 09218021201A Total Dissolved Solids	Sample number(s): 5741247-5741249 UNSPK: P740192 BKG: P740192 96 95 54-143 1 12 268 267 0 9								

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed
unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: TPH-GRO water C6-C10
Batch number: 09218A54A

	Trifluorotoluene-F	Trifluorotoluene-P
5741247	104	112
5741248	105	113
5741249	104	112
5741250		109
Blank	106	111
LCS	118	112
LCSD	119	112
MS	112	108
Limits:	63-135	69-129

Analysis Name: TPH-DRO water C10-C28
Batch number: 092170024A
Orthoterphenyl

5741247	88
5741248	84
5741249	90
Blank	73
LCS	96
LCSD	96
Limits:	54-127

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only

Acct. # 11842 Group # 1156247 Sample # 5741247-50 **COC #** 217443

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chescon</u> Acct. #: _____ Project Name/ID: <u>212201155, 201.250</u> PWSID #: _____ Project Manager: <u>Chad Howell</u> P.O. #: _____ Sampler: <u>Felix Howswell</u> Quote #: _____ Name of state where samples were collected: <u>Delaware</u>		2 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Date Collected</th> <th>Time Collected</th> <th>Location</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>MW063A</td> <td>8-4-09</td> <td>1312</td> <td>X</td> <td></td> </tr> <tr> <td>MW013A</td> <td>8-4-09</td> <td>1401</td> <td>X</td> <td></td> </tr> <tr> <td>MW031A</td> <td>8-4-09</td> <td>1444</td> <td>X</td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Date Collected	Time Collected	Location	Remarks	MW063A	8-4-09	1312	X		MW013A	8-4-09	1401	X		MW031A	8-4-09	1444	X		Trip Blank					3 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Date Collected</th> <th>Time Collected</th> <th>Location</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>MW063A</td> <td>8-4-09</td> <td>1312</td> <td>X</td> <td></td> </tr> <tr> <td>MW013A</td> <td>8-4-09</td> <td>1401</td> <td>X</td> <td></td> </tr> <tr> <td>MW031A</td> <td>8-4-09</td> <td>1444</td> <td>X</td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Date Collected	Time Collected	Location	Remarks	MW063A	8-4-09	1312	X		MW013A	8-4-09	1401	X		MW031A	8-4-09	1444	X		Trip Blank					4 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Date Collected</th> <th>Time Collected</th> <th>Location</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>MW063A</td> <td>8-4-09</td> <td>1312</td> <td>X</td> <td></td> </tr> <tr> <td>MW013A</td> <td>8-4-09</td> <td>1401</td> <td>X</td> <td></td> </tr> <tr> <td>MW031A</td> <td>8-4-09</td> <td>1444</td> <td>X</td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Date Collected	Time Collected	Location	Remarks	MW063A	8-4-09	1312	X		MW013A	8-4-09	1401	X		MW031A	8-4-09	1444	X		Trip Blank					5 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Date Collected</th> <th>Time Collected</th> <th>Location</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>MW063A</td> <td>8-4-09</td> <td>1312</td> <td>X</td> <td></td> </tr> <tr> <td>MW013A</td> <td>8-4-09</td> <td>1401</td> <td>X</td> <td></td> </tr> <tr> <td>MW031A</td> <td>8-4-09</td> <td>1444</td> <td>X</td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Date Collected	Time Collected	Location	Remarks	MW063A	8-4-09	1312	X		MW013A	8-4-09	1401	X		MW031A	8-4-09	1444	X		Trip Blank					6 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Date Collected</th> <th>Time Collected</th> <th>Location</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>MW063A</td> <td>8-4-09</td> <td>1312</td> <td>X</td> <td></td> </tr> <tr> <td>MW013A</td> <td>8-4-09</td> <td>1401</td> <td>X</td> <td></td> </tr> <tr> <td>MW031A</td> <td>8-4-09</td> <td>1444</td> <td>X</td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Date Collected	Time Collected	Location	Remarks	MW063A	8-4-09	1312	X		MW013A	8-4-09	1401	X		MW031A	8-4-09	1444	X		Trip Blank					7 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Date Collected</th> <th>Time Collected</th> <th>Location</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>MW063A</td> <td>8-4-09</td> <td>1312</td> <td>X</td> <td></td> </tr> <tr> <td>MW013A</td> <td>8-4-09</td> <td>1401</td> <td>X</td> <td></td> </tr> <tr> <td>MW031A</td> <td>8-4-09</td> <td>1444</td> <td>X</td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Date Collected	Time Collected	Location	Remarks	MW063A	8-4-09	1312	X		MW013A	8-4-09	1401	X		MW031A	8-4-09	1444	X		Trip Blank					8 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Date Collected</th> <th>Time Collected</th> <th>Location</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>MW063A</td> <td>8-4-09</td> <td>1312</td> <td>X</td> <td></td> </tr> <tr> <td>MW013A</td> <td>8-4-09</td> <td>1401</td> <td>X</td> <td></td> </tr> <tr> <td>MW031A</td> <td>8-4-09</td> <td>1444</td> <td>X</td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Date Collected	Time Collected	Location	Remarks	MW063A	8-4-09	1312	X		MW013A	8-4-09	1401	X		MW031A	8-4-09	1444	X		Trip Blank					9 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Date Collected</th> <th>Time Collected</th> <th>Location</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>MW063A</td> <td>8-4-09</td> <td>1312</td> <td>X</td> <td></td> </tr> <tr> <td>MW013A</td> <td>8-4-09</td> <td>1401</td> <td>X</td> <td></td> </tr> <tr> <td>MW031A</td> <td>8-4-09</td> <td>1444</td> <td>X</td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Date Collected	Time Collected	Location	Remarks	MW063A	8-4-09	1312	X		MW013A	8-4-09	1401	X		MW031A	8-4-09	1444	X		Trip Blank				
Sample ID	Date Collected	Time Collected	Location	Remarks																																																																																																																																																																																																																					
MW063A	8-4-09	1312	X																																																																																																																																																																																																																						
MW013A	8-4-09	1401	X																																																																																																																																																																																																																						
MW031A	8-4-09	1444	X																																																																																																																																																																																																																						
Trip Blank																																																																																																																																																																																																																									
Sample ID	Date Collected	Time Collected	Location	Remarks																																																																																																																																																																																																																					
MW063A	8-4-09	1312	X																																																																																																																																																																																																																						
MW013A	8-4-09	1401	X																																																																																																																																																																																																																						
MW031A	8-4-09	1444	X																																																																																																																																																																																																																						
Trip Blank																																																																																																																																																																																																																									
Sample ID	Date Collected	Time Collected	Location	Remarks																																																																																																																																																																																																																					
MW063A	8-4-09	1312	X																																																																																																																																																																																																																						
MW013A	8-4-09	1401	X																																																																																																																																																																																																																						
MW031A	8-4-09	1444	X																																																																																																																																																																																																																						
Trip Blank																																																																																																																																																																																																																									
Sample ID	Date Collected	Time Collected	Location	Remarks																																																																																																																																																																																																																					
MW063A	8-4-09	1312	X																																																																																																																																																																																																																						
MW013A	8-4-09	1401	X																																																																																																																																																																																																																						
MW031A	8-4-09	1444	X																																																																																																																																																																																																																						
Trip Blank																																																																																																																																																																																																																									
Sample ID	Date Collected	Time Collected	Location	Remarks																																																																																																																																																																																																																					
MW063A	8-4-09	1312	X																																																																																																																																																																																																																						
MW013A	8-4-09	1401	X																																																																																																																																																																																																																						
MW031A	8-4-09	1444	X																																																																																																																																																																																																																						
Trip Blank																																																																																																																																																																																																																									
Sample ID	Date Collected	Time Collected	Location	Remarks																																																																																																																																																																																																																					
MW063A	8-4-09	1312	X																																																																																																																																																																																																																						
MW013A	8-4-09	1401	X																																																																																																																																																																																																																						
MW031A	8-4-09	1444	X																																																																																																																																																																																																																						
Trip Blank																																																																																																																																																																																																																									
Sample ID	Date Collected	Time Collected	Location	Remarks																																																																																																																																																																																																																					
MW063A	8-4-09	1312	X																																																																																																																																																																																																																						
MW013A	8-4-09	1401	X																																																																																																																																																																																																																						
MW031A	8-4-09	1444	X																																																																																																																																																																																																																						
Trip Blank																																																																																																																																																																																																																									
Sample ID	Date Collected	Time Collected	Location	Remarks																																																																																																																																																																																																																					
MW063A	8-4-09	1312	X																																																																																																																																																																																																																						
MW013A	8-4-09	1401	X																																																																																																																																																																																																																						
MW031A	8-4-09	1444	X																																																																																																																																																																																																																						
Trip Blank																																																																																																																																																																																																																									

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6786
 Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories

Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2881 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

August 18, 2009

SAMPLE GROUP

The sample group for this submittal is 1156666. Samples arrived at the laboratory on Friday, August 07, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

Client Description

MW021A Grab Water Sample
MW021 Grab Water Sample
MW032 Grab Water Sample
MW065SA Grab Water Sample
MW066SA Grab Water Sample
Trip Blank Water Sample

Lancaster Labs Number

5743736
5743737
5743738
5743739
5743740
5743741

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC STANTEC International, Inc.
COPY TO
ELECTRONIC STANTEC International, Inc.
COPY TO

Attn: Chad Vowell

Attn: Steve Bell



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

A handwritten signature in cursive script that reads "Michele D. Hamilton".

Michele D. Hamilton
Group Leader



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5743736

Group No. 1156666

MW021A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/06/2009 12:30 by JL

Account Number: 11842

Submitted: 08/07/2009 09:00

STANTEC International, Inc.

Reported: 08/18/2009 at 15:36

10235 W. Little York

Discard: 09/18/2009

Ste 400

Houston TX 77040

E21A-

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	54	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	810	95	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.0318	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.0114	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	6,020	800	2000
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	13,300	1,200	10
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.031	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09222A54A	08/11/2009 04:04	Elizabeth J Marin	1
08213	BTEX (8021)	SW-846 8021B	1	09222A54A	08/11/2009 04:04	Elizabeth J Marin	1
01146	GC VOA Water Prep	SW-846 5030B	1	09222A54A	08/11/2009 04:04	Elizabeth J Marin	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092200009A	08/11/2009 18:39	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092200009A	08/10/2009 09:15	Cynthia J Salvatori	1
07035	Arsenic	SW-846 6010B	1	092235705003	08/13/2009 00:38	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092235705003	08/13/2009 00:38	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5743736

Group No. 1156666

NM

MW021A Grab Water Sample
Eunice North Gas Plant

Collected: 08/06/2009 12:30 by JL

Account Number: 11842

Submitted: 08/07/2009 09:00

STANTEC International, Inc.

Reported: 08/18/2009 at 15:36

10235 W. Little York

Discard: 09/18/2009

Ste 400

Houston TX 77040

E21A-

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01754	Iron	SW-846 6010B	1	092235705003	08/13/2009 00:38	John W Yanzuk II	1
07058	Manganese	SW-846 6010B	1	092235705003	08/13/2009 00:38	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092235705003	08/12/2009 14:35	James L Mertz	1
00224	Chloride	EPA 300.0	1	09223196601B	08/12/2009 16:10	Ashley M Adams	2000
00212	Total Dissolved Solids	SM20 2540 C	1	09224021201A	08/12/2009 09:43	Susan E Hibner	10
00276	Hexavalent Chromium	SW-846 7196A	1	09219027601A	08/07/2009 10:35	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5743737

Group No. 1156666

MW021 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/06/2009 13:10 by JL

Account Number: 11842

Submitted: 08/07/2009 09:00
Reported: 08/18/2009 at 15:36
Discard: 09/18/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

E021-

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	670	97	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.172	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	193	40.0	100
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	1,490	120	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	< 0.020	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09222A54A	08/11/2009 04:28	Elizabeth J Marin	1
08213	BTEX (8021)	SW-846 8021B	1	09222A54A	08/11/2009 04:28	Elizabeth J Marin	1
01146	GC VOA Water Prep	SW-846 5030B	1	09222A54A	08/11/2009 04:28	Elizabeth J Marin	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092200009A	08/11/2009 18:59	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092200009A	08/10/2009 09:15	Cynthia J Salvatori	1
07035	Arsenic	SW-846 6010B	1	092235705003	08/13/2009 00:41	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092235705003	08/13/2009 00:41	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5743737

Group No. 1156666

NM

MW021 Grab Water Sample

Eunice North Gas Plant

Collected: 08/06/2009 13:10 by JL

Account Number: 11842

Submitted: 08/07/2009 09:00

STANTEC International, Inc.

Reported: 08/18/2009 at 15:36

10235 W. Little York

Discard: 09/18/2009

Ste 400

Houston TX 77040

E021-

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01754	Iron	SW-846 6010B	1	092235705003	08/13/2009 00:41	John W Yanzuk II	1
07058	Manganese	SW-846 6010B	1	092235705003	08/13/2009 00:41	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092235705003	08/12/2009 14:35	James L Mertz	1
00224	Chloride	EPA 300.0	1	09223196601B	08/11/2009 21:47	Ashley M Adams	100
00212	Total Dissolved Solids	SM20 2540 C	1	09224021201A	08/12/2009 09:43	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09219027601A	08/07/2009 10:35	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5743738

Group No. 1156666

MW032 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/06/2009 13:56 by JL

Account Number: 11842

Submitted: 08/07/2009 09:00

STANTEC International, Inc.

Reported: 08/18/2009 at 15:36

10235 W. Little York

Discard: 09/18/2009

Ste 400

Houston TX 77040

E032-

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	240	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	490	96	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.0059	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	227	40.0	100
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	1,160	120	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	< 0.020	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09222A54A	08/11/2009 04:52	Elizabeth J Marin	1
08213	BTEX (8021)	SW-846 8021B	1	09222A54A	08/11/2009 04:52	Elizabeth J Marin	1
01146	GC VOA Water Prep	SW-846 5030B	1	09222A54A	08/11/2009 04:52	Elizabeth J Marin	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092200009A	08/11/2009 19:20	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092200009A	08/10/2009 09:15	Cynthia J Salvatori	1
07035	Arsenic	SW-846 6010B	1	092235705003	08/13/2009 00:44	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092235705003	08/13/2009 00:44	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5743738

Group No. 1156666

NM

MW032 Grab Water Sample

Eunice North Gas Plant

Collected: 08/06/2009 13:56 by JL

Account Number: 11842

Submitted: 08/07/2009 09:00

STANTEC International, Inc.

Reported: 08/18/2009 at 15:36

10235 W. Little York

Discard: 09/18/2009

Ste 400

Houston TX 77040

E032-

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01754	Iron	SW-846 6010B	1	092235705003	08/13/2009 00:44	John W Yanzuk II	1
07058	Manganese	SW-846 6010B	1	092235705003	08/13/2009 00:44	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092235705003	08/12/2009 14:35	James L Mertz	1
00224	Chloride	EPA 300.0	1	09223196601B	08/11/2009 22:02	Ashley M Adams	100
00212	Total Dissolved Solids	SM20 2540 C	1	09224021201A	08/12/2009 09:43	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09219027601A	08/07/2009 10:35	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5743739

Group No. 1156666

MW065SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/06/2009 15:46 by JL

Account Number: 11842

Submitted: 08/07/2009 09:00

STANTEC International, Inc.

Reported: 08/18/2009 at 15:36

10235 W. Little York

Discard: 09/18/2009

Ste 400

Houston TX 77040

E65SA

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	< 98	98	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.0741	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	967	200	500
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	2,920	240	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.066	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09222A54A	08/11/2009 05:15	Elizabeth J Marin	1
08213	BTEX (8021)	SW-846 8021B	1	09222A54A	08/11/2009 05:15	Elizabeth J Marin	1
01146	GC VOA Water Prep	SW-846 5030B	1	09222A54A	08/11/2009 05:15	Elizabeth J Marin	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092200009A	08/11/2009 19:40	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092200009A	08/10/2009 09:15	Cynthia J Salvatori	1
07035	Arsenic	SW-846 6010B	1	092235705003	08/13/2009 00:52	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092235705003	08/13/2009 00:52	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5743739

Group No. 1156666

NM

MW065SA Grab Water Sample
Eunice North Gas Plant

Collected: 08/06/2009 15:46 by JL

Account Number: 11842

Submitted: 08/07/2009 09:00
Reported: 08/18/2009 at 15:36
Discard: 09/18/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

E65SA

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01754	Iron	SW-846 6010B	1	092235705003	08/13/2009 00:52	John W Yanzuk II	1
07058	Manganese	SW-846 6010B	1	092235705003	08/13/2009 00:52	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092235705003	08/12/2009 14:35	James L Mertz	1
00224	Chloride	EPA 300.0	1	09223196601B	08/12/2009 16:25	Ashley M Adams	500
00212	Total Dissolved Solids	SM20 2540 C	1	09224021201A	08/12/2009 09:43	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09219027601A	08/07/2009 10:35	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5743740

Group No. 1156666

MW066SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/06/2009 14:59 by JL

Account Number: 11842

Submitted: 08/07/2009 09:00

STANTEC International, Inc.

Reported: 08/18/2009 at 15:36

10235 W. Little York

Discard: 09/18/2009

Ste 400

Houston TX 77040

E66SA

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	< 98	98	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.381	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	966	80.0	200
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	3,060	240	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	< 0.020	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09222A54A	08/11/2009 05:39	Elizabeth J Marin	1
08213	BTEX (8021)	SW-846 8021B	1	09222A54A	08/11/2009 05:39	Elizabeth J Marin	1
01146	GC VOA Water Prep	SW-846 5030B	1	09222A54A	08/11/2009 05:39	Elizabeth J Marin	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092200009A	08/11/2009 20:01	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092200009A	08/10/2009 09:15	Cynthia J Salvatori	1
07035	Arsenic	SW-846 6010B	1	092235705003	08/13/2009 00:55	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092235705003	08/13/2009 00:55	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5743740

Group No. 1156666

MW066SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/06/2009 14:59 by JL

Account Number: 11842

Submitted: 08/07/2009 09:00

STANTEC International, Inc.

Reported: 08/18/2009 at 15:36

10235 W. Little York

Discard: 09/18/2009

Ste 400

Houston TX 77040

E66SA

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01754	Iron	SW-846 6010B	1	092235705003	08/13/2009 00:55	John W Yanzuk II	1
07058	Manganese	SW-846 6010B	1	092235705003	08/13/2009 00:55	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092235705003	08/12/2009 14:35	James L Mertz	1
00224	Chloride	EPA 300.0	1	09223196601B	08/12/2009 16:41	Ashley M Adams	200
00212	Total Dissolved Solids	SM20 2540 C	1	09224021201A	08/12/2009 09:43	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09219027601A	08/07/2009 10:35	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5743741

Group No. 1156666

Trip Blank Water Sample
Eunice North Gas Plant

NM

Collected: 08/06/2009

Account Number: 11842

Submitted: 08/07/2009 09:00

STANTEC International, Inc.

Reported: 08/18/2009 at 15:36

10235 W. Little York

Discard: 09/18/2009

Ste 400

Houston TX 77040

66SAT

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846	8021B	GC Volatiles	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09222A54A	08/10/2009 22:10	Elizabeth J Marin	1
01146	GC VOA Water Prep	SW-846 5030B	1	09222A54A	08/10/2009 22:10	Elizabeth J Marin	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/18/09 at 03:36 PM

Group Number: 1156666

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09222A54A	Sample number(s): 5743736-5743741							
Benzene	< 1.0	1.0	ug/l	105	110	80-120	5	30
Ethylbenzene	< 1.0	1.0	ug/l	95	105	80-120	10	30
Toluene	< 1.0	1.0	ug/l	95	105	80-120	10	30
TPH-GRO water C6-C10	< 50	50.	ug/l	91	109	75-135	18	30
Total Xylenes	< 3.0	3.0	ug/l	97	105	80-120	8	30
Batch number: 092200009A	Sample number(s): 5743736-5743740							
TPH-DRO water C10-C28	< 100	100.	ug/l	85	84	56-122	1	20
Batch number: 092235705003	Sample number(s): 5743736-5743740							
Arsenic	< 0.0200	0.0200	mg/l	103		80-120		
Chromium	< 0.0150	0.0150	mg/l	100		90-110		
Iron	< 0.200	0.200	mg/l	101		90-112		
Manganese	< 0.0050	0.0050	mg/l	100		90-110		
Batch number: 09223196601B	Sample number(s): 5743736-5743740							
Chloride	< 0.40	0.40	mg/l	104		90-110		
Batch number: 09219027601A	Sample number(s): 5743736-5743740							
Hexavalent Chromium	< 0.020	0.020	mg/l	103		90-110		
Batch number: 09224021201A	Sample number(s): 5743736-5743740							
Total Dissolved Solids	< 30.0	30.0	mg/l	93		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09222A54A	Sample number(s): 5743736-5743741 UNSPK: P742823, P742826								
Benzene	110		70-152						
Ethylbenzene	110		75-133						
Toluene	110		78-129						
TPH-GRO water C6-C10	109		63-154						
Total Xylenes	110		67-155						
Batch number: 092235705003	Sample number(s): 5743736-5743740 UNSPK: P741695 BKG: P741695								
Arsenic	107	107	75-125	0	20	< 0.0200	< 0.0200	0 (1)	20
Chromium	98	99	81-120	1	20	< 0.0150	< 0.0150	0 (1)	20
Iron	141 (2)	115 (2)	75-125	4	20	4.80	4.89	2	20

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/18/09 at 03:36 PM

Group Number: 1156666

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Manganese	99	100	75-125	1	20	0.269	0.276	3	20
Batch number: 09223196601B Chloride	Sample number(s): 5743736-5743740 UNSPK: P743659 BKG: P743659 111* 90-110 32.1 32.2 0 20								
Batch number: 09219027601A Hexavalent Chromium	Sample number(s): 5743736-5743740 UNSPK: 5743736 BKG: 5743736 104 109 85-115 3 5 0.031 0.028 10* (1) 5								
Batch number: 09224021201A Total Dissolved Solids	Sample number(s): 5743736-5743740 UNSPK: 5743739 BKG: 5743739 98 95 54-143 1 12 2,920 2,910 0 9								

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed
unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: BTEX (8021)
Batch number: 09222A54A

Trifluorotoluene-F		Trifluorotoluene-P	
5743736	107	5743736	114
5743737	106	5743737	115
5743738	106	5743738	112
5743739	106	5743739	115
5743740	104	5743740	114
5743741	1	5743741	115
Blank	107	Blank	113
LCS	120	LCS	114
LCSD	119	LCSD	114
MS	118	MS	110
Limits:	63-135	Limits:	69-129

Analysis Name: TPH-DRO water C10-C28
Batch number: 092200009A
Orthoterphenyl

5743736	96
5743737	84
5743738	94
5743739	91
5743740	92
Blank	90
LCS	97
LCSD	96
Limits:	54-127

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/18/09 at 03:36 PM

Group Number: 1156666

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Lancaster Laboratories

Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

August 20, 2009

SAMPLE GROUP

The sample group for this submittal is 1157030. Samples arrived at the laboratory on Tuesday, August 11, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

<u>Client Description</u>	<u>Lancaster Labs Number</u>
MW071SA Grab Water Sample	5745830
MW086SA Grab Water Sample	5745831
Trip Blank Water Sample	5745832
DUP-100 Grab Water Sample	5745833
MW014 Grab Water Sample	5745834
MW013 Grab Water Sample	5745835
MW054SA Grab Water Sample	5745836
Trip Blank Water Sample	5745837

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC COPY TO STANTEC International, Inc.
ELECTRONIC COPY TO STANTEC International, Inc.

Attn: Chad Vowell

Attn: Steve Bell



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

A handwritten signature in cursive script, appearing to read "Valerie L. Tomayko".

Valerie L. Tomayko
Group Leader



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5745830

Group No. 1157030

MW071SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009 13:44 by JSL

Account Number: 11842

Submitted: 08/11/2009 09:10
Reported: 08/20/2009 at 16:08
Discard: 09/20/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

EUN71

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	150	95	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.0940	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.668	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	1,000	80.0	200
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	2,810	240	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.10	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09224A53A	08/13/2009 02:49	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09224A53A	08/13/2009 02:49	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09224A53A	08/13/2009 02:49	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092240009A	08/13/2009 16:29	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092240009A	08/12/2009 14:45	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092295705001	08/19/2009 16:24	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092295705001	08/19/2009 16:24	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092295705001	08/19/2009 16:24	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5745830

Group No. 1157030

NM

MW071SA Grab Water Sample

Eunice North Gas Plant

Collected: 08/10/2009 13:44 by JSL

Account Number: 11842

Submitted: 08/11/2009 09:10

STANTEC International, Inc.

Reported: 08/20/2009 at 16:08

10235 W. Little York

Discard: 09/20/2009

Ste 400

Houston TX 77040

EUN71

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092295705001	08/19/2009 16:24	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092295705001	08/18/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09224196602A	08/14/2009 06:47	Ashley M Adams	200
00212	Total Dissolved Solids	SM20 2540 C	1	09225021201A	08/13/2009 08:20	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09223027601A	08/11/2009 10:00	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5745831

Group No. 1157030

MW086SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009 14:15 by JSL

Account Number: 11842

Submitted: 08/11/2009 09:10
Reported: 08/20/2009 at 16:08
Discard: 09/20/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

EUN86

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	120	99	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.0601	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	1,330	200	500
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	4,120	600	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.063	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09224A53A	08/13/2009 03:13	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09224A53A	08/13/2009 03:13	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09224A53A	08/13/2009 03:13	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092240009A	08/13/2009 16:49	Diane V Do	1
0003	Extraction - DRO (Waters)	SW-846 3510C	1	092240009A	08/12/2009 14:45	Cody R Hanna	1
0035	Arsenic	SW-846 6010B	1	092295705001	08/19/2009 16:28	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092295705001	08/19/2009 16:28	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092295705001	08/19/2009 16:28	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5745831

Group No. 1157030

MW086SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009 14:15 by JSL

Account Number: 11842

Submitted: 08/11/2009 09:10

STANTEC International, Inc.

Reported: 08/20/2009 at 16:08

10235 W. Little York

Discard: 09/20/2009

Ste 400

Houston TX 77040

EUN86

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092295705001	08/19/2009 16:28	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092295705001	08/18/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09224196602A	08/14/2009 07:03	Ashley M Adams	500
00212	Total Dissolved Solids	SM20 2540 C	1	09225021201A	08/13/2009 08:20	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09223027601A	08/11/2009 10:00	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5745832

Group No. 1157030

Trip Blank Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009

Account Number: 11842

Submitted: 08/11/2009 09:10

STANTEC International, Inc.

Reported: 08/20/2009 at 16:08

10235 W. Little York

Discard: 09/20/2009

Ste 400

Houston TX 77040

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846	8021B	GC Volatiles	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09224A54A	08/13/2009 19:34	Elizabeth J Marin	1
01146	GC VOA Water Prep	SW-846 5030B	1	09224A54A	08/13/2009 19:34	Elizabeth J Marin	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5745833

Group No. 1157030

DUP-100 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009 by JSL

Account Number: 11842

Submitted: 08/11/2009 09:10

STANTEC International, Inc.

Reported: 08/20/2009 at 16:08

10235 W. Little York

Discard: 09/20/2009

Ste 400

Houston TX 77040

EUN-D

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	130	95	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.0595	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	1,500	200	500
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	3,900	600	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.062	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09224A53A	08/13/2009 03:37	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09224A53A	08/13/2009 03:37	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09224A53A	08/13/2009 03:37	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092240009A	08/13/2009 17:09	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092240009A	08/12/2009 14:45	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092295705001	08/19/2009 16:41	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092295705001	08/19/2009 16:41	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092295705001	08/19/2009 16:41	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5745833

Group No. 1157030

DUP-100 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009 by JSL

Account Number: 11842

Submitted: 08/11/2009 09:10

STANTEC International, Inc.

Reported: 08/20/2009 at 16:08

10235 W. Little York

Discard: 09/20/2009

Ste 400

Houston TX 77040

EUN-D

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092295705001	08/19/2009 16:41	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092295705001	08/18/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09224196602A	08/14/2009 07:49	Ashley M Adams	500
00212	Total Dissolved Solids	SM20 2540 C	1	09225021201A	08/13/2009 08:20	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09223027601A	08/11/2009 10:00	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5745834

Group No. 1157030

MW014 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009 13:32 by SB

Account Number: 11842

Submitted: 08/11/2009 09:10
Reported: 08/20/2009 at 16:08
Discard: 09/20/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

EUN14

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	1.1	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	650	96	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	0.0283	0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.354	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	133	40.0	100
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	647	30.0	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	< 0.020	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09224A53A	08/12/2009 21:12	Carrie E Miller	1
08213	BTEX (8021)	SW-846 8021B	1	09224A53A	08/12/2009 21:12	Carrie E Miller	1
01146	GC VOA Water Prep	SW-846 5030B	1	09224A53A	08/12/2009 21:12	Carrie E Miller	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092240009A	08/13/2009 17:30	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092240009A	08/12/2009 14:45	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092295705001	08/19/2009 16:46	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092295705001	08/19/2009 16:46	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092295705001	08/19/2009 16:46	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5745834

Group No. 1157030

MW014 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009 13:32 by SB

Account Number: 11842

Submitted: 08/11/2009 09:10

STANTEC International, Inc.

Reported: 08/20/2009 at 16:08

10235 W. Little York

Discard: 09/20/2009

Ste 400

Houston TX 77040

EUN14

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092295705001	08/19/2009 16:46	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092295705001	08/18/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09224196602A	08/13/2009 02:12	Ashley M Adams	100
00212	Total Dissolved Solids	SM20 2540 C	1	09225021201A	08/13/2009 08:20	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09223027601A	08/11/2009 10:00	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5745835

Group No. 1157030

MW013 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009 14:19 by SB

Account Number: 11842

Submitted: 08/11/2009 09:10
Reported: 08/20/2009 at 16:08
Discard: 09/20/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

EUN13

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	100	95	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.830	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	760	80.0	200
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	3,360	240	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.84	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09224A53A	08/12/2009 23:13	Carrie E Miller	1
08213	BTEX (8021)	SW-846 8021B	1	09224A53A	08/12/2009 23:13	Carrie E Miller	1
01146	GC VOA Water Prep	SW-846 5030B	1	09224A53A	08/12/2009 23:13	Carrie E Miller	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092240009A	08/13/2009 17:50	Diane V Do	1
7003	Extraction - DRO (Waters)	SW-846 3510C	1	092240009A	08/12/2009 14:45	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092295705001	08/19/2009 16:50	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092295705001	08/19/2009 16:50	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092295705001	08/19/2009 16:50	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5745835

Group No: 1157030

NM

MW013 Grab Water Sample

Eunice North Gas Plant

Collected: 08/10/2009 14:19 by SB

Account Number: 11842

Submitted: 08/11/2009 09:10

STANTEC International, Inc.

Reported: 08/20/2009 at 16:08

10235 W. Little York

Discard: 09/20/2009

Ste 400

Houston TX 77040

EUN13

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092295705001	08/19/2009 16:50	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092295705001	08/18/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09224196602A	08/14/2009 08:04	Ashley M Adams	200
00212	Total Dissolved Solids	SM20 2540 C	1	09225021201A	08/13/2009 08:20	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09223027601A	08/11/2009 10:00	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5745836

Group No. 1157030

MW054SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009 15:13 by SB

Account Number: 11842

Submitted: 08/11/2009 09:10

STANTEC International, Inc.

Reported: 08/20/2009 at 16:08

10235 W. Little York

Discard: 09/20/2009

Ste 400

Houston TX 77040

EUN54

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	110	97	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.107	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	834	80.0	200
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	2,350	240	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.10	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09224A53A	08/13/2009 04:01	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09224A53A	08/13/2009 04:01	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09224A53A	08/13/2009 04:01	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092240009A	08/13/2009 18:11	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092240009A	08/12/2009 14:45	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092295705001	08/19/2009 16:55	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092295705001	08/19/2009 16:55	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092295705001	08/19/2009 16:55	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5745836

Group No. 1157030

MW054SA Grab Water Sample

NM

Eunice North Gas Plant

Collected: 08/10/2009 15:13 by SB

Account Number: 11842

Submitted: 08/11/2009 09:10

STANTEC International, Inc.

Reported: 08/20/2009 at 16:08

10235 W. Little York

Discard: 09/20/2009

Ste 400

Houston TX 77040

EUN54

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092295705001	08/19/2009 16:55	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092295705001	08/18/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09224196602A	08/14/2009 08:20	Ashley M Adams	200
00212	Total Dissolved Solids	SM20 2540 C	1	09225021201A	08/13/2009 08:20	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09223027601A	08/11/2009 10:00	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5745837

Group No. 1157030

Trip Blank Water Sample
Eunice North Gas Plant

NM

Collected: 08/10/2009

Account Number: 11842

Submitted: 08/11/2009 09:10

STANTEC International, Inc.

Reported: 08/20/2009 at 16:08

10235 W. Little York

Discard: 09/20/2009

Ste 400

Houston TX 77040

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846	8021B	GC Volatiles	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09224A53A	08/12/2009 20:00	Carrie E Miller	1
01146	GC VOA Water Prep	SW-846 5030B	1	09224A53A	08/12/2009 20:00	Carrie E Miller	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/20/09 at 04:08 PM

Group Number: 1157030

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09224A53A	Sample number(s): 5745830-5745831, 5745833-5745837							
Benzene	< 1.0	1.0	ug/l	110	115	80-120	4	30
Ethylbenzene	< 1.0	1.0	ug/l	105	115	80-120	9	30
Toluene	< 1.0	1.0	ug/l	105	115	80-120	9	30
TPH-GRO water C6-C10	< 50	50.	ug/l	127	127	75-135	0	30
Total Xylenes	< 3.0	3.0	ug/l	107	117	80-120	9	30
Batch number: 09224A54A	Sample number(s): 5745832							
Benzene	< 1.0	1.0	ug/l	105	115	80-120	9	30
Ethylbenzene	< 1.0	1.0	ug/l	95	110	80-120	15	30
Toluene	< 1.0	1.0	ug/l	100	110	80-120	10	30
Total Xylenes	< 3.0	3.0	ug/l	98	108	80-120	10	30
Batch number: 092240009A	Sample number(s): 5745830-5745831, 5745833-5745836							
TPH-DRO water C10-C28	< 100	100.	ug/l	80	74	56-122	8	20
Batch number: 092295705001	Sample number(s): 5745830-5745831, 5745833-5745836							
Arsenic	< 0.0200	0.0200	mg/l	106		80-120		
Chromium	< 0.0150	0.0150	mg/l	100		90-110		
Iron	< 0.200	0.200	mg/l	94		90-112		
Manganese	< 0.0050	0.0050	mg/l	103		90-110		
Batch number: 09224196602A	Sample number(s): 5745830-5745831, 5745833-5745836							
Chloride	< 0.40	0.40	mg/l	107		90-110		
Batch number: 09223027601A	Sample number(s): 5745830-5745831, 5745833-5745836							
Hexavalent Chromium	< 0.020	0.020	mg/l	99		90-110		
Batch number: 09225021201A	Sample number(s): 5745830-5745831, 5745833-5745836							
Total Dissolved Solids	< 30.0	30.0	mg/l	91		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09224A53A	Sample number(s): 5745830-5745831, 5745833-5745837. UNSPK: 5745834, 5745835								
Benzene	120		70-152						
Ethylbenzene	120		75-133						
Toluene	115		78-129						
TPH-GRO water C6-C10	118		63-154						

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/20/09 at 04:08 PM

Group Number: 1157030

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Total Xylenes	120		67-155						
Batch number: 09224A54A	Sample number(s): 5745832 UNSPK: P745983								
Benzene	95		70-152						
Ethylbenzene	100		75-133						
Toluene	95		78-129						
Total Xylenes	97		67-155						
Batch number: 092295705001	Sample number(s): 5745830-5745831, 5745833-5745836 UNSPK: P749992 BKG: P749992								
Arsenic	110	110	75-125	1	20	< 0.0200	< 0.0200	0 (1)	20
Chromium	99	98	81-120	1	20	< 0.0150	< 0.0150	9 (1)	20
Iron	65 (2)	58 (2)	75-125	1	20	10.7	10.3	4	20
Manganese	98	93	75-125	2	20	0.745	0.715	4	20
Batch number: 09224196602A	Sample number(s): 5745830-5745831, 5745833-5745836 UNSPK: P746458 BKG: P746458								
Chloride	110		90-110			12,100	12,100	0	20
Batch number: 09223027601A	Sample number(s): 5745830-5745831, 5745833-5745836 UNSPK: 5745831 BKG: 5745831								
Hexavalent Chromium	104	101	85-115	2	5	0.063	0.065	2 (1)	5
Batch number: 09225021201A	Sample number(s): 5745830-5745831, 5745833-5745836 UNSPK: P746458 BKG: P746458								
Total Dissolved Solids	94	108	54-143	4	12	38,900	44,600	14*	9

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: TPH-GRO water C6-C10

Batch number: 09224A53A

Trifluorotoluene-F	Trifluorotoluene-P
5745830	83
5745831	82
5745833	83
5745834	81
5745835	82
5745836	81
5745837	
Blank	84
LCS	85
LCSD	85
MS	83

Limits: 63-135 69-129

Analysis Name: BTEX (8021)

Batch number: 09224A54A

Trifluorotoluene-F	Trifluorotoluene-P
--------------------	--------------------

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control SummaryClient Name: STANTEC International, Inc.
Reported: 08/20/09 at 04:08 PM

Group Number: 1157030

Surrogate Quality Control

5745832		113
Blank	115	116
LCS	115	114
LCS	111	116
MS	107	112

Limits:	63-135	69-129
---------	--------	--------

Analysis Name: TPH-DRO water C10-C28
Batch number: 092240009A
Orthoterphenyl

5745830	93
5745831	101
5745833	99
5745834	105
5745835	91
5745836	90
Blank	86
LCS	111
LCS	101

Limits:	54-127
---------	--------

*- Outside of specification

(1) The result for one or both determinations was less than five times the LOQ.

(2) The unspiked result was more than four times the spike added.

**Lancaster
Laboratories**

Accl. # 11842

COC # 217445

Please print. Instructions on reverse side correspond with circled numbers.

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories
Where quality is a science.

SCR#:

Group # 1157030

3566 Rev. 1/31/02

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300

Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories

Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

August 21, 2009

SAMPLE GROUP

The sample group for this submittal is 1157230. Samples arrived at the laboratory on Wednesday, August 12, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

Client Description

IW023 Grab Water Sample
IW024 Grab Water Sample
MW090SA Grab Water Sample
Trip Blank Water Sample

Lancaster Labs Number

5747033
5747034
5747035
5747036

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC STANTEC International, Inc.
COPY TO
ELECTRONIC STANTEC International, Inc.
COPY TO

Attn: Chad Vowell

Attn: Steve Bell



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,


Robert Strocko Jr.
Manager

Lancaster Laboratories Sample No. WW 5747033

Group No. 1157230

IW023 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/11/2009 12:07 by SB

Account Number: 11842

Submitted: 08/12/2009 09:00
Reported: 08/21/2009 at 10:11
Discard: 09/21/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

ENP23

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	< 95	95	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.300	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
01767	Sodium	7440-23-5	343	5.00	5
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	637	80.0	200
00228	Sulfate	14808-79-8	774	100	100
SM20 5310 C	Wet Chemistry		mg/l	mg/l	
00273	Total Organic Carbon	n.a.	4.4	1.0	1
SM20 2320 B	Wet Chemistry		mg/l as CaCO3	mg/l as CaCO3	
00202	Alkalinity to pH 4.5	n.a.	240	2.0	1
00201	Alkalinity to pH 8.3	n.a.	< 2.0	2.0	1
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	2,700	240	1
SM20 4500 H/B	Wet Chemistry		Std. Units	Std. Units	
00200	pH	n.a.	7.1	0.010	1
SM20 4500 S2 D	Wet Chemistry		mg/l	mg/l	
00230	Sulfide	18496-25-8	< 0.16	0.16	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.28	0.020	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5747033

Group No. 1157230

IW023 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/11/2009 12:07 by SB

Account Number: 11842

Submitted: 08/12/2009 09:00

STANTEC International, Inc.

Reported: 08/21/2009 at 10:11

10235 W. Little York

Discard: 09/21/2009

Ste 400

Houston TX 77040

ENP23

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
0636	TPH-GRO water C6-C10	SW-846 8015B	1	09225A53A	08/13/2009 20:12	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09225A53A	08/13/2009 20:12	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09225A53A	08/13/2009 20:12	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092240023A	08/14/2009 10:42	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092240023A	08/13/2009 08:55	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092295705001	08/19/2009 17:00	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092295705001	08/19/2009 17:00	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092295705001	08/19/2009 17:00	Eric L Eby	1
07058	Manganese	SW-846 6010B	1	092295705001	08/19/2009 17:00	Eric L Eby	1
01767	Sodium	SW-846 6010B	1	092295705001	08/20/2009 10:23	Joanne M Gates	5
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092295705001	08/18/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09225196602A	08/15/2009 01:01	Ashley M Adams	200
00228	Sulfate	EPA 300.0	1	09225196602A	08/14/2009 01:54	Ashley M Adams	100
00273	Total Organic Carbon	SM20 5310 C	1	09229049502A	08/17/2009 02:02	James S Mathiot	1
00202	Alkalinity to pH 4.5	SM20 2320 B	1	09229020201A	08/17/2009 18:08	Geraldine C Smith	1
00201	Alkalinity to pH 8.3	SM20 2320 B	1	09229020201A	08/17/2009 18:08	Geraldine C Smith	1
00212	Total Dissolved Solids	SM20 2540 C	1	09229021201A	08/17/2009 09:17	Susan E Hibner	1
00200	pH	SM20 4500 H/B	1	09224020001A	08/12/2009 22:40	Luz M Groff	1
00230	Sulfide	SM20 4500 S2 D	1	09224023002A	08/12/2009 22:01	Geraldine C Smith	1
00276	Hexavalent Chromium	SW-846 7196A	1	09224027604A	08/12/2009 10:10	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5747034

Group No. 1157230

IW024 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/11/2009 13:50 by SB

Account Number: 11842

Submitted: 08/12/2009 09:00
Reported: 08/21/2009 at 10:11
Discard: 09/21/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston, TX 77040

ENP24

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	< 96	96	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	1.47	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.398	0.0050	1
01767	Sodium	7440-23-5	601	10.0	10
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	1,020	80.0	200
00228	Sulfate	14808-79-8	1,670	200	200
SM20 5310 C	Wet Chemistry		mg/l	mg/l	
00273	Total Organic Carbon	n.a.	6.3	1.0	1
SM20 2320 B	Wet Chemistry		mg/l as CaCO3	mg/l as CaCO3	
00202	Alkalinity to pH 4.5	n.a.	210	2.0	1
00201	Alkalinity to pH 8.3	n.a.	< 2.0	2.0	1
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	4,840	600	1
SM20 4500 H/B	Wet Chemistry		Std. Units	Std. Units	
00200	pH	n.a.	7.2	0.010	1
SM20 4500 S2 D	Wet Chemistry		mg/l	mg/l	
00230	Sulfide	18496-25-8	< 0.16	0.16	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	1.2	0.040	2

Lancaster Laboratories Sample No. WW 5747034

Group No. 1157230

NM

IW024 Grab Water Sample
Eunice North Gas Plant

Collected: 08/11/2009 13:50 by SB

Account Number: 11842

Submitted: 08/12/2009 09:00

STANTEC International, Inc.

Reported: 08/21/2009 at 10:11

10235 W. Little York

Discard: 09/21/2009

Ste 400

Houston TX 77040

ENP24

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
0636	TPH-GRO water C6-C10	SW-846 8015B	1	09225A53A	08/13/2009 20:36	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09225A53A	08/13/2009 20:36	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09225A53A	08/13/2009 20:36	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092240023A	08/14/2009 11:23	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092240023A	08/13/2009 08:55	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092295705001	08/19/2009 17:04	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092295705001	08/19/2009 17:04	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092295705001	08/19/2009 17:04	Eric L Eby	1
07058	Manganese	SW-846 6010B	1	092295705001	08/19/2009 17:04	Eric L Eby	1
01767	Sodium	SW-846 6010B	1	092295705001	08/20/2009 10:26	Joanne M Gates	10
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092295705001	08/18/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09225196602A	08/15/2009 01:17	Ashley M Adams	200
00228	Sulfate	EPA 300.0	1	09225196602A	08/15/2009 01:17	Ashley M Adams	200
00273	Total Organic Carbon	SM20 5310 C	1	09229049502A	08/17/2009 02:09	James S Mathiot	1
00202	Alkalinity to pH 4.5	SM20 2320 B	1	09229020201A	08/17/2009 18:08	Geraldine C Smith	1
00201	Alkalinity to pH 8.3	SM20 2320 B	1	09229020201A	08/17/2009 18:08	Geraldine C Smith	1
00212	Total Dissolved Solids	SM20 2540 C	1	09229021201A	08/17/2009 09:17	Susan E Hibner	1
00200	pH	SM20 4500 H/B	1	09224020001A	08/12/2009 22:40	Luz M Groff	1
00230	Sulfide	SM20 4500 S2 D	1	09224023002A	08/12/2009 22:01	Geraldine C Smith	1
00276	Hexavalent Chromium	SW-846 7196A	1	09224027604A	08/12/2009 10:10	Michelle L Lalli	2



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5747035

Group No. 1157230

MW090SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/11/2009 15:31 by SB

Account Number: 11842

Submitted: 08/12/2009 09:00

STANTEC International, Inc.

Reported: 08/21/2009 at 10:11

10235 W. Little York

Discard: 09/21/2009

Ste 400

Houston TX 77040

ENP90

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	< 96	96	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.580	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
01767	Sodium	7440-23-5	472	10.0	10
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	648	80.0	200
00228	Sulfate	14808-79-8	1,170	100	100
SM20 5310 C	Wet Chemistry		mg/l	mg/l	
00273	Total Organic Carbon	n.a.	5.5	1.0	1
SM20 2320 B	Wet Chemistry		mg/l as CaCO3	mg/l as CaCO3	
00202	Alkalinity to pH 4.5	n.a.	231	2.0	1
00201	Alkalinity to pH 8.3	n.a.	< 2.0	2.0	1
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	3,290	240	1
SM20 4500 H/B	Wet Chemistry		Std. Units	Std. Units	
00200	pH	n.a.	7.1	0.010	1
SM20 4500 S2 D	Wet Chemistry		mg/l	mg/l	
00230	Sulfide	18496-25-8	< 0.16	0.16	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.52	0.020	1

Lancaster Laboratories Sample No. WW 5747035

Group No. 1157230

MW090SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/11/2009 15:31 by SB

Account Number: 11842

Submitted: 08/12/2009 09:00

STANTEC International, Inc.

Reported: 08/21/2009 at 10:11

10235 W. Little York

Discard: 09/21/2009

Ste 400

Houston TX 77040

ENP90

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT NO.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
0636	TPH-GRO water C6-C10	SW-846 8015B	1	09225A53A	08/13/2009 21:00	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09225A53A	08/13/2009 21:00	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09225A53A	08/13/2009 21:00	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092240023A	08/14/2009 11:43	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092240023A	08/13/2009 08:55	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092295705001	08/19/2009 17:09	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092295705001	08/19/2009 17:09	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092295705001	08/19/2009 17:09	Eric L Eby	1
07058	Manganese	SW-846 6010B	1	092295705001	08/19/2009 17:09	Eric L Eby	1
01767	Sodium	SW-846 6010B	1	092295705001	08/20/2009 10:35	Joanne M Gates	10
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092295705001	08/18/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09225196602A	08/15/2009 01:32	Ashley M Adams	200
00228	Sulfate	EPA 300.0	1	09225196602A	08/14/2009 02:25	Ashley M Adams	100
00273	Total Organic Carbon	SM20 5310 C	1	09229049502A	08/17/2009 02:33	James S Mathiot	1
00202	Alkalinity to pH 4.5	SM20 2320 B	1	09229020201A	08/17/2009 18:08	Geraldine C Smith	1
00201	Alkalinity to pH 8.3	SM20 2320 B	1	09229020201A	08/17/2009 18:08	Geraldine C Smith	1
00212	Total Dissolved Solids	SM20 2540 C	1	09229021201A	08/17/2009 09:17	Susan E Hibner	1
00200	pH	SM20 4500 H/B	1	09224020001A	08/12/2009 22:40	Luz M Groff	1
00230	Sulfide	SM20 4500 S2 D	1	09224023002A	08/12/2009 22:01	Geraldine C Smith	1
00276	Hexavalent Chromium	SW-846 7196A	1	09224027604A	08/12/2009 10:10	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5747036

Group No. 1157230

NM

Trip Blank Water Sample
Eunice North Gas Plant

Collected: 08/11/2009

Account Number: 11842

Submitted: 08/12/2009 09:00

STANTEC International, Inc.

Reported: 08/21/2009 at 10:11

10235 W. Little York

Discard: 09/21/2009

Ste 400

Houston TX 77040

ENPTB

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846	8021B		GC Volatiles	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09225A53A	08/13/2009 18:59	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09225A53A	08/13/2009 18:59	Marie D John	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/21/09 at 10:11 AM

Group Number: 1157230

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09225A53A	Sample number(s): 5747033-5747036							
Benzene	< 1.0	1.0	ug/l	120	105	80-120	13	30
Ethylbenzene	< 1.0	1.0	ug/l	115	100	80-120	14	30
Toluene	< 1.0	1.0	ug/l	115	100	80-120	14	30
TPH-GRO water C6-C10	< 50	50	ug/l	127	127	75-135	0	30
Total Xylenes	< 3.0	3.0	ug/l	115	103	80-120	11	30
Batch number: 092240023A	Sample number(s): 5747033-5747035							
TPH-DRO water C10-C28	< 100	100	ug/l	56	61	56-122	9	20
Batch number: 092295705001	Sample number(s): 5747033-5747035							
Arsenic	< 0.0200	0.0200	mg/l	106		80-120		
Chromium	< 0.0150	0.0150	mg/l	100		90-110		
Iron	< 0.200	0.200	mg/l	94		90-112		
Manganese	< 0.0050	0.0050	mg/l	103		90-110		
Sodium	< 1.00	1.00	mg/l	107		80-120		
Batch number: 09225196602A	Sample number(s): 5747033-5747035							
Chloride	< 0.40	0.40	mg/l	97		90-110		
Sulfate	< 1.0	1.0	mg/l	98		89-110		
Batch number: 09229049502A	Sample number(s): 5747033-5747035							
Total Organic Carbon	< 1.0	1.0	mg/l	105		91-113		
Batch number: 09224020001A	Sample number(s): 5747033-5747035							
pH				100		99-101		
Batch number: 09224023002A	Sample number(s): 5747033-5747035							
Sulfide	< 0.16	0.16	mg/l	100		90-110		
Batch number: 09224027604A	Sample number(s): 5747033-5747035							
Hexavalent Chromium	< 0.020	0.020	mg/l	105		90-110		
Batch number: 09229020201A	Sample number(s): 5747033-5747035							
Alkalinity to pH 4.5	< 2.0	2.0	mg/l as CaCO ₃	100		98-103		
Batch number: 09229021201A	Sample number(s): 5747033-5747035							
Total Dissolved Solids	< 30.0	30.0	mg/l	97		80-120		

Sample Matrix Quality Control

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.

Group Number: 1157230

Reported: 08/21/09 at 10:11 AM

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike

Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09225A53A	Sample number(s): 5747033-5747036 UNSPK: P747285								
Benzene	115	110	70-152	4	30				
Ethylbenzene	115	115	75-133	0	30				
Toluene	115	115	78-129	0	30				
TPH-GRO water C6-C10	118	118	63-154	0	30				
Total Xylenes	117	117	67-155	0	30				
Batch number: 092295705001	Sample number(s): 5747033-5747035 UNSPK: P749992 BKG: P749992								
Arsenic	110	110	75-125	1	20	< 0.0200	< 0.0200	0 (1)	20
Chromium	99	98	81-120	1	20	< 0.0150	< 0.0150	9 (1)	20
Iron	65 (2)	58 (2)	75-125	1	20	10.7	10.3	4	20
Manganese	98	93	75-125	2	20	0.745	0.715	4	20
Sodium	236 (2)	-105 (2)	75-125	6	20	568	563	1	20
Batch number: 09225196602A	Sample number(s): 5747033-5747035 UNSPK: P747981 BKG: P747981								
Chloride	73*		90-110			136	133	2	20
Sulfate	104		90-110			24.7	24.9	1 (1)	20
Batch number: 09229049502A	Sample number(s): 5747033-5747035 UNSPK: P749246 BKG: P749246								
Total Organic Carbon	114		64-141			2.8	2.8	2 (1)	4
Batch number: 09224020001A	Sample number(s): 5747033-5747035 BKG: P743504								
pH						7.3	7.3	0	1
Batch number: 09224023002A	Sample number(s): 5747033-5747035 UNSPK: P747138 BKG: P748130								
Sulfide	100	99	69-133	1	18	3.5	3.5	0	7
Batch number: 09224027604A	Sample number(s): 5747033-5747035 UNSPK: P747106 BKG: P747106								
Hexavalent Chromium	102	100	85-115	2	5	< 0.020	< 0.020	0 (1)	5
Batch number: 09229020201A	Sample number(s): 5747033-5747035 UNSPK: P744684 BKG: P744684								
Alkalinity to pH 4.5	99	99	64-130	0	2	34.7	34.7	0	4
Alkalinity to pH 8.3						< 2.0	< 2.0	0 (1)	4
Batch number: 09229021201A	Sample number(s): 5747033-5747035 UNSPK: P747300 BKG: P747300								
Total Dissolved Solids	95	98	54-143	1	12	48,200	47,400	2	9

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: TPH-GRO water C6-C10

Batch number: 09225A53A

Trifluorotoluene-F

Trifluorotoluene-P

5747033	80	97
5747034	80	97
5747035	82	98
5747036		96

*- Outside of specification

(1) The result for one or both determinations was less than five times the LOQ.

(2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/21/09 at 10:11 AM

Group Number: 1157230

Surrogate Quality Control

Blank	83	97
LCS	88	98
LCSD	86	99
MS	83	98
MSD	82	98

Limits: 63-135 69-129

Analysis Name: TPH-DRO water C10-C28
Batch number: 092240023A
Orthoterphenyl

5747033	76
5747034	78
5747035	85
Blank	70
LCS	86
LCSD	91

Limits: 54-127

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Lancaster
Laboratories

For Lancaster Laboratories use only

Acct. # 11842

Group#

1157230

Sample #5747033-36

CCC

217446

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Chercon</u> Acct. #: <u> </u>		Project Name: <u>REENTRY/212701/35.206PWSID#</u>		Project Manager: <u>Chad Vassell</u> P.O.#: <u> </u>		Sampler: <u>Steve Ball & Terry Lowrey</u> Quote #: <u> </u>		Name of state where samples were collected: <u>New Mexico</u>	
2		3	4	5 Analytes Requested		6		7	
Sample	Date	Time	Container	Water	Soil	Preservation Codes	Preservation Codes	Remarks	Time
120025	8-11-09	1207	X	X	X	TPH 020 BTEX (802)	TPH 020 BTEX (802)	Filter - Diox. Metals in Lab	2.3-24
120024	8-11-09	1350	X	X	X	TPH 020 BTEX (802)	TPH 020 BTEX (802)	"	"
120025A	8-11-09	1531	X	X	X	TPH 020 BTEX (802)	TPH 020 BTEX (802)	"	"
Trip Blank				X	X	TPH 020 BTEX (802)	TPH 020 BTEX (802)		

7 Turnaround Time Requested (TAT) (please circle) <u>Normal</u> Rush		Date results are needed: <u> </u>		Rush results requested by (please circle): <u> </u>		Phone # <u> </u> Fax <u> </u>		E-mail address: <u> </u>	
TX TRRP-13		Date		Time		Date		Time	
MA MCP		Date		Time		Date		Time	
Site-specific QC (MS/MSD/Dup)?		Date		Time		Date		Time	
Type I (Validation/NJ Reg)		Date		Time		Date		Time	
Type II (Tier II)		Date		Time		Date		Time	
Type III (Reduced NJ)		Date		Time		Date		Time	
Type IV (CLP SOW)		Date		Time		Date		Time	
Type VI (Raw Data Only)		Date		Time		Date		Time	

8 Data Package Options (please circle if required)		SDG Complete?	
Type I (Validation/NJ Reg)	TX TRRP-13	Yes	No
Type II (Tier II)	MA MCP	Yes	No
Type III (Reduced NJ)	Site-specific QC (MS/MSD/Dup)?	Yes	No
Type IV (CLP SOW)	(If yes, indicate QC sample and name indicate volume)	Yes	No
Type VI (Raw Data Only)	Internal COC Required? Yes / No	Yes	No

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 650-2300 Fax: (717) 650-0700
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

2102.03

Lancaster Laboratories Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

August 24, 2009

SAMPLE GROUP

The sample group for this submittal is 1157439. Samples arrived at the laboratory on Thursday, August 13, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

Client Description

MW024A Grab Water Sample
MW059 Grab Water Sample
MW023 Grab Water Sample
MW048SA Grab Water Sample
MW055SA Grab Water Sample
MW056SA Grab Water Sample
Trip Blank Water Sample

Lancaster Labs Number

5748266
5748267
5748268
5748269
5748270
5748271
5748272

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC COPY TO STANTEC International, Inc.
ELECTRONIC COPY TO STANTEC International, Inc.
ELECTRONIC COPY TO STANTEC

Attn: Chad Vowell

Attn: Steve Bell

Attn: Daniel Woodward



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

A handwritten signature in cursive script that reads "Tracy A. Cole".

Tracy A. Cole
Senior Specialist



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5748266

Group No. 1157439

MW024A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/12/2009 10:40 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EU24A

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	2.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	1.3	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	240	95	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.0307	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	63.5	8.0	20
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	452	30.0	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.034	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09229A94A	08/17/2009 19:06	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09229A94A	08/17/2009 19:06	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09229A94A	08/17/2009 19:06	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092270009A	08/19/2009 00:38	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092270009A	08/17/2009 08:45	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092325705002	08/21/2009 09:06	Joanne M Gates	1
07051	Chromium	SW-846 6010B	1	092325705002	08/21/2009 09:06	Joanne M Gates	1
01754	Iron	SW-846 6010B	1	092325705002	08/21/2009 09:06	Joanne M Gates	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5748266

Group No. 1157439

MW024A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/12/2009 10:40 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EU24A

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092325705002	08/21/2009 09:06	Joanne M Gates	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092325705002	08/20/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09226196601A	08/19/2009 02:20	Joseph E McKenzie	20
00212	Total Dissolved Solids	SM20 2540 C	1	09229021202A	08/17/2009 12:14	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09225027601A	08/13/2009 09:45	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5748267

Group No. 1157439

MW059 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/12/2009 12:04 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EUN59

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	110	97	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	0.0232	0.0200	1
07051	Chromium	7440-47-3	0.210	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	497	200	500
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	2,260	240	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.22	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09229A94A	08/17/2009 19:58	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09229A94A	08/17/2009 19:58	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09229A94A	08/17/2009 19:58	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092270009A	08/19/2009 00:59	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092270009A	08/17/2009 08:45	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092325705002	08/21/2009 09:24	Joanne M Gates	1
07051	Chromium	SW-846 6010B	1	092325705002	08/21/2009 09:24	Joanne M Gates	1
01754	Iron	SW-846 6010B	1	092325705002	08/21/2009 09:24	Joanne M Gates	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5748267

Group No. 1157439

MW059 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/12/2009 12:04 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EUN59

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092325705002	08/21/2009 09:24	Joanne M Gates	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092325705002	08/20/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09226196601A	08/14/2009 15:45	Ashley M Adams	500
00212	Total Dissolved Solids	SM20 2540 C	1	09229021202A	08/17/2009 12:14	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09225027601A	08/13/2009 09:45	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5748268

Group No. 1157439

MW023 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/12/2009 13:09 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EUN23

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	96	96	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	0.0218	0.0200	1
07051	Chromium	7440-47-3	1.69	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	771	200	500
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	3,890	240	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	1.6	0.040	2

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09229A94A	08/17/2009 20:25	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09229A94A	08/17/2009 20:25	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09229A94A	08/17/2009 20:25	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092270009A	08/19/2009 01:19	Diane V Do	1
0003	Extraction - DRO (Waters)	SW-846 3510C	1	092270009A	08/17/2009 08:45	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092325705002	08/21/2009 09:27	Joanne M Gates	1
07051	Chromium	SW-846 6010B	1	092325705002	08/21/2009 09:27	Joanne M Gates	1
01754	Iron	SW-846 6010B	1	092325705002	08/21/2009 09:27	Joanne M Gates	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5748268

Group No. 1157439

MW023 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/12/2009 13:09 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EUN23

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092325705002	08/21/2009 09:27	Joanne M Gates	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092325705002	08/20/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09226196601A	08/14/2009 16:01	Ashley M Adams	500
00212	Total Dissolved Solids	SM20 2540 C	1	09229021202A	08/17/2009 12:14	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09225027601A	08/13/2009 09:45	Michelle L Lalli	2

Lancaster Laboratories Sample No. WW 5748269

Group No. 1157439

MW048SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/12/2009 14:05 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EU48S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	< 96	96	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.310	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	492	200	500
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	1,740	240	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.32	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09229A94A	08/17/2009 20:51	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09229A94A	08/17/2009 20:51	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09229A94A	08/17/2009 20:51	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092270009A	08/19/2009 01:40	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092270009A	08/17/2009 08:45	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092325705002	08/21/2009 09:36	Joanne M Gates	1
07051	Chromium	SW-846 6010B	1	092325705002	08/21/2009 09:36	Joanne M Gates	1
01754	Iron	SW-846 6010B	1	092325705002	08/21/2009 09:36	Joanne M Gates	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5748269

Group No. 1157439

NM

MW048SA Grab Water Sample
Eunice North Gas Plant

Collected: 08/12/2009 14:05 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EU48S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092325705002	08/21/2009 09:36	Joanne M Gates	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092325705002	08/20/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09226196601A	08/14/2009 16:16	Ashley M Adams	500
00212	Total Dissolved Solids	SM20 2540 C	1	09229021202A	08/17/2009 12:14	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09225027601A	08/13/2009 09:45	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5748270

Group No. 1157439

MW055SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/12/2009 14:59 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EU55S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	< 95	95	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	0.243	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	589	200	500
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	1,830	240	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.25	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09229A94A	08/17/2009 21:18	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09229A94A	08/17/2009 21:18	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09229A94A	08/17/2009 21:18	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092270009A	08/19/2009 02:00	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092270009A	08/17/2009 08:45	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092325705002	08/21/2009 09:40	Joanne M Gates	1
07051	Chromium	SW-846 6010B	1	092325705002	08/21/2009 09:40	Joanne M Gates	1
01754	Iron	SW-846 6010B	1	092325705002	08/21/2009 09:40	Joanne M Gates	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5748270

Group No. 1157439

NM

MW055SA Grab Water Sample

Eunice North Gas Plant

Collected: 08/12/2009 14:59 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EU55S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092325705002	08/21/2009 09:40	Joanne M Gates	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092325705002	08/20/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09226196601A	08/14/2009 16:32	Ashley M Adams	500
00212	Total Dissolved Solids	SM20 2540 C	1	09229021202A	08/17/2009 12:14	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09225027601A	08/13/2009 09:45	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5748271

Group No. 1157439

MW056SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/12/2009 15:39 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EU56S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846 8015B	GC Volatiles		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
SW-846 8021B	GC Volatiles		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
SW-846 8015B	GC Extractable TPH		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	160	95	1
SW-846 6010B	Metals Dissolved		mg/l	mg/l	
07035	Arsenic	7440-38-2	0.0254	0.0200	1
07051	Chromium	7440-47-3	0.398	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
EPA 300.0	Wet Chemistry		mg/l	mg/l	
00224	Chloride	16887-00-6	1,330	200	500
SM20 2540 C	Wet Chemistry		mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	4,020	600	1
SW-846 7196A	Wet Chemistry		mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	0.41	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09229A94A	08/17/2009 21:44	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09229A94A	08/17/2009 21:44	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09229A94A	08/17/2009 21:44	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092270009A	08/19/2009 02:21	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092270009A	08/17/2009 08:45	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092325705002	08/21/2009 09:43	Joanne M Gates	1
07051	Chromium	SW-846 6010B	1	092325705002	08/21/2009 09:43	Joanne M Gates	1
01754	Iron	SW-846 6010B	1	092325705002	08/21/2009 09:43	Joanne M Gates	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5748271

Group No. 1157439

NM

MW056SA Grab Water Sample

Eunice North Gas Plant

Collected: 08/12/2009 15:39 by SB

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EU56S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092325705002	08/21/2009 09:43	Joanne M Gates	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092325705002	08/20/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09226196601A	08/14/2009 16:47	Ashley M Adams	500
00212	Total Dissolved Solids	SM20 2540 C	1	09229021202A	08/17/2009 12:14	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09225027601A	08/13/2009 09:45	Michelle L Lalli	1



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Page 1 of 1

Lancaster Laboratories Sample No. WW 5748272

Group No. 1157439

NM

Trip Blank Water Sample
Eunice North Gas Plant

Collected: 08/12/2009

Account Number: 11842

Submitted: 08/13/2009 09:05

STANTEC International, Inc.

Reported: 08/24/2009 at 15:13

10235 W. Little York

Discard: 09/24/2009

Ste 400

Houston TX 77040

EUN-T

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
SW-846	8021B		GC Volatiles	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09229A94B	08/18/2009 14:41	Carrie E Miller	1
01146	GC VOA Water Prep	SW-846 5030B	1	09229A94B	08/18/2009 14:41	Carrie E Miller	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/24/09 at 03:13 PM

Group Number: 1157439

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09229A94A	Sample number(s): 5748266-5748271							
Benzene	< 1.0	1.0	ug/l	115	115	80-120	0	30
Ethylbenzene	< 1.0	1.0	ug/l	110	110	80-120	0	30
Toluene	< 1.0	1.0	ug/l	110	110	80-120	0	30
TPH-GRO water C6-C10	< 50	50.	ug/l	109	100	75-135	9	30
Total Xylenes	< 3.0	3.0	ug/l	113	113	80-120	0	30
Batch number: 09229A94B	Sample number(s): 5748272							
Benzene	< 1.0	1.0	ug/l	115	115	80-120	0	30
Ethylbenzene	< 1.0	1.0	ug/l	110	110	80-120	0	30
Toluene	< 1.0	1.0	ug/l	110	110	80-120	0	30
Total Xylenes	< 3.0	3.0	ug/l	113	113	80-120	0	30
Batch number: 092270009A	Sample number(s): 5748266-5748271							
TPH-DRO water C10-C28	< 100	100.	ug/l	94	89	56-122	5	20
Batch number: 092325705002	Sample number(s): 5748266-5748271							
Arsenic	< 0.0200	0.0200	mg/l	105		80-120		
Chromium	< 0.0150	0.0150	mg/l	99		90-110		
Iron	< 0.200	0.200	mg/l	97		90-112		
Manganese	< 0.0050	0.0050	mg/l	103		90-110		
Batch number: 09226196601A	Sample number(s): 5748266-5748271							
Chloride	< 0.40	0.40	mg/l	97		90-110		
Batch number: 09225027601A	Sample number(s): 5748266-5748271							
Hexavalent Chromium	< 0.020	0.020	mg/l	105		90-110		
Batch number: 09229021202A	Sample number(s): 5748266-5748271							
Total Dissolved Solids	< 30.0	30.0	mg/l	96		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09229A94A	Sample number(s): 5748266-5748271 UNSPK: P748635, P748637								
Benzene	130		70-152						
Ethylbenzene	125		75-133						
Toluene	125		78-129						
TPH-GRO water C6-C10	127		63-154						

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.

Group Number: 1157439

Reported: 08/24/09 at 03:13 PM

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

<u>Analysis Name</u>	<u>MS</u>	<u>MSD</u>	<u>MS/MSD</u>	<u>RPD</u>	<u>RPD</u>	<u>BKG</u>	<u>DUP</u>	<u>DUP</u>	<u>Dup RPD</u>
<u>Total Xylenes</u>	<u>%REC</u>	<u>%REC</u>	<u>Limits</u>	<u>RPD</u>	<u>MAX</u>	<u>Conc</u>	<u>Conc</u>	<u>RPD</u>	<u>Max</u>
Total Xylenes	128		67-155						
Batch number: 09229A94B	Sample number(s): 5748272 UNSPK: P748635								
Benzene	130		70-152						
Ethylbenzene	125		75-133						
Toluene	125		78-129						
Total Xylenes	128		67-155						
Batch number: 092325705002	Sample number(s): 5748266-5748271 UNSPK: 5748266 BKG: 5748266								
Arsenic	107	106	75-125	1	20	< 0.0200	< 0.0200	7 (1)	20
Chromium	99	99	81-120	0	20	0.0307	0.0311	1 (1)	20
Iron	97	97	75-125	0	20	< 0.200	< 0.200	0 (1)	20
Manganese	103	103	75-125	0	20	< 0.0050	< 0.0050	0 (1)	20
Batch number: 09226196601A	Sample number(s): 5748266-5748271 UNSPK: P748640 BKG: P748640								
Chloride	99		90-110			11,000	10,900	1	20
Batch number: 09225027601A	Sample number(s): 5748266-5748271 UNSPK: 5748266 BKG: 5748266								
Hexavalent Chromium	109	102	85-115	5	5	0.034	0.034	0 (1)	5
Batch number: 09229021202A	Sample number(s): 5748266-5748271 UNSPK: P748640 BKG: P748640								
Total Dissolved Solids	102	101	54-143	1	12	22,900	22,700	1	9

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: BTEX (8021)

Batch number: 09229A94A

	Trifluorotoluene-F	Trifluorotoluene-P
5748266	86	100
5748267	87	100
5748268	86	99
5748269	86	101
5748270	86	100
5748271	85	100
Blank	85	99
LCS	95	100
LCSD	93	99
MS	93	100

Limits: 63-135 69-129

Analysis Name: BTEX (8021)

Batch number: 09229A94B

	Trifluorotoluene-F	Trifluorotoluene-P
5748272		100

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control SummaryClient Name: STANTEC International, Inc.
Reported: 08/24/09 at 03:13 PM

Group Number: 1157439

Surrogate Quality Control

Blank	85	100
LCS	95	100
LCSD	93	99
MS	93	100

Limits:	63-135	69-129
---------	--------	--------

Analysis Name: TPH-DRO water C10-C28
Batch number: 092270009A
Orthoterphenyl

5748266	98
5748267	97
5748268	95
5748269	93
5748270	100
5748271	99
Blank	92
LCS	110
LCSD	101

Limits:	54-127
---------	--------

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Lancaster Laboratories Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2881 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

August 31, 2009

SAMPLE GROUP

The sample group for this submittal is 1157622. Samples arrived at the laboratory on Friday, August 14, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

Client Description

IW025 Grab Water Sample
IW026 Grab Water Sample
MW084SA Grab Water Sample
Trip Blank Water Sample

Lancaster Labs Number

5749423
5749424
5749425
5749426

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC COPY TO STANTEC International, Inc.
ELECTRONIC COPY TO STANTEC International, Inc.

Attn: Chad Vowell

Attn: Steve Bell



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

A handwritten signature in black ink that reads "Max E. Snively".

Max E. Snively
Senior Specialist

Analysis Report

Page 1 of 2

Lancaster Laboratories Sample No. WW 5749423

Group No. 1157622

IW025 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/13/2009 13:21 by JL

Account Number: 11842

Submitted: 08/14/2009 09:00

STANTEC International, Inc.

Reported: 08/31/2009 at 14:12

10235 W. Little York

Discard: 10/01/2009

Ste 400

Houston TX 77040

IW025

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	5.8	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 190	ug/l 100	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	0.0387	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.263	0.0050	1
01767	Sodium	7440-23-5	563	10.0	10
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 582	mg/l 80.0	200
00228	Sulfate	14808-79-8	866	200	200
SM20 5310 C					
00273	Total Organic Carbon	n.a.	mg/l 60.8	mg/l 2.0	2
SM20 2320 B					
00202	Alkalinity to pH 4.5	n.a.	mg/l as CaCO3 799	mg/l as CaCO3 2.0	1
00201	Alkalinity to pH 8.3	n.a.	< 2.0	2.0	1
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 3,220	mg/l 240	1
SM20 4500 H/B					
00200	pH	n.a.	Std. Units 6.6	Std. Units 0.010	1
SM20 4500 S2 D					
00230	Sulfide	18496-25-8	mg/l 254	mg/l 32.0	200
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

Lancaster Laboratories Sample No. WW 5749423

Group No. 1157622

IW025 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/13/2009 13:21 by JL

Account Number: 11842

Submitted: 08/14/2009 09:00
Reported: 08/31/2009 at 14:12
Discard: 10/01/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

IW025

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
1636	TPH-GRO water C6-C10	SW-846 8015B	1	09232A54A	08/20/2009 20:57	Marie D John	1
213	BTEX (8021)	SW-846 8021B	1	09232A54A	08/20/2009 20:57	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09232A54A	08/20/2009 20:57	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092300008A	08/19/2009 18:42	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092300008A	08/18/2009 16:05	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092325705002	08/21/2009 09:46	Joanne M Gates	1
07051	Chromium	SW-846 6010B	1	092325705002	08/21/2009 09:46	Joanne M Gates	1
01754	Iron	SW-846 6010B	1	092325705002	08/21/2009 09:46	Joanne M Gates	1
07058	Manganese	SW-846 6010B	1	092325705002	08/21/2009 09:46	Joanne M Gates	1
01767	Sodium	SW-846 6010B	1	092325705002	08/24/2009 10:44	Joanne M Gates	10
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092325705002	08/20/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09231373102A	08/28/2009 21:41	Joseph E McKenzie	200
00228	Sulfate	EPA 300.0	1	09231373102A	08/24/2009 22:39	Joseph E McKenzie	200
00273	Total Organic Carbon	SM20 5310 C	1	09230049502B	08/19/2009 01:36	James S Mathiot	2
00202	Alkalinity to pH 4.5	SM20 2320 B	1	09229020201A	08/17/2009 18:08	Geraldine C Smith	1
00201	Alkalinity to pH 8.3	SM20 2320 B	1	09229020201A	08/17/2009 18:08	Geraldine C Smith	1
00212	Total Dissolved Solids	SM20 2540 C	1	09230021201A	08/18/2009 08:29	Hannah M Royer	1
00200	pH	SM20 4500 H/B	1	09226020001A	08/14/2009 20:45	Luz M Groff	1
00230	Sulfide	SM20 4500 S2 D	1	09230023002A	08/18/2009 22:09	Geraldine C Smith	200
00276	Hexavalent Chromium	SW-846 7196A	1	09226027601A	08/14/2009 10:00	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5749424

Group No. 1157622

IW026 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/13/2009 13:17 by JL

Account Number: 11842

Submitted: 08/14/2009 09:00
Reported: 08/31/2009 at 14:12
Discard: 10/01/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

IW026

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
Metals Dissolved					
	SW-846 6010B		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
01767	Sodium	7440-23-5	246	5.00	5
Wet Chemistry					
	EPA 300.0		mg/l	mg/l	
00224	Chloride	16887-00-6	460	40.0	100
00228	Sulfate	14808-79-8	390	100	100
SM20 2320 B					
			mg/l as CaCO3	mg/l as CaCO3	
00202	Alkalinity to pH 4.5	n.a.	256	2.0	1
00201	Alkalinity to pH 8.3	n.a.	< 2.0	2.0	1
SM20 2540 C					
			mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	1,640	120	1
SM20 4500 H/B					
			Std. Units	Std. Units	
00200	pH	n.a.	7.2	0.010	1
SW-846 7196A					
			mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	< 0.020	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092325705002	08/21/2009 09:49	Joanne M Gates	1
07051	Chromium	SW-846 6010B	1	092325705002	08/21/2009 09:49	Joanne M Gates	1
01754	Iron	SW-846 6010B	1	092325705002	08/21/2009 09:49	Joanne M Gates	1
07058	Manganese	SW-846 6010B	1	092325705002	08/21/2009 09:49	Joanne M Gates	1
01767	Sodium	SW-846 6010B	1	092325705002	08/24/2009 10:48	Joanne M Gates	5
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092325705002	08/20/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09231373102A	08/28/2009 23:07	Joseph E McKenzie	100
00228	Sulfate	EPA 300.0	1	09231373102A	08/24/2009 23:31	Joseph E McKenzie	100
00202	Alkalinity to pH 4.5	SM20 2320 B	1	09233020202A	08/21/2009 18:09	Geraldine C Smith	1
00201	Alkalinity to pH 8.3	SM20 2320 B	1	09233020202A	08/21/2009 18:09	Geraldine C Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5749424

Group No. 1157622

IW026 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/13/2009 13:17 by JL

Account Number: 11842

Submitted: 08/14/2009 09:00
Reported: 08/31/2009 at 14:12
Discard: 10/01/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

IW026

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
00212	Total Dissolved Solids	SM20 2540 C	1	09230021201A	08/18/2009 08:29	Hannah M Royer	1
00200	pH	SM20 4500 H/B	1	09232020001A	08/20/2009 22:30	Luz M Groff	1
00276	Hexavalent Chromium	SW-846 7196A	1	09226027601A	08/14/2009 10:00	Michelle L Lalli	1



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Page 1 of 2

Lancaster Laboratories Sample No. WW 5749425

Group No. 1157622

MW084SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/13/2009 15:29 by JL

Account Number: 11842

Submitted: 08/14/2009 09:00
Reported: 08/31/2009 at 14:12
Discard: 10/01/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW084

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 210	ug/l 93	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l 0.0229	mg/l 0.0200	1
07051	Chromium	7440-47-3	0.0982	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,980	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	SW-846 7196A n.a.	mg/l 4,760	mg/l 600	1
00276	Hexavalent Chromium	18540-29-9	mg/l 0.11	mg/l 0.020	1
This sample was analyzed twice for hexavalent chromium. The result of the second analysis was 0.10 mg/L.					

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09232A54A	08/20/2009 21:21	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09232A54A	08/20/2009 21:21	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09232A54A	08/20/2009 21:21	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092300008A	08/19/2009 18:21	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092300008A	08/18/2009 16:05	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092325705002	08/21/2009 09:52	Joanne M Gates	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5749425

Group No. 1157622

MW084SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/13/2009 15:29 by JL

Account Number: 11842

Submitted: 08/14/2009 09:00

STANTEC International, Inc.

Reported: 08/31/2009 at 14:12

10235 W. Little York

Discard: 10/01/2009

Ste 400

Houston TX 77040

MW084

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07051	Chromium	SW-846 6010B	1	092325705002	08/21/2009 09:52	Joanne M Gates	1
01754	Iron	SW-846 6010B	1	092325705002	08/21/2009 09:52	Joanne M Gates	1
07058	Manganese	SW-846 6010B	1	092325705002	08/21/2009 09:52	Joanne M Gates	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092325705002	08/20/2009 21:30	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09231373102A	08/28/2009 23:25	K. Robert Caulfeild-James	500
212	Total Dissolved Solids	SM20 2540 C	1	09230021201A	08/18/2009 08:29	Hannah M Royer	1
276	Hexavalent Chromium	SW-846 7196A	1	09226027601A	08/14/2009 10:00	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5749426

Group No. 1157622

NM

Trip Blank Water Sample
Eunice North Gas Plant

Collected: 08/13/2009

Account Number: 11842

Submitted: 08/14/2009 09:00

STANTEC International, Inc.

Reported: 08/31/2009 at 14:12

10235 W. Little York

Discard: 10/01/2009

Ste 400

Houston TX 77040

MW84T

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles		SW-846 8021B	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09232A54A	08/20/2009 17:25	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09232A54A	08/20/2009 17:25	Marie D John	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/31/09 at 02:12 PM

Group Number: 1157622

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09232A54A	Sample number(s): 5749423, 5749425-5749426							
Benzene	< 1.0	1.0	ug/l	105	110	80-120	5	30
Ethylbenzene	< 1.0	1.0	ug/l	95	100	80-120	5	30
Toluene	< 1.0	1.0	ug/l	95	100	80-120	5	30
TPH-GRO water: C6-C10	< 50	50	ug/l	100	100	75-135	0	30
Total Xylenes	< 3.0	3.0	ug/l	98	102	80-120	3	30
Batch number: 092300008A	Sample number(s): 5749423, 5749425							
TPH-DRO water C10-C28	< 100	100	ug/l	76	70	56-122	9	20
Batch number: 092325705002	Sample number(s): 5749423-5749425							
Arsenic	< 0.0200	0.0200	mg/l	105		80-120		
Chromium	< 0.0150	0.0150	mg/l	99		90-110		
Iron	< 0.200	0.200	mg/l	97		90-112		
Manganese	< 0.0050	0.0050	mg/l	103		90-110		
Sodium	< 1.00	1.00	mg/l	101		80-120		
Batch number: 09230049502B	Sample number(s): 5749423							
Total Organic Carbon	< 1.0	1.0	mg/l	109		91-113		
Batch number: 09231373102A	Sample number(s): 5749423-5749425							
Chloride	< 0.40	0.40	mg/l	107		90-110		
Sulfate	< 1.0	1.0	mg/l	104		89-110		
Batch number: 09226020001A	Sample number(s): 5749423							
pH				100		99-101		
Batch number: 09226027601A	Sample number(s): 5749423-5749425							
Hexavalent Chromium	< 0.020	0.020	mg/l	100		90-110		
Batch number: 09229020201A	Sample number(s): 5749423							
Alkalinity to pH 4.5	< 2.0	2.0	mg/l as CaCO ₃	100		98-103		
Batch number: 09230021201A	Sample number(s): 5749423-5749425							
Total Dissolved Solids	< 30.0	30.0	mg/l	97		80-120		
Batch number: 09230023002A	Sample number(s): 5749423							
Sulfide	< 0.16	0.16	mg/l	101		90-110		
Batch number: 09232020001A	Sample number(s): 5749424							
pH				100		99-101		
Batch number: 09233020202A	Sample number(s): 5749424							
Alkalinity to pH 4.5	< 2.0	2.0	mg/l as CaCO ₃	100		98-103		

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/31/09 at 02:12 PM

Group Number: 1157622

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09232A54A	Sample number(s): 5749423, 5749425-5749426 UNSPK: P748809, 5749425								
Benzene	115		70-152						
Ethylbenzene	115		75-133						
Toluene	110		78-129						
TPH-GRO water C6-C10	127		63-154						
Total Xylenes	117		67-155						
Batch number: 092325705002	Sample number(s): 5749423-5749425 UNSPK: P748266 BKG: P748266								
Arsenic	107	106	75-125	1	20	< 0.0200	< 0.0200	7 (1)	20
Chromium	99	99	81-120	0	20	0.0307	0.0311	1 (1)	20
Iron	97	97	75-125	0	20	< 0.200	< 0.200	0 (1)	20
Manganese	103	103	75-125	0	20	< 0.0050	< 0.0050	0 (1)	20
Sodium	90 (2)	101 (2)	75-125	2	20	48.2	47.8	1	20
Batch number: 09230049502B	Sample number(s): 5749423 UNSPK: P748640 BKG: P748640								
Total Organic Carbon	72		64-141			3.9	3.7	5* (1)	4
Batch number: 09231373102A	Sample number(s): 5749423-5749425 UNSPK: 5749423 BKG: 5749423								
Chloride	130*		90-110			582	616	6	20
Sulfate	141*		90-110			866	854	1	20
Batch number: 09226020001A	Sample number(s): 5749423 BKG: 5749423								
pH						6.6	6.6	0	1
Batch number: 09226027601A	Sample number(s): 5749423-5749425 UNSPK: 5749425 BKG: 5749425								
Hexavalent Chromium	105	103	85-115	1	5	0.11	0.11	3	5
Batch number: 09229020201A	Sample number(s): 5749423 UNSPK: P744684 BKG: P744684								
Alkalinity to pH 4.5	99	99	64-130	0	2	34.7	34.7	0	4
Alkalinity to pH 8.3						< 2.0	< 2.0	0 (1)	4
Batch number: 09230021201A	Sample number(s): 5749423-5749425 UNSPK: P750628 BKG: P750628								
Total Dissolved Solids	96	97	54-143	0	12	2,680	2,670	0	9
Batch number: 09230023002A	Sample number(s): 5749423 UNSPK: P749238 BKG: P749236								
Sulfide	97	97	69-133	0	18	7.7	7.8	0	7
Batch number: 09232020001A	Sample number(s): 5749424 BKG: 5749424								
pH						7.2	7.2	0	1
Batch number: 09233020202A	Sample number(s): 5749424 UNSPK: P750095 BKG: P750095								
Alkalinity to pH 4.5	99	99	64-130	0	2	56.5	57.8	2	4
Alkalinity to pH 8.3						< 2.0	< 2.0	0 (1)	4

Surrogate Quality Control

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 08/31/09 at 02:12 PM

Group Number: 1157622

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: BTEX (8021)

Batch number: 09232A54A

	Trifluorotoluene-F	Trifluorotoluene-P
5749423	107	112
5749425	101	109
5749426		114
Blank	107	112
LCS	116	112
LCSD	119	114
MS	107	109
Limits:	63-135	69-129

Analysis Name: TPH-DRO water C10-C28

Batch number: 092300008A

	Orthoterphenyl
5749423	84
5749425	97
Blank	81
LCS	108
LCSD	103
Limits:	54-127

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

**Lancaster
Laboratories**

Acct. # 11842

Group# 1157622 Sample # 5749423-26

COC # 217448

Please print. Instructions on reverse side correspond with circled numbers.

[illegible]

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2881 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

September 02, 2009

SAMPLE GROUP

The sample group for this submittal is 1157955. Samples arrived at the laboratory on Tuesday, August 18, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

Client Description

MW064SA Grab Water Sample
MW085SA Grab Water Sample
MW083SA Grab Water Sample
MW082SA Grab Water Sample
Trip Blank Water Sample

Lancaster Labs Number

5751568
5751569
5751570
5751571
5751572

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC STANTEC International, Inc.
COPY TO
ELECTRONIC STANTEC International, Inc.
COPY TO

Attn: Chad Vowell

Attn: Steve Bell



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

A handwritten signature in cursive script that reads "Max E. Snavelly".

Max E. Snavelly
Senior Specialist

Lancaster Laboratories Sample No. WW 5751568

Group No. 1157955

MW064SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/17/2009 10:09 by JSL

Account Number: 11842

Submitted: 08/18/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 11:41

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

W064S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 410	ug/l 110	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	0.0970	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,500	mg/l 200	500
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 3,320	mg/l 240	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l 0.098	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 04:26	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 04:26	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 04:26	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092320019A	08/22/2009 01:14	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092320019A	08/21/2009 06:00	Roman Kuropatkin	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5751568

Group No. 1157955

NM

MW064SA Grab Water Sample
Eunice North Gas Plant

Collected: 08/17/2009 10:09 by JSL

Account Number: 11842

Submitted: 08/18/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 11:41

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

W064S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705007	08/25/2009 05:24	Tara L Snyder	1
07051	Chromium	SW-846 6010B	1	092335705007	08/25/2009 05:24	Tara L Snyder	1
01754	Iron	SW-846 6010B	1	092335705007	08/25/2009 05:24	Tara L Snyder	1
07058	Manganese	SW-846 6010B	1	092335705007	08/25/2009 05:24	Tara L Snyder	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705007	08/23/2009 22:15	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09236373601B	08/28/2009 02:33	Joseph E McKenzie	500
0212	Total Dissolved Solids	SM20 2540 C	1	09232021201A	08/20/2009 08:47	Susan A Engle	1
0276	Hexavalent Chromium	SW-846 7196A	1	09230027601A	08/18/2009 10:05	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5751569

Group No. 1157955

MW085SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/17/2009 11:03 by JSL

Account Number: 11842

Submitted: 08/18/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 11:41

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

W085S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	n.a.	ug/l 440	ug/l 95	1
Metals Dissolved					
07035	Arsenic	7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	0.0156	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,300	mg/l 200	500
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 4,140	mg/l 600	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 04:50	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 04:50	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 04:50	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092320019A	08/22/2009 01:56	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092320019A	08/21/2009 06:00	Roman Kuropatkin	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5751569

Group No. 1157955

MW085SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/17/2009 11:03 by JSL

Account Number: 11842

Submitted: 08/18/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 11:41

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

W085S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705007	08/25/2009 05:29	Tara L Snyder	1
07051	Chromium	SW-846 6010B	1	092335705007	08/25/2009 05:29	Tara L Snyder	1
01754	Iron	SW-846 6010B	1	092335705007	08/25/2009 05:29	Tara L Snyder	1
07058	Manganese	SW-846 6010B	1	092335705007	08/25/2009 05:29	Tara L Snyder	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705007	08/23/2009 22:15	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09236373601B	08/28/2009 03:27	Joseph E McKenzie	500
212	Total Dissolved Solids	SM20 2540 C	1	09232021201A	08/20/2009 08:47	Susan A Engle	1
276	Hexavalent Chromium	SW-846 7196A	1	09230027601A	08/18/2009 10:05	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5751570

Group No. 1157955

MW083SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/17/2009 12:00 by JSL

Account Number: 11842

Submitted: 08/18/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 11:41

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

W083S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
C Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 420	ug/l 100	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	0.520	0.200	1
07058	Manganese	7439-96-5	1.09	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,980	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 4,170	mg/l 600	1
SW-846 7196A					
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 05:13	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 05:13	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 05:13	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092320019A	08/22/2009 01:35	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092320019A	08/21/2009 06:00	Roman Kuropatkin	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5751570

Group No. 1157955

MW083SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/17/2009 12:00 by JSL

Account Number: 11842

Submitted: 08/18/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 11:41

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

W083S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705007	08/25/2009 05:42	Tara L Snyder	1
07051	Chromium	SW-846 6010B	1	092335705007	08/25/2009 05:42	Tara L Snyder	1
01754	Iron	SW-846 6010B	1	092335705007	08/25/2009 05:42	Tara L Snyder	1
07058	Manganese	SW-846 6010B	1	092335705007	08/25/2009 05:42	Tara L Snyder	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705007	08/23/2009 22:15	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09236373601B	08/28/2009 03:45	Joseph E McKenzie	500
212	Total Dissolved Solids	SM20 2540 C	1	09232021201A	08/20/2009 08:47	Susan A Engle	1
276	Hexavalent Chromium	SW-846 7196A	1	09230027601A	08/18/2009 10:05	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5751571

Group No. 1157955

MW082SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/17/2009 13:20 by JSL

Account Number: 11842

Submitted: 08/18/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 11:41

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

W082S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 250	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	0.565	0.200	1
07058	Manganese	7439-96-5	3.15	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 366	mg/l 80.0	200
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 4,070	mg/l 600	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals..

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 05:37	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 05:37	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 05:37	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092320028A	08/24/2009 16:15	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092320028A	08/21/2009 09:35	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5751571

Group No. 1157955

MW082SA Grab Water Sample

Eunice North Gas Plant

NM

Collected: 08/17/2009 13:20 by JSL

Account Number: 11842

Submitted: 08/18/2009 09:05

Reported: 09/02/2009 at 11:41

Discard: 10/03/2009

STANTEC International, Inc.

10235 W. Little York

Ste 400

Houston TX 77040

W082S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705007	08/25/2009 05:46	Tara L Snyder	1
07051	Chromium	SW-846 6010B	1	092335705007	08/25/2009 05:46	Tara L Snyder	1
01754	Iron	SW-846 6010B	1	092335705007	08/25/2009 05:46	Tara L Snyder	1
07058	Manganese	SW-846 6010B	1	092335705007	08/25/2009 05:46	Tara L Snyder	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705007	08/23/2009 22:15	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09236373601B	08/24/2009 19:16	Ashley M Adams	200
212	Total Dissolved Solids	SM20 2540 C	1	09232021201A	08/20/2009 08:47	Susan A Engle	1
276	Hexavalent Chromium	SW-846 7196A	1	09230027601A	08/18/2009 10:05	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5751572

Group No. 1157955

NM

Trip Blank Water Sample
Eunice North Gas Plant

Collected: 08/17/2009

Account Number: 11842

Submitted: 08/18/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 11:41

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

W082T

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles		SW-846 8021B	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 02:04	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 02:04	Katrina T Longenecker	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 11:41 AM

Group Number: 1157955

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09233A54A	Sample number(s): 5751568-5751572							
Benzene	< 1.0	1.0	ug/l	110	110	80-120	0	30
Ethylbenzene	< 1.0	1.0	ug/l	100	100	80-120	0	30
Toluene	< 1.0	1.0	ug/l	105	100	80-120	5	30
TPH-GRO water C6-C10	< 50	50	ug/l	91	109	75-135	18	30
Total Xylenes	< 3.0	3.0	ug/l	103	102	80-120	2	30
Batch number: 092320019A	Sample number(s): 5751568-5751570							
TPH-DRO water C10-C28	< 100	100	ug/l	59		56-122		
Batch number: 092320028A	Sample number(s): 5751571							
TPH-DRO water C10-C28	< 100	100	ug/l	69	66	56-122	4	20
Batch number: 092335705007	Sample number(s): 5751568-5751571							
Arsenic	< 0.0200	0.0200	mg/l	101		80-120		
Chromium	< 0.0150	0.0150	mg/l	99		90-110		
Iron	< 0.200	0.200	mg/l	91		90-112		
Manganese	< 0.0050	0.0050	mg/l	99		90-110		
Batch number: 09236373601B	Sample number(s): 5751568-5751571							
Chloride	< 0.40	0.40	mg/l	96		90-110		
Batch number: 09230027601A	Sample number(s): 5751568-5751571							
Hexavalent Chromium	< 0.020	0.020	mg/l	101		90-110		
Batch number: 09232021201A	Sample number(s): 5751568-5751571							
Total Dissolved Solids	< 30.0	30.0	mg/l	105		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09233A54A	Sample number(s): 5751568-5751572 UNSPK: P751229, P752646								
Benzene	113		70-152						
Ethylbenzene	105		75-133						
Toluene	105		78-129						
TPH-GRO water C6-C10	100		63-154						
Total Xylenes	107		67-155						
Batch number: 092320019A	Sample number(s): 5751568-5751570 UNSPK: P749254								

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 11:41 AM

Group Number: 1157955

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
TPH-DRO water C10-C28	73	75	13-149	3	20				
Batch number: 092335705007	Sample number(s): 5751568-5751571 UNSPK: P752535 BKG: P752535								
Arsenic	102	102	75-125	0	20	< 0.0200	< 0.0200	0 (1)	20
Chromium	95	97	81-120	1	20	< 0.0150	< 0.0150	1 (1)	20
Iron	-6 (2)	32 (2)	75-125	2	20	21.6	21.3	1	20
Manganese	90	96	75-125	2	20	0.928	0.917	1	20
Batch number: 09236373601B	Sample number(s): 5751568-5751571 UNSPK: P751391 BKG: P751391								
Chloride	91		90-110			19,600	19,700	1 (1)	20
Batch number: 09230027601A	Sample number(s): 5751568-5751571 UNSPK: 5751568 BKG: 5751568								
Hexavalent Chromium	109	111	85-115	1	5	0.098	0.099	1 (1)	5
Batch number: 09232021201A	Sample number(s): 5751568-5751571 UNSPK: P752540 BKG: P752540								
Total Dissolved Solids	96	97	54-143	1	12	129	126	2 (1)	9

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: TPH-GRO water C6-C10

Batch number: 09233A54A

Trifluorotoluene-F Trifluorotoluene-P

5751568	104	117
5751569	107	116
5751570	102	114
5751571	105	113
5751572		113
Blank	102	114
LCS	117	115
LCSD	122	115
MS	113	116
Limits:	63-135	69-129

Analysis Name: TPH-DRO water C10-C28

Batch number: 092320019A

Orthoterphenyl

5751568	92
5751569	91
5751570	86
Blank	71
LCS	77
MS	81
MSD	84

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 11:41 AM

Group Number: 1157955

Surrogate Quality Control

Limits: 54-127

Analysis Name: TPH-DRO water C10-C28
Batch number: 092320028A
Orthoterphenyl

5751571	97
Blank	72
LCS	98
LCSD	94

Limits: 54-127

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Lancaster Laboratories Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

September 02, 2009

SAMPLE GROUP

The sample group for this submittal is 1158162. Samples arrived at the laboratory on Wednesday, August 19, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

Client Description

MW079SA Grab Water Sample
MW080SA Grab Water Sample
MW081SA Grab Water Sample
GOPWW2 Grab Water Sample
MW077SA Grab Water Sample
Trip Blank Water Sample

Lancaster Labs Number

5752643
5752644
5752645
5752646
5752647
5752648

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC STANTEC International, Inc.
COPY TO
ELECTRONIC STANTEC International, Inc.
COPY TO

Attn: Chad Vowell

Attn: Steve Bell



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

A handwritten signature in cursive script that reads "Max E. Snavelly".

Max E. Snavelly
Senior Specialist

Lancaster Laboratories Sample No. WW 5752643

Group No. 1158162

MW079SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/18/2009 11:17 by JL

Account Number: 11842

Submitted: 08/19/2009 09:00

STANTEC International, Inc.

Reported: 09/02/2009 at 11:44

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW079

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 97	ug/l 97	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.0893	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 398	mg/l 80.0	200
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 1,240	mg/l 120	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 06:00	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 06:00	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 06:00	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092320028A	08/24/2009 18:38	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092320028A	08/21/2009 09:35	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5752643

Group No. 1158162

MW079SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/18/2009 11:17 by JL

Account Number: 11842

Submitted: 08/19/2009 09:00

STANTEC International, Inc.

Reported: 09/02/2009 at 11:44

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW079

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 20:55	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 20:55	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 20:55	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 20:55	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09236373601B	08/24/2009 19:35	Ashley M Adams	200
0212	Total Dissolved Solids	SM20 2540 C	1	09233021201A	08/21/2009 08:37	Susan A Engle	1
0276	Hexavalent Chromium	SW-846 7196A	1	09231027601A	08/19/2009 09:45	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5752644

Group No. 1158162

MW080SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/18/2009 11:54 by JL

Account Number: 11842

Submitted: 08/19/2009 09:00

STANTEC International, Inc.

Reported: 09/02/2009 at 11:44

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW080

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
C Extractable TPH					
08269	TPH-DRO water C10-C28	n.a.	ug/l < 99	ug/l 99	1
Metals Dissolved					
07035	Arsenic	7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 735	mg/l 80.0	200
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 1,160	mg/l 120	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 06:24	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 06:24	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 06:24	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092320028A	08/24/2009 18:58	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092320028A	08/21/2009 09:35	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5752644

Group No. 1158162

MW080SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/18/2009 11:54 by JL

Account Number: 11842

Submitted: 08/19/2009 09:00

STANTEC International, Inc.

Reported: 09/02/2009 at 11:44

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW080

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 20:58	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 20:58	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 20:58	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 20:58	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09236373601B	08/24/2009 19:55	Ashley M Adams	200
0212	Total Dissolved Solids	SM20 2540 C	1	09233021201A	08/21/2009 08:37	Susan A Engle	1
0276	Hexavalent Chromium	SW-846 7196A	1	09231027601A	08/19/2009 09:45	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5752645

Group No. 1158162

MW081SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/18/2009 12:35 by JL

Account Number: 11842

Submitted: 08/19/2009 09:00
Reported: 09/02/2009 at 11:44
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW081

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 97	ug/l 97	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.0742	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,340	mg/l 200	500
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 1,640	mg/l 120	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 02:28	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 02:28	Katrina T Longenecker	1
146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 02:28	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092320028A	08/24/2009 19:19	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092320028A	08/21/2009 09:35	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5752645

Group No. 1158162

NM

MW081SA Grab Water Sample
Eunice North Gas Plant

Collected: 08/18/2009 12:35 by JL

Account Number: 11842

Submitted: 08/19/2009 09:00

STANTEC International, Inc.

Reported: 09/02/2009 at 11:44

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW081

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 21:07	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 21:07	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 21:07	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 21:07	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09236373601B	08/28/2009 04:21	Joseph E McKenzie	500
0212	Total Dissolved Solids	SM20 2540 C	1	09233021201A	08/21/2009 08:37	Susan A Engle	1
0276	Hexavalent Chromium	SW-846 7196A	1	09231027601A	08/19/2009 09:45	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5752646

Group No. 1158162
NM

GOPWW2 Grab Water Sample
Eunice North Gas Plant

Collected: 08/18/2009 13:43 by JL

Account Number: 11842

Submitted: 08/19/2009 09:00
Reported: 09/02/2009 at 11:44
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

OPWW2

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.577	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,420	mg/l 200	500
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 3,060	mg/l 240	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 02:52	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 02:52	Katrina T Longenecker	1
1146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 02:52	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092320028A	08/24/2009 19:39	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092320028A	08/21/2009 09:35	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5752646

Group No. 1158162

GOPWW2 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/18/2009 13:43 by JL

Account Number: 11842

Submitted: 08/19/2009 09:00

STANTEC International, Inc.

Reported: 09/02/2009 at 11:44

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

OPWW2

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 21:10	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 21:10	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 21:10	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 21:10	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09236373601B	08/28/2009 04:39	Joseph E McKenzie	500
0212	Total Dissolved Solids	SM20 2540 C	1	09233021201A	08/21/2009 08:37	Susan A Engle	1
00276	Hexavalent Chromium	SW-846 7196A	1	09231027601A	08/19/2009 09:45	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5752647

Group No. 1158162

MW077SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/18/2009 15:08 by JL

Account Number: 11842

Submitted: 08/19/2009 09:00

STANTEC International, Inc.

Reported: 09/02/2009 at 11:44

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW077

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	0.0157	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 755	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 2,690	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 06:48	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 06:48	Katrina T Longenecker	1
11146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 06:48	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092320028A	08/24/2009 20:00	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092320028A	08/21/2009 09:35	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5752647

Group No. 1158162

MW077SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/18/2009 15:08 by JL

Account Number: 11842

Submitted: 08/19/2009 09:00

STANTEC International, Inc.

Reported: 09/02/2009 at 11:44

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW077

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 21:13	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 21:13	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 21:13	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 21:13	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09236373601B	08/28/2009 04:57	Joseph E McKenzie	500
00212	Total Dissolved Solids	SM20 2540 C	1	09233021201A	08/21/2009 08:37	Susan A Engle	1
00276	Hexavalent Chromium	SW-846 7196A	1	09231027601A	08/19/2009 09:45	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5752648

Group No. 1158162

Trip Blank Water Sample
Eunice North Gas Plant

NM

Collected: 08/18/2009

Account Number: 11842

Submitted: 08/19/2009 09:00

STANTEC International, Inc.

Reported: 09/02/2009 at 11:44

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW77T

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles		SW-846 8021B	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 01:41	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 01:41	Katrina T Longenecker	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 11:44 AM

Group Number: 1158162

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09233A54A	Sample number(s): 5752643-5752648							
Benzene	< 1.0	1.0	ug/l	110	110	80-120	0	30
Ethylbenzene	< 1.0	1.0	ug/l	100	100	80-120	0	30
Toluene	< 1.0	1.0	ug/l	105	100	80-120	5	30
TPH-GRO water C6-C10	< 50	50.	ug/l	91	109	75-135	18	30
Total Xylenes	< 3.0	3.0	ug/l	103	102	80-120	2	30
Batch number: 092320028A	Sample number(s): 5752643-5752647							
TPH-DRO water C10-C28	< 100	100.	ug/l	69	66	56-122	4	20
Batch number: 092335705010	Sample number(s): 5752643-5752647							
Arsenic	< 0.0200	0.0200	mg/l	97		80-120		
Chromium	< 0.0150	0.0150	mg/l	95		90-110		
Iron	< 0.200	0.200	mg/l	90		90-112		
Manganese	< 0.0050	0.0050	mg/l	93		90-110		
Batch number: 09236373601B	Sample number(s): 5752643-5752647							
Chloride	< 0.40	0.40	mg/l	96		90-110		
Batch number: 09231027601A	Sample number(s): 5752643-5752647							
Hexavalent Chromium	< 0.020	0.020	mg/l	103		90-110		
Batch number: 09233021201A	Sample number(s): 5752643-5752647							
Total Dissolved Solids	< 30.0	30.0	mg/l	97		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09233A54A	Sample number(s): 5752643-5752648 UNSPK: P751229, 5752646								
Benzene	113		70-152						
Ethylbenzene	105		75-133						
Toluene	105		78-129						
TPH-GRO water C6-C10	100		63-154						
Total Xylenes	107		67-155						
Batch number: 092335705010	Sample number(s): 5752643-5752647 UNSPK: P754213 BKG: P754213								
Arsenic	103	101	75-125	3	20	< 0.0200	< 0.0200	0 (1)	20
Chromium	100	100	81-120	0	20	< 0.0150	< 0.0150	0 (1)	20
Iron	109	102	75-125	2	20	1.85	1.88	1	20

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 11:44 AM

Group Number: 1158162

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Manganese	102	104	75-125	1	20	0.730	0.743	2	20
Batch number: 09236373601B Chloride	Sample number(s): 5752643-5752647 UNSPK: P751391 BKG: P751391 91 90-110 19,600 19,700 1 (1) 20								
Batch number: 09231027601A Hexavalent Chromium	Sample number(s): 5752643-5752647 UNSPK: P752819 BKG: P752819 106 106 85-115 0 5 < 0.020 < 0.020 0 (1) 5								
Batch number: 09233021201A Total Dissolved Solids	Sample number(s): 5752643-5752647 UNSPK: 5752647 BKG: 5752647 102 99 54-143 1 12 2,690 2,640 2 9								

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed
unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: TPH-GRO water C6-C10
Batch number: 09233A54A

Trifluorotoluene-F	Trifluorotoluene-P
5752643 103	115
5752644 105	113
5752645 106	115
5752646 108	115
5752647 111	115
5752648 113	113
Blank 102	114
LCS 117	115
LCSD 122	115
MS 113	116

Limits: 63-135 69-129

Analysis Name: TPH+DRO water C10-C28
Batch number: 092320028A
Orthoterphenyl

5752643 81	
5752644 64	
5752645 87	
5752646 85	
5752647 79	
Blank 72	
LCS 98	
LCSD 94	

Limits: 54-127

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 11:44 AM

Group Number: 1158162

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Analysis Request / Environmental Services Chain of Custody



For Lancaster Laboratories use only

Act # 11842 Group # 1158162 Sample # 5752643-48 **COC #** 217450

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: Chevron Act. #: _____
 Project Name: Wentz 21290135.2017.50 PWSID #: _____
 Project Manager: Chad Howell / D. W. P. O. #
 Sampler: Elizabeth J. Penner's Quote #: _____
 Name of state where samples were collected: New Mexico

2

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

3

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

4

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

5

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

6

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

7

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

8

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

9

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

10

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

11

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

12

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

13

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

14

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

15

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

16

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

17

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

18

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

19

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

20

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

21

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

22

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

23

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

24

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

25

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

26

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

27

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

28

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

29

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

30

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		
MW077SA	8-18-09	1509		
Trip Blank	8-18-09			

31

Sample ID	Date	Time	Location	Remarks
MW079SA	8-18-09	1117		
MW080SA	8-18-09	1154		
MW081SA	8-18-09	1235		
GOR0022	8-18-09	1343		

Lancaster Laboratories Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAP unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

September 02, 2009

SAMPLE GROUP

The sample group for this submittal is 1158408. Samples arrived at the laboratory on Thursday, August 20, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

<u>Client Description</u>	<u>Lancaster Labs Number</u>
MW027 Grab Water Sample	5754380
MW010 Grab Water Sample	5754381
MW024 Grab Water Sample	5754382
MW058 Grab Water Sample	5754383
MW061 Grab Water Sample	5754384
MW018 Grab Water Sample	5754385
DUP-101 Grab Water Sample	5754386
Trip Blank Water Sample	5754387

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC COPY TO STANTEC International, Inc.
ELECTRONIC COPY TO STANTEC International, Inc.

Attn: Chad Vowell

Attn: Steve Bell



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

A handwritten signature in cursive script that reads "Max E. Snively".

Max E. Snively
Senior Specialist



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5754380

Group No. 1158408

MW027 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009 10:30 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05
Reported: 09/02/2009 at 10:54
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW027

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 344	mg/l 80.0	200
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 1,590	mg/l 120	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 07:11	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 07:11	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 07:11	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092340017A	08/25/2009 11:05	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092340017A	08/24/2009 08:55	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5754380

Group No. 1158408

NM

MW027 Grab Water Sample
Eunice North Gas Plant

Collected: 08/19/2009 10:30 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05
Reported: 09/02/2009 at 10:54
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW027

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 21:16	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 21:16	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 21:16	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 21:16	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09239373101B	08/29/2009 16:27	K. Robert Caulfeild-James	200
00212	Total Dissolved Solids	SM20 2540 C	1	09236021201A	08/24/2009 10:27	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09232027602A	08/20/2009 10:15	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5754381

Group No. 1158408

MW010 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009 11:31 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05
Reported: 09/02/2009 at 10:54
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW010

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l 1.1	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 660	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	0.0387	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 2,960	mg/l 200	500
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 5,150	mg/l 600	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l 0.028	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 08:22	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 08:22	Katrina T Longenecker	1
0146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 08:22	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092340017A	08/25/2009 11:26	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092340017A	08/24/2009 08:55	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5754381

Group No. 1158408

NM

MW010 Grab Water Sample

Eunice North Gas Plant

Collected: 08/19/2009 11:31 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 10:54

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW010

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 21:19	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 21:19	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 21:19	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 21:19	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
0224	Chloride	EPA 300.0	1	09239373101B	08/27/2009 22:41	Joseph E McKenzie	500
212	Total Dissolved Solids	SM20 2540 C	1	09236021201A	08/24/2009 10:27	Susan E Hibner	1
0276	Hexavalent Chromium	SW-846 7196A	1	09232027602A	08/20/2009 10:15	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5754382

Group No. 1158408

MW024 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009 12:24 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05
Reported: 09/02/2009 at 10:54
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW024

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 180	ug/l 97	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	0.0454	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 719	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 1,830	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l 0.037	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 08:46	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 08:46	Katrina T Longenecker	1
1146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 08:46	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092340017A	08/25/2009 11:48	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092340017A	08/24/2009 08:55	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5754382

Group No. 1158408

NM

MW024 Grab Water Sample

Eunice North Gas Plant

Collected: 08/19/2009 12:24 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 10:54

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW024

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 21:22	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 21:22	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 21:22	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 21:22	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09239373101B	08/27/2009 22:56	Joseph E McKenzie	500
0212	Total Dissolved Solids	SM20 2540 C	1	09236021201A	08/24/2009 10:27	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09232027602A	08/20/2009 10:15	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5754383

Group No. 1158408

MW058 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009 13:01 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05
Reported: 09/02/2009 at 10:54
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW058

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 100	ug/l 97	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	2.22	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,050	mg/l 200	500
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 3,890	mg/l 240	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l 1.1	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 09:10	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 09:10	Katrina T Longenecker	1
1146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 09:10	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092340017A	08/25/2009 12:09	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092340017A	08/24/2009 08:55	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5754383

Group No. 1158408

MW058 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009 13:01 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 10:54

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW058

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 21:26	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 21:26	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 21:26	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 21:26	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09239373101B	08/27/2009 23:12	Joseph E McKenzie	500
0212	Total Dissolved Solids	SM20 2540 C	1	09236021201A	08/24/2009 10:27	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09232027602A	08/20/2009 10:15	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5754384

Group No. 1158408

MW061 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009 14:03 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 10:54

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW061

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 98	ug/l 98	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	4.24	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.0615	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 716	mg/l 200	500
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 3,890	mg/l 240	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l 4.4	mg/l 0.080	4
This sample was analyzed twice for hexavalent chromium. The result of the second analysis performed outside the 24hr holding time was 4.0 mg/L.					

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 09:33	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 09:33	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 09:33	Katrina T Longenecker	1

Lancaster Laboratories Sample No. WW 5754384

Group No. 1158408

MW061 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009 14:03 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 10:54

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW061

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092340017A	08/25/2009 12:30	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092340017A	08/24/2009 08:55	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 21:29	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 21:29	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 21:29	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 21:29	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09239373101B	08/27/2009 23:28	Joseph E McKenzie	500
00212	Total Dissolved Solids	SM20 2540 C	1	09236021201A	08/24/2009 10:27	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09232027602A	08/20/2009 10:15	Michelle L Lalli	4



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5754385

Group No. 1158408

MW018 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009 14:52 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05
Reported: 09/02/2009 at 10:54
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW018

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 150	ug/l 97	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 200	mg/l 40.0	100
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 1,360	mg/l 120	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 09:57	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 09:57	Katrina T Longenecker	1
1146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 09:57	Katrina T Longenecker	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092340017A	08/25/2009 12:51	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092340017A	08/24/2009 08:55	Karen R Rettew	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5754385

Group No. 1158408

MW018 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009 14:52 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 10:54

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW018

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 21:32	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 21:32	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 21:32	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 21:32	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09239373101B	08/29/2009 16:42	K. Robert Caulfeild-James	100
00212	Total Dissolved Solids	SM20 2540 C	1	09236021201A	08/24/2009 10:27	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09232027602A	08/20/2009 10:15	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5754386

Group No. 1158408

DUP-101 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 10:54

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

DU101

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 100	ug/l 97	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	4.29	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.0645	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 836	mg/l 200	500
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 4,060	mg/l 240	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l 3.8	mg/l 0.080	4
This sample was analyzed twice for hexavalent chromium. The result of the second analysis performed outside the 24hr holding time was 4.1 mg/L.					

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09233A54A	08/24/2009 10:21	Katrina T Longenecker	1
08213	BTEX (8021)	SW-846 8021B	1	09233A54A	08/24/2009 10:21	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09233A54A	08/24/2009 10:21	Katrina T Longenecker	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5754386

Group No. 1158408

NM

DUP-101 Grab Water Sample
Eunice North Gas Plant

Collected: 08/19/2009 by JL

Account Number: 11842

Submitted: 08/20/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 10:54

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

DU101

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092340017A	08/25/2009 13:12	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092340017A	08/24/2009 08:55	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092335705010	08/25/2009 21:35	John P Hook	1
07051	Chromium	SW-846 6010B	1	092335705010	08/25/2009 21:35	John P Hook	1
01754	Iron	SW-846 6010B	1	092335705010	08/25/2009 21:35	John P Hook	1
07058	Manganese	SW-846 6010B	1	092335705010	08/25/2009 21:35	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092335705010	08/24/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09239373101B	08/28/2009 00:00	Joseph E McKenzie	500
00212	Total Dissolved Solids	SM20 2540 C	1	09236021201A	08/24/2009 10:27	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09232027602A	08/20/2009 10:15	Michelle L Lalli	4



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5754387

Group No. 1158408

Trip Blank Water Sample
Eunice North Gas Plant

NM

Collected: 08/19/2009

Account Number: 11842

Submitted: 08/20/2009 09:05

STANTEC International, Inc.

Reported: 09/02/2009 at 10:54

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

MW18T

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles		SW-846 8021B	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

This sample was received with headspace.

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09232A53B	08/24/2009 01:18	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09232A53B	08/24/2009 01:18	Marie D John	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 10:54 AM

Group Number: 1158408

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09232A53B	Sample number(s): 5754387							
Benzene	< 1.0	1.0	ug/l	120	120	80-120	0	30
Ethylbenzene	< 1.0	1.0	ug/l	110	110	80-120	0	30
Toluene	< 1.0	1.0	ug/l	110	110	80-120	0	30
Total Xylenes	< 3.0	3.0	ug/l	113	113	80-120	0	30
Batch number: 09233A54A	Sample number(s): 5754380-5754386							
Benzene	< 1.0	1.0	ug/l	110	110	80-120	0	30
Ethylbenzene	< 1.0	1.0	ug/l	100	100	80-120	0	30
Toluene	< 1.0	1.0	ug/l	105	100	80-120	5	30
TPH-GRO water C6-C10	< 50	50	ug/l	91	109	75-135	18	30
Total Xylenes	< 3.0	3.0	ug/l	103	102	80-120	2	30
Batch number: 092340017A	Sample number(s): 5754380-5754386							
TPH-DRO water C10-C28	< 100	100	ug/l	64	65	56-122	2	20
Batch number: 092335705010	Sample number(s): 5754380-5754386							
Arsenic	< 0.0200	0.0200	mg/l	97		80-120		
Chromium	< 0.0150	0.0150	mg/l	95		90-110		
Iron	< 0.200	0.200	mg/l	90		90-112		
Manganese	< 0.0050	0.0050	mg/l	93		90-110		
Batch number: 09239373101B	Sample number(s): 5754380-5754386							
Chloride	< 0.40	0.40	mg/l	99		90-110		
Batch number: 09232027602A	Sample number(s): 5754380-5754386							
Hexavalent Chromium	< 0.020	0.020	mg/l	106		90-110		
Batch number: 09236021201A	Sample number(s): 5754380-5754386							
Total Dissolved Solids	< 30.0	30.0	mg/l	103		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09232A53B	Sample number(s): 5754387 UNSPK: P755085								
Benzene	130		70-152						
Ethylbenzene	120		75-133						
Toluene	120		78-129						
Total Xylenes	123		67-155						

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 10:54 AM

Group Number: 1158408

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09233A54A	Sample number(s): 5754380-5754386 UNSPK: P751229, P752646								
Benzene	113		70-152						
Ethylbenzene	105		75-133						
Toluene	105		78-129						
TPH-GRO water C6-C10	100		63-154						
Total Xylenes	107		67-155						
Batch number: 092335705010	Sample number(s): 5754380-5754386 UNSPK: P754213 BKG: P754213								
Arsenic	103	101	75-125	3	20	< 0.0200	< 0.0200	0 (1)	20
Chromium	100	100	81-120	0	20	< 0.0150	< 0.0150	0 (1)	20
Iron	109	102	75-125	2	20	1.85	1.88	1	20
Manganese	102	104	75-125	1	20	0.730	0.743	2	20
Batch number: 09239373101B	Sample number(s): 5754380-5754386 UNSPK: P761559 BKG: P761559								
Chloride	71*		90-110			188	193	2 (1)	20
Batch number: 09232027602A	Sample number(s): 5754380-5754386 UNSPK: 5754380 BKG: 5754380								
Hexavalent Chromium	104	105	85-115	1	5	< 0.020	< 0.020	0 (1)	5
Batch number: 09236021201A	Sample number(s): 5754380-5754386 UNSPK: 5754382 BKG: 5754382								
Total Dissolved Solids	105	98	54-143	3	12	1,830	1,840	0	9

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: BTEX (8021)
Batch number: 09232A53B
Trifluorotoluene-P

5754387	100
Blank	100
LCS	100
LCSD	99
MS	99

Limits: 69-129

Analysis Name: TPH-GRO water C6-C10
Batch number: 09233A54A

	Trifluorotoluene-F	Trifluorotoluene-P
5754380	102	117
5754381	108	118
5754382	103	114
5754383	114	114
5754384	109	112
5754385	106	113

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control SummaryClient Name: STANTEC International, Inc.
Reported: 09/02/09 at 10:54 AM

Group Number: 1158408

Surrogate Quality Control

5754386	111	114
Blank	102	114
LCS	117	115
LCSD	122	115
MS	113	116

Limits:	63-135	69-129
---------	--------	--------

Analysis Name: TPH-DRO water C10-C28
Batch number: 092340017A
Orthoterphenyl

5754380	69
5754381	96
5754382	81
5754383	86
5754384	84
5754385	90
5754386	92
Blank	67
LCS	79
LCSD	82

Limits:	54-127
---------	--------

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Lancaster
Laboratories

Acc. # 11842 Group# 1158408 Sample # 5754380-87

1 Client: <u>Churon</u> Acct. #: <u>201250</u>		2 Name of state where samples were collected: <u>New Mexico</u>		3		4		5 Analysis		6	
Project Name#: <u>NiEnviro 212201135</u> PWSID #: <u>201250</u>		Project Manager: <u>Chad Howell / D. B. O. #</u>		Sampler: <u>T. Gonzalez / T. Promerig</u> Quote #: <u></u>		Preservation Codes		Preservation Codes		Preservation Codes	
Date results are needed: <u></u>		Rush results requested by (please circle): <u>Normal</u> <u>Rush</u>		Phone #: <u></u> Fax #: <u></u> E-mail: <u></u>		Relinquished by: <u></u>		Date Time Received by: <u>8-19-09 1655</u>		Date Time	
Rush results requested by (please circle): <u>Normal</u> <u>Rush</u>		Phone #: <u></u> Fax #: <u></u> E-mail: <u></u>		Relinquished by: <u></u>		Date Time Received by: <u></u>		Date Time		Date Time	
E-mail address: <u></u>		SDG Complete? Yes No		TX TRRP-13 MA MCP CT RCP		Site-specific QC (MS/MSD/Dup)? Yes No		Internal COC Required? Yes / No		Type VI (Raw Data Only)	
<u>mw027</u>	<u>8-19-09 1030</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>
<u>mw010</u>	<u>8-19-09 1131</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>
<u>mw024</u>	<u>8-19-09 1224</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>
<u>mw058</u>	<u>8-19-09 1301</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>
<u>mw061</u>	<u>8-19-09 1403</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>
<u>mw018</u>	<u>8-19-09 1452</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>
<u>DUP-101</u>	<u>8-19-09</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>
<u>Trip Blank</u>	<u></u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>	<u>X</u>
<u>Bobbles In Trip Blanks</u>											

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6766
Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

September 03, 2009

SAMPLE GROUP

The sample group for this submittal is 1158624. Samples arrived at the laboratory on Friday, August 21, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

Client Description

MW070 Grab Water Sample
MW070A Grab Water Sample
MW030 Grab Water Sample
MW023A Grab Water Sample
MW014A Grab Water Sample
DUP#200 Grab Water Sample
MW067SA Grab Water Sample
MW053SA Grab Water Sample
MW078SA Grab Water Sample
MW015 Grab Water Sample
MW025 Grab Water Sample
DUP-102 Grab Water Sample
Trip Blank Water Sample

Lancaster Labs Number

5755687
5755688
5755689
5755690
5755691
5755692
5755693
5755694
5755695
5755696
5755697
5755698
5755699

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.

ELECTRONIC

STANTEC International, Inc.

Attn: Chad Vowell



Analysis Report


2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

COPY TO
ELECTRONIC STANTEC International, Inc.
COPY TO

Attn: Steve Bell

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,


Robert Strocko Jr.
Manager



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755687

Group No. 1158624

MW070 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 11:12 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW070

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 280	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 197	mg/l 40.0	100
SM20 2540 C					
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 827	mg/l 60.0	1
SW-846 7196A					
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/25/2009 22:24	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/25/2009 22:24	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/25/2009 22:24	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092380009A	08/28/2009 02:14	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	2	092380009A	08/27/2009 09:00	Karen R Rettew	1
07035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 21:47	John P Hook	1
07051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 21:47	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 14:39	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5755687

Group No. 1158624

MW070 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 11:12 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW070

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 21:47	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241196602B	08/30/2009 14:13	Ashley M Adams	100
00212	Total Dissolved Solids	SM20 2540 C	1	09237021201A	08/25/2009 07:38	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027601A	08/21/2009 10:15	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755688

Group No. 1158624

MW070A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 12:08 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW70A

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 96	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 46.3	mg/l 4.0	10
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 545	mg/l 30.0	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/25/2009 22:47	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/25/2009 22:47	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/25/2009 22:47	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 08:21	Lisa A Reinert	1
7003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
7035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 21:51	John P Hook	1
7051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 21:51	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 14:43	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5755688

Group No. 1158624

NM

MW070A Grab Water Sample
Eunice North Gas Plant

Collected: 08/20/2009 12:08 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW70A

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 21:51	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241196602B	09/02/2009 13:25	K. Robert Caulfeild-James	10
00212	Total Dissolved Solids	SM20 2540 C	1	09237021201A	08/25/2009 07:38	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027601A	08/21/2009 10:15	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755689

Group No. 1158624

MW030 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 13:29 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW030

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 180	mg/l 40.0	100
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 986	mg/l 120	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/25/2009 23:11	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/25/2009 23:11	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/25/2009 23:11	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 08:42	Lisa A Reinert	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
07035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 21:56	John P Hook	1
07051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 21:56	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 14:48	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5755689

Group No. 1158624

MW030 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 13:29 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW030

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 21:56	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241196602B	08/30/2009 17:27	Ashley M Adams	100
00212	Total Dissolved Solids	SM20 2540 C	1	09237021201A	08/25/2009 07:38	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846, 7196A	1	09233027601A	08/21/2009 10:15	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755690

Group No. 1158624

MW023A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 14:12 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW23A

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 50.6	mg/l 4.0	10
SM20 2540 C					
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 526	mg/l 30.0	1
SW-846 7196A					
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/25/2009 23:34	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/25/2009 23:34	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/25/2009 23:34	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 09:02	Lisa A Reinert	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
07035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 22:00	John P Hook	1
07051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 22:00	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 14:52	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5755690

Group No. 1158624

NM

MW023A Grab Water Sample
Eunice North Gas Plant

Collected: 08/20/2009 14:12 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW23A

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 22:00	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241196602B	09/02/2009 13:45	K. Robert Caulfeild-James	10
00212	Total Dissolved Solids	SM20 2540 C	1	09237021201A	08/25/2009 07:38	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027601A	08/21/2009 10:15	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5755691

Group No. 1158624

MW014A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 15:06 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW14A

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 96	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l 0.0214	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 45.6	mg/l 4.0	10
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 507	mg/l 30.0	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/25/2009 23:58	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/25/2009 23:58	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/25/2009 23:58	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 12:07	Lisa A Reinert	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
07035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 22:05	John P Hook	1
07051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 22:05	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 14:56	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5755691

Group No. 1158624

NM

MW014A Grab Water Sample
Eunice North Gas Plant

Collected: 08/20/2009 15:06 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW14A

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 22:05	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241196602B	09/02/2009 14:04	Ashley M Adams	10
00212	Total Dissolved Solids	SM20 2540 C	1	09237021202A	08/25/2009 08:33	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027601A	08/21/2009 10:15	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755692

Group No. 1158624

DUP#200 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

DU200

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 96	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 49.1	mg/l 4.0	10
SM20 2540 C					
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 518	mg/l 30.0	1
SW-846 7196A					
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 00:21	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 00:21	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 00:21	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 09:23	Lisa A Reinert	1
0003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
07035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 22:18	John P Hook	1
07051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 22:18	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 15:01	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5755692

Group No. 1158624

DUP#200 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 by SB

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

DU200

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 22:18	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241196602B	09/02/2009 14:24	Ashley M Adams	10
00212	Total Dissolved Solids	SM20 2540 C	1	09238021201A	08/26/2009 07:48	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027601A	08/21/2009 10:15	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755693

Group No. 1158624

MW067SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 11:06 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW67S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 97	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 186	mg/l 40.0	100
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 1,050	mg/l 120	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 00:45	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 00:45	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 00:45	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 09:43	Lisa A Reinert	1
0003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
07035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 22:22	John P Hook	1
07051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 22:22	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 15:05	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5755693

Group No. 1158624

NM

MW067SA Grab Water Sample

Eunice North Gas Plant

Collected: 08/20/2009 11:06 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW67S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 22:22	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241196603A	08/30/2009 20:03	Ashley M Adams	100
00212	Total Dissolved Solids	SM20 2540 °C	1	09238021201A	08/26/2009 07:48	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027602A	08/21/2009 10:30	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755694

Group No. 1158624

MW053SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 11:45 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW53S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 205	mg/l 40.0	100
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 944	mg/l 120	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 01:55	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 01:55	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 01:55	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 10:04	Lisa A Reinert	1
7003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
7035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 22:26	John P Hook	1
7051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 22:26	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 15:10	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5755694

Group No. 1158624

MW053SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 11:45 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW53S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 22:26	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241196603A	08/30/2009 21:01	Ashley M Adams	100
00212	Total Dissolved Solids	SM20 2540 C	1	09238021201A	08/26/2009 07:48	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027602A	08/21/2009 10:30	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755695

Group No. 1158624

MW078SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 12:26 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW78S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 96	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 159	mg/l 40.0	100
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 790	mg/l 60.0	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 02:19	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 02:19	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 02:19	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 10:24	Lisa A Reinert	1
7003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
7035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 22:31	John P Hook	1
7051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 22:31	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 15:14	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5755695

Group No. 1158624

NM

MW078SA Grab Water Sample
Eunice North Gas Plant

Collected: 08/20/2009 12:26 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW78S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 22:31	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241196603A	08/30/2009 21:20	Ashley M Adams	100
00212	Total Dissolved Solids	SM20 2540 C	1	09238021201A	08/26/2009 07:48	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027602A	08/21/2009 10:30	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755696

Group No. 1158624

MW015 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 13:43 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW015

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 98	ug/l 98	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,590	mg/l 200	500
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 3,930	mg/l 600	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 02:43	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 02:43	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 02:43	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 10:45	Lisa A Reinert	1
0003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
07035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 22:35	John P Hook	1
07051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 22:35	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 15:27	Eric L Eby	1

Lancaster Laboratories Sample No. WW 5755696

Group No. 1158624

MW015 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 13:43 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10
Reported: 09/03/2009 at 16:05
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW015

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 22:35	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241373101B	09/02/2009 03:27	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09238021201A	08/26/2009 07:48	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027602A	08/21/2009 10:30	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755697

Group No. 1158624

MW025 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 14:37 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW025

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 410	ug/l 100	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.0125	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 432	mg/l 40.0	100
SM20 2540 C					
00212	Total Dissolved Solids *	n.a.	mg/l 1,690	mg/l 120	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 03:07	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 03:07	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 03:07	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 12:27	Lisa A Reinert	1
7003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
7035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 22:40	John P Hook	1
07051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 22:40	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 15:32	Eric L Eby	1

Lancaster Laboratories Sample No. WW 5755697

Group No. 1158624

NM

MW025 Grab Water Sample

Eunice North Gas Plant

Collected: 08/20/2009 14:37 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW025

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 22:40	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241373101B	08/30/2009 03:42	K. Robert Caulfeild-James	100
00212	Total Dissolved Solids	SM20 2540 C	1	09238021201A	08/26/2009 07:48	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027602A	08/21/2009 10:30	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5755698

Group No. 1158624

DUP-102 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

DUI102

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	n.a.	ug/l 440	ug/l 96	1
Metals Dissolved					
07035	Arsenic	7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.0127	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 439	mg/l 40.0	100
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 1,650	mg/l 120	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 03:30	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 03:30	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 03:30	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 12:48	Lisa A Reinert	1
7003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
7035	Arsenic	SW-846 6010B	1	092375705004	08/27/2009 22:45	John P Hook	1
7051	Chromium	SW-846 6010B	1	092375705004	08/27/2009 22:45	John P Hook	1
01754	Iron	SW-846 6010B	1	092375705004	08/28/2009 15:36	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5755698

Group No. 1158624

DUP-102 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/20/2009 by JL

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

DU102

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092375705004	08/27/2009 22:45	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092375705004	08/26/2009 14:46	James L Mertz	1
00224	Chloride	EPA 300.0	1	09241373101B	08/30/2009 03:58	K. Robert Caulfeild-James	100
00212	Total Dissolved Solids	SM20 2540 C	1	09238021201A	08/26/2009 07:48	Susan E Hibner	1
00276	Hexavalent Chromium	SW-846 7196A	1	09233027602A	08/21/2009 10:30	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5755699

Group No. 1158624

NM

Trip Blank Water Sample
Eunice North Gas Plant

Collected: 08/20/2009

Account Number: 11842

Submitted: 08/21/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 16:05

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

EUNNT

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles		SW-846 8021B	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09236A54A	08/24/2009 21:12	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09236A54A	08/24/2009 21:12	Katrina T Longenecker	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/03/09 at 04:05 PM

Group Number: 1158624

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09236A54A	Sample number(s): 5755699							
Benzene	< 1.0	1.0	ug/l	110	105	80-120	5	30
Ethylbenzene	< 1.0	1.0	ug/l	100	100	80-120	0	30
Toluene	< 1.0	1.0	ug/l	105	100	80-120	5	30
Total Xylenes	< 3.0	3.0	ug/l	103	100	80-120	3	30
Batch number: 09237A54A	Sample number(s): 5755687-5755698							
Benzene	< 1.0	1.0	ug/l	100	100	80-120	0	30
Ethylbenzene	< 1.0	1.0	ug/l	95	95	80-120	0	30
Toluene	< 1.0	1.0	ug/l	95	95	80-120	0	30
TPH-GRO water C6-C10	< 50	50	ug/l	100	91	75-135	10	30
Total Xylenes	< 3.0	3.0	ug/l	97	93	80-120	4	30
Batch number: 092370009A	Sample number(s): 5755688-5755698							
TPH-DRO water C10-C28	< 100	100	ug/l	71	74	56-122	3	20
Batch number: 092380009A	Sample number(s): 5755687							
TPH-DRO water C10-C28	< 100	100	ug/l	83		56-122		
Batch number: 092375705004	Sample number(s): 5755687-5755698							
Arsenic	< 0.0200	0.0200	mg/l	100		80-120		
Chromium	< 0.0150	0.0150	mg/l	100		90-110		
Iron	< 0.200	0.200	mg/l	97		90-112		
Manganese	< 0.0050	0.0050	mg/l	99		90-110		
Batch number: 09241196602B	Sample number(s): 5755687-5755692							
Chloride	< 0.40	0.40	mg/l	107		90-110		
Batch number: 09241196603A	Sample number(s): 5755693-5755695							
Chloride	< 0.40	0.40	mg/l	100		90-110		
Batch number: 09241373101B	Sample number(s): 5755696-5755698							
Chloride	< 0.40	0.40	mg/l	105		90-110		
Batch number: 09233027601A	Sample number(s): 5755687-5755692							
Hexavalent Chromium	< 0.020	0.020	mg/l	100		90-110		
Batch number: 09233027602A	Sample number(s): 5755693-5755698							
Hexavalent Chromium	< 0.020	0.020	mg/l	104		90-110		
Batch number: 09237021201A	Sample number(s): 5755687-5755690							
Total Dissolved Solids	< 30.0	30.0	mg/l	103		80-120		
Batch number: 09237021202A	Sample number(s): 5755691							
Total Dissolved Solids	< 30.0	30.0	mg/l	103		80-120		
Batch number: 09238021201A	Sample number(s): 5755692-5755698							

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/03/09 at 04:05 PM

Group Number: 1158624

Laboratory Compliance Quality Control

<u>Analysis Name</u>	<u>Blank Result</u>	<u>Blank LOQ</u>	<u>Report Units</u>	<u>LCS %REC</u>	<u>LCSD %REC</u>	<u>LCS/LCSD Limits</u>	<u>RPD</u>	<u>RPD Max</u>
Total Dissolved Solids	< 30.0	30.0	mg/l	97		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

<u>Analysis Name</u>	<u>MS %REC</u>	<u>MSD %REC</u>	<u>MS/MSD Limits</u>	<u>RPD</u>	<u>RPD MAX</u>	<u>BKG Conc</u>	<u>DUP Conc</u>	<u>DUP RPD</u>	<u>Dup RPD Max</u>
Batch number: 09236A54A	Sample number(s): 5755699 UNSPK: P757162								
Benzene	110		70-152						
Ethylbenzene	105		75-133						
Toluene	105		78-129						
Total Xylenes	107		67-155						
Batch number: 09237A54A	Sample number(s): 5755687-5755698 UNSPK: P757619, P757620								
Benzene	115		70-152						
Ethylbenzene	105		75-133						
Toluene	109		78-129						
TPH-GRO water C6-C10	109		63-154						
Total Xylenes	107		67-155						
Batch number: 092380009A	Sample number(s): 5755687 UNSPK: P755764								
TPH-DRO water C10-C28	84	79	13-149	4	20				
Batch number: 092375705004	Sample number(s): 5755687-5755698 UNSPK: P755000 BKG: P755000								
Arsenic	140*	130*	75-125	7	20	< 0.100	< 0.100	0 (1)	20
Chromium	102	103	81-120	1	20	< 0.0750	< 0.0750	0 (1)	20
Iron	94	92	75-125	2	20	< 1.00	< 1.00	0 (1)	20
Manganese	105	105	75-125	0	20	0.928	0.957	3	20
Batch number: 09241196602B	Sample number(s): 5755687-5755692 UNSPK: 5755687 BKG: 5755687								
Chloride	76*		90-110			197	198	1 (1)	20
Batch number: 09241196603A	Sample number(s): 5755693-5755695 UNSPK: 5755693 BKG: 5755693								
Chloride	73*		90-110			186	190	2 (1)	20
Batch number: 09241373101B	Sample number(s): 5755696-5755698 UNSPK: P755101 BKG: P755101								
Chloride	99		90-110			42.0	35.7	16 (1)	20
Batch number: 09233027601A	Sample number(s): 5755687-5755692 UNSPK: 5755687 BKG: 5755687								
Hexavalent Chromium	105	106	85-115	1	5	< 0.020	< 0.020	0 (1)	5
Batch number: 09233027602A	Sample number(s): 5755693-5755698 UNSPK: 5755693 BKG: 5755693								
Hexavalent Chromium	104	105	85-115	1	5	< 0.020	< 0.020	0 (1)	5
Batch number: 09237021201A	Sample number(s): 5755687-5755690 UNSPK: P757591 BKG: P757591								
Total Dissolved Solids	102	102	54-143	0	12	2,980	3,040	2	9
Batch number: 09237021202A	Sample number(s): 5755691 UNSPK: P755553 BKG: P755553								
Total Dissolved Solids	97	99	54-143	1	12	307	300	2	9

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/03/09 at 04:05 PM

Group Number: 1158624

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09238021201A	Sample number(s): 5755692-5755698 UNSPK: 5755694 BKG: 5755694								
Total Dissolved Solids	99	98	54-143	0	12	944	928	2	9

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: BTEX (8021)

Batch number: 09236A54A

	Trifluorotoluene-F	Trifluorotoluene-P
5755699		113
Blank	116	113
LCS	117	116
LCSD	113	116
MS	114	114

Limits: 63-135 69-129

Analysis Name: BTEX (8021)

Batch number: 09237A54A

	Trifluorotoluene-F	Trifluorotoluene-P
5755687	105	113
5755688	111	113
5755689	111	115
5755690	117	115
5755691	111	115
5755692	104	115
5755693	104	115
5755694	106	115
5755695	107	115
5755696	103	117
5755697	107	116
5755698	104	117
Blank	107	113
LCS	118	113
LCSD	120	114
MS	116	116

Limits: 63-135 69-129

Analysis Name: TPH-DRO water C10-C28

Batch number: 092370009A

	Orthoterphenyl
5755688	90
5755689	88
5755690	92

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control SummaryClient Name: STANTEC International, Inc.
Reported: 09/03/09 at 04:05 PM

Group Number: 1158624

Surrogate Quality Control

5755691	92
5755692	93
5755693	93
5755694	92
5755695	90
5755696	93
5755697	98
5755698	98
Blank	80
LCS	89
LCSD	92

Limits: 54-127

Analysis Name: TPH-DRO water C10-C28

Batch number: 092380009A
Orthoterphenyl

5755687	97
Blank	75
LCS	106
MS	102
MSD	99

Limits: 54-127

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only

Acct. # 11842 Group # 115824 Sample # 5755687-99 **COC #** 217452

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>CUX</u> Acct. #: <u>212201135-201250</u> Project Name: <u>River</u> PWSID #: <u>201250</u> Project Manager: <u>Chad Cowell</u> P.O. #: <u>201250</u> Sampler: <u>J. Karswell</u> Quote #: <u>201250</u> Name of state where samples were collected: <u>New Mexico</u>		2 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Time Collected</th> <th>Time Delivered</th> <th>Time Analyzed</th> <th>Time Reported</th> <th>Time Archived</th> <th>Time Retained</th> <th>Time Released</th> <th>Time Destroyed</th> </tr> </thead> <tbody> <tr> <td>MW0675A</td> <td>8-20-09 1106</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW0535A</td> <td>8-20-09 1145</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW0785A</td> <td>8-20-09 1226</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW015</td> <td>8-20-09 1343</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW025</td> <td>8-20-09 1437</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>DUP-102</td> <td>8-20-09</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Time Collected	Time Delivered	Time Analyzed	Time Reported	Time Archived	Time Retained	Time Released	Time Destroyed	MW0675A	8-20-09 1106								MW0535A	8-20-09 1145								MW0785A	8-20-09 1226								MW015	8-20-09 1343								MW025	8-20-09 1437								DUP-102	8-20-09								Trip Blank									3 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Time Collected</th> <th>Time Delivered</th> <th>Time Analyzed</th> <th>Time Reported</th> <th>Time Archived</th> <th>Time Retained</th> <th>Time Released</th> <th>Time Destroyed</th> </tr> </thead> <tbody> <tr> <td>MW0675A</td> <td>8-20-09 1106</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW0535A</td> <td>8-20-09 1145</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW0785A</td> <td>8-20-09 1226</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW015</td> <td>8-20-09 1343</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW025</td> <td>8-20-09 1437</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>DUP-102</td> <td>8-20-09</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Time Collected	Time Delivered	Time Analyzed	Time Reported	Time Archived	Time Retained	Time Released	Time Destroyed	MW0675A	8-20-09 1106								MW0535A	8-20-09 1145								MW0785A	8-20-09 1226								MW015	8-20-09 1343								MW025	8-20-09 1437								DUP-102	8-20-09								Trip Blank									4 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Time Collected</th> <th>Time Delivered</th> <th>Time Analyzed</th> <th>Time Reported</th> <th>Time Archived</th> <th>Time Retained</th> <th>Time Released</th> <th>Time Destroyed</th> </tr> </thead> <tbody> <tr> <td>MW0675A</td> <td>8-20-09 1106</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW0535A</td> <td>8-20-09 1145</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW0785A</td> <td>8-20-09 1226</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW015</td> <td>8-20-09 1343</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW025</td> <td>8-20-09 1437</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>DUP-102</td> <td>8-20-09</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Time Collected	Time Delivered	Time Analyzed	Time Reported	Time Archived	Time Retained	Time Released	Time Destroyed	MW0675A	8-20-09 1106								MW0535A	8-20-09 1145								MW0785A	8-20-09 1226								MW015	8-20-09 1343								MW025	8-20-09 1437								DUP-102	8-20-09								Trip Blank									5 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Time Collected</th> <th>Time Delivered</th> <th>Time Analyzed</th> <th>Time Reported</th> <th>Time Archived</th> <th>Time Retained</th> <th>Time Released</th> <th>Time Destroyed</th> </tr> </thead> <tbody> <tr> <td>MW0675A</td> <td>8-20-09 1106</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW0535A</td> <td>8-20-09 1145</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW0785A</td> <td>8-20-09 1226</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW015</td> <td>8-20-09 1343</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW025</td> <td>8-20-09 1437</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>DUP-102</td> <td>8-20-09</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Time Collected	Time Delivered	Time Analyzed	Time Reported	Time Archived	Time Retained	Time Released	Time Destroyed	MW0675A	8-20-09 1106								MW0535A	8-20-09 1145								MW0785A	8-20-09 1226								MW015	8-20-09 1343								MW025	8-20-09 1437								DUP-102	8-20-09								Trip Blank									6 <table border="1"> <thead> <tr> <th>Sample ID</th> <th>Time Collected</th> <th>Time Delivered</th> <th>Time Analyzed</th> <th>Time Reported</th> <th>Time Archived</th> <th>Time Retained</th> <th>Time Released</th> <th>Time Destroyed</th> </tr> </thead> <tbody> <tr> <td>MW0675A</td> <td>8-20-09 1106</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW0535A</td> <td>8-20-09 1145</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW0785A</td> <td>8-20-09 1226</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW015</td> <td>8-20-09 1343</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MW025</td> <td>8-20-09 1437</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>DUP-102</td> <td>8-20-09</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>Trip Blank</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Sample ID	Time Collected	Time Delivered	Time Analyzed	Time Reported	Time Archived	Time Retained	Time Released	Time Destroyed	MW0675A	8-20-09 1106								MW0535A	8-20-09 1145								MW0785A	8-20-09 1226								MW015	8-20-09 1343								MW025	8-20-09 1437								DUP-102	8-20-09								Trip Blank									7 Turnaround Time Requested (TAT) (please circle) <u>Normal</u> Rush (Rush TAT is subject to Lancaster Laboratories approval and surcharge.) Date results are needed: _____ Rush results requested by (please circle): Phone Fax E-mail Phone #: _____ Fax #: _____ E-mail address: _____		8 Data Package Options (please circle if required) Type I (validation/NJ Reg) TX TRRP-13 Type II (Tier II) MA MCP CT RCP Type III (Reduced NJ) Site-specific QC (MS/MSD/Dup)? Yes No Type IV (CLP SOW) Internal COC Required? Yes / No Type VI (Raw Data Only)		9 <table border="1"> <thead> <tr> <th>Relinquished by:</th> <th>Date</th> <th>Time</th> <th>Received by:</th> <th>Date</th> <th>Time</th> </tr> </thead> <tbody> <tr> <td><i>[Signature]</i></td> <td>8-20-09</td> <td>1700</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		Relinquished by:	Date	Time	Received by:	Date	Time	<i>[Signature]</i>	8-20-09	1700																																	
Sample ID	Time Collected	Time Delivered	Time Analyzed	Time Reported	Time Archived	Time Retained	Time Released	Time Destroyed																																																																																																																																																																																																																																																																																																																																																																																																																											
MW0675A	8-20-09 1106																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW0535A	8-20-09 1145																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW0785A	8-20-09 1226																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW015	8-20-09 1343																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW025	8-20-09 1437																																																																																																																																																																																																																																																																																																																																																																																																																																		
DUP-102	8-20-09																																																																																																																																																																																																																																																																																																																																																																																																																																		
Trip Blank																																																																																																																																																																																																																																																																																																																																																																																																																																			
Sample ID	Time Collected	Time Delivered	Time Analyzed	Time Reported	Time Archived	Time Retained	Time Released	Time Destroyed																																																																																																																																																																																																																																																																																																																																																																																																																											
MW0675A	8-20-09 1106																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW0535A	8-20-09 1145																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW0785A	8-20-09 1226																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW015	8-20-09 1343																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW025	8-20-09 1437																																																																																																																																																																																																																																																																																																																																																																																																																																		
DUP-102	8-20-09																																																																																																																																																																																																																																																																																																																																																																																																																																		
Trip Blank																																																																																																																																																																																																																																																																																																																																																																																																																																			
Sample ID	Time Collected	Time Delivered	Time Analyzed	Time Reported	Time Archived	Time Retained	Time Released	Time Destroyed																																																																																																																																																																																																																																																																																																																																																																																																																											
MW0675A	8-20-09 1106																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW0535A	8-20-09 1145																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW0785A	8-20-09 1226																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW015	8-20-09 1343																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW025	8-20-09 1437																																																																																																																																																																																																																																																																																																																																																																																																																																		
DUP-102	8-20-09																																																																																																																																																																																																																																																																																																																																																																																																																																		
Trip Blank																																																																																																																																																																																																																																																																																																																																																																																																																																			
Sample ID	Time Collected	Time Delivered	Time Analyzed	Time Reported	Time Archived	Time Retained	Time Released	Time Destroyed																																																																																																																																																																																																																																																																																																																																																																																																																											
MW0675A	8-20-09 1106																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW0535A	8-20-09 1145																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW0785A	8-20-09 1226																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW015	8-20-09 1343																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW025	8-20-09 1437																																																																																																																																																																																																																																																																																																																																																																																																																																		
DUP-102	8-20-09																																																																																																																																																																																																																																																																																																																																																																																																																																		
Trip Blank																																																																																																																																																																																																																																																																																																																																																																																																																																			
Sample ID	Time Collected	Time Delivered	Time Analyzed	Time Reported	Time Archived	Time Retained	Time Released	Time Destroyed																																																																																																																																																																																																																																																																																																																																																																																																																											
MW0675A	8-20-09 1106																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW0535A	8-20-09 1145																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW0785A	8-20-09 1226																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW015	8-20-09 1343																																																																																																																																																																																																																																																																																																																																																																																																																																		
MW025	8-20-09 1437																																																																																																																																																																																																																																																																																																																																																																																																																																		
DUP-102	8-20-09																																																																																																																																																																																																																																																																																																																																																																																																																																		
Trip Blank																																																																																																																																																																																																																																																																																																																																																																																																																																			
Relinquished by:	Date	Time	Received by:	Date	Time																																																																																																																																																																																																																																																																																																																																																																																																																														
<i>[Signature]</i>	8-20-09	1700																																																																																																																																																																																																																																																																																																																																																																																																																																	

Lancaster Laboratories, Inc., 2425 New Holland Pike, Lancaster, PA 17601 (717) 656-2300 Fax: (717) 656-6768
 Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

Lancaster Laboratories Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers		Inorganic Qualifiers	
A	TIC is a possible aldol-condensation product	B	Value is <CRDL, but ≥IDL
B	Analyte was also detected in the blank	E	Estimated due to interference
C	Pesticide result confirmed by GC/MS	M	Duplicate injection precision not met
D	Compound quantitated on a diluted sample	N	Spike amount not within control limits
E	Concentration exceeds the calibration range of the instrument	S	Method of standard additions (MSA) used for calculation
J	Estimated value	U	Compound was not detected
N	Presumptive evidence of a compound (TICs only)	W	Post digestion spike out of control limits
P	Concentration difference between primary and confirmation columns >25%	*	Duplicate analysis not within control limits
U	Compound was not detected	+	Correlation coefficient for MSA <0.995
X,Y,Z	Defined in case narrative		

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

September 02, 2009

SAMPLE GROUP

The sample group for this submittal is 1158860. Samples arrived at the laboratory on Saturday, August 22, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

<u>Client Description</u>	<u>Lancaster Labs Number</u>
MW073SA Grab Water Sample	5757619
MW057SA Grab Water Sample	5757620
MW018A Grab Water Sample	5757621
MW016A Grab Water Sample	5757622
MW015A Grab Water Sample	5757623
MW040A Grab Water Sample	5757624
Trip Blank Water Sample	5757625
MW019A Grab Water Sample	5757626
MW072SA Grab Water Sample	5757627
MW076SA Grab Water Sample	5757628
Trip Blanks Water Sample	5757629
MW020A Grab Water Sample	5757630
MW020 Grab Water Sample	5757631
LordWW Grab Water Sample	5757632
Trip Blanks Water Sample	5757633

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

ELECTRONIC STANTEC International, Inc.
COPY TO
ELECTRONIC STANTEC International, Inc.
COPY TO

Attn: Chad Vowell

Attn: Steve Bell

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

A handwritten signature in cursive script that reads "Robert Strocko Jr.".

Robert Strocko Jr.
Manager



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757619

Group No. 1158860

MW073SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 10:33 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

73A--

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 97	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 732	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 1,120	mg/l 120	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/25/2009 21:37	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/25/2009 21:37	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/25/2009 21:37	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 11:05	Lisa A Reinert	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
07035	Arsenic	SW-846 6010B	1	092385705002	08/28/2009 05:42	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092385705002	08/28/2009 05:42	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092385705002	08/28/2009 05:42	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757619

Group No. 1158860

MW073SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 10:33 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

73A--

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705002	08/28/2009 05:42	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705002	08/27/2009 09:20	Denise K Conners	1
00224	Chloride	EPA 300.0	1	09243373101B	09/02/2009 10:50	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027602A	08/22/2009 12:10	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757620

Group No. 1158860

MW057SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 11:12 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

57SA-

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	0.0393	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 581	mg/l 200	500
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 1,560	mg/l 120	1
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l 0.034	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/25/2009 22:00	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/25/2009 22:00	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/25/2009 22:00	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 11:26	Lisa A Reinert	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
07035	Arsenic	SW-846 6010B	1	092385705002	08/28/2009 05:45	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092385705002	08/28/2009 05:45	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092385705002	08/28/2009 05:45	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757620

Group No. 1158860

MW057SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 11:12 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

57SA-

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705002	08/28/2009 05:45	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705002	08/27/2009 09:20	Denise K Conners	1
00224	Chloride	EPA 300.0	1	09243373101B	08/31/2009 16:16	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027602A	08/22/2009 12:10	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757621

Group No. 1158860

MW018A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 11:57 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

18A--

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 96	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l 0.0209	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 304	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	SW-846 7196A n.a.	mg/l 1,020	mg/l 120	1
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 03:54	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 03:54	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 03:54	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370009A	08/26/2009 11:46	Lisa A Reinert	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370009A	08/25/2009 15:50	JoElla L Rice	1
7035	Arsenic	SW-846 6010B	1	092385705002	08/28/2009 05:56	John W Yanzuk II	1
7051	Chromium	SW-846 6010B	1	092385705002	08/28/2009 05:56	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092385705002	08/28/2009 05:56	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757621

Group No. 1158860

NM

MW018A Grab Water Sample
Eunice North Gas Plant

Collected: 08/21/2009 11:57 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

18A--

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705002	08/28/2009 05:56	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705002	08/27/2009 09:20	Denise K Conners	1
00224	Chloride	EPA 300.0	1	092433731018	08/31/2009 16:32	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20.2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027602A	08/22/2009 12:10	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757622

Group No. 1158860

MW016A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 12:52 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

16A--

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 509	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 1,100	mg/l 120	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 04:17	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 04:17	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 04:17	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370026A	08/26/2009 19:05	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370026A	08/26/2009 10:15	Kelli M Barto	1
07035	Arsenic	SW-846 6010B	1	092385705002	08/28/2009 05:59	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092385705002	08/28/2009 05:59	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092385705002	08/28/2009 05:59	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757622

Group No. 1158860

NM

MW016A Grab Water Sample
Eunice North Gas Plant

Collected: 08/21/2009 12:52 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10
Reported: 09/02/2009 at 16:49
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

16A--

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705002	08/28/2009 05:59	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705002	08/27/2009 09:20	Denise K Conners	1
00224	Chloride	EPA 300.0	1	09243373101B	08/31/2009 16:47	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027602A	08/22/2009 12:10	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757623

Group No. 1158860

MW015A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 13:28 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

15A--

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 2,270	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 3,820	mg/l 600	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 04:40	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 04:40	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 04:40	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370026A	08/26/2009 19:27	Diane V Do	1
7003	Extraction - DRO (Waters)	SW-846 3510C	1	092370026A	08/26/2009 10:15	Kelli M Barto	1
7035	Arsenic	SW-846 6010B	1	092385705002	08/28/2009 06:03	John W Yanzuk II	1
7051	Chromium	SW-846 6010B	1	092385705002	08/28/2009 06:03	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092385705002	08/28/2009 06:03	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757623

Group No. 1158860

MW015A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 13:28 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

15A--

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705002	08/28/2009 06:03	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705002	08/27/2009 09:20	Denise K Connors	1
00224	Chloride	EPA 300.0	1	09243373101B	08/31/2009 17:33	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027602A	08/22/2009 12:10	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757624

Group No. 1158860

MW040A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 14:04 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10
Reported: 09/02/2009 at 16:49
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

40A--

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 96	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l 0.0304	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 54.1	mg/l 10.0	25
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 446	mg/l 30.0	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 05:04	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 05:04	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 05:04	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370026A	08/26/2009 19:48	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370026A	08/26/2009 10:15	Kelli M Barto	1
07035	Arsenic	SW-846 6010B	1	092385705002	08/28/2009 06:07	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092385705002	08/28/2009 06:07	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092385705002	08/28/2009 06:07	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757624

Group No. 1158860

NM

MW040A Grab Water Sample
Eunice North Gas Plant

Collected: 08/21/2009 14:04 by SG

Account Number: 11842

Submitted: 08/22/2009 10:10
Reported: 09/02/2009 at 16:49
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

40A--

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705002	08/28/2009 06:07	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705002	08/27/2009 09:20	Denise K Connors	1
00224	Chloride	EPA 300.0	1	09243373101B	09/02/2009 05:02	K. Robert Caulfeild-James	25
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027602A	08/22/2009 12:10	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5757625

Group No. 1158860

NM

Trip Blank Water Sample
Eunice North Gas Plant

Collected: 08/21/2009

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

TB-1-

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles		SW-846 8021B	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/25/2009 21:13	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/25/2009 21:13	Marie D John	1

Lancaster Laboratories Sample No. WW 5757626

Group No. 1158860

MW019A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 13:19 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

19A--

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 491	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 1,180	mg/l 120	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A54A	08/26/2009 05:27	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A54A	08/26/2009 05:27	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A54A	08/26/2009 05:27	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370026A	08/26/2009 20:09	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370026A	08/26/2009 10:15	Kelli M Barto	1
07035	Arsenic	SW-846 6010B	1	092385705002	08/28/2009 06:10	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092385705002	08/28/2009 06:10	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092385705002	08/28/2009 06:10	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757626

Group No. 1158860

MW019A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 13:19 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

19A--

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705002	08/28/2009 06:10	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705002	08/27/2009 09:20	Denise K Connors	1
00224	Chloride	EPA 300.0	1	09243373101B	08/31/2009 18:04	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027601A	08/22/2009 11:20	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757627

Group No. 1158860

MW072SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 14:17 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

72SA-

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 96	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 351	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 1,380	mg/l 120	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A94A	08/25/2009 20:05	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A94A	08/25/2009 20:05	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A94A	08/25/2009 20:05	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370026A	08/26/2009 20:31	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370026A	08/26/2009 10:15	Kelli M Barto	1
07035	Arsenic	SW-846 6010B	1	092385705002	08/28/2009 06:14	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092385705002	08/28/2009 06:14	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092385705002	08/28/2009 06:14	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757627

Group No. 1158860

NM

MW072SA Grab Water Sample
Eunice North Gas Plant

Collected: 08/21/2009 14:17 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10
Reported: 09/02/2009 at 16:49
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

72SA-

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705002	08/28/2009 06:14	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705002	08/27/2009 09:20	Denise K Conners	1
00224	Chloride	EPA 300.0	1	09243373101B	08/31/2009 18:19	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027601A	08/22/2009 11:20	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757628

Group No. 1158860

MW076SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 15:00 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

76SA-

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 96	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 819	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 1,870	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A94A	08/25/2009 20:57	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A94A	08/25/2009 20:57	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A94A	08/25/2009 20:57	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370026A	08/26/2009 20:52	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370026A	08/26/2009 10:15	Kelli M Barto	1
07035	Arsenic	SW-846 6010B	1	092385705002	08/28/2009 06:17	John W Yanzuk II	1
07051	Chromium	SW-846 6010B	1	092385705002	08/28/2009 06:17	John W Yanzuk II	1
01754	Iron	SW-846 6010B	1	092385705002	08/28/2009 06:17	John W Yanzuk II	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757628

Group No. 1158860

NM

MW076SA Grab Water Sample
Eunice North Gas Plant

Collected: 08/21/2009 15:00 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

76SA-

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705002	08/28/2009 06:17	John W Yanzuk II	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705002	08/27/2009 09:20	Denise K Conners	1
00224	Chloride	EPA 300.0	1	09243373101B	08/31/2009 18:34	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027601A	08/22/2009 11:20	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5757629

Group No. 1158860

Trip Blanks Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

TB--2

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles		SW-846 8021B	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09237A94A	08/25/2009 19:38	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A94A	08/25/2009 19:38	Marie D John	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757630

Group No. 1158860

MW020A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 10:30 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10
Reported: 09/02/2009 at 16:49
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

20A--

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 96	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	0.0195	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,110	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 2,220	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A94A	08/25/2009 21:24	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A94A	08/25/2009 21:24	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A94A	08/25/2009 21:24	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370026A	08/26/2009 21:13	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370026A	08/26/2009 10:15	Kelli M Barto	1
07035	Arsenic	SW-846 6010B	1	092385705003	08/28/2009 18:15	John P Hook	1
07051	Chromium	SW-846 6010B	1	092385705003	08/28/2009 18:15	John P Hook	1
01754	Iron	SW-846 6010B	1	092385705003	08/28/2009 18:15	John P Hook	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757630

Group No. 1158860

MW020A Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 10:30 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

20A--

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705003	08/28/2009 18:15	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705003	08/27/2009 09:28	Denise K Connors	1
00224	Chloride	EPA 300.0	1	09243373101B	08/31/2009 18:50	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027601A	08/22/2009 11:20	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757631

Group No. 1158860

MW020 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 11:10 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10
Reported: 09/02/2009 at 16:49
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

20---

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
	SW-846 8015B		ug/l	ug/l	
01636	TPH-GRO water C6-C10	n.a.	< 50	50	1
GC Volatiles					
	SW-846 8021B		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
	SW-846 8015B		ug/l	ug/l	
08269	TPH-DRO water C10-C28	n.a.	200	97	1
Metals Dissolved					
	SW-846 6010B		mg/l	mg/l	
07035	Arsenic	7440-38-2	< 0.0200	0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
	EPA 300.0		mg/l	mg/l	
00224	Chloride	16887-00-6	1,180	200	500
SM20 2540 C					
			mg/l	mg/l	
00212	Total Dissolved Solids	n.a.	2,380	240	1
SW-846 7196A					
			mg/l	mg/l	
00276	Hexavalent Chromium	18540-29-9	< 0.020	0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A94A	08/25/2009 21:50	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A94A	08/25/2009 21:50	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A94A	08/25/2009 21:50	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370026A	08/26/2009 21:34	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370026A	08/26/2009 10:15	Kelli M Barto	1
07035	Arsenic	SW-846 6010B	1	092385705003	08/28/2009 18:19	John P Hook	1
07051	Chromium	SW-846 6010B	1	092385705003	08/28/2009 18:19	John P Hook	1
01754	Iron	SW-846 6010B	1	092385705003	08/28/2009 18:19	John P Hook	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757631

Group No. 1158860

MW020 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 11:10 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

20---

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705003	08/28/2009 18:19	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705003	08/27/2009 09:28	Denise K Conners	1
00224	Chloride	EPA 300.0	1	09243373102A	08/31/2009 19:36	Ashley M Adams	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027601A	08/22/2009 11:20	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5757632

Group No. 1158860

LordWW Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 12:00 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

LRDWW

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	1.34	0.200	1
07058	Manganese	7439-96-5	0.139	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 2,040	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 4,290	mg/l 600	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09237A94A	08/25/2009 22:16	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09237A94A	08/25/2009 22:16	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09237A94A	08/25/2009 22:16	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092370026A	08/26/2009 21:56	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092370026A	08/26/2009 10:15	Kelli M Barto	1
07035	Arsenic	SW-846 6010B	1	092385705003	08/28/2009 18:24	John P Hook	1
07051	Chromium	SW-846 6010B	1	092385705003	08/28/2009 18:24	John P Hook	1
01754	Iron	SW-846 6010B	1	092385705003	08/28/2009 18:24	John P Hook	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5757632

Group No. 1158860

LordWW Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/21/2009 12:00 by SB

Account Number: 11842

Submitted: 08/22/2009 10:10
Reported: 09/02/2009 at 16:49
Discard: 10/03/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

LRDWW

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092385705003	08/28/2009 18:24	John P Hook	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092385705003	08/27/2009 09:28	Denise K Connors	1
00224	Chloride	EPA 300.0	1	09243373102A	08/31/2009 20:53	Ashley M Adams	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09234027601A	08/22/2009 11:20	Daniel S Smith	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5757633

Group No. 1158860

NM

Trip Blanks Water Sample
Eunice North Gas Plant

Collected: 08/21/2009

Account Number: 11842

Submitted: 08/22/2009 10:10

STANTEC International, Inc.

Reported: 09/02/2009 at 16:49

10235 W. Little York

Discard: 10/03/2009

Ste 400

Houston TX 77040

TB-3-

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles		SW-846 8021B	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09236A53A	08/24/2009 20:22	Katrina T Longenecker	1
01146	GC VOA Water Prep	SW-846 5030B	1	09236A53A	08/24/2009 20:22	Katrina T Longenecker	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 04:49 PM

Group Number: 1158860

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09236A53A	Sample number(s): 5757633							
Benzene	< 1.0	1.0	ug/l	115	120	80-120	4	30
Ethylbenzene	< 1.0	1.0	ug/l	110	110	80-120	0	30
Toluene	< 1.0	1.0	ug/l	110	115	80-120	4	30
Total Xylenes	< 3.0	3.0	ug/l	112	113	80-120	1	30
Batch number: 09237A54A	Sample number(s): 5757619-5757626							
Benzene	< 1.0	1.0	ug/l	100	100	80-120	0	30
Ethylbenzene	< 1.0	1.0	ug/l	95	95	80-120	0	30
Toluene	< 1.0	1.0	ug/l	95	95	80-120	0	30
TPH-GRO water C6-C10	< 50	50	ug/l	100	91	75-135	10	30
Total Xylenes	< 3.0	3.0	ug/l	97	93	80-120	4	30
Batch number: 09237A94A	Sample number(s): 5757627-5757632							
Benzene	< 1.0	1.0	ug/l	115	110	80-120	4	30
Ethylbenzene	< 1.0	1.0	ug/l	110	105	80-120	5	30
Toluene	< 1.0	1.0	ug/l	110	105	80-120	5	30
TPH-GRO water C6-C10	< 50	50	ug/l	127	109	75-135	15	30
Total Xylenes	< 3.0	3.0	ug/l	112	107	80-120	5	30
Batch number: 092370009A	Sample number(s): 5757619-5757621							
TPH-DRO water C10-C28	< 100	100	ug/l	71	74	56-122	3	20
Batch number: 092370026A	Sample number(s): 5757622-5757624, 5757626-5757628, 5757630-5757632							
TPH-DRO water C10-C28	< 100	100	ug/l	85	84	56-122	1	20
Batch number: 092385705002	Sample number(s): 5757619-5757624, 5757626-5757628							
Arsenic	< 0.0200	0.0200	mg/l	106		80-120		
Chromium	< 0.0150	0.0150	mg/l	104		90-110		
Iron	< 0.200	0.200	mg/l	97		90-112		
Manganese	< 0.0050	0.0050	mg/l	106		90-110		
Batch number: 092385705003	Sample number(s): 5757630-5757632							
Arsenic	< 0.0200	0.0200	mg/l	108		80-120		
Chromium	< 0.0150	0.0150	mg/l	101		90-110		
Iron	< 0.200	0.200	mg/l	100		90-112		
Manganese	< 0.0050	0.0050	mg/l	107		90-110		
Batch number: 09243373101B	Sample number(s): 5757619-5757624, 5757626-5757628, 5757630							
Chloride	< 0.40	0.40	mg/l	108		90-110		
Batch number: 09243373102A	Sample number(s): 5757631-5757632							
Chloride	< 0.40	0.40	mg/l	99		90-110		
Batch number: 09234027601A	Sample number(s): 5757626-5757628, 5757630-5757632							
Hexavalent Chromium	< 0.020	0.020	mg/l	97		90-110		

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 04:49 PM

Group Number: 1158860

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09234027602A	Sample number(s): 5757619-5757624							
Hexavalent Chromium	< 0.020	0.020	mg/l	99		90-110		
Batch number: 09239021201A	Sample number(s): 5757619-5757624, 5757626-5757628, 5757630-5757632							
Total Dissolved Solids	< 30.0	30.0	mg/l	107		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09236A53A	Sample number(s): 5757633 UNSPK: P756235								
Benzene	125		70-152						
Ethylbenzene	119		75-133						
Toluene	120		78-129						
Total Xylenes	117 (2)		67-155						
Batch number: 09237A54A	Sample number(s): 5757619-5757626 UNSPK: 5757619, 5757620								
Benzene	115		70-152						
Ethylbenzene	105		75-133						
Toluene	109		78-129						
TPH-GRO water C6-C10	109		63-154						
Total Xylenes	107		67-155						
Batch number: 09237A94A	Sample number(s): 5757627-5757632 UNSPK: 5757627, P757805								
Benzene	120		70-152						
Ethylbenzene	115		75-133						
Toluene	115		78-129						
TPH-GRO water C6-C10	127		63-154						
Total Xylenes	112		67-155						
Batch number: 092385705002	Sample number(s): 5757619-5757624, 5757626-5757628 UNSPK: P755843 BKG: P755843								
Arsenic	107	107	75-125	0	20	< 0.0200	< 0.0200	200* (1)	20
Chromium	99	98	81-120	1	20	< 0.0150	< 0.0150	0 (1)	20
Iron	63 (2)	65 (2)	75-125	0	20	8.51	8.20	4	20
Manganese	81 (2)	82 (2)	75-125	0	20	2.98	2.88	3	20
Batch number: 092385705003	Sample number(s): 5757630-5757632 UNSPK: P755857 BKG: P755857								
Arsenic	112	113	75-125	0	20	< 0.0200	< 0.0200	14 (1)	20
Chromium	99	98	81-120	1	20	< 0.0150	< 0.0150	0 (1)	20
Iron	100	95	75-125	4	20	0.223	0.244	9 (1)	20
Manganese	104	101	75-125	1	20	0.675	0.670	1	20
Batch number: 09243373101B	Sample number(s): 5757619-5757624, 5757626-5757628, 5757630 UNSPK: 5757619 BKG: 5757619								
Chloride	98		90-110			732	782	7 (1)	20
Batch number: 09243373102A	Sample number(s): 5757631-5757632 UNSPK: 5757631 BKG: 5757631								
Chloride	84*		90-110			1,180	1,070	10	20

*- Outside of specification

(1) The result for one or both determinations was less than five times the LOQ.

(2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 04:49 PM

Group Number: 1158860

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09234027601A Hexavalent Chromium	91	100	85-115	10*	5	< 0.020	< 0.020	0 (1)	5
Batch number: 09234027602A Hexavalent Chromium	98	94	85-115	3	5	< 0.020	< 0.020	13* (1)	5
Batch number: 09239021201A Total Dissolved Solids	114	103	54-143	4	12	2,220	2,280	3	9

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: BTEX (8021)

Batch number: 09236A53A

Trifluorotoluene-F	Trifluorotoluene-P
5757633	99
Blank	97
LCS	99
LCSD	99
MS	98

Limits: 60-120 69-129

Analysis Name: BTEX (8021)

Batch number: 09237A54A

Trifluorotoluene-F	Trifluorotoluene-P
5757619	113
5757620	115
5757621	116
5757622	116
5757623	116
5757624	114
5757625	111
5757626	116
Blank	113
LCS	113
LCSD	114
MS	116

Limits: 63-135 69-129

Analysis Name: BTEX (8021)

Batch number: 09237A94A

Trifluorotoluene-F	Trifluorotoluene-P
--------------------	--------------------

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/02/09 at 04:49 PM

Group Number: 1158860

Surrogate Quality Control

5757627	95	101
5757628	87	100
5757629		100
5757630	87	101
5757631	87	101
5757632	87	101
Blank	85	101
LCS	94	100
LCSD	92	100
MS	91	101

Limits: 63-135 69-129

Analysis Name: TPH-DRO water C10-C28
Batch number: 092370009A
Orthoterphenyl

5757619	97
5757620	94
5757621	92
Blank	80
LCS	89
LCSD	92

Limits: 54-127

Analysis Name: TPH-DRO water C10-C28
Batch number: 092370026A
Orthoterphenyl

5757622	89
5757623	91
5757624	102
5757626	102
5757627	91
5757628	98
5757630	94
5757631	100
5757632	94
Blank	82
LCS	107
LCSD	107

Limits: 54-127

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Analysis Request/Environmental Services Chain of Custody



For Lancaster Laboratories use only

Acct. # 11842

Group # 115886

Sample # 5757619-33

COC # 217453

Project Name: Ched Powell / J. Wood

Project Manager: Ched Powell / J. Wood

Sampler: J. Wood

Name of state where samples were collected: New Mexico

Quote #: 201250

Preservation Codes

Preservation Codes

Remarks

Please print. Instructions on reverse side correspond with circled numbers.

1 Client: <u>Ched Powell</u>		2 Sample Identification		3 Date Collected		4 Date Analyzed		5 Preservation Codes		6 Preservation Codes		7 Turnaround Time Requested (TAT) (please circle):		8 Data Package Options (please circle if required)	
Project Name	Project Manager	Sampler	Sample ID	Date	Time	Date	Time	Code	Code	Code	Code	Normal	Rush	Type I (Validation/NJ Reg)	Type II (Tier II)
<u>MW0335A</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>MW0335A</u>	<u>8-21-09</u>	<u>1033</u>	<u>8-21-09</u>	<u>1033</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>MW0575A</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>MW0575A</u>	<u>8-21-09</u>	<u>1112</u>	<u>8-21-09</u>	<u>1112</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>MW0181A</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>MW0181A</u>	<u>8-21-09</u>	<u>1157</u>	<u>8-21-09</u>	<u>1157</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>MW0161A</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>MW0161A</u>	<u>8-21-09</u>	<u>1152</u>	<u>8-21-09</u>	<u>1152</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>MW0151A</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>MW0151A</u>	<u>8-21-09</u>	<u>1328</u>	<u>8-21-09</u>	<u>1328</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>MW0401A</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>MW0401A</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1404</u>	<u>8-21-09</u>	<u>1404</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>Normal</u>	<u>Rush</u>	<u>TX TRRP-13</u>	<u>MA MCP</u>
<u>Trip Blank</u>	<u>Ched Powell</u>	<u>J. Wood</u>	<u>Trip Blank</u>	<u>8-21-09</u>	<u>1</u>										

Chevron Generic Analysis Request/Chain of Custody

010312



For Lancaster Laboratories use only
Act. #: 11842 Sample #: 5757619-33 SCR#:

Where quality is a science

Temp. Date 8/21/09

715 1158860

Facility #: <u>Enbridge North Gas Plant - 212201135</u> Site Address: <u>Enbridge, New Mexico</u> Chevron PM: <u>J. Hansen</u> Lead Consultant: <u>Clawson</u> Consultant/Office: <u>Stanley-Harston</u> Consultant Pj. Mgr.: <u>Nancy Woodward</u> Consultant Phone #: <u>213-937-7973</u> Fax #: <u>213-937-8328</u> Sampler: <u>SJS</u> Service Order #: <u>Non SAR</u>				Analyses Requested Preservation Codes H = HCl T = Thiosulfate N = HNO ₃ B = NaOH S = H ₂ SO ₄ O = Other ☐ J value reporting needed ☐ Must meet lowest detection limits possible for 8260 compounds 8021 MTBE Confirmation ☐ Confirm MTBE + Naphthalene ☐ Confirm highest hit by 8260 ☐ Confirm all hits by 8260 ☐ Run ___ oxy's on highest hit ☐ Run ___ oxy's on all hits			
Matrix ☒ Potable ☐ NPDES ☐ Water ☐ Oil ☐ Air ☐ Soil ☐ Composite				Total Number of Containers 8260 full scan Oxygenates TPH G TPH D Lead Total VPHEPH NWTPH H CID quantification			
Sample Identification <u>MW019A</u> <u>MW072SA</u> <u>MW076SA</u> <u>TRIP Blanks</u>				Date Collected <u>8-21-09</u> <u>8-21-09</u> <u>8-21-09</u> <u>8-21-09</u>			
Time Collected <u>1319</u> <u>1417</u> <u>1500</u> <u>8260</u>				Relinquished by: <u>John Sell</u> Relinquished by: Relinquished by: Relinquished by:			
Turnaround Time Requested (TAT) (please circle) STD. TAT 24 hour 72 hour 48 hour 5 day				Date Received by: <u>8/21/09</u> Date Received by: Date Received by: Date Received by:			
Data Package Options (please circle if required) QC Summary Type I - Full Type VI (Raw Data) Disk / EDD WIP (RWQCB) Standard Format Disk Other				Received by: <u>Nancy Harston</u> Date Received by: <u>8/21/09</u> Date Received by: Date Received by:			
Temperature Upon Receipt: <u>18</u> °C				Custody Seals Intact? <u>(Yes)</u> No			

All times are Central Time Zone

Lancaster Laboratories Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below-Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers

A	TIC is a possible aldol-condensation product
B	Analyte was also detected in the blank
C	Pesticide result confirmed by GC/MS
D	Compound quantitated on a diluted sample
E	Concentration exceeds the calibration range of the instrument
J	Estimated value
N	Presumptive evidence of a compound (TICs only)
P	Concentration difference between primary and confirmation columns >25%
U	Compound was not detected
X,Y,Z	Defined in case narrative

Inorganic Qualifiers

B	Value is <CRDL, but ≥IDL
E	Estimated due to interference
M	Duplicate injection precision not met
N	Spike amount not within control limits
S	Method of standard additions (MSA) used for calculation
U	Compound was not detected
W	Post digestion spike out of control limits
*	Duplicate analysis not within control limits
+	Correlation coefficient for MSA <0.995

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

ANALYTICAL RESULTS

Prepared for:

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston, TX 77040

713-937-7973

Prepared by:

Lancaster Laboratories
2425 New Holland Pike
Lancaster, PA 17605-2425

September 03, 2009

SAMPLE GROUP

The sample group for this submittal is 1159028. Samples arrived at the laboratory on Tuesday, August 25, 2009. The PO# for this group is 89CH.49526.08 and the release number is EUNICE NORTH GP.

<u>Client Description</u>	<u>Lancaster Labs Number</u>
MW075SA Grab Water Sample	5758622
MW074SA Grab Water Sample	5758623
WoodellWW Grab Water Sample	5758624
MW026 Grab Water Sample	5758625
Trip Blank Water Sample	5758626
DUP#201 Grab Water Sample	5758627
MW028 Grab Water Sample	5758628
MW068 Grab Water Sample	5758629
MW060 Grab Water Sample	5758630
MW029 Grab Water Sample	5758631
MW033 Grab Water Sample	5758632
MW069 Grab Water Sample	5758633
DUP-103 Grab Water Sample	5758634
Trip Blank Water Sample	5758635

METHODOLOGY

The specific methodologies used in obtaining the enclosed analytical results are indicated on the Laboratory Sample Analysis Record.



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

ELECTRONIC STANTEC International, Inc.
COPY TO
ELECTRONIC STANTEC International, Inc.
COPY TO

Attn: Chad Vowell

Attn: Steve Bell

Questions? Contact your Client Services Representative
Wendy A Kozma at (717) 656-2300

Respectfully Submitted,

Martha L. Seidel

Martha L. Seidel
Senior Chemist



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758622

Group No. 1159028

MW075SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 10:35 by SB

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW75S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
0269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 95	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 586	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 2,400	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 14:31	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 14:31	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 14:31	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	08/31/2009 15:39	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 15:33	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:08	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 15:33	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758622

Group No. 1159028

MW075SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 10:35 by SB

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston, TX 77040

MW75S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:08	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102A	08/31/2009 21:08	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09239021201A	08/27/2009 09:30	Yolunder Y Bunch	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027601A	08/25/2009 09:50	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758623

Group No. 1159028

MW074SA Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 11:25 by SB

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW74S

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
C Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 94	ug/l 94	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 634	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 2,020	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 14:55	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 14:55	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 14:55	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	08/31/2009 16:00	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 15:46	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:11	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 15:46	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758623

Group No. 1159028

NM

MW074SA Grab Water Sample
Eunice North Gas Plant

Collected: 08/24/2009 11:25 by SB

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW74S

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:11	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102A	08/31/2009 21:23	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027601A	08/25/2009 09:50	Michelle L Lalli	1



2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Analysis Report

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758624

Group No. 1159028

WoodellWW Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 11:50 by SB

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

WOODE

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l < 96	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	0.0561	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 615	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	SW-846 7196A n.a.	mg/l 1,480	mg/l 120	1
00276	Hexavalent Chromium	18540-29-9	mg/l 0.058	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 15:19	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 15:19	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 15:19	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	08/31/2009 16:20	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 15:50	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:20	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 15:50	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758624

Group No. 1159028

NM

WoodellWW Grab Water Sample
Eunice North Gas Plant

Collected: 08/24/2009 11:50 by SB

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

WOODE

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:20	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102A	08/31/2009 21:39	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027601A	08/25/2009 09:50	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758625

Group No. 1159028

MW026 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 14:10 by SB

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW026

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 150	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 866	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 2,620	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 15:43	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 15:43	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 15:43	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	08/31/2009 18:04	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 15:55	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:23	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 15:55	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758625

Group No. 1159028

MW026 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 14:10 by SB

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW026

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:23	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102A	08/31/2009 21:54	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027602A	08/25/2009 10:10	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5758626

Group No. 1159028

NM

Trip Blank Water Sample
Eunice North Gas Plant

Collected: 08/24/2009

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles	SW-846 8021B		ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 13:19	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 13:19	Marie D John	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758627

Group No. 1159028

DUP#201 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 by SB

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

DU201

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 140	ug/l 95	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,250	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 2,290	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 16:07	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 16:07	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 16:07	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	08/31/2009 16:41	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 15:59	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:26	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 15:59	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758627

Group No. 1159028

DUP#201 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 by SB

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

DU201

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:26	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102A	08/31/2009 22:09	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027602A	08/25/2009 10:10	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758628

Group No. 1159028

MW028 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 10:52 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW028

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l 120	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
C Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 490	ug/l 190	2
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l 0.0255	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 438	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 1,470	mg/l 120	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 16:31	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 16:30	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 16:31	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	09/01/2009 10:33	Diane V Do	2
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 16:03	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:29	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 16:03	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758628

Group No. 1159028

MW028 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 10:52 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW028

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:29	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102A	08/31/2009 22:25	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027601A	08/25/2009 09:50	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758629

Group No. 1159028

MW068 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 11:35 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW068

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 110	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.588	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 2,110	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 3,500	mg/l 600	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 16:55	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 16:55	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 16:55	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	08/31/2009 17:02	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 16:08	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:32	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 16:08	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758629

Group No. 1159028

MW068 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 11:35 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW068

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:32	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102A	08/31/2009 22:40	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027601A	08/25/2009 09:50	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758630

Group No. 1159028

MW060 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 12:16 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW060

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 110	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	1.11	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 1,450	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 3,450	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 20:14	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 20:13	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 20:14	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	2	092390008A	08/31/2009 17:43	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 16:12	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:35	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 16:12	Eric L Eby	1

Lancaster Laboratories Sample No. WW 5758630

Group No. 1159028
NM

MW060 Grab Water Sample
Eunice North Gas Plant

Collected: 08/24/2009 12:16 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW060

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:35	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102A	08/31/2009 22:55	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027601A	08/25/2009 09:50	Michelle L Lalli	1

Lancaster Laboratories Sample No. WW 5758631

Group No. 1159028

MW029 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 13:39 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW029

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l < 50	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l < 1.0	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 99	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l 0.0239	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	< 0.0050	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 136	mg/l 40.0	100
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 706	mg/l 60.0	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 20:37	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 20:37	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 20:37	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	08/31/2009 18:45	Diane V Do	1
0003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 16:17	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:39	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 16:17	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758631

Group No. 1159028

NM

MW029 Grab Water Sample
Eunice North Gas Plant

Collected: 08/24/2009 13:39 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW029

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:39	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102B	09/02/2009 06:21	K. Robert Caulfeild-James	100
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027602A	08/25/2009 10:10	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758632

Group No. 1159028

MW033 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 14:30 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW033

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l 2,000	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l 180	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	260	1.0	1
08213	Toluene	108-88-3	150	1.0	1
08213	Total Xylenes	1330-20-7	85	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 890	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	1.04	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 915	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 1,870	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 21:01	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 21:01	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 21:01	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	08/31/2009 19:06	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 16:21	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:42	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 16:21	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758632

Group No. 1159028

MW033 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 14:30 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW033

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:42	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102B	09/01/2009 00:27	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027602A	08/25/2009 10:10	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758633

Group No. 1159028

MW069 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 15:14 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10
Reported: 09/03/2009 at 10:20
Discard: 10/04/2009

STANTEC International, Inc.
10235 W. Little York
Ste 400
Houston TX 77040

MW069

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l 120	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l 6.3	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	22	1.0	1
08213	Toluene	108-88-3	10	1.0	1
08213	Total Xylenes	1330-20-7	6.4	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 610	ug/l 97	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	0.288	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 3,470	mg/l 400	1000
SM20 2540 C					
00212	Total Dissolved Solids	n.a.	mg/l 6,690	mg/l 600	1
SW-846 7196A					
00276	Hexavalent Chromium	18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 21:25	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 21:25	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 21:25	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	08/31/2009 19:27	Diane V Do	1
07003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
07035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 16:25	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:45	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 16:25	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758633

Group No. 1159028

MW069 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 15:14 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

MW069

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:45	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102B	09/02/2009 08:12	K. Robert Caulfeild-James	1000
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027602A	08/25/2009 10:10	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 2

Lancaster Laboratories Sample No. WW 5758634

Group No. 1159028

DUP-103 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

DUI103

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles					
01636	TPH-GRO water C6-C10	SW-846 8015B n.a.	ug/l 1,900	ug/l 50	1
GC Volatiles					
08213	Benzene	SW-846 8021B 71-43-2	ug/l 170	ug/l 1.0	1
08213	Ethylbenzene	100-41-4	250	1.0	1
08213	Toluene	108-88-3	140	1.0	1
08213	Total Xylenes	1330-20-7	79	3.0	1
GC Extractable TPH					
08269	TPH-DRO water C10-C28	SW-846 8015B n.a.	ug/l 850	ug/l 96	1
Metals Dissolved					
07035	Arsenic	SW-846 6010B 7440-38-2	mg/l < 0.0200	mg/l 0.0200	1
07051	Chromium	7440-47-3	< 0.0150	0.0150	1
01754	Iron	7439-89-6	< 0.200	0.200	1
07058	Manganese	7439-96-5	1.02	0.0050	1
Wet Chemistry					
00224	Chloride	EPA 300.0 16887-00-6	mg/l 909	mg/l 200	500
SM20 2540 C					
00212	Total Dissolved Solids	SM20 2540 C n.a.	mg/l 1,850	mg/l 240	1
SW-846 7196A					
00276	Hexavalent Chromium	SW-846 7196A 18540-29-9	mg/l < 0.020	mg/l 0.020	1

General Sample Comments

This sample was filtered in the lab for dissolved metals.

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
01636	TPH-GRO water C6-C10	SW-846 8015B	1	09239A53A	08/27/2009 21:48	Marie D John	1
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 21:48	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 21:48	Marie D John	1
08269	TPH-DRO water C10-C28	SW-846 8015B	1	092390008A	08/31/2009 18:25	Diane V Do	1
0003	Extraction - DRO (Waters)	SW-846 3510C	1	092390008A	08/27/2009 14:50	Cody R Hanna	1
0035	Arsenic	SW-846 6010B	1	092405705004	09/01/2009 16:39	Eric L Eby	1
07051	Chromium	SW-846 6010B	1	092405705004	08/31/2009 09:48	Eric L Eby	1
01754	Iron	SW-846 6010B	1	092405705004	09/01/2009 16:39	Eric L Eby	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 2 of 2

Lancaster Laboratories Sample No. WW 5758634

Group No. 1159028

DUP-103 Grab Water Sample
Eunice North Gas Plant

NM

Collected: 08/24/2009 by JL

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

DU103

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
07058	Manganese	SW-846 6010B	1	092405705004	08/31/2009 09:48	Eric L Eby	1
05705	WW/TL SW 846 ICP Digest (tot)	SW-846 3010A	1	092405705004	08/30/2009 21:00	Mirit S Shenouda	1
00224	Chloride	EPA 300.0	1	09243373102B	09/01/2009 00:58	K. Robert Caulfeild-James	500
00212	Total Dissolved Solids	SM20 2540 C	1	09240021201A	08/28/2009 09:07	Hannah M Royer	1
00276	Hexavalent Chromium	SW-846 7196A	1	09237027602A	08/25/2009 10:10	Michelle L Lalli	1



Analysis Report

2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 • 717-656-2300 Fax: 717-656-2681 • www.lancasterlabs.com

Page 1 of 1

Lancaster Laboratories Sample No. WW 5758635

Group No. 1159028

NM

Trip Blank Water Sample
Eunice North Gas Plant

Collected: 08/24/2009

Account Number: 11842

Submitted: 08/25/2009 09:10

STANTEC International, Inc.

Reported: 09/03/2009 at 10:20

10235 W. Little York

Discard: 10/04/2009

Ste 400

Houston TX 77040

CAT No.	Analysis Name	CAS Number	As Received Result	As Received Limit of Quantitation	Dilution Factor
GC Volatiles		SW-846 8021B	ug/l	ug/l	
08213	Benzene	71-43-2	< 1.0	1.0	1
08213	Ethylbenzene	100-41-4	< 1.0	1.0	1
08213	Toluene	108-88-3	< 1.0	1.0	1
08213	Total Xylenes	1330-20-7	< 3.0	3.0	1

General Sample Comments

All QC is compliant unless otherwise noted. Please refer to the Quality Control Summary for overall QC performance data and associated samples.

Laboratory Sample Analysis Record

CAT No.	Analysis Name	Method	Trial#	Batch#	Analysis Date and Time	Analyst	Dilution Factor
08213	BTEX (8021)	SW-846 8021B	1	09239A53A	08/27/2009 13:43	Marie D John	1
01146	GC VOA Water Prep	SW-846 5030B	1	09239A53A	08/27/2009 13:43	Marie D John	1

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/03/09 at 10:20 AM

Group Number: 1159028

Matrix QC may not be reported if site-specific QC samples were not submitted. In these situations, to demonstrate precision and accuracy at a batch level, a LCS/LCSD was performed, unless otherwise specified in the method.

Laboratory Compliance Quality Control

Analysis Name	Blank Result	Blank LOQ	Report Units	LCS %REC	LCSD %REC	LCS/LCSD Limits	RPD	RPD Max
Batch number: 09239A53A	Sample number(s): 5758622-5758635							
Benzene	< 1.0	1.0	ug/l	105	110	80-120	5	30
Ethylbenzene	< 1.0	1.0	ug/l	95	100	80-120	5	30
Toluene	< 1.0	1.0	ug/l	100	105	80-120	5	30
TPH-GRO water C6-C10	< 50	50.	ug/l	118	118	75-135	0	30
Total Xylenes	< 3.0	3.0	ug/l	100	105	80-120	5	30
Batch number: 092390008A	Sample number(s): 5758622-5758625, 5758627-5758634							
TPH-DRO water C10-C28	< 100	100.	ug/l	81	80	56-122	2	20
Batch number: 092405705004	Sample number(s): 5758622-5758625, 5758627-5758634							
Arsenic	< 0.0200	0.0200	mg/l	100		80-120		
Chromium	< 0.0150	0.0150	mg/l	92		90-110		
Iron	< 0.200	0.200	mg/l	98		90-112		
Manganese	< 0.0050	0.0050	mg/l	93		90-110		
Batch number: 09243373102A	Sample number(s): 5758622-5758625, 5758627-5758630							
Chloride	< 0.40	0.40	mg/l	99		90-110		
Batch number: 09243373102B	Sample number(s): 5758631-5758634							
Chloride	< 0.40	0.40	mg/l	99		90-110		
Batch number: 09237027601A	Sample number(s): 5758622-5758624, 5758628-5758630							
Hexavalent Chromium	< 0.020	0.020	mg/l	100		90-110		
Batch number: 09237027602A	Sample number(s): 5758625, 5758627, 5758631-5758634							
Hexavalent Chromium	< 0.020	0.020	mg/l	99		90-110		
Batch number: 09239021201A	Sample number(s): 5758622							
Total Dissolved Solids	< 30.0	30.0	mg/l	107		80-120		
Batch number: 09240021201A	Sample number(s): 5758623-5758625, 5758627-5758634							
Total Dissolved Solids	< 30.0	30.0	mg/l	95		80-120		

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Batch number: 09239A53A	Sample number(s): 5758622-5758635 UNSPK: 5758623, 5758631								
Benzene	128		70-152						

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control Summary

Client Name: STANTEC International, Inc.
Reported: 09/03/09 at 10:20 AM

Group Number: 1159028

Sample Matrix Quality Control

Unspiked (UNSPK) = the sample used in conjunction with the matrix spike
Background (BKG) = the sample used in conjunction with the duplicate

Analysis Name	MS %REC	MSD %REC	MS/MSD Limits	RPD	RPD MAX	BKG Conc	DUP Conc	DUP RPD	Dup RPD Max
Ethylbenzene	120		75-133						
Toluene	123		78-129						
TPH-GRO water C6-C10	136		63-154						
Total Xylenes	123		67-155						
Batch number: 092405705004 Sample number(s): 5758622-5758625,5758627-5758634 UNSPK: P757365 BKG: P757365									
Arsenic	107	104	75-125	3	20	< 0.0200	< 0.0200	0 (1)	20
Chromium	93	92	81-120	1	20	< 0.0150	< 0.0150	0 (1)	20
Iron	97	100	75-125	2	20	0.333	0.321	3 (1)	20
Manganese	97	88	75-125	3	20	0.997	0.971	3	20
Batch number: 09243373102A Sample number(s): 5758622-5758625,5758627-5758630 UNSPK: P757631 BKG: P757631									
Chloride	84*		90-110			1,180	1,070	10	20
Batch number: 09243373102B Sample number(s): 5758631-5758634 UNSPK: 5758631 BKG: 5758631									
Chloride	96		90-110			136	160	16 (1)	20
Batch number: 09237027601A Sample number(s): 5758622-5758624,5758628-5758630 UNSPK: 5758622 BKG: 5758622									
Hexavalent Chromium	100	103	85-115	3	5	< 0.020	< 0.020	0 (1)	5
Batch number: 09237027602A Sample number(s): 5758625,5758627,5758631-5758634 UNSPK: 5758625 BKG: 5758625									
Hexavalent Chromium	105	105	85-115	1	5	< 0.020	< 0.020	0 (1)	5
Batch number: 09239021201A Sample number(s): 5758622 UNSPK: P757630 BKG: P757630									
Total Dissolved Solids	114	103	54-143	4	12	2,220	2,280	3	9
Batch number: 09240021201A Sample number(s): 5758623-5758625,5758627-5758634 UNSPK: 5758623 BKG: 5758623									
Total Dissolved Solids	99	97	54-143	1	12	2,020	2,020	0	9

Surrogate Quality Control

Surrogate recoveries which are outside of the QC window are confirmed unless attributed to dilution or otherwise noted on the Analysis Report.

Analysis Name: BTEX (8021)
Batch number: 09239A53A

Trifluorotoluene-F	Trifluorotoluene-P
5758622	78
5758623	78
5758624	81
5758625	78
5758626	96
5758627	79
5758628	81
5758629	82
5758630	80
5758631	80
5758632	87
5758633	79
	98
	99
	99
	100
	96
	100
	99
	99
	98
	99
	102
	95

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.

Quality Control SummaryClient Name: STANTEC International, Inc.
Reported: 09/03/09 at 10:20 AM

Group Number: 1159028

Surrogate Quality Control

5758634	86	99
5758635		97
Blank	80	97
LCS	82	98
LCSD	83	98
MS	83	99

Limits:	63-135	69-129
---------	--------	--------

Analysis Name: TPH-DRO water C10-C28
Batch number: 092390008A
Orthoterphenyl

5758622	86
5758623	83
5758624	84
5758625	92
5758627	88
5758628	92
5758629	89
5758630	94
5758631	95
5758632	107
5758633	110
5758634	104
Blank	74
LCS	98
LCSD	98

Limits:	54-127
---------	--------

*- Outside of specification

- (1) The result for one or both determinations was less than five times the LOQ.
- (2) The unspiked result was more than four times the spike added.



Where quality is a science.

Lancaster Laboratories

For Lancaster Laboratories use only

SCR#:

Sample #: 5758622-35

Acct. #:

11842

010313

1159028

Facility #: Enviro North Gas Plant 212201135 Site Address: Enviro, New Mexico Chevron PM: J. Harner Lead Consultant: C. Vaneil Consultant/Office: Sander - Houston Consultant Prj. Mgr.: Danny Woodward Consultant Phone #: 713.973.9973 Fax #: 713.983.8328 Sampler: SF Service Order #: _____ ☐ Non SAR: _____				<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th>Sample Identification</th> <th>Date Collected</th> <th>Time Collected</th> <th>Grab</th> <th>Composite</th> <th>Soil</th> <th>Water</th> <th>Oil</th> <th>Air</th> <th>Total Number of Containers</th> <th>Matrix</th> <th>TPH G</th> <th>TPH D</th> <th>Lead Total</th> <th>VPH/EPH</th> <th>NWTPH HClID</th> <th>Quantification</th> <th>Preservation Codes</th> <th>Preservative Codes</th> </tr> <tr> <td>MMW075SA</td> <td>8-24-09</td> <td>1035</td> <td>✓</td> <td></td> <td>✓</td> <td>✓</td> <td></td> <td></td> <td>7</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>H = HCl T = Thiou sulfate N = HNO₃ S = H₂SO₄ O = Other</td> </tr> <tr> <td>MMW074SA</td> <td>8-24-09</td> <td>1125</td> <td>✓</td> <td></td> <td>✓</td> <td>✓</td> <td></td> <td></td> <td>7</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>J value reporting needed Must meet lowest detection limits possible for 8260 compounds</td> </tr> <tr> <td>MMW071WW</td> <td>8-24-09</td> <td>1150</td> <td>✓</td> <td></td> <td>✓</td> <td>✓</td> <td></td> <td></td> <td>7</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>8021 MTBE Confirmation Confirm MTBE + Naphthalene Confirm highest hit by 8260 Confirm all hits by 8260 Run ___ oxy's on highest hit Run ___ oxy's on all hits</td> </tr> <tr> <td>MMW026</td> <td>8-28-09</td> <td>1410</td> <td>✓</td> <td></td> <td>✓</td> <td>✓</td> <td></td> <td></td> <td>7</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>Comments / Remarks Lab Filter for Dissolved Metals</td> </tr> <tr> <td colspan="19" style="text-align: center;"> All times are Central time 2009 </td> </tr> </table>				Sample Identification	Date Collected	Time Collected	Grab	Composite	Soil	Water	Oil	Air	Total Number of Containers	Matrix	TPH G	TPH D	Lead Total	VPH/EPH	NWTPH HClID	Quantification	Preservation Codes	Preservative Codes	MMW075SA	8-24-09	1035	✓		✓	✓			7	✓	✓	✓	✓	✓	✓	✓	✓	H = HCl T = Thiou sulfate N = HNO ₃ S = H ₂ SO ₄ O = Other	MMW074SA	8-24-09	1125	✓		✓	✓			7	✓	✓	✓	✓	✓	✓	✓	J value reporting needed Must meet lowest detection limits possible for 8260 compounds	MMW071WW	8-24-09	1150	✓		✓	✓			7	✓	✓	✓	✓	✓	✓	✓	8021 MTBE Confirmation Confirm MTBE + Naphthalene Confirm highest hit by 8260 Confirm all hits by 8260 Run ___ oxy's on highest hit Run ___ oxy's on all hits	MMW026	8-28-09	1410	✓		✓	✓			7	✓	✓	✓	✓	✓	✓	✓	Comments / Remarks Lab Filter for Dissolved Metals	All times are Central time 2009																		
Sample Identification	Date Collected	Time Collected	Grab	Composite	Soil	Water	Oil	Air	Total Number of Containers	Matrix	TPH G	TPH D	Lead Total	VPH/EPH	NWTPH HClID	Quantification	Preservation Codes	Preservative Codes																																																																																																				
MMW075SA	8-24-09	1035	✓		✓	✓			7	✓	✓	✓	✓	✓	✓	✓	✓	H = HCl T = Thiou sulfate N = HNO ₃ S = H ₂ SO ₄ O = Other																																																																																																				
MMW074SA	8-24-09	1125	✓		✓	✓			7	✓	✓	✓	✓	✓	✓	✓	J value reporting needed Must meet lowest detection limits possible for 8260 compounds																																																																																																					
MMW071WW	8-24-09	1150	✓		✓	✓			7	✓	✓	✓	✓	✓	✓	✓	8021 MTBE Confirmation Confirm MTBE + Naphthalene Confirm highest hit by 8260 Confirm all hits by 8260 Run ___ oxy's on highest hit Run ___ oxy's on all hits																																																																																																					
MMW026	8-28-09	1410	✓		✓	✓			7	✓	✓	✓	✓	✓	✓	✓	Comments / Remarks Lab Filter for Dissolved Metals																																																																																																					
All times are Central time 2009																																																																																																																						
Turnaround Time Requested (TAT) (please circle) STD. TAT 24 hour 72 hour 4 day 48 hour 5 day				Relinquished by: John S. D. Relinquished by: John S. D. Relinquished by: _____				Date 8/24/09 Date 8/24/09 Date _____				Time 1235 Time _____ Time _____																																																																																																										
Data Package Options (please circle if required) QC Summary Type VI (Raw Data) WIP (RWQCB) Type I - Full Disk / EDD Standard Format Other: _____				Relinquished by: FedEx Relinquished by: _____ Relinquished by: _____				Date _____ Date _____ Date _____				Time _____ Time _____ Time _____																																																																																																										
Temperature Upon Receipt 116.310 °C UPS Commercial Carrier: _____ Other: _____				Relinquished by: John S. D. Relinquished by: _____ Relinquished by: _____				Date _____ Date _____ Date _____				Time _____ Time _____ Time _____																																																																																																										

Lancaster Laboratories, Inc., 2425 New Holland Pike, PO Box 12425, Lancaster, PA 17605-2425 (717) 656-2300

Copies: White and yellow should accompany samples to Lancaster Laboratories. The pink copy should be retained by the client.

3566 Rev. 1/31/02

Lancaster Laboratories Explanation of Symbols and Abbreviations

The following defines common symbols and abbreviations used in reporting technical data:

N.D.	none detected	BMQL	Below Minimum Quantitation Level
TNTC	Too Numerous To Count	MPN	Most Probable Number
IU	International Units	CP Units	cobalt-chloroplatinate units
umhos/cm	micromhos/cm	NTU	nephelometric turbidity units
C	degrees Celsius	F	degrees Fahrenheit
Cal	(diet) calories	lb.	pound(s)
meq	milliequivalents	kg	kilogram(s)
g	gram(s)	mg	milligram(s)
ug	microgram(s)	l	liter(s)
ml	milliliter(s)	ul	microliter(s)
m3	cubic meter(s)	fib >5 um/ml	fibers greater than 5 microns in length per ml
<	less than – The number following the sign is the <u>limit of quantitation</u> , the smallest amount of analyte which can be reliably determined using this specific test.		
>	greater than		
ppm	parts per million – One ppm is equivalent to one milligram per kilogram (mg/kg), or one gram per million grams. For aqueous liquids, ppm is usually taken to be equivalent to milligrams per liter (mg/l), because one liter of water has a weight very close to a kilogram. For gases or vapors, one ppm is equivalent to one microliter of gas per liter of gas.		
ppb	parts per billion		
Dry weight basis	Results printed under this heading have been adjusted for moisture content. This increases the analyte weight concentration to approximate the value present in a similar sample without moisture.		

U.S. EPA data qualifiers:

Organic Qualifiers		Inorganic Qualifiers	
A	TIC is a possible aldol-condensation product	B	Value is <CRDL, but ≥IDL
B	Analyte was also detected in the blank	E	Estimated due to interference
C	Pesticide result confirmed by GC/MS	M	Duplicate injection precision not met
D	Compound quantitated on a diluted sample	N	Spike amount not within control limits
E	Concentration exceeds the calibration range of the instrument	S	Method of standard additions (MSA) used for calculation
J	Estimated value	U	Compound was not detected
N	Presumptive evidence of a compound (TICs only)	W	Post digestion spike out of control limits
P	Concentration difference between primary and confirmation columns >25%	*	Duplicate analysis not within control limits
U	Compound was not detected	+	Correlation coefficient for MSA <0.995
X,Y,Z	Defined in case narrative		

Analytical test results for methods listed on the laboratories' accreditation scope meet all requirements of NELAC unless otherwise noted under the individual analysis.

Tests results relate only to the sample tested. Clients should be aware that a critical step in a chemical or microbiological analysis is the collection of the sample. Unless the sample analyzed is truly representative of the bulk of material involved, the test results will be meaningless. If you have questions regarding the proper techniques of collecting samples, please contact us. We cannot be held responsible for sample integrity, however, unless sampling has been performed by a member of our staff. This report shall not be reproduced except in full, without the written approval of the laboratory.

WARRANTY AND LIMITS OF LIABILITY – In accepting analytical work, we warrant the accuracy of test results for the sample as submitted. THE FOREGOING EXPRESS WARRANTY IS EXCLUSIVE AND IS GIVEN IN LIEU OF ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED. WE DISCLAIM ANY OTHER WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING A WARRANTY OF FITNESS FOR PARTICULAR PURPOSE AND WARRANTY OF MERCHANTABILITY. IN NO EVENT SHALL LANCASTER LABORATORIES BE LIABLE FOR INDIRECT, SPECIAL, CONSEQUENTIAL, OR INCIDENTAL DAMAGES INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF PROFIT OR GOODWILL REGARDLESS OF (A) THE NEGLIGENCE (EITHER SOLE OR CONCURRENT) OF LANCASTER LABORATORIES AND (B) WHETHER LANCASTER LABORATORIES HAS BEEN INFORMED OF THE POSSIBILITY OF SUCH DAMAGES. We accept no legal responsibility for the purposes for which the client uses the test results. No purchase order or other order for work shall be accepted by Lancaster Laboratories which includes any conditions that vary from the Standard Terms and Conditions of Lancaster Laboratories and we hereby object to any conflicting terms contained in any acceptance or order submitted by client.

**APPENDIX C
2009 OPERATIONS AND MAINTENANCE FIELD
REPORTS**

**Eunice North Gas Plant
O&M Field Report**

Date	PSH LEVEL (ft.)	WATER LEVEL (ft.)	MW005			PSH LEVEL (ft.)	WATER LEVEL (ft.)	MW006			TRANSFER VOLUME TO SUMP?		COMMENTS
			PSH THICKNESS (ft.)	PSH VOLUME REMOVED (gal.)	WATER VOLUME REMOVED (gal.)			PSH THICKNESS (ft.)	PSH VOLUME REMOVED (gal.)	WATER VOLUME REMOVED (gal.)	YES	NO	
8/14/2008	~	45.16	~	~	~	45.60	45.60	Trace	~	~		x	JP
8/19/2008	~	45.19	~	~	~	45.64	45.64	Trace	~	~		x	JP
8/26/2008	~	45.25	~	~	~	45.67	45.67	Trace	~	~		x	JP/BB
9/2/2008	~	45.20	~	~	~	45.64	45.64	Trace	~	~		x	JP
9/10/2008	~	45.27	~	~	~	45.69	45.69	Trace	~	~		x	JP/NH
9/17/2008	~	45.26	~	~	~	45.71	45.71	Trace	~	~		x	JP
9/30/2008	~	45.29	~	~	~	45.75	45.75	Trace	~	~		x	JP
10/7/2008	~	45.27	~	~	~	45.68	45.68	Trace	~	~		x	JP
10/21/2008	~	45.29	~	~	~	45.67	45.67	Trace	~	~		x	JP
11/4/2008	~	45.24	~	~	~	~	45.65	~	~	~		x	JP
11/13/2008	~	45.26	~	~	~	~	45.68	~	~	~		x	JP
11/18/2008	~	45.28	~	~	~	~	45.66	~	~	~		x	JP
11/25/2008	~	45.29	~	~	~	~	45.71	~	~	~		x	JP/AV
12/2/2008	~	45.29	~	~	~	~	45.68	~	~	~		x	JP
12/11/2008	~	45.32	~	~	~	~	45.67	~	~	~		x	JP
12/17/2008	~	45.34	~	~	~	~	45.76	~	~	~		x	JP/AV
12/23/2008	~	45.36	~	~	~	~	45.73	~	~	~		x	JP
12/30/2008	~	45.35	~	~	~	~	45.73	~	~	~		x	JP
1/5/2009	~	45.42	~	~	~	~	45.75	~	~	~		x	JP
1/13/2009	~	45.38	~	~	~	~	45.72	~	~	~		x	JP
1/19/2009	~	45.38	~	~	~	~	45.79	~	~	~		x	JP/DM
1/28/2009	~	45.40	~	~	~	~	45.77	~	~	~		x	JP
2/10/2009	~	45.32	~	~	~	~	45.70	~	~	~			JP
2/17/2009	~	45.37	~	~	~	~	45.72	~	~	~			JP
2/24/2009	~	45.43	~	~	~	~	45.68	~	~	~			JP
3/3/2009	~	45.38	~	~	~	~	45.79	~	~	~			JP/DM
3/23/2009	~	45.47	~	~	~	~	45.75	~	~	~			JP/DM
4/21/2009	~	45.46	~	~	~	~	45.87	~	~	~			JP
5/22/2009	~	45.43	~	~	~	~	45.81	~	~	~			JP
7/14/2009	~	45.55	~	~	~	~	45.97	~	~	~			JP
8/24/2009	~	45.75	~	~	~	~	45.84	~	~	~			SB
10/6/2009	~	45.49	~	~	~	~	45.89	~	~	~			SB
11/3/2009	~	45.44	~	~	~	~	45.87	~	~	~			JB

****PSH should be removed whenever a PSH thickness of 0.1 feet or greater is observed.****

Volume Removed is amount of water/product bailed from each well. Bail into a bucket to estimate volume, then transfer to sump.
Transfer Cumulative Volume to Sump? should be marked "Yes" when product is transferred to the sump.