

3R - 422

**ANNUAL
MONITORING
REPORT**

05/04/2009

3R422

RECEIVED

BP AMERICA PRODUCTION CO.

2009 MAY 4 AM 9 44

GROUNDWATER REMEDIATION REPORT

**GCU #170
(K) SECTION 35, T29N, R12W, NMPM
SAN JUAN COUNTY, NEW MEXICO**

**PREPARED FOR:
NEW MEXICO OIL CONSERVATION DIVISION
1220 ST. FRANCIS DRIVE
SANTA FE, NEW MEXICO 87504**

APRIL 2009

**PREPARED BY:
BLAGG ENGINEERING, INC.
Consulting Petroleum / Reclamation Services
P.O. Box 87
Bloomfield, New Mexico 87413**

BP AMERICA PRODUCTION COMPANY
GCU # 170
NE/4 SW/4, Sec. 35, T29N, R12W

Monitor Well Sampling Dates: 6/24/08, 8/27/08

Site Historic Summary:

A site separator pit closure was initiated in March 1995 by removing impacted soil via excavation. Documentation for this work and subsequent groundwater monitoring data for the site have previously been submitted for New Mexico Oil Conservation Division (**NMOCD**) review. The reporting herein is for site monitoring conducted in 2008.

Groundwater Monitor Well Sampling Procedures:

Prior to sample collections, MW #3R was purged approximately three (3) well bore volumes with new disposable bailers. The groundwater samples were collected following US EPA: SW-846 protocol, were placed into laboratory supplied containers with appropriate preservative, and stored in an ice chest for express delivery to an analytical laboratory for testing under strict chain-of-custody procedures. Analytical testing for benzene, toluene, ethylbenzene, and total xylenes (**BTEX**) by US EPA Method 8021B was conducted.

Fluids generated during monitor well development and purging was managed by discarding into the separator below-grade tank (BGT) located on the well site. The BGT contents are then disposed through approved NMOCD operational procedures for removal of produced fluids.

Groundwater Quality & Flow Direction Information:

Sampling of the groundwater monitor well MW #3R was conducted in June & August 2008. A historical summary of laboratory analytical results is included within the tables on the following pages and field/laboratory reports are included.

Groundwater has consistently been measured with a gradient towards the northwest direction (Figures 2 and 3).

Summary and/or Recommendations:

Continued site monitoring per BP's NMOCD approved Ground Water Management Plan is recommended. Hydrocarbon impacts appear to be in a steady state condition. No additional remedial actions are indicated or suggested at this time. Further delineation of down-gradient impacts is indicated with one (1) or more additional monitor wells proposed to address this issue.

BP AMERICA GROUNDWATER MONITOR WELL LABORATORY RESULTS
 SUBMITTED BY BLAGG ENGINEERING, INC.

GCU # 170 - SEPARATOR PIT
UNIT K, SEC. 35, T29N, R12W


REVISED DATE: September 12, 2008

FILENAME: (17-3Q-08.WK4) NJV

SAMPLE DATE	MONITOR WELL #	D.T.W. (ft)	T.D. (ft)	TDS mg/L	COND. (umhos/cm)	pH	PRODUCT (ft)	BTEX EPA METHOD 8021B (ppb)			
								Benzene	Toluene	Ethyl Benzene	Total Xylene
28-Jun-95	MW #1	10.50	15.00		1,400	7.4		0.2	0.2	0.3	0.9
08-Sep-95		9.56			1,400	7.8		206	82.3	4.9	67.0
07-Dec-95		9.91			1,700	6.8		ND	0.37	ND	ND
08-Mar-96		10.93			1,200	6.6		ND	0.97	ND	ND
04-Jun-96		10.74			1,300	6.7		ND	ND	ND	ND
28-Jun-95	WP #2	10.45	15.00		1,600	7.4		1.9	38.3	0.2	0.8
08-Sep-95		9.35			1,300	7.4		47.1	19.8	1.2	17.6
07-Dec-95		9.45			1,600	7.2		ND	ND	ND	ND
08-Mar-96		10.24			1,700	7.0		ND	ND	ND	ND
04-Jun-96		10.00			2,100	6.9		ND	ND	ND	ND
28-Jun-95	MW #3	10.45	15.00		1,500	7.4		2115.7	4485.8	318	2704.4
08-Sep-95		9.60			1,700	7.8		1,200	815	131	661
07-Dec-95		9.80			1,800	7.0		4,830	7,680	294	2,760
08-Mar-96		10.74			1,500	6.6		5,020	6,410	105	2,603
04-Jun-96		10.57			1,600	6.6		5,140	5,560	116	2,631
24-Jun-97		10.72			1,700	6.9		1,115	542	88.2	850
08-Jun-98		10.69			1,600	7.3		921	1,020	16.1	279.4
28-May-99		10.29			1,700	7.0		69.3	78.1	3	88.7
24-May-00		10.70			1,700	7.1		1,100	770	19	410
26-Jun-01	MW #3R	10.45	19.50		2,200	7.21		160	540	76	590
31-May-02		10.45			2,600	7.18		32	17	2.3	29.6
29-May-03		10.34			1,800	6.95		75	30	4.8	38
24-Jun-04		10.30			2,300	6.92		71	26	6.4	36
27-Jun-05		10.15			2,000	7.00		80	47	6.6	53
29-Jun-06		9.91			1,900	6.92		130	39	8.3	150
25-Jun-07		9.71			2,000	6.76		270	170	27	310
09-Jun-08		9.82			1,100	7.01		142	104	12.2	114
27-Aug-08		9.39			1,800	7.06		200	150	24	190
26-Jun-01	MW #4	11.14	18.50		800	7.41		ND	ND	ND	ND
NMWQCC GROUNDWATER STANDARDS								10	750	750	620

- NOTES :
- 1) RESULTS IN BOLD RED TYPE INDICATE EXCEEDING NMWQCC STANDARDS .
 - 2) RESULTS IN BOLD BLUE TYPE INDICATE BELOW NMWQCC STANDARDS AFTER PREVIOUS RESULTS IN BOLD RED TYPE EXCEEDED .
 - 3) ND INDICATES NOT DETECTED AT THE REPORTING LIMITS (less than regulatory standards of at least a magnitude of 10) .

FIGURE 1



1 INCH = 25 FT.



MONITOR WELL LOCATIONS ARE ONLY AS ACCURATE AS THE INSTRUMENTS USED IN OBTAINING THE FOOTAGE AND BEARING FROM THE WELL HEAD (BRUNTON COMPASS AND LASER RANGE FINDER). ALL OTHER STRUCTURES DISPLAYED ON THE SITE MAP ARE SOLELY FOR REFERENCE AND MAY NOT BE TO SCALE.



BP AMERICA PRODUCTION COMPANY
GCU 170
NE/4 SW/4 SEC. 35, T29N, R12W
SAN JUAN COUNTY, NEW MEXICO

BLAGG ENGINEERING, INC.
CONSULTING PETROLEUM / RECLAMATION SERVICES
P.O. BOX 87
BLOOMFIELD, NEW MEXICO 87413
PHONE: (505) 632-1199

PROJECT: MW SAMPLING
DRAWN BY: NJV
FILENAME: GCU170-SM-06-06.SKF
REVISED: 06/29/06 NJV

**SITE
MAP**
06/06

FIGURE 2 (2nd 1/4, 2008)



MONITOR WELL LOCATIONS ARE ONLY AS ACCURATE AS THE INSTRUMENTS USED IN OBTAINING THE FOOTAGE AND BEARING FROM THE WELL HEAD (BRUNTON COMPASS AND LASER RANGE FINDER). ALL OTHER STRUCTURES DISPLAYED ON THE SITE MAP ARE SOLELY FOR REFERENCE AND MAY NOT BE TO SCALE.

	Top of Well Elevation
WP #2	(100.80)
MW #3R	(99.59)
MW #4	(101.14)
MW #4 (90.40)	Groundwater Elevation as of 6/9/08.

BP AMERICA PRODUCTION COMPANY
 GCU # 170
 NE/4 SW/4 SEC. 35, T29N, R12W
 SAN JUAN COUNTY, NEW MEXICO

BLAGG ENGINEERING, INC.
 CONSULTING PETROLEUM / RECLAMATION SERVICES
 P.O. BOX 87
 BLOOMFIELD, NEW MEXICO 87413
 PHONE: (505) 632-1199

PROJECT: MW SAMPLING
 DRAWN BY: NJV
 FILENAME: 06-09-08-GW.SKF
 REVISED: 06/20/08 NJV

**GROUNDWATER
 CONTOUR
 MAP
 06/08**

FIGURE 3 (3rd 1/4, 2008)



APPROXIMATE LOCATION
OF BLOW PIT TRENCH

APPARENT
GROUNDWATER
FLOW DIRECTION
~N16.75W

MW #3R
(90.20)

WELL HEAD 90.60

90.90

91.20

91.50

ORIGINAL
PIT
EXCAVATION

MW #4
(91.09)

PROD
TANK

FENCE

S
E
P

FENCE

TANK
PIT

WP #2
(91.84)

FENCE

WP #1

1 INCH = 25 FT.

0 25 50 FT.

MONITOR WELL LOCATIONS ARE ONLY AS ACCURATE AS THE INSTRUMENTS USED IN OBTAINING THE FOOTAGE AND BEARING FROM THE WELL HEAD (BRUNTON COMPASS AND LASER RANGE FINDER). ALL OTHER STRUCTURES DISPLAYED ON THE SITE MAP ARE SOLELY FOR REFERENCE AND MAY NOT BE TO SCALE.

	Top of Well Elevation
WP #2	(100.80)
MW #3R	(99.59)
MW #4	(101.14)
MW #4 (91.09)	Groundwater Elevation as of 8/27/08.

BP AMERICA PRODUCTION COMPANY

GCU # 170

NE/4 SW/4 SEC. 35, T29N, R12W

SAN JUAN COUNTY, NEW MEXICO

BLAGG ENGINEERING, INC.

CONSULTING PETROLEUM / RECLAMATION SERVICES

P.O. BOX 87

BLOOMFIELD, NEW MEXICO 87413

PHONE: (505) 632-1199

PROJECT: MW SAMPLING

DRAWN BY: NJV

FILENAME: 08-27-08-GW.SKF

REVISED: 08/27/08 NJV

**GROUNDWATER
CONTOUR
MAP
06/08**

BLAGG ENGINEERING, INC.

MONITOR WELL DEVELOPMENT & / OR SAMPLING DATA

CLIENT : **BP AMERICA PROD. CO.**

CHAIN-OF-CUSTODY # : N / A

GCU # 170 - SEPARATOR PIT
UNIT K, SEC. 35, T29N, R12W

LABORATORY (S) USED : PACE ANALYTICAL

Date : June 9, 2008

SAMPLER : N J V

Filename : 06-09-08.WK4

PROJECT MANAGER : N J V

WELL #	WELL ELEV. (ft)	WATER ELEV. (ft)	DEPTH TO WATER (ft)	TOTAL DEPTH (ft)	SAMPLING TIME	pH	CONDUCT (umhos)	TEMP. (celcius)	VOLUME PURGED (gal.)
WP-2	100.80	91.32	9.48	15.00	-	-	-	-	-
MW-3R	99.59	89.77	9.82	19.50	14.25	7.01	1,100	22.2	4.75
MW-4	101.14	90.40	10.74	18.50	-	-	-	-	-

INSTRUMENT CALIBRATIONS =	4.01/7.00/10.00	2,800
DATE & TIME =	06/09/08	0700

NOTES : Volume of water purged from well prior to sampling: $V = \pi \times r^2 \times h \times 7.48 \text{ gal./ft}^3 \times 3 \text{ (wellbores)}$.
(i.e. 2" MW r = (1/12) ft. h = 1 ft.) (i.e. 4" MW r = (2/12) ft. h = 1 ft.)

Ideally a minimum of three (3) wellbore volumes:

2.00 " well diameter = 0.49 gallons per foot of water.

Comments or note well diameter if not standard 2".

Excellent recovery in MW # 3R . Collected sample from MW # 3R for BTEX analysis only .

on-site	1:52	temp	79 F
off-site	2:37	temp	80 F
sky cond.	Sunny		
wind speed	0-10	direct.	North

ANALYTICAL RESULTS

Project: GCU 170
Pace Project No.: 6041666

Sample: MW #3R		Lab ID: 6041666001	Collected: 06/09/08 14:25	Received: 06/11/08 09:10	Matrix: Water			
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8260 MSV UST, Water		Analytical Method: EPA 8260						
Benzene	142 ug/L		5.0	5		06/14/08 03:48	71-43-2	
Ethylbenzene	12.2 ug/L		5.0	5		06/14/08 03:48	100-41-4	
Toluene	104 ug/L		5.0	5		06/14/08 03:48	108-88-3	
Xylene (Total)	114 ug/L		15.0	5		06/14/08 03:48	1330-20-7	
Dibromofluoromethane (S)	95 %		85-114	5		06/14/08 03:48	1868-53-7	
Toluene-d8 (S)	100 %		82-114	5		06/14/08 03:48	2037-26-5	
4-Bromofluorobenzene (S)	110 %		85-119	5		06/14/08 03:48	460-00-4	
1,2-Dichloroethane-d4 (S)	97 %		81-118	5		06/14/08 03:48	17060-07-0	
Preservation pH	1.0		1.0	5		06/14/08 03:48		

Atlantic Richfield Company

A BP affiliated company

Chain of Custody Record

Project Name: GCU 170
 BP BU/AR Region/Enfos Segment: SJOC SOUTH
 State or Lead Regulatory Agency: NMOC
 Requested Due Date (mm/dd/yy): 6/20/08

On-site Time: 1:52 Temp: 79°F
 Off-site Time: 2:37 Temp: 80°F
 Sky Conditions: SUNNY
 Meteorological Events:
 Wind Speed: 0-10 Direction: NORTH

Lab Name: Pace Analytical Services, Inc.		BP/AR Facility No.:		Consultant/Contractor: Blagg/URS															
Address: 9609 Loiret Blvd		BP/AR Facility Address:		Address: 110 N. Forth St.															
Lenexa, KS 66219		Site Lat/Long:		Bloomfield, NM 87413															
Lab PM: MJ Walls		California Global ID No.:		Consultant/Contractor Project No.:															
Tele/Fax: 913-563-1401		Enfos Project No.: 0018P-0001		Consultant/Contractor PM: Nelson Velez															
BP/AR EMB: Mike Whelan		Provision or OOC (circle one)		Tele: (505) 632-1199 Fax: (505) 632-3903															
Address: 501 Westlake Park Blvd.		Phase/WBS:		Report Type & QC Level: STD															
Rm28, 144B Houston, TX 77079		Sub Phase/Task:		E-Mail EDD To: blagg-njv@yahoo.com															
Tele: (281) 366-7485 Fax: (281) 366-7094		Cost Element:		Invoice to: Consultant or BP of Atlantic Richfield Co. (circle one)															
Lab Bottle Order No: <u>050508-3</u>		Matrix		Requested Analysis															
Item No.	Sample Description	Time	Date	Soil/Solid	Water/Liquid	Air	No. of Containers	Unpreserved	H ₂ SO ₄	HNO ₃	HCl	Methanol	BTEX (8260)	Date	Time	Accepted By / Affiliation	Date	Time	
1	MW # 3R	11425	6/19/08	✓	✓		3							6/11	910				
2																			
3																			
4																			
5																			
6																			
7																			
8																			
9																			
10																			
Sampler's Name: NELSON VELEZ		Relinquished By / Affiliation		Date		Time		Accepted By / Affiliation		Date		Time		Accepted By / Affiliation		Date		Time	
Sampler's Company: BLAGG ENG'G, INC.		Nelson Velez		6/10/08		1540													
Shipment Date: JUNE 10, 2008																			
Shipment Method: FED. EX.																			
Shipment Tracking No: 499434868Z																			
Special Instructions: REPORT BTEX CONSTITUENTS ONLY.																			
Custody Seals In Place: <input checked="" type="checkbox"/> Yes / No		Temp Blank: <input checked="" type="checkbox"/> Yes / No		Cooler Temp on Receipt: <u>5.2°F</u>		Trip Blank: <input checked="" type="checkbox"/> Yes / No		MS/MSD Sample Submitted: Yes <input checked="" type="checkbox"/> No											

SAMPLE ANALYTE COUNT

Project: GCU 170
Pace Project No.: 6041666

Lab ID	Sample ID	Method	Analysts	Analytes Reported
6041666001	MW #3R	EPA 8260	JTK	9

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..



PROJECT NARRATIVE

Project: GCU 170
Pace Project No.: 6041666

Method: EPA 8260
Description: 8260 MSV UST, Water
Client: BP-Blagg Engineering
Date: June 23, 2008

General Information:

1 sample was analyzed for EPA 8260. All samples were received in acceptable condition with any exceptions noted below.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Internal Standards:

All internal standards were within QC limits with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

QC Batch: MSV/15178

A matrix spike/matrix spike duplicate was not performed due to insufficient sample volume.

Duplicate Sample:

All duplicate sample results were within method acceptance criteria with any exceptions noted below.

Additional Comments:

This data package has been reviewed for quality and completeness and is approved for release.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..

QUALITY CONTROL DATA

Project: GCU 170
Pace Project No.: 6041666

QC Batch: MSV/15178 Analysis Method: EPA 8260
QC Batch Method: EPA 8260 Analysis Description: 8260 MSV UST-WATER
Associated Lab Samples: 6041666001

METHOD BLANK: 340016
Associated Lab Samples: 6041666001

Parameter	Units	Blank Result	Reporting Limit	Qualifiers
Benzene	ug/L	ND	1.0	
Ethylbenzene	ug/L	ND	1.0	
Toluene	ug/L	ND	1.0	
Xylene (Total)	ug/L	ND	3.0	
1,2-Dichloroethane-d4 (S)	%	98	81-118	
4-Bromofluorobenzene (S)	%	108	85-119	
Dibromofluoromethane (S)	%	94	85-114	
Toluene-d8 (S)	%	100	82-114	

LABORATORY CONTROL SAMPLE: 340017

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Benzene	ug/L	10	11.3	113	87-117	
Ethylbenzene	ug/L	10	11.0	110	84-123	
Toluene	ug/L	10	10.8	108	81-124	
Xylene (Total)	ug/L	30	33.6	112	83-125	
1,2-Dichloroethane-d4 (S)	%			94	81-118	
4-Bromofluorobenzene (S)	%			105	85-119	
Dibromofluoromethane (S)	%			96	85-114	
Toluene-d8 (S)	%			100	82-114	

QUALIFIERS

Project: GCU 170
Pace Project No.: 6041666

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to changes in sample preparation, dilution of the sample aliquot, or moisture content.

ND - Not Detected at or above adjusted reporting limit.

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

S - Surrogate

1,2-Diphenylhydrazine (8270 listed analyte) decomposes to Azobenzene.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

Pace Analytical is NELAP accredited. Contact your Pace PM for the current list of accredited analytes.

BATCH QUALIFIERS

Batch: MSV/15178

[1] A matrix spike/matrix spike duplicate was not performed for this batch due to insufficient sample volume.

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: GCU 170
Pace Project No.: 6041666

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
6041666001	MW #3R	EPA 8260	MSV/15178		

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..





Sample Condition Upon Receipt

Client Name: BE BLAGE

Project # C0241664

Courier: Fed Ex UPS USPS Client Commercial Pace Other _____

Tracking #: 8643 6005 2346

Custody Seal on Cooler/Box Present: yes no Seals intact: yes no

Packing Material: Bubble Wrap Bubble Bags None Other _____

Thermometer Used T-169 / ~~FA79~~

Type of Ice: Wet Blue None

Samples on ice, cooling process has begun

Cooler Temperature 5.2

Biological Tissue is Frozen: Yes No

Date and Initials of person examining contents: BEW 6/11
S: 1010 E: 1015

Temp should be above freezing to 6°C

Comments:

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	2.
Chain of Custody Relinquished:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	3.
Sampler Name & Signature on COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	5.
Short Hold Time Analysis (<72hr):	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	6.
Rush Turn Around Time Requested:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	7.
Sufficient Volume:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	8.
Correct Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	9.
-Pace Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	10.
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	11.
Sample Labels match COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes date/time/ID/Analysis Matrix: <u>WT</u>		
All containers needing preservation have been checked.	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
All containers needing preservation are found to be in compliance with EPA recommendation.	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
exceptions: <u>VOA</u> , coliform, TOC, O&G, WI-DRO (water)	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Initial when completed
		Lot # of added preservative
Samples checked for dechlorination:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	14.
Headspace in VOA Vials (>6mm):	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	15.
Trip Blank Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	16.
Trip Blank Custody Seals Present	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased): <u>051208</u>		

Client Notification/ Resolution:

Field Data Required? Y / N

Person Contacted: _____ Date/Time: _____

Comments/ Resolution: _____

Project Manager Review: mw 6/12/08

Date: _____

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEHNR Certification Office (i.e out of hold, incorrect preservative, out of temp, incorrect containers)

BLAGG ENGINEERING, INC.

MONITOR WELL DEVELOPMENT & / OR SAMPLING DATA

CLIENT: **BP AMERICA PROD. CO.**

CHAIN-OF-CUSTODY #: N / A

**GCU # 170 - SEPARATOR PIT
UNIT K, SEC. 35, T29N, R12W**

LABORATORY (S) USED: HALL ENVIRONMENTAL

Date: August 27, 2008

SAMPLER: N J V

Filename: 08-27-08.WK4

PROJECT MANAGER: N J V

WELL #	WELL ELEV. (ft)	WATER ELEV. (ft)	DEPTH TO WATER (ft)	TOTAL DEPTH (ft)	SAMPLING TIME	pH	CONDUCT (umhos)	TEMP. (celcius)	VOLUME PURGED (gal.)
WP-2	100.80	91.84	8.96	15.00	-	-	-	-	-
MW-3R	99.59	90.20	9.39	19.50	1145	7.06	1,800	21.8	5.00
MW-4	101.14	91.09	10.05	18.50	-	-	-	-	-

INSTRUMENT CALIBRATIONS =	4.01/7.00/10.00	2,800
DATE & TIME =	08/25/08	0730

NOTES: Volume of water purged from well prior to sampling: $V = \pi \times r^2 \times h \times 7.48 \text{ gal./ft}^3 \times 3 \text{ (wellbores)}$.
 (i.e. 2" MW $r = (1/12) \text{ ft}$. $h = 1 \text{ ft}$.) (i.e. 4" MW $r = (2/12) \text{ ft}$. $h = 1 \text{ ft}$.)

Ideally a minimum of three (3) wellbore volumes:

2.00 " well diameter = 0.49 gallons per foot of water.

Comments or note well diameter if not standard 2".

Excellent recovery in MW # 3R. Collected sample from MW # 3R for BTEX analysis only.

on-site	10:55	temp	82 F
off-site	12:00	temp	83 F
sky cond.	Mostly sunny		
wind speed	0-5	direct.	Southwest

Hall Environmental Analysis Laboratory, Inc.

Date: 09-Sep-08

CLIENT: Blagg Engineering
 Lab Order: 0808452
 Project: GCU #170
 Lab ID: 0808452-01

Client Sample ID: MW #3R
 Collection Date: 8/27/2008 11:45:00 AM
 Date Received: 8/28/2008
 Matrix: AQUEOUS

Analyses	Result	PQL	Qual	Units	DF	Date Analyzed
EPA METHOD 8021B: VOLATILES						Analyst: DAM
Benzene	200	2.0		µg/L	2	9/8/2008 2:29:21 PM
Toluene	150	2.0		µg/L	2	9/8/2008 2:29:21 PM
Ethylbenzene	24	1.0		µg/L	1	9/6/2008 1:41:15 PM
Xylenes, Total	190	2.0		µg/L	1	9/6/2008 1:41:15 PM
Surr: 4-Bromofluorobenzene	103	65.9-130		%REC	1	9/6/2008 1:41:15 PM

Qualifiers: * Value exceeds Maximum Contaminant Level
 E Value above quantitation range
 J Analyte detected below quantitation limits
 ND Not Detected at the Reporting Limit
 S Spike recovery outside accepted recovery limits

B Analyte detected in the associated Method Blank
 H Holding times for preparation or analysis exceeded
 MCL Maximum Contaminant Level
 RL Reporting Limit

QA/QC SUMMARY REPORT

Client: Blagg Engineering
 Project: GCU #170

Work Order: 0808452

Analyte	Result	Units	PQL	%Rec	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Method: EPA Method 8021B: Volatiles									
Sample ID: 5ML RB		<i>MBLK</i>			Batch ID: R30092	Analysis Date: 9/5/2008 9:01:25 AM			
Benzene	ND	µg/L	1.0						
Toluene	ND	µg/L	1.0						
Ethylbenzene	ND	µg/L	1.0						
Xylenes, Total	ND	µg/L	2.0						
Sample ID: B		<i>MBLK</i>			Batch ID: R30121	Analysis Date: 9/8/2008 11:06:35 AM			
Benzene	ND	µg/L	1.0						
Toluene	ND	µg/L	1.0						
Ethylbenzene	ND	µg/L	1.0						
Xylenes, Total	ND	µg/L	2.0						
Sample ID: 100NG BTEX LCS		<i>LCS</i>			Batch ID: R30092	Analysis Date: 9/6/2008 5:56:41 PM			
Benzene	17.37	µg/L	1.0	86.9	85.9	113			
Toluene	16.25	µg/L	1.0	81.2	86.4	113			S
Ethylbenzene	17.54	µg/L	1.0	87.7	83.5	118			
Xylenes, Total	52.19	µg/L	2.0	87.0	83.4	122			
Sample ID: 100NG BTEX LCSD		<i>LCSD</i>			Batch ID: R30092	Analysis Date: 9/6/2008 6:27:14 PM			
Benzene	17.39	µg/L	1.0	87.0	85.9	113	0.115	27	
Toluene	16.48	µg/L	1.0	82.4	86.4	113	1.39	19	S
Ethylbenzene	17.67	µg/L	1.0	88.4	83.5	118	0.738	10	
Xylenes, Total	52.43	µg/L	2.0	87.4	83.4	122	0.455	13	

Qualifiers:

- E Value above quantitation range
- J Analyte detected below quantitation limits
- R RPD outside accepted recovery limits
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- S Spike recovery outside accepted recovery limits

Hall Environmental Analysis Laboratory, Inc.

Sample Receipt Checklist

Client Name **BLAGG**


Date Received:

8/28/2008

Work Order Number **0808452**

Received by: **AT**

Checklist completed by: _____
Signature



8/28/08
Date

Sample ID labels checked by:

as
Initials

Matrix:

Carrier name UPS

- Shipping container/cooler in good condition? Yes No Not Present
- Custody seals intact on shipping container/cooler? Yes No Not Present Not Shipped
- Custody seals intact on sample bottles? Yes No N/A
- Chain of custody present? Yes No
- Chain of custody signed when relinquished and received? Yes No
- Chain of custody agrees with sample labels? Yes No
- Samples in proper container/bottle? Yes No
- Sample containers intact? Yes No
- Sufficient sample volume for indicated test? Yes No
- All samples received within holding time? Yes No
- Water - VOA vials have zero headspace? No VOA vials submitted Yes No
- Water - Preservation labels on bottle and cap match? Yes No N/A
- Water - pH acceptable upon receipt? Yes No N/A

Container/Temp Blank temperature?

1°

<6° C Acceptable
If given sufficient time to cool.

COMMENTS:

Client contacted _____ Date contacted: _____ Person contacted _____

Contacted by: _____ Regarding: _____

Comments: _____

Corrective Action _____