

WEST BRAVO DOME CDU #16
1980' FNL & 1980' FNL SEC 21 T18N R29E

ELEVATION: KB: 5445'
GL: 5435'


8 5/8" SURFACE CASING @ 824'
CMTD W/ 800 SX CMT. CIRC.

1 - 2 3/8" BAKER ON/OFF TOOL	1.25
1 - 2 3/8" X 5 1/2 BAKER LOK SET	3.70
87 - JTS 2 3/8" 4.7# J55 TBG	2800.11
TOTAL	2805.06
KB	10.00
SET AT	2815.06

	SURFACE	PRODUCTION	LINER
SIZE	8 5/8"	5 1/2"	4"
WEIGHT	24 #	14 #	10.48#
GRADE	K-55	K-55	J-55
THREAD	ST&C	ST&C	FL&S
DEPTH	800'	2975'	3211'

TUBING	
SIZE	2 3/8"
WEIGHT	4.7 #
GRADE	J-55
THREAD	8rd EU
DEPTH	2815'

PREPRD BY: JOE M. FLEMING
DATE : MAY 15, 1991



5 1/2" PACKER @ 2815'

5 1/2" CSG @ 2975' CMTD W/ 1150 SX
CMT CIRC

TUBG PERFS (2927' - 2994')

PBTD @ 3170'
4" LINER @ 3211' CMTD W/ 35 SX
TD @ 3212' CMT CIRC

Submit 3 Copies
to Appropriate
District Office
District I
P.O. Box 1980, Hobbs, NM 88240
District II
P.O. Drawer DD, Artesia, NM 88210
District III
1000 Rio Brazos Rd. Aztec, NM 87410

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-103
Revised 1-1-89

OIL CONSERVATION DIVISION
P.O. Box 2088
Santa Fe, New Mexico 87504-2088

WELL API NO.	30 - 021 - 20142
5. Indicate Type of Lease	STATE ☐ FEE ☒
6. State Oil & Gas Lease No.	
7. Lease Name or Unit agreement Name	WEST BRAVO DOME CDG UNIT
8. Well No.	16
9. Pool name or Wildcat	WEST BRAVO DOME

SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)	
1. Type of Well: OIL WELL ☐ GAS WELL ☐ OTHER CO2 SUPPLY	
2. Name of Operator OXY USA INC.	
3. Address of Operator P.O. Box 50250 Midland, TX 79710	
4. Well Location Unit Letter <u>F</u> : <u>1,980</u> Feet From The <u>NORTH</u> Line and <u>1,980</u> Feet From The <u>WEST</u> Line Section <u>21</u> Township <u>18 N</u> Range <u>29 E</u> NMPM <u>HARDING</u> County	
10. Elevation (Show whether DF, RKB, RT, GR, etc.) 5,435	

11. Check Appropriate Box to Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:	SUBSEQUENT REPORT OF:
PERFORM REMEDIAL WORK ☐	REMEDIAL WORK ☐
TEMPORARILY ABANDON ☐	ALTERING CASING ☐
PULL OR ALTER CASING ☐	COMMENCE DRILLING OPNS. ☐
OTHER: ☐	PLUG AND ABANDONMENT ☐
	CASING TEST AND CEMENT JOB ☐
	OTHER: YEARLY BRADENHEAD TEST (SI) ☒

12. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work) SEE RULE 1103.

TD - 3212' PBTD - 3170'	YEAR	DATE	TBG PSI	CSG PSI	BD TIME
PERFS - 2927' - 2994'	1990	11/28	460	0	
	1991	10/30	550	0	
	1992	9/22	390	0	
	1993	9/22	440	0	
	1994				
	1995				
	1996				
	1997				
	1998				
	1999				
	2000				

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE David Stewart TITLE REGULATORY ANALYST DATE 10 04 93
TYPE OR PRINT NAME DAVID STEWART TELEPHONE NO. 915 685-5717

(This space for State Use)

APPROVED BY [Signature] TITLE DISTRICT SUPERVISOR DATE 10-7-93
CONDITIONS OF APPROVAL, IF ANY: