

GW - 249

**GENERAL
CORRESPONDENCE**

YEAR(S):
2006 - 1996

RECEIVED

2007 NOV 13 AM 11 55



Environmental Department
188 County Road 4900
Bloomfield, NM 87413
505/632-4625
505/632-4781 Fax

November 7, 2007

Mr. Leonard Lowe
Oil Conservation Division, EMNRD
1220 South St. Francis Drive
Santa Fe, New Mexico 87505

RE: Update to Williams Four Corners, LLC OCD Discharge Plans

Dear Mr. Lowe,

Williams Four Corners, LLC (Williams) would like to update the "Description of Final Disposition" for wastes generated at its facilities, and to include clarification of sources of waste streams not previously specified in its existing OCD Discharge Plans. These items are discussed in Table 1, "Storage and Disposal of Process Fluids, Effluent and Waste Solids", and Table 2, "Source, Quantity, and Quality of Effluent and Waste Solids", in each of Williams' current facility-specific OCD Discharge Plans. (Note that in older plans, these table numbers are reversed).

More specifically, the updates to Table 1 include replacing language that stated waste would be disposed at a "NMOCD-approved" or simply "approved" disposal facility with text that states waste will be disposed at "any state, federal, or tribal agency to receive industrial solid waste. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such hazardous waste." Recently, Williams has had some difficulty using NMED-approved disposal sites due to the current language.

Updates to Table 2 include expanding the "Source" of "Used Process Filters" to include amine filters, charcoal, activated carbon, and molecular sieve in addition to the air, inlet, fuel, fuel gas and glycol filters typically included in the Discharge Plans. Additionally, the "Source" of "Condensate and/or Produced Water" has been expanded to include the inlet scrubber, gas inlet separator, and dehydrators. These changes are included for clarification purposes only and provide a more descriptive list of waste that may be generated at the facilities. All of the items listed are related to existing processes at the facilities.


Please see the attached Table 1 and Table 2, from the recent OCD Discharge Plan renewal application for Williams' Rosa Compressor Station, for an example of how the updates apply at a typical Williams' facility. The updated information is indicated by bold text. We will update this information in each OCD Discharge Plan as it comes up for renewal. In the meantime, we request that the updates described herein are effective immediately for the sites listed below upon your receipt of this letter.

Five Points (GW-078)
29-6#2 (GW-121)
29-6#3 (GW-198)
29-6#4 (GS-122)
30-5 (GW-108)
31-6 (GW-118)
32-7 (GW-117)
32-8#2 (GW-111)
32-8#3 (GW-116)
32-9 (GW-091)
Aztec (GW-155)
Blanco (GW-327)
Cabresto (GW-352)
Carracas (GW-112)
Cedar Hill (GW-087)
Chaco (GW-331)
Coyote (GW-250)
Crouch Mesa (GW-129)
Culpepper (GW-353)
Decker Junction (GW-134)
Dogie (GW-330)
El Cedro (GW-149)
Glade (GW-321)
Hare (GW-343)
Honolulu (GW-315)
Horse Canyon (GW-061)
Horton (GW-323)
Kernaghan (GW-271)

La Cosa (GW-187)
Laguna Seca (GW-307)
La Jara (GW-223)
Lateral N-30 (GW-256)
Lawson Straddle (GW-322)
Lybrook (GW-047)
Manzanares (GW-062)
Martinez (GW-308)
Middle Mesa (GW-064)
Milagro (GW-060)
Navajo (GW-182)
North Crandell (GW-310)
Pipkin (GW-120)
Pritchard (GW-274)
Pump Mesa (GW-063)
Quintana Mesa (GW-309)
Richardson (GW-320)
Sims Mesa (GW-068)
Snowshoe (GW-287)
Thompson (GW-328)
Trunk A (GW-248)
Trunk B (GW-249)
Trunk C (GW-257)
Trunk L (GW-180)
Trunk M (GW-181)
Trunk N (GW-306)
Wildhorse (GW-079)

These updates are not significant and do not pose a hazard to public health or undue risk to property. These facilities do not discharge wastewater to surface or subsurface waters. All wastes generated at these facilities are temporarily stored in tanks or containers.

Respectfully submitted,



David Bays
Senior Environmental Specialist

Attachment

**Table 1
Transfer, Storage and Disposal of Process Fluids, Effluent and Waste Solids**

PROCESS FLUID/WASTE	STORAGE	STORAGE CAPACITY (approximate)	CONTAINMENT/ SPILL PREVENTION	RCRA STATUS	DESCRIPTION OF FINAL DISPOSITION
Used Oil	Above Ground Storage Tank	500 gal*	Berm or concrete pad and wastewater system	Non-exempt	May be hauled to a Williams or contractor consolidation point before transport to EPA-registered used oil marketer for recycling.
Produced Water/Natural Gas Condensate	Above Ground Storage Tank	300 bbl 120 bbl 40 bbl	Berms	Exempt	Saleable liquids may be sold to refinery. The remaining liquids may be transported to a Williams' evaporation facility or may be disposed at any facility permitted by any state, federal, or tribal agency to receive industrial solid waste. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such hazardous waste.
Wash-down Water	Below Grade Sump, vaulted	70 bbl 45 bbl	Dual-walled tanks	Non-exempt	Contractor may pump wash water back into truck after washing; water may be transported to any facility permitted by any state, federal, or tribal agency to receive industrial solid waste ; or evaporation at Williams' facility may be considered. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such waste.
Used Oil Filters	Drum or other container	Varies	Transported in drum or other container	Non-exempt	Transported to a Williams or contractor consolidation point, drained, and ultimately transported for disposal at any facility permitted by any state, federal, or tribal agency to receive industrial solid waste. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such hazardous waste. A Waste Acceptance Profile will be filed with the disposal facility as necessary. Recycling options may be considered when available.
Used Process Filters	Drum or other container	Varies	Transported in drum or other container	Exempt	Transported to a Williams or contractor consolidation point, drained, and ultimately transported for disposal at any facility permitted by any state, federal, or tribal agency to receive industrial solid waste. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such hazardous waste. A Waste Acceptance Profile will be filed with the disposal facility as necessary. Recycling options may be considered when available.
Spill Residue (e.g., soil, gravel, etc.)	N/A	N/A	In situ treatment, land-farm, or alternate method	Incident dependent	Per Section VI, Remediation, in 8/13/93 NMOCD Guidelines for Remediation of Leaks, Spills, and Releases.
Used Absorbents	Drum or other container	Varies	Transported in drum or other container	Non-exempt	Transported to a Williams or contractor consolidation point, drained, and ultimately transported for disposal at any facility permitted by any state, federal, or tribal agency to receive industrial solid waste. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such hazardous waste. A Waste Acceptance Profile will be filed with the disposal facility as necessary. Recycling options may be considered when available.
Empty Drums / Containers	N/A	N/A	Berm	Non-exempt	Barrels are returned to supplier or transported to a Williams or contractor consolidation point and ultimately recycled/disposed consistent with applicable regulations.
Antifreeze	Above Ground Storage Tank		Berm or concrete pad and wastewater system	N/A	Off-spec material recycled or disposed consistent with applicable regulations.
Glycol	Above Ground Storage Tank	500 gal* 125 gal* 100 gal*	Berm or concrete pad and wastewater system	N/A	Off-spec material recycled or disposed consistent with applicable regulations.
Lube Oil	Above Ground Storage Tank	500 gal*	Berm or concrete pad and wastewater system	N/A	Off-spec material recycled or disposed consistent with applicable regulations.

*Number of tanks installed dependent on number of engines and dehydrators installed on site. Engines and dehydrators are installed or removed to meet demand.

Table 2
Source, Quantity, and Quality of Effluent and Waste Solids

PROCESS FLUID / WASTE	SOURCE	QUANTITY (Ranges)	QUALITY
Produced Water/Natural Gas Condensate	Inlet Scrubber, Gas Inlet Separator, Dehydrators	2000-8000 bbl/year	No Additives
Waste Water/Wash Down Water	Compressor and Dehy Skids	100-5000 gal/year/unit	Biodegradable soap and tap water with traces of used oil
Used Oil	Compressors	500-2000 gal/year/engine	Used Motor Oil w/ No Additives
Used Oil Filters	Compressors	50-500/year/engine	No Additives
Used Process Filters	Charcoal, Activated Carbon, Molecular Sieve	50-500 cubic yd/yr	No Additives
Used Process Filters	Air, Inlet, Fuel, Fuel Gas, Glycol, Amine, Amibitol	75-500/year	No Additives
Empty Drums/Containers	Liquid Containers	0-80/year	No Additives
Spill Residue (i.e. soil, gravel, etc)	Incidental Spill	Incident Dependent	Incident Dependent
Used Adsorbents	Incidental Spill/Leak Equipment Wipe-down	Incident Dependent	No Additives

2006 AUG 23 AM 11 44



Environmental Department
188 County Road 4900
Bloomfield, NM 87413
505/632-4606
505/632-4781 Fax

August 22, 2006

Mr. Wayne Price
New Mexico Oil Conservation Division
Environmental Bureau
1220 South St. Francis Drive
Santa Fe, NM 87505

Re: Change of Company Name

Dear Mr. Price;

In accordance with Conditions of Discharge Plan Approval attached to each discharge plan approved by the New Mexico Oil Conservation Division, we hereby provide notice of a change of ownership for the Williams facilities identified in the attached table to Williams Four Corners, LLC.

As a corporate strategy, Williams has created regional limited liability corporations for our assets. So, although a new corporation has been created, Williams Four Corners LLC is still a wholly-owned unit of Williams, and there is no change of corporate ownership for these facilities. Williams will continue to comply with the terms and conditions of all approved discharge plans. All other administrative items (responsible official, environmental contacts, mailing addresses, etc.) remain unchanged.

If you have any questions, please call David Bays, Senior Environmental Specialist, at (505) 634-4951 or Ingrid Deklau of Cirrus Consulting at (801) 583-3107.

Sincerely,

A handwritten signature in black ink that reads "David Bays".

David Bays
Senior Environmental Specialist

Attachments

xc: Clara Cardoza
Monica Sandoval
WFS FCA file 210

AFFIDAVIT OF PUBLICATION

Ad No. 53441

STATE OF NEW MEXICO County of San Juan:

CONNIE PRUITT, being duly sworn says:
That she is the ADVERTISING MANAGER of
THE DAILY TIMES, a daily newspaper of
general circulation published in English at
Farmington, said county and state, and that
the hereto attached Legal Notice was
published in a regular and entire issue of the
said DAILY TIMES, a daily newspaper duly
qualified for the purpose within the meaning of
Chapter 167 of the 1937 Session Laws of the
State of New Mexico for publication and
appeared in the Internet at The Daily Times
web site on the following day(s):

Friday, May 12, 2006.

And the cost of the publication is \$199.75.

Connie Pruitt

ON 5/19/06 CONNIE PRUITT
appeared before me, whom I know personally
to be the person who signed the above
document.

Wynell Corey
My Commission Expires November 17, 2008.

COPY OF PUBLICATION

918

Legals

NOTICE OF PUBLICATION

STATE OF NEW MEXICO ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to the New Mexico Water Quality Control Commission Regulations, the following discharge plan application has been submitted to the Director of the Oil Conservation Division, 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505, Telephone (505) 476-3440:

(GW-248) - Williams Field Service, David Bays, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 16 barrels per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. The OCD proposed conditions can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility.

(GW-249) - Williams Field Service, David Bays, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 16 barrels per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. The OCD proposed conditions can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility.

(GW-250) - Williams Field Service, David Bays, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Coyote Springs Compressor Station located in the SW/4 NE/4, Section 30, Township 32 North, Range 11 West, NMPM, San Juan County, New Mexico. Approximately 16 barrels per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 100 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. The OCD proposed conditions can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility.

(GW-216) - Arapahoe Drilling Company, Mr. Steve Schalk, P.O. Box 26687, Albuquerque, New Mexico 87125, has submitted a discharge plan renewal application for their Farmington facility located in the NW/4, Section 13, Township 29 North, Range 13 West, NMPM, San Juan County, New Mexico. All effluents that may be generated at the facility will be collected in a closed top tank transported offsite to an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 70 feet with a total dissolved solids concentrations of approximately 900 mg/l. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. The OCD proposed conditions can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility.

(GW-156) - Key Energy Services, Inc. Four Corners Drilling, Ms. Cynthia Gray, Consultant to Key Energy Services, has submitted a discharge plan renewal application for the Farmington facility located in the SW/4 SW/4 of Section 21, Township 29 North, Range 12 West, NMPM, San Juan County, New Mexico. Approximately 60 barrels per week of wastewater is collected in a double walled steel tank then transported offsite for disposal into Key Energy Class II Disposal well. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. Groundwater most likely to be affected by an accidental discharge is at a depth of 45 feet with a total dissolved solids concentrations ranging from approximately 200 mg/l to 2000 mg/l. The OCD proposed conditions can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility.

(GW-171) - BP America Production Company, Mr. Kevin Hansford, 200 Energy Court, Farmington, New Mexico 87401 has submitted a renewal application for their Gallegos Canyon 3-C Compressor Station located in the SW/4 SE/4 of Section 29, Township 29 North, Range 12 West, NMPM, San Juan County, New Mexico. All fluids generated at this site are contained within collection steel tanks prior to transport offsite for disposal in an OCD approved facility. Groundwater most likely to be affected in the event of an accidental discharge at the surface is at a depth ranging from approximately 200 to 250 feet with a total dissolved solids concentration of approximately 1000 mg/l. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. The OCD pro-

NOTICE OF PUBLICATION

STATE OF NEW MEXICO ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to the New Mexico Water Quality Control Commission Regulations, the following discharge plan application has been submitted to the Director of the Oil Conservation Division, 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. Telephone (505) 476-3440:

(GW-248) - Williams Field Service, David Bays, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 16 barrels per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. The OCD proposed conditions can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility.

(GW-249) - Williams Field Service, David Bays, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico.

Approximately 16 barrels per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. The OCD proposed conditions can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility.

(GW-250) - Williams Field Service, David Bays, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Coyote Springs Compressor Station located in the SW/4 NE/4, Section 30, Township 32 North, Range 11 West, NMPM, San Juan County, New Mexico. Approximately 16 barrels per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 100 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. The OCD

can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility

(GW-216) - Arapahoe Drilling Company, Mr. Steve Schalk, P.O. Box 26687, Albuquerque, New Mexico 87125, has submitted a discharge plan renewal application for their Farmington facility located in the NW/4, Section 13, Township 29 North, Range 13 West, NMPM, San Juan County, New Mexico. All effluents that may be generated at the facility will be collected in a closed top tank transported offsite to an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 70 feet with a total dissolved solids concentrations of approximately 900 mg/l. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. The OCD proposed conditions can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility.

(GW-156) - Key Energy Services, Inc. Four Corners Drilling, Ms. Cynthia Gray, Consultant to Key Energy Services, has submitted a discharge plan renewal application for the Farmington facility located in the SW/4 SW/4 of Section 21, Township 29 North, Range 12 West, NMPM, San Juan County, New Mexico. Approximately 60 barrels per week of wastewater is collected in a double walled steel tank then transported offsite for disposal into Key Energy Class II Disposal well. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. Groundwater most likely to be affected by an accidental discharge is at a depth of 45 feet with a total dissolved

ranging from approximately 200 mg/l to 2000 mg/l. The OCD proposed conditions can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility.

(GW-171) - BP America Production Company, Mr. Kevin Hansford, 200 Energy Court, Farmington, New Mexico 87401 has submitted a renewal application for their Gallegos Canyon 3-C Compressor Station located in the SW/4 SE/4 of Section 29, Township 29 North, Range 12 West, NMPM, San Juan County, New Mexico. All fluids generated at this site are contained within collection steel tanks prior to transport offsite for disposal in an OCD approved facility. Ground water most likely to be affected in the event of an accidental discharge at the surface is at a depth ranging from approximately 200 to 250 feet with a total dissolved solids concentration of approximately 1000 mg/l. The discharge permit addresses how oilfield products and waste will be properly handled, stored and disposed of, including how spills, leaks, and other accidental discharges to the surface will be managed in order to protect fresh water. The OCD proposed conditions can be viewed at www.emnrd.state.nm.us/ocd in the Draft Discharge Permit for this facility.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan application may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday thru Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and public hearing may be requested by any interested person. Request for public hearing shall set

a hearing shall be held. A hearing will be held if the director determines that there is significant public interest.

If no hearing is held, the Director will approve or disapprove the plan based on the information available. If a public hearing is held, the Director will approve the plan based on the information in the plan and information presented at the hearing.

GIVEN under the Seal of New Mexico Conservation Commission at Santa Fe, New Mexico, on this 6th day of April 2006.

STATE OF NEW MEXICO OIL CONSERVATION DIVISION

SEAL
MARK FESMIER, P.E.,
Director
Legal #78927
Pub. May 12, 2006

ACKNOWLEDGEMENT OF RECEIPT
OF CHECK/CASH

I hereby acknowledge receipt of check No. [REDACTED] dated 3/28/06

or cash received on _____ in the amount of \$ 100⁰⁰

from Williams Field Services Co.

for Truck B Booster station GW-249

Submitted by: Lawrence Rayero Date: 4/6/06

Submitted to ASD by: Lawrence Rayero Date: 4/6/06

Received in ASD by: _____ Date: _____

Filing Fee New Facility _____ Renewal _____

Modification _____ Other _____

Organization Code 521.07 Applicable FY 2004

To be deposited in the Water Quality Management Fund.

Full Payment _____ or Annual Increment _____

THIS MULTITONE AREA OF THE DOCUMENT CHANGES COLOR GRADUALLY AND EVENLY FROM DARK TO LIGHT WITH DARKER AREAS BOTH TOP AND BOTTOM. IT ALSO HAS A REFLECTIVE WATERMARK ON THE BACK.



WILLIAMS FIELD SERVICES COMPANY
PO Box 21218
Tulsa, OK 74121-1218
Customer Support 1-866-778-2665

J.P. Morgan Chase Bank, N.A.
Chicago, IL

18-2122 1/19
A/C 940116

DATE: 03/28/2006

PAY TO THE ORDER OF

PAY \rightarrow \$*****300.00

USD

NEW MEXICO OIL CONSERVATION DIV
WATER QUALITY MANAGEMENT FUND
2040 S PACHECO

SANTA FE
UNITED STATES

NM 87505

Michael Hill

Authorized Signer

SUPPLIER NUMBER
403816

GW-250 GW-249 GW-248





Environmental Affairs
188 CR 4900
Bloomfield, NM 87413
505/632-4625
505/632-4781 Fax

April 3, 2006

Mr. Jack Ford
New Mexico Oil Conservation Division
Water Quality Management Fund
1220 S St. Francis Dr.
Santa Fe NM 87505

Re: Discharge Plan GW-250, GW-249, and GW-248 Application Renewal and Filing Fees

Dear Mr. Ford:

Enclosed please find copies of Discharge Plan application renewal and check number 4027013316 for \$300.00 to cover the filling fee for the following Williams Field Services (WFS) Compressor Stations:

- **Coyote Springs Compressor Station (GW-250)**
- **Trunk B Booster Station (GW-249)**
- **Trunk A Booster Station (GW-248)**

Williams Field Services appreciates your assistance in handling these applications and fees. If you have any questions or require additional information, please contact me at 505/632/4625.

Thank you,

Monica Sandoval
Environmental Compliance

Xc: Denny Foust, Aztec, OCD Dist III
FCA Environmental File 220

District I - (505) 393-6161

P. O. Box 1980

Hobbs, NM 88241-1980

District II - (505) 748-1283

811 S. First

Artesia, NM 88210

District III - (505) 334-6178

1000 Rio Brazos Road

Aztec, NM 87410

District IV - (505) 827-7131

New Mexico

Energy Minerals and Natural Resources Departments

Oil Conservation Division

2040 South Pacheco Street

Santa Fe, New Mexico 87505

(505) 827-7131

Revised June 10, 2003

Submit Original

Plus 1 Copy

to Santa Fe

1 Copy to appropriate

District Office

**DISCHARGE PLAN APPLICATION FOR SERVICE COMPANIES,
GAS PLANTS, REFINERIES, COMPRESSOR, AND CRUDE OIL PUMP STATIONS**

(Refer to OCD Guidelines for assistance in completing the application)

New

Renewed

Modification

1. Type: Compressor Station (Trunk B Booster Station, GW-249)

2. Operator: Williams Field Services Company

Address: 188 CR 4900, Bloomfield, NM 87413

Contact Person: David Bays

3. Location: SW/4 SW/4 Section 28 Township 31N Range 8W

4. Attach the name, telephone number and address of the landowner of the facility site.

5. Attach the description of the facility with a diagram indicating location of fences, pits, dikes and tanks on the facility.

6. Attach a description of all materials stored or used at the facility.

7. Attach a description of present sources of effluent and waste solids. Average daily quality and daily volume of waste water must be included.

8. Attach a description of current liquid waste and solid waste collection/treatment/disposal systems.

9. Attach a description of proposed modifications to existing collection/treatment/disposal systems.

10. Attach a routine inspection and maintenance plan to ensure permit compliance.

11. Attach a contingency plan for reporting and clean-up of spills or releases.

12. Attach geological/hydrological information for the facility. Depth to and quality of ground water must be included.

13. Attach a facility closure plan, and other information as is necessary to demonstrate compliance with any other rules, regulations, and/or orders.

14. CERTIFICATION I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.

NAME: David Bays Title: Sr. Environmental Specialist

Signature:  Date: 03/24/2006

E-Mail Address: David.bays@williams.com



Four Corners Area
Environmental Department
#188 CR 4900
Bloomfield, N.M. 87413
Phone: (505) 634-4956
Fax: (505) 632-4781

November 30, 2001

Water Management Quality Management Fund
c/o: Oil Conservation Division
1220 South St. Francis Drive
Santa Fe, NM 87505

Dear Sir or Madam:

Enclosed please find, check number 1000388005 for \$17,000.00, to cover the fees for the following discharge plans:

Coyote Springs Compressor	GW-250	\$ 1,700.00
Trunk C Booster Station	GW-257	\$ 1,700.00
Trunk B Booster Station	GW-249	\$ 1,700.00
Lateral N-30 (Koch Gardner)	GW-256	\$ 1,700.00
32-9 CDP Compressor Station	GW-091	\$ 1,700.00
Pritchard Straddle Compressor Station	GW-274	\$ 1,700.00
Kernaghan Compressor	GW-271	\$ 1,700.00
Trunk A Booster Station	GW-248	\$ 1,700.00
Sims Mesa Compressor Station	GW-068	\$ 1,700.00
30-5 CDP Compressor Station	GW-108	\$ 1,700.00

Your assistance in processing this fee is greatly appreciated.

If you have any questions please contact me at (505) 634-4956.

Thank You,

Ethel Holiday
Environmental Compliance

ACKNOWLEDGEMENT OF RECEIPT
OF CHECK/CASH

I hereby acknowledge receipt of check No. [REDACTED] dated 11/29/01
or cash received on _____ in the amount of \$ 17,000.00
from See Attached List
for _____

Submitted by: ^(Family Name) W J Furt Date: ^(DP No.) 12/4/01

Submitted to ASD by: _____ Date: _____

Received in ASD by: _____ Date: _____

Filing Fee _____ New Facility _____ Renewal

Modification _____ Other _____
(optional)

Organization Code 521.07 Applicable FY 2001

To be deposited in the Water Quality Management Fund.

Full Payment or Annual Increment _____

THIS MULTI-TONE AREA OF THE DOCUMENT CHANGES COLOR GRADUALLY AND EVENLY FROM DARK TO LIGHT WITH DARKER AREAS BOTH TOP AND BOTTOM. IT ALSO HAS A REFLECTIVE WATERMARK ON THE BACK.

Williams WILLIAMS FIELD SERVICES COMPANY 78-2322 / 719
1800 South Baltimore Avenue * P.O. Box 645 * Tulsa, OK 74101-0645 A/C 9401076

DATE: 11/29/2001

PAY TO THE ORDER OF: NEW MEXICO OIL CONSERVATION DI
NM WATER QUALITY MGMT FUND
2040 S PACHECO

SANTA FE NM 87504
United States

Bank One, NA
Illinois

PAY \rightarrow *****\$17,000.00

W J Furt
Authorized Signer

MA1353 (10/99)

THE SANTA FE
NEW MEXICAN

Founded 1849

NM OIL CONSERVATION DIVISION
ATTN: ED MARTIN
1220 S. ST. FRANCIS DRIVE
SANTA FE, NM 87505

AD NUMBER: 220076 ACCOUNT: 56689
LEGAL NO: 69809 P.O.#: 0219900249
337 LINES 1 time(s) at \$ 148.55
AFFIDAVITS: 5.25
TAX: 9.61
TOTAL: 163.41

AFFIDAVIT OF PUBLICATION

STATE OF NEW MEXICO
COUNTY OF SANTA FE

I, Mm Weideman being first duly sworn declare and say that I am Legal Advertising Representative of THE SANTA FE NEW MEXICAN, a daily newspaper published in the English language, and having a general circulation in the Counties of Santa Fe and Los Alamos, State of New Mexico and being a Newspaper duly qualified to publish legal notices and advertisements under the provisions of Chapter 167 on Session Laws of 1937; that the publication #69809 a copy of which is hereto attached was published in said newspaper 1 day(s) between 08/06/2001 and 08/06/2001 and that the notice was published in the newspaper proper and not in any supplement; the first publication being on the 6 day of August, 2001 and that the undersigned has personal knowledge of the matter and things set forth in this affidavit.

/s/ Mm Weideman
LEGAL ADVERTISEMENT REPRESENTATIVE

Subscribed and sworn to before me on this
6 day of August A.D., 2001

Notary Laura E. Harding

Commission Expires 11/23/03

the caption, are hereby given notice of the above-captioned action in the captioned Court:
TONY MARRUFO
 9046 VILLA MADERO
 EL PASO, TEXAS 79907

The aforementioned Interested Party, and any persons claiming any interest whatsoever in the monies described above in the caption, are given notice that a civil lawsuit has been filed by the State of New Mexico ex rel. the Department of Public Safety, State Police Division, the Plaintiff, seeking forfeiture of all Interested Party's rights, title, and interest in the above-captioned monies. The monies is alleged to be subject to forfeiture as a result of its use in the State of New Mexico in a manner prohibited by NMSA 1988, Sections 30-31-1 to 30-31-42 (Repl. Pamp. 1989 & Cum. Supp. 1992), on or about March 31, 2001.

You are hereby given notice that unless you file a responsive pleading or motion in said cause on or before September 7, 2001, judgment or other appropriate relief will be rendered in this cause against you by default.

The attorney of record for the Plaintiff, the New Mexico Department of Public Safety, State Police Division, is Albert Roland Fugere, Special Assistant Attorney General for the State of New Mexico, P.O. Box 1628, Santa Fe, New Mexico 87504-1628.

WITNESS the Honorable James A. Hall, District Judge of the First Judicial District Court of the State of New Mexico.

Seal of the District Court of Santa Fe County, this 9 day of July, 2001.

JOANN VIGIL QUINTANA
 District Court Clerk

By:
 Eric Erb
 Deputy District Court Clerk
 Legal #69687
 Pub. July 17, 23, 30 & August 6, 2001

Notice

Take notice that Ayudantes, Inc. is applying for capital funding from the New Mexico State Highway and Transportation Department (NMSHTD) Public Transportation Programs Bureau (PTPB) to acquire three (3) vans or other para-transit vehicles for the purpose of transporting persons with substance abuse and/or mental health disabilities, and who participate in services provided by Ayudantes, Inc. at any one of its three sites, located in Santa Fe, Española and Las Vegas,

PUBLICATION

STATE OF NEW MEXICO ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to the New Mexico Water Quality Control Commission Regulations, the following discharge plan application has been submitted to the Director of the Oil Conservation Division, 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505. Telephone (505) 476-3440:

(GW-248) - Williams Field Service, Mark J. Baretz, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-249) - Williams Field Service, Mark J. Baretz, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-250) - Williams Field Service, Mark J. Baretz, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has

collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 140 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan application may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday thru Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and public hearing may be requested by any interested person. Request for public hearing shall set forth the reasons why a hearing shall be held.

A hearing will be held if the director determines that there is significant public interest.

If no hearing is held, the Director will approve or disapprove the plan based on the information available. If a public hearing is held, the Director will approve the plan based on the information in the plan and information presented at the hearing.

GIVEN under the Seal of New Mexico Conservation Commission at Santa Fe, New Mexico, on this 25th day of July, 2001.

STATE OF NEW MEXICO OIL CONSERVATION DIVISION

LORI WROTENBERY, Director
 Legal #69809
 Pub. August 6, 2001

STATE OF NEW MEXICO COUNTY OF SANTA FE IN THE DISTRICT COURT

PROBATE NO. D-0117-PB-200100087

IN THE MATTER OF THE ESTATE OF AMALIA SERNA, DECEASED

NOTICE TO CREDITORS

BELARMINO GIRON has been appointed Personal

Pjoaque Schools, weekdays from 8:00 a.m. to 4:00 p.m. Please bring with you identification which proves parentship or identification which matches the student records. Call 455-0801. Legal #69783
 Pub. August 6, 7, 8, 9 & 10, 2001



EQUAL HOUSING NOTICE

All real estate advertised in The Santa Fe New Mexican is subject to the Federal Fair Housing Act of 1968 which makes it illegal to advertise in general any preference, limitation, or discrimination based on race, color, religion, sex, handicap, familial status, or national origin, or intention to make any such preference, limitation or discrimination. We will not knowingly accept any advertising for real estate which is in violation of the law. All persons are hereby informed that all dwellings advertised are available on an equal opportunity basis.



EQUAL HOUSING OPPORTUNITY

010-SANTA FE

****10% FT. CEILINGS** unique open concept home. 2/1+1, sunroom, studio/office w/ separate entry, private country feel yet close in. \$217,000. Owner/Broker. The Fox Agency, 982-8794.

2 UNIT adobe + studio. Oak beams, FP's, .25 ac. \$299K. Noble RE, owners. 982-0596

****3 Bdrm., 1 1/4 Ba.,** new roof, stucco, Lg. yard. \$179K. 474-6016/780-0492.

3 BDRM., 1 1/4 ba., office/studio, LR, W/D, kiva FP, air conditioning, 1,780 sq.ft. \$180,000. 2602 Calle Primavera. By appt., (505) 438-8113

3 BDRM., 1 1/4 Ba., spacious LR, DR & yards, by Chaves center. \$145K. 473-4550

RARE

Huge home with indoor olympic-style pool on 3 1/2 acres. The views are incredible. Privacy, location, value. This home is different in style but it's your chance to buy low and have everything you want. Extras like sauna, 3-car garage, landscaped yards, mature trees! Let's talk price and terms since seller will finance.

MARES Realty 988-5585

1,972 sq. ft., 3 on 1/3 acre. De in great r \$306,000. Own

DOUBLE LOT W house & rental. owner. 10,000 lot. Room to be Plaza. \$239,000

EJ MARTINEZ Linda 3 bdm bath. Stamm 1 acre. Den hardwood finished closed yard. 0 Sat. & \$289,000. 98

ELDORADO, 2 bdr Passive solar hor plan. \$165,000. 9

ELDORADO, 3/4 shop/studio. Tr Noble RE, owner

FOR SALE by o 4 bdrm., 1 3/4 Well maintained.

FSBO, 2 ac. 2000 sq.ft. Dia beautiful yard, lowed. \$289k. 4

~LIG Lofts w/hug Homes/Art T-1 lit 474-3

PREMIER MO New Mexico. (5 Fax (505) 983 wide 1-800-441 professional ser

PRICED TO SI bdm. condo. V \$159,900. 820

RANCHO VIEJO Chapparal mod upgrades galo soon. Call Tom,

REDUCED BY new adobe, 2 North. \$140K. 4

TESUQUE CANY bdrm., 1 ba., 1 ac. \$425K; 3 2051 sq.ft., 1 983-4032; 662

NEW-OM

Using Yc helps your a GET NO Call 986-307 BE SEEN

025-TOWN CONDON

~LIG Lofts w/hug Homes/Art T-1 lit 474-

030-LOTS 8

13 AC. LOTS, derground elec lines for ea pumps, view, building sites owner financ +/- Owner. (5

2.5 ACRE L Campanas. Ex utilities. \$108 er. 505-471-5-

2.5 ACRES Lo views, all utilil lope Rd. off F near Las Cam 471-3198 or 5

AFFIDAVIT OF PUBLICATION

Ad No. 44844

STATE OF NEW MEXICO
County of San Juan:

CONNIE PRUITT, being duly sworn says:
That she is the Classified Manager of THE
DAILY TIMES, a daily newspaper of general
circulation published in English at Farmington,
said county and state, and that the hereto
attached Legal Notice was published in a
regular and entire issue of the said DAILY
TIMES, a daily newspaper duly qualified for
the purpose within the meeting of Chapter 167
of the 1937 Session Laws of the State of New
Mexico for publication on the following day(s):

Monday, August 6, 2001.

And the cost of the publication is \$157.41.

Connie Pruitt

ON 8.9.01 CONNIE PRUITT appeared
before me, whom I know personally to be the
person who signed the above document.

Gunny Beck

My Commission Expires April 02, 2004

COPY OF PUBLICATION

918

Legals

NOTICE OF PUBLICATION

STATE OF NEW MEXICO ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to the New Mexico Water Quality Control Commission Regulations, the following discharge plan application has been submitted to the Director of the Oil Conservation Division, 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505, Telephone (505) 476-3440:

(GW-248) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-249) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-250) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Coyote Springs Compressor Station located in the SW/4 NE/4, Section 30, Township 32 North, Range 11 West, NMPM, San Juan County, New Mexico. Approximately 26 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 100 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-257) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk C Booster Station located in the SE/4 SW/4, Section 9, Township 31 North, Range 10 West, NMPM, San Juan County, New Mexico. Approximately 75 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 140 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan application may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday thru Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and public hearing may be requested by any interested person. Request for public hearing shall set forth the reasons why a hearing shall be held.

A hearing will be held if the director determines that there is significant public interest.

If no hearing is held, the Director will approve or disapprove the plan based on the information available. If a public hearing is held, the Director will approve the plan based on the information in the plan and information presented at the hearing.

GIVEN under the Seal of New Mexico Conservation Commission at Santa Fe, New Mexico, on this 25th day of July, 2001.

STATE OF NEW MEXICO
OIL CONSERVATION DIVISION

SEAL

LORI WROTENBERY, Director

Legal No. 44844, published in The Daily Times, Farmington, New Mexico, Monday, August 6, 2001.

101

NOTICE OF PUBLICATION

STATE OF NEW MEXICO ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to the New Mexico Water Quality Control Commission Regulations, the following discharge plan application has been submitted to the Director of the Oil Conservation Division, 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505, Telephone (505) 476-3440:

(GW-248) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-249) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-250) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Coyote Springs Compressor Station located in the SW/4 NE/4, Section 30, Township 32 North, Range 11 West, NMPM, San Juan County, New Mexico. Approximately 26 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 100 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-257) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk C Booster Station located in the SE/4 SW/4, Section 9, Township 31 North, Range 10 West, NMPM, San Juan County, New Mexico. Approximately 75 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 140 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.


Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan application may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday thru Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and public hearing may be requested by any interested person. Request for public hearing shall set forth the reasons why a hearing shall be held.

A hearing will be held if the director determines that there is significant public interest.

If no hearing is held, the Director will approve or disapprove the plan based on the information available. If a public hearing is held, the Director will approve the plan based on the information in the plan and information presented at the hearing.

GIVEN under the Seal of New Mexico Conservation Commission at Santa Fe, New Mexico, on this 25th day of July, 2001.

STATE OF NEW MEXICO
OIL CONSERVATION DIVISION



LORI WROTENBERY, Director

SEAL

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 South First, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
2040 South Pacheco, Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources
Oil Conservation Division
2040 South Pacheco
Santa Fe, NM 87505

Revised March 17, 1999
Submit Original
Plus 1 Copy
to Santa Fe
1 Copy to Appropriate
District Office

**DISCHARGE PLAN APPLICATION FOR SERVICE COMPANIES,
GAS PLANTS, REFINERIES, COMPRESSOR, AND CRUDE OIL PUMP STATIONS**
(Refer to the OCD Guidelines for assistance in completing the application)

New Renewal Modification

San Juan

1. Type: Compressor Station (Trunk B Booster Station)

2. Operator: Williams Field Services Company

Address: 188 CR 4900, Bloomfield, New Mexico 87413

Contact Person: Mark J. Baretta

Phone: (505) 632-4634

3. Location: SW/4 SW/4 Section 28 Township 31 North Range 8 West
Submit large scale topographic map showing exact location.

4. Attach the name, telephone number and address of the landowner of the facility site.
5. Attach the description of the facility with a diagram indicating location of fences, pits, dikes and tanks on the facility.
6. Attach a description of all materials stored or used at the facility.
7. Attach a description of present sources of effluent and waste solids. Average quality and daily volume of waste water must be included.
8. Attach a description of current liquid and solid waste collection/treatment/disposal procedures.
9. Attach a description of proposed modifications to existing collection/treatment/disposal systems.
10. Attach a routine inspection and maintenance plan to ensure permit compliance.
11. Attach a contingency plan for reporting and clean-up of spills or releases.
12. Attach geological/hydrological information for the facility. Depth to and quality of ground water must be included.
13. Attach a facility closure plan, and other information as is necessary to demonstrate compliance with any other OCD rules, regulations and/or orders.

14. CERTIFICATION

I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.

Name: Mark J. Baretta

Title: Senior Environmental Specialist

Signature: *Clara M. Garcia for*

Date: *July 13, 2001*

DISCHARGE PLAN RENEWAL

**TRUNK B BOOSTER STATION
(GW-249)**

Williams Field Services Company

June 2001

Table of Contents

I.	Type of Operation-----	1
II.	Legally Responsible Party -----	1
III.	Location of Facility -----	1
IV.	Landowner -----	1
V.	Facility Description-----	1
VI.	Source, Quantity, and Quality of Effluents and Waste Solids-----	1
VII.	Transfer, Storage, and Disposal of Process Fluids, Effluents, and Waste Solids-----	2
VIII.	Storm Water Plan -----	4
IX.	Inspection, Maintenance, and Reporting -----	5
X.	Spill/Leak Prevention and Reporting (Contingency Plans)-----	5
XI.	Site Characteristics -----	5
XII.	Facility Closure Plan -----	6

List of Tables

Table 1 - Source, Quantity, and Quality of Effluent and Waste Solids -----	2
Table 2 - Transfer, Storage, and Disposal of Process Fluids, Effluents, and Waste Solids -----	3

List of Figures - All figures follow Section XI

- Figure 1 - Site Vicinity / Topographic Map
- Figure 2 - Facility Plot Plan

List of Appendices

- Appendix A – WES Spill Control Procedures
- Appendix B – NMOCD Notification of Fire, Breaks, Spills, Leaks, and Blowouts

I. TYPE OF OPERATION

The Trunk B Booster Station was built in 1996 to provide metering, compression, and dehydration services to various producers for the gathering of coal seam natural gas for treatment and delivery through Williams Field Services (WFS) Milagro Plant.

II. LEGALLY RESPONSIBLE PARTY

Williams Field Services
188 CR 4900
Bloomfield, NM 87413
(505) 632-4634

Contact Person:

Mark J. Baretta, Senior Environmental Specialist
Phone and Address, Same as Above

III. LOCATION OF FACILITY

The Trunk B Booster Station is located in Section 28, Township 31 North, Range 8 West, in San Juan County, New Mexico, approximately 16.3 miles northeast of Bloomfield, New Mexico. A site location map is attached (USGS 7.5 Min. Quadrangle: Archuleta, New Mexico) as Figure 1. The facility layout is illustrated in Figure 2. All figures are attached following Section XI of the text.

IV. LANDOWNER

Williams Field Services is leasing the subject property from:

Bureau of Land Management
1235 N. La Plata Highway
Farmington, NM 87401
(505) 599-8900

V. FACILITY DESCRIPTION

This facility is classified as a field compressor station and is unmanned. The air quality permit for this site has allowed the operation of seven 1367-hp engines. Only three units are currently installed at the site. In addition, there are various storage tanks, support structures and ancillary equipment. Records related to facility operations are maintained at central office locations.

VI. SOURCE, QUANTITY, AND QUALITY OF EFFLUENTS AND WASTE SOLIDS

The source, quantity, and quality of effluent and waste solids generated at the compressor station are summarized in Table 1.

TABLE 1
SOURCE, QUANTITY, AND QUALITY OF EFFLUENT AND WASTE SOLIDS
TRUNK B BOOSTER STATION

PROCESS FLUID/WASTE	SOURCE	QUANTITY (Ranges)	QUALITY
Used Oil	Compressor	1000-2000 gal/year/engine.	Used motor oil w/no additives
Used Oil Filters	Compressor	50-100 filters/year/engine	No additives
Wash-down Water	Compressor Skid	500-1500 gal/year/engine	Biodegradable Soap and tap water w/traces of used oil
Natural Gas Condensate	Scrubber, Gas Inlet Separator	1000-3000 bbl/year	No additives
Used Process Filters	Air, Inlet and Fuel Gas	75- 100/year	No additives
Empty Drums / Containers	Liquid Containers	20-40/year	No additives
Spill Residue (i.e., gravel, soil)	Incidental spills	Incident dependent	Incident dependent
Used Absorbents	Incidental spill/leak equipment wipe-down	Incident dependent	No additives

VII. TRANSFER, STORAGE, AND DISPOSAL OF PROCESS FLUIDS, EFFLUENTS AND WASTE SOLIDS

Wastes generated at this facility fall into two categories: exempt and non-exempt. Exempt wastes include, but may not be limited to, used process filters, condensate spill cleanups (spill residue), certain absorbents, and produced water with or without de minimus quantities of non-hazardous liquids. Non-exempt wastes include, but may not be limited to, used oil, used oil filters, and engine coolant. Table 2 describes the transfer, storage and disposal of exempt and non-exempt process fluids, effluents, and waste solids expected to be generated at the site.

Non-exempt waste management will be conducted in accordance with NMOCD requirements including the preparation of a Certificate of Waste Status for each non-exempt waste stream. Non-exempt wastes will be analyzed at a minimum for BTEX, TPH, RCRA D-List metals, ignitability, corrosivity, and reactivity to initially determine if such waste are hazardous as defined in 40 CFR Part 261. All wastes at the facility will be periodically surveyed for naturally occurring radioactive material (NORM) to determine if the concentrations of radium 226 exceed 30 picocuries per gram or if radiation exposure exceeds 50 microrentgens per hour. If affirmed, such materials will be handled and disposed in accordance with NMOCD NORM Regulations.

Barring facility modification and/or process changes, the classification of non-exempt wastes by laboratory analyses will be made once during the approval period of this plan. Subsequent laboratory analyses will be performed at the generator's discretion (minimum of once every five years), or more frequently to comply with waste acceptance procedures of the disposal facility.

TABLE 2
TRANSFER, STORAGE, AND DISPOSAL OF PROCESS FLUIDS, EFFLUENTS, AND WASTE SOLIDS
TRUNK B BOOSTER STATION

PROCESS FLUID/WASTE	STORAGE	CONTAINER CAPACITY (approximate)	CONTAINMENT/ SPILL PREVENTION	RCRA STATUS	DESCRIPTION OF FINAL DISPOSITION
Used Oil	Above Ground Storage Tanks	(3) 500 gallons	Berm	Non-exempt	May be hauled to a WFS or contractor consolidation point before transport to EPA-registered used oil marketer for recycling.
Used Oil Filters	Drum or other container	Varies	Transported to a WFS or contractor facility in drum or other container	Non-exempt	Transported to a WFS or contractor consolidation point, drained, and ultimately transported for disposal at an approved disposal facility. A Waste Acceptance Profile will be filed with the disposal facility. Recycling options may be considered when available.
Natural Gas Condensate	Above Ground Storage Tank	70 bbl	Berm	Exempt	Saleable liquids may be sold to refinery or liquid may be disposed at NMOCD- approved facility.
Wash-down Water	Below-ground sump, vaulted	740 gallons	Dual-walled tank	Non-Exempt	Water may be transported to NMOCD-approved facility; or evaporation at WFS facility may be considered in future.
Used Process Filters	Drum or other container	Varies	Transported to a WFS or contractor facility in drum or other container	Exempt	Transported to a WFS or contractor consolidation point, drained, and ultimately transported for disposal at an approved disposal facility. A Waste Acceptance Profile will be filed with the disposal facility. Recycling options may be considered when available.
Empty Drums / Containers	N/A	N/A	Berm	Non -exempt	Barrels are returned to supplier or transported to a WFS or contractor consolidation point and ultimately recycled/disposed
Spill Residue (i.e., soil, gravel)	N/A	N/A	In situ treatment, land-farm, or alternate method	Incident dependent	Per Section VI, Remediation, in 8/13/93 NMOCD Guidelines for Remediation of Leaks, Spills, and Releases.
Used Absorbents	Drum or other container	Varies	Transported to a WFS or contractor facility in drum or other container	Non-exempt	Transported to a WFS or contractor consolidation point, drained, and ultimately transported for disposal at an approved disposal facility. A Waste Acceptance Profile will be filed with the disposal facility. Recycling options may be considered when available.
Compressor Oil	Above ground storage tanks	(3) 500 gallons	Berm	N/A	Off-spec material recycled or disposed consistent with applicable regulations.

VIII. STORM WATER PLAN

This storm water section was developed to provide a plan to monitor and mitigate impact to storm water runoff from the facility. It serves to satisfy storm water management concerns of the NMOCD. It is not intended to comply with 40 CFR Part 122, Storm Water Discharges as this facility is excluded in 122.26 (c) (1) (iii).

This section concentrates on the identification of potential pollutants, inspection and maintenance of the pollutant controls, and gives a description of structural controls to prevent storm water pollution.

Site Assessment and Facility Controls

An evaluation of the material used and stored on this site that may be exposed to storm water indicates that no materials would routinely be exposed to precipitation. There are no engineered storm water controls or conveyances; all storm water leaves the site by overland flow.

Any leakage or spill from the identified potential pollutant sources, if uncontained by existing berms, curbs, or emergency response actions, could flow overland to open off-site drainage ditches (arroyos) and thus impact storm water. In such an event, containment would occur by blocking the ditch or culvert downstream of the pollutant. Cleanup of the substance and implementation of mitigation measures could be conducted while protecting downstream storm watercourses.

Best Management Practices

Following are Best Management Practices (BMPs) to be implemented to prevent or mitigate pollution to storm water from facility operations:

- All waste materials and debris will be properly disposed of on an on-going basis in appropriate containers and locations for collection and removal from the site.
- Temporary storage of potential pollutant sources will be located in areas with appropriate controls for storm water protection. This would include ensuring all containers are sealed/covered and otherwise protected from contact with precipitation.
- Periodic inspection of channels and culverts shall be performed at least twice annually and after any major precipitation event.
- Sediment deposits and debris will be removed from the channels and culverts as necessary and any erosion damage at the outfall (if any) will be repaired or controlled.
- Conduct inspections of the facility on a regular basis as part of the preventive maintenance site check. Such inspections will include the visual assessment of corroded or damaged drums and tanks, broken or breached containment structures, collapsed or clogged drainages or drain lines.

Implementation of the BMPs will prevent or mitigate impact to storm water runoff from this facility.

IX. INSPECTION, MAINTENANCE AND REPORTING

WFS's personnel will operate and maintain the compression unit at the facility. The facility will be remotely monitored for equipment malfunctions through Gas Dispatch. The facility will be visited several times per week at a minimum, and an operator will be on call 24 hours per day, 7 days per week, 52 weeks per year. The above ground and below-grade tanks will be gauged regularly, and monitored for leak detection.

In the event of a release of a reportable quantity, the operator reports the release to a WFS spill notification service. The service immediately notifies the WFS Environmental Department and all appropriate agencies.

X. SPILL/LEAK PREVENTION AND REPORTING (CONTINGENCY PLANS)

Spill containment berms around above ground storage tanks will be designed to contain 1-1/3 times the volume of the tank and will be equipped with an impermeable liner. The below-grade tanks will be constructed with a means of leak detection, and will either be double-bottomed tanks or a tank set on an impermeable pad.

WFS corporate policy and procedure for the controlling and reporting of Discharges or Spills of Oil or Hazardous Substances is provided in Appendix A. Significant spills and leaks are reported to the NMOCD pursuant to NMOCD Rule 116 and WQCC 1-203 using the NMOCD form (see Appendix B).

XI. SITE CHARACTERISTICS

The Trunk B Booster Station is located approximately 17 miles east of Aztec, New Mexico. The site elevation is approximately 6,500 feet above mean sea level. The natural ground surface topography slopes downward toward the east. The maximum relief over the site is approximately 10 feet. Intermittent flow from the site will follow natural drainage to the east to the Simon Canyon drainage. Simon Canyon drains to the south into the San Juan River. The San Juan River, approximately 3.1 miles to the south-southeast of the site, is nearest down-gradient perennial source of surface water at an elevation of approximately 5,700 feet.

A review of the available hydrologic data^{1,2} for this area revealed that there are no water wells within a 1/4-mile radius of Trunk B Booster Station. The water-bearing unit in this area is the San Jose Formation. The San Jose Formation is the youngest Tertiary bedrock unit. This formation consists of a sequence of interbedded sandstone and mudstone. The estimated ground water depth at the site is 400 to 800 feet. The total dissolved solids concentration of area ground water is expected to range from 200 to 2,000 parts per million.

The 100-year 24-hour precipitation event at a regional weather station is 2.8 inches. This small amount of rainfall for the area should pose no flood hazards. Vegetation in the area consists predominantly of sagebrush and native grasses

Flood Protection: Surface water runoff from the area surrounding the site will be diverted around the facility into the natural drainage path.

References

¹Stone, W.J., Lyford, F.P., Frenzel, P.F., Mizell, N.H., Padgett, E.T., 1983, Hydrology and Water Resources of San Juan Basin, New Mexico Bureau of Mines and Mineral Resources, Hydrologic Report 6.

²Online Well Reports and Downloads, New Mexico Office of the State Engineer, 2000.

XII. FACILITY CLOSURE PLAN

All reasonable and necessary measures will be taken to prevent the exceedence of WCQQ Section 3103 water quality standards should WFS choose to permanently close the facility. WFS will submit a detailed closure plan to the NMOCD prior to closure.

Generally, closure measures will include removal or closure in place of underground piping and other equipment. All wastes will be removed from the site and properly disposed in accordance with the rules and regulations in place at the time of closure. When all fluids, contaminants, and equipment have been removed from the site, the site will be graded as close to the original contour as possible.


Should contaminated soil be discovered, any necessary reporting under NMOCD Rule 116 and WQCC Section 1203 will be made and clean-up activities will commence. Post-closure maintenance and monitoring plans would not be necessary unless contamination is encountered.

FIGURE 1

SITE VICINITY / TOPOGRAPHIC MAP

FIGURE 2

SITE PLAN



Source: USGS Archuleta Quadrangle, New Mexico

Scale: 1" = 2,000'




Figure 1 Site Vicinity / Topographic Map
Trunk B Booster Station
 Section 28, Township 31N Range 8W
 San Juan County, New Mexico

Subject or Title:

SPILL PREVENTION CONTROL AND COUNTERMEASURE PLAN

ATTACHMENT "A" PRODUCT AND WASTE STORAGE LOCATIONS



OPERATIONS		
Manual	TRUNK "B" COMPRESSOR STATION	
Section	SPILL PREVENTION CONTROL	Tab 13 Document No. 4213.001
Effective Date	12-8-98	Issue No. 02 Page No. 5 of 8

S:\WFSDS\PM_EI\Trb\Eod\00070102.dwg Mon Mar 08 08:59:13 1999

REFERENCE DRAWINGS										REFERENCE DRAWINGS										REVISIONS										DRAFTING BY DATE DRAWN BY PHM 11-11-98 CHECKED BY APPROVED BY ENGINEER BY DATE DESIGNED BY PROJ. APPROVED		STATE: NEW MEXICO COUNTY: SAN JUAN		WILLIAMS FIELD SERVICES <small>ONE OF THE WILLIAMS COMPANIES</small>		TRUNK "B" COMPRESSOR STATION SPILL PREVENTION CONTROL AND COUNTERMEASURE PLAN PLOT PLAN				SCALE: 1" = 40' W.D. NO. 98408		DWG NO. TRB-1-P7		SHEET 1 OF 1 REV 02	
--------------------	--	--	--	--	--	--	--	--	--	--------------------	--	--	--	--	--	--	--	--	--	-----------	--	--	--	--	--	--	--	--	--	---	--	---------------------------------------	--	---	--	---	--	--	--	-----------------------------------	--	------------------	--	------------------------	--

APPENDIX A

SPILL CONTROL PROCEDURES

	Reference (Book Title) Operations/Maintenance Field Services	Task/Document No. 21.10.020
	Section General/Safety	Regulation No/Reference
	Subject Discharges or Spills of Oil or Hazardous Substances; Preventing, Controlling and Reporting of	Effective Date 12/15/99

[Back](#) | [Feedback](#) | [Index](#) | [Search Library](#)
 Hit "CTRL-F" to find text on this page.

▶ **Document History (ISO9001)**

▼ **Document Body**

1.0 PURPOSE AND SCOPE

- 1.1 To establish the policy and procedure for preventing, controlling and reporting of discharges or spills of oil or hazardous substances to the environment in accordance with Company practices and federal, state and local requirements, including Title 40 of the Code of Federal Regulations - Part 112 (Oil Pollution Prevention).
- 1.2 This document pertains to Company personnel, Company and non-company facilities. The spill prevention and control requirements in this Policy and Procedure are Federally mandated guidelines for oil pollution prevention. The Company policy is to also apply these standards, where appropriate, to facilities containing hazardous substances. This is a discretionary application of the standards; however, variations from the standards should be approved by the responsible Director.

2.0 CONTENTS

3.0 POLICY

3.1 GENERAL

- 3.1.1 All Company facilities which could discharge or spill, oil or hazardous substances which may affect natural resources or present an imminent and substantial danger to the public health or welfare including, but not limited to, fish, shellfish, wildlife, shorelines and beaches are subject to the provisions of this document.
- 3.1.2 Oil, for purpose of this document, means oil of any kind or in any form, including but not limited to petroleum hydrocarbon, fuel oil, Y grade, natural gas liquids, condensate, mixed products, sludge, oil refuse and oil mixed with wastes other than dredged spoil (earth and rock). LPG (propane, butane, ethane) is not considered to be oil.
- 3.1.3 Hazardous Substance, for purposes of this procedure, is defined as any chemical or

material that has or should have a Material Safety Data Sheet (MSDS); however, hazardous substances are further defined by the following environmental statutes:

- a. Section 101(N) and Section 102 of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA)
- b. Section 307(a) and Section 311(b)(2)(A) of the Clean Water Act
- c. Section 3001 of the Solid Waste Act (excluding items suspended by Congress)
- d. Section 112 of the Clean Air Act
- e. Section 7 of the Toxic Substance Control Act

3.1.4 The term hazardous substance does not include petroleum hydrocarbon, including crude oil or any fraction thereof and the term does not include natural gas, natural gas liquids (including condensate), liquefied natural gas or synthetic gas usable for fuel (or mixtures of natural gas and such synthetic gas).

3.1.5 Facilities which could discharge or spill, oil or hazardous substances into a watercourse must comply with the applicable federal, state or local laws and regulations. A discharge includes but is not limited to any spilling, leaking, pumping, pouring, emitting, emptying or dumping. A watercourse is any perennial or intermittent river, stream, gully, wash, lake or standing body of water capable of collecting or transporting an oil or hazardous substance.

3.1.6 Facilities which are subject to the requirements stated in this policy are as follows:

a. Non-Transportation Related Facilities

(1) Storage or drip tanks and other aboveground containers (excluding pressurized or inline process vessels) having a capacity in excess of 660 gallons for each single container or an aggregate capacity of 1,321 gallons or more for multiple containers.

(2) Underground storage facilities having a total capacity in excess of 42,000 gallons.

b. Transportation Related Facilities

(1) All vehicles, pipeline facilities, loading/unloading facilities and other mobile facilities which transport oil or hazardous substances.

3.1.7 Each Company location which has facilities subject to paragraph C.1.1 shall have a site specific Spill Prevention Control and Countermeasure Plan (SPCC Plan) which identifies all facilities subject to 40 CFR 112. The plan shall identify all oil and hazardous substance storage vessels (as defined in a.(1) above) at the facility and the spill prevention measures in place to control discharges or spills. This plan shall also identify all regulatory agencies that must be notified in case of a spill.

3.1.8 The facility superintendent is responsible for spill prevention. His/her duties include,

but are not limited to, the following:

- a. Instructing personnel in the operation and maintenance of equipment to prevent the discharge of oil.
- b. Conduct annual briefings for operating personnel at intervals frequent enough to assure adequate understanding of the Spill Plan at that facility.
- c. Briefings should highlight and describe known discharges or spills and recently developed precautionary measures.

3.1.9 Each individual facility is checked annually by the superintendent or designee to determine the potential for discharges or spills of oil or hazardous substances in harmful quantities that violate water quality standards or which may cause a film, sheen or discoloration on the surface of water. All facilities which have the potential for discharging or spilling harmful quantities of oil or hazardous substances into a watercourse are required to have the following preventive measures:

- a. Examination of all tanks, valves and fittings, at least annually, to determine any maintenance requirements.
- b. All tank batteries should, as far as practicable, have a secondary means of containment for the entire contents of the largest single tank plus sufficient freeboard in the containment facility to allow for precipitation.
- c. An annual monitoring and inspection program to prevent accidental spills or discharges into watercourses. This includes annual inspection for faulty systems and monitoring line valves and liquid pipelines for leaks or blowouts.

3.1.10 Any field drainage ditches, road ditches, traps, sumps or skimmers should be inspected at regular scheduled intervals for accumulation of oil or other hazardous substances which may have escaped from small leaks. Any such accumulations should be removed.

3.2 BULK STORAGE TANKS

- 3.2.1 A tank should not be used for storage of oil or hazardous substances unless the material and construction of the tank is compatible with the oil or substance stored and conditions of storage such as pressure and temperature. Buried storage tanks must be protected from corrosion by coatings, cathodic protection or other methods compatible with local soil conditions. Aboveground tanks should be subject to visual inspection for system integrity.
- 3.2.2 The facility superintendent should evaluate tank level monitoring requirements to prevent tank overflow.
- 3.2.3 Leaks which result in loss of oil or hazardous substances from tank seams, gaskets, rivets and bolts sufficiently large to cause accumulation of oil or hazardous substances in diked areas should be promptly corrected.
- 3.2.4 Mobile or portable oil or hazardous substances storage tanks should be positioned or located to prevent the contents from reaching a watercourse. The mobile facilities should be located so their support structure will not be undermined by periodic flooding or washout.

3.3 FACILITY DRAINAGE

- 3.3.1** Make provisions for drainage from diked storage areas where necessary in areas with high precipitation levels. Drainage from diked areas should be restrained by valves or other means to prevent a discharge or spill. Diked areas should be emptied by pumps or ejectors which are manually activated. Valves used for the drainage of diked areas should be of manual, open-and-closed design.
- 3.3.2** Rain water may be drained from diked areas providing drainage water does not contain oil or hazardous substances that may cause a harmful discharge. Drain valves must be closed following drainage of diked areas.
- 3.3.3** When possible, drainage systems from undiked areas should flow into ponds, lagoons or catchment basins designed to retain oil or hazardous substances or return the substances to the facility. Any drainage system which is not designed to allow flow into ponds, lagoons or catchment basins should be equipped with a diversion system that could, in the event of a discharge or spill, contain the oil or hazardous substances on the Site.
- 3.3.4** The principal means of containing discharges or spills is the use of dikes which are constructed wherever regulated quantities of oil or hazardous substances have the potential of reaching a watercourse. The construction of dikes must meet the following requirements:
- a. Capacity must be at least equivalent to the storage capacity of the largest tank of the battery plus sufficient freeboard to allow for precipitation or displacement by foreign materials.
 - b. Small dikes for temporary containment are constructed at valves where potential leaking of oil or hazardous substances may occur.
 - c. Any dike three feet or higher should have a minimum cross section of two feet at the top.
- Other means of containment or spill control include, but are not limited to:
- 3.3.5**
- a. Berms or retaining walls
 - b. Curbing
 - c. Culverting, gutters or other drainage systems
 - d. Weirs, booms or other barriers
 - e. Spill diversion ponds or retention ponds
 - f. Sorbent materials

3.4 TRANSFER OPERATIONS, PUMPING and IN-PLANT/STATION PROCESS

- 3.4.1** Aboveground valves and pipelines should be examined regularly by operating

personnel to determine whether there are any leaks from flange joints, expansion joints, valve glands and bodies, catch pans, pipeline supports, valve locks and metal surfaces.

3.5 FACILITY TANK CAR AND TANK TRUCK LOADING/UNLOADING RACK

- 3.5.1 Rack area drainage which does not flow into a catchment basin or treatment facility designed to handle spills should have a quick drainage system for use in tank truck loading and unloading areas. The containment system should have a maximum capacity of any single compartment of a truck loaded or unloaded in the station.
- 3.5.2 Aboveground piping that has potential for damage by vehicles entering the Site should be protected by logically placed warning signs or by concrete-filled pipe barriers.
- 3.5.3 Loading and unloading areas should be provided with an interlocked warning light, grounding shutdown, physical barrier system or warning signs to prevent vehicular departure before complete disconnect of flexible or fixed transfer lines. All drains and outlets of any truck should be closely examined for leakage prior to filling and departure. All drains and outlets that may allow leakage should be tightened, adjusted or replaced to prevent liquid leakage while in transit.

NOTE: LPG loading facilities and remote field loading of condensate are exempt from the C.5 requirements of this document.

4.0 PROCEDURE

4.1 Identifying, Containing and Initial Reporting of a Discharge or Spill of Oil or Hazardous Substance Any Employee

- 4.1.1 Upon noticing a discharge or spill of an oil or hazardous substance in any quantity shall immediately contain the release (if safe to do so) and notify the facility superintendent, dispatcher or other designee. Releases must be reported to gas control in the following three circumstances:

I. The Following Situations Always Require IMMEDIATE Reporting to Gas Control:

1. Release reaches or may reach surface water: (pond, lake, wash or ground water)
2. Release leaves Williams property
3. Release is of questionable nature (i.e., unknown product, unknown hazards)

II. Onsite Releases of Certain Common Industrial Materials Above 10 Gallon Threshold Are Reportable.

Releases that do not migrate off-site or reach surface water may require reporting as well. All releases of 10 gallons or greater of the following materials should be contained and promptly reported to Gas Control:

- Ammonia
- Antifreeze
- Amine

- Chromate Mixtures
- Condensate
- Glycol
- Lube Oil
- Methanol
- Sulfuric Acid
- Sodium Hydroxide
- Natural Gas Liquids
- Other Hydrocarbon Products
- Natural Gas (1 MMSCF)

III. Releases of Certain Other Materials Reportable:

Releases of the following materials above the indicated amount should be reported to gas control:

- PCB's (Concentration > 50 ppm) - any amount
- Mercaptan (Ethyl Mercaptan) - 1 lb.
- Mercury - 1 lb.
- Hydrogen Sulfide - 100 lbs.
- Pesticides - 1 lb.
- Other Material Not Listed - 1 lb.

NOTE 1: A release includes material released (intentionally or unintentionally) to air, water or soil. When notifying Gas Control of a Release, be prepared to provide information on the type of material spilled, amount released, weather conditions, time and date of release, person discovering release and measures taken to control the release.

NOTE 2: Refer to Attachment A for containment procedures.
Facility Superintendent, Controller or Designee

4.1.2 Contacts Gas Control immediately by telephone and provides the following information:

- a. Name of company facility and/or location of facility and nature of discharge or spill
- b. Description and quantity of emission or substance discharged
- c. Description of the circumstances causing the discharge or spill
- d. Name, title and telephone number of person initially reporting the discharge or spill and person reporting to Gas Control
- e. Action taken or being taken to mitigate and correct discharge or spill
- f. Water bodies or streams involved
- g. Time and duration of discharge or spill

h. Outside involvement during discharge or spill (public government agencies, etc. See Emergency Operating Procedure Manuals)

Gas Control Personnel

- 4.1.3 Advises Environmental Affairs departments immediately by telephone concerning the incident including any incidents reported by persons not employed with the Company.

NOTE: If Gas Control is contacted by a person not employed with the Company, the necessary information is obtained as indicated in D.1.2 and the Superintendent and Environmental Affairs are immediately contacted to begin containment and clean-up of the discharge or spill.

- 4.1.4 If Environmental Affairs cannot be contacted, notifies Director over Environmental Affairs.

Facility Superintendent

- 4.1.5 Coordinates containment and clean-up of discharge or spill, keeping the responsible Director Informed.
- 4.1.6 Coordinates containment and clean-up of discharge or spill, keeping the responsible Director Informed. If the discharge or spill is too large for Company personnel to contain, contacts qualified local contractors for assistance. (See Emergency Operating Procedure Manuals tab #11, contractors with available equipment and services).

- 4.1.7 Advises Environmental Affairs by telephone if emergency containment or clean-up assistance from a state agency or a response team from the U.S. Coast Guard is required.

Environmental Affairs

- 4.1.8 Assesses reporting requirements to state and federal agencies (contacts Legal Department and Right-of-Way Department, if appropriate). (See Emergency Operating Procedure Manuals).
- 4.1.9 Makes appropriate contacts with National Response Center and state and local agencies, when necessary.
- 4.1.10 If spill is significant, dispatches Environmental Specialist to scene to oversee cleanup and reporting responsibilities.

4.2 SUBMITTING WRITTEN NOTIFICATION OF A DISCHARGE OR SPILL
Facility Superintendent or Designee

- 4.2.1 Completes a written description of the incident as soon as possible after initial notification is given, which should include the following:
- a. Time and date of discharge or spill
 - b. Facility name and location
 - c. Type of material spilled
 - d. Quantity of material spilled

e. Area affected

f. Cause of spill

g. Special circumstances

h. Corrective measures taken

i. Description of repairs made

j. Preventative measures taken to prevent recurrence.

4.2.2 Forwards the completed written description to Environmental Affairs. Retains a copy for future reference.

NOTE: Environmental Affairs, in coordination with the Legal Department, if necessary, submits written reports to government agencies.

**ATTACHMENT A
DISCHARGE OR SPILL CONTAINMENT PROCEDURES AND MATERIALS**

TYPE OF FACILITY WHERE THE DISCHARGE OR SPILL OCCURS	CONTAINMENT PROCEDURES	MATERIALS USED FOR CONTAINMENT
A. Oil Pipeline (as defined in C.1.4)	1. Closes appropriate block valves. 2. Contains Discharge or spill by: Ditching covering, applying sorbents, constructing an earthen dam or burning. 3. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning.	1. Straw 2. Loose Earth 3. Oil Sorbent 3M Brand 4. Plain Wood chips 5. Sorb-Oil Chips Banta Co. 6. Sorb-Oil Swabs Banta Co. 7. Sorb-Oil Mats Banta Co. 8. Or Equivalent Materials
B. Vehicle	1. Contains discharge or spill by: ditching, covering surface with dirt, constructing earthen dams, apply sorbents or burning. 2. Notifies immediately Environmental Affairs and if there is any imminent danger to local residents; notifies immediately the highway patrol or local police officials.	

	<p>3. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning.</p> <p>Note: Any vehicle carrying any hazardous or toxic substance will carry a shovel or other ditching device to contain a spill. If the vehicle has sufficient room, sorbent materials should also be carried.</p>
<p>C. Bulk Storage Tanks or any other Facilities</p>	<p>1. Contains discharge or spill by: ditching, covering, applying sorbents, constructing an earthen dam or burning.</p> <p>2. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning.</p>

[Back](#) | [Feedback](#) | [Index](#) | [Search Library](#)

If you have questions, suggestions, comments or concerns regarding the SETS Library, please contact [Documentation Services](#).

APPENDIX B

**NMOCD NOTIFICATION OF FIRE, BREAKS, SPILLS, LEAKS,
AND BLOWOUTS**

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 South First, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
2040 South Pacheco, Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources

Oil Conservation Division
2040 South Pacheco
Santa Fe, NM 87505

Form C-141
Revised March 17, 1999

Submit 2 Copies to appropriate
District Office in accordance
with Rule 116 on back
side of form

Release Notification and Corrective Action

OPERATOR

Initial Report Final Report

Name of Company		Contact
Address		Telephone No.
Facility Name		Facility Type
Surface Owner	Mineral Owner	Lease No.

LOCATION OF RELEASE

Unit Letter	Section	Township	Range	Feet from the	North/South Line	Feet from the	East/West Line	County

NATURE OF RELEASE

Type of Release	Volume of Release	Volume Recovered
Source of Release	Date and Hour of Occurrence	Date and Hour of Discovery
Was Immediate Notice Given? <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Not Required	If YES, To Whom?	
By Whom?	Date and Hour	
Was a Watercourse Reached? <input type="checkbox"/> Yes <input type="checkbox"/> No	If YES, Volume Impacting the Watercourse.	
If a Watercourse was Impacted, Describe Fully.*		
Describe Cause of Problem and Remedial Action Taken.*		
Describe Area Affected and Cleanup Action Taken.*		

I hereby certify that the information given above is true and complete to the best of my knowledge and understand that pursuant to NMOCD rules and regulations all operators are required to report and/or file certain release notifications and perform corrective actions for releases which may endanger public health or the environment. The acceptance of a C-141 report by the NMOCD marked as "Final Report" does not relieve the operator of liability should their operations have failed to adequately investigate and remediate contamination that pose a threat to ground water, surface water, human health or the environment. In addition, NMOCD acceptance of a C-141 report does not relieve the operator of responsibility for compliance with any other federal, state, or local laws and/or regulations.

Signature:		OIL CONSERVATION DIVISION	
Printed Name:		Approved by District Supervisor:	
Title:		Approval Date:	Expiration Date:
Date:	Phone:	Conditions of Approval:	Attached <input type="checkbox"/>

* Attach Additional Sheets If Necessary

OIL CONSERVATION DIV.
01 JUL 23 PM 1:06



Environmental Affairs
188 CR 4900
Bloomfield, NM 87413
505/634-4956
505/632-4781 Fax

July 13, 2001

Mr. Jack Ford
New Mexico Oil Conservation Division
2040 South Pacheco
Santa Fe NM 87505

Re: Discharge Plan Application Renewal and Filing Fee

Dear Mr. Ford:

Enclosed please find copies of Discharge Plan application renewal and check number 1000318741 for \$700.00 to cover the filling fee for the following Williams Field Services (WFS) Compressor Stations:

- Coyote Springs *GW-250*
- Kernaghan *GW-271*
- Pritchard - *GW-274*
- Trunk A - *GW-248*
- Trunk B - *GW-249*
- Trunk C - *GW-257*
- 32-9 CDP - *GW-091*

Williams Field Services appreciates your assistance in handling these applications and fees. If you have any questions or require additional information, please contact me at 505/634/4956.

Thank you,

A handwritten signature in black ink, appearing to read "Clara M Garcia".

Clara M Garcia
Environmental Compliance

Xc: Denny Foust, Aztec, OCD Dist III

ACKNOWLEDGEMENT OF RECEIPT
OF CHECK/CASH

I hereby acknowledge receipt of check No. [REDACTED] dated 7/11/01
or cash received on _____ in the amount of \$ 700.00

from Williams Field Services
Coyote Springs - 250 Prichard - 274 Trunk B - 249 32-9 CDP-09
for Kernaghan - 211 Trunk A - 248 Trunk C - 257

Submitted by: [Signature] Date: 7/23/01
(Family Name) (DP No.)

Submitted to ASD by: _____ Date: _____

Received in ASD by: _____ Date: _____

Filing Fee New Facility _____ Renewal
Modification _____ Other _____
(quantity)

Organization Code 521.07 Applicable FY 2001

To be deposited in the Water Quality Management Fund.

Full Payment or Annual Increment _____

THIS MULTI-TONE AREA OF THE DOCUMENT CHANGES COLOR GRADUALLY AND EVENLY FROM DARK TO LIGHT WITH DARKER AREAS BOTH TOP AND BOTTOM. IT ALSO HAS A REFLECTIVE WATERMARK ON THE BACK.



WILLIAMS FIELD SERVICES COMPANY
1600 South Baltimore Avenue * P.O. Box 645 * Tulsa, OK 74101-0645

30-2322-1719
A/C 9401876

DATE: 07/11/2001

PAY TO THE ORDER OF:

PAY *****\$700.00

NEW MEXICO OIL CONSERVATION DI
NM WATER QUALITY MGMT FUND
2040 S PACHECO

SANTA FE
United States

NM 87504

Bank One, NA
Illinois

[Signature]

Authorized Signer



NEW MEXICO ENERGY, MINERALS and NATURAL RESOURCES DEPARTMENT

GARY E. JOHNSON
Governor
Jennifer A. Salisbury
Cabinet Secretary

February 9, 2001

Lori Wrotenbery
Director
Oil Conservation Division

CERTIFIED MAIL
RETURN RECEIPT NO. 5051 0074

Ms. Clara M. Garcia
Williams Field Services
188 CR 4900
Bloomfield, New Mexico 87413

RE: Discharge Plan Renewal Notice for Williams Field Services Facilities

Dear Ms. Garcia:

Williams Field Services has the following discharge plans, which expire during the current calendar year.

GW-060 expires 3/21/2001 – Milagro Compressor Station
GW-233 expires 4/1/2001 – La Jara Compressor Station
GW-061 expires 6/6/2001 – Horse Canyon Compressor Station
GW-062 expires 6/6/2001 – Manzanares Compressor Station
GW-063 expires 6/6/2001 – Pump Mesa Compressor Station
GW-064 expires 6/6/2001 – Middle Mesa Compressor Station
GW-079 expires 6/21/2001 – Wild Horse Compressor Station
GW-078 expires 6/21/2001 - 5-Points Compressor Station
GW-250 expires 8/9/2001 – Coyote Springs Compressor Station
GW-249 expires 8/9/2001 – Trunk B Booster Compressor Station
GW-248 expires 8/9/2001 – Trunk A Booster Compressor Station
GW-257 expires 9/18/2001 – Trunk C Compressor Station
GW-256 expires 9/18/2001 – Koch-Gardner Compressor Station
GW-087 expires 11/27/2001 – Cedar Hill Compressor Station
GW-271 expires 12/17/2001 – Kernaghan Compressor Station
GW-274 expires 12/17/2001 – Pritchard Straddle Compressor Station
GW-273 expires 12/17/2001 – Moore Compressor Station
GW-272 expires 12/17/2001 – Kernaghan B-8 Compressor Station

WQCC 3106.F. If the holder of an approved discharge plan submits an application for discharge plan renewal at least 120 days before the discharge plan expires, and the discharger is not in violation of the approved discharge plan on the date of its expiration, then the existing approved discharge plan for the same activity shall not expire until the application for renewal has been approved or disapproved. A discharge plan continued

under this provision remains fully effective and enforceable. An application for discharge plan renewal must include and adequately address all of the information necessary for evaluation of a new discharge plan. Previously submitted materials may be included by reference provided they are current, readily available to the secretary and sufficiently identified to be retrieved. [12-1-95]

The discharge plan renewal application for each of the above facilities is subject to WQCC Regulation 20NMAC 6.2.3114. Every billable facility submitting a discharge plan renewal will be assessed a fee equal to the filing fee of \$100.00. After January 15, 2001 renewal discharge plans require a flat fee equal to the flat fee schedule for gas processing facilities pursuant to revised WQCC Regulations 20NMAC 6.2.3114. A copy of the revised fee schedule is included for your assistance. The \$100.00 filing fee is to be submitted with each discharge plan renewal application and is nonrefundable.

Please make all checks payable to: **NMED-Water Quality Management** and addressed to the OCD Santa Fe Office. Please submit the original discharge plan renewal application and one copy to the OCD Santa Fe Office and one copy to the OCD Aztec District Office. **Note that the completed and signed application form must be submitted with your discharge plan renewal request.** A complete copy of the regulations is also available on NMED's website at www.nmenv.state.nm.us.

If any of the above-sited facilities no longer has any actual or potential discharges and a discharge plan is not needed, please notify this office. If the Williams Field Services has any questions, please do not hesitate to contact Mr. Jack Ford at (505) 476-3489.

Sincerely,



Roger C. Anderson
Oil Conservation Division

cc: OCD Aztec District Office

Work copy

SITE NAME	DISCHARGE PLAN #	CURRENT OCD PLAN # of Units/ HP	ACTUAL INSTALLS # of Units/ HP	AQB PERMITTED # of Units/ HP	
Category 1 - Update OCD Plans for actual compression; AQB permit allows additional installations					
OK 31-6 #1	X	GW-118	6 units/990 HP ea <i>5+4</i>	15 units/1370 HP ea	16 units/1370 HP ea
No Mod. request → OK 32-7 #1	X	GW-117	4 units/895 HP ea <i>ok</i>	6 units/1357 HP ea	8 units/1357 HP ea
No Mod. request → OK 32-8 #2	X	GW-111	4 units/895 HP ea <i>4+2</i>	5 units/1357 HP ea	9 units/1357 HP ea
OK HORSE CYN. CDP	ok	GW-61	4 units/895 HP ea <i>14</i>	6 units/1390 HP ea	14 units/1390 HP ea
OK MIDDLE MESA CDP	X	GW-64	10 units/895 HP ea <i>10+4</i>	19 units/1362 HP ea	20 units/1362 HP ea
OK PUMP MESA CDP	ok	GW-63	6 units/895 HP ea <i>6+6</i>	10 units/1363 HP ea	14 units/1363 HP ea
OK TRUNK N C.S.	ok	GW-306	5 units/1140 HP ea	6 units/1140 HP ea	8 units/1368 HP ea
No Mod. request → OK TRUNK L C.S.	X	GW-180	6 units/990 HP ea	10 units/990 HP ea	14 units/1131 HP ea
Category 2 - OCD Plan currently reflects all AQB permitted units; however, all units not yet installed					
29-6 #4CDP		GW-122	10 units; total site HP 10,980 <i>4+3</i>	6 units/1377 HP ea.; 1 unit/1148 HP	9 units/1377 HP ea.; 1 unit/1148 HP
32-9 CDP		GW-91	8 units/1379 HP ea	5 units/1379 HP ea	8 units/1379 HP ea
OK CEDAR HILL CDP		GW-87	10 units/1386 HP ea <i>ok 5+1</i>	7 units/1386 HP ea	10 units/1386 HP ea
KERNAGHAN B-8 STRADDLE		GW-272	2 units/764 HP ea	1 unit/764 HP	2 units/764 HP ea
MANZANARES CDP		GW-62	4 units/895 HP ea	3 units/895 HP ea	4 units/1300 HP ea
MOORE STRADDLE		GW-273	2 units/ 778 HP ea	1 unit/ 778 hp	2 units/ 778 hp ea
NAVAJO CDP		GW-182	4 units/2946 HP ea	3 units/2916 HP ea	4 units/2916 HP ea
TRUNK A BOOSTER C.S.		GW-248	6 units/1367 HP ea	3 units/1367 HP ea	6 units/1369 HP ea
TRUNK B BOOSTER C.S.		GW-249	7 units/1367 HP ea	3 units/1367 HP ea	7 units/1367 HP ea
MARTINEZ DRAW		GW-308	2 units/1380 HP ea	1 unit/1380 HP	2 units/1232 HP ea
QUINTANA MESA		GW-309	2 units/1380 HP & 1151 HP	1 unit/1232 HP	2 units/1232 HP & 1118 HP
Category 3 - Update OCD Plans for actual compression; all AQB permitted units installed					
29-6 #2CDP	X	GW-121	5 units/895 HP ea. <i>5+2</i>	12 units/1370 HP ea.	12 units/1370 HP ea.
ROSA #1 CDP	X	GW-292	1 unit/1372 HP	2 unit/1372 HP	2 units/1371 HP ea
TRUNK M C.S.	X	GW-181	1 unit/990 HP	2 units/1378 HP ea	2 units/1378 HP ea
PIPKIN		GW-120	2 units/856 HP total	1 unit/1403 HP	1 unit/1403 HP
LA JARA FIELD	X	GW-233	1 Solar T-3000/ 2831 hp; 2 Solar T-4000/ 2897 hp ea.	2 Solar T-4000, 2 Solar T-4700S, 1 Solar T-4700=total 17,700 hp	2 Solar T-4000, 2 Solar T-4700S, 1 Solar T-4700=total 17,700 hp

No Mod. request → OK
 No Mod. request → OK
 No Mod. request → OK

Notice of add'l. units 7-97 - No app.
 Notice on renewal
 (mod. to 14 units '96)
 (14 units in renewal app. '97)
 (6 units in appl. '95)
 (up to 8 units in renewal app. '98)

OK

-change hp rating



295 Chipeta Way
P.O. Box 58900
Salt Lake City, UT 84108
801/584-6543
801/584-7760

September 14, 1998

Mr. Jack Ford
New Mexico Oil Conservation Division
2040 South Pacheco Street
Santa Fe, New Mexico 87505

Re: Underground Line Testing Results at various Williams Field Services Facilities

Dear Mr. Ford:

Enclosed, please find a copy of the results of the underground line testing that was performed at the Williams Field Services (WFS) facilities listed below.

Trunk C (GW-259)	Carracas (GW-112)	30-5 (GW-108)
Hart Mountain (GW-208)	32-8#3 (GW-116)	30-8 (GW-133)
Decker Junction (GW-134)	Rosa #1 (GW-292)	Trunk B (GW-249)
Aztec (GW-155)	Manzanaras (GW-62)	32-9 (GW-91)
Cedar Hill (GW-87)	Simms Mesa (GW-68)	Kernaghan (GW-271)
Horse Canyon (GW-61)	Trunk A (GW-248)	Trunk N (GW-306)
32-7 (GW-117)	29-7 (GW-136)	32-8#2 (GW-111)

Also Added: Moore (GW-273) Pritchard (GW-274) Kernaghan B-8 (GW-272)

If you have any questions concerning this submittal, please call me at 801-584-6543.

Sincerely,



Ingrid Deklau
Environmental Specialist

XC: Denny Foust, NM OCD

ACKNOWLEDGEMENT OF RECEIPT
OF CHECK/CASH

I hereby acknowledge receipt of check No. [redacted] dated 2/5/97,

or cash received on _____ in the amount of \$ 150.00

from Williams Field Services

for Trunk A - GW 248 Trunk B - GW 249 Coyote Springs GW-250

Submitted by: _____ Date: _____

Submitted to ASD by: R. Anderson Date: 3/19/97

Received in ASD by: _____ Date: _____

Filing Fee New Facility _____ Renewal _____
Modification _____ Other _____

Organization Code 521.07 Applicable FY 97

To be deposited in the Water Quality Management Fund.

Full Payment _____ or Annual Increment _____

WILLIAMS FIELD SERVICES COMPANY
ONE OF THE WILLIAMS COMPANIES
P. O. Box 58900
Salt Lake City, Utah 84158-0900

Chase Manhattan Bank Delaware
1201 Market Street
Wilmington DE 19801
62-26 5736-09
311

DATE	CHECK NO.	CHECK AMOUNT
02/05/97	[redacted]	150.00

PAY
NE HUNDRED FIFTY AND 00/100-----

TO THE ORDER OF
NMED-WATER QUALITY MANAGEMENT
2040 SO. PACHECO
SANTA FE NM 87505

Williams Field Services Company
James A. Hill
VICE PRESIDENT
AUTHORIZED REPRESENTATIVE





NEW MEXICO ENERGY, MINERALS
& NATURAL RESOURCES DEPARTMENT

OIL CONSERVATION DIVISION
2040 South Pacheco Street
Santa Fe, New Mexico 87505
(505) 827-7131

January 28, 1997

CERTIFIED MAIL
RETURN RECEIPT NO. P-288-258-748

check request

\$150

16-112-17530-40-80116

FE-2

Ms. Leigh E. Gooding
Williams Field Services
P.O. Box 58900, M.S. 2G1
Salt Lake City, Utah 84158-0900

RE: Discharge Plan Filing Fees
Williams Field Services (WFS)
GW-248, GW-249, and GW-250
San Juan County, New Mexico

Dear Ms. Gooding:

On August 16, 1996, WFS, received, via certified mail, three discharge plan approval letters dated August 9, 1996 from the New Mexico Oil Conservation Division (OCD) for discharge plans GW-248 or "Trunk A", GW-249 or "Trunk B", and GW-250 or "Coyote Springs" compressor stations. Each discharge plan has a filing fee and a flat fee as described in WQCC Section 3114 (see attachment), the filing fee of \$50 for each of the above mentioned facilities has not been received by the OCD according to our records. **Please note:** Each of the approval letters dated August 9, 1996 from OCD had errors in them that indicated that the \$50 filing fee had been received.

WFS must submit each \$50 filing fee (Total amount of \$150) in full by February 28, 1997 in order to be in compliance with Water Quality Control Commission Regulation 3114.B.6. Please make all checks payable to: **NMED-Water Quality Management** and addressed to the OCD Santa Fe Office.

2/1 NT

If you have any questions regarding this matter, please contact me at (505)-827-7152 or Mr. Patricio Sanchez at (505) 827-7156.

Sincerely,

Roger Anderson
Environmental Bureau Chief

RCA/pws

xc: Mr. Denny Foust- Aztec OCD District
attachment 20 NMAC 6.2.3114

cc: 16 79109
R. Baumbach
SPECIAL

Check to be picked up by
Earlene x 7084 2/3/97

P.O. Box 58900 Salt Lake City, Utah 84158-0900

November 13, 1996

Mr. Pat Sanchez
NMOCD
2040 South Pacheco Street
Santa Fe, New Mexico 87505

RECEIVED

NOV 18 1996

Environmental Bureau
Oil Conservation Division

RE: Response to Discharge Inspection Reports

Dear Mr. Sanchez:

Milagro GW-60

8. Lab wastes have been characterized and accepted for disposal per Philip Environmental's report dated, October 24, 1996.

Coyote Springs GW-250

1. The lube oil drum has been placed on pad and curb type containment.
2. Oil-absorbent pads and catch basins will be used to contain leaking lube oil.
3. A catch basin has been placed underneath the condensate storage tank load line.
6. Operators have been instructed in how to inspect leak detection,
7. Below-grade process/wastewater piping is pressure tested at the time of installation.
10. Oil spills from the compressor will be contained using oil-absorbent pads and catch basins.

Trunk A Compressor Station GW-248

No compliance issues noted.

Trunk B Compressor Station GW-249

No compliance issues noted.

Trunk C Compressor Station GW-257

No compliance issues noted.

Lateral N-30 GW-256

3. The condensate above-ground storage tank is not placed on an impermeable type pad. The tank and valving is visually inspected at least annually as stated in the WFS Policy and Procedures for Spill Prevention (Appendix B of the Discharge Plan). In lieu of the impermeable type pad, WFS will clean out and visually inspect the interior of the tank at the time of the Discharge plan renewal.
6. The below-grade sump is inspected monthly and documented in a monthly inspection log retained on site.
7. A copy of the hydrostatic test of underground process/wastewater piping is attached.

If you have any questions or require additional information, please do not hesitate to contact me at (801) 584-6543.

Sincerely,



Leigh E. Gooding
Sr. Environmental Specialist

cc: Denny Foust

PIPELINE FACILITY TEST REPORT

FORM 310 1239 (1-94)

WORK ORDER NO.


FACILITY DESCRIPTION			
2-NAME OF FACILITY Gardner N-30	3-FACILITY LOCATION AREA _____ DISTRICT _____ COUNTY/STATE _____		
4-FACILITY TYPE <input type="checkbox"/> Gathering <input type="checkbox"/> Line Pipe <input type="checkbox"/> Hot Tap <input type="checkbox"/> Fabrication <input checked="" type="checkbox"/> Plant/Station <input type="checkbox"/> Line Junct. <input type="checkbox"/> Other _____	<input type="checkbox"/> Transmission <input type="checkbox"/> Vessel <input type="checkbox"/> Well Setting	3A-SECTION _____ TOWNSHIP _____ RANGE _____	5-PIPE MANUFACTURER _____
7-DESCRIPTION OF PORTION TESTED (FROM - TO)		6-PIPE DATA DIAMETER 40'-6" 80ft-12"-120ft-8" SPEC. & GRADE _____	WALL THICKNESS _____ LENGTH OF TEST SECTION _____

TEST SPECIFICATIONS			
8-TYPE OF TEST <input type="checkbox"/> Strength <input checked="" type="checkbox"/> Leak <input checked="" type="checkbox"/> Both	9-TEST STATIONS AND ELEVATION	BEGIN LOCATION _____	END LOCATION _____
10-REASON FOR TEST <input checked="" type="checkbox"/> New Facility <input type="checkbox"/> Pre-Test <input type="checkbox"/> Repair <input type="checkbox"/> Retest		HIGH POINT _____	LOW POINT _____
11-PRESSURE DATA	PRELIMINARY LEAK PRESSURE _____	BEGIN STATION MINIMUM PRESSURE _____	END STATION MINIMUM PRESSURE _____
	REQUIRED TEST PRESSURE 750#	HIGH POINT MINIMUM PRESSURE _____	LOW POINT MAXIMUM PRESSURE _____
	REQUIRED TEST DURATION 4 HRS	TEST LIMITATIONS (VALVES, FITTINGS, ETC.) _____	

TEST RESULTS			
12-TEST START DATE 9-25-96 HOUR 3:45pm	13-TEST COMPLETED DATE 9-25-96 HOUR 7:45pm	14-WEATHER cloudy turning to night fall	
15-COMMENTS _____			

TIME	D.W. PRESSURE	AMB. TEMP. °F	REMARKS
3:45	787	75	on test sunny
4:00	800	75	"
4:15	800	75	getting cloudy
4:30	805	72	cloudy
4:45	805	72	"
5:00	800	71	"
5:15	800	72	partly cloudy
5:30	790	72	"
5:40	790	72	pressured up to 846# partly cloudy
6:00	846	72	
6:15	840	69	
6:30	838	69	
6:45	830	69	
7:00	805 818	69	sunny going down
7:15	805	69	getting dark
7:30	792	63	dark
7:45	780	59	off test

DATA TAKEN BY: <i>W. A. [Signature]</i>	TEST APPROVED BY: _____	DATE: _____
TEST WITNESSED BY: _____	TEST COMPANY: Flint Eng.	



TEST CHART
 DREAD WIGGINS
 #12640
 12.8" D.
 7.45 P.
 9.25 '96

CHECKER
 853534
 3.45 P.
 9.25 '96

W.M. Gardner
 T-150

FORM 910 1891 (8-93)

TEST CHART DATA

DATE: 9-25-96 W.O.#:

FACILITY: Gardner U-30 MEDIUM:


PORTION TESTED: Suction & discharge

TEST START: TIME: 120818" - 50ft-6"

TEST END: TIME: 3.45pm D. W. PRESS. 7.82 #

DATA TAKEN BY: W.M. Gardner D. W. PRESS. 7.80 #

WITNESSED BY: W.M. Gardner



TEST CHART DATA

DATE: 9/23/68 W.O.#: 1171

FACILITY: 1171

PORTION TESTED: 1171

TEST START: TIME: 11:35 A

TEST END: TIME: 11:35 P

DATA TAKEN BY: [Signature]

WITNESSED BY: [Signature]

D.W. PRESS. D.W. PRESS.

SIZE: 1/2" STK

W.O.#: 1171

MEDIUM: AIR

TESTER: 1171

FORM 910 891 (8-59)

TEJAS
INSTRUMENT ENGINEERS

TEST NUMBER: _____

TIME PUT ON: _____

TIME PUT OFF: _____

TUBE OR ORIF. SIZE: _____

TIME TAKEN OFF: _____

DATE TAKEN OFF: _____

MW-AMP 50



NEW MEXICO ENERGY, MINERALS
& NATURAL RESOURCES DEPARTMENT

OIL CONSERVATION DIVISION
2040 South Pacheco Street
Santa Fe, New Mexico 87505
(505) 827-7131

November 7, 1996

CERTIFIED MAIL
RETURN RECEIPT NO. P-288-258-674

Ms. Leigh E. Gooding
Williams Field Services
P.O. Box 58900, M.S. 2G1
Salt Lake City, Utah 84158-0900

**RE: Inspection Reports for GW-60,
GW-248, GW-249, GW-250,
GW-256, and GW-257
San Juan County, New Mexico**

Dear Ms. Gooding:

The discharge plan inspection reports for the above captioned Williams Field Services Facilities are enclosed. Williams shall respond to each of the issues for each facility within 30 days of receipt of this letter and the enclosed inspection reports. Please send a copy of your response to OCD Santa Fe and the OCD Aztec District Office.

Williams Field Services continued commitment to the environmental quality of the State of New Mexico is appreciated. The OCD appreciates the professional conduct of WFS operations personnel who accompanied us during the inspections.

If you have any questions in the meantime feel free to give me a call at (505)-827-7156.

Sincerely,

Patricio W. Sanchez
Petroleum Engineering Specialist,
Environmental Bureau-OCD

xc: Mr. Denny Foust - OCD Aztec District Office.

DISCHARGE PLAN INSPECTION

FACILITY NAME: Trunk B "GW-249" LOCATION: SW/4 SW/4
Section 28, Township 31 North, Range 8 West NMPM
San Juan County, N.M.

DATE: 10/26/96 OWNER: Williams Field Services.

OCD INSPECTORS: Denny Faust and Pat Sanchez
"New Facility Discharge Plan"

1. **Drum Storage:** All drums containing materials other than fresh water must be stored on an impermeable pad and curb type containment. All empty drums should be stored on their sides with the bungs in place and lined up on a horizontal plane. Chemicals in other containers such as sacks or buckets should also be stored on an impermeable pad and curb type containment.

All drums and chemical containers shall be clearly labeled to identify their contents and other emergency information necessary if they were to rupture, spill, or ignite.

No Compliance issues.

2. **Process Areas:** All process and maintenance areas which show evidence that leaks and spills are reaching the ground surface must be either paved and curbed or have some type of spill collection device incorporated into the design.

No Compliance issues.

3. **Above Ground Tanks:** All above ground tanks which contain fluids other than fresh water must be bermed to contain a volume of one-third more than the total volume of the largest tank or of all interconnected tanks. All new facilities or modifications to existing facilities must place the tank on an impermeable type pad.

No Compliance issues.

4. **Above Ground Saddle Tanks:** Above ground saddle tanks must have impermeable pad and curb type containment unless they contain fresh water or fluids that are gases at atmospheric temperature and pressure.

No Compliance issues.

5. **Tank Labeling:** All tanks should be clearly labeled to identify their contents and other emergency information necessary if the tank were to rupture, spill, or ignite.

No Compliance issues.

6. **Below Grade Tanks/Sumps:** All below grade tanks, sumps, and pits must be approved by the OCD prior to installation or upon modification and must incorporate secondary containment and leak-detection into the design. All pre-existing sumps and below-grade tanks that do not have secondary containment and leak detection must demonstrate integrity on an annual basis. Integrity tests include pressure testing to 3 pounds per square inch above normal operating pressure and/or visual inspection of cleaned out tanks /or sumps.

No Compliance issues.

7. **Underground Process/Wastewater Lines:** All underground process/wastewater pipelines must be tested to demonstrate their mechanical integrity at present and then every 5 years there after. Companies may propose various methods for testing such as pressure testing to 3 pounds per square inch above normal operating pressure or other means acceptable to the OCD. The OCD will be notified at least 72 hours prior to all testing so that an OCD representative may witness the testing.

No Compliance issues.

8. **Onsite/Offsite Waste disposal and storage practices,** are all non-exempt wastes properly characterized and disposed of? Does the facility have an EPA hazardous waste number?

No Compliance issues.

9. **Class V Wells:** Leach fields and other wastewater disposal systems at OCD regulated facilities which inject fluid other than sewage below the surface are considered Class V injection wells under the EPA UIC program. All class V wells will be closed unless, it can be demonstrated that protectable groundwater will not be impacted in the reasonably foreseeable future. Class V wells must be closed through the Santa Fe Office. The OCD allows industry to submit closure plans which are protective of human health, environment and groundwater as defined by the WQCC, and are cost effective.

No Compliance issues.

10. **Housekeeping:** All systems designed for spill collection/prevention should be inspected to ensure proper operation and to prevent overtopping or system failure. Any contaminated soils that are collected at the facility will be tested for hazardous constituents, and after receiving OCD approval, will be disposed of at an OCD approved site.

No Compliance issues.

11. **Spill Reporting:** All spills/releases shall be reported pursuant to OCD Rule 116 and WQCC 1203 to the OCD District Office.

No Compliance issues.

12. **Does the facility have any other potential environmental concerns/issues?**

No Compliance issues.

13. **Does the facility have any other environmental permits - i.e. SPCC, Storm water Plan, etc?**

Not asked of operations people - Did have New Mexico Air Quality Permit posted.

WFS

GW-249 (PHOTOS BY OCD)




PHOTO NO. 1

DATE: 10/21/96



PHOTO NO. 2

DATE: 10/21/96

WFS

GW-249 (PHOTOS BY OCD)



PHOTO NO. 3

DATE: 10/21/96

~~NO
Photo Number~~

PHOTO NO. 4

DATE: 10/21/96

ACKNOWLEDGEMENT OF RECEIPT
OF CHECK/CASH

I hereby acknowledge receipt of check No. dated 8/26/96
or cash received on in the amount of \$ 1380.00
from Williams Field Services
for Trunk B C.S. GW-249

Submitted by: Date:
Submitted to ASD by: R. Anderson Date: 10/18/96
Received in ASD by: R. Kral Date: 11/23/96

Filing Fee New Facility Renewal
Modification Other

Organization Code 521.07 Applicable FY 97

To be deposited in the Water Quality Management Fund.

Full Payment or Annual Increment

WILLIAMS FIELD SERVICES COMPANY 
ONE OF THE WILLIAMS COMPANIES
P. O. Box 58900
Salt Lake City, Utah 84158-0900

Chase Manhattan Bank Delaware
1201 Market Street
Wilmington DE 19801

62-26 5736-09
311

DATE	CHECK NO.	NET AMOUNT
08/26/96	<u> </u>	1380.00

PAY
ONE THOUSAND THREE HUNDRED EIGHTY AND 00/100-----

TO THE
ORDER
OF
WQCC
OIL CONSERVATION DIVISION
2040 S. PACHECO
SANTA FE NM 87505

Williams Field Services Company

VICE PRESIDENT
AUTHORIZED REPRESENTATIVE



Williams Field Services Company

9810 WQCC

33139

08/26/96


INVOICE NUMBER	DESCRIPTION	INVOICE DATE	AMOUNT	DISCOUNT	NET AMOUNT
80996B Gw-249	TRUNCK B COMP STA	08/09/96	1380.00	0.00	1380.00
			1380.00	0.00	1380.00

PLEASE DETACH BEFORE DEPOSITING

WILLIAMS FIELD SERVICES
ONE OF THE WILLIAMS COMPANIES

P.O. Box 58900
Salt Lake City, UT 84158-0900
(801) 584-7033
FAX: (801) 584-6483

August 26, 1996



Mr. Roger Anderson
New Mexico Oil Conservation Division
2040 South Pacheco
Santa Fe, New Mexico 87504

Re: Discharge Plans Fees - San Juan County*
Trunk A (GW-248)
Trunk B (GW-249)
Coyote Springs (GW-250)
Milagro Plant (GW-60)

RECEIVED

SEP 09 1996

Environmental Bureau
Conservation Division

Dear Mr. Anderson:

Enclosed, please find the signed Conditions of Approval and four (4) checks made payable to the WQCC to cover the discharge plan fees for the above referenced Williams Field Services Company facilities.

If you have any questions or require additional information, please do not hesitate to contact me at (801) 584-6543.

Sincerely,

A handwritten signature in cursive script that reads "Leigh E. Gooding".

Leigh E. Gooding
Sr. Environmental Specialist

enclosure

Ms. Leigh Gooding
Williams Field Services
Page 3
August 9, 1996

RECEIVED

SEP 09 1996

Environmental Bureau
Oil Conservation Division

ATTACHMENT TO DISCHARGE PLAN GW-249
Williams Field Services - Trunk B Compressor Station
DISCHARGE PLAN REQUIREMENTS
(August 9, 1996)

1. **Payment of Discharge Plan Fees:** The \$1,380 flat fee shall be submitted upon receipt of this approval. The required flat fee may be paid in a single payment due at the time of approval, or in equal annual installments over the duration of the plan, with the first payment due upon receipt of this approval.
2. **Williams Field Services Commitments:** Williams Field Services will abide by all commitments submitted in the Application dated May 22, 1996, from Williams Field Services and this approval letter with conditions of approval from OCD dated August 9, 1996.
3. **Drum Storage:** All drums containing materials other than fresh water must be stored on an impermeable pad and curb type containment. All empty drums should be stored on their sides with the bungs in place and lined up on a horizontal plane. Chemicals in other containers such as sacks or buckets should also be stored on an impermeable pad and curb type containment.

All drums and chemical containers shall be clearly labeled to identify their contents and other emergency information necessary if they were to rupture, spill, or ignite.
4. **Process Areas:** All process and maintenance areas which show evidence that leaks and spills are reaching the ground surface must be either paved and curbed or have some type of spill collection device incorporated into the design.
5. **Above Ground Tanks:** All above ground tanks which contain fluids other than fresh water must be bermed to contain a volume of one-third more than the total volume of the largest tank or of all interconnected tanks. All new facilities or modifications to existing facilities must place the tank on an impermeable type pad.
6. **Above Ground Saddle Tanks:** Above ground saddle tanks must have impermeable pad and curb type containment unless they contain fresh water or fluids that are gases at atmospheric temperature and pressure.
7. **Tank Labeling:** All tanks should be clearly labeled to identify their contents and other emergency information necessary if the tank were to rupture, spill, or ignite.

RECEIVED

SEP 09 1996

Environmental Bureau
Oil Conservation Division

Ms. Leigh Gooding
Williams Field Services
Page 4
August 9, 1996

8. **Below Grade Tanks/Sumps:** All below grade tanks, sumps, and pits must be approved by the OCD prior to installation or upon modification and must incorporate secondary containment and leak-detection into the design. All pre-existing sumps and below-grade tanks that do not have secondary containment and leak detection must demonstrate integrity on an annual basis. Integrity tests include pressure testing to 3 pounds per square inch above normal operating pressure and/or visual inspection of cleaned out tanks /or sumps.

9. **Underground Process/Wastewater Lines:** All underground process/wastewater pipelines must be tested to demonstrate their mechanical integrity at present and then every 5 years there after. Companies may propose various methods for testing such as pressure testing to 3 pounds per square inch above normal operating pressure or other means acceptable to the OCD. The OCD will be notified at least 72 hours prior to all testing so that an OCD representative may witness the testing.

10. **Housekeeping:** All systems designed for spill collection/prevention should be inspected to ensure proper operation and to prevent overtopping or system failure.

Any contaminated soils that are collected at the facility will be tested for hazardous constituents, and after receiving OCD approval, will be disposed of at an OCD approved site.

11. **Spill Reporting:** All spills/releases shall be reported pursuant to OCD Rule 116 and WQCC 1203 to the Aztec OCD District Office at (505)-334-6178.

12. **Transfer of Discharge Plan:** The OCD will be notified prior to any transfer of ownership, control, or possession of a facility with an approved discharge plan. A written commitment to comply with the terms and conditions of the previously approved discharge plan must be submitted by the purchaser and approved by the OCD prior to transfer.

13. **New Mexico Oil Conservation Division Inspections:** Additional requirements may be placed on the facility based upon results from New Mexico Oil Conservation Division inspections.

14. **Closure:** The OCD will be notified when operations of the facility are discontinued for a period in excess of six months. Prior to closure of the facility a closure plan will be submitted for approval by the director. Closure and waste disposal will be in accordance with the statutes, rules and regulations in effect at the time of closure.

15. **Conditions accepted by:**  8-19-96
Company Representative Date
Manager EHS
Title

The Santa Fe New Mexican

Since 1849. We Read You.

NEW MEXICO OIL CONSERVATION
ATTN: SALEY MARTINEZ
2040 S. PACHECO
SANTA FE, NM 87505

AD NUMBER: 512789

ACCOUNT: 56689

LEGAL NO: 59833

P.O. #: 96199002997

257 LINES once at \$ 102.80

Affidavits: 5.25

Tax: 6.75

Total: \$ 114.80

AFFIDAVIT OF PUBLICATION

STATE OF NEW MEXICO
COUNTY OF SANTA FE

I, BETSY PERNER being first duly sworn declare and say that I am Legal Advertising Representative of THE SANTA FE NEW MEXICAN, a daily news paper published in the English language, and having a general circulation in the Counties of Santa Fe and Los Alamos, State of New Mexico and being a Newspaper duly qualified to publish legal notices and advertisements under the provisions of Chapter 167 on Session Laws of 1937; that the publication # 59833 a copy of which is hereto attached was published in said newspaper once each week for one consecutive week(s) and that the notice was published in the newspaper proper and not in any supplement; the first publication being on the 12th day of JUNE 1996 and that the undersigned has personal knowledge of the matter and things set forth in this affidavit.

/S/

Betsy Perner
LEGAL ADVERTISEMENT REPRESENTATIVE

Subscribed and sworn to before me on this
12th day of JUNE A.D., 1996



OFFICIAL SEAL

Candace C. Ruiz

NOTARY PUBLIC - STATE OF NEW MEXICO

My Commission Expires: 9/25/99

Candace C. Ruiz

NOTICE OF PUBLICATION

STATE OF NEW MEXICO

**ENERGY, MINERALS
AND NATURAL
RESOURCES
DEPARTMENT**

**OIL CONSERVATION
DIVISION**

Notice is hereby given that pursuant to New Mexico Water Quality Control Commission Regulations, the following discharge plan applications have been submitted to the Director of the Oil Conservation Division, 2040 South Pacheco, Santa Fe, New Mexico, 87505, Telephone (505) 827-7131:

(GW-248) - Williams Field Services, Leigh Gooding, Environmental Specialist, P.O. Box 58900, M.S. 10368, Salt Lake City, Utah 84158-0900, has submitted a discharge plan application for the Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 17 gallons per day of process wastewater will be stored in an above ground, closed top tank prior to disposal at an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations of approximately 2000 mg/l. The discharge plan addresses how spills, leaks, and other acci-

dental discharges to the surface will be managed.

(GW-249) - Williams Field Services, Leigh Gooding, Environmental Specialist, P.O. Box 58900, M.S. 10368, Salt Lake City, Utah 84158-0900, has submitted a discharge plan application for the Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 17 gallons per day of process wastewater will be stored in an above ground, closed top tank prior to disposal at an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentration of approximately 2000 mg/l. The discharge plan addresses how spills, leaks, and other accidental discharges will be managed.

(GW-250) - Williams Field Services, Leigh Gooding, Environmental Specialist, P.O. Box 58900, M.S. 10368, Salt Lake City, Utah 84158-0900, has submitted a discharge plan application for the Coyote Springs Compressor Station located in the SW/4 NE/4, Section 30, Township 32 North, Range 11 West, NMPM, San Juan County, New Mexico. Approximately 26 gallons per day of process wastewater will be stored in an above ground, closed top tank prior to disposal at an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 100 feet with a total dissolved solids concentrations of approximately 2000 mg/l. The discharge plan addresses how spills, leaks, and other accidental discharges will be managed.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan applications may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday thru Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and a public hearing may be requested by any interested person. Requests for a public hearing shall set forth the reasons why a hearing should be held. A hearing will be held if the Director determines there is significant public interest.

If no hearing is held, the Director will approve or disapprove the proposed plans based on information available. If a public hearing is held, the Director will approve or disapprove the plans based on the information in the plans and information presented at the hearing.

GIVEN under the Seal of New Mexico Oil Conservation Commission at Santa Fe, New Mexico, on this 4th day of June, 1996.

STATE OF NEW MEXICO
OIL CONSERVATION
DIVISION
WILLIAM J. LEMAY,
Director
Legal #59833
Pub. June 12, 1996

AFFIDAVIT OF PUBLICATION


No. 36464

STATE OF NEW MEXICO
County of San Juan:


ROBERT LOVETT being duly sworn says: That he is the Classified Manager of THE DAILY TIMES, a daily newspaper of general circulation published in English at Farmington, said county and state, and that the hereto attached Legal Notice was published in a regular and entire issue of the said DAILY TIMES, a daily newspaper duly qualified for the purpose within the meaning of Chapter 167 of the 1937 Session Laws of the State of New Mexico for publication on the following day(s):

Friday, June 14, 1996;

and the cost of publication is: \$86.45.



On 6/20/96 ROBERT LOVETT appeared before me, whom I know personally to be the person who signed the above document.


_____ My Commission Expires May 17, 2000



COPY OF PUBLICATION

Legals



NOTICE OF PUBLICATION

STATE OF NEW MEXICO
ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT
OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to the New Mexico Water Quality Control Commission Regulations, the following discharge plan applications have been submitted to the Director of the Oil Conservation Division, 2040 South Pacheco, Santa Fe, New Mexico 87505, Telephone (505) 827-7131:

(GW-248) - Williams Field Services, Leigh Gooding, Environmental Specialist, P.O. Box 58900, M.S. 10368, Salt Lake City, Utah 84158-0900, has submitted a discharge plan application for the Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 17 gallons per day of process wastewater will be stored in an above ground, closed top tank prior to disposal at an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations of approximately 2000 mg/l. The discharge plan addresses how spills, leaks, and other accidental discharges will be managed.

(GW-249) - Williams Field Services, Leigh Gooding, Environmental Specialist, P.O. Box 58900, M.S. 10368, Salt Lake City, Utah 84158-0900, has submitted a discharge plan application for the Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 17 gallons per day of process wastewater will be stored in an above ground, closed top tank prior to disposal at an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentrations of approximately 2000 mg/l. The discharge plan addresses how spills, leaks, and other accidental discharges will be managed.

(GW-250) - Williams Field Services, Leigh Gooding, Environmental Specialist, P.O. Box 58900, M.S. 10368, Salt Lake City, Utah 84158-0900, has submitted a discharge plan application for the Coyote Springs Compressor Station located in the SW/4 NE/4, Section 30, Township 32 North, Range 11 West, NMPM, San Juan County, New Mexico. Approximately 26 gallons per day of process wastewater will be stored in an above ground, closed top tank prior to disposal at an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 100 feet with a total dissolved solids concentrations of approximately 2000 mg/l. The discharge plan addresses how spills, leaks, and other accidental discharges will be managed.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan applications may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday thru Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and public hearing may be requested by any interested person. Request for public hearing shall set forth the reasons why a hearing shall be held. A hearing will be held if the director determines that there is significant public interest.

If no hearing is held, the Director will approve or disapprove the plans based on the information available. If a public hearing is held, the Director will approve the plans based on the information in the plans and information presented at the hearing.

GIVEN under the Seal of New Mexico Oil Conservation Commission at Santa Fe, New Mexico, on this 4th day of June, 1996.

STATE OF NEW MEXICO
OIL CONSERVATION DIVISION

/s/William J. LeMay
WILLIAM J. LEMAY, Director

SEAL

NOTICE OF PUBLICATION

STATE OF NEW MEXICO ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to the New Mexico Water Quality Control Commission Regulations, the following discharge plan applications have been submitted to the Director of the Oil Conservation Division, 2040 South Pacheco, Santa Fe, New Mexico 87505, Telephone (505) 827-7131:

(GW-248) - Williams Field Services, Leigh Gooding, Environmental Specialist, P.O. Box 58900, M.S. 10368, Salt Lake City, Utah 84158-0900, has submitted a discharge plan application for the Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 17 gallons per day of process wastewater will be stored in an above ground, closed top tank prior to disposal at an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations of approximately 2000 mg/l. The discharge plan addresses how spills, leaks, and other accidental discharges will be managed.

(GW-249) - Williams Field Services, Leigh Gooding, Environmental Specialist, P.O. Box 58900, M.S. 10368, Salt Lake City, Utah 84158-0900, has submitted a discharge plan application for the Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 17 gallons per day of process wastewater will be stored in an above ground, closed top tank prior to disposal at an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentrations of approximately 2000 mg/l. The discharge plan addresses how spills, leaks, and other accidental discharges will be managed.


(GW-250) - Williams Field Services, Leigh Gooding, Environmental Specialist, P.O. Box 58900, M.S. 10368, Salt Lake City, Utah 84158-0900, has submitted a discharge plan application for the Coyote Springs Compressor Station located in the SW/4 NE/4, Section 30, Township 32 North, Range 11 West, NMPM, San Juan County, New Mexico. Approximately 26 gallons per day of process wastewater will be stored in an above ground, closed top tank prior to disposal at an OCD approved disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 100 feet with a total dissolved solids concentrations of approximately 2000 mg/l. The discharge plan addresses how spills, leaks, and other accidental discharges will be managed.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan applications may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday thru Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and public hearing may be requested by any interested person. Request for public hearing shall set forth the reasons why a hearing shall be held. A hearing will be held if the director determines that there is significant public interest.

If no hearing is held, the Director will approve or disapprove the plans based on the information available. If a public hearing is held, the Director will approve the plans based on the information in the plans and information presented at the hearing.

GIVEN under the Seal of New Mexico Oil Conservation Commission at Santa Fe, New Mexico, on this 4th day of June, 1996.

STATE OF NEW MEXICO
OIL CONSERVATION DIVISION



WILLIAM J. LEMAY, Director

SEAL



P.O. Box 58900
Salt Lake City, UT 84158-0900
(801) 584-7033
FAX: (801) 584-6483

May 22, 1996

RECEIVED
MAY 31 1996
Environmental Bureau
Oil Conservation Division

Mr. Roger Anderson
New Mexico Oil Conservation Division
2040 South Pacheco
Santa Fe, New Mexico 87504

GW-249

Re: Discharge Plan for Trunk B Booster Station - San Juan County

Dear Mr. Anderson:

Enclosed please find two copies of the Discharge Plan for Williams Field Services' Trunk B Booster Station located in San Juan County, New Mexico.

If you have any questions or require additional information, please do not hesitate to contact me at (801) 584-6543.

Sincerely,

Leigh E. Gooding
Sr. Environmental Specialist

enclosure

cc: Denny Foust, OCD District III Office (letter and enclosure)

RECEIVED
MAY 31 1996
Environmental Bureau
Oil Conservation Division

DISCHARGE PLAN

**MANZANARES GATHERING SYSTEM
TRUNK B BOOSTER STATION**

Williams Field Services Company

May 1996

State of New Mexico
Energy, Minerals and Natural Resources Department
OIL CONSERVATION DIVISION
P.O. Box 2088
Santa Fe, NM 87501

**DISCHARGE PLAN APPLICATION FOR NATURAL GAS PROCESSING PLANTS,
OIL REFINERIES AND GAS COMPRESSOR STATIONS**
(Refer to OCD Guidelines for assistance in completing the application.)

- I. TYPE: Trunk B Booster Station
- II. OPERATOR: Williams Field Services
ADDRESS: 295 Chipeta Way P.O. Box 58900 Salt Lake City, UT 84158
CONTACT PERSON: Leigh Gooding PHONE: (801)584-6543
- III. LOCATION: SW/4 SW/4 Section 28 Township 31N Range 8W
Submit large scale topographic map showing exact location.
- IV. Attach the name and address of the landowner(s) of the disposal facility site.
- V. Attach description of the facility with a diagram indicating location of fences, pits, dikes, and tanks on the facility.
- VI. Attach a description of sources, quantities and quality of effluent and waste solids.
- VII. Attach a description of current liquid and solid waste transfer and storage procedures.
- VIII. Attach a description of current liquid and solid waste disposal procedures.
- IX. Attach a routine inspection and maintenance plan to ensure permit compliance.
- X. Attach a contingency plan for reporting and clean-up of spills or releases.
- XI. Attach geological/hydrological evidence demonstrating that disposal of oil field wastes will not adversely impact fresh water. Depth to and quality of ground water must be included.
- XII. Attach such other information as is necessary to demonstrate compliance with any other OCD rules, regulations and/or orders.
- XIII. CERTIFICATION

I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.

Name: Terry G. Spradlin Title: Manager, Environment, Health & Safety

Signature:  Date: 5-22-96

DISTRIBUTION: Original and one copy to Santa Fe with one copy to appropriate Division District Office.

I. TYPE OF OPERATION

The Trunk B Booster Station will provide metering and compression services to various producers for the gathering of coal seam natural gas on a contract basis for ultimate delivery through Williams Field Services (WFS) Milagro Plant in Bloomfield, New Mexico.

II. LEGALLY RESPONSIBLE PARTY

Williams Field Services
295 Chipeta Way
P.O. Box 58900
Salt Lake City, Utah 84158-0900
(801) 584-6543

Contact Person:

Ms. Leigh E. Gooding, Sr. Environmental Specialist
Phone and Address, Same as Above

III. LOCATION OF DISCHARGE

The Trunk B Booster Station well be located in the SW/4 of the SW/4 of Section 28, Township 31 North, Range 8 West, in San Juan County, New Mexico. A Site Location map is attached (USGS 7.5 Min. Quadrangles: Archuleta, New Mexico) as Figure 1. The site for this station will be 5.0 acres. The site boundary survey is provided in Figure 2. The facility layout is presented in Figure 3.

IV. LANDOWNER

Williams Field Services is leasing the subject property from:

Bureau of Land Management
1235 N. La Plata Highway
Farmington, NM 87401

V. FACILITY DESCRIPTION

Seven (7) Waukesha 7042 GL natural gas reciprocating engines, site rated at 1,367 horsepower (hp) each will be installed at the site. The units will be skid-mounted and self contained. This facility will be classified as a field compressor station; consequently, there will be no formal office or other support facilities not essential to field compression.

VI. SOURCES, QUANTITIES AND QUALITY OF EFFLUENTS AND WASTE SOLIDS

The sources, quantities and quality of effluent and waste solids generated at the compressor station are summarized in Table 1. Material Safety Data Sheets for glycol and oil used in the equipment were previously provided to New Mexico Oil Conservation Division (NMOCD) by WFS. For reference, representative samples of washdown wastewater and used motor oil have previously been collected from representative WFS compressor stations and analyzed for the parameters listed below.

<u>Sample</u>	<u>Parameters</u>
Washdown Wastewater	pH, TDS, TOX, TPH, BETX, As, Ba, Cd, Cr, Pb, Hg, Se, Ag.
Used Motor Oil	As, Cd, Cr, Pb, TOX, Flash Point

The results of previous tests conducted on similar waste streams showed that the washdown water did not exhibit any of the hazardous characteristics and used motor oil was suitable for recycling (Appendix A). Additional Chemicals listed in WQCC 1101.TT and 3103 are not expected to be present in any process fluids or in the gas transported at this compressor station.

Used oil filters have been collected from representative WFS compressor stations and analyzed for TCLP Metals. The results of the analysis found that the filters did not exceed TCLP concentrations for metals. The analyses were submitted to the San Juan County Regional Landfill along with the Waste Acceptance Profiles. These profiles are updated every two years or as required by the landfill.

VII. TRANSFER AND STORAGE OF PROCESS FLUIDS, EFFLUENTS AND WASTE SOLIDS

Used motor oil will be collected in a closed-piping system to above-ground storage tanks located at each compressor and transported by an EPA-registered used oil marketer (D&D Oil, EPA ID# NMD986682102).

All liquids from the gas-inlet separator will be collected separately in a 70-barrel above-ground condensate storage tank. The tank will be gauged every two weeks and the liquids will be transported to Basin Disposal. Washdown wastewater from engine deck plates will be collected in a closed piping system directly to a below-grade sump. The sump will be a 750-gallon, fiberglass, doubled wall tank, equipped with leak detection. Wastewater accumulations will be removed from the inner tank using a vacuum truck and transported to an NMOCD-approved surface disposal facility. A schematic drawing of the sump is presented in Figure 4.

Used oil filters will be drained, stored in 50-gallon plastic drums, and transported by Waste Management of Four Corners to the San Juan County Regional Landfill.

VIII. EFFLUENT AND WASTE SOLIDS DISPOSAL

Exempt and non-exempt wastes will be managed separately. Only exempt wastes will be disposed down Class II injection wells. Non-exempt wastes will be characterized for hazardous constituents.

- Used motor oil will be recycled by an EPA-registered used oil marketer (D&D Oil, EPA ID# NMD986682102).
- Natural gas liquids from the gas-inlet separator and dehydrator separator will be disposed at Basin Disposal.
- Washdown water has been shown to be non-hazardous and as such, will be disposed at an NMOCD-approved surface disposal facility.
- Porta-pottys present at this facility will be serviced under a contract requiring proper sewage disposal in accordance with applicable laws and regulations.

TABLE 1
SOURCES, QUANTITIES AND QUALITY OF EFFLUENT AND WASTE SOLIDS
TRUNK B BOOSTER STATION

PROCESS FLUID/WASTE	SOURCES	QUANTITY	QUALITY	DISPOSITION
Used Oil	Compressors	1,000 gal/yr	Used motor oil w/no additives	Collected separately at each compressor in a 520-gal AST. Transported to D&D Oil for recycling.
Natural Gas Liquids	Gas Inlet Separator Dehydrators	2,000 gal/yr	No additives	Collected separately in a 70-bbl AST. Transported to Basin Disposal.
Washdown Water	Compressor and Glycol Dehydrator	4,000 gal/yr	Soap and tap water w/traces of used oil and triethylene glycol	Collected separately in a 750-gal sump. Transported to NMOCD-approved surface disposal facility for disposal.
Oil Filters	Compressor	50/yr	No additives	Drained and placed in 55-gallon plastic drums. Transported to the San Juan County Landfill for disposal.

IX. INSPECTION, MAINTENANCE AND REPORTING

Production Operators, Incorporated (POI) is under contract to operate and maintain the compression unit at the facility. WFS's Manzanaras Gathering District operates the dehydration units. The facility will be inspected several times per week at a minimum and a POI operator will be on call 24 hours per day, 7 days per week, 52 weeks per year. The facility will be remotely monitored for equipment malfunctions. POI must comply with WFS' spill response procedures. In the event of a release of a reportable quantity, POI will immediately notify WFS' Environmental Service Department and WFS will report the release to NMOCD. The below-grade wastewater tank will be monitored monthly for leak detection.

X. SPILL/LEAK PREVENTION AND REPORTING (CONTINGENCY PLANS)

For overflow containment, lube oil tanks on saddle racks will be underlain by concrete splash aprons equipped with retainment curbs. Fluids which collect within the curbed area drain through a pipe into a closed containment system. A drip pan will be placed beneath the catwalk adjacent to the oil filter on each compressor unit to contain spillage during maintenance activities. Spill containment dikes around the bulk storage tanks will contain 1 1/3 volume of the largest vessel. Spill containment will also be provided around the tank loading valves. Surface runoff within the site will be diverted around facility processes into the natural drainage path to the southeast.

All pressure vessels on site will be tested in accordance with the requirement of the ASME Boiler and Pressure Vessel Code. All interconnecting gas piping on site will be tested in accordance with the requirements of the ASME Code for Pressure Piping, B31.8 Gas Transmission and Distribution Piping Systems.

WFS corporate policy and procedure for the controlling and reporting of Discharges or Spills of Oil or Hazardous Substances is provided in Appendix B. Significant spills and leaks will be reported to the NMOCD pursuant to NMOCD Rule 116 and WQCC 1-203 using the NMOCD form (see Appendix C).

XI. SITE CHARACTERISTICS

The Trunk B Booster Station will be located in the SW/4 of the SW/4 of Section 28, Township 31 North, Range 8 West, in San Juan County, New Mexico approximately 13 miles northeast of Blanco, New Mexico. The site elevation is 6,501 feet above mean sea level. The undeveloped site is covered by sagebrush and native grasses.

Hydrologic Features: The site is located along a County Road 4600, approximately one and a-half miles west of Simon Canyon. The site is underlain by sandstones and shales of the San Jose Formation. Surface runoff from the area surrounding the site is diverted around the yard and to the southwest. Runoff continues to an ephemeral tributary to Simon Canyon drainage located approximately 1,000 feet southwest of the site. Based on the elevation of the canyon (6,000 feet above sea level), the expected minimum depth to groundwater at the subject site is 500 feet below ground surface.

A review of the well records on file with the State Engineer found the closest ground water well to the site is owned by El Paso Natural Gas (SJ-198). The well is located in the SE/4 SW/4 SW/4 of Section 32, Township 31 North, Range 8 West, and was drilled to a depth of 2,003 feet (Appendix D). The closest documented source of ground water downgradient from the subject site are the alluvial deposits associated with the ephemeral tributary to the Simon Canyon. Ground water within these alluvial deposits is expected to have a total dissolved solids (TDS) concentration of approximately 2000 mg/l.¹

Flood Protection: Stormwater runoff from the area surrounding the site is diverted around the facility into the natural drainage path.

¹ Klausning, R.L. and G.E. Welder, "Availability of Hydrologic Data in San Juan County, New Mexico:", U.S.G.S. Open-File Report 84-608, 1984.

Lyford, F.P., "Ground Water in the San Juan Basin, New Mexico and Colorado", U.S.G.S. Water-Resource Investigations 79-73, May, 1979.

Stone, W.J., F.P. Lyford, P.F. Frenzel, N.H. Mizel, E.P. Padgett, "Hydrogeology and Water Resources of San Juan Basin, New Mexico", Hydrologic Report 6, New Mexico Bureau of Mines & Mineral Resources, 1983.

XII FACILITY CLOSURE PLAN

All reasonable and necessary measures will be taken to prevent the exceedance of WCQQ Section 3103 quality standards should WFS choose to permanently close the facility. WFS will submit a detailed closure plan to the NMOCD prior to closure.

Generally, closure measures will include removal or closure in place of all underground piping and equipment. All tanks will be emptied. No potentially toxic materials or effluents will remain on the site. All potentially toxic pollutants will be inspected. Should contaminated soil be discovered, any necessary reporting under NMOCD Rule 116 and WQCC Section 1203 will be made and clean-up activities will commence. Post-closure maintenance and monitoring plans would not be necessary unless contamination is encountered.

FIGURE 1

SITE LOCATION MAP


FIGURE 2
SITE SURVEY PLAN

MANZANARES GATHERING SYSTEM

WILLIAMS FIELD SERVICES

LINE _____ TRUNK "B" BOOSTER STATION
 FROM _____
 COUNTY SAN JUAN STATE NEW MEXICO
 SECTION 28 TOWNSHIP 31-N RANGE 8-W

SCALE: 1" = 1000'
 DRAWN BY: E.S.C. DATE 11/30/95
 CHECKED BY: L.M.T. SURVEYED 11/30/95
 APPROVED: _____ W.O. NO. _____
 APPROVED: _____ R/W NO. _____



LEGEND

- SET 1/2" REBAR W/ CAP LS #6707
- FD. AS NOTED

NOTE: BEARINGS SHOWN ARE BASED UPON A SOLAR OBSERVATION TAKEN AT THE NORTHWEST CORNER, ALONG THE NORTH LINE OF THIS BOOSTER STATION SITE.
 BEARS: N 89°12'13" E

NOTE: ALL COORDINATES AS SHOWN ARE UTM COORDINATES ZONE 13, IN METERS.
 PROJECT TBM = TOP OF 1/2" REBAR W/ CAP AT SOUTHWEST CORNER OF SITE.
 ELEV. = 6499.60

CERTIFICATE OF SURVEYOR

I HEREBY CERTIFY THAT THIS PLAN IS A TRUE REPRESENTATION OF A SURVEY MADE BY ME OR UNDER MY DIRECT SUPERVISION, AND THE SAME IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Harvey D. Peterson
 HARVEY D. PETERSON REGISTERED SURVEYOR
 NEW MEXICO L.S. # 6707

DESIGN FACTOR

DESIGN PRESSURE

TEST PRESSURE

MAOP	MINIMUM:		ACTUAL:		MAXIMUM:		
	SUBMISION	OWNER	LEASE	FEET	MILES	ACRES	RODS
Ownership	SEC. 28	BLM				5.00	
Rev.							

FIGURE 3
FACILITY PLOT PLAN

APPENDIX A
WASTE ANALYSIS

Enseco Incorporated

CEDAR HILL C.D.P.
WASTE OIL +
WASTEWATER

ANALYTICAL RESULTS

FOR

NORTHWEST PIPELINE CORPORATION

ENSECO-RMAL NO. 024601

SEPTEMBER 21, 1992

Enseco
A Corning Company

ANALYTICAL RESULTS
FOR
NORTHWEST PIPELINE CORPORATION
ENSECO-RMAL NO. 024601



SEPTEMBER 21, 1992

Reviewed by:

A handwritten signature in cursive script, appearing to read "Joe A. Maes".

Joe A. Maes

A handwritten signature in cursive script, appearing to read "Joel E. Holtz".

Joel E. Holtz



AMERICAN
WEST
ANALYTICAL
LABORATORIES

ORGANIC ANALYSIS REPORT

Client: Williams Field Services
Date Sampled: July 19, 1995
Date Received: July 20, 1995

Contact: Mark Harvey
Date Analyzed: July 26, 1995

Analysis Requested:
Volatile Aromatics
Total Purgeable Hydrocarbons

Method Ref. Number:
SW-846 #8250
(Purge & Trap GC/MS)

Field Sample ID:
SAN JUAN AREA
CEDAR HILL #1

Lab Sample ID:
L23218-8

463 West 3600 South
Salt Lake City, Utah
84115

Analytical Results

Units = mg/L(ppm)

BTX/TPH-P

<u>Compound:</u>	<u>Detection Limit:</u>	<u>Amount Detected:</u>
Benzene	0.020	0.036
Toluene	0.020	0.046
Ethylbenzene	0.020	0.14
Total Xylene	0.020	0.95
Total Purgeable Hydrocarbons	0.20	19.

(801) 263-8686
Fax (801) 263-8687

< Value = None detected above the specified detection limit, or a value that reflects a reasonable limit due to interferences.

Released By:


Laboratory Supervisor

Report Date: July 31, 1995

1 of 1



AMERICAN
WEST
ANALYTICAL
LABORATORIES

Client: Williams Field Service
Date Sampled: July 19, 1995
Lab Sample ID.: 23218-08
Field Sample ID: San Juan Area/Cedar Hill #1

Contact: Mark Harvey
Date Received: July 20, 1995
Received By: Laurie Hastings
Set Description: One Water and
Seven Soil Samples

INORGANIC ANALYSIS REPORT

Analytical Results

463 West 3600 South
Salt Lake City, Utah
84115

(801) 263-8686
Fax (801) 263-8687

	Method Used:	Detection Limit: mg/L	Amount Detected: mg/L
TOTAL METALS			
Arsenic	7060	0.005	<0.005
Barium	6010	0.002	2.8
Cadmium	6010	0.004	0.013
Chromium	6010	0.01	0.03
Lead	6010	0.05	0.13
Mercury	7471	0.001	<0.001
Selenium	7740	0.005	<0.005
Silver	6010	0.01	<0.01

OTHER CHEMISTRIES

pH	150.1	0.1	6.8
TDS	160.1	1.0	3,600.
TOX	9020	0.5	1.6

Released by:

[Signature]

Laboratory Supervisor

Report Date 8/2/95

1 of 1

Introduction

This report presents the analytical results as well as supporting information to aid in the evaluation and interpretation of the data and is arranged in the following order:

- o Sample Description Information
- o Analytical Test Requests
- o Analytical Results
- o Quality Control Report

All analyses at Enseco are performed so that the maximum concentration of sample consistent with the method is analyzed. Dilutions are at times required to avoid saturation of the detector, to achieve linearity for a specific target compound, or to reduce matrix interferences. In this event, reporting limits are adjusted proportionately. Surrogate compounds may not be measurable in samples which have been diluted.

Sample 024601-0001 was diluted for Method 8020 due to concentrations of target compounds present beyond linear range; the reporting limits have been increased accordingly.

Sample 024601-0002 was diluted for Method 9020 due to matrix interferences; the reporting limits have been increased accordingly.

Sample Description Information

The Sample Description Information lists all of the samples received in this project together with the internal laboratory identification number assigned for each sample. Each project received at Enseco-RMAL is assigned a unique six digit number. Samples within the project are numbered sequentially. The laboratory identification number is a combination of the six digit project code and the sample sequence number.

Also given in the Sample Description Information is the Sample Type (matrix), Date of Sampling (if known) and Date of Receipt at the laboratory.

Analytical Test Requests

The Analytical Test Requests lists the analyses that were performed on each sample. The Custom Test column indicates where tests have been modified to conform to the specific requirements of this project.

SAMPLE DESCRIPTION INFORMATION
for
Northwest Pipeline Corporation

Lab ID	Client ID	Matrix	Sampled		Received
			Date	Time	Date
024601-0001-SA	CEDAR HILL CDP WASTE WATER TAN	AQUEOUS	18 AUG 92	12:40	19 AUG 92
024601-0002-SA	WASTE OIL TANK CEDAR HILL	AQUEOUS	18 AUG 92	11:30	19 AUG 92
024601-0003-TB	TRIP BLANK	AQUEOUS			19 AUG 92

ANALYTICAL TEST REQUESTS
for
Northwest Pipeline Corporation

Lab ID: 024601	Group Code	Analysis Description	Custom Test?		
0001	A	pH	N		
		Total Dissolved Solids (TDS)	N		
		ICP Metals (Total)	Y		
		Prep - Total Metals, ICP	N		
		Total Organic Halogen (TOX)	N		
		Benzene, Toluene, Ethyl Benzene and Xylenes (BTEX)	N		
		Arsenic, Furnace AA (Total)	N		
		Prep - Total Metals, Furnace AA	N		
		Lead, Furnace AA (Total)	N		
		Mercury, Cold Vapor AA (Total)	N		
		Prep - Mercury, Cold Vapor AA (Total)	N		
		0002	B	Arsenic, Furnace AA	N
				Prep - Total Metals, Furnace AA	N
				ICP Suite	Y
Prep - Total Metals, ICP	N				
Lead, Furnace AA	N				
Total Organic Halogen (TOX)	N				
0003	C	Ignitability, Closed Cup	N		
		Benzene, Toluene, Ethyl Benzene and Xylenes (BTEX)	N		

Analytical Results

The analytical results for this project are presented in the following data tables. Each data table includes sample identification information, and when available and appropriate, dates sampled, received, authorized, prepared and analyzed. The authorization data is the date when the project was defined by the client such that laboratory work could begin.

Data sheets contain a listing of the parameters measured in each test, the analytical results and the Enseco reporting limit. Reporting limits are adjusted to reflect dilution of the sample, when appropriate. Solid and waste samples are reported on an "as received" basis, i.e. no correction is made for moisture content.

The results from the Standard Enseco QA/QC Program, which generates data which are independent of matrix effects, are provided subsequently.

Benzene, Toluene, Ethyl Benzene and Xylenes (BTEX)

Method 8020

Client Name: Northwest Pipeline Corporation
 Client ID: CEDAR HILL CDP WASTE WATER TANK
 Lab ID: 024601-0001-SA
 Matrix: AQUEOUS
 Authorized: 19 AUG 92
 Sampled: 18 AUG 92
 Prepared: NA
 Received: 19 AUG 92
 Analyzed: 22 AUG 92

Parameter	Result	Units	Reporting Limit
Benzene	19	ug/L	1.2
Toluene	63	ug/L	1.2
Ethylbenzene	12	ug/L	1.2
Xylenes (total)	240	ug/L	1.2
Surrogate	Recovery		
a,a,a-Trifluorotoluene	112	%	

ND = Not detected
 NA = Not applicable

Reported By: Steve Shurgot

Approved By: Stan Dunlavy

Benzene, Toluene, Ethyl Benzene and Xylenes (BTEX)

Method 8020

Client Name: Northwest Pipeline Corporation

Client ID: TRIP BLANK

Lab ID: 024601-0003-TB

Matrix: AQUEOUS

Authorized: 19 AUG 92

Sampled: Unknown

Prepared: NA

Received: 19 AUG 92

Analyzed: 24 AUG 92

Parameter	Result	Units	Reporting Limit
Benzene	ND	ug/L	0.50
Toluene	ND	ug/L	0.50
Ethylbenzene	ND	ug/L	0.50
Xylenes (total)	ND	ug/L	0.50
Surrogate	Recovery		
a,a,a-Trifluorotoluene	106	%	

ND = Not detected
NA = Not applicable

Reported By: Steve Shurgot

Approved By: Stan Dunlavy

Metals

Total Metals

Client Name: Northwest Pipeline Corporation
 Client ID: CEDAR HILL CDP WASTE WATER TANK
 Lab ID: 024601-0001-SA
 Matrix: AQUEOUS
 Authorized: 19 AUG 92

Sampled: 18 AUG 92
 Prepared: See Below

Received: 19 AUG 92
 Analyzed: See Below

Parameter	Result	Units	Reporting Limit	Analytical Method	Prepared Date	Analyzed Date
Arsenic	ND	mg/L	0.0050	7060	10 SEP 92	12 SEP 92
Barium	0.11	mg/L	0.010	6010	10 SEP 92	15 SEP 92
Cadmium	ND	mg/L	0.0050	6010	10 SEP 92	15 SEP 92 B
Chromium	0.15	mg/L	0.010	6010	10 SEP 92	15 SEP 92
Lead	0.020	mg/L	0.010	7421	10 SEP 92	11 SEP 92
Mercury	ND	mg/L	0.00020	7470	13 SEP 92	13 SEP 92

Note B : Compound is also detected in the blank.

ND = Not detected
 NA = Not applicable

Reported By: Jeff Malecha

Approved By: Sandra Jones

Metals

Total Metals

Client Name: Northwest Pipeline Corporation

Client ID: WASTE OIL TANK CEDAR HILL

Lab ID: 024601-0002-SA

Matrix: WASTE

Authorized: 19 AUG 92

Sampled: 18 AUG 92

Prepared: See Below

Received: 19 AUG 92

Analyzed: See Below

Parameter	Result	Units	Reporting Limit	Analytical Method	Prepared Date	Analyzed Date
Arsenic	ND	mg/kg	1.0	7060	14 SEP 92	16 SEP 92
Cadmium	ND	mg/kg	0.50	6010	14 SEP 92	15 SEP 92
Chromium	1.0	mg/kg	1.0	6010	14 SEP 92	15 SEP 92
Lead	2.8	mg/kg	2.2	7421	14 SEP 92	14 SEP 92

ND = Not detected
NA = Not applicable

Reported By: Bob Reilly

Approved By: Sandra Jones

General Inorganics

Client Name: Northwest Pipeline Corporation
Client ID: CEDAR HILL CDP WASTE WATER TANK
Lab ID: 024601-0001-SA
Matrix: AQUEOUS
Authorized: 19 AUG 92
Sampled: 18 AUG 92
Prepared: See Below
Received: 19 AUG 92
Analyzed: See Below

Parameter	Result	Units	Reporting Limit	Analytical Method	Prepared Date	Analyzed Date
pH	4.9	units	--	9040	NA	19 AUG 92
Total Organic Halogen as Cl	71.4	ug/L	30.0	9020	NA	10 SEP 92
Total Dissolved Solids	498	mg/L	10.0	160.1	NA	25 AUG 92

ND = Not detected
NA = Not applicable

Reported By: Pam Rosas

Approved By: Steve Shurgot

General Inorganics

Enseco
A Corning Company

Client Name: Northwest Pipeline Corporation
Client ID: WASTE OIL TANK CEDAR HILL
Lab ID: 024601-0002-SA
Matrix: WASTE
Authorized: 19 AUG 92

Sampled: 18 AUG 92
Prepared: See Below

Received: 19 AUG 92
Analyzed: See Below

Parameter	Result	Units	Reporting Limit	Analytical Method	Prepared Date	Analyzed Date
Ignitability	>160	deg. F	--	1010	NA	03 SEP 92 o
Total Organic Halogen as Cl	ND	mg/kg	3.0	9020	NA	15 SEP 92

Note o : This test is unreliable for any sample other than a non-aqueous liquid.

ND = Not detected
NA = Not applicable

Reported By: Leslie Gergurich

Approved By: Steve Shurgot

Quality Control Report

The Enseco laboratories operate under a vigorous QA/QC program designed to ensure the generation of scientifically valid, legally defensible data by monitoring every aspect of laboratory operations. Routine QA/QC procedures include the use of approved methodologies, independent verification of analytical standards, use of Duplicate Control Samples to assess the precision and accuracy of the methodology on a routine basis, and a rigorous system of data review.

In addition, the Enseco laboratories maintain a comprehensive set of certifications from both state and federal governmental agencies which require frequent analyses of blind audit samples. Enseco-Rocky Mountain Analytical Laboratory is certified by the EPA under the EPA/CLP program for Organic analyses, under the USATHAMA (U.S. Army) program, by the Army Corps of Engineers, and the states of Colorado, New Jersey, Utah, and Florida, among others.

The standard laboratory QC package is designed to:

- 1) establish a strong, cost-effective QC program that ensures the generation of scientifically valid, legally defensible data
- 2) assess the laboratory's performance of the analytical method using control limits generated with a well-defined matrix
- 3) establish clear-cut guidelines for acceptability of analytical data so that QC decisions can be made immediately at the bench, and
- 4) provide a standard set of reportables which assures the client of the quality of his data.

The Enseco QC program is based upon monitoring the precision and accuracy of an analytical method by analyzing a set of Duplicate Control Samples (DCS) at frequent, well-defined intervals. Each DCS is a well-characterized matrix which is spiked with target compounds at 5-100 times the reporting limit, depending upon the methodology being monitored. The purpose of the DCS is not to duplicate the sample matrix, but rather to provide an interference-free, homogeneous matrix from which to gather data to establish control limits. These limits are used to determine whether data generated by the laboratory on any given day is in control.

Control limits for accuracy (percent recovery) are based on the average, historical percent recovery +/- 3 standard deviation units. Control limits for precision (relative percent difference) range from 0 (identical duplicate DCS results) to the average, historical relative percent difference + 3 standard deviation units. These control limits are fairly narrow based on the consistency of the matrix being monitored and are updated on a quarterly basis.

For each batch of samples analyzed, an additional control measure is taken in the form of a Single Control Sample (SCS). The SCS consists of a control matrix that is spiked with either representative target compounds or surrogate compounds appropriate to the method being used. An SCS is prepared for each sample lot for which the DCS pair are not analyzed.

Accuracy for DCS and SCS is measured by Percent Recovery.

$$\% \text{ Recovery} = \frac{\text{Measured Concentration}}{\text{Actual Concentration}} \times 100$$

Precision for DCS is measured by Relative Percent Difference (RPD).

$$\text{RPD} = \frac{|\text{Measured Concentration DCS1} - \text{Measured Concentration DCS2}|}{(\text{Measured Concentration DCS1} + \text{Measured Concentration DCS2})/2} \times 100$$

All samples analyzed concurrently by the same test are assigned the same QC lot number. Projects which contain numerous samples, analyzed over several days, may have multiple QC lot numbers associated with each test. The QC information which follows includes a listing of the QC lot numbers associated with each of the samples reported, DCS and SCS (where applicable) recoveries from the QC lots associated with the samples, and control limits for these lots. The QC data is reported by test code, in the order that the tests are reported in the analytical results section of this report.

QC LOT ASSIGNMENT REPORT
Organics by Chromatography

Laboratory Sample Number	QC Matrix	QC Category	QC Lot Number (DCS)	QC Run Number (SCS/BLANK)
024601-0001-SA	AQUEOUS	602-A	18 AUG 92-1H	22 AUG 92-1H
024601-0003-TB	AQUEOUS	602-A	18 AUG 92-1H	24 AUG 92-1H

DUPLICATE CONTROL SAMPLE REPORT
Organics by Chromatography

Analyte	Concentration Spiked	Concentration Measured		AVG	Accuracy Average(%)		Precision (RPD)	
		DCS1	DCS2		DCS	Limits	DCS	Limit
Category: 602-A								
Matrix: AQUEOUS								
QC Lot: 18 AUG 92-1H								
Concentration Units: ug/L								
Benzene	5.0	5.28	5.29	5.28	106	72-112	0.2	10
Toluene	5.0	4.99	5.01	5.00	100	74-109	0.4	10
Ethylbenzene	5.0	4.85	4.89	4.87	97	76-105	0.8	10
Xylenes (total)	5.0	4.82	4.88	4.85	97	74-111	1.2	10
1,3-Dichlorobenzene	5.0	4.83	4.94	4.88	98	72-121	2.3	15

Calculations are performed before rounding to avoid round-off errors in calculated results.

SINGLE CONTROL SAMPLE REPORT
Organics by Chromatography

Analyte	Concentration		Accuracy(%)	
	Spiked	Measured	SCS	Limits

Category: 602-A
Matrix: AQUEOUS
QC Lot: 18 AUG 92-1H QC Run: 22 AUG 92-1H
Concentration Units: ug/L

a,a,a-Trifluorotoluene	30.0	31.2	104	90-113
------------------------	------	------	-----	--------

Category: 602-A
Matrix: AQUEOUS
QC Lot: 18 AUG 92-1H QC Run: 24 AUG 92-1H
Concentration Units: ug/L

a,a,a-Trifluorotoluene	30.0	30.9	103	90-113
------------------------	------	------	-----	--------

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT
Organics by Chromatography

Analyte	Result	Units	Reporting Limit
Test: 8020-BTEX-AP			
Matrix: AQUEOUS			
QC Lot: 18 AUG 92-1H QC Run: 22 AUG 92-1H			
Benzene	ND	ug/L	0.50
Toluene	ND	ug/L	0.50
Ethylbenzene	ND	ug/L	0.50
Xylenes (total)	ND	ug/L	0.50

Test: 8020-BTEX-AP
Matrix: AQUEOUS
QC Lot: 18 AUG 92-1H QC Run: 24 AUG 92-1H

Benzene	ND	ug/L	0.50
Toluene	ND	ug/L	0.50
Ethylbenzene	ND	ug/L	0.50
Xylenes (total)	ND	ug/L	0.50

QC LOT ASSIGNMENT REPORT
Metals Analysis and Preparation

Laboratory Sample Number	QC Matrix	QC Category	QC Lot Number (DCS)	QC Run Number (SCS/BLANK)
024601-0001-SA	AQUEOUS	ICP-AT	10 SEP 92-1A	10 SEP 92-1A
024601-0001-SA	AQUEOUS	AS-FAA-AT	10 SEP 92-1A	10 SEP 92-1A
024601-0001-SA	AQUEOUS	PB-FAA-AT	10 SEP 92-1A	10 SEP 92-1A
024601-0001-SA	AQUEOUS	HG-CVAA-AT	13 SEP 92-1A	13 SEP 92-1A
024601-0002-SA	SOIL	AS-FAA-S	11 SEP 92-1A	11 SEP 92-1A
024601-0002-SA	SOIL	ICP-S	14 SEP 92-1R	14 SEP 92-1R
024601-0002-SA	SOIL	PB-FAA-S	14 SEP 92-1R	14 SEP 92-1R

DUPLICATE CONTROL SAMPLE REPORT
Metals Analysis and Preparation

Analyte	Concentration			AVG	Accuracy Average(%)		Precision (RPD)	
	Spiked	DCS1	Measured DCS2		DCS	Limits	DCS	Limit
Category: ICP-AT								
Matrix: AQUEOUS								
QC Lot: 10 SEP 92-1A								
Concentration Units: mg/L								
Aluminum	2.0	2.03	2.04	2.03	102	75-125	0.2	20
Antimony	0.5	0.510	0.499	0.505	101	75-125	2.2	20
Arsenic	0.5	0.480	0.453	0.467	93	75-125	5.7	20
Barium	2.0	1.92	1.93	1.92	96	75-125	0.4	20
Beryllium	0.05	0.0500	0.0497	0.0498	100	75-125	0.6	20
Cadmium	0.05	0.0468	0.0442	0.0455	91	75-125	5.7	20
Calcium	100	103	102	103	103	75-125	1.0	20
Chromium	0.2	0.190	0.195	0.192	96	75-125	2.6	20
Cobalt	0.5	0.471	0.467	0.469	94	75-125	0.9	20
Copper	0.25	0.281	0.269	0.275	110	75-125	4.4	20
Iron	1.0	1.01	1.00	1.01	101	75-125	1.0	20
Lead	0.5	0.472	0.475	0.473	95	75-125	0.7	20
Magnesium	50	51.1	50.6	50.8	102	75-125	1.0	20
Manganese	0.5	0.489	0.477	0.483	97	75-125	2.5	20
Nickel	0.5	0.483	0.478	0.480	96	75-125	1.1	20
Potassium	50	52.5	51.9	52.2	104	75-125	1.2	20
Silver	0.05	0.0488	0.0477	0.0483	97	75-125	2.2	20
Sodium	100	110	109	109	109	75-125	1.6	20
Vanadium	0.5	0.495	0.497	0.496	99	75-125	0.4	20
Zinc	0.5	0.496	0.489	0.492	98	75-125	1.6	20

Category: AS-FAA-AT
Matrix: AQUEOUS
QC Lot: 10 SEP 92-1A
Concentration Units: mg/L

Arsenic	0.03	0.0329	0.0348	0.0338	113	75-125	5.6	20
---------	------	--------	--------	--------	-----	--------	-----	----

Category: PB-FAA-AT
Matrix: AQUEOUS
QC Lot: 10 SEP 92-1A
Concentration Units: mg/L

Lead	0.03	0.0349	0.0313	0.0331	110	75-125	11	20
------	------	--------	--------	--------	-----	--------	----	----

Calculations are performed before rounding to avoid round-off errors in calculated results.

DUPLICATE CONTROL SAMPLE REPORT
Metals Analysis and Preparation (cont.)

Analyte	Concentration				AVG	Accuracy		Precision	
	Spiked	DCS1	Measured DCS2	DCS		Average (%)	Limits	(RPD)	DCS Limit
Category: HG-CVAA-AT Matrix: AQUEOUS QC Lot: 13 SEP 92-1A Concentration Units: mg/L									
Mercury	0.0010	0.000967	0.00100	0.000983	98	75-125	3.4	20	
Category: AS-FAA-S Matrix: SOIL QC Lot: 11 SEP 92-1A Concentration Units: mg/kg									
Arsenic	145	102	104	103	71	59-141	1.0	20	
Category: ICP-S Matrix: SOIL QC Lot: 14 SEP 92-1R Concentration Units: mg/kg									
Aluminum	10700	6840	7480	7160	67	47-153	8.8	20	
Antimony	55.2	54.8	57.4	56.1	102	18-362	4.6	50	
Arsenic	145	128	135	131	91	59-141	4.9	20	
Barium	503	435	459	447	89	76-124	5.5	20	
Beryllium	129	118	124	121	94	53-131	4.9	20	
Cadmium	154	140	147	144	93	68-132	4.6	20	
Calcium	7390	6600	6960	6780	92	79-121	5.4	20	
Chromium	151	127	136	132	87	66-133	6.9	20	
Cobalt	122	110	116	113	93	70-130	5.4	20	
Copper	162	156	165	161	99	70-132	5.4	20	
Iron	15400	12400	13400	12900	84	66-134	7.2	20	
Lead	148	129	139	134	90	66-135	6.9	20	
Magnesium	3740	3250	3480	3360	90	74-126	7.0	20	
Manganese	423	376	397	387	91	74-125	5.5	20	
Molybdenum	159	145	152	148	93	71-129	5.1	20	
Nickel	166	154	162	158	95	67-133	5.1	20	
Potassium	4050	3530	3770	3650	90	68-132	6.6	20	
Silver	104	98.2	106	102	98	76-124	7.6	20	
Sodium	747	717	766	741	99	57-130	6.6	20	
Vanadium	154	135	142	138	90	73-127	5.2	20	
Zinc	530	478	504	491	93	65-135	5.3	20	

Calculations are performed before rounding to avoid round-off errors in calculated results.

DUPLICATE CONTROL SAMPLE REPORT
Metals Analysis and Preparation (cont.)

Analyte	Spiked	Concentration		Measured	AVG	Accuracy		Precision	
		DCS1	DCS2			DCS	Limits	DCS	Limit
Category: PB-FAA-S Matrix: SOIL QC Lot: 14 SEP 92-1R Concentration Units: mg/kg									
Lead	150	132	148	140	93	50-150	11	20	

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT
Metals Analysis and Preparation

Analyte	Result	Units	Reporting Limit
Test: ICP-AT Matrix: AQUEOUS QC Lot: 10 SEP 92-1A QC Run: 10 SEP 92-1A			
Barium	ND	mg/L	0.010
Cadmium	0.0099	mg/L	0.0050
Chromium	ND	mg/L	0.010
Test: AS-FAA-AT Matrix: AQUEOUS QC Lot: 10 SEP 92-1A QC Run: 10 SEP 92-1A			
Arsenic	ND	mg/L	0.0050
Test: PB-FAA-AT Matrix: AQUEOUS QC Lot: 10 SEP 92-1A QC Run: 10 SEP 92-1A			
Lead	ND	mg/L	0.0050
Test: HG-CVAA-AT Matrix: AQUEOUS QC Lot: 13 SEP 92-1A QC Run: 13 SEP 92-1A			
Mercury	ND	mg/L	0.00020
Test: AS-FAA-W Matrix: WASTE QC Lot: 11 SEP 92-1A QC Run: 11 SEP 92-1A			
Arsenic	ND	mg/kg	0.50
Test: ICP-W Matrix: WASTE QC Lot: 14 SEP 92-1R QC Run: 14 SEP 92-1R			
Cadmium	ND	mg/kg	0.50
Chromium	ND	mg/kg	1.0

METHOD BLANK REPORT
Metals Analysis and Preparation (cont.)

Analyte	Result	Units	Reporting Limit
Test: PB-FAA-W			
Matrix: WASTE			
QC Lot: 14 SEP 92-1R QC Run: 14 SEP 92-1R			
Lead	ND	mg/kg	0.50

QC LOT ASSIGNMENT REPORT
Wet Chemistry Analysis and Preparation

Laboratory Sample Number	QC Matrix	QC Category	QC Lot Number (DCS)	QC Run Number (SCS/BLANK)
024601-0001-SA	AQUEOUS	PH-A	19 AUG 92-1G	-
024601-0001-SA	AQUEOUS	TDS-A	25 AUG 92-1A	25 AUG 92-1A
024601-0001-SA	AQUEOUS	TOX-A	10 SEP 92-1A	-
024601-0002-SA	SOIL	TOX-S	15 SEP 92-1A	-


DUPLICATE CONTROL SAMPLE REPORT
Wet Chemistry Analysis and Preparation

Analyte	Spiked	Concentration		Measured	AVG	Accuracy		Precision	
		DCS1	DCS2			DCS	Limits	DCS	Limit
Category: PH-A Matrix: AQUEOUS QC Lot: 19 AUG 92-1G Concentration Units: units									
pH	9.1	9.04	9.05	9.04	99	98-102	0.1	5	
Category: TDS-A Matrix: AQUEOUS QC Lot: 25 AUG 92-1A Concentration Units: mg/L									
Total Dissolved Solids	1170	1150	1130	1140	97	90-110	1.8	10	
Category: TOX-A Matrix: AQUEOUS QC Lot: 10 SEP 92-1A Concentration Units: ug Cl/L									
Total Organic Halogen as Cl	100	90.0	90.6	90.3	90	80-120	0.7	20	
Category: TOX-S Matrix: SOIL QC Lot: 15 SEP 92-1A Concentration Units: mg/kg									
Total Organic Halogen as Cl	1.0	0.955	1.05	1.00	100	75-125	9.5	20	

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT
Wet Chemistry Analysis and Preparation

Analyte	Result	Units	Reporting Limit
Test: TDS-BAL-A			
Matrix: AQUEOUS			
QC Lot: 25 AUG 92-1A	QC Run: 25 AUG 92-1A		
Total Dissolved Solids	ND	mg/L	10.0



Appendix



Rocky Mountain Analytical Laboratory
 4955 Yarrow Street
 Arvada, CO 80002
 303/421-6611 FAX: 303/431-7171

CHAIN OF CUSTODY

ENSECO CLIENT	SAMPLE SAFE™ CONDITIONS	
	PACKED BY	SEAL NUMBER
PROJECT	SEAL INTACT UPON RECEIPT BY SAMPLING COMPANY	CONDITION OF CONTENTS
SAMPLING COMPANY	SEALED FOR SHIPPING BY	INITIAL CONTENTS TEMP. °C
SAMPLING SITE	SEAL NUMBER	SAMPLING STATUS <input type="checkbox"/> Done <input type="checkbox"/> Continuing Until
TEAM LEADER	SEAL INTACT UPON RECEIPT BY LAB. <input type="checkbox"/> Yes <input type="checkbox"/> No	CONTENTS TEMPERATURE UPON RECEIPT BY LAB. °C

DATE	TIME	SAMPLE ID/DESCRIPTION	SAMPLE TYPE	# CONTAINERS	ANALYSIS PARAMETERS	REMARKS
8-18-92	12:49	WASTE CEDAR HILL CDP WATER TANK	LIQUID AQUEOUS	1	PH / TDS	01
8-18-92	12:50	" " "	LIQUID AQUEOUS	1	PH / TDS	02
8-18-92	12:45	" " "	LIQUID METALS	4T	METALS	01 01
8-18-92	12:47	" " "	LIQUID METALS	4T	METALS	02
8-18-92	12:40	" " "	LIQUID	15	Tox -- SINGLE	01
8-18-92	12:40	" " "	LIQUID	15	Tox -- SINGLE	02
8-18-92	11:30	WASTE OIL TANK CEDAR HILL	USED OIL			
8-18-92	11:45	WASTE OIL TANK CEDAR HILL	USED OIL			02
8-18-92	11:50	WASTE OIL TANK CEDAR HILL	USED OIL			
8-18-92	12:00	WASTE OIL TANK CEDAR HILL	USED OIL			

CUSTODY TRANSFERS PRIOR TO SHIPPING				SHIPPING DETAILS	
RELINQUISHED BY (SIGNED)	RECEIVED BY (SIGNED)	DATE	TIME	DELIVERED TO SHIPPER BY	
<i>Veron Kettler</i>	<i>Frank Geller</i>	8/18/92	2:07	METHOD OF SHIPMENT	
				AIRBILL NUMBER	
				RECEIVED FOR LAB	SIGNED
				<i>RMMK</i>	<i>John Paul</i>
				ENSECO PROJECT NUMBER	DATE/TIME
				24601	0845 8/19/92



Rocky Mountain Analytical Laboratory
 4955 Yarrow Street
 Arvada, CO 80002
 303/421-6611 FAX: 303/431-7171

CHAIN OF CUSTODY

		SAMPLE SAFE™ CONDITIONS	
ENSECO CLIENT		PACKED BY	SEAL NUMBER
PROJECT		SEAL INTACT UPON RECEIPT BY SAMPLING COMPANY	CONDITION OF CONTENTS
SAMPLING COMPANY		SEALED FOR SHIPPING BY	INITIAL CONTENTS TEMP. °C
SAMPLING SITE		SEAL NUMBER	SAMPLING STATUS <input type="checkbox"/> Done <input type="checkbox"/> Continuing Until
TEAM LEADER		SEAL INTACT UPON RECEIPT BY LAB. <input type="checkbox"/> Yes <input type="checkbox"/> No	CONTENTS TEMPERATURE UPON RECEIPT BY LAB. °C

DATE	TIME	SAMPLE ID/DESCRIPTION	SAMPLE TYPE	# CONTAINERS	ANALYSIS PARAMETERS	REMARKS
8-18-92	12:51	CEDAR HILL COP WASTE WATER	LIQUIDS AQUEOUS	11	VOA	} 01
8-18-92	12:53	"	LIQUIDS AQUEOUS	11	VOA	
8-18-92	12:55	"	LIQUIDS AQUEOUS	11	VOA	

CUSTODY TRANSFERS PRIOR TO SHIPPING				SHIPPING DETAILS	
RELINQUISHED BY (SIGNED)	RECEIVED BY (SIGNED)	DATE	TIME	DELIVERED TO SHIPPER BY	
				METHOD OF SHIPMENT	AIRBILL NUMBER
				RECEIVED FOR LAB <i>PAITAL</i>	SIGNED <i>[Signature]</i>
				ENSECO PROJECT NUMBER <i>24601</i>	DATE/TIME <i>0815 8/19/92</i>

APPENDIX B

SPILL CONTROL PROCEDURES

WILLIAMS FIELD SERVICES COMPANY
 ONE OF THE WILLIAMS COMPANIES
OPERATIONS

Manual O & M Procedure	Department	
Section Safety/General	Tab 10	Document No. 21.10.020
Effective Date JUN 16 1993	Issue No. 1	Page No. 1 of 6

Subject of Title
 DISCHARGES OR SPILLS OF OIL OR HAZARDOUS SUBSTANCES; Preventing, Controlling and Reporting of

A. PURPOSE AND SCOPE

- A.1** To establish the policy and procedure for preventing, controlling, and reporting of spills or discharges of oil or hazardous substances to the environment in accordance with Company practices and federal, state, and local requirements, including Title 40 of the Code of Federal Regulations - Part 112 (Oil Pollution Prevention).
- A.2** This document pertains to Company personnel and Company and non-company facilities. The spill prevention and control requirements in this Policy and Procedure are Federally mandated guidelines for oil pollution prevention. The Company policy is to also apply these standards, where appropriate, to facilities containing hazardous substances. This is a discretionary application of the standards; however, variations from the standards should be approved by the responsible Director.

B. CONTENTS

C. POLICY

- C.1 General
- C.2 Bulk Storage Tanks
- C.3 Facility Drainage
- C.4 Transfer Operations, Pumping, and In-Plant/Station Process
- C.5 Facility Tank Car and Tank Truck Loading/Unloading Rack

D. PROCEDURE

- D.1 Identifying, Containing and Initial Reporting of a Discharge or Spill of a Hazardous or Toxic Substance
- D.2 Submitting Written Notification of a Discharge or Spill

ATTACHMENT A: Discharge or Spill Containment Procedures and Materials

C. POLICY

C.1 GENERAL

- C.1.1** All Company facilities which could discharge or spill oil or hazardous substances which may affect natural resources or present an imminent and substantial danger to the public health or welfare including, but not limited to fish, shellfish, wildlife, shorelines, and beaches are subject to the provisions of this document.
- C.1.2** Hazardous Substance, for purposes of this procedure, is defined as any chemical or material that has or should have a Material Safety Data Sheet (MSDS); however, hazardous substances are further defined by the following environmental statutes:
- a. Section 101 (N) and Section 102 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)
 - b. Section 307(a) and Section 311 (b)(2)(A) of the Clean Water Act
 - c. Section 3001 of the Solid Waste Act (excluding items suspended by Congress)
 - d. Section 112 of the Clean Air Act
 - e. Section 7 of the Toxic Substance Control Act

Supersedes Policy and Procedure 12.10.020 dated July 7, 1989.

Approval (Page 1 Only) <i>[Signature]</i>	Approval (Page 1 Only) <i>[Signature]</i> 6/18/93	Approval (Page 1 Only) <i>[Signature]</i>
--	--	--

OPERATIONS

Manual O & M Procedure	Department	
Section Safety/General	Tab 10	Document No. 21.10.020
Effective Date	Issue No. 1	Page No. 2 of 6

Subject of Title

DISCHARGES OR SPILLS OF OIL OR HAZARDOUS SUBSTANCES; Preventing, Controlling and Reporting of

- C.1.3 The term hazardous substance does not include petroleum, including crude oil or any fraction thereof, which is not otherwise specifically listed or designated as a hazardous substance in the first sentence of this paragraph, and the term does not include natural gas, natural gas liquids, liquefied natural gas or synthetic gas usable for fuel (or mixtures of natural gas and such synthetic gas).
- C.1.4 Oil, for the purpose of this document, means oil of any kind or in any form, including but not limited to petroleum, fuel oil, Y grade, mixed products, sludge, oil refuse, and oil mixed with wastes other than dredged spoil (earth and rock). LPG (propane, butane, ethane) are not considered to be oil.
- C.1.5 Facilities which could discharge or spill oil or hazardous substances into a watercourse must comply with the required federal, state, or local laws and regulations. A discharge includes but is not limited to any spilling, leaking, pumping, pouring, emitting, emptying, or dumping. A watercourse is any perennial or intermittent river, stream, gully, wash, lake, or standing body of water capable of collecting or transporting an oil or hazardous substance.
- C.1.6 Facilities which are subject to the requirements stated in this policy are as follows:
- a. Non-Transportation Related Facilities
 - (1) Storage or drip tanks and other aboveground containers (excluding pressurized or inline process vessels) having a capacity in excess of 660 gallons for each single container or an aggregate capacity of 1,321 gallons or more for multiple containers.
 - (2) Underground storage facilities having a total capacity in excess of 42,000 gallons.
 - b. Transportation Related Facilities
 - (1) All vehicles, pipeline facilities, loading/unloading facilities, and other mobile facilities which transport oil or hazardous substances.
- C.1.7 Each Company location which has facilities subject to paragraph C.1.1 shall have a site specific Spill Prevention Control and Countermeasure Plan (SPCC Plan) which identifies all facilities subject to 40 CFR 112. The plan shall identify all hazardous substance storage vessels at the facility and the spill prevention measures in place to control discharges or spills. This plan shall also identify all regulatory agencies that must be notified in case of a spill.
- C.1.8 The facility supervisor is responsible for spill prevention. His/her duties include, but are not limited to, the following:
- a. Instructing personnel in the operation and maintenance of equipment to prevent the discharge of oil.
 - b. Conduct briefings for operating personnel at intervals frequent enough to assure adequate understanding of the Spill Plan at that facility.
 - c. Briefings should highlight and describe known discharges or spills, and recently developed precautionary measures.
- C.1.9 Each individual facility is checked by the supervisor or designee to determine the potential for discharges or spills of oil or hazardous substances in harmful quantities that violate water quality standards or which may cause a film, sheen, or discoloration on the surface of water. All facilities which have the potential for discharging or spilling harmful quantities of oil or hazardous substances into a watercourse are required to have the following preventive measures:
- a. Examination of all tanks, valves and fittings, at least annually, to determine any maintenance requirements.

OPERATIONS

Manual O & M Procedure	Department	
Section Safety/General	Tab 10	Document No. 21.10.020
Effective Date	Issue No. 1	Page No. 3 of 6

Subject of Title
DISCHARGES OR SPILLS OF OIL OR HAZARDOUS SUBSTANCES; Preventing, Controlling and Reporting of

- b. All tank batteries should, as far as practicable, have a secondary means of containment for the entire contents of the largest single tank plus sufficient freeboard in the containment facility to allow for precipitation.
- c. A annual monitoring and inspection program to prevent accidental spills or discharges into watercourses. This includes annual inspection for faulty systems and monitoring line valves and liquid pipelines for leaks or blowouts.

C.1.10 Any field drainage ditches, road ditches, traps, sumps, or skimmers should be inspected at annual scheduled intervals for accumulation of liquid hydrocarbons or other hazardous substances which may have escaped from small leaks. Any such accumulations should be removed.

C.2 BULK STORAGE TANKS

C.2.1 A tank should not be used for storage of oil or hazardous substances unless the material and construction of the tank is compatible with the material stored and conditions of storage such as pressure and temperature. Buried storage tanks must be protected from corrosion by coatings, cathodic protection, or other methods compatible with local soil conditions. Aboveground tanks should be subject to visual inspection for system integrity.

C.2.2 The facility supervisor should evaluate level monitoring requirements to prevent tank overflow.

C.2.3 Leaks which result in loss of oil or hazardous substances from tank seams, gaskets, rivets and bolts sufficiently large to cause accumulation of oil or hazardous substances in diked areas should be promptly corrected.

C.2.4 Mobile or portable oil or hazardous substances storage tanks should be positioned or located to prevent the contents from reaching a watercourse. The mobile facilities should be located so their support structure will not be undermined by periodic flooding or washout.

C.3 FACILITY DRAINAGE

C.3.1 Make provisions for drainage from diked storage areas where necessary in areas with high precipitation levels. Drainage from dike areas should be restrained by valves or other means to prevent a discharge or spill. Diked areas should be emptied by pumps or ejectors which are manually activated. Valves used for the drainage of diked areas should be of manual, open-and-closed design.

C.3.2 Rain water may be drained from diked areas providing drainage water does not contain oil or hazardous substances that may cause a harmful discharge. Drain valves must be closed following drainage of diked areas.

C.3.3 When possible, drainage systems from undiked areas should flow into ponds, lagoons, or catchment basins designed to retain oil or hazardous substances or return the substances to the facility. Any drainage system which is not designed to allow flow into ponds, lagoons, or catchment basins should be equipped with a diversion system that could, in the event of a discharge or spill, contain the oil or hazardous substances on the Site.

C.3.4 The principal means of containing discharges or spills is the use of dikes which are constructed wherever regulated quantities of oil or hazardous substances have the potential of reaching a watercourse. The construction of dikes must meet the following requirements:

- a. Capacity must be at least equivalent to the storage capacity of the largest tank of the battery plus sufficient freeboard to allow for precipitation, or displacement by foreign materials.
- b. Small dikes for temporary containment are constructed at valves where potential leaking of oil or hazardous substances may occur.

OPERATIONS

Manual O & M Procedure	Department	
Section Safety/General	Tab 10	Document No. 21.10.020
Effective Date	Issue No. 1	Page No. 4 of 6

Subject of Title

DISCHARGES OR SPILLS OF OIL OR HAZARDOUS SUBSTANCES; Preventing, Controlling and Reporting of

- c. Any dike three feet or higher should have a minimum cross section of two feet at the top.

C.3.5 Other means of containment or spill control include, but are not limited to:

- a. Berms or retaining walls;
- b. Curbing;
- c. Culverting, gutters, or other drainage systems;
- d. Weirs, booms, or other barriers;
- e. Spill diversion ponds or retention ponds;
- f. Sorbent materials

C.4 TRANSFER OPERATIONS, PUMPING, AND IN-PLANT/STATION PROCESS

C.4.1 Aboveground valves and pipelines should be examined annually by operating personnel to determine whether there are any leaks from flange joints, expansion joints, valve glands and bodies, catch pans, pipeline supports, valve locks, and metal surfaces.

C.5 FACILITY TANK CAR AND TANK TRUCK LOADING/UNLOADING RACK

C.5.1 Rack area drainage which does not flow into a catchment basin or treatment facility designed to handle spills should have a quick drainage system for use in tank truck loading and unloading areas. The containment system should have a maximum capacity of any single compartment of a truck loaded or unloaded in the station.

C.5.2 Aboveground piping that has potential for damage by vehicles entering the Site should be protected by logically placed warning signs or by concrete-filled pipe barriers.

C.5.3 Loading and unloading areas should be provided with an interlocked warning light, grounding shutdown, physical barrier system, or warning signs to prevent vehicular departure before complete disconnect of flexible or fixed transfer lines. All drains and outlets of any truck should be closely examined for leakage prior to filling and departure. All drains and outlets which may allow leakage should be tightened, adjusted, or replaced to prevent liquid leakage while in transit.

NOTE: LPG loading facilities and remote field loading of condensate are exempt from the C.5 requirements of this document.

D. PROCEDURE

D.1 IDENTIFYING, CONTAINING AND INITIAL REPORTING OF A DISCHARGE OR SPILL OF OIL OR HAZARDOUS SUBSTANCE

Any Employee

D.1.1 Upon noticing a discharge or spill of an oil or hazardous substance in any quantity initiates immediate containment procedures and notifies facility supervisor.

NOTE: Refer to Attachment A for containment procedures.

Facility Supervisor

D.1.2 Contacts Gas Control and responsible Director immediately by telephone and provides the following information:

- a. Name of company facility and/or location of facility and nature of discharge or spill
- b. Description and quantity of emission or substance discharged
- c. Name, title, and telephone number of person initially reporting the discharge or spill and person reporting to Gas Control
- d. Action taken or being taken to mitigate and correct discharge or spill
- e. Water bodies or streams involved
- f. Time and duration of discharge or spill
- g. Outside involvement during discharge or spill (public government agencies, etc. See Emergency Operating Procedure Manuals)

WILLIAMS FIELD SERVICES COMPANY
 ONE OF THE WILLIAMS COMPANIES 
OPERATIONS

Manual O & M Procedure	Department	
Section Safety/General	Tab 10	Document No. 21.10.020
Effective Date	Issue No. 1	Page No. 5 of 6

Subject of Title

DISCHARGES OR SPILLS OF OIL OR HAZARDOUS SUBSTANCES; Preventing, Controlling and Reporting of

Gas Control Personnel

D.1.3 Advises Environmental Services departments immediately by telephone concerning the incident including any incidents reported by persons not employed with the Company.

NOTE: If Gas Control is contacted by a person not employed with the Company, the necessary information is obtained as indicated in D.1.2 and the Supervisor and Environmental Services are immediately contacted to begin containment and clean-up of the discharge or spill.

D.1.4 If Environmental Services cannot be contacted, notifies Director over Environmental Services.

Facility Supervisor

D.1.5 Coordinates containment and clean-up of discharge or spill, keeping the responsible Director informed.

D.1.6 If the discharge or spill is too large for Company personnel to contain, contacts qualified local contractors for assistance. (See Emergency Operating Procedure Manuals tab #11, contractors with available equipment and services).

D.1.7 Advises Environmental Services by telephone if emergency containment or clean-up assistance from a state agency or a response team from the U.S. Coast Guard is required.

Environmental Services

D.1.8 Contacts Legal Department (and Right-of-Way Department, if appropriate) and assesses reporting requirements to state and federal agencies. (See Emergency Operating Procedure Manuals).

D.1.9 Makes appropriate contacts with U.S. Coast Guard and state agencies when necessary.

D.1.10 If spill is significant, dispatches Environmental Specialist to scene to oversee cleanup and reporting responsibilities.

D.2 SUBMITTING WRITTEN NOTIFICATION OF A DISCHARGE OR SPILL

Facility Supervisor

D.2.1 Completes a written description of the incident as soon as possible after initial notification is given, which should include the following:

- a. Time and date of discharge or spill
- b. Facility name and location
- c. Type of material spilled
- d. Quantity of material spilled
- e. Area affected
- f. Cause of spill
- g. Special circumstances
- h. Corrective measures taken
- i. Description of repairs made
- j. Preventative measures taken to prevent recurrence.

D.2.2 Forwards the completed report to Environmental Services and a copy to Legal Department. Retains a copy for future reference.

NOTE: Environmental Services, in coordination with the Legal Department, submits written reports to government agencies.

WILLIAMS FIELD SERVICES COMPANY
 ONE OF THE WILLIAMS COMPANIES
OPERATIONS

Manual O & M Procedure	Department	
Section Safety/General	Tab 10	Document No. 21.10.020
Effective Date	Issue No. 1	Page No. 6 of 6

Subject of Title
 DISCHARGES OR SPILLS OF OIL OR HAZARDOUS SUBSTANCES; Preventing, Controlling and Reporting of

ATTACHMENT A

Discharge or Spill Containment Procedures and Materials

Type of Facility where the Discharge or Spill occurs	Containment Procedures	Material Used for Containment
A. Oil Pipeline (as defined in C.1.4)	<ol style="list-style-type: none"> 1. Closes appropriate block valves. 2. Contains discharge or spill by: ditching covering, applying sorbents, constructing an earthen dam, or burning. 3. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning. 	<ol style="list-style-type: none"> 1. Straw 2. Loose Earth 3. Oil Sorbent - 3M Brand 4. Plain Wood Chips 5. Sorb - Oil Chips Banta Co. 6. Sorb - Oil Swabs - Banta Co. 7. Sorb - Oil Mats - Banta Co. 8. Or Equivalent Materials.
B. Vehicle	<ol style="list-style-type: none"> 1. Contains discharge or spill by: ditching, covering surface with dirt, constructing earthen dams, applying sorbents, or burning. 2. Notifies immediately the Compliance and Safety Department and if there is any imminent danger to local residents; notifies immediately the highway patrol or local police officials. 3. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning. <p>NOTE: Any vehicle carrying any hazardous or toxic substance will carry a shovel or other ditching device to contain a spill. If the vehicle has sufficient room, sorbent materials should also be carried.</p>	
C. Bulk Storage Tanks or any other Facilities	<ol style="list-style-type: none"> 1. Contains discharge or spill by: ditching, covering, applying sorbents, constructing an earthen dam, or burning. 2. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning. 	

APPENDIX C

NMOCD NOTIFICATION OF FIRE, BREAKS, SPILLS, LEAKS, AND BLOWOUTS

DISTRICT I
P.O. Box 1980, Hobbs, NM 88241-1980

DISTRICT II
O. Drawer DD, Artesia, NM 88211-0719

DISTRICT III
1000 Rio Brazos Rd, Aztec, NM 87410

State of New Mexico
Energy, Minerals and Natural Resources Department

OIL CONSERVATION DIVISION
P.O. Box 2088
Santa Fe, New Mexico 87504-2088

SUBMIT 2 COPIES TO
APPROPRIATE DISTRICT
OFFICE IN ACCORDANCE
WITH RULE 116 PRINTED
ON BACK SIDE OF FORM

NOTIFICATION OF FIRE, BREAKS, SPILLS, LEAKS, AND BLOWOUTS

OPERATOR					ADDRESS			TELEPHONE #	
REPORT OF	FIRE	BREAK	SPILL	LEAK	BLOWOUT	OTHER*			
TYPE OF FACILITY	DRLG WELL	PROD WELL	TANK BTRY	PIPE LINE	GASO PLNT	OIL RFY	OTHER*		
FACILITY NAME:									
LOCATION OF FACILITY					SEC.	TWP.	RGE.	COUNTY	
Qtr/Qtr Sec. or Footage									
DISTANCE AND DIRECTION FROM NEAREST TOWN OR PROMINENT LANDMARK									
DATE AND HOUR OF OCCURRENCE				DATE AND HOUR OF DISCOVERY					
WAS IMMEDIATE NOTICE GIVEN?	YES	NO	NOT REQUIRED	IF YES, TO WHOM					
BY WHOM				DATE AND HOUR					
TYPE OF FLUID LOST				QUANTITY OF LOSS			VOLUME RECOVERED		
DID ANY FLUIDS REACH A WATERCOURSE?	YES	NO	QUANTITY						
IF YES, DESCRIBE FULLY**									
DESCRIBE CAUSE OF PROBLEM AND REMEDIAL ACTION TAKEN**									
DESCRIBE AREA AFFECTED AND CLEANUP ACTION TAKEN**									
DESCRIPTION OF AREA	FARMING	GRAZING	URBAN	OTHER*					
SURFACE CONDITIONS	SANDY	SANDY LOAM	CLAY	ROCKY	WET	DRY	SNOW		
DESCRIBE GENERAL CONDITIONS PREVAILING (TEMPERATURE, PRECIPITATION, ETC.)**									
I HEREBY CERTIFY THAT THE INFORMATION ABOVE IS TRUE AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF									
SIGNED	PRINTED NAME AND TITLE				DATE				

A. The Division shall be notified of any fire, break, leak, spill, or blowout occurring at any injection or disposal facility or at any oil or gas drilling, producing, transporting, or processing facility in the State of New Mexico by the person operating or controlling such facility.

B. "Facility," for the purpose of this rule, shall include any oil or gas well, any injection or disposal well, and any drilling or workover well; any pipe line through which crude oil, condensate, casinghead or natural gas, or injection or disposal fluid (gaseous or liquid) is gathered, piped, or transported (including field flow-lines and lead-lines but not including natural gas distribution systems); any receiving tank, holding tank, or storage tank, or receiving and storing receptacle into which crude oil, condensate, injection or disposal fluid, or casinghead or natural gas is produced, received, or stored; any injection or disposal pumping or compression station including related equipment; any processing or refining plant in which crude oil, condensate, or casinghead or natural gas is processed or refined; and any tank or drilling pit or slush pit associated with oil or gas well or injection or disposal well drilling operations or any tank, storage pit, or pond associated with oil or gas production or processing operations or with injection or disposal operations and containing hydrocarbons or hydrocarbon waste or residue, salt water, strong caustics or strong acids, or other deleterious chemicals or harmful contaminants.

C. Notification of such fire, break, leak, spill, or blowout shall be in accordance with the provisions set forth below:

(1) Well Blowouts. Notification of well blowouts and/or fires shall be "immediate notification" described below. ("Well blowout" is defined as being loss of control over and subsequent eruption of any drilling or workover well, or the rupture of the casing, casinghead, or wellhead or any oil or gas well or injection or disposal well, whether active or inactive, accompanied by the sudden emission of fluids, gaseous or liquid, from the well.)

(2) "Major" Breaks, Spills, or Leaks. Notification of breaks, spills, or leaks of 25 or more barrels of crude oil or condensate, or 100 barrels or more of salt water, none of which reaches a watercourse or enters a stream or lake; breaks, spills, or leaks in which one or more barrels of crude oil or condensate or 25 barrels or more of salt water does reach a watercourse or enters a stream or lake; and breaks, spills, or leaks of hydrocarbons or hydrocarbon waste or residue, salt water, strong caustics or strong acids, gases, or other deleterious chemicals or harmful contaminants of any magnitude which may with reasonable probability endanger human health or result in substantial damage to property, shall be "immediate notification" described below.

(3) "Minor" Breaks, Spills, or Leaks. Notification of breaks, spills, or leaks of 5 barrels or more but less than 25 barrels of crude oil or condensate, or 25 barrels or more but less than 100 barrels of salt water, none of which reaches a watercourse or enters a stream or lake, shall be "subsequent notification" described below.

(4) "Gas Leaks and Gas Line Breaks. Notification of gas leaks from any source or of gas pipe line breaks in which natural or casinghead gas of any quantity has escaped or is escaping which may with reasonable probability endanger human health or result in substantial damage to property shall be "immediate notification" described below. Notification of gas pipe line breaks or leaks in which the loss is estimated to be 1000 or more MCF of natural or casinghead gas but in which there is no danger to human health nor of substantial damage to property shall be "subsequent notification" described below.

(5) Tank Fires. Notification of fires in tanks or other receptacles caused by lightning or any other cause, if the loss is, or it appears that the loss will be, 25 or more barrels of crude oil or condensate, or fires which may with reasonable probability endanger human health or result in substantial damage to property, shall be "immediate notification" as described below. If the loss is, or it appears that the loss will be at least 5 barrels but less than 25 barrels, notification shall be "subsequent notification" described below.

(6) Drilling Pits, Slush Pits, and Storage Pits and Ponds. Notification of breaks and spills from any drilling pit, slush pit, or storage pit or pond in which any hydrocarbon or hydrocarbon waste or residue, strong caustic or strong acid, or other deleterious chemical or harmful contaminant endangers human health or does substantial surface damage, or reaches a watercourse or enters a stream or lake in such quantity as may with reasonable probability endanger human health or result in substantial damage to such watercourse, stream, or lake, or the contents thereof, shall be "immediate notification" as described below. Notification of breaks or spills of such magnitude as to not endanger human health, cause substantial surface damage, or result in substantial damage to any watercourse, stream, or lake, or the contents thereof, shall be "subsequent notification" described below, provided however, no notification shall be required where there is no threat of any damage resulting from the break or spill.

(7) IMMEDIATE NOTIFICATION. "Immediate Notification" shall be as soon as possible after discovery and shall be either in person or by telephone to the district office of the Division district in which the incident occurs, or if the incident occurs after normal business hours, to the District Supervisor, the Oil and Gas Inspector, or the Deputy Oil and Gas Inspector. A complete written report ("Subsequent Notification") of the incident shall also be submitted in DUPLICATE to the appropriate district office of the Division within ten days after discovery of the incident.

(8) SUBSEQUENT NOTIFICATION. "Subsequent Notification" shall be a complete written report of the incident and shall be submitted in duplicate to the district office of the Division district in which the incident occurred within ten days after discovery of the incident.

(9) CONTENT OF NOTIFICATION. All reports of fires, breaks, leaks, spills, or blowouts, whether verbal or written, shall identify the location of the incident by quarter-quarter, section, township, and range, and by distance and direction from the nearest town or prominent landmark so that the exact site of the incident can be readily located on the ground. The report shall specify the nature and quantity of the loss and also the general conditions prevailing in the area, including precipitation, temperature, and soil conditions. The report shall also detail the measures that have been taken and are being taken to remedy the situation reported.

(10) WATERCOURSE. for the purpose of this rule, is defined as any lake-bed or gully, draw, stream bed, wash, arroyo, or natural or man-made channel through which water flows or has flowed.

1995 OCT 27 PM 1: 25

B. Plans, specifications and reports required by this Section, if related to facilities for the production, refinement and pipeline transmission of oil and gas, or products thereof, shall be filed instead with the Oil Conservation Division. [1-4-68, 12-1-95]

C. Plans and specifications required to be filed under this Section must be filed prior to the commencement of construction. [9-3-72]

1203. NOTIFICATION OF DISCHARGE--REMOVAL.

A. With respect to any discharge from any facility of oil or other water contaminant, in such quantity as may with reasonable probability injure or be detrimental to human health, animal or plant life, or property, or unreasonably interfere with the public welfare or the use of property, the following notifications and corrective actions are required: [2-17-74, 12-24-87]

1. As soon as possible after learning of such a discharge, but in no event more than twenty-four (24) hours thereafter, any person in charge of the facility shall orally notify the Chief of the Ground Water Protection and Remediation Bureau of the department, or his counterpart in any constituent agency delegated responsibility for enforcement of these rules as to any facility subject to such delegation. To the best of that person's knowledge, the following items of information shall be provided:

a. the name, address, and telephone number of the person or persons in charge of the facility, as well as of the owner and/or operator of the facility;

b. the name and address of the facility;

c. the date, time, location, and duration of the discharge;

d. the source and cause of discharge;

e. a description of the discharge, including its chemical composition;

f. the estimated volume of the discharge; and

g. any actions taken to mitigate immediate damage from the discharge.

[2-17-74, 2-20-81, 12-24-87, 12-1-95]

2. When in doubt as to which agency to notify, the

1995 OCT 27 PM 1: 25

person in charge of the facility shall notify the Chief of the Ground Water Protection and Remediation Bureau of the department. If that department does not have authority pursuant to commission delegation, the department shall notify the appropriate constituent agency. [12-24-87, 12-1-95]

3. Within one week after the discharger has learned of the discharge, the facility owner and/or operator shall send written notification to the same department official, verifying the prior oral notification as to each of the foregoing items and providing any appropriate additions or corrections to the information contained in the prior oral notification. [12-24-87]

4. The oral and written notification and reporting requirements contained in this Subsection A are not intended to be duplicative of discharge notification and reporting requirements promulgated by the Oil Conservation Commission (OCC) or by the Oil Conservation Division (OCD); therefore, any facility which is subject to OCC or OCD discharge notification and reporting requirements need not additionally comply with the notification and reporting requirements herein. [2-17-74, 12-24-87]

5. As soon as possible after learning of such a discharge, the owner/operator of the facility shall take such corrective actions as are necessary or appropriate to contain and remove or mitigate the damage caused by the discharge. [2-17-74, 12-24-87]

6. If it is possible to do so without unduly delaying needed corrective actions, the facility owner/operator shall endeavor to contact and consult with the Chief of the Ground Water Protection and Remediation Bureau of the department or appropriate counterpart in a delegated agency, in an effort to determine the department's views as to what further corrective actions may be necessary or appropriate to the discharge in question. In any event, no later than fifteen (15) days after the discharger learns of the discharge, the facility owner/operator shall send to said Bureau Chief a written report describing any corrective actions taken and/or to be taken relative to the discharge. Upon a written request and for good cause shown, the Bureau Chief may extend the time limit beyond fifteen (15) days. [12-24-87, 12-1-95]

7. The Bureau Chief shall approve or disapprove in writing the foregoing corrective action report within thirty (30) days of its receipt by the department. In the event that the report is not satisfactory to the department, the Bureau Chief shall specify in writing to the facility owner/operator any shortcomings in the report or in the corrective actions already taken or proposed to be taken relative to the discharge, and shall give the facility owner/operator a reasonable and clearly specified

1995 OCT 27 PM 1:25

time within which to submit a modified corrective action report. The Bureau Chief shall approve or disapprove in writing the modified corrective action report within fifteen (15) days of its receipt by the department. [12-24-87]

8. In the event that the modified corrective action report also is unsatisfactory to the department, the facility owner/operator has five (5) days from the notification by the Bureau Chief that it is unsatisfactory to appeal to the department secretary. The department secretary shall approve or disapprove the modified corrective action report within five (5) days of receipt of the appeal from the Bureau Chief's decision. In the absence of either corrective action consistent with the approved corrective action report or with the decision of the secretary concerning the shortcomings of the modified corrective action report, the department may take whatever enforcement or legal action it deems necessary or appropriate. [12-24-87, 12-1-95]

9. If the secretary determines that the discharge causes or may with reasonable probability cause water pollution in excess of the standards and requirements of Section 4103 of this Part, and the water pollution will not be abated within one hundred and eighty (180) days after notice is required to be given pursuant to Section 1203.A.1 of this Part, the secretary may notify the facility owner/operator that he is a responsible person and that an abatement plan may be required pursuant to Sections 4104 and 4106.A of this Part. [12-1-95]

B. Exempt from the requirements of this Section are continuous or periodic discharges which are made: [2-17-74]

1. in conformance with regulations of the commission and rules, regulations or orders of other state or federal agencies; or [2-17-74]

2. in violation of regulations of the commission, but pursuant to an assurance of discontinuance or schedule of compliance approved by the commission or one of its duly authorized constituent agencies. [2-17-74]

C. As used in this Section and in Sections 4100 through 4115, but not in other Sections of this Part: [2-17-74, 12-1-95]

1. "discharge" means spilling, leaking, pumping, pouring, emitting, emptying, or dumping into water or in a location and manner where there is a reasonable probability that the discharged substance will reach surface or subsurface water; [2-17-74]

2. "facility" means any structure, installation, operation, storage tank, transmission line, motor vehicle, rolling

1995 OCT 27 PM 1:25

stock, or activity of any kind, whether stationary or mobile;
[2-17-74]

3. "oil" means oil of any kind or in any form including petroleum, fuel oil, sludge, oil refuse and oil mixed with wastes; [2-17-74]

4. "operator" means the person or persons responsible for the overall operations of a facility; and
[12-24-87]

5. "owner" means the person or persons who own a facility, or part of a facility. [12-24-87]

D. Notification of discharge received pursuant to this Part or information obtained by the exploitation of such notification shall not be used against any such person in any criminal case, except for perjury or for giving a false statement.
[2-17-74]

E. Any person who has any information relating to any discharge from any facility of oil or other water contaminant, in such quantity as may with reasonable probability injure or be detrimental to human health, animal or plant life, or property, or unreasonably interfere with the public welfare or the use of property, is urged to notify the Chief of the Ground Water Protection and Remediation Bureau of the department. Upon such notification, the secretary may require an owner/operator or a responsible person to perform corrective actions pursuant to Sections 1203.A.5 or 1203.A.9 of this Part. [12-1-95]

[1204-1209] Reserved

1210. VARIANCE PETITIONS.

A. Any person seeking a variance pursuant to Section 74-6-4 (G) NMSA 1978, shall do so by filing a written petition with the commission. The petitioner may submit with his petition any relevant documents or material which the petitioner believes would support his petition. Petitions shall: [7-19-68, 11-27-70, 9-3-72]

1. state the petitioner's name and address;
[7-19-68, 11-27-70]

2. state the date of the petition; [7-19-68]

3. describe the facility or activity for which the variance is sought; [7-19-68, 11-27-70]

4. state the address or description of the property upon which the facility is located; [11-27-70]

APPENDIX D
WELL SEARCH

CHECKLIST FOR WELL LOGS

Compressor Station Name Trunk B Booster Station

Location T 31N R 8W sec 28

Mark site on San Juan Basin Map ✓
Make file folder ✓

Area to request around well T31N, R8W, sec. 28, 29, 32, 33

FEMA Map order
1-800-358-9616 - ordered 5/13/96
Albuquerque: 768-2650

(Panel 350064 0315 B
or
350064 0350 B)

State Engineer Office well logs and water table database
Fax - 5/14/96
Copies made for file folder ✓

USGS well information
Fax - 5/14/96 (canceled 5/15)
file ✓

IMPORTANT - READ INSTRUCTIONS ON BACK BEFORE FILLING OUT THIS FORM.

Trunk B

Declaration of Owner of Underground Water Right

San Juan
BASIN NAME

77 MAR 31 AM 11 05

Declaration No. SJ-198 Date received Mar. 31, 1977

STATE ENGINEER OFFICE
SANTA FE, N.M. 87501

STATEMENT

1. Name of Declarant El Paso Natural Gas Company

Mailing Address P. O. Box 1492 79978

County of El Paso, State of Texas

2. Source of water supply Artesian
(artesian or shallow water aquifer)

3. Describe well location under one of the following subheadings:

a. SE $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$ of Sec. 32 Twp. 31N Rge. 8W N.M.P.M., in
San Juan County.

b. Tract No. _____ of Map No. _____ of the _____

c. X = _____ feet, Y = _____ feet, N. M. Coordinate System _____ Zone

in the _____ Grant.

On land owned by New Mexico State Land Water Easement #W-559

4. Description of well: date drilled 4-25-75 driller Young Drilling Co. depth 2003 feet.

outside diameter of casing 7-5/8 inches; original capacity _____ gal. per min.; present capacity _____

gal. per min.; pumping lift _____ feet; static water level _____ feet (above) (below) land surface;

make and type of pump Jacuzzi

make, type, horsepower, etc., of power plant 20 HP

Fractional or percentage interest claimed in well 100%

5. Quantity of water appropriated and beneficially used 30

(acre feet per acre) (acre feet per annum)

for Drilling & workover operations on gas wells. purposes.

6. Acreage actually irrigated _____ acres, located and described as follows (describe only lands actually irrigated):

Subdivision	Sec.	Twp.	Range	Acres Irrigated	Owner

(Note: location of well and acreage actually irrigated must be shown on plat on reverse side.)

7. Water was first applied to beneficial use 5 month 1 day 1975 year and since that time

has been used fully and continuously on all of the above described lands or for the above described purposes except

as follows: Used intermittently as drilling and workover operations required.

8. Additional statements or explanations _____

STATE ENGINEER OFFICE
ALBUQUERQUE, N. MEX.
APR 22 1977
P12:53

I, J. W. McCarthy being first duly sworn upon my oath, depose and say that the above is a full and complete statement prepared in accordance with the instructions on the reverse side of this form and submitted in evidence of ownership of a valid underground water right, that I have carefully read each and all of the items contained therein and that the same are true to the best of my knowledge and belief.

El Paso Natural Gas Company, declarant.

by: J. W. McCarthy

Subscribed and sworn to before me this 29 day of March, A.D. 1977

My commission expires June 1, 1977 Ruth Hanson Notary Public

RUTH HANSON

FILED
PER NEW MEXICO LAW A DECLARATION IS ONLY A STATEMENT OF FACTS. THIS CLAIM
ENTITLED FOR FILING DOES NOT CONSTITUTE APPROVAL OR REJECTION OF THE CLAIM.

Locate well and areas actually irrigated accurately as possible on following plat:

Section (s) _____ Township _____ Range _____ N. P. E. P.

INSTRUCTIONS

Declaration shall be executed (preferably typewritten) in triplicate, and must be accompanied by a \$1.00 filing fee. Each of triplicate copies must be properly signed and attested.

A separate declaration must be filed for each well in use.

All blanks shall be filled out fully. Required information which cannot be sworn to by declarant shall be supplied by affidavit of person or persons familiar with the facts and shall be submitted herewith.

Secs. 1-3. Complete all blanks.

Sec. 4. Fill out all blanks applicable as fully as possible.

Sec. 5. Irrigation use shall be stated in acre feet of water per acre per year applied on the land. If used for domestic, municipal, or other purposes, state total quantity in acre feet used annually.

Sec. 6. Describe only the acreage actually irrigated. When necessary to clearly define irrigated acreages, describe to nearest 3/4 acre subdivision. If located on unsurveyed lands, describe by legal subdivision "as projected" from the nearest government survey corners, or describe by metes and bounds and tie survey to some permanent, easily-located natural object.

Sec. 7. Explain and give dates as nearly as possible of any years when all or part of acreage claimed was not irrigated.

Sec. 8. If well irrigates or supplies supplemental water to any other land than that described above, or if land is also irrigated, from any other source, explain under this section. Give any other data necessary to fully describe water right.

If additional space is necessary, use a separate sheet or sheets and attach securely hereto.



1000