GW - 257

GENERAL CORRESPONDENCE

YEAR(S):
1996 - 2006

Lowe, Leonard, EMNRD

From: Lowe, Leonard, EMNRD
Sent: Tuesday, August 14, 2007 12:19 PM
To: 'Bays, David'
Cc: Price, Wayne, EMNRD
Subject: Williams Four Corners LLP Discharge Plans "Minor Modification", corrected Expiration Date

Mr. David Bays
188 County Road 4900
Bloomfield, N.M. 87413

August 14, 2007

Dear Mr. David Bays:

Re: Minor Modification to the following Discharge Plan Permits, Corrected Expiration Date(s)
GW - 068, SIMS MESA CS
GW - 248, TRUNK "A" BOOSTER
GW - 256, N-30 KOCH GARDNER
GW – 257, TRUNK "C" BOOSTER
GW – 274, PRITCHARD STRADDLE CS

Upon final review of the Discharge Plan (DP) Permits, the Oil Conservation Division discovered that the expiration dates on the following signed Discharge Plans (DP): GW-068, GW-248, GW-256, GW257 and GW-274 contained an incorrect "Expiration Date." This e-mail serves as a "Minor Modification" to the DP Permits and serves to correct the expiration date in each of the stated Discharge Plans.

DP	INCORRECT DATE	CORRECT DATE
GW - 068, SIMS MESA CS	04-04-12	01-17-12
GW - 248, TRUNK "A" BOOSTER	04-04-12	03-28-12
GW - 256, N-30 KOCH GARDNER	04-04-12	03-28-12
GW – 257, TRUNK "C" BOOSTER	04-04-12	03-28-12
GW – 274, PRITCHARD STRADDLE CS	04-04-12	03-28-12

This "Minor Modification" e-mail correspondence has been attached to the DP for each of the files stated above.

Please contact me if you have questions on the corrected and official expiration date of these approved Discharge Permits. Sorry for any inconvenience this may have caused you.

Thank you.

llowe

Leonard Lowe
Environmental Engineer
Oil Conservation Division, EMNRD
1220 S. St. Francis Drive
Santa Fe, New Mexico 87505
Phone: (505) 476-3492
Fax: (505) 476-3462
E-mail: leonard.lowe@state.nm.us

Environmental Department
188 County Road 4900
Bloomfield, NM 87413
505/632-4625
505/632-4781 Fax

November 7, 2007

Mr. Leonard Lowe
Oil Conservation Division, EMNRD
1220 South St. Francis Drive
Santa Fe, New Mexico 87505

RE: Update to Williams Four Corners, LLC OCD Discharge Plans

Dear Mr. Lowe,

Williams Four Corners, LLC (Williams) would like to update the "Description of Final Disposition" for wastes generated at its facilities, and to include clarification of sources of waste streams not previously specified in its existing OCD Discharge Plans. These items are discussed in Table 1, "Storage and Disposal of Process Fluids, Effluent and Waste Solids", and Table 2, "Source, Quantity, and Quality of Effluent and Waste Solids", in each of Williams' current facility-specific OCD Discharge Plans. (Note that in older plans, these table numbers are reversed).

More specifically, the updates to Table 1 include replacing language that stated waste would be disposed at a "NMOCD-approved" or simply "approved" disposal facility with text that states waste will be disposed at "any state, federal, or tribal agency to receive industrial solid waste. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such hazardous waste." Recently, Williams has had some difficulty using NMED-approved disposal sites due to the current language.

Updates to Table 2 include expanding the "Source" of "Used Process Filters" to include amine filters, charcoal, activated carbon, and molecular sieve in addition to the air, inlet, fuel, fuel gas and glycol filters typically included in the Discharge Plans. Additionally, the "Source" of "Condensate and/or Produced Water" has been expanded to include the inlet scrubber, gas inlet separator, and dehydrators. These changes are included for clarification purposes only and provide a more descriptive list of waste that may be generated at the facilities. All of the items listed are related to existing processes at the facilities.

Please see the attached Table 1 and Table 2, from the recent OCD Discharge Plan renewal application for Williams' Rosa Compressor Station, for an example of how the updates apply at a typical Williams' facility. The updated information is indicated by bold text. We will update this information in each OCD Discharge Plan as it comes up for renewal. In the meantime, we request that the updates described herein are effective immediately for the sites listed below upon your receipt of this letter.

Five Points (GW-078)
29-6#2 (GW-121)
29-6#3 (GW-198)
29-6#4 (GS-122)
30-5 (GW-108)
31-6 (GW-118)
32-7 (GW-117)
32-8#2 (GW-111)
32-8#3 (GW-116)
32-9 (GW-091)
Aztec (GW-155)
Blanco (GW-327)
Cabresto (GW-352)
Carracas (GW-112)
Cedar Hill (GW-087)
Chaco (GW-331)
Coyote (GW-250)
Crouch Mesa (GW-129)
Culpepper (GW-353)
Decker Junction (GW-134)
Dogie (GW-330)
El Cedro (GW-149)
Glade (GW-321)
Hare (GW-343)
Honolulu (GW-315)
Horse Canyon (GW-061)
Horton (GW-323)
Kernaghan (GW-271)
La Cosa (GW-187)
Laguna Seca (GW-307)
La Jara (GW-223)
Lateral N-30 (GW-256)
Lawson Straddle (GW-322)
Lybrook (GW-047)
Manzanares (GW-062)
Martinez (GW-308)
Middle Mesa (GW-064)
Milagro (GW-060)
Navajo (GW-182)
North Crandell (GW-310)
Pipkin (GW-120)
Pritchard (GW-274)
Pump Mesa (GW-063)
Quintana Mesa (GW-309)
Richardson (GW-320)
Sims Mesa (GW-068)
Snowshoe (GW-287)
Thompson (GW-328)
Trunk A (GW-248)
Trunk B (GW-249)
Trunk C (GW-257)
Trunk L (GW-180)
Trunk M (GW-181)
Trunk N (GW-306)
Wildhorse (GW-079)

These updates are not significant and do not pose a hazard to public health or undue risk to property. These facilities do not discharge wastewater to surface or subsurface waters. All wastes generated at these facilities are temporarily stored in tanks or containers.

Respectfully submitted,

David Bays
Senior Environmental Specialist

Attachment

Table 1
Transfer, Storage and Disposal of Process Fluids, Effluent and Waste Solids

PROCESS FLUID/WASTE	STORAGE	STORAGE CAPACITY (approximate)	CONTAINMENT/ SPILL PREVENTION	RCRA STATUS	DESCRIPTION OF FINAL DISPOSITION
Used Oil	Above Ground Storage Tank	500 gal*	Berm or concrete pad and wastewater system	Non-exempt	May be hauled to a Williams or contractor consolidation point before transport to EPA-registered used oil marketer for recycling.
Produced Water/Natural Gas Condensate	Above Ground Storage Tank	300 bbl 120 bbl 40 bbl	Berms	Exempt	Saleable liquids may be sold to refinery. The remaining liquids may be transported to a Williams' evaporation facility or may be disposed at **any facility permitted by any state, federal, or tribal agency to receive industrial solid waste. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such hazardous waste.**
Wash-down Water	Below Grade Sump, vaulted	70 bbl 45 bbl	Dual-walled tanks	Non-exempt	Contractor may pump wash water back into truck after washing; water may be transported to **any facility permitted by any state, federal, or tribal agency to receive industrial solid waste;** or evaporation at Williams' facility may be considered. **Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such waste.**
Used Oil Filters	Drum or other container	Varies	Transported in drum or other container	Non-exempt	Transported to a Williams or contractor consolidation point, drained, and ultimately transported for disposal at any facility permitted by **any state, federal, or tribal agency to receive industrial solid waste. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such hazardous waste.** A Waste Acceptance Profile will be filed with the disposal facility as necessary. Recycling options may be considered when available.
Used Process Filters	Drum or other container	Varies	Transported in drum or other container	Exempt	Transported to a Williams or contractor consolidation point, drained, and ultimately transported for disposal at **any facility permitted by any state, federal, or tribal agency to receive industrial solid waste. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such hazardous waste.** A Waste Acceptance Profile will be filed with the disposal facility as necessary. Recycling options may be considered when available.
Spill Residue (e.g., soil, gravel, etc.)	N/A	N/A	In situ treatment, land-farm, or alternate method	Incident dependent	Per Section VI, Remediation, in 8/13/93 NMOCD Guidelines for Remediation of Leaks, Spills, and Releases.
Used Absorbents	Drum or other container	Varies	Transported in drum or other container	Non-exempt	Transported to a Williams or contractor consolidation point, drained, and ultimately transported for disposal at **any facility permitted by any state, federal, or tribal agency to receive industrial solid waste. Any waste that is determined to be hazardous as defined by 40 CFR 260-265 will be disposed only at a facility permitted to accept such hazardous waste**. A Waste Acceptance Profile will be filed with the disposal facility as necessary. Recycling options may be considered when available.
Empty Drums / Containers	N/A	N/A	Berm	Non - exempt	Barrels are returned to supplier or transported to a Williams or contractor consolidation point and ultimately recycled/disposed consistent with applicable regulations.
Antifreeze	Above Ground Storage Tank		Berm or concrete pad and wastewater system	N/A	Off-spec material recycled or disposed consistent with applicable regulations.
Glycol	Above Ground Storage Tank	500 gal* 125 gal* 100 gal*	Berm or concrete pad and wastewater system	N/A	Off-spec material recycled or disposed consistent with applicable regulations.
Lube Oil	Above Ground Storage Tank	500 gal*	Berm or concrete pad and wastewater system	N/A	Off-spec material recycled or disposed consistent with applicable regulations.

*Number of tanks installed dependent on number of engines and dehydrators installed on site. Engines and dehydrators are installed or removed to meet demand.

Table 2
Source, Quantity, and Quality of Effluent and Waste Solids

PROCESS FLUID / WASTE	SOURCE	QUANTITY (Ranges)	QUALITY
Produced Water/Natural Gas Condensate	**Inlet Scrubber, Gas Inlet Separator, Dehydrators**	2000-8000 bbl/year	No Additives
Waste Water /Wash Down Water	Compressor and Dehy Skids	100-5000 gal/year/unit	Biodegradable soap and tap water with traces of used oil
Used Oil	Compressors	500-2000 gal/year/engine	Used Motor Oil w/ No Additives
Used Oil Filters	Compressors	50-500/year/engine	No Additives
Used Process Filters	**Charcoal, Activated Carbon, Molecular Sieve**	**50-500 cubic yd/yr**	**No Additives**
Used Process Filters	**Air, Inlet, Fuel, Fuel Gas, Glycol, Amine, Ambitrol**	75-500/year	No Additives
Empty Drums/Containers	Liquid Containers	0-80/year	No Additives
Spill Residue (i.e. soil, gravel, etc)	Incidental Spill	Incident Dependent	Incident Dependent
Used Adsorbents	Incidental Spill/Leak Equipment Wipe-down	Incident Dependent	No Additives

2006 AUG 23 AM 11 44

Environmental Department
188 County Road 4900
Bloomfield, NM 87413
505/632-4606
505/632-4781 Fax

August 22, 2006

Mr. Wayne Price
New Mexico Oil Conservation Division
Environmental Bureau
1220 South St. Francis Drive
Santa Fe, NM 87505

Re: Change of Company Name

Dear Mr. Price;

In accordance with Conditions of Discharge Plan Approval attached to each discharge plan approved by the New Mexico Oil Conservation Division, we hereby provide notice of a change of ownership for the Williams facilities identified in the attached table to Williams Four Corners, LLC.

As a corporate strategy, Williams has created regional limited liability corporations for our assets. So, although a new corporation has been created, Williams Four Corners LLC is still a wholly-owned unit of Williams, and there is no change of corporate ownership for these facilities. Williams will continue to comply with the terms and conditions of all approved discharge plans. All other administrative items (responsible official, environmental contacts, mailing addresses, etc.) remain unchanged.

If you have any questions, please call David Bays, Senior Environmental Specialist, at (505) 632-4951 or Ingrid Deklau of Cirrus Consulting at (801) 583-3107.

Sincerely,

David Bays
Senior Environmental Specialist

Attachments

xc: Clara Cardoza
Monica Sandoval
WFS FCA file 210

Four Corners Area
Environmental Department
#188 CR 4900
Bloomfield, N.M. 87413
Phone: (505) 634-4956
Fax: (505) 632-4781

November 30, 2001

Water Management Quality Management Fund
c/o: Oil Conservation Division
1220 South St. Francis Drive
Santa Fe, NM 87505

Dear Sir or Madam:

Enclosed please find, check number 1000388005 for $17,000.00, to cover the fees for the following discharge plans:

Coyote Springs Compressor	GW-250	$ 1,700.00
Trunk C Booster Station	GW-257	$ 1,700.00
Trunk B Booster Station	GW-249	$ 1,700.00
Lateral N-30 (Koch Gardner)	GW-256	$ 1,700.00
32-9 CDP Compressor Station	GW-091	$ 1,700.00
Pritchard Straddle Compressor Station	GW-274	$ 1,700.00
Kernaghan Compressor	GW-271	$ 1,700.00
Trunk A Booster Station	GW-248	$ 1,700.00
Sims Mesa Compressor Station	GW-068	$ 1,700.00
30-5 CDP Compressor Station	GW-108	$ 1,700.00

Your assistance in processing this fee is greatly appreciated.

If you have any questions please contact me at (505) 634-4956.

Thank You,

Ethel Holiday
Environmental Compliance

ACKNOWLEDGEMENT OF RECEIPT OF CHECK/CASH

I hereby acknowledge receipt of check No. [redacted] dated 11/29/01

or cash received on _____ in the amount of $ 17,000.00

from See Attached List

for _____
(Facility Name)

Submitted by: _____ Date: 12/4/01
(OP No.)

Submitted to ASD by: _____ Date: _____

Received in ASD by: _____ Date: _____

Filing Fee ___ New Facility ___ Renewal V

Modification ___ Other _____
(specify)

Organization Code 521.07 Applicable FY 2001

To be deposited in the Water Quality Management Fund.

Full Payment V or Annual Increment ___

THIS MULTI-TONE AREA OF THE DOCUMENT CHANGES COLOR GRADUALLY AND EVENLY FROM DARK TO LIGHT WITH DARKER AREAS BOTH TOP AND BOTTOM. IT ALSO HAS A REFLECTIVE WATERMARK ON THE BACK.

Williams

WILLIAMS FIELD SERVICES COMPANY
1800 South Baltimore Avenue * P.O. Box 645 * Tulsa, OK 74101-0645

70-2322 / 719
A/C 9401076

[redacted]

DATE: 11/29/2001

PAY TO THE ORDER OF:

PAY ➔ *****$17,000.00

NEW MEXICO OIL CONSERVATION DI
NM WATER QUALITY MGMT FUND
2040 S PACHECO

SANTA FE NM 87504
United States

Bank One, NA
Illinois

Authorized Signer

MA1353 (10/99)

[redacted]

THE SANTA FE
NEW MEXICAN
Founded 1849

NM OIL CONSERVATION DIVISION
ATTN: ED MARTIN
1220 S. ST. FRANCIS DRIVE
SANTA FE, NM 87505

AD NUMBER: 220076 ACCOUNT: 56689
LEGAL NO: 69809 P.O.#: 02199000249
337 LINES 1 time(s) at $ 148.55
AFFIDAVITS: 5.25
TAX: 9.61
TOTAL: 163.41

AFFIDAVIT OF PUBLICATION

STATE OF NEW MEXICO
COUNTY OF SANTA FE
I, MM Weideman being first duly sworn declare and say that I am Legal Advertising Representative of THE SANTA FE NEW MEXICAN, a daily newspaper published in the English language, and having a general circulation in the Counties of Santa Fe and Los Alamos, State of New Mexico and being a Newspaper duly qualified to publish legal notices and advertisements under the provisions of Chapter 167 on Session Laws of 1937; that the publication #69809 a copy of which is hereto attached was published in said newspaper 1 day(s) between 08/06/2001 and 08/06/2001 and that the notice was published in the newspaper proper and not in any supplement; the first publication being on the 6 day of August, 2001 and that the undersigned has personal knowledge of the matter and things set forth in this affidavit.

/S/ MM Weideman
LEGAL ADVERTISEMENT REPRESENTATIVE

Subscribed and sworn to before me on this
6 day of August A.D., 2001

Notary Laura E. Harding

Commission Expires 11/23/03

NOTICE OF PUBLICATION

STATE OF NEW MEXICO ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to the New Mexico Water Quality Control Commission Regulations, the following discharge plan application has been submitted to the Director of the Oil Conservation Division, 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505, Telephone (505) 476-3440:

(GW-248) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-249) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-250) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Coyote Springs Compressor Station located in the SW/4 NE/4, Section 30, Township 32 North, Range 11 West, NMPM, San Juan County, New Mexico. Approximately 26 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 100 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

GW-257) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk C Booster Station located in the SE/4 SW/4, Section 9, Township 31 North, Range 10 West, NMPM, San Juan County, New Mexico. Approximately 75 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 140 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan application may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday thru Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and public hearing may be requested by any interested person. Request for public hearing shall set forth the reasons why a hearing shall be held.

A hearing will be held if the director determines that there is significant public interest.

If no hearing is held, the Director will approve or disapprove the plan based on the information available. If a public hearing is held, the Director will approve the plan based on the information in the plan and information presented at the hearing.

GIVEN under the Seal of New Mexico Conservation Commission at Santa Fe, New Mexico, on this 25th day of July, 2001.

STATE OF NEW MEXICO
OIL CONSERVATION DIVISION

LORI WROTENBERY, Director
Legal #69809
Pub. August 6, 2001

AFFIDAVIT OF PUBLICATION

Ad No. 44844

STATE OF NEW MEXICO
County of San Juan:

CONNIE PRUITT, being duly sworn says: That she is the Classified Manager of THE DAILY TIMES, a daily newspaper of general circulation published in English at Farmington, said county and state, and that the hereto attached Legal Notice was published in a regular and entire issue of the said DAILY TIMES, a daily newspaper duly qualified for the purpose within the meeting of Chapter 167 of the 1937 Session Laws of the State of New Mexico for publication on the following day(s):

Monday, August 6, 2001.

And the cost of the publication is $157.41.

Connie Pruitt

ON 8-9-01 CONNIE PRUITT appeared before me, whom I know personally to be the person who signed the above document.

Ginny Beck

My Commission Expires April 02, 2004

COPY OF PUBLICATION

NOTICE OF PUBLICATION

STATE OF NEW MEXICO
ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT
OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to the New Mexico Water Quality Control Commission Regulations, the following discharge plan application has been submitted to the Director of the Oil Conservation Division, 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505, Telephone (505) 476-3440:

(GW-248) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-249) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-250) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Coyote Springs Compressor Station located in the SW/4 NE/4, Section 30, Township 32 North, Range 11 West, NMPM, San Juan County, New Mexico. Approximately 26 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 100 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-257) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk C Booster Station located in the SE/4 SW/4, Section 9, Township 31 North, Range 10 West, NMPM, San Juan County, New Mexico. Approximately 75 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 140 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan application may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday thru Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and public hearing may be requested by any interested person. Request for public hearing shall set forth the reasons why a hearing shall be held.

Ford, Jack

From: Martin, Ed
Sent: Wednesday, August 01, 2001 8:55 AM
To: 'Farmington Daily Times'
Cc: Ford, Jack; Anaya, Mary
Subject: Legal Notices

Please publish the attached legal notices, one time only, by Monday, August 6, 2001.

After publication, please forward to this office:

1. Publisher's affidavit
2. Invoice. Our purchase order number is **02199000251**

If you have any questions, e-mail me or phone (505) 476-3492.

Thank you.

Publ. Notice
GW-257.doc

Ford, Jack

From: Martin, Ed
Sent: Wednesday, August 01, 2001 8:33 AM
To: 'Santa Fe New Mexican'
Cc: Ford, Jack; Anaya, Mary
Subject: Legal Notices

Please publish the attached legal notices, one time only, by Monday, August 6, 2001.

Upon publication, please forward to this office:

1. Publisher's affidavit
2. Invoice. Our purchase order number is **02199000249**

If you have any questions, please e-mail me or call (505) 476-3492
Thank you.

Publ. Notice
GW-257.doc

NOTICE OF PUBLICATION

STATE OF NEW MEXICO
ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT
OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to the New Mexico Water Quality Control Commission Regulations, the following discharge plan application has been submitted to the Director of the Oil Conservation Division, 1220 South Saint Francis Drive, Santa Fe, New Mexico 87505, Telephone (505) 476-3440:

(GW-248) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk A Booster Station located in the NE/4 NW/4, Section 8, Township 29 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 460 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-249) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk B Booster Station located in the SW/4 SW/4, Section 28, Township 31 North, Range 8 West, NMPM, San Juan County, New Mexico. Approximately 20 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 500 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-250) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Coyote Springs Compressor Station located in the SW/4 NE/4, Section 30, Township 32 North, Range 11 West, NMPM, San Juan County, New Mexico. Approximately 26 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 100 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

(GW-257) - Williams Field Service, Mark J. Barets, Senior Environmental Specialist, 188 CR 4900, Bloomfield, New Mexico 87413, has submitted a discharge plan renewal application for their Trunk C Booster Station located in the SE/4 SW/4, Section 9, Township 31 North, Range 10 West, NMPM, San Juan County, New Mexico. Approximately 75 gallons per day of process wastewater is collected in an above ground, closed top tank prior to transport to an OCD approved off-site disposal facility. Groundwater most likely to be affected by an accidental discharge is at a depth of 140 feet with a total dissolved solids concentrations ranging from 200 to 2000 mg/l. The discharge plan addresses how spill, leaks, and other accidental discharges to the surface will be managed.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan application may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday thru Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and public hearing may be requested by any interested person. Request for public hearing shall set forth the reasons why a hearing shall be held.
A hearing will be held if the director determines that there is significant public interest.

If no hearing is held, the Director will approve or disapprove the plan based on the information available. If a public hearing is held, the Director will approve the plan based on the information in the plan and information presented at the hearing.

GIVEN under the Seal of New Mexico Conservation Commission at Santa Fe, New Mexico, on this 25th day of July, 2001.

STATE OF NEW MEXICO
OIL CONSERVATION DIVISION

SEAL

LORI WROTENBERY, Director

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 South First, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
2040 South Pacheco, Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources

Oil Conservation Division
2040 South Pacheco
Santa Fe, NM 87505

GW-251

Revised March 17, 1999

Submit Original
Plus 1 Copy
to Santa Fe
1 Copy to Appropriate
District Office

DISCHARGE PLAN APPLICATION FOR SERVICE COMPANIES, GAS PLANTS. REFINERIES, COMPRESSOR, AND CRUDE OIL PUMP STATIONS

(Refer to the OCD Guidelines for assistance in completing the application)

☐ New ☑ Renewal ☐ Modification

1. Type: Compressor Station (Trunk C Booster Station)

2. Operator: Williams Field Services Company

   Address: 188 CR 4900, Bloomfield, New Mexico 87413

   Contact Person: Mark J. Bareta Phone: (505) 632-4634

3. Location: SE/4 SW/4 Section 9 Township 31 North Range 10 West
   Submit large scale topographic map showing exact location.

4. Attach the name, telephone number and address of the landowner of the facility site.

5. Attach the description of the facility with a diagram indicating location of fences, pits, dikes and tanks on the facility.

6. Attach a description of all materials stored or used at the facility.

7. Attach a description of present sources of effluent and waste solids. Average quality and daily volume of waste water must be included.

8. Attach a description of current liquid and solid waste collection/treatment/disposal procedures.

9. Attach a description of proposed modifications to existing collection/treatment/disposal systems.

10. Attach a routine inspection and maintenance plan to ensure permit compliance.

11. Attach a contingency plan for reporting and clean-up of spills or releases.

12. Attach geological/hydrological information for the facility. Depth to and quality of ground water must be included.

13. Attach a facility closure plan, and other information as is necessary to demonstrate compliance with any other OCD rules, regulations and/or orders.

14. CERTIFICATION

    I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.

    Name: Mark J. Bareta Title: Senior Environmental Specialist

    Signature: Marilyn M. Juarez for Date: July 13, 2001

DISCHARGE PLAN RENEWAL

TRUNK C BOOSTER STATION
(GW-257)

Williams Field Services Company

June 2001

Table of Contents

List of Tables

List of Figures - All figures follow Section XI

List of Appendices

I. TYPE OF OPERATION

The Trunk C Booster Station was built in 1996 to provide metering, compression, and dehydration services to various producers for the gathering of coal seam natural gas for treatment and delivery through Williams Field Services (WFS) Milagro Plant.

II. LEGALLY RESPONSIBLE PARTY

Williams Field Services
188 CR 4900
Bloomfield, NM 87413
(505) 632-4634

Contact Person:
Mark J. Bareta, Senior Environmental Specialist
Phone and Address, Same as Above

III. LOCATION OF FACILITY

The Trunk C Booster Station is located in Section 9, Township 31 North, Range 10 West, in San Juan County, New Mexico, approximately 8.5 miles northeast of Aztec, New Mexico. A site location map is attached (USGS 7.5 Min. Quadrangle: Cedar Hill, New Mexico) as Figure 1. The facility layout is illustrated in Figure 2. All figures are attached following Section XI of the text.

IV. LANDOWNER

Williams Field Services is leasing the subject property from:

Bureau of Land Management
1235 N. La Plata Highway
Farmington, NM 87401
(505) 599-8900

V. FACILITY DESCRIPTION

This facility is classified as a field compressor station and is unmanned. The air quality permit for this site has allowed the operation of four 1268-hp engines. Only two units are currently installed at the site. In addition, there are various storage tanks, support structures and ancillary equipment. Records related to facility operations are maintained at central office locations.

VI. SOURCE, QUANTITY, AND QUALITY OF EFFLUENTS AND WASTE SOLIDS

The source, quantity, and quality of effluent and waste solids generated at the compressor station are summarized in Table 1.

TABLE 1
SOURCE, QUANTITY, AND QUALITY OF EFFLUENT AND WASTE SOLIDS
TRUNK C BOOSTER STATION

PROCESS FLUID/WASTE	SOURCE	QUANTITY (Ranges)	QUALITY
Used Oil	Compressor	1000–2000 gal/year/engine.	Used motor oil w/no additives
Used Oil Filters	Compressor	50-100 filters/year/engine	No additives
Wash-down Water	Compressor Skid	500-1500 gal/year/engine	Biodegradable Soap and tap water w/traces of used oil
Natural Gas Condensate	Scrubber, Gas Inlet Separator	1000-3000 bbl/year	No additives
Used Process Filters	Air, Inlet and Fuel Gas	75- 100/year	No additives
Empty Drums / Containers	Liquid Containers	20-40/year	No additives
Spill Residue (i.e., gravel, soil)	Incidental spills	Incident dependent	Incident dependent
Used Absorbents	Incidental spill/leak equipment wipe-down	Incident dependent	No additives

VII. TRANSFER, STORAGE, AND DISPOSAL OF PROCESS FLUIDS, EFFLUENTS AND WASTE SOLIDS

Wastes generated at this facility fall into two categories: exempt and non-exempt. Exempt wastes include, but may not be limited to, used process filters, condensate spill cleanups (spill residue), certain absorbents, and produced water with or without de minimus quantities of non-hazardous liquids. Non-exempt wastes include, but may not be limited to, used oil, used oil filters, and engine coolant. Table 2 describes the transfer, storage and disposal of exempt and non-exempt process fluids, effluents, and waste solids expected to be generated at the site.

Non-exempt waste management will be conducted in accordance with NMOCD requirements including the preparation of a Certificate of Waste Status for each non-exempt waste stream. Non-exempt wastes will be analyzed at a minimum for BTEX, TPH, RCRA D-List metals, ignitability, corrosivity, and reactivity to initially determine if such waste are hazardous as defined in 40 CFR Part 261. All wastes at the facility will be periodically surveyed for naturally occurring radioactive material (NORM) to determine if the concentrations of radium 226 exceed 30 picocuries per gram or if radiation exposure exceeds 50 microroentgens per hour. If affirmed, such materials will be handled and disposed in accordance with NMOCD NORM Regulations.

Barring facility modification and/or process changes, the classification of non-exempt wastes by laboratory analyses will be made once during the approval period of this plan. Subsequent laboratory analyses will be performed at the generator's discretion (minimum of once every five years), or more frequently to comply with waste acceptance procedures of the disposal facility.

TABLE 2
TRANSFER, STORAGE, AND DISPOSAL OF PROCESS FLUIDS, EFFLUENTS, AND WASTE SOLIDS
TRUNK C BOOSTER STATION

PROCESS FLUID/WASTE	STORAGE	CONTAINER CAPACITY (approximate)	CONTAINMENT/ SPILL PREVENTION	RCRA STATUS	DESCRIPTION OF FINAL DISPOSITION
Used Oil	Above Ground Storage Tanks	(2) 500 gallons	Berm	Non-exempt	May be hauled to a WFS or contactor consolidation point before transport to EPA-registered used oil marketer for recycling.
Used Oil Filters	Drum or other container	Varies	Transported to a WFS or contractor facility in drum or other container	Non-exempt	Transported to a WFS or contractor consolidation point, drained, and ultimately transported for disposal at an approved disposal facility. A Waste Acceptance Profile will be filed with the disposal facility. Recycling options may be considered when available.
Natural Gas Condensate	Above Ground Storage Tank	70 bbl	Berm	Exempt	Saleable liquids may be sold to refinery or liquid may be disposed at NMOCD- approved facility.
Wash-down Water	Below-ground sump, vaulted	740 gallons	Dual-walled tank	Non-Exempt	Water may be transported to NMOCD-approved facility; or evaporation at WFS facility may be considered in future.
Used Process Filters	Drum or other container	Varies	Transported to a WFS or contractor facility in drum or other container	Exempt	Transported to a WFS or contractor consolidation point, drained, and ultimately transported for disposal at an approved disposal facility. A Waste Acceptance Profile will be filed with the disposal facility. Recycling options may be considered when available.
Empty Drums / Containers	N/A	N/A	Berm	Non -exempt	Barrels are returned to supplier or transported to a WFS or contractor consolidation point and ultimately recycled/disposed
Spill Residue (i.e., soil, gravel)	N/A	N/A	In situ treatment, land-farm, or alternate method	Incident dependent	Per Section VI, Remediation, in 8/13/93 NMOCD Guidelines for Remediation of Leaks, Spills, and Releases.
Used Absorbents	Drum or other container	Varies	Transported to a WFS or contractor facility in drum or other container	Non-exempt	Transported to a WFS or contractor consolidation point, drained, and ultimately transported for disposal at an approved disposal facility. A Waste Acceptance Profile will be filed with the disposal facility. Recycling options may be considered when available.
Glycol	Above ground storage tank	500 gallons	Berm	N/A	Off-spec material recycled or disposed consistent with applicable regulations.
Compressor Oil	Above ground storage tanks	(2) 500 gallons	Berm	N/A	Off-spec material recycled or disposed consistent with applicable regulations.

VIII. STORM WATER PLAN

This storm water section was developed to provide a plan to monitor and mitigate impact to storm water runoff from the facility. It serves to satisfy storm water management concerns of the NMOCD. It is not intended to comply with 40 CFR Part 122, Storm Water Discharges as this facility is excluded in 122.26 (c) (1) (iii).

This section concentrates on the identification of potential pollutants, inspection and maintenance of the pollutant controls, and gives a description of structural controls to prevent storm water pollution.

Site Assessment and Facility Controls

An evaluation of the material used and stored on this site that may be exposed to storm water indicates that no materials would routinely be exposed to precipitation. There are no engineered storm water controls or conveyances; all storm water leaves the site by overland flow.

Any leakage or spill from the identified potential pollutant sources, if uncontained by existing berms, curbs, or emergency response actions, could flow overland to open off-site drainage ditches (arroyos) and thus impact storm water. In such an event, containment would occur by blocking the ditch or culvert downstream of the pollutant. Cleanup of the substance and implementation of mitigation measures could be conducted while protecting downstream storm watercourses.

Best Management Practices

Following are Best Management Practices (BMPs) to be implemented to prevent or mitigate pollution to storm water from facility operations:

- All waste materials and debris will be properly disposed of on an on-going basis in appropriate containers and locations for collection and removal from the site.
- Temporary storage of potential pollutant sources will be located in areas with appropriate controls for storm water protection. This would include ensuring all containers are sealed/covered and otherwise protected from contact with precipitation.
- Periodic inspection of channels and culverts shall be performed at least twice annually and after any major precipitation event.
- Sediment deposits and debris will be removed from the channels and culverts as necessary and any erosion damage at the outfall (if any) will be repaired or controlled.
- Conduct inspections of the facility on a regular basis as part of the preventive maintenance site check. Such inspections will include the visual assessment of corroded or damaged drums and tanks, broken or breached containment structures, collapsed or clogged drainages or drain lines.

Implementation of the BMPs will prevent or mitigate impact to storm water runoff from this facility.

IX. INSPECTION, MAINTENANCE AND REPORTING

WFS's personnel will operate and maintain the compression unit at the facility. The facility will be remotely monitored for equipment malfunctions through Gas Dispatch. The facility will be visited several times per week at a minimum, and an operator will be on call 24 hours per day, 7 days per week, 52 weeks per year. The above ground and below-grade tanks will be gauged regularly, and monitored for leak detection.

In the event of a release of a reportable quantity, the operator reports the release to a WFS spill notification service. The service immediately notifies the WFS Environmental Department and all appropriate agencies.

X. SPILL/LEAK PREVENTION AND REPORTING (CONTINGENCY PLANS)

Spill containment berms around above ground storage tanks will be designed to contain 1-1/3 times the volume of the tank and will be equipped with an impermeable liner. The below-grade tanks will be constructed with a means of leak detection, and will either be double-bottomed tanks or a tank set on an impermeable pad.

WFS corporate policy and procedure for the controlling and reporting of Discharges or Spills of Oil or Hazardous Substances is provided in Appendix A. Significant spills and leaks are reported to the NMOCD pursuant to NMOCD Rule 116 and WQCC 1-203 using the NMOCD form (see Appendix B).

XI. SITE CHARACTERISTICS

The Trunk C Booster Station is located approximately 8.5 miles northeast of Aztec, New Mexico. The site elevation is approximately 6,140 feet above mean sea level. The natural ground surface topography slopes downward toward the west. The maximum relief over the site is approximately 10 feet. Intermittent flow from the site will follow natural drainage to the west and then to the north into the Miller Canyon drainage. Miller Canyon drains to the west into the Animas River. The Animas River is the nearest down-gradient perennial source of surface water and is located approximately 1.5 miles west from the site, at an elevation of approximately 5,770 feet.

A review of the available hydrologic data[1,2] for this area revealed that there are no water wells within a 1/4-mile radius of Trunk C Booster Station. The water-bearing unit in this area is the San Jose Formation. The San Jose Formation is the youngest Tertiary bedrock unit. This formation consists of a sequence of interbedded sandstone and mudstone. The estimated ground water depth at the site is 200 to 400 feet. The total dissolved solids concentration of area ground water is expected to range from 200 to 2,000 parts per million.

The 100-year 24-hour precipitation event at a regional weather station is 2.8 inches. This small amount of rainfall for the area should pose no flood hazards. Vegetation in the area consists predominantly of sagebrush and native grasses

Flood Protection: Surface water runoff from the area surrounding the site will be diverted around the facility into the natural drainage path.

References

[1]Stone, W.J., Lyford, F.P., Frenzel, P.F., Mizell, N.H., Padgett, E.T., 1983, Hydrology and Water Resources of San Juan Basin, New Mexico Bureau of Mines and Mineral Resources, Hydrologic Report 6.

[2]Online Well Reports and Downloads, New Mexico Office of the State Engineer, 2000.

XII. FACILITY CLOSURE PLAN

All reasonable and necessary measures will be taken to prevent the exceedence of WCQQ Section 3103 water quality standards should WFS choose to permanently close the facility. WFS will submit a detailed closure plan to the NMOCD prior to closure.

Generally, closure measures will include removal or closure in place of underground piping and other equipment. All wastes will be removed from the site and properly disposed in accordance with the rules and regulations in place at the time of closure. When all fluids, contaminants, and equipment have been removed from the site, the site will be graded as close to the original contour as possible.

Should contaminated soil be discovered, any necessary reporting under NMOCD Rule 116 and WQCC Section 1203 will be made and clean-up activities will commence. Post-closure maintenance and monitoring plans would not be necessary unless contamination is encountered.

FIGURE 1

SITE VICINITY / TOPOGRAPHIC MAP

FIGURE 2

SITE PLAN



Source:USGS Cedar Hill Quadrangle, New Mexico

Scale: 1" = 2,000'

Williams

Figure 1 Site Vicinity / Topographic Map

Trunk C Booster Station

Section 9, Township 31N Range 10W

San Juan County, New Mexico

Subject or Title:

SPILL PREVENTION CONTROL AND COUNTERMEASURE PLAN

OPERATIONS			
Manual: TRUNK "C" COMPRESSOR STATION			
Section: SPILL PREVENTION CONTROL	Tab: 13	Document No.: 42.13.001	
Effective Date: 12-6-98	Issue No.: 01	Page No.: 5 of 8	

ATTACHMENT "A" PRODUCT AND WASTE STORAGE LOCATIONS



REFERENCE DRAWINGS				REFERENCE DRAWINGS				REVISIONS															
DRAWING NO.	TITLE	DRAWING NO.	TITLE	DRAWING NO.	TITLE	DRAWING NO.	TITLE	NO.	DATE	BY	DESCRIPTION	W.O.NO.	CHK.	APP.	NO.	DATE	BY	DESCRIPTION	W.O.NO.	CHK.	APP.
															01	12-6-98	PHIM	PLACED ON AUTOCAD PER AS-BUILT	98408		

DRAFTING	BY	DATE
DRAWN BY	PHIM	12-6-98
CHECKED BY		
APPROVED BY		
ENGINEER	BY	DATE
DESIGNED BY		
PROJ. APPROVED		

STATE: NEW MEXICO
COUNTY: SAN JUAN

WILLIAMS FIELD SERVICES
ONE OF THE WILLIAMS COMPANIES

TRUNK "C" COMPRESSOR STATION
SPILL PREVENTION CONTROL AND COUNTERMEASURE PLAN
PLOT PLAN

SCALE: 1" = 30'
W.O. NO. 98408
DWG NO. TRC-1-P7
SHEET 1 OF 1
REV 01

S:\wfsds\PM_E1\frc\EOD\00070101 Mon Jan 04 10:55:06 1999

APPENDIX A

SPILL CONTROL PROCEDURES

	Reference (Book Title) Operations/Maintenance Field Services	Task/Document No. 21.10.020
Williams	Section General/Safety	Regulation No./Reference
	Subject Discharges or Spills of Oil or Hazardous Substances; Preventing, Controlling and Reporting of	Effective Date 12/15/99

▸ **Document History (ISO9001)**

▾ **Document Body**

1.0 PURPOSE AND SCOPE

1.1 To establish the policy and procedure for preventing, controlling and reporting of discharges or spills of oil or hazardous substances to the environment in accordance with Company practices and federal, state and local requirements, including Title 40 of the Code of Federal Regulations - Part 112 (Oil Pollution Prevention).

1.2 This document pertains to Company personnel, Company and non-company facilities. The spill prevention and control requirements in this Policy and Procedure are Federally mandated guidelines for oil pollution prevention. The Company policy is to also apply these standards, where appropriate, to facilities containing hazardous substances. This is a discretionary application of the standards; however, variations from the standards should be approved by the responsible Director.

2.0 CONTENTS

3.0 POLICY

3.1 GENERAL

3.1.1 All Company facilities which could discharge or spill, oil or hazardous substances which may affect natural resources or present an imminent and substantial danger to the public health or welfare including, but not limited to, fish, shellfish, wildlife, shorelines and beaches are subject to the provisions of this document.

3.1.2 Oil, for purpose of this document, means oil of any kind or in any form, including but not limited to petroleum hydrocarbon, fuel oil, Y grade, natural gas liquids, condensate, mixed products, sludge, oil refuse and oil mixed with wastes other than dredged spoil (earth and rock). LPG (propane, butane, ethane) is not considered to be oil.

3.1.3 Hazardous Substance, for purposes of this procedure, is defined as any chemical or

material that has or should have a Material Safety Data Sheet (MSDS); however, hazardous substances are further defined by the following environmental statutes:

a. Section 101(N) and Section 102 of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA)

b. Section 307(a) and Section 311(b)(2)(A) of the Clean Water Act

c. Section 3001 of the Solid Waste Act (excluding items suspended by Congress)

d. Section 112 of the Clean Air Act

e. Section 7 of the Toxic Substance Control Act

3.1.4 The term hazardous substance does not include petroleum hydrocarbon, including crude oil or any fraction thereof and the term does not include natural gas, natural gas liquids (including condensate), liquefied natural gas or synthetic gas usable for fuel (or mixtures of natural gas and such synthetic gas).

3.1.5 Facilities which could discharge or spill, oil or hazardous substances into a watercourse must comply with the applicable federal, state or local laws and regulations. A discharge includes but is not limited to any spilling, leaking, pumping, pouring, emitting, emptying or dumping. A watercourse is any perennial or intermittent river, stream, gully, wash, lake or standing body of water capable of collecting or transporting an oil or hazardous substance.

3.1.6 Facilities which are subject to the requirements stated in this policy are as follows:

a. Non-Transportation Related Facilities

(1) Storage or drip tanks and other aboveground containers (excluding pressurized or inline process vessels) having a capacity in excess of 660 gallons for each single container or an aggregate capacity of 1,321 gallons or more for multiple containers.

(2) Underground storage facilities having a total capacity in excess of 42,000 gallons.

b. Transportation Related Facilities

(1) All vehicles, pipeline facilities, loading/unloading facilities and other mobile facilities which transport oil or hazardous substances.

3.1.7 Each Company location which has facilities subject to paragraph C.1.1 shall have a site specific Spill Prevention Control and Countermeasure Plan (SPCC Plan) which identifies all facilities subject to 40 CFR 112. The plan shall identify all oil and hazardous substance storage vessels (as defined in a.(1) above) at the facility and the spill prevention measures in place to control discharges or spills. This plan shall also identify all regulatory agencies that must be notified in case of a spill.

3.1.8 The facility superintendent is responsible for spill prevention. His/her duties include,

but are not limited to, the following:

a. Instructing personnel in the operation and maintenance of equipment to prevent the discharge of oil.

b. Conduct annual briefings for operating personnel at intervals frequent enough to assure adequate understanding of the Spill Plan at that facility.

c. Briefings should highlight and describe known discharges or spills and recently developed precautionary measures.

3.1.9 Each individual facility is checked annually by the superintendent or designee to determine the potential for discharges or spills of oil or hazardous substances in harmful quantities that violate water quality standards or which may cause a film, sheen or discoloration on the surface of water. All facilities which have the potential for discharging or spilling harmful quantities of oil or hazardous substances into a watercourse are required to have the following preventive measures:

a. Examination of all tanks, valves and fittings, at least annually, to determine any maintenance requirements.

b. All tank batteries should, as far as practicable, have a secondary means of containment for the entire contents of the largest single tank plus sufficient freeboard in the containment facility to allow for precipitation.

c. An annual monitoring and inspection program to prevent accidental spills or discharges into watercourses. This includes annual inspection for faulty systems and monitoring line valves and liquid pipelines for leaks or blowouts.

3.1.10 Any field drainage ditches, road ditches, traps, sumps or skimmers should be inspected at regular scheduled intervals for accumulation of oil or other hazardous substances which may have escaped from small leaks. Any such accumulations should be removed.

3.2 BULK STORAGE TANKS

3.2.1 A tank should not be used for storage of oil or hazardous substances unless the material and construction of the tank is compatible with the oil or substance stored and conditions of storage such as pressure and temperature. Buried storage tanks must be protected from corrosion by coatings, cathodic protection or other methods compatible with local soil conditions. Aboveground tanks should be subject to visual inspection for system integrity.

3.2.2 The facility superintendent should evaluate tank level monitoring requirements to prevent tank overflow.

3.2.3 Leaks which result in loss of oil or hazardous substances from tank seams, gaskets, rivets and bolts sufficiently large to cause accumulation of oil or hazardous substances in diked areas should be promptly corrected.

3.2.4 Mobile or portable oil or hazardous substances storage tanks should be positioned or located to prevent the contents from reaching a watercourse. The mobile facilities should be located so their support structure will not be undermined by periodic flooding or washout.

3.3 FACILITY DRAINAGE

3.3.1 Make provisions for drainage from diked storage areas where necessary in areas with high precipitation levels. Drainage from diked areas should be restrained by valves or other means to prevent a discharge or spill. Diked areas should be emptied by pumps or ejectors which are manually activated. Valves used for the drainage of diked areas should be of manual, open-and-closed design.

3.3.2 Rain water may be drained from diked areas providing drainage water does not contain oil or hazardous substances that may cause a harmful discharge. Drain valves must be closed following drainage of diked areas.

3.3.3 When possible, drainage systems from undiked areas should flow into ponds, lagoons or catchment basins designed to retain oil or hazardous substances or return the substances to the facility. Any drainage system which is not designed to allow flow into ponds, lagoons or catchment basins should be equipped with a diversion system that could, in the event of a discharge or spill, contain the oil or hazardous substances on the Site.

3.3.4 The principal means of containing discharges or spills is the use of dikes which are constructed wherever regulated quantities of oil or hazardous substances have the potential of reaching a watercourse. The construction of dikes must meet the following requirements:

a. Capacity must be at least equivalent to the storage capacity of the largest tank of the battery plus sufficient freeboard to allow for precipitation or displacement by foreign materials.

b. Small dikes for temporary containment are constructed at valves where potential leaking of oil or hazardous substances may occur.

c. Any dike three feet or higher should have a minimum cross section of two feet at the top.

3.3.5 Other means of containment or spill control include, but are not limited to:

a. Berms or retaining walls

b. Curbing

c. Culverting, gutters or other drainage systems

d. Weirs, booms or other barriers

e. Spill diversion ponds or retention ponds

f. Sorbent materials

3.4 TRANSFER OPERATIONS, PUMPING and IN-PLANT/STATION PROCESS

3.4.1 Aboveground valves and pipelines should be examined regularly by operating

personnel to determine whether there are any leaks from flange joints, expansion joints, valve glands and bodies, catch pans, pipeline supports, valve locks and metal surfaces.

3.5 FACILITY TANK CAR AND TANK TRUCK LOADING/UNLOADING RACK

3.5.1 Rack area drainage which does not flow into a catchment basin or treatment facility designed to handle spills should have a quick drainage system for use in tank truck loading and unloading areas. The containment system should have a maximum capacity of any single compartment of a truck loaded or unloaded in the station.

3.5.2 Aboveground piping that has potential for damage by vehicles entering the Site should be protected by logically placed warning signs or by concrete-filled pipe barriers.

3.5.3 Loading and unloading areas should be provided with an interlocked warning light, grounding shutdown, physical barrier system or warning signs to prevent vehicular departure before complete disconnect of flexible or fixed transfer lines. All drains and outlets of any truck should be closely examined for leakage prior to filling and departure. All drains and outlets that may allow leakage should be tightened, adjusted or replaced to prevent liquid leakage while in transit.

NOTE: LPG loading facilities and remote field loading of condensate are exempt from the C.5 requirements of this document.

4.0 PROCEDURE

4.1 Identifying, Containing and Initial Reporting of a Discharge or Spill of Oil or Hazardous Substance
Any Employee

4.1.1 Upon noticing a discharge or spill of an oil or hazardous substance in any quantity shall immediately contain the release (if safe to do so) and notify the facility superintendent, dispatcher or other designee. Releases must be reported to gas control in the following three circumstances:

I. The Following Situations Always Require IMMEDIATE Reporting to Gas Control:

1. Release reaches or may reach surface water: (pond, lake, wash or ground water

2. Release leaves Williams property

3. Release is of questionable nature (i.e., unknown product, unknown hazards)

II. Onsite Releases of Certain Common Industrial Materials Above 10 Gallon Threshold Are Reportable.
Releases that do not migrate off-site or reach surface water may require reporting as well. All releases of 10 gallons or greater of the following materials should be contained and promptly reported to Gas Control:

- Ammonia
- Antifreeze
- Amine

- Chromate Mixtures
- Condensate
- Glycol
- Lube Oil
- Methanol
- Sulfuric Acid
- Sodium Hydroxide
- Natural Gas Liquids
- Other Hydrocarbon Products
- Natural Gas (1 MMSCF)

III. Releases of Certain Other Materials Reportable:

Releases of the following materials above the indicated amount should be reported to gas control:

- PCB's (Concentration > 50 ppm) - any amount
- Mercaptan (Ethyl Mercaptan) - 1 lb.
- Mercury - 1 lb.
- Hydrogen Sulfide - 100 lbs.
- Pesticides - 1 lb.
- Other Material Not Listed - 1 lb.

NOTE 1: A release includes material released (intentionally or unintentionally) to air, water or soil. When notifying Gas Control of a Release, be prepared to provide information on the type of material spilled, amount released, weather conditions, time and date of release, person discovering release and measures taken to control the release.

NOTE 2: Refer to Attachment A for containment procedures.
Facility Superintendent, Controller or Designee

4.1.2 Contacts Gas Control immediately by telephone and provides the following information:

a. Name of company facility and/or location of facility and nature of discharge or spill

b. Description and quantity of emission or substance discharged

c. Description of the circumstances causing the discharge or spill

d. Name, title and telephone number of person initially reporting the discharge or spill and person reporting to Gas Control

e. Action taken or being taken to mitigate and correct discharge or spill

f. Water bodies or streams involved

g. Time and duration of discharge or spill

h. Outside involvement during discharge or spill (public government agencies, etc. See Emergency Operating Procedure Manuals)

Gas Control Personnel

4.1.3 Advises Environmental Affairs departments immediately by telephone concerning the incident including any incidents reported by persons not employed with the Company.

NOTE: If Gas Control is contacted by a person not employed with the Company, the necessary information is obtained as indicated in D.1.2 and the Superintendent and Environmental Affairs are immediately contacted to begin containment and clean-up of the discharge or spill.

4.1.4 If Environmental Affairs cannot be contacted, notifies Director over Environmental Affairs.

Facility Superintendent

4.1.5 Coordinates containment and clean-up of discharge or spill, keeping the responsible Director Informed.

4.1.6 Coordinates containment and clean-up of discharge or spill, keeping the responsible Director Informed. If the discharge or spill is too large for Company personnel to contain, contacts qualified local contractors for assistance. (See Emergency Operating Procedure Manuals tab #11, contractors with available equipment and services).

4.1.7 Advises Environmental Affairs by telephone if emergency containment or clean-up assistance from a state agency or a response team from the U.S. Coast Guard is required.

Environmental Affairs

4.1.8 Assesses reporting requirements to state and federal agencies (contacts Legal Department and Right-of-Way Department, if appropriate). (See Emergency Operating Procedure Manuals).

4.1.9 Makes appropriate contacts with National Response Center and state and local agencies, when necessary.

4.1.10 If spill is significant, dispatches Environmental Specialist to scene to oversee cleanup and reporting responsibilities.

4.2 SUBMITTING WRITTEN NOTIFICATION OF A DISCHARGE OR SPILL

Facility Superintendent or Designee

4.2.1 Completes a written description of the incident as soon as possible after initial notification is given, which should include the following:

a. Time and date of discharge or spill

b. Facility name and location

c. Type of material spilled

d. Quantity of material spilled

e. Area affected

f. Cause of spill

g. Special circumstances

h. Corrective measures taken

i. Description of repairs made

j. Preventative measures taken to prevent recurrence.

4.2.2 Forwards the completed written description to Environmental Affairs. Retains a copy for future reference.

NOTE: Environmental Affairs, in coordination with the Legal Department, if necessary, submits written reports to government agencies.

ATTACHMENT A
DISCHARGE OR SPILL CONTAINMENT PROCEDURES AND MATERIALS

TYPE OF FACILITY WHERE THE DISCHARGE OR SPILL OCCURS	CONTAINMENT PROCEDURES	MATERIALS USED FOR CONTAINMENT
A. Oil Pipeline (as defined in C.1.4)	1. Closes appropriate block valves. 2. Contains Discharge or spill by: Ditching covering, applying sorbents, constructing an earthen dam or burning. 3. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning.	1.Straw 2.Loose Earth 3.Oil Sorbent 3M Brand 4.Plain Wood chips 5.Sorb-Oil Chips Banta Co. 6.Sorb-Oil Swabs Banta Co. 7.Sorb-Oil Mats Banta Co. 8.Or Equivalent Materials
B. Vehicle	1. Contains discharge or spill by: ditching, covering surface with dirt, constructing earthen dams, apply sorbents or burning. 2. Notifies immediately Environmental Affairs and if there is any imminent danger to local residents; notifies immediately the highway patrol or local police officials.	

	3. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning. **Note**: Any vehicle carrying any hazardous or toxic substance will carry a shovel or other ditching device to contain a spill. If the vehicle has sufficient room, sorbent materials should also be carried.
C. Bulk Storage Tanks or any other Facilities	1. Contains discharge or spill by: ditching, covering, applying sorbents, constructing an earthen dam or burning. 2. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning.

APPENDIX B

NMOCD NOTIFICATION OF FIRE, BREAKS, SPILLS, LEAKS, AND BLOWOUTS

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 South First, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
2040 South Pacheco, Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources

Oil Conservation Division
2040 South Pacheco
Santa Fe, NM 87505

Form C-141
Revised March 17, 1999

Submit 2 Copies to appropriate District Office in accordance with Rule 116 on back side of form

Release Notification and Corrective Action

OPERATOR

☐ Initial Report ☐ Final Report

Name of Company	Contact
Address	Telephone No.
Facility Name	Facility Type

Surface Owner	Mineral Owner	Lease No.

LOCATION OF RELEASE

Unit Letter	Section	Township	Range	Feet from the	North/South Line	Feet from the	East/West Line	County

NATURE OF RELEASE

Type of Release	Volume of Release	Volume Recovered
Source of Release	Date and Hour of Occurrence	Date and Hour of Discovery
Was Immediate Notice Given? ☐ Yes ☐ No ☐ Not Required	If YES, To Whom?	
By Whom?	Date and Hour	
Was a Watercourse Reached? ☐ Yes ☐ No	If YES, Volume Impacting the Watercourse.	

If a Watercourse was Impacted, Describe Fully.*

Describe Cause of Problem and Remedial Action Taken.*

Describe Area Affected and Cleanup Action Taken.*

I hereby certify that the information given above is true and complete to the best of my knowledge and understand that pursuant to NMOCD rules and regulations all operators are required to report and/or file certain release notifications and perform corrective actions for releases which may endanger public health or the environment. The acceptance of a C-141 report by the NMOCD marked as "Final Report" does not relieve the operator of liability should their operations have failed to adequately investigate and remediate contamination that pose a threat to ground water, surface water, human health or the environment. In addition, NMOCD acceptance of a C-141 report does not relieve the operator of responsibility for compliance with any other federal, state, or local laws and/or regulations.

Signature:	OIL CONSERVATION DIVISION	
Printed Name:	Approved by District Supervisor:	
Title:	Approval Date:	Expiration Date:
Date: Phone:	Conditions of Approval:	Attached ☐

* Attach Additional Sheets If Necessary

OIL CONSERVATION DIV.

01 JUL 23 PM 1:06

Environmental Affairs
188 CR 4900
Bloomfield, NM 87413
505/634-4956
505/632-4781 Fax

July 13, 2001

Mr. Jack Ford
New Mexico Oil Conservation Division
2040 South Pacheco
Santa Fe NM 87505

Re: Discharge Plan Application Renewal and Filing Fee

Dear Mr. Ford:

Enclosed please find copies of Discharge Plan application renewal and check number 1000318741 for $700.00 to cover the filling fee for the following Williams Field Services (WFS) Compressor Stations:

- Coyote Springs GW-250
- Kernaghan GW-271
- Pritchard - GW-274
- Trunk A - GW-248
- Trunk B - GW-249
- Trunk C - GW-257
- 32-9 CDP - GW-091

Williams Field Services appreciates your assistance in handling these applications and fees. If you have any questions or require additional information, please contact me at 505/634/4956.

Thank you,

Clara M. Garcia

Clara M Garcia
Environmental Compliance

Xc: Denny Foust, Aztec, OCD Dist III

ACKNOWLEDGEMENT OF RECEIPT OF CHECK/CASH

I hereby acknowledge receipt of check No. [redacted] dated 7/11/01

or cash received on _____ in the amount of $ 700.00

from Williams Field Services

for Kernaghan-211 (Facility Name) Coyote Springs-250 Prichard-274 Trunk B-245 32-9 COP-09 Trunk A-248 Trunk C-257

Submitted by: _____ (OP No.) Date: 7/23/01

Submitted to ASD by: _____ Date: _____

Received in ASD by: _____ Date: _____

Filing Fee ✓ New Facility ___ Renewal ✓

Modification ___ Other _____ (specify)

Organization Code 521.07 Applicable FY 2001

To be deposited in the Water Quality Management Fund.

Full Payment ✓ or Annual Increment ___

THIS MULTI-TONE AREA OF THE DOCUMENT CHANGES COLOR GRADUALLY AND EVENLY FROM DARK TO LIGHT WITH DARKER AREAS BOTH TOP AND BOTTOM. IT ALSO HAS A REFLECTIVE WATERMARK ON THE BACK.

Williams

WILLIAMS FIELD SERVICES COMPANY
1800 South Baltimore Avenue * P.O. Box 645 * Tulsa, OK 74101-0645

"70-2322/1719"
A/C 9401076

[redacted]

DATE: 07/11/2001

PAY TO THE ORDER OF:

PAY ********$700.00

NEW MEXICO OIL CONSERVATION DI
NM WATER QUALITY MGMT FUND
2040 S PACHECO

SANTA FE NM 87504
United States

Bank One, NA
Illinois

Authorized Signer

MA1353 (10/99)

COPYRIGHT ANTI-FRAUD PROTECTION - PATENTS 4,210,346; 4,227,720; 4,310,180; 5,197,765; 5,340,159

[redacted]

NEW MEXICO ENERGY, MINERALS and
NATURAL RESOURCES DEPARTMENT

GARY E. JOHNSON
Governor
Jennifer A. Salisbury
Cabinet Secretary

February 9, 2001

Lori Wrotenbery
Director
Oil Conservation Division

CERTIFIED MAIL
RETURN RECEIPT NO. 5051 0074

Ms. Clara M. Garcia
Williams Field Services
188 CR 4900
Bloomfield, New Mexico 87413

RE: Discharge Plan Renewal Notice for Williams Field Services Facilities

Dear Ms. Garcia:

Williams Field Services has the following discharge plans, which expire during the current calendar year.

GW-060 expires 3/21/2001 – Milagro Compressor Station
GW-233 expires 4/1/2001 – La Jara Compressor Station
GW-061 expires 6/6/2001 – Horse Canyon Compressor Station
GW-062 expires 6/6/2001 – Manzanares Compressor Station
GW-063 expires 6/6/2001 – Pump Mesa Compressor Station
GW-064 expires 6/6/2001 – Middle Mesa Compressor Station
GW-079 expires 6/21/2001 – Wild Horse Compressor Station
GW-078 expires 6/21/2001 - 5-Points Compressor Station
GW-250 expires 8/9/2001 – Coyote Springs Compressor Station
GW-249 expires 8/9/2001 – Trunk B Booster Compressor Station
GW-248 expires 8/9/2001 – Trunk A Booster Compressor Station
GW-257 expires 9/18/2001 – Trunk C Compressor Station
GW-256 expires 9/18/2001 – Koch-Gardner Compressor Station
GW-087 expires 11/27/2001 – Cedar Hill Compressor Station
GW-271 expires 12/17/2001 – Kernaghan Compressor Station
GW-274 expires 12/17/2001 – Pritchard Straddle Compressor Station
GW-273 expires 12/17/2001 – Moore Compressor Station
GW-272 expires 12/17/2001 – Kernaghan B-8 Compressor Station

WQCC 3106.F. If the holder of an approved discharge plan submits an application for discharge plan renewal at least 120 days before the discharge plan expires, and the discharger is not in violation of the approved discharge plan on the date of its expiration, then the existing approved discharge plan for the same activity shall not expire until the application for renewal has been approved or disapproved. A discharge plan continued

under this provision remains fully effective and enforceable. An application for discharge plan renewal must include and adequately address all of the information necessary for evaluation of a new discharge plan. Previously submitted materials may be included by reference provided they are current, readily available to the secretary and sufficiently identified to be retrieved. [12-1-95]

The discharge plan renewal application for each of the above facilities is subject to WQCC Regulation 20NMAC 6.2.3114. Every billable facility submitting a discharge plan renewal will be assessed a fee equal to the filing fee of $100.00. After January 15, 2001 renewal discharge plans require a flat fee equal to the flat fee schedule for gas processing facilities pursuant to revised WQCC Regulations 20NMAC 6.2.3114. A copy of the revised fee schedule is included for your assistance. The $100.00 filing fee is to be submitted with each discharge plan renewal application and is nonrefundable.

Please make all checks payable to: **NMED-Water Quality Management** and addressed to the OCD Santa Fe Office. Please submit the original discharge plan renewal application and one copy to the OCD Santa Fe Office and one copy to the OCD Aztec District Office. **Note that the completed and signed application form must be submitted with your discharge plan renewal request.** A complete copy of the regulations is also available on NMED's website at **www.nmenv.state.nm.us**).

If any of the above-sited facilities no longer has any actual or potential discharges and a discharge plan is not needed, please notify this office. If the Williams Field Services has any questions, please do not hesitate to contact Mr. Jack Ford at (505) 476-3489.

Sincerely,

Roger C. Anderson
Oil Conservation Division

cc: OCD Aztec District Office

Work Copy

SITE NAME	DISCHARGE PLAN #	CURRENT OCD PLAN # of Units/ HP	ACTUAL INSTALLS # of Units/ HP	AQB PERMITTED # of Units/ HP
Category 4 - Current OCD Plan reflects more units than actual install; AQB permit allows additional installs				
CARRACAS CDP	GW-112	2 units/895 HP ea	1 unit/895 HP	3 units/1378 HP ea
LA COSA C.S.	GW-187	8 units/ 1185 hp ea.	1 unit/2980 hp; 1 unit/1408 hp	1 unit/2980 hp; 4 units/1408 hp ea
Category 5 - Current OCD Plan reflects actual installations; AQB permit allows additional installs				
30-5 #1CDP	GW-108	9 units/1088 HP ea.	9 units/1088 HP ea.	12 units/1374 HP ea.
30-8 CDP	GW-133	10 units/1085 HP ea	10 units/1085 HP ea	14 units/1375 HP ea
DECKER JUNCTION CDP	GW-134	10 units/895 HP ea	10 units/895 HP ea	16 units/1388 HP ea
SIMS MESA CDP	GW-68	7 units/895 HP ea ok	7 units/895 HP ea	10 units/1374 HP ea
LATERAL N-30 C.S.	GW-256	2 units/1117 HP ea	2 units/1117 HP ea	6 units/1356 HP ea
Category 6 - Current OCD Plan reflects actual installations; all AQB permitted units are installed				
29-6 #3CDP	GW-198	1 unit/1129 HP ea.	1 unit/1129 HP ea.	1 unit/1129 HP ea,
32-8 #3	GW-116	6 units; /total site HP 8178	6 units/1373 HP ea	6 units/1373 HP ea
AZTEC CDP	GW-155	12 units/1384 HP ea	12 units/1384 HP ea	12 units/1384 HP ea
HART MTN. BOOSTER C.S.	GW-208	2 units/895 HP ea	2 units/895 HP ea	2 units/1151 HP ea
KERNAGHAN STRADDLE	GW-271	2 units/895 HP ea	2 units/895 HP ea	2 units/1121 HP ea
PRITCHARD STRADDLE C.S.	GW-273	3 units/1270 HP ea	3 units/1270 HP ea	3 units/1279 HP ea
TRUNK C BOOSTER C.S	GW-257	2 units/1268 HP ea	2 units/1268 HP ea	2 units/1268 HP ea
LAGUNA SECA	GW-307	2 units/1375 HP & 1146 hp	2 units/1375 HP& 1146 hp	2 units/1232 HP ea
TRUNK G C.S.	GW-229	1 unit/1373 HP	1 unit/1373 HP	1 unit/1373 HP
NORTH CRANDELL	GW-310	1 Sup 8GTL; 1059 hp	1 Sup 8GTL; 1059 hp	1 Sup 8GTL; 1059 hp
SNOW SHOE STRADDLE	GW-287	1 Caterpilla 500 HP	1 Caterpilla 500 HP	1 Caterpilla 500 HP
5-POINTS	GW-78	1Wauk H24GL; 418 hp	1Wauk H24GL; 418 hp	1Wauk H24GL; 418 hp
GALLEGOS	GW-293	1 Wauk F18; 335 hp	1 Wauk F18; 335 hp	1 Wauk F18; 335 hp
WILD HORSE	GW-79	1 unit/540 HP	1 unit/540 HP	1 unit/538 HP
COYOTE SPRINGS	GW-250	1 unit/1367 HP	1 unit/1367 HP	1 unit/1367 HP
CROUCH MESA	GW-129	1 unit/110 HP	1 unit/110 HP	1unit/677 HP

ACKNOWLEDGEMENT OF RECEIPT OF CHECK/CASH

I hereby acknowledge receipt of check No. [redacted] dated 9/26/96,

or cash received on ____________ in the amount of $ 690.00

from Williams Field Services

for Trunk C CS. GW-257

(Facility Name) (DP No.)

Submitted by: ____________________ Date: ____________

Submitted to ASD by: ____________________ Date: 10/18/96

Received in ASD by: ____________________ Date: 10/23/96

Filing Fee ____ New Facility X Renewal ____

Modification ____ Other ____________________

(specify)

Organization Code 521.07 Applicable FY 97

To be deposited in the Water Quality Management Fund.

Full Payment X or Annual Increment ____

WILLIAMS FIELD SERVICES COMPANY
ONE OF THE WILLIAMS COMPANIES

P. O. Box 58900
Salt Lake City, Utah 84158-0900

Chase Manhattan Bank Delaware
1201 Market Street
Wilmington DE 19801

62-26 / 311 5736-09

DATE	CHECK NO.	NET AMOUNT
09/26/96	[redacted]	690.00

PAY
SIX HUNDRED NINETY AND 00/100--

TO THE ORDER OF

NEW MEXICO OIL CONSERVATION DI
NM WATER QUALITY MGMT FUND
2040 SOUTH PACHECO
SANTA FE NM 87504

Williams Field Services Company

VICE PRESIDENT

AUTHORIZED REPRESENTATIVE

[redacted]

WILLIAMS FIELD SERVICES
ONE OF THE WILLIAMS COMPANIES, INC.

P.O. Box 58900 Salt Lake City, Utah 84158-0900

September 23, 1996

Mr. Roger Anderson
New Mexico Oil Conservation Division
2040 South Pacheco
Santa Fe, New Mexico 87504

Re: Discharge Plans Fee - San Juan County
Trunk C Booster Station GW-257

Dear Mr. Anderson:

Enclosed, please find the signed Conditions of Approval and a check made payable to the WQCC to cover the discharge plan fees for the above referenced Williams Field Services Company facility.

If you have any questions or require additional information, please do not hesitate to contact me at (801) 584-6543.

Sincerely,

Leigh E. Gooding
Sr. Environmental Specialist

enclosure

295 Chipeta Way Salt Lake City, Utah 84108
(801) 584-7033

Williams Field Services Company

4341 NEW MEXICO OIL CONSERVATION DI [redacted] 09/26/96

INVOICE NUMBER	DESCRIPTION	INVOICE DATE	AMOUNT	DISCOUNT	NET AMOUNT
91896	DIS. PLAN TRUNK C GW-257	09/18/96	690.00	0.00	690.00
			690.00	0.00	690.00

PLEASE DETACH BEFORE DEPOSITING

AFFIDAVIT OF PUBLICATION

No. 36712

STATE OF NEW MEXICO
County of San Juan:

ROBERT LOVETT being duly sworn says: That he is the Classified Manager of THE DAILY TIMES, a daily newspaper of general circulation published in English at Farmington, said county and state, and that the hereto attached Legal Notice was published in a regular and entire issue of the said DAILY TIMES, a daily newspaper duly qualified for the purpose within the meaning of Chapter 167 of the 1937 Session Laws of the State of New Mexico for publication on the following day(s):

Thursday, August 8, 1996;

and the cost of publication is: $76.28.

Robert Lovett

On 8/12/96 ROBERT LOVETT appeared before me, whom I kno personally to be the person who signed th above document.

Denise W. Henson

My Commission Expires May 17, 2000

COPY OF PUBLICATION

Legals

NOTICE OF PUBLICATION

STATE OF NEW MEXICO
ENERGY, MINERALS, AND NATURAL RESOURCES DEPARTMENT
OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to New Mexico Water Quality Control Commission Regul the following discharge plan applica" s have been submitted to the Director of the Oil Con tion Division, 2040 South Pacheco, Santa Fe, New Mexico 87505, Telephone (505) 827-7131:

(GW-256) - Williams Field Services, Ms. Leigh Gooding, (801)-584-6543, P.O. Box 58900 2G1, Salt Lake City, Utah 84158-0900, has submitted a Discharge Plan Application fc Manzanares Gathering System Koch-Gardner Compressor Station located in the NW/4, S Section 25, Township 32 North, Range 9 West, NMPM, San Juan County, New Mexic proximately 75 gallons per day of waste water is stored in an above ground bermed clos tank. All wastes are disposed of offsite at an NMOCD approved facility. Groundwater mos ly to be affected by a spill, leak, or accidental discharge to the surface is at a depth of ap imately 350 feet with a total dissolved solids concentration of approximately 2,000 mg/l discharge plan addresses how spills, leaks, and other accidental discharges to the surfac be managed.

(GW-257) - Williams Field Services, Ms. Leigh Gooding, (801)-584-6543, P.O. Box 58900. 2G1, Salt Lake City, Utah 84158-0900, has submitted a Discharge Plan Application fo Manzanares Gathering System Trunk C Compressor Station located in the SE/4 SW/4, Se 9, Township 31 North, Range 10 West, NMPM, San Juan County, New Mexico. Approxir 75 gallons per day of waste water is stored in an above ground bermed closed top tan wastes are disposed of offsite at an NMOCD approved facility. Groundwater most likely affected by a spill, leak, or accidental discharge to the surface is at a depth of approxir 140 feet with a total dissolved solids concentration of approximately 2,000 mg/L. The disct plan addresses how spills, leaks, and other accidental discharges to the surface will be aged.

Any interested person may obtain further information from the Oil Conservation Division and submit written comments to the Director of the Oil Conservation Division at the address g above. The discharge plan applications may be viewed at the above address between 8:00 and 4:00 p.m., Monday through Friday. Prior to ruling on any proposed discharge plan or its m cation, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the of publication of this notice during which comments may be submitted to him and a public hea may be requested by any interested person. Requests for public hearing shall set forth the reas why a hearing should be held. A hearing will be held if the Director determines there is signifi public interest.

If no public hearing is held, the Director will approve or disapprove the proposed plan based or formation available. If a public hearing is held, the Director will approve or disapprove the propc plan based on information in the discharge plan application and information submitted at the h ing.

GIVEN under the Seal of New Mexico Oil Conservation Commission at Santa Fe, New Mexico, this 30th day of July, 1996.

STATE OF NEW MEXICO
OIL CONSERVATION DIVIS
/s/William J. Lemay
WILLIAM J. LEMAY, Direct

SEAL

Legal No. 36712 published in The Daily Times, Farmington, New Mexico on Thursday, August 8, 1996.

The Santa Fe New Mexican
Since 1849. We Read You.

NEW MEXICO OIL CONSERVATION

AD NUMBER: 533115 ACCOUNT: 56689

LEGAL NO: 60161 P.O. #: 9619900299

223 LINES once at $ 89.20

Affidavits: 5.25

Tax: 5.90

Total: $ 100.35

AFFIDAVIT OF PUBLICATION

STATE OF NEW MEXICO
COUNTY OF SANTA FE

I, BETSY PERNER being first duly sworn declare and say that I am Legal Advertising Representative of THE SANTA FE NEW MEXICAN, a daily news paper published in the English language, and having a general circulation in the Counties Santa Fe and Los Alamos, State of New Mexico and being a Ne paper duly qualified to publish legal notices and advertisements under the provisions of Chapter 167 on Session Laws of 1937; that the publication # 60161 a copy of which is hereto attached was published in said newspaper once each week for one consecutive week(s) and that the notice was published in the newspaper proper and not in any supplement; the first publication being on the 5th day of AUGUST 1996 and that the undersigned has personal knowledge of the matter and things set forth in this affidavit.

/S/ Betsy Perner
LEGAL ADVERTISEMENT REPRESENTATIVE

Subscribed and sworn to before me on this 5th day of AUGUST A.D., 1996

OFFICIAL SEAL
Candace C. Ruiz
NOTARY PUBLIC
STATE OF NEW MEXICO
My Commission Expires: 7/29/99

202 East Marcy Street • P.O. Box 2048 • Santa Fe, New Mexico 87501
505~983~3303 • NEWMEX@NEW MEXICO.COM • http://www.interart.net/zia.connection/

NOTICE OF PUBLICATION

STATE OF NEW MEXICO

ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT

OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to New Mexico Water Quality Control Commission Regulations, the following discharge plan applications have been submitted to the Director of the Oil Conservation Division, 2040 South Pacheco, Santa Fe, New Mexico, 87505, Telephone (505) 827-7131:

(GW-256) - Williams Field Services, Ms. Leigh Gooding, (801)-584-6543, P.O. Box 58900, M.S. 2G1, Salt Lake City, Utah 84158-0900, has submitted a Discharge Plan Application for the Manzanares Gathering System Koch-Gardner Compressor Station located in the NW/4 SE/4 of Section 25, Township 32 North, Range 9 West, NMPM, San Juan County, New Mexico. Approximately 75 gallons per day of waste water is stored in an above ground bermed closed top tank. All wastes are disposed of offsite at an NMOCD approved facility. Groundwater most likely to be affected by a spill, leak, or accidental discharge to the surface is at a depth of approximately 350 feet with a total dissolved solids concentration of approximately 2,000 mg/L. The discharge plan addresses how spills, leaks, and other accidental discharges to the surface will be managed.

(GW-257) - Williams Field Services, Ms. Leigh Gooding, (801)-584-6543, P.O. Box 58900, M.S. 2G1, Salt Lake City, Utah 84158-0900, has submitted a Discharge Plan Application for the Manzanares Gathering System Trunk C Compressor Station located in the SE/4 SW/4 of Section 9, Township 31 North, Range 10 West, NMPM, San Juan County, New Mexico. Approximately 75 gallons per day of waste water is stored in an above ground bermed closed top tank. All wastes are disposed of offsite at an NMOCD approved facility. Groundwater most likely to be affected by a spill, leak, or accidental discharge to the surface is at a depth of approximately 140 feet with a total dissolved solids concentration of approximately 2,000 mg/L. The discharge plan addresses how spills, leaks, and other accidental discharges to the surface will be managed.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan applications may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday through Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and a public hearing may be requested by any interested person. Requests for a public hearing shall set forth the reasons why a hearing should be held. A hearing will be held if the Director determines there is significant public interest.

If no public hearing is held, the Director will approve or disapprove the proposed plan based on information available. If a public hearing is held, the director will approve or disapprove the proposed plan based on information in the discharge plan application and information submitted at the hearing.

GIVEN under the Seal of New Mexico Oil Conservation Commission at Santa Fe, New Mexico, on this 30th day of July 1996.

STATE OF NEW MEXICO
OIL CONSERVATION DIVISION
WILLIAM J. LEMAY,
Director
Legal #60161
Pub. August 5, 1996

NOTICE OF PUBLICATION

STATE OF NEW MEXICO
ENERGY, MINERALS AND NATURAL RESOURCES DEPARTMENT
OIL CONSERVATION DIVISION

Notice is hereby given that pursuant to New Mexico Water Quality Control Commission Regulations, the following discharge plan applications have been submitted to the Director of the Oil Conservation Division, 2040 South Pacheco, Santa Fe, New Mexico 87505, Telephone (505) 827-7131:

(GW-256) - Williams Field Services, Ms. Leigh Gooding, (801)-584-6543, P.O. Box 58900, M.S. 2G1, Salt Lake City, Utah 84158-0900, has submitted a Discharge Plan Application for the Manzanares Gathering System Koch-Gardner Compressor Station located in the NW/4 SE/4 of Section 25, Township 32 North, Range 9 West, NMPM, San Juan County, New Mexico. Approximately 75 gallons per day of waste water is stored in an above ground bermed closed top tank. All wastes are disposed of offsite at an NMOCD approved facility. Groundwater most likely to be affected by a spill, leak, or accidental discharge to the surface is at a depth of approximately 350 feet with a total dissolved solids concentration of approximately 2,000 mg/L. The discharge plan addresses how spills, leaks, and other accidental discharges to the surface will be managed.

(GW-257) - Williams Field Services, Ms. Leigh Gooding, (801)-584-6543, P.O. Box 58900, M.S. 2G1, Salt Lake City, Utah 84158-0900, has submitted a Discharge Plan Application for the Manzanares Gathering System Trunk C Compressor Station located in the SE/4 SW/4 of Section 9, Township 31 North, Range 10 West, NMPM, San Juan County, New Mexico. Approximately 75 gallons per day of waste water is stored in an above ground bermed closed top tank. All wastes are disposed of offsite at an NMOCD approved facility. Groundwater most likely to be affected by a spill, leak, or accidental discharge to the surface is at a depth of approximately 140 feet with a total dissolved solids concentration of approximately 2,000 mg/L. The discharge plan addresses how spills, leaks, and other accidental discharges to the surface will be managed.

Any interested person may obtain further information from the Oil Conservation Division and may submit written comments to the Director of the Oil Conservation Division at the address given above. The discharge plan applications may be viewed at the above address between 8:00 a.m. and 4:00 p.m., Monday through Friday. Prior to ruling on any proposed discharge plan or its modification, the Director of the Oil Conservation Division shall allow at least thirty (30) days after the date of publication of this notice during which comments may be submitted to him and a public hearing may be requested by any interested person. Requests for a public hearing shall set forth the reasons why a hearing should be held. A hearing will be held if the Director determines there is significant public interest.

If no public hearing is held, the Director will approve or disapprove the proposed plan based on information available. If a public hearing is held, the Director will approve or disapprove the proposed plan based on information in the discharge plan application and information submitted at the hearing.

GIVEN under the Seal of New Mexico Oil Conservation Commission at Santa Fe, New Mexico, on this 30th day of July, 1996.

STATE OF NEW MEXICO
OIL CONSERVATION DIVISION

SEAL

WILLIAM J. LEMAY, Director

WILLIAMS FIELD SERVICES
ONE OF THE WILLIAMS COMPANIES

P.O. Box 58900
Salt Lake City, UT 84158-0900
(801) 584-7033
FAX: (801) 584-6483

July 19, 1996

Mr. Roger Anderson
New Mexico Oil Conservation Division
2040 South Pacheco
Santa Fe, New Mexico 87504

Re: Discharge Plans for Trunk C and Koch-Gardner Compressor Stations - San Juan County

Dear Mr. Anderson:

Enclosed please find two copies of the Discharge Plan for Williams Field Services' Trunk C Compressor Station and Koch-Gardner Compressor Station. Both stations are located in San Juan County, New Mexico. Also enclosed, please find a check for $100.00, payable to the New Mexico Water Quality Management Fund, to cover the application fees for the above referenced projects.

If you have any questions or require additional information, please do not hesitate to contact me at (801) 584-6543.

Sincerely,

Leigh E. Gooding
Sr. Environmental Specialist

enclosure

cc: Denny Foust, OCD District III Office (letter and enclosure)

ACKNOWLEDGEMENT OF RECEIPT OF CHECK/CASH

I hereby acknowledge receipt of check No. [redacted] dated 7/18/96,

or cash received on _____ in the amount of $ 100.00

from Williams Field Svcs

for Koch C.S GW 256
Trunk C C.S GW 257
(Facility Name) (DP No.)

Submitted by: _____ Date: _____

Submitted to ASD by: R. Chandler Date: 7/31/96

Received in ASD by: _____ Date: _____

Filing Fee X New Facility ___ Renewal ___

Modification ___ Other _____
(specify)

Organization Code 521.07 Applicable FY 97

To be deposited in the Water Quality Management Fund.

Full Payment ___ or Annual Increment ___

WILLIAMS FIELD SERVICES COMPANY
ONE OF THE WILLIAMS COMPANIES

P. O. Box 58900
Salt Lake City, Utah 84158-0900

Chemical Bank Delaware
1201 Market Street
Wilmington DE 19801

62-26
311

5736-09

DATE	CHECK NO.	NET AMOUNT
07/18/96	[redacted]	100.00

PAY
ONE HUNDRED AND 00/100----------

TO THE ORDER OF
NEW MEXICO OIL CONSERVATION DI
NM WATER QUALITY MGMT FUND
2040 SOUTH PACHECO
SANTA FE NM 87504

Williams Field Services Company
VICE PRESIDENT
AUTHORIZED REPRESENTATIVE

[redacted]

DISCHARGE PLAN

GW-257

MANZANARES GATHERING SYSTEM
TRUNK C BOOSTER STATION

Williams Field Services Company

July 1996

State of New Mexico
Energy, Minerals and Natural Resources Department
OIL CONSERVATION DIVISION
P.O. Box 2088
Santa Fe, NM 87501

DISCHARGE PLAN APPLICATION FOR NATURAL GAS PROCESSING PLANTS, OIL REFINERIES AND GAS COMPRESSOR STATIONS

(Refer to OCD Guidelines for assistance in completing the application.)

I. TYPE: Trunk C Booster Compressor Station

II. OPERATOR: Williams Field Services Company

ADDRESS: 295 Chipeta Way P.O. Box 58900 Salt Lake City, Utah 84158

CONTACT PERSON: Ms. Leigh Gooding PHONE: (801) 584-6543

III. LOCATION: SE /4 SW /4 Section 9 Township 31 North Range 10 West
Submit large scale topographic map showing exact location.

IV. Attach the name and address of the landowner(s) of the disposal facility site.

V. Attach description of the facility with a diagram indicating location of fences, pits, dikes, and tanks on the facility.

VI. Attach a description of sources, quantities and quality of effluent and waste solids.

VII. Attach a description of current liquid and solid waste transfer and storage procedures.

VIII. Attach a description of current liquid and solid waste disposal procedures.

IX. Attach a routine inspection and maintenance plan to ensure permit compliance.

X. Attach a contingency plan for reporting and clean-up of spills or releases.

XI. Attach geological/hydrological evidence demonstrating that disposal of oil field wastes will not adversely impact fresh water. Depth to and quality of ground water must be included.

XII. Attach such other information as is necessary to demonstrate compliance with any other OCD rules, regulations and/or orders.

XIII. CERTIFICATION

I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.

Name: Terry G. Spradlin Title: Manager, Environment Health & Safet

Signature: Terry G. Spradlin Date: 7-10-96

DISTRIBUTION: Original and one copy to Santa Fe with one copy to appropriate Division District Office.

I. TYPE OF OPERATION

The Trunk C Booster Station will provide metering and compression services to various producers for the gathering of coal seam natural gas on a contract basis for ultimate delivery through Williams Field Services (WFS) Milagro Plant in Bloomfield, New Mexico.

II. LEGALLY RESPONSIBLE PARTY

Williams Field Services Company
295 Chipeta Way
P.O. Box 58900
Salt Lake City, Utah 84158-0900
(801) 584-6543

Contact Person:

Ms. Leigh E. Gooding, Sr. Environmental Specialist
Phone and Address, Same as Above

III. LOCATION OF DISCHARGE

The Trunk C Booster Station is located in the SE/4 of the SW/4 of Section 9, Township 31 North, Range 10 West, in San Juan County, New Mexico. A Site Location map is attached (USGS 7.5 Min. Quadrangle: Cedar Hill and Mount Nebo, New Mexico) as Figure 1. The site for this station will be 3.65 acres. The site boundary survey is provided in Figure 2. The facility layout is presented in Figure 3.

IV. LANDOWNER

Williams Field Services is leasing the subject property from:

Bureau of Land Management
1235 N. La Plata Highway
Farmington, NM 87401
(505) 599-6332

V. FACILITY DESCRIPTION

Two (2) Waukesha 7042 GL natural gas reciprocating engines, site rated at 1,268 horsepower (hp) each will installed at the site. The units are skid-mounted and self contained. This facility is classified as a field compressor station; consequently, there are no formal office or other support facilities not essential to field compression.

VI. SOURCES, QUANTITIES AND QUALITY OF EFFLUENTS AND WASTE SOLIDS

The sources, quantities and quality of effluent and waste solids generated at the compressor station are summarized in Table 1. Material Safety Data Sheets for glycol and oil used in the equipment were previously provided to New Mexico Oil Conservation Division (NMOCD) by WFS. For reference, representative samples of washdown wastewater and used motor oil have previously been collected from representative WFS compressor stations and analyzed for the parameters listed below.

Sample	Parameters
Washdown Wastewater	pH, TDS, TOX, TPH, BETX, As, Ba, Cd, Cr, Pb, Hg, Se, Ag.
Used Motor Oil	As, Cd, Cr, Pb, TOX, Flash Point

The results of previous tests conducted on similar waste streams showed that the washdown water did not exhibit any of the hazardous characteristics and used motor oil was suitable for recycling (Appendix A). Additional Chemicals listed in WQCC 1101.TT and 3103 are not expected to be present in any process fluids or in the gas transported at the Trunk C Booster Station.

Used oil filters have been collected from representative WFS compressor stations and analyzed for TCLP Metals. The results of the analysis found that the filters did not exceed TCLP concentrations for metals. The analyses were submitted to the San Juan County Regional Landfill along with the Waste Acceptance Profiles. These profiles are updated every two years or as required by the landfill.

VII. TRANSFER AND STORAGE OF PROCESS FLUIDS, EFFLUENTS AND WASTE SOLIDS

Used motor oil is collected in a closed-piping system to a 500-gallon above-ground storage tank located at each compressor and transported by an EPA-registered used oil marketer (D&D Oil, EPA ID# NMD986682102).

All liquids from the gas-inlet separator are collected separately in a 70-barrel (bbl) above-ground storage tank. The tank is gauged every two weeks and the liquids are transported to Basin Disposal. Washdown wastewater from engine deck plates will be collected in a closed piping system directly to a below-grade sump. The sump will be a 750-gallon, fiberglass, doubled wall tank, equipped with leak detection. Wastewater accumulations will be removed from the inner tank using a vacuum truck and transported to an NMOCD-approved surface disposal facility. A schematic drawing of the sump is presented in Figure 4.

Used oil filters are drained, stored in 50-gallon plastic drums, and transported by Waste Management of Four Corners to the San Juan County Regional Landfill.

VIII. EFFLUENT AND WASTE SOLIDS DISPOSAL

Exempt and non-exempt wastes are managed separately. Only exempt wastes are disposed down Class II injection wells. Non-exempt wastes are characterized for hazardous constituents.

- Used motor oil is recycled by an EPA-registered used oil marketer (D&D Oil, EPA ID# NMD986682102).
- Natural gas liquids from the gas-inlet separator and dehydrator separator is disposed at Basin Disposal.
- Washdown water has been shown to be non-hazardous and as such, is disposed at an NMOCD-approved surface disposal facility.
- Porta-pottys present at this facility are serviced under a contract requiring proper sewage disposal in accordance with applicable laws and regulations.

TABLE 1
SOURCES, QUANTITIES AND QUALITY OF EFFLUENT AND WASTE SOLIDS
TRUNK C COMPRESSOR STATION

PROCESS FLUID/WASTE	SOURCES	QUANTITY	QUALITY	DISPOSITION
Used Oil	Compressors	250 gal/yr	Used motor oil w/no additives	Collected separately in 500-gal AST at each compressor. Transported to D&D Oil for recycling.
Natural Gas Liquids	Gas Inlet Separator Dehydrators	500 gal/yr	No additives	Collected separately in 70-bbl AST. Transported to Basin Disposal.
Washdown Water	Compressor and Glycol Dehydrator	500 gal/yr	Soap and tap water w/traces of used oil and triethylene glycol	Collected in a below-grade tank. Transported to NMOCD-approved surface disposal facility for disposal.
Oil Filters	Compressor	20/yr	No additives	Drained and placed in 55-gallon plastic drums. Transported to the San Juan County Landfill for disposal.

IX. INSPECTION, MAINTENANCE AND REPORTING

Production Operators, Incorporated (POI) is under contract to operate and maintain the compression unit at the facility. WFS's Manzanares Gathering District operates the dehydration units. The facility is inspected several times per week at a minimum and a POI operator is on call 24 hours per day, 7 days per week, 52 weeks per year. The facility is remotely monitored for equipment malfunctions. POI must comply with WFS' spill response procedures. In the event of a release of a reportable quantity, POI will immediately notify WFS' Environmental Service Department and WFS will report the release to NMOCD. The below-grade wastewater tank is monitored monthly for leak detection.

X. SPILL/LEAK PREVENTION AND REPORTING (CONTINGENCY PLANS)

For overflow containment, lube oil tanks on saddle racks are underlain by concrete splash aprons equipped with retainment curbs. Fluids which collect within the curbed area drain through a pipe into a closed containment system. A drip pan is placed beneath the catwalk adjacent to the oil filter on each compressor unit to contain spillage during maintenance activities. Spill containment dikes around the bulk storage tanks will contain 1 1/3 volume of the largest vessel. Spill containment will also be provided around the tank loading valves. Surface runoff within the site is diverted around facility processes into the natural drainage path to the west.

All pressure vessels on site will be tested in accordance with the requirement of the ASME Boiler and Pressure Vessel Code. All interconnecting gas piping on site will be tested in accordance with the requirements of the ASME Code for Pressure Piping, B31.8 Gas Transmission and Distribution Piping Systems.

WFS corporate policy and procedure for the controlling and reporting of Discharges or Spills of Oil or Hazardous Substances is provided in Appendix B. Significant spills and leaks are reported to the NMOCD pursuant to NMOCD Rule 116 and WQCC 1-203 using the NMOCD form (see Appendix C).

XI. SITE CHARACTERISTICS

The Trunk C Booster Station is located in the SE/4 SW/4 of Section 9, Township 31 North, Range 10 West, San Juan County, New Mexico approximately 3 kilometers south-southeast of Cedar Hill, New Mexico. The site elevation is approximately 6,140 feet above mean sea level. The undeveloped site is covered by sagebrush, crested wheat grass, and native grasses.

Hydrologic Features: The site is located along a dirt road, approximately 1,300 feet southwest of Miller Canyon. The site is underlain by silty clays over sandstones and shales of the Animas Formation. Surface runoff from the area surrounding the site is diverted around the yard and to the west. Runoff continues to an ephemeral tributary to the Miller Canyon drainage located approximately 500 feet west of the site.

A review of the well records on file with the State Engineer's Office revealed twelve (12) ground water wells within a one-mile radius of the site (Appendix D). A review of available hydrologic data[1] for this area revealed that the closest documented source of ground water downgradient from the subject site are the alluvial deposits associated with the Miller Canyon drainage. Ground water within these alluvial deposits is expected to have a total dissolved solids (TDS) concentration of approximately 2000 mg/l. Based on the elevation of the canyon (6000'), the depth to groundwater is approximately 140 feet below ground surface.

Flood Protection: Stormwater runoff from the area surrounding the site is diverted around the facility into the natural drainage path.

XII FACILITY CLOSURE PLAN

All reasonable and necessary measures will be taken to prevent the exceedance of WCQQ Section 3103 quality standards should WFS choose to permanently close the facility. WFS will submit a detailed closure plan to the NMOCD prior to closure.

Generally, closure measures will include removal or closure in place of all underground piping and equipment. All tanks will be emptied. No potentially toxic materials or effluents will remain on the site. All potentially toxic pollutants will be inspected. Should contaminated soil be discovered, any necessary reporting under NMOCD Rule 116 and WQCC Section 1203 will be made and clean-up activities will commence. Post-closure maintenance and monitoring plans would not be necessary unless contamination is encountered.

---

[1] Klausing, R.L. and G.E. Welder, "Availability of Hydrologic Data in San Juan County, New Mexico:, U.S.G.S. Open-File Report 84-608, 1984.

Lyford, F.P., "Ground Water in the San Juan Basin, New Mexico and Colorado", U.S.G.S. Water-Resource Investigations 79-73, May, 1979.

Stone, W.J., F.P. Lyford, P.F. Frenzel, N.H. Mizel, E.P. Padgett, "Hydrogeology and Water Resources of San Juan Basin, New Mexico", Hydrologic Report 6, New Mexico Bureau of Mines & Mineral Resources, 1983.

FIGURE 1

SITE LOCATION MAP



Location of Trunk C Booster Station

FIGURE 2

SITE SURVEY PLAN



PLAN VIEW



DETAIL

NOTES
1. ALL COORDINATES AS SHOWN ARE DERIVED FROM U.S.G.S. QUAD MAP. UTM COORDINATES, ZONE 13, IN METERS
2. ○ DENOTES SET 1/2" REBAR W/CAP STAMPED L.S. #6707

CERTIFICATION OF SURVEYOR

I HEREBY CERTIFY THAT THIS PLAT IS A TRUE REPRESENTATION OF A SURVEY MADE BY ME OR UNDER MY DIRECT SUPERVISION AND THE SAME IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

PRELIMINARY

DATE

HARVEY B. PETERSON
NEW MEXICO L.S. #6707

WILLIAMS FIELD SERVICES

MANZANARES GATHERING SYSTEM
TRUNK C BOOSTER SITE
SEC. 9, T-31-N, R-10-W, NMPM
SAN JUAN COUNTY, NEW MEXICO

NO.	DATE	BY	REVISION	APP.
1	3/25/96	CJF	ISSUED FOR REVIEW	

SURVEYED	3/20/96	DRG. NO.	798.9-X-51	SCALE:		DATE	3/25/96
FIELD BOOK:		OWNER	BLM	DRAWN BY	CJF	CHECKED BY	PB

APPROVED BY:
DRG. NO. 796.12-X-33
REV.

N

Site Survey

FIGURE 3

FACILITY PLOT PLAN



PRODUCTION OPERATORS INC.

DWG. No.	DESCRIPTION
TRC-1-M1	TRUNK "C" EXCAVATION & SITE LAYOUT

REFERENCE DRAWINGS

NO.	DATE	BY	DESCRIPTION	W.O. #	APP.

REVISIONS

NO.	DATE	BY	DESCRIPTION	W.O. #	APP.
0	7/8/96	TT	ISSUED FOR CONSTRUCTION		

REVISIONS

DRAFTING	BY	DATE
DRAWN	TT	7/3/96
CHECKED	JK	7/8/96
APPROVED	-	
ENGINEERING	BY	DATE
C & S REVIEW		
PROJECT APPROVED	-	
PLOT DATE/TIME	7/3/1996 9:44 AM	

WILLIAMS FIELD SERVICES
ONE OF THE WILLIAMS COMPANIES

SAN JUAN TRUNK "C" BOOSTER COMPR. SITE
FOUNDATION LOCATION PLAN

SCALE: 1" = 20'-0"
W.O. # 12680

DWG. NO. TRC-2-M5

FIGURE 4

BELOW-GRADE WASTEWATER SUMP



WASTE WATER SUMP
PLAN VIEW



WASTE WATER SUMP
ELEVATION

PRELIMINARY

LEGEND	REFERENCE DRAWINGS				REVISIONS													
	DRAWING NO.	TITLE	DRAWING NO.	TITLE	NO.	DATE	BY	DESCRIPTION	W.O.NO.	CHK.	APP.	NO.	DATE	BY	DESCRIPTION	W.O.NO.	CHK.	APP.

DRAFTING	BY	DATE
DRAWN	RJB	03/02/95
CHECKED		
APPROVED		
ENGINEERING	BY	DATE
PROJ. APPROVED		

WILLIAMS GAS PROCESSING
ONE OF THE WILLIAMS COMPANIES

GATHERING SYSTEM STANDARD
FIBERGLASS WATER SUMP

SCALE: 1"=1' | W.O. NO. 11807 | DWG. NO. STD-D-1-4042 | REV.

APPENDIX A

WASTE ANALYSIS

Enseco Incorporated

CEDAR HILL C.D.P.
WASTE OIL +
WASTEWATER

Enseco
A Corning Company

ANALYTICAL RESULTS

FOR

NORTHWEST PIPELINE CORPORATION

ENSECO-RMAL NO. 024601

SEPTEMBER 21, 1992

Rocky Mountain
Analytical Laboratory

Enseco
A CORNING Company

ANALYTICAL RESULTS

FOR

NORTHWEST PIPELINE CORPORATION

ENSECO-RMAL NO. 024601

SEPTEMBER 21, 1992

Reviewed by:

Joe A. Maes

Joel E. Holtz

Enseco Incorporated
4955 Yarrow Street
Arvada, Colorado 80002
303/421-6611 Fax: 303/431-7171

ORGANIC ANALYSIS REPORT

AMERICAN WEST ANALYTICAL LABORATORIES

463 West 3600 South
Salt Lake City, Utah
84115

(801) 263-8686
Fax (801) 263-8687

Client: Williams Field Services
Date Sampled: July 19,1995
Date Received: July 20,1995

Contact: Mark Harvey
Date Analyzed: July 26,1995

Analysis Requested:
Volatile Aromatics
Total Purgeable Hydrocarbons

Method Ref.Number:
SW-846 #8260
(Purge & Trap GC/MS)

Field Sample ID:
SAN JUAN AREA
CEDAR HILL #1

Lab Sample ID:
L23218-8

Analytical Results — **BTX/TPH-P**

Units = mg/L(ppm)

Compound:	Detection Limit:	Amount Detected:
Benzene	0.020	**0.036**
Toluene	0.020	**0.046**
Ethylbenzene	0.020	**0.14**
Total Xylene	0.020	**0.95**
Total Purgeable Hydrocarbons	0.20	**19.**

< Value = None detected above the specified detection limit, or a value that reflects a reasonable limit due to interferences.

Released By: _____
Laboratory Supervisor

Report Date: July 31,1995

AMERICAN WEST ANALYTICAL LABORATORIES

463 West 3600 South
Salt Lake City, Utah
84115

(801) 263-8686
Fax (801) 263-8687

INORGANIC ANALYSIS REPORT

Client: Williams Field Service
Date Sampled: July 19, 1995
Lab Sample ID.: 23218-08
Field Sample ID: San Juan Area/Cedar Hill #1

Contact: Mark Harvey
Date Received: July 20, 1995
Received By: Laurie Hastings
Set Description: One Water and Seven Soil Samples

Analytical Results

	Method Used:	Detection Limit: mg/L	Amount Detected: mg/L
TOTAL METALS			
Arsenic	7060	0.005	<0.005
Barium	6010	0.002	2.8
Cadmium	6010	0.004	0.013
Chromium	6010	0.01	0.03
Lead	6010	0.05	0.13
Mercury	7471	0.001	<0.001
Selenium	7740	0.005	<0.005
Silver	6010	0.01	<0.01
OTHER CHEMISTRIES			
pH	150.1	0.1	6.8
TDS	160.1	1.0	3,600.
TOX	9020	0.5	1.6

Released by: _____
Laboratory Supervisor

Report Date 8/2/95

Introduction

This report presents the analytical results as well as supporting information to aid in the evaluation and interpretation of the data and is arranged in the following order:

- Sample Description Information
- Analytical Test Requests
- Analytical Results
- Quality Control Report

All analyses at Enseco are performed so that the maximum concentration of sample consistent with the method is analyzed. Dilutions are at times required to avoid saturation of the detector, to achieve linearity for a specific target compound, or to reduce matrix interferences. In this event, reporting limits are adjusted proportionately. Surrogate compounds may not be measurable in samples which have been diluted.

Sample 024601-0001 was diluted for Method 8020 due to concentrations of target compounds present beyond linear range; the reporting limits have been increased accordingly.

Sample 024601-0002 was diluted for Method 9020 due to matrix interferences; the reporting limits have been increased accordingly.

Sample Description Information

The Sample Description Information lists all of the samples received in this project together with the internal laboratory identification number assigned for each sample. Each project received at Enseco-RMAL is assigned a unique six digit number. Samples within the project are numbered sequentially. The laboratory identification number is a combination of the six digit project code and the sample sequence number.

Also given in the Sample Description Information is the Sample Type (matrix), Date of Sampling (if known) and Date of Receipt at the laboratory.

Analytical Test Requests

The Analytical Test Requests lists the analyses that were performed on each sample. The Custom Test column indicates where tests have been modified to conform to the specific requirements of this project.

Enseco
A Corning Company

SAMPLE DESCRIPTION INFORMATION
for
Northwest Pipeline Corporation

Lab ID	Client ID	Matrix	Sampled Date	Sampled Time	Received Date
024601-0001-SA	CEDAR HILL CDP WASTE WATER TAN	AQUEOUS	18 AUG 92	12:40	19 AUG 92
024601-0002-SA	WASTE OIL TANK CEDAR HILL	AQUEOUS	18 AUG 92	11:30	19 AUG 92
024601-0003-TB	TRIP BLANK	AQUEOUS			19 AUG 92

Enseco
A Corning Company

ANALYTICAL TEST REQUESTS
for
Northwest Pipeline Corporation

Lab ID: 024601	Group Code	Analysis Description	Custom Test?
0001	A	pH	N
		Total Dissolved Solids (TDS)	N
		ICP Metals (Total)	Y
		Prep - Total Metals, ICP	N
		Total Organic Halogen (TOX)	N
		Benzene, Toluene, Ethyl Benzene and Xylenes (BTEX)	N
		Arsenic, Furnace AA (Total)	N
		Prep - Total Metals, Furnace AA	N
		Lead, Furnace AA (Total)	N
		Mercury, Cold Vapor AA (Total)	N
		Prep - Mercury, Cold Vapor AA (Total)	N
0002	B	Arsenic, Furnace AA	N
		Prep - Total Metals, Furnace AA	N
		ICP Suite	Y
		Prep - Total Metals, ICP	N
		Lead, Furnace AA	N
		Total Organic Halogen (TOX)	N
		Ignitability, Closed Cup	N
0003	C	Benzene, Toluene, Ethyl Benzene and Xylenes (BTEX)	N

Analytical Results

The analytical results for this project are presented in the following data tables. Each data table includes sample identification information, and when available and appropriate, dates sampled, received, authorized, prepared and analyzed. The authorization data is the date when the project was defined by the client such that laboratory work could begin.

Data sheets contain a listing of the parameters measured in each test, the analytical results and the Enseco reporting limit. Reporting limits are adjusted to reflect dilution of the sample, when appropriate. Solid and waste samples are reported on an "as received" basis, i.e. no correction is made for moisture content.

The results from the Standard Enseco QA/QC Program, which generates data which are independent of matrix effects, are provided subsequently.

Enseco
A Corning Company

Benzene, Toluene, Ethyl Benzene and Xylenes (BTEX)

Method 8020

Client Name: Northwest Pipeline Corporation
Client ID: CEDAR HILL CDP WASTE WATER TANK
Lab ID: 024601-0001-SA
Matrix: AQUEOUS Sampled: 18 AUG 92 Received: 19 AUG 92
Authorized: 19 AUG 92 Prepared: NA Analyzed: 22 AUG 92

Parameter	Result	Units	Reporting Limit
Benzene	19	ug/L	1.2
Toluene	63	ug/L	1.2
Ethylbenzene	12	ug/L	1.2
Xylenes (total)	240	ug/L	1.2
Surrogate	**Recovery**		
a,a,a-Trifluorotoluene	112	%	

ND = Not detected
NA = Not applicable

Reported By: Steve Shurgot Approved By: Stan Dunlavy

Enseco
A Corning Company

Benzene, Toluene, Ethyl Benzene and Xylenes (BTEX)

Method 8020

Client Name: Northwest Pipeline Corporation
Client ID: TRIP BLANK
Lab ID: 024601-0003-TB
Matrix: AQUEOUS Sampled: Unknown Received: 19 AUG 92
Authorized: 19 AUG 92 Prepared: NA Analyzed: 24 AUG 92

Parameter	Result	Units	Reporting Limit
Benzene	ND	ug/L	0.50
Toluene	ND	ug/L	0.50
Ethylbenzene	ND	ug/L	0.50
Xylenes (total)	ND	ug/L	0.50
Surrogate	**Recovery**		
a,a,a-Trifluorotoluene	106	%	

ND = Not detected
NA = Not applicable

Reported By: Steve Shurgot Approved By: Stan Dunlavy

Enseco
A Corning Company

Metals

Total Metals

Client Name: Northwest Pipeline Corporation
Client ID: CEDAR HILL CDP WASTE WATER TANK
Lab ID: 024601-0001-SA
Matrix: AQUEOUS Sampled: 18 AUG 92 Received: 19 AUG 92
Authorized: 19 AUG 92 Prepared: See Below Analyzed: See Below

Parameter	Result	Units	Reporting Limit	Analytical Method	Prepared Date	Analyzed Date	
Arsenic	ND	mg/L	0.0050	7060	10 SEP 92	12 SEP 92	
Barium	0.11	mg/L	0.010	6010	10 SEP 92	15 SEP 92	
Cadmium	ND	mg/L	0.0050	6010	10 SEP 92	15 SEP 92	B
Chromium	0.15	mg/L	0.010	6010	10 SEP 92	15 SEP 92	
Lead	0.020	mg/L	0.010	7421	10 SEP 92	11 SEP 92	
Mercury	ND	mg/L	0.00020	7470	13 SEP 92	13 SEP 92	

Note B : Compound is also detected in the blank.

ND = Not detected
NA = Not applicable

Reported By: Jeff Malecha Approved By: Sandra Jones

Enseco
A Corning Company

Metals

Total Metals

Client Name: Northwest Pipeline Corporation
Client ID: WASTE OIL TANK CEDAR HILL
Lab ID: 024601-0002-SA
Matrix: WASTE Sampled: 18 AUG 92 Received: 19 AUG 92
Authorized: 19 AUG 92 Prepared: See Below Analyzed: See Below

Parameter	Result	Units	Reporting Limit	Analytical Method	Prepared Date	Analyzed Date
Arsenic	ND	mg/kg	1.0	7060	14 SEP 92	16 SEP 92
Cadmium	ND	mg/kg	0.50	6010	14 SEP 92	15 SEP 92
Chromium	1.0	mg/kg	1.0	6010	14 SEP 92	15 SEP 92
Lead	2.8	mg/kg	2.2	7421	14 SEP 92	14 SEP 92

ND = Not detected
NA = Not applicable

Reported By: Bob Reilly Approved By: Sandra Jones

General Inorganics

Client Name: Northwest Pipeline Corporation
Client ID: CEDAR HILL CDP WASTE WATER TANK
Lab ID: 024601-0001-SA
Matrix: AQUEOUS Sampled: 18 AUG 92 Received: 19 AUG 92
Authorized: 19 AUG 92 Prepared: See Below Analyzed: See Below

Parameter	Result	Units	Reporting Limit	Analytical Method	Prepared Date	Analyzed Date
pH	4.9	units	--	9040	NA	19 AUG 92
Total Organic Halogen as Cl	71.4	ug/L	30.0	9020	NA	10 SEP 92
Total Dissolved Solids	498	mg/L	10.0	160.1	NA	25 AUG 92

ND = Not detected
NA = Not applicable

Reported By: Pam Rosas Approved By: Steve Shurgot

General Inorganics

Client Name: Northwest Pipeline Corporation
Client ID: WASTE OIL TANK CEDAR HILL
Lab ID: 024601-0002-SA
Matrix: WASTE Sampled: 18 AUG 92 Received: 19 AUG 92
Authorized: 19 AUG 92 Prepared: See Below Analyzed: See Below

Parameter	Result	Units	Reporting Limit	Analytical Method	Prepared Date	Analyzed Date
Ignitability	>160	deg. F	--	1010	NA	03 SEP 92 o
Total Organic Halogen as Cl	ND	mg/kg	3.0	9020	NA	15 SEP 92

Note o : This test is unreliable for any sample other than a non-aqueous liquid.

ND = Not detected
NA = Not applicable

Reported By: Leslie Gergurich Approved By: Steve Shurgot

Quality Control Report

The Enseco laboratories operate under a vigorous QA/QC program designed to ensure the generation of scientifically valid, legally defensible data by monitoring every aspect of laboratory operations. Routine QA/QC procedures include the use of approved methodologies, independent verification of analytical standards, use of Duplicate Control Samples to assess the precision and accuracy of the methodology on a routine basis, and a rigorous system of data review.

In addition, the Enseco laboratories maintain a comprehensive set of certifications from both state and federal governmental agencies which require frequent analyses of blind audit samples. Enseco-Rocky Mountain Analytical Laboratory is certified by the EPA under the EPA/CLP program for Organic analyses, under the USATHAMA (U.S. Army) program, by the Army Corps of Engineers, and the states of Colorado, New Jersey, Utah, and Florida, among others.

The standard laboratory QC package is designed to:

1) establish a strong, cost-effective QC program that ensures the generation of scientifically valid, legally defensible data

2) assess the laboratory's performance of the analytical method using control limits generated with a well-defined matrix

3) establish clear-cut guidelines for acceptability of analytical data so that QC decisions can be made immediately at the bench, and

4) provide a standard set of reportables which assures the client of the quality of his data.

The Enseco QC program is based upon monitoring the precision and accuracy of an analytical method by analyzing a set of Duplicate Control Samples (DCS) at frequent, well-defined intervals. Each DCS is a well-characterized matrix which is spiked with target compounds at 5-100 times the reporting limit, depending upon the methodology being monitored. The purpose of the DCS is not to duplicate the sample matrix, but rather to provide an interference-free, homogeneous matrix from which to gather data to establish control limits. These limits are used to determine whether data generated by the laboratory on any given day is in control.

Control limits for accuracy (percent recovery) are based on the average, historical percent recovery +/- 3 standard deviation units. Control limits for precision (relative percent difference) range from 0 (identical duplicate DCS results) to the average, historical relative percent difference + 3 standard deviation units. These control limits are fairly narrow based on the consistency of the matrix being monitored and are updated on a quarterly basis.

For each batch of samples analyzed, an additional control measure is taken in the form of a Single Control Sample (SCS). The SCS consists of a control matrix that is spiked with either representative target compounds or surrogate compounds appropriate to the method being used. An SCS is prepared for each sample lot for which the DCS pair are not analyzed.

Accuracy for DCS and SCS is measured by Percent Recovery.

$$\% \text{ Recovery} = \frac{\text{Measured Concentration}}{\text{Actual Concentration}} \times 100$$

Precision for DCS is measured by Relative Percent Difference (RPD).

$$RPD = \frac{\left| \text{Measured Concentration DCS1} - \text{Measured Concentration DCS2} \right|}{(\text{Measured Concentration DCS1} + \text{Measured Concentration DCS2})/2} \times 100$$

All samples analyzed concurrently by the same test are assigned the same QC lot number. Projects which contain numerous samples, analyzed over several days, may have multiple QC lot numbers associated with each test. The QC information which follows includes a listing of the QC lot numbers associated with each of the samples reported, DCS and SCS (where applicable) recoveries from the QC lots associated with the samples, and control limits for these lots. The QC data is reported by test code, in the order that the tests are reported in the analytical results section of this report.

Enseco
A Corning Company

QC LOT ASSIGNMENT REPORT
Organics by Chromatography

Laboratory Sample Number	QC Matrix	QC Category	QC Lot Number (DCS)	QC Run Number (SCS/BLANK)
024601-0001-SA	AQUEOUS	602-A	18 AUG 92-1H	22 AUG 92-1H
024601-0003-TB	AQUEOUS	602-A	18 AUG 92-1H	24 AUG 92-1H

Enseco
A Corning Company

DUPLICATE CONTROL SAMPLE REPORT
Organics by Chromatography

Analyte	Concentration Spiked	Measured DCS1	Measured DCS2	AVG	Accuracy Average(%) DCS	Accuracy Limits	Precision (RPD) DCS	Precision Limit
Category: 602-A								
Matrix: AQUEOUS								
QC Lot: 18 AUG 92-1H								
Concentration Units: ug/L								
Benzene	5.0	5.28	5.29	5.28	106	72-112	0.2	10
Toluene	5.0	4.99	5.01	5.00	100	74-109	0.4	10
Ethylbenzene	5.0	4.85	4.89	4.87	97	76-105	0.8	10
Xylenes (total)	5.0	4.82	4.88	4.85	97	74-111	1.2	10
1,3-Dichlorobenzene	5.0	4.83	4.94	4.88	98	72-121	2.3	15

Calculations are performed before rounding to avoid round-off errors in calculated results.

Enseco
A Corning Company

SINGLE CONTROL SAMPLE REPORT
Organics by Chromatography

Analyte	Concentration Spiked	Measured	Accuracy(%) SCS	Limits
Category: 602-A Matrix: AQUEOUS QC Lot: 18 AUG 92-1H QC Run: 22 AUG 92-1H Concentration Units: ug/L				
a,a,a-Trifluorotoluene	30.0	31.2	104	90-113
Category: 602-A Matrix: AQUEOUS QC Lot: 18 AUG 92-1H QC Run: 24 AUG 92-1H Concentration Units: ug/L				
a,a,a-Trifluorotoluene	30.0	30.9	103	90-113

Calculations are performed before rounding to avoid round-off errors in calculated results.

Enseco
A Corning Company

METHOD BLANK REPORT
Organics by Chromatography

Analyte	Result	Units	Reporting Limit
Test: 8020-BTEX-AP Matrix: AQUEOUS QC Lot: 18 AUG 92-1H QC Run: 22 AUG 92-1H			
Benzene	ND	ug/L	0.50
Toluene	ND	ug/L	0.50
Ethylbenzene	ND	ug/L	0.50
Xylenes (total)	ND	ug/L	0.50
Test: 8020-BTEX-AP Matrix: AQUEOUS QC Lot: 18 AUG 92-1H QC Run: 24 AUG 92-1H			
Benzene	ND	ug/L	0.50
Toluene	ND	ug/L	0.50
Ethylbenzene	ND	ug/L	0.50
Xylenes (total)	ND	ug/L	0.50

Enseco
A Corning Company

QC LOT ASSIGNMENT REPORT
Metals Analysis and Preparation

Laboratory Sample Number	QC Matrix	QC Category	QC Lot Number (DCS)	QC Run Number (SCS/BLANK)
024601-0001-SA	AQUEOUS	ICP-AT	10 SEP 92-1A	10 SEP 92-1A
024601-0001-SA	AQUEOUS	AS-FAA-AT	10 SEP 92-1A	10 SEP 92-1A
024601-0001-SA	AQUEOUS	PB-FAA-AT	10 SEP 92-1A	10 SEP 92-1A
024601-0001-SA	AQUEOUS	HG-CVAA-AT	13 SEP 92-1A	13 SEP 92-1A
024601-0002-SA	SOIL	AS-FAA-S	11 SEP 92-1A	11 SEP 92-1A
024601-0002-SA	SOIL	ICP-S	14 SEP 92-1R	14 SEP 92-1R
024601-0002-SA	SOIL	PB-FAA-S	14 SEP 92-1R	14 SEP 92-1R

Enseco
A Corning Company

DUPLICATE CONTROL SAMPLE REPORT
Metals Analysis and Preparation

Analyte	Concentration Spiked	Measured DCS1	Measured DCS2	Measured AVG	Accuracy Average(%) DCS	Accuracy Limits	Precision (RPD) DCS	Precision Limit
Category: ICP-AT Matrix: AQUEOUS QC Lot: 10 SEP 92-1A Concentration Units: mg/L								
Aluminum	2.0	2.03	2.04	2.03	102	75-125	0.2	20
Antimony	0.5	0.510	0.499	0.505	101	75-125	2.2	20
Arsenic	0.5	0.480	0.453	0.467	93	75-125	5.7	20
Barium	2.0	1.92	1.93	1.92	96	75-125	0.4	20
Beryllium	0.05	0.0500	0.0497	0.0498	100	75-125	0.6	20
Cadmium	0.05	0.0468	0.0442	0.0455	91	75-125	5.7	20
Calcium	100	103	102	103	103	75-125	1.0	20
Chromium	0.2	0.190	0.195	0.192	96	75-125	2.6	20
Cobalt	0.5	0.471	0.467	0.469	94	75-125	0.9	20
Copper	0.25	0.281	0.269	0.275	110	75-125	4.4	20
Iron	1.0	1.01	1.00	1.01	101	75-125	1.0	20
Lead	0.5	0.472	0.475	0.473	95	75-125	0.7	20
Magnesium	50	51.1	50.6	50.8	102	75-125	1.0	20
Manganese	0.5	0.489	0.477	0.483	97	75-125	2.5	20
Nickel	0.5	0.483	0.478	0.480	96	75-125	1.1	20
Potassium	50	52.5	51.9	52.2	104	75-125	1.2	20
Silver	0.05	0.0488	0.0477	0.0483	97	75-125	2.2	20
Sodium	100	110	109	109	109	75-125	1.6	20
Vanadium	0.5	0.495	0.497	0.496	99	75-125	0.4	20
Zinc	0.5	0.496	0.489	0.492	98	75-125	1.6	20
Category: AS-FAA-AT Matrix: AQUEOUS QC Lot: 10 SEP 92-1A Concentration Units: mg/L								
Arsenic	0.03	0.0329	0.0348	0.0338	113	75-125	5.6	20
Category: PB-FAA-AT Matrix: AQUEOUS QC Lot: 10 SEP 92-1A Concentration Units: mg/L								
Lead	0.03	0.0349	0.0313	0.0331	110	75-125	11	20

Calculations are performed before rounding to avoid round-off errors in calculated results.

DUPLICATE CONTROL SAMPLE REPORT
Metals Analysis and Preparation (cont.)

Analyte	Concentration Spiked	Measured DCS1	Measured DCS2	Measured AVG	Accuracy Average(%) DCS	Accuracy Limits	Precision (RPD) DCS	Precision Limit
Category: HG-CVAA-AT Matrix: AQUEOUS QC Lot: 13 SEP 92-1A Concentration Units: mg/L								
Mercury	0.0010	0.000967	0.00100	0.000983	98	75-125	3.4	20
Category: AS-FAA-S Matrix: SOIL QC Lot: 11 SEP 92-1A Concentration Units: mg/kg								
Arsenic	145	102	104	103	71	59-141	1.0	20
Category: ICP-S Matrix: SOIL QC Lot: 14 SEP 92-1R Concentration Units: mg/kg								
Aluminum	10700	6840	7480	7160	67	47-153	8.8	20
Antimony	55.2	54.8	57.4	56.1	102	18-362	4.6	50
Arsenic	145	128	135	131	91	59-141	4.9	20
Barium	503	435	459	447	89	76-124	5.5	20
Beryllium	129	118	124	121	94	53-131	4.9	20
Cadmium	154	140	147	144	93	68-132	4.6	20
Calcium	7390	6600	6960	6780	92	79-121	5.4	20
Chromium	151	127	136	132	87	66-133	6.9	20
Cobalt	122	110	116	113	93	70-130	5.4	20
Copper	162	156	165	161	99	70-132	5.4	20
Iron	15400	12400	13400	12900	84	66-134	7.2	20
Lead	148	129	139	134	90	66-135	6.9	20
Magnesium	3740	3250	3480	3360	90	74-126	7.0	20
Manganese	423	376	397	387	91	74-125	5.5	20
Molybdenum	159	145	152	148	93	71-129	5.1	20
Nickel	166	154	162	158	95	67-133	5.1	20
Potassium	4050	3530	3770	3650	90	68-132	6.6	20
Silver	104	98.2	106	102	98	76-124	7.6	20
Sodium	747	717	766	741	99	57-130	6.6	20
Vanadium	154	135	142	138	90	73-127	5.2	20
Zinc	530	478	504	491	93	65-135	5.3	20

Calculations are performed before rounding to avoid round-off errors in calculated results.

Enseco
A Corning Company

DUPLICATE CONTROL SAMPLE REPORT
Metals Analysis and Preparation (cont.)

Analyte	Concentration Spiked	Measured DCS1	Measured DCS2	Measured AVG	Accuracy Average(%) DCS	Accuracy Limits	Precision (RPD) DCS	Precision Limit
Category: PB-FAA-S Matrix: SOIL QC Lot: 14 SEP 92-1R Concentration Units: mg/kg								
Lead	150	132	148	140	93	50-150	11	20

Calculations are performed before rounding to avoid round-off errors in calculated results.

Enseco
A Corning Company

METHOD BLANK REPORT
Metals Analysis and Preparation

Analyte	Result	Units	Reporting Limit
Test: ICP-AT			
Matrix: AQUEOUS			
QC Lot: 10 SEP 92-1A QC Run: 10 SEP 92-1A			
Barium	ND	mg/L	0.010
Cadmium	0.0099	mg/L	0.0050
Chromium	ND	mg/L	0.010
Test: AS-FAA-AT			
Matrix: AQUEOUS			
QC Lot: 10 SEP 92-1A QC Run: 10 SEP 92-1A			
Arsenic	ND	mg/L	0.0050
Test: PB-FAA-AT			
Matrix: AQUEOUS			
QC Lot: 10 SEP 92-1A QC Run: 10 SEP 92-1A			
Lead	ND	mg/L	0.0050
Test: HG-CVAA-AT			
Matrix: AQUEOUS			
QC Lot: 13 SEP 92-1A QC Run: 13 SEP 92-1A			
Mercury	ND	mg/L	0.00020
Test: AS-FAA-W			
Matrix: WASTE			
QC Lot: 11 SEP 92-1A QC Run: 11 SEP 92-1A			
Arsenic	ND	mg/kg	0.50
Test: ICP-W			
Matrix: WASTE			
QC Lot: 14 SEP 92-1R QC Run: 14 SEP 92-1R			
Cadmium	ND	mg/kg	0.50
Chromium	ND	mg/kg	1.0

METHOD BLANK REPORT
Metals Analysis and Preparation (cont.)

Analyte	Result	Units	Reporting Limit
Test: PB-FAA-W			
Matrix: WASTE			
QC Lot: 14 SEP 92-1R QC Run: 14 SEP 92-1R			
Lead	ND	mg/kg	0.50

Enseco
A Corning Company

QC LOT ASSIGNMENT REPORT
Wet Chemistry Analysis and Preparation

Laboratory Sample Number	QC Matrix	QC Category	QC Lot Number (DCS)	QC Run Number (SCS/BLANK)
024601-0001-SA	AQUEOUS	PH-A	19 AUG 92-1G	-
024601-0001-SA	AQUEOUS	TDS-A	25 AUG 92-1A	25 AUG 92-1A
024601-0001-SA	AQUEOUS	TOX-A	10 SEP 92-1A	-
024601-0002-SA	SOIL	TOX-S	15 SEP 92-1A	-

Enseco
A Coming Company

DUPLICATE CONTROL SAMPLE REPORT
Wet Chemistry Analysis and Preparation

Analyte	Concentration Spiked	Measured DCS1	Measured DCS2	AVG	Accuracy Average(%) DCS	Accuracy Limits	Precision (RPD) DCS	Precision Limit
Category: PH-A Matrix: AQUEOUS QC Lot: 19 AUG 92-1G Concentration Units: units								
pH	9.1	9.04	9.05	9.04	99	98-102	0.1	5
Category: TDS-A Matrix: AQUEOUS QC Lot: 25 AUG 92-1A Concentration Units: mg/L								
Total Dissolved Solids	1170	1150	1130	1140	97	90-110	1.8	10
Category: TOX-A Matrix: AQUEOUS QC Lot: 10 SEP 92-1A Concentration Units: ug Cl/L								
Total Organic Halogen as Cl	100	90.0	90.6	90.3	90	80-120	0.7	20
Category: TOX-S Matrix: SOIL QC Lot: 15 SEP 92-1A Concentration Units: mg/kg								
Total Organic Halogen as Cl	1.0	0.955	1.05	1.00	100	75-125	9.5	20

Calculations are performed before rounding to avoid round-off errors in calculated results.

Enseco
A Corning Company

METHOD BLANK REPORT
Wet Chemistry Analysis and Preparation

Analyte	Result	Units	Reporting Limit
Test: TDS-BAL-A			
Matrix: AQUEOUS			
QC Lot: 25 AUG 92-1A QC Run: 25 AUG 92-1A			
Total Dissolved Solids	ND	mg/L	10.0

Appendix

Enseco
A Corning Company

Rocky Mountain Analytical Laboratory
4955 Yarrow Street
Arvada, CO 80002
303/421-6611 FAX: 303/431-7171

CHAIN OF CUSTODY

ENSECO CLIENT		SAMPLE SAFE™ CONDITIONS	
		PACKED BY	SEAL NUMBER
PROJECT		SEAL INTACT UPON RECEIPT BY SAMPLING COMPANY	CONDITION OF CONTENTS
SAMPLING COMPANY		SEALED FOR SHIPPING BY	INITIAL CONTENTS TEMP. °C
SAMPLING SITE		SEAL NUMBER	SAMPLING STATUS ☐ Done ☐ Continuing Until
TEAM LEADER		SEAL INTACT UPON RECEIPT BY LAB. ☐ Yes ☐ No	CONTENTS TEMPERATURE UPON RECEIPT BY LAB. JM °C

DATE	TIME	SAMPLE ID/DESCRIPTION	SAMPLE TYPE	# CONTAINERS	ANALYSIS PARAMETERS	REMARKS
8-18-92	12:49	CEDAR HILL CDP WATER TANK WASTE	LIQUID AQUEOUS	1	PH / TDS	01
8-18-92	12:50	" "	LIQUID AQUEOUS	1	PH / TDS	02
8-18-92	12:45	" "	LIQUID ~~METALS~~	4T	METALS	01 01
8-18-92	12:47	" "	LIQUID ~~METALS~~	4T	METALS	02
8-18-92	12:40	" "	LIQUID	15	TOX -- SINGLE	01
8-18-92	12:40	" "	LIQUID	15	TOX -- SINGLE	02
8-18-92	11:30	WASTE OIL TANK CEDAR HILL	USED OIL			
8-18-92	11:45	WASTE OIL TANK CEDAR HILL	USED OIL			02
8-18-92	11:50	WASTE OIL TANK CEDAR HILL	USED OIL			
8-18-92	12:00	WASTE OIL TANK CEDAR HILL	USED OIL			

CUSTODY TRANSFERS PRIOR TO SHIPPING

RELINQUISHED BY (SIGNED)	RECEIVED BY (SIGNED)	DATE	TIME
Vern Rothhaupt	Frank Gallegos	8/18/92	2:07

SHIPPING DETAILS

DELIVERED TO SHIPPER BY

METHOD OF SHIPMENT | AIRBILL NUMBER

RECEIVED FOR LAB: RMM | SIGNED | DATE/TIME: 0845 8/19/92

ENSECO PROJECT NUMBER: 24601

ENS—1133

White – CLIENT Pink – LAB

Enseco
A Corning Company

Rocky Mountain Analytical Laboratory
4955 Yarrow Street
Arvada, CO 80002
303/421-6611 FAX: 303/431-7171

CHAIN OF CUSTODY

ENSECO CLIENT		SAMPLE SAFE™ CONDITIONS	
		PACKED BY	SEAL NUMBER
PROJECT		SEAL INTACT UPON RECEIPT BY SAMPLING COMPANY	CONDITION OF CONTENTS
SAMPLING COMPANY		SEALED FOR SHIPPING BY	INITIAL CONTENTS TEMP. °C
SAMPLING SITE		SEAL NUMBER	SAMPLING STATUS ☐ Done ☐ Continuing Until
TEAM LEADER		SEAL INTACT UPON RECEIPT BY LAB. ☐ Yes ☐ No	CONTENTS TEMPERATURE UPON RECEIPT BY LAB. °C

DATE	TIME	SAMPLE ID/DESCRIPTION	SAMPLE TYPE	# CONTAINERS	ANALYSIS PARAMETERS	REMARKS
8-18-92	12:51	CEDAR HILL COP WASTE WATER	LIQUIDS AQUEOUS	11	VOA	> 01
8-18-92	12:53	" "	LIQUIDS AQUEOUS	11	VOA	
8-18-92	12:55	" "	LIQUIDS AQUEOUS	11	VOA	

CUSTODY TRANSFERS PRIOR TO SHIPPING

RELINQUISHED BY (SIGNED)	RECEIVED BY (SIGNED)	DATE	TIME

SHIPPING DETAILS

DELIVERED TO SHIPPER BY

METHOD OF SHIPMENT | AIRBILL NUMBER

RECEIVED FOR LAB: FINAL | SIGNED | DATE/TIME: 8/19/92 0845

ENSECO PROJECT NUMBER: 24601

ENS—1133

White – CLIENT Pink – LAB

APPENDIX B

SPILL CONTROL PROCEDURES

A. PURPOSE AND SCOPE

A.1 To establish the policy and procedure for preventing, controlling, and reporting of spills or discharges of oil or hazardous substances to the environment in accordance with Company practices and federal, state, and local requirements, including Title 40 of the Code of Federal Regulations - Part 112 (Oil Pollution Prevention).

A.2 This document pertains to Company personnel and Company and non-company facilities. The spill prevention and control requirements in this Policy and Procedure are Federally mandated guidelines for oil pollution prevention. The Company policy is to also apply these standards, where appropriate, to facilities containing hazardous substances. This is a discretionary applicaton of the standards; however, variations from the standards should be approved by the responsible Director.

B. CONTENTS

C. POLICY

C.1 GENERAL

C.1.1 All Company facilities which could discharge or spill oil or hazardous substances which may affect natural resources or present an imminent and substantial danger to the public health or welfare including, but not limited to fish, shellfish, wildlife, shorelines, and beaches are subject to the provisions of this document.

C.1.2 Hazardous Substance, for purposes of this procedure, is defined as any chemical or material that has or should have a Material Safety Data Sheet (MSDS); however, hazardous substances are further defined by the following environmental statutes:

a. Section 101 (N) and Section 102 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)

b. Section 307(a) and Section 311 (b)(2)(A) of the Clean Water Act

c. Section 3001 of the Solid Waste Act (excluding items suspended by Congress)

d. Section 112 of the Clean Air Act

e. Section 7 of the Toxic Substance Control Act

Supersedes Policy and Procedure 12.10.020 dated July 7, 1989.

C.1.3 The term hazardous substance does not include petroleum, including crude oil or any fraction thereof, which is not otherwise specifically listed or designated as a hazardous substance in the first sentence of this paragraph, and the term does not include natural gas, natural gas liquids, liquefied natural gas or synthetic gas usable for fuel (or mixtures of natural gas and such synthetic gas).

C.1.4 Oil, for the purpose of this document, means oil of any kind or in any form, including but not limited to petroleum, fuel oil, Y grade, mixed products, sludge, oil refuse, and oil mixed with wastes other than dredged spoil (earth and rock). LPG (propane, butane, ethane) are not considered to be oil.

C.1.5 Facilities which could discharge or spill oil or hazardous substances into a watercourse must comply with the required federal, state, or local laws and regulations. A discharge includes but is not limited to any spilling, leaking, pumping, pouring, emitting, emptying, or dumping. A watercourse is any perennial or intermittent river, stream, gully, wash, lake, or standing body of water capable of collecting or transporting an oil or hazardous substance.

C.1.6 Facilities which are subject to the requirements stated in this policy are as follows:

a. Non-Transportation Related Facilities

(1) Storage or drip tanks and other aboveground containers (excluding pressurized or inline process vessels) having a capacity in excess of 660 gallons for each single container or an aggregate capacity of 1,321 gallons or more for multiple containers.

(2) Underground storage facilities having a total capacity in excess of 42,000 gallons.

b. Transportation Related Facilities

(1) All vehicles, pipeline facilities, loading/unloading facilities, and other mobile facilities which transport oil or hazardous substances.

C.1.7 Each Company location which has facilities subject to paragraph C.1.1 shall have a site specific Spill Prevention Control and Countermeasure Plan (SPCC Plan) which identifies all facilities subject to 40 CFR 112. The plan shall identify all hazardous substance storage vessels at the facility and the spill prevention measures in place to control discharges or spills. This plan shall also identify all regulatory agencys that must be notified in case of a spill.

C.1.8 The facility supervisor is responsible for spill prevention. His/her duties include, but are not limited to, the following:

a. Instructing personnel in the operation and maintenance of equipment to prevent the discharge of oil.
b. Conduct briefings for operating personnel at intervals frequent enough to assure adequate understanding of the Spill Plan at that facility.
c. Briefings should highlight and describe known discharges or spills, and recently developed precautionary measures.

C.1.9 Each individual facility is checked by the supervisor or designee to determine the potential for discharges or spills of oil or hazardous substances in harmful quantities that violate water quality standards or which may cause a film, sheen, or discoloration on the surface of water. All facilities which have the potential for discharging or spilling harmful quantities of oil or hazardous substances into a watercourse are required to have the following preventive measures:

a. Examination of all tanks, valves and fittings, at least annually, to determine any maintenance requirements.

b. All tank batteries should, as far as practicable, have a secondary means of containment for the entire contents of the largest single tank plus sufficient freeboard in the containment facility to allow for precipitation.
c. A annual monitoring and inspection program to prevent accidental spills or discharges into watercourses. This includes annual inspection for faulty systems and monitoring line valves and liquid pipelines for leaks or blowouts.

C.1.10 Any field drainage ditches, road ditches, traps, sumps, or skimmers should be inspected at annual scheduled intervals for accumulation of liquid hydrocarbons or other hazardous substances which may have escaped from small leaks. Any such accumulations should be removed.

C.2 BULK STORAGE TANKS

C.2.1 A tank should not be used for storage of oil or hazardous substances unless the material and construction of the tank is compatible with the material stored and conditions of storage such as pressure and temperature. Buried storage tanks must be protected from corrosion by coatings, cathodic protection, or other methods compatible with local soil conditions. Aboveground tanks should be subject to visual inspection for system integrity.

C.2.2 The facility supervisor should evaluate level monitoring requirements to prevent tank overflow.

C.2.3 Leaks which result in loss of oil or hazardous substances from tank seams, gaskets, rivets and bolts sufficiently large to cause accumulation of oil or hazardous substances in diked areas should be promptly corrected.

C.2.4 Mobile or portable oil or hazardous substances storage tanks should be positioned or located to prevent the contents from reaching a watercourse. The mobile facilities should be located so their support structure will not be undermined by periodic flooding or washout.

C.3 FACILITY DRAINAGE

C.3.1 Make provisions for drainage from diked storage areas where necessary in areas with high precipitation levels. Drainage from dike areas should be restrained by valves or other means to prevent a discharge or spill. Diked areas should be emptied by pumps or ejectors which are manually activated. Valves used for the drainage of diked areas should be of manual, open-and-closed design.

C.3.2 Rain water may be drained from diked areas providing drainage water does not contain oil or hazardous substances that may cause a harmful discharge. Drain valves must be closed following drainage of diked areas.

C.3.3 When possible, drainage systems from undiked areas should flow into ponds, lagoons, or catchment basins designed to retain oil or hazardous substances or return the substances to the facility. Any drainage system which is not designed to allow flow into ponds, lagoons, or catchment basins should be equipped with a diversion system that could, in the event of a discharge or spill, contain the oil or hazardous substances on the Site.

C.3.4 The principal means of containing discharges or spills is the use of dikes which are constructed wherever regulated quantities of oil or hazardous substances have the potential of reaching a watercourse. The construction of dikes must meet the following requirements:

a. Capacity must be at least equivalent to the storage capacity of the largest tank of the battery plus sufficient freeboard to allow for pecipitation, or displacement by foreign materials.
b. Small dikes for temporary containment are constructed at valves where potential leaking of oil or hazardous substances may occur.

c. Any dike three feet or higher should have a minimum cross section of two feet at the top.

C.3.5 Other means of containment or spill control include, but are not limited to:

a. Berms or retaining walls;
b. Curbing;
c. Culverting, gutters, or other drainage systems;
d. Weirs, booms, or other barriers;
e. Spill diversion ponds or retention ponds;
f. Sorbent materials

C.4 TRANSFER OPERATIONS, PUMPING, AND IN-PLANT/STATION PROCESS

C.4.1 Aboveground valves and pipelines should be examined annually by operating personnel to determine whether there are any leaks from flange joints, expansion joints, valve glands and bodies, catch pans, pipeline supports, valve locks, and metal surfaces.

C.5 FACILITY TANK CAR AND TANK TRUCK LOADING/UNLOADING RACK

C.5.1 Rack area drainage which does not flow into a catchment basin or treatment facility designed to handle spills should have a quick drainage system for use in tank truck loading and unloading areas. The containment system should have a maximum capacity of any single compartment of a truck loaded or unloaded in the station.

C.5.2 Aboveground piping that has potential for damage by vehicles entering the Site should be protected by logically placed warning signs or by concrete-filled pipe barriers.

C.5.3 Loading and unloading areas should be provided with an interlocked warning light, grounding shutdown, physical barrier system, or warning signs to prevent vehicular departure before complete disconnect of flexible or fixed transfer lines. All drains and outlets of any truck should be closely examined for leakage prior to filling and departure. All drains and outlets which may allow leakage should be tightened, adjusted, or replaced to prevent liquid leakage while in transit.

NOTE: LPG loading facilities and remote field loading of condensate are exempt from the C.5 requirements of this document.

D. PROCEDURE

D.1 IDENTIFYING, CONTAINING AND INITIAL REPORTING OF A DISCHARGE OR SPILL OF OIL OR HAZARDOUS SUBSTANCE

Any Employee

D.1.1 Upon noticing a discharge or spill of an oil or hazardous substance in any quantity initiates immediate containment procedures and notifies facility supervisor.

NOTE: Refer to Attachment A for containment procedures.

Facility Supervisor

D.1.2 Contacts Gas Control and responsible Director immediately by telephone and provides the following information:

a. Name of company facility and/or location of facility and nature of discharge or spill
b. Description and quantity of emission or substance discharged
c. Name, title, and telephone number of person initially reporting the discharge or spill and person reporting to Gas Control
d. Action taken or being taken to mitigate and correct discharge or spill
e. Water bodies or streams involved
f. Time and duration of discharge or spill
g. Outside involvement during discharge or spill (public government agencies, etc. See Emergency Operating Procedure Manuals)

Gas Control Personnel

D.1.3 Advises Environmental Services departments immediately by telephone concerning the incident including any incidents reported by persons not employed with the Company.

NOTE: If Gas Control is contacted by a person not employed with the Company, the necessary information is obtained as indicated in D.1.2 and the Supervisor and Environmental Services are immediately contacted to begin containment and clean-up of the discharge or spill.

D.1.4 If Environmental Services cannot be contacted, notifies Director over Environmental Services.

Facility Supervisor

D.1.5 Coordinates containment and clean-up of discharge or spill, keeping the responsible Director Informed.

D.1.6 If the discharge or spill is too large for Company personnel to contain, contacts qualified local contractors for assistance. (See Emergency Operating Procedure Manuals tab #11, contractors with available equipment and services).

D.1.7 Advises Environmental Services by telephone if emergency containment or clean-up assistance from a state agency or a response team from the U.S. Coast Guard is required.

Environmental Services

D.1.8 Contacts Legal Department (and Right-of-Way Department, if appropriate) and assesses reporting requirements to state and federal agencies. (See Emergency Operating Procedure Manuals).

D.1.9 Makes appropriate contacts with U.S. Coast Guard and state agencies when necessary.

D.1.10 If spill is significant, dispatches Environmental Specialist to scene to oversee cleanup and reporting responsibilities.

D.2 SUBMITTING WRITTEN NOTIFICATION OF A DISCHARGE OR SPILL

Facility Supervisor

D.2.1 Completes a written description of the incident as soon as possible after initial notification is given, which should include the following:

a. Time and date of discharge or spill
b. Facility name and location
c. Type of material spilled
d. Quantity of material spilled
e. Area affected
f. Cause of spill
g. Special circumstances
h. Corrective measures taken
i. Description of repairs made
j. Preventative measures taken to prevent recurrence.

D.2.2 Forwards the completed report to Environmental Services and a copy to Legal Department. Retains a copy for future reference.

NOTE: Environmental Services, in coordination with the Legal Department, submits written reports to government agencies.

ATTACHMENT A

Discharge or Spill Containment Procedures and Materials

Type of Facility where the Discharge or Spill occurs	Containment Procedures	Material Used for Containment
A. Oil Pipeline (as defined in C.1.4)	1. Closes appropriate block valves. 2. Contains discharge or spill by: ditching covering, applying sorbents, constructing an earthen dam, or burning. 3. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning.	1. Straw 2. Loose Earth 3. Oil Sorbent - 3M Brand 4. Plain Wood Chips 5. Sorb - Oil Chips Banta Co. 6. Sorb - Oil Swabs - Banta Co. 7. Sorb - Oil Mats - Banta Co. 8. Or Equivalent Materials.
B. Vehicle	1. Contains discharge or spill by: ditching, covering surface with dirt, constructing earthen dams, applying sorbents, or burning. 2. Notifies immediately the Compliance and Safety Department and if there is any imminent danger to local residents; notifies immediately the highway patrol or local police officials. 3. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning. NOTE: Any vehicle carrying any hazardous or toxic substance will carry a shovel or other ditching device to contain a spill. If the vehicle has sufficient room, sorbent materials should also be carried.	
c. Bulk Storage Tanks or any other Facilities	1. Contains discharge or spill by: ditching, covering, applying sorbents, constructing an earthen dam, or burning. 2. If burning is required, obtains approval from the appropriate state air quality control government agencies before burning.	

APPENDIX C

NMOCD NOTIFICATION OF FIRE, BREAKS, SPILLS, LEAKS, AND BLOWOUTS

DISTRICT I
P.O.Box 1980, Hobbs, NM 88241-1980
DISTRICT II
P.O. Drawer DD, Artesia, NM 88211-0719
DISTRICT III
1000 Rio Brazos Rd, Aztec, NM 87410

State of New Mexico
Energy, Minerals and Natural Resources Department

OIL CONSERVATION DIVISION
P.O. Box 2088
Santa Fe, New Mexico 87504-2088

SUBMIT 2 COPIES TO APPROPRIATE DISTRICT OFFICE IN ACCORDANCE WITH RULE 116 PRINTED ON BACK SIDE OF FORM

NOTIFICATION OF FIRE, BREAKS, SPILLS, LEAKS, AND BLOWOUTS

OPERATOR						ADDRESS	TELEPHONE #
REPORT OF	FIRE	BREAK	SPILL	LEAK		BLOWOUT	OTHER*
TYPE OF FACILITY	DRLG WELL	PROD WELL	TANK BTRY	PIPE LINE	GASO PLNT	OIL RFY	OTHER*
FACILITY NAME:							
LOCATION OF FACILITY Qtr/Qtr Sec. or Footage						SEC.	TWP. RGE. COUNTY
DISTANCE AND DIRECTION FROM NEAREST TOWN OR PROMINENT LANDMARK							
DATE AND HOUR OF OCCURRENCE						DATE AND HOUR OF DISCOVERY	
WAS IMMEDIATE NOTICE GIVEN?	YES	NO	NOT REQUIRED			IF YES, TO WHOM	
BY WHOM						DATE AND HOUR	
TYPE OF FLUID LOST						QUANTITY OF LOSS	VOLUME RECOVERED
DID ANY FLUIDS REACH A WATERCOURSE?	YES	NO	QUANTITY				
IF YES, DESCRIBE FULLY**							
DESCRIBE CAUSE OF PROBLEM AND REMEDIAL ACTION TAKEN**							
DESCRIBE AREA AFFECTED AND CLEANUP ACTION TAKEN**							
DESCRIPTION OF AREA	FARMING	GRAZING	URBAN	OTHER*			
SURFACE CONDITIONS	SANDY	SANDY LOAM	CLAY	ROCKY	WET	DRY	SNOW
DESCRIBE GENERAL CONDITIONS PREVAILING (TEMPERATURE, PRECIPITATION, ETC.)**							

I HEREBY CERTIFY THAT THE INFORMATION ABOVE IS TRUE AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF

SIGNED | PRINTED NAME AND TITLE | DATE

B. Plans, specifications and reports required by this Section, if related to facilities for the production, refinement and pipeline transmission of oil and gas, or products thereof, shall be filed instead with the Oil Conservation Division. [1-4-68, 12-1-95]

C. Plans and specifications required to be filed under this Section must be filed prior to the commencement of construction. [9-3-72]

1203. NOTIFICATION OF DISCHARGE--REMOVAL.

A. With respect to any discharge from any facility of oil or other water contaminant, in such quantity as may with reasonable probability injure or be detrimental to human health, animal or plant life, or property, or unreasonably interfere with the public welfare or the use of property, the following notifications and corrective actions are required: [2-17-74, 12-24-87]

1. As soon as possible after learning of such a discharge, but in no event more than twenty-four (24) hours thereafter, any person in charge of the facility shall orally notify the Chief of the Ground Water Protection and Remediation Bureau of the department, or his counterpart in any constituent agency delegated responsibility for enforcement of these rules as to any facility subject to such delegation. To the best of that person's knowledge, the following items of information shall be provided:

a. the name, address, and telephone number of the person or persons in charge of the facility, as well as of the owner and/or operator of the facility;

b. the name and address of the facility;

c. the date, time, location, and duration of the discharge;

d. the source and cause of discharge;

e. a description of the discharge, including its chemical composition;

f. the estimated volume of the discharge; and

g. any actions taken to mitigate immediate damage from the discharge.
[2-17-74, 2-20-81, 12-24-87, 12-1-95]

2. When in doubt as to which agency to notify, the

person in charge of the facility shall notify the Chief of the Ground Water Protection and Remediation Bureau of the department. If that department does not have authority pursuant to commission delegation, the department shall notify the appropriate constituent agency. [12-24-87, 12-1-95]

3. Within one week after the discharger has learned of the discharge, the facility owner and/or operator shall send written notification to the same department official, verifying the prior oral notification as to each of the foregoing items and providing any appropriate additions or corrections to the information contained in the prior oral notification. [12-24-87]

4. The oral and written notification and reporting requirements contained in this Subsection A are not intended to be duplicative of discharge notification and reporting requirements promulgated by the Oil Conservation Commission (OCC) or by the Oil Conservation Division (OCD); therefore, any facility which is subject to OCC or OCD discharge notification and reporting requirements need not additionally comply with the notification and reporting requirements herein. [2-17-74, 12-24-87]

5. As soon as possible after learning of such a discharge, the owner/operator of the facility shall take such corrective actions as are necessary or appropriate to contain and remove or mitigate the damage caused by the discharge. [2-17-74, 12-24-87]

6. If it is possible to do so without unduly delaying needed corrective actions, the facility owner/operator shall endeavor to contact and consult with the Chief of the Ground Water Protection and Remediation Bureau of the department or appropriate counterpart in a delegated agency, in an effort to determine the department's views as to what further corrective actions may be necessary or appropriate to the discharge in question. In any event, no later than fifteen (15) days after the discharger learns of the discharge, the facility owner/operator shall send to said Bureau Chief a written report describing any corrective actions taken and/or to be taken relative to the discharge. Upon a written request and for good cause shown, the Bureau Chief may extend the time limit beyond fifteen (15) days. [12-24-87, 12-1-95]

7. The Bureau Chief shall approve or disapprove in writing the foregoing corrective action report within thirty (30) days of its receipt by the department. In the event that the report is not satisfactory to the department, the Bureau Chief shall specify in writing to the facility owner/operator any shortcomings in the report or in the corrective actions already taken or proposed to be taken relative to the discharge, and shall give the facility owner/operator a reasonable and clearly specified

time within which to submit a modified corrective action report. The Bureau Chief shall approve or disapprove in writing the modified corrective action report within fifteen (15) days of its receipt by the department. [12-24-87]

8. In the event that the modified corrective action report also is unsatisfactory to the department, the facility owner/operator has five (5) days from the notification by the Bureau Chief that it is unsatisfactory to appeal to the department secretary. The department secretary shall approve or disapprove the modified corrective action report within five (5) days of receipt of the appeal from the Bureau Chief's decision. In the absence of either corrective action consistent with the approved corrective action report or with the decision of the secretary concerning the shortcomings of the modified corrective action report, the department may take whatever enforcement or legal action it deems necessary or appropriate. [12-24-87, 12-1-95]

9. If the secretary determines that the discharge causes or may with reasonable probability cause water pollution in excess of the standards and requirements of Section 4103 of this Part, and the water pollution will not be abated within one hundred and eighty (180) days after notice is required to be given pursuant to Section 1203.A.1 of this Part, the secretary may notify the facility owner/operator that he is a responsible person and that an abatement plan may be required pursuant to Sections 4104 and 4106.A of this Part. [12-1-95]

B. Exempt from the requirements of this Section are continuous or periodic discharges which are made: [2-17-74]

1. in conformance with regulations of the commission and rules, regulations or orders of other state or federal agencies; or [2-17-74]

2. in violation of regulations of the commission, but pursuant to an assurance of discontinuance or schedule of compliance approved by the commission or one of its duly authorized constituent agencies. [2-17-74]

C. As used in this Section and in Sections 4100 through 4115, but not in other Sections of this Part: [2-17-74, 12-1-95]

1. "discharge" means spilling, leaking, pumping, pouring, emitting, emptying, or dumping into water or in a location and manner where there is a reasonable probability that the discharged substance will reach surface or subsurface water; [2-17-74]

2. "facility" means any structure, installation, operation, storage tank, transmission line, motor vehicle, rolling

stock, or activity of any kind, whether stationary or mobile; [2-17-74]

3. "oil" means oil of any kind or in any form including petroleum, fuel oil, sludge, oil refuse and oil mixed with wastes; [2-17-74]

4. "operator" means the person or persons responsible for the overall operations of a facility; and [12-24-87]

5. "owner" means the person or persons who own a facility, or part of a facility. [12-24-87]

D. Notification of discharge received pursuant to this Part or information obtained by the exploitation of such notification shall not be used against any such person in any criminal case, except for perjury or for giving a false statement. [2-17-74]

E. Any person who has any information relating to any discharge from any facility of oil or other water contaminant, in such quantity as may with reasonable probability injure or be detrimental to human health, animal or plant life, or property, or unreasonably interfere with the public welfare or the use of property, is urged to notify the Chief of the Ground Water Protection and Remediation Bureau of the department. Upon such notification, the secretary may require an owner/operator or responsible person to perform corrective actions pursuant to Sections 1203.A.5 or 1203.A.9 of this Part. [12-1-95]

[1204-1209] Reserved

1210. VARIANCE PETITIONS.

A. Any person seeking a variance pursuant to Section 74-6-4 (G) NMSA 1978, shall do so by filing a written petition with the commission. The petitioner may submit with his petition any relevant documents or material which the petitioner believes would support his petition. Petitions shall: [7-19-68, 11-27-70, 9-3-72]

1. state the petitioner's name and address; [7-19-68, 11-27-70]

2. state the date of the petition; [7-19-68]

3. describe the facility or activity for which the variance is sought; [7-19-68, 11-27-70]

4. state the address or description of the property upon which the facility is located; [11-27-70]

APPENDIX D

WELL SEARCH

Revised June 1972

'78 JUL 12 PM 1 26

STATE ENGINEER OFFICE

WELL RECORD

STATE ENGINEER OFFICE
SANTA FE, N.M. 87501

Mark C

Section 1. GENERAL INFORMATION

(A) Owner of well Marshall J. D. Johnson Owner's Well No. 1
Street or Post Office Address Rt. 1 Box 19-C
City and State Aztec, N.M. 87410

Well was drilled under Permit No. SJ 498 and is located in the:

a. ¼ ¼ ¼ ¼ of Section 4 Township 31N Range 10 W N.M.P.M.

b. Tract No. _____ of Map No. _____ of the _____

c. Lot No. _____ of Block No. _____ of the _____
Subdivision, recorded in _____ County.

d. X= _____ feet, Y= _____ feet, N.M. Coordinate System _____ Zone in the _____ Grant.

(B) Drilling Contractor Johnson Enterprises License No. WD 697

Address P O Box 192, Aztec, N.M. 87410

Drilling Began 7-1-78 Completed 7-5-78 Type tools cable Size of hole 6 5/8 in.

Elevation of land surface or _____ at well is _____ ft. Total depth of well 26 ft.

Completed well is ☒ shallow ☐ artesian. Depth to water upon completion of well 8 ft.

Section 2. PRINCIPAL WATER-BEARING STRATA

Depth in Feet From	Depth in Feet To	Thickness in Feet	Description of Water-Bearing Formation	Estimated Yield (gallons per minute)
11	25	14	sand	45

Section 3. RECORD OF CASING

Diameter (inches)	Pounds per foot	Threads per in.	Depth in Feet Top	Depth in Feet Bottom	Length (feet)	Type of Shoe	Perforations From	Perforations To
6 5/8	12.92		0	26'6"	26'6"	steel weld on	13	25

Section 4. RECORD OF MUDDING AND CEMENTING

Depth in Feet From	Depth in Feet To	Hole Diameter	Sacks of Mud	Cubic Feet of Cement	Method of Placement

78 JUL 17 AM 8:21
STATE ENGINEER OFFICE
DISTRICT II
ALBUQUERQUE, N. MEX.

Section 5. PLUGGING RECORD

Plugging Contractor _____
Address _____
Plugging Method _____
Date Well Plugged _____
Plugging approved by: _____
State Engineer Representative

No.	Depth in Feet Top	Depth in Feet Bottom	Cubic Feet of Cement
1			
2			
3			
4			

FOR USE OF STATE ENGINEER ONLY

Date Received 7/12/78

Quad _____ FWL _____ FSL _____

File No. SJ-498 Use Dom. Location No. 31N.10W.4 120

Section 6. LOG OF HOLE

Depth in Feet From	Depth in Feet To	Thickness in Feet	Color and Type of Material Encountered
0	4	4	mud clay
4	11	7	clay and boulders
11	25	14	sand
25	26	1	sand stone

Section 7. REMARKS AND ADDITIONAL INFORMATION

The undersigned hereby certifies that, to the best of his knowledge and belief, the foregoing is a true and correct record of the above described hole.

Pamela M Madson
Driller

INSTRUCTIONS: This form should be executed in triplicate, preferably typewritten, and submitted to the appropriate district office of the State Engineer. All sections, except Section 5, shall be answered as completely and accurately as possible when any well is

Revised June 1968

Trunk C

STATE ENGINEER OFFICE

WELL RECORD

Section 1. GENERAL INFORMATION

1978 MAY 8 PM 12:50
STATE ENGINEER OFFICE
SANTA FE, N.M.

(A) Owner of well Joseph & Margaret Morrison Owner's Well No. 1
Street or Post Office Address 4004 Wilshire Drive
City and State Farmington, N.M. 87401

Well was drilled under Permit No. SJ-573 and is located in the:

a. SE ¼ NW ¼ ¼ ¼ ¼ of Section 4 Township 31N Range 10W N.M.P.M.

b. Tract No. _____ of Map No. _____ of the _____

c. Lot No. _____ of Block No. _____ of the _____
Subdivision, recorded in San Juan County.

d. X= _____ feet, Y= _____ feet, N.M. Coordinate System _____ Zone in the _____ Grant.

(B) Drilling Contractor J.D. North Drilling License No. WD - 744

Address 602 Ruins Rd. #11 Aztec, New Mexico 87410

Drilling Began 4/26/78 Completed 4/29/78 Type tools cable Size of hole 7 in.

Elevation of land surface or _____ at well is _____ ft. Total depth of well 37 ft.

Completed well is ☐ shallow ☐ artesian. Depth to water upon completion of well 12 ft.

Section 2. PRINCIPAL WATER-BEARING STRATA

Depth in Feet From	Depth in Feet To	Thickness in Feet	Description of Water-Bearing Formation	Estimated Yield (gallons per minute)
18'	27'	9	40-60 mesh sand on down to 5-10 mesh sand	10

Section 3. RECORD OF CASING

Diameter (inches)	Pounds per foot	Threads per in.	Depth in Feet Top	Depth in Feet Bottom	Length (feet)	Type of Shoe	Perforations From	Perforations To
6 5/8"			2' above	27' below	29'	weld-on	20'	26'

Section 4. RECORD OF MUDDING AND CEMENTING

Depth in Feet From	Depth in Feet To	Hole Diameter	Sacks of Mud	Cubic Feet of Cement	Method of Placement

78 MAY 9 P 1:17
STATE ENGINEER OFFICE
DISTRICT I
ALBUQUERQUE, N. MEX.

Section 5. PLUGGING RECORD

Plugging Contractor _____
Address _____
Plugging Method _____
Date Well Plugged _____
Plugging approved by:
_____
State Engineer Representative

No.	Depth in Feet Top	Depth in Feet Bottom	Cubic Feet of Cement
1			
2			
3			
4			

FOR USE OF STATE ENGINEER ONLY

Date Received 5/8/78

Quad _____ FWL _____ FSL _____

File No. SJ-63 SJ-573 Use Dom. Location No. 31N.10W.4.420

Section 6. LOG OF HOLE

Depth in Feet From	Depth in Feet To	Thickness in Feet	Color and Type of Material Encountered
0'	18'	18	red clay and Med boulders
18'	27'	9	sand
27'	37'	10	clay and blue shale

Section 7. REMARKS AND ADDITIONAL INFORMATION

The undersigned hereby certifies that, to the best of his knowledge and belief, the foregoing is a true and correct record of the above described hole.

Jimmy Don Heath
Driller

INSTRUCTIONS: This form should be executed in triplicate, preferably typewritten, and submitted to the appropriate district office of the State Engineer. All sections, except Section 5, shall be answered as completely and accurately as possible when any well is

HC #72[redacted] for $2.00 in SF

Revised December 1975

IMPORTANT — READ INSTRUCTIONS ON BACK BEFORE FILLING OUT THIS FORM.

Declaration of Owner of Underground Water Right

'77 DEC 13 AM 11 28
STATE ENGINEER OFFICE
SANTA FE, N.M. 87501

Trunk C

~~SAN JUAN UNDERGROUND WATER BASIN~~
BASIN NAME

Declaration No. SAN-595-S Date received Dec. 13, 1977

STATEMENT well # 2

1. Name of Declarant Garrett Van Diest
   Mailing Address P.O. Box 417, Aztec, New Mexico 87410
   County of San Juan, State of New Mexico
2. Source of water supply Shallow Water Aquifer (underground)
   (artesian or shallow water aquifer)
3. Describe well location under one of the following subheadings:
   a. NE ¼ SE ¼ NW ¼ of Sec. 4 Twp. 31N Rge. 10W N.M.P.M., in San Juan County.
   b. Tract No. N/A of Map No. _____ of the _____
   c. X = N/A feet, Y = _____ feet, N. M. Coordinate System _____ Zone in the _____ Grant.
   On land owned by _____
4. Description of well: date drilled February 10, 1974 driller Lewis Brothers depth 70 feet. outside diameter of casing 10" inches; original capacity 40 gal. per min.; present capacity 40 gal. per min.; pumping lift _____ feet; static water level 10 feet (above) (below) land surface; make and type of pump _____ make, type, horsepower, etc., of power plant _____ Fractional or percentage interest claimed in well 100%
5. Quantity of water appropriated and beneficially used _____ (acre feet per acre) 57 (acre feet per annum) for domestic purposes.
6. Acreage actually irrigated N/A acres, located and described as follows (describe only lands actually irrigated):
   Acreage for domestic use=

Subdivision	Sec.	Twp.	Range	Acres Irrigated	Owner
S½NW¼ & SW¼	3	31N	10W		
E½SW¼ & SE¼	4	31N	10W		
N½NE¼ & NE¼NW¼	9	31N	10W		
NW¼NW¼	10	31N	10W		

(Note: location of well and acreage actually irrigated must be shown on plat on reverse side.)

7. Water was first applied to beneficial use N/A (month / day / year) and since that time has been used fully and continuously on all of the above described lands or for the above described purposes except as follows: New Subdivision laws were just passed at the time the wells were drilled. This made the costs increase and the time required to get the Subdivision going much longer than I had figured on. That is the reason for the delay of putting the water to beneficial use. The project never was abandoned. I am now completing the subdivision and will put the water
8. Additional statements or explanations to beneficial use for domestic purposes.

I, Garrett Van Diest being first duly sworn upon my oath, depose and say that the above is a full and complete statement prepared in accordance with the instructions on the reverse side of this form and submitted in evidence of ownership of a valid underground water right, that I have carefully read each and all of the items contained therein and that the same are true to the best of my knowledge and belief.

Garrett Van Diest, declarant.
by: Garrett Van Diest

Subscribed and sworn to before me this 1st day of December, A.D. 1977

My commission expires 2/24/81 Notary Public

FILED
'78 MAR 13 AM 8 28
STATE ENGINEER OFFICE
ALBUQUERQUE, NEW MEXICO

UNDER NEW MEXICO LAW A DECLARATION IS ONLY A STATEMENT OF DECLARANT'S CLAIM. ACCEPTANCE FOR FILING DOES NOT CONSTITUTE APPROVAL OR REJECTION OF THE CLAIM.

Locate well and areas actually irrigated as accurately as possible on following plat:

Section (s) 3,4 9,10 Township 31N Range 10W N. M. P. M.

W = Location of well

Shaded area = Place of beneficial use for domestic purposes only.



INSTRUCTIONS

Declaration shall be executed (preferably typewritten) in triplicate and must be accompanied by a $1.00 filing fee. Each of triplicate copies must be properly signed and attested.

A separate declaration must be filed for each well in use.

All blanks shall be filled out fully. Required information which cannot be sworn to by declarant shall be supplied by affidavit of person or persons familiar with the facts and shall be submitted herewith.

Secs. 1-3. Complete all blanks.

Sec. 4. Fill out all blanks applicable as fully as possible.

Sec. 5. Irrigation use shall be stated in acre feet of water per acre per year applied on the land. If used for domestic, municipal, or other purposes, state total quantity in acre feet used annually.

Sec. 6. Describe only the acreage actually irrigated. When necessary to clearly define irrigated acreages, describe to nearest 2½ acre subdivision. If located on unsurveyed lands, describe by legal subdivision "as projected" from the nearest government survey corners, or describe by metes and bounds and tie survey to some permanent, easily-located natural object.

Sec. 7. Explain and give dates as nearly as possible of any years when all or part of acreage claimed was not irrigated.

Sec. 8. If well irrigates or supplies supplemental water to any other land than that described above, or if land is also irrigated from any other source, explain under this section. Give any other data necessary to fully describe water right.

If additional space is necessary, use a separate sheet or sheets and attach securely hereto.

HC #72[illegible] for $2.00 in SF

Revised December 1975

IMPORTANT — READ INSTRUCTIONS ON BACK BEFORE FILLING OUT THIS FORM.

'77 DEC 13 AM 11 26

STATE ENGINEER OFFICE
SANTA FE, N.M. 87501

Declaration of Owner of Underground Water Right

SAN JUAN UNDERGROUND WATER BASIN
Basin Name

Declaration No. SJ-595 Date received Dec. 13, 1977

STATEMENT well #1

1. Name of Declarant Garrett Van Diest
   Mailing Address P.O. Box 417, Aztec, New Mexico 87410
   County of San Juan, State of New Mexico
2. Source of water supply Shallow Water Aquifer (underground)
   (artesian or shallow water aquifer)
3. Describe well location under one of the following subheadings:
   a. NE ¼ SE ¼ NW ¼ of Sec. 4 Twp. 31N Rge. 10W N.M.P.M., in San Juan County.
   b. Tract No. N/A of Map No. _____ of the _____
   c. X = N/A feet, Y = _____ feet, N. M. Coordinate System _____ Zone in the _____ Grant.
   On land owned by _____.
4. Description of well: date drilled February 10, 1974 driller Lewis Brothers depth 90 feet. outside diameter of casing 10" inches; original capacity 40 gal. per min.; present capacity 40 gal. per min.; pumping lift _____ feet; static water level 10 feet (above) (below) land surface; make and type of pump _____ make, type, horsepower, etc., of power plant _____ Fractional or percentage interest claimed in well 100%
5. Quantity of water appropriated and beneficially used _____ (acre feet per acre) 57 (acre feet per annum) for domestic purposes.
6. Acreage actually irrigated N/A acres, located and described as follows (describe only lands actually irrigated):

Acreage for domestic use=

Subdivision	Sec.	Twp.	Range	Acres Irrigated	Owner
S½NW¼ & SW¼	3	31N	10W		
E½SW¼ & SE¼	4	31N	10W		
N½NE¼ & NE¼NW¼	9	31N	10W		
NW¼NW¼	10	31N	10W		

(Note: location of well and acreage actually irrigated must be shown on plat on reverse side)

7. Water was first applied to beneficial use N/A (month, day, year) and since that time has been used fully and continuously on all of the above described lands or for the above described purposes except as follows: New Subdivision laws were just passed at the time the wells were drilled. This made the costs increase and the time required to get the Subdivision going much longer than I had figured on. That is the reason for the delay of putting the water to beneficial use. The project never was abandoned. I am now completing the subdivision and will put the water
8. Additional statements or explanations to beneficial use for domestic purposes.

I, Garrett Van Diest being first duly sworn upon my oath, depose and say that the above is a full and complete statement prepared in accordance with the instructions on the reverse side of this form and submitted in evidence of ownership of a valid underground water right, that I have carefully read each and all of the items contained therein and that the same are true to the best of my knowledge and belief.

Garrett Van Diest, declarant.

by: Garrett Van Diest

Subscribed and sworn to before me this 12 day of December, A.D. 19 77

My commission expires 3/26/81 Notary Public

FILED
1977 MAR 20 AM 8:28
STATE ENGINEER OFFICE
ALBUQUERQUE, NEW MEXICO

UNDER NEW MEXICO LAW A DECLARATION IS ONLY A STATEMENT OF DECLARANT'S CLAIM. ACCEPTANCE FOR FILING DOES NOT CONSTITUTE APPROVAL OR REJECTION OF THE CLAIM.

Locate well and areas actually irrigated as accurately as possible on following plat:

Section (s) 3,4 9,10 Township 31N Range 10W M. P. P. M.

W = Location of well

Shaded area = Place of beneficial use for domestic purposes only.



INSTRUCTIONS

Declaration shall be executed (preferably typewritten) in triplicate and must be accompanied by a $1.00 filing fee. Each of triplicate copies must be properly signed and attested.

A separate declaration must be filed for each well in use.

All blanks shall be filled out fully. Required information which cannot be sworn to by declarant shall be supplied by affidavit of person or persons familiar with the facts and shall be submitted herewith.

Secs. 1-3. Complete all blanks.

Sec. 4. Fill out all blanks applicable as fully as possible.

Sec. 5. Irrigation use shall be stated in acre feet of water per acre per year applied on the land. If used for domestic, municipal, or other purposes, state total quantity in acre feet used annually.

Sec. 6. Describe only the acreage actually irrigated. When necessary to clearly define irrigated acreages, describe to nearest 2½ acre subdivision. If located on unsurveyed lands, describe by legal supdivision "as projected" from the nearest government survey corners, or describe by metes and bounds and tie survey to some permanent, easily-located natural object.

Sec. 7. Explain and give dates as nearly as possible of any years when all or part of acreage claimed was not irrigated.

Sec. 8. If well irrigates or supplies supplemental water to any other land than that described above, or if land is also irrigated from any other source, explain under this section. Give any other data necessary to fully describe water right.

If additional space is necessary, use a separate sheet or sheets and attach securely hereto.

Lucerne Well No. 1

Revised April, 1974

IMPORTANT – READ INSTRUCTIONS BEFORE FILLING OUT THIS FORM

HC 479A $56.00

Trunk C

CHANGE OF OWNERSHIP OF WATER RIGHT

1. NAME OF WATER RIGHT OWNER OF RECORD El Paso Natural Gas Company
Mailing Address P. O. Box 1492
City and State El Paso, Texas 79978
the owner and holder of a water right set forth in file number _____
of record in the office of the State Engineer has conveyed all (all or part) of said right to:

Name Meridian Oil Production, Inc.
Mailing Address P. O. Box 4289
City and State Farmington, New Mexico 87499

2. IRRIGATION: The conveyed water right is appurtenant to lands described as follows (describe only lands with actual water right and diversion as that amount of water measured at the well and/or farm headgate):

SUBDIVISION (District or Hydrographic Survey)	SECTION	TOWNSHIP (Map No.)	RANGE (Tract No.)	ACREAGE	DIVERSION (Acre Feet Per Annum)	PRIORITY
			TOTAL			

OTHER: Purpose Industrial/Drilling/Development ; Amount 29 (acre feet per annum of diversion); Priority 1/25/55.

3. DESIGNATE WELLS TO ACCOMPANY THE CONVEYED RIGHT: (To be executed if conveyance involves only a part of a ground water right):

WELL FILE NO.	SUBDIVISION (District or Hydrographic Survey)	SECTION	TOWNSHIP (Map No.)	RANGE (Tract No.)
SJ-54	NE/4	10	31N	10W

4. I HEREBY CONSENT TO A LAWFUL CHANGE IN THE PLACE AND/OR PURPOSE OF USE OF THE ABOVE-DESCRIBED WATER RIGHT: (To be executed if water right described above is a right for irrigation purposes and has been conveyed separate from the land to which it is appurtenant.)

_____

The undersigned, being first duly sworn upon oath, deposes and says that he has read the foregoing statements and that the same are true to the best of his knowledge and belief.

William F. Lorang, P.E.

Subscribed and sworn to before me this 5th day of June, A.D., 19 85

GLORIA BOCANEGRA
Notary Public in and for STATE of TEXAS
My commission expires: My Commission Expires 12-14-87

Gloria Bocanegra Notary Public

INSTRUCTIONS

Change of ownership shall be filed in triplicate and executed either by conveyor (seller) or by the new owner and shall be accompanied by a filing fee of $1.00. If executed by the new owner it shall be accompanied by a certified copy of the deed or other instrument of conveyance.

FOR STATE ENGINEER USE ONLY

A _____ from _____ to _____
(warranty deed, other)

was found by me to be recorded on the _____ day of _____, A. D., 19 _____ on page _____ of Book No. _____ of record of _____ County.

By: _____ Date: _____

Date Received JUne 17 1985 File No. SJ-54

U.S. ENGINEER OFFICE
ALBUQUERQUE, N. MEX.
JUN 17 8:26

Lucerne W. W. #1

Revised December 1975

IMPORTANT — READ INSTRUCTIONS ON BACK BEFORE FILLING OUT THIS FORM.

Amended Declaration of Owner of Underground Water Right

San Juan

BASIN NAME

Declaration No. SJ-54 Date received February 1, 1985

STATEMENT

1. Name of Declarant El Paso Natural Gas Company
   Mailing Address P. O. Box 1492
   County of El Paso, State of Texas
2. Source of water supply artesian
   (artesian or shallow water aquifer)
3. Describe well location under one of the following subheadings:
   a. ____ ¼ ____ ¼ NE ¼ of Sec. 10 Twp. 31N Rge. 10W N.M.P.M., in San Juan County.
   b. Tract No. ____ of Map No. ____ of the ____
   c. X = ____ feet, Y = ____ feet, N. M. Coordinate System ____ Zone in the ____ Grant.
   On land owned by USA
4. Description of well: date drilled 1/21/55 driller Cox depth 455 feet.
   outside diameter of casing 8-5/8 inches; original capacity 25 gal. per min.; present capacity 18 gal. per min.; pumping lift ____ feet; static water level ____ feet (above) (below) land surface; as noted on original application misc. 1-SJ-43;4/12/55
   make and type of pump ____
   make, type, horsepower, etc., of power plant ____
   Fractional or percentage interest claimed in well ____
5. Quantity of water appropriated and beneficially used 29 (acre feet per acre) (acre feet per annum)
   for industrial purposes.
6. Acreage actually irrigated N/A acres, located and described as follows (describe only lands actually irrigated):

Subdivision	Sec.	Twp.	Range	Acres Irrigated	Owner

(Note: location of well and acreage actually irrigated must be shown on plat on reverse side)

7. Water was first applied to beneficial use 1 (month) 25 (day) 55 (year) and since that time has been used fully and continuously on all of the above described lands or for the above described purposes except as follows: ____
8. Additional statements or explanations This well is being held on standby for future water requirements for oil and gas exploration/development drilling.

I, William F. Lorang, P.E. being first duly sworn upon my oath, depose and say that the above is a full and complete statement prepared in accordance with the instructions on the reverse side of this form and submitted in evidence of ownership of a valid underground water right, that I have carefully read each and all of the items contained therein and that the same are true to the best of my knowledge and belief.

El Paso Natural Gas Company, declarant.

by: W F Lorang

Subscribed and sworn to before me this 30th day of January, A.D. 1985

My commission expires December 14, 1985 Gloria Borrego Notary Public

FILED
UNDER NEW MEXICO LAW A DECLARATION IS ONLY A STATEMENT OF DECLARANT'S CLAIM.
ACCEPTANCE FOR FILING DOES NOT CONSTITUTE APPROVAL OR REJECTION OF THE CLAIM.

85 FEB 1 A 9:33
STATE ENGINEER OFFICE
DISTRICT I
ALBUQUERQUE, N. MEX.

Locate well ~~and acres actually irrigated~~ as accurately as possible on following plat:

Section (s) 10, Township 31N, Range 10W N. M. P. M.



INSTRUCTIONS

Declaration shall be executed (preferably typewritten) in triplicate and must be accompanied by a $1.00 filing fee. Each of triplicate copies must be properly signed and attested.

A separate declaration must be filed for each well in use.

All blanks shall be filled out fully. Required information which cannot be sworn to by declarant shall be supplied by affidavit of person or persons familiar with the facts and shall be submitted herewith.

Secs. 1-3. Complete all blanks.

Sec. 4. Fill out all blanks applicable as fully as possible.

Sec. 5. Irrigation use shall be stated in acre feet of water per acre per year applied on the land. If used for domestic, municipal, or other purposes, state total quantity in acre feet used annually.

Sec. 6. Describe only the acreage actually irrigated. When necessary to clearly define irrigated acreages, describe to nearest 2½ acre subdivision. If located on unsurveyed lands, describe by legal supdivision "as projected" from the nearest government survey corners, or describe by metes and bounds and tie survey to some permanent, easily-located natural object.

Sec. 7. Explain and give dates as nearly as possible of any years when all or part of acreage claimed was not irrigated.

Sec. 8. If well irrigates or supplies supplemental water to any other land than that described above, or if land is also irrigated from any other source, explain under this section. Give any other data necessary to fully describe water right.

If additional space is necessary, use a separate sheet or sheets and attach securely hereto.

Lucerne Water Well #1 SJ-54

IMPORTANT — READ INSTRUCTIONS ON BACK BEFORE FILLING OUT THIS FORM.

Declaration of Owner of Underground Water Right

SJ-54

Declaration No. ~~Misc.1-SJ-43~~ Book Misc. 2 Date received April 12, 1955

I, El Paso Natural Gas Company being first duly sworn upon my oath, depose and say that the following is a full and complete statement prepared in accordance with the instructions on the reverse side of this form and submitted in evidence of ownership of a valid underground water right, that I have carefully read each and all of the items contained therein and that the same are true to the best of my knowledge and belief.

El Paso Natural Gas Company, declarant.

BY: John F. Schaffer, Chief Civil Engineer

Subscribed and sworn to before me this 23rd day of March, A.D. 1955

My commission expires A. H. Viescas
Notary Public, in and for El Paso County, Texas
My commission expires June 1, 1955
Notary Public

STATEMENT

1. Name of water right owner U. S. Government
   of
   County of , State of
2. Source of water supply shallow
   (state whether artesian or shallow water basin)
   located in Animas River Valley
   (name of underground stream, valley, artesian basin, etc.)
3. The well is located in the ¼, ¼, NE ¼
   of section 10, Township 31N, Range 10W, N.M.P.M.
   on land owned by U. S. Government
4. Description of well: date drilled 1-21-55 driller Cox depth 455 feet.
   diameter (outside) of casing 8-5/8 inches; original flow 25 gal. per min.;
   present flow 18 gal. per min.; maximum pumping lift feet;
   make and type of pump On jet

   make, type, horsepower, etc., of power plant

   Fractional or percentage interest claimed in well 100%
5. Quantity of water appropriated and beneficially used 100%
   (feet depth or acre feet per acre)
   for Industrial purposes.
6. Acreage actually irrigated and with water right acres,
   located and described as follows (describe only lands actually irrigated):

Subdivision	Sec.	Twp.	Range	Acres Irrigated	Owner

(Note: location of well and acreage actually irrigated must be shown on plat on reverse side.)

7. Water was first applied to beneficial use and since that time has been used fully and continuously on all of the above described lands or for the above described purposes except as follows:
8. Additional statements or explanations

open case

APR 1955
PM
7|8|9|10|11|12|1|2|3|4|5|6
A

Locate well and areas actually irrigated as accurately as possible on following plat:

Section (s) 10, Township 21 North, Range 10 West N. M. P. M.



INSTRUCTIONS

Declaration shall be executed (preferably typewritten) in triplicate and must be accompanid by a $1.00 filing fee. Each of triplicate copies must be properly signed and attested.

A separate declaration must be filed for each well in use.

All blanks shall be filled out fully. Required information which cannot be sworn to by declarant shall be supplied by affidavit of person or persons familiar with the facts and shall be submitted herewith.

Secs. 1-3. Complete all blanks.

Sec. 4. Fill out all blanks applicable as fully as possible.

Sec. 5. Irrigation use shall be stated in feet depth or acre feet of water per acre applied on the land. If used for domestic, municipal. or other purposes, state total quantity in acre feet used annually.

Sec. 6. Describe only the acreage actually irrigated. When necessary to clearly define irrigated acreages, describe to nearest 2½ acre subdivision. If located on unsurveyed lands. describe by legal supdivision "as projected" from the nearest government survey corners, or describe by metes and bounds and tie survey to some permanent, easily-located natural object.

Sec. 7. Explain and give dates as nearly as possible of any years when all or part of acreage claimed was not irrigated.

Sec. 8. If well irrigates or supplies supplemental water to any other land than that described above, or if land is also irrigated from any other source, explain under this section. Give any other data necessary to fully describe water right.

If additional space is necessary, use a separate sheet or sheets and attach securely hereto.

Lucerne Water Well #1

(This form is to be executed in triplicate)

WELL RECORD

25-43

Date of Receipt April 12, 1955 Permit No. Misc. 1-SJ-43

Name of permitee, El Paso Natural Gas Company

Street or P. O. P. O. Box 1492, City and State El Paso, Texas

1. Well location and description: The shallow (shallow or artesian) well is located in ¼, ¼, NE ¼ of Section 10, Township 31N, Range 10W; Elevation of top of casing above sea level, ... feet; diameter of hole, 10 inches; total depth, 455 feet; depth to water upon completion, ... feet; drilling was commenced 1-21-55, 19..., and completed 1-25-55, 19...; name of drilling contractor Conley Cox

Box 785; Address, Aztec, New Mexico; Driller's License No. 85-0106595

2. Principal Water-bearing Strata:

	Depth in Feet From	To	Thickness	Description of Water-bearing Formation
No. 1				
No. 2				
No. 3				
No. 4				
No. 5				

3. Casing Record:

Diameter in Inches	Pounds per ft.	Threads per inch	Depth of Casing or Liner Top	Depth of Casing or Liner Bottom	Feet of Casing	Type of Shoe	Perforation From	Perforation To
8-5/8							76	96
							289	336

4. If above construction replaces old well to be abandoned, give location: ¼, ¼, ¼ of Section ....., Township ....., Range .....; name and address of plugging contractor,

.....

.....

date of plugging ....., 19.....; describe how well was plugged: .....

.....

.....

.....



6. Log of Well:

Depth in Feet From	Depth in Feet To	Thickness in feet	Description of Formation
0	15	15	Surface Soil
15	65	50	Sand and Shale
65	70	5	Sand
70	80	10	Sand and Shale
80	90	10	Sand
90	220	130	Sand and Shale
220	230	10	Shale
230	250	20	Sand
250	295	45	Shale and red bed
295	310	15	Sandy Shale
310	322	12	Water Sand
322	433	111	Shale
435	447	12	Sand
447	455	8	Shale

The undersigned hereby certifies that, to the best of his knowledge and belief, the foregoing is a true and correct record of the above described well.

.....
Licensed Well Driller

Instructions

This form shall be executed, preferaoly typewritten, in triplicate and filed with the State Engineer's Office at Roswell, New Mexico, within 10 days after drilling has been completed. Data on water-bearing strata and on all formations encountered should be as complete and accurate as possible.

Revised June 1972

STATE ENGINEER OFFICE

WELL RECORD

DOMESTIC (TrunkC)

Section 1. GENERAL INFORMATION

(A) Owner of well WAYNE WEST Owner's Well No. _____
Street or Post Office Address # 50 CR 2345
City and State AZTEC, N.M.

Well was drilled under Permit No. SJ-2089 and is located in the:

a. NW ¼ NW ¼ NE ¼ ¼ of Section 4 Township 31 Range 10 N.M.P.M.

b. Tract No. _____ of Map No. _____ of the _____

c. Lot No. _____ of Block No. _____ of the _____
Subdivision, recorded in _____ County.

d. X= _____ feet, Y= _____ feet, N.M. Coordinate System _____ Zone in the _____ Grant.

(B) Drilling Contractor TERRY HOOD License No. WD-917

Address FLORA VISTA, N.M.

Drilling Began 11-5-86 Completed 11-10-86 Type tools _____ Size of hole 6 in.

Elevation of land surface or _____ at well is 5500 ft. Total depth of well 55 ft.

Completed well is ☑ shallow ☐ artesian. Depth to water upon completion of well 40 ft.

Section 2. PRINCIPAL WATER-BEARING STRATA

Depth in Feet From	Depth in Feet To	Thickness in Feet	Description of Water-Bearing Formation	Estimated Yield (gallons per minute)
40	55	15	WATER BEARING SAN DY GRAVEL	12

Section 3. RECORD OF CASING

Diameter (inches)	Pounds per foot	Threads per in.	Depth in Feet Top	Depth in Feet Bottom	Length (feet)	Type of Shoe	Perforations From	Perforations To
6	17		0	55	55	DRIVE SHOE	50	55

Section 4. RECORD OF MUDDING AND CEMENTING

Depth in Feet From	Depth in Feet To	Hole Diameter	Sacks of Mud	Cubic Feet of Cement	Method of Placement

86 NOV 19 PM 1:13
STATE ENGINEER OFFICE
DISTRICT II
ALBUQUERQUE, N. MEX.

Section 5. PLUGGING RECORD

Plugging Contractor _____
Address _____
Plugging Method _____
Date Well Plugged _____
Plugging approved by: _____
State Engineer Representative

No.	Depth in Feet Top	Depth in Feet Bottom	Cubic Feet of Cement
1			
2			
3			
4			

FOR USE OF STATE ENGINEER ONLY

Date Received Nov 19, 1986

FWL _____ FSL _____

Section 6. LOG OF HOLE

Depth in Feet From	Depth in Feet To	Thickness in Feet	Color and Type of Material Encountered
0	40	40	OVERBURDEN + BOULDERS
40	55	15	WATER BEARING SAND + GRAVEL

Section 7. REMARKS AND ADDITIONAL INFORMATION

The undersigned hereby certifies that, to the best of his knowledge and belief, the foregoing is a true and correct record of the above described hole.

Driller

Revised June 1972

DOMESTIC

STATE ENGINEER OFFICE

WELL RECORD

Trunk C

Section 1. GENERAL INFORMATION

(A) Owner of well ALBERT KARLIN Owner's Well No. 1

Street or Post Office Address RT 1 BOX 0-5

City and State AZTEC, NEW MEXICO 87410

Well was drilled under Permit No. SJ 175 and is located in the:

a. ____ ¼ ____ ¼ SW¼ NW¼ ¼ of Section 4 Township 31N Range 10 W N.M.P.M.

b. Tract No. ____ of Map No. ____ of the ____

c. Lot No. ____ of Block No. ____ of the ____
Subdivision, recorded in ____ County.

d. X= ____ feet, Y= ____ feet, N.M. Coordinate System ____ Zone in the ____ Grant.

(B) Drilling Contractor MADSON ENTERPRISES License No. WD 697

Address PO BOX 192 AZTEC, NEW MEXICO 87410

Drilling Began 4/20/77 Completed 4/22/77 Type tools CABLE TOOL Size of hole 6 5/8 in.

Elevation of land surface or 5899 at well is ____ ft. Total depth of well 28' 6" ft.

Completed well is ☒ shallow ☐ artesian. Depth to water upon completion of well 13'6" ft.

Section 2. PRINCIPAL WATER-BEARING STRATA

Depth in Feet From	Depth in Feet To	Thickness in Feet	Description of Water-Bearing Formation	Estimated Yield (gallons per minute)
20	28' 6"	8' 6"	COBSE SAND & GRAVEL	20

Section 3. RECORD OF CASING

Diameter (inches)	Pounds per foot	Threads per in.	Depth in Feet Top	Depth in Feet Bottom	Length (feet)	Type of Shoe	Perforations From	Perforations To
6 5/8	12.92		0	31	31	STEEL WELD ON	25	30

Section 4. RECORD OF MUDDING AND CEMENTING

Depth in Feet From	Depth in Feet To	Hole Diameter	Sacks of Mud	Cubic Feet of Cement	Method of Placement

Section 5. PLUGGING RECORD

Plugging Contractor ____

Address ____

Plugging Method ____

Date Well Plugged ____

Plugging approved by: ____ State Engineer Representative

No.	Depth in Feet Top	Depth in Feet Bottom	Cubic Feet of Cement
1			
2			
3			
4			

FOR USE OF STATE ENGINEER ONLY

Date Received 5/3/77

Quad ____ FWL ____ FSL ____

From	To	Thickness	
0	12	12	RED CLAY
12	20	8	RED CLAY WITH RIVER BOLDERS
20	28' 6"	8' 6"	CORSE SAND & GRAVEL

Section 7. REMARKS AND ADDITIONAL INFORMATION

The undersigned hereby certifies that, to the best of his knowledge and belief, the foregoing is a true and correct record of the above described hole.

Lloyd E Madsen
Driller

INSTRUCTIONS: This form should be executed in triplicate, preferably typewritten, and submitted to the appropriate district office of the State Engineer. All sections, except Section 5, shall be answered as completely and accurately as possible when any well is drilled, repaired or deepened. When this form is used as a plugging r[illegible] only Section 1(a) and Section 5 need be completed.

Revised June 1972

DOMESTIC

STATE ENGINEER OFFICE

WELL RECORD

MAR 24 AM 8 25

STATE ENGINEER OFFICE
SANTA FE, N.M. 87501

Trunk C

Section 1. GENERAL INFORMATION

(A) Owner of well Howard S. Custafson Owner's Well No. 1

Street or Post Office Address 2806 Cherry Hills Place

City and State Farmington, New Mexico 87401

Well was drilled under Permit No. SJ-585 and is located in the:

a. ____ ¼ ____ ¼ ____ ¼ N½ ¼ of Section 8 Township 31 Range 10W N.M.P.M.
San Juan County

b. Tract No. ____ of Map No. ____ of the ____

c. Lot No. ____ of Block No. ____ of the ____
Subdivision, recorded in ____ County.

d. X= ____ feet, Y= ____ feet, N.M. Coordinate System ____ Zone in the ____ Grant.

(B) Drilling Contractor Gilbert Drilling Co. License No. WD-666

Address Box 973, Farmington, New Mexico 87401

Drilling Began 3/18/78 Completed 3/22/78 Type tools Cable Size of hole 8 in.

Elevation of land surface or ____ at well is ____ ft. Total depth of well 40 ft.

Completed well is ☒ shallow ☐ artesian. Depth to water upon completion of well 23 ft.

Section 2. PRINCIPAL WATER-BEARING STRATA

Depth in Feet From	Depth in Feet To	Thickness in Feet	Description of Water-Bearing Formation	Estimated Yield (gallons per minute)
32	40	8	Gravel	15

Section 3. RECORD OF CASING

Diameter (inches)	Pounds per foot	Threads per in.	Depth in Feet Top	Depth in Feet Bottom	Length (feet)	Type of Shoe	Perforations From	Perforations To
6			0	40	40			

Section 4. RECORD OF MUDDING AND CEMENTING

Depth in Feet From	Depth in Feet To	Hole Diameter	Sacks of Mud	Cubic Feet of Cement	Method of Placement

Section 5. PLUGGING RECORD

Plugging Contractor ____

Address ____

Plugging Method ____

Date Well Plugged ____

Plugging approved by: ____
State Engineer Representative

No.	Depth in Feet Top	Depth in Feet Bottom	Cubic Feet of Cement
1			
2			
3			
4			

FOR USE OF STATE ENGINEER ONLY

Date Received 3/24/78

Quad ____ FWL ____ FSL ____

31N.10W.8 100

Section 6. LOG OF HOLE

Depth in Feet From	Depth in Feet To	Thickness in Feet	Color and Type of Material Encountered
0	32	32	Sand
32	40	8	Gravel & Boulders

Section 7. REMARKS AND ADDITIONAL INFORMATION

The undersigned hereby certifies that, to the best of his knowledge and belief, the foregoing is a true and correct record of the above described hole.

WELL RECORD... John D. Gilbert
Driller

INSTRUCTIONS: This form should be executed in triplicate, preferably typewritten, and submitted to the appropriate district office

Revised June 1972

DOMESTIC

STATE ENGINEER OFFICE

WELL RECORD

Trunk C

Section 1. GENERAL INFORMATION

(A) Owner of well Carl F. Brandenburg Owner's Well No. SJ- 2150

Street or Post Office Address Rd. 2900 # 887

City and State Aztec, N.M. 87410

Well was drilled under Permit No. SJ- 2150 and is located in the:

a. ~~SE¼NE¼SE¼SW¼~~ NW ¼ NW ¼ of Section 7. & 8 Township 31 Range 10W N.M.P.M.

b. Tract No. _____ of Map No. _____ of the _____

c. Lot No. _____ of Block No. _____ of the _____
Subdivision, recorded in San Juan County.

d. X= _____ feet, Y= _____ feet, N.M. Coordinate System _____ Zone in the _____ Grant.

(B) Drilling Contractor Leon Thompson License No. WD-527

Address P.O.Box1651

Drilling Began 4-16-88 Completed 4-19-88 Type tools Cabletool Size of hole 6 in.

Elevation of land surface or _____ at well is _____ ft. Total depth of well 41 ft.

Completed well is [X] shallow [ ] artesian. Depth to water upon completion of well 23 ft.

Section 2. PRINCIPAL WATER-BEARING STRATA

Depth in Feet From	Depth in Feet To	Thickness in Feet	Description of Water-Bearing Formation	Estimated Yield (gallons per minute)
31	40	9	Sand & Gravel	6

Section 3. RECORD OF CASING

Diameter (inches)	Pounds per foot	Threads per in.	Depth in Feet Top	Depth in Feet Bottom	Length (feet)	Type of Shoe	Perforations From	Perforations To
7	23	Welded			30	none	20	30
5	(160 Pvc)	Liner			20		21	41

Section 4. RECORD OF MUDDING AND CEMENTING

Depth in Feet From	Depth in Feet To	Hole Diameter	Sacks of Mud	Cubic Feet of Cement	Method of Placement

88 APR 26 P 1:07
STATE ENGINEER OFFICE
DISTRICT I
ALBUQUERQUE, N. MEX.

Section 5. PLUGGING RECORD

Plugging Contractor _____

Address _____

Plugging Method _____

Date Well Plugged _____

Plugging approved by: _____
State Engineer Representative

No.	Depth in Feet Top	Depth in Feet Bottom	Cubic Feet of Cement
1			
2			
3			
4			

FOR USE OF STATE ENGINEER ONLY

Date Received April 26, 1988

Quad _____ FWL _____ FSL _____

Section 6. LOG OF HOLE

Depth in Feet From	Depth in Feet To	Thickness in Feet	Color and Type of Material Encountered
0	15	15	Sand
15	31	16	Boulders
31	41	10	Sand & Gravel

Section 7. REMARKS AND ADDITIONAL INFORMATION

The undersigned hereby certifies that, to the best of his knowledge and belief, the foregoing is a true and correct record of the above described hole.

Driller

STATE ENGINEER OFFICE

WELL RECORD

Trunk C

Section 1. GENERAL INFORMATION

(A) Owner of well EDWARD ZINK Owner's Well No. _____

Street or Post Office Address 5126 HWY 550

City and State AZTEC, NM 87410

Well was drilled under Permit No. SJ-2304 and is located in the:

a. _____ ¼ NE ¼ NW ¼ — ¼ of Section 8 Township 31 Range 10 N.M.P.M.

b. Tract No. _____ of Map No. _____ of the _____

c. Lot No. _____ of Block No. _____ of the _____
Subdivision, recorded in _____ County.

d. X= _____ feet, Y= _____ feet, N.M. Coordinate System _____ Zone in the _____ Grant.

(B) Drilling Contractor TERRY HOOD License No. WD-717

Address FLORA VISTA, NM

Drilling Began 1-11-91 Completed 1-14-91 Type tools _____ Size of hole 6 in.

Elevation of land surface or _____ at well is _____ ft. Total depth of well 35 ft.

Completed well is ☑ shallow ☐ artesian. Depth to water upon completion of well 29 ft.

Section 2. PRINCIPAL WATER-BEARING STRATA

Depth in Feet From	Depth in Feet To	Thickness in Feet	Description of Water-Bearing Formation	Estimated Yield (gallons per minute)
30	35	5	SAND GRAVEL BOULDERS	10

STATE ENGINEER OFFICE
ALBUQUERQUE, N. MEX.
JAN 16 9 11

Section 3. RECORD OF CASING

Diameter (inches)	Pounds per foot	Threads per in.	Depth in Feet Top	Depth in Feet Bottom	Length (feet)	Type of Shoe	Perforations From	Perforations To
6	18		0	35	35		30	35

Section 4. RECORD OF MUDDING AND CEMENTING

Depth in Feet From	Depth in Feet To	Hole Diameter	Sacks of Mud	Cubic Feet of Cement	Method of Placement

Section 5. PLUGGING RECORD

Plugging Contractor _____

Address _____

Plugging Method _____

Date Well Plugged _____

Plugging approved by:

_____
State Engineer Representative

No.	Depth in Feet Top	Depth in Feet Bottom	Cubic Feet of Cement
1			
2			
3			
4			

FOR USE OF STATE ENGINEER ONLY

Date Received 1-16-91 Quad NE¼NW¼ FWL _____ FSL _____

File No. SJ-2304 Use Dom Location No. 31N.10W.08

Depth in Feet From	To	Thickness in Feet	Color and Type of Material Encountered
0	29	29	RECENT SAND + CLAY
29	35	6	SAND & GRAVEL BOULDERS

Section 7. REMARKS AND ADDITIONAL INFORMATION

The undersigned hereby certifies that, to the best of his knowledge and belief, the foregoing is a true and correct record of the above described hole.

Driller

INSTRUCTIONS: This form should be executed in triplicate, preferably typewritten, and submitted to the appropriate district office of the State Engineer. All sections, except Section 5, shall be answered as completely and accurately as possible when any well is drilled, repaired or deepened. When this form is used as a plugging record, only Section 1(a) and Section 5 need be completed.