

3R - 197

REPORTS

DATE:

2004

**EPFS GROUNDWATER SITES
2004 CLOSURE REPORT**

**Jennepah #1
Meter Code: 71816**

TABLE OF CONTENTS

- ❖ EPFS Groundwater Sites Closure Report, Jennepah #1 Meter Code 71816
- ❖ Table 1: Summary of Historic BTEX Compounds in Groundwater Samples
- ❖ Figures
 - ◆ Figure 1: Jennepah #1, June 2003
 - ◆ Figure 2: Jennepah #1, September 2003
 - ◆ Figure 3: Jennepah #1, December 2003
 - ◆ Figure 4: Jennepah #1, March 2004
 - ◆ Figure 5: Historic BTEX Concentrations and Groundwater Elevations, MW-1
 - ◆ Figure 6: Historic BTEX Concentrations and Groundwater Elevations, MW-2
 - ◆ Figure 7: Historic BTEX Concentrations and Groundwater Elevations, MW-3
- ❖ Appendix A: Phase I Pit Site Assessment (1994)
- ❖ Appendix B: Pit Excavation and Soil Sample Results (1994, 1995)
- ❖ Appendix C: Soil Boring Sample Results (1997)
- ❖ Appendix D: Monitoring Well Borelogs and Well Construction Forms (1997, 1999)
- ❖ Appendix E: ORC Injection Borelogs and Location Map (1998)
- ❖ Appendix F: Laboratory Reports (2003/2004)
- ❖ Appendix G: Field Documentation (2003/2004)
- ❖ Appendix H: Navajo Nation EPA Closure Approval Letter (March 2004)

RECEIVED

APR 02 2004

Oil Conservation Division
Environmental Bureau

**EPFS GROUNDWATER SITES
2004 CLOSURE REPORT**

**Jennepah #1
Meter Code: 71816**

SITE DETAILS

Legal Description:	Town: 28N	Range: 9W	Sec: 36	Unit: H
NMOCD Haz Ranking:	40	Land Type: Navajo	Operator: Amoco Production	

PREVIOUS ACTIVITIES

Site Assessment:	May /94	Excavation:	Jun/94 (70 cy)	Soil Boring:	Feb/97
Monitor Well:	Feb/97	Geoprobe:	NA	Additional MWs:	May/99
Downgradient MWs:	May/99	Replace MW:	NA	Quarterly Initiated:	Jun/97
ORC Nutrient Injection:	Jun/98	Re-Excavation:	Nov/95 (234 cy)	PSH Removal Initiated:	Mar/01 (MW-1)
Annual Initiated:	NA	Quarterly Resumed:	NA		

Following the initial site assessment in May 1994 (see Appendix A), the existing pit was excavated to a depth of 12 feet below ground surface (bgs). Approximately 70 cubic yards (cy) of source material were removed and disposed of at the Envirotech land farm. The head space soil reading from the bottom of the excavation was 314 ppm and no groundwater was encountered. Soil analytical for the sample was as follows: benzene, 1.1 mg/kg; toluene, 43 mg/kg; ethylbenzene, 10 mg/kg; total xylenes, 110 mg/kg; total BTEX, 164 mg/kg; and total petroleum hydrocarbons (TPH), 3,380 mg/kg (see Appendix B).

A phase II soil re-excavation was conducted in November 1995. The surficial dimensions of the re-excavated area were 19 feet by 19 feet, and the depth was 19 feet bgs. Approximately 234 cy of source material were removed and disposed of at the Envirotech land farm. The headspace soil reading from the bottom of the excavation was 208 ppm and no groundwater was encountered. Soil analytical data for the sample were as follows: benzene, < 0.5 mg/kg; toluene, 4.4 mg/kg; ethylbenzene, 5.7 mg/kg; total xylenes, 48.5 mg/kg; total BTEX, 58.6 mg/kg; and total petroleum hydrocarbons (TPH), 828 mg/kg (see Appendix B).

In February 1997, a soil boring was drilled in the center of the pit to a depth of 32 feet bgs. A soil sample was collected from the interval from 20 to 22 feet bgs. The headspace soil reading from the sample was 2000 ppm, and the analytical data for the soil sample were as follows: benzene, < 0.5 mg/kg; toluene, < 0.5 mg/kg; ethylbenzene, < 0.5 mg/kg; total xylenes, < 1.5 mg/kg; total BTEX, 3 mg/kg; and total petroleum hydrocarbons (TPH), 311 mg/kg (see Appendix C). Groundwater was encountered in the borehole at 22 feet bgs, and monitoring well MW-1 was constructed and screened from 15

**EPFS GROUNDWATER SITES
2004 CLOSURE REPORT**

**Jennepah #1
Meter Code: 71816**

to 30 feet bgs (see Appendix D). Groundwater sampling was initiated in 1997. Periodically in 1999 through 2001, a small amount of free-product was detected and removed from MW-1. A total of approximately 0.5 gallons was removed during this period.

In June 1998, oxygen releasing compound (ORC) slurry was injected into the subsurface via three borings, each containing 10 pounds of ORC for a total of 30 pounds. Appendix E contains the injection borelogs and ORC boring location map.

Monitoring wells MW-2 and MW-3 were drilled and installed in May 1999. MW-2 was placed to the northwest of MW-1 and MW-3 was placed to the southwest of MW-1. Both wells were installed to a total depth of 30 feet bgs, with screened intervals between 15 and 13 feet bgs. Initial groundwater samples were collected from these wells in 1999 and analytical data for BTEX compounds were all below detection limits. Subsequent samples collected from these wells in January 2001 also indicated BTEX concentrations below the detection limits. Historic analytical data for monitoring wells MW-1, MW-2 and MW-3 are presented in Table 1. Because analytical data reports from prior years has been submitted in previous annual reports, only the analytical data reports for 2003 are included with this report as Appendix F. Similarly, field documentation for 2003 activities are included in Appendix G.

SUMMARY OF 2003/2004 ACTIVITIES

MW-1: Quarterly groundwater sampling and water level monitoring was performed in 2003 and the first quarter of 2004. First quarter 2003 analytical results for benzene and total xylenes were above NMWQCC standards. However, BTEX analytical results from the second, third and fourth quarters of 2003 and the first quarter of 2004 were all below standards, representing four consecutive quarters of data below closure standards.

MW-2: Quarterly water level monitoring was performed, and groundwater samples were collected for closure in June 2003, December 2003 and March 2004. BTEX concentrations during all of these sampling events were below analytical detection limits and closure standards.

MW-3: Quarterly water level monitoring was performed, and groundwater samples were collected for closure in June 2003, December 2003 and March 2004. BTEX concentrations during all of these sampling events were below analytical detection limits and closure standards.

NNEPA Closure: This site was submitted to Navajo Nation EPA for closure in February 2004. Navajo Nation EPA approved closure for this site in a letter dated March 8, 2004 (Appendix H).

EPFS GROUNDWATER SITES 2004 CLOSURE REPORT

**Jennepah #1
Meter Code: 71816**

SITE MAPS

Site maps (June 2003, September 2003, December 2003 and March 2004) are attached in Figures 1 through 4, which present 2003/2004 analytical data and the locations of the former pit and monitoring wells.

SUMMARY TABLES AND GRAPHS

Historic analytical data (1997 through present) are summarized in Table 1 and presented graphically in Figures 5 through 7 for wells MW-1, MW-2 and MW-3, respectively.

GEOLOGIC LOGS AND WELL COMPLETION DIAGRAMS

No subsurface activities were performed at this site during 2003/2004.

DISPOSITION OF GENERATED WASTES

No wastes were generated at this site during 2003/2004.

ISOCONCENTRATION MAPS

No isoconcentration maps were prepared for this site, however, the attached site maps present water level and analytical data collected during 2003 and 2004.

CONCLUSIONS

EPFS excavated a total of 304 cy of source material from the former pit during 1994 and 1995. A confirmation soil sample from the pit following the final excavation indicated a benzene concentration below the detection limit (< 0.5 mg/kg). A monitoring well, MW-1, was installed in the former pit in 1997, and analytical data indicated benzene and total xylenes concentrations (39.4 and 785 $\mu\text{g/L}$, respectively) above standards. Concentrations fluctuated between 1997 and early 2003, until June 2003 when concentrations of BTEX compounds consistently fell below closure standards. BTEX concentrations were below closure standards in MW-1 for four consecutive quarters in June 2003 through March 2004. Historic BTEX concentrations in MW-2 and MW-3, including samples collected in June 2003, December 2003 and March 2004, have consistently been below analytical detection limits. Navajo Nation EPA approved closure for this site in March 2004 based on three consecutive samples below closure criteria.

Minimal impact to groundwater exists at this site. Based on the data presented in this, and previous annual reports, the site poses minimal risk to human health and the environment. Furthermore, no potential receptors exist within 1,000 feet of the site and the majority of source material has been removed from the former EPFS pit. Therefore, EPFS requests that this site be closed, and MW-1, MW-2 and MW-3 be approved for abandonment.

**EPFS GROUNDWATER SITES
2004 CLOSURE REPORT**

**Jennepah #1
Meter Code: 71816**

RECOMMENDATIONS


- New Mexico Oil Conservation Division (NMOCD) criteria have been met. EPFS requests closure of this site from NMOCD.
 - Following NMOCD approval for closure, MW-1, MW-2 and MW-3 will be abandoned in accordance with the approved Monitoring Well Abandonment Plan.
-

TABLES

TABLE 1
SUMMARY OF HISTORIC BTEX COMPOUNDS IN GROUNDWATER SAMPLES
JENNEPAH #1 (METER #71816)

Site Name	Monitoring Well	Sample Date	Benzene (ug/L)	Toluene (ug/L)	Ethylbenzene (ug/L)	Total Xylenes (ug/L)	Groundwater Elevation (ft btoc)
Jennepah #1	MW-1	3/13/1997	39.4	352	89.2	785	76.56
Jennepah #1	MW-1	6/10/1997	10.3	53.5	28.4	233	76.69
Jennepah #1	MW-1	9/25/1997	21	185	51.2	520	77.02
Jennepah #1	MW-1	12/5/1997	23.4	211	73.5	674	77.24
Jennepah #1	MW-1	3/26/1998	18.5	171	69.1	701	77.33
Jennepah #1	MW-1	6/2/1998	12.3	134	62.2	548	77.10
Jennepah #1	MW-1	9/10/1998	20.7	165	105	882	77.50
Jennepah #1	MW-1	12/15/1998	9.8	79	61	460	77.84
Jennepah #1	MW-1	3/16/1999	8.2	79.5	64.7	437	77.87
Jennepah #1	MW-1	6/14/1999	9.6	110	70	520	77.70
Jennepah #1	MW-1	9/20/1999	9	310	200	1,900	76.19
Jennepah #1	MW-1	12/13/1999	< 1.0	17	73	550	76.11
Jennepah #1	MW-1	3/16/2000	1.3	32	58	470	76.16
Jennepah #1	MW-1	6/12/2000	< 1.0	18	52	430	76.16
Jennepah #1	MW-1	9/25/2000	41	350	300	2,400	75.71
Jennepah #1	MW-1	12/12/2000	210	1,200	1,900	14,000	75.76
Jennepah #1	MW-1	12/17/2001	< 1.0	15	32	260	76.54
Jennepah #1	MW-1	3/18/2002	< 1.0	7.3	13	150	76.21
Jennepah #1	MW-1	6/5/2002	11	< 1.0	14	94	76.01
Jennepah #1	MW-1	9/17/2002	32	52	27	140	72.25
Jennepah #1	MW-1	12/23/2002	27.4	67.1	62.5	338	76.44
Jennepah #1	MW-1	3/25/2003	74	190	168	788	76.39
Jennepah #1	MW-1	6/24/2003	< 1.0	< 1.0	< 1.0	44.1	76.12
Jennepah #1	MW-1	9/23/2003	< 1.0	< 1.0	< 1.0	38.1	76.45
Jennepah #1	MW-1	12/16/2003	< 1.0	< 1.0	< 1.0	19	76.78
Jennepah #1	MW-1	3/23/2004	< 1.0	< 1.0	< 1.0	22	76.83
Jennepah #1	TW2	5/11/1999	< 1.0	< 1.0	< 1.0	< 3.0	not surveyed
Jennepah #1	MW-2	1/29/2001	< 1.0	< 1.0	< 1.0	< 3.0	75.47
Jennepah #1	MW-2	6/24/2003	< 1.0	< 1.0	< 1.0	< 3.0	73.30
Jennepah #1	MW-2	12/16/2003	< 1.0	< 1.0	< 1.0	< 3.0	73.93
Jennepah #1	MW-2	3/23/2004	< 1.0	< 1.0	< 1.0	< 3.0	73.97
Jennepah #1	TW3	5/11/1999	< 1.0	< 1.0	< 1.0	< 3.0	not surveyed
Jennepah #1	MW-3	1/29/2001	< 1.0	< 1.0	< 1.0	< 3.0	75.88
Jennepah #1	MW-3	6/24/2003	< 1.0	< 1.0	< 1.0	< 3.0	73.64
Jennepah #1	MW-3	12/16/2003	< 1.0	< 1.0	< 1.0	< 3.0	74.12
Jennepah #1	MW-3	3/23/2004	< 1.0	< 1.0	< 1.0	< 3.0	74.30

FIGURES



	MW-1	MW-2	MW-3
B	<1.0	<1.0	<1.0
T	<1.0	<1.0	<1.0
E	<1.0	<1.0	<1.0
X	44.1	<3.0	<3.0

LEGEND

- MW-1 Approximate Monitoring Well Location and Number
- B Benzene ($\mu\text{g/L}$)
- T Toluene ($\mu\text{g/L}$)
- E Ethylbenzene ($\mu\text{g/L}$)
- X Total Xylenes ($\mu\text{g/L}$)
- NS Not Sampled
- < Not Detected. Value Shown is Detection Limit.
- GWEL Groundwater Elevation
(FT Above Mean Sea Level Unless Noted Otherwise)
- TOC Top of Casing
- 75.6 Potentiometric Surface
(Approximate & Assumed Where Dashed)
- Direction of Groundwater Flow
(Estimated)




NOT TO SCALE

JENNAPAH #1, METER 71816
JUNE 2003

GROUNDWATER SITES
EL PASO FIELD SERVICES

FIGURE 1



MW-1	
B	<1.0
T	<1.0
E	<1.0
X	38.1

LEGEND

- ⊙ MW-1 Approximate Monitoring Well Location and Number
- B Benzene ($\mu\text{g/L}$)
- T Toluene ($\mu\text{g/L}$)
- E Ethylbenzene ($\mu\text{g/L}$)
- X Total Xylenes ($\mu\text{g/L}$)
- NS Not Sampled
- < Not Detected. Value Shown is Detection Limit.
- GWEL Groundwater Elevation
(FT Above Mean Sea Level Unless Noted Otherwise)
- TOC Top of Casing
- 75.6 Potentiometric Surface
(Assumed Where Dashed)
- Direction of Groundwater Flow
(Estimated)




NOT TO SCALE

JENNAPAH #1, METER 71816
SEPTEMBER 2003

GROUNDWATER SITES
EL PASO FIELD SERVICES

FIGURE 2



LEGEND

- MW-1 Approximate Monitoring Well Location and Number
- B Benzene ($\mu\text{g/L}$)
- T Toluene ($\mu\text{g/L}$)
- E Ethylbenzene ($\mu\text{g/L}$)
- X Total Xylenes ($\mu\text{g/L}$)
- NS Not Sampled
- < Not Detected. Value Shown is Detection Limit.
- J Value Estimated. May Be Biased High.
- GWEL Groundwater Elevation (FT Above Mean Sea Level Unless Noted Otherwise)
- TOC Top of Casing
- 75.6 Potentiometric Surface (Assumed Where Dashed)
- Direction of Groundwater Flow (Estimated)

	MW-1	MW-2	MW-3
B	<1.0	<1.0	<1.0
T	<1.0	<1.0	<1.0
E	<1.0	<1.0	<1.0
X	19J	<3.0	<3.0




NOT TO SCALE

JENNAPAH #1, METER 71816
DECEMBER 2003

GROUNDWATER SITES
EL PASO FIELD SERVICES

FIGURE 3



	MW-1	MW-2	MW-3
B	<1.0	<1.0	<1.0
T	<1.0	<1.0	<1.0
E	<1.0	<1.0	<1.0
X	22	<3.0	<3.0

LEGEND

- MW-1 Approximate Monitoring Well Location and Number
- B Benzene ($\mu\text{g/L}$)
- T Toluene ($\mu\text{g/L}$)
- E Ethylbenzene ($\mu\text{g/L}$)
- X Total Xylenes ($\mu\text{g/L}$)
- NS Not Sampled
- GWEL Groundwater Elevation (FT Above Mean Sea Level Unless Noted Otherwise)
- TOC Top of Casing
- 75.0 Potentiometric Surface (Approximate & Assumed Where Dashed)
- Direction of Groundwater Flow (Estimated)



NOT TO SCALE

JENNAPAH #1, METER 71816
MARCH 2004

GROUNDWATER SITES
EL PASO FIELD SERVICES

FIGURE 4

FIGURE 5
HISTORIC BTEX CONCENTRATIONS AND GROUNDWATER ELEVATIONS
JENNEPAH #1
MW-1




FIGURE 6
HISTORIC BTX CONCENTRATIONS AND GROUNDWATER ELEVATIONS
JENNPAH #1
MW-2




FIGURE 7
HISTORIC BTEX CONCENTRATIONS AND GROUNDWATER ELEVATIONS
JENNEPAH #1
MW-3



APPENDIX A
PHASE I PIT SITE ASSESSMENT
(1994)


FIELD PIT SITE ASSESSMENT FORM

GENERAL	Meter: <u>71816</u> Location: <u>Jennapah No 1</u> Operator #: <u>0203</u> Operator Name: <u>Ames</u> P/L District: <u>Blanco</u> Coordinates: Letter: <u>H</u> Section <u>36</u> Township: <u>28</u> Range: <u>9</u> Or Latitude _____ Longitude _____ Pit Type: Dehydrator _____ Location Drip: ☒ Line Drip: _____ Other: _____ Site Assessment Date: <u>5/17/94</u> Area: <u>03</u> Run: <u>92</u>
SITE ASSESSMENT	NMOCD Zone: (From NMOCD Maps) Inside ☒ (1) Outside ☐ (2) Land Type: BLM ☐ (1) State ☐ (2) Fee ☐ (3) Indian <u>Navajo Tribe</u> Depth to Groundwater Less Than 50 Feet (20 points) ☒ (1) 50 Ft to 99 Ft (10 points) ☐ (2) Greater Than 100 Ft (0 points) ☐ (3) Wellhead Protection Area : Is it less than 1000 ft from wells, springs, or other sources of fresh water extraction? , or ; Is it less than 200 ft from a private domestic water source? ☐ (1) YES (20 points) ☒ (2) NO (0 points) Horizontal Distance to Surface Water Body Less Than 200 Ft (20 points) ☒ (1) 200 Ft to 1000 Ft (10 points) ☐ (2) Greater Than 1000 Ft (0 points) ☐ (3) Name of Surface Water Body <u>Blanco Canyon</u> (Surface Water Body : Perennial Rivers, Major Wash, Streams, Creeks, Irrigation Canals, Ditches, Lakes, Ponds) Distance to Nearest Ephemeral Stream ☒ (1) < 100' (Navajo Pits Only) ☐ (2) > 100' TOTAL HAZARD RANKING SCORE: <u>40</u> POINTS
REMARKS	Remarks : <u>Redline & Vuln - Inside</u> <u>3 pits Will Dig & Haul 1 Pit Dry</u> <u>Dig & Haul</u>

ORIGINAL PIT LOCATION

ORIGINAL PIT LOCATION

Original Pit : a) Degrees from North 65° Footage from Wellhead 151'
b) Length : 17' Width : 17' Depth : 1'



REMARKS

Remarks :

Pictures @ 10:00 (19-22)

End Dump

Completed By:

Cory Chase
Signature

5/17/94
Date

APPENDIX B
PIT EXCAVATION AND SOIL SAMPLE RESULTS
(1994, 1995)

FIELD PIT REMEDIATION/CLOSURE FORM

GENERAL

Meter: 71816 Location: JENNAPAH NO#1
 Coordinates: Letter: H Section: 36 Township: 28 Range: 9
 Or Latitude _____ Longitude _____
 Date Started : 6-1-94 Area: 03 Run: 82

FIELD OBSERVATIONS

Sample Number(s): KP #73
 Sample Depth: 12' Feet
 Final PID Reading 314 PID Reading Depth 12' Feet
 Yes No
 Groundwater Encountered ☐ (1) ☒ (2) Approximate Depth _____ Feet

CLOSURE

Remediation Method :
 Excavation ☒ (1) Approx. Cubic Yards 70
 Onsite Bioremediation ☐ (2)
 Backfill Pit Without Excavation ☐ (3)
 Soil Disposition:
 Envirotech ☐ (1) ☒ (3) Tierra
 Other Facility ☐ (2) Name: _____
 Pit Closure Date: 6-1-94 Pit Closed By: B.E.I

REMARKS

Remarks : SOME line markers started Remediating 12'
Soil DARK gray smell BAD. At 12 soil still the same.
Pid 314.

Signature of Specialist: Kelly Peltz

El Paso Natural Gas Company

FIELD SERVICES LABORATORY

ANALYTICAL REPORT

PIT CLOSURE PROJECT - Soil

SAMPLE IDENTIFICATION

	Field ID	Lab ID
SAMPLE NUMBER:	KP 73	945329
MTR CODE SITE NAME:	71814	N/A
SAMPLE DATE TIME (Hrs):	6-1-94	1122
SAMPLED BY:	N/A	
DATE OF TPH EXT. ANAL.:	6-2-94	6/2/94
DATE OF BTEX EXT. ANAL.:	6/6/94	6/7/94
TYPE DESCRIPTION:	VC	BROWN GRAY COARSE SAND

REMARKS:

RESULTS

PARAMETER	RESULT	UNITS	QUALIFIERS			
			DF	Q	M(g)	V(ml)
BENZENE	1.1	MG/KG	25			
TOLUENE	43	MG/KG	25			
ETHYL BENZENE	10	MG/KG	25			
TOTAL XYLENES	110	MG/KG	25			
TOTAL BTEX	164	MG/KG				
TPH (418.1)	3380	MG/KG			1.99	28
HEADSPACE PID	314	PPM				
PERCENT SOLIDS	93.5	%				

- TPH is by EPA Method 418.1 and BTEX is by EPA Method 8020 -

The Surrogate Recovery was at 35 % for this sample All QA/QC was acceptable.

Attentive:

ATI results attached. Surrogate recovery was outside ATI QC limits due to matrix interference.

F = Dilution Factor Used

Approved By:

John Furch

Date:

7/14/94



Analytical Technologies, Inc.

2709-D Pan American Freeway, NE Albuquerque, NM 87107
Phone (505) 344-3777 FAX (505) 344-4413

ATI I.D. 406313

June 30, 1994

El Paso Natural Gas
P.O. Box 4990
Farmington, NM 87499

Project Name/Number: PIT CLOSURE 24324

Attention: John Lambdin

On 06/03/94, Analytical Technologies, Inc., (ADHS License No. AZ0015), received a request to analyze non-aqueous samples. The samples were analyzed with EPA methodology or equivalent methods. The results of these analyses and the quality control data, which follow each set of analyses, are enclosed.

This report is being reissued to correct the client I.D. for ATI #406313-03 on the results page.


This report is being reissued in part to correct notations for samples: 945329, 945332 and 94533.

If you have any questions or comments, please do not hesitate to contact us at (505) 344-3777.

H. Mitchell Rubenstein, Ph.D.
Laboratory Manager

MR:jd

Enclosure





Analytical Technologies, Inc.

GAS CHROMATOGRAPHY RESULTS

TEST : BTEX (EPA 8020)

CLIENT : EL PASO NATURAL GAS

ATI I.D.: 406313

PROJECT # : 24324

PROJECT NAME : PIT CLOSURE

SAMPLE ID. #	CLIENT I.D.	MATRIX	DATE SAMPLED	DATE EXTRACTED	DATE ANALYZED	DIL. FACTOR
13	945329	NON-AQ	06/01/94	06/06/94	06/07/94	25
14	945330	NON-AQ	06/01/94	06/06/94	06/07/94	1
15	945331	NON-AQ	06/01/94	06/06/94	06/07/94	1

PARAMETER	UNITS	13	14	15
BENZENE	MG/KG	1.1	<0.25	<0.025
TOLUENE	MG/KG	43	<0.25	<0.025
ETHYLBENZENE	MG/KG	10	0.035	<0.025
TOTAL XYLENES	MG/KG	110	0.37	0.054

SURROGATE:

BROMOFLUOROBENZENE (%)

35*

98

94

*OUTSIDE ATI QUALITY CONTROL LIMITS DUE TO MATRIX INTERFERENCE

Test Method for
Oil and Grease and Petroleum Hydrocarbons
in Water and Soil

Perkin-Elmer Model 1600 FT-IR
Analysis Report

74/06/02 13:34

Sample identification

45329

Initial mass of sample, g

.990

Volume of sample after extraction, ml

28.000

Petroleum hydrocarbons, ppm


3382.929

Net absorbance of hydrocarbons (2930 cm⁻¹)

.410

Y: Petroleum hydrocarbons spectrum

13:34





Page _____ of _____

White - Testing Laboratory Canary - EPNG Lab Pink - Field Sampler

FIELD PIT REMEDIATION/CLOSURE FORM/PHASE II

Meter: 71816 Location: Jenna Pah No. 1

Coordinates: Letter: H Section: 36 Township: 28 Range: 7

Or Latitude _____ Longitude _____

Date Started : 11/16/95 Area: 03 Run: 82

Sample Number(s): JK140

Sample Depth: 19' Feet

Final PID Reading 208.0 PID Reading Depth 19 Feet

Yes No

Groundwater Encountered ☐ (1) ☒ (2) Approximate Depth _____ Feet

Final Dimensions: Length 19' Width 19' Depth 19'

Remediation Method :

Excavation ☒ (1) Approx. Cubic Yards 234 LT 12/1/95

Onsite Bioremediation ☐ (2)

Backfill Pit Without Excavation ☐ (3)

Overburden Cubic Yards 60 yds

Soil Disposition:

Envirotech ☒ (1) ☐ (3) Tierra

Other Facility ☐ (2) Name: _____

Pit Closure Date: 11-17-95 LT 12/1/95 Pit Closed By: Philip

Remarks : Pit PID Readings (N-89.5)(S-25.2)(E-16.4)(W-16.1)

Less Than 100' From Ephemeral Stream.

No Fence EPNB Alton James on site

Signature of Specialist: James R. King

El Paso Natural Gas Company

FIELD SERVICES LABORATORY

ANALYTICAL REPORT

PIT CLOSURE PROJECT - Soil Samples Inside the GWV Zone

SAMPLE IDENTIFICATION

	Field ID	Lab ID
SAMPLE NUMBER:	JK140	947790
MTR CODE SITE NAME:	71816	Jenna Pah No.1
SAMPLE DATE TIME (Hrs):	11-16-95	1130
PROJECT:	Phase I Navajo	
DATE OF TPH EXT. ANAL.:	11/17/95	
DATE OF BTEX EXT. ANAL.:	11/20/95	11/20/95
TYPE DESCRIPTION:	VG	Brown Sand

Field Remarks: .

RESULTS

PARAMETER	RESULT	UNITS	QUALIFIERS			
			DF	Q	M(g)	V(ml)
BENZENE	< 0.5	MG/KG				
TOLUENE	4.4	MG/KG				
ETHYL BENZENE	5.7	MG/KG				
TOTAL XYLENES	48.5	MG/KG				
TOTAL BTEX	58.6	MG/KG				
TPH (418.1)	828	MG/KG			2.05	28
HEADSPACE PID	208	PPM				
PERCENT SOLIDS	77.6	%				


-- TPH is by EPA Method 418.1 and BTEX is by EPA Method 8020 --

The Surrogate Recovery was at
Narrative:

103%

for this sample All QA/QC was acceptable.

DF = Dilution Factor Used

Approved By: 

Date: 11/21/95

BTEX SOIL SAMPLE WORKSHEET

File	:	947790	Date Printed	:	11/21/95
Soil Mass (g)	:	5.10	Multiplier (L/g)	:	0.00098
Extraction vol. (mL)	:	10	CAL FACTOR (Analytical):	:	200
Shot Volume (uL)	:	50	CAL FACTOR (Report):	:	0.19608

		DILUTION FACTOR:	1	Det. Limit
Benzene (ug/L)	:	0.00	Benzene (mg/Kg):	0.000 0.490
Toluene (ug/L)	:	22.43	Toluene (mg/Kg):	4.398 0.490
Ethylbenzene (ug/L)	:	29.32	Ethylbenzene (mg/Kg):	5.749 0.490
p & m-xylene (ug/L)	:	197.42	p & m-xylene (mg/Kg):	38.710 0.980
o-xylene (ug/L)	:	49.75	o-xylene (mg/Kg):	9.755 0.490
			Total xylenes (mg/Kg):	48.465 1.471
			Total BTEX (mg/Kg):	58.612

EL PASO NATURAL GAS


EPA METHOD 8020 - BTEX SOILS

File : C:\LABQUEST\CHROM001\112095-2.022
 Method : C:\LABQUEST\METHODS\1-112095.MET
 Sample ID : 947790,5.10G,50U
 Acquired : Nov 21, 1995 04:44:04
 Printed : Nov 21, 1995 05:10:33
 User : MARLON

Channel A Results

COMPONENT	RET TIME	AREA	CONC (ug/L)
BENZENE	5.603	0	0.0000
TOLUENE	9.713	6451324	22.4339
ETHYLBENZENE	13.857	7569423	29.3195
M & P XYLENE	14.250	59948040	197.4217
O XYLENE	15.373	12657514	49.7518
BFB	16.957	68031680	103.3437

C:\LABQUEST\CHROM001\112095-2.022 - Channel A



Test Method for
Oil and Grease and Petroleum Hydrocarbons
in Water and Soil
Perkin-Elmer Model 1600 FT-IR
Analysis Report

95/11/17 16:33


Sample identification
747790

Initial mass of sample, g
.050

Volume of sample after extraction, ml
8.000

Petroleum hydrocarbons, ppm
827.542

Net absorbance of hydrocarbons (2930 cm^{-1})
.113



BTEX SOIL SAMPLE WORKSHEET

File	:	947790	Date Printed	:	11/21/95
Soil Mass (g)	:	5.10	Multiplier (L/g)	:	0.00098
Extraction vol. (mL)	:	10	CAL FACTOR (Analytical):	:	400
Shot Volume (uL)	:	25	CAL FACTOR (Report):	:	0.39216

		DILUTION FACTOR:	2	Det. Limit
Benzene (ug/L)	:	0.00	Benzene (mg/Kg):	0.000 0.980
Toluene (ug/L)	:	10.88	Toluene (mg/Kg):	4.267 0.980
Ethylbenzene (ug/L)	:	11.29	Ethylbenzene (mg/Kg):	4.427 0.980
p & m-xylene (ug/L)	:	97.57	p & m-xylene (mg/Kg):	38.263 1.961
o-xylene (ug/L)	:	25.20	o-xylene (mg/Kg):	9.882 0.980
			Total xylenes (mg/Kg):	48.145 2.941
			Total BTEX (mg/Kg):	56.839


EL PASO NATURAL GAS

EPA METHOD 8020 - BTEX SOILS

File : C:\LABQUEST\CHROM001\112095-2.021
 Method : C:\LABQUEST\METHODS\1-112095.MET
 Sample ID : 947790,5.10G,25U
 Acquired : Nov 21, 1995 04:04:55
 Printed : Nov 21, 1995 04:31:22
 User : MARLON

Channel A Results

COMPONENT	RET TIME	AREA	CONC (ug/L)
BENZENE	5.603	0	0.0000
TOLUENE	9.713	3036492	10.8803
ETHYLBENZENE	13.857	2738793	11.2927
M & P XYLENE	14.240	30203248	97.5742
O XYLENE	15.367	5965838	25.1995
BFB	16.957	64555352	98.0630





Page

White • Testing Laboratory Canary • EPNG Lab Pink • Field Sampler

APPENDIX C
SOIL BORING SAMPLE RESULTS
(1997)



EL PASO FIELD SERVICES
FIELD SERVICES LABORATORY

ANALYTICAL REPORT
PIT CLOSURE PROJECT

SAMPLE IDENTIFICATION

	Field ID	Lab ID
SAMPLE NUMBER:	DRC6	970112
MTR CODE SITE NAME:	71816	Jennapha #1
SAMPLE DATE TIME (Hrs):	2/14/97	900
PROJECT:	PHASE IIIDrilling 20-22'	
DATE OF TPH EXT. ANAL.:	2/24/97	2/24/97
DATE OF BTEX EXT. ANAL.:	2/26/97	2/26/97
TYPE DESCRIPTION:	VG	Brown sand

Field Remarks: _____

RESULTS

PARAMETER	RESULT	UNITS	QUALIFIERS			
			DF	Q	M(g)	V(ml)
BENZENE	<0.5	MG/KG				
TOLUENE	<0.5	MG/KG				
ETHYL BENZENE	<0.5	MG/KG				
TOTAL XYLENES	<1.5	MG/KG				
TOTAL BTEX	<3	MG/KG				
TPH (418.1)	311	MG/KG				
HEADSPACE PID	2000 +	PPM				
PERCENT SOLIDS	96.5	%				

— TPH is by EPA Method 418.1 and BTEX is by EPA Method 8020 —

The Surrogate Recovery was at 98.1 % for this sample All QA/QC was acceptable.

Narrative:

Headspace reading was overrange.

DF = Dilution Factor Used

Approved By: John Savicki

INGVZPIT.XLS

Date: 3-4-97

BTEX SOIL SAMPLE WORKSHEET

File	:	970112	Date Printed	:	3/4/97
Soil Mass (g)	:	5.34	Multiplier (L/g)	:	0.00094
Extraction vol. (mL)	:	10	CAL FACTOR (Analytical):	:	200
Shot Volume (uL)	:	50	CAL FACTOR (Report):	:	0.18727

		DILUTION FACTOR:	1	Det. Limit
Benzene (ug/L)	:	0.00	Benzene (mg/Kg):	0.000 0.468
Toluene (ug/L)	:	0.00	Toluene (mg/Kg):	0.000 0.468
Ethylbenzene (ug/L)	:	0.00	Ethylbenzene (mg/Kg):	0.000 0.468
p & m-xylene (ug/L)	:	2.67	p & m-xylene (mg/Kg):	0.500 0.936
o-xylene (ug/L)	:	6.57	o-xylene (mg/Kg):	1.230 0.468
			Total xylenes (mg/Kg):	1.730 1.404
			Total BTEX (mg/Kg):	1.730

EL PASO FIELD SERVICES LABORATORY

EPA METHOD 8020 - BTEX

File : C:\LABQUEST\CHROM000\022697-0.004
 Method : C:\LABQUEST\METHODS\0-013197.MET
 Sample ID : 970112,5.34G,50U
 Acquired : Feb 26, 1997 12:50:31
 Printed : Feb 26, 1997 13:20:59
 User : MARLON


Channel A Results

COMPONENT	RET TIME	AREA	CONC (ug/L)
BENZENE	7.800	0	0.0000
a,a,a-TFT	10.063	1946979	89.0386
TOLUENE	12.470	0	0.0000
ETHYLBENZENE	16.700	20378	0.9270
M,P-XYLENES	17.253	86794	2.6655
O-XYLENE	18.250	179474	6.5656
BFB	19.567	8045092	98.1185

Channel A Group Results

COMPONENT	RET TIME	AREA	CONC (ug/L)
TOTAL XYLENES		266269	9.2311

C:\LABQUEST\CHROM000\022697-0.004 -- Channel A



Test Method for
Oil and Grease and Petroleum Hydrocarbons
in Water and Soil

Perkin-Elmer Model 1600 FT-IR
Analysis Report

97/02/24 13:50

Sample identification

970112

Initial mass of sample, g

2.370

Volume of sample after extraction, ml

28.000

Petroleum hydrocarbons, ppm


310.520

Net absorbance of hydrocarbons (2930 cm⁻¹)

0.047

Y: Petroleum hydrocarbons spectrum

13:50





A 2234

CHAIN OF CUSTODY RECORD

[illegible]

APPENDIX D
MONITORING WELL BORELOGS
AND WELL CONSTRUCTION FORMS
(1997, 1999)

MONITORING WELL INSTALLATION RECORD

Philip Environmental Services, Inc.
4000 Monroe Rd.
Farmington, NM 87401
(505) 326-2262 FAX (505) 326-2388

Borehole # 1
Well # 1
Page 1 of 1


Project Name EPFS GW PITS
Project Number 17520 Phase 6005.77
Site Location JENNAPPAH #1
71810

Elevation _____
Well Location H/536/T28/R9
GWL Depth 22' BES
Installed By M. McNUHUE

On-Site Geologist D. CESARK
Personnel On-Site D. CHARLEY
Contractors On-Site _____
Client Personnel On-Site _____

Date/Time Started 2-14-17/0930
Date/Time Completed 11/1130

Depths in Reference to Ground Surface		
Item	Material	Depth (feet)
Top of Protective Casing		
Bottom of Protective Casing		
Top of Permanent Borehole Casing		N/A
Bottom of Permanent Borehole Casing		N/A
Top of Concrete		
Bottom of Concrete		
Top of Grout		-0'
Bottom of Grout		-12'
Top of Well Riser	4" 40 P/C	+3'
Bottom of Well Riser	"	-17'
Top of Well Screen	1" 65 S/L	-17'
Bottom of Well Screen	"	-32'
Top of Peltonite Seal	ENHANCED	-12'
Bottom of Peltonite Seal	"	-14'
Top of Gravel Pack	16-20 SAND	-14'
Bottom of Gravel Pack	"	-32'
Top of Natural Cave-In		-32'
Bottom of Natural Cave-In		-32'
Top of Groundwater		-22'
Total Depth of Borehole		-32'



Comments: _____

[Signature]

RECORD OF SUBSURFACE EXPLORATION

PHILIP ENVIRONMENTAL SERVICES INC.

4000 Monroe Road

Farmington, New Mexico 87401

(505) 326-2262 FAX (505) 326-2388

Borehole # BH-

Well #

Page 1 of 1



Project Name

EPFS GW PITS

Project Number

17520

Phase

6001.77

Project Location

JENNIFER #1 - 71816

Elevation

Borehole Location

LH-536 T28-R9

GWL Depth

22' BES

Logged By

D Cesark

Drilled By

M Donohue

Date/Time Started

2/14/97 - 0830

Date/Time Completed

1130

Well Logged By

D Cesark

Personnel On-Site

D. CHAPLEY

Contractors On-Site

Client Personnel On-Site

Drilling Method

4 1/4" ID HSA

Air Monitoring Method

PID, CGI

Depth (Feet)	Sample Number	Sample Interval	Sample Type & Recovery (inches)	Sample Description Classification System: USCS	USCS Symbol	Depth Lithology Change (feet)	Air Monitoring Units: PPM			Drilling Conditions & Blow Counts
							BZ	BH	S/H	
0				BACKFILL						TIME
5				TC						
10				19'						
15										
20	1	20'-22'-24"	24"	SILTY SAND, SAND SILT						
25	1	23'-25'-27"	24"	MIXTURE. HC STAINING						
				(OLIVE GRAY) + STRONG HC						
				ODOR. GW @ 22' BES.						
30				OVER-DRILLED THROUGH						
				HEAVY CONTAMINATED SOIL						
				(BLACK) w/ STRONG HC						
35				ODOR TO 32' BES. SET						
				WELL						
40										

Comments:

TD = 32'. GW ENCOUNTERED @ 22' BES. DRC @ COLLECTED IMMEDIATELY.
ABOVE GW SUBMITTED TO LAB FOR TPH & BTEX ANALYSES.
BORING COMPLETED AS A WELL - PLEASE REFER TO MW INST. RECORD

Geologist Signature

[Signature]

MONITORING WELL INSTALLATION RECORD

Environmental Services Corp.

Monroe Road

Alamogordo, New Mexico 87401

326-2262 FAX (505) 326-2388

Borehole # 2
Well # MW 2
Page 1 of 1

Project Name EPFS GW Inv.

Project Number 20990 Phase 100%

Project Location Jennepath #1

On-Site Geologist P. Chancy

Personnel On-Site K. Padilla, A. Padilla

Contractors On-Site -

Client Personnel On-Site -

Location -

Depth 22


Drilled By K. Padilla

Time Started 5/4/99

Time Completed 5/4/99

Depths in Reference to Ground Surface

Item	Material	Depth
Top of Protective Casing		N.A.
Bottom of Protective Casing		N.A.
Top of Permanent Borehole Casing		N.A.
Bottom of Permanent Borehole Casing		N.A.
Top of Concrete		N.A.
Bottom of Concrete		N.A.
Top of Grout		N.A.
Bottom of Grout		N.A.
Top of Well Fiser		+1
Bottom of Well Fiser		15
Top of Well Screen		15
Bottom of Well Screen		30
Top of Peltonite Seal		N.A.
Bottom of Peltonite Seal		N.A.
Top of Gravel Pack		13
Bottom of Gravel Pack		30
Top of Natural Cave-In		N.A.
Bottom of Natural Cave-In		N.A.
Top of Groundwater		22
Total Depth of Borehole		30



Comments: Temporary Completion

Geologist Signature

Paul Chancy

RECORD OF SUBSURFACE EXPLORATION

Philip Environmental Services Corp.

4000 Morroe Road

Farmington, New Mexico 87401

(505) 326-2262 FAX (505) 326-2388

Borehole #

2

Well #

MW-2

Page

1

of

1

Project Name

Project Number

Project Location

Phase

Jennapch

Well Logged By

P. Cheney

Personnel On-Site

K. Padilla, D. Padilla

Contractors On-Site

Client Personnel On-Site

Drilling Method

4 1/2" ID HSA

Air Monitoring Method

PID

Elevation

Borehole Location

GWL Depth

22.5'

Logged By

P. Cheney

Drilled By

K. Padilla

Date/Time Started

5/4/99

Date/Time Completed

5/4/99 - temp. completion

Depth (Feet)	Sample Interval	Sample Type & Recovery (Inches)	Sample Description Classification System: USCS	USCS Symbol	Depth Lithology Change (feet)	Air Monitoring Units: NDU			Drilling Conditions & Blow Counts
						BZ	BH	SS	
0			Surface: reddish yellow medium grained sand, unconsolidated			0			
5			5' (from cuttings) med. grained reddish brown sand, unconsolidated, damp						
10	10-12	20"	med. to coarse grained sand, reddish brown w/pea gravel			0			BC = 14 S/H5 = 0.1
15	15-17		reddish brown sandy clay w/ limonite staining. Moist, low plasticity, soft			0			BC = 14 S/H5 = 0.6
20	20-22		reddish brown coarse sand, unconsolidated			0			BC = 24 S/H5 = 0.3
25	25-27		yellowish brown coarse sand, unconsolidated, wet at 25'. Water level rose to 22.5' after five minutes			0			BC = 15 S/H5 = 0.7
30			TD = 30'						
35									
40									

Comments:

Saturated at 25'. After $\approx$ 5 minutes, WL rose to 22.5'. Set temp. well with 15' screen, 15' riser. Sand packs to 13' (open BH to surface. Bailed 10 gallons from well)

Geologist Signature

Paul Cheney

MONITORING WELL INSTALLATION RECORD

Phillip Environmental Services Corp.
 1000 Marvot Road
 Farmington, New Mexico 87401
 (505) 326-2262 FAX (505) 326-2388

Borehole # 3
 Well # MW-3
 Page 1 of 1

Project Name EPFS GW Inv.

Project Number 20990 Phase 1000


Project Location Jennepah #1

On-Site Geologist P. Cheney
 Personnel On-Site K. Padilla, D. Padilla
 Contractors On-Site _____
 Client Personnel On-Site _____

Elevation _____
 Well Location _____
 SWL Depth 23
 Installed By K. Padilla

Date/Time Started 5/4/99
 Date/Time Completed 5/4/99

Depths in Reference to Ground Surface		
Item	Material	Depth
Top of Protective Casing		N.A.
Bottom of Protective Casing		N.A.
Top of Permanent Borehole Casing		N.A.
Bottom of Permanent Borehole Casing		N.A.
Top of Concrete		N.A.
Bottom of Concrete		N.A.
Top of Grout		N.A.
Bottom of Grout		N.A.
Top of Well Riser		+1
Bottom of Well Riser		15
Top of Well Screen		15
Bottom of Well Screen		30
Top of Peltonite Seal		N.A.
Bottom of Peltonite Seal		N.A.
Top of Gravel Pack		13
Bottom of Gravel Pack		30
Top of Natural Cave-In		N.A.
Bottom of Natural Cave-In		N.A.
Top of Groundwater		23
Total Depth of Borehole		30



Comments: Temporary Completion

Geologist Signature

Paul Cheney

RECORD OF SUBSURFACE EXPLORATION

Philip Environmental Services Corp.

4000 Monroe Road

Farmington, New Mexico 87401

(505) 326-2282 FAX (505) 326-2388

Borehole #

3

Well #

MW-3

Page

of

Project Name

EPFS

Project Number

Phase

Project Location

Jenhepah #1

Well Logged By

P. Cheney

Personnel On-Site

K. Padilla, A. Padilla

Contractors On-Site

Client Personnel On-Site

Drilling Method

4 1/2" HSA

Air Monitoring Method

PIB

Elevation

Borehole Location

GWL Depth

Logged By

P. Cheney

Drilled By

K. Padilla

Date/Time Started

5/4

Date/Time Completed

5/4

Depth (Feet)	Sample Interval	Sample Type & Recovery (inches)	Sample Description Classification System: USCS	USCS Symbol	Depth Lithology Change (feet)	Air Monitoring Units: NDU			Drilling Conditions & Blow Counts
						BZ	BH	SS	
0			surface: reddish yellow medium grained sand						
5			5' (from cuttings) reddish brown sand, unconsolidated						
10	1-10 1-12	2.1"	yellowish brown med. grained sand, unconsolidated			0		0	BC = 22 S/Hs = 5.4
15	2-15 2-17	18"	yellowish brown medium grained sand			0		0	BC = 20 S/Hs = 3.2
20	3-20 3-22	18"	yellowish brown coarse grained sand, $\approx$ 5% pea-gravel			0		0	BC = 21 S/Hs = 1
25	25-27	2.1"	very coarse grained yellowish brown sand. Saturated at 25' several 1" x 1 1/4" gravel rocks TD = 30'						
30									
35									
40									


Comments:

Saturated at 25' WL Rose to $\approx$ 23' after 5 minutes. Set run well
with 15' screen, 15' riser, sand pack to 13' open bit to surface. used 5 gallon
bucket as a well protector

Geologist Signature

Paul Cheney

APPENDIX E
ORC INJECTION BORLOGS AND LOCATION MAP
(1998)



LEGEND

- ORG Location
- e MW-1 APPROXIMATE MONITORING WELL LOCATION AND NUMBER
- B BENZENE (ug\L)
- T TOLUENE (ug\L)
- E ETHYL BENZENE (ug\L)
- X XYLENE (ug\L)
- ug\L MICROGRAMS PER LITER

NOT TO SCALE



COL. 17520BN-001 PSC PHILIP SERVICES CORP.	TITLE:	JENNAPAH #1 71816	DWN: TMM	DES.: CC	PROJECT NO.: 17520 EPFS GW PITS
			CHKD: CC	APPD:	FIGURE 1
			DATE: 1/19/98	REV.: 0	

NUTRIENT INJECTION


PHILIP SERVICES CORP.

4000 Monroe Rd.

Farmington, NM 87401

(505) 326-2262 FAX (505) 326-2388

Project Name	<u>EPFS GW Pits</u>	BH #	<u>BH-1</u>
Project Number/Phase	<u>17520 9000</u>	BH Location	<u>SW of MW-1</u>
Driller	<u>K. Padilla</u>	Site Name	<u>Jennapah #1 71816</u>
Date/Time Started	<u>7/8/98</u>		
Date/Time Completed	<u>7/8/98</u>		



Comments: 10 pounds ORC 2 gal water. Bentonite seal hydrated w/ 5 gal potable water

Drillers Signature

Cory Chavez

NUTRIENT INJECTION

PHILIP SERVICES CORP.

4000 Monroe Rd.

Farmington, NM 87401

(505) 326-2262 FAX (505) 326-2388

Project Name

EPFS GLW PITS

Project Number/Phase

17520 9000

Driller

K. Padilla

Date/Time Started

7/8/98

Date/Time Completed

7/8/98

BH #

2

BH Location

SE of MW1

Site Name

Jennapah #1 71816

BOREHOLE

Ground Surface



Top of Grout

0'

Cement/Bentonite Grout
(5% Bentonite)



Top of Bentonite

19'

Bentonite Seal



Top of Slurry

21'

ORC Slurry



Top of Groundwater

22'

Depth of Borehole

27'

Comments:

10 pounds ORC 2 gal water Bentonite hydrated w/ 5 gal
potable water.

Drillers/Geologist Signature

Long Chen

NUTRIENT INJECTION

PHILIP SERVICES CORP.

4000 Monroe Rd.

Farmington, NM 87401

(505) 326-2262 FAX (505) 326-2388

Project Name EPFS GLW Pits
Project Number/Phase 17520 9000
Driller K. Padilla
Date/Time Started 7/8/98
Date/Time Completed 7/8/98

BH # 3
BH Location NW of MW1
Site Name Jennapah #1 7/8/6

BOREHOLE

Ground Surface →

Top of Grout 0'

Cement/Bentonite Grout
(5% Bentonite) →

Top of Bentonite 19'

Bentonite Seal →

Top of Slurry 21'

ORC Slurry →

Top of Groundwater 22'

Depth of Borehole 27'

Comments: 10 gal pounds ORC, 2 gal water. Seal hydrated w/ 5 gal potable water

Drillers/Geologist Signature

Cory Chavez

APPENDIX F
LABORATORY REPORTS
(2003)

(Page 1 of 2)

: Lisa Butts 4-7-04
(Date/Signature)

[illegible]

DATA VERIFICATION WORKSHEET

(Page 2 of 2)

Analytical Method: SW-846 8021B (BTEX) MWH Job Number: EPC-SJRB (Groundwater)

Laboratory: Accutest Batch Identification: T7132

Verification Criteria								
Sample ID	Jennapah MW-1	Jennapah MW-2	Jennapah MW-3	230304TB 01				
Lab ID	T7132-01	T7132-02	T7132-03	T7132-04				
Holding Time	A	A	A	A				
Analyte List	A	A	A	A				
Reporting Limits	A	A	A	A				
Surrogate Spike Recovery	A ¹	A	A	A				
Trip Blank	A	A	A	A				
Equipment Rinseate Blanks	N/A	N/A	N/A	N/A				
Field Duplicate/Replicate	N/A	N/A	N/A	N/A				
Initial Calibration	N	N	N	N				
Initial Calibration Verification (ICV)	N	N	N	N				
Continuing Calibration Verification (CCV)	N	N	N	N				
Method Blank	A	A	A	A				
Laboratory Control Sample (LCS)	A	A	A	A				
Laboratory Control Sample Duplicate (LCSD)	N	N	N	N				
Matrix Spike/Matrix Spike Dup. (MS/MSD)	N/A	N/A	N/A	N/A				
Retention Time Window	N	N	N	N				
Injection Time(s)	N	N	N	N				
Hardcopy vs. Chain-of-Custody	A	A	A	A				
EDD vs. Hardcopy	N	N	N	N				
EDD vs. Chain of Custody	N	N	N	N				

(a) List QC batch identification if different than Batch ID

A indicates verification criteria were met

A/L indicates verification criteria met based upon Laboratory's QC Summary Form

X indicates verification criteria were not met

N indicates data review were not a project specific requirement

N/A indicates criteria are not applicable for the specified analytical method or sample

N/R indicates data not available for review

NOTES:

- Surrogate percent recovery outside acceptance criteria for aaa-Trifluorotoluene @ 139% (80-126), indicating a possible high bias. Only one surrogate outside acceptance criteria, no data qualified.



04/06/04

Technical Report for

Montgomery Watson

EPFS San Juan Basin Groundwater Site

D-MWH-04-01-03-MSG-01

Accutest Job Number: T7132

Report to:

Montgomery Watson

brian.buttars@us.mwhglobal.com

ATTN: Brian Buttars

Total number of pages in report: 16



Test results contained within this data package meet the requirements of the National Environmental Laboratory Accreditation Conference and/or state specific certification programs as applicable.

A handwritten signature in black ink, appearing to read 'Ron Martino'.

Ron Martino
Laboratory Manager

This report shall not be reproduced, except in its entirety, without the written approval of Accutest Laboratories.

Table of Contents

Sections:

1
2
3
4

-1-

Section 1: Sample Summary	3
Section 2: Sample Results	4
2.1: T7132-1: JENNAPAH MW-1	4
2.2: T7132-2: JENNAPAH MW-2	5
2.3: T7132-3: JENNAPAH MW-3	6
2.4: T7132-4: 230304 TB01	7
Section 3: Misc. Forms	8
3.1: Chain of Custody	9
Section 4: GC Volatiles - QC Data (Accutest New Jersey)	12
4.1: Method Blank Summary	13
4.2: Blank Spike Summary	15
4.3: Matrix Spike/Matrix Spike Duplicate Summary	16

Sample Summary

Montgomery Watson

Job No: T7132

EPFS San Juan Basin Groundwater Site
Project No: D-MWH-04-01-03-MSG-01

Sample Number	Collected Date	Time By	Received	Matrix Code	Type	Client Sample ID
T7132-1	03/23/04	08:48 MN	03/24/04	AQ	Ground Water	JENNAPAH MW-1
T7132-2	03/23/04	08:00 MN	03/24/04	AQ	Ground Water	JENNAPAH MW-2
T7132-3	03/23/04	07:37 MN	03/24/04	AQ	Ground Water	JENNAPAH MW-3
T7132-4	03/23/04	00:00 MN	03/24/04	AQ	Trip Blank Water	230304 TB01

Report of Analysis

Page 1 of 1

2.1

2

Client Sample ID: JENNAPAH MW-1
 Lab Sample ID: T7132-1
 Matrix: AQ - Ground Water
 Method: SW846 8021B
 Project: EPFS San Juan Basin Groundwater Site

Date Sampled: 03/23/04
 Date Received: 03/24/04
 Percent Solids: n/a

Run #	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1	NP48409.D	1	04/05/04	ANJ	n/a	n/a	N:GNP2597
Run #2 ^a	NP48394.D	2.5	04/05/04	ANJ	n/a	n/a	N:GNP2597

Run #	Purge Volume
Run #1	5.0 ml
Run #2	5.0 ml

Purgeable Aromatics

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.053	ug/l	
108-88-3	Toluene	ND	1.0	0.14	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.029	ug/l	
1330-20-7	Xylenes (total)	22.0	1.0	0.082	ug/l	
95-47-6	o-Xylene	5.7	1.0	0.10	ug/l	
	m,p-Xylene	16.3	1.0	0.082	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
462-06-6	Fluorobenzene	86%	88%	72-130%
98-08-8	aaa-Trifluorotoluene	139% ^b	131% ^c	80-126%

(a) Confirmation run.

(b) Outside control limits due to matrix interference. Confirmed by reanalysis.

(c) Outside control limits due to matrix interference.

ND = Not detected MDL - Method Detection Limit
 RL = Reporting Limit
 E = Indicates value exceeds calibration range

J = Indicates an estimated value
 B = Indicates analyte found in associated method blank
 N = Indicates presumptive evidence of a compound

Report of Analysis

Page 1 of 1

Client Sample ID: JENNAPAH MW-2
 Lab Sample ID: T7132-2
 Matrix: AQ - Ground Water
 Method: SW846 8021B
 Project: EPFS San Juan Basin Groundwater Site

Date Sampled: 03/23/04
 Date Received: 03/24/04
 Percent Solids: n/a

	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1	NP48408.D	1	04/05/04	ANJ	n/a	n/a	N:GNP2597
Run #2							

	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.053	ug/l	
108-88-3	Toluene	ND	1.0	0.14	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.029	ug/l	
1330-20-7	Xylenes (total)	ND	1.0	0.082	ug/l	
95-47-6	o-Xylene	ND	1.0	0.10	ug/l	
	m,p-Xylene	ND	1.0	0.082	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
462-06-6	Fluorobenzene	88%		72-130%
98-08-8	aaa-Trifluorotoluene	102%		80-126%

ND = Not detected MDL - Method Detection Limit
 RL = Reporting Limit
 E = Indicates value exceeds calibration range

J = Indicates an estimated value
 B = Indicates analyte found in associated method blank
 N = Indicates presumptive evidence of a compound

Report of Analysis

Page 1 of 1

2.3

2

Client Sample ID: JENNAPAH MW-3

Lab Sample ID: T7132-3

Date Sampled: 03/23/04

Matrix: AQ - Ground Water

Date Received: 03/24/04

Method: SW846 8021B

Percent Solids: n/a

Project: EPFS San Juan Basin Groundwater Site

	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1	NP48407.D	1	04/05/04	ANJ	n/a	n/a	N:GNP2597
Run #2							

	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.053	ug/l	
108-88-3	Toluene	ND	1.0	0.14	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.029	ug/l	
1330-20-7	Xylenes (total)	ND	1.0	0.082	ug/l	
95-47-6	o-Xylene	ND	1.0	0.10	ug/l	
	m,p-Xylene	ND	1.0	0.082	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
462-06-6	Fluorobenzene	87%		72-130%
98-08-8	aaa-Trifluorotoluene	103%		80-126%

ND = Not detected MDL - Method Detection Limit

RL = Reporting Limit

E = Indicates value exceeds calibration range

J = Indicates an estimated value

B = Indicates analyte found in associated method blank

N = Indicates presumptive evidence of a compound

Report of Analysis

Page 1 of 1

Client Sample ID:	230304 TB01	Date Sampled:	03/23/04
Lab Sample ID:	T7132-4	Date Received:	03/24/04
Matrix:	AQ - Trip Blank Water	Percent Solids:	n/a
Method:	SW846 8021B		
Project:	EPFS San Juan Basin Groundwater Site		

	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1	NP48406.D	1	04/05/04	ANJ	n/a	n/a	N:GNP2597
Run #2							

	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.053	ug/l	
108-88-3	Toluene	ND	1.0	0.14	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.029	ug/l	
1330-20-7	Xylenes (total)	ND	1.0	0.082	ug/l	
95-47-6	o-Xylene	ND	1.0	0.10	ug/l	
	m,p-Xylene	ND	1.0	0.082	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
462-06-6	Fluorobenzene	87%		72-130%
98-08-8	aaa-Trifluorotoluene	102%		80-126%

ND = Not detected MDL - Method Detection Limit
 RL = Reporting Limit
 E = Indicates value exceeds calibration range

J = Indicates an estimated value
 B = Indicates analyte found in associated method blank
 N = Indicates presumptive evidence of a compound



Misc. Forms

Custody Documents and Other Forms

Includes the following where applicable:

- Chain of Custody



CHAIN OF CUSTODY 230304mm01

10165 Harwin Drive, Ste. 150, Houston, TX 77036
TEL: 713-271-4700 FAX: 713-271-4770
www.accuratest.com

FED-EX Tracking #
842152796850
Accurate! Quote #

Bottle Order Control #	
------------------------	--

Accutest Job # **T7132**

[illegible]

3.1 (b)

T7132: Chain of Custody

Page 1 of 3



9 of 16

ACCUTEST.
Laboratories

ACCUTEST.

SAMPLE RECEIPT LOG

JOB #:

T 7132

DATE/TIME RECEIVED: 3/24/09 1000

CLIENT: _____

3. Paso

INITIALS:



Condition/Variance (Circle "Y" for yes and "N" for no. If "N" is circled, see variance for explanation):

1. ☒ N Sample received in undamaged condition.
2. ☒ N Samples received within time range.
3. ☒ Y Sample received with proper pH.
4. ☒ N Sample received in proper containers.
5. ☒ N Sample volume sufficient for analysis.
6. ☒ N Sample received with chain of custody.
7. ☒ N Chain of Custody matches sample IDs on containers.
8. ☒ Y Custody seal received intact and tamper evident on cooler.
9. ☒ N Custody seal received intact and tamper evident on bottles.

[illegible]

LOCATION:	WI: Walk-In	VR: Volatile Refig.	SUB: Subcontract	EF: Encore Freezer
-----------	-------------	---------------------	------------------	--------------------

PRESERVATIVES: 1: None 2: HCL 3: HNO3 4: H2SO4 5: NaOH 6: Other

Comments:

pH of waters checked excluding volatiles

Delivery method: Couriers

Tracking#:

COOLER TEMP:

COOLER TEMP:

COOLER TEMP:

COOLER TEMP:

Method of sample disposal: (circle one)	AccuTest disposal	Hold	Return to Client
☐ AccuTest disposal ☐ Hold ☐ Return to Client			

Form: SM012

3.1 3

GC Volatiles

QC Data Summaries

(Accutest New Jersey)

Includes the following where applicable:

- Method Blank Summaries
- Blank Spike Summaries
- Matrix Spike and Duplicate Summaries

Method Blank Summary

Page 1 of 1

Job Number: T7132

Account: ALGC Accutest Laboratories Gulf Coast, Inc.

Project: MWHSLCUT: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GNP2597-MB2	NP48403.D	1	04/05/04	YHY	n/a	n/a	GNP2597

The QC reported here applies to the following samples:

Method: SW846 8021B

T7132-1, T7132-2, T7132-3, T7132-4

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.053	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.029	ug/l	
108-88-3	Toluene	ND	1.0	0.14	ug/l	
1330-20-7	Xylenes (total)	ND	1.0	0.082	ug/l	
95-47-6	o-Xylene	ND	1.0	0.10	ug/l	
	m,p-Xylene	ND	1.0	0.082	ug/l	

CAS No.	Surrogate Recoveries	Limits
462-06-6	Fluorobenzene	87% 72-130%
98-08-8	aaa-Trifluorotoluene	102% 80-126%

13 of 16

Method Blank Summary

Page 1 of 1

Job Number: T7132

Account: ALGC Accutest Laboratories Gulf Coast, Inc.

Project: MWHS LCUT: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GNP2597-MB	NP48390.D	1	04/05/04	YHY	n/a	n/a	GNP2597

The QC reported here applies to the following samples:

Method: SW846 8021B

GNP2597-BS, T7131-2MS, T7131-2MSD

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.053	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.029	ug/l	
108-88-3	Toluene	ND	1.0	0.14	ug/l	
1330-20-7	Xylenes (total)	ND	1.0	0.082	ug/l	
95-47-6	o-Xylene	ND	1.0	0.10	ug/l	
	m,p-Xylene	ND	1.0	0.082	ug/l	

CAS No.	Surrogate Recoveries	Limits
462-06-6	Fluorobenzene	88% 72-130%
98-08-8	aaa-Trifluorotoluene	103% 80-126%

14 of 14

Blank Spike Summary

Page 1 of 1

Job Number: T7132

Account: ALGC Accutest Laboratories Gulf Coast, Inc.

Project: MWHS LCUT: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GNP2597-BS	NP48391.D	1	04/05/04	YHY	n/a	n/a	GNP2597

The QC reported here applies to the following samples:

Method: SW846 8021B

T7132-1, T7132-2, T7132-3, T7132-4

CAS No.	Compound	Spike ug/l	BSP ug/l	BSP %	Limits
71-43-2	Benzene	5	4.2	84	82-111
100-41-4	Ethylbenzene	5	4.5	90	84-113
108-88-3	Toluene	5	4.5	90	78-118
1330-20-7	Xylenes (total)	15	13.6	91	84-116
95-47-6	o-Xylene	5	4.5	90	83-117
	m,p-Xylene	10	9.1	91	84-116

CAS No.	Surrogate Recoveries	BSP	Limits
462-06-6	Fluorobenzene	87%	72-130%
98-08-8	aaa-Trifluorotoluene	100%	80-126%

15 of 16

Matrix Spike/Matrix Spike Duplicate Summary

Page 1 of 1

Job Number: T7132

Account: ALGC Accutest Laboratories Gulf Coast, Inc.

Project: MWHS LCUT: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
T7131-2MS	NP48396.D	100	04/05/04	YHY	n/a	n/a	GNP2597
T7131-2MSD	NP48397.D	100	04/05/04	YHY	n/a	n/a	GNP2597
T7131-2	NP48392.D	100	04/05/04	YHY	n/a	n/a	GNP2597

The QC reported here applies to the following samples:

Method: SW846 8021B

T7132-1, T7132-2, T7132-3, T7132-4

CAS No.	Compound	T7131-2 ug/l	Q	Spike ug/l	MS ug/l	MS %	MSD ug/l	MSD %	RPD	Limits Rec/RPD
71-43-2	Benzene	13000		1000	13600	60* a	13600	60* a	0	69-134/13
100-41-4	Ethylbenzene	321		1000	1280	96	1270	95	1	74-128/11
108-88-3	Toluene	8880		1000	9660	78	9630	75	0	67-132/13
1330-20-7	Xylenes (total)	2850		3000	5720	96	5690	95	1	74-132/11
95-47-6	o-Xylene	472		1000	1430	96	1420	95	1	76-130/15
	m,p-Xylene	2380		2000	4290	96	4270	95	0	71-138/11

CAS No.	Surrogate Recoveries	MS	MSD	T7131-2	Limits
462-06-6	Fluorobenzene	90%	90%	90%	72-130%
98-08-8	aaa-Trifluorotoluene	105%	106%	106%	80-126%

(a) Outside control limits due to high level in sample relative to spike amount.

16 of 16



(Page 1 of 3)

Ligin Tuffaro 1-7-04
(Date/Signature)

[illegible]

DATA VALIDATION WORKSHEET

(Page 2 of 3)

Analytical Method: SW-846 8021B (BTEX) MWH Job Number: EPC-SJRB (Groundwater)

Laboratory: Accutest Batch Identification: T6395

Validation Criteria								
Sample ID	161203TB 01	Jennapah MW-2	Jennapah MW-3	Jennapah MW-1				
Lab ID	T6395-01	T6395-02	T6395-03	T6395-04				
Holding Time	A	A	A	A				
Analyte List	A	A	A	A				
Reporting Limits	A	A	A	A				
Surrogate Spike Recovery	A ¹	A ²	A ³	A ^{4,5}				
Trip Blank	A	A	A	A				
Equipment Rinseate Blanks	N/A	N/A	N/A	N/A				
Field Duplicate/Replicate	N/A	N/A	N/A	N/A				
Initial Calibration	N	N	N	N				
Initial Calibration Verification (ICV)	N	N	N	N				
Continuing Calibration Verification (CCV)	N	N	N	N				
Method Blank	A ⁶	A ⁶	A ⁶	A ^{6,7}				
Laboratory Control Sample (LCS)	A ^{8,9}	A ^{8,9}	A ^{8,9}	A ^{8,9,10,11}				
Laboratory Control Sample Duplicate (LCSD)	N	N	N	N				
Matrix Spike/Matrix Spike Dup. (MS/MSD)	N/A	N/A	N/A	A ^{12,13}				
Retention Time Window	N	N	N	N				
Injection Time(s)	N	N	N	N				
Hardcopy vs. Chain-of-Custody	A	A	A	A				
EDD vs. Hardcopy	N	N	N	N				
EDD vs. Chain of Custody	N	N	N	N				

(a) List QC batch identification if different than Batch ID

A indicates validation criteria were met

A/L indicates validation criteria met based upon Laboratory's QC Summary Form

X indicates validation criteria were not met

N indicates data review were not a project specific requirement

N/A indicates criteria are not applicable for the specified analytical method or sample

N/R indicates data not available for review

NOTES:

- Surrogate percent recovery for aaa-Trifluorotoluene outside acceptance criteria @ 131% (71-121), indicating a possible high bias. Only one surrogate outside acceptance criteria, no analytes detected in the sample, no data qualified.
- Surrogate percent recovery for aaa-Trifluorotoluene outside acceptance criteria @ 129% (71-121), indicating a possible high bias. Only one surrogate outside acceptance criteria, no analytes detected in the sample, no data qualified.
- Surrogate percent recovery for aaa-Trifluorotoluene outside acceptance criteria @ 126% (71-121), indicating a possible high bias. Only one surrogate outside acceptance criteria, no analytes detected in the sample, no data qualified.
- Surrogate percent recovery outside acceptance criteria for the following compounds:
 - 4-Bromofluorobenzene @ 125% (64-121), indicating a possible high bias. No analytes detected in the sample associated with Run #1, no data qualified.
 - aaa-Trifluorotoluene @ 191% (71-121), indicating a possible high bias. No analytes detected in the sample associated with Run #1, no data qualified.

DATA VALIDATION WORKSHEET

(Page 3 of 3)

- 5) Surrogate percent recovery for 4-Bromofluorobenzene outside acceptance criteria @ 122% (64-121), indicating a possible high bias. Only one surrogate outside acceptance criteria, no data qualified.
- 6) Surrogate percent recovery for aaa-Trifluorotoluene outside acceptance criteria @ 126% (71-121), indicating a possible high bias. Only one surrogate outside acceptance criteria, no analytes detected in the sample, no data qualified.
- 7) Surrogate percent recovery outside acceptance criteria for the following compounds:
 - a) 4-Bromofluorobenzene @ 137% (64-121), indicating a possible high bias. No analytes detected in the sample, no data qualified.
 - b) aaa-Trifluorotoluene @ 130% (71-121), indicating a possible high bias. No analytes detected in the sample, no data qualified.
- 8) Surrogate percent recovery for aaa-Trifluorotoluene outside acceptance criteria @ 126% (71-121), indicating a possible high bias. Only one surrogate outside acceptance criteria, no data qualified.
- 9) LCS percent recovery outside acceptance criteria for the following compounds (GKK338-BS):
 - a) Ethylbenzene @ 118% (82-115), indicating a possible high bias. Analyte not detected in associated samples, no data qualified.
 - b) Toluene @ 119% (77-116), indicating a possible high bias. Analyte not detected in associated samples, no data qualified.
 - c) o-Xylene @ 129% (78-114), indicating a possible high bias. Analyte not detected in associated samples, no data qualified.
- 10) Surrogate percent recovery outside acceptance criteria for the following compounds:
 - a) 4-Bromofluorobenzene @ 130% (64-121), indicating a possible high bias. This explains the high percent recovery for associated analytes, no data qualified.
 - b) aaa-Trifluorotoluene @ 124% (71-121), indicating a possible high bias. This explains the high percent recovery for associated analytes, no data qualified.
- 11) LCS percent recovery outside acceptance criteria for the following compounds (GKK339-BS):
 - a) Xylenes (total) @ 117% (79-115), indicating a possible high bias. Qualify associated sample hits with "J" flags indicating the data are estimated and possibly biased high.
 - b) o-Xylene @ 117% (78-114), indicating a possible high bias. Analyte not detected in associated samples, no data qualified.
 - c) m/p-Xylenes @ 117% (79-116), indicating a possible high bias. Qualify associated sample hits with "J" flags indicating the data are estimated and possibly biased high.
- 12) MS/MSD surrogate percent recoveries outside acceptance criteria for the following compounds:
 - a) 4-Bromofluorobenzene @ 135% & 133% (64-121), indicating a possible high bias. This helps to explain the high percent recovery for associated analytes, no data qualified.
 - b) aaa-Trifluorotoluene @ 171% & 168% (71-121), indicating a possible high bias. This helps to explain the high percent recovery for associated analytes, no data qualified.
- 13) MS/MSD percent recovery outside acceptance criteria for the following compounds:
 - a) Toluene @ 138% & 171% (64-120), indicating a possible high bias. Analyte not detected in associated samples, no data qualified.



Gulf Coast

01/07/04

Technical Report for

Montgomery Watson

EPFS San Juan Basin Groundwater Site

D-MWH-04-01-03-MSG-01

Accutest Job Number: T6395

Report to:

Montgomery Watson

brian.buttars@us.mwhglobal.com

ATTN: Brian Buttars

Total number of pages in report: 18



Test results contained within this data package meet the requirements of the National Environmental Laboratory Accreditation Conference and/or state specific certification programs as applicable.


Ron Martino
Laboratory Manager

This report shall not be reproduced, except in its entirety, without the written approval of Accutest Laboratories.

Table of Contents

Sections:

-1-

Section 1: Sample Summary	3
Section 2: Sample Results	4
2.1: T6395-1: 161203TB01	4
2.2: T6395-2: JENNAPAH MW-2	5
2.3: T6395-3: JENNAPAH MW-3	6
2.4: T6395-4: JENNAPAH MW-1	7
Section 3: Misc. Forms	8
3.1: Chain of Custody	9
Section 4: GC Volatiles - QC Data Summaries	12
4.1: Method Blank Summary	13
4.2: Blank Spike Summary	15
4.3: Matrix Spike/Matrix Spike Duplicate Summary	17

Sample Summary

Montgomery Watson

Job No: T6395

EPFS San Juan Basin Groundwater Site
Project No: D-MWH-04-01-03-MSG-01

Sample Number	Collected Date	Time By	Received	Matrix Code	Type	Client Sample ID
T6395-1	12/16/03	07:00 MN	12/18/03	AQ	Ground Water	161203TB01
T6395-2	12/16/03	09:25 MN	12/18/03	AQ	Ground Water	JENNAPAH MW-2
T6395-3	12/16/03	09:52 MN	12/18/03	AQ	Ground Water	JENNAPAH MW-3
T6395-4	12/16/03	10:40 MN	12/18/03	AQ	Ground Water	JENNAPAH MW-1

Report of Analysis

Page 1 of 1

Client Sample ID: 161203TB01
 Lab Sample ID: T6395-1
 Matrix: AQ - Ground Water
 Method: SW846 8021B
 Project: EPFS San Juan Basin Groundwater Site

Date Sampled: 12/16/03
 Date Received: 12/18/03
 Percent Solids: n/a

Run #	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1 ^a	KK006296.D	1	12/29/03	BC	n/a	n/a	GKK338
Run #2							

Run #	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.50	ug/l	
108-88-3	Toluene	ND	1.0	0.50	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.50	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	1.0	ug/l	
95-47-6	o-Xylene	ND	1.0	0.50	ug/l	
	m,p-Xylene	ND	2.0	1.0	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
460-00-4	4-Bromofluorobenzene	121%		64-121%
98-08-8	aaa-Trifluorotoluene	131% ^b		71-121%

(a) Confirmed by GC/MS

(b) High bias spike.

ND = Not detected MDL - Method Detection Limit
 RL = Reporting Limit
 E = Indicates value exceeds calibration range

J = Indicates an estimated value
 B = Indicates analyte found in associated method blank
 N = Indicates presumptive evidence of a compound

Report of Analysis

Client Sample ID: JENNAPAH MW-2
 Lab Sample ID: T6395-2
 Matrix: AQ - Ground Water
 Method: SW846 8021B
 Project: EPFS San Juan Basin Groundwater Site

Date Sampled: 12/16/03
 Date Received: 12/18/03
 Percent Solids: n/a

	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1 ^a	KK006298.D	1	12/30/03	BC	n/a	n/a	GKK338
Run #2							

	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.50	ug/l	
108-88-3	Toluene	ND	1.0	0.50	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.50	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	1.0	ug/l	
95-47-6	o-Xylene	ND	1.0	0.50	ug/l	
	m,p-Xylene	ND	2.0	1.0	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
460-00-4	4-Bromofluorobenzene	119%		64-121%
98-08-8	aaa-Trifluorotoluene	129% ^b		71-121%

(a) Confirmed by GC/MS

(b) High bias spike.

ND = Not detected MDL - Method Detection Limit
 RL = Reporting Limit
 E = Indicates value exceeds calibration range

J = Indicates an estimated value
 B = Indicates analyte found in associated method blank
 N = Indicates presumptive evidence of a compound

Report of Analysis

Client Sample ID:	JENNAPAH MW-3	Date Sampled:	12/16/03
Lab Sample ID:	T6395-3	Date Received:	12/18/03
Matrix:	AQ - Ground Water	Percent Solids:	n/a
Method:	SW846 8021B		
Project:	EPFS San Juan Basin Groundwater Site		

Run #	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1 ^a	KK006299.D	1	12/30/03	BC	n/a	n/a	GKK338
Run #2							

Run #	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.50	ug/l	
108-88-3	Toluene	ND	1.0	0.50	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.50	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	1.0	ug/l	
95-47-6	o-Xylene	ND	1.0	0.50	ug/l	
	m,p-Xylene	ND	2.0	1.0	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
460-00-4	4-Bromofluorobenzene	118%		64-121%
98-08-8	aaa-Trifluorotoluene	126% ^b		71-121%

(a) Confirmed by GC/MS

(b) High bias spike.

ND = Not detected MDL - Method Detection Limit
 RL = Reporting Limit
 E = Indicates value exceeds calibration range

J = Indicates an estimated value
 B = Indicates analyte found in associated method blank
 N = Indicates presumptive evidence of a compound

Report of Analysis

Page 1 of 1

Client Sample ID:	JENNAPAH MW-1	Date Sampled:	12/16/03
Lab Sample ID:	T6395-4	Date Received:	12/18/03
Matrix:	AQ - Ground Water	Percent Solids:	n/a
Method:	SW846 8021B		
Project:	EPFS San Juan Basin Groundwater Site		

Run #	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1 ^a	KK006300.D	1	12/30/03	BC	n/a	n/a	GKK338
Run #2	KK006316.D	10	12/30/03	BC	n/a	n/a	GKK339

Run #	Purge Volume
Run #1	5.0 ml
Run #2	5.0 ml

Purgeable Aromatics

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.50	ug/l	
108-88-3	Toluene	ND	1.0	0.50	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.50	ug/l	
1330-20-7	Xylenes (total)	19 ^b	30	10	ug/l	
95-47-6	o-Xylene	ND ^b	10	5.0	ug/l	
	m,p-Xylene	19 ^b	20	10	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
460-00-4	4-Bromofluorobenzene	125% ^c	122%	64-121%
98-08-8	aaa-Trifluorotoluene	191% ^c	119%	71-121%

(a) Confirmed by GC/MS

(b) Result is from Run# 2

(c) High bias spike.

ND = Not detected MDL - Method Detection Limit
 RL = Reporting Limit
 E = Indicates value exceeds calibration range

J = Indicates an estimated value
 B = Indicates analyte found in associated method blank
 N = Indicates presumptive evidence of a compound

Misc. Forms

Custody Documents and Other Forms

Includes the following where applicable:

- Chain of Custody



10165 Harwin Drive, Ste. 150, Houston, TX 77036
TEL: 713-271-4700 FAX: 713-271-4770
www.accufest.com

FED-EX Tracking #
842152945351
Accurate! Quote #

Bottle Order Control #

Acquired Job

T6395

[illegible]

دے

6

T6395: Chain of Custody

Page 1 of 3

ACCUTEST

VARIANCE MEMO
SAMPLE LOG-IN

SAMPLE(S)
PROJECT
FILED BY

DATE **12-18-03**
LAB NO. **T6395**

VARIANCE - Check applicable items(s):

☐ Insufficient sample sent for proper analysis; received approx. **1 of 2**
☐ Sample bottles received broken and/or cap not intact for **Sx # 2 (Jennapsh MW-3)**
☐ Samples received without paperwork; paperwork received without samples.
☐ Samples received without proper refrigeration, when it has been deemed necessary. Temperature at receipt: _____
☐ Illegible sample number or label missing from bottle.
☐ Numbers on sample not the same as numbers on paper work.
☐ Incomplete instructions received with sample(s) i.e., no request for analysis, no chain of custody, incomplete billing instructions, no due date, etc. Temperature at receipt: _____
☐ Samples received in improper container or lacking proper preservation.
☐ Physical characteristics different than those on sampling sheets; Describe: _____
☐ Rush samples on hold because of incomplete paperwork.
☐ Other (specify) _____

CORRECTIVE ACTION TAKEN

☒ Person Contacted
☐ Client informed verbally.
☐ Client informed by memo/letter.
☐ Samples processed as is.
☐ Samples preserved by lab.
☐ Client will resample and resubmit.

☒ By phone.
☐ Samples processed for information only and noted on report.
☐ Samples processed with higher detection limits accepted.
☐ Samples rejected.

Notes: **left message**

ROUTING

TITLE	DATE	INITIALS	CORRECTED?
Sample Manager:	12-18-03	MS	
Login:			
Project Manager:	12-18-03	KS	
Comments:			

T6395: Chain of Custody
Page 3 of 3

GC Volatiles

QC Data Summaries

Includes the following where applicable:

- Method Blank Summaries
- Blank Spike Summaries
- Matrix Spike and Duplicate Summaries

Method Blank Summary

Page 1 of 1

Job Number: T6395

Account: MWHSLCUT Montgomery Watson

Project: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GKK338-MB	KK006295.D1		12/29/03	BC	n/a	n/a	GKK338

The QC reported here applies to the following samples:

Method: SW846 8021B

T6395-1, T6395-2, T6395-3, T6395-4

CAS No.	Compound	Result	RL	MDL	Units	Q
71-43-2	Benzene	ND	1.0	0.50	ug/l	
100-41-4	Ethylbenzene	ND	1.0	0.50	ug/l	
108-88-3	Toluene	ND	1.0	0.50	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	1.0	ug/l	
95-47-6	o-Xylene	ND	1.0	0.50	ug/l	
	m,p-Xylene	ND	2.0	1.0	ug/l	

CAS No.	Surrogate Recoveries	Limits
460-00-4	4-Bromofluorobenzene	118% 64-121%
98-08-8	aaa-Trifluorotoluene	126%* ^a 71-121%

(a) High bias spike.

Method Blank Summary

Page 1 of 1

Job Number: T6395
Account: MWHSLCUT Montgomery Watson
Project: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GKK339-MB	KK006315.D1		12/30/03	BC	n/a	n/a	GKK339

The QC reported here applies to the following samples:

Method: SW846 8021B

T6395-4

CAS No.	Compound	Result	RL	MDL	Units	Q
1330-20-7	Xylenes (total)	ND	3.0	1.0	ug/l	
95-47-6	o-Xylene	ND	1.0	0.50	ug/l	
	m,p-Xylene	ND	2.0	1.0	ug/l	

CAS No.	Surrogate Recoveries	Limits
460-00-4	4-Bromofluorobenzene	137%* a 64-121%
98-08-8	aaa-Trifluorotoluene	130%* a 71-121%

(a) High bias spike.

Blank Spike Summary

Page 1 of 1

Job Number: T6395
Account: MWHSLCUT Montgomery Watson
Project: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GKK338-BS ^a	KK006294.D1		12/29/03	BC	n/a	n/a	GKK338

The QC reported here applies to the following samples:

Method: SW846 8021B

T6395-1, T6395-2, T6395-3, T6395-4

CAS No.	Compound	Spike ug/l	BSP ug/l	BSP %	Limits
71-43-2	Benzene	20	21.6	108	74-119
100-41-4	Ethylbenzene	20	23.5	118*	82-115
108-88-3	Toluene	20	23.7	119*	77-116
1330-20-7	Xylenes (total)	60	68.7	115	79-115
95-47-6	o-Xylene	20	25.8	129*	78-114
	m,p-Xylene	40	42.9	107	79-116

CAS No.	Surrogate Recoveries	BSP	Limits
460-00-4	4-Bromofluorobenzene	121%	64-121%
98-08-8	aaa-Trifluorotoluene	126%* ^b	71-121%

(a) High bias spike but no compound were reported with it's associated samples.

(b) High bias spike.

Blank Spike Summary

Page 1 of 1

Job Number: T6395
Account: MWHSLCUT Montgomery Watson
Project: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GKK339-BS ^a	KK006313.D1		12/30/03	BC	n/a	n/a	GKK339

The QC reported here applies to the following samples:

Method: SW846 8021B

T6395-4

CAS No.	Compound	Spike ug/l	BSP ug/l	BSP %	Limits
1330-20-7	Xylenes (total)	60	70.3	117*	79-115
95-47-6	o-Xylene	20	23.4	117*	78-114
	m,p-Xylene	40	46.9	117*	79-116

CAS No.	Surrogate Recoveries	BSP	Limits
460-00-4	4-Bromofluorobenzene	130%* ^a	64-121%
98-08-8	aaa-Trifluorotoluene	124%* ^a	71-121%

(a) High bias spike.

Matrix Spike/Matrix Spike Duplicate Summary

Page 1 of 1

Job Number: T6395
Account: MWHSLCUT Montgomery Watson
Project: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
T6395-4MS	KK006301.D 1		12/30/03	BC	n/a	n/a	GKK338
T6395-4MSD	KK006302.D 1		12/30/03	BC	n/a	n/a	GKK338
T6395-4 ^a	KK006300.D 1		12/30/03	BC	n/a	n/a	GKK338

The QC reported here applies to the following samples:

Method: SW846 8021B

T6395-1, T6395-2, T6395-3, T6395-4

CAS No.	Compound	T6395-4 ug/l	Q	Spike ug/l	MS ug/l	MS %	MSD ug/l	MSD %	RPD	Limits Rec/RPD
71-43-2	Benzene	ND		20	22.6	113	22.4	112	1	64-124/16
100-41-4	Ethylbenzene	ND		20	21.9	110	30.5	153*	33*	64-123/14
108-88-3	Toluene	ND		20	27.5	138*	34.1	171*	21*	64-120/13
1330-20-7	Xylenes (total)	<i>Not Applicable</i>		60	96.0	94	105	109	9	66-118/18
95-47-6	o-Xylene	39		20	34.2	-26*	37.0	-12*	8	65-119/20
	m,p-Xylene	ND		40	61.8	155*	68.1	170*	10	66-120/14

CAS No.	Surrogate Recoveries	MS	MSD	T6395-4	Limits
460-00-4	4-Bromofluorobenzene	135%* ^b	133%* ^b	125%* ^b	64-121%
98-08-8	aaa-Trifluorotoluene	171%* ^b	168%* ^b	191%* ^b	71-121%

(a) Confirmed by GC/MS

(b) High bias spike.

Matrix Spike/Matrix Spike Duplicate Summary

Page 1 of 1

Job Number: T6395
Account: MWHSLCUT Montgomery Watson
Project: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
T6396-4MS ^a	KK006320.D	100	12/30/03	BC	n/a	n/a	GKK339
T6396-4MSD	KK006321.D	100	12/30/03	BC	n/a	n/a	GKK339
T6396-4 ^b	KK006319.D	100	12/30/03	BC	n/a	n/a	GKK339

The QC reported here applies to the following samples:

Method: SW846 8021B

T6395-4

CAS No.	Compound	T6396-4 ug/l	Q	Spike ug/l	MS ug/l	MS %	MSD ug/l	MSD %	RPD	Limits Rec/RPD
1330-20-7	Xylenes (total)	219	J	6000	6220	96	6870	107	10	66-118/18
95-47-6	o-Xylene	ND		2000	2010	101	2190	110	9	65-119/20
	m,p-Xylene	219		4000	4220	94	4680	106	10	66-120/14

CAS No.	Surrogate Recoveries	MS	MSD	T6396-4	Limits
460-00-4	4-Bromofluorobenzene	124%*	119%	125%* ^c	64-121%
98-08-8	aaa-Trifluorotoluene	4%*	111%	117%	71-121%

(a) High RPD due to poor purging of the MS.

(b) Confirmed by GC/MS. Samples were not preserved.

(c) High bias spike.

(Page 1 of 2)

By Travis Butters 9-30-03
(Date/Signature)

[illegible]

DATA VALIDATION WORKSHEET

(Page 2 of 2)

Analytical Method: SW-846 8021B (BTEX) MWH Job Number: EPC-SJRB (Groundwater)

Laboratory: Accutest Batch Identification: T5436

Validation Criteria								
Sample ID	Jennapah MW-1	230903TB 01						
Lab ID	T5436-01	T5436-02						
Holding Time	A	A						
Analyte List	A	A						
Reporting Limits	A	A						
Trip Blank	A	A						
Equipment Rinseate Blanks	N/A	N/A						
Field Duplicate/Replicate	N/A	N/A						
Surrogate Spike Recovery	A	A						
Initial Calibration	N	N						
Initial Calibration Verification (ICV)	N	N						
Continuing Calibration Verification (CCV)	N	N						
Laboratory Control Sample (LCS)	A	A						
Laboratory Control Sample Duplicate (LCSD)	N	N						
Method Blank	A	A						
Matrix Spike/Matrix Spike Dup. (MS/MSD)	N/A	N/A						
Retention Time Window	N	N						
Injection Time(s)	N	N						
Hardcopy vs. Chain-of-Custody	A	A						
EDD vs. Hardcopy	N	N						
EDD vs. Chain of Custody	N	N						

(a) List QC batch identification if different than Batch ID

A indicates validation criteria were met

A/L indicates validation criteria met based upon Laboratory's QC Summary Form

X indicates validation criteria were not met

N indicates data review were not a project specific requirement

N/A indicates criteria are not applicable for the specified analytical method or sample

N/R indicates data not available for review

NOTES:

Laboratories

CHAIN OF CUSTODY # 230903mnp1

10165 Harwin Drive, Ste. 150, Houston, TX 77036
TEL: 713-271-4700 FAX: 713-271-4770
www.aacufest.com

FED-EX Tracking # 835603757125	Bottle Order Control #
Accutest Quote #	Accutest Job #

[illegible]

Technical Report for

Montgomery Watson

EPFS San Juan Basin Groundwater Site

Accutest Job Number: T5436

Report to:

MWH

pamela.j.anderson@us.mwhglobal.com

ATTN: Pam Anderson

Lennapah

Total number of pages in report: 8



Test results contained within this data package meet the requirements of the National Environmental Laboratory Accreditation Conference and/or state specific certification programs as applicable.


Ron Martino
Laboratory Manager

This report shall not be reproduced, except in its entirety, without the written approval of Accutest Laboratories.

Accutest Laboratories

Sample Summary

Montgomery Watson

Job No: T5436

EPFS San Juan Basin Groundwater Site

Sample Number	Collected Date	Time By	Received	Matrix Code Type	Client Sample ID
T5436-1	09/23/03	09:10 MJN	09/24/03	AQ Ground Water	JENNAPAH MW-1
T5436-2	09/23/03	07:00 MJN	09/24/03	AQ Trip Blank Water	230903TB01

Report of Analysis

Page 1 of 1

Client Sample ID:	JENNAPAH MW-1	Date Sampled:	09/23/03
Lab Sample ID:	T5436-1	Date Received:	09/24/03
Matrix:	AQ - Ground Water	Percent Solids:	n/a
Method:	SW846 8021B		
Project:	EPFS San Juan Basin Groundwater Site		

	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1	KK005868.D	1	09/30/03	BC	n/a	n/a	GKK316
Run #2							

	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	Units	Q
71-43-2	Benzene	ND	1.0	ug/l	
108-88-3	Toluene	ND	1.0	ug/l	
100-41-4	Ethylbenzene	ND	1.0	ug/l	
1330-20-7	Xylenes (total)	38.1	3.0	ug/l	
95-47-6	o-Xylene	4.4	1.0	ug/l	
	m,p-Xylene	33.6	2.0	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
460-00-4	4-Bromofluorobenzene	100%		64-121%
98-08-8	aaa-Trifluorotoluene	113%		71-121%

ND = Not detected
RL = Reporting Limit
E = Indicates value exceeds calibration range

J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Report of Analysis

Page 1 of 1

Client Sample ID: 230903TB01
Lab Sample ID: T5436-2
Matrix: AQ - Trip Blank Water
Method: SW846 8021B
Project: EPFS San Juan Basin Groundwater Site

Date Sampled: 09/23/03
Date Received: 09/24/03
Percent Solids: n/a

	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1	KK005865.D	1	09/30/03	BC	n/a	n/a	GKK316
Run #2							

	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	Units	Q
71-43-2	Benzene	ND	1.0	ug/l	
108-88-3	Toluene	ND	1.0	ug/l	
100-41-4	Ethylbenzene	ND	1.0	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	ug/l	
95-47-6	o-Xylene	ND	1.0	ug/l	
	m,p-Xylene	ND	2.0	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
460-00-4	4-Bromofluorobenzene	92%		64-121%
98-08-8	aaa-Trifluorotoluene	94%		71-121%

ND = Not detected
RL = Reporting Limit
E = Indicates value exceeds calibration range

J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

GC Volatiles

QC Data Summaries

Includes the following where applicable:

- *Method Blank Summaries*
- *Blank Spike Summaries*
- *Matrix Spike and Duplicate Summaries*

Blank Spike Summary

Page 1 of 1

Job Number: T5436
Account: MWHSLCUT Montgomery Watson
Project: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GKK316-BS	KK005863.D 1		09/30/03	BC	n/a	n/a	GKK316

The QC reported here applies to the following samples:

Method: SW846 8021B

T5436-1, T5436-2

CAS No.	Compound	Spike ug/l	BSP ug/l	BSP %	Limits
71-43-2	Benzene	20	19.5	98	74-119
100-41-4	Ethylbenzene	20	19.7	99	82-115
108-88-3	Toluene	20	19.0	95	77-116
1330-20-7	Xylenes (total)	60	57.8	96	79-115
95-47-6	o-Xylene	20	19.0	95	78-114
	m,p-Xylene	40	38.9	97	79-116

CAS No.	Surrogate Recoveries	BSP	Limits
460-00-4	4-Bromofluorobenzene	93%	64-121%
98-08-8	aaa-Trifluorotoluene	96%	71-121%

Method Blank Summary

Page 1 of 1

Job Number: T5436
Account: MWHSLCUT Montgomery Watson
Project: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GKK316-MB	KK005864.D 1		09/30/03	BC	n/a	n/a	GKK316

The QC reported here applies to the following samples:

Method: SW846 8021B

T5436-1, T5436-2

CAS No.	Compound	Result	RL	Units	Q
71-43-2	Benzene	ND	1.0	ug/l	
100-41-4	Ethylbenzene	ND	1.0	ug/l	
108-88-3	Toluene	ND	1.0	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	ug/l	
95-47-6	o-Xylene	ND	1.0	ug/l	
	m,p-Xylene	ND	2.0	ug/l	

CAS No.	Surrogate Recoveries		Limits
460-00-4	4-Bromofluorobenzene	89%	64-121%
98-08-8	aaa-Trifluorotoluene	94%	71-121%

Matrix Spike/Matrix Spike Duplicate Summary

Page 1 of 1

Job Number: T5436
Account: MWHSLCUT Montgomery Watson
Project: EPFS San Juan Basin Groundwater Site

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
T5403-2MS	KK005869.D	10	09/30/03	BC	n/a	n/a	GKK316
T5403-2MSD	KK005870.D	10	09/30/03	BC	n/a	n/a	GKK316
T5403-2	KK005867.D	10	09/30/03	BC	n/a	n/a	GKK316

The QC reported here applies to the following samples:

Method: SW846 8021B

T5436-1, T5436-2

CAS No.	Compound	T5403-2 ug/l	Q	Spike ug/l	MS ug/l	MS %	MSD ug/l	MSD %	RPD	Limits Rec/RPD
71-43-2	Benzene	150		200	343	97	342	96	0	64-124/16
100-41-4	Ethylbenzene	ND		200	201	101	200	100	0	64-123/14
108-88-3	Toluene	77.2		200	268	95	269	96	0	64-120/13
1330-20-7	Xylenes (total)	12.6	J	600	606	99	603	98	0	66-118/18
95-47-6	o-Xylene	ND		200	198	99	197	99	1	65-119/20
	m,p-Xylene	ND		400	408	102	406	102	0	66-120/14

CAS No.	Surrogate Recoveries	MS	MSD	T5403-2	Limits
460-00-4	4-Bromofluorobenzene	92%	90%	90%	64-121%
98-08-8	aaa-Trifluorotoluene	92%	91%	92%	71-121%



10165 Harwin Drive, Ste. 150, Houston, TX 77036
TEL: 713-271-4700 FAX: 713-271-4770
www.aacutest.com

Laboratories

[illegible]



JOB #: T5436

DATE/TIME RECEIVED: 9/24/03 0900

CLIENT: MWH / EL PASO

INITIALS: KS

1. ☒ Y ☐ N Sample received in undamaged condition. 2. ☒ Y ☐ N Samples received within temp. range.
3. ☐ Y ☒ NA Sample received with proper pH. 4. ☒ Y ☐ N Sample received in proper containers.
5. ☒ Y ☐ N Sample volume sufficient for analysis. 6. ☒ Y ☐ N Sample received with chain of custody.
7. ☒ Y ☐ N Chain of Custody matches sample IDs on containers.
8. ☒ Y ☐ N Custody seal received intact and tamper evident on cooler.
9. ☐ Y ☒ NA Custody seal received intact and tamper evident on bottles.

[illegible]

PRESERVATIVES: 1: None 2: HCL 3: HNO3 4: H2SO4 5: NAOH 6: Other

~~pH of waters checked excluding volatiles~~

pH of soils N/A

Comments:

Delivery method: Courier:

Tracking#:

COOLER TEMP:

COOLER TEMP:

COOLER TEMP:

COOLER TEMP:

Method of sample disposal: (circle one) Accutest disposal Hold Return to Client

Form: SM012

(Page 1 of 2)

(Date/Signature)

[illegible]

DATA VALIDATION WORKSHEET

(Page 2 of 2)

Analytical Method:	SW-846 8021B (BTEX)	MWH Job Number:	EPC-SJRB (Groundwater)
Laboratory:	Accutest	Batch Identification:	T4642

Validation Criteria								
Sample ID	240603TB 01	Jennepah MW-1	Jennepah MW-2	Jennepah MW-3				
Lab ID	T4642-01	T4642-02	T4642-03	T4642-04				
Holding Time	A	A	A	A				
Analyte List	A	A	A	A				
Reporting Limits	A	A	A	A				
Trip Blank	A	A	A	A				
Equipment Rinseate Blanks	N/A	N/A	N/A	N/A				
Field Duplicate/Replicate	N/A	N/A	N/A	N/A				
Surrogate Spike Recovery	A	A	A	A				
Initial Calibration	N	N	N	N				
Initial Calibration Verification (ICV)	N	N	N	N				
Continuing Calibration Verification (CCV)	N	N	N	N				
Laboratory Control Sample (LCS)	A	A	A	A				
Laboratory Control Sample Duplicate (LCSD)	N	N	N	N				
Method Blank	A	A	A	A				
Matrix Spike/Matrix Spike Dup. (MS/MSD)	N/A	N/A	N/A	N/A				
Retention Time Window	N	N	N	N				
Injection Time(s)	N	N	N	N				
Hardcopy vs. Chain-of-Custody	A	A	A	A				
EDD vs. Hardcopy	N	N	N	N				
EDD vs. Chain of Custody	N	N	N	N				

(a) List QC batch identification if different than Batch ID
 A indicates validation criteria were met
 A/L indicates validation criteria met based upon Laboratory's QC Summary Form
 X indicates validation criteria were not met
 N indicates data review were not a project specific requirement
 N/A indicates criteria are not applicable for the specified analytical method or sample
 N/R indicates data not available for review

NOTES:



Gulf Coast
ACCUTEST.
Laboratories

06/27/03

Technical Report for

Montgomery Watson

EPFS San Juan Basin GS

Accutest Job Number: T4642

Report to:

El Paso

lynn.benally@elpaso.com

ATTN: Lynn Benally

Total number of pages in report: 13



Test results contained within this data package meet the requirements of the National Environmental Laboratory Accreditation Conference and/or state specific certification programs as applicable.

Ron Martino
Laboratory Manager

This report shall not be reproduced, except in its entirety, without the written approval of Accutest Laboratories.

Accutest Laboratories

Sample Summary

Montgomery Watson

Job No: T4642

EPFS San Juan Basin GS

Sample Number	Collected Date	Time By	Received	Matrix Code Type	Client Sample ID
T4642-1	06/24/03	06:00 MJN	06/25/03	AQ Trip Blank Water	240603TB01
T4642-2	06/24/03	08:17 MJN	06/25/03	AQ Water	JENNEPAH MW-1
T4642-3	06/24/03	09:15 MJN	06/25/03	AQ Water	JENNEPAH MW-2
T4642-4	06/24/03	08:44 MJN	06/25/03	AQ Water	JENNEPAH MW-3

Report of Analysis

Page 1 of 1

Client Sample ID: 240603TB01
 Lab Sample ID: T4642-1
 Matrix: AQ - Trip Blank Water
 Method: SW846 8021B
 Project: EPFS San Juan Basin GS

Date Sampled: 06/24/03
 Date Received: 06/25/03
 Percent Solids: n/a

	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1	KK005318.D	1	06/25/03	BC	n/a	n/a	GKK280
Run #2							

	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	Units	Q
71-43-2	Benzene	ND	1.0	ug/l	
108-88-3	Toluene	ND	1.0	ug/l	
100-41-4	Ethylbenzene	ND	1.0	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	ug/l	
95-47-6	o-Xylene	ND	1.0	ug/l	
	m,p-Xylene	ND	2.0	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
460-00-4	4-Bromofluorobenzene	103%		64-121%
98-08-8	aaa-Trifluorotoluene	103%		71-121%

ND = Not detected
 RL = Reporting Limit
 E = Indicates value exceeds calibration range

J = Indicates an estimated value
 B = Indicates analyte found in associated method blank
 N = Indicates presumptive evidence of a compound

Report of Analysis

Page 1 of 1

Client Sample ID: JENNEPAH MW-1
Lab Sample ID: T4642-2
Matrix: AQ - Water
Method: SW846 8021B
Project: EPFS San Juan Basin GS

Date Sampled: 06/24/03
Date Received: 06/25/03
Percent Solids: n/a

	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1	KK005332.D	1	06/26/03	BC	n/a	n/a	GKK281
Run #2	KK005319.D	5	06/25/03	BC	n/a	n/a	GKK280

	Purge Volume
Run #1	5.0 ml
Run #2	5.0 ml

Purgeable Aromatics

CAS No.	Compound	Result	RL	Units	Q
71-43-2	Benzene	ND	1.0	ug/l	
108-88-3	Toluene	ND	1.0	ug/l	
100-41-4	Ethylbenzene	ND	1.0	ug/l	
1330-20-7	Xylenes (total)	44.1	3.0	ug/l	
95-47-6	o-Xylene	ND	1.0	ug/l	
	m,p-Xylene	44.1	2.0	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
460-00-4	4-Bromofluorobenzene	233% ^a	111%	64-121%
98-08-8	aaa-Trifluorotoluene	490% ^a	117%	71-121%

(a) Outside control limits due to matrix interference.

ND = Not detected
RL = Reporting Limit
E = Indicates value exceeds calibration range

J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Report of Analysis

Page 1 of 1

Client Sample ID: JENNEPAH MW-2
Lab Sample ID: T4642-3
Matrix: AQ - Water
Method: SW846 8021B
Project: EPFS San Juan Basin GS

Date Sampled: 06/24/03
Date Received: 06/25/03
Percent Solids: n/a

	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1	KK005326.D	1	06/26/03	BC	n/a	n/a	GKK280
Run #2							

	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	Units	Q
71-43-2	Benzene	ND	1.0	ug/l	
108-88-3	Toluene	ND	1.0	ug/l	
100-41-4	Ethylbenzene	ND	1.0	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	ug/l	
95-47-6	o-Xylene	ND	1.0	ug/l	
	m,p-Xylene	ND	2.0	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
460-00-4	4-Bromofluorobenzene	106%		64-121%
98-08-8	aaa-Trifluorotoluene	106%		71-121%

ND = Not detected
RL = Reporting Limit
E = Indicates value exceeds calibration range

J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

Report of Analysis

Page 1 of 1

Client Sample ID: JENNEPAH MW-3
Lab Sample ID: T4642-4
Matrix: AQ - Water
Method: SW846 8021B
Project: EPFS San Juan Basin GS

Date Sampled: 06/24/03
Date Received: 06/25/03
Percent Solids: n/a

	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
Run #1	KK005327.D	1	06/26/03	BC	n/a	n/a	GKK280
Run #2							

	Purge Volume
Run #1	5.0 ml
Run #2	

Purgeable Aromatics

CAS No.	Compound	Result	RL	Units	Q
71-43-2	Benzene	ND	1.0	ug/l	
108-88-3	Toluene	ND	1.0	ug/l	
100-41-4	Ethylbenzene	ND	1.0	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	ug/l	
95-47-6	o-Xylene	ND	1.0	ug/l	
	m,p-Xylene	ND	2.0	ug/l	

CAS No.	Surrogate Recoveries	Run# 1	Run# 2	Limits
460-00-4	4-Bromofluorobenzene	95%		64-121%
98-08-8	aaa-Trifluorotoluene	95%		71-121%

ND = Not detected
RL = Reporting Limit
E = Indicates value exceeds calibration range

J = Indicates an estimated value
B = Indicates analyte found in associated method blank
N = Indicates presumptive evidence of a compound

GC Volatiles

QC Data Summaries

Includes the following where applicable:

- Method Blank Summaries
- Blank Spike Summaries
- Matrix Spike and Duplicate Summaries

Blank Spike Summary

Page 1 of 1

Job Number: T4642

Account: MWHSLCUT Montgomery Watson

Project: EPFS San Juan Basin GS

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GKK280-BS	KK005308.D1		06/25/03	BC	n/a	n/a	GKK280

The QC reported here applies to the following samples:

Method: SW846 8021B

T4642-1, T4642-2, T4642-3, T4642-4

CAS No.	Compound	Spike ug/l	BSP ug/l	BSP %	Limits
71-43-2	Benzene	20	20.2	101	74-119
100-41-4	Ethylbenzene	20	20.4	102	82-115
108-88-3	Toluene	20	19.8	99	77-116
1330-20-7	Xylenes (total)	60	60.2	100	79-115
95-47-6	o-Xylene	20	19.8	99	78-114
	m,p-Xylene	40	40.3	101	79-116

CAS No.	Surrogate Recoveries	BSP	Limits
460-00-4	4-Bromofluorobenzene	99%	64-121%
98-08-8	aaa-Trifluorotoluene	96%	71-121%

Blank Spike Summary

Page 1 of 1

Job Number: T4642

Account: MWHSLCUT Montgomery Watson

Project: EPFS San Juan Basin GS

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GKK281-BS	KK005330.D1		06/26/03	BC	n/a	n/a	GKK281

The QC reported here applies to the following samples:

Method: SW846 8021B

T4642-2

CAS No.	Compound	Spike ug/l	BSP ug/l	BSP %	Limits
71-43-2	Benzene	20	20.9	105	74-119
100-41-4	Ethylbenzene	20	20.8	104	82-115
108-88-3	Toluene	20	20.6	103	77-116
1330-20-7	Xylenes (total)	60	62.1	104	79-115
95-47-6	o-Xylene	20	20.6	103	78-114
	m,p-Xylene	40	41.4	104	79-116

CAS No.	Surrogate Recoveries	BSP	Limits
460-00-4	4-Bromofluorobenzene	97%	64-121%
98-08-8	aaa-Trifluorotoluene	95%	71-121%

Method Blank Summary

Page 1 of 1

Job Number: T4642
Account: MWHSLCUT Montgomery Watson
Project: EPFS San Juan Basin GS

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GKK280-MB	KK005309.D1		06/25/03	BC	n/a	n/a	GKK280

The QC reported here applies to the following samples:

Method: SW846 8021B

T4642-1, T4642-2, T4642-3, T4642-4

CAS No.	Compound	Result	RL	Units	Q
71-43-2	Benzene	ND	1.0	ug/l	
100-41-4	Ethylbenzene	ND	1.0	ug/l	
108-88-3	Toluene	ND	1.0	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	ug/l	
95-47-6	o-Xylene	ND	1.0	ug/l	
	m,p-Xylene	ND	2.0	ug/l	

CAS No.	Surrogate Recoveries		Limits
460-00-4	4-Bromofluorobenzene	106%	64-121%
98-08-8	aaa-Trifluorotoluene	107%	71-121%

Method Blank Summary

Page 1 of 1

Job Number: T4642

Account: MWHSLCUT Montgomery Watson

Project: EPFS San Juan Basin GS

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
GKK281-MB	KK005331.D 1		06/26/03	BC	n/a	n/a	GKK281

The QC reported here applies to the following samples:

Method: SW846 8021B

T4642-2

CAS No.	Compound	Result	RL	Units	Q
71-43-2	Benzene	ND	1.0	ug/l	
100-41-4	Ethylbenzene	ND	1.0	ug/l	
108-88-3	Toluene	ND	1.0	ug/l	
1330-20-7	Xylenes (total)	ND	3.0	ug/l	
95-47-6	o-Xylene	ND	1.0	ug/l	
	m,p-Xylene	ND	2.0	ug/l	

CAS No.	Surrogate Recoveries	Limits
460-00-4	4-Bromofluorobenzene	102% 64-121%
98-08-8	aaa-Trifluorotoluene	101% 71-121%

Matrix Spike/Matrix Spike Duplicate Summary

Page 1 of 1

Job Number: T4642

Account: MWHS LCUT Montgomery Watson

Project: EPFS San Juan Basin GS

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
T4643-4MS	KK005336.D1		06/26/03	BC	n/a	n/a	GKK281
T4643-4MSD	KK005337.D1		06/26/03	BC	n/a	n/a	GKK281
T4643-4	KK005335.D1		06/26/03	BC	n/a	n/a	GKK281

The QC reported here applies to the following samples:

Method: SW846 8021B

T4642-2

CAS No.	Compound	T4643-4 ug/l	Q	Spike ug/l	MS ug/l	MS %	MSD ug/l	MSD %	RPD	Limits Rec/RPD
71-43-2	Benzene	ND		20	21.4	107	21.2	106	1	64-124/16
100-41-4	Ethylbenzene	ND		20	21.9	110	21.5	108	2	64-123/14
108-88-3	Toluene	ND		20	21.2	106	21.1	106	0	64-120/13
1330-20-7	Xylenes (total)	ND		60	64.6	108	63.1	105	2	66-118/18
95-47-6	o-Xylene	ND		20	21.3	107	20.8	104	2	65-119/20
	m,p-Xylene	ND		40	43.3	108	42.2	106	3	66-120/14

CAS No.	Surrogate Recoveries	MS	MSD	T4643-4	Limits
460-00-4	4-Bromofluorobenzene	99%	100%	98%	64-121%
98-08-8	aaa-Trifluorotoluene	95%	98%	95%	71-121%

Matrix Spike/Matrix Spike Duplicate Summary

Page 1 of 1

Job Number: T4642
Account: MWHSLCUT Montgomery Watson
Project: EPFS San Juan Basin GS

Sample	File ID	DF	Analyzed	By	Prep Date	Prep Batch	Analytical Batch
T4644-2MS	KK005314.D 1		06/25/03	BC	n/a	n/a	GKK280
T4644-2MSD	KK005315.D 1		06/25/03	BC	n/a	n/a	GKK280
T4644-2	KK005311.D 1		06/25/03	BC	n/a	n/a	GKK280

The QC reported here applies to the following samples:

Method: SW846 8021B

T4642-1, T4642-2, T4642-3, T4642-4

CAS No.	Compound	T4644-2 ug/l	Spike Q	MS ug/l	MS %	MSD ug/l	MSD %	RPD	Limits Rec/RPD
71-43-2	Benzene	ND	20	20.9	105	20.9	105	0	64-124/16
100-41-4	Ethylbenzene	ND	20	20.2	101	19.8	99	2	64-123/14
108-88-3	Toluene	ND	20	19.5	98	19.3	97	1	64-120/13
1330-20-7	Xylenes (total)	ND	60	31.8	53*	28.0	47*	13	66-118/18
95-47-6	o-Xylene	ND	20	14.2	71	12.9	65	10	65-119/20
	m,p-Xylene	ND	40	17.7	44*	15.1	38*	16*	66-120/14

CAS No.	Surrogate Recoveries	MS	MSD	T4644-2	Limits
460-00-4	4-Bromofluorobenzene	102%	114%	109%	64-121%
98-08-8	aaa-Trifluorotoluene	100%	113%	111%	71-121%


ACCUTEST:

Laboratories

CHAIN OF CUSTODY ⁴ 240603 MND

10165 Harwin Drive, Ste. 150, Houston, TX 77036
TEL: 713-271-4700 FAX: 713-271-4770
www.aacutest.com

FED-EX Tracking # 836857900581	Bottle Order Control #
Accutest Quote #	Accutest Job #

[illegible]

DATA VALIDATION WORKSHEET

(Page 1 of 2)

Analytical Method/Analytes: SW-846 8021B (BTEX) Sample Collection Date(s): 03/25/03Laboratory: APCL

MWH Job Number: EPC-SJRB
(Groundwater)

Batch Identification: 03-02406

Matrix: Water

MS/MSD Parent(s)^(a): NoneField Replicate Parent(s): None

Validation Complete:

1313 4-23-03
(Date/Signature)

[illegible]

Applied P & Ch Laboratory

13760 Magnolia Ave. Chino CA 91710

Tel: (909) 590-1828 Fax: (909) 590-1498

Submitted to:

Montgomery Watson Harza

Attention: Brian Buttars

10619 South Jordan Gateway

Salt Lake City UT 84095

Tel: (801)617-3200 Fax: (801)617-4200

APCL Analytical Report

Service ID #: 801-032406

Collected by: MJN

Collected on: 03/25/03

Received: 03/26/03

Extracted: N/A

Tested: 03/28/03

Reported: 03/31/03

Sample Description: Water

Project Description: 220013 San Juan Basin

Analysis of Water Samples

Component Analyzed	Method	Unit	PQL	Analysis Result	
				Jenepah MW-1	TB
				03-02406-1	03-02406-2
BTXE					
Dilution Factor				5	1
BENZENE	8021B	µg/L	0.5	74	<0.5
ETHYLBENZENE	8021B	µg/L	0.5	168	<0.5
TOLUENE	8021B	µg/L	0.5	190	0.2J
O-XYLENE	8021B	µg/L	0.5	576	<0.5
M,P-XYLENE	8021B	µg/L	1	212	<1

PQL: Practical Quantitation Limit.

MDL: Method Detection Limit.

CRDL: Contract Required Detection Limit


N.D.: Not Detected or less than the practical quantitation limit.

"-": Analysis is not required.

J: Reported between PQL and MDL.

Listed Dilution Factors (DF) are relative to the method default DF. All unlisted DFs are 1.0

Respectfully submitted,


Dominic Lau

Laboratory Director

Applied P & Ch Laboratory

Chain of Custody ID 250303MN-1
 Page 1 of 1
 Air Bill No. 835603757044

LABORATORY APCL
Contract El Paso Corp., San Jaun River Basin

Phone (801) 617-3200 FAX (801) 617-4200

MWH Contact Brian Butters

Project San Juan Basin

Project Number 220013Date Due 8/24/2012

Sampler's Name MFN
(print clearly)

[illegible]

Applied P & Ch Laboratory

13760 Magnolia Ave. Chino CA 91710

Tel: (909) 590-1828 Fax: (909) 590-1498

APCL QA/QC Report

Submitted to:

Montgomery Watson Harza

Attention: Brian Buttars

10619 South Jordan Gateway

Salt Lake City, UT 84095

Tel: (801)617-3200 Fax: (801)617-4200

Service ID #: 801-032406

Collected by: MJN

Collected on: 03/25/03

Sample description:

Water

Project: San Juan Basin /220013

Received: 03/26/03

Tested: 03/28/03

Reported: 04/21/03

Analysis of Water

801-032406QC

Component Name	Analysis Batch #	CCV (µg/L)	CCV %Rec	M-Blank	Conc. Unit	SP Level	LCS %Rec	MS %Rec	MSD %Rec	MS/MSD %RPD	Control Limit %Rec	Control Limit %Diff
BTXE												
Benzene	03G1854	100	90	N.D.	µg/L	18.0	99	94	97	3	71-126	28
Toluene	03G1854	100	98	N.D.	µg/L	70.0	97	94	97	3	70-117	24
Ethylbenzene	03G1854	100	101	N.D.	µg/L	18.0	87	97	103	6	65-131	33
m/p-Xylene	03G1854	200	95	N.D.	µg/L	70.0	96	91	97	6	66-122	28
o-Xylene	03G1854	100	95	N.D.	µg/L	25.0	95	88	95	8	65-130	33

Notation: ICV - Initial Calibration Verification
CCV - Continuation Calibration Verification
LCS - Lab Control Spike
MS - Matrix Spike
MSD - Matrix Spike Duplicate
ICS - Interference Check Standard
MD - Matrix Duplicate
N.D. - Not detected or less than PQL

CCB - Continuation Calibration Blank
M-blank - Method Blank
SP Level - Spike Level
%Rec - Recovery Percent
%RPD - Relative Percent Differences
%Diff - Control Limit for %RPD
ICP-SD - ICP Serial Dilution
N.A. - Not Applicable

Respectfully submitted,


Regina Kirakozova,
Associate QA/QC Director
Applied P & Ch Laboratory

FORM-2A

Applied P & Ch Laboratory

Surrogate Recovery Summary for Method 8021B

Client Name: Montgomery Watson Harza

Contract No:

Lab Code: APCL

Case No:

SAS No:

SDG Number: 032406

Project ID: San Juan Basin

Project No: 220013

Sample Matrix: Water

Batch No: 03G1854

#	Client Sample No	Lab Sample ID	S1 % #	TOT OUT
1		03G1854-LCS-01	97	0
2		03G1854-LSD-01	93	0
3		03G1854-MB-01	100	0
4	TB <i>250303MW-1</i>	03-2406-2	99	0
5	<i>Jenney</i> MW-1	03-2406-1	114	0
6	LF821	03-2389-7MS	97	0
7	LF821	03-2389-7MSD	97	0
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				

S1 = 4-BROMO-FLUOROBENZENE (PID)

QC Control Limit

66-133

Column to be used to flag recovery values:

* - Values outside of contract required QC Limits

D - Surrogate diluted out

I - Matrix Interference

LABORATORY
APCZ

Contract El Paso Corp., San Jaun River Basin

MWH

Phone (801) 617-3200 FAX (801) 617-4200

MWH Contact Brian Butters

Project San Juan Basin

Project Number 220013

Date Due Apr 26

Sampler's Name MTN

(print clearly)

Chain of Custody ID Z503Q3MN-1

Page -

Air Bill No. 835603757044

CHAIN OF CUSTODY RECORD/LAB WORK REQUEST

LABORATORY USE ONLY			
SAMPLES WERE:			
1 Shipped or hand delivered Notes:			
2 Ambient or Chilled Notes:			
3 Temperature _____			
4 Received Broken/Leaking (Improperly Sealed) Y N Notes:			
5 Properly Preserved Y N Notes:			
6 Received Within Holding Times Y N Notes:			
COC Tape Was:			
1 Present on Outer Package Y N NA			
2 Unbroken on Outer Package Y N NA			
3 Present on Sample Y N NA			
4 Unbroken on Sample Y N NA Notes:			
Discrepancies Between Sample Labels and COC Record? Y N Notes:			
ANALYSES REQUESTED			
BTEX SW-846 8021B			
Alkalinity SM 2320B			
TDS USEPA 160.1			
NM WQCC Metals SW-846 6010B & 7470A			
Cations SW-846 6010B			
Anions USEPA 300.0			
Nitrate USEPA 300.0			
Nitrite USEPA 300.0			
Sampling Technique (b)			
Matrix (a)			
Time Collected			
Date Collected			
Depth Interval (ft)			
Sample ID			
Location ID			
(print clearly)			
Sampler's Name			
Date Due			
Project Number			
Project			
P-MWH Contact			
(801) 617-4200 FAX (801) 617-4200			

Sample Receiving Checklist

APCL ServiceID:

2406Client Name/Project: Montgomery Watson

1. Sample Arrival

Date/Time Received 3/26/03 0900 Date/Time Opened 3/26/03 0900 By (name): Paul KernCustody Transfer: ☐ Client ☐ Golden State ☐ UPS ☐ US Mail ☒ FedEx ☐ APCL Empl: _____

2. Chain-of-Custody (CoC)

☒ With Samples? ☐ Faxed? ☒ Client has Copy? ☐ Signed, dated? By: _____
☐ Project ID? ☒ Analyses Clear? ☐ Hold Samples? # on Hold _____ # Received 2
☒ CoC/Docs Zip-Locked under lid? ☐ Compos. #: _____ ☒ #Samples OK?
☐ Discrepancies? ☐ Client notified? ☐ Response (attach docs): _____

3. Shipping Container/Cooler

☒ Cooler Used? # of 1 Cooled by: ☒ Ice ☐ Blue Ice ☐ Dry Ice ☐ None
 Temp °C 4.2°C

(Cooler temperature measured from temp blank if present, otherwise measured from the cooler).

Cooler Custody Seal? ☐ Absent ☐ Intact ☐ Tampered?

4. Sample Preservation

☐ pH <2 ☐ pH >12
 if Not, pH = _____ Preserved by: ☐ Client ☐ APCL ☐ Third Party

5. Holding-time Requirements

☐ pH 24hr ☐ BACT 6/24hr ☐ Cr^{VJ} 24hr ☐ NO₃⁻ 48hr ☐ BOD 48hr
☐ Cl₂ ASAP ☐ Turbidity 48hr ☐ DO ASAP ☐ Fe(II) ASAP
☐ HT Expired? ☐ Client notified?

6. Sample Container Condition

☒ Intact? ☐ Broken? ☐ Documented? Number: _____
 Type: ☐ plastic ☐ glass ☐ Tube: brass/SS ☐ Tedlar Bag
☒ Quantity OK? ☐ Leaking? ☐ Anomaly?
☒ Caps tight? ☐ Air Bubbles? ☐ Anomaly?
 Labels: ☒ Unique ID? ☐ Date/Time ☐ Preserved?

7. Turn Around Time

☒ RUSH TAT: 5 days ☐ Std (7-10 days) ☐ Not Marked

8. Sample Matrix

☐ Drinking H₂O ☒ Other Liq ☐ Soil ☐ Wipe ☐ Polymer ☐ Air ☐ Other: _____
☐ Ground H₂O ☐ Sludge ☐ Filter ☐ Oil/Petro ☐ Paint ☐ W. Water ☐ Extract ☐ Unknown

9. Pre-Login Check List Completed & OK?

☒ ALL OK? (if not, attach docs) ☐ Client Contact? (Name: _____) Date/Time: _____

Received/Checked by: Paul Kern Date: 26 Mar 2003 Time: 7:42 a.m.

*HT: Samples must be analyzed for results to reflect total concentrations. Results generated outside required of holding times are considered minimal values and may be used to define waste as hazardous but not as non-hazardous.

Applied P & Ch Laboratory

13760 Magnolia Ave. Chino CA 91710

Tel: (909) 590-1828 Fax: (909) 590-1498

Sample Login: Check List

03-02406 (0984_1043) (2721900_1043)

03/26/03

Part 1: General Information

☐ Company Information	Name:	Montgomery Watson Harza
	Address:	10619 South Jordan Gateway ,Salt Lake City ,UT 84095
☐ Project Information	Project Description:	San Juan Basin
		Hill AFB
	Project #:	220013
☐ Billing Information	P.O. #:	
	Bill Address:	10619 South Jordan Gateway ,Salt Lake City ,UT 84095
	Lab Project ID:	1999-0746
	Client Database #:	04
☐ Receiving Information	Who Received Sample?	Paul Kou
	Receiving Date/Time:	03/26/03 0900
	COC No.	
☐ Shipping Information	Shipping Company	Express
	Packing Information:	Cooler/Ice Chester
	Cooler Temperature:	4.2 °C
☐ Container Information	Container Provider:	Client
☐ Sampling Information	Sampling Person:	
	Sampling Company:	Client
☐ Turn-Around-Time Option:		Rush 5 working day(s)
☐ QC Option:		QC and Surro. Rep.
☐ Disposal Option:		Not specify

Part 2: Sample Information

Seq. #	Sample ID (on COC)	Sample Sub-ID	APCL Sample ID	Matrix	Cont. tainer	Preser- vative	Vol, ml Am. g	# of Replica	Condition G, L, B	Collected mmddyy	Hold ?	Composite Group	TAT Days
1	MW-1	BTEX	03-02406-1	W	V	C	40	2	G	032503	N	0	7 ☐
2	TB	BTEX	03-02406-2	W	V	C	40	1	G	032503	N	0	7 ☐

Part 3: Analysis Information

Test Items:

☒ 8021B

BTXE

Seq. #	Client's Sample ID (as given on COC)	Sample Sub-ID	APCL Sample ID	Matrix	BTXE	
1	MW-1	BTEX	03-02406-1	W	X	☐
2	TB	BTEX	03-02406-2	W	X	☐

Login By En-Yu Paul Kou

Check By 132

Applied P & Ch Laboratory

13760 Magnolia Ave. Chino CA 91710

Tel: (909) 590-1828 Fax: (909) 590-1498

Submitted to:

Montgomery Watson Harza

Attention: Brian Buttars

10619 South Jordan Gateway

Salt Lake City UT 84095

Tel: (801)617-3200 Fax: (801)617-4200

APCL Analytical Report

Service ID #: 801-032406

Collected by: MJN

Collected on: 03/25/03

Sample Description: Water

Project Description: 220013 San Juan Basin

Received: 03/26/03

Extracted: N/A

Tested: 03/28/03

Reported: 03/31/03

Analysis of Water Samples

Component Analyzed	Method	Unit	PQL	Analysis Result	
				Jennepah MW-1	TB
				03-02406-1	03-02406-2
BTXE					
Dilution Factor				5	1
BENZENE	8021B	µg/L	0.5	74	<0.5
ETHYLBENZENE	8021B	µg/L	0.5	168	<0.5
TOLUENE	8021B	µg/L	0.5	190	0.2J
O-XYLENE	8021B	µg/L	0.5	576	<0.5
M,P-XYLENE	8021B	µg/L	1	212	<1

PQL: Practical Quantitation Limit. MDL: Method Detection Limit. CRDL: Contract Required Detection Limit

N.D.: Not Detected or less than the practical quantitation limit.

"-": Analysis is not required.

J: Reported between PQL and MDL.

Listed Dilution Factors (DF) are relative to the method default DF. All unlisted DFs are 1.0

Respectfully submitted,



Dominic Lau

Laboratory Director

Applied P & Ch Laboratory

APPENDIX G
FIELD DOCUMENTATION
(2003)

WELL DEVELOPMENT AND SAMPLING LOG

Project No.: 30001.0 Project Name: SJB Groundwater Client: MWH/EL Paso
 Location: Jennapah Well No: MW-3 Development Sampling
 Project Manager MJN Date 03/23/04 start Time 0713 Weather Sunny 40s
 Depth to Water 25.70 Depth to Product na Product Thickness na Measuring Point TOC
 Water Column Height 5.67 Well Dia. 2"

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐
 Bottom Valve Bailer ☒ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐

Criteria: 3 to 5 Casing Volumes of Water Removal ☒ stabilization of Indicator Parameters ☒ Other or bail dry

Gal/ft x ft of water	Water Volume in Well		Gal/oz to be removed
	Gallons	Ounces	
5.67 x 0.16	.91x 3		2.72

Time (military)	pH (su)	SC (umhos/cm)	Temp (°F)	ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gallons)	Comments/ Flow rate
<u>0721</u>	<u>7.29</u>	<u>1020</u>	<u>55.4</u>				<u>.25</u>	<u>clear</u>
	<u>7.40</u>	<u>1060</u>	<u>56.2</u>				<u>.5</u>	<u>cloudy</u>
	<u>7.41</u>	<u>1090</u>	<u>56.4</u>				<u>.75</u>	<u>cloudy</u>
	<u>7.42</u>	<u>1120</u>	<u>56.6</u>				<u>2.0</u>	<u>cloudy</u>
	<u>7.39</u>	<u>1130</u>	<u>56.6</u>				<u>2.25</u>	<u>cloudy</u>
	<u>7.41</u>	<u>1120</u>	<u>56.7</u>				<u>2.5</u>	<u>cloudy</u>
<u>0735</u>	<u>7.42</u>	<u>1130</u>	<u>56.7</u>				<u>2.75</u>	<u>cloudy</u>

Final: Time	pH	SC	Temp	Eh-ORP	D.O.	Turbidity	Ferrous Iron	Vol Evac.	Comments/Flow Rate
<u>0735</u>	<u>7.42</u>	<u>1130</u>	<u>56.7</u>					<u>2.75</u>	<u>cloudy</u>

COMMENTS: Navajo EPA called and canceled visit, said to proceed without them.

INSTRUMENTATION: pH Meter ☒ _____ Temperature Meter ☒
 DO Monitor _____ Other _____
 Conductivity Meter ☒ _____

Water Disposal Kutz Sample ID Jennapah MW-3 Sample Time 0737
BTEX VOCs Alkalinity TDS Cations Anions Nitrate Nitrite Ammonia TKN NMWQCC Metals Total Phosphorus

MS/MSD _____ BD _____ BD Name/Time _____ TB 230304tb01

WELL DEVELOPMENT AND SAMPLING LOG

Project No.: 30001.0 Project Name: SJB Groundwater Client: MWH/EL Paso
 Location: Jennapah Well No: MW-2 Development Sampling
 Project Manager MJN Date 3/23/04 Start Time 0744 Weather Sunny 40s
 Depth to Water 25.88 Depth to Product na Product Thickness na Measuring Point TOC
 Water Column Height 5.97 Well Dia. 2"

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐
 Bottom Valve Bailer ☒ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐

Criteria: 3 to 5 Casing Volumes of Water Removal ☒ stabilization of Indicator Parameters ☒ Other or bail dry

Gal/ft x ft of water	Water Volume in Well		Gal/oz to be removed
	Gallons	Ounces	
5.97 x 0.16	.96 x 3		2.87

Time (military)	pH (su)	SC (umhos/cm)	Temp (°F)	ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gallons)	Comments/ Flow rate
0747	7.20	1240	57.3				0.5	cloudy
	7.29	1240	57.7				1	cloudy
	7.31	1220	57.9				1.5	cloudy
	7.31	1220	57.9				2	cloudy
	7.32	1210	57.9				2.5	cloudy
0759	7.33	1230	57.9				3.0	cloudy

Final: Time	pH	SC	Temp	Eh-ORP	D.O.	Turbidity	Ferrous Iron	Vol Evac.	Comments/Flow Rate
0759	7.33	1230	57.9					3.0	cloudy

COMMENTS: Navajo EPA called and canceled visit, said to proceed without them.

INSTRUMENTATION: pH Meter ☒ _____ Temperature Meter ☒
 DO Monitor _____ Other _____
 Conductivity Meter ☒ _____
 Water Disposal Kutz Sample ID Jennapah MW-2 Sample Time 00800
BTEX VOCs Alkalinity TDS Cations Anions Nitrate Nitrite Ammonia TKN NMWQCC Metals Total Phosphorus
 MS/MSD _____ BD _____ BD Name/Time _____ TB 230304tb01

WELL DEVELOPMENT AND SAMPLING LOG

Project No.: 30001.0 Project Name: SJB Groundwater Client: MWH/EL Paso
 Location: Jennapah Well No: MW-1 Development Sampling
 Project Manager MJN Date 3/23/04 Start Time 0807 Weather Sunny 40s
 Depth to Water 25.41 Depth to Product na Product Thickness na Measuring Point TOC
 Water Column Height 8.80 Well Dia. 4"

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐
 Bottom Valve Bailer ☒ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐

Criteria: 3 to 5 Casing Volumes of Water Removal ☒ stabilization of Indicator Parameters ☒ Other or bail dry

Gal/ft x ft of water	Water Volume in Well		Gal/oz to be removed
	Gallons	Ounces	
8.80 x 0.65	5.72 x 3		17.16

Time (military)	pH (su)	SC (umhos/cm)	Temp (°F)	ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gallons)	Comments/ Flow rate
0811	7.03	1230	57.8				1	Clear
	7.02	1230	58.0				2	Clear
	7.04	1230	57.9				3	Clear
	7.24	1230	58.2				15	Cloudy
	7.24	1220	58.2				16	Clear
	7.26	1240	58.2				17	Clear
0838	7.24	1230	58.2				18	Clear

Final: Time	pH	SC	Temp	Eh-ORP	D.O.	Turbidity	Ferrous Iron	Vol Evac.	Comments/Flow Rate
0838	7.24	1230	58.2					18	Clear

COMMENTS: Navajo EPA called and canceled visit, said to proceed without them.

INSTRUMENTATION: pH Meter ☒ _____ Temperature Meter ☒
 DO Monitor _____ Other _____
 Conductivity Meter ☒ _____
 Water Disposal Kutz Sample ID Jennapah MW-1 Sample Time 0848
BTEX VOCs Alkalinity TDS Cations Anions Nitrate Nitrite Ammonia TKN NMWQCC Metals Total Phosphorus
 MS/MSD _____ BD _____ BD Name/Time _____ TB 230304tb01

WELL DEVELOPMENT AND SAMPLING LOG

Project No.: 30001.0 Project Name: SJB Groundwater Client: MWH/EL Paso
 Location: Jennapah Well No: MW-1 Development Sampling
 Project Manager MJN Date 12/16/03 Start Time 0958 Weather Sunny teens
 Depth to Water 25.46 Depth to Product na Product Thickness na Measuring Point TOC
 Water Column Height 8.65 Well Dia. 4"

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐
 Bottom Valve Bailer ☒ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐

Criteria: 3 to 5 Casing Volumes of Water Removal ☒ stabilization of Indicator Parameters ☒ Other or bail dry

Gal/ft x ft of water	Water Volume in Well		Gal/oz to be removed
	Gallons	Ounces	
8.65 x 0.65	5.62 x 3		16.86

Time (military)	pH (su)	SC (umhos/cm)	Temp (°F)	ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gallons)	Comments/ Flow rate
1002	7.22	1420	54.3				1	Clear
	7.27	1420	53.2				2	Clear
	7.33	1390	53.5				3	Clear
	7.47	1350	51.9				10	Clear
	7.56	1310	53.5				15	Clear
	7.59	1360	53.0				16	Clear
1034	7.60	1370	53.3				17	Clear

Final: Time	pH	SC	Temp	Eh-ORP	D.O.	Turbidity	Ferrous Iron	Vol Evac.	Comments/Flow Rate
1034	7.60	1370	53.3					17	Clear

COMMENTS: Navajo EPA called and canceled visit, said to proceed without them.

INSTRUMENTATION: pH Meter ☒ Temperature Meter ☒
 DO Monitor _____ Other _____
 Conductivity Meter ☒ _____
 Water Disposal Kutz Sample ID Jennapah MW-1 Sample Time 1040
BTEX VOCs Alkalinity TDS Cations Anions Nitrate Nitrite Ammonia TKN NMWQCC Metals Total Phosphorus
 MS/MSD _____ BD _____ BD Name/Time _____ TB 1612031b01

WELL DEVELOPMENT AND SAMPLING LOG

Project No.: 30001.0 Project Name: SJB Groundwater Client: MWH/EL Paso
 Location: Jennapah Well No: MW-2 Development Sampling
 Project Manager MJN Date 12/16/03 Start Time 0858 Weather Sunny teens
 Depth to Water 25.92 Depth to Product na Product Thickness na Measuring Point TOC
 Water Column Height 5.93 Well Dia. 2"

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐
 Bottom Valve Bailer ☒ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐

Criteria: 3 to 5 Casing Volumes of Water Removal ☒ stabilization of Indicator Parameters ☒ Other or bail dry

Gal/ft x ft of water	Water Volume in Well		Gal/oz to be removed
	Gallons	Ounces	
5.93 x 0.16	.95 x 3		2.85

Time (military)	pH (su)	SC (umhos/cm)	Temp (°F)	ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gallons)	Comments/ Flow rate
0904	7.7	1470	54.4				0.25	tan silty
	7.68	1520	54.9				0.5	tan silty
	7.68	1520	55.7				0.75	tan silty
	7.72	1500	54.3				1.75	tan silty
	7.74	1480	53.9				2.75	tan silty
0919	7.76	1450	54.0				3.75	tan silty

Final: Time	pH	SC	Temp	Eh-ORP	D.O.	Turbidity	Ferrous Iron	Vol Evac.	Comments/Flow Rate
0919	7.76	1450	54.0					3.75	tan silty

COMMENTS: Navajo EPA called and canceled visit, said to proceed without them.

INSTRUMENTATION: pH Meter ☒ Temperature Meter ☒
 DO Monitor _____ Other _____
 Conductivity Meter ☒ _____
 Water Disposal Kutz Sample ID Jennapah MW-2 Sample Time 0925
BTEX VOCs Alkalinity TDS Cations Anions Nitrate Nitrite Ammonia TKN NMWQCC Metals Total Phosphorus
 MS/MSD _____ BD _____ BD Name/Time _____ TB 1612031b01

WELL DEVELOPMENT AND SAMPLING LOG

Project No.: 30001.0 Project Name: SJB Groundwater Client: MVH/EL Paso
 Location: Jennapah Well No: MW-3 Development Sampling
 Project Manager MJN Date 12/16/03 Start Time 0931 Weather Sunny teens
 Depth to Water 25.88 Depth to Product na Product Thickness na Measuring Point TOC
 Water Column Height 5.49 Well Dia. 2"

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐

Bottom Valve Bailer ☒ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐

Criteria: 3 to 5 Casing Volumes of Water Removal ☒ stabilization of Indicator Parameters ☒ Other or bail dry

Gal/ft x ft of water	Water Volume in Well		Gal/oz to be removed
	Gallons	Ounces	
5.49 x 0.16	.88 x 3		2.64

Time (military)	pH (su)	SC (umhos/cm)	Temp (°F)	ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gallons)	Comments/ Flow rate
0934	7.91	1230	53.0				0.25	tan silty
	7.96	1350	53.3				0.75	tan silty
	7.91	1380	53.7				1.0	tan silty
	7.92	1380	52.8				2.0	tan silty
0948	7.94	1390	53.1				3.0	tan silty

Final: Time	pH	SC	Temp	Eh-ORP	D.O.	Turbidity	Ferrous Iron	Vol Evac.	Comments/Flow Rate
0948	7.94	1390	53.1					3.0	tan silty

COMMENTS: Navajo EPA called and canceled visit, said to proceed without them.

INSTRUMENTATION: pH Meter ☒ Temperature Meter ☒
 DO Monitor ☐ Other ☐
 Conductivity Meter ☒

Water Disposal Kutz Sample ID Jennapah MW-3 Sample Time 00952

BTEX VOCs Alkalinity TDS Cations Anions Nitrate Nitrite Ammonia TKN NMWQCC Metals Total Phosphorus

MS/MSD _____ BD _____ BD Name/Time _____ TB 1612031b01

PRODUCT RECOVERY/WATER LEVEL DATA

Martin J. Nee
PO Box 3861
Farmington, NM 87499-3861
(505)334-2791 (505)320-9675cell

Project Name_ San Juan Basin Ground Water Project No. 30001.0
Project Manager MJN
Client Company MWH Date 9-23-03
Site Name Jennapah

Well	Time	Depth to Product (ft)	Depth to Water (ft)	Product Thickness (ft)	Volume Removed
MW-1	0807	-	25.795	-	-
MW-2		-	26.06	-	-
MW-3		-	26.21	-	-

Comments

Signature: Martin J. Nee Date: September 23, 2003

WELL DEVELOPMENT AND SAMPLING LOG

Project No.: 30001.0 Project Name: SJB Groundwater Client: MWH/EL Paso
 Location: Jennapah Well No: MW-1 Development Sampling
 Project Manager MJN Date 9/23/03 Start Time 0825 Weather Sunny 70s
 Depth to Water 25.975 Depth to Product na Product Thickness na Measuring Point TOC
 Water Column Height 8.315 Well Dia. 4"

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐
 Bottom Valve Bailer ☒ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐

Criteria: 3 to 5 Casing Volumes of Water Removal ☒ stabilization of Indicator Parameters ☒ Other or bail dry

Gal/ft x ft of water	Water Volume in Well		Gal/oz to be removed
	Gallons	Ounces	
8.315 x 0.65	5.400 x 3		16.21

Time (military)	pH (su)	SC (umhos/cm)	Temp (°C)	ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gallons)	Comments/ Flow rate
<u>0835</u>	<u>6.36</u>	<u>1230</u>	<u>13</u>				<u>1</u>	<u>Clear</u>
	<u>6.79</u>	<u>1340</u>	<u>13.5</u>				<u>2</u>	<u>Clear</u>
	<u>6.89</u>	<u>1480</u>	<u>13.5</u>				<u>3</u>	<u>Clear</u>
<u>0850</u>	<u>7.10</u>	<u>1460</u>	<u>13.1</u>				<u>8</u>	<u>Clear</u>
	<u>7.05</u>	<u>1450</u>	<u>13.2</u>				<u>15</u>	<u>Clear</u>
<u>0901</u>	<u>7.17</u>	<u>1400</u>	<u>13.5</u>				<u>17</u>	<u>Clear</u>

Final: Time	pH	SC	Temp	Eh-ORP	D.O.	Turbidity	Ferrous Iron	Vol Evac.	Comments/Flow Rate
<u>0901</u>	<u>7.17</u>	<u>1400</u>	<u>13.5</u>					<u>17</u>	<u>Clear</u>

COMMENTS: Malvina Clah of the Navajo EPA arrived at 0830 hrs

INSTRUMENTATION: pH Meter ☒ _____ Temperature Meter ☒
 DO Monitor _____ Other _____
 Conductivity Meter ☒ _____
 Water Disposal Kutz Sample ID Jennapah MW-1 Sample Time 0910
BTEX VOCs Alkalinity TDS Cations Anions Nitrate Nitrite Ammonia TKN NMWQCC Metals Total Phosphorus
 MS/MSD _____ BD _____ BD Name/Time _____ TB 230903tb01

WELL DEVELOPMENT AND SAMPLING LOG

Project No: 30009.0 Project Name: San Juan Basin Client: MWH
 Location: Jennepah Well No: MW-1 Development ☐ Sampling ☒
 Project Manager: MON Date: 6-24-03 Start Time: 6735 Weather: 80s clear
 Depth to Water: 26'2 Depth to Product: — Product Thickness: — Measuring Point: TOC
 Water Column Height: 7.99 Well Dia.: 4in

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐
 Bottom Valve Bailer ☒ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐
 Criteria: 3 to 5 Casing Volumes of Water Removal ☒ Stabilization of Indicator Parameters ☒ Other: or bailing

Gal/ft x ft of water	Water Volume In Well		Gal/oz to be removed
	Gallons	Ounces	
<u>7.99 x .65</u>	<u>5.19 x 3</u>		<u>15.58</u>

Time (military)	pH	SC (umhos/cm)	Temp (°C)	Eh-ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gal.)	Comments/ Flow rate
<u>0740</u>	<u>6.63</u>	<u>2080</u>	<u>175</u>				<u>1</u>	<u>clear</u>
	<u>7.08</u>	<u>1430</u>	<u>165</u>				<u>2</u>	
<u>0752</u>	<u>7.10</u>	<u>1230</u>	<u>161</u>				<u>8</u>	
	<u>7.10</u>	<u>1140</u>	<u>164</u>				<u>12</u>	
	<u>7.12</u>	<u>1120</u>	<u>161</u>				<u>14</u>	
<u>0814</u>	<u>7.17</u>	<u>1110</u>	<u>159</u>				<u>16</u>	

Final:

Time	pH	SC	Temp	Eh-ORP	D.O.	Turbidity	Ferrous Iron	Vol Evac.	Comments/Flow rate
<u>0814</u>	<u>7.17</u>	<u>1110</u>	<u>159</u>					<u>16</u>	<u>clear</u>

COMMENTS: Mex as good water did not bail down

INSTRUMENTATION: pH Meter ☒ _____ Temperature Meter ☒ _____
 DO Monitor ☐ _____ Other ☐ _____
 Conductivity Meter ☒ _____
 Water Disposal: KITZ
 Sample ID: Jennepah MW-1 Sample Time: 0817 BTEX ☒ VOCs ☐ Alkalinity ☐
 TDS ☐ Cations ☐ Anions ☐ Nitrate ☐ Nitrite ☐ Ammonia ☐ TKN ☐ NM WQCC Metals ☐
 Total Phosphorus ☐ _____
 MS/MSD: _____ BD: _____ BD Name/Time: _____ TB 240603TB01

WELL DEVELOPMENT AND SAMPLING LOG

Project No: 30001.0 Project Name: San Juan Basin Client: MWH
 Location: Tennepah Well No: MW-2 Development ☐ Sampling ☒
 Project Manager MJ Ne Date 6.24.03 Start Time 0850 Weather 80s Clear
 Depth to Water 2655 Depth to Product - Product Thickness - Measuring Point TOC
 Water Column Height 5.05 Well Dia. 2"

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐
 Bottom Valve Bailer ☒ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐
 Criteria: 3 to 5 Casing Volumes of Water Removal ☒ Stabilization of Indicator Parameters ☒ Other or bail dry

Gal/ft x ft of water	Water Volume In Well		Gal/oz to be removed
	Gallons	Ounces	
<u>5.05 x 10</u>	<u>.808 x 3</u>		<u>2.42</u>

Time (military)	pH	SC (umhos/cm)	Temp (°C)	Eh-ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gal.)	Comments/Flow rate
<u>0856</u>	<u>6.85</u>	<u>1080</u>	<u>17.5</u>				<u>.5</u>	<u>silty</u>
	<u>7.06</u>	<u>1090</u>	<u>16.4</u>				<u>1</u>	
	<u>7.08</u>	<u>1120</u>	<u>16.1</u>				<u>1.5</u>	
	<u>7.04</u>	<u>1090</u>	<u>16.0</u>				<u>2.0</u>	
<u>0909</u>	<u>7.06</u>	<u>1090</u>	<u>16.3</u>				<u>2.5</u>	

Final:

Time	pH	SC	Temp	Eh-ORP	D.O.	Turbidity	Ferrous Iron	Vol Evac.	Comments/Flow rate
<u>0909</u>	<u>7.06</u>	<u>1090</u>	<u>16.3</u>					<u>2.5</u>	<u>Silty</u>

COMMENTS: Makes good water. Navejo EPA onsite

INSTRUMENTATION: pH Meter ☒ _____ Temperature Meter ☒ _____
 DO Monitor ☐ _____ Other ☐ _____
 Conductivity Meter ☒ _____

Water Disposal KUTZ

Sample ID Tennepah Sample Time 0915 BTEX ☒ VOCs ☐ Alkalinity ☐
 TDS ☐ Cations ☐ Anions ☐ Nitrate ☐ Nitrite ☐ Ammonia ☐ TKN ☐ NM WQCC Metals ☐
 Total Phosphorus ☐ _____
 MS/MSD _____ BD _____ BD Name/Time _____ TB 240031B41

WELL DEVELOPMENT AND SAMPLING LOG

Project No: 30001-0 Project Name: San Juan Basin Client: MWH
 Location: Tennepah Well No: MW-3 Development ☒ Sampling ☒
 Project Manager MJN Date 6/24/03 Start Time 0826 Weather 90s Clear
 Depth to Water 26.36 Depth to Product - Product Thickness - Measuring Point TOC
 Water Column Height 4.85 Well Dia. 2"

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐
 Bottom Valve Bailer ☐ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐
 Criteria: 3 to 5 Casing Volumes of Water Removal ☐ Stabilization of Indicator Parameters ☐ Other ☐

Gal/ft x ft of water	Water Volume In Well		Gal/oz to be removed
	Gallons	Ounces	
4.85 x 16	77.6	3	2.32

Time (military)	pH	SC (umhos/cm)	Temp (°C)	Eh-ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gal.)	Comments/Flow rate
0831	6.89	1110	17.8				.5	silty Tan
	7.17	1100	16.7				1	
	7.16	1100	16.2				1.5	
0838	7.5	1090	16.4				2.0	
0840	7.17	1110	16.3				2.5	

Final:
 Time 0840 pH 7.17 SC 1110 Temp 16.3 Eh-ORP - D.O. - Turbidity - Ferrous Iron - Vol Evac. 2.5 Comments/Flow rate silty tan

COMMENTS: Makes good water Navajo Epp onsite

INSTRUMENTATION: pH Meter ☒ Temperature Meter ☒
 DO Monitor ☐ Other ☐
 Conductivity Meter ☒

Water Disposal Kutiz
 Sample ID Tennepah MW-3 Sample Time 0844 BTEX ☒ VOCs ☐ Alkalinity ☐
 TDS ☐ Cations ☐ Anions ☐ Nitrate ☐ Nitrite ☐ Ammonia ☐ TKN ☐ NM WQCC Metals ☐
 Total Phosphorus ☐ ☐ ☐ ☐ ☐ ☐
 MS/MSD - BD - BD Name/Time - TB 240031801

Product Recovery and Well Observation Data

Project Name: San Juan Basin
Project Manager: MTN
Client Company: MWH
Site Name: Tennepah #1

Project No: 220013
Date: 3-13-03

Well	Time	Depth to Water (ft)	Depth to Product (ft)	Total Well Depth (ft)	Product Thickness (ft)	Volume Removed	Comments
MW-1	0839	25.85	—	—	—	—	
MW-2	0925	26.27	—	—	—	—	
MW-3	0938	26.07	—	—	—	—	

COMMENTS: _____

Signature: [Signature]

Date: 3-13-03

WELL DEVELOPMENT AND SAMPLING LOG

Project No: 220013 Project Name: San Juan Basin Client: MWH
 Location: Tennepah #1 Well No: MW-1 Development ☐ Sampling ☒
 Project Manager MTN Date 3-25-03 Start Time 1024 Weather Clear 40s
 Depth to Water 25 35 Depth to Product No Product Thickness No Measuring Point TOC
 Water Column Height 832 Well Dia. 4"

Sampling Method: Submersible Pump ☐ Centrifugal Pump ☐ Peristaltic Pump ☐ Other ☐
 Bottom Valve Bailer ☐ Double Check Valve Bailer ☐ Stainless-Steel Kemmerer ☐
 Criteria: 3 to 5 Casing Volumes of Water Removal ☐ Stabilization of Indicator Parameters ☐ Other ☐

Gal/ft x ft of water	Water Volume In Well		Gal/oz to be removed
	Gallons	Ounces	
<u>8.32 x .65</u>	<u>5.4 x 3</u>		<u>18.20</u>

Time (military)	pH	SC (umhos/cm)	Temp (°C)	Eh-ORP (millivolts)	D.O. (mg/L)	Turbidity (NTU)	Vol Evac. (gal.)	Comments/ Flow rate
<u>1024</u>	<u>658</u>	<u>1230</u>	<u>21</u>				<u>1</u>	<u>Clear</u>
	<u>72</u>	<u>1140</u>	<u>19</u>				<u>2</u>	<u>Large odiferous</u>
	<u>722</u>	<u>1090</u>	<u>178</u>				<u>3</u>	<u>sewage smell</u>
	<u>712</u>	<u>1070</u>	<u>173</u>				<u>4</u>	
	<u>725</u>	<u>1080</u>	<u>186</u>				<u>6</u>	
	<u>730</u>	<u>1240</u>	<u>184</u>				<u>8</u>	
	<u>735</u>	<u>1070</u>	<u>176</u>				<u>10</u>	<u>Clear</u>
	<u>739</u>	<u>1210</u>	<u>188</u>				<u>12</u>	
	<u>739</u>	<u>1090</u>	<u>184</u>				<u>14</u>	
	<u>738</u>	<u>1110</u>	<u>185</u>				<u>16</u>	
<u>1052</u>	<u>739</u>	<u>1100</u>	<u>185</u>				<u>18</u>	
<u>1053</u>								

Final:
 Time 1052 pH 739 SC 1100 Temp 185 Eh-ORP _____ D.O. _____ Turbidity _____ Ferrous Iron _____ Vol Evac. 18 Comments/Flow rate _____


COMMENTS: _____

INSTRUMENTATION: pH Meter ☒ _____ Temperature Meter ☒ _____
 DO Monitor ☐ _____ Other ☐ _____
 Conductivity Meter ☒ _____

Water Disposal KUTZ
 Sample ID Tennepah #1 MW-1 Sample Time 1053 BTEX ☒ VOCs ☐ Alkalinity ☐

DS ☐ Cations ☐ Anions ☐ Nitrate ☐ Nitrite ☐ Ammonia ☐ TKN ☐ NM WQCC Metals ☐
 Total Phosphorus ☐ _____
 MS/MSD _____ BD _____ BD Name/Time _____ TB 250303MTN-1

APPENDIX H
NAVAJO NATION EPA CLOSURE APPROVAL LETTER
(MARCH 2004)



NAVAJO NATION ENVIRONMENTAL PROTECTION AGENCY

P.O. Box 1999
Shiprock, New Mexico 87420
(505) 368-1040



Joe Shirley, Jr.
PRESIDENT

Frank Dayish, Jr.
VICE-PRESIDENT

March 8, 2004

Scott T. Pope
El Paso Energy Corporation
614 Reilly Avenue
Farmington, New Mexico
87401

Dear Mr. Pope:

Pursuant to your request, you may proceed with closure of the Jennapah #1 Pit Site (Sec.36H, T28N-R09W San Juan Co., NM). The Navajo Nation EPA bases its approval of this pit closure on the information and data provided by Montgomery Watson Harza to El Paso Field Services in their February 2004 Pit Closure Report. Analyses of the last three consecutive samples from MW-1, MW-2, and MW-3 at this site indicate Benzene concentrations of <1.0 ug/L; the USEPA and NNEPA limit standard for Benzene in groundwater is 5.0 ug/L (ppb).

Closure of the Jennapah #1 site must be done in compliance with the "*Unlined Surface Impoundment Closure Guidelines*" issued by the BLM - Farmington and Albuquerque Districts in December, 1993.

Approval by the Navajo Nation Environmental Protection Agency does not relieve El Paso Field Services of responsibility if remaining contaminants are found to pose a future threat to surface water, ground water, human health or the environment.

If you have any questions you may contact me at (505) 368-1040, or Jim Walker (USEPA) at (505) 599-6317.

Sincerely,

A handwritten signature in black ink, appearing to read "W. Freeman", is written over a horizontal line.

William E. Freeman
Senior Hydrologist
Navajo Nation Environmental Protection Agency - Shiprock

cc: Jim Walker (USEPA - Farmington)

Pam Anderson MWH

Groundwater FILE

OLD FILE