

Submit 1 Copy To Appropriate District
Office
District I - (575) 393-6161
1625 N. French Dr., Hobbs, NM 88240
District II - (575) 748-1283
811 S. First St., Artesia, NM 88210
District III - (505) 334-6178
1000 Rio Brazos Rd., Aztec, NM 87410
District IV - (505) 476-3460
1220 S. St. Francis Dr., Santa Fe, NM
87505

State of New Mexico
Energy, Minerals and Natural Resources

Form C-103
Revised August 1, 2011

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

WELL API NO.
30-015-20405

5. Indicate Type of Lease
STATE ☐ FEE ☒

6. State Oil & Gas Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS)

1. Type of Well: Oil Well ☒ Gas Well ☐ Other:

2. Name of Operator
Yates Petroleum Corporation

3. Address of Operator
105 South Fourth Street, Artesia, NM 88210

4. Well Location
Unit Letter L : 1650 feet from the South line and 990 feet from the West line
Section 23 Township 17S Range 25E NMPM Eddy County

11. Elevation (Show whether DR, RKB, RT, GR, etc.)
3507' GR

7. Lease Name or Unit Agreement Name
Gissler AV

8. Well Number
4

9. OGRID Number
025575

10. Pool name or Wildcat
Eagle Creek SA

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:

PERFORM REMEDIAL WORK ☐ PLUG AND ABANDON ☒
TEMPORARILY ABANDON ☐ CHANGE PLANS ☐
PULL OR ALTER CASING ☐ MULTIPLE COMPL ☐
DOWNHOLE COMMINGLE ☐

OTHER: ☐

SUBSEQUENT REPORT OF:

REMEDIAL
COMMENT
CASING

**SEE ATTACHED
CONDITIONS OF
APPROVAL**

OTHER: ☐

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 19.15.7.14 NMAC. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

Yates Petroleum Corporation plans to plug and abandon this well as follows:

1. MIRU. Install BOP. TOOH with production equipment. LD rods and pump.
2. TIH with CIBP and set at 1,230 feet.
3. Cement to surface with 150 SX Class C cement.
4. Cut off wellhead, install dry hole marker and clean location as per regulations.

Wellbore schematics attached.

NOTE: Yates Petroleum Corporation will use steel pits and no earth pits.

Spud Date:

Rig Release Date:

RECEIVED

APR 2 2012

NMOCD ARTESIA

Notify OCD 24 hrs. prior
to any work done.

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Sharon Coll TITLE Regulatory Reporting Technician DATE March 29, 2012


Type or print name Sharon Coll E-mail address: scoll@yatespetroleum.com PHONE: 575-748-4507

For State Use Only

APPROVED BY: [Signature] TITLE Approval Granted providing work is complete by 7/9/2012 DATE 4/9/2012
Conditions of Approval (if any):

Well Name: Gissler AV #4 Field: Eagle Creek
 Location: 1650' FSL & 990' FWL Sec 23-17S-25E
 County: Eddy State: New Mexico
 GL: 3,507' Zero: KB:
 Spud Date: 4/9/1971 Completion Date: 4/21/1971
 Comments: API # 30015204050000

Casing Program	
Size/WV/Grade	Depth Set
10 3/4" 32# K-55	209'
7" 23# K-55	1,143'
4 1/2" 9.5# & 5 1/2" 15.5# K-55	1,454'




SKETCH NOT TO SCALE

DATE: 2/7/2012

Well Name: Gissler AV #4 Field: Eagle Creek
 Location: 1650' FSL & 990' FWL Sec 23-17S-25E
 County: Eddy State: New Mexico
 GL: 3,507' Zero: KB:
 Spud Date: 4/9/1971 Completion Date: 4/21/1971
 Comments: API # 30015204050000

Casing Program	
Size/Wt/Grade	Depth Set
10 3/4" 32# K-55	209'
7" 23# K-55	1,143'
4 1/2" 9.5# & 5 1/2" 15.5# K-55	1,454'



SKETCH NOT TO SCALE

DATE: 2/7/2012

NEW MEXICO OIL CONSERVATION DIVISION
DISTRICT 2 OFFICE
811 S. FIRST STREET
ARTESIA, NM 88210
(575)748-1283

CONDITIONS OF APPROVAL FOR PLUGGING & ABANDONMENT

Operator: Yates Petroleum Corp.
Well Name & Number: Gissler AV # 4
API #: 30-015-20405

1. Produced water **will not** be used during any part of the plugging & abandonment operation.
2. Notify NMOCD Dist. 2 office at least 24 hrs before beginning work.
3. Closed Loop System is to be used for entire plugging operation. Upon completion, contents of steel pit are to be hauled to a permitted disposal location.
4. Trucking companies being used to haul oilfield waste fluids to a disposal – commercial or private – shall have an approved NMOCD C-133 permit. A copy of this permit shall be available in each truck used to haul waste products. It is the responsibility of the operator, as well as the contractor, to verify that this permit is place prior to performing work. Drivers shall produce a copy upon request of NMOCD Field Inspectors.
5. A subsequent C-103 will serve as notification that the well bore has been plugged **ONLY**. A C-103 FINAL shall be filed before any bonding can be released on the well. Upon receipt of the Final, an inspection will be performed to verify that the location has been satisfactorily cleaned to NMOCD standards.
6. If work has not begun within 90 days of the approval of this procedure, an extension request must be filed, stating reason that well has not been plugged.
7. Every attempt must be made to clean the well bore out to below the perms, before any plugs can be set, by whatever means possible.

8. Cement Retainers may not be used.

9. Squeeze pressures not to exceed 500 psi., unless approval is given by NMOCD Plugging Supervisor.

10. Plugs may be combined after consulting with NMOCD P & A Supervisor.

11. Minimum WOC time for tag plugs will be 4 hrs.

Date: 4/9/2012