Form 3160-3 (August 2007)

UNITED STATES DEPARTMENT OF THE INTERIOR

BUREAU OF LAND MANAGEMENT

FORM APPROVED OMB No 1004-0137 Expires July 31, 2010

5 Lease Serial No. NM-99014

APPLICATION FOR PERMIT TO	6. If Indian, Allotee or Tribe Name								
la. Type of work: DRILL REENT		7. If Unit or CA Agre	eement, Na	ıme an	d No.				
lb. Type of Well: ✓ Oil Well ☐ Gas Well ☐ Other									
2. Name of Operator Mewbourne Oil Company		4744	>	9 API Well No.	: 40	5 <u>2</u>	05		
3a. Address PO Box 5270	3b Phone No	,		10. Field and Pool, or	Explorator	y	1 C l		
Hobbs, NM 88240	(575) 393-	5905		North Seven River	 				
4. Location of Well (Report location clearly and in accordance with a	ny State requirem	ents.*)	ال ۱۱ ، سا	11. Sec., T. R. M. or E		rvey o	r Area		
At surface 160' FNL & 1670' FEL (Unit B)		UNORT	TION	Sec 17, T20S, R25	įΕ				
At proposed prod. zone 330' FSL & 1670' FEL (Unit O)		LOCA	11101	1					
 Distance in miles and direction from nearest town or post office* 19.5 miles NW of Carlsbad, NM 			·	12 County or Parish Eddy		13. S NM	tate		
15 Distance from proposed* location to nearest property or lease line, ft (Also to nearest drig. unit line, if any)	16. No. of a 320	cres in lease	17 Spacin 160	g Unit dedicated to this	well				
18 Distance from proposed location* 560' West of the Pine	19 Propose	d Depth	20 BLM/I	BIA Bond No. on file	•	0			
to nearest well, drilling, completed, Box 17 Fed Com #1 applied for, on this lease, ft.	7094' MD 2554' TVD			, Nationwide					
21 Elevations (Show whether DF, KDB, RT, GL, etc.)		mate date work will star	rt*	23. Estimated duration	n				
3510' GL	06/15/201			12 days					
	24. Attac								
The following, completed in accordance with the requirements of Onsho	re Oil and Gas	Order No.1, must be at	ttached to thi	s form:					
 Well plat certified by a registered surveyor. A Drilling Plan. 		4 Bond to cover the Item 20 above).	he operation	ns unless covered by an	existing b	ond o	n file (see		
3 A Surface Use Plan (if the location is on National Forest System SUPO must be filed with the appropriate Forest Service Office)	Lands, the			ormation and/or plans as	s may be r	equire	d by the		
25 8:	Nama	BLM. (Printed/Typed)			Date				
25 Signature R n H R a L		(<i>i rimeu rypeu)</i> Bednarz			02/23/2	2012			
Title Petroleum Engineer	_				<u></u>				
Approved by (Signature) Codi L. Lauther	Name	(Printed/Typed)			APR	1	8 2012		
Title FIELD MANAGER	Office	CARLSBAD F	IELD OFF	ICE	J				
Application approval does not warrant or certify that the applicant hold	ls legal or equi	table title to those righ	ts in the sub	ject lease which would o	entitle the a	applica	ant to		
conduct operations thereon Conditions of approval, if any, are attached.	···			APPROVAL	FOR 7	ΓW(O YEARS		
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a c States any false, fictitious or fraudulent statements or representations as			villfully to m	ake to any department of	or agency	of the	United		

(Continued on page 2)

Roswell Controlled Water Basin

RECEIVED

APR 23 2012

*(Instructions on page 2)

SEE ATTACHED FOR CONDITIONS OF APPROVAL **NMOCD ARTESIA**

Approval Subject to General Requirements & Special Stipulations Attached

Mewbourne Oil Company

PO Box 5270 Hobbs, NM 88241 (575) 393-5905

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Executed this 23 day of Fed., 2012.

Name: NM Young

Signature: Forth Bedy

Young

Position Title: Hobbs District Manager

Address: PO Box 5270, Hobbs NM 88241

Telephone: <u>575-393-5905</u>

E-mail: myoung@mewbourne.com

DISTRICT I
1625 N. French Dr., Hobbs, NM 88240
Phone (575) 393-6161 Fax: (575) 393-0720
DISTRICT II
811 S. First St., Artesia, NM 88210
Phone (575) 748-1283 Fax: (575) 748-9720
DISTRICT III

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-102 Revised August 1, 2011

Submit one copy to appropriate
District Office

OIL CONSERVATION DIVISION

WELL LOCATION AND ACREAGE DEDICATION PLAT

1220 South St. Francis Dr. Santa Fe, New Mexico 87505

☐ AMENDED REPORT

DISTRICT IV 1220 S. St. Francis Dr., Santa Fe, NM 87505 Phone (505) 478-3460 Fax: (505) 476-3462

1000 Rio Brazos Rd., Aztec, NM 87410 Phone (505) 334-6178 Fax: (505) 334-6170

API Number 30-0/5-40205 97565 North Seven Rivers-Glorietta Yese

Property Code Property Name Well Number 1H OGRID No.

Operator Name Elevation 14744 MEWBOURNE OIL COMPANY 3510'


Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
В	17	20 S	25 E		160	NORTH	1670	EAST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
0	17	20 S	25 E		330	SOUTH	1670	EAST	EDDY
Dedicated Acre	Joint o	r Infill Co	nsolidation (Code Or	der No.				
160									

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



<u>Drilling Program</u> Mewbourne Oil Company

Pine Box "17" BO Fed #1H 160' FNL & 1670' FEL (SHL) Sec 17-T20S-R25E Eddy County, New Mexico

1. The estimated tops of geological markers are as follows:

Grayburg 430'
*San Andres 710'
*Glorietta 2300'
*Yeso 2470'

2. Estimated depths of anticipated fresh water, oil, or gas:

Water Fresh water is anticipated @ 190' and will be protected by setting surface

casing at 735' and cementing to surface.

Hydrocarbons Oil and gas are anticipated in the above (*) formations. These zones will

be protected by casing as necessary.

3. Pressure control equipment:

A 2000# WP annular BOP will be installed after running 9 %" & 7" casing. Pressure tests will be conducted and BOPE will remain in use until completion of drilling operations. The BOP will be inspected and operated daily to ensure mechanical integrity and the inspection will be recorded on the daily drilling report.

Will test the BOPE to 1500# with a third party testing company before drilling below shoe as per BLM Onshore Oil and Gas Order #2.

4. MOC proposes to drill a vertical wellbore to 2028' & kick off to horizontal @ 2506' TVD. The well will be drilled to 7094' MD (2554' TVD). See attached directional plan.

5. Proposed casing and cementing program:

A. Cas	ing Program:			~	
Hole Size	Casing	<u>Wt/Ft.</u>	<u>Grade</u>	<u>Depth</u>	<u>Jt Type</u>
12 1/4"	9 %" (new)	36#	J55	0'-735'	LT&C
8 ³ / ₄ "	7" (new)	26#	J55	0'-2028'	LT&C
8 ³ / ₄ "	7" (new)	26#	J55	2028'-2773' MD	BT&C
6 1/8"	4 ½" (new)	11.6#	J55	2573'-7094' MD	LT&C

Minimum casing design factors: Collapse 1.125, Burst 1.0, Tensile strength 1.8. *Subject to availability of casing.

B. Cementing Program:

- i. <u>Surface Casing</u>: 350 sacks Class "C" w/2% CaCl2. Yield at 1.34 cuft/sk. Cmt circulated to surface with 100% excess.
- ii. <u>Production Casing</u>: 150 sacks Class C light cement w/ salt & LCM additives. Yield at 2.05 cuft/sk. 400 sacks Class C cement w/ fluid loss & R3 additives. Yield at 1.33 cuft/sk Cmt circulated to surface with 25% excess.
- iii. <u>Production Liner</u>: This will be a Packer/Port completion from TD up inside 7" casing with packer type liner hanger.

Drilling Program Mewbourne Oil Company Pine Box "17" BO Fed #1H Page 2

*Referring to above blends of lite cement: (wt% fly ash: wt% cement: wt% bentonite of the total of first two numbers). Generic names of additives are used since the availability of specific company and products are unknown at this time.

6. Mud Program:

<u>Interval</u>	Type System	Weight	<u>Viscosity</u>	Fluid Loss
0'-735'	FW spud mud	8.6-9.0	32-34	NA
735'-1928' (KOP-100')	Fresh water	8.4-8.6	28-30	NA
1928'- TD	FW w/ Polymer	8.5-8.7	32-35	20

7. Evaluation Program: See CoA

Samples: 10' samples from surface casing to TD. Logging: Gyro, CN,& GR Surface to 1928'.

8. Downhole Conditions

Zones of abnormal pressure: None anticipated

Zones of lost circulation: Anticipated in surface and intermediate holes

Maximum bottom hole temperature: 100 degree F

Maximum bottom hole pressure: 8.4 lbs/gal gradient or less

9. Anticipated Starting Date:

Mewbourne Oil Company intends to drill this well as soon as possible after receiving approval with approximately 15 days involved in drilling operations and an additional 10 days involved in completion operations on the project.

Mewbourne Oil Co

Eddy County, New Mexico Sec 17-20S-25E Pine Box 17BO Federal #1H

Pine Box 17BO Fed 1H

Plan: Design#2

DDC Well Planning Report

22 February, 2012



DDC

Well Planning Report



BILLIAN SALIS S Database: Local Co-ordinate Reference: EDM 5000.1 Single User Db Well Pine Box 17BO Federal #1H Company: Mewbourne Oil Co TVD Reference: GL 3510 +19' KB @ 3529.0usft (Patterson UTI-101) Eddy County, New Mexico GL 3510 +19' KB @ 3529.0usft (Patterson MD Reference UTI-101) Sec 17-20S-25E North Reference Grid Pine Box 17BO Federal #1H Survey Calculation Method: Minimum Curvature Pine Box 17BO Fed 1H Wellbore:

Project Eddy County, New Mexico

Design#2

Map System: Map Zone:

US State Plane 1927 (Exact solution)

Geo Datum:

NAD 1927 (NADCON CONUS)

New Mexico East 3001

System Datum:

Mean Sea Level

Sec 17-20S-25E

Site Position:

From:

Мар

Northing:

574,694.25 usft

Latitude: Longitude: 32° 34' 47 393 N

Position Uncertainty:

Easting:

448,901,26 usft

104° 29' 57,203 W

-0.09

0.0 usft Slot Radius:

13-3/16 "

Grid Convergence:

THE REPORT OF THE PARTY OF THE Well Pine Box 17BO Federal #1H UDING ANTAN KANDUR SANDIYAN IN ING MARKAN KANDUR IN PROGRAMMAN KANDAN K Well Position +N/-S 211.7 usft 32° 34' 49.469 N Northing: 574.906.00 usft Latitude: 104° 30' 11.731 W +E/-W -1,242.7 usft 447,658.57 usft Easting: Longitude: 3,510.0 usft **Position Uncertainty** 0.0 usft Wellhead Elevation: **Ground Level:**

1	Wellbore Pine Box 17BO F		aliging stational for the property of the prop		\$
Party Land St.	Magnetics Model Name	Sample Date	Declination Dip	Angle F	eld Strength
3	IGRF20	2/14/2012	7 96	60.34	48,658

Design Design#2 Audit Notes:			en eren en maar en erene beloek met en aan en madelek En stern bekommen fant 'n 'n bestisk fan 'n beloegt k		
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0	
Vertical Section:	Depth From (TVD) (usft) 0.0	+N/-S (usft) 0.0	+E/-W (usft) 0.0	Direction (c) (7) (7) (7) (7) (7) (7) (7) (7) (7) (7	

# SE 783	Sections asured epth Incliiusfi) (nation A	zimuth	· 原则 。	+N/S (usft)	+E/-W	Rate	Service and the service of the servi	The state of the s	TFO	Target
	A DESCRIPTION OF THE PERSON OF					等源。据《本》 。			Grant State		
	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
	2,028.6	0.00	360.00	2,028.6	0.0	0.0	0.00	0.00	0.00	360.00	
	2,773.3	89.36	179.73	2,506.0	-472.2	2.2	12.00	12.00	24.13	179.73	
	7,093.5	89.36	179.73	2,554.0	-4,792.0	22.6	0.00	0.00	0.00	0.00 Pine	Box 17 BO Fed ·

DDC

Well Planning Report



Database:

Eddy County, New Mexico

Sec 17-20S-25E

Site: Well: Wellbore: Design: Pine Box 17BO Federal #1H Pine Box 17BO Fed 1H

Design#2

MD Reference:

North Reference:

Survey Calculation Method:

EDM 5000.1 Single User Db

Local Co-ordinate Reference: Well Pine Box 17BO Federal #1H

Mewbourne Oil Co

TVD Reference: GL 3510 +19' KB @ 3529.0usft (Patterson UTI-101)

UTI-101)

GL 3510 +19' KB @ 3529.0usft (Patterson

UTI-101)

Minimum Curvature

The State Column	Design L	resign#2	e	CHARLES AND		59.78 7 6.123(8)	encial and the		with and the second the same	and the construction of the construction
Measured Vertical Pepti		NORTH WAR TO SELECT	经2000年的基本的基本的企业	ion-representation of the state	BUTTERS TO SEE THE SEE THE SEE THE SEE	经过少时间的时间的时间的	66%,在其中,10年1日1日,10年1日	995. CA \$10 \$-\$15 CA \$25 CA \$2	a the whereast continues of	LOTERATORICANE PARTICIPAL AND CONTRACTOR AND CONTRA
Part	Planned Survey	inderen er en	VALUE AND SERVICE OF THE SERVICE	Marian Carlos Ca	andri Safakka Prancis G	har yn Ca T iaeologiae	TESTERATION OF THE SEC	Carametrace - Stead of	touthouse the control of the control	n magnetem etterset
Capt						the Telephone				
Carbon C	Measured	And the second second		Vertical			Vertical	Doalea	Build	Turn
Company Comp	是一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个	4.4		A STATE OF THE STA			TOP COMPANY OF THE PARTY OF THE		THE REPORT OF THE PERSON OF TH	
0.0 0.00 0.00 0.00 0.00 0.0 0.0 0.0 0.0	The state of the s	Market Street British and Street Street Street	A TOTAL OF THE PARTY OF THE PAR	SECTION AND LANGE OF THE PARTY	Manager and the second second	CONTRACTOR AND	The state of the state of the state of	2. 15-11-16-16-15-15-15-15-15-15-15-15-15-15-15-15-15-	是是一个人,他们就是他们不是一个人的。 第二章	经产品的工具 "这个好一个时间的一个
20.2 2028 FB Sepin Build 92* DLS 20.28 6 0.00 380.00 2.028.6 0.0 0.0 0.0 0.0 0.00 0.00 0.00 2,100.0 8.67 179.73 2.098.7 -5.3 0.0 5.3 12.00 12.00 0.00 2,200.0 20.67 179.73 2.198.3 -30.4 0.1 30.4 12.00 12.00 0.00 2,300.0 32.67 179.73 2.285.6 -75.1 0.4 75.1 12.00 12.00 0.00 2,300.0 32.67 179.73 2.285.6 -75.1 0.4 75.1 12.00 12.00 0.00 2,500.0 56.57 179.73 2.285.6 -75.1 0.4 75.1 12.00 12.00 0.00 2,500.0 56.57 179.73 2.497.1 -214.4 1.0 214.4 1.0 21.00 12.00 0.00 2,700.8 0.57 179.73 2.497.3 -303.0 1.4 303.0 12.00 12.00 0.00 2,700.8 0.57 179.73 2.497.3 -303.0 1.4 303.0 12.00 12.00 0.00 2,700.8 0.57 179.73 2.497.5 -3.992.2 1.9 399.2 12.00 12.00 0.00 2,700.8 0.57 179.73 2.500.4 472.2 2.2 472.2 11.99 11.99 0.00 2,700.8 0.57 179.73 2.500.3 472.2 2.2 472.2 11.99 11.99 0.00 2,800.0 89.36 179.73 2.500.3 472.2 2.2 472.2 11.99 11.99 0.00 2,800.0 89.36 179.73 2.500.3 4.89.8 2.8 588.9 0.00 0.00 0.00 3,100.0 89.36 179.73 2.500.3 4.89.8 3.3 588.8 8.00 0.00 0.00 3,100.0 89.36 179.73 2.500.6 8.89.8 3.3 8.88.8 0.00 0.00 0.00 3,100.0 89.36 179.73 2.500.6 8.89.8 3.3 8.88.8 0.00 0.00 0.00 3,100.0 89.36 179.73 2.510.8 8.89.8 4.7 998.8 0.00 0.00 0.00 3,100.0 89.36 179.73 2.511.8 8.98.8 4.7 998.8 0.00 0.00 0.00 3,100.0 89.36 179.73 2.511.8 8.98.8 4.7 998.8 0.00 0.00 0.00 3,100.0 89.36 179.73 2.511.8 8.98.8 4.7 998.8 0.00 0.00 0.00 3,100.0 89.36 179.73 2.511.8 8.98.8 4.7 998.8 0.00 0.00 0.00 3,500.0 89.36 179.73 2.511.9 8.98.8 4.7 998.8 0.00 0.00 0.00 3,500.0 89.36 179.73 2.511.9 8.98.8 4.7 998.8 0.00 0.00 0.00 3,500.0 89.36 179.73 2.511.8 8.98.8 1.7 1.1 1.498.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2.511.9 8.98.8 4.7 998.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2.511.8 8.98.8 1.7 1.1 1.498.8 0.00 0.00 0.00 0.00 0.00 0.00 0.00	(usft)	(°) (°)	(°)	(usft)	(usft)	(usft)				/100ust)
2028 FWD: Repline Build @ 12* DLS 2.028 6 0.00 380.00 2.028 5 0.0 0.0 0.0 0.0 0.0 0.0 0.00 2.100.0 8.57 179.73 2.798.3 -30.4 0.1 30.4 12.00 12.00 0.00 2.200.0 2.57 179.73 2.798.3 -30.4 0.1 30.4 12.00 12.00 0.00 2.300.0 32.57 179.73 2.285.5 -75.1 0.4 75.1 12.00 12.00 0.00 2.300.0 46.67 179.73 2.285.5 -75.1 0.4 75.1 12.00 12.00 0.00 2.300.0 46.67 179.73 2.2827.1 -214.4 0.0 244.4 12.00 12.00 0.00 2.300.0 86.57 179.73 2.2472.1 -214.4 0.0 244.4 12.00 12.00 0.00 2.700.0 80.57 179.73 2.2472.1 -214.4 1.0 244.4 12.00 12.00 0.00 2.700.0 80.57 179.73 2.2495.6 -398.2 1.9 399.2 12.00 12.00 0.00 2.700.0 80.57 179.73 2.2495.6 -398.2 1.9 399.2 12.00 12.00 0.00 2.773.3 MD: End of Curve wiR9.36* Incl. 178.73* Pline Box 17 BO Ted. 114 Landing Pt. 2.773.3 80.36 179.73 2.506.0 472.2 2.2 472.2 11.99 11.99 0.00 2.900.0 89.36 179.73 2.506.5 -598.8 2.8 599.9 0.00 0.00 0.00 3.000.0 89.36 179.73 2.506.5 -598.8 3.3 698.8 0.00 0.00 0.00 3.000.0 89.36 179.73 2.506.5 -598.8 3.3 698.8 0.00 0.00 0.00 3.000.0 89.36 179.73 2.506.5 -598.8 3.3 698.8 0.00 0.00 0.00 3.000.0 89.36 179.73 2.506.5 -598.8 3.8 798.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.8 -898.8 4.2 898.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.8 -898.8 4.2 898.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.8 -898.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.8 -898.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.8 -898.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.7 1.198.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.7 1.198.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.7 1.198.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.9 1.198.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.9 1.198.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.9 1.198.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.9 1.198.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.9 1.198.8 5.2 1.098.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.516.9 1.198.8 0.00 0.00 0.00 3.300.0 89.36 179.73 2.526.8 1.198.8 0.00 0.00 0.00 0.00 0.00 0.00	THE STREET PROPERTY OF THE PARTY OF	The Later of Car	outsign selections	Herrich Strategy (1986)	能以 的常识。					San strategica for contract transcrip
2,028.6 0.00 860.00 2,028.6 0.0 0.0 0.0 0.0 0.00 0.00 0.00 2,100.0 8.57 179.73 2,196.3 3.0.4 0.1 30.4 12.00 12.00 0.00 2,200.0 20.57 179.73 2,196.3 30.4 0.1 30.4 12.00 12.00 0.00 2,300.0 32.67 179.73 2,286.6 -75.1 0.4 75.1 12.00 12.00 0.00 2,500.0 56.57 179.73 2,286.7 173.3 0.6 137.3 12.00 12.00 0.00 2,500.0 56.57 179.73 2,437.1 -214.4 1.0 214.4 1.0 214.4 1.0 210.0 12.00 0.00 2,700.8 0.57 179.73 2,437.1 -303.0 1.4 303.0 12.00 12.00 0.00 2,700.8 0.57 179.73 2,437.5 -399.2 1.9 399.2 12.00 12.00 0.00 12.00 0.00 12.70 0.00 12.00 12.00 0.00 12.00 12.00 0.00 0	0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
2,028.6 0.00 860.00 2,028.6 0.0 0.0 0.0 0.0 0.00 0.00 0.00 2,100.0 8.57 179.73 2,196.3 3.0.4 0.1 30.4 12.00 12.00 0.00 2,200.0 20.57 179.73 2,196.3 30.4 0.1 30.4 12.00 12.00 0.00 2,300.0 32.67 179.73 2,286.6 -75.1 0.4 75.1 12.00 12.00 0.00 2,500.0 56.57 179.73 2,286.7 173.3 0.6 137.3 12.00 12.00 0.00 2,500.0 56.57 179.73 2,437.1 -214.4 1.0 214.4 1.0 214.4 1.0 210.0 12.00 0.00 2,700.8 0.57 179.73 2,437.1 -303.0 1.4 303.0 12.00 12.00 0.00 2,700.8 0.57 179.73 2,437.5 -399.2 1.9 399.2 12.00 12.00 0.00 12.00 0.00 12.70 0.00 12.00 12.00 0.00 12.00 12.00 0.00 0	2028.6'MD: Begi	in Build @ 12°	DLS							
2,100.0 8.57 179.73 2,196.3 -30.0 5.3 12.00 12.00 0.00 2,200.0 2,500.0 32.57 179.73 2,196.3 -30.4 0.1 30.4 12.00 12.00 0.00 2,300.0 32.57 179.73 2,196.3 -30.4 0.1 30.4 12.00 12.00 0.00 2,400.0 4.57 179.73 2,285.6 7.51 0.4 75.1 12.00 12.00 0.00 2,500.0 58.57 179.73 2,283.7 -137.3 0.6 137.3 12.00 12.00 0.00 2,500.0 58.57 179.73 2,247.1 291.4 1.0 214.4 12.00 12.00 12.00 0.00 2,500.0 86.57 179.73 2,479.6 30.00 1.4 303.0 12.00 12.00 0.00 2,700.0 86.57 179.73 2,479.6 399.2 1.9 399.2 12.00 12.00 0.00 12.73.3 190.5 190	_	_		2 028 6	0.0	0.0	0.0	0.00	0.00	0.00
2200.0 20.57 179.73 2,285.6 -75.1 0.4 75.1 12.00 12.00 0.00 2.300.0 32.57 179.73 2,285.6 -75.1 0.4 75.1 12.00 12.00 0.00 2.300.0 44.57 179.73 2,285.6 -75.1 0.4 75.1 12.00 12.00 0.00 2.500.0 58.57 178.73 2,247.3 0.30.0 14.4 303.0 12.00 12.00 0.00 2.500.0 58.57 178.73 2,2473.0 303.0 14.4 303.0 12.00 12.00 0.00 2.500.0 80.57 178.73 2,473.0 303.0 14.4 303.0 12.00 12.00 0.00 2.500.0 80.57 178.73 2,473.0 303.0 14.4 303.0 12.00 12.00 0.00 2.500.0 80.57 178.73 2,493.6 399.2 19.3 399.2 12.00 12.00 0.00 2.500.0 12.70 12.00 0.00 2.500.0 10.5 1.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 0.00 12.00 12.00 12.00 0.00 12.00 12.00 12.00 0.00 12.00 12.00 12.00 12.00 0.00 12.00 12.00 12.00 12.00 0.00 12.00 12.00 12.00 12.00 12.00 0.00 12	1			•						
2,300,0 32,57 179,73 2,285,6 75,1 0.4 75,1 12,00 12,00 0.00 2,400,0 44,57 179,73 2,437,1 -137,3 0.6 137,3 12,00 12,00 0.00 0.00 2,500,0 56,57 179,73 2,427,1 -214,4 1.0 214,4 1.0 12,00 12,00 0.00 2,700,0 68,57 179,73 2,473,0 -303,0 1,4 303,0 12,00 12,00 0.00 0.00 2,700,0 189,36 179,73 2,473,0 -303,0 1,4 303,0 12,00 12,00 0.00 0.00 12,773,3 80,36 179,73 2,499,6 -399,2 1,9 399,2 12,0 12,00 0.00 0.00 0.00 0.00 0.00 0.00 0.00										
2,400.0	1			_,						
2,500,0 56,67 179,73 2,473,0 -303,0 14 10 2144 12,00 12,00 0,00 2,000, 68,57 179,73 2,473,0 -303,0 14, 303,0 12,00 12,00 12,00 0,00 2,700,0 80,57 179,73 2,473,0 -303,0 14, 303,0 12,00 12,00 12,00 0,00 2,700,0 80,57 179,73 2,499,6 399,2 1.9 399,2 12,00 12,00 0,00 0,00 2,773,3 MD: End of Curve wi89,36* In -Am. 179,73* 2,506,0 472,2 2,2 472,2 11,99 11,99 0,00 0,00 2,900,0 89,36 179,73 2,506,4 498,9 2,4 499,9 0,00 0,00 0,00 0,00 3,000,0 89,36 179,73 2,506,6 699,8 3,3 699,8 0,00 0,00 0,00 0,00 3,100,0 89,36 179,73 2,509,7 -798,8 3,8 798,8 0,00 0,00 0,00 0,00 3,100,0 89,36 179,73 2,509,7 -798,8 3,8 798,8 0,00 0,00 0,00 0,00 3,200,0 89,36 179,73 2,510,8 898,8 4,2 898,8 0,00 0,00 0,00 0,00 3,100,0 89,36 179,73 2,510,8 898,8 4,2 898,8 0,00 0,00 0,00 0,00 3,100,0 89,36 179,73 2,510,8 198,8 198,8 4,2 898,8 0,00 0,00 0,00 0,00 3,500,0 89,36 179,73 2,513,0 1,098,8 5,2 1,098,8 0,00 0,00 0,00 0,00 3,500,0 89,36 179,73 2,513,0 1,098,8 5,2 1,098,8 0,00 0,00 0,00 0,00 3,500,0 89,36 179,73 2,514,1 1,198,8 5,7 1,198,8 0,00 0,00 0,00 0,00 3,500,0 89,36 179,73 2,514,1 1,198,8 5,7 1,198,8 0,00 0,00 0,00 0,00 3,700,0 89,36 179,73 2,516,3 1,398,8 6,5 1,298,8 0,00 0,00 0,00 0,00 3,500,0 89,36 179,73 2,516,3 1,398,8 6,5 1,398,8 0,00 0,00 0,00 0,00 3,500,0 89,36 179,73 2,516,3 1,398,8 6,5 1,398,8 0,00 0,00 0,00 0,00 4,000 89,36 179,73 2,516,3 1,398,8 6,5 1,398,8 0,00 0,00 0,00 0,00 4,000 89,36 179,73 2,516,5 1,598,8 7,6 1,598,8 0,00 0,00 0,00 0,00 4,000 89,36 179,73 2,518,5 1,598,8 7,6 1,598,8 0,00 0,00 0,00 0,00 4,000 89,36 179,73 2,518,5 1,598,8 7,6 1,598,8 0,00 0,00 0,00 0,00 4,000 89,36 179,73 2,518,5 1,798,8 8,5 1,798,8 0,00 0,00 0,00 0,00 4,000 89,36 179,73 2,518,5 1,998,7 1,998,7 9,0 1,998,7 0,00 0,00 0,00 0,00 0,00 0,00 4,000 89,36 179,73 2,520,8 1,798,8 8,5 1,798,8 0,00 0,00 0,00 0,00 0,00 0,00 0,00	2,300.0	32.57	179.73	2,285.6	<i>-</i> 75.1	0.4	75.1	12.00	12.00	0.00
2,500.0 56.57 179.73 2,473.0 -303.0 14 1.0 214.4 12.0 12.00 12.00 0.00 2,700.0 80.57 179.73 2,473.0 -303.0 14.8 303.0 12.00 12.00 12.00 0.00 2,700.0 80.57 179.73 2,489.6 399.2 1.9 399.2 12.00 12.00 0.00 2,700.0 80.57 179.73 2,489.6 399.2 1.9 399.2 12.00 12.00 0.00 0.00 2,773.3 MD: End of Curve wi89.36° IndAm. 179.73 2,506.0 472.2 2.2 472.2 11.99 11.99 0.00 0.00 2.900.0 89.36 179.73 2,506.3 498.9 2.4 499.9 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,506.6 6.99.8 2.8 599.9 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,506.6 6.99.8 3.3 699.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,506.6 6.99.8 3.3 699.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,510.8 8.99.8 4.2 898.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,510.8 8.99.8 4.2 898.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,510.8 8.99.8 4.2 898.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,511.9 -998.8 4.7 998.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,511.9 -998.8 4.7 998.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,511.9 1.998.8 5.2 1.098.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,513.0 1.098.8 5.2 1.098.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,515.5 1.198.8 5.7 1.198.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,515.5 1.198.8 5.7 1.198.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,516.3 1.398.8 6.5 1.298.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,516.3 1.398.8 6.5 1.298.8 0.00 0.00 0.00 0.00 4.00 0.3 3,000.0 89.36 179.73 2,516.3 1.398.8 6.6 1.298.8 0.00 0.00 0.00 0.00 4.00 0.00 4.00 0.00 89.36 179.73 2,516.5 1.398.8 8.0 0.00 0.00 0.00 0.00 4.00 0.00 89.36 179.73 2,516.5 1.398.8 8.0 0.00 0.00 0.00 0.00 4.00 0.00 0.	2 400 0	44.57	470.72	0.262.7	107.0	0.6	127.2	12.00	12.00	0.00
2,600.0 68.57 179.73 2,499.6 3.99.2 1.9 399.2 12.00 12.00 0.00 2773.3MD: End of Curve wi89.38° Incl Azm. 179.73 - 2,499.6 3.99.2 1.9 399.2 12.00 12.00 0.00 2773.3MD: End of Curve wi89.38° Incl Azm. 179.73 - 2,506.0 472.2 2.2 472.2 11.99 11.99 0.00 0.00 2.900.0 89.36 179.73 2,506.3 4.99.9 2.4 498.9 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,506.6 6.99.8 3.3 598.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,506.6 6.99.8 3.3 598.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,509.6 6.99.8 3.3 598.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,509.6 6.99.8 8.3 3.3 698.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,510.8 898.8 4.2 898.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,510.8 898.8 4.2 898.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,511.9 998.8 4.7 998.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,511.9 998.8 4.7 998.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,511.4 1,188.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,511.5 1.988.8 5.2 1,198.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,515.2 1,288.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,515.2 1,288.8 6.1 1,288.8 0.00 0.00 0.00 0.00 3.0000.0 89.36 179.73 2,515.5 1,598.8 6.5 1,398.8 0.00 0.00 0.00 0.00 0.00 0.00 0.00				•						
2,700.0	,			•						
2773.3*WD: End of Curve w/88.36* incl Azm. 179.73* - Pine Box 17 BO Fed. 1H Landing Pt. 2,773.3	2,600.0	68.57		2,473.0	-303.0	1.4	303.0	12.00	12.00	0.00
2,773.3 89.36 179.73 2,506.0 472.2 2.2 472.2 11.99 11.99 0.00 2,900.0 89.36 179.73 2,506.3 498.9 2.4 498.9 0.00 0.00 0.00 3,000.0 89.36 179.73 2,507.4 598.8 2.8 598.9 0.00 0.00 0.00 3,000.0 89.36 179.73 2,508.6 698.8 3.3 698.8 0.00 0.00 0.00 3,100.0 89.36 179.73 2,509.7 7-98.8 3.8 798.8 0.00 0.00 0.00 3,200.0 89.36 179.73 2,510.8 898.8 4.2 898.8 0.00 0.00 0.00 3,300.0 89.36 179.73 2,510.8 898.8 4.2 898.8 0.00 0.00 0.00 3,300.0 89.36 179.73 2,510.8 1898.8 4.2 898.8 0.00 0.00 0.00 3,400.0 89.36 179.73 2,511.9 998.8 4.7 998.8 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.9 198.8 5.7 1,198.8 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.9 1,198.8 5.7 1,198.8 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.5 1,198.8 5.7 1,198.8 0.00 0.00 0.00 3,700.0 89.36 179.73 2,511.5 1,198.8 5.7 1,198.8 0.00 0.00 0.00 3,700.0 89.36 179.73 2,511.5 1,198.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,700.0 89.36 179.73 2,511.5 1,198.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,900.0 89.36 179.73 2,511.5 1,198.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,511.5 1,598.8 76 1,598.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,511.5 1,598.8 76 1,598.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,511.7 1,498.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,100.0 89.36 179.73 2,511.7 1,498.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,100.0 89.36 179.73 2,521.9 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,521.9 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,522.0 1,998.7 9.9 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,522.0 1,998.7 9.9 1,898.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,523.0 1,998.7 9.9 1,898.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 2,998.7 10.9 2,998.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 2,998.7 10.9 2,998.8 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 2,488.7 11.8 2,498.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 2,498.7 11.8 2,498.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 2,398.6 16.1 3,398.6 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,546.3 3,498.6 16.5 3,498.7 0.00 0.00 0.00 0.00 6,	2,700.0	80.57	179.73	2,499.6	-399.2	1.9	399.2	12.00	12.00	0.00
2,773.3 89.36 179.73 2,506.0 472.2 2.2 472.2 11.99 11.99 0.00 2,900.0 89.36 179.73 2,506.3 498.9 2.4 498.9 0.00 0.00 0.00 3,000.0 89.36 179.73 2,507.4 598.8 2.8 598.9 0.00 0.00 0.00 3,000.0 89.36 179.73 2,508.6 698.8 3.3 698.8 0.00 0.00 0.00 3,100.0 89.36 179.73 2,509.7 7-98.8 3.8 798.8 0.00 0.00 0.00 3,200.0 89.36 179.73 2,510.8 898.8 4.2 898.8 0.00 0.00 0.00 3,300.0 89.36 179.73 2,510.8 898.8 4.2 898.8 0.00 0.00 0.00 3,300.0 89.36 179.73 2,510.8 1898.8 4.2 898.8 0.00 0.00 0.00 3,400.0 89.36 179.73 2,511.9 998.8 4.7 998.8 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.9 198.8 5.7 1,198.8 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.9 1,198.8 5.7 1,198.8 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.5 1,198.8 5.7 1,198.8 0.00 0.00 0.00 3,700.0 89.36 179.73 2,511.5 1,198.8 5.7 1,198.8 0.00 0.00 0.00 3,700.0 89.36 179.73 2,511.5 1,198.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,700.0 89.36 179.73 2,511.5 1,198.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,900.0 89.36 179.73 2,511.5 1,198.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,511.5 1,598.8 76 1,598.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,511.5 1,598.8 76 1,598.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,511.7 1,498.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,100.0 89.36 179.73 2,511.7 1,498.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,100.0 89.36 179.73 2,521.9 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,521.9 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,522.0 1,998.7 9.9 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,522.0 1,998.7 9.9 1,898.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,523.0 1,998.7 9.9 1,898.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 2,998.7 10.9 2,998.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 2,998.7 10.9 2,998.8 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 2,488.7 11.8 2,498.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 2,498.7 11.8 2,498.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 2,398.6 16.1 3,398.6 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,546.3 3,498.6 16.5 3,498.7 0.00 0.00 0.00 0.00 6,	2772 2'MD: End	of Curvo w/90	26º Incl Azm	170 73° - Dina	Boy 17 BO Fed	1H Landing P	•			
2,800.0 89.36 179.73 2,506.3 -498.9 2.4 498.9 0.00 0.00 0.00 0.00 2,900.0 89.36 179.73 2,507.4 -598.8 2.8 598.9 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,508.6 -698.8 3.8 798.8 0.00 0.00 0.00 0.00 3,200.0 89.36 179.73 2,508.6 -698.8 3.8 798.8 0.00 0.00 0.00 0.00 3,200.0 89.36 179.73 2,510.8 -898.8 4.2 898.8 0.00 0.00 0.00 0.00 3,200.0 89.36 179.73 2,511.9 -998.8 4.7 998.8 0.00 0.00 0.00 0.00 3,400.0 89.36 179.73 2,511.0 1,098.8 5.2 1,098.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.0 1,198.8 5.2 1,098.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.2 1,198.8 5.2 1,098.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.2 1,198.8 5.1 1,198.8 0.00 0.00 0.00 0.00 3,700.0 89.36 179.73 2,511.2 1,198.8 5.1 1,198.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.2 1,198.8 7.1 1,198.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.2 1,198.8 7.1 1,198.8 0.00 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,511.2 1,198.8 7.1 1,198.8 0.00 0.00 0.00 0.00 0.00 0.00 0.00	4					•		11.00	11.00	0.00
2,900.0	2,773.3	89.36	179.73	2,506.0	-412.2	2.2	412.2	11.99	11.99	0.00
2,900.0	2 800 0	89.36	179 73	2 506 3	_498 Q	24	498 9	0.00	0.00	0.00
3,000.0 89.36 179.73 2,508.6 -698.8 3.3 698.8 0.00 0.00 0.00 0.00 3,200.0 89.36 179.73 2,510.8 -898.8 4.2 898.8 0.00 0.00 0.00 0.00 3,200.0 89.36 179.73 2,510.8 -898.8 4.2 898.8 0.00 0.00 0.00 0.00 3,400.0 89.36 179.73 2,511.9 -998.8 4.7 998.8 0.00 0.00 0.00 0.00 3,400.0 89.36 179.73 2,514.1 -1,198.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,514.1 -1,198.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,700.0 89.36 179.73 2,514.1 -1,198.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,700.0 89.36 179.73 2,514.2 1,498.8 7.1 1,498.8 0.00 0.00 0.00 0.00 3,700.0 89.36 179.73 2,514.5 -1,598.8 7.6 1,598.8 0.00 0.00 0.00 0.00 3,700.0 89.36 179.73 2,514.5 -1,598.8 7.6 1,598.8 0.00 0.00 0.00 0.00 0.00 0.00 0.00	· ·			*						
3,100.0 89,36 179,73 2,509.7 -798.8 3.8 798.8 0.00 0.00 0.00 0.00 3,200.0 89,36 179,73 2,510.8 898.8 4.2 898.8 0.00 0.00 0.00 0.00 3,300.0 89,36 179,73 2,513.0 1,098.8 5.2 1,098.8 0.00 0.00 0.00 0.00 3,500.0 89,36 179,73 2,513.0 1,098.8 5.2 1,098.8 0.00 0.00 0.00 0.00 3,500.0 89,36 179,73 2,515.2 1,198.8 6.1 1,298.8 0.00 0.00 0.00 0.00 3,700.0 89,36 179,73 2,515.2 1,298.8 6.1 1,298.8 0.00 0.00 0.00 0.00 3,700.0 89,36 179,73 2,515.2 1,298.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,700.0 89,36 179,73 2,515.5 1,598.8 7.6 1,598.8 0.00 0.00 0.00 0.00 3,900.0 89,36 179,73 2,515.5 1,598.8 7.6 1,598.8 0.00 0.00 0.00 0.00 4,000 89,36 179,73 2,515.5 1,598.8 7.6 1,598.8 0.00 0.00 0.00 0.00 4,000 89,36 179,73 2,5219.7 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200 89,36 179,73 2,5219.7 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200 89,36 179,73 2,521.9 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200 89,36 179,73 2,522.9 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89,36 179,73 2,522.9 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,522.9 1,898.7 9.9 1,898.7 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,524.1 2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.2 2,198.7 10.9 2,298.7 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.2 2,198.7 10.9 2,298.7 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.2 2,198.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.2 2,198.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,525.5 2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,525.5 2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,528.5 2,398.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,528.5 2,398.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,528.5 2,398.7 11.3 2,598.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,533.0 2,898.7 11.3 2,298.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,533.0 2,898.7 11.3 3,998.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,533.0 2,898.7 11.3 3,998.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,544.1 3,898.6 116.5 3,498.7 0.00 0.00 0.00 0.00				,						
3,200.0 89,36 179,73 2,510.8 -898.8 4.2 898.8 0.00 0.00 0.00 0.00 3,300.0 89,36 179,73 2,511.9 -998.8 4.7 998.8 0.00 0.00 0.00 0.00 3,500.0 89,36 179,73 2,511.9 1,998.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,500.0 89,36 179,73 2,515.2 -1,298.8 6.1 1,298.8 0.00 0.00 0.00 0.00 3,700.0 89,36 179,73 2,515.2 -1,298.8 6.1 1,298.8 0.00 0.00 0.00 0.00 3,700.0 89,36 179,73 2,515.2 -1,298.8 6.1 1,298.8 0.00 0.00 0.00 0.00 3,900.0 89,36 179,73 2,516.3 -1,398.8 7.1 1,498.8 0.00 0.00 0.00 0.00 3,900.0 89,36 179,73 2,516.5 -1,598.8 8.0 1,598.8 0.00 0.00 0.00 0.00 4,000.0 89,36 179,73 2,516.5 -1,598.8 8.0 1,598.8 0.00 0.00 0.00 0.00 4,000.0 89,36 179,73 2,5219.7 -1,698.8 8.0 1,698.8 0.00 0.00 0.00 0.00 4,100.0 89,36 179,73 2,5219.7 -1,698.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,100.0 89,36 179,73 2,5219.7 -1,698.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,100.0 89,36 179,73 2,5219.7 -1,698.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,100.0 89,36 179,73 2,5219.7 -1,698.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,400.0 89,36 179,73 2,5219.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89,36 179,73 2,5219.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89,36 179,73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.2 -2,198.7 10.9 2,298.7 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.5 -2,498.7 11.9 2,298.7 0.00 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.5 -2,298.7 11.9 2,298.7 0.00 0.00 0.00 0.00 5,200.0 89,36 179,73 2,525.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 0.00 5,200.0 89,36 179,73 2,531.9 -2,798.7 12.3 2,598.7 0.00 0.00 0.00 0.00 5,200.0 89,36 179,73 2,531.9 -2,798.7 11.3 2,598.7 0.00 0.00 0.00 0.00 5,500.0 89,36 179,73 2,534.1 -2,998.7 14.6 3,998.7 0.00 0.00 0.00 0.00 5,500.0 89,36 179,73 2,534.1 -3,988.6 170,0 3,798.6 0.00 0.00 0.00 0.00 5,500.0 89,36 179,73 2,534.1 -3,988.6 170,0 3,988.6 0.00 0.00 0.00 0.00 6,000 89,36 179,73 2,544.1 -3,898.6 170,0 3,988.6 0.00 0.00 0.00 0.00 6,										
3,300.0 89.36 179.73 2,511.9 998.8 4.7 998.8 0.00 0.00 0.00 0.00 3,400.0 89.36 179.73 2,513.0 1,098.8 5.2 1,098.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,514.1 1,198.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,515.2 1,298.8 6.1 1,298.8 0.0 0.00 0.00 0.00 3,700.0 89.36 179.73 2,515.3 1,398.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,700.0 89.36 179.73 2,516.3 1,398.8 7.1 1,498.8 0.0 0.00 0.00 0.00 3,900.0 89.36 179.73 2,515.4 1,598.8 7.6 1,598.8 0.0 0.00 0.00 0.00 0.00 4,000 99.36 179.73 2,518.5 1,598.8 7.6 1,598.8 0.0 0.00 0.00 0.00 0.00 4,000 89.36 179.73 2,518.5 1,598.8 8.5 1,798.8 0.0 0.00 0.00 0.00 0.00 4,100.0 89.36 179.73 2,520.8 1,798.8 8.5 1,798.8 0.0 0.00 0.00 0.00 4,200 89.36 179.73 2,521.9 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200 89.36 179.73 2,521.9 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,521.9 1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,524.1 2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,524.1 2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 2,098.7 10.4 2,198.7 0.00 0.00 0.00 4,700.0 89.36 179.73 2,524.1 2,298.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.4 2,398.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,525.2 2,498.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,533.0 2,898.7 12.7 2,698.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,533.0 2,898.7 12.7 2,898.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,533.0 2,898.7 13.7 2,898.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,533.0 2,898.7 14.6 3,098.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,533.1 3,398.6 15.6 3,398.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,533.6 3,398.6 15.6 3,398.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,534.1 3,898.6 18.4 3,898.6 0.00 0.00 0.00 0.00 6,500.0 89.36 179.73 2,541.1 9,388.	3,100.0	89.36	179.73	2,509.7	-798.8	3.8	798.8	0.00	0.00	0.00
3 400 0 88 36 179.73 2,514.0 1,098.8 5.2 1,098.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,514.1 -1,198.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,600.0 89.36 179.73 2,516.3 -1,398.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,516.3 -1,398.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,516.3 -1,398.8 7.1 1,498.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,518.5 -1,598.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,518.5 -1,598.8 8.0 1,598.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,519.7 -1,698.8 8.0 1,698.8 0.00 0.00 0.00 0.00 4,200 0 89.36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200 0 89.36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200 0 89.36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,523.0 -1,998.7 9.4 1,998.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 -2,298.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,525.2 -2,198.7 10.9 2,288.7 0.00 0.00 0.00 0.00 4,700.0 89.36 179.73 2,526.3 -2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,700.0 89.36 179.73 2,526.3 -2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,526.3 -2,289.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,528.5 -2,498.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,530.8 -2,698.7 12.3 2,588.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,530.8 -2,698.7 12.3 2,588.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,530.8 -2,698.7 12.3 2,598.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,530.8 -2,698.7 12.3 2,598.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,531.9 -2,738.7 13.2 2,738.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,531.9 -2,738.7 13.2 2,738.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,531.5 -3,898.6 15.6 3,298.7 0.00 0.00 0.00 0.00 6,000 89.36 179.73	3,200.0	89.36	179.73	2,510.8	-898.8	4.2	898.8	0.00	0.00	0.00
3 400 0 88 36 179.73 2,514.0 1,098.8 5.2 1,098.8 0.00 0.00 0.00 0.00 3,500.0 89.36 179.73 2,514.1 -1,198.8 5.7 1,198.8 0.00 0.00 0.00 0.00 3,600.0 89.36 179.73 2,516.3 -1,398.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,516.3 -1,398.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,516.3 -1,398.8 7.1 1,498.8 0.00 0.00 0.00 0.00 3,000.0 89.36 179.73 2,518.5 -1,598.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,518.5 -1,598.8 8.0 1,598.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,519.7 -1,698.8 8.0 1,698.8 0.00 0.00 0.00 0.00 4,200 0 89.36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200 0 89.36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200 0 89.36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,523.0 -1,998.7 9.4 1,998.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 -2,298.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,525.2 -2,198.7 10.9 2,288.7 0.00 0.00 0.00 0.00 4,700.0 89.36 179.73 2,526.3 -2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,700.0 89.36 179.73 2,526.3 -2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,526.3 -2,289.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,528.5 -2,498.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,530.8 -2,698.7 12.3 2,588.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,530.8 -2,698.7 12.3 2,588.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,530.8 -2,698.7 12.3 2,598.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,530.8 -2,698.7 12.3 2,598.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,531.9 -2,738.7 13.2 2,738.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,531.9 -2,738.7 13.2 2,738.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,531.5 -3,898.6 15.6 3,298.7 0.00 0.00 0.00 0.00 6,000 89.36 179.73					000.0	4 -	000.0	0.00	0.00	0.00
3,500.0 89,36 179,73 2,515.2 -1,298.8 6.1 1,298.8 0.00 0.00 0.00 0.00 3,700.0 89,36 179,73 2,516.3 -1,398.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,700.0 89,36 179,73 2,516.3 -1,398.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,900.0 89,36 179,73 2,516.5 -1,598.8 7.6 1,598.8 0.00 0.00 0.00 0.00 4,000.0 89,36 179,73 2,518.5 -1,598.8 8.0 1,698.8 0.00 0.00 0.00 0.00 4,100.0 89,36 179,73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,100.0 89,36 179,73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,200 89,36 179,73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,200 89,36 179,73 2,521.0 -1,898.7 9.0 1,898.7 9.0 0.00 0.00 0.00 0.00 4,400.0 89,36 179,73 2,521.0 -1,998.7 9.4 1,998.8 0.00 0.00 0.00 0.00 4,400.0 89,36 179,73 2,522.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,522.1 -2,098.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,600.0 89,36 179,73 2,525.1 -2,298.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,600.0 89,36 179,73 2,525.1 -2,298.7 10.9 2,298.8 0.00 0.00 0.00 0.00 4,600.0 89,36 179,73 2,525.6 2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.6 2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.6 2,498.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.6 2,498.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,000.0 89,36 179,73 2,530.8 2,698.7 12.3 2,598.7 0.00 0.00 0.00 0.00 5,000.0 89,36 179,73 2,530.8 2,698.7 12.3 2,598.7 0.00 0.00 0.00 0.00 5,000.0 89,36 179,73 2,531.0 2,298.7 13.2 2,598.7 0.00 0.00 0.00 5,000.0 89,36 179,73 2,531.0 2,398.7 13.7 2,898.7 0.00 0.00 0.00 0.00 5,000.0 89,36 179,73 2,531.0 2,398.7 13.2 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89,36 179,73 2,531.0 2,398.7 13.2 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89,36 179,73 2,531.0 2,398.7 13.2 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89,36 179,73 2,531.0 3,398.7 14.6 3,398.7 0.00 0.00 0.00 0.00 5,000.0 89,36 179,73 2,531.0 3,398.7 13.7 2,898.7 0.00 0.00 0.00 0.00 5,000.0 89,36 179,73 2,531.0 3,398.6 15.5 3,398.6 15.5 3,398.6 10.00 0.00 0.00 0.00 0.00 6,000.0 89,36 179,73 2,541.0 3,398.6 15.5 3,398.6 10.00 0.00 0.00 0.0	1									
3,600.0 89,36 179,73 2,516.2 -1,298.8 6.1 1,298.8 0.00 0.00 0.00 0.00 3,700.0 89,36 179,73 2,516.3 -1,398.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,800.0 89,36 179,73 2,518.5 -1,598.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,000.0 89,36 179,73 2,518.5 -1,598.8 8.0 1,698.8 0.00 0.00 0.00 0.00 4,100.0 89,36 179,73 2,521.9 -1,898.7 8.8 5 1,798.8 0.00 0.00 0.00 0.00 4,100.0 89,36 179,73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200.0 89,36 179,73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,000 89,36 179,73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89,36 179,73 2,522.1 -1,998.7 9.4 1,998.8 0.00 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.2 -2,198.7 10,4 2,198.7 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.2 -2,198.7 10,4 2,198.7 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.2 -2,198.7 10,4 2,198.7 0.00 0.00 0.00 4,700.0 89,36 179,73 2,525.4 -2,298.7 10,9 2,298.7 0.00 0.00 0.00 0.00 4,700.0 89,36 179,73 2,525.4 -2,398.7 11,3 2,398.7 0.00 0.00 0.00 0.00 4,800.0 89,36 179,73 2,525.5 -2,498.7 10,9 2,198.7 0.00 0.00 0.00 0.00 4,700.0 89,36 179,73 2,526.5 -2,498.7 11,3 2,398.7 0.00 0.00 0.00 0.00 4,900.0 89,36 179,73 2,526.5 -2,498.7 11,3 2,398.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,525.6 -2,598.7 12,3 2,598.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,525.6 -2,598.7 12,3 2,598.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,531.9 2,598.7 12,3 2,598.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,531.9 2,598.7 12,3 2,598.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,531.0 2,898.7 13.7 2,898.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,531.0 2,898.7 13.7 2,898.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,531.9 2,598.7 13.7 2,898.7 0.00 0.00 0.00 0.00 5,000 89,36 179,73 2,531.9 2,531.	3,400.0	89.36	179.73	2,513.0	-1,098.8	5.2	1,098.8	0.00	0.00	0.00
3,700.0 89.36 179.73 2,516.3 -1,398.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,800.0 89.36 179.73 2,5141,498.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,519.7 -1,698.8 8.0 1,698.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,520.8 -1,798.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,521.0 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,521.0 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 -2,098.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,600.0 89.36 179.73 2,526.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 0.00 4,600.0 89.36 179.73 2,526.3 -2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,800.0 89.36 179.73 2,524.1 -2,098.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,800.0 89.36 179.73 2,526.3 -2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,528.5 -2,498.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,529.6 -2,598.7 12.3 2,598.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,898.7 12.7 2,698.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,898.7 12.7 2,698.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,898.7 13.7 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,898.7 13.7 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,898.7 13.7 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,534.1 -2,998.7 13.2 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,534.1 -3,998.6 15.6 3,998.7 0.00 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,544.1 -3,898.6 179.73 3,544.1 -3,898.6 179.73 3,544.1 -3,898.6 179.73 3,544.1 -3,898.6 179.73 3,544.1 -3,898.6 179.73 3,544.1 -3,89	3,500.0	89.36	179.73	2,514.1	-1,198.8	5.7	1,198.8	0.00	0.00	0.00
3,700.0 89.36 179.73 2,516.3 -1,398.8 6.6 1,398.8 0.00 0.00 0.00 0.00 3,800.0 89.36 179.73 2,5141,498.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,519.7 -1,698.8 8.0 1,698.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,520.8 -1,798.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,521.0 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200.0 89.36 179.73 2,521.0 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 -2,098.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,600.0 89.36 179.73 2,526.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 0.00 4,600.0 89.36 179.73 2,526.3 -2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,800.0 89.36 179.73 2,524.1 -2,098.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,800.0 89.36 179.73 2,526.3 -2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,528.5 -2,498.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,529.6 -2,598.7 12.3 2,598.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,898.7 12.7 2,698.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,898.7 12.7 2,698.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,898.7 13.7 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,898.7 13.7 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,898.7 13.7 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,534.1 -2,998.7 13.2 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,534.1 -3,998.6 15.6 3,998.7 0.00 0.00 0.00 0.00 0.00 5,000.0 89.36 179.73 2,544.1 -3,898.6 179.73 3,544.1 -3,898.6 179.73 3,544.1 -3,898.6 179.73 3,544.1 -3,898.6 179.73 3,544.1 -3,898.6 179.73 3,544.1 -3,89	3.600.0	89.36	179.73	2.515.2	-1.298.8	6.1	1.298.8	0.00	0.00	0.00
3,800.0 89.36 179.73 2,517.4 -1,498.8 7.1 1,498.8 0.00 0.00 0.00 0.00 4,000 89.36 179.73 2,518.5 -1,598.8 76 1,598.8 0.00 0.00 0.00 0.00 4,000 89.36 179.73 2,519.7 -1,698.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,100.0 89.36 179.73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,200 0 89.36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,200 0 89.36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,523.0 -1,998.7 9.4 1,998.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.3 -2,298.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,700.0 89.36 179.73 2,524.2 -2,398.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,700.0 89.36 179.73 2,528.5 -2,498.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 0.00 5,100.0 89.36 179.73 2,531.9 2,598.7 12.3 2,598.7 0.00 0.00 0.00 5,100.0 89.36 179.73 2,531.9 -2,798.7 12.3 2,598.7 0.00 0.00 0.00 5,100.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 0.00 5,200.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 0.00 5,200.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 0.00 5,200.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 0.00 5,400.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 0.00 5,400.0 89.36 179.73 2,531.9 -2,798.7 14.6 3,098.7 0.00 0.00 0.00 0.00 5,400.0 89.36 179.73 2,531.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,534.1 -2,998.7 14.6 3,998.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,541.9 -3,698.6 16.5 3,498.7 0.00 0.00 0.00 0.00 5,700.0 89.36 179.73 2,544.1 -3,898.6 16.5 3,498.7 0.00 0.00 0.00 0.00 0.00 6,000 0.93.6 179.73 2,544.1 -3,898.6 17.9 3,598.6 17.9 3,598.6 0.00 0.00 0.00 0.00 0.00 6,000 0.93.6 179.73 2,544.1 -3,898.6 17.9 3,598.6 0.00 0.00	t .			•						
3,900.0 89.36 179.73 2,518.5 -1,598.8 7 6 1,598.8 0.00 0.00 0.00 0.00 4,000.0 89.36 179.73 2,552.0 1,798.8 8.0 1,698.8 0.00 0.00 0.00 0.00 4,200 0 89.36 179.73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 0.00 4,200 0 89.36 179.73 2,520.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,300.0 89.36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 0.00 4,400.0 89.36 179.73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 0.00 4,500.0 89.36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,600.0 89.36 179.73 2,525.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 0.00 4,600.0 89.36 179.73 2,525.3 -2,298.7 11.3 2,398.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,525.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,529.6 -2,598.7 11.3 2,398.7 0.00 0.00 0.00 0.00 5,100.0 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00 0.00 0.00 0.00 5,100.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 0.00 5,200.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 0.00 5,200.0 89.36 179.73 2,532.0 -2,898.7 13.2 2,998.7 0.00 0.00 0.00 5,200.0 89.36 179.73 2,532.5 -3,098.7 14.6 3,098.7 0.00 0.00 0.00 5,500.0 89.36 179.73 2,532.5 -3,098.7 14.6 3,098.7 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 0.00 5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 0.00 5,500.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 0.00 5,000 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 0.00 6,000 89.36 179.73 2,544.1 -3,898.6 17.5 3,898.7 0.00 0.00 0.00 0.00 6,000 89.36 179.73 2,544.1 -3,898.6 17.5 3,898.7 0.00 0.00 0.00 0.00 6,000 89.36 179.73 2,544.1 -3,898.6 17.5 3,898.6 0.00 0.00 0.00 0.00 6,000 89.36 179.73 2,544.1 -3,898.6 17.5 3,898.6 0.00 0.00 0.00 0.00 6,000 89.36 179.73 2,544.1 -3,	3,700.0	05.00	175.70	2,010.0	1,000.0	0.0	1,000.0	0.00	0.00	0.00
4,000.0 89,36 179,73 2,519.7 -1,698.8 8.0 1,698.8 0.00 0.00 0.00 4,100.0 89,36 179,73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 4,200.0 89,36 179,73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 4,400.0 89,36 179,73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 4,600.0 89,36 179,73 2,525.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 4,700.0 89,36 179,73 2,525.5 -2,498.7 11.3 2,398.7 0.00 0.00 0.00 4,900.0 89,36 179,73 2,525.6 -2,498.7 11.8 2,498.7 0.00 0.00 0.00	3,800.0	89.36	179.73	2,517.4	-1,498.8	7.1	1,498.8	0.00	0.00	0.00
4,000.0 89,36 179,73 2,519.7 -1,698.8 8.0 1,698.8 0.00 0.00 0.00 4,100.0 89,36 179,73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 4,200.0 89,36 179,73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 4,400.0 89,36 179,73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 4,500.0 89,36 179,73 2,525.3 -2,298.7 10.4 2,198.7 0.00 0.00 0.00 4,600.0 89,36 179,73 2,525.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 4,700.0 89,36 179,73 2,525.3 -2,298.7 11.3 2,398.7 0.00 0.00 0.00 4,900.0 89,36 179,73 2,525.6 -2,498.7 11.8 2,498.7 0.00 0.00 0.00	3 900 0	89 36	179.73	2 518.5	-1 598.8	7.6	1.598.8	0.00	0.00	0.00
4,100.0 89,36 179.73 2,520.8 -1,798.8 8.5 1,798.8 0.00 0.00 0.00 4,200.0 89,36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 4,300.0 89,36 179.73 2,523.0 -1,998.7 9.4 1,998.8 0.00 0.00 0.00 4,600.0 89,36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 4,600.0 89,36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 4,600.0 89,36 179.73 2,525.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 4,700.0 89,36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 4,800.0 89,36 179.73 2,530.8 -2,698.7 12.3 2,598.7 0.00 0.00 0.00 <tr< td=""><td>1</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr<>	1									
4,200 0 89.36 179.73 2,521.9 -1,898.7 9.0 1,898.8 0.00 0.00 0.00 4,300.0 89.36 179.73 2,523.0 -1,998.7 9.4 1,998.8 0.00 0.00 0.00 4,600.0 89.36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,600.0 89.36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 0.00 4,600.0 89.36 179.73 2,525.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 0.00 4,700.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 0.00 4,900.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00				•			•			
4,300.0 89.36 179.73 2,523.0 -1,998.7 9.4 1,998.8 0.00 0.00 0.00 4,400.0 89.36 179.73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 4,500.0 89.36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 4,600.0 89.36 179.73 2,527.4 -2,398.7 11.3 2,398.7 0.00 0.00 0.00 4,800.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 4,900.0 89.36 179.73 2,529.6 -2,598.7 12.3 2,598.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,529.6 -2,598.7 12.7 2,698.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 5,200.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,99	1			,	•					
4,400.0 89.36 179.73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 4,500.0 89.36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 4,600.0 89.36 179.73 2,526.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 4,700.0 89.36 179.73 2,527.4 -2,398.7 11.3 2,398.7 0.00 0.00 0.00 4,800.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 4,900.0 89.36 179.73 2,529.6 -2,598.7 12.3 2,598.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,531.8 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 5,200.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 <	4,200 0	89.36	1/9./3	2,521.9	-1,898.7	9.0	1,898.8	0.00	0.00	0.00
4,400.0 89.36 179.73 2,524.1 -2,098.7 9.9 2,098.8 0.00 0.00 0.00 4,500.0 89.36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 4,600.0 89.36 179.73 2,526.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 4,700.0 89.36 179.73 2,527.4 -2,398.7 11.3 2,398.7 0.00 0.00 0.00 4,800.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 4,900.0 89.36 179.73 2,529.6 -2,598.7 12.3 2,598.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,531.8 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 5,200.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 <	4 300 0	80.36	170 73	2 523 0	1 008 7	0.4	1 008 8	0.00	0.00	0.00
4,500.0 89.36 179.73 2,525.2 -2,198.7 10.4 2,198.7 0.00 0.00 0.00 4,600.0 89.36 179.73 2,526.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 4,700.0 89.36 179.73 2,528.5 -2,498.7 11.3 2,398.7 0.00 0.00 0.00 4,900.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,698.7 12.3 2,598.7 0.00 0.00 0.00 5,100.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 5,200.0 89.36 179.73 2,533.0 -2,898.7 13.7 2,898.7 0.00 0.00 0.00 5,300.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 5,400.0 89.36 179.73 2,535.2 -3,098.7 14.6 3,				•	•					
4,600.0 89.36 179.73 2,526.3 -2,298.7 10.9 2,298.7 0.00 0.00 0.00 4,700.0 89.36 179.73 2,527.4 -2,398.7 11.3 2,398.7 0.00 0.00 0.00 4,800.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,529.6 -2,598.7 12.3 2,598.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00 0.00 0.00 5,100.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 5,200.0 89.36 179.73 2,535.4 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 5,300.0 89.36 179.73 2,535.2 -3,098.7 14.2 2,998.7 0.00 0.00 0.00 5,400.0 89.36 179.73 2,536.3 -3,198.7 15.1 3,				•	•					
4,700.0 89.36 179.73 2,527.4 -2,398.7 11.3 2,398.7 0.00 0.00 0.00 4,800.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,529.6 -2,598.7 12.3 2,598.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00 0.00 0.00 5,100.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 5,200.0 89.36 179.73 2,533.0 -2,898.7 13.7 2,898.7 0.00 0.00 0.00 5,300.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 5,400.0 89.36 179.73 2,535.2 -3,098.7 14.6 3,098.7 0.00 0.00 0.00				•			•			
4,800.0 89.36 179.73 2,528.5 -2,498.7 11.8 2,498.7 0.00 0.00 0.00 4,900.0 89.36 179.73 2,529.6 -2,598.7 12.3 2,598.7 0.00 0.00 0.00 5,000.0 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00 0.00 0.00 5,100.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 5,200.0 89.36 179.73 2,533.0 -2,898.7 13.7 2,898.7 0.00 0.00 0.00 5,300.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 5,400.0 89.36 179.73 2,535.2 -3,098.7 14.6 3,098.7 0.00 0.00 0.00 5,500.0 89.36 179.73 2,536.3 -3,198.7 15.1 3,198.7 0.00 0.00 0.00 5,600.0 89.36 179.73 2,538.5 -3,398.6 15.6 3,	4,600.0	89.36	179.73	2,526.3	-2,298.7	10.9	2,298.7	0.00	0.00	0.00
4,900.0 89.36 179.73 2,529.6 -2,598.7 12.3 2,598.7 0.00 <td< td=""><td>4,700.0</td><td>89.36</td><td>179.73</td><td>2,527.4</td><td>-2,398.7</td><td>11.3</td><td>2,398.7</td><td>0.00</td><td>0.00</td><td>0.00</td></td<>	4,700.0	89.36	179.73	2,527.4	-2,398.7	11.3	2,398.7	0.00	0.00	0.00
4,900.0 89.36 179.73 2,529.6 -2,598.7 12.3 2,598.7 0.00 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></td<>										
5,000.0 89.36 179.73 2,530.8 -2,698.7 12.7 2,698.7 0.00<	1			•						
5,100.0 89.36 179.73 2,531.9 -2,798.7 13.2 2,798.7 0.00 0.00 0.00 5,200.0 89.36 179.73 2,533.0 -2,898.7 13.7 2,898.7 0.00 0.00 0.00 5,300.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 5,400.0 89.36 179.73 2,535.2 -3,098.7 14.6 3,098.7 0.00 0.00 0.00 5,500.0 89.36 179.73 2,536.3 -3,198.7 15.1 3,198.7 0.00 0.00 0.00 5,600.0 89.36 179.73 2,537.4 -3,298.6 15.6 3,298.7 0.00 0.00 0.00 5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,800.0 89.36 179.73 2,539.6 -3,498.6 16.5 3,498.7 0.00 0.00 0.00	4,900.0			2,529.6	-2,598.7	12.3	•	0.00		0.00
5,200.0 89.36 179.73 2,533.0 -2,898.7 13.7 2,898.7 0.00 0.00 0.00 5,300.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 5,400.0 89.36 179.73 2,535.2 -3,098.7 14.6 3,098.7 0.00 0.00 0.00 5,500.0 89.36 179.73 2,536.3 -3,198.7 15.1 3,198.7 0.00 0.00 0.00 5,600.0 89.36 179.73 2,537.4 -3,298.6 15.6 3,298.7 0.00 0.00 0.00 5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,800.0 89.36 179.73 2,539.6 -3,498.6 16.5 3,498.7 0.00 0.00 0.00 5,900.0 89.36 179.73 2,541.9 -3,698.6 17.0 3,598.7 0.00 0.00 0.00	5,000.0	89.36	179.73	2,530.8	-2,698.7	12.7	2,698.7	0.00	0.00	0.00
5,200.0 89.36 179.73 2,533.0 -2,898.7 13.7 2,898.7 0.00 0.00 0.00 5,300.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 5,400.0 89.36 179.73 2,535.2 -3,098.7 14.6 3,098.7 0.00 0.00 0.00 5,500.0 89.36 179.73 2,536.3 -3,198.7 15.1 3,198.7 0.00 0.00 0.00 5,600.0 89.36 179.73 2,537.4 -3,298.6 15.6 3,298.7 0.00 0.00 0.00 5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,800.0 89.36 179.73 2,539.6 -3,498.6 16.5 3,498.7 0.00 0.00 0.00 5,900.0 89.36 179.73 2,541.9 -3,698.6 17.0 3,598.7 0.00 0.00 0.00	5,100.0	89.36	179.73	2,531.9	-2,798.7	13.2	2,798.7	0.00	0.00	0.00
5,300.0 89.36 179.73 2,534.1 -2,998.7 14.2 2,998.7 0.00 0.00 0.00 5,400.0 89.36 179.73 2,535.2 -3,098.7 14.6 3,098.7 0.00 0.00 0.00 5,500.0 89.36 179.73 2,536.3 -3,198.7 15.1 3,198.7 0.00 0.00 0.00 5,600.0 89.36 179.73 2,537.4 -3,298.6 15.6 3,298.7 0.00 0.00 0.00 5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,800.0 89.36 179.73 2,539.6 -3,498.6 16.5 3,498.7 0.00 0.00 0.00 5,900.0 89.36 179.73 2,540.7 -3,598.6 17.0 3,598.7 0.00 0.00 0.00 6,000.0 89.36 179.73 2,541.9 -3,698.6 17.5 3,698.7 0.00 0.00 0.00 6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,										
5,400.0 89.36 179.73 2,535.2 -3,098.7 14.6 3,098.7 0.00 0.00 0.00 5,500.0 89.36 179.73 2,536.3 -3,198.7 15.1 3,198.7 0.00 0.00 0.00 5,600.0 89.36 179.73 2,537.4 -3,298.6 15.6 3,298.7 0.00 0.00 0.00 5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,800.0 89.36 179.73 2,539.6 -3,498.6 16.5 3,498.7 0.00 0.00 0.00 5,900.0 89.36 179.73 2,540.7 -3,598.6 17.0 3,598.7 0.00 0.00 0.00 6,000.0 89.36 179.73 2,541.9 -3,698.6 17.5 3,698.7 0.00 0.00 0.00 6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,798.6 0.00 0.00 0.00 6,200.0 89.36 179.73 2,545.2 -3,998.6 18.4 3,										
5,500.0 89.36 179.73 2,536.3 -3,198.7 15.1 3,198.7 0.00 0.00 0.00 5,600.0 89.36 179.73 2,537.4 -3,298.6 15.6 3,298.7 0.00 0.00 0.00 5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,800.0 89.36 179.73 2,539.6 -3,498.6 16.5 3,498.7 0.00 0.00 0.00 5,900.0 89.36 179.73 2,540.7 -3,598.6 17.0 3,598.7 0.00 0.00 0.00 6,000.0 89.36 179.73 2,541.9 -3,698.6 17.5 3,698.7 0.00 0.00 0.00 6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,798.6 0.00 0.00 0.00 6,200.0 89.36 179.73 2,545.2 -3,898.6 18.4 3,898.6 0.00 0.00 0.00	5,300.0			2,534.1		14.2	· ·			0.00
5,500.0 89.36 179.73 2,536.3 -3,198.7 15.1 3,198.7 0.00 0.00 0.00 5,600.0 89.36 179.73 2,537.4 -3,298.6 15.6 3,298.7 0.00 0.00 0.00 5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,800.0 89.36 179.73 2,539.6 -3,498.6 16.5 3,498.7 0.00 0.00 0.00 5,900.0 89.36 179.73 2,540.7 -3,598.6 17.0 3,598.7 0.00 0.00 0.00 6,000.0 89.36 179.73 2,541.9 -3,698.6 17.5 3,698.7 0.00 0.00 0.00 6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,798.6 0.00 0.00 0.00 6,200.0 89.36 179.73 2,545.2 -3,898.6 18.4 3,898.6 0.00 0.00 0.00	5,400.0	89.36	179.73	2,535.2	-3,098.7	14.6	3,098.7	0.00	0.00	0.00
5,600.0 89.36 179.73 2,537.4 -3,298.6 15.6 3,298.7 0.00 0.00 0.00 5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,800.0 89.36 179.73 2,539.6 -3,498.6 16.5 3,498.7 0.00 0.00 0.00 5,900.0 89.36 179.73 2,540.7 -3,598.6 17.0 3,598.7 0.00 0.00 0.00 6,000.0 89.36 179.73 2,541.9 -3,698.6 17.5 3,698.7 0.00 0.00 0.00 6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,798.6 0.00 0.00 0.00 6,200.0 89.36 179.73 2,544.1 -3,898.6 18.4 3,898.6 0.00 0.00 0.00 6,300.0 89.36 179.73 2,545.2 -3,998.6 18.9 3,998.6 0.00 0.00 0.00	1	89.36	179.73		-3,198.7		3,198.7		0.00	
5,700.0 89.36 179.73 2,538.5 -3,398.6 16.1 3,398.7 0.00 0.00 0.00 5,800.0 89.36 179.73 2,539.6 -3,498.6 16.5 3,498.7 0.00 0.00 0.00 5,900.0 89.36 179.73 2,540.7 -3,598.6 17.0 3,598.7 0.00 0.00 0.00 6,000.0 89.36 179.73 2,541.9 -3,698.6 17.5 3,698.7 0.00 0.00 0.00 6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,798.6 0.00 0.00 0.00 6,200.0 89.36 179.73 2,544.1 -3,898.6 18.4 3,898.6 0.00 0.00 0.00 6,300.0 89.36 179.73 2,545.2 -3,998.6 18.9 3,998.6 0.00 0.00 0.00 6,400.0 89.36 179.73 2,546.3 -4,098.6 19.4 4,098.6 0.00 0.00 0.00										
5,800.0 89.36 179.73 2,539.6 -3,498.6 16.5 3,498.7 0.00 0.00 0.00 5,900.0 89.36 179.73 2,540.7 -3,598.6 17.0 3,598.7 0.00 0.00 0.00 6,000.0 89.36 179.73 2,541.9 -3,698.6 17.5 3,698.7 0.00 0.00 0.00 6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,798.6 0.00 0.00 0.00 6,200.0 89.36 179.73 2,544.1 -3,898.6 18.4 3,898.6 0.00 0.00 0.00 6,300.0 89.36 179.73 2,545.2 -3,998.6 18.9 3,998.6 0.00 0.00 0.00 6,400.0 89.36 179.73 2,546.3 -4,098.6 19.4 4,098.6 0.00 0.00 0.00 6,500.0 89.36 179.73 2,547.4 -4,198.6 19.8 4,198.6 0.00 0.00 0.00 6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,										
5,900.0 89.36 179.73 2,540.7 -3,598.6 17.0 3,598.7 0.00 0.00 0.00 6,000.0 89.36 179.73 2,541.9 -3,698.6 17.5 3,698.7 0.00 0.00 0.00 6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,798.6 0.00 0.00 0.00 6,200.0 89.36 179.73 2,544.1 -3,898.6 18.4 3,898.6 0.00 0.00 0.00 6,300.0 89.36 179.73 2,545.2 -3,998.6 18.9 3,998.6 0.00 0.00 0.00 6,400.0 89.36 179.73 2,546.3 -4,098.6 19.4 4,098.6 0.00 0.00 0.00 6,500.0 89.36 179.73 2,547.4 -4,198.6 19.8 4,198.6 0.00 0.00 0.00 6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00	5,700.0	69.30	1/9./3	∠,538.5	-3,398.0	16.1	3,398.7	0.00	0.00	0.00
5,900.0 89.36 179.73 2,540.7 -3,598.6 17.0 3,598.7 0.00 0.00 0.00 6,000.0 89.36 179.73 2,541.9 -3,698.6 17.5 3,698.7 0.00 0.00 0.00 6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,798.6 0.00 0.00 0.00 6,200.0 89.36 179.73 2,544.1 -3,898.6 18.4 3,898.6 0.00 0.00 0.00 6,300.0 89.36 179.73 2,545.2 -3,998.6 18.9 3,998.6 0.00 0.00 0.00 6,400.0 89.36 179.73 2,546.3 -4,098.6 19.4 4,098.6 0.00 0.00 0.00 6,500.0 89.36 179.73 2,547.4 -4,198.6 19.8 4,198.6 0.00 0.00 0.00 6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00	5 800 0	89.36	179 73	2 539 6	-3 498 6	16.5	3 498 7	0.00	0.00	0.00
6,000.0 89.36 179.73 2,541.9 -3,698.6 17.5 3,698.7 0.00 0.00 0.00 6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,798.6 0.00 0.00 0.00 6,200.0 89.36 179.73 2,544.1 -3,898.6 18.4 3,898.6 0.00 0.00 0.00 6,300.0 89.36 179.73 2,545.2 -3,998.6 18.9 3,998.6 0.00 0.00 0.00 6,400.0 89.36 179.73 2,546.3 -4,098.6 19.4 4,098.6 0.00 0.00 0.00 6,500.0 89.36 179.73 2,547.4 -4,198.6 19.8 4,198.6 0.00 0.00 0.00 6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00	-			•						
6,100.0 89.36 179.73 2,543.0 -3,798.6 17.9 3,798.6 0.00 0.00 0.00 0.00 6,200.0 89.36 179.73 2,544.1 -3,898.6 18.4 3,898.6 0.00 0.00 0.00 6,300.0 89.36 179.73 2,545.2 -3,998.6 18.9 3,998.6 0.00 0.00 0.00 6,400.0 89.36 179.73 2,546.3 -4,098.6 19.4 4,098.6 0.00 0.00 0.00 6,500.0 89.36 179.73 2,547.4 -4,198.6 19.8 4,198.6 0.00 0.00 0.00 6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00										
6,200.0 89.36 179.73 2,544.1 -3,898.6 18.4 3,898.6 0.00 0.00 0.00 6,300.0 89.36 179.73 2,545.2 -3,998.6 18.9 3,998.6 0.00 0.00 0.00 6,400.0 89.36 179.73 2,546.3 -4,098.6 19.4 4,098.6 0.00 0.00 0.00 6,500.0 89.36 179.73 2,547.4 -4,198.6 19.8 4,198.6 0.00 0.00 0.00 6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00										
6,300.0 89.36 179.73 2,545.2 -3,998.6 18.9 3,998.6 0.00 0.00 0.00 6,400.0 89.36 179.73 2,546.3 -4,098.6 19.4 4,098.6 0.00 0.00 0.00 6,500.0 89.36 179.73 2,547.4 -4,198.6 19.8 4,198.6 0.00 0.00 0.00 6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00	6,100.0	89.36			-3,798.6					
6,300.0 89.36 179.73 2,545.2 -3,998.6 18.9 3,998.6 0.00 0.00 0.00 6,400.0 89.36 179.73 2,546.3 -4,098.6 19.4 4,098.6 0.00 0.00 0.00 6,500.0 89.36 179.73 2,547.4 -4,198.6 19.8 4,198.6 0.00 0.00 0.00 6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00	6,200.0	89.36	179.73	2,544.1	-3,898.6	18.4	3,898.6	0.00	0.00	0.00
6,400.0 89.36 179.73 2,546.3 -4,098.6 19.4 4,098.6 0.00 0.00 0.00 6,500.0 89.36 179.73 2,547.4 -4,198.6 19.8 4,198.6 0.00 0.00 0.00 6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00										
6,500.0 89.36 179.73 2,547.4 -4,198.6 19.8 4,198.6 0.00 0.00 0.00 6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00										
6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00	6,400.0	89.36		2,546.3	-4,098.6	19,4	4,098.6	0.00	0.00	0.00
6,600.0 89.36 179.73 2,548.5 -4,298.6 20.3 4,298.6 0.00 0.00 0.00	6.500.0	89.36	179.73	2,547.4	-4,198.6	19.8	4,198.6	0.00	0.00	0.00
0,100.0 00.00 110.10 2,070.0 20.0 4,000.0 0.00 0.00 0.00	0,700.0	05.50	113,13	2,540.0	, ,550.0	20.0	4,550.0	0.00	0.00	0.00

DDC

Well Planning Report



Design#2

Planned Survey			vic-palekai mea. Priisipalekai				aanaan ahaa ah oo Saalahaa Talaan	in and the state of	
Measured	gradingsis same		Vertical	and the state of	nic aligner (co.)	Vertical	Dogleg	Build	Turn
Depth In (usft)	clination (°)	Azimuth (°)	Depth (usft)	+N/-S (usft)	+E/-W (usft)	Section (usft)	Rate (°/100usft) (°	Rate /100usft) (Rate 1/100usft)
6,800.0	89.36	179.73	2,550.7	-4,498.6	21.3	4,498.6	0.00	0.00	0.00
6,900.0 7,000.0	89.36 89.36	179.73 179.73	2,551.9 2,553.0	-4,598.5 -4,698.5	21.7 22.2	4,598.6 4,698.6	0.00 0.00	0.00 0.00	0.00 0.00
TD at 7093.5'MD	- 2554'TVD - P	ine Box 17 BO	Fed 1H PBHL						
7,093.5	89.36	179.73	2,554.0	-4,792.0	22.6	4,792.1	0.00	0.00	0.00


Design:Targets TargetName - hit/miss;target Dip - Shape	Angle (2)	Dip Dir:		+N/-S (usft)	rE/-W (usft)	Northing (usft):	Easting (usft)	Latitude	Longitude
Pine Box 17 BO Fed. 1F - plan hits target center - Point	0.00	360.00	2,506.0	-472.2	2.2	574,433.80	447,660.77	32° 34' 44.796 N	104° 30' 11.696 W
Pine Box 17 BO Fed 1H - plan hits target center - Point	0.00	0.00	2,554.0	-4,792.0	22.6	570,113.99	447,681.21	32° 34' 2.048 N	104° 30′ 11.377 W

Plan Annotations				
Measured Depth	Depth	Local Coordin	+E/-W:	
		LUSIU CARRENT	(usit)	Comment
2,028.6	2,028.6	0.0	0.0	2028.6'MD· Begin Build @ 12° DLS
2,773.3	2,506.0	-472.2	2.2	2773.3'MD: End of Curve w/89.36° Incl Azm. 179.73°
7,093.5	2,554.0	-4,792.0	22.6	TD at 7093.5'MD - 2554'TVD

Mewbourne Oil Co

Pine Box 17BO Federal #1H Eddy County, New Mexico Design#2






Mewbourne Oil Co

Pine Box 17BO Federal #1H Eddy County, New Mexico Design#2





Notes Regarding Blowout Preventer

Mewbourne Oil Company

Pine Box "17" BO Fed #1H 160' FNL & 1670' FEL (SHL) Sec 17-T20S-R25E Eddy County, New Mexico

- I. Drilling nipple (bell nipple) to be constructed so that it can be removed without the use of a welder through the opening of the rotary table, with minimum internal diameter equal to blowout preventer bore.
- II. Blowout preventer and all fittings must be in good condition with a minimum 2000 psi working pressure on 9 5/8" & 7" casing.
- III. Safety valve must be available on the rig floor at all times with proper connections to install in the drill string. Valve must be full bore with minimum 2000 psi working pressure.
- IV. Equipment through which bit must pass shall be at least as large as internal diameter of the casing.
- V. A kelly cock shall be installed on the kelly at all times.

Blowout preventer closing equipment to include and accumulator of at least 40 gallon capacity, two independent sources of pressure on closing unit, and meet all other API specifications.

Mewbourne Oil Company

BOP Schematic for 8 3/4" & 6 1/8" Hole






Exhibit #2

Pine Box "17" BO Fed #1H 160' FNL & 1670' FEL Sec 17-T20S-R25E Eddy, County New Mexico




2000# BOP manifold system for Exhibit 2 & 2A

Pine Box "17" BO Fed #1H



Pine Box "17" BO Fed #14

Closed Loop Pad Dimensions and H2S Plan 300'x 230'



Legend
Wellbore Location
■ Briefing Area w/ SCBA

+ H2S Sensors
■ Windsocks

Mewbourne Oil Company
Pine Box "17" BO Fed #1H
160' FNL & 1670' FEL
Sec 17-T20S-R25E
Eddy County, NM

Ker 3/2/12

Hydrogen Sulfide Drilling Operations Plan

Mewbourne Oil Company Pine Box "17" BO Fed #1H 160' FNL & 1670' FEL Sec 17-T20S-R25E

Eddy County, New Mexico

1. General Requirements

Rule 118 does not apply to this well because MOC has researched this area and no high concentrations of H2S were found. MOC will have on location and working all H2S safety equipment before the surface casing shoe for purposes of safety and insurance requirements.

2. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will have received training from a qualified instructor in the following areas prior to entering the drilling pad area of the well:

- 1. The hazards and characteristics of hydrogen sulfide gas.
- 2. The proper use of personal protective equipment and life support systems.
- 3. The proper use of hydrogen sulfide detectors, alarms, warning systems, briefing areas, evacuation procedures.
- 4. The proper techniques for first aid and rescue operations.

Additionally, supervisory personnel will be trained in the following areas:

- 1 The effects of hydrogen sulfide on metal components. If high tensile tubular systems are utilized, supervisory personnel will be trained in their special maintenance requirements.
- 2 Corrective action and shut in procedures, blowout prevention, and well control procedures while drilling a well.
- The contents of the Hydrogen Sulfide Drilling Operations Plan.

There will be an initial training session prior to encountering a know hydrogen sulfide source. The initial training session shall include a review of the site specific Hydrogen Sulfide Drilling Operations Plan.

3. Hydrogen Sulfide Safety Equipment and Systems

All hydrogen sulfide safety equipment and systems will be installed, tested, and operational prior to drilling below the intermediate casing.

1. Well Control Equipment

- A. Choke manifold with minimum of one adjustable choke.
- B. Blowout preventers equipped with blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
- C. Auxiliary equipment including annular type blowout preventer.
- 2. Protective Equipment for Essential Personnel

Thirty minute self contained work unit located in the dog house and at briefing areas.

Additionally: If H2S is encountered in concentrations less than 10 ppm, fans will be placed in work areas to prevent the accumulation of hazardous amounts of poisonous gas. If higher concentrations of H2S are detected the well will be shut in and a rotating head, mud/gas separator, and flare line with igniter will be installed.

Hydrogen Sulfide Drilling Operations Plan Mewbourne Oil Company Pine Box "17" BO Fed #1H Page 2

3. Hydrogen Sulfide Protection and Monitoring Equipment

Two portable hydrogen sulfide monitors positioned on location for optimum coverage and detection. The units shall have audible sirens to notify personnel when hydrogen sulfide levels exceed 20 PPM.

4. <u>Visual Warning Systems</u>

- A. Wind direction indicators as indicated on the wellsite diagram.
- B. Caution signs shall be posted on roads providing access to location. Signs shall be painted a high visibility color with lettering of sufficient size to be readable at reasonable distances from potentially contaminated areas.

4. Mud Program

The mud program has been designed to minimize the amount of hydrogen sulfide entrained in the mud system. Proper mud weight, safe drilling practices, and the use of hydrogen sulfide scavengers will minimize hazards while drilling the well.

5. Metallurgy

All tubular systems, wellheads, blowout preventers, drilling spools, kill lines, choke manifolds, and valves shall be suitable for service in a hydrogen sulfide environment when chemically treated.

6. Communications

State & County Officials phone numbers are posted on rig floor and supervisors trailer. Communications in company vehicles and toolpushers are either two way radios or cellular phones.

7. Well Testing


Drill stem testing is not an anticipated requirement for evaluation of this well. A drill stem test is required, it will be conducted with a minimum number of personnel in the immediate vicinity. The test will be conducted during daylight hours only.


8. Emergency Phone Numbers

Eddy County Sheriff's Office	911 or 575-887-7551
Ambulance Service	911 or 575-885-2111
Artesia Fire Dept	911 or 575-616-7155
Loco Hills Volunteer Fire Dept.	911 or 575-677-3266
Closest Medical Facility – Artesia General Hospital	575-748-3333

Mewbourne Oil Company	Hobbs District Office Fax 2 nd Fax	575-393-5905 575-397-6252 575-393-7259
District Manager	Mickey Young	575-390-0999
Drilling Superintendent	Frosty Lathan	575-390-4103
Drilling Engineer	Wesley Noseff	575-441-0729
Engineer	Brett Bednarz	575-390-6838

Exhibit 6





Pine Box "17" BO Fed #1H

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME: Mewbourne Oil Co
LEASE NO.: NM99014
WELL NAME & NO.: 1H Pine Box 17 BO Fed
SURFACE HOLE FOOTAGE: 160' FNL & 1670' FEL
BOTTOM HOLE FOOTAGE 330' FSL & 1670' FEL
LOCATION: Section 17, T.20 S., R.25 E., NMPM
COUNTY: Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

General Provisions
☐ Permit Expiration ☐ Archaeology, Paleontology, and Historical Sites
Noxious Weeds
Special Requirements
Aplomado Falcon
Cave/Karst
◯ Construction
Notification
Topsoil
Closed Loop System
Federal Mineral Material Pits
Well Pads
Roads
Road Section Diagram
☑ Drilling
Waste Material and Fluids
Logging Requirements
High Cave/Karst
☑ Production (Post Drilling)
Well Structures & Facilities
Pipelines
Electric Lines
Interim Reclamation
☐ Final Abandonment & Reclamation

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Conditions-of-Approval for Drilling in Aplomado Falcon Habitat

The following well pad construction and reclamation measures will be implemented to provide for minimal long-term disturbance:

No Yuccas or trees over 5 feet in height will be damaged by vehicular use or any other activity associated with this project.

Remove all caliche from well pads and roads that are plugged and abandoned. Reclamation will consist of disking, mulching, seeding with a drill (See seed mixture below), and application of water to encourage seed germination.

Well pad size will not exceed 300 ft. x 390 ft. (unless multiple wells are drilled from the same well pad). All unused portions of the well pad associated with producing wells will be reclaimed using the seed mixture below:

Buffalograss (Buchloe dactyloides)	4 lbs/acre
Blue grama (Bouteloua gracilis)	1 lbs/acre
Cane bluestem (Bothriochloa barbinodis)	5 lbs/acre
Sideoats grama (Boutelou curtipendula)	5 lbs/acre
Plains bristlegrass (Setaria macrostachya)	6 lbs/acre

Cave and Karst

** Depending on location, additional Drilling, Casing, and Cementing procedures may be required by engineering to protect critical karst groundwater recharge areas.

Cave/Karst Surface Mitigation

The following stipulations will be applied to minimize impacts during construction, drilling and production.

Construction:

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

No Blasting:

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

Pad Berming:

The pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the pad. All sides will be bermed.

Tank Battery Liners and Berms:

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

Leak Detection System:

A method of detecting leaks is required. The method could incorporate gauges to measure loss, situating values and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

Automatic Shut-off Systems:

Automatic shut off, check values, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and ground water concerns:

Rotary Drilling with Fresh Water:

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

Directional Drilling:

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

Lost Circulation:

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cavebearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

Abandonment Cementing:

Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

Pressure Testing:

Annual pressure monitoring will be performed by the operator on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-6235 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall stockpile the topsoil in a low profile manner in order to prevent wind/water erosion of the topsoil. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be used for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty (20) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning


Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:




Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope:
$$\frac{400'}{4\%}$$
 + 100' = 200' lead-off ditch interval

Culvert Installations

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

Fence Requirement

Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

lumout, 10' Întervisible trimous shall be constructed all single lane roods on all blind culves a additional trinouts as needed to keep sp below 1000 feet. Typical Turnout Plan Embankment Section :03 --05 ft/ft .02 - .04 ft/ft .02,- .03 h/h; **Side Hill Section** Typical Outsloped Section Typical Inslope Section

Figure 1 - Cross Sections and Plans For Typical Road Sections

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. Although Hydrogen Sulfide has not been reported in this section, it is always a potential hazard. If Hydrogen Sulfide is encountered, please report measured amounts and formations to the BLM.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. If the drilling rig is removed without approval an Incident of Non-Compliance will be written and will be a "Major" violation.
- 3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies.

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

HIGH CAVE/KARST – CONTINGENCY CASING WILL BE REQUIRED IF LOST CIRCULATION OCCURS WHILE DRILLING THE SURFACE HOLE. THE SURFACE HOLE WILL HAVE TO BE REAMED AND A LARGER CASING INSTALLED.

Possible lost circulation in the San Andres formation.

- 1. The 9-5/8 inch surface casing shall be set at approximately 985 feet and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 7 inch production casing is:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst concerns.

- 3. The minimum required fill of cement behind the 4-1/2 inch production casing is:
 - ☐ Cement not required Packer/Port system to be used.
- 4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000** (**2M**) psi.
- 3. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - c. The results of the test shall be reported to the appropriate BLM office.

- d. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- e. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.
- f. Effective November 1, 2008, no variances will be granted on reduced pressure tests on the surface casing and BOP/BOPE. Onshore Order 2 requirements will be in effect.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

CRW 041712

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Containment Structures

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color Shale Green, Munsell Soil Color Chart # 5Y 4/2

B. PIPELINES

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the APD and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- 1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
- 2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
- 3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the

Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

- 4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:
- a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
- b. Activities of other parties including, but not limited to:
 - (1) Land clearing.
 - (2) Earth-disturbing and earth-moving work.
 - (3) Blasting.
 - (4) Vandalism and sabotage.
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

- 6. The pipeline shall be routed no farther than 6 feet from and parallel to existing roads. The authorized right-of-way width will be 20 feet. 14 feet of the right-of-way width will consist of existing disturbance (existing lease roads) and the remaining 6 feet will consist of area adjacent to the disturbance. All construction and maintenance activity will be confined to existing roads.
- 7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.
- 8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky of duney areas, the pipeline will be "snaked" around hummocks and dunes rather then suspended across these features.
- 9. The pipeline shall be buried with a minimum of <u>24</u> ____ inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.
- 10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
- 11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.
- 12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.
- 13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.
- 14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline

route is not used as a roadway.

- 15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.
- 16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the APD and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- 1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
- 2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

- 3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
- 4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.
- 5. Powerlines shall be constructed in accordance to standards outlined in "Suggested Practices for Raptor Protection on Powerlines," Raptor Research Foundation, Inc., 1981. The holder shall assume the burden and expense of proving that pole designs not shown in the above publication are "raptor safe." Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.
- 6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
- 7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.
- 8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.
- 9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.
- 10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land

shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- Poles shall be placed no farther than 10 feet from the edge of the access road.
- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 3, for Shallow Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be <u>no</u> primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species	<u>lb/acre</u>
Plains Bristlegrass (Setaria magrostachya)	1.0
Green Spangletop (Leptochloa dubia)	2.0
Side oats Grama (Bouteloua curtipendula)	5.0

^{*}Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed