#### OCD Artesia

Fom 3160-3 (April 2004)				OMB N	APPROVED to, 1004-0137 March 31, 20	-05
UNITED STATES  DEPARTMENT OF THE 1  BUREAU OF LAND MAN	NTERIOR	•		5. Lease Seriol No. NMLC- 0293		9/20/202
APPLICATION FOR PERMIT TO				6. If Indian, Allotee	or Tribe N	Jame
la. Type of work: DRILL REENTE	ER.			7. If Unit or CA Agr	eement, Nar	ne and No.
lb. Type of Well: Oil Well Gas Well Other	<b>✓</b> Si	ngle Zone Multi	ple Zone	8. Lease Name and LEE FEDER.		308720>
2. Name of Operator  APACHE CORPORATION		>&r	134	9. API Well No. 30-015-	407	730
3a. Address 303 VETERANS AIRPARK LN #3000 MIDLAND, TX 79705		. (include area code) 8-1167		10. Field and Pool, or CEDAR LAK		10 · 00 · 1
4. Location of Well (Report location clearly and in accordance with an 2300' FSL & 450' FWL	y State requirem	ents.*)		11. Sec., T. R. M. or I	3lk, and Surv	vey or Area
At surface 2300° FSL & 450° FWL  At proposed prod. zone 2310° FSL 4 990	FWL			SEC: 17 T17	S R31E	
14. Distance in miles and direction from nearest town or post office* APPROX 5 MILES EAST OF LOCO HILLS, NM				12. County or Parish EDDY		13. State NM
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig, unit line, if any)	16. No. of a	cres in lease	17. Spa	cing Unit dedicated to this 40 ACRES	well	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. ~ 422'		1Depth ND~6400' MD~6430'	BI	M/BIA Bond No. on file  M - CO - 1463 NATIO	ONWIDE	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3704'	22. Approxim	mate date work will sta		23. Estimated duration 23. To DAYS	n	
The following, completed in accordance with the requirements of Onshor	24. Attac		ittached to	this form:		
Well plat certified by a registered surveyor.     A Dulling Plan.				tions unless covered by an	existing bo	nd on file (see
3. A Surface Use Plan (if the location is on National Forest System SUPO shall be filed with the appropriate Forest Service Office).	Lands, the	Operator certification     Such other site authorized office	specific	information and/or plans as	may be req	quired by the
25. Signature Sorina Sollare	<b>I</b>	(Printed/Typed) SORINA L. FLOR	ES		Date 9	/11/12
Title SUPV OF DRILLING SERVICES					• ,	4
Approved by (Signature) /s/ Don Peterson	Name	(Printed/Typed)	/s/ D	on Peterson	Date SEF	P 1 8 2012
Title (**FIELD MANAGER	Office		CARI	SBAD FIELD OFFI		
Application approval does not warrant or certify that the applicant holds conduct operations thereon. Conditions of approval, if any, are attached.	legal or equit	able title to those righ	_	subject lease which would e		
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a cr States any false, fictitious or fraudulent statements or representations as to	me for any pe	erson knowingly and vithin its jurisdiction.	villfully to	o make to any department o	r agency of	the United
*(Instructions on page 2)	RE	CEIVE	7		0	
Roswell Controlled Water Basin	S	EP 2 0 2012		Approvat & Si	Subject Decial St	to General Regulrements ipulations Attached

NMOCD ARTESIA
SEE ATTACHED FOR CONDITIONS OF APPROVAL

# UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT CARLSBAD FIELD OFFICE 620 E. GREENE STREET CARLSBAD, NM 88220

#### **OPERATOR CERTIFICATION**

I HEARBY CERTIFY THAT I, OR SOMEONE UNDER MY DIRECT SUPERVISION, HAVE INSPECTED THE DRILL SITE AND ACCESS ROUTE PROPOSED HEREIN; THAT I AM FAMILIAR WITH THE CONDITIONS WHICH CURRENTLY EXIST; THAT I HAVE FULL KNOWLEDGE OF STATE AND FEDERAL laws applicable to this operation; that the statements made in the APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S>C. 1001 for the filing of false statements.

Well: <u>LEE_FEDERAL #56</u> Operator Name: <u>APACHE C</u>	ORPORATION
Signature: Fd. Lange	
Title: Drilling Engineer	Date:
Email (optional):bob.lang	ge@apachecorp.com
Street or Box: 303 Vetera	ans Airpark Ln., Ste. 3000
City, State, Zip Code: <u>Midland, 1</u>	TX 79705
Telephone:	432-818-1114
Field Representative (if not above s	
Address (if different from above): _	
Telephone (if different from above)	):
Email (optional):	

Executed this 37 day of January, 2012

Agents not directly employed by the operator must submit a letter from the operator authorizing that the agent to act or file this application on their behalf.

DISTRICT 1
1625 N French Dr., Hobbs, NM 88240
Phone (575) 393-6161 Fax. (575) 393-0720
DISTRICT II

BISTRICT III

1000 Rto Biazos Road, Azlec, NM 87410 Phone (505) 334-6178 Fax: (505) 334-6170 DISTRICT IV

1220 S St Francis Dr , Santa Fe, NM 87505 Phone (505) 476-3460 Fax (505) 476-3462

# State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION 1220 South St. Francis Dr. Santa Fe, New Mexico 87505


Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

AMENDED REPORT

#### WELL LOCATION AND ACREAGE DEDICATION PLAT

30-015	PI Number - 40	730	961	Pool Code	C	edar hake	Pool Name		
Property C	Code				Property Name LEE FEDER		•	W	ell Number
<i>3</i> 08720									56
973	No			APAC	Operator Name			1	Elevation 3704'
					Surface Locati	on			
UL or lot No	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
L	17	17-S	31-E		2300	SOUTH	450	WEST	EDDY
				Bottom Hol	e Location If Diffe	erent From Surface			
UL or lot No	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
L	17	17-S	31-E		2310	SOUTH	990	WEST	EDDY
Dedicated Acres	Joint or	Infill C	onsolidation C	ode Ord	er No	I			

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



#### DRILLING PLAN: BLM COMPLIANCE (Supplement to BLM 3160-3)

#### APACHE CORPORATION (OGRID: 873) LEE FEDERAL #56

Lease #: NMLC-029395B Projected TVD: 6400' MD: 6430'

SHL: 2300' FSL & 450' FWL BHL: 2310' FSL & 990' FWL UL: L SEC: 17 T17S R31E EDDY COUNTY, NM

#### 1. GEOLOGIC NAME OF SURFACE FORMATION: Eolian/Piedmond Alluvial Deposits

#### 2. ESTIMATED TOPS OF GEOLOGICAL MARKERS & DEPTHS OF ANTICIPATED FRESH WATER, OIL OR GAS:

Eolian/Piedmont Alluvials	Surface	Queen	2351′
Rustler	178'	Grayburg	2696' (oil)
Salt Top	516'	San Andres	3062' (oil)
Salt Bottom	1271'	Glorieta	4546' (oil)
Yates	1452'	Yeso	4613' (oil)
Seven Rivers	1740′	TVD / MD	6400′ / 6430′
Depth to Ground Water:	~ 91'		

All fresh water & prospectively valuable minerals, as described by BLM, encountered during drilling, will be recorded by depth and adequately protected. All oil & gas shows within zones of correlative rights will be tested to determine commercial potential. The surface fresh water sands will be protected by setting 13-3/8" csg @ 205' & circ cmt back to surface. All intervals will be isolated by setting 5-1/2" csg to TD & circ cmt above the base of 8-5/8" csg.

3. CASING PROGRAM: All casing is new & API approved

Secup

HOLE SIZE	DEPTH	OD CSG	WEIGHT	COLLAR	GRADE	COLLAPSE	BURST	TENSION
17-1/2"	0'-205'380	13-3/8"	48#	STC	H-40	1.125	1.0	1.8
11"	205'-3500'	8-5/8"	32#	STC	J-55	1.125	1.0	1.8
7-7/8"	03500'-6400'	5-1/2"	17#	LTC	J-55	1.125	1.0	1.8

#### 4. CEMENT PROGRAM:

#### 13-3/8" Surface (100% excess cmt to surf) Cmt with:

COR

Lead: 240 sx Class C w/ 1% CaCl2, 0.25% R38 (14.8 wt, 1.34 yld) Compressive Strengths: 12 hr - 813 psi 24 hr - 1205 psi

**8-5/8"** Intermediate: (100% excess cmt to surf) Cmt with: В.

<u>Lead</u>: 670 sx (35:65) Poz C w/ 6% Bentonite, 5% Salt, 0.25% R38 (12.4wt, 2.1 yld)

Compressive Strengths: 12 hr - 589 psi **24 hr** – 947 psi

Tail: 210 sx Class C w/, 0.25% R38 (14.8 wt, 1.34 yld)

Compressive Strengths: 12 hr - 813 psi 24 hr - 1205 psi

#### 5-1/2" Production: (35% excess cmt; TOC: ~500' from surface) Cmt with:

Lead: 300 sx (65:35) Poz C w/ 5% Salt, 0.25% R38, 6% Bentonite (12.4 wt, 2.1 yld)

Compressive Strengths: 12 hr – 540 psi 24 hr – 866 psi

Tail: 700 sx (50:50) Poz C w/ 5% Salt, 0.25% R38, 2% Bentonite (14.2 wt, 1.28 yld)

Compressive Strengths: 12 hr – 1379 psi 24 psi – 2332 psi

<sup>\*\*</sup> The above cmt volumes could be revised pending caliper measurement from open hole logs. For Surface csg: If cmt does not circ to surface, the appropriate BLM office shall be notified & a tag with 1" will be performed at four positions 90 degrees apart to verify cmt depth. If depth is greater than 100' or water is standing in the annulus, remedial cementing will be done. If no water & TOC tag is less than 100', when 100% excess cmt of the annulus volume is run on the primary job, ready-mix will be used to bring cmt to surface.

5. PROPOSED CONTROL EQUIPMENT

"EXHIBIT 3" shows a 11" 3M psi WP BOP consisting of an annular bag type preventer, middle blind rams, bottom pipe rams. The BOP will be nippled up on the 13-3/8" surface csg head & tested to 70% of csg burst. After intermediate csg is set & cemented an 11" 3M spool & BOP (2M if available) will be installed on the 8 5/8" casing & utilized continuously until total depth is reached. The BOP will be tested at 2000 psi, maximum surface pressure is not expected to exceed 2M psi, BHP is calculated to be approximately 2816 psi. \*All BOP's and associated equipment will be tested as per BLM Drilling Operations Order #2. The BOP will be operated & checked each 24 hr period & the blind rams will be operated & checked when the drill pipe is out of the hole. Functional tests will be documented on the daily driller's log. "EXHIBIT 3" also shows a 3M psi choke manifold with a 3" blow down line. Full opening stabbing valve & Kelly cock will be on derrick floor in case of need. No abnormal pressures of temperatures are expected in this well. No nearby wells have encountered any problems.

#### 6. PROPOSED MUD CIRCULATION SYSTEM: (Closed Loop System)

INTERVAL	MW (ppg)	VISC (sec/qt)	FLUID LOSS (cc)	MUD TYPE	
0' -285' 380	8.4	29	NC	Fresh Water	
205' to 3500'	9.8 – 10.0	29	NC	Brine	
3500' - 6500' (30	8.9 – 9.0	29	NC	Cut Brine	

<sup>\*\*</sup> The necessary mud products for weight addition and fluid loss control will be on location at all times. In order to run open hole logs & casing, the above mud properties may have to be altered to meet these needs.

#### 7. AUXILIARY WELL CONTROL EQUIPMENT / MONITORING EQUIPMENT:

11" x 3000 psi Double BOP/Blind & pipe ram (2M if available)

4-1/2" x 3000 psi Kelly valve

11" x 3000 psi mud cross – H2S detector on production hole

Gate-type safety valve 3" choke line from BOP to manifold

2" adjustable chokes - 3" blow down line

Fill up line as per Onshore Order 2

# 8. LOGGING, CORING & TESTING PROGRAM: See COA

- A. OH logs: Dual Laterolog, MSFL, CNL, Litho-Density, Gamma Ray, Caliper & Sonic from TD back to 8-5/8" csg shoe.
- B. Run CNL, Gamma Ray from 8-5/8" csg shoe back to surface.
- C. No cores, DST's or mud logger are planned at this time.
- **D.** Additional testing will be initiated subsequent to setting the 5-1/2" production casing. Specific intervals will be targeted based on log evaluation, geological sample shows & drill stem tests.

#### 9. POTENTIAL HAZARDS:

No abnormal pressures or temperatures are anticipated. In the event abnormal pressures are encountered, however, the proposed mud program will be modified to increase the mud-weight. There is known presence of H<sub>2</sub>S in this area. If H<sub>2</sub>S is encountered the operator will comply with the provisions of *Onshore Oil & Gas Order No. 6*. No lost circulation is expected to occur. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. Estimated BHP: 2816 psi and estimated BHT: 115°.

#### 10. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

Road and location construction will begin after BLM has approved APD. Anticipated spud date will be as soon after Santa Fe and BLM approval and as soon as rig will be available. Move in operations and drilling is expected to take 10 days. If production casing is run then an additional 90 days will be needed to complete well and construct surface facilities and/or lay flow lines in order to place well on production.

#### 11. OTHER FACETS OF OPERATION:

After running csg, cased hole Gamma Ray, Neutron Collar logs will be run from TD back to all possible productive zones. The Cedar Lake; Glorieta-Yeso formation will be perforated and stimulated in order to establish production. The well will be swab tested & potentialed as an oil well.



# **Apache**

Eddy County, New Mexico (NAD 27) Lee Federal #56

Wellbore #1

Plan: Design #1

# **Standard Planning Report**

30 August, 2012





Planning Report



Database: Company: Southern Region

Apache

Eddy County, New Mexico (NAD 27)

Project: Site:

Lee Federal

Well: #56 Wellbore #1 Wellbore: Design #1 Design:

Local Co-ordinate Reference:

**TVD Reference:** 

MD Reference: North Reference:

**Survey Calculation Method:** 

Well #56

WELL @ 3704.00usft (Original Well Elev) WELL @ 3704.00usft (Original Well Elev)

Mınimum Curvature

Project

Map Zone:

**Well Position** 

Eddy County, New Mexico (NAD 27)

Map System: Geo Datum:

US State Plane 1927 (Exact solution) NAD 1927 (NADCON CONUS)

New Mexico East 3001

System Datum:

Mean Sea Level

Well

#56

+N/-S

667,195.40 usft

Northing: Easting:

667,195.40 usft

Latitude:

32° 50' 0.4232 N

633,568.50 usft +E/-W

633,568.50 usft

Longitude:

103° 53' 54.536 W

**Position Uncertainty** 

0 00 usft

Wellhead Elevation:

Ground Level:

3,704 00 usft

Wellbore #1 Wellbore Declination Magnetics **Model Name** Sample Date Dip Angle Field Strength (°) (°) (nT) WMM 2010 8/30/2012 7.65 60.66 48,822

Design	Design #1					
Audit Notes:						
Version:		Phase:	PROTOTYPE	Tie On Depth:	0.00	
Vertical Section:		Depth From (TVD)	+N/-S	+E/-W	Direction	
		(usft)	(usft)	(usft)	(°)	
		0.00	0 00	0.00	88.50	

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0 00	0.00	0.00	0.00	0.00	0.00	0 00	0 00	0 00	0.00	<del></del>
1,450 00	0.00	0.00	1,450 00	0 00	0 00	0.00	0 00	0 00	0.00	
1,771.60	6.43	88.50	1,770 92	0 47	18 03	2 00	2.00	27.52	88 50	
6,430 00	6.43	88 50	6,400.00	14 10	539.70	0 00	0.00	0 00	0.00 PE	BHL v1 - Lee Fed



Planning Report



Database: Company: Project:

Site:

Southern Region

Apache

Eddy County, New Mexico (NAD 27)

Lee Federal

Well: Wellbore: Design:

#56

Wellbore #1 Design #1

Local Co-ordinate Reference:

TVD Reference:

MD Reference: North Reference:

Survey Calculation Method:

Well #56

WELL @ 3704 00usft (Original Well Elev)

WELL @ 3704.00usft (Original Well Elev)

Minimum Curvature

ed Survey	L						<del> </del>		and the second s
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn. Rate (°/100usft)
0 00	0.00	0 00	0.00	0 00	0.00	0.00	0.00	0 00	0.00
100.00	0.00	0 00	100 00	0 00	0.00	0 00	0 00	0 00	0.00
200 00	0 00	0 00	200.00	0 00	0.00	0.00	0 00	0 00	0 00
Rustler									
300 00	0 00	0 00	300 00	0 00	0.00	0 00	0 00	0 00	0 00
400 00	0 00	0 00	400 00	0 00	0.00	0 00	0 00	0 00	0 00
500 00	0 00	0.00	500.00	0 00	0.00	0.00	0 00	0.00	0 00
538 00	0 00	0.00	538 00	0 00	0 00	0.00	0 00	0 00	0 00
T/Salt									
600.00	0.00	0.00	600 00	0 00	0 00	0 00	0 00	0 00	0.00
700 00	0 00	0.00	700.00	0 00	0.00	0 00	0 00	0 00	0.00
800 00	0 00	0.00	800 00	0.00	0.00	0 00	0.00	0 00	0 00
900 00	0 00	0 00	900.00	0.00	0.00	0.00	0.00	0.00	0 00
1,000 00	0 00	0.00	1,000.00	0.00	0.00	0 00	0.00	0 00	0 00
1,100.00	0.00	0 00	1,100 00	0.00	0 00	0 00	0 00	0 00	0.00
1,200.00	0.00	0 00	1,200 00	0 00	0 00	0 00	0 00	0.00	0 00
1,293.00	0 00	0 00	1,293.00	0 00	0 00	0 00	0 00	0 00	0 00
B/Salt			·						
1,300 00	0 00	0 00	1.300.00	0.00	0.00	0 00	0 00	0 00	0 00
1,400.00	0 00	0 00	1,400.00	0.00	0.00	0 00	0.00	0.00	0 00
1,450.00	0 00	0.00	1,450.00	0.00	0.00	0 00	0.00	0.00	0.00
· ·		0.00	1,400.00	0.00	0.00	0 00	0.00	0 00	0.00
KOP, 2.00°/1 1,474 00	0.48	88.50	1,474 00	0 00	0.10	0.10	2 00	2.00	0 00
Yates	0.40	00.00	1,474 00	0.00	0.10	0.10	2 00	2.00	0 00
1,500 00	1 00	88.50	1,500 00	0 01	0.44	0.44	2 00	2 00	0 00
•									
1,600 00	3.00	88.50	1,599 93	0 10	3 92	3 93	2 00	2.00	0 00
1,700.00	5.00	88 50	1,699.68	0.28	10.90	10.90	2 00	2 00	0 00
1,771 60	6.43	88 50	1,770.92	0.47	18.03	18.03	2 00	2 00	0 00
Begin 6.43°	-	99.50	1,799.15	0.55	24.24	24.24	0.00	0.00	0 00
1,800 00 1,900,00	6 43 6.43	88 50 88 50	1,799.15	0.55 0.85	21.21 32.41	21 21 32.42	0.00 0 00	0.00	0 00
•									
2,000 00	6.43	88 50	1,997 89	1 14	43 60	43 62	0 00	0 00	0 00
2,100 00	6 43	88 50	2,097 26	1.43	54.80	54 82	0 00	0 00	0.00
2,200 00	6.43	88 50	2,196 63	1 72	66.00	66.02	0 00	0 00	0.00
2,300 00	6 43	88 50	2,296 00	2 02	77.20	77.23	0 00	0 00	0 00
2,400 00	6 43	88.50	2,395.37	2 31	88.40	88.43	0 00	0 00	0.00
2,500 00	6 43	88 50	2,494 74	2.60	99.60	99 63	0 00	0 00	0 00
2,600 00	6.43	88 50	2,594 11	2 89	110 80	110 83	0 00	0 00	0 00
2,700 00	6 43	88 50	2,693 48	3 19	121 99	122.04	0 00	0.00	0 00
2,724 67	6.43	88 50	2,718 00	3 26	124.76	124 80	00.0	0.00	0 00
Grayburg									
2,800 00	6.43	88.50	2,792.85	3.48	133.19	133.24	0 00	0 00	0 00
2,900.00	6 43	88.50	2,892.22	3.77	144.39	144.44	0.00	0 00	0 00
3,000 00	6.43	88 50	2,991 59	4 06	155.59	155.64	0.00	0 00	0 00
3,092 99	6 43	88 50	3,084 00	4 34	166.00	166.06	0 00	0 00	0.00
San Andres	<b>,</b>								
3,100 00	6.43	88 50	3,090 96	4.36	166,79	166 84	0 00	0 00	0 00
3,200.00	6 43	88,50	3,190.33	4.65	177,99	178.05	0.00	0 00	0.00
					· · · · - <del>-</del>				

3,300 00

3,400 00

3,500 00

3,600.00

3,700 00

4 94

5 24

5.53

5.82

6 11

189.19

200.38

211.58

222.78

233.98

189 25

200.45

211.65

222.86

234.06

0.00

0.00

0 00

0.00

0.00

0.00

0.00

0.00

0 00

0.00

88 50

88.50

88 50

88 50

88 50

6.43

6 43

6 43

6.43

6 43

3,289 70

3,389 08

3,488.45

3,587.82

3,687 19

0.00

0.00

0.00

0 00

0.00



Planning Report



Database: Company:

Project:

Southern Region

Apache

Eddy County, New Mexico (NAD 27)

Lee Federal

Site: Lee Well: #56

Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference:

TVD Reference:

MD Reference: North Reference:

Survey Calculation Method:

Well #56

WELL @ 3704.00usft (Original Well Elev) WELL @ 3704.00usft (Original Well Elev)

Grid

Minimum Curvature

Danih			Vertical			Vertical	Dogleg	Build	Turn
Depth (usft)	Inclination (°)	Azimuth (°)	Depth (usft)	+N/-S (usft)	+E/-W (usft)	Section (usft)	Rate (°/100usft)	`Rate (°/100usft)	Rate (°/100usft)
3,800 00	6.43	88 50	3,786 56	6.41	245.18	245.26	0 00	0 00	0 00
3,900 00	6 43	88.50	3,885 93	6.70	256.38	256.46	0 00	0.00	0 00
4,000 00	6 43	88 50	3,985 30	6.99	267 58	267 67	0 00	0.00	0.00
4,100 00	6.43	88 50	4,084 67	7.28	278 77	278 87	0 00	0 00	0.00
4,200 00	6 43	88 50	4,184.04	7.58	289 97	290 07	0.00	0 00	0 00
4,300 00	6.43	88 50	4,283.41	7.87	301 17	301 27	0 00	0 00	0 00
4,400.00	6.43	88 50	4,382.78	8.16	312 37	312 48	0 00	0 00	0.00
4,500 00	6.43	88 50	4,482.15	8.45	323 57	323 68	0 00	0 00	0 00
4,586 39	6 43	88 50	4,568.00	8.71	333 24	333 36	0 00	0 00	0.00
Glorieta									
4,600 00	6 43	88.50	4,581 52	8 75	334 77	334.88	0 00	0 00	0 00
4,653 82	6.43	88 50	4,635.00	8 90	340 79	340 91	0.00	0 00	0.00
Paddock									
4,700.00	6 43	88.50	4,680.89	9.04	345.97	346 08	0 00	0.00	0 00
4,800.00	6 43	88 50	4,780.26	9.33	357 16	357 29	0 00	0.00	0 00
4,900.00	6 43	88 50	4,879.63	9.62	368 36	368 49	0.00	0 00	0 00
5,000 00	6.43	88 50	4,979.00	9.92	379 56	379 69	0.00	0 00	0 00
5,100 00	6.43	88.50	5,078 37	10 21	390 76	390 89	0 00	0 00	0 00
5,168 05	6 43	88 50	5,146 00	10.41	398 38	398 52	0.00	0 00	0 00
Blinebry									
5,200 00	6 43	88 50	5,177.75	10.50	401 96	402 10	0 00	0.00	0.00
5,300 00	6 43	88 50	5,277.12	10 79	413 16	413.30	0 00	0 00	0.00
5,400 00	6.43	88 50	5,376 49	11.09	424 36	424.50	0 00	0.00	0 00
5,500 00	6.43	88 50	5,475.86	11 38	435 55	435.70	0 00	0.00	0.00
5,600 00	6.43	88 50	5,575.23	11 67	446 75	446.90	0.00	0.00	0.00
5,700.00	6.43	88 50	5,674.60	11 96	457 95	458.11	0.00	0 00	0.00
5,800.00	6 43	88 50	5,773 97	12 26	469 15	469 31	0 00	0 00	0 00
5,900 00	6 43	88 50	5,873 34	12 55	480.35	480.51	0 00	0 00	0 00
6,000.00	6 43	88.50	5,972 71	12.84	491 55	491.71	0 00	0 00	0.00
6,100 00	6.43	88 50	6,072.08	13 13 13 23	502.75	502 92	0 00	0 00	0 00

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL v1 - Lee Federal # - plan hits target cen - Point		0 00	6,400 00	14 10	539.70	667,209 50	634,108.20	32° 50' 0 5407 N	103° 53' 48 210 W

13.43

13.72

14.01

14.10

513.94

525.14

536 34

539.70

514 12

525 32

536 52

539 88

0.00

0 00

0 00

0 00

0 00

0.00

0 00

0 00

6,200 00

6,300 00

6,400.00

6,430.00

PBHL

6.43

6 43

6.43

6 43

88 50

88 50

88 50

88 50

6,171.45

6,270.82

6,370.19

6,400.00

0 00

0 00

0 00

0.00



Planning Report



Database: Company:

Well:

Southern Region

Apache

Eddy County, New Mexico (NAD 27)

Project: Site:

Lee Federal #56

Wellbore #1 Wellbore: Design #1 Design:

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

Survey Calculation Method:

Well #56

WELL @ 3704 00usft (Original Well Elev) WELL @ 3704.00usft (Original Well Elev)

Minimum Curvature

Formations						
	Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	. Dip Direction (°)
	200 00	200 00	Rustler		0 00	
	538 00	538.00	T/Salt		0 00	
	1,293 00	1,293 00	B/Salt		0 00	
	1,474.00	1,474.00	Yates		0 00	
	2,724 67	2,718.00	Grayburg		0.00	
	3,092 99	3,084 00	San Andres		0 00	
	4,586 39	4,568 00	Glorieta		0 00	
	4,653.82	4,635 00	Paddock			
	5,168 05	5,146.00	Blinebry			
	6,132 12	6,104.00	Tubb			

Plan Annotati	ons				
	Measured	Vertical	Local Coor	dinates	
	Depth	Depth	+N/-S	+E/-W	
	(usft)	(usft)	(usft)	(usft)	Comment
	1,450 00	1,450 00	0 00	0 00	KOP, 2 00°/100' Build
	1,771.60	1,770.92	0.47	18.03	Begin 6 43° Tangent
	6,430 00	6,400.00	14.10	539.70	PBHL



Company: Apache Site: Lee Federal Well: #56


Rig Name: Original Well Elev


Project: Eddy County, New Mexico (NAD 27)



Planning 936 442 2510 Fax 936 442 2515 Operations 936 442 2500 Fax, 936 442 2599

				ANNOTA	ATIONS			
MD	Inc	Azı	TVD	+N/-S	+E/-W	VSect	Departure	Annotation
1450.00	0 00	0 00	1450.00	0 00	0 00	0.00	0.00	KOP, 2 00°/100' Build
1771.60	6 43	88 50	1770 92	0.47	18 03	18.03	18.03	Begin 6.43° Tangent
6430.00	6.43	88,50	6400.00	14.10	539 70	539 88	539 88	PBHL





T G M

Azımuths to Grid North True North -0 24° Magnetic North 7 42°


Magnetic Field Strength 488218snT Dip Angle, 60 66° Date 8/30/2012 Model WMM\_2010

US State Plane 1927 (Exact solution) New Mexico East 3001

Created By Vanessa Scott

Date 14 06, August 30 2012


Plan Design #1



# 3M psi BOPE & Choke Manifold Exhibit 3

All valve & lines on choke manifold are 2" unless noted.

Exact manifold configuration may vary





#### DESIGN PLAN, OPERATING & MAINTENANCE PLAN, & CLOSURE PLAN FOR OCD FOR C-144

#### LEE FEDERAL #56

#### **DESIGN PLAN**

Fluid & cuttings coming from drilling operations will pass over the Shale Shaker with the cuttings going to the Sundance Inc / CRI haul off bin and the cleaned fluid returning to the working steel pits.

#### Equipment includes:

- 2 500 bbl steel frac tanks (fresh water for drilling)
- 2 180 bbl steel working pits
- 3 75 bbl steel haul off bins
- 2 Pumps (6-1/2" x 10" PZ 10 or equivalent)
- 1 Shale shaker
- 1 Mud cleaner QMAX MudStripper


#### **OPERATING AND MAINTENANCE PLAN**


Inspection to occur every tour for proper operation of system and individual components. If any problems are found they will be repaired and/or corrected immediately.

#### **CLOSURE PLAN**

All haul bins containing cuttings will be removed from location and hauled to Sundance Incorporated (NM-01-0003) disposal site located 3 miles East of Eunice, NM on the Texas border / Controlled Recovery, Inc's (NM-01-0006) disposal site located near mile marker 66 on Highway 62/180.

Sorina L. Flores Supv. of Drilling Services





#### HYDROGEN SULFIDE (H2S) DRILLING OPERATIONS PLAN

#### **Hydrogen Sulfide Training:**

<u>All regularly assigned personnel, contracted or employed by Apache Corporation</u> will receive training from qualified instructor(s) in the following areas prior to commencing drilling possible hydrogen sulfide bearing formations in this well:

- The hazards and characteristics of hydrogen sulfide (H<sub>2</sub>S)
- The proper use and maintenance of personal protective equipment and life support systems.
- The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing area, evacuation procedures & prevailing winds.
- The proper techniques for first aid and rescue procedures.

#### Supervisory personnel will be trained in the following areas:

- The effects of H<sub>2</sub>S on metal components. If high tensile tubulars are to be utilized, personnel will be trained in their special maintenance requirements.
- Corrective action & shut-in procedures when drilling or reworking a well & blowout prevention / well control procedures.
- The contents and requirements of the H<sub>2</sub>S Drilling Operations Plan

There will be an initial training session just prior to encountering a known or probable  $H_2S$  zone (within 3 days or 500') and weekly  $H_2S$  and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific  $H_2S$  Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received proper training.

#### H<sub>2</sub>S SAFETY EQUIPMENT AND SYSTEMS:

#### Well Control Equipment that will be available & installed if H<sub>2</sub>S is encountered:

- Flare Line with electronic igniter or continuous pilot.
- Choke manifold with a minimum of one remote choke.
- Blind rams & pipe rams to accommodate all pipe sizes with properly sized closing unit.
- · Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head & flare gun with flares

#### **Protective Equipment for Essential Personnel:**

• Mark II Survive-air 30 minute units located in dog house & at briefing areas, as indicated on wellsite diagram.

#### **H2S Dection and Monitoring Equipment:**

- Two portable H<sub>2</sub>S monitors positioned on location for best coverage & response. These units have warning lights & audible sirens when H<sub>2</sub>S levels of 20 ppm are reached.
- One portable H<sub>2</sub>S monitor positioned near flare line.

#### **H2S Visual Warning Systems:**

- Wind direction indicators are shown on wellsite diagram.
- Caution / Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

#### Mud Program:

- The Mud Program has been designed to minimize the volume of H<sub>2</sub>S circulated to the surface. Proper mud weights, safe
  drilling practices & the use of H<sub>2</sub>S scavengers will minimize hazards when penetrating H<sub>2</sub>S bearing zones.
- A mud-gas separator and H<sub>2</sub>S gas buster will be utilized as needed.

#### Metallurgy:

- All drill strings, casing, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold & lines, & valves will be suitable for H₂S service.
- All elastomers used for packing & seals shall be H<sub>2</sub>S trim.

#### Communication:

Cellular telephone and 2-way radio communications in company vehicles, rig floor and mud logging trailer.

### HYDROGEN SULFIDE (H<sub>2</sub>S) CONTINGENCY PLAN

#### **Assumed 100 ppm ROE = 3000'**

100 ppm H<sub>2</sub>S concentration shall trigger activation of this plan.

#### **Emergency Procedures**

In the event of a release of gas containing H<sub>2</sub>S, the first responder(s) must

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE.
- Be equipped with H<sub>2</sub>S monitors and air packs in order to control the release.
- Use the "buddy system" to ensure no injuries occur during the response
- Take precautions to avoid personal injury during this operation.
- Contact operators and/or local officials to aid in operation. See list of phone numbers attached.
- Have received training in the :
  - o Detection of H<sub>2</sub>S, and
  - o Measures for protection against the gas,
  - o Equipment used for protection and emergency response.

#### Ignition of Gas source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever this is an ignition of the gas.

Characteristics of H<sub>2</sub>S and SO<sub>2</sub>

		· ·			
Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H₂S	1.189 Air = I	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO <sub>2</sub>	2.21 Air = I	2 ppm	N/A	1000 ppm

#### **Contacting Authorities**

Apache Corporation personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Apache's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

#### WELL CONTROL EMERGENCY RESPONSE PLAN

#### I. GENERAL PHILOSOPHY

Our objective is to ensure that during an emergency, a predetermined procedure is followed so that prompt decisions can be made based on accurate information.

The best way to handle and emergency is with an experienced organization set up for the sole purpose of solving the problem. The *Well Control Emergency Response Team* was organized to handle dangerous & expensive well control problems. The *Team* is structured such that each individual can contribute the most from his area of expertise. Key decision-makers are determined prior to an emergency to avoid confusion about who is in charge.

If the well is flowing uncontrolled at the surface or subsurface, *The Emergency Response Team* will be mobilized. The *Team* is customized for the people currently on the Apache staff. Staff changes may require a change in the plan.

#### II. EMERGENCY PROCEDURE ON DRILLING OR COMPLETION OPERATIONS

**A.** In the event of an emergency the *Drilling Foreman or Tool-Pusher* will immediately contact only one of the following starting with the first name listed:

Name	Office	Mobile	Home
Danny Laman – Drlg Superintendent	432-818-1022	432-634-0288	432-520-3528
Bob Lange – Drilling Engineer	432-818-1114	432-661-6404	
Bobby Smith – Drilling Manager	432-818-1020	432-556-7701	
Jeff Burt – EH&S Coordinator		432-631-9081	

<sup>\*\*</sup>This one phone call will free the Drilling Foreman to devote his full time to securing the safety of personnel & equipment. This call will initiate the process to mobilize the Well Control Emergency Response Team. Apache maintains an Emergency Telephone Conference Room in the Houston office. This room is available for us by the Permian Region. The room has 50 separate telephone lines.


- **B.** The Apache employee contacted by the Drilling Foreman will begin contacting the rest of the *Team*. If **Danny Laman** is out of contact, **Bob Lange** will be notified.
- **C.** If a member of the *Emergency Response Team* is away from the job, he must be available for call back. Telephone numbers should be left with secretaries or a key decision-maker.
- **D.** Apache's reporting procedure for spills or releases of oil or hazardous materials will be implemented when spills or releases have occurred or are probable.

#### **EMERGENCY RESPONSE NUMBERS:**

SHERIFF DEPARTMENT	
Eddy County	575-887-7551
Lea County	575-396-3611
FIRE DEPARTMENT	911
Artesia	575-746-5050
Carlsbad	575-885-2111
Eunice	575-394-2111
Hobbs	575-397-9308
Jal	575-395-2221
Lovington	575-396-2359
HOSPITALS	911
Artesia Medical Emergency	575-746-5050
Carlsbad Medical Emergency	575-885-2111
Eunice Medical Emergency	575-394-2112
Hobbs Medical Emergency	575-397-9308
Jal Medical Emergency	575-395-2221
Lovington Medical Emergency	575-396-2359
AGENT NOTIFICATIONS	
Bureau of Land Management	575-393-3612
New Mexico Oil Conservation Division	575-393-6161

# INTERIM RECLAMATION LAYOUT LEE FEDERAL #56 EXHIBIT #6





### PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME: APACHE CORPORATION
LEASE NO.: NMLC029395B
WELL NAME & NO.: 56 LEE FEDERAL
SURFACE HOLE FOOTAGE: 2300' FSL & 450' FWL
BOTTOM HOLE FOOTAGE
LOCATION: Section 17, T.17 S., R.31 E., NMPM
COUNTY: Eddy County, New Mexico

#### TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

General Provisions
Permit Expiration
Archaeology, Paleontology, and Historical Sites
Noxious Weeds
Special Requirements
Pad Restriction
Lesser Prairie-Chicken Timing Stipulations
Ground-level Abandoned Well Marker
Construction
Notification
Topsoil
Closed Loop System
Federal Mineral Material Pits
Well Pads
Roads
☐ Road Section Diagram
<b>⊠</b> Drilling
H <sub>2</sub> S Requirements-Onshore Order #6
Logging Requirements
Waste Material and Fluids
<b>☐</b> Production (Post Drilling)
Well Structures & Facilities
Pipelines
Electric Lines
<b>Interim Reclamation</b>
<b>▼</b> Final Abandonment & Reclamation