

**RECEIVED**  
OCD Artesia 1/11/2013  
**NMOCD ARTESIA**

FORM APPROVED  
OMB No. 1004-0137  
Expires March 31, 2007

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**APPLICATION FOR PERMIT TO DRILL OR REENTER**

5. Lease Serial No. <b>NMNM-013814; UL F:NM-07752</b>	
6. If Indian, Allotee or Tribe Name N/A	
7. If Unit or CA Agreement, Name and No. N/A	
8. Lease Name and Well No. <b>Twelve-Pack Federal Com #3H</b>	
9. API Well No. <b>30-015- 40965</b>	
1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER	10. Field and Pool, or Exploratory <b>Loco Hills; Glorieta Yeso 96718</b>
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone	11. Sec., T. R. M. or Blk. and Survey or Area <b>Sec 6, T17S, R30E</b>
2. Name of Operator <b>COG Operating LLC</b>	12. County or Parish <b>Eddy</b>
3a. Address <b>One Concho Center 600 W Illinois Ave Midland, TX 79701</b>	13. State <b>NM</b>
3b. Phone No. (include area code) <b>(432) 685-4384</b>	14. Distance in miles and direction from nearest town or post office* <b>2.5 miles Northeast of Loco Hills, NM</b>
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface <b>1650' FNL &amp; 330' FWL, Lot 5</b> At proposed prod. zone <b>1650' FNL &amp; 330' FEL, Unit H</b>	15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) <b>330'</b>
16. No. of acres in lease <b>312.97; UL F: 1154.53</b>	17. Spacing Unit dedicated to this well <b>157.03</b>
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. <b>547'</b>	19. Proposed Depth <b>TVD: 5380' MD: 9768'</b>
20. BLM/BIA Bond No. on file <b>NMB000740; NMB000215</b>	21. Elevations (Show whether DF, KDB, RT, GL, etc.) <b>3689' GL</b>
22. Approximate date work will start* <b>11/30/2012</b>	23. Estimated duration <b>10 days</b>

**24. Attachments**

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- 1. Well plat certified by a registered surveyor.
- 2. A Drilling Plan.
- 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- 5. Operator certification
- 6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature 	Name (Printed/Typed) <b>Kelly J. Holly</b>	Date <b>09/05/2012</b>
---	---	---------------------------

Title **Permitting Tech**

Approved by (Signature) <b>/s/ James A. Amos</b>	Name (Printed/Typed)	Date <b>JAN 9 2013</b>
--	----------------------	------------------------

Title **FIELD MANAGER** Office **CARLSBAD FIELD OFFICE**

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

**APPROVAL FOR TWO YEARS**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on page 2)

**Roswell Controlled Water Basin**

**Approval Subject to General Requirements & Special Stipulations Attached**

**SEE ATTACHED FOR  
CONDITIONS OF APPROVAL**

DISTRICT I  
1625 N. French Dr., Hobbs, NM 88240  
Phone: (575) 393-6161 Fax: (575) 393-0720

DISTRICT II  
811 S. First St., Artesia, NM 88210  
Phone: (575) 748-1283 Fax: (575) 748-9720

DISTRICT III  
1000 Rio Brazos Road, Aztec, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170

DISTRICT IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources Department  
OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Santa Fe, New Mexico 87505

Form C-102  
Revised August 1, 2011  
Submit one copy to appropriate  
District Office

AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-015- <b>40965</b>	Pool Code 96718	Pool Name LOCO HILLS; GLORIETA-YESO
Property Code <b>39626</b>	Property Name TWELVE-PACK FEDERAL COM	Well Number 3H
OGRID No. 229137	Operator Name COG OPERATING, LLC	Elevation 3689'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
5	6	17-S	30-E		1650	NORTH	330	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
H	6	17-S	30-E		1650	NORTH	330	EAST	EDDY

Dedicated Acres 157.03	Joint or Infill	Consolidation Code	Order No.
---------------------------	-----------------	--------------------	-----------

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

GRID AZ. = 89°50'15"  
HORIZ. DIST. = 4523.0'

Producing Area  
Project Area

COORDINATE TYPE	POINT	N	E	
CORNER COORDINATES TABLE	A)	679281.9	596475.0	
	B)	679306.6	601655.3	
	C)	677961.7	596474.3	
	D)	677996.4	601659.9	
SURFACE LOCATION	Y	678953.5	X	596804.7
	LAT.	32.866129° N	LONG.	104.018056° W
BOTTOM HOLE LOCATION	Y	678966.3	X	601326.6

**OPERATOR CERTIFICATION**

I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

*Robyn M. Odom* 10/12/2012  
Signature Date  
Robyn M. Odom  
Printed Name  
Rodom@concho.com  
E-mail Address

**SURVEYOR CERTIFICATION**

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

JUNE 22, 2012  
Date of Survey

*Ronald J. Eidson*  
Signature & Seal of Professional Surveyor:  
RONALD J. EIDSON  
NEW MEXICO  
3239  
Professional Surveyor  
Certificate Number  
R. J. Eidson 12641  
R. J. Eidson 3239  
AF JWSC W.O.: 12.11.0839

*Surface Use Plan*  
*COG Operating, LLC*  
*Twelve-Pack Federal Com# 3H*  
*SL: 1650' FNL & 330' FWL UN 5*  
*BHL: 1650' FNL 330' FEL UL H*  
*Section 6, T-17-S, R-30-E*  
*Eddy County, New Mexico*

---

I hereby certify that I, or persons under my direct supervision, have inspected the drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or COG Operating, LLC, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 4th day of September, 2012.

Signed: Carl Bird

Printed Name: Carl Bird

Position: Drilling Engineer

Address: One Concho Center, 600 W. Illinois, Midland, Texas 79701

Telephone: (432) 683-7443

Field Representative (if not above signatory): Same

E-mail: cbird@concho.com

ATTACHMENT TO FORM 3160-3  
 COG Operating, LLC  
 TWELVE-PACK FEDERAL COM #3H  
 SHL: 1650' FNL & 330' FWL, LOT 5  
 BHL: 1650' FNL & 330' FEL, Unit H  
 Sec 6, T17S, R32E  
 Eddy County, NM

1. Proration Unit Spacing: 160 Acres
2. Ground Elevation: 3689'
3. Proposed Depths: Horizontal: **EOC (end of curve) TVD=5450' MD= 5731'**  
**Toe (end of lateral) TVD=5380' MD 9768'**
4. Estimated tops of geological markers:

Rustler	341'
Top of Salt	600'
Base of Salt	1000'
Yates	1176'
Seven Rivers	1453'
Queen	2054'
Grayburg	2459'
San Andres	2782'
Glorieta	4211'
Paddock	4273'
Blinebry	4674'
Tubb	5622'

5. Possible mineral bearing formations:

Water Sand	130'	Fresh Water
Grayburg	2459'	
San Andres	2782'	
Glorieta	4211'	
Paddock	4273'	
Blinebry	4674'	
Tubb	5622'	

No other formations are expected to give up oil, gas or fresh water in measurable quantities. Setting 13 3/8" casing to 366' (25' into Rustler) and circulating cement back to the surface will protect the surface fresh water sand. The Salt Section will be protected by setting 9 5/8" casing to 1180' and circulating cement back to surface in a single or multi-stage job and/or with an ECP. Any shallower zones above TD, which contain commercial quantities of oil and/or gas, will have cement circulated across them or be isolated by external casing packers. This will be achieved by cementing 7" casing from the KOP by single or multi-stage job using ECP & DV Tools as necessary. The 7" portion of the tapered 7" x 5 1/2" production casing will be cemented back to a minimum of 200' into the intermediate casing (although cement volume is actually calculated to surface). At the KOP the 7" casing will be tapered to 5 1/2" casing which will be run thru curve and lateral with external casing packers for zone isolation. If wellbore conditions arise that require immediate action and/or a change to this program, COG Operating LLC personnel will always react to protect the wellbore and/or environment.

*See COA*

*See COA*

**ATTACHMENT TO FORM 3160-3**  
**COG Operating, LLC**  
**TWELVE PACK FEDERAL COM #3H**  
Page 2 of 6

**6. Proposed Mud System**

The well will be drilled to TD with a combination of fresh water, brine, cut brine and polymer mud systems. The applicable depths and properties of these systems are as follows:

DEPTH (MD)	TYPE	WEIGHT	VISCOSITY	WATERLOSS
0-366'	Fresh Water	8.5	28	N.C.
366'-1180'	Brine	10	30	N.C.
1180'-4973'	Cut Brine	8.7-9.2	30	N.C.
4973'-5731'	Cut Brine/polymer mud	8.7-9.2	30	N.C.
5731'-9768'	Cut Brine/polymer mud	8.7-9.2	30	N.C.

Sufficient mud materials will be kept at the well site to maintain mud properties and meet minimum lost circulation and weight increase requirements at all times.

**6. Proposed Casing Program**

Hole Size	Interval MD	OD Casing	Weight	Grade	Condition	Jt.	brst/clps/ten
17 1/2"	0-366' <i>410</i>	13 3/8"	48#	H-40/J-55 Hybrid	New	ST&C	4.73/4.75/21.1
12 1/4"	366'-1180'	9 5/8"	40#	J/K-55	New	ST&C	3.35/4.18/12.97
8 3/4"	1180'-4973'	7"	26#	L-80	New	LT&C	1.45/2.27/4.60
8 3/4"	4973'-5731'	5 1/2"	17#	L-80	New	LT&C	1.55/2.64/4.65
7 7/8"	5731'-9768'	5 1/2"	17#	L-80	New	LT&C	1.55/2.64/4.65

Production string will be a tapered string with 7" 26# L-80 LTC run from surface to kick off point (4973') and then crossed over to 5 1/2" 17# L-80 LTC.

*see COA*

ATTACHMENT TO FORM 3160-3  
 COG Operating, LLC  
 TWELVE-PACKER FEDERAL COM #3H  
 Page 3 of 6

7. Proposed Cement Program *See COA*

**13 3/8" SURFACE:** (Circulate to Surface)

Lead: 0'-366'	425 sks	Class "C" w/2% CaCl2	1.32 cf/sk	14.8 ppg
Excess 94%				

**9 5/8" INTERMEDIATE:**

**Option #1: Single Stage (Circulate to Surface)**

Lead: 0'-850'	300 sks	50:50:10 C:Poz:Gel w/ 5% Salt+ 0.25% CF +5 pps LCM	2.45 cf/sk	11.8 ppg
Excess 153%				

Tail: 850'-1180'	200 sks	Class C w/2% CaCl2	1.32 cf/sk	14.8 ppg
Excess 159%				

**Option #2: Multi-stage w/ DV Tool @ +/-416' (DV Tool 50' below 13 3/8" csg. Shoe)  
 (Circulate to Surface)**

**Stage #1:**

Lead: 416'-880'	200 sks	50:50:10 C:Poz:Gel w/5%	2.45 cf/sk	11.8 ppg
Excess 238%				

Tail: 880'-1180'	200 sks	Class "C" w/2% CaCl2	1.32 cf/sk	14.8 ppg
Excess 144%				

**Stage #2**

Lead: 0'-416'	200 sks	50:50:10 C:Poz:Gel w/5% salt+ 0.25% CF	2.45 cf/sk	11.8 ppg
Excess 218%				

Note: Multi-stage tool to be set depending on hole conditions at approximately 416' (50' below the surface casing shoe). Cement volumes will be adjusted proportionately for depth changes of multi-stage tool.

**ATTACHMENT TO FORM 3160-3  
COG Operating, LLC  
TWELVE PACK FEDERAL #3H  
Page 4 of 6**

**7" X 5 1/2" TAPERED PRODUCTION CASING:**

Cement details for 7" portion of tapered casing string as follows:

**Option #1: Single Stage (Cement cal to Surface)  
DV Tool & ECP (external csg. Packer ) @ 4973' KOP:**

Lead: 980'-4400' (min. tie back 200' above 9 5/8" shoe) Excess 53.0%	500 sks	35:65:6 C:Poz Gel w/5% salt+ 5 pps LCM+ 0.2 % SMS+ 0.3% FL-52A+ 0.125 pps CF+1 % BA-58+ 1% FL-25	2.05 cf/sk	12.5 ppg
Tail: 4400'-4973' Excess 226%	250 sks	50:50:2 C:Poz Gel w/5% salt+ 3 pps LCM+ 0.6 % SMS+ 0.3% FL-52A+ 0.125 pps CF+1% FL-25+ 1% BA-58	1.37 cf/sk	14.0 ppg

**Option #2: Multi-stage (2 Stages) w/DV Tool & ECP@ +/-4973'**

**Stage #1:**

Lead: 1230'-4400' Excess 65.0%	500 sks	50:50:2 C:Poz Gel w/5% salt+ 3 pps LCM+ 0.6 % SMS+ 0.3% FL-52A+ 0.125 pps CF+1% FL-25+ 1% BA-58	1.37 cf/sk	14.0 ppg
Tail: 4400'-4973' Excess 65%	250 sks	Class "C" w/0.3% R-3+ 1.5% CD-32	1.02 cf/sk	16.8 ppg

Note: This densified cement recipe is used to control water flows if encountered.

**Stage #2:**

**2<sup>nd</sup> DV Tool @ 1230' (50' below 9 5/8" csg shoe) (Cement cal to Surface)**

Lead: 980'-1230' (min. tie back 200' above 9 5/8" shoe) Excess 41%	200 sks	50:50:2 C:Poz Gel w/5% salt+ 3 pps LCM+ 0.6 % SMS+ 0.3% FL-52A+ 0.125 pps CF+1% FL-25+ 1% BA-58	1.37 cf/sk	14.0 ppg
--	---------	---	------------	----------

**ATTACHMENT TO FORM 3160-3**  
**COG Operating, LLC**  
**TWELVE PACK FEDERAL #3H**  
Page 5 of 6

Note: 5 ½" casing will be run from KOP at 4973' thru curve and lateral to TD of 9768' MD. Productive intervals will be isolated by a Peak Packer system or similar.

Note: Assumption for 2nd DV tool is water flow. Cement volumes will be adjusted proportionately for depth changes of multi-stage tool.

Note: FL-52A is fluid loss additive, R-3 is retarder.

Note: Multi-stage tool to be set depending on hole conditions at approximately 1230'  
Cement volumes will be adjusted proportionately for depth changes of multi-stage tool.

8. Pressure Control Equipment:

The blowout preventer equipment (BOP) shown in Exhibit #9 will consist of a double ram-type (2000 psi WP) preventer, and in some cases possibly a 2000 psi Hydril type annular preventer as provided for in Onshore Order #2. This unit will be hydraulically operated and the ram type preventer will be equipped with blind rams on top and 4 1/2" drill pipe rams on the bottom. A 13-5/8" BOP will be used during the drilling of the well. A 13 5/8" permanent casing head will be installed on the 13 3/8" casing. The BOP will be nipped up on the 13 5/8" permanent casing head and tested to 2000 psig. After setting 9-5/8", permanent "B section" well head will be installed and the BOP will then be nipped up on the permanent B . BOP and well head will be tested by a third party to 2000 psig and used continuously until total depth is reached. Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve, choke lines and a choke manifold with a 2000 psi WP rating all of which will also be tested to working pressure by independent tester also.

9. Production Hole Drilling Summary:

**Drill 8 ¼" hole and kick off at +/- 4973', building curve over +/- 758' to horizontal at 5731' MD/5450'TVD. Drill 7 7/8" lateral section in a easterly direction for +/-4037' lateral to TD at +/-9768' MD, 5380' TVD. Run 7" x 5-1/2" production casing. 7" to be run from surface to kickoff point and then changed over to 5 ½" with DV Tool and ECP at kickoff point. 5 ½" casing will be run from kickoff point to td and isolation packers set throughout lateral. 7" to be cemented from kickoff point to surface.**

10. Auxiliary Well Control and Monitoring Equipment

- A. Kelly cock will be kept in the drill string at all times.
- B. A full opening drill pipe-stabbing valve with proper drill pipe connections will be on the rig floor at all times.

11. Logging, Testing and Coring Program: *See COA*

- A. The following logs will be run in the vertical portion of the hole to KOP: SLB-PEX/HRLA, HNGS.

**ATTACHMENT TO FORM 3160-3**  
**COG Operating, LLC**  
**TWELVE PACK FEDERAL #3H**  
Page 6 of 6

- B. The mud logging program will consist of lagged 10' samples from KOP to TD in Horizontal hole.
- C. Drill Stem test is not anticipated.
- D. No conventional coring is anticipated.
- E. Further testing procedures will be determined after the 7" x 5 1/2" production casing has been cemented at TD based on drill shows and log evaluation.

12. Abnormal Conditions, Pressures, Temperatures and Potential Hazards:

No abnormal pressures or temperatures are anticipated. The estimated bottom hole temperature at TD is 90° Fahrenheit and estimated maximum bottom hole pressure is 2398 psi. Wells in the Loco Hills area will penetrate formations that are known or could reasonably be expected to contain Hydrogen Sulfide. Measurable gas volumes or Hydrogen Sulfide levels have not been encountered during drilling operations in this area, However as per Onshore order No. 6 a H2S drilling operations plan is included with this APD. No major loss circulation zones have been reported in offsetting wells.

13. Anticipated Starting Date

Drilling operations will commence approximately on November 30, 2012 with drilling and completion operations lasting approximately 90 days.

# **COG Operating LLC**

**Eddy County, NM**

**Twelve-Pack Federal Com 3H**

**Twelve-Pack Federal Com 3H**

**Wellbore #1**

**Plan: Plan #1**

Surface: 1650' FNL, 330' FWL, Sec 6, T17S, R30E, Lot 5

BHL: 1650' FNL, 330' FEL, Sec 6, T17S, R30E, Unit H

## **Standard Planning Report**

**20 August, 2012**

Planning Report

<b>Database:</b>	Houston R5000 Database	<b>Local Co-ordinate Reference:</b>	Site Twelve-Pack Federal Com 3H
<b>Company:</b>	COG Operating LLC	<b>TVD Reference:</b>	WELL @ 3707.00ft (Original Well Elev)
<b>Project:</b>	Eddy County, NM	<b>MD Reference:</b>	WELL @ 3707.00ft (Original Well Elev)
<b>Site:</b>	Twelve-Pack Federal Com 3H	<b>North Reference:</b>	Grid
<b>Well:</b>	Twelve-Pack Federal Com 3H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Plan #1		

<b>Project</b>	Eddy County, NM		
<b>Map System:</b>	US State Plane 1927 (Exact solution)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	New Mexico East 3001		

<b>Site</b>	Twelve-Pack Federal Com 3H				
<b>Site Position:</b>		<b>Northing:</b>	678,953.50 ft	<b>Latitude:</b>	32.866125
<b>From:</b>	Map	<b>Easting:</b>	596,804.70 ft	<b>Longitude:</b>	-104.018060
<b>Position Uncertainty:</b>	0.00 ft	<b>Slot Radius:</b>	13.200 in	<b>Grid Convergence:</b>	0.17 °

<b>Well</b>	Twelve-Pack Federal Com 3H					
<b>Well Position</b>	<b>+N-S</b>	0.00 ft	<b>Northing:</b>	678,953.50 ft	<b>Latitude:</b>	32.866125
	<b>+E-W</b>	0.00 ft	<b>Easting:</b>	596,804.70 ft	<b>Longitude:</b>	-104.018060
<b>Position Uncertainty</b>		0.00 ft	<b>Wellhead Elevation:</b>		<b>Ground Level:</b>	3,689.00 ft

<b>Wellbore</b>	Wellbore #1				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination</b>	<b>Dip Angle</b>	<b>Field Strength</b>
	IGRF2010	7/20/2012	(°)	(°)	(nT)
			7.71	60.68	48,842

<b>Design</b>	Plan #1				
<b>Audit Notes:</b>					
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.00	
<b>Vertical Section:</b>	<b>Depth From (TVD)</b>	<b>+N-S</b>	<b>+E-W</b>	<b>Direction</b>	
	(ft)	(ft)	(ft)	(°)	
	0.00	0.00	0.00	89.84	

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N-S (ft)	+E-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,972.61	0.00	0.00	4,972.61	0.00	0.00	0.00	0.00	0.00	0.00	
5,730.94	91.00	89.84	5,450.00	1.38	485.80	12.00	12.00	0.00	89.84	
9,767.68	91.00	89.84	5,379.55	12.80	4,521.90	0.00	0.00	0.00	0.00	PBHL (Twelve-Pack F

Planning Report

Database: Houston R5000 Database  
 Company: COG Operating LLC  
 Project: Eddy County, NM  
 Site: Twelve-Pack Federal Com 3H  
 Well: Twelve-Pack Federal Com 3H  
 Wellbore: Wellbore #1  
 Design: Plan #1

Local Co-ordinate Reference: Site Twelve-Pack Federal Com 3H  
 TVD Reference: WELL @ 3707.00ft (Original Well Elev)  
 MD Reference: WELL @ 3707.00ft (Original Well Elev)  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,972.61	0.00	0.00	4,972.61	0.00	0.00	0.00	0.00	0.00	0.00
<b>KOP - Start Build @ 12.00°/100'</b>									
5,000.00	3.29	89.84	4,999.99	0.00	0.79	0.79	12.00	12.00	0.00
5,100.00	15.29	89.84	5,098.49	0.05	16.89	16.89	12.00	12.00	0.00
5,200.00	27.29	89.84	5,191.50	0.15	53.13	53.13	12.00	12.00	0.00
5,300.00	39.29	89.84	5,274.94	0.31	107.91	107.91	12.00	12.00	0.00
5,400.00	51.29	89.84	5,345.17	0.51	178.85	178.85	12.00	12.00	0.00
5,500.00	63.29	89.84	5,399.11	0.74	262.83	262.83	12.00	12.00	0.00
5,600.00	75.29	89.84	5,434.42	1.01	356.20	356.20	12.00	12.00	0.00
5,700.00	87.29	89.84	5,449.54	1.29	454.86	454.86	12.00	12.00	0.00
5,730.94	91.00	89.84	5,450.00	1.38	485.80	485.80	12.00	12.00	0.00
<b>Landing Point - Hold @ 91.00° INC; 89.84° AZ</b>									
5,800.00	91.00	89.84	5,448.80	1.57	554.84	554.85	0.00	0.00	0.00
5,900.00	91.00	89.84	5,447.05	1.85	654.83	654.83	0.00	0.00	0.00
6,000.00	91.00	89.84	5,445.31	2.14	754.81	754.81	0.00	0.00	0.00
6,100.00	91.00	89.84	5,443.56	2.42	854.80	854.80	0.00	0.00	0.00
6,200.00	91.00	89.84	5,441.81	2.70	954.78	954.78	0.00	0.00	0.00
6,300.00	91.00	89.84	5,440.07	2.99	1,054.76	1,054.77	0.00	0.00	0.00
6,400.00	91.00	89.84	5,438.32	3.27	1,154.75	1,154.75	0.00	0.00	0.00
6,500.00	91.00	89.84	5,436.58	3.55	1,254.73	1,254.74	0.00	0.00	0.00
6,600.00	91.00	89.84	5,434.83	3.83	1,354.72	1,354.72	0.00	0.00	0.00
6,700.00	91.00	89.84	5,433.09	4.12	1,454.70	1,454.71	0.00	0.00	0.00
6,800.00	91.00	89.84	5,431.34	4.40	1,554.69	1,554.69	0.00	0.00	0.00
6,900.00	91.00	89.84	5,429.60	4.68	1,654.67	1,654.68	0.00	0.00	0.00
7,000.00	91.00	89.84	5,427.85	4.97	1,754.66	1,754.66	0.00	0.00	0.00
7,100.00	91.00	89.84	5,426.11	5.25	1,854.64	1,854.65	0.00	0.00	0.00
7,200.00	91.00	89.84	5,424.36	5.53	1,954.62	1,954.63	0.00	0.00	0.00
7,300.00	91.00	89.84	5,422.62	5.82	2,054.61	2,054.62	0.00	0.00	0.00
7,400.00	91.00	89.84	5,420.87	6.10	2,154.59	2,154.60	0.00	0.00	0.00
7,500.00	91.00	89.84	5,419.13	6.38	2,254.58	2,254.59	0.00	0.00	0.00
7,600.00	91.00	89.84	5,417.38	6.66	2,354.56	2,354.57	0.00	0.00	0.00
7,700.00	91.00	89.84	5,415.64	6.95	2,454.55	2,454.56	0.00	0.00	0.00
7,800.00	91.00	89.84	5,413.89	7.23	2,554.53	2,554.54	0.00	0.00	0.00
7,900.00	91.00	89.84	5,412.15	7.51	2,654.51	2,654.53	0.00	0.00	0.00
8,000.00	91.00	89.84	5,410.40	7.80	2,754.50	2,754.51	0.00	0.00	0.00
8,100.00	91.00	89.84	5,408.66	8.08	2,854.48	2,854.50	0.00	0.00	0.00
8,200.00	91.00	89.84	5,406.91	8.36	2,954.47	2,954.48	0.00	0.00	0.00
8,300.00	91.00	89.84	5,405.16	8.65	3,054.45	3,054.46	0.00	0.00	0.00
8,400.00	91.00	89.84	5,403.42	8.93	3,154.44	3,154.45	0.00	0.00	0.00
8,500.00	91.00	89.84	5,401.67	9.21	3,254.42	3,254.43	0.00	0.00	0.00
8,600.00	91.00	89.84	5,399.93	9.50	3,354.41	3,354.42	0.00	0.00	0.00
8,700.00	91.00	89.84	5,398.18	9.78	3,454.39	3,454.40	0.00	0.00	0.00
8,800.00	91.00	89.84	5,396.44	10.06	3,554.37	3,554.39	0.00	0.00	0.00
8,900.00	91.00	89.84	5,394.69	10.34	3,654.36	3,654.37	0.00	0.00	0.00
9,000.00	91.00	89.84	5,392.95	10.63	3,754.34	3,754.36	0.00	0.00	0.00
9,100.00	91.00	89.84	5,391.20	10.91	3,854.33	3,854.34	0.00	0.00	0.00
9,200.00	91.00	89.84	5,389.46	11.19	3,954.31	3,954.33	0.00	0.00	0.00
9,300.00	91.00	89.84	5,387.71	11.48	4,054.30	4,054.31	0.00	0.00	0.00
9,400.00	91.00	89.84	5,385.97	11.76	4,154.28	4,154.30	0.00	0.00	0.00
9,500.00	91.00	89.84	5,384.22	12.04	4,254.26	4,254.28	0.00	0.00	0.00
9,600.00	91.00	89.84	5,382.48	12.33	4,354.25	4,354.27	0.00	0.00	0.00
9,700.00	91.00	89.84	5,380.73	12.61	4,454.23	4,454.25	0.00	0.00	0.00
9,767.68	91.00	89.84	5,379.55	12.80	4,521.90	4,521.92	0.00	0.00	0.00

Planning Report

Database: Houston R5000 Database  
 Company: COG Operating LLC  
 Project: Eddy County, NM  
 Site: Twelve-Pack Federal Com 3H  
 Well: Twelve-Pack Federal Com 3H  
 Wellbore #: Wellbore #1  
 Design: Plan #1

Local Co-ordinate Reference: Site Twelve-Pack Federal Com 3H  
 TVD Reference: WELL @ 3707.00ft (Original Well Elev)  
 MD Reference: WELL @ 3707.00ft (Original Well Elev)  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N-S (ft)	+E-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
TD @ 9767.68' MD, 5379.55' TVD - PBHL (Twelve-Pack Federal Com 3H Plan 1)									

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N-S (ft)	+E-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
PBHL (Twelve-Pack Fed - plan hits target center - Point	0.00	0.00	5,379.55	12.80	4,521.90	678,966.30	601,326.60	32,866122	-104.003333

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N-S (ft)	+E-W (ft)	
4,972.61	4,972.61	0.00	0.00	KOP - Start Build @ 12.00°/100'
5,730.94	5,450.00	1.38	485.80	Landing Point - Hold @ 91.00° INC, 89.84° AZ
9,767.68	5,379.55	12.80	4,521.90	TD @ 9767.68' MD, 5379.55' TVD





COG Operating LLC  
 Twelve-Pack Federal Com 3H  
 Eddy County, NM  
 Plan #1



Surface Location		Ground Elev: 3689.00' WELL @ 3707.00ft (Original Well Elev)			
+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	678953.50	596804.70	32.866125	-104.018060


TARGET DETAILS							
Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
PBHL (Twelve-Pack Federal Com 3H Plan 1)	5379.55	12.80	4521.90	678966.30	601326.60	32.866122	-104.003333

SECTION DETAILS										
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Annotation
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2	4972.61	0.00	0.00	4972.61	0.00	0.00	0.00	0.00	0.00	KOP - Start Build @ 12.00°/100'
3	5730.94	91.00	89.84	5450.00	1.38	485.80	12.00	89.84	485.80	Landing Point - Hold @ 91.00° INC, 89.84° AZ
4	9767.68	91.00	89.84	5379.55	12.80	4521.90	0.00	0.00	4521.92	TD @ 9767.68' MD, 5379.55' TVD



Azimuths to Grid North  
 True North: -0.17°  
 Magnetic North: 7.54°  
 Magnetic Field  
 Strength: 48841.5snT  
 Dip Angle: 60.68°  
 Date: 7/20/2012  
 Model: IGRF2010

13 5/8" 2K ANNULAR



FILL LINE

FLOW DIVERTER

13 5/8" 2000 psi  
ANNULAR

Specar Spool

Mid Cross


4-1/16" 2K VALVES

13 5/8" 3K "A" SECTION

# COG Operating LLC


## Exhibit #9

### BOPE and Choke Schematic



Minimum 4" Nominal choke and kill lines

Choke Manifold Requirement (2000 psi WP)  
No Annular Required



**NOTES REGARDING THE BLOWOUT PREVENTERS**

**Master Drilling Plan  
Eddy County, New Mexico**

1. Drilling nipple to be so constructed that it can be removed without use of a welder through rotary table opening, with minimum I.D. equal to preventer bore.
2. Wear ring to be properly installed in head.
3. Blow out preventer and all fittings must be in good condition, 2000 psi WP minimum.
4. All fittings to be flanged.
5. Safety valve must be available on rig floor at all times with proper connections, valve to be full 2000 psi WP minimum.
6. All choke and fill lines to be securely anchored especially ends of choke lines.
7. Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
8. Kelly cock on Kelly.
9. Extension wrenches and hands wheels to be properly installed.
10. Blow out preventer control to be located as close to driller's position as feasible.
11. Blow out preventer closing equipment to include minimum 40-gallon accumulator, two independent sources of pump power on each closing unit installation all API specifications.



## COG Operating LLC

### Hydrogen Sulfide Drilling Operation Plan

#### I. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H<sub>2</sub>S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H<sub>2</sub>S on metal components. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H<sub>2</sub>S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H<sub>2</sub>S zone (within 3 days or 500 feet) and weekly H<sub>2</sub>S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan. **The concentrations of H<sub>2</sub>S of wells in this area from surface to TD are low enough that a contingency plan is not required.**

---

## II. H2S SAFETY EQUIPMENT AND SYSTEMS

Note: All H2S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonable expected to contain H2S.

### 1. Well Control Equipment:

- A. Flare line.
- B. Choke manifold. - w/ remotely operated Choke
- C. Closed Loop Blow Down Tank
- D. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
- E. Auxiliary equipment may include if applicable: annular preventer & rotating head.

### 2. Protective equipment for essential personnel:

- A. SCBA (Self contained breathing apparatus) 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

### 3. H2S detection and monitoring equipment:

- A. Portable H2S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 PPM are reached.

### 4. Visual warning systems:

- A. Wind direction indicators as shown on well site diagram.
- B. Caution/Danger signs (Exhibit #7) shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.

### 5. Mud program:

- A. The mud program has been designed to minimize the volume of H2S circulated to surface. Proper mud weight, safe drilling practices, and the use of H2S scavengers will minimize hazards when penetrating H2S bearing zones.
-

**6. Metallurgy:**

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- B. All elastomers used for packing and seals shall be H2S trim.

**7. Communication:**

- A. Radio communications in company vehicles including cellular telephone and 2-way radio.
- B. Land line (telephone) communication at Office.

**8. Well testing:**

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safely and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H2S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

**EXHIBIT #7**

**WARNING**  
**YOU ARE ENTERING AN H<sub>2</sub>S**  
**AUTHORIZED PERSONNEL ONLY**

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED
- 2. HARD HATS REQUIRED
- 3. SMOKING IN DESIGNATED AREAS ONLY
- 4. BE WIND CONSCIOUS AT ALL TIMES
- 5. CHECK WITH COG OPERATING FOREMAN AT

**COG OPERATING LLC**  
**1-432-683-7443**  
**1-575-746-2010**


**EDDY COUNTY EMERGENCY NUMBERS**  
ARTESIA FIRE DEPT. 575-746-5050  
ARTESIA POLICE DEPT. 575-746-5000  
EDDY CO. SHERIFF DEPT. 575-746-9888


**LEA COUNTY EMERGENCY NUMBERS**  
HOBBS FIRE DEPT. 575-397-9308  
HOBBS POLICE DEPT. 575-397-9285  
LEA CO. SHERIFF DEPT. 575-396-1196

COG Operating LLC

Drilling Location - H2S Safety Equipment Diagram

# EXHIBIT 8- Twelve Pack 3H





## PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	COG OPERATING, LLC
LEASE NO.:	NM013814
WELL NAME & NO.:	3H-TWELVE-PACK FEDERAL COM
SURFACE HOLE FOOTAGE:	1650'/N. & 330'/W.
BOTTOM HOLE FOOTAGE:	1650'/N. & 330'/E.
LOCATION:	Section 6, T. 17 S., R. 30 E., NMPM
COUNTY:	Eddy County, New Mexico

### TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
  - Lesser Prairie-Chicken Timing Stipulations
  - Ground-level Abandoned Well Marker
  - Communitization Agreement
- Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- Road Section Diagram**
- Drilling**
  - H2S requirement
  - Logging requirement
  - Waste Material and Fluids
- Production (Post Drilling)**
  - Well Structures & Facilities
  - Pipelines
  - Electric Lines
- Interim Reclamation**
- Final Abandonment & Reclamation**