Form 3160 - 3 (March 2012)

HIGH CAVEKARST

FORM APPROVED OMB No. 1004-0137 Expires October 31, 2014

UNITED STATES H CAVEKARST DEPARTMENT OF THE	INTERIOR	SEP	IVED	5. Lease Serial No. SL:NMNM 06808;	BHL:NMLC 0	<b>9-9</b> 64827A
APPLICATION FOR PERMIT TO		R REENTER	7.4	6. If Indian; Allotee		
la. Type of work: DRILL REENTI	ER			7. If Unit or CA Agre James Ranch Unit	,	d No.
lb. Type of Well: Oil Well Gas Well Other	<b>✓</b> s	ingle Zone Multip	ole Zone	8. Lease Name and V James Ranch Unit		= 400
2. Name of Operator BOPCO, L.P.		42/01	0237>	9, API Well No.	-426	29
3a. Address P.O. Box 2760 Midland, TX 79702	3b. Phone N 432-683-2	0. (include area code) 2277 . <b>U</b>	PLOCAT	10. Field and Pool, or I Undesignated; Bon	e Spring	16; R.
4. Location of Well (Report location clearly and in accordance with ar	ry State require	ments.*)		11. Sec., T. R. M. or B	lk. and Survey o	r Area
At surface SWNE, ULG, 1434' FNL & 1495' FEL, Lat:N3	•		405	Sec 21, T22S-R30I	Ξ	·
At proposed prod. zone 660' FSL,330'FEL,Sec23,T22S-R3  14. Distance in miles and direction from nearest town or post office*  12 miles northeast of Loving, NM	UE,Latin32	3720,Long.w103.8	435	12. County or Parish Eddy County	13. S NM	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)	16. No. of 2.600.86	acres in lease	17. Spacin 440 acre	g Unit dedicated to this v s	vell	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.		19. Proposed Depth 20. BLM/ 22,142 MD / 9,396 TVD COB 00		/BIA Bond No. on file 00050		
21. Elevations (Show whether DF, KDB, 'RT, GL, etc.) 3165' GL	22 Approx 12/25/20	timate date work will sta	rt*	23. Estimated duration 45 days	n	
	24. Atta	nchments	1			
The following, completed in accordance with the requirements of Onsho	re Oil and Gas	s Order No.1, must be at	tached to thi	s form:		
<ol> <li>Well plat certified by a registered surveyor.</li> <li>A Drilling Plan.</li> <li>A Surface Use Plan (if the location is on National Forest System SUPO must be filed with the appropriate Forest Service Office).</li> </ol>	Lands, the	Item 20 above).  5. Operator certific	ation	ns unless covered by an	, -	·
25. Signifure & Brefer		e (Printed/Typed) tney McKee		-	Date 1/21	114
Title Engineering Assistant	ı				· · · /	· · · · · · · · · · · · · · · · · · ·
Approved by (Signate George MacDone):	Nam	e (Printed/Typed)			SEP _	2 2014
Title FIELD MANAGER	Offic	CARLSBAD FIE				
Application approval does not warrant or certify that the applicant hold conduct operations thereon.  Conditions of approval, if any, are attached.	s legal or equ	nitable title to those righ		ject lease which would e	• •	
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a ci	rime for any	person knowingly and v				

(Continued on page 2)

\*(Instructions on page 2)

Carlsbad Controlled Water Basin

Approval Subject to General Requirements & Special Stipulations Attached

SEE ATTACHED FOR CONDITIONS OF APPROVAL Ť

State of New Mexico Energy, Minerals and Natural Resources Department

Form C-102 Revised August 1, 2011

Submit one copy to appropriate District Office

#### DISTRICT III 1000 Rio Brazos Rd., Aztec, NM 87410 Phone (505) 334-6178 Fax: (505) 334-6170

#### DISTRICT IV 1220 S. St. Francis Dr., Santa Fe, NM 67505 Phone (505) 476-3460 Fax: (505) 476-3462

### OIL CONSERVATION DIVISION

1220 South St. Francis Dr. Santa Fe, New Mexico 87505


WELL LOCATION AND ACREAGE DEDICATION PLAT

□ AMENDED REPORT

30-01	Number / 2	262'	9	7905	$\omega$	ILDCA	T 6-07	SZZESEP DESIGNATED	,2/6 <del>), BO</del>	, はら NE SPRIN	G
Property (		0211	<u>-</u>		Property	Name	* ,			Well Number	
- <del>36040</del>	7 4	0211		JAM	ES RANCI	TINU H	- DI1			16	4H
OGRID No	). <u>,</u>				Operator	Name				Eleva	
260737	7 .				BOPCO,	L.P.				316	5'
_	Surface Location										
UL or lot No.	Section	Township	Range	Lot Idn	Feet from t	he Noi	rth/South line	Feet from th	ne Eas	st/West line	County
G	21	22 S	30 E		1434	-	NORTH	1495		EAST	EDDY
			Bottom	Hole Lo	cation If D	ifferen	t From Su	ırface	-		
UL or lot No.	Section	Township	Range	Lot Idn	Feet from t	he Noi	rth/South line	Feet from th	e Eas	st/West line	County
P	23	22 S	30 E		660		SOUTH	330		EAST	EDDY
Dedicated Acres	Joint o	r Infill C	onsolidation (	Code Or	der No.	•		•			•
400							•				

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED

OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



### OPERATOR'S CERTIFICATION

APPLICATION FOR PERMIT TO DRILL JAMES RANCH UNIT DI1 164H 1434' FNL, 1495' FEL, Section 21, T22S, R30E, Eddy County, NM.

In reference to the above captioned well, I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in the APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filling of false statements.

Executed this  $22^{nd}$  day of  $40^{nd}$ ,  $20^{nd}$ .

If you have any questions regarding the accuracy of the plan provided herein, please do not hesitate to contact me at (432) 683-2277.

Courtney Lockhart Regulatory Analyst SECTION 21, TOWNSHIP 22 SOUTH, RANGE 30 EAST, N.M.P.M., NEW MEXICO. EDDY COUNTY,

> ELEV. - 3165' Lat - N 32\*22'51.16" Long - W 103'52'55.01" NMSPCE- N 502572.0 E 639345.9 (NAD-27) DRILLING ISLAND 1 2728293031 32 33 0 0 0 0 0 0 0 0 12345 0000000 343536**37**383940 41 42 43 44 45 OOOOO OOOOO 46 47 48 49 50 ⊙ SWD 11 12 13 14 15 16 17 18 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 19 2021 2223242526 WELL WATER:

> > SLOT 37 = JAMES RANCH UNIT DIL 164H

LOVING, NM IS ±14 MILES TO THE SOUTHWEST OF LOCATION.

BOPCO, L.P. JAMES RANCH UNIT DII 164H

200 0 200 400 FEET SCALE: 1" = 200

#### Directions to Location:

FROM THE JUNCTION OF HWY 128 AND CIMARRON, GO NORTH ON CIMARRON FOR APPROX. 6.2 MILES TO LEASE ROAD, ON LEASE ROAD GO SOUTHWESTERLY 0.2 MILES TURNING NORTHWESTERLY 1.3 MILES TO PROPOSED WELL LOCATION.




P.O. Box 1786 (575) 393-7316 - Office 1120 N. West County Rd. (575) 392-2206 - Fax Hobbs, New Mexico 88241 basinsurveys.com

JAMES RANCH UNIT DI1 164H / WELL PAD TOPO REF:

THE JAMES RANCH UNIT DI1 164H LOCATED 1434' FROM THE NORTH LINE AND 1495' FROM THE EAST LINE OF SECTION 21, TOWNSHIP 22 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

DI1 WEL: PLAWS By: J. SMALL Date: 10-16-2013 Survey Date: 10-17-2013 Sheet 1 of 1 Sheets W.O. Number:




# JAMES RANCH UNIT DI1 164H Located 1434' FNL and 1495 FEL Section 21, Township 22 South, Range 30 East, N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393—7316 — Office (575) 392—2206 — Fax basinsurveys.com

	0 1 MI 2 MI 3 MI 4 MI	
***	SCALE: 1" = 2 MILES	4
1	W.O. Number: JMS DI1 WELL PLATS	1
1	Survey Date: 10-17-2013	ď,
-	YELLOW TINT - USA LAND	
	BLUE TINT — STATE LAND NATURAL COLOR — FEE LAND	1






# JAMES RANCH UNIT DI1 164H Located 1434' FNL and 1495 FEL Section 21, Township 22 South, Range 30 East, N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393-7316 - Office (575) 392-2206 - Fax basinsurveys.com

١	0' 1000' 2000' 3000' 4000'	
	SCALE: 1" = 2000'	
Amount my	W.O. Number: JMS DI1 WELL PLATS	Section Name
	Survey Date: 10-17-2013	
	YELLOW TINT - USA LAND	
	BLUE TINT — STATE LAND NATURAL COLOR — FEE LAND	

BOPCO, L.P. 💝




### JAMES RANCH UNIT DI1 164H BOTTOM


Located 660' FSL and 330' FEL Section 23, Township 22 South, Range 30 East, N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393-7316 — Office (575) 392-2206 — Fax basinsurveys.com

7	0' 1000' 2000' 3000' 4000'	
	SCALE: 1" = 2000'	
	W.O. Number: JMS DI1 WELL PLATS	
	Survey Date: 10-17-2013	•
	YELLOW TINT - USA LAND	
	BLUE TINT — STATE LAND NATURAL COLOR — FEE LAND	






JAMES RANCH UNIT DI1 164H
Located 1434' FNL and 1495 FEL
Section 21, Township 22 South, Range 30 East,
N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393—7316 — Office (575) 392—2206 — Fax basinsurveys.com

٦	0' 1000' 2000' 3000' 4000'	
	SCALE: 1" = 2000'	
Andrew Spinger	W.O. Number: JMS DI1 WELL PLATS	
	Survey Date: 10-17-2013	
	YELLOW TINT - USA LAND	
ᆀ	BLUE TINT — STATE LAND NATURAL COLOR — FEE LAND	





### JAMES RANCH UNIT DI1 164H BOTTOM

Located 660' FSL and 330' FEL Section 23, Township 22 South, Range 30 East, N.M.P.M., Eddy County, New Mexico.




P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393-7316 — Office (575) 392-2206 — Fax basinsurveys.com

1	0' 1000' 2000' 3000' 4000'	
	SCALE: 1" = 2000"	
-	W.O. Number: JMS DI1 WELL PLATS	
-	Survey Date: 10-17-2013	
	YELLOW TINT - USA LAND	
	BLUE TINT — STATE LAND NATURAL COLOR — FEE LAND	



### Flowline Route Diagram 4



### Access Road Diagram



### EIGHT POINT DRILLING PROGRAM BOPCO, L.P.

### NAME OF WELL: James Ranch Unit DI 1 #164H

LEGAL DESCRIPTION - SURFACE: 1434' FNL, 1495' FEL, Section 21, T22S, R30E, Eddy County, NM.

BHL: 660' FSL, 330' FEL, Section 23, T22S, R30E, Eddy County, New Mexico.

The surface hole location is nonstandard and in the James Ranch Unit.

POINT 1: ESTIMATED FORMATION TOPS (See No. 2 Below)

### POINT 2: WATER, OIL, GAS AND/OR MINERAL BEARING FORMATIONS

Anticipated Formation Tops: KB 3191' (estimated)

GL 3165'

Formation Description	Est from	Est (MD)	SUB-SEATOP	BEARING
	KB (TVD)	A ROLL POT A TOTAL		
Fresh Water	130'	130'	+ 3,061'	Fresh water
Rustler	191	191;	+ 3,000'	Barren
Salado	556'	556'	+ 2,635'	Barren
Lamar	3,536'	3,541'	- 345'	Barren
Ramsey	3,581'	3,587'	- 390'	Oil/Gas
Cherry Canyon	4,459'	4,468'	- 1,268'	Oil/Gas
Brushy Canyon	5,7.84'	5,798'	- 2,593'	Oil/Gas
Bone Spring Lime	7,384'	7,404'	- 4,193'	Oil/Gas
1 <sup>st</sup> Bone Spring	8,388'	8,412'	- 5,197'	Oil/Gas
KOP	8,468'	8,493'	- 5,277'	Oil/Gas
2 <sup>nd</sup> Bone Spring Sand	9,123'	9,252'	- 5,932'	Oil/Gas
2 <sup>nd</sup> Bone Spring Sand Target	9,376'	10,109'	- 6,185'	Oil/Gas
TD Horizontal	9,396'	22,142'	- 6,205'	Oil/Gas

### **POINT 3: CASING PROGRAM**

I OINT 5. OADING I ROCKAII				
TYPE	INTERVALME	HOLE SIZE	PURPOSE	INSTALLATION TYPE
20"	0' – 120'	30"	Conductor	Contractor Discretion
13-3/8", 48 ppf, H-40 ST&C*	0' – 535'	17-1/2"	Surface	New
9-5/8" 40 ppf, J-55, 8rd, LT&C*	0' – 3,566'	12-1/4"	Intermediate	New
7", 26 ppf, HCP-110 <b>B</b> てC	0' – 9,944'	8-3/4"	Production	New

Completion System				
4-1/2", 11.6 ppf, HCP-110 8rd LT&C,	9,894' 22,142'	6-1/8"	Completion System	New
BRC				

<sup>\*</sup> Depending on availability.

#### CASING DESIGN SAFETY FACTORS:

TYPE TYPE	NSION 🐆	COLLAPSE	BURST
13-3/8", 48 ppf, H-40, 8rd, ST&C*	14.59	2.82	1.13
9-5/8", 40 ppf, J-55, 8rd, LT&C*	5.23	1.25	1.99
7", 26 ppf, N-80*	3.30	1.21	1.90

Completion System		TEMPS FOR	
4-1/2", 11.6 ppf, HCP-110 8rd. LT&C	2.98	1.59	2.04

<sup>\*</sup> Depending on availability.

### **DESIGN CRITERIA AND CASING LOADING ASSUMPTIONS:**

### SURFACE CASING - (13-3/8")

A 1.6 design factor utilizing the effects of buoyancy (9.2 ppg). Tension

A 1.0 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the Collapse

casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

A 1.3 design factor with a surface pressure equal to the fracture gradient at setting depth less a gas Burst gradient to the surface. Internal burst force at the shoe will be fracture pressure a that depth. Backup pressure will be formation pore pressure. In all cases a conservative fracture pressure will be used such that it represents the upper limit of potential fracture resistance up to a 1.0 psi/ft gradient. The effects of

tension on burst will not be utilized.

### PROTECTIVE CASING - (9-5/8")

Tension A 1.6 design factor utilizing the effects of buoyancy (10.2 ppg).

A 1.125 design factor with full internal evacuation and a collapse force equal to the mud gradient in which Collapse the casing will be run (0.52 psi/ft). The effects of axial load on collapse will be considered.

In the case of development drilling, collapse design should be analyzed using internal evacuation equal to 1/3 the proposed total depth of the well. This criterion will be used when there is absolutely no potential of

the protective string being used as a production casing string.

Burst A 1.0 surface design factor and a 1.3 downhole design factor with a surface pressure equivalent to the fracture gradient at setting depth less a gas gradient to the surface. Internal burst force at the shoe will be fracture pressure at that depth. Back pressure will be formation pore pressure. In all cases a conservative

fracture pressure will be used such that it represents the upper limit of potential fracture resistance up to a

1.0 psi/ft gradient.

### Production CASING - (7")

Tension A 1.6 design factor utilizing the effects of buoyancy (9.0 ppg).

A 1.125 design factor with full internal evacuation and a collapse force equal to the mud gradient in which Collapse

the casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

Burst A 1.25 design factor with anticipated maximum tubing pressure (5000 psig) on top of the maximum anticipated packer fluid gradient. (0.433 psi/ft) Backup on production strings will be formation pore

pressure. (0.433 psi/ft) The effects of tension on burst will not be utilized.

### Completion System - (4-1/2")

Tension

A 1.6 design factor utilizing the effects of buoyancy (9.2 ppg).

Collapse

A 1.125 design factor with full internal evacuation and a collapse force equal to the mud gradient in which

the casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

Burst

A 1.25 design factor with anticipated maximum tubing pressure (5000 psig) on top of the maximum anticipated packer fluid gradient. (0.433 psi/ft) Backup on production strings will be formation pore pressure. (0.433 psi/ft) The effects of tension on burst will not be utilized.

### POINT 4: PRESSURE CONTROL EQUIPMENT (SEE ATTACHED DIAGRAMS A, B, C or Z)

See COA

After running the 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed on the Cameron Multi-Bowl System (MBS) wellhead. The BOP/BOPE will be pressure tested to 250 psi low and 3,000 psi high after installation on the surface casing which will cover testing requirements for the duration of the well as per Onshore Order #2. The 9-5/8" intermediate casing and 7" production casing will be run with a mandrel hanger through the 13-5/8" BOP/BOPE system without breaking any connections on the BOP/BOPE system and thus not requiring a pressure test. Please find attached wellhead schematic. The field reports from the Cameron representative and the BOP test information will be provided in a subsequent report.

These tests will be performed:

- a) Upon installation
- b) After any component changes
- c) Thirty days after a previous test
- d) As required by well conditions
- e) Any time a seal is broken within a system

A function test to insure that the preventers are operating correctly will be performed on each trip  $\exists ee \ CSA$ 

BOPCO, L.P. would like to request a variance to use an armored, 3", 5000 psi WP flex hose for the choke line in the drilling of the well if the rig is equip with hose. (See specification for hose that might be used, attached with APD exhibits). This is rig equipment and will help quicken nipple up time thus saving money without a safety problem. The hose itself is rated to 5000 psi, and has 5000 psi flanges on each end. This well is to be drilled to 9,396' TVD and max surface pressure should be +/- 2427 psi as prescribed in onshore order #2 shown as max BHP minus 0.22 psi/ft. Thus, 3000 psi BOPE is all that is needed for this well. Please refer to diagrams A, B, or C for choke manifold and closed loop system layout. If an armored flex hose is utilized, the company man will have all of the proper certified paper work for that hose available on location.

### POINT 5: MUD PROGRAM

DEPTH DEPTH	MUD TYPE	WEIGHT	. FV	PV	Ϋ́Р	FL	PH
0 -535'	FW Spud Mud	8.5 – 9.2	38-70	NC	NC	NC	10.0
535' - 3,566'	Brine Water	9.8 – 10.2	28-30	NC	NC	NC	9.5 – 10.5
3,566'-9,944'	FW/Gel	8.7 – 9.0	28-36	NC	NC	NC	9.5 – 10.0
9,944'-22,142'	Oil Based Mud	8.7 – 9.2	36-55	16-30	16-30	14-26	NA

NOTE: May increase vis for logging purposes only.

#### MUD MONITORING SYSTEM

- 1. BOPCO L.P. plans to drill the proposed well with water and does not expect to mud up. In the event of abnormal pressures that require mudding up, BOPCO L.P will record slow pump rates on the daily drilling report on a daily basis.
- 2. Visual mud monitoring equipment will be installed to detect volume changes.
- 3. Pit volume totalizers are installed on rig before spud.
- 4. BOPCO L.P. has the drilling mud checked every 24 hrs., and the daily mud check will be posted in the company man's trailer.
- 5. BOPCO L.P will be using a 3M system so trip tanks will not be required per Onshore Order #2.
- 6. Gas detections systems will be installed on exploratory wells per Onshore Order #2. Please refer to section G under point 6 in the 8pt drilling program for H2S safety information.

BOPCO, L.P. will have auxiliary equipment in place and a 24 hour mud engineer during the drilling in the lateral to minimize the risk of an OBM spill.

Sufficient mud materials will be kept at the well site to maintain mud properties and meet minimum lost circulation and weight increase requirements at all times (sack or bulk barite will not be on location until 500' above the top of the Wolfcamp.)

### POINT 6: TECHNICAL STAGES OF OPERATION

A) TESTING None anticipated.

### B) LOGGING

Run #1: GR with MWD during drilling of build and horizontal portions of 8-3/4" and 6-1/8" hole.

Run #2: Shuttle log w/GR, PE, Density, Neutron, Resistivity in lateral leg open hole are possible.

Mud Logger: Rigged up at 100'

### C) CONVENTIONAL CORING

None anticipated

### D) CEMENT

INTERVAL	AMOUNT SXS	Control of the second second	TYPE	GALS/SX	PPG	*:FT.*SX
SURFACE: Lead: 0' – 235'	190	235	Class C +2% CACL + 4% Bentonite + 0.25 LB/SK Cello Flake + 3 lb/sk LCM-1	8.69	13.50	1.75
Tail: 235' – 535'	340	300	Class C + 2% CACL + 0.25 LB/SK CF	6.35	14.80	1.35
INTERMEDIATE:			0.25LB/SK Cello Flake + 3 lb/sk LCM-1			
Lead: 0' - 3,066'.	680	3066	EconoCEM HLC + 5% CaCl + 5#/sk Gilsonite	9.32	12.90	1.85
Tail: 3,066' – 3,566'	190	500	HalCem C	6.34	14.80	1.33
Production						
Stage 1: Lead: 5,000' – 8,493'	300	3493	Tuned Light + 0.125 pps Poly-E- Flake	14.87	11.0	2.64
Tail: 8,493' – 9,944'	180	1451	Class "H" + 0.5% Halad-344 + 0.25% CFR-3 + 0.5% Econolite	11.41	12.00	2.03
DV Tool @ 5,000' Stage 2:					·	
Lead: 0' – 5,000'	410	5000	Tuned Light + 0.125 pps Poly-E- Flake	11.70	11.0	2.35

Cement excesses will be as follows:

Surface – 100% excess with cement circulated to surface.

1<sup>st</sup> Intermediate – 30% excess above fluid caliper with cement circulated to surface.

Production – 50% above gauge hole or 35% above electric log caliper with cement circulated 500' up into the 9-5/8" 1<sup>st</sup> intermediate casing in areas outside the SOPA. Cement will be circulated to surface on areas inside the SOPA. Cement volumes will be adjusted proportionately for depth changes of the multi stage tool.

### E) COMPLETION SYSTEM

A 4-1/2" completion system with open hole packers will be run in the producing lateral to a depth of 22,142'. The top of the completion system will be set at approximately 9,894', 50' inside the 7" casing. Cement will not be required for the 4-1/2" completion system

### F) DIRECTIONAL DRILLING

BOPCO, L.P. plans to drill out the 9-5/8" intermediate casing with a 8-3/4" bit to a TVD of approximately 8,493' MD, at which point a directional hole will be kicked off and drilled at an azimuth of 150.00 degrees, building angle at 6.00 deg/100' to 80 degrees at a TVD of approximately 9,326' (MD 9,744'). This angle will be held to a depth of approximately 9,944' MD (9,361' TVD). At this depth 7", 26#, HCP-110 casing will be installed and cemented in two stages (DV Tool @ approximately 5000') with cement circulated to surface. A 6-1/8" open hole lateral will then be drilled out from 7" casing at an azimuth of 160 degrees, building inclination to 89.90 degrees and azimuth to 90.05, at a measured depth of approximately 10,789', TVD 9,377'. This angle and azimuth will be maintained to a MD of 22,142'. At this depth a 4-1/2" Completion System with packers installed for zone isolation will be run into the producing lateral.

### G) H2S SAFETY EQUIPMENT



H2S monitors shall be installed prior to drilling out the surface shoe. If H2S is encountered in quantities greater than 10 PPM, the well will be shut in and H2S equipment will be installed, including a flare line that will be extended pursuant to Onshore Oil and Gas Order #6. (Please refer to diagram A, B, or C for choke manifold and closed loop system layout when H2S is present) Please refer to H2S location diagram for location of important H2S safety items.

### H) CLOSED LOOP AND CHOKE MANIFLOLD

Please see diagram A, B, C or Z depending on configuration.

### POINT 7: ANTICIPATED RESERVOIR CONDITIONS

Normal pressures are anticipated throughout the Delaware section. A BHP of 4733 psi (max) or MWE of 9.2 ppg is expected. Lost circulation may exist in the Delaware section from 3,581'- 9,894' TVD.

### **POINT 8: OTHER PERTINENT INFORMATION**

A) Auxiliary Equipment

Upper and lower kelly cocks. Full opening stab in valve on the rig floor.

B) Anticipated Starting Date

Upon approval

30 days drilling operations

14 days completion operations




### BOPCO, L.P. Slot: JRU DI1 No.164H

Location: Eddy County, NM Field: JRU NAD27 Facility: JRU Drilling Island 1

Well: No.164H Wellbore: No.164H PWB





True vertical depths are referenced to Rig on No. 184H SML (KB)	Grid System: NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet
Measured depths are referenced to Rig on No. 154H SHL (KB)	North Reference; Grid north
Rig on No. 164H SHL (KB) to Mean Sea Level: 3191 feet	Scale: True distance
Mean Sea Level to Mud line (At Slot: JRU DR No.164H ): 0 feet	Depths are in feet
Coordinates are in feet referenced to Slot	Created by: gentbry on 3/11/2014



			W	ell Profi	le Data			
Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	26.00	0.000	150.000	26.00	0.00	0.00	0.00	0.00
Nudge	1800.00	0.000	150.000	1800.00	0.00	0.00	0.00	0.00
EOB	2050.00	5.000	150.000	2049.68	-9.44	5.45	2.00	7.70
Est KOP	8493.20	5.000	150,000	8468.36	-495.77	286.23	0.00	404.16
80° Curve	9744.49	80.000	160.000	9326.76	-1230.19	565.36	6.00	862.87
200' Tangent	9944.49	80.000	160.000	9361.49	-1415.28	632.72	0.00	975.59
EOC	10109.63	89.904	160.000	9376.00	-1569.67	688.92	6.00	1069.61
Hold	10789.63	89.904	160.000	9377.14	-2208.66	921.49	0.00	1458.78
TL	12538.19	89.907	90.058	9380.44	-3151.14	2266.05	4.00	3000.58
No.164H PBHL	22142.49	89.907	.90.058	9396.00	-3160.82	11870.34	0.00	12283.96

i											/[X			200' Tangent	9944.49	80.000	160.000	9361.49	-1415.28	632.72	0.00	975.59	
1 ~								BGGM (1945.0 to 2015.0) Dip: 60.20° Field: 48382.2 nT						EOC			160.000		-1569.67	688.92	6.00	1069.61	
8	1	i							Magnetic	North is 7.52 degree:	s East of True Nor	th (at 3/11/2014)		Hold			160.000		2208.66	921.49	0.00	1458.78	- 1
º 82	50 -	1						Grid North is 0.24 degrees East of True North To correct azimuth from True to Grid subtract 0.24 degrees						TL					-3151.14	2266.05	4.00	3000.58	- 1
Depth (ft) Scale 1 inch = 1500	- 1	1 FAKOB . F	000 1 0400	004 145 0400	0004 77/17	04 409 110			To con	ect azimuth from Ma	gnetic to Grid add	7.28 degrees		No.164H PBHL	22142.49	89.907	.90.058	9396.00	-3160.82	11870.34	0.00	12283.96	
۽ ڇ		+ Est KOP : 5	.00° inc, 8493	1.20π MD, 8468	3.36ft IVD, 4	04.16ft VS																	
<u>5</u> .5		6.00°/100																					
စ္ဖ				no 0744 40ft h	MD none zer	+T\/D 062.076	+ \/C											N - 10	411.00111				
I <sup>∟∟</sup> 90	∞⊢	\ 80° Curve : 80.00° Inc, 9744.49ft MD, 9326.76ft TVD, 862.87ft VS No.164H PBHL \ 200' Tangent : 80.00° Inc, 9944.49ft MD, 9361.49ft TVD, 975.59ft VS																					
ातु र	~ I			.00° inc, 9944.	.4911 IVID, 936	1.4911 1 VD, 97	5.59π ۷5														•		
I⊭		<u> </u>	5.00°/100ft																				
<u> </u>		++	<del></del>		<del></del>						— — <b>—</b> -												
>		E	OC : 89.90° Inc	c, 10109.63ft N	AD. 9376 00f	TVD 1069 61	ft VS							N- 40		00.040			D 0000 00	T. (D. 40)	200 004 1/0		
_ 0 07	50	-		.90° Inc, 10789										NO.16	4H PBHL	89,91	inc, 221	42.49ft N	ID, 9396.00	OTT I VID, 122	283.96ft VS		
≥ "/	∾r		1 1014 . 00	.00 1110, 10100																			
<b> </b> -	- 1				IL:89.	91° inc, 12538.	19ft MD, 938	0.44ft IVD,	3000.58ft VS	•													
,	-	1	1	1 .		1.			- 1		1		1	ı					ı				
		750	1500	2250	3000	3750	4500	5250	6000	8750	7500	8250	9000	9750	10500	١.	11250	120	200	-			
		. 50	.550		5555	0.50	-500	5250	Vertical S	<b>6750</b> Section (ft)	, 200	0200	3000	3750		•	. 200						
										` ,								Scal	e 1 inch = 1500	ħ.			
								Azimuth	104.91° with re	eterence 0.00 N	1, 0.00 E											Rev-A	4.0 I
L					1 40-	<u> </u>								Α,			,						



## Planned Wellpath Report Rev-A.0 Page 1 of 7



सम्बद्धाः	ENCE WELLPATH IDENTIFICATION		
Operator	BOPCO, L.P.	Slot	JRU DI1 No.164H
Area	Eddy County, NM	Well	No.164H
Field	JRU NAD27	Wellbore	No.164H PWB
Facility	JRU Drilling Island 1		

REPORTSETUE	PINFORMATION	Marie Company of the	
Projection System	NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet	Software System	WellArchitect® 4.0.1
North Reference	Grid	User	Gentbry
Scale	0.999931	Report Generated	3/11/2014 at 3:19:40 PM
Convergence at slot	0.24° East	Database/Source file	MidlandDB/No.164H_PWB.xml

WELLPATH LOCATION										
	Local coordinates		Grid co	ordinates	Geographic coordinates					
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude				
Slot Location	16.90	325.84	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W				
Facility Reference Pt			639020.08	502555.10	32°22'51.004"N	103°52'58.816"W				
Field Reference Pt			652495.44	494904.92	32°21'34.711"N	103°50'22.090"W				

WELLPATH DATUM			
Calculation method	Minimum curvature	Rig on No.164H SHL (KB) to Facility Vertical Datum	3191.00ft
Horizontal Reference Pt	Slot	Rig on No.164H SHL (KB) to Mean Sea Level	3191.00ft
Vertical Reference Pt	Rig on No.164H SHL (KB)	Rig on No.164H SHL (KB) to Mud Line at Slot (JRU DI1 No.164H)	3191.00ft
MD Reference Pt	Rig on No.164H SHL (KB)	Section Origin	N 0.00, E 0.00 ft
Field Vertical Reference	Mean Sea Level	Section Azimuth	104.91°



## Planned Wellpath Report Rev-A.0 Page 2 of 7



RODDR	ENCE WELLPATH IDENTIFICATION		
Operator	BOPCO, L.P.	Slot	JRU DI1 No.164H
Area	Eddy County, NM	Well	No.164H
Field	JRU NAD27	Wellbore	No.164H PWB
Facility	JRU Drilling Island 1		

WELLP	ATH DA	TA (24	1 station	1S) †=i	nterpolat	ed/extr	apolated sta	tion			THE POWER THE POPULATION AND ADDRESS OF THE POPULATION AND ADDRESS	
MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
0.00†		150.000	0.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
26.00	0.000	150.000	26.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	Tie On
126.00†	0.000	150.000	126.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
130.00†	0.000	150.000	130.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	Fresh Water
226.00†	0.000	150.000	226.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	2000
326.00†	0.000	150.000	326.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
426.00†	0.000	150.000	426.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
526.00†	0.000	150.000	526.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
556.00†	0.000	150.000	556.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	Salado
626.00†	0.000	150.000	626.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
726.00†	0.000	150.000	726.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
826.00†	0.000	150.000	826.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
926.00†	0.000	150.000	926.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
1026.00†		150.000		0.00	0.00	0.00	<del> </del>	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
1126:00†			1126.00	0.00	0.00	0.00				103°52'55.016"W	0.00	(17-12-14) (17-17)
1226.00†	0.000	150.000	1226.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
1326.00†	0.000	150.000	1326.00	0.00	0.00	0.00		502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
1426.00†	0.000	150.000	1426.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
1526.00†	0.000	150.000	1526.00	0.00	0.00	0.00	639345.90	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
1626.00†			1626:00	0.00	0.00	0.00	639345.90		32°22'51.158"N		0.00	
1726.00†		150.000		0.00	0.00	0.00	A TOTAL PROPERTY OF THE PARTY O	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	
1800.00		150.000		0.00	0.00	0.00	\$	502572.00	32°22'51.158"N	103°52'55.016"W	0.00	Nudge
1826.00†		150.000		0.08	-0.10	0.06	639345.96	502571.90	32°22'51.157"N	103°52'55.015"W	2.00	
1926.00†	2.520	150.000	1925.96	1.96	-2.40	1.39	639347.29	502569.60	32°22'51.134"N	103°52'55.000"W	2.00	
2026:00†		150.000		6.29	-7.72	Common reservations	hanner of the same		32°22'51.081"N		2.00	
2050.00		150.000		7.70	-9.44	5.45	639351.35	502562.56	32°22'51.064"N	103°52'54.953"W	2.00	
2126.00†		150.000		12.37	-15.18	8.76	639354.66	502556.82	32°22'51.007"N	103°52'54.915"W	0.00	
2226.00†		150.000		18.53	-22.73	13.12	639359.02	502549.28	32°22'50.932"N	103°52'54.864"W	0.00	
2326.00†		150.000		24.68	-30.27	17.48	639363.38	502541.73	32°22'50.858"N	103°52'54.814"W	0.00	
2426.00†	5.000	150.000	2424.25	30.83	-37.82	21:84	639367.73	502534.18			0.00	
2526.00†		150.000	2523.87	36.99	-45.37		639372.09	502526.63	32°22'50.708"N	103°52'54.713"W	0.00	September of the order of the section of the sectio
2626.00†	5.000	150.000	2623.49	43.14	-52.92	30.55	639376.45	502519.09	32°22'50.633"N	103°52'54.662"W	0.00	***************************************
2726.00†		150.000	2723.11	49.29	-60.46	34.91	639380.81	502511.54	32°22'50.558"N	103°52'54.612"W	0.00	
2826.00†	5.000	150.000	2822.73	55.45	-68.01	39.27	639385.16	502503.99	32°22'50.483"N	103°52'54.562"W	0.00	
2926.00†	5.000	150.000	2922.35	61.60	-75.56	43.62	639389.52	502496.44	32°22'50.408"N	103°52'54.511''W	0.00	
3026.00†	5.000	150.000	3021.97	67.75	-83.11	47.98	639393.88	502488.90	32°22'50.333"N	103°52'54.461"W	0.00	YOUR SELECTION IN WITH HERE TO BE CAN WEEK LOT
3126.00†		150.000		73.91	-90.66	<u></u>	639398.24	502481.35	32°22'50.259"N	103°52'54.410"W	0.00	-
3226.00†	·	150.000		80.06			639402.59		32°22'50.184"N	103°52'54.360"W	0.00	
3326.00†		150.000		86.21				\$	32°22'50.109"N	103°52'54.309"W	0.00	
3426.00†			3420.45							103°52'54.259"W	CONTRACTOR CONTRACTOR	
3526.00†		150.000		98.52	***************************************		639415.67	502451.16	32°22'49.959"N	103°52'54.208"W	0.00	
3541.99†	λ	150.000			-122.06			502449.95	32°22'49.947"N	103°52'54.200"W		Lamar
3587.17†		150.000			-125.46			502446.54	32°22'49.913"N	103°52'54.178"W		Ramsey
3626.00†		150.000			-128.40			502443.61	32°22'49.884"N	103°52'54.158"W	0.00	- caingo j
	annuari a compressione de la com	Commence of the state of the st								103°52'54.108"W		
<u> </u>		Company of Company		EEEE SALES	o Live Committee		337.027.50		7,00	TANDET TO STATE OF THE STATE OF	0.002	



### Planned Wellpath Report Rev-A.0 Page 3 of 7



स्रविविविद्य	ENCE WELLPATH IDENTIFICATION	Cours of	
Operator	BOPCO, L.P.	Slot	JRU DI1 No.164H
Area	Eddy County, NM	Well	No.164H
Field	JRU NAD27	Wellbore	No.164H PWB
Facility	JRU Drilling Island 1		

WITTIN T	DA DIET IN	100 1 /0										
						,	trapolated		T -424 - N	Y 14 1	DIC	6
MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	[US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
3826.00†		150.000	3818.92	116.98	-143.49				32°22'49.735"N	103°52'54.057"W	0.00	
3926.00†	5.000	150.000	3918.54	123.13	-151.04	87.20	639433.10	502420.97	32°22'49.660"N	103°52'54.007"W	0.00	
4026.00†	5.000	150.000	4018.16	129.28	-158.59	91.56	639437.45	502413.42	32°22'49.585"N	103°52'53.956"W	0.00	
4126.00†	5.000	150.000	4117.78	135.44	-166.14	95.92	639441.81	502405.88	32°22'49.510"N	103°52'53.906"W	0.00	A STATE OF THE PARTY OF THE PAR
4226.00†	5.000	150.000	4217.40	141.59	-173.68	100.28	639446.17	502398.33	32°22'49.435"N	103°52'53.855"W	0.00	
4326.00†	5.000	150.000	4317.02	147.74	-181.23	104.63	639450.53	502390.78	32°22'49.360"N	103°52'53.805"W	0.00	
4426.00†	5.000	150.000	4416.64	153.90	-188.78	108.99	639454.88	502383.23	32°22'49.285"N	103°52'53.754"W	0.00	
4468.52†	5.000	150.000	4459.00	156.51	-191.99	110.84	639456.74	502380.02	32°22'49.253"N	103°52′53.733″W	0.00	Cherry Canyon
4526.00†	5.000	150.000	4516.26	160.05	-196.33	113.35	639459.24	502375.69	32°22'49.210"N	103°52'53.704"W	0.00	
4626.00†	5.000	150.000	4615.88	166.20	-203.88	117.71	639463.60	502368.14	32°22'49.136"N	103°52'53.654"W	0.00	
4726.00†	5.000	150.000	4715.50	172.36	-211.42	122.07	639467.96	502360.59	32°22'49.061"N	103°52'53.603"W	0.00	
4826.00†	5.000	150.000	4815.12	178.51	-218.97	126.42	639472.31	502353.04	32°22'48.986"N	103°52'53.553"W	0.00	
4926.00†	5.000	150.000	4914.74	184.66	-226.52	130.78	639476.67	502345.50	32°22'48.911"N	103°52'53.502"W	0.00	
5026.00†	5.000	150.000	5014.36	190.82	-234.07	135.14	639481.03	502337.95	32°22'48.836"N	103°52'53.452"W	0.00	
5126.00†	5.000	150.000	5113.98	196.97	-241.61	139.50	639485.39	502330.40	32°22'48.761"N	103°52'53.401"W	0.00	
5226.00†	5.000	150.000	5213.60	203.12	-249.16	143.85	639489.74	502322.86	32°22'48.686"N	103°52'53.351"W	0.00	
5326.00†	5.000	150.000	5313.22	209.28	-256.71	148.21	639494.10	502315.31	32°22'48.611"N	103°52'53.300"W	0.00	
5426.00†	5.000	150.000	5412.84	215.43	-264.26	152.57	639498.46	502307.76	32°22'48.537"N	103°52'53.250"W	0.00	
5526.00†	5.000	150.000	5512.46	221.58	-271.81	156.93	639502.82	502300.21	32°22'48.462"N	103°52'53.200"W	0.00	
5626.00†	5.000	150.000	5612.08	227.74	-279.35	161.29	639507.17	502292.67	32°22'48.387"N	103°52'53.149"W	0.00	
5726.00†	5.000	150.000	5711.69	233.89	-286.90	165.64	639511.53	502285.12	32°22'48.312"N	103°52'53.099"W	0.00	
5798.58†	5.000	150.000	5784.00	238.36	-292.38	168.81	639514.69	502279.64	32°22'48.258"N	103°52'53.062"W	0.00	Brushy Canyon
5826.00†	5.000	150.000	5811.31	240.04	-294.45	170.00	639515.89	502277.57	32°22'48.237"N	103°52'53.048"W	0.00	
5926.00†	5.000	150.000	5910.93	246.20	-302.00	174.36	639520.25	502270.02	32°22'48.162"N	103°52'52.998"W	0.00	
6026.00†	5:000	150.000	6010.55	252.35	-309.55	178.72	639524.60	502262.48	32°22'48.087"N	103°52'52.947"W	0.00	
6126.00†	5.000	150.000	6110.17	258.50	-317.09	183.07	639528.96	502254.93	32°22'48.013"N	103°52'52.897"W	0.00	
6226.00†	5.000	150.000	6209.79	264.66	-324.64	187.43	639533.32	502247.38	32°22'47.938"N	103°52'52.847"W	0.00	
6326.00†	5.000	150.000	6309.41	270.81	-332.19	191.79	639537.68	502239.83	32°22'47.863"N	103°52'52.796"W	0.00	
6426.00†	5.000	150.000	6409.03	276.96	-339.74	196.15	639542.03	502232.29	32°22'47.788"N	103°52'52.746"W	0.00	
6526.00†	5.000	150.000	6508.65	283.11	-347.29	200,51	639546.39	502224.74	32°22'47.713"N	103°52'52.695"W	0.00	
6626.00†	5.000	150.000	6608.27	289.27	-354.83	204.86	639550.75	502217.19	32°22'47.638"N	103°52'52.645"W	0.00	
6726.00†	5.000	150.000	6707.89	295.42	-362.38	209.22	639555.11	502209.64	32°22'47.563"N	103°52'52.594"W	0.00	
6826.00†	5.000	150.000	6807.51						32°22'47.488"N	103°52'52.544"W	0.00	
6926.00†	5.000	150.000	6907.13						32°22'47.414"N	103°52'52.493"W	0.00	
7026.00†	5.000	150.000	7006.75	313.88	-385.02	222.29	639568.18	502187.00	32°22'47.339"N	103°52'52.443"W	0.00	
7126.00†			7106.37							103°52'52.393"W	0.00	
7226.00†	5.000	150.000	7205.99	326.19	-400.12	231.01	639576.89	502171.91	32°22'47.189"N	103°52'52.342"W	0.00	
7326.00†	5.000	150.000	7305.61	332.34	-407.67	235.37	639581.25	502164.36	32°22'47.114"N	103°52'52.292"W	0.00	
7404.69†	5.000	150.000	7384.00	337.18	-413.61	238.80	639584.68	502158.42	32°22'47.055"N	103°52'52.252"W	0.00	Bone Spring Lime
7426.00†				en orrespective and the format in the first		h	Annual Company of the Company	THE RESERVE OF THE PERSON NAMED IN COLUMN TWO	Company of the compan	103°52'52.241"W	0.00	
7526.00†			7504.84				Committee of the Commit	502149.27	***************************************	103°52'52.191"W	0.00	A STATE OF THE PROPERTY OF THE
7626.00†			7604.46					·	32°22'46.889"N	103°52'52.140"W	0.00	
7726.00†			7704.08						32°22'46.815"N	103°52'52.090"W	0.00	
7826.00†			7803.70				daire	£		103°52'52.039"W	0.00	
7926.00+										103°52'51.989"W		<b> </b>
processor to the second of the	amount of the state of the stat	engen adjacon i e etropica di	Account your a region residence of the	engenner (i vonafrijskalise) de 1996 j	and the second s	manuscription of the second se	LETTE THE LA SERVICE AND ADDRESS OF THE PERSON OF THE PERS	Transportation of the second o	The state of the s		Carlo Maria de Carlo	Parameter and the second secon



### Planned Wellpath Report Rev-A.0 Page 4 of 7



Ranar	ENCE WELLPATH IDENTIFICATION		
Operator	BOPCO, L.P.	Slot	JRU DI1 No.164H
Area	Eddy County, NM	Well	No.164H
Field	JRU NAD27	Wellbore	No.164H PWB
Facility	JRU Drilling Island 1		

WELLI MD	Inclination	Azimuth	TVD	Vert Sect	North	East	Grid East	Grid North	Latitude	Longitude	DLS	Comments
[ft]	[°]	[°]	[ft]	[ft]	[ft]	[ft]	[US ft]	[US ft]			[°/100ft]	
8026.00	5.000	150.000	8002.94	375.41	-460.50	265.87	639611.75	502111.53	32°22'46.590"N	103°52'51.939"W	0.00	
8126.00	5.000	150.000	8102.56	381.57	-468.05	270.23	639616.11	502103.98	32°22'46.515"N	103°52'51.888"W	0.00	
8226.00	5.000	150.000	8202.18	387.72	-475.60	274.59	639620.47	502096.43	32°22'46.440"N	103°52'51.838"W	0.00	
8326.00			8301.80		-483.15	278.95	639624.83	502088.89	32°22'46.365"N	103°52'51.787"W	0.00	
8412.53	5.000	150.000	8388.00	399.20	-489.68	282.72	639628.60	502082.36	32°22'46,301"N	103°52'51.744"W	0.00	1st Bone Spring
8426.00	5.000	150.000	8401.42	400.03	-490.70					103°52'51.737"W	0.00	
8493.20	5.000	150.000	8468.36	404.16	-495.77	286.23	639632.11	502076.27	32°22'46.240"N	103°52'51.703"W	0.00	Est KOP
8526.00	† 6.946	152.881	8500.98	406.50	-498.77	287.85	639633.73	502073.26	32°22'46.210"N	103°52'51.684"W	6.00	
8626.00	† 12.919	156.300	8599.44	417.53	-514.40	295.11	639640.99	502057.63	32°22'46.055"N	103°52'51.600"W	6.00	
8726.00	18.909	157.575	8695.57	434.35	-539.64	305.79	639651.67	502032.40	32°22'45.805"N	103°52'51.477"W	6.00	
8826.00	24.904	158.252	8788.30	456.77	-574.21	319.79	639665.66	501997.83	32°22'45.463"N	103°52'51.316"W	6.00	
8926.00			8876.64	484.54	-617.72	336.94	639682.82	501954.32	32°22'45.031"N	103°52'51.118"W	6.00	
9026.00			8959.60	517.37	-669.71	357.06	639702.94	501902.33	32°22'44.516"N	103°52'50.886"W	6.00	
9126.00	······································	159.205	9036.29	554.88	-729.61	379.94	639725.81	501842.45	32°22'43.922"N	103°52'50.622"W	6.00	
9226.00				596.67	-796.75	405.31	639751.18	501775.31	32°22'43.257"N	103°52'50.329"W	6.00	
9252.51	7.5 and to the second s	159.427	9123.00	608.42	-815.67	412.42	639758.29	501756.39	32°22'43.069"N	103°52'50.247"W	6.00	2nd Bone Spring Sand
9326.00			9167.53	642.29	-870.40	432.90	639778.77	501701.66	32°22'42.527"N	103°52'50.011"W	6.00	
9426.00			9220.66	691.23	-949.76	462.41	639808.28	501622.31	32°22'41.741"N	103°52'49.671"W	6.00	
9526.00			9264.64	·	-1033.95	493.52	639839.38	501538.12	32°22'40.906"N	103°52'49.312"W	6.00	
9626.00	in house management and		9299.01	THE RESERVE THE PROPERTY OF THE PARTY.	-1122.06	525.88	639871.74	501450.02	32°22'40.033"N	103°52'48.940"W	6.00	
9726.00			9323.37	Call Transferred and the second and the second	-1213.11	Concession Contraction of the Co	America Dide to remove the control of			103°52'48.556"W	6.00	
9744.49			9326.76	862.87	-1230.19	<u> </u>	Assert VI Course Company Company		<u> </u>	103°52'48.485"W	6.00	80° Curve
9826.00		160.000	<del></del>	·	-1305.62	ļ	<del></del>	<del></del>		103°52'48.168"W	0.00	
9926.00			9358.28		-1398.17	L				103°52'47.780"W	0.00	**************************************
9944.49			·	975.59						103°52'47.708"W	0.00	200' Tangent
10026.00		A CAMPA SECTION OF A SECTION OF	4	1021.82						103°52'47.390"W	6.00	
10109.63	<u></u>			1069.61						103°52'47.061"W		EOC
10126.00			L	1078.98						103°52'46.996"W	0.00	
10226.00				1136.21		<u> </u>	<del></del>			103°52'46.602"W	0.00	
10326.00				1193.44			Contraction Contraction Contraction	CHARLES CONTRACTOR CON	<u> </u>	103°52'46.208"W	0.00	Non-phillips (1777)
10426.00 <sup>-</sup>				1250.67	***************************************					103°52'45.814"W	0.00	Control of the Contro
10526.00				1307.90						103°52'45.420"W	0.00	
0626.00				1365.13	***	865.52	640211.36	500517.25	32°22'30.788"N	103°52'45.025"W	0.00	
10726.00		160.000	9377.03	1422.36	-2148.86	899.73	640245.56	500423.29	32°22'29.857"N	103°52'44.631"W	0.00	
10789.63		160.000	9377.14	1458.78	-2208.66					103°52'44.380"W	0.00	Hold:
10826.00				1479.97						103°52'44.232"W	4.00	
0926.00				1542.02		974.15	640319.99	500237.78	32°22'28.018"N	103°52'43.773"W	4.00	
1026.00							<u> </u>		<u> </u>	103°52'43.240"W	4.00	
1126.00										103°52'42.636"W	4.00	
1226.00	and the same of th									103°52'41.963"W		
1326.00										103°52'41.226"W	4.00	
1426.00										103°52'40.428"W	4.00	<del>                                     </del>
1526.00			-			<u> </u>	Association and the state of th	Company of the second s	A STREET, STRE	103°52'39.573"W	4.00	
1626.00			<u> </u>	(						103°52'38.664"W.	4.00	*
1726.00	THE COMPANY OF STREET		properties and residence and residence	Same representation with the property of the	CONTRACTOR	Service of the servic	Service and the service and th	Carrier Committee for the Committee of t	Anny de la company de la compa	103°52'37.707"W	L	
1120.00	11 07:000	164.373	JJJ 0.73	12.77.19		P-170177	WT0072.711	E7770100	JULULUITUIN	LUJUJUJUJUJUJUJ	7.00	Land Maria



### Planned Wellpath Report Rev-A.0 Page 5 of 7



RIBIDIDER	ENGE WELLPATH IDENTIFICATION		
Operator	BOPCO, L.P.	Slot	JRU DI1 No.164H
Area	Eddy County, NM	Well	No.164H
Field	JRU NAD27	Wellbore	No.164H PWB
Facility	JRU Drilling Island 1		·

WELLPATH DATA (241 stations) †=\interpolated/extrapolated station												
<u></u>		,							Y _ 424 A _	Tdo	DIE	Commonto
MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
11826.00†				2295.75	-2977.02	1583.02	640928.81	499595.19	32°22'21.633"N	103°52'36.705"W	4.00	
11926.00†				2393.67	-3021.70	1672.46	641018.25	499550.51	32°22'21.188"N	103°52'35.665"W	4.00	
12026.00†		110.545			-3060.03	1764.80	641110.58	499512.18	32°22'20.804"N	103°52'34.590"W	4.00	
12126.00†	89.892			2592.54	-3091.83	1859.59	641205.36	499480.39	32°22'20.486"N	103°52'33.487"W	4.00	
12226:00†	<b>89.89</b> 5				-3116.94	1956.37	641302.13	499455.28	32°22'20:233"N	103°52'32.360"W	4.00	
12326.00†	89.898		9380.08		-3135.24	2054.66	641400.41	499436.98	32°22'20.048"N	103°52'31.214"W	4.00	
12426.00†	89.902	94.545	9380.25	2891.13	-3146.63	2153.99	641499.73	499425.59	32°22'19.931"N	103°52'30.057"W	4.00	
12526.00†	89.907	90.545	9380.42	2988.79	-3151.07	2253.87	641599.61	499421.15	32°22'19.883"N	103°52'28.893"W	4.00	
12538.19	89.907	90.058	9380.44	3000.58	-3151.14	2266.05	641611.79	499421.08	32°22'19.882"N	103°52'28.751"W	4.00	TL
12626.00†	89.907	90.058	9380.58	3085.46	-3151.23	2353.87	641699.60	499421.00	32°22'19'877."N	103°52'27.727"W	0.00	1
12726.00†	89.907	90.058	9380.75	3182.12	-3151.33	2453.87	641799.59	499420.89	32°22'19.872"N	103°52'26.561"W	0.00	
12826.00†	89.907	90.058	9380.91	3278.78	-3151.43	2553.87	641899.59	499420.79	32°22'19.866"N	103°52'25.395"W	0.00	
12926.00†	89.907	90.058	9381.07	3375.43	-3151.53	2653.87	641999.58	499420.69	32°22'19.861"N	103°52'24.229"W	0.00	
13026.00†	89.907	90.058	9381.23	3472.09	-3151.63	2753.87	642099.57	499420.59	32°22'19.856"N	103°52'23.063"W	0.00	
13126.00†	89.907	90.058	9381.39	3568.75	-3151.73	2853.87	642199.56	499420.49	32°22'19.851"N	2103°52'21:897"W	0:00	101
13226.00†	89.907	90.058	9381.56	3665.41	-3151.83	2953.86	642299.56	499420.39	32°22'19.845"N	103°52'20.731"W	0.00	
13326.00†	89.907	90.058	9381.72	3762.07	-3151.93	3053.86	642399.55	499420.29	32°22'19.840"N	103°52'19.565"W	0.00	
13426.00†	89.907	90.058	9381.88	3858.73	-3152.03	3153.86	642499.54	499420.19	32°22'19.835"N	103°52'18.399"W	0.00	
13526.00†	89.907	90.058	9382.04	3955.39	-3152.13	3253.86	642599.53	499420.09	32°22'19.830"N	103°52'17.233"W	0.00	
13626.00†	89.907	90.058	9382:20	4052.04	-3152.24	3353.86	642699:53	499419.99	32°22'19:824"N	103°52'16.068"W	0.00	
13726.00†	89.907	90.058	9382.37	4148.70	-3152.34	3453.86	642799.52	499419.89	32°22'19.819"N	103°52'14.902"W	0.00	
13826.00†	89.907	90.058	9382.53	4245.36	-3152.44	3553.86	642899.51	499419.79	32°22'19.814"N	103°52'13.736"W	0.00	
13926.00†	89.907	90.058	9382.69	4342.02	-3152.54	3653.86	642999.51	499419.68	32°22'19.809"N	103°52'12.570"W	0.00	
14026.00†	89.907	90.058	9382.85	4438.68	-3152.64	3753.86	643099.50	499419.58	32°22'19.803"N	103°52'11.404"W	0.00	
14126.00†	89.907	90.058	9383.01	4535.34	-3152.74	3853.86	643199.49	499419.48	32°22'19.798"N	-103°52'10.238"W	0.00	
14226.00†	89.907	90.058	9383.18	4632.00	-3152.84	3953.86	643299.48	499419.38	32°22'19.793"N	103°52'09.072"W	0.00	
14326.00†	89.907	90.058	9383.34	4728.65	-3152.94	4053.86	643399.48	499419.28	32°22'19.787"N	103°52'07.906"W	0.00	
14426.00†	89.907			4825.31	-3153.04	4153.86	643499.47	499419.18	32°22'19.782"N	103°52'06.740"W	0.00	
14526.00†	89.907			4921.97	-3153.14	4253.86	643599.46	499419.08	32°22'19.777"N	103°52'05.574"W	0.00	
14626:00†	89.907	90.058	9383.82	5018.63	-3153.24	4353.86	643699.45	499418.98	32°22\19!772"N	, 103°52'04.408"W	0.00	
14726.00†	<sup>4</sup> 89.907	90.058	9383.99	5115.29	-3153.34	4453.86	643799.45	499418.88	32°22'19.766"N	103°52'03.242"W	0.00	
14826.00†	89.907			5211.95	-3153.45	4553.86	643899.44	499418.78	32°22'19.761"N	103°52'02.077"W	0.00	
14926.00†	89.907		9384.31		-3153.55	4653.86	643999.43	499418.68	32°22'19.756"N	103°52'00.911"W	0.00	
15026.00†	89.907			5405.26	-3153.65	4753.86	644099.43		32°22'19.750"N	103°51'59.745"W	0.00	
15126.00†	89.907							499418.47	32°22'19.745"N	103°51'58.579"W	0.00	28/05/201
15226.00†	89.907			5598.58	<del></del>	<del></del>	644299.41	499418.37	32°22'19.740"N	103°51'57.413"W	0.00	
15326.00†	89.907			<del></del>	·		<del></del>	499418.27		103°51'56.247"W	0.00	
15426.00†	89.907	90.058	9385.12	5791.90	-3154.05	5153.86	644499.40	499418.17	32°22'19.729"N	103°51'55.081"W	0.00	
15526.00†	89.907			5888.56			644599.39		32°22'19.724"N	103°51'53.915"W	0.00	
15626.00†	89.907						644699.38			103°51'52.749"W	0.00	
15726.00†	89.907	90.058	9385.61	6081.87	-3154.35	5453.86	644799.38	499417.87	32°22'19.713"N	103°51'51.583"W	0.00	
15826.00†	89.907	90.058	9385.77	6178.53	-3154.45	5553.86	644899.37	499417.77	32°22'19.708"N	103°51'50.417"W	0.00	
15926.00†	89.907	90.058	9385.93	6275.19	-3154.55	5653.86	644999.36	499417.67	32°22'19.702"N	103°51'49.251"W	0.00	
16026.00†	89.907	90.058	9386.09	6371.85	-3154.66	5753.86	645099.35	499417.57	32°22'19.697"N	103°51'48.086"W	0.00	
16126.00†	89.907	90.058	9386:25	6468.51	-3154.76	5853.86	645199.35	499417.47	32°22'19:692 <u>"</u> N	103°51'46.920"W	0.00	



## Planned Wellpath Report Rev-A.0 Page 6 of 7



REDEER	ENCE WELLPATH IDENTIFICATION		
Operator	BOPCO, L.P.	Slot	JRU DI1 No.164H
Area	Eddy County, NM	Well	No.164H
Field	JRU NAD27	Wellbore	No.164H PWB
Facility	JRU Drilling Island 1		

WELLPA	ATH DA'	TA (24	l statio	ns) t=ir	nternolateo	l/extrapola	ted station					
	Inclination [°]			Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
16226.00†	89.907		9386.42	6565.17	-3154.86	5953.86	645299.34	499417.37	32°22'19.686"N	103°51'45.754"W	0.00	
16326.00†	89.907		9386.58	6661.83	-3154.96	<u></u>	645399.33	499417.26	32°22'19.681"N	103°51'44.588"W	0.00	***************************************
16426.00†	89.907	L	9386.74	6758.48	-3155.06		645499.32	499417.16	32°22'19.676"N	103°51'43.422"W	0.00	
16526.00†	89.907	***************************************	9386.90	6855.14	-3155.16	<u> </u>	645599.32	499417.06	32°22'19.670"N	103°51'42.256"W	0.00	
16626:00†			9387.06				L		32°22'19.665"N		0.00	
16726.00†	89.907	,	9387.23	7048.46	-3155.36	6453.86		499416.86	32°22'19.660"N	103°51'39.924"W	0.00	
16826.00†	89.907		9387.39	7145.12	-3155.46	6553.86	645899.30	<del></del>	32°22'19.654"N	103°51'38.758"W	0.00	
16926.00†	89.907	<u> </u>	9387.55	7241.78	-3155.56		645999.29	499416.66	32°22'19.649"N	103°51'37.592"W	0.00	
17026.00†	89.907		9387.71	7338.44	-3155.66		646099.28	499416.56	32°22'19.643"N	103°51'36.426"W	0.00	
17126.00†			9387.87		-3155.76					103°51'35.260"W	<b>**</b> 0.00	
17226.00†	89.907		9388.04	7531.75	-3155.87		646299.27	499416.36	32°22'19.633"N	103°51'34.095"W	0.00	East Control State (State Control of Control
17326.00†	89.907		9388.20	7628.41	-3155.97	7053.86	646399.26	499416.26	32°22'19:627"N	103°51'32.929"W	0.00	
17426.00†	89.907		9388.36	7725.07	-3156.07	7153.86	646499.25	499416.16	32°22'19.622"N	103°51'31.763"W	0.00	
17526.00†	89.907		9388.52	7821.73	-3156.17	7253.86	646599.24		32°22'19.617"N	103°51'30.597"W	0.00	
17626.00†			9388.68		-3156.27		i		32°22'19.611"N	103°51'29.431"W	0.00	
17726.00†	89.907	Alleman harmed by annihing	9388.85	8015.05	-3156.37	and the second s	646799.23		32°22'19.606"N	103°51'28.265"W	0.00	ACT COLOR
17826.00†	89.907		9389.01	8111.70	-3156.47	<u> </u>	646899.22		32°22'19.600"N	103°51'27.099"W	0.00	
17926.00†	89.907		9389.17	8208.36	-3156.57		646999.22	499415.65	32°22'19.595"N	103°51'25.933"W	0.00	
18026.00†	89.907		9389.33	8305.02	-3156.67	7753.86	647099.21	499415.55	32°22'19.590"N	103°51'24.767"W	0.00	
18126!00†				8401.68	<u> </u>				32°22'19.584"N	103°51'23.601"W		
18226.00†	89.907	TOTAL PROPERTY OF THE PROPERTY OF	9389.66	8498.34	-3156.87	7953.86	647299.19	499415.35	32°22'19.579"N	103°51'22.435"W	0.00	121.715 (42.57)
18326.00†	89.907		9389.82	8595.00	-3156.97	<del></del>	647399.19	499415.25	32°22'19.573"N	103°51'21.270"W	0.00	
18426.00†	89.907		9389.98	8691.66	-3157.08		647499.18	499415.15	32°22'19.568"N	103°51'20.104"W	0.00	
18526.00†	89.907		9390.14	8788.31	-3157.18		647599.17	499415.05	32°22'19.562"N	103°51'18.938"W	0.00	
18626.00†			9390.30	<u></u>	-3157.18		L			103°51'17!772"W	#+0.00	
18726.00†	89.907		9390.47	8981.63	-3157.38	8453.85	647799.16		32°22'19.552"N	103°51'16.606"W	0.00	2.2
18826.00†	89.907		9390.47	9078.29	-3157.48	8553.85	647899.15		32°22'19.546"N	103°51'15.440"W	0.00	
18926.00†	89.907		9390.03	9174.95	-3157.58	8653.85		499414.64	32°22'19.540 N	103°51'14.274"W	0.00	
19026.00†	89.907		9390.95	9271.61	-3157.68	8753.85	<del></del>	499414.54	32°22'19.535"N	103°51'13.108"W	0.00	
19126:00†				29368.27		<u> </u>	l	.i		103°51'11.942"W	<u> </u>	
19226.00†	89.907		9391.28		-3157.88	8953.85	648299.12		32°22'19.524"N	103°51'10.776"W	0.00	
19326.00†	89.907		9391.44	9561.58	-3157.98	9053.85	648399.11	499414.24	32°22'19.519"N	103°51'09.610"W	0.00	
19426.00†	89.907		9391.60	9658.24	-3158.08	9153.85	648499.11	499414.14	32°22'19.514"N	103°51'08.444"W	0.00	
19526.00†	89.907		9391.76	9754.90	-3158.18	9253.85	648599.10		32°22'19.508"N	103°51'07.279"W	0.00	
19626:00†				9851 56						103°51'06:1113"W	0.00	
19726.00†	89.907	indiagram in the second	9392.09	9948.22	-3158.39				32°22'19.497"N	103°51'04.947"W	0.00	المستقد محسندا
19826.00†	89.907			10044.88						103°51'03.781"W		
19926.00†				10141.54					32°22'19.486"N		0.00	
20026.00†	89.907			10238.19	-3158.69		<del></del>	499413.53	32°22'19.481"N	103°51'01.449"W	0.00	
20126:00†	89.907			L						103°51'00.283"W	0.00	
20226.00†	89.907	24,00		10431.51	-3158.89		649299.05	· · · · · · · · · · · · · · · · · · ·	32°22'19.470"N	103°50'59.117"W	0.00	ar destroyable
20326.00†	89.907			10528.17	-3158.99	<u> </u>	649399.04		32°22'19.464"N	103 30 39.117 W	0.00	
20426.00†	89.907			10528.17	-3159.09	<del></del>	L	499413.23	32°22'19.459"N	103°50'56.785"W		
20426.00†	89.907			10024.83	<del></del>			499413.13	32°22'19.454"N		0.00	
										103°50'55.619"W 103°50'54:454"W	0.00	
EZUUZU.UU	33.7U/	30:038	フンフン・ンサー	(C1.01001)	<u>193.291</u>	10222:00	UH7U77.UZ	+77412.73	22.22.17.440.N	<sup>™</sup> เกว <sup>®</sup> จก <sup>เ</sup> วส:ส่วส®М¶	E. U.UU,	



## Planned Wellpath Report Rev-A.0 Page 7 of 7




REDEER	ENCEWELLPATH IDENTIFICATION		
Operator	BOPCO, L.P.	Slot	JRU DI1 No.164H
Area	Eddy County, NM	Well	No.164H
Field	JRU NAD27	Wellbore	No.164H PWB
Facility	JRU Drilling Island 1		


WELLP	ATH DA	TA (24	11 statio	ons) †=	interpolat	ted/extrap	olated stati	on				
MD	Inclination	Azimuth	TVD	Vert Sect	North	East	Grid East	Grid North	Latitude	Longitude	DLS	Comments
[ft]	[°]	[°]	[ft]	[ft]	[ft]	[ft]	[US ft]	[US ft]			[°/100ft]	
20726.00†	89.907	90.058	9393.71	10914.80	-3159.39	10453.85	649799.01	499412.83	32°22'19.443"N	103°50'53.288"W	0.00	
20826.00†	89.907	90.058	9393.87	11011.46	-3159.50	10553.85	649899.01	499412.73	32°22'19.437"N	103°50'52.122"W	0.00	
20926.00†	89.907	90.058	9394.03	11108.12	-3159.60	10653.85	649999.00	499412.63	32°22'19.432"N	103°50'50.956"W	0.00	
21026.00†	J									103°50'49.790"W	0.00	
21126.00†	89.907	90.058	9394.35	11301.44	-3159.80	10853.85	650198.98	499412.42	32°22119.421"N	103°50'48.624"W	0.00	
21226.00†	89.907	90.058	9394.52	11398.10	-3159.90	10953.85	650298.98	499412.32	32°22'19.415"N	103°50'47.458"W	0.00	
21326.00†	89.907	90.058	9394.68	11494.76	-3160.00	11053.85	650398.97	499412.22	32°22'19.410"N	103°50'46.292"W	0.00	
21426.00†	89.907	90.058	9394.84	11591.41	-3160.10	11153.85	650498.96	499412.12	32°22'19.404"N	103°50'45.126"W	0.00	
21526.00†	89.907	90.058	9395.00	11688.07	-3160.20	11253.85	650598.95	499412.02	32°22'19.399"N	103°50'43.960"W	0.00	
21626.00†	<b>89.907</b>	290.058	9395.16	11784:73	-3160:30	11353.85	650698.95	499411.92	32°22'19.393"N	103°50'42.794"W	0.00	4 4 4
21726.00†	89.907	90.058	9395.33	11881.39	-3160.40	11453.85	650798.94	499411.82	32°22'19.388"N	103°50'41.629"W	0.00	
21826.00†	89.907	90.058	9395.49	11978.05	-3160.50	11553.85	650898.93	499411.72	32°22'19.382"N	103°50'40.463"W	0.00	
21926.00†	89.907	90.058	9395.65	12074.71	-3160.61	11653.85	650998.93	499411.62	32°22'19.377"N	103°50'39.297"W	0.00	
22026.00†	89.907	90.058	9395.81	12171.37	-3160.71	11753.85	651098.92	499411.52	32°22'19.371"N	103°50'38.131"W	0.00	
22126:00†	₹×89.907	490.058	9395.97	12268.02	-3160.81	11853.85	651198.91	499411:42	32°22'19'365"N	103°50'36.965".W	0.00	
22142.49	89.907	90.058	9396.00 <sup>1</sup>	12283.96	-3160.82	11870.34	651215.40	499411.40	32°22'19.365 <u>"</u> N	103°50'36:773"W	0.00	No.164H PBHL


TARGETS									
Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	Shape
1) No.164H PBHL	22142.49	9396.00	=3160:82	211870.34	651215.40	499411.40	32°22¦19;365#N	103°50'36:773"W	point


S	J <b>RVEY PRO</b>	)GRAM - Ref	Wellbore: No.164H PWB Ref	Wellpath: Rev-A.0	·	•
	Start MD	End MD	Positional Uncertainty	Model	Log Name/Comment	Wellbore
L	[ft]	[ft]				
	26.00	22142.49	NaviTrak (Standard)			No.164H PWB



Jeanette 7-22-13 # 21077904-A







### MIDWEST

### HOSE AND SPECIALTY INC.

II	NTERNAL	. HYDROST	ATIC TEST	REPOR	T							
Custome LATSHAW	r: / DRILLING			P.O. Numb RIG#4	er:							
		HOSE SPECIF	FICATIONS			·						
Type:	CHOKE LIN	E		Length:	30'	·····						
I.D.	3"	INCHES	O.D.	6"	INC	CHES						
WORKING	PRESSURE	TEST PRESSUR	E	BURST PRES	SSURE							
5,000	PSI	10,000	PSI			PSI						
•	COUPLINGS											
Type of E	nd Fitting 4 1/16 5K FL	ANGE										
Type of 0	Coupling: SWEDGED		MANUFACTU MIDWEST HOS		ALTY							
		PROC	EDURE	·								
	Hose assemble	/ pressure tested w	ith water at ambier	it temnerature								
		TEST PRESSURE	<del></del>	URST PRESSU								
	1	MIN.			0	PŠI						
COMMEN	SO#81610 Hose is cov wraped with	ered with stainle fire resistant vated for 1500 de	ermiculite coat	ed fiberglas	S							
Date:	3/2/2011	Tested By: BOBBY FINK		Approved: MENDI		NC						

### Internal Hydrostatic Test Graph

April 4, 2012

Customer: Latshaw

Pick Ticket #: 81610

Midwest Hose & Specialty, Inc.

### Hose Specifications

Hose Type
p
LD.
3"
Working Pressu

5000 PSI

 $D_{a}D_{b}$ 415/32 Burst Pressure

Standard Salety Multiplier Applies

Length

### Verification


VALUE AND A RES	ы.	ч
41/165K		
Die Size	2	
5.12"		
	_	

Hose Serial # 6884

Coupling Method Swage

Final D.D. 5.16"

Hose Assembly Serial # 81610



10000 PSI


6 1/4 Minutes

10195 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Dannie Mclemore

Approved By: Booby Fink



### TABLE OF CONTENTS

### I. H<sub>2</sub>S Contingency Plan

- A. Scope
- B. Objective
- C. Discussion of Plan

### II. Emergency Procedures

- A. Emergency Procedures and Public Protection
- B. Emergency Procedures Implementation
- C. Simulated Blowout Control Drills

### III. Ignition Procedures

- A. Responsibility
- B. Instructions

### IV. Training Requirements

### V. Emergency Equipment

### VI. Evacuation Plan

- A. General Plan
- B. Emergency Phone Lists

### VII. General Information

- A. H<sub>2</sub>S Toxicity Table
- B. Respirator Use
- C. Emergency Rescue

### H<sub>2</sub>S CONTINGENCY PLAN SECTION

### Scope:

This contingency plan provides an organized plan of action for alerting and protecting the public within an area of exposure prior to an intentional release, or following the accidental release of a potentially hazardous volume of hydrogen sulfide. The plan establishes guidelines for all personnel whose work activity may involve exposure to Hydrogen Sulfide Gas  $(H_2S)$ .

### Objective:

Prevent any and all accidents, and prevent the uncontrolled release of H<sub>2</sub>S into the atmosphere.

Provide proper evacuation procedures to cope with emergencies.

Provide immediate and adequate medical attention should an injury occur.

### Discussion of Plan:

### Suspected Problem Zones:

*Implementation:* This plan, with all details, is to be fully implemented 500' above or three days prior to drilling into the first known sour zone

Emergency Response and Public Protection Procedure: This section outlines the conditions and denotes steps to be taken in the event of an emergency.

**Emergency Equipment and Procedure:** This section outlines the safety and emergency equipment that will be required for the drilling of this well.

*Training Provisions:* This section outlines the training provisions that must be adhered to 500 feet above or three days prior to drilling into the first known sour zone.

**Emergency call lists:** Included are the telephone numbers of all persons that would need to be contacted should an H<sub>2</sub>S emergency occur.

**Briefing:** This section deals with the briefing of all persons involved with the drilling of this well.

**Public Safety:** Public Safety Personnel will be made aware of the drilling of this well.

### **EMERGENCY PROCEDURES AND PUBLIC PROTECTION SECTION**

- 1. In the event of any evidence of H<sub>2</sub>S levels above 10 ppm, take the following steps immediately:
  - A. Secure breathing apparatus.
  - B. Order non-essential personnel out of the danger zone.
  - C. Take steps to determine if the H<sub>2</sub>S level can be corrected or suppressed, and if so, proceed with normal operations.
- II. If uncontrollable conditions occur, proceed with the following:
  - A. Take steps to protect and/or remove any public downwind of the rig, including partial evacuation or isolation. Notify necessary public safety personnel and the New Mexico Oil & Gas of the situation.
  - B. Isolate area and prevent entry by unauthorized persons into the 100 ppm ROE.
  - C. Remove all personnel to the Safe Briefing Area.
  - D. Notify public safety personnel for help with maintaining roadblocks and implementing evacuation. Phone number list attached.
  - E. Determine and proceed with the best possible plan to regain control of the well. Maintain tight security and safety measures.

### III. Responsibility:

- A. The Company Approved Supervisor shall be responsible for the total implementation of the plan.
- B. The Company Approved Supervisor shall be in complete command during any emergency.
- C. The Company Approved Supervisor shall designate a back up Supervisor in the event that he/she is not available.

### EMERGENCY PROCEDURE IMPLEMENTATION

### I. Drilling or Tripping

### A. All Personnel

- 1. When alarm sounds, don escape unit and report to upwind Safe Briefing Area.
- 2. Check status of other personnel (buddy system).
- 3. Secure breathing apparatus.
- 4. Wait for orders from supervisor.

### B. Drilling Foreman

- 1. Report to the upwind Safe Briefing Area.
- 2. Don Breathing Apparatus and return to the point of release with the Tool Pusher or Driller (buddy system).
- 3. Determine the concentration of H<sub>2</sub>S.
- 4. Assess the situation and take appropriate control measures.

### C. Tool Pusher

- 1. Report to the upwind Safe Briefing Area.
- 2. Don breathing apparatus and return to the point of release with the Drilling Foreman or the Driller (buddy system).
- 3. Determine the concentration.
- 4. Assess the situation and take appropriate control measures.

### D. Driller

- 1. Check the status of other personnel (in a rescue attempt, always use the buddy system).
- 2. Assign the least essential person to notify the Drilling Foreman and Tool Pusher, in the event of their absence.

3. Assume the responsibility of the Drilling Foreman and the Tool Pusher until they arrive, in the event of their absence.

# E. Derrick Man and Floor Hands

1. Remain in the upwind Safe Briefing Area until otherwise instructed by a supervisor.

# F. Mud Engineer

- 1. Report to the upwind Safe Briefing Area.
- 2. When instructed, begin check of mud for pH level and H<sub>2</sub>S level.

# G. On-site Safety Personnel

- 1. Don Breathing Apparatus.
- 2. Check status of all personnel.
- 3. Wait for instructions from Drilling Foreman or Tool Pusher.

# II. Taking a Kick

- A. All personnel report to the upwind Safe Briefing Area.
- B. Follow standard BOP procedures.

# III. Open Hole Logging

- A. All unnecessary personnel should leave the rig floor.
- B. Drilling Foreman and Safety Personnel should monitor the conditions and make necessary safety equipment recommendations.

# IV. Running Casing or Plugging

- A. Follow "Drilling or Tripping" procedures.
- B. Assure that all personnel have access to protective equipment:

# SIMULATED BLOWOUT CONTROL DRILLS

All drills will be initiated by activating alarm devices (air horn). Use one long blast on the air horn for ACTUAL and SIMULATED Blowout Control Drills. This operation will be performed by the Drilling Foreman or Tool Pusher at least one time per week for each of the following conditions, with each crew:

Drill # 1 Bottom Drilling

Drill # 2 Tripping Drill Pipe

In each of these drills, the initial reaction time to shutting in the well shall be timed as well as the total time for the crew to complete its entire pit drill assignment. The times must be recorded on the IADC Driller's Log as "Blowout Control Drill".

Drill No.:

Reaction Time to Shut-In:

minutes,

seconds.

Total Time to Complete Assignment:

minutes,

# I. Drill Overviews

- A. Drill No. 1- Bottom Drilling
  - 1. Sound the alarm immediately.
  - 2. Stop the rotary and hoist kelly joint above the rotary table.
  - 3. Stop the circulatory pump.
  - 4. Close the drill pipe rams.
  - 5. Record casing and drill pipe shut-in pressures and pit volume increases.
- B. Drill No. 2 Tripping Drill Pipe
  - Sound the alarm immediately.
  - 2. Position the upper tool joint just above the rotary table and set the slips.

- 3. Install a full opening valve or inside blowout preventor tool in order to close the drill pipe.
- 4. Close the drill pipe rams.
- 5. Record the shut-in annular pressure.

# II. Crew Assignments

# A. Drill No. 1 - Bottom Drilling

# 1. Driller

- a) Stop the rotary and hoist kelly joint above the rotary table.
- b) Stop the circulatory pump.
- c) Check flow.
- d) If flowing, sound the alarm immediately.
- e) Record the shut-in drill pipe pressure.
- f) Determine the mud weight increase needed or other courses of action.

#### 2. Derrickman

- a) Open choke line valve at BOP.
- b) Signal Floor Man # 1 at accumulator that choke line is open.
- c) Close choke and upstream valve after pipe tams have been closed.
- d) Read the shut-in annular pressure and report readings to Driller.

#### 3. Floor Man # 1

- a) Close the pipe rams after receiving the signal from the Derrickman.
- b) Report to Driller for further instructions.

# 4. Floor Man # 2

- a) Notify the Tool Pusher and Operator Representative of the H<sub>2</sub>S alarms.
- b) Check for open fires and, if safe to do so, extinguish them.
- c) Stop all welding operations.
- d) Turn-off all non-explosion proof lights and instruments.
- e) Report to Driller for further instructions.

# 5. Tool Pusher

- a) Report to the rig floor.
- b) Have a meeting with all crews.
- c) Compile and summarize all information.
- d) Calculate the proper kill weight.
- e) Ensure that proper well procedures are put into action.

# 6. Operator Representative

- a) Notify the Drilling Superintendent.
- b) Determine if an emergency exists and if so, activate the contingency plan.

# B. Drill No. 2 - Tripping Pipe

# 1. Driller

- a) Sound the alarm immediately when mud volume increase has been detected.
- b) Position the upper tool joint just above the rotary table and set slips.
- c) Install a full opening valve or inside blowout preventor tool to close the drill pipe.
- d) Check flow.

- e) Record all data reported by the crew.
- f) Determine the course of action.

#### 2. Derrickman

- a) Come down out of derrick.
- b) Notify Tool Pusher and Operator Representative.
- c) Check for open fires and, if safe to do so, extinguish them.
- d) Stop all welding operations.
- e) Report to Driller for further instructions.

# 3. Floor Man # 1

- a) Pick up full opening valve or inside blowout preventor tool and stab into tool joint above rotary table (with Floor Man # 2).
- b) Tighten valve with back-up tongs.
- c) Close pipe rams after signal from Floor Man # 2.
- d) Read accumulator pressure and check for possible high pressure fluid leaks in valves or piping.
- e) Report to Driller for further instructions.

# 4. Floor Man # 2

- a) Pick-up full opening valve or inside blowout preventor tool and stab into tool joint above rotary table (with Floor Man # 1).
- b) Position back-up tongs on drill pipe.
- c) Open choke line valve at BOP.
- d) Signal Floor Man # 1 at accumulator that choke line is open.
- e) Close choke and upstream valve after pipe rams have been closed.
- f) Check for leaks on BOP stack and choke manifold.

- g) Read annular pressure.
- h) Report readings to the Driller.

# 5. Tool Pusher

- a) Report to the rig floor.
- b) Have a meeting with all of the crews.
- c) Compile and summarize all information.
- d) See that proper well kill procedures are put into action.

# 6. Operator Representative

- a) Notify Drilling Superintendent
- b) Determine if an emergency exists, and if so, activate the contingency plan.

#### **IGNITION PROCEDURES**

# Responsibility:

The decision to ignite the well is the responsibility of the DRILLING FOREMAN in concurrence with the STATE POLICE. The State Police shall be the Incident Command on the scene of any major release. Intentional ignition must be coordinated with the NMOCD and local officials. In the event the Drilling Foreman is incapacitated, it becomes the responsibility of the RIG TOOL PUSHER. This decision should be made only as a last resort and in a situation where it is clear that:

- 1. Human life and property are endangered.
- 2. There is no hope of controlling the blowout under the prevailing conditions.

If time permits, notify the main office, but do not delay if human life is in danger. Initiate the first phase of the evacuation plan.

# Instructions for Igniting the Well:

- 1. Two people are required for the actual igniting operation. Both men must wear self-contained breathing apparatus and must use a full body harness and attach a retrievable safety line to the D-Ring in the back. One man must monitor the atmosphere for explosive gases with the LEL monitor, while the Drilling Foreman is responsible for igniting the well.
- 2. The primary method to ignite is a 25mm flare gun with a range of approximately 500 feet.
- 3. Ignite from upwind and do not approach any closer than is warranted.
- 4. Select the ignition site best suited for protection and which offers an easy escape route.
- 5. Before igniting, check for the presence of combustible gases.
- 6. After igniting, continue emergency actions and procedures as before.
- 7. All unassigned personnel will limit their actions to those directed by the Drilling Foreman.

**NOTE:** After the well is ignited, burning Hydrogen Sulfide will convert to Sulfur Dioxide (SO<sub>2</sub>), which is also highly toxic. Do not assume the area is safe after the well is ignited.

# TRAINING REQUIREMENTS

When working in an area where Hydrogen Sulfide (H<sub>2</sub>S) might be encountered, definite training requirements must be carried out. The Company Supervisor will ensure that all personnel at the well site, whether regularly assigned, contracted, or employed on an unscheduled basis, have had adequate training by a qualified instructor in the following:

- 1. Hazards and Characteristics of Hydrogen Sulfide and Sulfur Dioxide.
  - 2. Physicals effects of Hydrogen Sulfide on the human body.
  - 3. Toxicity of Hydrogen Sulfide and Sulfur Dioxide.
  - 4. H<sub>2</sub>S detection, emergency alarm and sensor location.
  - 5. Emergency rescue.
  - 6. First aid and artificial resuscitation.
  - 7. The effects of Hydrogen Sulfide on metals.
  - 8. Location safety.

In addition, Supervisory Personnel will be trained in the following areas:

- 1. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
- 2. Corrective action and shut-in procedures when drilling or reworking a well as blowout prevention and well control procedures.
- 3. The contents and requirements of the H<sub>2</sub>S Drilling Operations Contingency Plan and the Public Protection Plan.

Service company personnel and visiting personnel must be notified if the zone contains H<sub>2</sub>S, and each service company must provide adequate training and equipment for their employees before they arrive at the well site.

#### **EMERGENCY EQUIPMENT**

As stated in the BLM Onshore Order 6, for wells located in a known  $H_2S$  areas,  $H_2S$  equipment will be rigged up after setting surface casing. For wells located inside known  $H_2S$  areas, the flare pit will be located 150' from the location and for wells located outside known  $H_2S$  areas, the flare pit will be located 100' away from the location. (See page 6 of Survey plat package and diagram B or C.)

It is not anticipated that any  $H_2S$  is in the area, however in the event that  $H_2S$  is encountered, the attached  $H_2S$  Contingency Plan will be implemented. (Please refer to diagrams B or C for choke manifold and closed loop system layout.) See  $H_2S$  location layout diagram for location of all  $H_2S$  equipment on location.

All  $H_2S$  safety equipment and systems will be installed, tested and be operational when drilling reaches a depth of 500' above, or three days prior to penetrating a known formation containing  $H_2S$ .

# Lease Entrance Sign:

Caution signs should be located at all roads providing direct access to the location. Signs shall have a yellow background with black lettering and contain the words "CAUTION" and "POISON GAS" that is legible from a distance of at least 50 feet.

# LEASE NAME CAUTION – POTENTIAL POISON GAS HYDROGEN SULFIDE NO ADMITTANCE WITHOUT AUTHORIZATION

# Windsocks or Wind Streamers:

- A minimum of two 10" windsocks located at strategic locations so that they
  may be seen from any point on location.
- Wind streamers (if preferred) should be placed at various locations on the well site to ensure wind consciousness at all times. (Corners of location)

# **Hydrogen Sulfide Detector and Alarms:**

• H<sub>2</sub>S monitors with alarms will be located on the rig floor, at the cellar, and at the mud pits. These monitors will be set to alarm at 10 PPM with a red light and to alarm at 15 PPM with a red light and audible alarm.

# Well Condition Flags:

The Well Condition flags should be located at all roads providing direct access to the location. It should have three (3) color coded flags (green, yellow and red) that will be used to denote the following location conditions:

GREEN – Normal Operating Conditions YELLOW – Potential Danger RED – Danger, H<sub>2</sub>S Gas Present

# **Respiratory Equipment:**

- Fresh air breathing equipment should be placed at the company supervision trailer and the safe briefing areas and should include the following:
  - A minimum of two SCBA's at each briefing area and the supervisor company supervision trailer.
  - Enough air line units to operate safely, anytime the H<sub>2</sub>S concentration reaches the IDLH level (100 PPM).
  - Cascade system with enough breathing air hose and manifolds to reach the rig floor, the derrickman and the other operation areas.

# Fire Extinguishers:

Adequate fire extinguishers shall be located at strategic locations.

# Mud Program:

The mud program has been designed to minimize the volume of  $H_2S$  circulated to the surface. Proper mud weight, safe drilling practices and the use of  $H_2S$  scavengers will minimize hazards when penetrating  $H_2S$  bearing zones.

# Metallurgy:

All drill strings, casing, tubing, wellhead; blowout preventer, drilling spools, kill lines, choke manifold and lines, and valves shall be suitable for H<sub>2</sub>S service.

# **Well Control Equipment:**

- Flare Line (See page 6 of survey plat package for flare line reference).
- Choke manifold (See diagram B or C and refer to H2S location diagram for location of important H2S safety items).
- Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing units.
- Auxiliary equipment may include, if applicable, annular preventer & rotating head.

# **Communication Equipment:**

• Proper communication equipment such as cell phones or 2 – way radios should be available for communication between the company man's trailer, rig floor and tool pusher's trailer.

# Well Testing:

• There will be no drill stem testing.

# **Evacuation Plan:**

- Evacuation routes should be established prior to spudding the well.
- Should be discussed with all rig personnel.

# **Designated Areas:**

# Parking and Visitor area:

- All vehicles are to be parked at a pre-determined safe distance from the wellhead.
- A smoking area will be designated at a pre-determined safe distance from the wellhead and any other possible flammable areas.

# Safe Briefing Areas:

 Two Safe Briefing Areas shall be designated on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds or they are at a 180 degree angle if wind directions tend to shift in the area.  Personal protective equipment should be stored at both briefing areas or if a moveable cascade trailer is used, it should be kept upwind of existing winds. When wind is from the prevailing direction, both briefing areas should be accessible.

# NOTE:

 Additional equipment will be available at Indian Fire and Safety in Hobbs, NM or at Total Safety in Hobbs, NM.

# **EVACUATION PLAN**

#### General Plan

The direct lines of action to protect the public from hazardous gas situations are as follows:

- 1. When the company approved supervisor (Drilling Foremen, Tool Pusher or Driller) determine that Hydrogen Sulfide gas cannot be limited to the well location, and the public will be involved, he will activate the evacuation plan. Escape routes are noted on the Area Map.
- 2. Company safety personnel or designee will notify the appropriate local government agency that a hazardous condition exists and evacuation needs to be implemented.
- 3. Company approved safety personnel that have been trained in the use of the proper emergency equipment will be utilized.
- 4. Law enforcement personnel (State Police, Local Police Department, Fire Department, and the Sheriff's Department) will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.

NOTE: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

5. After the discharge of gas has been controlled, Company approved safety personnel will determine when the area is safe for re-entry.

# See Emergency Action Plan

# **Contacting Authorities**

BOPCO L.P. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. (Operator Name)'s response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

# H<sub>2</sub>S CONTINGENCY PLAN EMERGENCY CONTACTS

BOPCO L. P. Midland Office   Key Personnel   Key Personnel	H23 CONT	INGENCIFEAN LINERGENCI C	ONTACTS	
Name	BOPCO L.P. Midland	432-683-2277		
Stephen Martinez   Drilling & Completions Manager Charles Warne   Division Engineer   432-312-4431	Key Personnel			
Charles Warne   Division Engineer   432-312-4431   Don Wood   Division Drilling Specialist   432-266-2674   Leo Bojorquez   Area Drilling Superintendent   702-280-4424   Chris Giese   Engineer   432-661-7328   Chris Volek   Engineer   785-979-2643   Brian Braun   Engineer   210-683-9849   Jeremy Braden   Engineer   432-312-1113   Kevin Burns   Engineer   432-312-1113   Kevin Burns   Engineer   432-934-5499   Artesia   Ambulance   911   State Police   575-746-2703   Sheriff's Office   575-746-2703   Sheriff's Office   575-746-2703   Sheriff's Office   575-746-2701   Local Emergency Planning Committee   575-746-2701   Local Emergency Planning Committee   575-746-2701   Local Emergency Planning Committee   575-748-1283   Carlsbad   Ambulance   911   State Police   575-885-3137   City Police   575-885-2111   Sheriff's Office   575-887-7551   Fire Department   575-887-7551   Fire Department   575-887-7551   Fire Department   575-887-6544   US Bureau of Land Management   505-476-9600   24 Hour   505-476-9635   National Emergency Response Center (Washington, DC)   800-424-8802   Other   432-550-6202 (Permian Basin)   Flight For Life - 4000 24th St. Lubbock, Texas   806-743-9911   Aerocare - R3, Box 49f, Lubbock, Texas   806-743-8923   Med Flight Air Amb - 2301 Yale Blvd SE #D3, Albuq, NM   505-842-4493   Indian Fire and Safety - 3317 NW Cnty Rd, Hobbs, NM   505-842-4493   Indian Fire and Safety - 3317 NW Cnty Rd, Hobbs, NM   505-842-4493   Indian Fire and Safety - 3317 NW Cnty Rd, Hobbs, NM   505-842-4493   Indian Fire and Safety - 3317 NW Cnty Rd, Ho				
Don Wood   Division Drilling Specialist   432-266-2674   Leo Bojorquez   Area Drilling Superintendent   702-280-4424   Area Drilling Superintendent   785-979-2643   Brian Braun   Engineer   210-683-9849   Brian Braun   Engineer   432-312-1113   Engineer   432-312-1113   Engineer   432-934-5499   Artesia   Ambulance   911   State Police   575-746-2703   Steriff's Office   575-746-2703   Steriff's Office   575-746-2703   Steriff's Office   575-746-2701   Local Emergency Planning Committee   575-746-2701   Local Emergency Planning Committee   575-746-2702   Steriff's Office   575-746-2703   Steriff's Office   575-887-3137   City Police   575-885-3137   City Police   575-885-3111   Steriff's Office   575-887-7551   Steriff's Office   575-887-7551   Steriff's Office   575-887-7551   Steriff's Office   575-887-7551   Steriff's Office   575-887-6544   US Bureau of Land Management   575-887-6544   Orea Description   505-476-9600   Steriff of the Properior   505-476-9635   Steriff of the Properior	Stephen Martinez		432-556-0262	
Chris Giese	Charles Warne	Division Engineer	432-312-4431	
Chris Giese	Don Wood	Division Drilling Specialist	· ·	
Chris Volek         Engineer         785-979-2643           Brian Braun         Engineer         210-683-9849           Jeremy Braden         Engineer         432-312-1113           Kevin Burns         Engineer         432-934-5499           Artesia		Area Drilling Superintendent	702-280-4424	
Brian Braun	Chris Giese	Engineer	432-661-7328	
Artesia	Chris Volek	Engineer	785-979-2643	
Artesia         Ambulance         911           State Police         575-746-2703           City Police         575-746-2703           Sheriff's Office         575-746-2701           Fire Department         575-746-2701           Local Emergency Planning Committee         575-746-2122           New Mexico Oil Conservation Division         575-748-1283           Carlsbad         4Ambulance         911           State Police         575-885-3137           City Police         575-885-2111           Sheriff's Office         575-887-7551           Fire Department         575-887-3798           Local Emergency Planning Committee         575-887-3798           Local Emergency Planning Committee         575-887-6544           US Bureau of Land Management         575-887-6544           US Bureau of Land Management         575-887-6544           New Mexico Emergency Response Commission (Santa Fe)         505-476-9600           24 Hour         505-827-9126           New Mexico State Emergency Operations Center         505-476-9635           National Emergency Response Center (Washington, DC)         800-424-8802           Other         Wild Well Control         432-550-6202 (Permian Basin)           Flight For Life – 40000 24th St. Lubbock, Texas	Brian Braun	Engineer	210-683-9849	
Artesia         Ambulance         911           State Police         575-746-2703           City Police         575-746-2703           Sheriff's Office         575-746-2701           Fire Department         575-746-2701           Local Emergency Planning Committee         575-746-2122           New Mexico Oil Conservation Division         575-748-1283           Carlsbad         4Ambulance         911           State Police         575-885-3137           City Police         575-885-2111           Sheriff's Office         575-887-7551           Fire Department         575-887-3798           Local Emergency Planning Committee         575-887-3798           Local Emergency Planning Committee         575-887-6544           US Bureau of Land Management         575-887-6544           US Bureau of Land Management         575-887-6544           New Mexico Emergency Response Commission (Santa Fe)         505-476-9600           24 Hour         505-827-9126           New Mexico State Emergency Operations Center         505-476-9635           National Emergency Response Center (Washington, DC)         800-424-8802           Other         Wild Well Control         432-550-6202 (Permian Basin)           Flight For Life – 40000 24th St. Lubbock, Texas	Jeremy Braden	Engineer	432-312-1113	
Ambulance         911           State Police         575-746-2703           City Police         575-746-2703           Sheriff's Office         575-746-9888           Fire Department         575-746-2121           Local Emergency Planning Committee         575-746-2122           New Mexico Oil Conservation Division         575-748-1283           Carlsbad         911           State Police         575-885-3137           City Police         575-885-2111           Sheriff's Office         575-887-7551           Fire Department         575-887-3798           Local Emergency Planning Committee         575-887-6544           US Bureau of Land Management         575-887-6544           New Mexico Emergency Response Commission (Santa Fe)         505-476-9600           24 Hour         505-827-9126           New Mexico State Emergency Operations Center         505-476-9635           National Emergency Response Center (Washington, DC)         800-424-8802           Other         Wild Well Control         432-580-3544 or 432-570-5300 (Permian Basin)           Flight For Life - 4000 24th St. Lubbock, Texas         806-743-9911           Aerocare - R3, Box 49f, Lubbock, Texas         806-747-8923           Med Flight Air Amb - 2301 Yale Blvd SE #D3, Albuq., NM			432-934-5499	
State Police         575-746-2703           City Police         575-746-2703           Sheriff's Office         575-746-9888           Fire Department         575-746-2701           Local Emergency Planning Committee         575-746-2122           New Mexico Oil Conservation Division         575-748-1283           Carlsbad         Ambulance           Ambulance         911           State Police         575-885-3137           City Police         575-885-2111           Sheriff's Office         575-887-7551           Fire Department         575-887-3798           Local Emergency Planning Committee         575-887-6544           US Bureau of Land Management         575-887-6544           New Mexico Emergency Response Commission (Santa Fe)         505-476-9600           24 Hour         505-827-9126           New Mexico State Emergency Operations Center         505-476-9635           National Emergency Response Center (Washington, DC)         800-424-8802           Other         Wild Well Control         432-580-3544 or 432-570-5300 (Permian Basin)           Cudd PressureControl         432-580-3544 or 432-570-5300 (Permian Basin)           Flight For Life – 4000 24th St. Lubbock, Texas         806-743-9911           Aerocare – R3, Box 49f, Lubbock, Texas	Artesia	•		
State Police         575-746-2703           City Police         575-746-2703           Sheriff's Office         575-746-2888           Fire Department         575-746-2122           Local Emergency Planning Committee         575-746-2122           New Mexico Oil Conservation Division         575-748-1283           Carlsbad         4Ambulance           Ambulance         911           State Police         575-885-3137           City Police         575-887-7551           Sheriff's Office         575-887-3798           Local Emergency Planning Committee         575-887-3798           Local Emergency Planning Committee         575-887-6544           US Bureau of Land Management         575-887-6544           New Mexico Emergency Response Commission (Santa Fe)         505-476-9600           24 Hour         505-827-9126           New Mexico State Emergency Operations Center         505-476-9635           National Emergency Response Center (Washington, DC)         800-424-8802           Other         Wild Well Control         432-550-6202 (Permian Basin)           Cudd PressureControl         432-580-3544 or 432-570-5300 (Permian Basin)           Flight For Life - 4000 24th St. Lubbock, Texas         806-743-9911           Aerocare - R3, Box 49F, Lubbock, Texas	Ambulance		911	
City Police         575-746-2703           Sheriff's Office         575-746-9888           Fire Department         575-746-2701           Local Emergency Planning Committee         575-746-2122           New Mexico Oil Conservation Division         575-748-1283           Carlsbad         Ambulance           Ambulance         911           State Police         575-885-3137           City Police         575-885-2111           Sheriff's Office         575-887-7551           Fire Department         575-887-3798           Local Emergency Planning Committee         575-887-6544           US Bureau of Land Management         575-887-6544           New Mexico Emergency Response Commission (Santa Fe)         505-476-9600           24 Hour         505-827-9126           New Mexico State Emergency Operations Center         505-476-9635           National Emergency Response Center (Washington, DC)         800-424-8802           Other         Wild Well Control         432-550-6202 (Permian Basin)           Cudd PressureControl         432-580-3544 or 432-570-5300 (Permian Basin)           Flight For Life - 4000 24th St. Lubbock, Texas         806-743-9911           Aerocare - R3, Box 49F, Lubbock, Texas         806-743-9911           Aerocare - R3, Box 49F, Lubbock, Texas	State Police		575-746-2703	
Size	City Police		575-746-2703	
Carlsbad         911           State Police         575-885-3137           City Police         575-885-2111           Sheriff's Office         575-887-7551           Fire Department         575-887-3798           Local Emergency Planning Committee         575-887-6544           US Bureau of Land Management         575-887-6544           New Mexico Emergency Response Commission (Santa Fe)         505-476-9600           24 Hour         505-827-9126           New Mexico State Emergency Operations Center         505-476-9635           National Emergency Response Center (Washington, DC)         800-424-8802           Other         Wild Well Control         432-550-6202 (Permian Basin)           Cudd PressureControl         432-580-3544 or 432-570-5300 (Permian Basin)           Flight For Life – 4000 24th St. Lubbock, Texas         806-743-9911           Aerocare – R3, Box 49F, Lubbock, Texas         806-747-8923           Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM         505-842-4433           S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM         505-842-4949           Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM         575-393-3093	Sheriff's Office	•	575-746-9888	
Carlsbad         911           State Police         575-885-3137           City Police         575-885-2111           Sheriff's Office         575-887-7551           Fire Department         575-887-3798           Local Emergency Planning Committee         575-887-6544           US Bureau of Land Management         575-887-6544           New Mexico Emergency Response Commission (Santa Fe)         505-476-9600           24 Hour         505-827-9126           New Mexico State Emergency Operations Center         505-476-9635           National Emergency Response Center (Washington, DC)         800-424-8802           Other         Wild Well Control         432-550-6202 (Permian Basin)           Cudd PressureControl         432-580-3544 or 432-570-5300 (Permian Basin)           Flight For Life – 4000 24th St. Lubbock, Texas         806-743-9911           Aerocare – R3, Box 49F, Lubbock, Texas         806-747-8923           Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM         505-842-4433           S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM         505-842-4949           Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM         575-393-3093	Fire Department	· ·	575-746-2701	
Carlsbad         911           State Police         575-885-3137           City Police         575-885-2111           Sheriff's Office         575-887-7551           Fire Department         575-887-3798           Local Emergency Planning Committee         575-887-6544           US Bureau of Land Management         575-887-6544           New Mexico Emergency Response Commission (Santa Fe)         505-476-9600           24 Hour         505-827-9126           New Mexico State Emergency Operations Center         505-476-9635           National Emergency Response Center (Washington, DC)         800-424-8802           Other         Wild Well Control         432-550-6202 (Permian Basin)           Cudd PressureControl         432-580-3544 or 432-570-5300 (Permian Basin)           Flight For Life – 4000 24th St. Lubbock, Texas         806-743-9911           Aerocare – R3, Box 49F, Lubbock, Texas         806-747-8923           Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM         505-842-4433           S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM         505-842-4949           Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM         575-393-3093	Local Emergency Plant	anning Committee	575-746-2122	
Ambulance       911         State Police       575-885-3137         City Police       575-885-2111         Sheriff's Office       575-887-7551         Fire Department       575-887-3798         Local Emergency Planning Committee       575-887-6544         US Bureau of Land Management       575-887-6544         New Mexico Emergency Response Commission (Santa Fe)       505-476-9600         24 Hour       505-827-9126         New Mexico State Emergency Operations Center       505-476-9635         National Emergency Response Center (Washington, DC)       800-424-8802         Other       432-550-6202 (Permian Basin)         Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	New Mexico Oil Con	servation Division	575-748-1283	
Ambulance         911           State Police         575-885-3137           City Police         575-885-2111           Sheriff's Office         575-887-7551           Fire Department         575-887-3798           Local Emergency Planning Committee         575-887-6544           US Bureau of Land Management         575-887-6544           New Mexico Emergency Response Commission (Santa Fe)         505-476-9600           24 Hour         505-827-9126           New Mexico State Emergency Operations Center         505-476-9635           National Emergency Response Center (Washington, DC)         800-424-8802           Other         Wild Well Control         432-550-6202 (Permian Basin)           Cudd PressureControl         432-580-3544 or 432-570-5300 (Permian Basin)           Flight For Life – 4000 24th St. Lubbock, Texas         806-743-9911           Aerocare – R3, Box 49F, Lubbock, Texas         806-747-8923           Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM         505-842-4433           S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM         505-842-4949           Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM         575-393-3093	Carlsbad			
State Police       575-885-3137         City Police       575-885-2111         Sheriff's Office       575-887-7551         Fire Department       575-887-3798         Local Emergency Planning Committee       575-887-6544         US Bureau of Land Management       575-887-6544         New Mexico Emergency Response Commission (Santa Fe)       505-476-9600         24 Hour       505-827-9126         New Mexico State Emergency Operations Center       505-476-9635         National Emergency Response Center (Washington, DC)       800-424-8802         Other       Wild Well Control       432-550-6202 (Permian Basin)         Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093			911	
City Police       575-885-2111         Sheriff's Office       575-887-7551         Fire Department       575-887-3798         Local Emergency Planning Committee       575-887-6544         US Bureau of Land Management       575-887-6544         New Mexico Emergency Response Commission (Santa Fe)       505-476-9600         24 Hour       505-827-9126         New Mexico State Emergency Operations Center       505-476-9635         National Emergency Response Center (Washington, DC)       800-424-8802         Other       Wild Well Control       432-550-6202 (Permian Basin)         Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	State Police		575-885-3137	
Sheriff's Office       575-887-7551         Fire Department       575-887-3798         Local Emergency Planning Committee       575-887-6544         US Bureau of Land Management       575-887-6544         New Mexico Emergency Response Commission (Santa Fe)       505-476-9600         24 Hour       505-827-9126         New Mexico State Emergency Operations Center       505-476-9635         National Emergency Response Center (Washington, DC)       800-424-8802         Other       Wild Well Control       432-550-6202 (Permian Basin)         Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	City Police		575-885-2111	
S75-887-3798   Local Emergency Planning Committee	Sheriff's Office		575-887-7551	
New Mexico Emergency Response Commission (Santa Fe)       505-476-9600         24 Hour       505-827-9126         New Mexico State Emergency Operations Center       505-476-9635         National Emergency Response Center (Washington, DC)       800-424-8802         Other       432-550-6202 (Permian Basin)         Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	Fire Department		575-887-3798	
New Mexico Emergency Response Commission (Santa Fe)       505-476-9600         24 Hour       505-827-9126         New Mexico State Emergency Operations Center       505-476-9635         National Emergency Response Center (Washington, DC)       800-424-8802         Other       432-550-6202 (Permian Basin)         Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	Local Emergency Planning Committee		575-887-6544	
24 Hour       505-827-9126         New Mexico State Emergency Operations Center       505-476-9635         National Emergency Response Center (Washington, DC)       800-424-8802         Other       432-550-6202 (Permian Basin)         Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	US Bureau of Land Management575-887-6544			
24 Hour       505-827-9126         New Mexico State Emergency Operations Center       505-476-9635         National Emergency Response Center (Washington, DC)       800-424-8802         Other       432-550-6202 (Permian Basin)         Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	New Mexico Emerge	ncy Response Commission (Santa Fe	505-476-9600	
National Emergency Response Center (Washington, DC)       800-424-8802         Other         Wild Well Control       432-550-6202 (Permian Basin)         Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093		·		
Other           Wild Well Control         432-550-6202 (Permian Basin)           Cudd PressureControl         432-580-3544 or 432-570-5300 (Permian Basin)           Flight For Life – 4000 24th St. Lubbock, Texas         806-743-9911           Aerocare – R3, Box 49F, Lubbock, Texas         806-747-8923           Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM         505-842-4433           S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM         505-842-4949           Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM         575-393-3093	New Mexico State Er	505-476-9635		
Wild Well Control       432-550-6202 (Permian Basin)         Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	National Emergency	Response Center (Washington, DC)_	800-424-8802	
Cudd PressureControl       432-580-3544 or 432-570-5300 (Permian Basin)         Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	<u>Other</u>			
Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	Wild Well Control	432	2-550-6202 (Permian Basin)	
Flight For Life – 4000 24th St. Lubbock, Texas       806-743-9911         Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093		ol432-580-3544 or 432	2-570-5300 (Permian Basin)	
Aerocare – R3, Box 49F, Lubbock, Texas       806-747-8923         Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093				
Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM       505-842-4433         S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM       505-842-4949         Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM       575-393-3093	Aerocare – R3, Box 49F, Lubbock, Texas806-747-89			
S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM505-842-4949 Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM575-393-3093	Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM505-842-443			
Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM575-393-3093				
	Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM575-393-3093			
710"00E"LO[0	Total Safety – 3229 Industrial Dr., Hobbs, NM 575-392-29			

# TOXIC EFFECTS OF HYDROGEN SULFIDE

Hydrogen Sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 PPM, which is .001% by volume. Hydrogen Sulfide is heavier than air (specific gravity = 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in Table I. Physical effects at various Hydrogen Sulfide exposure levels are shown in Table II.

Table I - TOXICITY OF VARIOUS GASES

Common	Chemical	Specific	Threshold	Hazardous	Lethal
Name	Formula	Gravity	Limit	Limit	Concentration
		(SC=1)	(1)	(2)	(3)
Hydrogen Cyanide	HCN	0.94	10 PPM	150 PPM/HR	300 PPM
Hydrogen Sulfide	H2S	1.18	10 PPM	250 PPM/HR	600 PPM
Sulfur Dioxide	SO2	2.21	5 PPM		1000 PPM
Chlorine	CL2	2.45	1 PPM	4 PPM/HR	1000 PPM
Carbon Monoxide	СО	0.97	50 PPM	400 PPM/HR	1000 PPM
Carbon Dioxide	CO2	1.52	5000 PPM	5%	10%
Methane	CH4	0.55	90,000 PPM	Combustible in air	Above 5%

- 1) Threshold Limit Concentration at which it is believed that all worker may be repeatedly exposed day after day without adverse effects.
- 2) Hazardous Limit Concentration that will cause death with short-term exposure.
- 3) Lethal Concentration Concentration that will cause death with short-term exposure.

Table II – PHYSICAL EFFECTS OF HYDROGEN SULFIDE

Percent (%)	PPM	Concentration Grains 100 STD. FT3*	Physical Effects
0.001	< 10	00.65	Obvious & unpleasant odor.
0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kills smell in 3-15 minutes. May sting eyes & throat.
0.020	200	12.96	Kills smell shortly; stings eyes & throat.
0.050	500	32.96	Dizziness; Breathing ceases in a few minutes. Needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; Death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; Followed by death within minutes.

• At 15.00 PSIA and 60° F.

# **USE OF SELF-CONTAINED BREATHING APPARATUS**

- Anyone who uses an SCBA shall: Be approved by a physician or licensed health care practitioner; Pass a fit test; Be trained in donning and doffing, proper use, including how to ensure a proper face seal, conducting an inspection of the SCBA, and conduct proper maintenance.
- 2. Such items as facial hair (beard or sideburns) and eyeglasses will not allow a proper face mask seal.
- 3. Anyone reasonably expected to wear SCBA's shall have these items removed before entering a toxic atmosphere.
- 4. A special mask with a mount for prescription glasses must be obtained for anyone who must wear eyeglasses in order to see while using an SCBA.
- 5. SCBA's should be worn in H<sub>2</sub>S concentrations above 10 PPM.

# RESCUE & FIRST AID FOR H2S POISONING


# DO NOT PANIC - REMAIN CALM - THINK

- 1. Hold your breath do not inhale first.
- Put on SCBA.
- 3. Remove victim(s) to fresh air as quickly as possible. Go upwind from source or at right angle to the wind. Do not go downwind.
- 4. Briefly apply chest pressure using arm lift method of artificial respiration to clean victim's lungs and to avoid inhaling any toxic gas directly from victim's lungs.
- 5. Provide artificial respiration if needed.
- 6. Provide for prompt transportation to the hospital and continue giving artificial respiration if needed.
- 7. Inform hospital/medical facilities of the possibility of H2S gas poisoning before they treat.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration and CPR, as well as first aid for eyes and skin contact with liquid H<sub>2</sub>S.

# Proposed H2S Safety Schematic

- 1) Location of windsocks.
- 4) Terrain of surrounding area (Please refer to page 2 of survey plat package also see point 11 of multi-surface use plan)
- 2) Location of H2S alarms
- 5) Location of flare line(s) and pit(s) (Please refer to diagram 2 choke manifold diagram and or page six of survey plat packet)
- 3) Location of briefing areas.
- 6) Location of caution and/or danger signs.
- (7) Location of Breathing Equipment



# **Location On-Site Notes**

Location on-site conducted by Cecil Watkins-BOPCO L.P., Stephen Martinez-BOPCO L.P., Carlos Cruz-BOPCO, L.P., Bill Franks-BOPCO, L.P., Cody Layton-BLM, and Robert Gomez-Basin Survey on 3/20/2012. The James Ranch Unit 12 Pad added additional footage to the east and west sides of existing location. Surface footage calls are at 1434' FNL & 1495' FEL of Section 21,T22S-R30E. Location layout is as follows: v-door will face the west, frac pad will be on northeast corner, access road will enter location from the east corner and topsoil will be stockpiled to the north side of location.

SECTION 21, TOWNSHIP 22 SOUTH, RANGE 30 EAST, N.M.P.M., NEW MEXICO. EDDY COUNTY, EXISTING PAD DRILLING ISLAND 1 27 28 29 30 31 32 33 O O O O O O O 1 2 3 4 5 O O O O O O O O 34 35 36 37 38 39 40 41 42 43 44 45 O O O O O 11 12 13 14 15 16 17 18 O O O O O O O O METER SLOT 37 = JAMES RANCH UNIT DI1 164H 100 100 200 FEET SCALE: 1" = 100' REF: JAMES RANCH UNIT DI1 164H / WELL PAD TOPO THE JAMES RANCH UNIT DI1 164H LOCATED 1434' FROM THE NORTH LINE AND 1495' FROM THE EAST LINE OF SECTION 21, TOWNSHIP 22 SOUTH, RANGE 30 EAST, (575) 393-7316 - Office (575) 392-2206 - Fax P.O. Box 1786 1120 N. West County Rd. (575) 393-7316 Hobbs, New Mexico 88241 basinsurveys.com N.M.P.M., EDDY COUNTY, NEW MEXICO.

1

Survey Date: 10-17-2013

Sheet 1 of 1 Sheets

**PtA**₩® By: **J. SMALL** Date: 08-09-2013

W.O. Number: DI1 WEL

#### MULTI-POINT SURFACE USE PLAN

#### NAME OF WELL: James Ranch Unit DI1 164H

LEGAL DESCRIPTION

SURFACE: 1434' FNL, 1495' FEL, Section 21, T22S, R30E, Eddy County, NM.

BHL: 660' FSL, 330' FEL, Section 23, T22S, R30E, Eddy County, NM.

# **POINT 1: EXISTING ROADS**

A) Proposed Well Site Location:

See Form C-102 (Survey Plat).

B) Existing Roads:

From the junction of Hwy 128 and Cimarron, go north on Cimarron for approximately 6.2 miles to lease road. On the lease road go southwesterly 0.2 miles turning northwesterly 1.3 miles to proposed well location.

C) Existing Road Maintenance or Improvement Plan:

Existing roads will be maintained and kept in the same or better condition than before operations began. See the Well Pad Layout and Topo Map of the survey plat (Sheet 1 and 2 of plat package)

#### POINT 2: NEW PLANNED ACCESS ROUTE

A) Route Location:

There will be no new road built. (See the Well Pad Layout of the survey plat (Sheet 1 of plat package).

B) Width

14' wide

C) Maximum Grade

Grade to match existing topography or as per BLM requirements.

D) Turnout Ditches

As required by BLM stipulations.

E) Culverts, Cattle Guards, and Surfacing Equipment

If required, culverts and cattle guards will be set per BLM Specs.

#### POINT 3: LOCATION OF EXISTING WELLS

The following wells are located within a one-mile radius of the location site. See the One-Mile Radius Map (Sheet 5 of the plat package).

Existing wells	· · · · · · · · · · · · · · · · · · ·	2 (Two
Water wells		3 (Three

# POINT 4: LOCATION OF EXISTING OR PROPOSED FACILITIES

- A) Existing facilities operated by BOPCO, L.P. are located within one mile of the James Ranch Unit DI1 164H.
- B) New Facilities in the Event of Production:

New production facilities will be installed at the Legg Federal #1 (Sec. 27 T22S-R30E). A 2-7/8" steel flowline will be routed above ground from the Legg Federal #1, along the existing pipeline right-of-way, to the James Ranch #164H (JRU #12 drilling pad) location as required. The steel flowline will be suspended across low water crossing and/or areas of significant erosion as required by the BLM.

C) Rehabilitation of Disturbed Areas Unnecessary for Production:

Following the construction, those access areas required for continued production will be graded to provide drainage and minimize erosion. The areas unnecessary for use will be graded to blend in with the surrounding topography (see Point 10).

# POINT 5: LOCATION AND TYPE OF WATER SUPPLY

A) Location and Type of Water Supply

Fresh water will be hauled from Johnson Station 50 miles east of Carlsbad, New Mexico or other commercial facilities. Brine water will be hauled from commercial facilities.

B) Water Transportation System

Water hauling to the location will be over the existing and proposed roads.

# POINT 6: SOURCE OF CONSTRUCTION MATERIALS

#### A) Materials

On-site caliche will be used. If this is not sufficient, caliche will be hauled from a BLM approved pit.

# B) Land Ownership Federally Owned

# C) Materials Foreign to the Site

No construction materials foreign to this area are anticipated for this drill site.

# D) Access Roads

See the Well Pad Layout and Aerial Map of the survey plat (Sheet 1 and 4 of plat package).

# POINT 7: METHODS FOR HANDLING WASTE MATERIAL

# A) Cuttings

Cuttings will be contained in the roll off bins and disposed at R360 Environmental located in Lea County, NM.

# B) Drilling Fluids

Drilling fluids will be contained in the steel pits, frac tanks and disposed at licensed disposal sites.

#### C) Produced Fluids

Water production will be contained in the steel pits.

Hydrocarbon fluid or other fluids that may be produced during testing will be retained in test tanks. Prior to cleanup operations, any hydrocarbon material in the reserve pit will be removed by skimming or burning as the situation would dictate.

#### D) Sewage

Current laws and regulations pertaining to the disposal of human waste will be complied with.

# E) Garbage

Portable containers will be utilized for garbage disposal during the drilling of this well.

# F) Cleanup of Well Site

Upon release of the drilling rig, the surface of the drilling pad will be graded to accommodate a completion rig if electric log analysis indicate potential productive zones. Reasonable cleanup will be performed prior to the final restoration of the site.

# **POINT 8: ANCILLARY FACILITIES**

None required.

# **POINT 9: WELL SITE LAYOUT**

# A) Rig Orientation and Layout

The "Rig Layout Schematic" (Sheet 6 of plat package) shows the dimensions of the well pad, closed loop system, and the location of major rig components. Only minor leveling of the well site will be required. No significant cuts or fills will be necessary. The top soil will be stockpiled on the north side of the location.

# B) Locations of Access Road

See the Well Pad Layout, Topo Map, and Vicinity Map of the survey plat (Sheet 1, 2, and 3 of plat package).

#### C) Lining of the Pits

No reserve pits - closed loop system.

# POINT 10: PLANS FOR RESTORATION OF THE SURFACE

- A) Reserve Pit Cleanup Not applicable. Closed loop drilling fluid system will be used
- B) Restoration Plans Production Developed

BOPCO, L.P. has no plans for interim reclamation to allow for additional wells to be drilled on this pad

# C) Restoration Plans - No Production Developed

BOPCO, L.P. has no plans for interim reclamation to allow for additional wells to be drilled on this pad

# **POINT 11: OTHER INFORMATION**

# A) On-Site

Location on-site conducted by Cecil Watkins-BOPCO L.P., Stephen Martinez-BOPCO L.P., Carlos Cruz-BOPCO, L.P., Bill Franks-BOPCO, L.P., Cody Layton-BLM, and Robert Gomez-Basin Survey on 3/20/2012. The James Ranch Unit 12 Pad added additional footage to the east and west sides of existing location. Surface footage calls are at 1434' FNL & 1495' FEL of Section 21,T22S-R30E. Location layout is as follows: v-door will face the west, frac pad will be on northeast corner, access road will enter location from the east corner and topsoil will be stockpiled to the north side of location.

B) Soil

Caliche and sand.

C) Vegetation

Sparse, primarily grasses and mesquite with very little grass.

D) Surface Use

Primarily grazing.

E) Surface Water

There are no ponds, lakes, streams or rivers within several miles of the wellsite.

F) Water Wells

There are three water wells located within a 1 mile radius of the proposed location.

G) Residences and Buildings

None in the immediate vicinity.

H) Historical Sites

None observed.

I) Archeological Resources

No independent archeological survey has been done. This pad location is located in the area covered by Memorandum of Agreement – Permian Basin. The James Ranch 12 Pad is covered by a blanketed MOA for the entire Drilling Island. Any location or construction conflicts will be resolved before construction begins. Please see diagram 4 for flowline route.

# J) Surface Ownership

The well site is on federally owned land. There will be no new road required for this location.

K) Well signs will be posted at the drilling site.

# L) Open Pits

No open pits will be used for drilling or production. Any open top tanks will be netted.

#### M) Terrain

Slightly rolling hills.

# POINT 12: OPERATOR'S FIELD REPRESENTATIVE

(Field personnel responsible for compliance with development plan for surface use).

DRILLING Stephen Martinez Box 2760 Midland, Texas 79702 (432) 683-2277 PRODUCTION
Gary Fletcher
3104 East Green Street
Carlsbad, New Mexico 88220
(575) 887-7329

Fritz Schoch Box 2760 Midland, Texas 79702 (432) 683-2277

**WBM** 

# PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:
LEASE NO.:
WELL NAME & NO.:
SURFACE HOLE FOOTAGE:
BOTTOM HOLE FOOTAGE
LOCATION:
COUNTY:
BOPCO, L.P.
NMLC-064827A
James Ranch Unit DI 1 164H
1434' FNL & 1495' FEL
0660' FSL & 0330' FEL Sec. 23, T. 22 S., R 30 E.
Section 21, T. 22 S., R 30 E., NMPM
Eddy County, New Mexico

# TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

☐ General Provisions
Permit Expiration
Archaeology, Paleontology, and Historical Site
Noxious Weeds
Special Requirements
Lesser Prairie-Chicken Timing Stipulations
Ground-level Abandoned Well Marker
Commercial Well Determination
Unit Well Sign Specs
Cave/Karst
☐ Construction
Notification
Topsoil
Closed Loop System
Federal Mineral Material Pits
Well Pads
Roads
Road Section Diagram
Drilling  Coment Paguirements
Cement Requirements
H2S Requirements
R-111-P-Potash
High Cave/Karst
Logging Requirements
Waste Material and Fluids
☐ Production (Post Drilling)
Well Structures & Facilities
Pipelines
Interim Reclamation
Final Abandanment & Declaration

# 1. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

# II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

# III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

# IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

# V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

# Ground-level Abandoned Well Marker to avoid raptor perching:

Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

# VI. SPECIAL REQUIREMENT(S)

# **Cave and Karst**

\*\* Depending on location, additional Drilling, Casing, and Cementing procedures may be required by engineering to protect critical karst groundwater recharge areas.

# **Cave/Karst Surface Mitigation**

The following stipulations will be applied to minimize impacts during construction, drilling and production.

# **Construction:**

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

# No Blasting:

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

# **Pad Berming:**

The pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the pad. All sides will be bermed.

# **Tank Battery Liners and Berms:**

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

# **Leak Detection System:**

A method of detecting leaks is required. The method could incorporate gauges to measure loss, situating values and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

# **Automatic Shut-off Systems:**

Automatic shut off, check values, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

# Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and ground water concerns:

# **Rotary Drilling with Fresh Water:**

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

# **Directional Drilling:**

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

#### **Lost Circulation:**

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cavebearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

# **Abandonment Cementing:**

Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

#### **Pressure Testing:**

Annual pressure monitoring will be performed by the operator on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

# **Drilling:**

# **Commercial Well Determination**

A commercial well determination shall be submitted after production has been established for at least six months.

# **Unit Wells**

The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation, but will replace the unit number with the participating area number when the sign is replaced.

# VII. CONSTRUCTION

# A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

#### B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

# C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

# D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

#### E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

# F. EXCLOSURE FENCING (CELLARS & PITS)

# **Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

# G. ON LEASE ACCESS ROADS

# Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

# Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

#### Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

#### Ditching

Ditching shall be required on both sides of the road.

# Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

# Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

# **Cross Section of a Typical Lead-off Ditch**



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

# Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: 
$$\frac{400'}{4\%}$$
 + 100' = 200' lead-off ditch interval

# **Cattleguards**

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

#### **Fence Requirement**

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

# **Construction Steps**

- 1. Salvage topsoil
- 2. Construct road 4. Revege
- 3. Redistribute topsoil4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

# VIII. DRILLING

# A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

# **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is encountered in quantities greater than 10 PPM the well shall be shut in and H2S equipment shall be installed and flare line must be extended pursuant to Onshore Oil and Gas Order #6. Report measured values and formation to the BLM. After detection, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. If the drilling rig is removed without approval an Incident of Non-Compliance will be written and will be a "Major" violation.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
- 4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

#### B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. IF OPERATOR DOES NOT HAVE THE WELL SPECIFIC CEMENT DETAILS ONSITE PRIOR TO PUMPING THE CEMENT FOR EACH CASING STRING, THE WOC WILL BE 30 HOURS. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

R-111-P-Potash High Cave/Karst Possibility of water flows in the Salado and Castile. Possibility of lost circulation in the Rustler and Delaware.

- 1. The 13-3/8 inch surface casing shall be set at approximately 535 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. If salt is encountered, set casing at least 25 feet above the salt.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
  - □ Cement to surface. If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst and potash.

Centralizers required through the curve and a minimum of one every other joint.

3. The minimum required fill of cement behind the 7 inch production casing is:

Operator has proposed DV tool at depth of 5000', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range.

- a. First stage to DV tool:
- Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.
- b. Second stage above DV tool:
- □ Cement to surface. If cement does not circulate, contact the appropriate BLM office. Excess calculates to 23% Additional cement may be required. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to potash.
- 4. Cement not required on the 4-1/2" casing. Packer system being used.
- 5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
- 6. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

# C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor. If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).
- 3. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 3000 (3M) psi.
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Operator shall perform the 9-5/8" and 7" casing integrity tests to 70% of the casing burst. This will test the multi-bowl seals.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- 4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.

- b. The tests shall be done by an independent service company utilizing a test plug **not** a **cup** or **J-packer**.
- c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

# D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

# E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 081314

# IX. PRODUCTION (POST DRILLING)

# A. WELL STRUCTURES & FACILITIES

# **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

# **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

# Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

# **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the

largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

# **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008). The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

- 2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
- 3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
- 4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:
  - a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
  - b. Activities of other parties including, but not limited to:
    - (1) Land clearing.
    - (2) Earth-disturbing and earth-moving work.
    - (3) Blasting.

(4) Vandalism and sabotage.

# c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

- 5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.
- 6. All construction and maintenance activity will be confined to the authorized right-of-way width of \_\_\_\_\_\_\_ feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline must be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline must be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.
- 7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.
- 8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky of duney areas, the pipeline will be "snaked" around hummocks and dunes rather then suspended across these features.
- 9. The pipeline shall be buried with a minimum of <u>24</u> inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.
- 10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their

former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

- 11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.
- 12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.
- 13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.
- 14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.
- 15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.
- 16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.
- 17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

# X. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

# X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

# Seed Mixture for LPC Sand/Shinnery Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be <u>no</u> primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure

this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

Species	lb/acre
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

<sup>\*</sup>Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed