

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

NM OIL CONSERVATION
ARTESIA DISTRICT

FEB 17 2016

ATJ-16-532

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER RECEIVED

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM81586	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name	
2. Name of Operator OXY USA INCORPORATED Contact: DAVID STEWART E-Mail: david_stewart@oxy.com		7. If Unit or CA Agreement, Name and No.	
3a. Address 5 GREENWAY PLAZA STE 110 HOUSTON, TX 77046-0521		8. Lease Name and Well No. CEDAR CANYON 22 FEDERAL 21H	
3b. Phone No. (include area code) Ph: 432.685.5717		9. API Well No. 30-015-43642	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NESE 2540FSL 260FEL 32.202504 N Lat, 103.964108 W Lon At proposed prod. zone SWNW 1830FNL 180FWL 32.205132 N Lat, 103.979806 W Lon		10. Field and Pool, or Exploratory UNKNOWN Pierce Crossing; Pine Spring	
14. Distance in miles and direction from nearest town or post office* 6 MILES NORTHEAST FROM LOVING, NM		11. Sec., T., R., M., or Bld. and Survey or Area Sec 22 T24S R29E Mer NMP SME: BLM	
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 1220	16. No. of Acres in Lease	12. County or Parish EDDY	13. State NM
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 30	19. Proposed Depth 13692 MD 8844 TVD	17. Spacing Unit dedicated to this well 160.00	
21. Elevations (Show whether DF, KB, RT, GL, etc.) 2958 GL	22. Approximate date work will start 03/01/2016	20. BLM/BIA Bond No. on file ESB000226	
		23. Estimated duration 35	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature (Electronic Submission)	Name (Printed/Typed) DAVID STEWART Ph: 432.685.5717	Date 12/17/2015
Title REGULATORY ADVISOR		
Approved by (Signature) Steve Caffey	Name (Printed/Typed)	Date 2016 FEB - 9
Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #326724 verified by the BLM Well Information System
For OXY USA INCORPORATED, sent to the Carlsbad
Committed to AFMSS for processing by JAMIE RHOADES on 12/18/2015 (16JLR0144AE)

filed
2/18/16

Carlsbad Controlled Water Basin

Approval Subject to General Requirements
& Special Stipulations Attached

** BLM REVISED **

SEE ATTACHED FOR
CONDITIONS OF APPROVAL

Additional Operator Remarks:

OXY USA Inc. respectfully requests approval for the following APD:

This well will be on a multi-well pad to accommodate batch drilling with skidding operations. An EA has already been done on the pad and one of the wells has an approved APD, the Cedar Canyon 23 Federal #3H, API No. 30-015-43290.

See attached for the following:

1. APD Drilling Plan
2. Surface Use Plan of Operations
3. Plats/surveys/diagrams
4. Directional Drilling Plan
5. BOP Diagrams
6. Choke Manifold Diagrams
7. Closed Loop Diagrams
8. Flex Hose Information
9. H2S Plan
10. Staking Notice
11. Operator Certification

Division I
1433 N. Francis Dr., Hobbs, NM 88240
Phone: (575) 993-4141 Fax: (575) 993-4730
Division II
311 S. First St., Arroyo, NM 88218
Phone: (575) 744-1143 Fax: (575) 744-4730
Division III
1000 Rio Grande Road, Aztec, NM 87418
Phone: (505) 334-4178 Fax: (505) 334-4179
Division IV
1230 S. St. Francis Dr., Santa Fe, NM 87508
Phone: (505) 474-3480 Fax: (505) 474-3483

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-015-43642	Pool Code 907143	Pool Name Piece Crossing Bone Springs, East
Property Code 315242	Property Name CEDAR CANYON "22" FEDERAL	Well Number 21H
OGRID No. 16694	Operator Name OXY USA INC.	Elevation 2958.4'

Surface Location


UL or lot no.	Section	Township	Range	Lot Ids	Feet from the	North/South line	Feet from the	East/West line	County
1	22	24 SOUTH	29 EAST, N.M.P.M.		2540'	SOUTH	230'	EAST	EDDY

Bottom Hole Location If Different From Surface


UL or lot no.	Section	Township	Range	Lot Ids	Feet from the	North/South line	Feet from the	East/West line	County
E	22	24 SOUTH	29 EAST, N.M.P.M.		1830'	NORTH	180'	WEST	EDDY

Dedicated Acres No	Joint or Infill 160	Consolidation Code	Order No.
------------------------------	-------------------------------	--------------------	-----------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



OXY USA INC. CEDAR CANYON "22" FEDERAL #21H SITE PLAN




SURVEYORS CERTIFICATE

I, TERRY J. ASEL, NEW MEXICO PROFESSIONAL SURVEYOR NO. 15079, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND MEETS THE "MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO" AS ADOPTED BY THE NEW MEXICO STATE BOARD OF REGISTRATION FOR PROFESSIONAL ENGINEERS AND SURVEYORS.

Terry J. Asel 10/28/2015
Terry J. Asel N.M. R.P.L.S. No. 15079


Asel Surveying

P.O. BOX 393 - 310 W. TAYLOR
HOBBS, NEW MEXICO - 575-393-9146



LEGEND

- DENOTES STOCK PILE AREA
- DENOTES PROPOSED WELL PAD
- DENOTES PROPOSED ROAD
- DENOTES FENCE LINE




OXY USA INC.

CEDAR CANYON "22" FEDERAL #21H LOCATED
AT 2540' FSL & 230' FEL IN SECTION 22,
TOWNSHIP 24 SOUTH, RANGE 29 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO

Survey Date: 10/27/15	Sheet 1 of 1 Sheets	
W.O. Number: 151027WL-b	Drawn By: KA	Rev:
Date: 10/28/15	151027WL-b	Scale: 1"=300'

Location

SECTION 22, TOWNSHIP 24 SOUTH, RANGE 29 EAST, N.M.P.M.,
EDDY COUNTY
NEW MEXICO



DRIVING DIRECTIONS:
 FROM THE INTERSECTION OF U.S. HWY.
 #285 AND BLACK RIVER VILLAGE ROAD IN
 MALAGA, GO EAST ON COUNTY ROAD #720
 FOR 0.8 MILES, TURN LEFT ON COUNTY
 ROAD #745 (HARROUN ROAD) AND GO
 NORTH FOR 1.0 MILES, TURN RIGHT AND GO
 EAST/NORTHEAST FOR 2.1 MILES, TURN
 RIGHT ON DOG TOWN ROAD AND GO
 SOUTHEAST FOR 1.3 MILES, TURN LEFT ON
 CALICHE ROAD AND GO EAST/SOUTHEAST
 FOR 2.1 MILES, CONTINUE SOUTH FOR 1.6
 MILES, TURN LEFT AND GO NORTHEAST
 THEN SOUTHEAST FOR 1.1 MILES TO
 LOCATION.



SURVEYORS CERTIFICATE

I, TERRY J. ASEL, NEW MEXICO PROFESSIONAL SURVEYOR
 NO. 15079, DO HEREBY CERTIFY THAT I CONDUCTED AND AM
 RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS
 TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND
 BELIEF, AND MEETS THE "MINIMUM STANDARDS FOR
 SURVEYING IN NEW MEXICO" AS ADOPTED BY THE NEW
 MEXICO STATE BOARD OF REGISTRATION FOR
 PROFESSIONAL ENGINEERS AND SURVEYORS.

Terry J. Asel 10/28/2015
 Terry J. Asel, N.M. R.P.L.S. No. 15079


Asel Surveying



P.O. BOX 393 - 310 W. TAYLOR
 HOBBS, NEW MEXICO - 575-393-9146

LEGEND

● - DENOTES FOUND MONUMENT AS NOTED




OXY USA INC.

CEDAR CANYON "22" FEDERAL #14H LOCATED
 AT 2540' FSL & 230' FEL IN SECTION 22,
 TOWNSHIP 24 SOUTH, RANGE 29 EAST,
 N.M.P.M., EDDY COUNTY, NEW MEXICO

Survey Date: 10/27/15	Sheet 1 of 1 Sheets
W.O. Number: 151027WL-b	Drawn By: KA Rev:
Date: 10/28/15	151027WL-b Scale: 1"=1000'

UM

VICINITY MAP




SEC. 22 TWP. 24-S RGE. 29-E
 SURVEY N.M.P.M.
 COUNTY EDDY
 DESCRIPTION 2540' FSL & 230' FEL
 ELEVATION 2958.4'
 OPERATOR OXY USA INC.

SCALE: 1" = 2 MILES

Asel Surveying

P.O. BOX 393 - 310 W. TAYLOR
 HOBBS, NEW MEXICO - 575-393-9146




LEASE CEDAR CANYON "22" FEDERAL #21 H

DIRECTIONS FROM THE INTERSECTION OF U.S. HWY. #285 AND BLACK RIVER VILLAGE ROAD IN MALAGA, GO EAST ON COUNTY ROAD #720 FOR 0.8 MILES, TURN LEFT ON COUNTY ROAD #745 (HARROUN ROAD) AND GO NORTH FOR 1.0 MILES, TURN RIGHT AND GO EAST/NORTHEAST FOR 2.1 MILES, TURN RIGHT ON DOG TOWN ROAD AND GO SOUTHEAST FOR 1.3 MILES, TURN LEFT ON CALICHE ROAD AND GO EAST/SOUTHEAST FOR 2.1 MILES, CONTINUE SOUTH FOR 1.6 MILES, TURN LEFT AND GO NORTHEAST THEN SOUTHEAST FOR 1.1 MILES TO LOCATION.

LUM

LOCATION VERIFICATION MAP



SCALE: 1" = 2000'

CONTOUR INTERVAL: 10'

SEC. 22 TWP. 24-S RGE. 29-E

SURVEY N.M.P.M.

COUNTY EDDY

DESCRIPTION 2540' FSL & 230' FEL

ELEVATION 2958.4'

OPERATOR OXY USA INC.

LEASE CEDAR CANYON "22" FEDERAL #24H



U.S.G.S. TOPOGRAPHIC MAP
PIERCE CANYON, N.M.

Asel Surveying

P.O. BOX 393 - 310 W. TAYLOR
HOBBS, NEW MEXICO - 575-393-9146





Facility Layout



REVISION BLOCK		ENGINEERING RECORD	
NO.	DATE	BY	DATE
		KAO	11/11/15
DESCRIPTION		APP	
Production Facility Layout Diagram CEDAR CANYON 22 FED #2H & 4H Cedar Canyon 23 Fed # 3H EDDY COUNTY, NEW MEXICO			

Well Pad Layout / Reclamation



8' Diameter x 8' Deep Tinhorn
Cellar

FLEX 3 RIG DIAGRAM
CEDAR CANYON 22 FED #21H & 4H
CEDAR CANYON 23 Fed # 3H
EDDY COUNTY, NEW MEXICO

REVISION BLOCK		ENGINEERING RECORD		
NO.	DATE	DESCRIPTION	BY	DATE

OXY USA Inc. - Cedar Canyon 22 Federal #21H

1. Geologic Formations

TVD of target	8844	Pilot hole depth	N/A
MD at TD:	13692	Deepest expected fresh water:	480

Delaware Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Top Rustler	480	Water	
Top Salado (salt)	782	Water	
Top Castile (anhydrite)	1348	Water	
Top Lamar / Delaware	3075	Oil/Gas	
Top Bell Canyon	3100	Oil/Gas	Lost Circulation
Top Cherry Canyon	3639	Oil/Gas	Lost Circulation
Top Brushy Canyon	5047	Oil/Gas	Lost Circulation
Bone Spring	6586	Oil/Gas	
1st Bone Spring Sand	7571	Oil/Gas	
2nd Bone Spring	7791	Oil/Gas	
2nd Bone Spring Sand	8580	Target Zone	
3rd Bone Spring (Approx.)	8780	Oil/Gas	

*H2S, water flows, loss of circulation, abnormal pressures, etc.

OXY USA Inc. - Cedar Canyon 22 Federal #21H

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
14.75"	0	480	10.75"	45.5	J55	BTC	10.94	1.4	6.11
9.875"	0	8113	7.625"	29.7	L80	BTC	5	1.31	2.19
6.75"	0	9053	5.5"	20	P-110	Ultra SF	2.69	1.22	2.05
6.75"	9053	13692	4.5"	13.5	P-110	DQX	2.42	1.23	2.15
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N/A
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

OXY USA Inc. - Cedar Canyon 22 Federal #21H

3. Cementing Program

Casing	#Sks	Wt. lb/gal	Yld ft3/sack	H ₂ O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surf.	494	14.8	1.35	6.53	6:50	Premium Plus Cement 2% Calcium Chloride – Flake (Accelerator)
Inter.	1086	10.2	3.05	15.63	15:07	TUNED LIGHT (TM) SYSTEM 0.80% HR-601(Retarder), 3 lbm/sk Kol-Seal (Lost Circulation Additive), 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive)
	150	13.2	1.65	8.45	12:57	Super H Cement, 0.1 % HR-800 (Retarder), 0.5 % Halad(R)-344 (Low Fluid Loss Control), 0.3 % CFR-3 (Dispersant), 2 lbm Kol-Seal (Lost Circulation Additive), 3 lbm Salt (Accelerator)
	DV/ECP Tool @ 3,075' (We request the option to cancel the second stage if cement is circulated to surface during the first stage of cement operations)					
	486	12.9	1.85	9.86	12:44	Halliburton Light Premium Plus Cement with 5% Salt, 0.125 lbs/sk Poly-E-Flake, 5 lbs/sk Kol-Seal, 0.35% HR-800
	182	14.8	1.33	6.34	6:31	Premium Plus cement
Prod.	724	13.2	1.65	8.45	12:57	Tuned Light, 3 lbm/sk Kol-Seal (Lost Circulation Additive), 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive), 0.65 % SCR-100 (Retarder)
	DV/ECP Tool N/A					
	N/A					
	N/A					

Casing String	TOC	% Excess (Tail/Lead)
Surface	0'	150%
Intermediate	0'	15% / 125%
Production	7113'	50%

Include Pilot Hole Cementing specs:

Pilot hole depth N/A

KOP 8163' TVD

Plug top	Plug Bottom	% Excess	No. Sacks	Wt. lb/gal	Yld ft3/sack	Water gal/sk	Slurry Description and Cement Type
N/A							
N/A							

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
9.875" Intermediate	13-3/8"	5M	Annular	✓	70% of working pressure 250/5000psi
			Blind Ram	✓	
			Pipe Ram		
			Double Ram	✓	
			Other*		
			Annular		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other		
			Annular		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

✓	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
✓	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
Y	Are anchors required by manufacturer?
✓	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. See attached schematic. We will run the wellhead through the rotary table with the surface casing string.

OXY USA Inc. - Cedar Canyon 22 Federal #21H

5. Mud Program

Depth		Type	Weight(ppg)	Viscosity	Water Loss
From	To				
0	Surf. shoe	FW Gel	8.4-8.8	28-38	N/C
Surf csg	3075'	Saturated Brine	9.8-10	28-32	N/C
3075'	Int shoe	EnerSeal (MMH)	8.8-9.6	38-50	N/C
Int shoe	TD	OBM	8.8-9.4	28-100	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/MD Totco/Visual Monitoring
---	--------------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
Yes	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
Yes	No Logs are planned based on well control or offset log information.
No	Drill stem test? If yes, explain
No	Coring? If yes, explain

Additional logs planned	Interval
No	Resistivity
No	Density
No	CBL
Yes	Mud log Int CSG - TD
No	PEX

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	4051 psi
Abnormal Temperature	No

Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times. Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal isolation.

OXY USA Inc. - Cedar Canyon 22 Federal #21H

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
N	H2S is present
Y	H2S Plan attached

8. Other facets of operation

*See
COA*

	Yes/No
<p>Will the well be drilled with a walking/skidding operation? If yes, describe.</p> <p>X • We plan to drill the three well pad in batch by section: all surface sections, intermediate sections and production sections.</p>	Yes
<p>Will more than one drilling rig be used for drilling operations? If yes, describe.</p>	No

Attachments

- Directional Plan
- H2S Contingency Plan
- Flex III Attachments

PERFORMANCE DATA

TMK UP ULTRA™ SF
Technical Data Sheet

5.500 in

20.00 lbs/ft

P-110

Tubular Parameters


Size	5.500	in	Minimum Yield	110,000	psi
Nominal Weight	20.00	lbs/ft	Minimum Tensile	125,000	psi
Grade	P-110		Yield Load	641,000	lbs
PE Weight	19.81	lbs/ft	Tensile Load	728,000	lbs
Wall Thickness	0.361	in	Min. Internal Yield Pressure	12,600	psi
Nominal ID	4.778	in	Collapse Pressure	11,100	psi
Drift Diameter	4.653	in			
Nom. Pipe Body Area	5.828	in ²			

Connection Parameters

Connection OD	5.646	in
Connection ID	4.734	in
Make-Up Loss	5.526	in
Critical Section Area	5.289	in ²
Tension Efficiency	90.5	%
Compression Efficiency	90.5	%
Yield Load In Tension	580,000	lbs
Min. Internal Yield Pressure	12,600	psi
Collapse Pressure	11,100	psi
Uniaxial Bending	83	°/ 100 ft

Make-Up Torques

Min. Make-Up Torque	10,200	ft-lbs
Opt. Make-Up Torque	11,200	ft-lbs
Max. Make-Up Torque	12,300	ft-lbs
Yield Torque	15,400	ft-lbs



Printed on: December-10-2014

NOTE:

The content of this Technical Data Sheet is for general information only and does not guarantee performance or imply fitness for a particular purpose, which only a competent drilling professional can determine considering the specific installation and operation parameters. Information that is printed or downloaded is no longer controlled by TMK IPSCO and might not be the latest information. Anyone using the information herein does so at their own risk. To verify that you have the latest TMK IPSCO technical information, please contact TMK IPSCO Technical Sales toll-free at 1-888-258-2000.







DP-1

Borehole:	Well:	Field:	Structure:
Orig. Borehole	Oxy Cedar Canyon 22 Fed 2411	NM Eddy County (NAD 27)	H&P 615

Gravity & Magnetic Parameters	Surface Location	Miscellaneous
Model: MOON 2010 Dec 04 06:47 Date: 22-Oct-2018 Mag Dec: 7.277° PS: 48222.80147 Gravity PS: 980.46749m (19 82685 Revised)	198227 New Mexico State Plane, Cartesian Coord. US Feet Lat: N 33 12 9.87 Lon: W 102 07 26.44 Easting: 944232.89103 Scale Feet: 0.99997884	Well: Oxy Cedar Canyon 22 Fed 2411 TVD Ref: 487264.0m above MSL Plan: Oxy Cedar Canyon 22 Fed 2411 Rev0 MMC 28Oct15



Vertical Section (ft) Azim = 280.682° Scale = 1 1100(ft) Origin = 0N/S, 0E/W

DP-2

Schumberger

Oxy Cedar Canyon 22 Fed. 21H Rev0 MMC 28Oct15 Proposal Geodetic Report

(Non-Def Plan)



Reopen Date:	October 29, 2015 - 01 14 PM	Survey / DLS Computation:	Minimum Curvature / Lubinski
Client:	OXY	Vertical Section Azimuth:	290 882 ° (Grid North)
Field:	NM Esby County (NAD 27)	Vertical Section Origin:	0 000 0, 0 000 11
Structure / Slot:	Oxy Cedar Canyon 22 Fed. 21H / Oxy Cedar Canyon 22 Fed. 21H	TVD Reference Datum:	RKB
Well:	Oxy Cedar Canyon 22 Fed. 21H	TVD Reference Elevation:	2984 900 ft above MSL
Borehole:	Oxy Cedar Canyon 22 Fed. 21H - Orig. Borehole	Sealed / Ground Elevation:	2958 400 ft above MSL
UWI / API#:	Unknown / Unknown	Magnetic Declination:	7.277 °
Survey Name:	Oxy Cedar Canyon 22 Fed. 21H Rev0 MMC 28Oct15	Total Gravity Field Strength:	988 4572mgm (9 80665 Based)
Survey Date:	October 28, 2015	Gravity Model:	GARM
Tort / AHD / ODI / ERD Ratio:	119 169 ° / 5984 371 R / 6 043 / 0 677	Total Magnetic Field Strength:	48202 081 nT
Coordinate Reference System:	NAD27 New Mexico State Plane, Eastern Zone, US Feet	Magnetic Dip Angle:	60 054 °
Location Lat / Long:	N 32° 12' 9 01288", W 103° 57' 50 44088"	Declination Date:	October 28, 2015
Location Grid NE YX:	N 437588 710 NUS, E 814235 880 RUS	Magnetic Declination Model:	HDGM 2015
CRS Grid Convergence Angle:	0.1968 °	North Reference:	Grid North
Grid Scale Factor:	0.99992404	Grid Convergence Used:	0.1968 °
Version / Patch:	2 8 572 0	Total Corr Mag North->Grid North:	7 8066 °
		Local Coord Referenced To:	Structure Reference Point

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (ft/rod)	Northing (NUS)	Easting (RUS)	Latitude (N 32 12 01)	Longitude (EW 103 57 50 44)
Top In	0 00	0 00	8 94	0 00	-2884 90	0 00	0 00	0 00	N/A	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	100 00	0 00	8 94	100 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	200 00	0 00	8 94	200 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	300 00	0 00	8 94	300 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	400 00	0 00	8 94	400 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	500 00	0 00	8 94	500 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	600 00	0 00	8 94	600 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	700 00	0 00	8 94	700 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	800 00	0 00	8 94	800 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	900 00	0 00	8 94	900 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	1000 00	0 00	8 94	1000 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	1100 00	0 00	8 94	1100 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	1200 00	0 00	8 94	1200 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	1300 00	0 00	8 94	1300 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	1400 00	0 00	8 94	1400 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	1500 00	0 00	8 94	1500 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	1600 00	0 00	8 94	1600 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	1700 00	0 00	8 94	1700 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	1800 00	0 00	8 94	1800 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	1900 00	0 00	8 94	1900 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	2000 00	0 00	8 94	2000 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	2100 00	0 00	8 94	2100 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	2200 00	0 00	8 94	2200 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	2300 00	0 00	8 94	2300 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	2400 00	0 00	8 94	2400 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	2500 00	0 00	8 94	2500 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	2600 00	0 00	8 94	2600 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	2700 00	0 00	8 94	2700 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	2800 00	0 00	8 94	2800 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	2900 00	0 00	8 94	2900 00	-2884 90	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	3000 00	0 00	8 94	3000 00	-2884 90	15 10	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
Top Lateral / Delaware	3001.00	0 00	8 94	3001.00	18.10	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
Top Bell Canyon	3024.00	0 00	8 94	3024.00	39.10	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	3100 00	0 00	8 94	3100 00	115.10	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	3200 00	0 00	8 94	3200 00	215.10	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	3300 00	0 00	8 94	3300 00	315.10	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	3400 00	0 00	8 94	3400 00	415.10	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
Back Build 2" DLS	3490 00	0 00	8 94	3490 00	505.10	0 00	0 00	0 00	0 00	437588.71	814235.88	N 32 12 0 01	W 103 57 50 44
	3500 00	0 20	8 94	3500 00	515.10	0 00	0 02	0 00	2 00	437586.73	814235.88	N 32 12 0 01	W 103 57 50 44
	3600 00	2 20	8 94	3589 97	615.07	0 07	0 20	0 33	2 00	437568.00	814230.21	N 32 12 0 03	W 103 57 50 44
Top Cherry Canyon	3696.18	4.12	8 94	3696.00	711.10	0.23	7.33	1.15	2.00	437594.04	814237.03	N 32 12 0 09	W 103 57 50 43
	3700 00	4 20	8 94	3699 81	714.91	0.28	7.89	1.20	2 00	437594.31	814237.08	N 32 12 0 09	W 103 57 50 43
	3800 00	8 20	8 94	3709 40	814.50	0.57	16.55	2.80	2 00	437603.28	814238.48	N 32 12 0 18	W 103 57 50 41
	3900 00	8 20	8 94	3808 80	913.70	0.99	28.93	4.55	2 00	437615.64	814240.43	N 32 12 0 30	W 103 57 50 39
	4000 00	10 20	8 94	3897 31	1012.41	1.53	44.73	7.04	2 00	437631.43	814242.92	N 32 12 0 48	W 103 57 50 36
	4100 00	12 20	8 94	4095 40	1110.50	2.19	63.91	10.05	2 00	437650.62	814245.95	N 32 12 0 54	W 103 57 50 32
	4189 89	14 00	8 94	4182 95	1198.05	2.88	84.04	13.22	2 00	437670.74	814249.10	N 32 12 0 54	W 103 57 50 28
	4200 00	14 00	8 94	4182 78	1207.86	2.97	86.48	13.60	0 00	437673.81	814249.48	N 32 12 0 87	W 103 57 50 28
	4300 00	14 00	8 94	4289 79	1304.89	3.78	110.35	17.38	0 00	437687.05	814253.24	N 32 12 10 10	W 103 57 50 23
	4400 00	14 00	8 94	4386 82	1401.92	4.81	134.24	21.12	0 00	437720.94	814257.00	N 32 12 10 34	W 103 57 50 19
	4500 00	14 00	8 94	4483 85	1498.95	5.43	158.14	24.88	0 00	437744.83	814260.76	N 32 12 10 58	W 103 57 50 14
Top Castle (anhydrite)	4581.99	14.00	8 94	4544.00	1559.10	5.83	172.95	27.21	0 00	437759.65	814263.09	N 32 12 10 72	W 103 57 50 12
	4600 00	14 00	8 94	4580 88	1595.98	6.24	182.03	28.84	0 00	437768.73	814264.51	N 32 12 10 81	W 103 57 50 10
	4700 00	14 00	8 94	4677 91	1693.01	7.06	205.93	32.40	0 00	437792.62	814268.27	N 32 12 11 05	W 103 57 50 06
	4800 00	14 00	8 94	4774 94	1790.04	7.88	229.82	36.18	0 00	437816.51	814272.03	N 32 12 11 29	W 103 57 50 01
	4900 00	14 00	8 94	4871 97	1887.07	8.70	253.71	39.91	0 00	437840.41	814275.79	N 32 12 11 52	W 103 57 49 97
	5000 00	14 00	8 94	4968 00	1984.10	9.52	277.61	43.67	0 00	437864.30	814279.55	N 32 12 11 78	W 103 57 49 92
	5100 00	14 00	8 94	5065 03	2081.13	10.34	301.50	47.43	0 00	437888.19	814283.31	N 32 12 11 99	W 103 57 49 88
Top Brushy Canyon	5118.46	14.00	8 94	5082.00	2097.10	10.48	305.44	48.05	0 00	437892.12	814283.03	N 32 12 12 03	W 103 57 49 87
	5200 00	14 00	8 94	5183 08	2178.18	11.18	325.40	51.19	0 00	437912.08	814287.07	N 32 12 12 23	W 103 57 49 83
	5300 00	14 00	8 94	5269 09	2275.19	11.98	349.29	54.95	0 00	437935.98	814290.83	N 32 12 12 47	W 103 57 49 79

DP-3

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	TVDSS (ft)	VBEC (ft)	NS (ft)	EW (ft)	DLS (7190ft)	Northing (ft)	Easting (ft)	Latitude (N/S ° ° ' '')	Longitude (E/W ° ° ' '')
Top Salado (sand)	5392.68	14.00	8.94	5350.00	2385.10	12.74	371.43	58.43	0.00	437958.12	814294.31	N 32 12 12.89	W 103 57 49.75
	5400.00	14.00	8.94	5357.12	2372.22	12.80	373.19	58.71	0.00	437959.87	814294.58	N 32 12 12.70	W 103 57 49.74
	5500.00	14.00	8.94	5454.15	2447.25	13.82	397.08	62.47	0.00	437963.78	814296.34	N 32 12 12.84	W 103 57 49.70
	5600.00	14.00	8.94	5551.18	2568.28	14.44	420.98	66.23	0.00	438007.65	814302.10	N 32 12 13.18	W 103 57 49.65
Top Rustler	5683.59	14.00	8.94	5642.00	2657.10	15.21	443.34	69.75	0.00	438030.02	814305.62	N 32 12 13.47	W 103 57 49.61
	5700.00	14.00	8.94	5648.22	2643.32	15.26	444.67	69.99	0.00	438031.55	814305.88	N 32 12 13.41	W 103 57 49.61
	5800.00	14.00	8.94	5745.25	2760.35	16.06	468.77	73.75	0.00	438055.44	814309.62	N 32 12 13.85	W 103 57 49.58
	5900.00	14.00	8.94	5842.28	2857.38	16.80	492.66	77.50	0.00	438079.33	814313.38	N 32 12 14.89	W 103 57 49.52
	6000.00	14.00	8.94	5939.31	2954.41	17.72	516.56	81.26	0.00	438103.23	814317.14	N 32 12 14.12	W 103 57 49.47
	6100.00	14.00	8.94	6036.34	3051.44	18.54	540.45	85.02	0.00	438127.12	814320.90	N 32 12 14.38	W 103 57 49.43
	6200.00	14.00	8.94	6133.37	3148.47	19.36	564.35	88.78	0.00	438151.01	814324.65	N 32 12 14.59	W 103 57 49.38
	6300.00	14.00	8.94	6230.40	3245.50	20.18	588.24	92.54	0.00	438174.90	814328.41	N 32 12 14.83	W 103 57 49.34
	6400.00	14.00	8.94	6327.43	3342.53	21.00	612.14	96.30	0.00	438198.80	814332.17	N 32 12 15.07	W 103 57 49.30
	6500.00	14.00	8.94	6424.46	3439.56	21.82	636.03	100.06	0.00	438222.69	814335.93	N 32 12 15.30	W 103 57 49.25
	6600.00	14.00	8.94	6521.49	3536.59	22.64	659.92	103.82	0.00	438246.58	814339.69	N 32 12 15.54	W 103 57 49.21
	6700.00	14.00	8.94	6618.52	3633.62	23.46	683.82	107.58	0.00	438270.48	814343.45	N 32 12 15.78	W 103 57 49.16
1st Bone Spring Sand	6749.99	14.00	8.94	6667.00	3682.10	23.87	695.78	109.45	0.00	438282.41	814345.33	N 32 12 15.89	W 103 57 49.14
	6800.00	14.00	8.94	6715.55	3730.65	24.26	707.71	111.34	0.00	438294.34	814347.21	N 32 12 16.01	W 103 57 49.12
	6900.00	14.00	8.94	6812.58	3827.68	25.10	731.61	115.09	0.00	438318.26	814351.07	N 32 12 16.25	W 103 57 49.07
	7000.00	14.00	8.94	6909.61	3924.71	25.92	755.50	118.85	0.00	438342.18	814354.92	N 32 12 16.48	W 103 57 49.03
	7100.00	14.00	8.94	7006.64	4021.74	26.74	779.40	122.61	0.00	438366.05	814358.78	N 32 12 16.72	W 103 57 48.98
	7200.00	14.00	8.94	7103.67	4118.77	27.56	803.29	126.37	0.00	438389.94	814362.64	N 32 12 16.96	W 103 57 48.94
	7300.00	14.00	8.94	7200.70	4215.80	28.38	827.19	130.13	0.00	438413.83	814366.50	N 32 12 17.19	W 103 57 48.89
	7400.00	14.00	8.94	7297.73	4312.83	29.20	851.08	133.89	0.00	438437.73	814370.36	N 32 12 17.43	W 103 57 48.85
Over 2' DLS	7409.60	14.20	8.94	7307.05	4322.15	29.28	853.38	134.25	0.00	438440.02	814370.12	N 32 12 17.45	W 103 57 48.84
	7500.00	12.19	8.94	7395.09	4410.10	29.97	877.81	137.43	2.00	438460.25	814373.30	N 32 12 17.65	W 103 57 48.81
	7600.00	10.18	8.94	7483.13	4508.29	30.63	902.70	140.45	2.00	438479.42	814376.52	N 32 12 17.84	W 103 57 48.77
	7700.00	8.19	8.94	7571.17	4607.00	31.17	926.55	142.93	2.00	438495.19	814379.80	N 32 12 18.00	W 103 57 48.74
	7800.00	6.19	8.94	7659.21	4706.21	31.59	950.41	144.88	2.00	438507.55	814383.14	N 32 12 18.12	W 103 57 48.72
	7900.00	4.13	8.94	7749.69	4805.79	31.90	974.25	146.28	2.00	438518.19	814386.51	N 32 12 18.21	W 103 57 48.70
	8000.00	2.19	8.94	7840.53	4905.63	32.08	998.05	147.15	2.00	438521.96	814389.81	N 32 12 18.26	W 103 57 48.69
2nd Bone Spring	8031.48	1.56	8.94	7822.00	4837.10	32.12	936.38	147.31	2.00	438523.00	814383.17	N 32 12 18.27	W 103 57 48.69
	8100.00	0.18	8.94	7990.51	5005.61	32.16	937.40	147.47	2.00	438524.03	814383.34	N 32 12 18.28	W 103 57 48.69
Return to vertical	8109.49	0.00	8.94	8000.00	5015.10	32.18	937.41	147.47	2.00	438524.05	814383.34	N 32 12 18.28	W 103 57 48.69
	8200.00	0.00	8.94	8090.51	5105.61	32.16	937.41	147.47	0.00	438524.05	814383.34	N 32 12 18.28	W 103 57 48.69
KCP	8209.49	0.00	8.94	8100.00	5115.10	32.16	937.41	147.47	0.00	438524.05	814383.34	N 32 12 18.28	W 103 57 48.69
KOP Build 8.25'100' DLS	8258.49	0.00	8.94	8190.00	5165.10	32.16	937.41	147.47	0.00	438524.05	814383.34	N 32 12 18.28	W 103 57 48.69
	8300.00	3.34	270.03	8190.48	5205.58	33.32	937.41	148.28	8.25	438524.05	814382.16	N 32 12 18.28	W 103 57 48.70
	8400.00	11.59	270.03	8289.55	5304.65	49.07	937.42	153.31	8.25	438524.08	814388.18	N 32 12 18.28	W 103 57 48.65
	8500.00	19.84	270.03	8385.73	5400.83	72.85	937.43	168.24	8.25	438524.07	814342.11	N 32 12 18.29	W 103 57 49.17
	8600.00	28.09	270.03	8477.03	5492.13	112.51	937.45	183.86	8.25	438524.09	814301.53	N 32 12 18.29	W 103 57 49.64
	8700.00	36.34	270.03	8561.56	5578.68	154.82	937.48	199.38	8.25	438524.11	814246.27	N 32 12 18.29	W 103 57 50.26
	8800.00	44.59	270.03	8637.57	5652.87	236.51	937.50	214.86	8.25	438524.14	814180.43	N 32 12 18.29	W 103 57 51.01
	8900.00	52.84	270.03	8703.49	5718.59	302.28	937.54	227.54	8.25	438524.18	814108.35	N 32 12 18.29	W 103 57 51.89
	9000.00	61.09	270.03	8757.96	5773.08	384.51	937.58	241.30	8.25	438524.21	814024.60	N 32 12 18.30	W 103 57 52.66
2nd Bone Spring Sand	9053.52	65.51	270.03	8782.00	5797.10	431.48	937.60	258.10	8.25	438524.24	813978.80	N 32 12 18.30	W 103 57 53.42
	9100.00	69.34	270.03	8789.84	5814.94	473.80	937.62	262.01	8.25	438524.28	813933.89	N 32 12 18.30	W 103 57 53.92
	9200.00	77.59	270.03	8828.27	5841.37	567.87	937.68	297.70	8.25	438524.30	813838.12	N 32 12 18.30	W 103 57 55.03
	9300.00	85.84	270.03	8842.67	5857.77	644.77	937.71	308.66	8.25	438524.35	813738.25	N 32 12 18.31	W 103 57 56.18
Landing Point	9354.82	91.17	270.03	8844.35	5859.45	728.19	937.74	318.24	8.25	438524.38	813674.88	N 32 12 18.31	W 103 57 56.93
	9400.00	91.17	270.03	8843.82	5858.72	782.83	937.75	326.81	8.25	438524.39	813630.31	N 32 12 18.31	W 103 57 57.35
	9500.00	91.17	270.03	8841.58	5856.68	859.12	937.80	336.59	0.00	438524.44	813539.34	N 32 12 18.32	W 103 57 58.51
	9600.00	91.17	270.03	8839.53	5854.83	959.31	937.85	348.57	0.00	438524.48	813439.37	N 32 12 18.32	W 103 57 59.67
	9700.00	91.17	270.03	8837.48	5852.58	1057.50	937.89	362.55	0.00	438524.53	813339.40	N 32 12 18.32	W 103 58 0.64
	9800.00	91.17	270.03	8835.44	5850.54	1155.89	937.94	376.53	0.00	438524.57	813239.43	N 32 12 18.33	W 103 58 2.00
	9900.00	91.17	270.03	8833.39	5848.49	1253.88	937.98	390.51	0.00	438524.62	813139.46	N 32 12 18.33	W 103 58 3.16
	10000.00	91.17	270.03	8831.34	5846.44	1352.06	938.03	404.49	0.00	438524.67	813039.49	N 32 12 18.34	W 103 58 4.33
	10100.00	91.17	270.03	8829.29	5844.39	1450.25	938.08	418.47	0.00	438524.71	812939.52	N 32 12 18.34	W 103 58 5.49
	10200.00	91.17	270.03	8827.25	5842.35	1548.44	938.12	432.44	0.00	438524.78	812839.54	N 32 12 18.34	W 103 58 6.65
	10300.00	91.17	270.03	8825.20	5840.30	1646.63	938.17	446.42	0.00	438524.80	812739.57	N 32 12 18.35	W 103 58 7.82
	10400.00	91.17	270.03	8823.15	5838.25	1744.82	938.21	460.40	0.00	438524.85	812639.60	N 32 12 18.35	W 103 58 8.99
	10500.00	91.17	270.03	8821.10	5836.21	1843.01	938.26	474.38	0.00	438524.90	812539.63	N 32 12 18.35	W 103 58 10.15
	10600.00	91.17	270.03	8819.06	5834.18	1941.20	938.31	488.36	0.00	438524.94	812439.66	N 32 12 18.36	W 103 58 11.31
	10700.00	91.17	270.03	8817.01	5832.14	2039.39	938.35	502.34	0.00	438524.99	812339.69	N 32 12 18.36	W 103 58 12.47
	10800.00	91.17	270.03	8814.96	5830.11	2137.58	938.40	516.32	0.00	438525.03	812239.72	N 32 12	

DP-4

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TYD (ft)	TVDS (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (ft/100ft)	Northing (BUS)	Easting (BUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
Survey Error Model: Survey Program:	ISCWGA Rev 0 3-D at 900% Confidence 2.7955 sigma												
Description	Part	MD From (ft)	MD To (ft)	ECU Feet (ft)	Hole Size (in)	Casing Diameter (in)	Survey Tool Type			Borehole / Survey			
	1	0 000	28 500	1/100 000	30 000	30 000	SLB_MWD-STD_HDGM-Depth Only			Oxy Cedar Canyon 22 Fed 21H Rev0 MMC			
	1	28 500	13682.245	1/100 000	30 000	30 000	SLB_MWD-STD_HDGM			Oxy Cedar Canyon 22 Fed 21H Oxy Borehole / Oxy Cedar			

DP-5

Schlumberger

Oxy Cedar Canyon 22 Fed. 21H Rev0 MMC 28Oct15 Proposal Geodetic Report

(Non-Def Plan)



Report Date: October 28, 2015 - 01:13 PM Client: OXY Field: NM Eddy County (NAD 27) Structure / Blot: Oxy Cedar Canyon 22 Fed. 21H / Oxy Cedar Canyon 22 Fed. 21H Well: Oxy Cedar Canyon 22 Fed. 21H Borehole: Oxy Cedar Canyon 22 Fed. 21H - Orig. Borehole UWI / API#: Unknown / Unknown Survey Name: Oxy Cedar Canyon 22 Fed. 21H Rev0 MMC 28Oct15 Survey Date: October 28, 2015 Tort / AHD / DDI / ERD Ratio: 119.169 * / 5984 371 ft / 8 043 / 0 877	Survey / DLS Computation: Minimum Curvature / Lubinski Vertical Section Azimuth: 280 882 * (Grid North) Vertical Section Origin: 0 000 ft, 0 000 ft TVD Reference Datum: RKB TVD Reference Elevation: 2984 900 ft above MSL Seabed / Ground Elevation: 2958 400 ft above MSL Magnetic Declination: 7.277 * Total Gravity Field Strength: 998 4873mgm (9 80665 Based) Gravity Model: GARM Total Magnetic Field Strength: 48292 061 nT	Coordinate Reference System: NAD27 New Mexico State Plane, Eastern Zone, US Feet Magnetic Dip Angle: 60 054 * Location Lat / Long: N 32° 12' 9.01288", W 103° 57' 50.44068" Declination Date: October 28, 2015 Location Grid N/E Y/X: N 437586 710 NUS, E 614235 880 NUS Magnetic Declination Model: HDGM 2015 CRS Grid Convergence Angle: 0.1968 * North Reference: Grid North Grid Scale Factor: 0.99992404 Grid Convergence Used: 0.1968 * Version / Patch: 2 B 572 0 Total Corr Mag North->Grid North: 7.0806 * Local Coord Referenced To: Structure Reference Point
--	---	--

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	TVDSS (ft)	YSEC (ft)	N8 (ft)	EW (ft)	DLS (ft/100ft)	Northing (NUS)	Easting (NUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
Top-In	0 00	0 00	8 94	0 00	-2984 90	0 00	0 00	0 00	N/A	437586 71	614235 88	N 32 12 9 01	W 103 57 50 44
Back 5.000 2" DLS	3490 00	0 00	8 94	3490 00	505.10	0 00	0 00	0 00	0 00	437586 71	614235 88	N 32 12 9 01	W 103 57 50 44
Hold 14" Inc	4189 89	14 00	8 94	4182 85	1198 05	2 88	84 04	13 22	2 00	437670 74	614249 10	N 32 12 9 84	W 103 57 50 28
Drop 2" DLS	7409 60	14 00	8 94	7307 05	4322 15	29 28	853 38	134 25	0 00	438440 02	614370 12	N 32 12 17 45	W 103 57 48 84
Return to vertical	8108 49	0 00	8 94	8000 00	3015.10	32.18	837 41	147 47	2 00	438524 05	614383 34	N 32 12 18 28	W 103 57 48 89
KOP Build 8 25' 100" DLS	8250 49	0 00	8 94	8150 00	5165.10	32.18	837 41	147 47	0 00	438524 05	614383 34	N 32 12 18 28	W 103 57 48 89
Landing Point	9364 62	91 17	270 03	8844 35	5859 45	728 19	837 74	-981 24	8 25	438524 38	613874 68	N 32 12 18 31	W 103 57 58 03
Bottom Perf.	13538 24	91 17	270 03	8758 90	5774 00	4826 26	838 65	-4733 99	0 00	438526 28	609502 28	N 32 12 18 47	W 103 58 45 50
Plat BH.	13692 24	91 17	270 03	8755 75	5770 85	4977 47	838 72	-4887 96	0 00	438526 36	609348 30	N 32 12 18 47	W 103 58 47 29


Survey Type: Non-Def Plan

Survey Error Model: ISCWSA Rev 0 *** 3-D 95 000% Confidence 2.7855 sigma

Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Survey Tool Type	Borehole / Survey
	1	0 000	28 500	1/100 000	30 000	30 000	SLB_MWD-STD_HDGM-Depth Only	Oxy Cedar Canyon 22 Fed. 21H Rev0 MMC
	1	26 500	13692 245	1/100 000	30 000	30 000	SLB_MWD-STD_HDGM	Oxy Cedar Canyon 22 Fed. 21H - Orig Borehole / Oxy Cedar

5M BOP Stack



Mud Cross Valves:

- 5. 5M Check Valve
- 6. Outside 5M Kill Line Valve
- 7. Inside 5M Kill Line
- 8. Outside 5M Kill Line Valve
- 9. 5M HCR Valve

*Minimum ID = 2-1/16" on Kill Line side and 3" minimum ID on choke line side

1. 5,000 psi Annular Ram (13-3/8" ID)

2. 5,000 psi Upper Pipe Ram (13-3/8" ID)


3. 5,000 psi Blind Ram (13-3/8" ID)

4. 5,000 psi Lower Pipe Ram (13-3/8" ID)

BOP-1



Note: Dimensional information reflected on this drawing are estimated measurements only.



11" 10K MBS w/ 5.5" Mandrel



JEANETTE	8-5-15	#	J-9579-4
----------	--------	---	----------



Fluid Technology

Quality Document

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. N°:	746	
PURCHASER:			Phoenix Beattie Co.		P.O. N°:	002491
CONTITECH ORDER N°:		412638		HOSE TYPE:	3" ID Choke and Kill Hose	
HOSE SERIAL N°:		52777		NOMINAL / ACTUAL LENGTH:	10,67 m	
W.P.	68,96 MPa	10000	psi	T.P.	103,4 MPa	15000 psi
				Duration:	60	min.
Pressure test with water at ambient temperature <p style="text-align: center;">See attachment. (1 page)</p>						
↑ 10 mm = 10 Min. → 10 mm = 25 MPa						
COUPLINGS						
Type	Serial N°		Quality	Heat N°		
3" coupling with 4 1/16" Flange end	917	913	AISI 4130	T7998A		
			AISI 4130	26984		
INFOCHIP INSTALLED				API Spec 16 C Temperature rate: "B"		
All metal parts are flawless						
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.						
Date:	Inspector		Quality Control			
04. April. 2008			Contitech Rubber Industrial Kit Quality Control Dept. (1)			

Coflex Hose Certification

The image shows a large grid of vertical lines, possibly representing a technical drawing or a data table. The grid is composed of many vertical lines, with some faint markings and a vertical line on the left side. The grid is oriented vertically on the page.

Coflex
Conf Testi Rubber
Industrial Kft.
Supply Control Dept
20



Coflex Hose Certification

Form No 100/12



Phoenix Beattie Corp

11525 Brittain Park Drive
Houston, TX 77041
Tel: (832) 327-0141
Fax: (832) 327-0148
E-mail: sa11@phoenixbeattie.com
www.phoenixbeattie.com

Delivery Note

Customer Order Number	370-369-001	Delivery Note Number	003078	Page	1
Customer / Invoice Address HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		Delivery / Address HELMERICH & PAYNE IOC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD HOUSTON, TX 77015			

Customer Acc No	Phoenix Beattie Contract Manager	Phoenix Beattie Reference	Date
H01	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
1	HP10CK3A-35-4F1 3" 10K 16C C&K HOSE x 35ft OAL CW 4.1/16" API SPEC FLANGE E/ End 1: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange End 2: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange c/w BX155 Standard ring groove at each end Suitable for H2S Service Working pressure: 10,000psi Test pressure: 15,000psi Standard: API 16C Full specification Armor Guarding: Included Fire Rating: Not Included Temperature rating: -20 Deg C to +100 Deg C	1	1	0
2	SECK3-HPF3 LIFTING & SAFETY EQUIPMENT TO SUIT HP10CK3-35-F1 2 x 160mm ID Safety Clamps 2 x 244mm ID Lifting Collars & element C's 2 x 7ft Stainless Steel wire rope 3/4" OD 4 x 7.75t Shackles	1	1	0
3	SC725-200CS SAFETY CLAMP 200MM 7.25T C/S GALVANISED	1	1	0

Continued...

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days. Returns may be subject to a handling charge.



Phoenix Beattie Corp

11525 Brittonmore Park Drive
Houston, TX 77043
Tel: (832) 327-0141
Fax: (832) 327-0148
E-mail: sa@phoenixbeattie.com
www.phoenixbeattie.com

Delivery Note

Customer Order Number	370-369-001	Delivery Note Number	003078	Page	2
Customer / Invoice Address HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		Delivery / Address HELMERICH & PAYNE IDC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD HOUSTON, TX 77015			

Customer Acc No	Phoenix Beattie Contract Manager	Phoenix Beattie Reference	Date
HD1	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
4	SC725-132CS SAFETY CLAMP 132MM 7.25T C/S GALVANIZED C/W BOLTS	1	1	0
5	00CERT-HYDRO HYDROSTATIC PRESSURE TEST CERTIFICATE	1	1	0
6	00CERT-LOAD LOAD TEST CERTIFICATES	1	1	0
7	00FREIGHT INBOUND / OUTBOUND FREIGHT PRE-PAY & ADD TO FINAL INVOICE NOTE: MATERIAL MUST BE ACCOMPANIED BY PAPERWORK INCLUDING THE PURCHASE ORDER, RIG NUMBER TO ENSURE PROPER PAYMENT	1	1	0

Phoenix Beattie Inspection Signature : _____

Received in Good Condition : Signature _____

Print Name _____

Date _____

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days. Returns may be subject to a handling charge.


CERTIFICATE OF CONFORMITY

Supplier : CONTITECH RUBBER INDUSTRIAL KFT.
Equipment : 6 pcs. Choke and Kill Hose with installed couplings
Type : 3" x 10,67 m WP: 10000 psi
Supplier File Number : 412638
Date of Shipment : April. 2008
Customer : Phoenix Beattie Co.
Customer P.o. : 002491
Referenced Standards
/ Codes / Specifications : API Spec 16 C
Serial No.: 52754,52755,52776,52777,52778,52782

STATEMENT OF CONFORMITY

We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.

COUNTRY OF ORIGIN HUNGARY/EU


Signed : 

ContiTech Rubber
Industrial Kft.
Quality Control Dept.
(2)

Date: 04. April. 2008

Position: Q.C. Manager

5M Choke Panel



Return to Active System

To Gas Buster

Green Indicates Open
Red Indicates Closed

To Panic Line

MC

Gauge and Test Port

To Choke Line

1. 4" Choke Manifold Valve
2. 4" Choke Manifold Valve
3. 3" Choke Manifold Valve
4. 3" Choke Manifold Valve
5. 3" Choke Manifold Valve
6. 3" Choke Manifold Valve
7. 3" Choke Manifold Valve
8. PC - Power Choke
9. 3" Choke Manifold Valve
10. 3" Choke Manifold Valve
11. Choke Manifold Valve
12. MC - Manual Choke

18. Choke Manifold Valve


21. Vertical Choke Manifold Valve

*All Valves 3" minimum


CM-1




10M REMOTE KILL LINE SCHEMATIC




Choke Manifold – Gas Separator (Top View)



Choke Manifold – Gas Separator (Side View)



Oxy Single Centrifuge
 Closed Loop System – New
 Mexico Flex III
 May 28, 2013



Roll off bins – for waste solids

Waste tank 10.5'

Single Centrifuge 8.5'

23'

33'

10.5'

MAST IN HORIZONTAL POSITION

END OF BOGEY GUIDE

DRILL FLOOR UTILITY BOOM

CHOKE MANIFOLD

TRIP TANK

SHOCK SKID

38'-7\"/>

WASTE TANKS

TURBINE PUMP

VARABLE FREQUENCY DRIVE HOUSE

GENERATOR HOUSE

GENERATOR HOUSE

GENERATOR HOUSE


GENERATOR HOUSE

27'-0\"/>

DIESEL TANK

CL-2


Oxy




Oxy Single Centrifuge
 Closed Loop System – New
 Mexico Flex III
 May 28, 2013

Rig Layout

**Pad Site Overall Rig Layout
3 Well Pad Site – Cedar Canyon 2 2 Fed #2/H Pad**



Pipeline 1



LINE TABLE


LINE	BEARING	DISTANCE
L1	S88°21'11"E	174.9'
L2	S69°09'51"E	352.1'
L3	N89°45'23"E	405.5'
L4	N03°15'56"W	55.7'
L5	N05°20'44"E	949.2'
L6	S84°47'59"E	532.8'
L7	S79°40'18"E	541.0'
L8	N77°40'01"E	173.3'
L9	N47°20'37"E	429.5'
L10	N05°27'05"E	500.6'
L11	N78°35'49"E	346.0'
L12	N66°39'01"W	436.6'
L13	N05°08'41"E	69.3'
L14	N26°07'06"W	97.7'
L15	N24°46'05"E	196.5'
L16	N07°34'09"E	287.2'
L17	N40°35'54"E	73.6'
L18	N00°06'59"W	38.4'
L19	N89°22'00"E	494.5'
L20	N54°45'19"E	60.5'
L21	N02°37'47"E	346.0'
L22	N37°17'02"E	119.3'
L23	N05°03'10"W	38.4'
L24	S89°56'44"W	118.8'
L25	N28°35'31"E	48.2'
L26	S89°58'06"E	144.4'

DESCRIPTION

SURVEY FOR A STRIP OF LAND 50.0 FEET WIDE AND 6612.2 FEET OR 1,290 ACRES IN LENGTH CROSSING USA LAND IN SECTION 22, TOWNSHIP 24 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO, AND BEING 25.0 FEET LEFT AND 25.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

I, RONALD J. EDSON, NEW MEXICO PROFESSIONAL SURVEYOR No. 2138, DO HEREBY CERTIFY THAT THIS SURVEY PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY; THAT THIS SURVEY MEETS THE COMMON STANDARDS FOR SURVEYING IN NEW MEXICO; AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

RONALD J. EDSON DATE: 02/11/2015



NOTE

BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.


PROVIDING SURVEYING SERVICES SINCE 1946
JOHN WEST SURVEYING COMPANY
 413 N. DAL PALO, NORMAN, N.M. 86340
 (505) 883-3117 www.jwsc.com
 TEMPLATES 10027000

On Surface:
 (3) 4" Composite Flowlines along surveyed route operating < 75% MAWP.

LEGEND
 © DENOTES FOUND CORNER AS NOTED
 Scale: 1"=1000'
 1000 0 1000 2000 Feet

OXY U.S.A. INC.
 SURVEY FOR A PIPELINE TO THE CEDAR CANYON ZI FEDERAL #311, #44, #54 & #711 CROSSING SECTION 22, TOWNSHIP 24 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO
 Survey Date: 1/3/15 Rev: CAD Date: 2/10/15 Drawn By: L.S.
 S.D. No.: 141112/9 Ref. No.: Sheet 1 of 1

Pipeline - 2



DESCRIPTION

SURVEY FOR A PIPELINE CROSSING SECTION 22, TOWNSHIP 24 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO, AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT IN THE SOUTHWEST QUARTER, WHICH LIES S44°39'52"E 19526.9 FEET FROM THE WEST QUARTER CORNER; THEN 17°19'29"E 15.0 FEET; THEN S72°34'48"E 184.3 FEET; THEN N17°25'35"E 84.5 FEET; THEN S88°01'53"E 4.5 FEET TO A POINT IN THE EAST LINE OF THE W/2 W/2, WHICH LIES S74°22'19"E 4114.9 FEET FROM THE EAST QUARTER CORNER.

TOTAL LENGTH EQUALS 268.3 FEET OR 16.26 RODS.

NOTE

BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.

I, RONALD J. EIDSON, NEW MEXICO PROFESSIONAL SURVEYOR No. 3239, DO HEREBY CERTIFY THAT THIS SURVEY PLAN AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

RONALD J. EIDSON *[Signature]*
 DATE: 02/11/2017

LEGEND

⊙ DENOTES FOUND CORNER AS NOTED




OXY U.S.A. INC.

SURVEY FOR A PIPELINE TO THE CEDAR CANYON
 23 FEDERAL #4H & #5H CROSSING
 SECTION 22, TOWNSHIP 24 SOUTH,
 RANGE 29 EAST, N.M.P.M.,
 EDDY COUNTY, NEW MEXICO

Survey Date: 1/9/15 CAD Date: 2/10/15 Drawn By: LSL
 W.O. No.: 14111379 Rev. Rel. W.O.: Sheet 1 of 1

PROVIDING SURVEYING SERVICES SINCE 1946
JOHN WEST SURVEYING COMPANY
 412 N. DAL PASO MOBES, N.M. 88240
 (575) 393-3117 www.jwsc.biz
 TBPLSP 10021000



**Permian Drilling
Hydrogen Sulfide Drilling Operations Plan
Cedar Canyon 22 Federal 21H**

Open drill site. No homes or buildings are near the proposed location.

1. Escape

Personnel shall escape upwind of wellbore in the event of an emergency gas release. Escape can take place through the lease road on the Northwest side of the location. Personnel need to move to a safe distance and block the entrance to location. If the primary route is not an option due to the wind direction, then a secondary egress route should be taken.

H2S-2

Exit to road. Caution sign placed here.



Rig Layout

▲ H2S Detectors. At least three detectors will be installed: bell nipple, rig floor and Shakers.


● Briefing Areas. At least two briefing areas will be placed, 90 deg off.

■ Wind direction indicators. Visible from rig floor and from the mud pits area.


A gas buster is connected to both the choke manifold and flowline outlets.

Secondary Briefing Area


Primary Briefing Area



WIND: Prevailing winds are from the Southwest



Secondary Egress



Permian Drilling Hydrogen Sulfide Drilling Operations Plan New Mexico

Scope

This contingency plan establishes guidelines for the public, all company employees, and contract employees who's work activities may involve exposure to hydrogen sulfide (H₂S) gas.

While drilling this well, it is possible to encounter H₂S bearing formations. At all times, the first barrier to control H₂S emissions will be the drilling fluid, which will have a density high enough to control influx.

Objective

1. Provide an immediate and predetermined response plan to any condition when H₂S is detected. All H₂S detections in excess of 10 parts per million (ppm) concentration are considered an Emergency.
2. Prevent any and all accidents, and prevent the uncontrolled release of hydrogen sulfide into the atmosphere.
3. Provide proper evacuation procedures to cope with emergencies.
4. Provide immediate and adequate medical attention should an injury occur.

Discussion

Implementation:	This plan with all details is to be fully implemented before drilling to <u>commence</u> .
Emergency response Procedure:	This section outlines the conditions and denotes steps to be taken in the event of an emergency.
Emergency equipment Procedure:	This section outlines the safety and emergency equipment that will be required for the drilling of this well.
Training provisions:	This section outlines the training provisions that must be adhered to prior to drilling.
Drilling emergency call lists:	Included are the telephone numbers of all persons to be contacted should an emergency exist.
Briefing:	This section deals with the briefing of all people involved in the drilling operation.
Public safety:	Public safety personnel will be made aware of any potential evacuation and any additional support needed.
Check lists:	Status check lists and procedural check lists have been included to insure adherence to the plan.
General information:	A general information section has been included to supply support information.

Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on the well:

1. The hazards and characteristics of H2S.
2. Proper use and maintenance of personal protective equipment and life support systems.
3. H2S detection.
4. Proper use of H2S detectors, alarms, warning systems, briefing areas, evacuation procedures and prevailing winds.
5. Proper techniques for first aid and rescue procedures.
6. Physical effects of hydrogen sulfide on the human body.
7. Toxicity of hydrogen sulfide and sulfur dioxide.
8. Use of SCBA and supplied air equipment.
9. First aid and artificial respiration.
10. Emergency rescue.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H2S on metal components. If high tensile strength tubular is to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling a well, blowout prevention and well control procedures.
3. The contents and requirements of the H2S Drilling Operations Plan.

H2S training refresher must have been taken within one year prior to drilling the well. Specifics on the well to be drilled will be discussed during the pre-spud meeting. H2S and well control (choke) drills will be performed while drilling the well, at least on a weekly basis. This plan shall be available in the well site. All personnel will be required to carry the documentation proving that the H2S training has been taken.

Service company and visiting personnel

- A. Each service company that will be on this well will be notified if the zone contains H2S.
- B. Each service company must provide for the training and equipment of their employees before they arrive at the well site.
- C. Each service company will be expected to attend a well site briefing

Emergency Equipment Requirements

1. Well control equipment

The well shall have hydraulic BOP equipment for the anticipated pressures. Equipment is to be tested on installation and follow Oxy Well Control standard, as well as BLM Onshore Order #2.

Special control equipment:

- A. Hydraulic BOP equipment with remote control on ground. Remotely operated choke.
- B. Rotating head
- C. Gas buster equipment shall be installed before drilling out of surface pipe.

2. Protective equipment for personnel

- A. Four (4) 30-minute positive pressure air packs (2 at each briefing area) on location.
- B. Adequate fire extinguishers shall be located at strategic locations.
- C. Radio / cell telephone communication will be available at the rig.
 - Rig floor and trailers.
 - Vehicle.

3. Hydrogen sulfide sensors and alarms

- A. H₂S sensor with alarms will be located on the rig floor, at the bell nipple, and at the flow line. These monitors will be set to alarm at 10 ppm with strobe light, and audible alarm.
- B. Hand operated detectors with tubes.
- C. H₂S monitor tester (to be provided by contract Safety Company.)
- D. There shall be one combustible gas detector on location at all times.

4. Visual Warning Systems

- A. One sign located at each location entrance with the following language:

**Caution – potential poison gas
Hydrogen sulfide
No admittance without authorization**

Wind sock – wind streamers:

- A. One 36" (in length) wind sock located at protection center, at height visible from rig floor.
- B. One 36" (in length) wind sock located at height visible from pit areas.

Condition flags

- A. One each condition flag to be displayed to denote conditions.

green – normal conditions
yellow – potential danger
red – danger, H₂S present

- B. Condition flag shall be posted at each location sign entrance.

5. Mud Program

The mud program is designed to minimize the risk of having H₂S and other formation fluids at surface. Proper mud weight and safe drilling practices will be applied. H₂S scavengers will be used to minimize the hazards while drilling. Below is a summary of the drilling program.

Mud inspection devices:

Garrett gas train or hatch tester for inspection of sulfide concentration in mud system.

6. Metallurgy

- A. Drill string, casing, tubing, wellhead, blowout preventers, drilling spools or adapters, kill lines, choke manifold, lines and valves shall be suitable for the H₂S service.
- B. All the elastomers, packing, seals and ring gaskets shall be suitable for H₂S service.

7. Well Testing

No drill stem test will be performed on this well.

8. Evacuation plan

Evacuation routes should be established prior to well spud for each well and discussed with all rig personnel.

9. Designated area

- A. Parking and visitor area: all vehicles are to be parked at a predetermined safe distance from the wellhead.
- B. There will be a designated smoking area.
- C. Two briefing areas on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds perpendicularly, or at a 45-degree angle if wind direction tends to shift in the area.

Emergency procedures

- A. In the event of any evidence of H₂S level above 10 ppm, take the following steps:
 - 1. The Driller will pick up off bottom, shut down the pumps, slow down the pipe rotation.
 - 2. Secure and don escape breathing equipment, report to the upwind designated safe briefing / muster area.
 - 3. All personnel on location will be accounted for and emergency search should begin for any missing, the Buddy System will be implemented.
 - 4. Order non-essential personnel to leave the well site, order all essential personnel out of the danger zone and upwind to the nearest designated safe briefing / muster area.
 - 5. Entrance to the location will be secured to a higher level than our usual "Meet and Greet" requirement, and the proper condition flag will be displayed at the entrance to the location.
 - 6. Take steps to determine if the H₂S level can be corrected or suppressed and, if so, proceed as required.
- B. If uncontrollable conditions occur:
 - 1. Take steps to protect and/or remove any public in the down-wind area from the rig – partial evacuation and isolation. Notify necessary public safety personnel and appropriate regulatory entities (i.e. BLM) of the situation.

- 2. Remove all personnel to the nearest upwind designated safe briefing / muster area or off location.
- 3. Notify public safety personnel of safe briefing / muster area.
- 4. An assigned crew member will blockade the entrance to the location. No unauthorized personnel will be allowed entry to the location.
- 5. Proceed with best plan (at the time) to regain control of the well. Maintain tight security and safety procedures.

C. Responsibility:

- 1. Designated personnel.
 - a. Shall be responsible for the total implementation of this plan.
 - b. Shall be in complete command during any emergency.
 - c. Shall designate a back-up.

- All personnel:
- 1. On alarm, don escape unit and report to the nearest upwind designated safe briefing / muster area upw
 - 2. Check status of personnel (buddy system).
 - 3. Secure breathing equipment.
 - 4. Await orders from supervisor.

- Drill site manager:
- 1. Don escape unit if necessary and report to nearest upwind designated safe briefing / muster area.
 - 2. Coordinate preparations of individuals to return to point of release with tool pusher and driller (using the buddy system).
 - 3. Determine H2S concentrations.
 - 4. Assess situation and take control measures.

- Tool pusher:
- 1. Don escape unit Report to up nearest upwind designated safe briefing / muster area.
 - 2. Coordinate preparation of individuals to return to point of release with tool pusher drill site manager (using the buddy system).
 - 3. Determine H2S concentration.
 - 4. Assess situation and take control measures.

- Driller:
- 1. Don escape unit, shut down pumps, continue

- rotating DP.
2. Check monitor for point of release.
 3. Report to nearest upwind designated safe briefing / muster area.
 4. Check status of personnel (in an attempt to rescue, use the buddy system).
 5. Assigns least essential person to notify Drill Site Manager and tool pusher by quickest means in case of their absence.
 6. Assumes the responsibilities of the Drill Site Manager and tool pusher until they arrive should they be absent.
- Derrick man
Floor man #1
Floor man #2
1. Will remain in briefing / muster area until instructed by supervisor.
- Mud engineer:
1. Report to nearest upwind designated safe briefing / muster area.
 2. When instructed, begin check of mud for ph and H₂S level. (Garett gas train.)
- Safety personnel:
1. Mask up and check status of all personnel and secure operations as instructed by drill site manager.

Taking a kick

When taking a kick during an H₂S emergency, all personnel will follow standard Well control procedures after reporting to briefing area and masking up.

Open-hole logging

All unnecessary personnel off floor. Drill Site Manager and safety personnel should monitor condition, advise status and determine need for use of air equipment.

Running casing or plugging

Following the same "tripping" procedure as above. Drill Site Manager and safety personnel should determine if all personnel have access to protective equipment.

Ignition procedures

The decision to ignite the well is the responsibility of the operator (Oxy Drilling Management). The decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.
2. There is no hope controlling the blowout under the prevailing conditions at the well.

Instructions for igniting the well

1. Two people are required for the actual igniting operation. They must wear self-contained breathing units and have a safety rope attached. One man (tool pusher or safety engineer) will check the atmosphere for explosive gases with the gas monitor. The other man is responsible for igniting the well.
2. Primary method to ignite: 25 mm flare gun with range of approximately 500 feet.
3. Ignite upwind and do not approach any closer than is warranted.
4. Select the ignition site best for protection, and which offers an easy escape route.
5. Before firing, check for presence of combustible gas.
6. After lighting, continue emergency action and procedure as before.
7. All unassigned personnel will remain in briefing area until instructed by supervisor or directed by the Drill Site Manager.

Remember: After well is ignited, burning hydrogen sulfide will convert to sulfur dioxide, which is also highly toxic. **Do not assume the area is safe after the well is ignited.**

Status check list

Note: All items on this list must be completed before drilling to production casing point.

1. H₂S sign at location entrance.
2. Two (2) wind socks located as required.
3. Four (4) 30-minute positive pressure air packs (2 at each Briefing area) on location for all rig personnel and mud loggers.
4. Air packs inspected and ready for use.
5. Cascade system and hose line hook-up as needed.
6. Cascade system for refilling air bottles as needed.
7. Condition flag on location and ready for use.
8. H₂S detection system hooked up and tested.
9. H₂S alarm system hooked up and tested.
10. Hand operated H₂S detector with tubes on location.
11. 1 – 100' length of nylon rope on location.
12. All rig crew and supervisors trained as required.
13. All outside service contractors advised of potential H₂S hazard on well.
14. No smoking sign posted and a designated smoking area identified.
15. Calibration of all H₂S equipment shall be noted on the IADC report.

Checked by: _____ Date: _____

Procedural check list during H₂S events

Perform each tour:

1. Check fire extinguishers to see that they have the proper charge.
2. Check breathing equipment to ensure that it is in proper working order.
3. Make sure all the H₂S detection system is operative.

Perform each week:

1. Check each piece of breathing equipment to make sure that demand or forced air regulator is working. This requires that the bottle be opened and the mask assembly be put on tight enough so that when you inhale, you receive air or feel air flow.
2. BOP skills (well control drills).
3. Check supply pressure on BOP accumulator stand by source.
4. Check breathing equipment mask assembly to see that straps are loosened and turned back, ready to put on.
5. Check pressure on breathing equipment air bottles to make sure they are charged to full volume. (Air quality checked for proper air grade "D" before bringing to location)
6. Confirm pressure on all supply air bottles.
7. Perform breathing equipment drills with on-site personnel.
8. Check the following supplies for availability.
 - A. Emergency telephone list.
 - B. Hand operated H₂S detectors and tubes.

General evacuation plan

1. When the company approved supervisor (Drill Site Manager, consultant, rig pusher, or driller) determines the H₂S gas cannot be limited to the well location and the public will be involved, he will activate the evacuation plan.
2. Drill Site Manager or designee will notify local government agency that a hazardous condition exists and evacuation needs to be implemented.
3. Company or contractor safety personnel that have been trained in the use of H₂S detection equipment and self-contained breathing equipment will monitor H₂S concentrations, wind directions, and area of exposure. They will delineate the outer perimeter of the hazardous gas area. Extension to the evacuation area will be determined from information gathered.
4. Law enforcement personnel (state police, police dept., fire dept., and sheriff's dept.) Will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.
5. After the discharge of gas has been controlled, company safety personnel will determine when the area is safe for re-entry.

Important: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

Emergency actions

Well blowout – if emergency

1. Evacuate all personnel to “Safe Briefing / Muster Areas” or off location if needed.
2. If sour gas – evacuate rig personnel.
3. If sour gas – evacuate public within 3000 ft radius of exposure.
4. Don SCBA and shut well in if possible using the buddy system.
5. Notify Drilling Superintendent and call 911 for emergency help (fire dept and ambulance) if needed.
6. Implement the Blowout Contingency Plan, and Drilling Emergency Action Plan.
6. Give first aid as needed.

Person down location/facility

1. If immediately possible, contact 911. Give location and wait for confirmation.
2. Don SCBA and perform rescue operation using buddy system.

Toxic effects of hydrogen sulfide

Hydrogen sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 ppm, which is .001% by volume. Hydrogen sulfide is heavier than air (specific gravity – 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in table i. Physical effects at various hydrogen sulfide exposure levels are shown in table ii.

Table i
Toxicity of various gases

Common name	Chemical formula	Specific gravity (sc=1)	Threshold limit (1)	Hazardous limit (2)	Lethal concentration (3)
Hydrogen Cyanide	Hcn	0.94	10 ppm	150 ppm/hr	300 ppm
Hydrogen Sulfide	H ₂ S	1.18	10 ppm	250 ppm/hr	600 ppm
Sulfur Dioxide	So ₂	2.21	5 ppm	-	1000 ppm
Chlorine	Cl ₂	2.45	1 ppm	4 ppm/hr	1000 ppm
Carbon Monoxide	Co	0.97	50 ppm	400 ppm/hr	1000 ppm
Carbon Dioxide	Co ₂	1.52	5000 ppm	5%	10%
Methane	Ch ₄	0.55	90,000 ppm	Combustible above 5% in air	

- 1) threshold limit – concentration at which it is believed that all workers may be repeatedly exposed day after day without adverse effects.
- 2) hazardous limit – concentration that will cause death with short-term exposure.
- 3) lethal concentration – concentration that will cause death with short-term exposure.

Toxic effects of hydrogen sulfide

Table ii
Physical effects of hydrogen sulfide

<u>Percent (%)</u>	<u>Ppm</u>	<u>Concentration</u> Grains 100 std. Ft ³ *	<u>Physical effects</u>
0.001	<10	00.65	Obvious and unpleasant odor.

0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kill smell in 3 - 15 minutes. May sting eyes and throat.
0.020	200	12.96	Kills smell shortly; stings eyes and throat.
0.050	500	32.96	Dizziness; breathing ceases in a few minutes; needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; followed by death within minutes.

*at 15.00 psia and 60'f.

Use of self-contained breathing equipment (SCBA)

1. Written procedures shall be prepared covering safe use of SCBA's in dangerous atmosphere, which might be encountered in normal operations or in emergencies. Personnel shall be familiar with these procedures and the available SCBA.
2. SCBA's shall be inspected frequently at random to insure that they are properly used, cleaned, and maintained.
3. Anyone who may use the SCBA's shall be trained in how to insure proper face-piece to face seal. They shall wear SCBA's in normal air and then wear them in a test atmosphere. (note: such items as facial hair {beard or sideburns} and eyeglasses will not allow proper seal.) Anyone that may be reasonably expected to wear SCBA's should have these items removed before entering a toxic atmosphere. A special mask must be obtained for anyone who must wear eyeglasses or contact lenses.
4. Maintenance and care of SCBA's:
 - a. A program for maintenance and care of SCBA's shall include the following:
 1. Inspection for defects, including leak checks.
 2. Cleaning and disinfecting.
 3. Repair.
 4. Storage.
 - b. Inspection, self-contained breathing apparatus for emergency use shall be inspected monthly.
 1. Fully charged cylinders.
 2. Regulator and warning device operation.
 3. Condition of face piece and connections.
 4. Rubber parts shall be maintained to keep them pliable and prevent deterioration.
 - c. Routinely used SCBA's shall be collected, cleaned and disinfected as frequently as necessary to insure proper protection is provided.
5. Persons assigned tasks that requires use of self-contained breathing equipment shall be certified physically fit (medically cleared) for breathing equipment usage at least annually.
6. SCBA's should be worn when:
 - A. Any employee works near the top or on top of any tank unless test reveals less than 10 ppm of H₂S.

- B. When breaking out any line where H₂S can reasonably be expected.
- C. When sampling air in areas to determine if toxic concentrations of H₂S exists.
- D. When working in areas where over 10 ppm H₂S has been detected.
- E. At any time there is a doubt as to the H₂S level in the area to be entered.

Rescue
First aid for H₂S poisoning

Do not panic!

Remain calm – think!

1. Don SCBA breathing equipment.
2. Remove victim(s) utilizing buddy system to fresh air as quickly as possible. (go up-wind from source or at right angle to the wind. Not down wind.)
3. Briefly apply chest pressure – arm lift method of artificial respiration to clean the victim's lungs and to avoid inhaling any toxic gas directly from the victim's lungs.
4. Provide for prompt transportation to the hospital, and continue giving artificial respiration if needed.
5. Hospital(s) or medical facilities need to be informed, before-hand, of the possibility of H₂S gas poisoning – no matter how remote the possibility is.
6. Notify emergency room personnel that the victim(s) has been exposed to H₂S gas.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration.

Revised CM 6/27/2012

Surface Use Plan of Operations

Operator Name/Number: OXY USA Inc. – 16696
Lease Name/Number: Cedar Canyon 22 Federal #21H
Pool Name/Number: Pierce Crossing Bone Spring, East – 96473
Surface Location: 2540 FSL 230 FEL NESE (I) Sec 22 T24S R29E NMNM81586
Bottom Hole Location: 1830 FNL 180 FWL SWNW (E) Sec 22 T24S R29E

1. Existing Roads

- a. A copy of the USGS "Pierce Canyon, NM" quadrangle map is attached showing the proposed location. The well location is spotted on the map, which shows the existing road system.
- b. The well was staked by Terry J. Asel, Certificate No. 15079 on 10/27/15, certified 10/28/15.
- c. Directions to Location: From the intersection of USH 285 and Black River Road in Malaga, go east on CR 720 for 0.8 miles. Turn left on CR 745 and go north for 1.0 miles. Turn right and go east/northeast for 2.1 miles. Turn right on Dog Town road and go southeast for 1.3 miles. Turn left on caliche road and go east/southeast for 2.1 miles, continue south for 1.6 miles. Turn left and go northeast then southeast for 1.1 miles to location.

2. New or Reconstructed Access Roads:

- a. No new access road will be built.
- b. Surfacing material: N/A
- c. Maximum Grade: N/A
- d. Turnouts: None needed
- e. Drainage Design: N/A
- f. Culverts: None needed
- g. Cut and fills: N/A
- h. Gates or cattleguards: none required
- i. Blade, water & repair existing caliche road as needed.

3. Location of Existing Wells:

Existing wells within a one mile radius of the proposed well are shown on attached plat.

4. Location of Existing and/or Proposed Facilities:

- a. In the event the well is found productive, the Cedar Canyon 22 Federal tank battery would be utilized and the necessary production equipment will be installed at the well site. See proposed Production Facilities Layout diagram.
- b. Electric line already exists on current well pad.
- c. All flow lines will adhere to API standards, see attached for detail and proposed route. 3-4" composite flowline along surveyed route operating <75% MAWP. Survey for a strip of land 50.0' wide and 4721.5' in length crossing USA land in Section 22 T24S R29E, N.M.P.M. Eddy County, NM and being 25' left and 25' right of the attached platted centerline surveys, see attached.

6. Construction Materials:

Primary

All caliche utilized for the drilling pad and proposed access road will be obtained from an existing BLM/State/Fee approved pit or from prevailing deposits found on the location. Will use BLM recommended extra caliche from other locations close by for roads, if available.

Secondary

The secondary way of obtaining caliche to build locations and roads will be by "turning over" the location. This means, caliche will be obtained from the actual well site. A caliche permit will be obtained from BLM prior to pushing up any caliche. 2400 cubic yards is max amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:

- a. The top 6" of topsoil is pushed off and stockpiled along the side of the location.
- b. An approximate 120' X 120' area is used within the proposed well site to remove caliche.
- c. Subsoil is removed and piled alongside the 120' X 120' within the pad site.
- d. When caliche is found, material will be stockpiled within the pad site to build the location and road.
- e. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
- f. Once the well is drilled the stockpiled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced. Neither caliche nor subsoil will be stockpiled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in the attached plat.

7. Methods of Handling Waste Material:

- a. A closed loop system will be utilized consisting of above ground steel tanks and haul-off bins. Disposal of liquids, drilling fluids and cuttings will be disposed of at an approved facility. Solids-CRI, Liquids-Laguna
- b. All trash, junk and other waste material will be contained in trash cages or bins to prevent scattering. When the job is completed, all contents will be removed and disposed of in an approved sanitary landfill.
- c. The supplier, including broken sacks, will pickup slats remaining after completion of well.
- d. A Porto-john will be provided for the rig crews. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.
- e. Disposal of fluids to be transported will be by the following companies. TFH Ltd, Laguna SWD Facility

8. Ancillary Facilities: None needed.

9. Well Site Layout:

The proposed well site layout with dimensions of the pad layout and equipment location.

V-Door – East

CL Tanks – North

Pad – 280' X 470' (600')

10. Plans for Surface Reclamation:

- a. After concluding the drilling and/or completion operations, if the well is found non-commercial, the caliche will be removed from the pad and transported to the original caliche pit or used for other drilling locations. The road will be reclaimed as directed by the BLM. The original topsoil will again be returned to the pad and contoured, as close as possible, to the original topography, and the area will be seeded with an approved BLM mixture to re-establish vegetation.
- b. If the well is deemed commercially productive, caliche from the areas of the pad site not required for operations will be reclaimed. The original topsoil will be returned to the area of the drill pad not necessary to operate the well.

These unused areas of the drill pad will be contoured, as close as possible, to match the original topography, and the area will be seeded with an approved BLM mixture to re-establish vegetation.

11. Surface Ownership:

The surface is owned by the U.S. Government and is administered by the BLM. The surface is multiple use with the primary uses of the region for the grazing of livestock and the production of oil and gas. The surface is leased to: Henry McDonald, P.O. Box 597, Loving, NM 88256 – John D. Brantley, 706 Riverside Dr., Carlsbad, NM 88220. They will be notified of our intention to drill prior to any activity.

12. Other Information:

- a. The vegetation cover is generally sparse consisting of mesquite, yucca, shinnery oak, sandsage and perennial native range grass. The topsoil is sandy in nature. Wildlife in the area is also sparse consisting of deer, coyotes, rabbits, rodents, reptiles, dove and quail.
- b. There is no permanent or live water in the general proximity of the location.
- c. There are no dwellings within one mile of the proposed well site.
- d. Cultural Resources Examination – This well will be on a multi-well pad to accommodate batch drilling with skidding operations. An EA has already been done on the pad and one of the wells has an approved APD, the Cedar Canyon 23 Federal #3H, API No. 30-015-43290.

13. Bond Coverage:

Bond coverage is Individual-NMB000862, Nationwide-ESB00226.

14. Operators Representatives:

The OXY Permian representatives responsible for ensuring compliance of the surface use plan are listed below:

Don Kendrick
 Production Coordinator
 1502 West Commerce Dr.
 Carlsbad, NM 88220
 Office – 575-628-4132
 Cellular – 575-602-1484

Charles Wagner
 Manager Field Operations
 1502 West Commerce Dr.
 Carlsbad, NM 88220
 Office – 575-628-4151
 Cellular – 575-725-8306

Calvin (Dusty) Weaver
 Operation Specialist
 P.O. Box 50250
 Midland, TX 79710
 Office – 432-685-5723
 Cellular – 806-893-3067

Omar Lisigurski
 RMT Leader
 P.O. Box 4294
 Houston, TX 77210
 Office – 713-215-7506
 Cellular – 281-222-7248

Oxy U.S.A Inc.

New Mexico Staking Form

Date Staked: 11-9-15

Lease/Well Name: Cedar Canyon 22 Fed # 214

Legal Description: 2540 FSL 230 FEL Sec 22 T24.5 R29E

Latitude: 32.2025036 NAD 27

Longitude: -103.9640113

Move Information:

County: Eddy

Surface Owner/Tenant: BLM

Nearest Residence: 2 mile

Nearest Water Well:

V-Door: EAST

Road Description: Road into SW corner from SOUTH

New Road: 0

Upgrade Existing Road:

Interim Reclamation:

Source of Caliche:

Top Soil:

Onsite Date Performed:

Onsite Attendees:

Special Notes:

OPERATOR NAME / NUMBER: OXY USA INC

16696

LEASE NAME / NUMBER: Cedar Canyon 22 Federal #21H Federal Lease No. NMNM81586

STATE: NM

COUNTY: Eddy

POOL NAME/NUMBER: Pierce Crossing Bone Spring, East 96473

SURFACE LOCATION: 2540 FSL 230 FEL NESE (I) Sec 22 T24S R29E
SL: LAT: 32.2025036N LONG:103.9640113W X:614235.88 Y:437586.71 NAD: 27

TOP PERFORATION: 1830 FNL 335 FEL SENE (H) Sec 22 T24S R29E
TP: LAT: 32.2050816N LONG:103.9643486W X:614128.34 Y:438524.17 NAD: 27

BOTTOM PERFORATION: 1830 FNL 335 FWL SWNW (E) Sec 22 T24S R29E
BP: LAT: 32.2051302N LONG:103.9793047W X:609502.26 Y:438526.29 NAD: 27

BOTTOM HOLE LOCATION: 1830 FNL 180 FWL SWNW (E) Sec 22 T24S R29E
BHL: LAT: 32.2051318N LONG:103.9798058W X:609347.26 Y:438526.36 NAD: 27

APPROX GR ELEV: 2958.4'


EST KB ELEV: 2983.4' (25' KB-GL)

COMPANY PERSONNEL:

<u>Name</u>	<u>Title</u>	<u>Office Phone</u>	<u>Mobile Phone</u>
R. Chan Tysor	Drilling Engineer	713-513-6668	832-564-6454
Ryan Farrell	Drilling Engineer Supervisor	713-366-5058	832-291-4744
Roger Allen	Drilling Superintendent	713-215-7617	281-682-3919

OPERATOR CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 17th day of December, 2015.

Signature: 
Name: Omar Lisigurski
Position: Reservoir Management Team Leader
Address: 5 Greenway Plaza, Suite 110, Houston, TX 77046
Telephone: 713-215-7506
E-mail: (optional): omar_lisigurski@oxy.com
Company: Occidental Permian LP/OXY USA Inc /OXY USA WTP LP
Field Representative (if not above signatory): Dusty Weaver
Address (if different from above): P.O. Box 50250 Midland, TX 79710
Telephone (if different from above): 432-685-5723
E-mail (if different from above): calvin_weaver@oxy.com

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	OXY USA Inc
LEASE NO.:	NM81586
WELL NAME & NO.:	21H-Cedar Canyon 22 Federal
SURFACE HOLE FOOTAGE:	2540'/S & 260'/E
BOTTOM HOLE FOOTAGE:	1830'/N & 180'/W
LOCATION:	Section 22, T. 24 S., R. 29 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
 - Range
 - VRM
 - Karst
 - Watershed
- Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- Road Section Diagram**
- Drilling**
 - Medium Cave/Karst
 - Logging Requirements
 - Waste Material and Fluids
- Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
- Interim Reclamation**
- Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Livestock Watering Requirement

Structures that provide water to livestock, such as windmills, pipelines, drinking troughs, and earthen reservoirs, will be avoided by moving the proposed action.

Above-ground structures including meter housing that are not subject to safety requirements are painted a flat non-reflective paint color, Shale Green from the BLM Standard Environmental Color Chart (CC-001: June 2008).

Low-profile tanks not greater than eight-feet-high shall be used.

Construction Mitigation

In order to mitigate the impacts from construction activities on cave and karst resources, the following Conditions of Approval will apply to this APD:

- In the event that any underground voids are encountered during construction activities, construction activities will be halted and the BLM will be notified immediately.
- No Blasting to prevent geologic structure instabilities.
- Pad Berming to minimize effects of any spilled contaminants.

Drilling Mitigation

Federal regulations and standard Conditions of Approval applied to all APDs require that adequate measures are taken to prevent contamination to the environment. Due to the extreme sensitivity of the cave and karst resources in this project area, the following additional Conditions of Approval will be added to this APD.

To prevent cave and karst resource contamination the following will be required.

- Closed Mud System Using Steel Tanks with All Fluids and Cuttings Hauled Off.
- Rotary drilling with fresh water where cave or karst features are expected to prevent contamination of freshwater aquifers.
- Directional Drilling allowed after at least 100 feet below the cave occurrence zone to prevent additional impacts resulting from directional drilling.
- Lost Circulation zones logged and reported in the drilling report so BLM can assess the situation and work with the operator on corrective actions.
- Additional drilling, casing, and cementing procedures to protect cave zones and fresh water aquifers. See Drilling COAs.

Production Mitigation

In order to mitigate the impacts from production activities and due to the nature of karst terrain, the following Conditions of Approval will apply to this APD:

- Tank battery liners and berms to minimize the impact resulting from leaks.

- Leak detection system to provide an early alert to operators when a leak has occurred.
- Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of line failures used in production or drilling.

Residual and Cumulative Mitigation

- Nontoxic fluorescent dyes will be added to the drilling fluid when the hole is spudded and will be circulated to the bottom of the karst layers. This provides data as part of a long-term monitoring study.
- Annual pressure monitoring will be performed by the operator. If the test results indicate a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

Plugging and Abandonment Mitigation

Abandonment Cementing: Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

- **The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The berm shall be maintained through the life of the well and after interim reclamation has been completed.**
- **Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion.**

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattleguards

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. **Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. **The operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. (For surface casing the BOP can be nipped up after the cement has reached 500 psi compressive strength.)

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Medium cave/karst

Possible water flows in Castile and Salado.

Possible lost circulation in Rustler, Salado and Delaware.

1. The 10 3/4 inch surface casing shall be set at approximately 480 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, the operator shall set the casing 25' above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Formation below the 10-3/4" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe and the mud weight for the bottom of the hole. Report results to BLM office.

The 7-5/8 inch intermediate casing must be kept liquid filled while running into hole to meet minimum BLM requirements for collapse.

2. The minimum required fill of cement behind the 7-5/8 inch intermediate casing is:

a. First stage to DV tool:

- Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

Operator has proposed a contingency DV tool at 3075'. If operator circulates cement on the first stage, operator is approved to inflate the ACP and run the DV tool cancellation plug and cancel the second stage of the proposed cement plan. If cement does not circulate, operator will inflate ACP and proceed with the second stage.

b. Second stage above DV tool:

- Cement to surface. If cement does not circulate see B.1.a, c-d above.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.

Formation below the 7-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.

3. The minimum required fill of cement behind the 5-1/2 x 4-1/2 inch production casing is:

- Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification.

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored

according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).

3. **Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 5000 (5M) psi.**
 - a. **Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.**
 - b. **If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.**
 - c. **Manufacturer representative shall install the test plug for the initial BOP test.**
 - d. **Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.**
 - e. **If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.**

5M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.

4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer.**

- c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

CRW 011116

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all

open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

VRM Facility Requirement

Low-profile tanks not greater than eight-feet-high shall be used.

B. PIPELINES

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the application (Grant, Sundry Notice, APD) and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
- b. Activities of other parties including, but not limited to:

- (1) Land clearing.
- (2) Earth-disturbing and earth-moving work.
- (3) Blasting.
- (4) Vandalism and sabotage.

c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

6. All construction and maintenance activity will be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline must be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline must be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.

8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline will be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species	lb/acre
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sand love grass (<i>Eragrostis trichodes</i>)	1.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed