

RECEIVED

JAN 28 2019

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
DISTRICT II-ARTESIA O.C.D.

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. OMLC0029338B
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator EOG RESOURCES INCORPORATED		8. Lease Name and Well No. KIRK FEDERAL COM 3H 324919
3a. Address 1111 Bagby Sky Lobby2 Houston TX 77002	3b. Phone No. (include area code) (713)651-7000	9. API Well No. 30-015-45662
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NWNW / 1296 FNL / 628 FWL / LAT 32.852722 / LONG -103.9319416 At proposed prod. zone NENE / 502 FNL / 100 FEL / LAT 32.8548667 / LONG -103.9171176		10. Field and Pool, or Exploratory LOGO HILLS / GLORIETA YESO 96718
11. Sec., T, R, M, or Blk. and Survey or Area SEC 12 / T17S / R30E / NMP		12. County or Parish EDDY
13. State NM		14. Distance in miles and direction from nearest town or post office* 30.3 miles
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 628 feet	16. No of acres in lease 160	17. Spacing Unit dedicated to this well 240
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 550 feet	19. Proposed Depth 4840 feet / 8560 feet	20. BLM/BIA Bond No. in file FED: NM2308
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3745 feet	22. Approximate date work will start* 01/15/2019	23. Estimated duration 60 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM. |

25. Signature (Electronic Submission)	Name (Printed/Typed) Tina Huerta / Ph: (575)748-4168	Date 08/07/2018
Title Regulatory Specialist		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	Date 01/24/2019
Title Assistant Field Manager Lands & Minerals		
Office CARLSBAD		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

APPROVED WITH CONDITIONS

(Continued on page 2)

*(Instructions on page 2)

Approval Date: 01/24/2019

RNP 1-30-19

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM 1: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM connects this information to a new evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

1. SHL: NWNW / 1296 FNL / 628 FWL / TWSP: 17S / RANGE: 30E / SECTION: 12 / LAT: 32.852722 / LONG: -103.9319416 (TVD: 0 feet, MD: 0 feet)
PPP: NENW / 502 FNL / 1420 FWL / TWSP: 17S / RANGE: 30E / SECTION: 12 / LAT: 32.8548987 / LONG: -103.9293599 (TVD: 4835 feet, MD: 5801 feet)
BHL: NENE / 502 FNL / 100 FEL / TWSP: 17S / RANGE: 30E / SECTION: 12 / LAT: 32.8548667 / LONG: -103.9171976 (TVD: 4840 feet, MD: 9560 feet)

BLM Point of Contact

Name: Katrina Ponder
Title: Geologist
Phone: 5752345969
Email: kponder@blm.gov

CONFIDENTIAL

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

CONFIDENTIAL

PECOS DISTRICT

DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	EOG Resources Incorporated
LEASE NO.:	NMLC0029338B
WELL NAME & NO.:	Kirk Federal Com 3H
SURFACE HOLE FOOTAGE:	1296'/N & 628'/W
BOTTOM HOLE FOOTAGE:	502'/N & 100'/E
LOCATION:	Section 12, T.17 S., R.30 E., NMPM
COUNTY:	Eddy County, New Mexico

COA

H2S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP

A. Hydrogen Sulfide

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Grayburg** formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING

1. The 9-5/8 inch surface casing shall be set at approximately **400** feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 7 x 5 ½ inch intermediate casing is:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above.

C. PRESSURE CONTROL

- 1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M) psi**.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties
Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.
During office hours call (575) 627-0272.
After office hours call (575)

☒ Eddy County
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County
Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

- 1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).

- b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log (one log per well pad is acceptable) run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:

- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
 - c. The tests shall be done by an independent service company utilizing a test plug. The results of the test shall be reported to the appropriate BLM office.
 - d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be

submitted to the appropriate BLM office.

- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

ZS 122818

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	EOG Resources Incorporated
LEASE NO.:	NMLC0029338B
WELL NAME & NO.:	Kirk Federal Com 3H
SURFACE HOLE FOOTAGE:	1296'/N & 628'/W
BOTTOM HOLE FOOTAGE	502'/N & 100'/E
LOCATION:	Section 12, T.17 S., R.30 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Ground-level Abandoned Well Marker
 - Hydrology
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

Timing Limitation Exceptions:

The Carlsbad Field Office will publish an annual map of where the LPC timing and noise stipulations and conditions of approval (Limitations) will apply for the identified year (between March 1 and June 15) based on the latest survey information. The LPC Timing Area map will identify areas which are Habitat Areas (HA), Isolated Population Area (IPA), and Primary Population Area (PPA). The LPC Timing Area map will also have an area in red crosshatch. The red crosshatch area is the only area where an operator is required to submit a request for exception to the LPC Limitations. If an operator is operating outside the red crosshatch area, the LPC Limitations do not apply for that year and an exception to LPC Limitations is not required.

Hydrology:

The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. The compacted berm shall be constructed at a minimum of 12 inches with impermeable mineral material (e.g. caliche). Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion. Stockpiling of topsoil is required. The top soil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control. If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Electric Lines: Any water erosion that may occur due to the construction of overhead electric line and during the life of the power line will be quickly corrected and proper measures will be taken to prevent future erosion.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.


Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.


Construction Steps

1. Salvage topsoil
2. Construct road


3. Redistribute topsoil
4. Revegetate slopes




Typical Turnout Plan




Level Ground Section



Side Hill Section



Typical Outslope Section



Typical Inslope Section

Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, Shale Green from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the Grant and attachments, including stipulations, survey plat(s) and/or map(s), shall be on location during construction. BLM personnel may request to review a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, Holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC § 2601 *et seq.* (1982) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant (*see* 40 CFR, Part 702-799 and in particular, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193). Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. Holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. § 9601, *et seq.* or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, *et seq.*) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way Holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way Holder on the Right-of-Way. This provision applies without

regard to whether a release is caused by Holder, its agent, or unrelated third parties.

4. Holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. Holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of Holder including, but not limited to: construction, operation, maintenance, and termination of the facility;
- b. Activities of other parties including, but not limited to:
 - (1) Land clearing
 - (2) Earth-disturbing and earth-moving work
 - (3) Blasting
 - (4) Vandalism and sabotage;

c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of Holder, regardless of fault. Upon failure of Holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he/she deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of Holder. Such action by the Authorized Officer shall not relieve Holder of any responsibility as provided herein.

6. All construction and maintenance activity shall be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline shall be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline shall be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity shall be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation shall be allowed unless approved in

writing by the Authorized Officer.

8. Holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline shall be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible

for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines shall be less than or equal to 4 inches and a working pressure below 125 psi.

18. Special Stipulations:

- a. **Lesser Prairie-Chicken:** Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

01/24/2019

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Tina Huerta

Signed on: 08/07/2018

Title: Regulatory Specialist

Street Address: 104 SOUTH FOURTH STREET

City: Artesia

State: NM

Zip: 88210

Phone: (575)748-4168

Email address: tina_huerta@eogresources.com

Field Representative

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data Report

01/24/2019

APD ID: 10400032289

Submission Date: 08/07/2018

Highlighted data
reflects the most
recent changes

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - General

APD ID: 10400032289

Tie to previous NOS?

Submission Date: 08/07/2018

BLM Office: CARLSBAD

User: Tina Huerta

Title: Regulatory Specialist

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMLC0029338B

Lease Acres: 160

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: EOG RESOURCES INCORPORATED

Operator letter of designation:

Operator Info

Operator Organization Name: EOG RESOURCES INCORPORATED

Operator Address: 1111 Bagby Sky Lobby2

Zip: 77002

Operator PO Box:

Operator City: Houston

State: TX

Operator Phone: (713)651-7000

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: KIRK FEDERAL COM

Well Number: 3H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: LOCO HILLS

Pool Name: GLORIETA YESO

Is the proposed well in an area containing other mineral resources? USEABLE WATER,OIL

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

Describe other minerals:

Is the proposed well in a Helium production area? N **Use Existing Well Pad?** NO **New surface disturbance?**

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: KIRK **Number:** 1H
FEDERAL COM

Well Class: HORIZONTAL

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 30.3 Miles

Distance to nearest well: 550 FT

Distance to lease line: 628 FT

Reservoir well spacing assigned acres Measurement: 240 Acres

Well plat: C102_20181030144853.pdf

Well work start Date: 01/15/2019

Duration: 60 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	129 6	FNL	628	FWL	17S	30E	12	Aliquot NWN W	32.85272 2	- 103.9319 416	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 029338 B	374 5	0	0
KOP Leg #1	129 6	FNL	628	FWL	17S	30E	12	Aliquot NWN W	32.85272 2	- 103.9319 416	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 029338 B	-265	401 0	401 0
PPP Leg #1	502	FNL	142 0	FWL	17S	30E	12	Aliquot NENW	32.85489 87	- 103.9293 599	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 002748	- 109 0	580 1	483 5

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
EXIT Leg #1	502	FNL	100	FEL	17S	30E	12	Aliquot NENE	32.85486 67	- 103.9171 176	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 055264	- 109 5	956 0	484 0
BHL Leg #1	502	FNL	100	FEL	17S	30E	12	Aliquot NENE	32.85486 67	- 103.9171 176	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 055264	- 109 5	956 0	484 0



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

01/24/2019

APD ID: 10400032289

Submission Date: 08/07/2018

Highlighted data
reflects the most
recent changes

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	RUSTLER	3745	300	300		USEABLE WATER,OIL	No
2	GRAYBURG	969	2776	2776		OIL	No
3	SAN ANDRES	661	3084	3084		OIL	No
4	GLORIETA	-797	4542	4542		OIL	No
5	YESO	-856	4601	4601		OIL	Yes

Section 2 - Blowout Prevention

Pressure Rating (PSI): 3M

Rating Depth: 400

Equipment: Rotating head, remote hydraulic choke, flare line. A multibowl wellhead system will be used

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart

Testing Procedure: The minimum blowout preventer equipment (BOPE) attached will consist of mud cross and double ram-type (3000 psi WP) preventer and an annular preventer (3000 psi WP). Both units will be hydraulically operated and the ram-type will be equipped with blind rams on bottom and drill pipe rams on top. All BOPE will be tested in accordance with Onshore Order No. 2. Before drilling out the surface casing, the ram-type BOP and accessory equipment will be tested to 3000/250 psig and the annular preventer to 1500/250 psig. The surface casing will be tested to 1500 psi for 30 minutes. Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. A hydraulically operated choke will be installed prior to drilling out of the surface casing shoe.

Choke Diagram Attachment:

3MChokeManifoldDiagram_20180727143157.pdf

BOP Diagram Attachment:

3000BOPEXHIBIT1_20180727143210.pdf

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	12.25	9.625	NEW	API	N	0	400	0	400			400	J-55	36	LTC	1.125	1.25	BUOY	1.8	BUOY	1.6
2	PRODUCTION	8.75	7.0	NEW	API	N	0	4752	0	4752			4752	L-80	29	BUTT	1.125	1.25	BUOY	1.8	BUOY	1.6
3	PRODUCTION	8.75	5.5	NEW	API	N	4752	9560	4752	9560			4808	L-80	17	BUTT	1.125	1.25	BUOY	1.8	BUOY	1.6

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

KirkFederalCom3HBLMPlan_20180802161326.pdf

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

Casing Attachments

Casing ID: 2 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

KirkFederalCom3HBLMPlan_20180802161336.pdf

Casing ID: 3 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

KirkFederalCom3HBLMPlan_20180802161345.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	400	190	1.34	1.34	45	100	Class C	Calcium Chloride

PRODUCTION	Lead		0	4752	390	2.47	11.9	172	35	Class 50/50 Poz C	BWOW, Salt, Bentonite Gel, Anti Settling Agent, Kolseal, Celloflake, Defoamer
------------	------	--	---	------	-----	------	------	-----	----	-------------------	---

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Lead		4752	9560	1110	1.48	13	293	35	Class PVL	BWOW, Salt, Expanding Cement, Fluid Loss, Anti Settling Agent, Defoamer

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Adequate Barite to raise mud weight in system to 10 ppg

Describe the mud monitoring system utilized: Pason Flow Sensors and PVT Monitor Systems

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
400	9429	WATER-BASED MUD	9.2	10.2							
0	400	WATER-BASED MUD	8.6	8.8							

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

No logs planned for this well

List of open and cased hole logs run in the well:

DS

Coring operation description for the well:

No coring planned

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 2554

Anticipated Surface Pressure: 1489.2

Anticipated Bottom Hole Temperature(F): 105

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

KirkFederalCom3HH2SPlanSummaryAPD_20180727143335.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

KirkFederalCom3HSurveys_20180802163109.pdf

KirkFederalCom3HPlot_20180802163120.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

Kirk3HGasCapture_20180727143406.pdf

KirkFederalCom3HH2SPlanSummaryAPD_20180731133337.pdf

WellheadSystemSurfProd_20180731133358.pdf

WellheadSystemProd_20180731133435.pdf

WellSiteDiagram_20180731133514.pdf

FlexHoseAtt_20180731133548.pdf

KirkWaterMap_20180731133658.pdf

KirkWellsAerialMap_20180731133659.pdf

KirkWellsMiscMap_20180731133659.pdf

KirkFederalCom3HPlat_20180731133734.pdf

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

KirkFederalCom3HAnticollisionRpt_20180802163725.pdf

KirkFederalCom3HOtherAtt_20180802164317.pdf

KirkFederalCom3HWellboreSchematic_20180802164422.pdf

KirkWellsInfrastructure_20181010075922.pdf

KirkFederalCom3HReclamationPlat10dayletterResponse_20181010080521.pdf

KirkFederalCom3H10dayletter_20181011143624.pdf

Other Variance attachment:

EXHIBIT 1a
EOG Resources, Inc.
3M Choke Manifold Equipment





EXHIBIT 1

EOG Resources
3000 PSI BOPE



**EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H**

1. GEOLOGIC NAME OF SURFACE FORMATION:

Permian

2. ESTIMATED TOPS OF IMPORTANT GEOLOGICAL MARKERS:

Rustler	300'
Tansill	1,313'
Yates	1,483'
Seven Rivers	1,758'
Queen	2,352'
Grayburg	2,776'
San Andres	3,084'
Glorieta	4,542'
Yeso	4,601'
TD	9,560'

3. ESTIMATED DEPTHS OF ANTICIPATED FRESH WATER, OIL OR GAS:

Rustler	300'	Fresh Water, Oil
Grayburg	2,776'	Oil
San Andres	3,084'	Oil
Glorieta	4,542'	Oil
Yeso	4,601'	Oil

No other Formations are expected to give up oil, gas or fresh water in measurable quantities. Surface fresh water sands will be protected by setting 9.625" casing at 400' and circulating cement back to surface.

4. CASING PROGRAM - NEW

Hole Size	Interval	Csg OD	Weight	Grade	Conn	DF _{min} Collapse	DF _{min} Burst	DF _{min} Tension
12.25"	0'-400'	9.625"	36#	J-55	LTC	1.125	1.25	1.60
8.75"	0' -4752 '	7"	29#	L-80	BTC	1.125	1.25	1.60
8.75"	4752'-9560'	5 ½"	17#	L-80	BTC	1.125	1.25	1.60

**EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H**

Cementing Program:

Note: Cement volumes based on bit size plus at least 100% excess on surface and 35% excess in production string.

Depth	No. Sacks	Wt. lb/gal	Yld Ft ³ /ft	Volume Ft ³	Slurry Description
400'	190	1.34	1.34	45	Tail: Class 'C' + 2%PF1(Calcium Chloride) (100% excess)
9560'	390	11.9	2.47	172	Lead: Class 50/50 PozC + 5%PF44(BWOW)(Salt) + 10% PF20(Bentonite Gel) +.2%PF153(Anti Settling Agent(+ 3#/sk OF42(Kolseal) + 0.125#/sk PF29 (celloflake) + 0.4#/sk PF45 (Defoamer) (TOC @ Surface) 35% Excess
	1110	13	1.48	293	Tail: Class PVL + 1.3% PF44(BWOW)(Salt) + 5% PF174 (Expanding Cement) + 0.5% PF606 (Fluid Loss) + 0.1% PF153 (Anti Settling Agent) + 0.4#/sk PF45 (Defoamer) 35% Excess

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

A variance is requested to use a co-flex line between the BOP and choke manifold, dependent on rig selection (instead of using a steel line). Certification and specs are attached.

The minimum blowout preventer equipment (BOPE) shown in Exhibit #1 will consist of a double rams with blind rams & pipe rams preventer (3,000 psi WP) and an annular preventer (3,000-psi WP). Both units will be hydraulically operated and the ram-type will be equipped with blind rams on bottom and drill pipe rams on top. All BOPE will be tested in accordance with Onshore Oil & Gas order No. 2.

Before drilling out of the surface casing, the ram-type BOP and accessory equipment will be tested to 3,000/ 250 psig and the annular preventer to 1,500/ 250 psig. The surface casing will be tested to 1200 psi for 30 minutes.

Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets.

A hydraulically operated choke will be installed prior to drilling out of the surface casing shoe.

EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H

6. TYPES AND CHARACTERISTICS OF THE PROPOSED MUD SYSTEM:

During this procedure we plan to use a Closed-Loop System and haul contents to the required disposal.

The applicable depths and properties of the drilling fluid systems are as follows.

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0 – 400'	Fresh Water	8.6-8.8	28-32	N/c
400' – 9560' Vertical/Curve/Lateral	Brine/Cut Brine	9.2-10.2	32-34	N/c

The highest mud weight needed to balance formation is expected to be 10.2 ppg. In order to maintain hole stability, mud weights up to 10.2 ppg may be utilized.

An electronic pit volume totalizer (PVT) will be utilized on the circulating system, to monitor pit volume, flow rate, pump pressure and stroke rate.

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept at the wellsite at all times.

7. AUXILIARY WELL CONTROL AND MONITORING EQUIPMENT:

- (A) A kelly cock will be kept in the drill string at all times.
- (B) A full opening drill pipe-stabbing valve (inside BOP) with proper drill pipe connections will be on the rig floor at all times.
- (C) H₂S monitoring and detection equipment will be utilized from surface casing point to TD.

8. LOGGING, TESTING AND CORING PROGRAM:

Open-hole logs are not planned for this well.

GR–Directional surveys will be run in open hole during drilling phase of operations.

9. ABNORMAL CONDITIONS, PRESSURES, TEMPERATURES AND POTENTIAL HAZARDS:

The estimated bottom-hole temperature (BHT) at TD is 105 degrees F with an estimated maximum bottom-hole pressure (BHP) at TD of 2554 psig (based on 10.2 ppg MW). Hydrogen sulfide has been encountered, reported or are known to exist at this depth in this area. Severe loss circulation is expected from spud to surface casing point.

EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H

10. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

The drilling operation should be finished in approximately one month. If the well is productive, an additional 60-90 days will be required for completion and testing before a decision is made to install permanent facilities.

(A) EOG Resources requests the option to contract a Surface Rig to drill, set surface casing, and cement on the subject well. After WOC 8 hours or 500 psi compressive strength (whichever is greater), the Surface Rig will move off so the wellhead can be installed. A welder will cut the casing to the proper height and weld on the wellhead (both "A" and "B" sections). The weld will be tested to 1000 psi. All valves will be closed and a wellhead cap will be installed (diagram attached). If the timing between rigs is such that EOG Resources would not be able to preset the surface, the Primary Rig will MIRU and drill the well in its entirety per the APD.

11. WELLHEAD:

A multi-bowl wellhead system will be utilized.

After running the 9-5/8" surface casing, a 9 5/8" BOP/BOPE system with a minimum working pressure of 3,000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 3,000 psi pressure test. This pressure test will be repeated at least every 30 days, as per Onshore Order No. 2

The minimum working pressure of the BOP and related BOPE required for drilling below the surface casing shoe shall be 3,000 psi.

The multi-bowl wellhead will be installed by vendor's representative(s). A copy of the installation instructions for the Stream Flo HES Multi-Bowl WH system has been sent to the NM BLM office in Carlsbad, NM.

The wellhead will be installed by a third party welder while being monitored by WH vendor's representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater.

EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H

1. GEOLOGIC NAME OF SURFACE FORMATION:

Permian

2. ESTIMATED TOPS OF IMPORTANT GEOLOGICAL MARKERS:

Rustler	300'
Tansill	1,313'
Yates	1,483'
Seven Rivers	1,758'
Queen	2,352'
Grayburg	2,776'
San Andres	3,084'
Glorieta	4,542'
Yeso	4,601'
TD	9,560'

3. ESTIMATED DEPTHS OF ANTICIPATED FRESH WATER, OIL OR GAS:

Rustler	300'	Fresh Water, Oil
Grayburg	2,776'	Oil
San Andres	3,084'	Oil
Glorieta	4,542'	Oil
Yeso	4,601'	Oil

No other Formations are expected to give up oil, gas or fresh water in measurable quantities.
Surface fresh water sands will be protected by setting 9.625" casing at 400' and circulating cement back to surface.

4. CASING PROGRAM - NEW

Hole Size	Interval	Csg OD	Weight	Grade	Conn	DF _{min} Collapse	DF _{min} Burst	DF _{min} Tension
12.25"	0'-400'	9.625"	36#	J-55	LTC	1.125	1.25	1.60
8.75"	0' -4752 '	7"	29#	L-80	BTC	1.125	1.25	1.60
8.75"	4752'-9560'	5 ½"	17#	L-80	BTC	1.125	1.25	1.60

**EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H**

Cementing Program:

Note: Cement volumes based on bit size plus at least 100% excess on surface and 35% excess in production string.

Depth	No. Sacks	Wt. lb/gal	Yld Ft ³ /ft	Volume Ft ³	Slurry Description
400'	190	1.34	1.34	45	Tail: Class 'C' + 2%PF1(Calcium Chloride) (100% excess)
9560'	390	11.9	2.47	172	Lead: Class 50/50 PozC + 5%PF44(BWOW)(Salt) + 10% PF20(Bentonite Gel) +.2%PF153(Anti Settling Agent(+ 3#/sk OF42(Kolseal) + 0.125#/sk PF29 (celloflake) + 0.4#/sk PF45 (Defoamer) (TOC @ Surface) 35% Excess
	1110	13	1.48	293	Tail: Class PVL + 1.3% PF44(BWOW)(Salt) + 5% PF174 (Expanding Cement) + 0.5% PF606 (Fluid Loss) + 0.1% PF153 (Anti Settling Agent) + 0.4#/sk PF45 (Defoamer) 35% Excess

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

A variance is requested to use a co-flex line between the BOP and choke manifold, dependent on rig selection (instead of using a steel line). Certification and specs are attached.

The minimum blowout preventer equipment (BOPE) shown in Exhibit #1 will consist of a double rams with blind rams & pipe rams preventer (3,000 psi WP) and an annular preventer (3,000-psi WP). Both units will be hydraulically operated and the ram-type will be equipped with blind rams on bottom and drill pipe rams on top. All BOPE will be tested in accordance with Onshore Oil & Gas order No. 2.

Before drilling out of the surface casing, the ram-type BOP and accessory equipment will be tested to 3,000/ 250 psig and the annular preventer to 1,500/ 250 psig. The surface casing will be tested to 1200 psi for 30 minutes.

Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets.

A hydraulically operated choke will be installed prior to drilling out of the surface casing shoe.

EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H

6. TYPES AND CHARACTERISTICS OF THE PROPOSED MUD SYSTEM:

During this procedure we plan to use a Closed-Loop System and haul contents to the required disposal.

The applicable depths and properties of the drilling fluid systems are as follows.

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0 – 400'	Fresh Water	8.6-8.8	28-32	N/c
400' – 9560' Vertical/Curve/Lateral	Brine/Cut Brine	9.2-10.2	32-34	N/c

The highest mud weight needed to balance formation is expected to be 10.2 ppg. In order to maintain hole stability, mud weights up to 10.2 ppg may be utilized.

An electronic pit volume totalizer (PVT) will be utilized on the circulating system, to monitor pit volume, flow rate, pump pressure and stroke rate.

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept at the wellsite at all times.

7. AUXILIARY WELL CONTROL AND MONITORING EQUIPMENT:

- (A) A kelly cock will be kept in the drill string at all times.
- (B) A full opening drill pipe-stabbing valve (inside BOP) with proper drill pipe connections will be on the rig floor at all times.
- (C) H₂S monitoring and detection equipment will be utilized from surface casing point to TD.

8. LOGGING, TESTING AND CORING PROGRAM:

Open-hole logs are not planned for this well.

GR–Directional surveys will be run in open hole during drilling phase of operations.

9. ABNORMAL CONDITIONS, PRESSURES, TEMPERATURES AND POTENTIAL HAZARDS:

The estimated bottom-hole temperature (BHT) at TD is 105 degrees F with an estimated maximum bottom-hole pressure (BHP) at TD of 2554 psig (based on 10.2 ppg MW). Hydrogen sulfide has been encountered, reported or are known to exist at this depth in this area. Severe loss circulation is expected from spud to surface casing point.

EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H

10. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

The drilling operation should be finished in approximately one month. If the well is productive, an additional 60-90 days will be required for completion and testing before a decision is made to install permanent facilities.

(A) EOG Resources requests the option to contract a Surface Rig to drill, set surface casing, and cement on the subject well. After WOC 8 hours or 500 psi compressive strength (whichever is greater), the Surface Rig will move off so the wellhead can be installed. A welder will cut the casing to the proper height and weld on the wellhead (both "A" and "B" sections). The weld will be tested to 1000 psi. All valves will be closed and a wellhead cap will be installed (diagram attached). If the timing between rigs is such that EOG Resources would not be able to preset the surface, the Primary Rig will MIRU and drill the well in its entirety per the APD.

11. WELLHEAD:

A multi-bowl wellhead system will be utilized.

After running the 9-5/8" surface casing, a 9 5/8" BOP/BOPE system with a minimum working pressure of 3,000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 3,000 psi pressure test. This pressure test will be repeated at least every 30 days, as per Onshore Order No. 2

The minimum working pressure of the BOP and related BOPE required for drilling below the surface casing shoe shall be 3,000 psi.

The multi-bowl wellhead will be installed by vendor's representative(s). A copy of the installation instructions for the Stream Flo HES Multi-Bowl WH system has been sent to the NM BLM office in Carlsbad, NM.

The wellhead will be installed by a third party welder while being monitored by WH vendor's representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater.

EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H

1. GEOLOGIC NAME OF SURFACE FORMATION:

Permian

2. ESTIMATED TOPS OF IMPORTANT GEOLOGICAL MARKERS:

Rustler	300'
Tansill	1,313'
Yates	1,483'
Seven Rivers	1,758'
Queen	2,352'
Grayburg	2,776'
San Andres	3,084'
Glorieta	4,542'
Yeso	4,601'
TD	9,560'

3. ESTIMATED DEPTHS OF ANTICIPATED FRESH WATER, OIL OR GAS:

Rustler	300'	Fresh Water, Oil
Grayburg	2,776'	Oil
San Andres	3,084'	Oil
Glorieta	4,542'	Oil
Yeso	4,601'	Oil

No other Formations are expected to give up oil, gas or fresh water in measurable quantities. Surface fresh water sands will be protected by setting 9.625" casing at 400' and circulating cement back to surface.

4. CASING PROGRAM - NEW

Hole Size	Interval	Csg OD	Weight	Grade	Conn	DF _{min} Collapse	DF _{min} Burst	DF _{min} Tension
12.25"	0'-400'	9.625"	36#	J-55	LTC	1.125	1.25	1.60
8.75"	0' -4752 '	7"	29#	L-80	BTC	1.125	1.25	1.60
8.75"	4752'-9560'	5 1/2"	17#	L-80	BTC	1.125	1.25	1.60

**EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H**

Cementing Program:

Note: Cement volumes based on bit size plus at least 100% excess on surface and 35% excess in production string.

Depth	No. Sacks	Wt. lb/gal	Yld Ft ³ /ft	Volume Ft ³	Slurry Description
400'	190	1.34	1.34	45	Tail: Class 'C' + 2%PF1(Calcium Chloride) (100% excess)
9560'	390	11.9	2.47	172	Lead: Class 50/50 PozC + 5%PF44(BWOW)(Salt) + 10% PF20(Bentonite Gel) +.2%PF153(Anti Settling Agent(+ 3#/sk OF42(Kolseal) + 0.125#/sk PF29 (celloflake) + 0.4#/sk PF45 (Defoamer) (TOC @ Surface) 35% Excess
	1110	13	1.48	293	Tail: Class PVL + 1.3% PF44(BWOW)(Salt) + 5% PF174 (Expanding Cement) + 0.5% PF606 (Fluid Loss) + 0.1% PF153 (Anti Settling Agent) + 0.4#/sk PF45 (Defoamer) 35% Excess

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

A variance is requested to use a co-flex line between the BOP and choke manifold, dependent on rig selection (instead of using a steel line). Certification and specs are attached.

The minimum blowout preventer equipment (BOPE) shown in Exhibit #1 will consist of a double rams with blind rams & pipe rams preventer (3,000 psi WP) and an annular preventer (3,000-psi WP). Both units will be hydraulically operated and the ram-type will be equipped with blind rams on bottom and drill pipe rams on top. All BOPE will be tested in accordance with Onshore Oil & Gas order No. 2.

Before drilling out of the surface casing, the ram-type BOP and accessory equipment will be tested to 3,000/ 250 psig and the annular preventer to 1,500/ 250 psig. The surface casing will be tested to 1200 psi for 30 minutes.

Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets.

A hydraulically operated choke will be installed prior to drilling out of the surface casing shoe.

EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H

6. TYPES AND CHARACTERISTICS OF THE PROPOSED MUD SYSTEM:

During this procedure we plan to use a Closed-Loop System and haul contents to the required disposal.

The applicable depths and properties of the drilling fluid systems are as follows.

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0 – 400'	Fresh Water	8.6-8.8	28-32	N/c
400' – 9560' Vertical/Curve/Lateral	Brine/Cut Brine	9.2-10.2	32-34	N/c

The highest mud weight needed to balance formation is expected to be 10.2 ppg. In order to maintain hole stability, mud weights up to 10.2 ppg may be utilized.

An electronic pit volume totalizer (PVT) will be utilized on the circulating system, to monitor pit volume, flow rate, pump pressure and stroke rate.

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept at the wellsite at all times.

7. AUXILIARY WELL CONTROL AND MONITORING EQUIPMENT:

- (A) A kelly cock will be kept in the drill string at all times.
- (B) A full opening drill pipe-stabbing valve (inside BOP) with proper drill pipe connections will be on the rig floor at all times.
- (C) H₂S monitoring and detection equipment will be utilized from surface casing point to TD.

8. LOGGING, TESTING AND CORING PROGRAM:

Open-hole logs are not planned for this well.

GR–Directional surveys will be run in open hole during drilling phase of operations.

9. ABNORMAL CONDITIONS, PRESSURES, TEMPERATURES AND POTENTIAL HAZARDS:

The estimated bottom-hole temperature (BHT) at TD is 105 degrees F with an estimated maximum bottom-hole pressure (BHP) at TD of 2554 psig (based on 10.2 ppg MW). Hydrogen sulfide has been encountered, reported or are known to exist at this depth in this area. Severe loss circulation is expected from spud to surface casing point.

**EOG RESOURCES, INC.
KIRK FEDERAL COM NO. 3H**

10. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

The drilling operation should be finished in approximately one month. If the well is productive, an additional 60-90 days will be required for completion and testing before a decision is made to install permanent facilities.

(A) EOG Resources requests the option to contract a Surface Rig to drill, set surface casing, and cement on the subject well. After WOC 8 hours or 500 psi compressive strength (whichever is greater), the Surface Rig will move off so the wellhead can be installed. A welder will cut the casing to the proper height and weld on the wellhead (both "A" and "B" sections). The weld will be tested to 1000 psi. All valves will be closed and a wellhead cap will be installed (diagram attached). If the timing between rigs is such that EOG Resources would not be able to preset the surface, the Primary Rig will MIRU and drill the well in its entirety per the APD.

11. WELLHEAD:

A multi-bowl wellhead system will be utilized.

After running the 9-5/8" surface casing, a 9 5/8" BOP/BOPE system with a minimum working pressure of 3,000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 3,000 psi pressure test. This pressure test will be repeated at least every 30 days, as per Onshore Order No. 2

The minimum working pressure of the BOP and related BOPE required for drilling below the surface casing shoe shall be 3,000 psi.

The multi-bowl wellhead will be installed by vendor's representative(s). A copy of the installation instructions for the Stream Flo HES Multi-Bowl WH system has been sent to the NM BLM office in Carlsbad, NM.

The wellhead will be installed by a third party welder while being monitored by WH vendor's representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater.

EOG RESOURCES, INC.
Kirk Federal Com 3H

Hydrogen Sulfide Plan Summary

- A. All personnel shall receive proper H₂S training in accordance with Onshore Order III.C.3.a.
- B. Briefing Area: two perpendicular areas will be designated by signs and readily accessible.
- C. Required Emergency Equipment:
- Well control equipment
 - a. Flare line 150' from wellhead to be ignited by flare gun.
 - b. Choke manifold with a remotely operated choke.
 - c. Mud/gas separator
 - Protective equipment for essential personnel.

Breathing apparatus:

 - a. Rescue Packs (SCBA) — 1 unit shall be placed at each breathing area, 2 shall be stored in the safety trailer.
 - b. Work/Escapes packs — 4 packs shall be stored on the rig floor with sufficient air hose not to restrict work activity.
 - c. Emergency Escape Packs — 4 packs shall be stored in the doghouse for emergency evacuation.

Auxiliary Rescue Equipment:

 - a. Stretcher
 - b. Two OSHA full body harness
 - c. 100 ft 5/8 inch OSHA approved rope
 - d. 1-20# class ABC fire extinguisher
 - H₂S detection and monitoring equipment:

The stationary detector with three sensors will be placed in the upper dog house if equipped, set to visually alarm @ 10 ppm and audible @ 14 ppm. Calibrate a minimum of every 30 days or as needed. The sensors will be placed in the following places: Rig floor / Bell nipple / End of flow line or where well bore fluid is being discharged.
(Gas sample tubes will be stored in the safety trailer)
 - Visual warning systems.
 - a. One color code condition sign will be placed at the entrance to the site reflecting the possible conditions at the site.
 - b. A colored condition flag will be on display, reflecting the current condition at the site at the time.
 - c. Two wind socks will be placed in strategic locations, visible from all angles.

EOG RESOURCES, INC.
Kirk Federal Com 3H

- **Mud program:**
The mud program has been designed to minimize the volume of H₂S circulated to surface. The operator will have the necessary mud products to minimize hazards while drilling in H₂S bearing zones.
- **Metallurgy:**
All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H₂S service.
- **Communication:**
Communication will be via cell phones and land lines where available.

EOG RESOURCES, INC.
Kirk Federal Com 3H

Emergency Assistance Telephone List

PUBLIC SAFETY: **911 or**

Eddy County Sheriff's Department (575) 887-7551

Fire Department:

Carlsbad (575) 885-3125

Artesia (575) 746-5050

Hospitals:

Carlsbad (575) 887-4121

Artesia (575) 748-3333

Hobbs (575) 392-1979

Dept. of Public Safety/Carlsbad (575) 748-9718

Highway Department (575) 885-3281

New Mexico Oil Conservation (575) 476-3440

U.S. Dept. of Labor (575) 887-1174

EOG Resources, Inc.

EOG / Artesia Office (575) 748-1471

Company Drilling Consultants:

Brent Patterson Cell (575) 365-7032

Drilling Engineer

Jeremiah Mullen Office (575) 748-4378

Cell (575) 703-5467

Drilling Manager

Tim Bussell Office (575) 748-4221

Cell (575) 365-5695

Safety

Brian Chandler (HSE Manager) Office (432) 686-3695

Cell (817) 239-0251



EOG Resources - Artesia

Eddy County (NAD83)

Kirk

Kirk Federal Com #3H

Lateral

Plan: Plan #1

Standard Planning Report

02 August, 2018

Database: EDM 5000.14
Company: EOG Resources - Artesia
Project: Eddy County (NAD83)
Site: Kirk
Well: Kirk Federal Com #3H
Wellbore: Lateral
Design: Plan #1

Local Co-ordinate Reference: Well Kirk Federal Com #3H
TVD Reference: KB @ 3775.000usft (Training Rig)
MD Reference: KB @ 3775.000usft (Training Rig)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Project	Eddy County (NAD83)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Kirk		
Site Position:		Northing:	673,405.00 usft
From:	Map	Easting:	664,546.00 usft
Position Uncertainty:	0.000 usft	Slot Radius:	13-3/16 "
		Latitude:	32° 51' 2.056 N
		Longitude:	103° 55' 55.649 W
		Grid Convergence:	0.22 °

Well	Kirk Federal Com #3H		
Well Position	+N/-S	783.000 usft	Northing: 674,188.00 usft
	+E/-W	53.000 usft	Easting: 664,599.00 usft
Position Uncertainty	0.000 usft	Wellhead Elevation:	3,763.000 usft
		Latitude:	32° 51' 9.802 N
		Longitude:	103° 55' 54.993 W
		Ground Level:	3,745.000 usft

Wellbore	Lateral		
Magnetics	Model Name	Sample Date	Declination
	IGRF2015	6/12/2018	(°)
			7.06
			Dip Angle (°)
			60.57
			Field Strength (nT)
			48,167.74692583

Design	Plan #1		
Audit Notes:			
Version:	Phase:	PROTOTYPE	Tie On Depth: 0.000
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W
	(usft)	(usft)	(usft)
	0.000	0.000	0.000
			Direction
			(°)
			80.050

Plan Survey Tool Program	Date 8/2/2018		
Depth From	Depth To	Survey (Wellbore)	Tool Name
(usft)	(usft)		
1 0.000	9,558.751	Plan #1 (Lateral)	MWD
			OWSG MWD - Standard

Plan Sections										
Measured Depth	Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Dogleg Rate	Build Rate	Turn Rate	TFO	Target
(usft)	(°)	(°)	(usft)	(usft)	(usft)	(°/100usft)	(°/100usft)	(°/100usft)	(°)	
0.000	0.00	0.000	0.000	0.000	0.000	0.00	0.00	0.00	0.00	
400.000	0.00	0.000	400.000	0.000	0.000	0.00	0.00	0.00	0.00	
3,500.000	0.00	0.000	3,500.000	0.000	0.000	0.00	0.00	0.00	0.00	
4,010.388	0.00	0.000	4,010.388	0.000	0.000	0.00	0.00	0.00	0.00	
4,677.054	60.00	1.000	4,561.717	318.261	5.555	9.00	9.00	0.00	1.00	
4,752.054	60.00	1.000	4,599.217	383.203	6.689	0.00	0.00	0.00	0.00	
5,493.737	89.92	89.893	4,834.465	790.377	482.999	12.00	4.03	11.99	89.51	
9,559.749	89.92	89.893	4,840.000	798.000	4,549.000	0.00	0.00	0.00	0.00	[KFC#3H]BHL1



Planning Report

Database: EDM 5000.14
 Company: EOG Resources - Artesia
 Project: Eddy County (NAD83)
 Site: Kirk
 Well: Kirk Federal Com #3H
 Wellbore: Lateral
 Design: Plan #1

Local Co-ordinate Reference: Well Kirk Federal Com #3H
 TVD Reference: KB @ 3775.000usft (Training Rig)
 MD Reference: KB @ 3775.000usft (Training Rig)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.000	0.00	0.000	0.000	0.000	0.000	0.000	0.00	0.00	0.00
100.000	0.00	0.000	100.000	0.000	0.000	0.000	0.00	0.00	0.00
200.000	0.00	0.000	200.000	0.000	0.000	0.000	0.00	0.00	0.00
300.000	0.00	0.000	300.000	0.000	0.000	0.000	0.00	0.00	0.00
400.000	0.00	0.000	400.000	0.000	0.000	0.000	0.00	0.00	0.00
500.000	0.00	0.000	500.000	0.000	0.000	0.000	0.00	0.00	0.00
600.000	0.00	0.000	600.000	0.000	0.000	0.000	0.00	0.00	0.00
700.000	0.00	0.000	700.000	0.000	0.000	0.000	0.00	0.00	0.00
800.000	0.00	0.000	800.000	0.000	0.000	0.000	0.00	0.00	0.00
900.000	0.00	0.000	900.000	0.000	0.000	0.000	0.00	0.00	0.00
1,000.000	0.00	0.000	1,000.000	0.000	0.000	0.000	0.00	0.00	0.00
1,100.000	0.00	0.000	1,100.000	0.000	0.000	0.000	0.00	0.00	0.00
1,200.000	0.00	0.000	1,200.000	0.000	0.000	0.000	0.00	0.00	0.00
1,300.000	0.00	0.000	1,300.000	0.000	0.000	0.000	0.00	0.00	0.00
1,400.000	0.00	0.000	1,400.000	0.000	0.000	0.000	0.00	0.00	0.00
1,500.000	0.00	0.000	1,500.000	0.000	0.000	0.000	0.00	0.00	0.00
1,600.000	0.00	0.000	1,600.000	0.000	0.000	0.000	0.00	0.00	0.00
1,700.000	0.00	0.000	1,700.000	0.000	0.000	0.000	0.00	0.00	0.00
1,800.000	0.00	0.000	1,800.000	0.000	0.000	0.000	0.00	0.00	0.00
1,900.000	0.00	0.000	1,900.000	0.000	0.000	0.000	0.00	0.00	0.00
2,000.000	0.00	0.000	2,000.000	0.000	0.000	0.000	0.00	0.00	0.00
2,100.000	0.00	0.000	2,100.000	0.000	0.000	0.000	0.00	0.00	0.00
2,200.000	0.00	0.000	2,200.000	0.000	0.000	0.000	0.00	0.00	0.00
2,300.000	0.00	0.000	2,300.000	0.000	0.000	0.000	0.00	0.00	0.00
2,400.000	0.00	0.000	2,400.000	0.000	0.000	0.000	0.00	0.00	0.00
2,500.000	0.00	0.000	2,500.000	0.000	0.000	0.000	0.00	0.00	0.00
2,600.000	0.00	0.000	2,600.000	0.000	0.000	0.000	0.00	0.00	0.00
2,700.000	0.00	0.000	2,700.000	0.000	0.000	0.000	0.00	0.00	0.00
2,800.000	0.00	0.000	2,800.000	0.000	0.000	0.000	0.00	0.00	0.00
2,900.000	0.00	0.000	2,900.000	0.000	0.000	0.000	0.00	0.00	0.00
3,000.000	0.00	0.000	3,000.000	0.000	0.000	0.000	0.00	0.00	0.00
3,100.000	0.00	0.000	3,100.000	0.000	0.000	0.000	0.00	0.00	0.00
3,200.000	0.00	0.000	3,200.000	0.000	0.000	0.000	0.00	0.00	0.00
3,300.000	0.00	0.000	3,300.000	0.000	0.000	0.000	0.00	0.00	0.00
3,400.000	0.00	0.000	3,400.000	0.000	0.000	0.000	0.00	0.00	0.00
3,500.000	0.00	0.000	3,500.000	0.000	0.000	0.000	0.00	0.00	0.00
3,600.000	0.00	0.000	3,600.000	0.000	0.000	0.000	0.00	0.00	0.00
3,700.000	0.00	0.000	3,700.000	0.000	0.000	0.000	0.00	0.00	0.00
3,800.000	0.00	0.000	3,800.000	0.000	0.000	0.000	0.00	0.00	0.00
3,900.000	0.00	0.000	3,900.000	0.000	0.000	0.000	0.00	0.00	0.00
4,000.000	0.00	0.000	4,000.000	0.000	0.000	0.000	0.00	0.00	0.00
4,010.388	0.00	0.000	4,010.388	0.000	0.000	0.000	0.00	0.00	0.00
KOP 9°/100' BUILD RATE									
4,050.000	3.57	1.000	4,049.974	1.232	0.022	0.234	9.00	9.00	0.00
4,100.000	8.07	1.000	4,099.704	6.296	0.110	1.186	9.00	9.00	0.00
4,150.000	12.57	1.000	4,148.883	15.245	0.266	2.896	9.00	9.00	0.00
4,200.000	17.07	1.000	4,197.209	28.025	0.489	5.324	9.00	9.00	0.00
4,250.000	21.57	1.000	4,244.382	44.556	0.778	8.465	9.00	9.00	0.00
4,300.000	26.07	1.000	4,290.113	64.737	1.130	12.299	9.00	9.00	0.00
4,350.000	30.57	1.000	4,334.120	88.443	1.544	16.802	9.00	9.00	0.00
4,400.000	35.07	1.000	4,376.130	115.529	2.017	21.948	9.00	9.00	0.00
4,450.000	39.57	1.000	4,415.885	145.826	2.545	27.704	9.00	9.00	0.00
4,500.000	44.07	1.000	4,453.141	179.149	3.127	34.034	9.00	9.00	0.00
4,550.000	48.57	1.000	4,487.667	215.292	3.758	40.901	9.00	9.00	0.00



Planning Report

Database: EDM 5000.14
 Company: EOG Resources - Artesia
 Project: Eddy County (NAD83)
 Site: Kirk
 Well: Kirk Federal Com #3H
 Wellbore: Lateral
 Design: Plan #1

Local Co-ordinate Reference: Well Kirk Federal Com #3H
 TVD Reference: KB @ 3775.000usft (Training Rig)
 MD Reference: KB @ 3775.000usft (Training Rig)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,600.000	53.07	1.000	4,519.250	254.031	4.434	48.260	9.00	9.00	0.00
4,650.000	57.57	1.000	4,547.696	295.129	5.152	56.068	9.00	9.00	0.00
4,677.055	60.00	1.000	4,561.717	318.262	5.555	60.462	9.00	9.00	0.00
START 75' TANGENT									
4,700.000	60.00	1.000	4,573.189	338.130	5.902	64.237	0.00	0.00	0.00
4,752.055	60.00	1.000	4,599.217	383.204	6.689	72.800	0.00	0.00	0.00
END 60° TANGENT									
4,775.000	60.06	4.178	4,610.681	403.057	7.587	77.115	12.00	0.27	13.85
4,800.000	60.22	7.633	4,623.131	424.617	9.817	83.037	12.00	0.61	13.82
4,825.000	60.46	11.074	4,635.507	446.047	13.348	90.217	12.00	0.97	13.76
4,850.000	60.79	14.496	4,647.773	467.288	18.169	98.636	12.00	1.33	13.69
4,875.000	61.21	17.892	4,659.897	488.280	24.267	108.269	12.00	1.67	13.59
4,900.000	61.71	21.259	4,671.844	508.968	31.625	119.091	12.00	2.01	13.47
4,925.000	62.29	24.592	4,683.583	529.293	40.223	131.072	12.00	2.33	13.33
4,950.000	62.96	27.887	4,695.081	549.201	50.038	144.179	12.00	2.65	13.18
4,975.000	63.69	31.142	4,706.307	568.636	61.043	158.377	12.00	2.95	13.02
5,000.000	64.50	34.353	4,717.230	587.546	73.208	173.626	12.00	3.24	12.84
5,025.000	65.38	37.519	4,727.819	605.879	86.498	189.884	12.00	3.52	12.66
5,050.000	66.33	40.639	4,738.046	623.583	100.879	207.107	12.00	3.78	12.48
5,075.000	67.34	43.713	4,747.884	640.612	116.310	225.248	12.00	4.03	12.30
5,100.000	68.40	46.741	4,757.304	656.918	132.748	244.257	12.00	4.26	12.11
5,125.000	69.52	49.724	4,766.281	672.456	150.150	264.082	12.00	4.47	11.93
5,150.000	70.69	52.662	4,774.791	687.185	168.468	284.669	12.00	4.67	11.75
5,175.000	71.90	55.558	4,782.809	701.062	187.650	305.960	12.00	4.86	11.58
5,200.000	73.16	58.414	4,790.315	714.051	207.645	327.899	12.00	5.03	11.42
5,225.000	74.46	61.231	4,797.288	726.117	228.398	350.424	12.00	5.19	11.27
5,250.000	75.79	64.013	4,803.708	737.225	249.851	373.474	12.00	5.33	11.13
5,275.000	77.15	66.761	4,809.558	747.345	271.947	396.986	12.00	5.45	10.99
5,300.000	78.54	69.480	4,814.822	756.450	294.624	420.895	12.00	5.57	10.87
5,325.000	79.96	72.172	4,819.485	764.514	317.820	445.136	12.00	5.67	10.77
5,350.000	81.40	74.840	4,823.535	771.516	341.472	469.643	12.00	5.75	10.67
5,375.000	82.85	77.488	4,826.960	777.437	365.515	494.347	12.00	5.83	10.59
5,400.000	84.33	80.119	4,829.752	782.260	389.884	519.182	12.00	5.89	10.52
5,425.000	85.81	82.736	4,831.902	785.971	414.510	544.079	12.00	5.93	10.47
5,450.000	87.30	85.344	4,833.405	788.562	439.327	568.971	12.00	5.97	10.43
5,475.000	88.80	87.945	4,834.256	790.024	464.267	593.788	12.00	5.99	10.40
5,493.738	89.92	89.893	4,834.465	790.377	482.999	612.300	12.00	6.00	10.39
[KFC#3H]EOC1 5484' MD (4834' TVD)									
5,500.000	89.92	89.893	4,834.474	790.389	489.261	618.470	0.00	0.00	0.00
5,600.000	89.92	89.893	4,834.610	790.576	589.261	716.998	0.00	0.00	0.00
5,700.000	89.92	89.893	4,834.746	790.764	689.261	815.526	0.00	0.00	0.00
5,800.000	89.92	89.893	4,834.882	790.951	789.260	914.054	0.00	0.00	0.00
5,800.747	89.92	89.893	4,834.883	790.953	790.007	914.790	0.00	0.00	0.00
[KFC#3H]FTP1 5801' MD (4835' TVD)									
5,900.000	89.92	89.893	4,835.018	791.139	889.260	1,012.582	0.00	0.00	0.00
6,000.000	89.92	89.893	4,835.154	791.326	989.260	1,111.110	0.00	0.00	0.00
6,100.000	89.92	89.893	4,835.290	791.514	1,089.260	1,209.638	0.00	0.00	0.00
6,200.000	89.92	89.893	4,835.426	791.701	1,189.259	1,308.166	0.00	0.00	0.00
6,300.000	89.92	89.893	4,835.563	791.889	1,289.259	1,406.694	0.00	0.00	0.00
6,400.000	89.92	89.893	4,835.699	792.076	1,389.259	1,505.222	0.00	0.00	0.00
6,500.000	89.92	89.893	4,835.835	792.264	1,489.258	1,603.751	0.00	0.00	0.00
6,600.000	89.92	89.893	4,835.971	792.451	1,589.258	1,702.279	0.00	0.00	0.00
6,700.000	89.92	89.893	4,836.107	792.639	1,689.258	1,800.807	0.00	0.00	0.00

Database: EDM 5000.14
Company: EOG Resources - Artesia
Project: Eddy County (NAD83)
Site: Kirk
Well: Kirk Federal Com #3H
Wellbore: Lateral
Design: Plan #1

Local Co-ordinate Reference: Well Kirk Federal Com #3H
TVD Reference: KB @ 3775.000usft (Training Rig)
MD Reference: KB @ 3775.000usft (Training Rig)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
6,800.000	89.92	89.893	4,836.243	792.826	1,789.258	1,899.335	0.00	0.00	0.00
6,900.000	89.92	89.893	4,836.379	793.014	1,889.257	1,997.863	0.00	0.00	0.00
7,000.000	89.92	89.893	4,836.515	793.201	1,989.257	2,096.391	0.00	0.00	0.00
7,100.000	89.92	89.893	4,836.652	793.389	2,089.257	2,194.919	0.00	0.00	0.00
7,200.000	89.92	89.893	4,836.788	793.576	2,189.257	2,293.447	0.00	0.00	0.00
7,300.000	89.92	89.893	4,836.924	793.763	2,289.256	2,391.975	0.00	0.00	0.00
7,400.000	89.92	89.893	4,837.060	793.951	2,389.256	2,490.503	0.00	0.00	0.00
7,500.000	89.92	89.893	4,837.196	794.138	2,489.256	2,589.031	0.00	0.00	0.00
7,600.000	89.92	89.893	4,837.332	794.326	2,589.255	2,687.559	0.00	0.00	0.00
7,700.000	89.92	89.893	4,837.468	794.513	2,689.255	2,786.088	0.00	0.00	0.00
7,800.000	89.92	89.893	4,837.604	794.701	2,789.255	2,884.616	0.00	0.00	0.00
7,900.000	89.92	89.893	4,837.741	794.888	2,889.255	2,983.144	0.00	0.00	0.00
8,000.000	89.92	89.893	4,837.877	795.076	2,989.254	3,081.672	0.00	0.00	0.00
8,100.000	89.92	89.893	4,838.013	795.263	3,089.254	3,180.200	0.00	0.00	0.00
8,200.000	89.92	89.893	4,838.149	795.451	3,189.254	3,278.728	0.00	0.00	0.00
8,300.000	89.92	89.893	4,838.285	795.638	3,289.254	3,377.256	0.00	0.00	0.00
8,400.000	89.92	89.893	4,838.421	795.826	3,389.253	3,475.784	0.00	0.00	0.00
8,500.000	89.92	89.893	4,838.557	796.013	3,489.253	3,574.312	0.00	0.00	0.00
8,600.000	89.92	89.893	4,838.693	796.201	3,589.253	3,672.840	0.00	0.00	0.00
8,700.000	89.92	89.893	4,838.829	796.388	3,689.252	3,771.368	0.00	0.00	0.00
8,800.000	89.92	89.893	4,838.966	796.576	3,789.252	3,869.896	0.00	0.00	0.00
8,900.000	89.92	89.893	4,839.102	796.763	3,889.252	3,968.425	0.00	0.00	0.00
9,000.000	89.92	89.893	4,839.238	796.951	3,989.252	4,066.953	0.00	0.00	0.00
9,100.000	89.92	89.893	4,839.374	797.138	4,089.251	4,165.481	0.00	0.00	0.00
9,200.000	89.92	89.893	4,839.510	797.326	4,189.251	4,264.009	0.00	0.00	0.00
9,300.000	89.92	89.893	4,839.646	797.513	4,289.251	4,362.537	0.00	0.00	0.00
9,400.000	89.92	89.893	4,839.782	797.700	4,389.251	4,461.065	0.00	0.00	0.00
9,500.000	89.92	89.893	4,839.918	797.888	4,489.250	4,559.593	0.00	0.00	0.00
9,559.749	89.92	89.893	4,840.000	798.000	4,549.000	4,618.463	0.00	0.00	0.00

[KFC#3H]BHL1 9560' MD (4840' TVD)

Design Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
[KFC#3H]FTP1	0.00	0.000	4,835.000	795.000	790.000	674,983.00	665,389.00	32° 51' 17.638 N	103° 55' 45.696 W
- hit/miss target									
- Shape									
- plan misses target center by 4.049usft at 5800.747usft MD (4834.883 TVD, 790.953 N, 790.008 E)									
- Point									
[KFC#3H]BHL1	0.00	0.073	4,840.000	798.000	4,549.000	674,986.00	669,148.00	32° 51' 17.523 N	103° 55' 1.629 W
- plan hits target center									
- Point									

Database:	EDM 5000.14	Local Co-ordinate Reference:	Well Kirk Federal Com #3H
Company:	EOG Resources - Artesia	TVD Reference:	KB @ 3775.000usft (Training Rig)
Project:	Eddy County (NAD83)	MD Reference:	KB @ 3775.000usft (Training Rig)
Site:	Kirk	North Reference:	Grid
Well:	Kirk Federal Com #3H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Lateral		
Design:	Plan #1		

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
4,010.388	4,010.388	0.000	0.000	KOP 9°/100' BUILD RATE
4,677.055	4,561.717	318.262	5.555	START 75' TANGENT
4,752.055	4,599.217	383.204	6.689	END 60° TANGENT
5,493.738	4,834.465	790.377	482.999	[KFC#3H]EOC1 5494' MD (4834' TVD)
5,800.747	4,834.883	790.953	790.007	[KFC#3H]FTP1 5801' MD (4835' TVD)
9,559.749	4,840.000	798.000	4,549.000	[KFC#3H]BHL1 9560' MD (4840' TVD)

Project: Eddy County (NAD83)
 Site: Kirk
 Well: Kirk Federal Com #3H
 Wellbore: Lateral
 Design: Plan #1
 Ground Elevation 3745.000
 Northing 674188.00
 Easting 664599.00
 KB @ 3763.000usft (Planning Rig)

PROJECT DETAILS: Eddy County (NAD83)

Geodetic System: US State Plane 1983
 Datum: North American Datum 1983
 Ellipsoid: GRS 1980
 Zone: New Mexico Eastern Zone

System Datum: Mean Sea Level




SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect
1	0.000	0.00	0.000	0.000	0.000	0.000	0.00	0.00	0.000
2	400.000	0.00	0.000	400.000	0.000	0.000	0.00	0.00	0.000
3	3500.000	0.00	0.000	3500.000	0.000	0.000	0.00	0.00	0.000
4	4010.388	0.00	0.000	4010.388	0.000	0.000	0.00	0.00	0.000
5	4677.055	60.00	1.000	4561.717	318.261	5.555	9.00	1.00	60.462
6	4752.055	60.00	1.000	4599.217	383.203	6.689	0.00	0.00	72.800
7	5493.738	89.92	89.893	4834.465	790.377	482.999	12.00	89.51	612.300
8	9559.750	89.92	89.893	4840.000	798.000	4549.000	0.00	0.00	4618.463

DESIGN TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting
[KFC#3H]FTP1	4835.000	795.000	790.000	674983.00	665389.00
- plan misses target center by 4.049usft at 5800.747usft MD (4834.883 TVD, 790.953 N, 790.008 E)					
[KFC#3H]BHL1	4840.000	798.000	4549.000	674986.00	669148.00
- plan hits target center					



EOG RESOURCES, INC.
Kirk Federal Com 3H

Hydrogen Sulfide Plan Summary

- A. All personnel shall receive proper H₂S training in accordance with Onshore Order III.C.3.a.
- B. Briefing Area: two perpendicular areas will be designated by signs and readily accessible.
- C. Required Emergency Equipment:
 - Well control equipment
 - a. Flare line 150' from wellhead to be ignited by flare gun.
 - b. Choke manifold with a remotely operated choke.
 - c. Mud/gas separator
 - Protective equipment for essential personnel.

Breathing apparatus:

 - a. Rescue Packs (SCBA) — 1 unit shall be placed at each breathing area, 2 shall be stored in the safety trailer.
 - b. Work/Escapes packs — 4 packs shall be stored on the rig floor with sufficient air hose not to restrict work activity.
 - c. Emergency Escape Packs — 4 packs shall be stored in the doghouse for emergency evacuation.

Auxiliary Rescue Equipment:

 - a. Stretcher
 - b. Two OSHA full body harness
 - c. 100 ft 5/8 inch OSHA approved rope
 - d. 1-20# class ABC fire extinguisher
 - H₂S detection and monitoring equipment:

The stationary detector with three sensors will be placed in the upper dog house if equipped, set to visually alarm @ 10 ppm and audible @ 14 ppm. Calibrate a minimum of every 30 days or as needed. The sensors will be placed in the following places: Rig floor / Bell nipple / End of flow line or where well bore fluid is being discharged.
(Gas sample tubes will be stored in the safety trailer)
 - Visual warning systems.
 - a. One color code condition sign will be placed at the entrance to the site reflecting the possible conditions at the site.
 - b. A colored condition flag will be on display, reflecting the current condition at the site at the time.
 - c. Two wind socks will be placed in strategic locations, visible from all angles.

EOG RESOURCES, INC.
Kirk Federal Com 3H

- **Mud program:**
The mud program has been designed to minimize the volume of H₂S circulated to surface. The operator will have the necessary mud products to minimize hazards while drilling in H₂S bearing zones.
- **Metallurgy:**
All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H₂S service.
- **Communication:**
Communication will be via cell phones and land lines where available.

EOG RESOURCES, INC.
Kirk Federal Com 3H

Emergency Assistance Telephone List

PUBLIC SAFETY: **911 or**

Eddy County Sheriff's Department (575) 887-7551

Fire Department:

Carlsbad (575) 885-3125

Artesia (575) 746-5050

Hospitals:

Carlsbad (575) 887-4121

Artesia (575) 748-3333

Hobbs (575) 392-1979

Dept. of Public Safety/Carlsbad (575) 748-9718

Highway Department (575) 885-3281

New Mexico Oil Conservation (575) 476-3440

U.S. Dept. of Labor (575) 887-1174

EOG Resources, Inc.

EOG / Artesia Office (575) 748-1471

Company Drilling Consultants:

Brent Patterson Cell (575) 365-7032

Drilling Engineer

Jeremiah Mullen Office (575) 748-4378

Cell (575) 703-5467

Drilling Manager


Tim Bussell Office (575) 748-4221

Cell (575) 365-5695

Safety

Brian Chandler (HSE Manager) Office (432) 686-3695

Cell (817) 239-0251



*CONCEPT QUOTE DRAWING

EDG RESOURCES INC.


9-5/8" X 7" 5M
HES WELLHEAD SYSTEM
QUOTE: HDU - 119274

DWN	CB	1/25/18
CHK		
APP		
	BY	DATE



Worldwide Expertise - Global Strength

DRAWING NO
WH-17830



*CONCEPT QUOTE DRAWING

EOG RESOURCES INC.

9-5/8" X 5-1/2" 5M
HES WELLHEAD SYSTEM
QUOTE: HDU - 119274

DWN	CB	3/01/18
CHK		
APP		
	BY	DATE




Worldwide Expertise - Global Strength

DRAWING NO
WH-17830
PG 2

EOG Resources

Well Site Diagram



Manufacturer: Midwest Hose & Specialty

Serial Number: SN#90067

Length: 35'

Size: OD = 8" ID = 4"

Ends: Flanges Size: 4-1/16"

WP Rating: 10,000 psi Anchors required by manufacturer: No

M I D W E S T
HOSE AND SPECIALTY INC.

INTERNAL HYDROSTATIC TEST REPORT			
Customer: CACTUS		P.O. Number: RIG #123	
Asset # M10761			
HOSE SPECIFICATIONS			
Type: CHOKE LINE		Length: 35'	
I.D. 4" INCHES		O.D. 8" INCHES	
WORKING PRESSURE 10,000 PSI	TEST PRESSURE 15,000 PSI		BURST PRESSURE PSI
COUPLINGS			
Type of End Fitting 4 1/16 10K FLANGE			
Type of Coupling: SWEDGED		MANUFACTURED BY MIDWEST HOSE & SPECIALTY	
PROCEDURE			
<i>Hose assembly pressure tested with water at ambient temperature.</i>			
TIME HELD AT TEST PRESSURE 1 MIN.		ACTUAL BURST PRESSURE: 0 PSI	
COMMENTS: SN#90087 M10761 Hose is covered with stainless steel armour cover and wrapped with fire resistant vermiculite coated fiberglass insulation rated for 1500 degrees complete with lifting eyes			
Date: 6/6/2011	Tested By: BOBBY FINK		Approved: MENDI JACKSON



Midwest Hose
& Specialty, Inc.

Internal Hydrostatic Test Graph

Customer: CACTUS


SALES ORDER# 90067

Hose Specifications

<u>Hose Type</u>	<u>Length</u>
C & K	35'
<u>I.D.</u>	<u>O.D.</u>
4"	8"
<u>Working Pressure</u>	<u>Burst Pressure</u>
10000 PSI	Standard Safety Multiplier Applies

Verification

<u>Type of Fitting</u>	<u>Coupling Method</u>
4 1/16 10K	Swage
<u>Die Size</u>	<u>Final O.D.</u>
6.62"	6.68"
<u>Hose Serial #</u>	<u>Hose Assembly Serial #</u>
	90067



Test Pressure
15000 PSI

Time Held at Test Pressure
11 1/4 Minutes

Actual Burst Pressure

Peak Pressure
15439 PSI



Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Bobby Fink

Bobby Fink

Approved By: Mendi Jackson

Mendi Jackson



Legend

- Jeffersonian Sections
- Artesia SHL Directional
- Artesia Well Path
- Well Plans
- Well Pad Areas

Land Calendar Legend

EXPIRATION

OBLIGATION

PAYMENT



ARTESIA DIVISION

Water Source
Kirk Federal Com #1H, #2H,
#3H

Author: Trixy Duke

35,352.5 0 17,676.27 35,352.5 Feet

1: 212,115


Projection: WGS_1984_Web_Mercator_Auxiliary_Sphere

This map is a user generated static output from an Internet mapping site and is for reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.

THIS MAP IS NOT TO BE USED FOR NAVIGATION

Date: 7/19/2018





District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources
Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

FORM C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office
☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number		² Pool Code 96718	³ Pool Name Loco Hills; Glorieta-Yeso
⁴ Property Code	⁵ Property Name KIRK FEDERAL COM		⁶ Well Number 3H
⁷ OGRID No. 7377	⁸ Operator Name EOG RESOURCES, INC.		⁹ Elevation 3745'

¹⁰Surface Location


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
D	12	17-S	30-E	-	1296	NORTH	628	WEST	EDDY

¹¹Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
A	12	17-S	30-E	-	502	NORTH	100	EAST	EDDY

¹² Dedicated Acres 240	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
--------------------------------------	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



17 OPERATOR CERTIFICATION
I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or undivided mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Tina Huerta 7/19/2018
Signature Date

Tina Huerta
Printed Name

tina.huerta@eogresources.com
E-mail Address

18 SURVEYOR CERTIFICATION
I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true to the best of my belief.

06/27/2018
Date of Survey

MICHAEL B. BROWN
NEW MEXICO
18329
PROFESSIONAL SURVEYOR

[Signature]
Signature

669263.14
670207.66
Certificate Number



EOG Resources - Artesia

Eddy County (NAD83)

Kirk

Kirk Federal Com #3H

Lateral

Plan #1

Anticollision Report

02 August, 2018

Company: EOG Resources - Artesia
Project: Eddy County (NAD83)
Reference Site: Kirk
Site Error: 0.000 usft
Reference Well: Kirk Federal Com #3H
Well Error: 0.000 usft
Reference Wellbore: Lateral
Reference Design: Plan #1

Local Co-ordinate Reference: Well Kirk Federal Com #3H
TVD Reference: KB @ 3763.000usft (Planning Rig)
MD Reference: KB @ 3763.000usft (Planning Rig)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.14
Offset TVD Reference: Offset Datum

Reference	Plan #1
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria
Interpolation Method:	Stations
Depth Range:	Unlimited
Results Limited by:	Maximum center-center distance of 9,999.980 usft
Warning Levels Evaluated at:	2.00 Sigma
Error Model:	ISCWSA
Scan Method:	Closest Approach 3D
Error Surface:	Combined Pedal Curve
Casing Method:	Not applied

Survey Tool Program		Date	8/2/2018		
From (usft)	To (usft)	Survey (Wellbore)		Tool Name	Description
0.000	9,558.751	Plan #1 (Lateral)		MWD	OWSG MWD - Standard

Summary						
Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Harvard						
Harvard Federal #18 - Directional - Directional	4,950.746	4,751.781	319.025	295.122	13.347	CC, ES
Harvard Federal #18 - Directional - Directional	4,975.000	4,761.363	319.206	295.271	13.336	SF

Offset Design	Harvard - Harvard Federal #18 - Directional - Directional										Offset Site Error:	0.000 usft
Survey Program:	100-GYRO-NS, 1398-MWD										Offset Well Error:	0.000 usft
Reference	Offset	Semi Major Axis		Distance		Minimum Separation		Separation Factor	Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	
0.000	0.000	14.367	14.367	0.000	0.022	28.01	890.093	473.450	1,008.177			
100.000	100.000	117.188	117.187	0.147	0.215	27.99	890.060	473.144	1,008.009	1,007.749	0.26	3,876.534
200.000	200.000	220.616	220.614	0.505	0.577	27.99	889.631	472.844	1,007.506	1,006.740	0.77	1,314.113
300.000	300.000	322.403	322.398	0.864	0.933	28.00	888.880	472.638	1,006.760	1,005.488	1.27	791.651
400.000	400.000	424.095	424.085	1.222	1.290	28.02	887.928	472.441	1,005.842	1,004.065	1.78	566.042
500.000	500.000	524.515	524.499	1.581	1.642	28.02	886.960	471.967	1,004.789	1,002.490	2.28	440.859
600.000	600.000	621.759	621.739	1.939	1.983	28.01	886.300	471.387	1,003.889	1,001.115	2.77	361.973
700.000	700.000	721.137	721.114	2.298	2.331	27.99	885.747	470.827	1,003.134	999.860	3.27	306.481
800.000	800.000	819.082	819.037	2.656	2.674	27.98	885.309	470.384	1,002.526	998.757	3.77	265.980
900.000	900.000	916.457	916.432	3.015	3.015	27.98	884.970	470.220	1,002.140	997.876	4.26	235.035
958.052	958.052	972.076	972.051	3.223	3.209	27.99	884.838	470.324	1,002.069	997.521	4.55	220.326
1,000.000	1,000.000	1,012.580	1,012.554	3.373	3.350	28.00	884.781	470.503	1,002.104	997.350	4.75	210.782
1,100.000	1,100.000	1,111.267	1,111.238	3.732	3.693	28.04	884.683	471.169	1,002.333	997.083	5.25	190.912
1,200.000	1,200.000	1,212.749	1,212.711	4.090	4.048	28.12	884.207	472.435	1,002.506	996.752	5.75	174.231
1,300.000	1,300.000	1,310.703	1,310.656	4.449	4.372	28.19	883.820	473.717	1,002.775	996.539	6.24	160.799
1,400.000	1,400.000	1,432.262	1,432.203	4.807	4.532	28.28	882.876	474.952	1,002.687	996.082	6.60	151.814
1,500.000	1,500.000	1,586.409	1,586.169	5.166	4.601	28.33	876.254	472.476	998.129	991.227	6.90	144.594
1,600.000	1,600.000	1,730.928	1,730.032	5.524	4.731	28.43	863.568	467.555	998.848	981.616	7.23	136.724
1,700.000	1,700.000	1,867.655	1,865.394	5.883	4.925	28.63	845.377	461.420	974.931	967.346	7.59	128.524
1,800.000	1,800.000	1,971.219	1,967.520	6.241	5.121	28.89	828.679	457.318	958.862	950.904	7.96	120.482
1,900.000	1,900.000	2,063.373	2,058.442	6.599	5.321	29.14	814.072	453.825	943.151	934.806	8.35	113.018
2,000.000	2,000.000	2,155.397	2,149.350	6.958	5.541	29.39	800.151	450.594	928.222	919.478	8.74	106.153
2,100.000	2,100.000	2,265.009	2,257.644	7.316	5.828	29.69	783.642	446.834	913.449	904.291	9.16	99.743
2,200.000	2,200.000	2,376.476	2,367.422	7.675	6.157	30.01	764.974	441.807	896.614	887.028	9.59	93.534
2,300.000	2,300.000	2,469.210	2,458.731	8.033	6.448	30.28	749.370	437.481	879.712	869.694	10.02	87.816

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company: EOG Resources - Artesia
Project: Eddy County (NAD83)
Reference Site: Kirk
Site Error: 0.000 usft
Reference Well: Kirk Federal Com #3H
Well Error: 0.000 usft
Reference Wellbore: Lateral
Reference Design: Plan #1

Local Co-ordinate Reference: Well Kirk Federal Com #3H
TVD Reference: KB @ 3763.000usft (Planning Rig)
MD Reference: KB @ 3763.000usft (Planning Rig)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.14
Offset TVD Reference: Offset Datum

Offset Design Harvard - Harvard Federal #18 - Directional - Directional													Offset Site Error:	0.000 usft
Survey Program: 100-GYRO-NS, 1396-MWD													Offset Well Error:	0.000 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (usft)	Separation Factor	Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference	Offset		Between Centres (usft)	Between Ellipses (usft)				Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	
2,400.000	2,400.000	2,572.419	2,560.451	8.392	6.785	30.58	732.528	432.878	863.382	852.923	10.46	732.528	432.878	82.548
2,500.000	2,500.000	2,670.143	2,656.672	8.750	7.121	30.87	716.140	428.087	846.451	835.544	10.91	716.140	428.087	77.605
2,600.000	2,600.000	2,759.581	2,744.837	9.109	7.435	31.13	701.743	423.754	830.137	818.779	11.38	701.743	423.754	73.085
2,700.000	2,700.000	2,871.337	2,854.911	9.467	7.843	31.47	683.275	418.147	813.368	801.545	11.82	683.275	418.147	68.800
2,800.000	2,800.000	2,968.796	2,950.813	9.826	8.211	31.76	666.754	412.839	796.062	783.775	12.29	666.754	412.839	64.789
2,900.000	2,900.000	3,064.023	3,044.572	10.184	8.578	32.06	650.907	407.704	779.071	766.316	12.76	650.907	407.704	61.076
3,000.000	3,000.000	3,159.142	3,138.302	10.543	8.943	32.36	635.503	402.707	762.554	749.326	13.23	635.503	402.707	57.646
3,100.000	3,100.000	3,265.236	3,242.858	10.901	9.360	32.71	618.387	397.163	746.154	732.448	13.71	618.387	397.163	54.442
3,200.000	3,200.000	3,385.477	3,360.695	11.260	9.865	33.21	595.622	389.920	726.858	712.873	14.18	595.622	389.920	51.242
3,300.000	3,300.000	3,480.576	3,453.690	11.618	10.277	33.67	576.614	384.045	706.744	692.070	14.67	576.614	384.045	48.162
3,400.000	3,400.000	3,572.203	3,543.456	11.977	10.673	34.09	559.114	378.463	687.460	672.292	15.17	559.114	378.463	45.323
3,500.000	3,500.000	3,668.806	3,638.273	12.335	11.081	34.57	541.574	373.243	669.002	653.338	15.66	541.574	373.243	42.710
3,600.000	3,600.000	3,762.234	3,729.926	12.693	11.493	35.11	523.935	368.321	650.852	634.689	16.16	523.935	368.321	40.268
3,700.000	3,700.000	3,856.029	3,822.105	13.052	11.896	35.65	507.200	363.801	633.475	616.809	16.67	507.200	363.801	38.011
3,800.000	3,800.000	3,951.496	3,915.983	13.410	12.306	36.27	490.323	359.774	616.648	599.477	17.17	490.323	359.774	35.911
3,900.000	3,900.000	4,047.451	4,010.430	13.769	12.716	36.91	473.831	355.902	600.400	582.720	17.68	473.831	355.902	33.959
4,000.000	4,000.000	4,141.192	4,102.751	14.127	13.114	37.57	457.978	352.305	584.585	566.393	18.19	457.978	352.305	32.135
4,010.388	4,010.388	4,150.367	4,111.800	14.165	13.153	37.63	456.502	351.959	583.018	564.773	18.25	456.502	351.959	31.955
4,050.000	4,049.974	4,185.444	4,146.423	14.307	13.299	37.30	451.038	350.644	576.246	557.797	18.45	451.038	350.644	31.235
4,100.000	4,099.704	4,229.490	4,189.951	14.488	13.481	38.49	444.487	349.088	565.342	546.635	18.71	444.487	349.088	30.221
4,150.000	4,148.683	4,271.960	4,231.983	14.665	13.651	40.07	438.585	347.619	551.947	532.984	18.96	438.585	347.619	29.106
4,200.000	4,197.209	4,312.745	4,272.416	14.840	13.811	42.05	433.441	346.145	536.270	517.053	19.22	433.441	346.145	27.906
4,250.000	4,244.382	4,351.522	4,310.920	15.011	13.960	44.45	429.041	344.841	518.622	499.153	19.47	429.041	344.841	26.638
4,300.000	4,290.113	4,392.980	4,352.132	15.182	14.116	47.53	424.725	343.543	499.143	479.419	19.72	424.725	343.543	25.307
4,350.000	4,334.120	4,432.788	4,391.714	15.363	14.263	51.23	420.679	342.297	477.906	457.823	19.98	420.679	342.297	23.916
4,400.000	4,376.130	4,468.192	4,426.949	15.550	14.392	55.35	417.399	341.198	455.550	435.301	20.25	417.399	341.198	22.498
4,450.000	4,415.885	4,502.257	4,460.885	15.748	14.514	60.02	414.633	340.149	432.659	412.132	20.53	414.633	340.149	21.077
4,500.000	4,453.141	4,534.907	4,493.438	15.959	14.627	65.18	412.350	339.091	409.812	388.985	20.83	412.350	339.091	19.677
4,550.000	4,487.687	4,566.084	4,524.539	16.186	14.734	70.70	410.472	338.030	387.758	368.602	21.16	410.472	338.030	18.329
4,600.000	4,519.250	4,595.033	4,553.423	16.431	14.832	76.31	408.789	337.049	367.409	345.888	21.52	408.789	337.049	17.072
4,650.000	4,547.696	4,620.806	4,579.139	16.697	14.919	81.61	407.310	336.187	349.962	328.037	21.92	407.310	336.187	15.962
4,677.054	4,561.717	4,633.368	4,591.674	16.850	14.961	84.23	406.595	335.771	342.198	320.043	22.16	406.595	335.771	15.445
4,700.000	4,573.189	4,643.606	4,601.890	16.985	14.996	85.80	406.016	335.433	336.772	314.417	22.36	406.016	335.433	15.065
4,752.054	4,599.217	4,666.880	4,625.114	17.312	15.075	89.42	404.703	334.672	328.903	306.097	22.81	404.703	334.672	14.422
4,775.000	4,610.681	4,677.114	4,635.327	17.464	15.109	89.44	404.126	334.341	326.929	303.935	22.99	404.126	334.341	14.218
4,800.000	4,623.131	4,688.198	4,646.377	17.633	15.147	89.48	403.500	333.984	324.985	301.799	23.19	403.500	333.984	14.017
4,825.000	4,635.507	4,699.152	4,657.318	17.807	15.184	89.53	402.881	333.632	323.275	299.914	23.36	402.881	333.632	13.838
4,850.000	4,647.773	4,709.978	4,668.122	17.983	15.220	89.60	402.268	333.287	321.819	298.304	23.52	402.268	333.287	13.685
4,875.000	4,659.897	4,720.637	4,678.758	18.162	15.257	89.69	401.665	332.949	320.642	296.993	23.65	401.665	332.949	13.559
4,900.000	4,671.844	4,731.099	4,689.198	18.344	15.292	89.80	401.073	332.620	319.768	296.009	23.76	401.073	332.620	13.460
4,925.000	4,683.583	4,741.338	4,699.415	18.528	15.327	89.92	400.493	332.299	319.220	295.378	23.84	400.493	332.299	13.389
4,950.000	4,695.081	4,751.481	4,709.537	18.714	15.361	90.08	399.918	331.981	319.025	295.124	23.90	399.918	331.981	13.348
4,950.748	4,695.420	4,751.781	4,709.836	18.719	15.362	90.08	399.901	331.971	319.025	295.122	23.90	399.901	331.971	13.347 CC, ES
4,975.000	4,706.307	4,761.363	4,719.398	18.902	15.395	90.25	399.359	331.666	319.206	295.271	23.94	399.359	331.666	13.336 SF
5,000.000	4,717.230	4,770.921	4,728.936	19.093	15.427	90.41	398.818	331.358	319.789	295.845	23.94	398.818	331.358	13.356
5,025.000	4,727.819	4,780.130	4,738.126	19.287	15.459	90.57	398.298	331.057	320.800	296.870	23.93	398.298	331.057	13.406
5,050.000	4,738.046	4,788.964	4,746.940	19.485	15.489	90.71	397.799	330.765	322.261	298.367	23.89	397.799	330.765	13.487
5,075.000	4,747.884	4,797.396	4,755.354	19.686	15.517	90.83	397.323	330.483	324.195	300.356	23.84	397.323	330.483	13.600
5,100.000	4,757.304	4,805.404	4,763.345	19.891	15.544	90.93	396.872	330.212	326.618	302.851	23.77	396.872	330.212	13.742
5,125.000	4,766.281	4,812.965	4,770.889	20.101	15.570	90.99	396.446	329.953	329.544	305.861	23.68	396.446	329.953	13.915
5,150.000	4,774.791	4,820.059	4,777.968	20.316	15.594	91.01	396.046	329.709	332.983	309.393	23.59	396.046	329.709	14.116
5,175.000	4,782.809	4,826.666	4,784.561	20.536	15.617	90.98	395.674	329.479	336.938	313.447	23.49	395.674	329.479	14.343

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company: EOG Resources - Artesia
Project: Eddy County (NAD83)
Reference Site: Kirk
Site Error: 0.000 usft
Reference Well: Kirk Federal Com #3H
Well Error: 0.000 usft
Reference Wellbore: Lateral
Reference Design: Plan #1

Local Co-ordinate Reference: Well Kirk Federal Com #3H
TVD Reference: KB @ 3763.000usft (Planning Rig)
MD Reference: KB @ 3763.000usft (Planning Rig)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.14
Offset TVD Reference: Offset Datum

Harvard - Harvard Federal #18 - Directional - Directional														Offset Site Error:	0.000 usft
Survey Program: 100-GYRO-NS, 1396-MWD														Offset Well Error:	0.000 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance				Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N-S (usft)	+E-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor			
5,200.000	4,790.315	4,832.769	4,790.650	20.762	15.638	90.90	395.331	329.265	341.410	318.019	23.39	14.596			
5,225.000	4,797.288	4,838.351	4,796.220	20.994	15.657	90.77	395.017	329.067	346.393	323.100	23.29	14.871			
5,250.000	4,803.708	4,843.398	4,801.256	21.232	15.674	90.58	394.734	328.888	351.877	328.676	23.20	15.167			
5,275.000	4,809.558	4,847.768	4,805.616	21.478	15.689	90.31	394.488	328.737	357.848	334.733	23.12	15.481			
5,300.000	4,814.822	4,851.694	4,809.534	21.731	15.702	90.00	394.266	328.602	364.285	341.243	23.04	15.810			
5,325.000	4,819.485	4,855.080	4,812.912	21.980	15.714	89.64	394.076	328.487	371.163	348.183	22.98	16.152			
5,350.000	4,823.535	4,857.913	4,815.739	22.258	15.723	89.22	393.916	328.391	378.455	355.524	22.93	16.504			
5,375.000	4,826.960	4,860.182	4,818.003	22.532	15.731	88.76	393.788	328.314	386.132	363.234	22.90	16.864			
5,400.000	4,829.752	4,861.879	4,819.696	22.813	15.737	88.25	393.692	328.257	394.159	371.282	22.88	17.229			
5,425.000	4,831.802	4,862.995	4,820.810	23.101	15.741	87.71	393.629	328.220	402.502	379.632	22.87	17.599			
5,450.000	4,833.405	4,863.524	4,821.337	23.395	15.742	87.13	393.599	328.203	411.125	388.248	22.88	17.971			
5,475.000	4,834.256	4,863.460	4,821.274	23.695	15.742	86.52	393.603	328.205	419.989	397.095	22.89	18.345			
5,493.737	4,834.465	4,863.022	4,820.836	23.924	15.741	86.04	393.627	328.219	428.767	403.854	22.91	18.625			
5,500.000	4,834.474	4,862.819	4,820.634	24.002	15.740	86.01	393.639	328.226	429.090	406.169	22.92	18.720			
5,600.000	4,834.610	4,859.552	4,817.375	25.385	15.729	85.54	393.823	328.335	475.889	452.758	23.13	20.574			
5,700.000	4,834.746	4,856.228	4,814.058	27.066	15.718	85.07	394.011	328.448	537.403	514.012	23.39	22.975			
5,800.000	4,834.882	4,852.846	4,810.683	28.992	15.706	84.58	394.202	328.563	609.189	585.557	23.63	25.778			
5,900.000	4,835.018	4,849.403	4,807.247	31.112	15.694	84.08	394.396	328.681	688.040	664.208	23.83	28.868			
6,000.000	4,835.154	4,845.898	4,803.750	33.385	15.682	83.58	394.593	328.802	771.792	747.796	24.00	32.164			
6,100.000	4,835.290	4,842.329	4,800.189	35.776	15.670	83.07	394.794	328.927	859.013	834.888	24.12	35.607			
6,200.000	4,835.426	4,838.695	4,796.563	38.260	15.658	82.55	394.998	329.055	948.746	924.518	24.23	39.158			
6,300.000	4,835.563	4,835.336	4,793.211	40.818	15.646	82.06	395.187	329.174	1,040.342	1,016.028	24.31	42.789			
6,400.000	4,835.699	4,832.075	4,789.957	43.436	15.635	81.60	395.370	329.289	1,133.349	1,108.965	24.38	46.478			
6,500.000	4,835.835	4,828.842	4,786.731	46.103	15.624	81.14	395.552	329.403	1,227.448	1,203.003	24.44	50.214			
6,600.000	4,835.971	4,825.636	4,783.533	48.809	15.613	80.68	395.732	329.515	1,322.404	1,297.908	24.50	53.985			
6,700.000	4,836.107	4,822.457	4,780.361	51.549	15.602	80.23	395.911	329.625	1,418.047	1,393.506	24.54	57.783			
6,800.000	4,836.243	4,819.305	4,777.216	54.317	15.592	79.78	396.089	329.735	1,514.248	1,489.665	24.58	61.602			
6,900.000	4,836.379	4,816.179	4,774.097	57.108	15.581	79.34	396.265	329.843	1,610.901	1,586.284	24.62	65.437			
7,000.000	4,836.515	4,813.079	4,771.004	59.920	15.571	78.90	396.439	329.950	1,707.936	1,683.285	24.65	69.286			
7,100.000	4,836.652	4,810.005	4,767.936	62.748	15.560	78.46	396.612	330.055	1,805.288	1,780.606	24.68	73.143			
7,200.000	4,836.788	4,806.956	4,764.894	65.582	15.550	78.03	396.784	330.159	1,902.910	1,878.199	24.71	77.008			
7,300.000	4,836.924	4,803.933	4,761.877	68.449	15.539	77.61	396.955	330.262	2,000.761	1,976.023	24.74	80.877			
7,400.000	4,837.060	4,800.934	4,758.884	71.317	15.529	77.19	397.124	330.363	2,098.811	2,074.046	24.76	84.750			
7,500.000	4,837.196	4,797.959	4,755.916	74.195	15.519	76.77	397.291	330.464	2,197.032	2,172.241	24.79	88.623			
7,600.000	4,837.332	4,795.009	4,752.972	77.082	15.509	76.36	397.458	330.563	2,295.402	2,270.586	24.82	92.497			
7,700.000	4,837.468	4,792.082	4,750.052	79.977	15.499	75.95	397.623	330.661	2,393.904	2,369.063	24.84	96.370			
7,800.000	4,837.604	4,789.179	4,747.155	82.879	15.489	75.55	397.787	330.758	2,492.521	2,467.655	24.87	100.240			
7,900.000	4,837.741	4,786.299	4,744.281	85.788	15.479	75.15	397.949	330.853	2,591.240	2,566.350	24.89	104.108			
8,000.000	4,837.877	4,783.443	4,741.431	88.702	15.470	74.76	398.111	330.948	2,690.051	2,665.136	24.91	107.971			
8,100.000	4,838.013	4,780.608	4,738.603	91.621	15.460	74.37	398.271	331.041	2,788.943	2,764.004	24.94	111.830			
8,200.000	4,838.149	4,777.797	4,735.797	94.545	15.451	73.98	398.429	331.134	2,887.908	2,862.944	24.96	115.683			
8,300.000	4,838.285	4,775.007	4,733.014	97.472	15.441	73.60	398.587	331.225	2,986.940	2,961.951	24.99	119.530			
8,400.000	4,838.421	4,772.240	4,730.252	100.404	15.432	73.22	398.744	331.315	3,086.031	3,061.016	25.01	123.371			
8,500.000	4,838.557	4,769.494	4,727.512	103.339	15.422	72.85	398.899	331.404	3,185.176	3,160.136	25.04	127.204			
8,600.000	4,838.693	4,766.770	4,724.793	106.278	15.413	72.48	399.053	331.492	3,284.370	3,259.304	25.07	131.029			
8,700.000	4,838.829	4,764.066	4,722.096	109.219	15.404	72.11	399.206	331.579	3,383.609	3,358.517	25.09	134.848			
8,800.000	4,838.966	4,761.384	4,719.419	112.163	15.395	71.75	399.357	331.666	3,482.890	3,457.771	25.12	138.655			
8,900.000	4,839.102	4,758.722	4,716.763	115.110	15.386	71.39	399.508	331.751	3,582.208	3,557.062	25.15	142.454			
9,000.000	4,839.238	4,756.081	4,714.127	118.059	15.377	71.04	399.658	331.835	3,681.561	3,656.387	25.17	146.243			
9,100.000	4,839.374	4,753.396	4,711.442	121.010	15.376	71.03	399.662	331.843	3,780.942	3,755.734	25.21	149.991			
9,200.000	4,839.510	4,752.819	4,710.872	123.963	15.365	70.61	399.842	331.941	3,880.358	3,855.123	25.24	153.767			
9,300.000	4,839.646	4,749.631	4,707.691	126.918	15.355	70.18	400.023	332.040	3,979.801	3,954.537	25.26	157.532			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Company:	EOG Resources - Artesia	Local Co-ordinate Reference:	Well Kirk Federal Com #3H
Project:	Eddy County (NAD83)	TVD Reference:	KB @ 3763.000usft (Planning Rig)
Reference Site:	Kirk	MD Reference:	KB @ 3763.000usft (Planning Rig)
Site Error:	0.000 usft	North Reference:	Grid
Reference Well:	Kirk Federal Com #3H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.000 usft	Output errors are at	2.00 sigma
Reference Wellbore	Lateral	Database:	EDM 5000.14
Reference Design:	Plan #1	Offset TVD Reference:	Offset Datum

Offset Design Harvard - Harvard Federal #18 - Directional - Directional													Offset Site Error: 0.000 usft
Survey Program: 100-GYRO-NS, 1396-MWD													Offset Well Error: 0.000 usft
Reference		Offset		Semi Major Axis		Highside Tooface (")	Distance		Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)					
9,400.000	4,839.782	4,746.431	4,704.498	129.874	15.344	69.76	400.204	332.140	4,079.269	4,053.977	25.29	161.286	
9,500.000	4,839.918	4,743.220	4,701.294	132.833	15.333	69.34	400.386	332.240	4,178.760	4,153.439	25.32	165.030	
9,559.749	4,840.000	4,741.296	4,699.374	133.943	15.326	69.09	400.495	332.300	4,238.216	4,210.753	27.46	154.327	


Company: EOG Resources - Artesia
Project: Eddy County (NAD83)
Reference Site: Kirk
Site Error: 0.000 usft
Reference Well: Kirk Federal Com #3H
Well Error: 0.000 usft
Reference Wellbore: Lateral
Reference Design: Plan #1

Local Co-ordinate Reference: Well Kirk Federal Com #3H
TVD Reference: KB @ 3763.000usft (Planning Rig)
MD Reference: KB @ 3763.000usft (Planning Rig)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.14
Offset TVD Reference: Offset Datum

Reference Depths are relative to KB @ 3763.000usft (Planning Rig)
 Offset Depths are relative to Offset Datum
 Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: Kirk Federal Com #3H
 Coordinate System is US State Plane 1983, New Mexico Eastern Zone
 Grid Convergence at Surface is: 0.22°

Ladder Plot



LEGEND

 Harvard Federal #18, Directional Directional V0


Company: EOG Resources - Artesia
Project: Eddy County (NAD83)
Reference Site: Kirk
Site Error: 0.000 usft
Reference Well: Kirk Federal Com #3H
Well Error: 0.000 usft
Reference Wellbore: Lateral
Reference Design: Plan #1

Local Co-ordinate Reference: Well Kirk Federal Com #3H
TVD Reference: KB @ 3763.000usft (Planning Rig)
MD Reference: KB @ 3763.000usft (Planning Rig)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.14
Offset TVD Reference: Offset Datum

Reference Depths are relative to KB @ 3763.000usft (Planning Rig)
 Offset Depths are relative to Offset Datum
 Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: Kirk Federal Com #3H
 Coordinate System is US State Plane 1983, New Mexico Eastern Zone
 Grid Convergence at Surface is: 0.22°


Separation Factor Plot



LEGEND

 Harvard Federal #18, Directional, Directional V0

LOCATION & ELEVATION VERIFICATION MAP



LEASE NAME & WELL NO.: KIRK FEDERAL COM 3H

SECTION 12 TWP 17-S RGE 30-E SURVEY N.M.P.M.
 COUNTY EDDY STATE NM ELEVATION 3745'
 DESCRIPTION 1296 FN/SL & 628 FWEL

LATITUDE N 32.8527220 LONGITUDE W 103.9319416



SCALE: 1" = 2000'
 0' 1000' 2000'

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.


ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.



TOPOGRAPHIC
 LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
 2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
 TELEPHONE: (432) 882-1853 OR (800) 767-1853 • FAX (432) 882-1743
 WWW.TOPOGRAPHIC.COM

EXHIBIT 2 VICINITY MAP




LEASE NAME & WELL NO.: KIRK FEDERAL COM 3H

SECTION 12 TWP 17-S RGE 30-E SURVEY N.M.P.M.
COUNTY EDDY STATE NM
DESCRIPTION 1296 FN/SL & 628 FW/EL

DISTANCE & DIRECTION
FROM INT. OF NM-18 N. & HWY. 82. GO WEST ON HWY. 82 ±36.8 MILES.
THENCE RIGHT (NORTH) ON SQUARE LAKE ROAD ±2.5. THENCE LEFT
(WEST) ON LEASE ROAD ±0.3 MILES TO A POINT ±166 FEET SOUTH OF
THE LOCATION.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY


1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 787-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM



EXHIBIT 2B

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DETAIL VIEW
SCALE: 1" = 100'



ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 140 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1853 OR (800) 787-1853 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

ORIGINAL DOCUMENT SIZE: 8.5" X 11"


S:\SURVEY\EOG_ARTESIA\KIRK_FEDERAL_COM\FINAL_PRODUCTS\SLO_KIRK_FED_COM_3H.DWG 7/18/2018 5:38:31 PM camih5

EXHIBIT 2C


RECLAMATION AND FACILITY DIAGRAM - PRODUCTION FACILITIES DIAGRAM

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DETAIL VIEW
SCALE: 1" = 100'



LEASE NAME & WELL NO.: KIRK FEDERAL COM 3H
3H LATITUDE N 32.8527220 3H LONGITUDE W 103.9319416



LEASE NAME & WELL NO.: KIRK FEDERAL COM 3H

#3H LONGITUDE W 103.9319416

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1853 OR (800) 787-1853 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM


Kirk Federal Com #3H
Eddy County, New Mexico

1296' FNL
628' FWL
Section 12
T-17-S, R-30-E

Proposed Wellbore

API: 30-015-*****

KB: 3,745'
GL: 3,763'



Lateral: 9,560' MD, 4,840' TVD


BH Location: 502' FNL & 100' FEL
Section 12
T-17-S, R-30-E

EXHIBIT 5

SECTIONS 3, 10, 11, & 12, TOWNSHIP 17 SOUTH, RANGE 30 EAST, N.M.P.M.

EDDY COUNTY, NEW MEXICO

KIRK FEDERAL COM 1H-3H SPOCK FEDERAL COM 1H-4H INFRASTRUCTURE



Geog resources, Inc.

KIRK FEDERAL COM 1H-3H SPOCK FEDERAL COM 1H-4H INFRASTRUCTURE	REVISION:	
	INT	DATE
DATE: 10/9/2018		
FILE: SK KIRK SPOCK FEDERAL COM INFRASTRUCTURE		
DRAWN BY: C.E.S.		
SHEET: 1 OF 1		


--- PROPOSED ROAD
- TOTAL FOOTAGE 2,328 FT
FROM LEASE RD.
TO: KIRK FEDERAL COM 1H & 2H
SPOCK FEDERAL COM 4H & 5H
2,184 FT
FROM: KIRK FEDERAL COM 1H & 2H
SPOCK FEDERAL COM 4H & 5H
TO: KIRK FEDERAL COM 3H
SPOCK FEDERAL COM 6H
62 FT

--- PROPOSED GAS LINE
- TOTAL FOOTAGE 3,447 FT
--- PROPOSED WATER LINE
- TOTAL FOOTAGE 9,716 FT

EXHIBIT 2C
RECLAMATION AND FACILITY DIAGRAM - PRODUCTION FACILITIES DIAGRAM

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DETAIL VIEW
SCALE: 1" = 100'



LEASE NAME & WELL NO.: KIRK FEDERAL COM 3H
3H LATITUDE N 32.8527220 3H LONGITUDE W 103.9318416



United States Department of the Interior



BUREAU OF LAND MANAGEMENT
CARLSBAD FIELD OFFICE
620 E. GREENE ST.
CARLSBAD, NM 88220
BLM_NM_CFO_APD@BLM.GOV

In Reply To:
3160 (Office Code)
[NMLC0029338B]

10/05/2018

Attn: TINA HUERTA
EOG RESOURCES INCORPORATED
1111 BAGBY SKY LOBBY2
HOUSTON, TX 77002

Re: Receipt and Acceptability of Application for Permit to Drill (APD)

FEDERAL - NMLC0029338B

Well Name / Number: **KIRK FEDERAL COM / 3H**
Legal Description: **T17S, R30E, SEC 12, NWNW**
County, State: **EDDY, NM**
Date APD Received: **08/07/2018**

Dear Operator:

The BLM received your Application for Permit to Drill (APD), for the referenced well, on 08/07/2018. The BLM reviewed the APD package pursuant to part III.D of Onshore Oil and Gas Order No.1 and it is:

1. ☒ Incomplete/Deficient (*The BLM cannot process the APD until you submit the identified items within 45 calendar days of the date of this notice or the BLM will return your APD.*)

- ☐ Well Plat
- ☒ Drilling Plan
- ☒ Surface Use Plan of Operations (SUPO)
- ☒ Certification of Private Surface Owner Access Agreement
- ☐ Bonding
- ☐ Onsite (The BLM has scheduled the onsite to be on _____)
This requirement is exempt of the 45-day timeframe to submit deficiencies. This requirement will be satisfied on the date of the onsite.
- ☒ Other

[Please See Addendum for further clarification of deficiencies]

2. ☐ Missing Necessary Information (*The BLM can start, but cannot complete the analysis until you submit the identified items. This is an early notice and the BLM will restate this in a 30-day deferral letter, if you have not submitted the information at that time. You will have two (2) years from the date of the deferral to submit this information or the BLM will deny your APD.*)

[Please See Addendum for further clarification of deficiencies]

NOTE: The BLM will return your APD package to you, unless you correct all deficiencies identified above (item 1) within 45 calendar days.

- The BLM will not refund an APD processing fee or apply it to another APD for any returned APD.

Extension Requests:

- If you know you will not be able to meet the 45-day timeframe for reasons beyond your control, you must submit a written request through email/standard mail for extension prior to the 45th calendar day from this notice, 11/19/2018.
- The BLM will consider the extension request if you can demonstrate your diligence (providing reasons and examples of why the delay is occurring beyond your control) in attempting to correct the deficiencies and can provide a date by which you will correct the deficiencies. If the BLM determines that the request does not warrant an extension, the BLM will return the APD as incomplete after the 45 calendar days have elapsed.
 - The BLM will determine whether to grant an extension beyond the required 45 calendar days and will document this request in the well file. If you fail to submit deficiencies by the date defined in the extension request, the BLM will return the APD.

APDs remaining Incomplete:

- If the APD is still not complete, the BLM will notify you and allow 10 additional business days to submit a written request to the BLM for an extension. The request must describe how you will address all outstanding deficiencies and the timeframe you request to complete the deficiencies.
 - The BLM will consider the extension request if you can prove your diligence (providing reasons and examples of why the delay is occurring) in attempting to correct the deficiencies and you can provide a date by which you will correct the deficiencies. If the BLM determines that the request does not warrant an additional extension, the BLM will return the APD as incomplete.

If you have any questions, please contact Katrina Ponder at (575) 234-5969.

Sincerely,

Cody Layton
Assistant Field Manager

cc: Official File

ADDENDUM - Deficient

Surface Comments

- Well Site Layout Deficiency:
Well site and production facilities layout needs to be a professional plat.
- Plans for Surface Reclamation Deficiency:
Reclamation plan needs to be a professional plat.

Engineering Comments

- BOP requirements are not met
Submit a variance to use a flex choke hose line.
- * - Engineering Review: Other submitted information are inadequate and/or incomplete
Submit a contingency casing plan if there was a total loss of fluid.

ADDENDUM - Incomplete or Necessary Information

Adjudication Comments


- Adjudicator additional information:
In well location table of AFMSS 2, MD/TVD for SHL should be 0'.

* Gota Stovens resubmitted contingency request
10/11/18, 1:15 pm phone conversation.

EXHIBIT 5

SECTIONS 3, 10, 11, & 12, TOWNSHIP 17 SOUTH, RANGE 30 EAST, N.M.P.M.
EDDY COUNTY, NEW MEXICO

KIRK FEDERAL COM 1H-3H SPOCK FEDERAL COM 1H-4H INFRASTRUCTURE



Geog resources, Inc.

KIRK FEDERAL COM 1H-3H SPOCK FEDERAL COM 1H-4H INFRASTRUCTURE	REVISION:	
	INT	DATE
DATE: 10/9/2018		
FILE: KIRK SPOCK FEDERAL COM INFRASTRUCTURE		
DRAWN BY: C.E.S.		
SHEET: 1 OF 1		


--- PROPOSED ROAD
-TOTAL FOOTAGE- 2,238 FT
FROM LEASE RD.
TO: KIRK FEDERAL COM 1H & 2H
SPOCK FEDERAL COM 4H & 5H
-TOTAL FOOTAGE- 2,184 FT
FROM KIRK FEDERAL COM 1H & 2H
SPOCK FEDERAL COM 4H & 5H
TO: KIRK FEDERAL COM 3H
SPOCK FEDERAL COM 4H
-TOTAL FOOTAGE- 52 FT

--- PROPOSED GAS LINE
-TOTAL FOOTAGE- 2,447 FT
--- PROPOSED WATER LINE
-TOTAL FOOTAGE- 9,718 FT

EXHIBIT 2C
RECLAMATION AND FACILITY DIAGRAM - PRODUCTION FACILITIES DIAGRAM

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DETAIL VIEW
SCALE: 1" = 100'



LEASE NAME & WELL NO.: KIRK FEDERAL COM 3H
3H LATITUDE N 32.8527220 3H LONGITUDE W 103.9318416

APD ID: 10400032289

Submission Date: 08/07/2018

Highlighted data
reflects the most
recent changes

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

KirkFederalCom3HExistingRoadMap_20180719165005.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? NO

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

KirkFederalCom3HExistingWellsMap_20180719165148.pdf

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

Existing Wells description:

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description:

Production Facilities map:

KirkWellsproductionfacilitymap_20180802101204.pdf

EP_ENTERPRISE_CTB_GL_SEC12_20181101145027.pdf

BO_ENTERPRISE_CTB_T17S_R30E_SEC12_20181101145027.pdf

EP_ENTERPRISE_CTB_WL_SEC3_20181101145028.pdf

EP_ENTERPRISE_CTB_WL_SEC10_20181101145028.pdf

EP_ENTERPRISE_CTB_WL_SEC11_20181101145029.pdf

EP_ENTERPRISE_CTB_WL_SEC12_20181101145029.pdf

Section 5 - Location and Types of Water Supply

Water Source Table

Water source use type: DUST CONTROL,
INTERMEDIATE/PRODUCTION CASING, STIMULATION, SURFACE
CASING

Water source type: GW WELL

Describe type:

Source longitude:

Source latitude:

Source datum: NAD83

Water source permit type: WATER WELL

Source land ownership: PRIVATE

Water source transport method: PIPELINE

Source transportation land ownership: PRIVATE

Water source volume (barrels): 120000

Source volume (acre-feet): 15.467172

Source volume (gal): 5040000

Water source and transportation map:

KirkWaterMap_20180719165313.pdf

Water source comments:

New water well? NO

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Construction Materials description:

Construction Materials source location attachment:

Section 7 - Methods for Handling Waste

Waste type: DRILLING

Waste content description: Drill fluids and produced oil and water from the well during drilling and completing operations will be stored safely and disposed of properly in an NMOCD approved disposal facility. Garbage and trash produced during drilling and completion operations will be collected in a trash container and disposed of properly. Human waste and grey water will be properly contained of and disposed of properly. After drilling and completion operations; trash, chemicals, salts, frac sand, and other waste material will be removed and disposed of properly at a state approved disposal facility.

Amount of waste: 0 barrels

Waste disposal frequency : Daily

Safe containment description: Steel Tanks

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Trucked to NMOCD approved disposal facility

Reserve Pit

Reserve Pit being used? NO

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.)

Reserve pit width (ft.)

Reserve pit depth (ft.)

Reserve pit volume (cu. yd.)

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? NO

Description of cuttings location

Cuttings area length (ft.)

Cuttings area width (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

WellSiteDiagram_20180719165433.pdf

KirkWellsInfrastructure_20181010075905.pdf

KirkFederalCom3HOtherAtt_20181106084336.pdf

Comments:

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

Section 10 - Plans for Surface Reclamation

Type of disturbance: No New Surface Disturbance **Multiple Well Pad Name:** KIRK FEDERAL COM

Multiple Well Pad Number: 1H

Recontouring attachment:

KirkFederalCom3HReclamationPlat10dayletterResponse_20181010080441.pdf

Drainage/Erosion control construction: Proper erosion control methods will be used on the area to control erosion, runoff, and siltation of the surrounding area.

Drainage/Erosion control reclamation: The interim reclamation will be monitored periodically to ensure that vegetation has reestablished and that erosion is controlled.

Well pad proposed disturbance (acres): 0	Well pad interim reclamation (acres):	Well pad long term disturbance (acres):
Road proposed disturbance (acres): 0	Road interim reclamation (acres):	Road long term disturbance (acres):
Powerline proposed disturbance (acres): 0	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0
Pipeline proposed disturbance (acres): 0	Pipeline interim reclamation (acres):	Pipeline long term disturbance (acres):
Other proposed disturbance (acres): 0	Other interim reclamation (acres):	Other long term disturbance (acres):
Total proposed disturbance: 0	Total interim reclamation:	Total long term disturbance:

Disturbance Comments:

Reconstruction method: In areas planned for interim reclamation, all the surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads. Areas planned for interim reclamation will be recontoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Where applicable, the fill material of the well pad will be backfilled into the cut to bring the area back to the original contour. The interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be recontoured to the above ratios during interim reclamation.

Topsoil redistribution: Topsoil will be evenly respreads and aggressively revegetated over the entire disturbed area not needed for all-weather operations including cuts and fills. To see the area, the proper BLM seed mixture, free of noxious weeds, will be used. Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.

Soil treatment: Re-seed according to BLM standards. All reclaimed areas will be monitored periodically to ensure that revegetation occurs, that the area is not redisturbed, and that erosion is controlled.

Existing Vegetation at the well pad: Grass, forbs, and small wood vegetation, such as mesquite will be excavated as the topsoil is removed. Large wood vegetation will be stripped and stored separately and respreads evenly on the site following topsoil resspreading. Topsoil depth is defined as the top layer of soil that contains 80% of the roots. In areas to be heavily disturbed, the top 6 inches of soil material, will be stripped and stockpiled on the perimeter of the well location and along the perimeter of the access road to control run-on and run-off, to keep topsoil viable, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil should include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils.

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road: All disturbed areas, including roads, pipelines, pads, will be recontoured to the contour existing prior to the initial construction or a contour that blends indistinguishably with the surrounding landscape. Topsoil that was spread over the interim reclamation areas will be stockpiled prior to recontouring. The topsoil will be redistributed evenly over the entire disturbed site to ensure successful revegetation.

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline: All disturbed areas, including roads, pipelines, pads, will be recontoured to the contour existing prior to the initial construction or a contour that blends indistinguishably with the surrounding landscape. Topsoil that was spread over the interim reclamation areas will be stockpiled prior to recontouring. The topsoil will be redistributed evenly over the entire disturbed site to ensure successful revegetation.

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances: All disturbed areas, including roads, pipelines, pads, will be recontoured to the contour existing prior to the initial construction or a contour that blends indistinguishably with the surrounding landscape. Topsoil that was spread over the interim reclamation areas will be stockpiled prior to recontouring. The topsoil will be redistributed evenly over the entire disturbed site to ensure successful revegetation.

Existing Vegetation Community at other disturbances attachment:

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Seed Management

Seed Table

Seed type:

Seed source:

Seed name:

Source name:

Source address:

Source phone:

Seed cultivar:

Seed use location:

PLS pounds per acre:

Proposed seeding season:

Seed Summary

Total pounds/Acre:

Seed Type

Pounds/Acre

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

First Name:

Last Name:

Phone:

Email:

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: All reclaimed areas will be monitored periodically to ensure that revegetation occurs, that the area is not redisturbed, erosion is controlled, and free of noxious weeds. Weeds will be treated if found.

Weed treatment plan attachment:

Monitoring plan description: Reclamation will be completed within 6 months of well plugging. All reclaimed areas will be monitored periodically to ensure that revegetation occurs, that the area is not redisturbed, erosion is controlled, and free of noxious weeds.

Monitoring plan attachment:

Success standards: N/A

Pit closure description: N/A

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

Operator Name: EOG RESOURCES INCORPORATED

Well Name: KIRK FEDERAL COM

Well Number: 3H

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Section 12 - Other Information

Right of Way needed? NO

Use APD as ROW?

ROW Type(s):

ROW Applications

SUPO Additional Information:


Use a previously conducted onsite? NO

Previous Onsite information:

Other SUPO Attachment

KirkFederalCom3HSUPO_20180719165510.pdf

EXHIBIT 2 VICINITY MAP



LEASE NAME & WELL NO.: KIRK FEDERAL COM 3H

SECTION 12 TWP 17-S RGE 30-E SURVEY N.M.P.M.

COUNTY EDDY STATE NM


DESCRIPTION 1296 FN/SL & 628 FWEL

DISTANCE & DIRECTION

FROM INT. OF NM-18 N. & HWY. 82 GO WEST ON HWY. 82 ±36.8 MILES.
THENCE RIGHT (NORTH) ON SQUARE LAKE ROAD ±2.5. THENCE LEFT
(WEST) ON LEASE ROAD ±0.3 MILES TO A POINT ±166 FEET SOUTH OF
THE LOCATION.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.


ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
 2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
 TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
 WWW.TOPOGRAPHIC.COM

EXHIBIT 3

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO **Eog resources, Inc.**


ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID
BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY
FEET.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND
UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF
SURVEY, AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED
TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE.
THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1853 OR (800) 787-1853 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM



Legend/Key	
Color	Description
	Kirk/Spock Drilling Pads
	Proposed Electrical Hookup
	Current CVE Electric Grid
	Projected Wellbore Paths
	Kirk #3H Flowline Path
	Kirk #2H Flowline Path
	Kirk #1H Flowline Path
	Proposed location for Enterprise CTB
	Water Transfer Line
	EOG Acreage Outline
	Surface gas gathering lines to Gissler batteries


Proposed Flowlines for Wells, water takeaway, and gas takeaway		
	Proposed Electrical Hookup	Total Footage - 675 ft
	Kirk #3H Flowline Path	2- 4" Poly SDR-7 Flowlines, 2- 4" Flexsteel Lines (working pressures 75-125 psi) total footage per line 1,500 ft
	Kirk #2H Flowline Path	2- 4" Poly SDR-7 Flowlines, 2- 4" Flexsteel Lines (working pressures 75-125 psi) total footage per line 500 ft
	Kirk #1H Flowline Path	2- 4" Poly SDR-7 Flowlines, 2- 4" Flexsteel Lines (working pressures 75-125 psi) total footage per line 500 ft
	Water Transfer Line	4- 4" Poly SDR-7 Flowlines, total footage per line = 6,500'




Legend/Key	
Color	Description
	Kirk/Spock Drilling Pads
	Proposed Electrical Hookup
	Current CVE Electric Grid
	Projected Wellbore Paths
	Kirk #3H Flowline Path
	Kirk #2H Flowline Path
	Kirk #1H Flowline Path
	Proposed location for Enterprise CTB
	Water Transfer Line
	EOG Acreage Outline
	Surface gas gathering lines to Gissler batteries

Proposed Flowlines for Wells, water takeaway, and gas takeaway		
	Proposed Electrical Hookup	Total Footage - 675 ft
	Kirk #3H Flowline Path	2- 4" Poly SDR-7 Flowlines, 2- 4" Flexsteel Lines (working pressures 75-125 psi) total footage per line 1,500 ft
	Kirk #2H Flowline Path	2- 4" Poly SDR-7 Flowlines, 2- 4" Flexsteel Lines (working pressures 75-125 psi) total footage per line 500 ft
	Kirk #1H Flowline Path	2- 4" Poly SDR-7 Flowlines, 2- 4" Flexsteel Lines (working pressures 75-125 psi) total footage per line 500 ft
	Water Transfer Line	4- 4" Poly SDR-7 Flowlines, total footage per line = 6,500'

Legend/Key	
Color	Description
	Kirk/Spock Drilling Pads
	Proposed Electrical Hookup
	Current CVE Electric Grid
	Projected Wellbore Paths
	Kirk #3H Flowline Path
	Kirk #2H Flowline Path
	Kirk #1H Flowline Path
	Proposed location for Enterprise CTB
	Water Transfer Line
	EOG Acreage Outline
	Surface gas gathering lines to Gissler batteries






SCALE: 1" = 1000'


0' 500' 1000'

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



LEGEND

- SURVEY/SECTION LINE
- RANGE LINE
- TRACT BORDER
- SURVEYED BASELINE
- EDGE OF EASEMENT
- ROAD WAY
- FENCE LINE
- EXISTING PIPELINE
- OVERHEAD ELECTRIC
- WATER LINE
- IRON ROD FOUND
- IRON PIPE FOUND
- POINT OF INTERSECTION



Being a proposed gasline easement being 30 feet in width, 15 feet left, and 15 feet right of the above platted centerline total line footage containing 3446.98 feet or 208.91 rods, containing 2.37 acres more or less.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX: (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 787-1653 • FAX: (432) 682-1743
WWW.TOPOGRAPHIC.COM

"PRELIMINARY, THIS DOCUMENT SHALL NOT
BE RECORDED FOR ANY PURPOSE."

Michael Blake Brown, P.S. No. 18329
OCTOBER 1, 2018

eo resources, inc.


ENTERPRISE CTB GASLINE	REVISION:	
	INT	DATE
DATE: 10/01/2018		
FILE: EP_ENTERPRISE_CTG_GL_SEC12		
DRAWN BY: IMU		
SHEET: 1 OF 1		

NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY EOG RESOURCES, INC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
4. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
5. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT
6. ADJOINER INFORMATION SHOWN FOR INFORMATIONAL PURPOSES ONLY.

SCALE: 1" = 1000'

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



Metes and Bounds Description of a proposed 2.73 acre CTB located within Section 12, Township 17 South, Range 30 East, N.M.P.M., in Eddy County, New Mexico.

BEGINNING at a 1/2" iron rod with cap stamped "Topographic" set for the Southwest corner of this site, from whence a brass cap found for the West Quarter corner of said Section 12, bears:

S 21°05'18" W, a distance of 306.76 feet;


Thence N 00°00'00" W, a distance of 200.00 feet, to a 1/2" iron rod with cap stamped "Topographic" set for the Northeast corner of this site;

Thence N 90°00'00" E, a distance of 600.00 feet to a 1/2" iron rod with cap stamped "Topographic" set for the Northeast corner of this site;

Thence S 00°00'00" E, a distance of 80.00 feet to a 1/2" iron rod with cap stamped "Topographic" set for an angle point of this site;

Thence S 07°35'41" W, a distance of 121.06 feet to a 1/2" iron rod with cap stamped "Topographic" set for the Southeast corner of this site;

Thence N 90°00'00" W, a distance of 584.00 feet to the Point of Beginning.



LEGEND

- SURVEY/SECTION LINE
- TRACT BORDER
- PROPOSED SITE
- ROAD WAY
- X FENCE LINE
- EXISTING PIPELINE
- OHE OVERHEAD ELECTRIC
- W WATER LINE
- IRON ROD FOUND
- ⊙ IRON PIPE FOUND
- ⊙ IRON ROD SET

ENTERPRISE CTB
BOUNDARY

ENTERPRISE CTB BOUNDARY - 119,040 SQ. FT.
2.73 ACRES

LINE TABLE

LINE	BEARING	DISTANCE
1	N 00°00'00" W	200.00'
2	N 90°00'00" E	600.00'
3	S 00°00'00" E	80.00'
4	S 07°35'41" W	121.06'
5	N 90°00'00" W	584.00'



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX: (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 787-1653 • FAX: (432) 682-1743
WWW.TOPOGRAPHIC.COM

"PRELIMINARY, THIS DOCUMENT SHALL NOT
BE RECORDED FOR ANY PURPOSE."

Michael Blake Brown, P.S. No. 18329
AUGUST 12, 2018

eg resources, Inc.

ENTERPRISE CTB	REVISION:	
	INT	DATE
DATE: 08/14/2018		
FILE: BO_ENTERPRISE_CTB_T17S_R30E_SEC12		
DRAWN BY: SME		
SHEET: 1 OF 1		

NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY EGO RESOURCES, INC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
4. B.O.L.P. O.B. = BEGINNING OF LINE/POINT OF BEGINNING
5. E.O.L.P. O.E. = END OF LINE/POINT OF EXIT
6. ADJOINER INFORMATION SHOWN FOR INFORMATIONAL PURPOSES ONLY.

SCALE: 1" = 1000'

0' 500' 1000'

SECTION 3, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



33 34

4 3

2" IRON PIPE
FOUND

34 35


3 2

LEGEND

	SURVEY/SECTION LINE
	BLOCK/TOWNSHIP LINE
	TRACT BORDER
	SURVEYED BASELINE
	CONTINUED BASELINE
	EDGE OF EASEMENT
	ROAD WAY
	FENCE LINE
	EXISTING PIPELINE
	OVERHEAD ELECTRIC
	IRON ROD FOUND
	IRON PIPE FOUND

LINE TABLE

LINE	BEARING	DISTANCE
1	N 09°01'23" E	251.50'



P.O.B.
X=656630.28
Y=675450.08

DETAIL VIEW
SCALE: 1" = 30'

U.S.A.

1" IRON PIPE
FOUND

S 00°10'35" E, 2638.67'

4 3

9 10

S 89°52'28" W
3219.31'

S 89°52'28" W, 5278.45'

S 83°06'54" E
2034.36'

2" IRON PIPE
FOUND

SEE
DETAIL

ENTERPRISE CTB
WATERLINE

OHE

OHE

OHE

Being a proposed waterline easement being 30 feet in width, 15 feet left, and 15 feet right of the above platted centerline
total line footage containing 251.50 feet or 15.24 rods, containing 0.17 acres more or less.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140

TELEPHONE: (817) 744-7512 • FAX: (817) 744-7554

2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705

TELEPHONE: (432) 682-1853 OR (800) 767-1853 • FAX: (432) 682-1743

WWW.TOPOGRAPHIC.COM


"PRELIMINARY, THIS DOCUMENT SHALL NOT
BE RECORDED FOR ANY PURPOSE."

Michael Blake Brown, P.S. No. 18329

OCTOBER 1, 2018



ENTERPRISE CTB WATERLINE	REVISION:		NOTES:
	INT	DATE	
DATE: 10/01/2018			<p>1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"</p> <p>2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.</p> <p>3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY EOG RESOURCES, INC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.</p> <p>4. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING</p> <p>5. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT</p> <p>6. ADJOINER INFORMATION SHOWN FOR INFORMATIONAL PURPOSES ONLY.</p>
FILE:EP_ENTERPRISE_CTB_WL_SEC3			
DRAWN BY: IMU			
SHEET: 1 OF 1			



Being a proposed waterline easement being 30 feet in width, 15 feet left, and 15 feet right of the above platted centerline total line footage containing 2487.14 feet or 150.74 rods, containing 1.71 acres more or less.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY


1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 787-1853 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM



"PRELIMINARY, THIS DOCUMENT SHALL NOT
BE RECORDED FOR ANY PURPOSE."

Michael Blake Brown, P.S. No. 18329
OCTOBER 1, 2018

ENTERPRISE CTB WATERLINE	REVISION:		NOTES:
	INT	DATE	
DATE: 10/01/2018			<p>1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"</p> <p>2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.</p> <p>3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY EOG RESOURCES, INC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.</p> <p>4. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING</p> <p>5. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT</p> <p>6. ADJOINER INFORMATION SHOWN FOR INFORMATIONAL PURPOSES ONLY.</p>
FILE: EP_ENTERPRISE_CTB_WL_SEC10			
DRAWN BY: IMU			
SHEET: 1 OF 1			



eoog resources, inc.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1853 OR (800) 787-1853 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM


"PRELIMINARY, THIS DOCUMENT SHALL NOT
BE RECORDED FOR ANY PURPOSE."

Michael Blake Brown, P.S. No. 18329
OCTOBER 1, 2018

ENTERPRISE CTB WATERLINE	REVISION:		NOTES:
	INT	DATE	
DATE: 10/01/2018			1. ORIGINAL DOCUMENT SIZE: 8.5" X 11" 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET. 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY EOG RESOURCES, INC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY. 4. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING 5. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT 6. ADJOINER INFORMATION SHOWN FOR INFORMATIONAL PURPOSES ONLY.
FILE:EP_ENTERPRISE_CTB_WL_SEC11			
DRAWN BY: IMU			
SHEET: 1 OF 1			


SCALE: 1" = 1000'

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



LEGEND

- SURVEY/SECTION LINE
- BLOCK/TOWNSHIP LINE
- TRACT BORDER
- SURVEYED BASELINE
- CONTINUED BASELINE
- EDGE OF EASEMENT
- ROAD WAY
- FENCE LINE
- EXISTING PIPELINE
- OVERHEAD ELECTRIC
- WATER LINE
- IRON ROD FOUND
- IRON PIPE FOUND
- POINT OF INTERSECTION



DETAIL VIEW
SCALE: 1" = 30'

Being a proposed waterline easement being 30 feet in width, 15 feet left, and 15 feet right of the above platted centerline total line footage containing 463.17 feet or 28.07 rods, containing 0.32 acres more or less.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY



1400 EVERMAN PARKWAY, Ste. 148 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX: (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1853 OR (800) 787-1653 • FAX: (432) 682-1743
WWW.TOPOGRAPHIC.COM

geog resources, Inc.

"PRELIMINARY, THIS DOCUMENT SHALL NOT
BE RECORDED FOR ANY PURPOSE."

Michael Blake Brown, P.S. No. 18329
OCTOBER 1, 2018

ENTERPRISE CTB WATERLINE	REVISION:		NOTES:
	INT	DATE	
DATE: 10/01/2018			<p>1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"</p> <p>2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.</p> <p>3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY EOG RESOURCES, INC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.</p> <p>4. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING</p> <p>5. E.O.L./P.O.E. = END OF LINE/POINT OF EXIT</p> <p>6. ADJOINER INFORMATION SHOWN FOR INFORMATIONAL PURPOSES ONLY.</p>
FILE: EP_ENTERPRISE_CTB_WL_SEC12			
DRAWN BY: IMU			
SHEET: 1 OF 1			



Legend

- Jeffersonian Sections
- Artesia SHL Directional
- Artesia Well Path
- Well Plans
- Well Pad Areas
- Land Calendar Legend**
 - EXPIRATION
 - OBLIGATION
 - PAYMENT



ARTESIA DIVISION

Water Source
Kirk Federal Com #1H, #2H,
#3H

Author: Trixy Duke

35,352.5 0 17,676.27 35,352.5 Feet

1: 212,115

Projection: WGS_1984_Web_Mercator_Auxiliary_Sphere

This map is a user generated static output from an Internet mapping site and is for reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.

THIS MAP IS NOT TO BE USED FOR NAVIGATION

Date: 7/19/2018

EOG Resources

Well Site Diagram





EXHIBIT 5

SECTIONS 3, 10, 11, & 12, TOWNSHIP 17 SOUTH, RANGE 30 EAST, N.M.P.M.

EDDY COUNTY, NEW MEXICO

KIRK FEDERAL COM 1H-3H SPOCK FEDERAL COM 1H-4H INFRASTRUCTURE



oog resources, Inc.


KIRK FEDERAL COM 1H-3H SPOCK FEDERAL COM 1H-4H INFRASTRUCTURE	REVISION:	
	INT	DATE
DATE: 10/9/2018		
FILE: SI KIRK SPOCK FEDERAL COM INFRASTRUCTURE		
DRAWN BY: C.E.S.		
SHEET: 1 OF 1		

--- PROPOSED ROAD
-TOTAL FOOTAGE- 2,238 FT
FROM LEABE RD.
TO: KIRK FEDERAL COM 1H & 2H
SPOCK FEDERAL COM 4H & 5H 2,184 FT
FROM: KIRK FEDERAL COM 1H & 2H
SPOCK FEDERAL COM 4H & 5H
TO: KIRK FEDERAL COM 3H
SPOCK FEDERAL COM 6H 52 FT

— PROPOSED GAS LINE
-TOTAL FOOTAGE- 3,447 FT
— PROPOSED WATER LINE
-TOTAL FOOTAGE- 8,718 FT

[illegible]

EXHIBIT 2 VICINITY MAP



LEASE NAME & WELL NO.: KIRK FEDERAL COM 3H

SECTION 12 TWP 17-S RGE 30-E SURVEY N.M.P.M.
COUNTY EDDY STATE NM
DESCRIPTION 1296 FN/SL & 628 FW/EL

DISTANCE & DIRECTION

FROM INT. OF NM-18 N. & HWY. 82. GO WEST ON HWY. 82 ±36.8 MILES.
THENCE RIGHT (NORTH) ON SQUARE LAKE ROAD ±2.5. THENCE LEFT
(WEST) ON LEASE ROAD ±0.3 MILES TO A POINT ±166 FEET SOUTH OF
THE LOCATION.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.



SCALE: 1" = 1000'
0' 500' 1000'



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY


1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1853 OR (800) 787-1853 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM



EXHIBIT 2B

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DETAIL VIEW
SCALE: 1" = 100'



ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID
BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY
FEET.

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER
MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY,
AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE
PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS
SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 140 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1853 OR (800) 787-1853 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM


ORIGINAL DOCUMENT SIZE: 8.5" X 11"

S:\SURVEY\EOG_ARTESIA\KIRK_FEDERAL_COM\FINAL_PRODUCTS\SILO_KIRK_FED_COM_3H.DWG 7/16/2018 5:38:51 PM csmth5

EXHIBIT 2C
RECLAMATION AND FACILITY DIAGRAM - PRODUCTION FACILITIES DIAGRAM

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DETAIL VIEW
SCALE: 1" = 100'



LEASE NAME & WELL NO.: KIRK FEDERAL COM 3H
3H LATITUDE N 32.8527220 3H LONGITUDE W 103.9319416



Geog resources, inc.



Geog resources, inc.


Geog resources, inc.

Geog resources, inc.



Geog resources, inc.



Geog resources, inc.
Geog resources, inc.
Geog resources, inc.
Geog resources, inc.
Geog resources, inc.

EXHIBIT 2C

RECLAMATION AND FACILITY DIAGRAM - PRODUCTION FACILITIES DIAGRAM

SECTION 12, TOWNSHIP 17-S, RANGE 30-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DETAIL VIEW
SCALE: 1" = 100'



LEASE NAME & WELL NO.: KIRK FEDERAL COM 3H
3H LATITUDE N 32.8527220 3H LONGITUDE W 103.9319416

MULTI-POINT SURFACE USE AND OPERATIONS PLAN

EOG Resources, Inc.

Kirk Federal Com 3H

1296' FNL and 628' FWL Section 12, T17S-R30E - Surface Hole Location

502' FNL and 100' FEL Section 12, T17S-R30E -Bottom Hole Location

Eddy County, New Mexico

This plan is submitted with Form 3160-3, Application for Permit to Drill, covering the above described well. The purpose of this plan is to describe the location of the proposed well, the proposed construction activities and operations plan, the magnitude of the surface disturbance involved and the procedures to be followed in rehabilitating the surface after completion of the operations, so that a complete appraisal can be made of the environmental effect associated with the operations.

1. EXISTING ROADS:

The County map showing the well and roads in the vicinity of the proposed location. The proposed well site is located approximately 27 miles northeast of Artesia, New Mexico and the access route to the location is indicated on Exhibit. Operator will maintain existing roads in condition the same or better than before operations begin. Operator will repair pot holes, clear ditches, repair the crown, etc. All existing structures along the entire access route such as cattle guards, other range improvement projects, culverts, etc. will be properly repaired or replaced if they are damaged or have deteriorated beyond practical use. Operator will reasonably prevent and abate fugitive dust as needed when created by vehicular traffic and equipment caused by the operator. The BLM's written approval will be acquired before application of surfactants, binding agents, or other dust suppression chemicals on roadways.

DIRECTIONS:

(See Exhibit A) From Artesia, go West on US-82 for approximately 27.5 miles. Turn left (North) onto CR220 (Square Lake Rd). Travel North on CR220 for 2.5 miles. Turn left (West) to lease road. Continue down lease road for 0.3 miles. Location will be located south of roadway approximately 10 yards.

2. PLANNED ACCESS ROAD.

- A. (See Exhibit) Existing access road runs along Southeast edge of well location. The road will be crowned and ditched to a 2% slope from the tip of the crown to the edge of the driving surface.
- B. The road will be 14 feet in width (driving surface) and will be adequately drained to control to control runoff and soil erosion. Ditches will be 3' wide with a 3:1 slopes.
- C. The road will be bladed with drainage on one side. A traffic turnout may be built.
- D. Existing roads will be maintained in the same or better condition.
- E. The route of road is visible.

3. LOCATION OF EXISTING WELL

- A. There is no drilling activity within a one-mile radius of the well site.
- B. Exhibits shows existing wells within a one-mile radius of the proposed well site.

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

- A. There are no production facilities on this lease at the present time.
- B. Central tank battery will be an on location gathering facility with water and gas take away.

5. LOCATION AND TYPE OF WATER SUPPLY:

- A. It is planned to drill the proposed well with a fresh water system. The water will be obtained from commercial sources and will be hauled to the location by truck over the existing and proposed roads shown in Exhibit.

6. SOURCE OF CONSTRUCTION MATERIALS:

Dirt contractor will locate closest pit and obtain any permits and materials needed for construction of the well location.

7. METHODS OF HANDLING WASTE DISPOSAL:

- A. This well will be drilled with a closed loop system
- B. The closed loop system will be constructed, maintained, and closed in compliance with the State of New Mexico, Energy and Natural Resources Department, Oil Conservation Division – the “Pit Rule” 19.15.17 NMAC.
- C. Drilling fluids will be removed after drilling and completions are completed.
- D. Water produced during operations will be collected in tanks until hauled to an approved disposal system, or separate disposal application will be submitted.
- E. Oil produced during operations will be stored in tanks until sold.
- F. Current laws and regulations pertaining to the disposal of human waste will be complied with.
- G. All trash, junk, and other waste materials will be contained in trash cages or bins to prevent scattering and will be removed and deposited in an approved sanitary landfill. Burial on site is not approved.

8. ANCILLARY FACILITIES: None.

9. WELLSITE LAYOUT:

- A. Exhibit shows the relative location and dimensions of the well pad, the closed loop mud system, location of the drilling equipment. All of the location will be constructed within the 300' x 400' staked area.
- B. A 300' x 400' area has been staked and flagged.

9. PLANS FOR RESTORATION:

- A. After finishing drilling and/or completion operations, all equipment and other material not needed for further operations will be removed. The location will be cleaned of all trash and junk to leave the well site in as aesthetically pleasing a condition as possible. The location will be reduced to a 250' x 250' after completion operations have been conducted. At this point the surfacing material will be removed and topsoil will be redistributed. The area will be contoured as closely as possible to its original state and reseeded. Please note Reclamation Plat.

- B. If the proposed well is plugged and abandoned, all equipment and other material will be removed. The location will be cleaned of all trash and junk to leave the well site in as aesthetically pleasing a condition as possible. At this point the surfacing material will be removed, topsoil will be redistributed. The area will be contoured as closely as possible to its original location and reseeded. These actions will be completed and accomplished as expeditiously as possible.
- C. The reclamation of the pad will be done in sixty days if possible after the well is put in production.

11. SURFACE OWNERSHIP:

Surface Estate: Bureau of Land Management
620 E. Greene Street
Carlsbad, NM 88220-6292

Mineral Estate: BLM – NMLC-029338B leased to
COG Operating LLC
600 W Illinois Ave
Midland, TX 79701/4882

12. OTHER INFORMATION:

- A. Topography: Refer to the existing archaeological report for a description of the topography, flora, fauna, soil characteristics, dwellings, historical and cultural sites.
- B. The primary surface use is for grazing.



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

PWD Data Report

01/24/2019

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data Report

01/24/2019

Bond Information

Federal/Indian APD: FED

BLM Bond number: NM2308

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: