RECEIVED

Form 3160-3
(June 2015)

APR 2 4 2019

DISTRICT II-ARTESIA O.C.D.

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No.
NMNM0544986

6. If Indian, Allotee or Tribe Name

1a. Type of work: ☑ DRILL ☐ REENTER

1b. Type of Well: ☑ Oil Well ☐ Gas Well ☐ Other

1c. Type of Completion: ☐ Hydraulic Fracturing ☑ Single Zone ☐ Multiple Zone

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.
TODD 36-25 STATE FED COM 234H 325417

2. Name of Operator
DEVON ENERGY PRODUCTION COMPANY LP 6137

9. API Well No.
30-015-45907

3a. Address	3b. Phone No. *(include area code)*	10. Field and Pool, or Exploratory
333 West Sheridan Avenue Oklahoma City OK 73102	(800)583-3866	Wildcat

4. Location of Well *(Report location clearly and in accordance with any State requirements.*)*

At surface SWSE / 330 FSL / 1666 FEL / LAT 32.25475 / LONG -103.7283687

At proposed prod. zone NENE / 20 FNL / 1280 FEL / LAT 32.2826307 / LONG -103.7271093

11. Sec., T. R. M. or Blk. and Survey or Area
SEC 36 / T23S / R31E / NMP

14. Distance in miles and direction from nearest town or post office*

12. County or Parish
EDDY

13. State
NM

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)	16. No of acres in lease	17. Spacing Unit dedicated to this well
330 feet	600	320

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.	19. Proposed Depth	20. BLM/BIA Bond No. in file
5950 feet	10560 feet / 20823 feet	FED: CO1104

21. Elevations (Show whether DF, KDB, RT, GL, etc.)	22. Approximate date work will start*	23. Estimated duration
3508 feet	06/24/2019	30 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM.

25. Signature	Name *(Printed/Typed)*	Date
(Electronic Submission)	Jenny Harms / Ph: (405)552-6560	10/10/2018

Title
Regulatory Compliance Professional

Approved by *(Signature)*	Name *(Printed/Typed)*	Date
(Electronic Submission)	Christopher Walls / Ph: (575)234-2234	04/23/2019

Title	Office
Petroleum Engineer	CARLSBAD

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

APPROVED WITH CONDITIONS

Approval Date: 04/23/2019

RWP 4-24-19

(Continued on page 2)

*(Instructions on page 2)

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the wen, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionany drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.
AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160
PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service wen or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.
ROUTINE USE: Information from the record and/or the record win be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.
EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:
The BLM conects this information to anow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Conection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

(Continued on page 3)

Additional Operator Remarks

Location of Well

1. SHL: SWSE / 330 FSL / 1666 FEL / TWSP: 23S / RANGE: 31E / SECTION: 36 / LAT: 32.25475 / LONG: -103.7283687 (TVD: 0 feet, MD: 0 feet)
   PPP: SESE / 100 FSL / 1280 FEL / TWSP: 23S / RANGE: 31E / SECTION: 36 / LAT: 32.2539426 / LONG: -103.7271201 (TVD: 10301 feet, MD: 10340 feet)
   BHL: NENE / 20 FNL / 1280 FEL / TWSP: 23S / RANGE: 31E / SECTION: 25 / LAT: 32.2826307 / LONG: -103.7271093 (TVD: 10560 feet, MD: 20823 feet)

BLM Point of Contact

Name: Candy Vigil
Title: Admin Support Assistant
Phone: 5752345982
Email: cvigil@blm.gov

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

PECOS DISTRICT
DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Devon Energy Production Company LP
LEASE NO.:	NMNM0544986
WELL NAME & NO.:	Todd 36-25 State Fed Com 234H
SURFACE HOLE FOOTAGE:	330'/S & 1666'/E
BOTTOM HOLE FOOTAGE	20'/N & 1280'/E
LOCATION:	Section 36, T.23 S., R.31 E., NMPM
COUNTY:	Eddy County, New Mexico

COA

H2S	○ Yes	◉ No	
Potash	○ None	◉ Secretary	○ R-111-P
Cave/Karst Potential	◉ Low	○ Medium	○ High
Variance	○ None	◉ Flex Hose	○ Other
Wellhead	○ Conventional	○ Multibowl	◉ Both
Other	☐ 4 String Area	☐ Capitan Reef	☐ WIPP
Other	☑ Fluid Filled	☐ Cement Squeeze	☐ Pilot Hole
Special Requirements	☐ Water Disposal	☑ COM	☐ Unit

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **837 feet** (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite and above the salt) and cemented to the surface.

    a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
    b. Wait on cement (WOC) time for a primary cement job will be a minimum of **24 hours in the Potash Area** or 500 pounds compressive strength, whichever

is greater. (This is to include the lead cement)

c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

2. The minimum required fill of cement behind the **9-5/8** inch intermediate casing shall be set at approximately **4490 feet** is:

Option 1 (Single Stage):

- Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**

Option 2:

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.

b. Second stage above DV tool:

- Cement to surface. If cement does not circulate, contact the appropriate BLM office.
  Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.

3. The minimum required fill of cement behind the **5-1/2** inch production casing is:

- Cement should tie-back at least **500 feet** into previous casing string. Operator shall provide method of verification.
  Cement excess is less than 25%, more cement might be required.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'

2.

Option 1:

a. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M)** psi.

b. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the intermediate casing shoe shall be **5000 (5M)** psi.

Option 2:

1. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M)** psi.

    a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
    b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
    c. Manufacturer representative shall install the test plug for the initial BOP test.
    d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
    e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees

of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

a. Spudding well (minimum of 24 hours)
b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties
Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.
During office hours call (575) 627-0272.
After office hours call (575)

☒ Eddy County
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

☒ Lea County
Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.

   a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
   b. When the operator proposes to set surface casing with Spudder Rig
      - Notify the BLM when moving in and removing the Spudder Rig.
      - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
      - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.

2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.

3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.

7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.

2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.

4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:

    a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
    b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
    c. Manufacturer representative shall install the test plug for the initial BOP test.
    d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
    e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.

5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.

    a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the

plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.

c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.

e. The results of the test shall be reported to the appropriate BLM office.

f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.

g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Devon Energy Production Company LP
WELL NAME & NO.:	Todd 36-25 State Fed Com 234H
SURFACE HOLE FOOTAGE:	330'/S & 1666'/E
BOTTOM HOLE FOOTAGE	20'/N & 1280'/E
LOCATION:	Section 36, T.23 S., R.31 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

In May 2008, the Pecos District Special Status Species Resource Management Plan Amendment (RMPA) was approved and is being implemented. In addition to the standard practices that minimize impacts, as listed above, the following COA will apply:

- Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken, to minimize noise associated impacts which could disrupt breeding and nesting activities.
- Upon abandonment, a low profile abandoned well marker will be installed to prevent raptor perching.
- Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006. The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all power line structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. The holder without liability or expense shall make such modifications and/or additions to the United States.

Livestock Watering Requirement
Any damage to structures that provide water to livestock throughout the life of the well, caused by operations from the well site, must be immediately corrected by the operator. The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

Fence Requirement
Where entry is granted across a fence line, the fence must be braced and tied off on both sides of the passageway with H-braces prior to cutting. Once the work is completed, the fence will be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

The operator must contact the allotment holder prior to construction to identify the location of the pipeline. The operator must take measures to protect the pipeline from compression or other damages. If the pipeline is damaged or compromised in any way near the proposed project as a result of oil and gas activity, the operator is responsible for repairing the pipeline immediately. The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

During construction, the proponent shall minimize disturbance to existing fences, water lines, troughs, windmills, and other improvements on public lands. The proponent is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the grazing permittee/allottee prior to disturbing any range improvement projects. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

Lessees must comply with the 2012Secretarial Potash Order. The Order is designed to manage the efficient development of oil, gas, and potash resources. Section 6 of the Order provides

general provisions which must be followed to minimize conflict between the industries and ensure the safety of operations.

To minimize impacts to potash resources, the proposed well is confined within the boundaries of the established Todd 36-25's Drill Island (See Potash Memo and Map in attached file for Drill Island description).

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing
The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width
The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing
Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning
Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching
Ditching shall be required on both sides of the road.

Turnouts
Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: $\frac{400'}{4\%} + 100' = 200'$ lead-off ditch interval

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road
3. Redistribute topsoil
4. Revegetate slopes



Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities
Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)
Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening
The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures
The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures
Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus

freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement
All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

STANDARD STIPULATIONS FOR OIL AND GAS RELATED SITES

A copy of the application (Grant/Sundry Notice) and attachments, including stipulations and map, will be on location during construction. BLM personnel may request to view a copy of your permit during construction to ensure compliance with all stipulations.

The holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer, BLM.

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant and for all response costs, penalties, damages, claims, and other costs arising from the provisions of the Resource Conservation and Recovery Act (RCRA), 42 U.S.C. Chap. 82, Section 6901 et. seq., from the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), 42 U.S.C. Chap. 109, Section 9601 et. seq., and from other applicable environmental statues.

2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976, as amended (15 U.S.C. 2601, et. seq.) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized by this grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation and Liability Act, Section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et. seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et. seq.) on the right-of-way (unless the release or threatened release is wholly unrelated to the right-of-way holder's activity on the right-of-way). This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the site or related pipeline(s), any oil or other pollutant should be discharged from site facilities, the pipeline(s) or from containers or vehicles impacting Federal lands, the control and total removal, disposal, and cleanup of such oil of other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages to Federal lands resulting therefrom, the Authorized Officer may take such measures as deemed necessary to control and cleanup the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any liability or responsibility.

5. Sites shall be maintained in an orderly, sanitary condition at all times. Waste materials, both liquid and solid, shall be disposed of promptly at an appropriate, authorized waste disposal facility in accordance with all applicable State and Federal laws. "Waste" means all discarded matter including, but not limited to, human waste, trash, garbage, refuse, petroleum products, brines, chemicals, oil drums, ashes, and equipment.

6. The operator will notify the Bureau of Land Management (BLM) authorized officer and nearest Fish and Wildlife Service (FWS) Law Enforcement office within 24 hours, if the operator discovers a dead or injured federally protected species (i.e., migratory bird species, bald or golden eagle, or species listed by the FWS as threatened or endangered) in or adjacent to a pit, trench, tank, exhaust stack, or fence. (If the operator is unable to contact the FWS Law Enforcement office, the operator must contact the nearest FWS Ecological Services office.)

7. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" designated by the Rocky Mountain Five-State Interagency Committee. The color selected for this project is **Shale Green**, Munsell Soil Color Chart Number 5Y 4/2.

8. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on the holder's behalf, on public or Federal land shall be immediately reported to the Authorized Officer. The holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to the proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

9. A sales contract for removal of mineral material (caliche, sand, gravel, fill dirt) from an authorized pit, site, or on location must be obtained from the BLM prior to commencing construction. There are several options available for purchasing mineral material: contact the BLM office (575-234-5972).

10. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

11. Once the site is no longer in service or use, the site must undergo final abandonment. At final abandonment, the site and access roads must undergo "final" reclamation so that the character and productivity of the land are restored. Earthwork for final reclamation must be completed within six (6) months of the abandonment of the site. All pads and facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact. After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

12. The holder shall stockpile an adequate amount of topsoil where blading occurs. The topsoil to be stripped is approximately ___6___ inches in depth. The topsoil will be segregated from other spoil piles. The topsoil will be used for final reclamation.

13. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

( ) seed mixture 1	( ) seed mixture 3
( ) seed mixture 2	( ) seed mixture 4
(X) seed mixture 2/LPC	( ) Aplomado Falcon Mixture

14. In those areas where erosion control structures are required to stabilize soil conditions, the holder shall install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound management practices. Any earth work will require prior approval by the Authorized Officer.

15. Open-topped Tanks - The operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps

16. The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an

impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

17. Open-Vent Exhaust Stack Exclosures – The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

18. Containment Structures - Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

19. Special Stipulations:

- The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The berm shall be maintained through the life of the well and after interim reclamation has been completed.
- Any water erosion that may occur due to the construction of the well pad during the life of the well will be corrected within two weeks and proper measures will be taken to prevent future erosion.

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except

between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from permanent engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

B. PIPELINES

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C.6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure

of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.

6. The pipeline will be buried with a minimum cover of **36** inches between the top of the pipe and ground level.

7. The maximum allowable disturbance for construction in this right-of-way will be **30** feet:

- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed **20** feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)

- Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed **30** feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)

- The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)

8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

( ) seed mixture 1	( ) seed mixture 3
( ) seed mixture 2	( ) seed mixture 4
(X) seed mixture 2/LPC	( ) Aplomado Falcon Mixture

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches that are not otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or

other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

19. Special Stipulations:

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b.

A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.

5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply

with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:
- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken: Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce

the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species	lb/acre
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed **x** percent purity **x** percent germination = pounds pure live seed

AFMSS

U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

04/23/2019

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Jenny Harms **Signed on:** 10/10/2018

Title: Regulatory Compliance Professional

Street Address: 333 W Sheridan Ave

City: Oklahoma City **State:** OK **Zip:** 73102

Phone: (405)552-6560

Email address: jenny.harms@dvn.com

Field Representative

Representative Name: RAY VAZ

Street Address: 333 WEST SHERIDAN AVENUE

City: OKLAHOMA CITY **State:** OK **Zip:** 73102-5015

Phone: (575)748-1871

Email address: RAY.VAZ@DVN.COM

AFMSS

U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data Report

04/23/2019

APD ID: 10400035010 **Submission Date:** 10/10/2018

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Well Type: OIL WELL **Well Work Type:** Drill

Highlighted data reflects the most recent changes

Show Final Text

Section 1 - General

APD ID: 10400035010 **Tie to previous NOS?** **Submission Date:** 10/10/2018

BLM Office: CARLSBAD **User:** Jenny Harms **Title:** Regulatory Compliance Professional

Federal/Indian APD: FED **Is the first lease penetrated for production Federal or Indian?** FED

Lease number: NMNM0544986 **Lease Acres:** 600

Surface access agreement in place? **Allotted?** **Reservation:**

Agreement in place? NO **Federal or Indian agreement:**

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO **APD Operator:** DEVON ENERGY PRODUCTION COMPANY LP

Operator letter of designation:

Operator Info

Operator Organization Name: DEVON ENERGY PRODUCTION COMPANY LP

Operator Address: 333 West Sheridan Avenue **Zip:** 73102

Operator PO Box:

Operator City: Oklahoma City **State:** OK

Operator Phone: (800)583-3866

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO **Master Development Plan name:**

Well in Master SUPO? NO **Master SUPO name:**

Well in Master Drilling Plan? NO **Master Drilling Plan name:**

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H **Well API Number:**

Field/Pool or Exploratory? Exploratory **Field Name:** WILDCAT **Pool Name:**

Is the proposed well in an area containing other mineral resources? POTASH

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Describe other minerals:

Is the proposed well in a Helium production area? N **Use Existing Well Pad?** NO **New surface disturbance?**

Type of Well Pad: MULTIPLE WELL **Multiple Well Pad Name:** TODD 36 WELLPAD **Number:** 3

Well Class: HORIZONTAL **Number of Legs:** 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: **Distance to nearest well:** 5950 FT **Distance to lease line:** 330 FT

Reservoir well spacing assigned acres Measurement: 320 Acres

Well plat: TODD_36_25_STATE_FED_COM_234H_C102_9_23_2018_signed_20181010074339.pdf

Well work start Date: 06/24/2019 **Duration:** 30 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83 **Vertical Datum:** NAVD88

Survey number:

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	330	FSL	1666	FEL	23S	31E	36	Aliquot SWSE	32.25475	-103.7283687	EDDY	NEW MEXICO	NEW MEXICO	S	STATE	3508	0	0
KOP Leg #1	50	FSL	1280	FEL	23S	31E	36	Aliquot SESE	32.35382	-103.727125	EDDY	NEW MEXICO	NEW MEXICO	S	STATE	-6480	10010	9988
PPP Leg #1	100	FSL	1280	FEL	23S	31E	36	Aliquot SESE	32.2539426	-103.7271201	EDDY	NEW MEXICO	NEW MEXICO	S	STATE	-6793	10340	10301

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
EXIT Leg #1	100	FNL	1280	FEL	23S	31E	25	Aliquot NENE	32.284108	-103.7271094	EDDY	NEW MEXICO	NEW MEXICO	F	NMNM 0544986	-7052	20743	10560
BHL Leg #1	20	FNL	1280	FEL	23S	31E	25	Aliquot NENE	32.282607	-103.7271093	EDDY	NEW MEXICO	NEW MEXICO	F	NMNM 0544986	-7052	20823	10560

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
SITE MAP



Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

DEVON ENERGY PRODUCTION COMPANY, L.P.
TODD 36-25 STATE FED COM 234H
LOCATED 330 FT. FROM THE SOUTH LINE AND 1666 FT. FROM THE EAST LINE OF SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

0 100 200

DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF NM-128 AND RED ROAD HEAD NORTH ON RED ROAD FOR 0.09 MILES. TURN RIGHT ONTO AN ACCESS ROAD AND HEAD NORTHEAST FOR 0.07 MILES TO THE POINT OF BEGINNING OF THE PROPOSED TODD 36 WELLPAD 1 ACCESS ROAD. LEAVE THE EXISTING ACCESS ROAD AND HEAD NORTH AND EAST ON THE PROPOSED TODD 36 WELLPAD 1 ACCESS ROAD FOR 0.19 MILES TO THE SAME EXISTING ACCESS ROAD AND THEN HEAD EAST FOR 0.50 MILES TO THE POINT OF BEGINNING OF THE PROPOSED TODD 36 WELLPAD 3 ACCESS ROAD. HEAD SOUTH ALONG THE PROPOSED TODD 36 WELLPAD 3 ACCESS ROAD FOR 46 FEET TO THE TO THE NORTHWEST CORNER OF THE TODD 36 WELLPAD 3.

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

Drawn by: CHRIS MAAS | Date: 09/20/2018

Drawn for: devon

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
INTERIM SITE BUILD PLAN



DENOTES INTERIM PAD RECLAMATION AREA

DENOTES GRADING SITE RECLAMATION AREA

1.770± ACRES INTERIM PAD RECLAMATION AREA
3.800± ACRES GRADING SITE RECLAMATION AREA
1.661± ACRES NON-RECLAIMED AREA
7.231± ACRES GRADING SITE RECLAMATION AREA

0 100 200

DEVON ENERGY PRODUCTION COMPANY, L.P.
TODD 36-25 STATE FED COM 234H
LOCATED 330 FT. FROM THE SOUTH LINE
AND 1666 FT. FROM THE EAST LINE OF
SECTION 36, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

Drawn by: CHRIS MAAS

Date: 09/20/2018

Drawn for:

devon

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
VICINITY MAP



DEVON ENERGY PRODUCTION COMPANY, L.P.
TODD 36-25 STATE FED COM 234H
LOCATED 330 FT. FROM THE SOUTH LINE AND 1666 FT. FROM THE EAST LINE OF SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF NM-128 AND RED ROAD HEAD NORTH ON RED ROAD FOR 0.09 MILES. TURN RIGHT ONTO AN ACCESS ROAD AND HEAD NORTHEAST FOR 0.07 MILES TO THE POINT OF BEGINNING OF THE PROPOSED TODD 36 WELLPAD 1 ACCESS ROAD. LEAVE THE EXISTING ACCESS ROAD AND HEAD NORTH AND EAST ON THE PROPOSED TODD 36 WELLPAD 1 ACCESS ROAD FOR 0.19 MILES TO THE SAME EXISTING ACCESS ROAD AND THEN HEAD EAST FOR 0.50 MILES TO THE POINT OF BEGINNING OF THE PROPOSED TODD 36 WELLPAD 3 ACCESS ROAD. HEAD SOUTH ALONG THE PROPOSED TODD 36 WELLPAD 3 ACCESS ROAD FOR 46 FEET TO THE TO THE NORTHWEST CORNER OF THE TODD 36 WELLPAD 3.

0 1000 2000

HORIZON ROW LLC		Drawn for: devon
DEVON ENERGY PRODUCTION CO., L.P.		
Drawn by: CHRIS MAAS	Date: 09/20/2018	

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
LOCATION VERIFICATION MAP



DEVON ENERGY PRODUCTION COMPANY, L.P.
TODD 36-25 STATE FED COM 234H
LOCATED 330 FT. FROM THE SOUTH LINE
AND 1666 FT. FROM THE EAST LINE OF
SECTION 36, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

0 1000 2000

HORIZON ROW LLC	Drawn for: devon
DEVON ENERGY PRODUCTION CO., L.P.	
Drawn by: CHRIS MAAS	Date: 09/20/2018

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL PHOTO



DEVON ENERGY PRODUCTION COMPANY, L.P.
TODD 36-25 STATE FED COM 234H
LOCATED 330 FT. FROM THE SOUTH LINE
AND 1666 FT. FROM THE EAST LINE OF
SECTION 36, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

0 2000 4000

HORIZON ROW LLC		Drawn for: devon
DEVON ENERGY PRODUCTION CO., L.P.		
Drawn by: CHRIS MAAS	Date: 09/20/2018	

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



DEVON ENERGY PRODUCTION COMPANY, L.P.
TODD 36-25 STATE FED COM 234H
LOCATED 330 FT. FROM THE SOUTH LINE
AND 1666 FT. FROM THE EAST LINE OF
SECTION 36, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

0 1000 2000

HORIZON ROW LLC		Drawn for: devon
DEVON ENERGY PRODUCTION CO., L.P.		
Drawn by: CHRIS MAAS	Date: 09/20/2018	

EXHIBIT "A"

ACCESS ROAD PLAT
SECTION 36, T23S–R31E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



30' EASEMENT AREA = 0.032 ACRE(S)
46.36 FEET OR 2.81 RODS

0+00.0 P.O.B./EXISTING ACCESS ROAD
0+03.9 EDGE OF ROAD
0+11.6 EXISTING FLOW LINE
0+16.3 POWER LINE
0+46.3 P.O.E./TODD 36 WELLPAD 3

SEE THE ATTACHED LEGAL DESCRIPTION

Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

NEW MEXICO 22404 PROFESSIONAL SURVEYOR

B.L. Laman PLS #22404
Date Signed: 09-23-2018
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizonrow, LLC

0 1000 2000

HORIZON ROW LLC	DEVON ENERGY PRODUCTION COMPANY, L.P.		LINE NUMBER:
Drawn for: devon	TODD 36 WELLPAD 3 ACCESS ROAD		WBS NUMBER:
			SCALE: 1" = 1000'
	PROPOSED 30' EASEMENT ON THE PROPERTY OF BUREAU OF LAND MANAGEMENT SECTION 36, T23S–R31E, N.M.P.M.		REVISIONS:
Drawn by: CHRIS MAAS	Date: 07/07/2018		SURVEY DATE: 6/30/18

SECTION 36, T23S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

ACCESS ROAD PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southeast quarter (SE ¼) of Section 36, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 1" iron pipe w/BC for the east quarter corner of Section 36, T23S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence S 45°28'13" W a distance of 3031.10' to the **Point of Beginning** of this easement having coordinates of Northing=457067.69, Easting=727843.19 feet and continuing the following course;

Thence S 08°21'32" E a distance of 46.36' to the **Point of Ending** having coordinates of Northing=457021.82, Easting=727849.93 feet from said point a 2" iron pipe w/BC for the southeast corner of Section 36, T23S-R31E bears S 77°49'11" E a distance of 2218.65', covering **46.36' or 2.81 rods** and having an area of **0.032 acres**.

NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

B.L. Laman PLS 22404
Date Signed: 09/23/2018
Horizon Row, LLC
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizon Row, LLC

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
PLAN VIEW



DEVON ENERGY PRODUCTION COMPANY, L.P.
TODD 36-25 STATE FED COM 234H
LOCATED 330 FT. FROM THE SOUTH LINE
AND 1666 FT. FROM THE EAST LINE OF
SECTION 36, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

0 150 300

EARTHWORK QUANTITIES FOR
TODD 36 WELLPAD 3

CUT	FILL	NET
12,929 CY	12,929 CY	0 CY

EARTHWORK QUANTITIES ARE ESTIMATED

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

Drawn by: CHRIS MAAS

Date: 09/20/2018

Drawn for:

devon

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
CROSS SECTIONS



DEVON ENERGY PRODUCTION COMPANY, L.P.
TODD 36–25 STATE FED COM 234H
LOCATED 330 FT. FROM THE SOUTH LINE
AND 1666 FT. FROM THE EAST LINE OF
SECTION 36, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

SCALE 1" = 150' HORIZONTAL
SCALE 1" = 20' VERTICAL

EARTHWORK QUANTITIES FOR
TODD 36 WELLPAD 3

CUT	FILL	NET
12,929 CY	12,929 CY	0 CY

EARTHWORK QUANTITIES ARE ESTIMATED

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

Drawn by: CHRIS MAAS

Date: 09/20/2018

Drawn for: devon

Drilling Plan Data Report

04/23/2019

APD ID: 10400035010 **Submission Date:** 10/10/2018

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Well Type: OIL WELL **Well Work Type:** Drill

Highlighted data reflects the most recent changes

Show Final Text

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	UNKNOWN	3508	0	0	ALLUVIUM	NONE	No
2	RUSTLER	2711	797	797	SALT	NONE	No
3	SALADO	2375	1133	1133	SALT	NONE	No
4	BASE OF SALT	-924	4432	4432	SALT	NONE	No
5	DELAWARE	-998	4506	4506	SANDSTONE	NONE	No
6	BONE SPRING LIME	-4849	8357	8357	LIMESTONE	NONE	No
7	BONE SPRING 1ST	-6141	9649	9649	SANDSTONE	NATURAL GAS,OIL	No
8	2ND BONE SPRING LIME	-6215	9723	9723	LIMESTONE	NONE	No
9	BONE SPRING 2ND	-7047	10555	20555	SANDSTONE	NATURAL GAS,OIL	Yes

Section 2 - Blowout Prevention

Pressure Rating (PSI): 3M **Rating Depth:** 6000

Equipment: BOP/BOPE will be installed per Onshore Oil & Gas Order #2 requirements prior to drilling below intermediate casing, a BOP/BOPE system with the above minimum rating will be installed on the wellhead system. BOP/BOPE will be tested by an independent service company per Onshore Oil & Gas Order #2 requirements and MASP (Maximum Anticipated Surface Pressure) calculations. If the system is upgraded, all the components installed will be functional and tested.
Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.
Testing Procedure: A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Choke Diagram Attachment:

3M_BOPE_CK_20190402060442.pdf

3M_BOPE_CK_20190402060442.pdf

BOP Diagram Attachment:

3M_BOPE_CK_20190402060449.pdf

Pressure Rating (PSI): 5M **Rating Depth:** 10560

Equipment: BOP/BOPE will be installed per Onshore Oil & Gas Order #2 requirements prior to drilling below intermediate casing, a BOP/BOPE system with the above minimum rating will be installed on the wellhead system. BOP/BOPE will be tested by an independent service company per Onshore Oil & Gas Order #2 requirements and MASP (Maximum Anticipated Surface Pressure) calculations. If the system is upgraded, all the components installed will be functional and tested.
Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.
Testing Procedure: A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Choke Diagram Attachment:

5M_BOPE__CK_20190319123811.pdf

BOP Diagram Attachment:

5M_BOPE__CK_20190319123818.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	837	0	837			837	H-40	48	STC	1.125	1	BUOY	1.6	BUOY	1.6
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	6000	0	6000			6000	J-55	40	OTHER - BTC	1.125	1	BUOY	1.6	BUOY	1.6
3	PRODUCTION	8.75	5.5	NEW	API	N	0	20823	0	10560			20823	P-110	17	OTHER - BTC	1.125	1	BUOY	1.6	BUOY	1.6

Casing Attachments

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Surf_Csg_Ass_20181009120933.pdf

Casing ID: 2 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Int_Csg_Ass_20181009121011.pdf

Casing ID: 3 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Prod_Csg_Ass_20181009121046.pdf

Section 4 - Cement

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	837	873	1.33	13.2	1162	100	c	Class C + adds
INTERMEDIATE	Lead		0	5500	757	1.94	9	1469	50	C	Class C + Adds
INTERMEDIATE	Tail		5500	6000	196	1.33	13.2	261	50	C	Class C + Adds
PRODUCTION	Lead		5500	10010	460	1.94	9	1644	10	TUNED	Class C + adds
PRODUCTION	Tail		10010	20823	1882	1.6	13.2	2747	10	H	(50:50) Clas H Cement: Poz (Fly Ash) + 0.5% bwoc HALAD-344 + 0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2% bwoc Bentonite

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Describe the mud monitoring system utilized: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	837	OTHER : FRESH WATER	8.5	9							

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
6000	10560	WATER-BASED MUD	8.5	9							
837	6000	OTHER : BRINE	10	10.5							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Will run GRMWD from TD to from KOP. Cement bond logs will be run in vertical to determine top of cement. Stated logs run will be in the Completion Report and submitted to the BLM.

List of open and cased hole logs run in the well:

CALIPER,CBL,DS,GR,MUDLOG

Coring operation description for the well:

N/A

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 4942 **Anticipated Surface Pressure:** 2618.8

Anticipated Bottom Hole Temperature(F): 169

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

Todd_36_25_State_Fed_Com_234H_H2S_20181010071822.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Devon_Todd_36_25_State_Fed_Com_234H_AC_Report_Permit_Plan_1_20181010071858.pdf

Devon_Todd_36_25_State_Fed_Com_234H_Permit_Plan_1_20181010071859.pdf

Devon_Todd_36_25_State_Fed_Com_234H_Plot_Permit_Plan_1_20181010071859.pdf

Other proposed operations facets description:

Drill plan revision- intermediate casing to 6000' and 5M-corrections made 4/2/2019

Other proposed operations facets attachment:

Clsd_Loop_20181009090953.pdf

MB_Verb_5M_20190319124224.pdf

MB_Wellhd_5M_20190319124225.pdf

Spudder_Rig_Info_20190319124248.pdf

TODD_36_Fed_Com_GasCapturePlan_10_4_2018_20190319124329.pdf

Todd_36_25_Fed_Com_234H_Drilling_Plan_Rev_1_20190402060738.pdf

Other Variance attachment:

Co_flex_20181009090519.pdf

13-5/8" 3M BOPE & Closed Loop Equipment Schematic



13-5/8" 5M BOPE & Closed Loop Equipment Schematic



13-5/8" 3M BOPE & Closed Loop Equipment Schematic



13-5/8" 5M BOPE & Closed Loop Equipment Schematic



Casing Assumptions and Load Cases

Production

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Production Casing Burst Design		
Load Case	**External Pressure**	**Internal Pressure**
Pressure Test	Formation Pore Pressure	Fluid in hole (water or produced water) + test psi
Tubing Leak	Formation Pore Pressure	Packer @ KOP, leak below surface 8.6 ppg packer fluid
Stimulation	Formation Pore Pressure	Max frac pressure with heaviest frac fluid

Production Casing Collapse Design		
Load Case	**External Pressure**	**Internal Pressure**
Full Evacuation	Water gradient in cement, mud above TOC.	None
Cementing	Wet cement weight	Water (8.33ppg)

Production Casing Tension Design	
Load Case	**Assumptions**
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Surface

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Surface Casing Burst Design		
Load Case	**External Pressure**	**Internal Pressure**
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Displace to Gas	Formation Pore Pressure	Dry gas from next casing point

Surface Casing Collapse Design		
Load Case	**External Pressure**	**Internal Pressure**
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Surface Casing Tension Design	
Load Case	**Assumptions**
Overpull	100kips
Runing in hole	3 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Intermediate

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Intermediate Casing Burst Design		
Load Case	**External Pressure**	**Internal Pressure**
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Fracture @ Shoe	Formation Pore Pressure	Dry gas

Intermediate Casing Collapse Design		
Load Case	**External Pressure**	**Internal Pressure**
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Intermediate Casing Tension Design	
Load Case	**Assumptions**
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A

devon

Devon Energy Center
333 West Sheridan Avenue
Oklahoma City, Oklahoma 73102-5015

Hydrogen Sulfide (H_2S) Contingency Plan

For

Todd 36-25 State Fed Com 234H

Sec-36 T-23S R-31E
330' FSL & 1666' FEL
LAT. = 32.2545750' N (NAD83)
LONG = 103.7283687' W

Eddy County NM

Todd 36-25 State Fed Com 234H

This is an open drilling site. H_2S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H_2S, including warning signs, wind indicators and H_2S monitor.





Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crews should then block the entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are no homes or buildings in or near the ROE.

Assumed 100 ppm ROE = 3000'

100 ppm H_2S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H_2S, the first responder(s) must

- **Isolate the area and prevent entry by other persons into the 100 ppm ROE.**
- **Evacuate any public places encompassed by the 100 ppm ROE.**
- **Be equipped with H_2S monitors and air packs in order to control the release.**
- **Use the "buddy system" to ensure no injuries occur during the response**
- **Take precautions to avoid personal injury during this operation.**
- **Contact operator and/or local officials to aid in operation. See list of phone numbers attached.**
- **Have received training in the**
  - **Detection of H_2S, and**
  - **Measures for protection against the gas,**
  - **Equipment used for protection and emergency response.**

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO_2). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

Characteristics of H_2S and SO_2

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H_2S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO_2	2.21 Air = 1	2 ppm	N/A	1000 ppm

Contacting Authorities

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER)

Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE (H_2S) TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H_2S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H_2S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H_2S metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H_2S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H_2S zone (within 3 days or 500 feet) and weekly H_2S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H_2S Drilling Operations Plan and the Public Protection Plan.

II. HYDROGEN SULFIDE TRAINING

Note: All H_2S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H_2S.

1. **Well Control Equipment**

   A. Flare line

   B. Choke manifold – Remotely Operated

   C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit

   D. Auxiliary equipment may include if applicable: annular preventer and rotating head.

   E. Mud/Gas Separator

2. **Protective equipment for essential personnel:**

   30-minute SCBA units located at briefing areas, as indicated on well site diagram, with escape units available in the top doghouse. As it may be difficult to communicate audibly while wearing these units, hand signals shall be utilized.

3. **H_2S detection and monitoring equipment:**

   Portable H_2S monitors positioned on location for best coverage and response. These units have warning lights which activate when H_2S levels reach 10 ppm and audible sirens which activate at 15 ppm. Sensor locations:

   - **Bell nipple**
   - **Rig floor**
   - **Cellar**
   - **Possum Belly/Shale shaker**
   - **Choke manifold**

   Visual warning systems:

   A. Wind direction indicators as shown on well site diagram

   B. Caution/ Danger signs shall be posted on roads providing direct access to locations. Signs will be painted a high visibility yellow with black lettering of sufficient size to be reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

4. **Mud program:**

   The mud program has been designed to minimize the volume of H_2S circulated to surface. Proper mud weight, safe drilling practices and the use of H_2S scavengers will minimize hazards when penetrating H_2S bearing zones.

5. **Metallurgy:**

   A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold lines, and valves shall be H_2S trim.

   B. All elastomers used for packing and seals shall be H_2S trim.

6. **Communication:**

   A. Company personnel have/use cellular telephones in the field.

   B. Land line (telephone) communications at Office

7. **Well testing:**

   A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safety and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H_2S environment will use the closed chamber method of testing.

   B. There will be no drill stem testing.

Devon Energy Corp. Company Call List		
Drilling Supervisor – Basin – Mark Kramer		405-823-4796
EHS Professional – Laura Wright		405-439-8129
Agency Call List		
Lea County (575)	**Hobbs**	
	Lea County Communication Authority	393-3981
	State Police	392-5588
	City Police	397-9265
	Sheriff's Office	393-2515
	Ambulance	**911**
	Fire Department	397-9308
	LEPC (Local Emergency Planning Committee)	393-2870
	NMOCD	393-6161
	US Bureau of Land Management	393-3612
Eddy County (575)	**Carlsbad**	
	State Police	885-3137
	City Police	885-2111
	Sheriff's Office	887-7551
	Ambulance	**911**
	Fire Department	885-3125
	LEPC (Local Emergency Planning Committee)	887-3798
	US Bureau of Land Management	887-6544
	NM Emergency Response Commission (Santa Fe)	(505) 476-9600
	24 HR	(505) 827-9126
	National Emergency Response Center	(800) 424-8802
	National Pollution Control Center: Direct	(703) 872-6000
	For Oil Spills	(800) 280-7118
	Emergency Services	
	Wild Well Control	(281) 784-4700
	Cudd Pressure Control (915) 699-0139	(915) 563-3356
	Halliburton	(575) 746-2757
	B. J. Services	(575) 746-3569
Give GPS position:	Native Air – Emergency Helicopter – Hobbs	(575) 392-6429
	Flight For Life - Lubbock, TX	(806) 743-9911
	Aerocare - Lubbock, TX	(806) 747-8923
	Med Flight Air Amb - Albuquerque, NM	(575) 842-4433
	Lifeguard Air Med Svc. Albuquerque, NM	(800) 222-1222
	Poison Control (24/7)	(575) 272-3115
	Oil & Gas Pipeline 24 Hour Service	(800) 364-4366
	NOAA – Website - www.nhc.noaa.gov	

Prepared in conjunction with
Dave Small SHARP communications and consulting

WCDSC Permian NM

Eddy County (NAD 83 NM Eastern)
Sec. 36-T23S-R31E
Todd 36-25 State Fed Com 234H

Wellbore #1
Permit Plan 1

Anticollision Report

04 October, 2018

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Reference Permit Plan 1

Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria		
Interpolation Method:	MD Interval 50.00ft	**Error Model:**	ISCWSA
Depth Range:	Unlimited	**Scan Method:**	Closest Approach 3D
Results Limited by:	Maximum center-center distance of 1,500.00 ft	**Error Surface:**	Pedal Curve
Warning Levels Evaluated at:	2.00 **Sigma**	**Casing Method:**	Not applied

Survey Tool Program **Date** 10/4/2018

From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description
0.00	20,823.96	Permit Plan 1 (Wellbore #1)	MWD+HDGM	OWSG MWD + HDGM

Summary

Site Name / Offset Well - Wellbore - Design	Reference Measured Depth (ft)	Offset Measured Depth (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Separation Factor	Warning
Sec. 25-T23S-R31E						
Aldabra 25 Fed 3H - Wellbore #1 - Wellbore #1						Out of range
Aldabra 25 Fed 6H - Wellbore #1 - Wellbore #1	17,742.03	11,281.67	1,481.80	1,390.99	16.317	CC
Aldabra 25 Fed 6H - Wellbore #1 - Wellbore #1	20,550.00	14,052.00	1,490.95	1,353.65	10.859	ES
Aldabra 25 Fed 6H - Wellbore #1 - Wellbore #1	20,650.00	14,052.00	1,496.88	1,358.37	10.807	SF
Aldabra 25 Fed 7H - Wellbore #1 - Wellbore #1						Out of range
Aldabra 25 Fed Com 1H - Wellbore #1 - Wellbore #1						Out of range
Aldabra 25 Fed Com 2H - Wellbore #1 - Wellbore #1						Out of range
Todd 25 Fed 001Z SWD (Offset) - Wellbore #1 - Wellbor						Out of range
Sec. 36-T23S-R31E						
Todd 36 State 01 SWD - Wellbore #1 - Wellbore #1						Out of range
Todd 36 State 231H - Wellbore #1 - Permit Plan 1						Out of range
Todd 36_25 State Fed Com 232H - Wellbore #1 - Origina						Out of range
Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit	2,500.00	2,499.50	29.99	12.48	1.713	Minor Risk, CC
Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit	2,550.00	2,549.28	30.17	12.32	1.690	Minor Risk, ES
Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit	2,600.00	2,599.04	30.73	12.53	1.688	Minor Risk, SF
Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit	2,500.00	2,500.30	30.02	12.51	1.715	Minor Risk, CC
Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit	2,550.00	2,550.04	30.23	12.38	1.693	Minor Risk, ES, SF
Todd 36-25 State Fed Com 230H - Wellbore #1 - Permit	10,134.60	10,259.94	961.09	889.09	13.348	CC
Todd 36-25 State Fed Com 230H - Wellbore #1 - Permit	20,823.96	20,578.59	982.50	691.67	3.378	Alert, ES, SF
Todd 36B State 20H (Offset) - Wellbore #1 - Wellbore #1	9,087.24	13,880.55	1,019.98	869.29	6.769	CC, ES, SF

Offset Design Sec. 25-T23S-R31E - Aldabra 25 Fed 6H - Wellbore #1 - Wellbore #1 — **Offset Site Error:** 0.00 ft

Survey Program: 100-GYRO-NS-CT, 8328-MWD+IGRF — **Offset Well Error:** 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
16,350.00	10,560.00	9,931.27	9,141.21	92.43	36.82	-15.30	5,775.67	-41.04	1,499.76	1,426.57	73.19	20.491	
16,400.00	10,560.00	9,979.45	9,141.84	93.10	37.13	-15.21	5,823.78	-38.47	1,498.36	1,424.62	73.73	20.321	
16,450.00	10,560.00	10,019.48	9,142.26	93.76	37.40	-15.12	5,863.75	-36.29	1,497.09	1,422.80	74.30	20.150	
16,500.00	10,560.00	10,052.93	9,142.26	94.43	37.63	-15.05	5,897.15	-34.54	1,496.33	1,421.46	74.88	19.984	
16,543.37	10,560.00	10,081.95	9,141.97	95.01	37.84	-14.99	5,926.14	-33.07	1,496.12	1,420.74	75.38	19.848	
16,550.00	10,560.00	10,086.39	9,141.90	95.10	37.87	-14.98	5,930.56	-32.85	1,496.13	1,420.67	75.46	19.828	
16,600.00	10,560.00	10,128.15	9,141.09	95.77	38.19	-14.89	5,972.27	-30.87	1,496.38	1,420.35	76.03	19.682	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 25-T23S-R31E - Aldabra 25 Fed 6H - Wellbore #1 - Wellbore #1 — Offset Site Error: 0.00 ft

Survey Program: 100-GYRO-NS-CT, 8328-MWD+IGRF — Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
16,650.00	10,560.00	10,173.28	9,140.11	96.44	38.55	-14.80	6,017.35	-28.91	1,496.82	1,420.21	76.61	19.539	
16,700.00	10,560.00	10,225.68	9,138.91	97.12	39.00	-14.70	6,069.69	-26.78	1,497.34	1,420.15	77.19	19.399	
16,750.00	10,560.00	10,282.74	9,137.79	97.79	39.50	-14.58	6,126.68	-24.24	1,497.66	1,419.90	77.76	19.260	
16,800.00	10,560.00	10,335.88	9,136.89	98.46	39.99	-14.47	6,179.75	-21.69	1,497.81	1,419.47	78.34	19.119	
16,850.00	10,560.00	10,398.07	9,136.02	99.14	40.58	-14.34	6,241.86	-18.63	1,497.84	1,418.93	78.91	18.980	
16,900.00	10,560.00	10,485.39	9,136.99	99.81	41.47	-14.21	6,329.11	-15.37	1,496.67	1,417.18	79.50	18.827	
16,950.00	10,560.00	10,523.52	9,137.69	100.49	41.88	-14.16	6,367.22	-14.16	1,495.33	1,415.18	80.14	18.659	
17,000.00	10,560.00	10,561.66	9,138.07	101.17	42.30	-14.11	6,405.33	-12.87	1,494.38	1,413.59	80.78	18.498	
17,050.00	10,560.00	10,606.09	9,138.19	101.85	42.80	-14.04	6,449.73	-11.27	1,493.74	1,412.31	81.42	18.345	
17,100.00	10,560.00	10,652.00	9,138.14	102.52	43.32	-13.96	6,495.61	-9.44	1,493.24	1,411.19	82.06	18.198	
17,150.00	10,560.00	10,708.29	9,138.06	103.20	43.98	-13.87	6,551.84	-7.11	1,492.76	1,410.07	82.68	18.054	
17,200.00	10,560.00	10,768.26	9,138.41	103.88	44.69	-13.77	6,611.77	-4.82	1,491.96	1,408.64	83.31	17.908	
17,250.00	10,560.00	10,819.35	9,138.92	104.56	45.33	-13.70	6,662.83	-3.06	1,491.00	1,407.03	83.97	17.757	
17,300.00	10,560.00	10,872.32	9,139.60	105.24	46.00	-13.64	6,715.77	-1.43	1,489.95	1,405.33	84.63	17.606	
17,350.00	10,560.00	10,926.31	9,140.47	105.93	46.70	-13.58	6,769.73	0.06	1,488.78	1,403.49	85.30	17.454	
17,400.00	10,560.00	10,975.55	9,141.38	106.61	47.35	-13.53	6,818.95	1.28	1,487.53	1,401.56	85.98	17.302	
17,450.00	10,560.00	11,021.85	9,142.15	107.29	47.97	-13.49	6,865.23	2.37	1,486.38	1,399.72	86.66	17.152	
17,500.00	10,560.00	11,068.29	9,142.84	107.97	48.61	-13.45	6,911.65	3.35	1,485.36	1,398.01	87.35	17.005	
17,550.00	10,560.00	11,114.83	9,143.48	108.66	49.25	-13.42	6,958.18	4.05	1,484.45	1,396.40	88.05	16.859	
17,600.00	10,560.00	11,164.26	9,144.15	109.34	49.95	-13.40	7,007.61	4.49	1,483.63	1,394.87	88.76	16.715	
17,650.00	10,560.00	11,216.33	9,144.92	110.03	50.70	-13.38	7,059.67	4.88	1,482.77	1,393.29	89.48	16.571	
17,700.00	10,560.00	11,254.34	9,145.43	110.71	51.25	-13.37	7,097.68	5.09	1,482.00	1,391.80	90.20	16.430	
17,742.03	10,560.00	11,281.67	9,145.55	111.29	51.66	-13.37	7,125.01	5.06	1,481.80	1,390.99	90.81	16.317	CC
17,750.00	10,560.00	11,286.85	9,145.54	111.40	51.73	-13.37	7,130.19	5.04	1,481.80	1,390.88	90.93	16.297	
17,800.00	10,560.00	11,326.00	9,145.21	112.09	52.31	-13.37	7,169.33	4.69	1,482.22	1,390.56	91.66	16.171	
17,850.00	10,560.00	11,362.25	9,144.63	112.77	52.86	-13.37	7,205.58	4.25	1,483.03	1,390.64	92.39	16.052	
17,900.00	10,560.00	11,407.80	9,143.74	113.46	53.55	-13.37	7,251.11	3.82	1,484.03	1,390.90	93.13	15.935	
17,950.00	10,560.00	11,457.44	9,142.67	114.15	54.31	-13.37	7,300.74	3.34	1,485.13	1,391.25	93.87	15.820	
18,000.00	10,560.00	11,508.57	9,141.69	114.84	55.10	-13.39	7,351.85	2.49	1,486.20	1,391.56	94.63	15.705	
18,050.00	10,560.00	11,550.92	9,140.84	115.53	55.76	-13.40	7,394.19	1.64	1,487.35	1,391.96	95.39	15.592	
18,100.00	10,560.00	11,592.00	9,139.74	116.22	56.41	-13.41	7,435.25	0.91	1,488.80	1,392.66	96.14	15.486	
18,150.00	10,560.00	11,711.78	9,138.53	116.91	58.31	-13.47	7,554.98	-1.49	1,489.78	1,392.78	97.00	15.358	
18,200.00	10,560.00	11,752.94	9,139.12	117.60	58.98	-13.50	7,596.12	-2.49	1,489.29	1,391.50	97.79	15.229	
18,250.00	10,560.00	11,799.80	9,139.71	118.29	59.74	-13.54	7,642.97	-3.62	1,488.90	1,390.31	98.59	15.102	
18,287.68	10,560.00	11,827.46	9,139.92	118.81	60.19	-13.56	7,670.62	-4.28	1,488.78	1,389.60	99.18	15.011	
18,300.00	10,560.00	11,836.63	9,139.95	118.98	60.34	-13.57	7,679.78	-4.49	1,488.79	1,389.42	99.37	14.982	
18,350.00	10,560.00	11,873.83	9,139.87	119.67	60.95	-13.59	7,716.97	-5.34	1,489.11	1,388.96	100.15	14.868	
18,400.00	10,560.00	11,917.96	9,139.41	120.37	61.67	-13.61	7,761.09	-6.30	1,489.81	1,388.87	100.94	14.759	
18,450.00	10,560.00	11,969.49	9,138.86	121.06	62.52	-13.64	7,812.60	-7.39	1,490.52	1,388.78	101.74	14.651	
18,500.00	10,560.00	12,017.81	9,138.35	121.75	63.32	-13.66	7,860.91	-8.39	1,491.21	1,388.67	102.53	14.544	
18,550.00	10,560.00	12,064.33	9,137.77	122.45	64.09	-13.69	7,907.41	-9.35	1,492.00	1,388.68	103.33	14.440	
18,600.00	10,560.00	12,113.22	9,137.06	123.14	64.91	-13.71	7,956.29	-10.36	1,492.89	1,388.77	104.12	14.338	
18,650.00	10,560.00	12,163.57	9,136.32	123.83	65.75	-13.73	8,006.63	-11.36	1,493.78	1,388.85	104.93	14.236	
18,700.00	10,560.00	12,207.51	9,135.58	124.53	66.49	-13.74	8,050.56	-12.09	1,494.73	1,389.02	105.71	14.140	
18,750.00	10,560.00	12,249.11	9,134.56	125.22	67.19	-13.73	8,092.15	-12.39	1,495.95	1,389.47	106.48	14.050	
18,800.00	10,560.00	12,313.41	9,132.77	125.92	68.27	-13.70	8,156.41	-12.35	1,497.27	1,390.02	107.25	13.960	
18,850.00	10,560.00	12,386.27	9,132.16	126.62	69.50	-13.69	8,229.27	-12.60	1,497.61	1,389.56	108.06	13.860	
18,900.00	10,560.00	12,435.36	9,132.01	127.31	70.33	-13.69	8,278.36	-12.82	1,497.75	1,388.91	108.84	13.761	
18,950.00	10,560.00	12,487.70	9,131.85	128.01	71.22	-13.69	8,330.70	-13.02	1,497.89	1,388.26	109.63	13.663	
19,000.00	10,560.00	12,543.30	9,131.88	128.71	72.18	-13.69	8,386.30	-13.36	1,497.87	1,387.44	110.43	13.564	
19,050.00	10,560.00	12,595.71	9,132.09	129.40	73.08	-13.70	8,438.71	-13.77	1,497.70	1,386.47	111.23	13.465	
19,100.00	10,560.00	12,647.27	9,132.35	130.10	73.96	-13.70	8,490.26	-14.12	1,497.48	1,385.45	112.03	13.366	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 25-T23S-R31E - Aldabra 25 Fed 6H - Wellbore #1 - Wellbore #1 — **Offset Site Error:** 0.00 ft

Survey Program: 100-GYRO-NS-CT, 8328-MWD+IGRF — **Offset Well Error:** 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
19,150.00	10,560.00	12,699.62	9,132.67	130.80	74.87	-13.71	8,542.61	-14.46	1,497.20	1,384.36	112.84	13.268	
19,200.00	10,560.00	12,751.99	9,133.08	131.50	75.78	-13.71	8,594.99	-14.80	1,496.83	1,383.19	113.64	13.171	
19,250.00	10,560.00	12,800.71	9,133.46	132.20	76.62	-13.72	8,643.70	-15.09	1,496.46	1,382.01	114.45	13.075	
19,300.00	10,560.00	12,851.01	9,133.83	132.89	77.50	-13.72	8,694.00	-15.36	1,496.11	1,380.86	115.25	12.981	
19,350.00	10,560.00	12,905.15	9,134.34	133.59	78.44	-13.73	8,748.14	-15.73	1,495.67	1,379.60	116.07	12.886	
19,400.00	10,560.00	12,955.76	9,134.97	134.29	79.33	-13.74	8,798.73	-16.21	1,495.12	1,378.23	116.89	12.791	
19,450.00	10,560.00	13,002.33	9,135.49	134.99	80.15	-13.76	8,845.30	-16.74	1,494.65	1,376.94	117.71	12.698	
19,500.00	10,560.00	13,048.91	9,135.93	135.69	80.97	-13.78	8,891.87	-17.36	1,494.29	1,375.76	118.53	12.607	
19,550.00	10,560.00	13,095.48	9,136.28	136.39	81.80	-13.80	8,938.44	-18.07	1,494.04	1,374.68	119.36	12.517	
19,600.00	10,560.00	13,144.43	9,136.56	137.10	82.66	-13.82	8,987.38	-18.90	1,493.90	1,373.70	120.19	12.429	
19,650.00	10,560.00	13,196.80	9,136.93	137.80	83.59	-13.85	9,039.74	-19.81	1,493.71	1,372.67	121.04	12.341	
19,700.00	10,560.00	13,249.30	9,137.38	138.50	84.53	-13.88	9,092.23	-20.75	1,493.44	1,371.55	121.88	12.253	
19,750.00	10,560.00	13,301.89	9,137.98	139.20	85.47	-13.91	9,144.80	-21.85	1,493.08	1,370.34	122.74	12.164	
19,800.00	10,560.00	13,344.55	9,138.45	139.90	86.23	-13.95	9,187.46	-22.85	1,492.77	1,369.18	123.59	12.078	
19,823.69	10,560.00	13,363.65	9,138.57	140.23	86.58	-13.96	9,206.55	-23.31	1,492.74	1,368.74	123.99	12.039	
19,850.00	10,560.00	13,384.86	9,138.63	140.60	86.96	-13.98	9,227.75	-23.83	1,492.78	1,368.35	124.44	11.996	
19,900.00	10,560.00	13,430.62	9,138.58	141.31	87.78	-14.01	9,273.50	-24.99	1,493.07	1,367.79	125.29	11.917	
19,950.00	10,560.00	13,483.02	9,138.58	142.01	88.73	-14.06	9,325.87	-26.46	1,493.35	1,367.18	126.16	11.837	
20,000.00	10,560.00	13,541.58	9,138.82	142.71	89.79	-14.12	9,384.41	-28.31	1,493.47	1,366.41	127.07	11.754	
20,050.00	10,560.00	13,603.65	9,139.61	143.41	90.91	-14.19	9,446.43	-30.45	1,493.22	1,365.23	127.99	11.667	
20,100.00	10,560.00	13,643.55	9,140.12	144.12	91.64	-14.24	9,486.30	-31.92	1,492.98	1,364.11	128.87	11.585	
20,122.66	10,560.00	13,662.74	9,140.30	144.44	91.99	-14.27	9,505.48	-32.66	1,492.95	1,363.68	129.28	11.548	
20,150.00	10,560.00	13,685.89	9,140.47	144.82	92.41	-14.30	9,528.60	-33.57	1,492.99	1,363.23	129.76	11.505	
20,200.00	10,560.00	13,743.94	9,140.97	145.53	93.47	-14.38	9,586.60	-35.98	1,493.03	1,362.32	130.71	11.423	
20,250.00	10,560.00	13,804.12	9,141.94	146.23	94.57	-14.48	9,646.72	-38.65	1,492.73	1,361.07	131.67	11.337	
20,300.00	10,560.00	13,850.81	9,142.78	146.93	95.43	-14.56	9,693.35	-40.87	1,492.39	1,359.79	132.61	11.254	
20,350.00	10,560.00	13,902.28	9,143.78	147.64	96.38	-14.66	9,744.74	-43.48	1,492.03	1,358.46	133.57	11.170	
20,400.00	10,560.00	13,955.88	9,144.97	148.34	97.37	-14.77	9,798.25	-46.38	1,491.57	1,357.01	134.56	11.085	
20,450.00	10,560.00	14,006.50	9,146.24	149.05	98.30	-14.88	9,848.77	-49.29	1,491.03	1,355.48	135.55	11.000	
20,500.00	10,560.00	14,056.42	9,147.51	149.75	99.22	-14.99	9,898.58	-52.21	1,490.49	1,353.95	136.55	10.916	
20,511.46	10,560.00	14,052.00	9,147.39	149.92	99.14	-14.98	9,894.18	-51.96	1,490.45	1,353.74	136.72	10.902	
20,550.00	10,560.00	14,052.00	9,147.39	150.46	99.14	-14.98	9,894.18	-51.96	1,490.95	1,353.65	137.30	10.859	ES
20,600.00	10,560.00	14,052.00	9,147.39	151.17	99.14	-14.98	9,894.18	-51.96	1,493.08	1,355.12	137.96	10.822	
20,650.00	10,560.00	14,052.00	9,147.39	151.87	99.14	-14.98	9,894.18	-51.96	1,496.88	1,358.37	138.51	10.807	SF

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit Plan 1 — **Offset Site Error:** 0.00 ft

Survey Program: 0-MWD+HDGM — **Offset Well Error:** 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
0.00	0.00	0.50	-0.50	0.50	0.50	-90.32	-0.17	-29.99	29.99				
50.00	50.00	49.50	49.50	0.50	0.50	-90.32	-0.17	-29.99	29.99	28.98	1.01	29.796	
100.00	100.00	100.50	99.50	0.52	0.52	-90.32	-0.17	-29.99	29.99	28.95	1.04	28.945	
150.00	150.00	149.50	149.50	0.59	0.59	-90.32	-0.17	-29.99	29.99	28.81	1.18	25.423	
200.00	200.00	200.50	199.50	0.70	0.70	-90.32	-0.17	-29.99	29.99	28.58	1.41	21.336	
250.00	250.00	249.50	249.50	0.84	0.84	-90.32	-0.17	-29.99	29.99	28.31	1.67	17.913	
300.00	300.00	300.50	299.50	0.99	0.99	-90.32	-0.17	-29.99	29.99	28.01	1.98	15.174	
350.00	350.00	349.50	349.50	1.15	1.14	-90.32	-0.17	-29.99	29.99	27.70	2.29	13.098	
400.00	400.00	400.50	399.50	1.31	1.31	-90.32	-0.17	-29.99	29.99	27.37	2.62	11.446	
450.00	450.00	449.50	449.50	1.48	1.47	-90.32	-0.17	-29.99	29.99	27.04	2.95	10.162	
500.00	500.00	500.50	499.50	1.65	1.65	-90.32	-0.17	-29.99	29.99	26.69	3.29	9.104	
550.00	550.00	549.50	549.50	1.82	1.82	-90.32	-0.17	-29.99	29.99	26.35	3.63	8.253	
600.00	600.00	600.50	599.50	1.99	1.99	-90.32	-0.17	-29.99	29.99	26.00	3.98	7.529	
650.00	650.00	649.50	649.50	2.16	2.16	-90.32	-0.17	-29.99	29.99	25.66	4.33	6.930	
700.00	700.00	700.50	699.50	2.34	2.34	-90.32	-0.17	-29.99	29.99	25.31	4.68	6.407	
750.00	750.00	749.50	749.50	2.51	2.51	-90.32	-0.17	-29.99	29.99	24.96	5.03	5.964	
800.00	800.00	800.50	799.50	2.69	2.69	-90.32	-0.17	-29.99	29.99	24.60	5.38	5.571	
850.00	850.00	849.50	849.50	2.87	2.87	-90.32	-0.17	-29.99	29.99	24.25	5.73	5.231	
900.00	900.00	900.50	899.50	3.04	3.05	-90.32	-0.17	-29.99	29.99	23.90	6.09	4.925	Alert
950.00	950.00	949.50	949.50	3.22	3.22	-90.32	-0.17	-29.99	29.99	23.55	6.44	4.657	Alert
1,000.00	1,000.00	1,000.50	999.50	3.40	3.40	-90.32	-0.17	-29.99	29.99	23.19	6.80	4.412	Alert
1,050.00	1,050.00	1,049.50	1,049.50	3.58	3.57	-90.32	-0.17	-29.99	29.99	22.84	7.15	4.195	Alert
1,100.00	1,100.00	1,100.50	1,099.50	3.75	3.75	-90.32	-0.17	-29.99	29.99	22.48	7.51	3.995	Alert
1,150.00	1,150.00	1,149.50	1,149.50	3.93	3.93	-90.32	-0.17	-29.99	29.99	22.13	7.86	3.816	Alert
1,200.00	1,200.00	1,200.50	1,199.50	4.11	4.11	-90.32	-0.17	-29.99	29.99	21.77	8.22	3.649	Alert
1,250.00	1,250.00	1,249.50	1,249.50	4.29	4.28	-90.32	-0.17	-29.99	29.99	21.42	8.57	3.499	Alert
1,300.00	1,300.00	1,300.50	1,299.50	4.46	4.47	-90.32	-0.17	-29.99	29.99	21.06	8.93	3.358	Alert
1,350.00	1,350.00	1,349.50	1,349.50	4.64	4.64	-90.32	-0.17	-29.99	29.99	20.70	9.28	3.230	Alert
1,400.00	1,400.00	1,400.50	1,399.50	4.82	4.82	-90.32	-0.17	-29.99	29.99	20.34	9.64	3.110	Alert
1,450.00	1,450.00	1,449.50	1,449.50	5.00	5.00	-90.32	-0.17	-29.99	29.99	19.99	10.00	3.000	Alert
1,500.00	1,500.00	1,500.50	1,499.50	5.18	5.18	-90.32	-0.17	-29.99	29.99	19.63	10.36	2.896	Alert
1,550.00	1,550.00	1,549.50	1,549.50	5.36	5.35	-90.32	-0.17	-29.99	29.99	19.28	10.71	2.800	Alert
1,600.00	1,600.00	1,600.50	1,599.50	5.53	5.54	-90.32	-0.17	-29.99	29.99	18.92	11.07	2.709	Alert
1,650.00	1,650.00	1,649.50	1,649.50	5.71	5.71	-90.32	-0.17	-29.99	29.99	18.56	11.42	2.625	Alert
1,700.00	1,700.00	1,700.50	1,699.50	5.89	5.89	-90.32	-0.17	-29.99	29.99	18.20	11.78	2.545	Alert
1,750.00	1,750.00	1,749.50	1,749.50	6.07	6.07	-90.32	-0.17	-29.99	29.99	17.85	12.14	2.471	Minor Risk
1,800.00	1,800.00	1,800.50	1,799.50	6.25	6.25	-90.32	-0.17	-29.99	29.99	17.49	12.50	2.399	Minor Risk
1,850.00	1,850.00	1,849.50	1,849.50	6.43	6.43	-90.32	-0.17	-29.99	29.99	17.13	12.85	2.333	Minor Risk
1,900.00	1,900.00	1,900.50	1,899.50	6.61	6.61	-90.32	-0.17	-29.99	29.99	16.77	13.21	2.269	Minor Risk
1,950.00	1,950.00	1,949.50	1,949.50	6.78	6.78	-90.32	-0.17	-29.99	29.99	16.42	13.57	2.210	Minor Risk
2,000.00	2,000.00	2,000.50	1,999.50	6.96	6.97	-90.32	-0.17	-29.99	29.99	16.06	13.93	2.153	Minor Risk
2,050.00	2,050.00	2,049.50	2,049.50	7.14	7.14	-90.32	-0.17	-29.99	29.99	15.70	14.28	2.100	Minor Risk
2,100.00	2,100.00	2,100.50	2,099.50	7.32	7.32	-90.32	-0.17	-29.99	29.99	15.34	14.64	2.048	Minor Risk
2,150.00	2,150.00	2,149.50	2,149.50	7.50	7.50	-90.32	-0.17	-29.99	29.99	14.99	15.00	1.999	Minor Risk
2,200.00	2,200.00	2,200.50	2,199.50	7.68	7.68	-90.32	-0.17	-29.99	29.99	14.63	15.36	1.952	Minor Risk
2,250.00	2,250.00	2,249.50	2,249.50	7.86	7.86	-90.32	-0.17	-29.99	29.99	14.27	15.71	1.908	Minor Risk
2,300.00	2,300.00	2,300.50	2,299.50	8.04	8.04	-90.32	-0.17	-29.99	29.99	13.91	16.07	1.865	Minor Risk
2,350.00	2,350.00	2,349.50	2,349.50	8.22	8.21	-90.32	-0.17	-29.99	29.99	13.56	16.43	1.825	Minor Risk
2,400.00	2,400.00	2,400.50	2,399.50	8.39	8.40	-90.32	-0.17	-29.99	29.99	13.20	16.79	1.786	Minor Risk
2,450.00	2,450.00	2,449.50	2,449.50	8.57	8.57	-90.32	-0.17	-29.99	29.99	12.84	17.14	1.749	Minor Risk
2,500.00	2,500.00	2,499.50	2,499.50	8.75	8.75	-90.32	-0.17	-29.99	29.99	12.48	17.50	1.713	Minor Risk, CC
2,550.00	2,550.00	2,549.28	2,549.28	8.93	8.92	-90.53	-0.28	-30.17	30.17	12.32	17.85	1.690	Minor Risk, ES

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit Plan 1 — **Offset Site Error:** 0.00 ft

Survey Program: 0-MWD+HDGM — **Offset Well Error:** 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
2,600.00	2,600.00	2,599.04	2,599.04	9.11	9.09	-91.14	-0.61	-30.72	30.73	12.53	18.20	1.688	Minor Risk, SF
2,650.00	2,650.00	2,648.80	2,648.78	9.29	9.26	-92.11	-1.17	-31.64	31.67	13.13	18.54	1.708	Minor Risk
2,700.00	2,700.00	2,698.53	2,698.49	9.47	9.42	-93.38	-1.95	-32.93	33.00	14.12	18.88	1.748	Minor Risk
2,750.00	2,750.00	2,748.23	2,748.15	9.65	9.59	-94.87	-2.95	-34.59	34.74	15.52	19.22	1.807	Minor Risk
2,800.00	2,800.00	2,797.89	2,797.76	9.83	9.76	-96.50	-4.17	-36.62	36.89	17.33	19.56	1.886	Minor Risk
2,850.00	2,850.00	2,847.51	2,847.30	10.00	9.92	-98.19	-5.61	-39.01	39.47	19.57	19.90	1.983	Minor Risk
2,900.00	2,900.00	2,897.07	2,896.76	10.18	10.09	-99.88	-7.27	-41.76	42.48	22.24	20.24	2.099	Minor Risk
2,950.00	2,950.00	2,946.58	2,946.13	10.36	10.26	-101.53	-9.16	-44.88	45.93	25.36	20.57	2.233	Minor Risk
3,000.00	3,000.00	2,996.32	2,995.71	10.54	10.43	-103.07	-11.21	-48.28	49.71	28.79	20.91	2.377	Minor Risk
3,050.00	3,050.00	3,046.16	3,045.39	10.72	10.60	-104.40	-13.27	-51.70	53.53	32.27	21.26	2.518	Alert
3,100.00	3,100.00	3,096.00	3,095.07	10.90	10.77	-105.55	-15.33	-55.11	57.38	35.77	21.61	2.656	Alert
3,150.00	3,150.00	3,145.84	3,144.75	11.08	10.94	-106.55	-17.40	-58.53	61.25	39.29	21.95	2.790	Alert
3,200.00	3,200.00	3,195.68	3,194.43	11.26	11.11	-107.44	-19.46	-61.95	65.13	42.83	22.30	2.921	Alert
3,250.00	3,250.00	3,245.52	3,244.11	11.44	11.28	-108.22	-21.52	-65.37	69.03	46.38	22.65	3.048	Alert
3,300.00	3,300.00	3,304.64	3,293.79	11.62	11.49	-108.92	-23.58	-68.79	72.94	49.91	23.03	3.167	Alert
3,350.00	3,350.00	3,345.20	3,343.47	11.80	11.63	-109.55	-25.65	-72.21	76.86	53.51	23.35	3.292	Alert
3,400.00	3,400.00	3,404.96	3,393.15	11.97	11.84	-110.12	-27.71	-75.62	80.79	57.06	23.73	3.405	Alert
3,450.00	3,450.00	3,444.88	3,442.83	12.15	11.98	-110.64	-29.77	-79.04	84.73	60.68	24.05	3.524	Alert
3,500.00	3,500.00	3,505.28	3,492.50	12.33	12.19	-111.11	-31.83	-82.46	88.67	64.24	24.43	3.629	Alert
3,550.00	3,550.00	3,544.56	3,542.18	12.51	12.33	-111.54	-33.90	-85.88	92.61	67.87	24.75	3.743	Alert
3,600.00	3,600.00	3,605.60	3,591.86	12.69	12.54	-111.93	-35.96	-89.30	96.57	71.43	25.14	3.842	Alert
3,650.00	3,650.00	3,644.24	3,641.54	12.87	12.68	-112.30	-38.02	-92.71	100.52	75.08	25.45	3.950	Alert
3,700.00	3,700.00	3,705.93	3,691.22	13.05	12.90	-112.63	-40.08	-96.13	104.48	78.64	25.84	4.044	Alert
3,750.00	3,750.00	3,743.91	3,740.90	13.23	13.03	-112.95	-42.15	-99.55	108.45	82.30	26.15	4.147	Alert
3,800.00	3,800.00	3,806.25	3,790.58	13.41	13.25	-113.24	-44.21	-102.97	112.41	85.87	26.54	4.235	Alert
3,850.00	3,850.00	3,843.59	3,840.26	13.59	13.38	-113.51	-46.27	-106.39	116.38	89.53	26.85	4.334	Alert
3,900.00	3,900.00	3,906.57	3,889.94	13.77	13.61	-113.76	-48.33	-109.80	120.35	93.10	27.25	4.417	Alert
3,950.00	3,950.00	3,943.27	3,939.62	13.94	13.74	-113.99	-50.40	-113.22	124.33	96.77	27.56	4.512	Alert
4,000.00	4,000.00	4,006.89	3,989.30	14.12	13.96	-114.22	-52.46	-116.64	128.30	100.34	27.96	4.589	Alert
4,050.00	4,050.00	4,042.94	4,038.97	14.30	14.09	119.68	-54.52	-120.06	132.41	104.16	28.25	4.686	Alert
4,100.00	4,099.99	4,107.25	4,088.61	14.47	14.32	119.73	-56.58	-123.47	136.79	108.14	28.65	4.775	Alert
4,150.00	4,149.97	4,142.53	4,138.23	14.63	14.45	119.97	-58.64	-126.89	141.45	112.51	28.94	4.888	Alert
4,200.00	4,199.94	4,207.73	4,187.81	14.80	14.68	120.37	-60.70	-130.30	146.38	117.04	29.33	4.990	Alert
4,250.00	4,249.88	4,241.97	4,237.36	14.96	14.81	120.91	-62.76	-133.71	151.59	121.98	29.62	5.118	
4,300.00	4,299.79	4,308.37	4,286.85	15.13	15.05	121.58	-64.81	-137.11	157.11	127.09	30.02	5.234	
4,350.00	4,349.66	4,341.23	4,336.30	15.30	15.16	122.37	-66.87	-140.51	162.94	132.64	30.30	5.378	
4,400.00	4,399.49	4,409.23	4,385.68	15.47	15.41	123.24	-68.92	-143.91	169.10	138.39	30.70	5.508	
4,450.00	4,449.29	4,440.27	4,435.02	15.63	15.52	124.21	-70.97	-147.31	175.53	144.55	30.98	5.666	
4,500.00	4,499.09	4,489.77	4,484.36	15.80	15.70	125.13	-73.01	-150.70	182.02	150.70	31.32	5.811	
4,550.00	4,548.88	4,539.26	4,533.69	15.97	15.88	125.99	-75.06	-154.10	188.55	156.89	31.66	5.955	
4,600.00	4,598.68	4,588.76	4,583.03	16.14	16.06	126.79	-77.11	-157.49	195.12	163.12	32.00	6.097	
4,650.00	4,648.47	4,638.25	4,632.36	16.31	16.24	127.54	-79.16	-160.88	201.73	169.38	32.35	6.236	
4,700.00	4,698.27	4,687.74	4,681.70	16.48	16.42	128.24	-81.21	-164.28	208.37	175.68	32.69	6.374	
4,750.00	4,748.06	4,737.24	4,731.03	16.65	16.59	128.90	-83.26	-167.67	215.04	182.00	33.04	6.509	
4,800.00	4,797.86	4,786.73	4,780.37	16.82	16.77	129.52	-85.30	-171.07	221.73	188.35	33.38	6.643	
4,850.00	4,847.65	4,836.23	4,829.71	16.99	16.95	130.10	-87.35	-174.46	228.45	194.73	33.73	6.774	
4,900.00	4,897.45	4,885.72	4,879.04	17.16	17.13	130.65	-89.40	-177.86	235.19	201.12	34.07	6.903	
4,950.00	4,947.25	4,935.22	4,928.38	17.34	17.31	131.17	-91.45	-181.25	241.95	207.54	34.42	7.030	
5,000.00	4,997.04	4,984.71	4,977.71	17.51	17.49	131.66	-93.50	-184.65	248.73	213.97	34.76	7.155	
5,050.00	5,046.84	5,034.21	5,027.05	17.68	17.67	132.13	-95.55	-188.04	255.53	220.42	35.11	7.278	
5,100.00	5,096.63	5,083.70	5,076.38	17.86	17.85	132.57	-97.59	-191.43	262.34	226.88	35.46	7.399	
5,150.00	5,146.43	5,133.20	5,125.72	18.03	18.04	132.98	-99.64	-194.83	269.16	233.36	35.80	7.518	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit Plan 1 — Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM — Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
5,200.00	5,196.22	5,182.69	5,175.05	18.20	18.22	133.38	-101.69	-198.22	276.00	239.85	36.15	7.635	
5,250.00	5,246.02	5,232.18	5,224.39	18.38	18.40	133.76	-103.74	-201.62	282.86	246.36	36.50	7.749	
5,300.00	5,295.81	5,281.68	5,273.72	18.55	18.58	134.12	-105.79	-205.01	289.72	252.87	36.85	7.862	
5,350.00	5,345.61	5,331.17	5,323.06	18.73	18.76	134.46	-107.84	-208.41	296.59	259.40	37.20	7.973	
5,400.00	5,395.41	5,380.67	5,372.40	18.90	18.94	134.79	-109.88	-211.80	303.48	265.93	37.55	8.083	
5,450.00	5,445.20	5,430.16	5,421.73	19.08	19.12	135.11	-111.93	-215.20	310.37	272.47	37.90	8.190	
5,500.00	5,495.00	5,479.66	5,471.07	19.25	19.30	135.41	-113.98	-218.59	317.27	279.03	38.25	8.295	
5,550.00	5,544.79	5,529.15	5,520.40	19.43	19.48	135.69	-116.03	-221.98	324.18	285.59	38.60	8.399	
5,600.00	5,594.59	5,578.65	5,569.74	19.61	19.66	135.97	-118.08	-225.38	331.10	292.16	38.95	8.501	
5,650.00	5,644.38	5,628.14	5,619.07	19.78	19.85	136.23	-120.13	-228.77	338.03	298.73	39.30	8.602	
5,700.00	5,694.18	5,677.64	5,668.41	19.96	20.03	136.49	-122.17	-232.17	344.96	305.31	39.65	8.700	
5,750.00	5,743.97	5,727.13	5,717.74	20.14	20.21	136.73	-124.22	-235.56	351.90	311.90	40.00	8.797	
5,800.00	5,793.77	5,776.62	5,767.08	20.31	20.39	136.96	-126.27	-238.96	358.84	318.49	40.35	8.893	
5,850.00	5,843.56	5,826.12	5,816.42	20.49	20.57	137.19	-128.32	-242.35	365.79	325.09	40.70	8.987	
5,900.00	5,893.36	5,875.61	5,865.75	20.67	20.76	137.41	-130.37	-245.74	372.75	331.69	41.06	9.079	
5,950.00	5,943.16	5,925.11	5,915.09	20.85	20.94	137.61	-132.42	-249.14	379.71	338.30	41.41	9.170	
6,000.00	5,992.95	5,974.60	5,964.42	21.03	21.12	137.82	-134.46	-252.53	386.67	344.91	41.76	9.259	
6,050.00	6,042.75	6,024.10	6,013.76	21.21	21.30	138.01	-136.51	-255.93	393.64	351.53	42.11	9.347	
6,100.00	6,092.54	6,073.59	6,063.09	21.38	21.48	138.20	-138.56	-259.32	400.62	358.15	42.47	9.434	
6,150.00	6,142.34	6,123.09	6,112.43	21.56	21.67	138.38	-140.61	-262.72	407.60	364.78	42.82	9.519	
6,200.00	6,192.13	6,172.58	6,161.76	21.74	21.85	138.55	-142.66	-266.11	414.58	371.40	43.17	9.602	
6,250.00	6,241.93	6,222.08	6,211.10	21.92	22.03	138.72	-144.71	-269.51	421.56	378.04	43.53	9.685	
6,300.00	6,291.72	6,271.57	6,260.43	22.10	22.21	138.89	-146.75	-272.90	428.55	384.67	43.88	9.766	
6,350.00	6,341.52	6,321.06	6,309.77	22.28	22.40	139.04	-148.80	-276.29	435.55	391.31	44.24	9.846	
6,400.00	6,391.32	6,370.56	6,359.11	22.46	22.58	139.20	-150.85	-279.69	442.54	397.95	44.59	9.925	
6,450.00	6,441.11	6,420.05	6,408.44	22.64	22.76	139.35	-152.90	-283.08	449.54	404.59	44.94	10.002	
6,500.00	6,490.91	6,469.55	6,457.78	22.82	22.94	139.49	-154.95	-286.48	456.54	411.24	45.30	10.078	
6,550.00	6,540.70	6,519.04	6,507.11	23.00	23.13	139.63	-157.00	-289.87	463.55	417.89	45.65	10.153	
6,600.00	6,590.50	6,568.54	6,556.45	23.18	23.31	139.77	-159.05	-293.27	470.55	424.54	46.01	10.227	
6,650.00	6,640.29	6,618.03	6,605.78	23.36	23.49	139.90	-161.09	-296.66	477.56	431.20	46.36	10.300	
6,700.00	6,690.09	6,667.53	6,655.12	23.54	23.68	140.02	-163.14	-300.06	484.57	437.85	46.72	10.372	
6,750.00	6,739.88	6,717.02	6,704.45	23.72	23.86	140.15	-165.19	-303.45	491.59	444.51	47.08	10.442	
6,800.00	6,789.68	6,766.51	6,753.79	23.90	24.04	140.27	-167.24	-306.84	498.60	451.17	47.43	10.512	
6,850.00	6,839.48	6,816.01	6,803.12	24.09	24.23	140.39	-169.29	-310.24	505.62	457.83	47.79	10.581	
6,900.00	6,889.27	6,865.50	6,852.46	24.27	24.41	140.50	-171.34	-313.63	512.64	464.50	48.14	10.648	
6,950.00	6,939.07	6,915.00	6,901.80	24.45	24.59	140.61	-173.38	-317.03	519.66	471.16	48.50	10.715	
7,000.00	6,988.86	6,964.49	6,951.13	24.63	24.78	140.72	-175.43	-320.42	526.69	477.83	48.86	10.780	
7,050.00	7,038.66	7,013.99	7,000.47	24.81	24.96	140.82	-177.48	-323.82	533.71	484.50	49.21	10.845	
7,100.00	7,088.45	7,063.48	7,049.80	24.99	25.14	140.93	-179.53	-327.21	540.74	491.17	49.57	10.909	
7,150.00	7,138.25	7,112.98	7,099.14	25.18	25.33	141.03	-181.58	-330.61	547.77	497.84	49.93	10.972	
7,200.00	7,188.04	7,162.47	7,148.47	25.36	25.51	141.12	-183.63	-334.00	554.80	504.52	50.28	11.033	
7,250.00	7,237.84	7,211.97	7,197.81	25.54	25.69	141.22	-185.67	-337.39	561.83	511.19	50.64	11.095	
7,300.00	7,287.64	7,261.46	7,247.14	25.72	25.88	141.31	-187.72	-340.79	568.87	517.87	51.00	11.155	
7,350.00	7,337.43	7,310.95	7,296.48	25.90	26.06	141.40	-189.77	-344.18	575.90	524.55	51.36	11.214	
7,400.00	7,387.23	7,360.45	7,345.82	26.09	26.24	141.49	-191.82	-347.58	582.94	531.23	51.71	11.273	
7,450.00	7,437.02	7,409.94	7,395.15	26.27	26.43	141.58	-193.87	-350.97	589.98	537.91	52.07	11.330	
7,500.00	7,486.82	7,459.44	7,444.49	26.45	26.61	141.66	-195.92	-354.37	597.02	544.59	52.43	11.387	
7,550.00	7,536.61	7,508.93	7,493.82	26.64	26.79	141.74	-197.96	-357.76	604.06	551.27	52.79	11.444	
7,600.00	7,586.41	7,558.43	7,543.16	26.82	26.98	141.82	-200.01	-361.15	611.10	557.96	53.14	11.499	
7,650.00	7,636.20	7,607.92	7,592.49	27.00	27.16	141.90	-202.06	-364.55	618.14	564.64	53.50	11.554	
7,700.00	7,686.00	7,657.42	7,641.83	27.19	27.35	141.98	-204.11	-367.94	625.19	571.33	53.86	11.608	
7,750.00	7,735.79	7,706.91	7,691.16	27.37	27.53	142.05	-206.16	-371.34	632.23	578.01	54.22	11.661	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit Plan 1

Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
7,800.00	7,785.59	7,756.41	7,740.50	27.55	27.71	142.12	-208.21	-374.73	639.28	584.70	54.58	11.713	
7,850.00	7,835.39	7,805.90	7,789.83	27.74	27.90	142.20	-210.25	-378.13	646.32	591.39	54.94	11.765	
7,900.00	7,885.18	7,855.39	7,839.17	27.92	28.08	142.27	-212.30	-381.52	653.37	598.08	55.29	11.816	
7,950.00	7,934.98	7,904.89	7,888.51	28.10	28.27	142.33	-214.35	-384.92	660.42	604.77	55.65	11.867	
8,000.00	7,984.77	7,954.38	7,937.84	28.29	28.45	142.40	-216.40	-388.31	667.47	611.46	56.01	11.917	
8,050.00	8,034.57	8,003.88	7,987.18	28.47	28.63	142.47	-218.45	-391.70	674.52	618.15	56.37	11.966	
8,100.00	8,084.36	8,053.37	8,036.51	28.65	28.82	142.53	-220.50	-395.10	681.57	624.84	56.73	12.014	
8,150.00	8,134.16	8,102.87	8,085.85	28.84	29.00	142.59	-222.54	-398.49	688.63	631.54	57.09	12.062	
8,200.00	8,183.95	8,152.36	8,135.18	29.02	29.19	142.66	-224.59	-401.89	695.68	638.23	57.45	12.110	
8,250.00	8,233.75	8,201.86	8,184.52	29.21	29.37	142.72	-226.64	-405.28	702.73	644.93	57.81	12.156	
8,300.00	8,283.55	8,251.35	8,233.85	29.39	29.55	142.78	-228.69	-408.68	709.79	651.62	58.17	12.202	
8,350.00	8,333.34	8,300.84	8,283.19	29.58	29.74	142.83	-230.74	-412.07	716.84	658.32	58.53	12.248	
8,400.00	8,383.14	8,350.34	8,332.52	29.76	29.92	142.89	-232.79	-415.47	723.90	665.01	58.89	12.293	
8,450.00	8,432.93	8,399.83	8,381.86	29.94	30.11	142.95	-234.83	-418.86	730.96	671.71	59.25	12.337	
8,500.00	8,482.73	8,449.33	8,431.20	30.13	30.29	143.00	-236.88	-422.25	738.01	678.41	59.61	12.381	
8,550.00	8,532.52	8,501.18	8,480.53	30.31	30.48	143.06	-238.93	-425.65	745.07	685.10	59.98	12.423	
8,600.00	8,582.32	8,548.32	8,529.87	30.50	30.66	143.11	-240.98	-429.04	752.13	691.80	60.33	12.468	
8,650.00	8,632.11	8,602.19	8,579.20	30.68	30.86	143.16	-243.03	-432.44	759.19	698.49	60.70	12.507	
8,700.00	8,681.91	8,647.31	8,628.54	30.87	31.03	143.21	-245.08	-435.83	766.25	705.20	61.05	12.552	
8,750.00	8,731.71	8,703.20	8,677.87	31.05	31.24	143.26	-247.12	-439.23	773.31	711.88	61.43	12.588	
8,800.00	8,781.50	8,746.30	8,727.21	31.24	31.40	143.31	-249.17	-442.62	780.37	718.61	61.77	12.634	
8,850.00	8,831.30	8,795.79	8,776.54	31.42	31.58	143.36	-251.22	-446.02	787.43	725.31	62.13	12.674	
8,900.00	8,881.09	8,845.28	8,825.88	31.61	31.77	143.41	-253.27	-449.41	794.50	732.01	62.49	12.714	
8,950.00	8,930.89	8,905.22	8,875.22	31.79	31.99	143.45	-255.32	-452.80	801.56	738.67	62.89	12.746	
9,000.00	8,980.68	8,944.27	8,924.55	31.98	32.14	143.50	-257.37	-456.20	808.62	745.41	63.21	12.793	
9,050.00	9,030.48	8,993.77	8,973.89	32.16	32.32	143.54	-259.41	-459.59	815.69	752.12	63.57	12.831	
9,100.00	9,080.27	9,043.26	9,023.22	32.35	32.50	143.59	-261.46	-462.99	822.75	758.82	63.93	12.869	
9,150.00	9,130.07	9,092.76	9,072.56	32.54	32.69	143.63	-263.51	-466.38	829.82	765.52	64.29	12.907	
9,200.00	9,179.87	9,142.25	9,121.89	32.72	32.87	143.67	-265.56	-469.78	836.88	772.23	64.65	12.944	
9,250.00	9,229.66	9,191.75	9,171.23	32.91	33.06	143.71	-267.61	-473.17	843.95	778.93	65.01	12.981	
9,300.00	9,279.46	9,241.24	9,220.56	33.09	33.24	143.75	-269.66	-476.56	851.01	785.64	65.38	13.017	
9,350.00	9,329.27	9,290.76	9,269.92	33.28	33.43	143.83	-271.71	-479.96	857.93	792.20	65.74	13.051	
9,400.00	9,379.13	9,340.34	9,319.35	33.46	33.61	143.90	-273.76	-483.36	864.34	798.25	66.10	13.077	
9,450.00	9,429.04	9,401.62	9,380.46	33.64	33.84	143.94	-276.05	-487.17	869.91	803.38	66.53	13.075	
9,500.00	9,478.98	9,463.53	9,442.27	33.82	34.07	143.98	-277.86	-490.16	874.26	807.30	66.97	13.055	
9,550.00	9,528.95	9,525.62	9,504.32	34.00	34.29	144.00	-279.15	-492.30	877.39	810.01	67.39	13.020	
9,600.00	9,578.94	9,587.84	9,566.51	34.18	34.51	144.02	-279.92	-493.58	879.30	811.50	67.80	12.970	
9,650.00	9,628.93	9,650.12	9,628.79	34.35	34.73	144.03	-280.17	-493.99	879.98	811.79	68.19	12.905	
9,700.00	9,678.93	9,700.24	9,678.43	34.52	34.89	-90.01	-280.17	-493.99	879.99	811.46	68.53	12.841	
9,750.00	9,728.93	9,749.76	9,728.43	34.69	35.06	-90.01	-280.17	-493.99	879.99	811.12	68.87	12.778	
9,800.00	9,778.93	9,800.24	9,778.43	34.86	35.23	-90.01	-280.17	-493.99	879.99	810.78	69.21	12.715	
9,850.00	9,828.93	9,849.76	9,828.43	35.03	35.39	-90.01	-280.17	-493.99	879.99	810.44	69.55	12.653	
9,900.00	9,878.93	9,900.24	9,878.43	35.20	35.56	-90.01	-280.17	-493.99	879.99	810.09	69.89	12.591	
9,950.00	9,928.93	9,949.76	9,928.43	35.38	35.73	-90.01	-280.17	-493.99	879.99	809.75	70.23	12.530	
9,957.86	9,936.79	9,957.62	9,936.29	35.40	35.76	-90.01	-280.17	-493.99	879.99	809.70	70.29	12.520	
10,000.00	9,978.93	9,999.75	9,978.42	35.55	35.90	-90.01	-280.17	-493.99	879.99	809.41	70.57	12.469	
10,050.00	10,028.90	10,049.34	10,027.94	35.72	36.06	-89.67	-277.90	-494.00	879.99	809.08	70.91	12.410	
10,100.00	10,078.54	10,098.85	10,077.01	35.88	36.22	-89.61	-271.38	-494.03	880.00	808.76	71.23	12.354	
10,150.00	10,127.49	10,148.30	10,125.27	36.04	36.37	-89.57	-260.66	-494.09	880.00	808.46	71.55	12.300	
10,200.00	10,175.37	10,197.70	10,172.37	36.19	36.51	-89.52	-245.85	-494.16	880.01	808.16	71.84	12.249	
10,250.00	10,221.81	10,247.04	10,217.97	36.33	36.64	-89.48	-227.05	-494.26	880.01	807.88	72.13	12.201	
10,300.00	10,266.47	10,296.32	10,261.75	36.45	36.76	-89.45	-204.43	-494.38	880.02	807.62	72.40	12.156	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit Plan 1

Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
10,350.00	10,309.00	10,345.57	10,303.38	36.57	36.87	-89.41	-178.15	-494.52	880.02	807.37	72.65	12.113	
10,400.00	10,349.08	10,394.78	10,342.57	36.68	36.97	-89.39	-148.43	-494.67	880.03	807.13	72.90	12.072	
10,450.00	10,386.41	10,443.95	10,379.05	36.77	37.05	-89.36	-115.47	-494.84	880.03	806.90	73.13	12.033	
10,500.00	10,420.70	10,493.10	10,412.54	36.85	37.12	-89.34	-79.53	-495.03	880.03	806.68	73.36	11.996	
10,550.00	10,451.68	10,542.22	10,442.83	36.92	37.18	-89.33	-40.86	-495.23	880.04	806.46	73.58	11.961	
10,600.00	10,479.13	10,591.34	10,469.68	36.98	37.23	-89.32	0.24	-495.44	880.04	806.25	73.79	11.926	
10,650.00	10,502.84	10,640.44	10,492.92	37.04	37.27	-89.32	43.48	-495.66	880.04	806.04	74.00	11.892	
10,700.00	10,522.62	10,689.55	10,512.36	37.11	37.30	-89.32	88.55	-495.90	880.04	805.83	74.21	11.859	
10,750.00	10,538.32	10,738.65	10,527.88	37.18	37.34	-89.33	135.13	-496.14	880.04	805.62	74.42	11.825	
10,800.00	10,549.83	10,787.78	10,539.36	37.26	37.40	-89.34	182.87	-496.39	880.04	805.41	74.63	11.792	
10,850.00	10,557.06	10,836.91	10,546.71	37.36	37.49	-89.36	231.44	-496.64	880.03	805.20	74.83	11.760	
10,900.00	10,559.94	10,886.08	10,549.87	37.46	37.59	-89.38	280.49	-496.89	880.03	804.99	75.04	11.727	
10,926.18	10,560.22	10,912.05	10,550.00	37.52	37.65	-89.37	306.46	-497.03	880.03	804.87	75.16	11.709	
10,950.00	10,560.00	10,935.87	10,550.00	37.57	37.70	-89.38	330.28	-497.15	880.03	804.76	75.27	11.691	
11,000.00	10,560.00	10,985.87	10,550.00	37.69	37.83	-89.38	380.28	-497.41	880.03	804.52	75.51	11.655	
11,050.00	10,560.00	11,035.87	10,550.00	37.83	37.98	-89.38	430.28	-497.67	880.03	804.24	75.79	11.612	
11,100.00	10,560.00	11,085.87	10,550.00	37.98	38.13	-89.38	480.28	-497.93	880.03	803.95	76.08	11.567	
11,150.00	10,560.00	11,135.87	10,550.00	38.16	38.30	-89.38	530.28	-498.19	880.03	803.62	76.41	11.517	
11,200.00	10,560.00	11,185.87	10,550.00	38.33	38.49	-89.38	580.28	-498.45	880.03	803.28	76.75	11.466	
11,250.00	10,560.00	11,235.87	10,550.00	38.53	38.68	-89.38	630.28	-498.71	880.03	802.89	77.14	11.408	
11,300.00	10,560.00	11,285.87	10,550.00	38.73	38.89	-89.38	680.28	-498.96	880.03	802.50	77.53	11.350	
11,350.00	10,560.00	11,335.87	10,550.00	38.95	39.11	-89.38	730.28	-499.22	880.03	802.06	77.97	11.287	
11,400.00	10,560.00	11,385.87	10,550.00	39.18	39.34	-89.38	780.28	-499.48	880.03	801.62	78.42	11.223	
11,450.00	10,560.00	11,435.87	10,550.00	39.42	39.58	-89.38	830.27	-499.74	880.03	801.13	78.90	11.154	
11,500.00	10,560.00	11,485.87	10,550.00	39.67	39.84	-89.38	880.27	-500.00	880.03	800.64	79.39	11.085	
11,550.00	10,560.00	11,535.87	10,550.00	39.94	40.10	-89.38	930.27	-500.26	880.03	800.11	79.93	11.011	
11,600.00	10,560.00	11,585.87	10,550.00	40.21	40.38	-89.38	980.27	-500.52	880.03	799.57	80.46	10.937	
11,650.00	10,560.00	11,635.87	10,550.00	40.51	40.67	-89.38	1,030.27	-500.78	880.03	798.99	81.04	10.859	
11,700.00	10,560.00	11,685.87	10,550.00	40.80	40.97	-89.38	1,080.27	-501.04	880.03	798.41	81.63	10.781	
11,750.00	10,560.00	11,735.87	10,550.00	41.11	41.28	-89.38	1,130.27	-501.30	880.03	797.78	82.25	10.700	
11,800.00	10,560.00	11,785.87	10,550.00	41.43	41.59	-89.38	1,180.27	-501.56	880.03	797.16	82.87	10.619	
11,850.00	10,560.00	11,835.87	10,550.00	41.76	41.92	-89.38	1,230.27	-501.82	880.03	796.50	83.54	10.535	
11,900.00	10,560.00	11,885.87	10,550.00	42.10	42.26	-89.38	1,280.27	-502.07	880.03	795.83	84.20	10.451	
11,950.00	10,560.00	11,935.87	10,550.00	42.45	42.61	-89.38	1,330.27	-502.33	880.03	795.13	84.90	10.365	
12,000.00	10,560.00	11,985.87	10,550.00	42.80	42.97	-89.38	1,380.27	-502.59	880.03	794.42	85.61	10.279	
12,050.00	10,560.00	12,035.87	10,550.00	43.18	43.34	-89.38	1,430.27	-502.85	880.03	793.68	86.35	10.191	
12,100.00	10,560.00	12,085.87	10,550.00	43.55	43.71	-89.38	1,480.27	-503.11	880.03	792.94	87.09	10.104	
12,150.00	10,560.00	12,135.87	10,550.00	43.94	44.10	-89.38	1,530.27	-503.37	880.03	792.16	87.87	10.015	
12,200.00	10,560.00	12,185.87	10,550.00	44.33	44.49	-89.38	1,580.26	-503.63	880.03	791.38	88.65	9.927	
12,250.00	10,560.00	12,235.87	10,550.00	44.73	44.89	-89.38	1,630.26	-503.89	880.03	790.58	89.46	9.838	
12,300.00	10,560.00	12,285.87	10,550.00	45.14	45.30	-89.38	1,680.26	-504.15	880.03	789.76	90.27	9.749	
12,350.00	10,560.00	12,335.87	10,550.00	45.56	45.72	-89.38	1,730.26	-504.41	880.03	788.92	91.11	9.659	
12,400.00	10,560.00	12,385.87	10,550.00	45.99	46.14	-89.38	1,780.26	-504.67	880.03	788.08	91.95	9.570	
12,450.00	10,560.00	12,435.87	10,550.00	46.42	46.58	-89.38	1,830.26	-504.93	880.03	787.21	92.83	9.481	
12,500.00	10,560.00	12,485.87	10,550.00	46.86	47.02	-89.38	1,880.26	-505.18	880.03	786.33	93.70	9.392	
12,550.00	10,560.00	12,535.87	10,550.00	47.31	47.46	-89.38	1,930.26	-505.44	880.03	785.43	94.60	9.303	
12,600.00	10,560.00	12,585.87	10,550.00	47.76	47.92	-89.38	1,980.26	-505.70	880.03	784.53	95.50	9.215	
12,650.00	10,560.00	12,635.87	10,550.00	48.23	48.38	-89.38	2,030.26	-505.96	880.03	783.61	96.43	9.126	
12,700.00	10,560.00	12,685.87	10,550.00	48.69	48.84	-89.38	2,080.26	-506.22	880.03	782.68	97.36	9.039	
12,750.00	10,560.00	12,735.87	10,550.00	49.17	49.32	-89.38	2,130.26	-506.48	880.03	781.72	98.31	8.952	
12,800.00	10,560.00	12,785.87	10,550.00	49.65	49.80	-89.38	2,180.26	-506.74	880.03	780.77	99.27	8.865	
12,850.00	10,560.00	12,835.87	10,550.00	50.14	50.28	-89.38	2,230.26	-507.00	880.03	779.79	100.24	8.779	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit Plan 1

Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
12,900.00	10,560.00	12,885.87	10,550.00	50.62	50.77	-89.38	2,280.26	-507.26	880.03	778.81	101.22	8.694	
12,950.00	10,560.00	12,935.87	10,550.00	51.12	51.27	-89.38	2,330.25	-507.52	880.04	777.82	102.22	8.609	
13,000.00	10,560.00	12,985.87	10,550.00	51.63	51.77	-89.38	2,380.25	-507.78	880.04	776.82	103.22	8.526	
13,050.00	10,560.00	13,035.87	10,550.00	52.14	52.28	-89.38	2,430.25	-508.03	880.04	775.80	104.24	8.442	
13,100.00	10,560.00	13,085.87	10,550.00	52.65	52.79	-89.38	2,480.25	-508.29	880.04	774.77	105.26	8.360	
13,150.00	10,560.00	13,135.87	10,550.00	53.17	53.31	-89.38	2,530.25	-508.55	880.04	773.73	106.30	8.279	
13,200.00	10,560.00	13,185.87	10,550.00	53.69	53.83	-89.38	2,580.25	-508.81	880.04	772.69	107.35	8.198	
13,250.00	10,560.00	13,235.87	10,550.00	54.22	54.36	-89.38	2,630.25	-509.07	880.04	771.63	108.40	8.118	
13,300.00	10,560.00	13,285.87	10,550.00	54.75	54.89	-89.38	2,680.25	-509.33	880.04	770.57	109.47	8.039	
13,350.00	10,560.00	13,335.87	10,550.00	55.29	55.43	-89.38	2,730.25	-509.59	880.04	769.49	110.54	7.961	
13,400.00	10,560.00	13,385.87	10,550.00	55.83	55.97	-89.38	2,780.25	-509.85	880.04	768.41	111.62	7.884	
13,450.00	10,560.00	13,435.87	10,550.00	56.38	56.51	-89.38	2,830.25	-510.11	880.04	767.32	112.72	7.808	
13,500.00	10,560.00	13,485.87	10,550.00	56.92	57.06	-89.38	2,880.25	-510.37	880.04	766.22	113.81	7.732	
13,550.00	10,560.00	13,535.87	10,550.00	57.48	57.61	-89.38	2,930.25	-510.63	880.04	765.11	114.92	7.658	
13,600.00	10,560.00	13,585.87	10,550.00	58.04	58.17	-89.38	2,980.25	-510.89	880.04	764.00	116.03	7.584	
13,650.00	10,560.00	13,635.87	10,550.00	58.60	58.73	-89.38	3,030.25	-511.14	880.04	762.88	117.16	7.511	
13,700.00	10,560.00	13,685.87	10,550.00	59.16	59.29	-89.38	3,080.24	-511.40	880.04	761.75	118.29	7.440	
13,750.00	10,560.00	13,735.87	10,550.00	59.73	59.86	-89.38	3,130.24	-511.66	880.04	760.61	119.43	7.369	
13,800.00	10,560.00	13,785.87	10,550.00	60.30	60.43	-89.38	3,180.24	-511.92	880.04	759.47	120.57	7.299	
13,850.00	10,560.00	13,835.87	10,550.00	60.88	61.01	-89.38	3,230.24	-512.18	880.04	758.32	121.72	7.230	
13,900.00	10,560.00	13,885.87	10,550.00	61.46	61.58	-89.38	3,280.24	-512.44	880.04	757.16	122.87	7.162	
13,950.00	10,560.00	13,935.87	10,550.00	62.04	62.16	-89.38	3,330.24	-512.70	880.04	756.00	124.04	7.095	
14,000.00	10,560.00	13,985.87	10,550.00	62.62	62.75	-89.38	3,380.24	-512.96	880.04	754.83	125.21	7.029	
14,050.00	10,560.00	14,035.87	10,550.00	63.21	63.33	-89.38	3,430.24	-513.22	880.04	753.66	126.38	6.963	
14,100.00	10,560.00	14,085.87	10,550.00	63.80	63.92	-89.38	3,480.24	-513.48	880.04	752.48	127.56	6.899	
14,150.00	10,560.00	14,135.87	10,550.00	64.39	64.52	-89.38	3,530.24	-513.74	880.04	751.29	128.75	6.835	
14,200.00	10,560.00	14,185.87	10,550.00	64.99	65.11	-89.38	3,580.24	-514.00	880.04	750.10	129.94	6.773	
14,250.00	10,560.00	14,235.87	10,550.00	65.59	65.71	-89.38	3,630.24	-514.25	880.04	748.90	131.14	6.711	
14,300.00	10,560.00	14,285.87	10,550.00	66.19	66.31	-89.38	3,680.24	-514.51	880.04	747.70	132.34	6.650	
14,350.00	10,560.00	14,335.87	10,550.00	66.79	66.91	-89.38	3,730.24	-514.77	880.04	746.49	133.55	6.590	
14,400.00	10,560.00	14,385.87	10,550.00	67.40	67.52	-89.38	3,780.24	-515.03	880.04	745.28	134.76	6.530	
14,450.00	10,560.00	14,435.87	10,550.00	68.01	68.13	-89.38	3,830.23	-515.29	880.04	744.06	135.98	6.472	
14,500.00	10,560.00	14,485.87	10,550.00	68.62	68.74	-89.38	3,880.23	-515.55	880.04	742.84	137.20	6.414	
14,550.00	10,560.00	14,535.87	10,550.00	69.23	69.35	-89.38	3,930.23	-515.81	880.04	741.61	138.43	6.357	
14,600.00	10,560.00	14,585.87	10,550.00	69.85	69.96	-89.38	3,980.23	-516.07	880.04	740.38	139.66	6.301	
14,650.00	10,560.00	14,635.87	10,550.00	70.47	70.58	-89.38	4,030.23	-516.33	880.04	739.14	140.90	6.246	
14,700.00	10,560.00	14,685.87	10,550.00	71.09	71.20	-89.38	4,080.23	-516.59	880.04	737.91	142.13	6.192	
14,750.00	10,560.00	14,735.87	10,550.00	71.71	71.82	-89.38	4,130.23	-516.85	880.04	736.66	143.38	6.138	
14,800.00	10,560.00	14,785.87	10,550.00	72.33	72.44	-89.38	4,180.23	-517.11	880.04	735.42	144.63	6.085	
14,850.00	10,560.00	14,835.87	10,550.00	72.96	73.07	-89.38	4,230.23	-517.36	880.04	734.16	145.88	6.033	
14,900.00	10,560.00	14,885.87	10,550.00	73.58	73.69	-89.38	4,280.23	-517.62	880.04	732.91	147.13	5.981	
14,950.00	10,560.00	14,935.87	10,550.00	74.21	74.32	-89.38	4,330.23	-517.88	880.04	731.65	148.39	5.931	
15,000.00	10,560.00	14,985.87	10,550.00	74.84	74.95	-89.38	4,380.23	-518.14	880.04	730.39	149.65	5.881	
15,050.00	10,560.00	15,035.87	10,550.00	75.48	75.59	-89.38	4,430.23	-518.40	880.04	729.12	150.92	5.831	
15,100.00	10,560.00	15,085.87	10,550.00	76.11	76.22	-89.38	4,480.23	-518.66	880.04	727.85	152.19	5.783	
15,150.00	10,560.00	15,135.87	10,550.00	76.75	76.85	-89.38	4,530.23	-518.92	880.04	726.58	153.46	5.735	
15,200.00	10,560.00	15,185.87	10,550.00	77.39	77.49	-89.38	4,580.22	-519.18	880.04	725.31	154.74	5.687	
15,250.00	10,560.00	15,235.87	10,550.00	78.03	78.13	-89.38	4,630.22	-519.44	880.04	724.03	156.02	5.641	
15,300.00	10,560.00	15,285.87	10,550.00	78.67	78.77	-89.38	4,680.22	-519.70	880.04	722.74	157.30	5.595	
15,350.00	10,560.00	15,335.87	10,550.00	79.31	79.41	-89.38	4,730.22	-519.96	880.04	721.46	158.58	5.549	
15,400.00	10,560.00	15,385.87	10,550.00	79.95	80.06	-89.38	4,780.22	-520.22	880.04	720.17	159.87	5.505	
15,450.00	10,560.00	15,435.87	10,550.00	80.60	80.70	-89.38	4,830.22	-520.47	880.04	718.88	161.16	5.461	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit Plan 1 — Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM — Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
15,500.00	10,560.00	15,485.87	10,550.00	81.25	81.35	-89.38	4,880.22	-520.73	880.04	717.59	162.46	5.417	
15,550.00	10,560.00	15,535.87	10,550.00	81.89	81.99	-89.38	4,930.22	-520.99	880.04	716.29	163.75	5.374	
15,600.00	10,560.00	15,585.87	10,550.00	82.54	82.64	-89.38	4,980.22	-521.25	880.04	714.99	165.05	5.332	
15,650.00	10,560.00	15,635.87	10,550.00	83.20	83.29	-89.38	5,030.22	-521.51	880.04	713.69	166.36	5.290	
15,700.00	10,560.00	15,685.87	10,550.00	83.85	83.95	-89.38	5,080.22	-521.77	880.04	712.39	167.66	5.249	
15,750.00	10,560.00	15,735.87	10,550.00	84.50	84.60	-89.38	5,130.22	-522.03	880.04	711.08	168.97	5.208	
15,800.00	10,560.00	15,785.87	10,550.00	85.15	85.25	-89.38	5,180.22	-522.29	880.04	709.77	170.27	5.168	
15,850.00	10,560.00	15,835.87	10,550.00	85.81	85.91	-89.38	5,230.22	-522.55	880.04	708.46	171.59	5.129	
15,900.00	10,560.00	15,885.87	10,550.00	86.47	86.56	-89.38	5,280.22	-522.81	880.04	707.14	172.90	5.090	
15,950.00	10,560.00	15,935.87	10,550.00	87.13	87.22	-89.38	5,330.21	-523.07	880.04	705.83	174.22	5.051	
16,000.00	10,560.00	15,985.87	10,550.00	87.78	87.88	-89.38	5,380.21	-523.33	880.05	704.51	175.54	5.013	
16,050.00	10,560.00	16,035.87	10,550.00	88.45	88.54	-89.38	5,430.21	-523.58	880.05	703.19	176.86	4.976	Alert
16,100.00	10,560.00	16,085.87	10,550.00	89.11	89.20	-89.38	5,480.21	-523.84	880.05	701.87	178.18	4.939	Alert
16,150.00	10,560.00	16,135.87	10,550.00	89.77	89.86	-89.38	5,530.21	-524.10	880.05	700.54	179.50	4.903	Alert
16,200.00	10,560.00	16,185.87	10,550.00	90.43	90.52	-89.38	5,580.21	-524.36	880.05	699.22	180.83	4.867	Alert
16,250.00	10,560.00	16,235.87	10,550.00	91.10	91.19	-89.38	5,630.21	-524.62	880.05	697.89	182.16	4.831	Alert
16,300.00	10,560.00	16,285.87	10,550.00	91.76	91.85	-89.38	5,680.21	-524.88	880.05	696.56	183.49	4.796	Alert
16,350.00	10,560.00	16,335.87	10,550.00	92.43	92.52	-89.38	5,730.21	-525.14	880.05	695.22	184.82	4.762	Alert
16,400.00	10,560.00	16,385.87	10,550.00	93.10	93.19	-89.38	5,780.21	-525.40	880.05	693.89	186.16	4.727	Alert
16,450.00	10,560.00	16,435.87	10,550.00	93.76	93.85	-89.38	5,830.21	-525.66	880.05	692.55	187.49	4.694	Alert
16,500.00	10,560.00	16,485.87	10,550.00	94.43	94.52	-89.38	5,880.21	-525.92	880.05	691.22	188.83	4.660	Alert
16,550.00	10,560.00	16,535.87	10,550.00	95.10	95.19	-89.38	5,930.21	-526.18	880.05	689.87	190.17	4.628	Alert
16,600.00	10,560.00	16,585.87	10,550.00	95.77	95.86	-89.38	5,980.21	-526.44	880.05	688.53	191.51	4.595	Alert
16,650.00	10,560.00	16,635.87	10,550.00	96.44	96.53	-89.38	6,030.21	-526.69	880.05	687.19	192.86	4.563	Alert
16,700.00	10,560.00	16,685.87	10,550.00	97.12	97.20	-89.38	6,080.20	-526.95	880.05	685.85	194.20	4.532	Alert
16,750.00	10,560.00	16,735.87	10,550.00	97.79	97.88	-89.38	6,130.20	-527.21	880.05	684.50	195.55	4.500	Alert
16,800.00	10,560.00	16,785.87	10,550.00	98.46	98.55	-89.38	6,180.20	-527.47	880.05	683.15	196.90	4.470	Alert
16,850.00	10,560.00	16,835.87	10,550.00	99.14	99.22	-89.38	6,230.20	-527.73	880.05	681.80	198.25	4.439	Alert
16,900.00	10,560.00	16,885.87	10,550.00	99.81	99.90	-89.38	6,280.20	-527.99	880.05	680.45	199.60	4.409	Alert
16,950.00	10,560.00	16,935.87	10,550.00	100.49	100.58	-89.38	6,330.20	-528.25	880.05	679.10	200.95	4.379	Alert
17,000.00	10,560.00	16,985.87	10,550.00	101.17	101.25	-89.38	6,380.20	-528.51	880.05	677.75	202.30	4.350	Alert
17,050.00	10,560.00	17,035.87	10,550.00	101.85	101.93	-89.38	6,430.20	-528.77	880.05	676.39	203.66	4.321	Alert
17,100.00	10,560.00	17,085.87	10,550.00	102.52	102.61	-89.38	6,480.20	-529.03	880.05	675.03	205.01	4.293	Alert
17,150.00	10,560.00	17,135.87	10,550.00	103.20	103.29	-89.38	6,530.20	-529.29	880.05	673.68	206.37	4.264	Alert
17,200.00	10,560.00	17,185.87	10,550.00	103.88	103.96	-89.38	6,580.20	-529.54	880.05	672.32	207.73	4.236	Alert
17,250.00	10,560.00	17,235.87	10,550.00	104.56	104.64	-89.38	6,630.20	-529.80	880.05	670.96	209.09	4.209	Alert
17,300.00	10,560.00	17,285.87	10,550.00	105.24	105.32	-89.38	6,680.20	-530.06	880.05	669.59	210.46	4.182	Alert
17,350.00	10,560.00	17,335.87	10,550.00	105.93	106.01	-89.38	6,730.20	-530.32	880.05	668.23	211.82	4.155	Alert
17,400.00	10,560.00	17,385.87	10,550.00	106.61	106.69	-89.38	6,780.20	-530.58	880.05	666.87	213.18	4.128	Alert
17,450.00	10,560.00	17,435.87	10,550.00	107.29	107.37	-89.38	6,830.19	-530.84	880.05	665.50	214.55	4.102	Alert
17,500.00	10,560.00	17,485.87	10,550.00	107.97	108.05	-89.38	6,880.19	-531.10	880.05	664.13	215.92	4.076	Alert
17,550.00	10,560.00	17,535.87	10,550.00	108.66	108.74	-89.38	6,930.19	-531.36	880.05	662.77	217.28	4.050	Alert
17,600.00	10,560.00	17,585.87	10,550.00	109.34	109.42	-89.38	6,980.19	-531.62	880.05	661.40	218.65	4.025	Alert
17,650.00	10,560.00	17,635.87	10,550.00	110.03	110.11	-89.38	7,030.19	-531.88	880.05	660.03	220.02	4.000	Alert
17,700.00	10,560.00	17,685.87	10,550.00	110.71	110.79	-89.38	7,080.19	-532.14	880.05	658.66	221.40	3.975	Alert
17,750.00	10,560.00	17,735.87	10,550.00	111.40	111.48	-89.38	7,130.19	-532.40	880.05	657.28	222.77	3.951	Alert
17,800.00	10,560.00	17,785.87	10,550.00	112.09	112.16	-89.38	7,180.19	-532.65	880.05	655.91	224.14	3.926	Alert
17,850.00	10,560.00	17,835.87	10,550.00	112.77	112.85	-89.38	7,230.19	-532.91	880.05	654.53	225.52	3.902	Alert
17,900.00	10,560.00	17,885.87	10,550.00	113.46	113.54	-89.38	7,280.19	-533.17	880.05	653.16	226.89	3.879	Alert
17,950.00	10,560.00	17,935.87	10,550.00	114.15	114.23	-89.38	7,330.19	-533.43	880.05	651.78	228.27	3.855	Alert
18,000.00	10,560.00	17,985.87	10,550.00	114.84	114.91	-89.38	7,380.19	-533.69	880.05	650.41	229.65	3.832	Alert
18,050.00	10,560.00	18,035.87	10,550.00	115.53	115.60	-89.38	7,430.19	-533.95	880.05	649.03	231.03	3.809	Alert

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit Plan 1 — Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM — Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
18,100.00	10,560.00	18,085.87	10,550.00	116.22	116.29	-89.38	7,480.19	-534.21	880.05	647.65	232.40	3.787	Alert
18,150.00	10,560.00	18,135.87	10,550.00	116.91	116.98	-89.38	7,530.19	-534.47	880.05	646.27	233.79	3.764	Alert
18,200.00	10,560.00	18,185.87	10,550.00	117.60	117.67	-89.38	7,580.18	-534.73	880.05	644.89	235.17	3.742	Alert
18,250.00	10,560.00	18,235.87	10,550.00	118.29	118.36	-89.38	7,630.18	-534.99	880.05	643.50	236.55	3.720	Alert
18,300.00	10,560.00	18,285.87	10,550.00	118.98	119.05	-89.38	7,680.18	-535.25	880.05	642.12	237.93	3.699	Alert
18,350.00	10,560.00	18,335.87	10,550.00	119.67	119.75	-89.38	7,730.18	-535.51	880.05	640.74	239.32	3.677	Alert
18,400.00	10,560.00	18,385.87	10,550.00	120.37	120.44	-89.38	7,780.18	-535.76	880.05	639.35	240.70	3.656	Alert
18,450.00	10,560.00	18,435.87	10,550.00	121.06	121.13	-89.38	7,830.18	-536.02	880.05	637.97	242.09	3.635	Alert
18,500.00	10,560.00	18,485.87	10,550.00	121.75	121.82	-89.38	7,880.18	-536.28	880.05	636.58	243.47	3.615	Alert
18,550.00	10,560.00	18,535.87	10,550.00	122.45	122.52	-89.38	7,930.18	-536.54	880.05	635.19	244.86	3.594	Alert
18,600.00	10,560.00	18,585.87	10,550.00	123.14	123.21	-89.38	7,980.18	-536.80	880.05	633.80	246.25	3.574	Alert
18,650.00	10,560.00	18,635.87	10,550.00	123.83	123.90	-89.38	8,030.18	-537.06	880.05	632.42	247.64	3.554	Alert
18,700.00	10,560.00	18,685.87	10,550.00	124.53	124.60	-89.38	8,080.18	-537.32	880.05	631.03	249.03	3.534	Alert
18,750.00	10,560.00	18,735.87	10,550.00	125.22	125.29	-89.38	8,130.18	-537.58	880.05	629.64	250.42	3.514	Alert
18,800.00	10,560.00	18,785.87	10,550.00	125.92	125.99	-89.38	8,180.18	-537.84	880.05	628.24	251.81	3.495	Alert
18,850.00	10,560.00	18,835.87	10,550.00	126.62	126.69	-89.38	8,230.18	-538.10	880.05	626.85	253.20	3.476	Alert
18,900.00	10,560.00	18,885.87	10,550.00	127.31	127.38	-89.38	8,280.17	-538.36	880.05	625.46	254.59	3.457	Alert
18,950.00	10,560.00	18,935.87	10,550.00	128.01	128.08	-89.38	8,330.17	-538.62	880.05	624.07	255.99	3.438	Alert
19,000.00	10,560.00	18,985.87	10,550.00	128.71	128.77	-89.38	8,380.17	-538.87	880.05	622.67	257.38	3.419	Alert
19,050.00	10,560.00	19,035.87	10,550.00	129.40	129.47	-89.38	8,430.17	-539.13	880.06	621.28	258.78	3.401	Alert
19,100.00	10,560.00	19,085.87	10,550.00	130.10	130.17	-89.38	8,480.17	-539.39	880.06	619.88	260.17	3.383	Alert
19,150.00	10,560.00	19,135.87	10,550.00	130.80	130.87	-89.38	8,530.17	-539.65	880.06	618.49	261.57	3.365	Alert
19,200.00	10,560.00	19,185.87	10,550.00	131.50	131.56	-89.38	8,580.17	-539.91	880.06	617.09	262.97	3.347	Alert
19,250.00	10,560.00	19,235.87	10,550.00	132.20	132.26	-89.38	8,630.17	-540.17	880.06	615.69	264.36	3.329	Alert
19,300.00	10,560.00	19,285.87	10,550.00	132.89	132.96	-89.38	8,680.17	-540.43	880.06	614.30	265.76	3.311	Alert
19,350.00	10,560.00	19,335.87	10,550.00	133.59	133.66	-89.38	8,730.17	-540.69	880.06	612.90	267.16	3.294	Alert
19,400.00	10,560.00	19,385.87	10,550.00	134.29	134.36	-89.38	8,780.17	-540.95	880.06	611.50	268.56	3.277	Alert
19,450.00	10,560.00	19,435.87	10,550.00	134.99	135.06	-89.38	8,830.17	-541.21	880.06	610.10	269.96	3.260	Alert
19,500.00	10,560.00	19,485.87	10,550.00	135.69	135.76	-89.38	8,880.17	-541.47	880.06	608.70	271.36	3.243	Alert
19,550.00	10,560.00	19,535.87	10,550.00	136.39	136.46	-89.38	8,930.17	-541.73	880.06	607.30	272.76	3.226	Alert
19,600.00	10,560.00	19,585.87	10,550.00	137.10	137.16	-89.38	8,980.17	-541.98	880.06	605.89	274.16	3.210	Alert
19,650.00	10,560.00	19,635.87	10,550.00	137.80	137.86	-89.38	9,030.16	-542.24	880.06	604.49	275.56	3.194	Alert
19,700.00	10,560.00	19,685.87	10,550.00	138.50	138.56	-89.38	9,080.16	-542.50	880.06	603.09	276.97	3.177	Alert
19,750.00	10,560.00	19,735.87	10,550.00	139.20	139.26	-89.38	9,130.16	-542.76	880.06	601.69	278.37	3.161	Alert
19,800.00	10,560.00	19,785.87	10,550.00	139.90	139.97	-89.38	9,180.16	-543.02	880.06	600.28	279.77	3.146	Alert
19,850.00	10,560.00	19,835.87	10,550.00	140.60	140.67	-89.38	9,230.16	-543.28	880.06	598.88	281.18	3.130	Alert
19,900.00	10,560.00	19,885.87	10,550.00	141.31	141.37	-89.38	9,280.16	-543.54	880.06	597.47	282.58	3.114	Alert
19,950.00	10,560.00	19,935.87	10,550.00	142.01	142.07	-89.38	9,330.16	-543.80	880.06	596.07	283.99	3.099	Alert
20,000.00	10,560.00	19,985.87	10,550.00	142.71	142.78	-89.38	9,380.16	-544.06	880.06	594.66	285.40	3.084	Alert
20,050.00	10,560.00	20,035.87	10,550.00	143.41	143.48	-89.38	9,430.16	-544.32	880.06	593.26	286.80	3.069	Alert
20,100.00	10,560.00	20,085.87	10,550.00	144.12	144.18	-89.38	9,480.16	-544.58	880.06	591.85	288.21	3.054	Alert
20,150.00	10,560.00	20,135.87	10,550.00	144.82	144.88	-89.38	9,530.16	-544.84	880.06	590.44	289.62	3.039	Alert
20,200.00	10,560.00	20,185.87	10,550.00	145.53	145.59	-89.38	9,580.16	-545.09	880.06	589.03	291.02	3.024	Alert
20,250.00	10,560.00	20,235.87	10,550.00	146.23	146.29	-89.38	9,630.16	-545.35	880.06	587.63	292.43	3.009	Alert
20,300.00	10,560.00	20,285.87	10,550.00	146.93	147.00	-89.38	9,680.16	-545.61	880.06	586.22	293.84	2.995	Alert
20,350.00	10,560.00	20,335.87	10,550.00	147.64	147.70	-89.38	9,730.16	-545.87	880.06	584.81	295.25	2.981	Alert
20,400.00	10,560.00	20,385.87	10,550.00	148.34	148.41	-89.38	9,780.15	-546.13	880.06	583.40	296.66	2.967	Alert
20,450.00	10,560.00	20,435.87	10,550.00	149.05	149.11	-89.38	9,830.15	-546.39	880.06	581.99	298.07	2.953	Alert
20,500.00	10,560.00	20,485.87	10,550.00	149.75	149.82	-89.38	9,880.15	-546.65	880.06	580.58	299.48	2.939	Alert
20,550.00	10,560.00	20,535.87	10,550.00	150.46	150.52	-89.38	9,930.15	-546.91	880.06	579.17	300.89	2.925	Alert
20,600.00	10,560.00	20,585.87	10,550.00	151.17	151.23	-89.38	9,980.15	-547.17	880.06	577.76	302.31	2.911	Alert
20,650.00	10,560.00	20,635.87	10,550.00	151.87	151.93	-89.38	10,030.15	-547.43	880.06	576.34	303.72	2.898	Alert

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 233H - Wellbore #1 - Permit Plan 1

Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
20,700.00	10,560.00	20,685.87	10,550.00	152.58	152.64	-89.38	10,080.15	-547.69	880.06	574.93	305.13	2.884	Alert
20,750.00	10,560.00	20,735.87	10,550.00	153.28	153.34	-89.38	10,130.15	-547.95	880.06	573.52	306.54	2.871	Alert
20,800.00	10,560.00	20,785.87	10,550.00	153.99	154.05	-89.38	10,180.15	-548.20	880.06	572.11	307.96	2.858	Alert
20,823.96	10,560.00	20,809.83	10,550.00	154.33	154.39	-89.38	10,204.10	-548.33	880.06	571.43	308.63	2.851	Alert

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit Plan 1

Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
0.00	0.00	0.30	0.30	0.50	0.50	89.68	0.17	30.02	30.02				
50.00	50.00	50.30	50.30	0.50	0.50	89.68	0.17	30.02	30.02	29.01	1.01	29.822	
100.00	100.00	100.30	100.30	0.52	0.52	89.68	0.17	30.02	30.02	28.98	1.04	28.980	
150.00	150.00	150.30	150.30	0.59	0.59	89.68	0.17	30.02	30.02	28.84	1.18	25.416	
200.00	200.00	200.30	200.30	0.70	0.70	89.68	0.17	30.02	30.02	28.61	1.40	21.365	
250.00	250.00	250.30	250.30	0.84	0.84	89.68	0.17	30.02	30.02	28.34	1.68	17.907	
300.00	300.00	300.30	300.30	0.99	0.99	89.68	0.17	30.02	30.02	28.04	1.98	15.194	
350.00	350.00	350.30	350.30	1.15	1.15	89.68	0.17	30.02	30.02	27.73	2.29	13.097	
400.00	400.00	400.30	400.30	1.31	1.31	89.68	0.17	30.02	30.02	27.40	2.62	11.461	
450.00	450.00	450.30	450.30	1.48	1.48	89.68	0.17	30.02	30.02	27.06	2.95	10.163	
500.00	500.00	500.30	500.30	1.65	1.65	89.68	0.17	30.02	30.02	26.72	3.29	9.115	
550.00	550.00	550.30	550.30	1.82	1.82	89.68	0.17	30.02	30.02	26.38	3.64	8.255	
600.00	600.00	600.30	600.30	1.99	1.99	89.68	0.17	30.02	30.02	26.04	3.98	7.538	
650.00	650.00	650.30	650.30	2.16	2.17	89.68	0.17	30.02	30.02	25.69	4.33	6.932	
700.00	700.00	700.30	700.30	2.34	2.34	89.68	0.17	30.02	30.02	25.34	4.68	6.414	
750.00	750.00	750.30	750.30	2.51	2.52	89.68	0.17	30.02	30.02	24.99	5.03	5.967	
800.00	800.00	800.30	800.30	2.69	2.69	89.68	0.17	30.02	30.02	24.64	5.38	5.577	
850.00	850.00	850.30	850.30	2.87	2.87	89.68	0.17	30.02	30.02	24.28	5.73	5.234	
900.00	900.00	900.30	900.30	3.04	3.04	89.68	0.17	30.02	30.02	23.93	6.09	4.930	Alert
950.00	950.00	950.30	950.30	3.22	3.22	89.68	0.17	30.02	30.02	23.58	6.44	4.660	Alert
1,000.00	1,000.00	1,000.30	1,000.30	3.40	3.40	89.68	0.17	30.02	30.02	23.22	6.80	4.417	Alert
1,050.00	1,050.00	1,050.30	1,050.30	3.58	3.58	89.68	0.17	30.02	30.02	22.87	7.15	4.198	Alert
1,100.00	1,100.00	1,100.30	1,100.30	3.75	3.75	89.68	0.17	30.02	30.02	22.51	7.51	3.999	Alert
1,150.00	1,150.00	1,150.30	1,150.30	3.93	3.93	89.68	0.17	30.02	30.02	22.16	7.86	3.818	Alert
1,200.00	1,200.00	1,200.30	1,200.30	4.11	4.11	89.68	0.17	30.02	30.02	21.80	8.22	3.653	Alert
1,250.00	1,250.00	1,250.30	1,250.30	4.29	4.29	89.68	0.17	30.02	30.02	21.44	8.57	3.501	Alert
1,300.00	1,300.00	1,300.30	1,300.30	4.46	4.47	89.68	0.17	30.02	30.02	21.09	8.93	3.362	Alert
1,350.00	1,350.00	1,350.30	1,350.30	4.64	4.64	89.68	0.17	30.02	30.02	20.73	9.29	3.233	Alert
1,400.00	1,400.00	1,400.30	1,400.30	4.82	4.82	89.68	0.17	30.02	30.02	20.38	9.64	3.113	Alert
1,450.00	1,450.00	1,450.30	1,450.30	5.00	5.00	89.68	0.17	30.02	30.02	20.02	10.00	3.002	Alert
1,500.00	1,500.00	1,500.30	1,500.30	5.18	5.18	89.68	0.17	30.02	30.02	19.66	10.36	2.899	Alert
1,550.00	1,550.00	1,550.30	1,550.30	5.36	5.36	89.68	0.17	30.02	30.02	19.31	10.71	2.802	Alert
1,600.00	1,600.00	1,600.30	1,600.30	5.53	5.54	89.68	0.17	30.02	30.02	18.95	11.07	2.712	Alert
1,650.00	1,650.00	1,650.30	1,650.30	5.71	5.71	89.68	0.17	30.02	30.02	18.59	11.43	2.627	Alert
1,700.00	1,700.00	1,700.30	1,700.30	5.89	5.89	89.68	0.17	30.02	30.02	18.23	11.78	2.547	Alert
1,750.00	1,750.00	1,750.30	1,750.30	6.07	6.07	89.68	0.17	30.02	30.02	17.88	12.14	2.472	Minor Risk
1,800.00	1,800.00	1,800.30	1,800.30	6.25	6.25	89.68	0.17	30.02	30.02	17.52	12.50	2.402	Minor Risk
1,850.00	1,850.00	1,850.30	1,850.30	6.43	6.43	89.68	0.17	30.02	30.02	17.16	12.86	2.335	Minor Risk
1,900.00	1,900.00	1,900.30	1,900.30	6.61	6.61	89.68	0.17	30.02	30.02	16.80	13.21	2.272	Minor Risk
1,950.00	1,950.00	1,950.30	1,950.30	6.78	6.79	89.68	0.17	30.02	30.02	16.45	13.57	2.212	Minor Risk
2,000.00	2,000.00	2,000.30	2,000.30	6.96	6.96	89.68	0.17	30.02	30.02	16.09	13.93	2.155	Minor Risk
2,050.00	2,050.00	2,050.30	2,050.30	7.14	7.14	89.68	0.17	30.02	30.02	15.73	14.29	2.101	Minor Risk
2,100.00	2,100.00	2,100.30	2,100.30	7.32	7.32	89.68	0.17	30.02	30.02	15.37	14.64	2.050	Minor Risk
2,150.00	2,150.00	2,150.30	2,150.30	7.50	7.50	89.68	0.17	30.02	30.02	15.02	15.00	2.001	Minor Risk
2,200.00	2,200.00	2,200.30	2,200.30	7.68	7.68	89.68	0.17	30.02	30.02	14.66	15.36	1.954	Minor Risk
2,250.00	2,250.00	2,250.30	2,250.30	7.86	7.86	89.68	0.17	30.02	30.02	14.30	15.72	1.910	Minor Risk
2,300.00	2,300.00	2,300.30	2,300.30	8.04	8.04	89.68	0.17	30.02	30.02	13.94	16.07	1.867	Minor Risk
2,350.00	2,350.00	2,350.30	2,350.30	8.22	8.22	89.68	0.17	30.02	30.02	13.59	16.43	1.827	Minor Risk
2,400.00	2,400.00	2,400.30	2,400.30	8.39	8.40	89.68	0.17	30.02	30.02	13.23	16.79	1.788	Minor Risk
2,450.00	2,450.00	2,450.30	2,450.30	8.57	8.57	89.68	0.17	30.02	30.02	12.87	17.15	1.751	Minor Risk
2,500.00	2,500.00	2,500.30	2,500.30	8.75	8.75	89.68	0.17	30.02	30.02	12.51	17.51	1.715	Minor Risk, CC
2,550.00	2,550.00	2,550.04	2,550.04	8.93	8.93	89.77	0.12	30.23	30.23	12.38	17.86	1.693	Minor Risk, ES, SF

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit Plan 1 — **Offset Site Error:** 0.00 ft

Survey Program: 0-MWD+HDGM — **Offset Well Error:** 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
2,600.00	2,600.00	2,599.78	2,599.78	9.11	9.10	90.06	-0.03	30.86	30.87	12.66	18.21	1.695	Minor Risk
2,650.00	2,650.00	2,649.50	2,649.49	9.29	9.27	90.50	-0.28	31.92	31.93	13.38	18.55	1.721	Minor Risk
2,700.00	2,700.00	2,699.20	2,699.16	9.47	9.43	91.07	-0.62	33.39	33.41	14.52	18.89	1.769	Minor Risk
2,750.00	2,750.00	2,748.88	2,748.80	9.65	9.60	91.74	-1.07	35.28	35.33	16.09	19.23	1.837	Minor Risk
2,800.00	2,800.00	2,798.51	2,798.37	9.83	9.77	92.46	-1.61	37.58	37.67	18.09	19.57	1.924	Minor Risk
2,850.00	2,850.00	2,848.10	2,847.88	10.00	9.94	93.20	-2.25	40.31	40.44	20.53	19.91	2.031	Minor Risk
2,900.00	2,900.00	2,897.63	2,897.31	10.18	10.11	93.94	-2.99	43.44	43.65	23.40	20.25	2.155	Minor Risk
2,950.00	2,950.00	2,947.11	2,946.66	10.36	10.28	94.66	-3.83	46.99	47.29	26.70	20.59	2.297	Minor Risk
3,000.00	3,000.00	2,996.52	2,995.90	10.54	10.45	95.34	-4.76	50.94	51.36	30.43	20.92	2.455	Minor Risk
3,050.00	3,050.00	3,045.85	3,045.03	10.72	10.62	95.97	-5.79	55.31	55.86	34.60	21.26	2.628	Alert
3,100.00	3,100.00	3,095.11	3,094.04	10.90	10.79	96.56	-6.91	60.07	60.79	39.21	21.59	2.816	Alert
3,150.00	3,150.00	3,144.28	3,142.92	11.08	10.97	97.10	-8.13	65.24	66.16	44.24	21.92	3.018	Alert
3,200.00	3,200.00	3,193.35	3,191.66	11.26	11.14	97.59	-9.44	70.80	71.95	49.70	22.25	3.234	Alert
3,250.00	3,250.00	3,242.32	3,240.24	11.44	11.31	98.04	-10.84	76.76	78.17	55.60	22.57	3.463	Alert
3,300.00	3,300.00	3,291.18	3,288.67	11.62	11.48	98.44	-12.33	83.10	84.82	61.92	22.90	3.704	Alert
3,350.00	3,350.00	3,339.92	3,336.92	11.80	11.66	98.81	-13.92	89.83	91.89	68.67	23.22	3.957	Alert
3,400.00	3,400.00	3,388.55	3,384.99	11.97	11.83	99.14	-15.59	96.95	99.38	75.84	23.54	4.221	Alert
3,450.00	3,450.00	3,437.04	3,432.87	12.15	12.01	99.44	-17.36	104.43	107.29	83.43	23.86	4.497	Alert
3,500.00	3,500.00	3,485.40	3,480.55	12.33	12.19	99.71	-19.21	112.29	115.62	91.45	24.18	4.782	Alert
3,550.00	3,550.00	3,534.28	3,528.69	12.51	12.37	99.95	-21.15	120.55	124.29	99.78	24.52	5.070	
3,600.00	3,600.00	3,583.52	3,577.17	12.69	12.55	100.17	-23.12	128.90	132.99	108.12	24.86	5.349	
3,650.00	3,650.00	3,632.75	3,625.65	12.87	12.73	100.36	-25.09	137.25	141.68	116.47	25.21	5.620	
3,700.00	3,700.00	3,681.99	3,674.14	13.05	12.92	100.53	-27.05	145.60	150.38	124.82	25.56	5.883	
3,750.00	3,750.00	3,731.22	3,722.62	13.23	13.11	100.67	-29.02	153.94	159.08	133.17	25.91	6.139	
3,800.00	3,800.00	3,780.46	3,771.10	13.41	13.29	100.81	-30.98	162.29	167.78	141.52	26.26	6.389	
3,850.00	3,850.00	3,829.69	3,819.59	13.59	13.48	100.93	-32.95	170.64	176.48	149.87	26.61	6.632	
3,900.00	3,900.00	3,878.93	3,868.07	13.77	13.67	101.04	-34.92	178.99	185.19	158.22	26.96	6.868	
3,950.00	3,950.00	3,928.17	3,916.55	13.94	13.86	101.14	-36.88	187.33	193.89	166.57	27.31	7.099	
4,000.00	4,000.00	3,977.40	3,965.04	14.12	14.05	101.23	-38.85	195.68	202.59	174.93	27.67	7.323	
4,050.00	4,050.00	4,026.68	4,013.56	14.30	14.24	-24.63	-40.81	204.03	211.05	183.04	28.01	7.535	
4,100.00	4,099.99	4,076.04	4,062.17	14.47	14.43	-24.60	-42.79	212.40	219.02	190.67	28.36	7.724	
4,150.00	4,149.97	4,125.48	4,110.85	14.63	14.62	-24.63	-44.76	220.78	226.50	197.81	28.70	7.893	
4,200.00	4,199.94	4,174.98	4,159.60	14.80	14.82	-24.72	-46.74	229.18	233.49	204.46	29.04	8.042	
4,250.00	4,249.88	4,224.55	4,208.41	14.96	15.01	-24.85	-48.72	237.58	239.99	210.62	29.38	8.170	
4,300.00	4,299.79	4,274.18	4,257.28	15.13	15.21	-25.03	-50.70	246.00	246.01	216.29	29.72	8.278	
4,350.00	4,349.66	4,323.86	4,306.20	15.30	15.40	-25.26	-52.68	254.42	251.53	221.47	30.06	8.367	
4,400.00	4,399.49	4,373.59	4,355.17	15.47	15.60	-25.53	-54.67	262.85	256.58	226.17	30.41	8.438	
4,450.00	4,449.29	4,423.35	4,404.17	15.63	15.80	-25.85	-56.65	271.28	261.26	230.51	30.75	8.496	
4,500.00	4,499.09	4,473.11	4,453.17	15.80	15.99	-26.17	-58.64	279.72	265.93	234.83	31.10	8.551	
4,550.00	4,548.88	4,522.87	4,502.17	15.97	16.19	-26.48	-60.63	288.16	270.60	239.16	31.45	8.606	
4,600.00	4,598.68	4,572.63	4,551.16	16.14	16.39	-26.78	-62.61	296.59	275.29	243.50	31.79	8.659	
4,650.00	4,648.47	4,622.39	4,600.16	16.31	16.59	-27.06	-64.60	305.03	279.98	247.84	32.14	8.711	
4,700.00	4,698.27	4,672.15	4,649.16	16.48	16.79	-27.34	-66.59	313.47	284.68	252.19	32.49	8.762	
4,750.00	4,748.06	4,721.91	4,698.16	16.65	16.99	-27.61	-68.57	321.90	289.38	256.54	32.84	8.812	
4,800.00	4,797.86	4,771.67	4,747.16	16.82	17.19	-27.87	-70.56	330.34	294.09	260.90	33.19	8.861	
4,850.00	4,847.65	4,821.43	4,796.16	16.99	17.39	-28.12	-72.55	338.77	298.81	265.27	33.54	8.909	
4,900.00	4,897.45	4,871.19	4,845.16	17.16	17.59	-28.36	-74.53	347.21	303.53	269.64	33.89	8.956	
4,950.00	4,947.25	4,920.95	4,894.16	17.34	17.80	-28.60	-76.52	355.65	308.26	274.02	34.24	9.002	
5,000.00	4,997.04	4,970.71	4,943.16	17.51	18.00	-28.83	-78.51	364.08	312.99	278.40	34.60	9.047	
5,050.00	5,046.84	5,020.47	4,992.16	17.68	18.20	-29.05	-80.50	372.52	317.73	282.78	34.95	9.091	
5,100.00	5,096.63	5,070.23	5,041.16	17.86	18.40	-29.26	-82.48	380.95	322.47	287.17	35.30	9.135	
5,150.00	5,146.43	5,119.99	5,090.16	18.03	18.61	-29.47	-84.47	389.39	327.22	291.56	35.66	9.177	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit Plan 1

Survey Program: 0-MWD+HDGM

Offset Site Error: 0.00 ft

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
5,200.00	5,196.22	5,169.75	5,139.16	18.20	18.81	-29.68	-86.46	397.83	331.97	295.96	36.01	9.219	
5,250.00	5,246.02	5,219.51	5,188.16	18.38	19.02	-29.87	-88.44	406.26	336.72	300.36	36.36	9.260	
5,300.00	5,295.81	5,269.27	5,237.16	18.55	19.22	-30.07	-90.43	414.70	341.48	304.76	36.72	9.300	
5,350.00	5,345.61	5,319.03	5,286.16	18.73	19.42	-30.25	-92.42	423.14	346.24	309.17	37.08	9.339	
5,400.00	5,395.41	5,368.79	5,335.16	18.90	19.63	-30.43	-94.40	431.57	351.01	313.58	37.43	9.377	
5,450.00	5,445.20	5,418.55	5,384.16	19.08	19.83	-30.61	-96.39	440.01	355.78	317.99	37.79	9.415	
5,500.00	5,495.00	5,468.31	5,433.16	19.25	20.04	-30.78	-98.38	448.44	360.55	322.40	38.14	9.452	
5,550.00	5,544.79	5,518.07	5,482.16	19.43	20.25	-30.95	-100.36	456.88	365.32	326.82	38.50	9.488	
5,600.00	5,594.59	5,567.83	5,531.16	19.61	20.45	-31.11	-102.35	465.32	370.10	331.24	38.86	9.524	
5,650.00	5,644.38	5,617.59	5,580.16	19.78	20.66	-31.27	-104.34	473.75	374.88	335.66	39.22	9.559	
5,700.00	5,694.18	5,667.35	5,629.16	19.96	20.86	-31.43	-106.32	482.19	379.67	340.09	39.58	9.593	
5,750.00	5,743.97	5,717.11	5,678.16	20.14	21.07	-31.58	-108.31	490.62	384.45	344.52	39.94	9.627	
5,800.00	5,793.77	5,766.87	5,727.16	20.31	21.28	-31.73	-110.30	499.06	389.24	348.95	40.29	9.660	
5,850.00	5,843.56	5,816.63	5,776.16	20.49	21.48	-31.87	-112.29	507.50	394.03	353.38	40.65	9.692	
5,900.00	5,893.36	5,866.39	5,825.15	20.67	21.69	-32.01	-114.27	515.93	398.83	357.81	41.01	9.724	
5,950.00	5,943.16	5,916.15	5,874.15	20.85	21.90	-32.15	-116.26	524.37	403.62	362.25	41.37	9.755	
6,000.00	5,992.95	5,965.92	5,923.15	21.03	22.11	-32.28	-118.25	532.81	408.42	366.69	41.73	9.786	
6,050.00	6,042.75	6,015.68	5,972.15	21.21	22.32	-32.41	-120.23	541.24	413.22	371.13	42.10	9.816	
6,100.00	6,092.54	6,065.44	6,021.15	21.38	22.52	-32.54	-122.22	549.68	418.03	375.57	42.46	9.846	
6,150.00	6,142.34	6,115.20	6,070.15	21.56	22.73	-32.67	-124.21	558.11	422.83	380.01	42.82	9.875	
6,200.00	6,192.13	6,164.96	6,119.15	21.74	22.94	-32.79	-126.19	566.55	427.64	384.46	43.18	9.904	
6,250.00	6,241.93	6,214.72	6,168.15	21.92	23.15	-32.91	-128.18	574.99	432.45	388.90	43.54	9.932	
6,300.00	6,291.72	6,264.48	6,217.15	22.10	23.36	-33.03	-130.17	583.42	437.26	393.35	43.90	9.959	
6,350.00	6,341.52	6,314.24	6,266.15	22.28	23.57	-33.14	-132.15	591.86	442.07	397.80	44.27	9.986	
6,400.00	6,391.32	6,364.00	6,315.15	22.46	23.77	-33.25	-134.14	600.30	446.88	402.25	44.63	10.013	
6,450.00	6,441.11	6,413.76	6,364.15	22.64	23.98	-33.36	-136.13	608.73	451.70	406.71	44.99	10.039	
6,500.00	6,490.91	6,463.52	6,413.15	22.82	24.19	-33.47	-138.11	617.17	456.52	411.16	45.36	10.065	
6,550.00	6,540.70	6,513.28	6,462.15	23.00	24.40	-33.57	-140.10	625.60	461.34	415.62	45.72	10.090	
6,600.00	6,590.50	6,563.04	6,511.15	23.18	24.61	-33.68	-142.09	634.04	466.16	420.07	46.08	10.115	
6,650.00	6,640.29	6,612.80	6,560.15	23.36	24.82	-33.78	-144.07	642.48	470.98	424.53	46.45	10.140	
6,700.00	6,690.09	6,662.56	6,609.15	23.54	25.03	-33.88	-146.06	650.91	475.80	428.99	46.81	10.164	
6,750.00	6,739.88	6,712.32	6,658.15	23.72	25.24	-33.97	-148.05	659.35	480.63	433.45	47.18	10.187	
6,800.00	6,789.68	6,762.08	6,707.15	23.90	25.45	-34.07	-150.04	667.78	485.45	437.91	47.54	10.211	
6,850.00	6,839.48	6,811.84	6,756.15	24.09	25.66	-34.16	-152.02	676.22	490.28	442.37	47.91	10.234	
6,900.00	6,889.27	6,861.60	6,805.15	24.27	25.87	-34.25	-154.01	684.66	495.11	446.83	48.27	10.256	
6,950.00	6,939.07	6,911.36	6,854.15	24.45	26.08	-34.34	-156.00	693.09	499.94	451.30	48.64	10.279	
7,000.00	6,988.86	6,961.12	6,903.15	24.63	26.29	-34.43	-157.98	701.53	504.77	455.76	49.00	10.300	
7,050.00	7,038.66	7,010.88	6,952.15	24.81	26.51	-34.51	-159.97	709.97	509.60	460.23	49.37	10.322	
7,100.00	7,088.45	7,060.64	7,001.15	24.99	26.72	-34.60	-161.96	718.40	514.43	464.70	49.74	10.343	
7,150.00	7,138.25	7,110.40	7,050.15	25.18	26.93	-34.68	-163.94	726.84	519.27	469.17	50.10	10.364	
7,200.00	7,188.04	7,160.16	7,099.14	25.36	27.14	-34.76	-165.93	735.27	524.10	473.63	50.47	10.385	
7,250.00	7,237.84	7,209.92	7,148.14	25.54	27.35	-34.84	-167.92	743.71	528.94	478.10	50.84	10.405	
7,300.00	7,287.64	7,259.68	7,197.14	25.72	27.56	-34.92	-169.90	752.15	533.78	482.57	51.20	10.425	
7,350.00	7,337.43	7,309.44	7,246.14	25.90	27.77	-35.00	-171.89	760.58	538.62	487.05	51.57	10.444	
7,400.00	7,387.23	7,359.20	7,295.14	26.09	27.98	-35.07	-173.88	769.02	543.45	491.52	51.94	10.464	
7,450.00	7,437.02	7,408.96	7,344.14	26.27	28.19	-35.15	-175.86	777.45	548.29	495.99	52.31	10.483	
7,500.00	7,486.82	7,458.72	7,393.14	26.45	28.41	-35.22	-177.85	785.89	553.14	500.46	52.67	10.501	
7,550.00	7,536.61	7,508.48	7,442.14	26.64	28.62	-35.29	-179.84	794.33	557.98	504.94	53.04	10.520	
7,600.00	7,586.41	7,558.24	7,491.14	26.82	28.83	-35.36	-181.82	802.76	562.82	509.41	53.41	10.538	
7,650.00	7,636.20	7,608.00	7,540.14	27.00	29.04	-35.43	-183.81	811.20	567.66	513.89	53.78	10.556	
7,700.00	7,686.00	7,657.76	7,589.14	27.19	29.25	-35.50	-185.80	819.64	572.51	518.36	54.14	10.574	
7,750.00	7,735.79	7,707.52	7,638.14	27.37	29.47	-35.56	-187.79	828.07	577.35	522.84	54.51	10.591	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit Plan 1 — Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM — Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
7,800.00	7,785.59	7,757.28	7,687.14	27.55	29.68	-35.63	-189.77	836.51	582.20	527.32	54.88	10.608	
7,850.00	7,835.39	7,807.04	7,736.14	27.74	29.89	-35.69	-191.76	844.94	587.05	531.80	55.25	10.625	
7,900.00	7,885.18	7,856.80	7,785.14	27.92	30.10	-35.76	-193.75	853.38	591.89	536.27	55.62	10.642	
7,950.00	7,934.98	7,906.56	7,834.14	28.10	30.32	-35.82	-195.73	861.82	596.74	540.75	55.99	10.658	
8,000.00	7,984.77	7,956.32	7,883.14	28.29	30.53	-35.88	-197.72	870.25	601.59	545.23	56.36	10.675	
8,050.00	8,034.57	8,006.08	7,932.14	28.47	30.74	-35.94	-199.71	878.69	606.44	549.71	56.73	10.691	
8,100.00	8,084.36	8,055.84	7,981.14	28.65	30.95	-36.00	-201.69	887.12	611.29	554.19	57.10	10.706	
8,150.00	8,134.16	8,105.60	8,030.14	28.84	31.17	-36.06	-203.68	895.56	616.14	558.68	57.47	10.722	
8,200.00	8,183.95	8,155.36	8,079.14	29.02	31.38	-36.12	-205.67	904.00	620.99	563.16	57.84	10.737	
8,250.00	8,233.75	8,205.12	8,128.14	29.21	31.59	-36.18	-207.65	912.43	625.84	567.64	58.21	10.752	
8,300.00	8,283.55	8,254.88	8,177.14	29.39	31.80	-36.23	-209.64	920.87	630.70	572.12	58.58	10.767	
8,350.00	8,333.34	8,304.65	8,226.14	29.58	32.02	-36.29	-211.63	929.31	635.55	576.60	58.95	10.782	
8,400.00	8,383.14	8,354.41	8,275.14	29.76	32.23	-36.34	-213.61	937.74	640.40	581.09	59.32	10.797	
8,450.00	8,432.93	8,404.17	8,324.14	29.94	32.44	-36.39	-215.60	946.18	645.26	585.57	59.69	10.811	
8,500.00	8,482.73	8,453.93	8,373.13	30.13	32.66	-36.45	-217.59	954.61	650.11	590.06	60.06	10.825	
8,550.00	8,532.52	8,503.69	8,422.13	30.31	32.87	-36.50	-219.58	963.05	654.97	594.54	60.43	10.839	
8,600.00	8,582.32	8,553.45	8,471.13	30.50	33.08	-36.55	-221.56	971.49	659.82	599.03	60.80	10.853	
8,650.00	8,632.11	8,603.21	8,520.13	30.68	33.30	-36.60	-223.55	979.92	664.68	603.51	61.17	10.866	
8,700.00	8,681.91	8,652.97	8,569.13	30.87	33.51	-36.65	-225.54	988.36	669.54	608.00	61.54	10.880	
8,750.00	8,731.71	8,702.73	8,618.13	31.05	33.72	-36.70	-227.52	996.80	674.40	612.49	61.91	10.893	
8,800.00	8,781.50	8,752.49	8,667.13	31.24	33.94	-36.75	-229.51	1,005.23	679.25	616.97	62.28	10.906	
8,850.00	8,831.30	8,802.25	8,716.13	31.42	34.15	-36.79	-231.50	1,013.67	684.11	621.46	62.65	10.919	
8,900.00	8,881.09	8,852.01	8,765.13	31.61	34.36	-36.84	-233.48	1,022.10	688.97	625.95	63.02	10.932	
8,950.00	8,930.89	8,901.77	8,814.13	31.79	34.58	-36.89	-235.47	1,030.54	693.83	630.44	63.39	10.945	
9,000.00	8,980.68	8,951.53	8,863.13	31.98	34.79	-36.93	-237.46	1,038.98	698.69	634.92	63.77	10.957	
9,050.00	9,030.48	9,001.29	8,912.13	32.16	35.00	-36.98	-239.44	1,047.41	703.55	639.41	64.14	10.969	
9,100.00	9,080.27	9,051.05	8,961.13	32.35	35.22	-37.02	-241.43	1,055.85	708.41	643.90	64.51	10.981	
9,150.00	9,130.07	9,100.81	9,010.13	32.54	35.43	-37.07	-243.42	1,064.28	713.27	648.39	64.88	10.993	
9,200.00	9,179.87	9,150.57	9,059.13	32.72	35.65	-37.11	-245.40	1,072.72	718.13	652.88	65.25	11.005	
9,250.00	9,229.66	9,200.33	9,108.13	32.91	35.86	-37.15	-247.39	1,081.16	722.99	657.37	65.63	11.017	
9,300.00	9,279.46	9,250.09	9,157.13	33.09	36.07	-37.19	-249.38	1,089.59	727.86	661.86	66.00	11.029	
9,350.00	9,329.27	9,300.16	9,206.11	33.28	36.29	-37.26	-251.36	1,098.03	732.87	666.50	66.37	11.042	
9,400.00	9,379.13	9,349.53	9,255.05	33.46	36.50	-37.31	-253.35	1,106.45	738.38	671.64	66.74	11.064	
9,450.00	9,429.04	9,399.16	9,303.93	33.64	36.71	-37.34	-255.33	1,114.87	744.40	677.30	67.10	11.093	
9,500.00	9,478.98	9,448.73	9,352.73	33.82	36.93	-37.34	-257.31	1,123.27	750.95	683.48	67.47	11.130	
9,550.00	9,528.95	9,498.21	9,401.46	34.00	37.14	-37.32	-259.29	1,131.66	758.01	690.18	67.83	11.175	
9,600.00	9,578.94	9,547.61	9,450.10	34.18	37.35	-37.27	-261.26	1,140.03	765.59	697.40	68.19	11.227	
9,650.00	9,628.93	9,603.09	9,498.65	34.35	37.59	-37.20	-263.23	1,148.39	773.68	705.11	68.57	11.283	
9,700.00	9,678.93	9,646.15	9,547.14	34.52	37.78	88.90	-265.19	1,156.74	782.12	713.22	68.90	11.352	
9,750.00	9,728.93	9,695.39	9,595.62	34.69	37.99	89.06	-267.16	1,165.09	790.57	721.32	69.25	11.416	
9,800.00	9,778.93	9,744.21	9,643.72	34.86	38.20	89.14	-268.22	1,173.36	799.03	729.43	69.60	11.481	
9,850.00	9,828.93	9,792.66	9,691.37	35.03	38.40	88.95	-265.41	1,181.54	807.53	737.59	69.94	11.545	
9,900.00	9,878.93	9,840.30	9,737.85	35.20	38.58	88.48	-258.68	1,189.50	816.12	745.84	70.28	11.612	
9,950.00	9,928.93	9,886.53	9,782.26	35.38	38.75	87.77	-248.42	1,197.08	824.90	754.29	70.61	11.683	
10,000.00	9,978.93	9,930.83	9,823.94	35.55	38.90	86.87	-235.21	1,204.18	833.99	763.09	70.90	11.762	
10,050.00	10,028.90	9,973.37	9,862.90	35.72	39.03	85.38	-219.50	1,210.80	843.47	772.30	71.17	11.852	
10,100.00	10,078.54	10,015.02	9,899.83	35.88	39.15	83.50	-201.31	1,217.05	853.14	781.75	71.39	11.950	
10,150.00	10,127.49	10,055.91	9,934.74	36.04	39.26	81.69	-180.85	1,222.95	862.89	791.31	71.58	12.055	
10,200.00	10,175.37	10,096.15	9,967.59	36.19	39.35	79.97	-158.30	1,228.48	872.59	800.87	71.73	12.166	
10,250.00	10,221.81	10,135.81	9,998.37	36.33	39.43	78.34	-133.85	1,233.65	882.15	810.31	71.84	12.279	
10,300.00	10,266.47	10,174.96	10,027.06	36.45	39.51	76.81	-107.64	1,238.44	891.45	819.52	71.92	12.394	
10,350.00	10,309.00	10,213.68	10,053.63	36.57	39.57	75.39	-79.84	1,242.86	900.39	828.40	71.98	12.508	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit Plan 1

Survey Program: 0-MWD+HDGM

Offset Site Error: 0.00 ft

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
10,400.00	10,349.08	10,252.02	10,078.06	36.68	39.63	74.08	-50.57	1,246.91	908.87	836.85	72.02	12.619	
10,450.00	10,386.41	10,290.04	10,100.32	36.77	39.68	72.89	-19.99	1,250.58	916.82	844.76	72.05	12.724	
10,500.00	10,420.70	10,327.78	10,120.40	36.85	39.71	71.82	11.79	1,253.87	924.14	852.07	72.07	12.822	
10,550.00	10,451.68	10,365.28	10,138.27	36.92	39.75	70.87	44.63	1,256.77	930.78	858.68	72.10	12.909	
10,600.00	10,479.13	10,402.59	10,153.91	36.98	39.77	70.05	78.40	1,259.28	936.67	864.53	72.14	12.985	
10,650.00	10,502.84	10,439.74	10,167.29	37.04	39.80	69.35	112.98	1,261.40	941.74	869.56	72.19	13.046	
10,700.00	10,522.62	10,476.76	10,178.41	37.11	39.81	68.79	148.24	1,263.13	945.97	873.71	72.26	13.092	
10,750.00	10,538.32	10,513.68	10,187.24	37.18	39.83	68.35	184.06	1,264.46	949.31	876.94	72.36	13.119	
10,800.00	10,549.83	10,550.00	10,193.70	37.26	39.85	68.04	219.78	1,265.38	951.72	879.23	72.49	13.129	
10,850.00	10,557.06	10,587.35	10,197.99	37.36	39.86	67.85	256.87	1,265.92	953.20	880.55	72.66	13.120	
10,900.00	10,559.94	10,624.14	10,199.89	37.46	39.88	67.80	293.61	1,266.06	953.73	880.87	72.85	13.091	
10,950.00	10,560.00	10,670.00	10,200.00	37.57	39.91	67.80	339.47	1,265.84	953.71	880.61	73.10	13.047	
11,000.00	10,560.00	10,720.00	10,200.00	37.69	39.94	67.80	389.47	1,265.58	953.71	880.34	73.37	12.999	
11,050.00	10,560.00	10,770.00	10,200.00	37.83	40.00	67.80	439.46	1,265.31	953.71	880.04	73.67	12.946	
11,100.00	10,560.00	10,820.00	10,200.00	37.98	40.06	67.80	489.46	1,265.05	953.70	879.72	73.98	12.891	
11,150.00	10,560.00	10,870.00	10,200.00	38.16	40.14	67.80	539.46	1,264.79	953.70	879.37	74.33	12.831	
11,200.00	10,560.00	10,920.00	10,200.00	38.33	40.23	67.80	589.46	1,264.53	953.70	879.01	74.69	12.769	
11,250.00	10,560.00	10,970.00	10,200.00	38.53	40.34	67.80	639.46	1,264.27	953.70	878.61	75.09	12.701	
11,300.00	10,560.00	11,020.00	10,200.00	38.73	40.47	67.80	689.46	1,264.01	953.69	878.20	75.50	12.632	
11,350.00	10,560.00	11,070.00	10,200.00	38.95	40.62	67.80	739.46	1,263.74	953.69	877.75	75.94	12.558	
11,400.00	10,560.00	11,120.00	10,200.00	39.18	40.78	67.80	789.46	1,263.48	953.69	877.29	76.39	12.484	
11,450.00	10,560.00	11,170.00	10,200.00	39.42	40.96	67.80	839.46	1,263.22	953.69	876.80	76.88	12.404	
11,500.00	10,560.00	11,220.00	10,200.00	39.67	41.15	67.80	889.46	1,262.96	953.68	876.30	77.38	12.325	
11,550.00	10,560.00	11,270.00	10,200.00	39.94	41.37	67.80	939.46	1,262.70	953.68	875.77	77.91	12.241	
11,600.00	10,560.00	11,320.00	10,200.00	40.21	41.59	67.80	989.46	1,262.43	953.68	875.23	78.45	12.156	
11,650.00	10,560.00	11,370.00	10,200.00	40.51	41.84	67.80	1,039.46	1,262.17	953.67	874.65	79.02	12.068	
11,700.00	10,560.00	11,420.00	10,200.00	40.80	42.10	67.80	1,089.46	1,261.91	953.67	874.07	79.60	11.980	
11,750.00	10,560.00	11,470.00	10,200.00	41.11	42.37	67.80	1,139.46	1,261.65	953.67	873.46	80.21	11.889	
11,800.00	10,560.00	11,520.00	10,200.00	41.43	42.65	67.80	1,189.45	1,261.39	953.67	872.83	80.83	11.798	
11,850.00	10,560.00	11,570.00	10,200.00	41.76	42.95	67.80	1,239.45	1,261.13	953.66	872.18	81.48	11.704	
11,900.00	10,560.00	11,620.00	10,200.00	42.10	43.26	67.80	1,289.45	1,260.86	953.66	871.52	82.14	11.610	
11,950.00	10,560.00	11,670.00	10,200.00	42.45	43.58	67.80	1,339.45	1,260.60	953.66	870.84	82.82	11.514	
12,000.00	10,560.00	11,720.00	10,200.00	42.80	43.91	67.80	1,389.45	1,260.34	953.66	870.14	83.51	11.419	
12,050.00	10,560.00	11,770.00	10,200.00	43.18	44.26	67.80	1,439.45	1,260.08	953.65	869.42	84.23	11.322	
12,100.00	10,560.00	11,820.00	10,200.00	43.55	44.61	67.80	1,489.45	1,259.82	953.65	868.69	84.96	11.225	
12,150.00	10,560.00	11,870.00	10,200.00	43.94	44.97	67.80	1,539.45	1,259.55	953.65	867.94	85.71	11.127	
12,200.00	10,560.00	11,920.00	10,200.00	44.33	45.35	67.80	1,589.45	1,259.29	953.65	867.18	86.46	11.029	
12,250.00	10,560.00	11,970.00	10,200.00	44.73	45.73	67.80	1,639.45	1,259.03	953.64	866.40	87.25	10.931	
12,300.00	10,560.00	12,020.00	10,200.00	45.14	46.12	67.80	1,689.45	1,258.77	953.64	865.61	88.03	10.833	
12,350.00	10,560.00	12,070.00	10,200.00	45.56	46.52	67.80	1,739.45	1,258.51	953.64	864.80	88.84	10.734	
12,400.00	10,560.00	12,120.00	10,200.00	45.99	46.93	67.80	1,789.45	1,258.25	953.64	863.98	89.66	10.636	
12,450.00	10,560.00	12,170.00	10,200.00	46.42	47.34	67.80	1,839.45	1,257.98	953.63	863.14	90.50	10.538	
12,500.00	10,560.00	12,220.00	10,200.00	46.86	47.77	67.80	1,889.44	1,257.72	953.63	862.29	91.34	10.440	
12,550.00	10,560.00	12,270.00	10,200.00	47.31	48.20	67.80	1,939.44	1,257.46	953.63	861.42	92.20	10.343	
12,600.00	10,560.00	12,320.00	10,200.00	47.76	48.64	67.80	1,989.44	1,257.20	953.63	860.55	93.07	10.246	
12,650.00	10,560.00	12,370.00	10,200.00	48.23	49.08	67.80	2,039.44	1,256.94	953.62	859.66	93.96	10.149	
12,700.00	10,560.00	12,420.00	10,200.00	48.69	49.53	67.80	2,089.44	1,256.67	953.62	858.77	94.85	10.054	
12,750.00	10,560.00	12,470.00	10,200.00	49.17	49.99	67.80	2,139.44	1,256.41	953.62	857.85	95.77	9.958	
12,800.00	10,560.00	12,520.00	10,200.00	49.65	50.46	67.80	2,189.44	1,256.15	953.62	856.93	96.68	9.864	
12,850.00	10,560.00	12,570.00	10,200.00	50.14	50.93	67.80	2,239.44	1,255.89	953.61	856.00	97.61	9.769	
12,900.00	10,560.00	12,620.00	10,200.00	50.62	51.41	67.80	2,289.44	1,255.63	953.61	855.06	98.55	9.676	
12,950.00	10,560.00	12,670.00	10,200.00	51.12	51.89	67.80	2,339.44	1,255.37	953.61	854.10	99.51	9.583	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit Plan 1

Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
13,000.00	10,560.00	12,720.00	10,200.00	51.63	52.38	67.80	2,389.44	1,255.10	953.60	853.14	100.46	9.492	
13,050.00	10,560.00	12,770.00	10,200.00	52.14	52.88	67.80	2,439.44	1,254.84	953.60	852.16	101.44	9.401	
13,100.00	10,560.00	12,820.00	10,200.00	52.65	53.38	67.80	2,489.44	1,254.58	953.60	851.18	102.41	9.311	
13,150.00	10,560.00	12,870.00	10,200.00	53.17	53.88	67.80	2,539.44	1,254.32	953.60	850.19	103.41	9.222	
13,200.00	10,560.00	12,920.00	10,200.00	53.69	54.40	67.80	2,589.44	1,254.06	953.59	849.19	104.40	9.134	
13,250.00	10,560.00	12,970.00	10,200.00	54.22	54.91	67.80	2,639.43	1,253.79	953.59	848.18	105.41	9.046	
13,300.00	10,560.00	13,020.00	10,200.00	54.75	55.43	67.80	2,689.43	1,253.53	953.59	847.16	106.42	8.960	
13,350.00	10,560.00	13,070.00	10,200.00	55.29	55.96	67.80	2,739.43	1,253.27	953.59	846.14	107.45	8.875	
13,400.00	10,560.00	13,120.00	10,200.00	55.83	56.49	67.80	2,789.43	1,253.01	953.58	845.10	108.48	8.790	
13,450.00	10,560.00	13,170.00	10,200.00	56.38	57.02	67.80	2,839.43	1,252.75	953.58	844.06	109.52	8.707	
13,500.00	10,560.00	13,220.00	10,200.00	56.92	57.56	67.80	2,889.43	1,252.49	953.58	843.01	110.56	8.625	
13,550.00	10,560.00	13,270.00	10,200.00	57.48	58.10	67.80	2,939.43	1,252.22	953.58	841.96	111.62	8.543	
13,600.00	10,560.00	13,320.00	10,200.00	58.04	58.65	67.80	2,989.43	1,251.96	953.57	840.89	112.68	8.463	
13,650.00	10,560.00	13,370.00	10,200.00	58.60	59.20	67.80	3,039.43	1,251.70	953.57	839.82	113.75	8.383	
13,700.00	10,560.00	13,420.00	10,200.00	59.16	59.75	67.80	3,089.43	1,251.44	953.57	838.75	114.82	8.305	
13,750.00	10,560.00	13,470.00	10,200.00	59.73	60.31	67.80	3,139.43	1,251.18	953.57	837.68	115.90	8.227	
13,800.00	10,560.00	13,520.00	10,200.00	60.30	60.87	67.80	3,189.43	1,250.92	953.56	836.57	116.99	8.151	
13,850.00	10,560.00	13,570.00	10,200.00	60.88	61.44	67.80	3,239.43	1,250.65	953.56	835.48	118.09	8.075	
13,900.00	10,560.00	13,620.00	10,200.00	61.46	62.01	67.80	3,289.43	1,250.39	953.56	834.38	119.18	8.001	
13,950.00	10,560.00	13,670.00	10,200.00	62.04	62.58	67.80	3,339.43	1,250.13	953.56	833.27	120.29	7.927	
14,000.00	10,560.00	13,720.00	10,200.00	62.62	63.16	67.80	3,389.42	1,249.87	953.55	832.15	121.40	7.855	
14,050.00	10,560.00	13,770.00	10,200.00	63.21	63.73	67.80	3,439.42	1,249.61	953.55	831.03	122.52	7.783	
14,100.00	10,560.00	13,820.00	10,200.00	63.80	64.32	67.80	3,489.42	1,249.34	953.55	829.91	123.64	7.712	
14,150.00	10,560.00	13,870.00	10,200.00	64.39	64.90	67.80	3,539.42	1,249.08	953.55	828.78	124.77	7.643	
14,200.00	10,560.00	13,920.00	10,200.00	64.99	65.49	67.80	3,589.42	1,248.82	953.54	827.65	125.90	7.574	
14,250.00	10,560.00	13,970.00	10,200.00	65.59	66.08	67.80	3,639.42	1,248.56	953.54	826.51	127.03	7.506	
14,300.00	10,560.00	14,020.00	10,200.00	66.19	66.67	67.80	3,689.42	1,248.30	953.54	825.36	128.17	7.439	
14,350.00	10,560.00	14,070.00	10,200.00	66.79	67.27	67.80	3,739.42	1,248.04	953.53	824.21	129.32	7.373	
14,400.00	10,560.00	14,120.00	10,200.00	67.40	67.86	67.80	3,789.42	1,247.77	953.53	823.06	130.47	7.308	
14,450.00	10,560.00	14,170.00	10,200.00	68.01	68.46	67.80	3,839.42	1,247.51	953.53	821.90	131.63	7.244	
14,500.00	10,560.00	14,220.00	10,200.00	68.62	69.07	67.80	3,889.42	1,247.25	953.53	820.74	132.79	7.181	
14,550.00	10,560.00	14,270.00	10,200.00	69.23	69.67	67.80	3,939.42	1,246.99	953.52	819.57	133.95	7.118	
14,600.00	10,560.00	14,320.00	10,200.00	69.85	70.28	67.80	3,989.42	1,246.73	953.52	818.40	135.12	7.057	
14,650.00	10,560.00	14,370.00	10,200.00	70.47	70.89	67.80	4,039.42	1,246.46	953.52	817.23	136.29	6.996	
14,700.00	10,560.00	14,420.00	10,200.00	71.09	71.50	67.80	4,089.41	1,246.20	953.52	816.05	137.47	6.936	
14,750.00	10,560.00	14,470.00	10,200.00	71.71	72.12	67.80	4,139.41	1,245.94	953.51	814.87	138.65	6.877	
14,800.00	10,560.00	14,520.00	10,200.00	72.33	72.73	67.80	4,189.41	1,245.68	953.51	813.68	139.83	6.819	
14,850.00	10,560.00	14,570.00	10,200.00	72.96	73.35	67.80	4,239.41	1,245.42	953.51	812.49	141.02	6.762	
14,900.00	10,560.00	14,620.00	10,200.00	73.58	73.97	67.80	4,289.41	1,245.16	953.51	811.30	142.21	6.705	
14,950.00	10,560.00	14,670.00	10,200.00	74.21	74.59	67.80	4,339.41	1,244.89	953.50	810.10	143.40	6.649	
15,000.00	10,560.00	14,720.00	10,200.00	74.84	75.22	67.80	4,389.41	1,244.63	953.50	808.90	144.60	6.594	
15,050.00	10,560.00	14,770.00	10,200.00	75.48	75.84	67.80	4,439.41	1,244.37	953.50	807.70	145.80	6.540	
15,100.00	10,560.00	14,820.00	10,200.00	76.11	76.47	67.80	4,489.41	1,244.11	953.50	806.49	147.00	6.486	
15,150.00	10,560.00	14,870.00	10,200.00	76.75	77.10	67.80	4,539.41	1,243.85	953.49	805.28	148.21	6.433	
15,200.00	10,560.00	14,920.00	10,200.00	77.39	77.73	67.80	4,589.41	1,243.58	953.49	804.07	149.42	6.381	
15,250.00	10,560.00	14,970.00	10,200.00	78.03	78.37	67.80	4,639.41	1,243.32	953.49	802.86	150.63	6.330	
15,300.00	10,560.00	15,020.00	10,200.00	78.67	79.00	67.80	4,689.41	1,243.06	953.49	801.64	151.85	6.279	
15,350.00	10,560.00	15,070.00	10,200.00	79.31	79.64	67.80	4,739.41	1,242.80	953.48	800.42	153.07	6.229	
15,400.00	10,560.00	15,120.00	10,200.00	79.95	80.27	67.80	4,789.41	1,242.54	953.48	799.19	154.29	6.180	
15,450.00	10,560.00	15,170.00	10,200.00	80.60	80.91	67.80	4,839.40	1,242.28	953.48	797.97	155.51	6.131	
15,500.00	10,560.00	15,220.00	10,200.00	81.25	81.55	67.80	4,889.40	1,242.01	953.47	796.74	156.74	6.083	
15,550.00	10,560.00	15,270.00	10,200.00	81.89	82.20	67.80	4,939.40	1,241.75	953.47	795.51	157.97	6.036	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit Plan 1

Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
15,600.00	10,560.00	15,320.00	10,200.00	82.54	82.84	67.80	4,989.40	1,241.49	953.47	794.27	159.20	5.989	
15,650.00	10,560.00	15,370.00	10,200.00	83.20	83.49	67.80	5,039.40	1,241.23	953.47	793.04	160.43	5.943	
15,700.00	10,560.00	15,420.00	10,200.00	83.85	84.13	67.80	5,089.40	1,240.97	953.46	791.80	161.67	5.898	
15,750.00	10,560.00	15,470.00	10,200.00	84.50	84.78	67.80	5,139.40	1,240.70	953.46	790.56	162.91	5.853	
15,800.00	10,560.00	15,520.00	10,200.00	85.15	85.43	67.80	5,189.40	1,240.44	953.46	789.31	164.15	5.809	
15,850.00	10,560.00	15,570.00	10,200.00	85.81	86.08	67.80	5,239.40	1,240.18	953.46	788.07	165.39	5.765	
15,900.00	10,560.00	15,620.00	10,200.00	86.47	86.73	67.80	5,289.40	1,239.92	953.45	786.82	166.63	5.722	
15,950.00	10,560.00	15,670.00	10,200.00	87.13	87.38	67.80	5,339.40	1,239.66	953.45	785.57	167.88	5.679	
16,000.00	10,560.00	15,720.00	10,200.00	87.78	88.04	67.80	5,389.40	1,239.40	953.45	784.32	169.13	5.637	
16,050.00	10,560.00	15,770.00	10,200.00	88.45	88.69	67.80	5,439.40	1,239.13	953.45	783.06	170.38	5.596	
16,100.00	10,560.00	15,820.00	10,200.00	89.11	89.35	67.80	5,489.40	1,238.87	953.44	781.81	171.64	5.555	
16,150.00	10,560.00	15,870.00	10,200.00	89.77	90.01	67.80	5,539.39	1,238.61	953.44	780.55	172.89	5.515	
16,200.00	10,560.00	15,920.00	10,200.00	90.43	90.67	67.80	5,589.39	1,238.35	953.44	779.29	174.15	5.475	
16,250.00	10,560.00	15,970.00	10,200.00	91.10	91.32	67.80	5,639.39	1,238.09	953.44	778.03	175.41	5.436	
16,300.00	10,560.00	16,020.00	10,200.00	91.76	91.99	67.80	5,689.39	1,237.83	953.43	776.76	176.67	5.397	
16,350.00	10,560.00	16,070.00	10,200.00	92.43	92.65	67.80	5,739.39	1,237.56	953.43	775.50	177.93	5.358	
16,400.00	10,560.00	16,120.00	10,200.00	93.10	93.31	67.80	5,789.39	1,237.30	953.43	774.23	179.20	5.321	
16,450.00	10,560.00	16,170.00	10,200.00	93.76	93.97	67.80	5,839.39	1,237.04	953.43	772.96	180.46	5.283	
16,500.00	10,560.00	16,220.00	10,200.00	94.43	94.64	67.80	5,889.39	1,236.78	953.42	771.69	181.73	5.246	
16,550.00	10,560.00	16,270.00	10,200.00	95.10	95.30	67.80	5,939.39	1,236.52	953.42	770.42	183.00	5.210	
16,600.00	10,560.00	16,320.00	10,200.00	95.77	95.97	67.80	5,989.39	1,236.25	953.42	769.15	184.27	5.174	
16,650.00	10,560.00	16,370.00	10,200.00	96.44	96.64	67.80	6,039.39	1,235.99	953.42	767.87	185.54	5.138	
16,700.00	10,560.00	16,420.00	10,200.00	97.12	97.30	67.80	6,089.39	1,235.73	953.41	766.59	186.82	5.103	
16,750.00	10,560.00	16,470.00	10,200.00	97.79	97.97	67.80	6,139.39	1,235.47	953.41	765.32	188.09	5.069	
16,800.00	10,560.00	16,520.00	10,200.00	98.46	98.64	67.80	6,189.39	1,235.21	953.41	764.04	189.37	5.035	
16,850.00	10,560.00	16,570.00	10,200.00	99.14	99.31	67.80	6,239.39	1,234.95	953.40	762.75	190.65	5.001	
16,900.00	10,560.00	16,620.00	10,200.00	99.81	99.98	67.80	6,289.38	1,234.68	953.40	761.47	191.93	4.967	Alert
16,950.00	10,560.00	16,670.00	10,200.00	100.49	100.66	67.80	6,339.38	1,234.42	953.40	760.19	193.21	4.934	Alert
17,000.00	10,560.00	16,720.00	10,200.00	101.17	101.33	67.80	6,389.38	1,234.16	953.40	758.90	194.49	4.902	Alert
17,050.00	10,560.00	16,770.00	10,200.00	101.85	102.00	67.80	6,439.38	1,233.90	953.39	757.62	195.78	4.870	Alert
17,100.00	10,560.00	16,820.00	10,200.00	102.52	102.68	67.80	6,489.38	1,233.64	953.39	756.33	197.06	4.838	Alert
17,150.00	10,560.00	16,870.00	10,200.00	103.20	103.35	67.80	6,539.38	1,233.37	953.39	755.04	198.35	4.807	Alert
17,200.00	10,560.00	16,920.00	10,200.00	103.88	104.03	67.80	6,589.38	1,233.11	953.39	753.75	199.64	4.776	Alert
17,250.00	10,560.00	16,970.00	10,200.00	104.56	104.71	67.80	6,639.38	1,232.85	953.38	752.46	200.93	4.745	Alert
17,300.00	10,560.00	17,020.00	10,200.00	105.24	105.38	67.80	6,689.38	1,232.59	953.38	751.16	202.22	4.715	Alert
17,350.00	10,560.00	17,070.00	10,200.00	105.93	106.06	67.80	6,739.38	1,232.33	953.38	749.87	203.51	4.685	Alert
17,400.00	10,560.00	17,120.00	10,200.00	106.61	106.74	67.80	6,789.38	1,232.07	953.38	748.57	204.80	4.655	Alert
17,450.00	10,560.00	17,170.00	10,200.00	107.29	107.42	67.80	6,839.38	1,231.80	953.37	747.28	206.10	4.626	Alert
17,500.00	10,560.00	17,220.00	10,200.00	107.97	108.10	67.80	6,889.38	1,231.54	953.37	745.98	207.39	4.597	Alert
17,550.00	10,560.00	17,270.00	10,200.00	108.66	108.78	67.79	6,939.38	1,231.28	953.37	744.68	208.69	4.568	Alert
17,600.00	10,560.00	17,320.00	10,200.00	109.34	109.46	67.79	6,989.38	1,231.02	953.37	743.38	209.99	4.540	Alert
17,650.00	10,560.00	17,370.00	10,200.00	110.03	110.14	67.79	7,039.37	1,230.76	953.36	742.08	211.28	4.512	Alert
17,700.00	10,560.00	17,420.00	10,200.00	110.71	110.82	67.79	7,089.37	1,230.49	953.36	740.78	212.58	4.485	Alert
17,750.00	10,560.00	17,470.00	10,200.00	111.40	111.51	67.79	7,139.37	1,230.23	953.36	739.47	213.88	4.457	Alert
17,800.00	10,560.00	17,520.00	10,200.00	112.09	112.19	67.79	7,189.37	1,229.97	953.36	738.17	215.19	4.430	Alert
17,850.00	10,560.00	17,570.00	10,200.00	112.77	112.88	67.79	7,239.37	1,229.71	953.35	736.86	216.49	4.404	Alert
17,900.00	10,560.00	17,620.00	10,200.00	113.46	113.56	67.79	7,289.37	1,229.45	953.35	735.56	217.79	4.377	Alert
17,950.00	10,560.00	17,670.00	10,200.00	114.15	114.24	67.79	7,339.37	1,229.19	953.35	734.25	219.10	4.351	Alert
18,000.00	10,560.00	17,720.00	10,200.00	114.84	114.93	67.79	7,389.37	1,228.92	953.35	732.94	220.40	4.325	Alert
18,050.00	10,560.00	17,770.00	10,200.00	115.53	115.62	67.79	7,439.37	1,228.66	953.34	731.63	221.71	4.300	Alert
18,100.00	10,560.00	17,820.00	10,200.00	116.22	116.30	67.79	7,489.37	1,228.40	953.34	730.33	223.01	4.275	Alert
18,150.00	10,560.00	17,870.00	10,200.00	116.91	116.99	67.79	7,539.37	1,228.14	953.34	729.01	224.32	4.250	Alert

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit Plan 1 — **Offset Site Error:** 0.00 ft

Survey Program: 0-MWD+HDGM — **Offset Well Error:** 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
18,200.00	10,560.00	17,920.00	10,200.00	117.60	117.68	67.79	7,589.37	1,227.88	953.33	727.70	225.63	4.225	Alert
18,250.00	10,560.00	17,970.00	10,200.00	118.29	118.37	67.79	7,639.37	1,227.62	953.33	726.39	226.94	4.201	Alert
18,300.00	10,560.00	18,020.00	10,200.00	118.98	119.05	67.79	7,689.37	1,227.35	953.33	725.08	228.25	4.177	Alert
18,350.00	10,560.00	18,070.00	10,200.00	119.67	119.74	67.79	7,739.36	1,227.09	953.33	723.76	229.56	4.153	Alert
18,400.00	10,560.00	18,120.00	10,200.00	120.37	120.43	67.79	7,789.36	1,226.83	953.32	722.45	230.88	4.129	Alert
18,450.00	10,560.00	18,170.00	10,200.00	121.06	121.12	67.79	7,839.36	1,226.57	953.32	721.13	232.19	4.106	Alert
18,500.00	10,560.00	18,220.00	10,200.00	121.75	121.81	67.79	7,889.36	1,226.31	953.32	719.82	233.50	4.083	Alert
18,550.00	10,560.00	18,270.00	10,200.00	122.45	122.50	67.79	7,939.36	1,226.04	953.32	718.50	234.82	4.060	Alert
18,600.00	10,560.00	18,320.00	10,200.00	123.14	123.20	67.79	7,989.36	1,225.78	953.31	717.18	236.13	4.037	Alert
18,650.00	10,560.00	18,370.00	10,200.00	123.83	123.89	67.79	8,039.36	1,225.52	953.31	715.86	237.45	4.015	Alert
18,700.00	10,560.00	18,420.00	10,200.00	124.53	124.58	67.79	8,089.36	1,225.26	953.31	714.54	238.76	3.993	Alert
18,750.00	10,560.00	18,470.00	10,200.00	125.22	125.27	67.79	8,139.36	1,225.00	953.31	713.22	240.08	3.971	Alert
18,800.00	10,560.00	18,520.00	10,200.00	125.92	125.97	67.79	8,189.36	1,224.74	953.30	711.90	241.40	3.949	Alert
18,850.00	10,560.00	18,570.00	10,200.00	126.62	126.66	67.79	8,239.36	1,224.47	953.30	710.58	242.72	3.928	Alert
18,900.00	10,560.00	18,620.00	10,200.00	127.31	127.35	67.79	8,289.36	1,224.21	953.30	709.26	244.04	3.906	Alert
18,950.00	10,560.00	18,670.00	10,200.00	128.01	128.05	67.79	8,339.36	1,223.95	953.30	707.94	245.36	3.885	Alert
19,000.00	10,560.00	18,720.00	10,200.00	128.71	128.74	67.79	8,389.36	1,223.69	953.29	706.61	246.68	3.864	Alert
19,050.00	10,560.00	18,770.00	10,200.00	129.40	129.44	67.79	8,439.36	1,223.43	953.29	705.29	248.00	3.844	Alert
19,100.00	10,560.00	18,820.00	10,200.00	130.10	130.13	67.79	8,489.35	1,223.16	953.29	703.96	249.32	3.823	Alert
19,150.00	10,560.00	18,870.00	10,200.00	130.80	130.83	67.79	8,539.35	1,222.90	953.29	702.64	250.65	3.803	Alert
19,200.00	10,560.00	18,920.00	10,200.00	131.50	131.52	67.79	8,589.35	1,222.64	953.28	701.31	251.97	3.783	Alert
19,250.00	10,560.00	18,970.00	10,200.00	132.20	132.22	67.79	8,639.35	1,222.38	953.28	699.99	253.29	3.764	Alert
19,300.00	10,560.00	19,020.00	10,200.00	132.89	132.92	67.79	8,689.35	1,222.12	953.28	698.66	254.62	3.744	Alert
19,350.00	10,560.00	19,070.00	10,200.00	133.59	133.61	67.79	8,739.35	1,221.86	953.28	697.33	255.94	3.725	Alert
19,400.00	10,560.00	19,120.00	10,200.00	134.29	134.31	67.79	8,789.35	1,221.59	953.27	696.00	257.27	3.705	Alert
19,450.00	10,560.00	19,170.00	10,200.00	134.99	135.01	67.79	8,839.35	1,221.33	953.27	694.67	258.60	3.686	Alert
19,500.00	10,560.00	19,220.00	10,200.00	135.69	135.71	67.79	8,889.35	1,221.07	953.27	693.34	259.92	3.667	Alert
19,550.00	10,560.00	19,270.00	10,200.00	136.39	136.40	67.79	8,939.35	1,220.81	953.26	692.01	261.25	3.649	Alert
19,600.00	10,560.00	19,320.00	10,200.00	137.10	137.10	67.79	8,989.35	1,220.55	953.26	690.68	262.58	3.630	Alert
19,650.00	10,560.00	19,370.00	10,200.00	137.80	137.80	67.79	9,039.35	1,220.28	953.26	689.35	263.91	3.612	Alert
19,700.00	10,560.00	19,420.00	10,200.00	138.50	138.50	67.79	9,089.35	1,220.02	953.26	688.02	265.24	3.594	Alert
19,750.00	10,560.00	19,470.00	10,200.00	139.20	139.20	67.79	9,139.35	1,219.76	953.25	686.69	266.57	3.576	Alert
19,800.00	10,560.00	19,520.00	10,200.00	139.90	139.90	67.79	9,189.35	1,219.50	953.25	685.35	267.90	3.558	Alert
19,850.00	10,560.00	19,570.00	10,200.00	140.60	140.60	67.79	9,239.34	1,219.24	953.25	684.02	269.23	3.541	Alert
19,900.00	10,560.00	19,620.00	10,200.00	141.31	141.30	67.79	9,289.34	1,218.98	953.25	682.69	270.56	3.523	Alert
19,950.00	10,560.00	19,670.00	10,200.00	142.01	142.00	67.79	9,339.34	1,218.71	953.24	681.35	271.89	3.506	Alert
20,000.00	10,560.00	19,720.00	10,200.00	142.71	142.70	67.79	9,389.34	1,218.45	953.24	680.02	273.22	3.489	Alert
20,050.00	10,560.00	19,770.00	10,200.00	143.41	143.40	67.79	9,439.34	1,218.19	953.24	678.68	274.56	3.472	Alert
20,100.00	10,560.00	19,820.00	10,200.00	144.12	144.11	67.79	9,489.34	1,217.93	953.24	677.35	275.89	3.455	Alert
20,150.00	10,560.00	19,870.00	10,200.00	144.82	144.81	67.79	9,539.34	1,217.67	953.23	676.01	277.22	3.438	Alert
20,200.00	10,560.00	19,920.00	10,200.00	145.53	145.51	67.79	9,589.34	1,217.40	953.23	674.67	278.56	3.422	Alert
20,250.00	10,560.00	19,970.00	10,200.00	146.23	146.21	67.79	9,639.34	1,217.14	953.23	673.34	279.89	3.406	Alert
20,300.00	10,560.00	20,020.00	10,200.00	146.93	146.91	67.79	9,689.34	1,216.88	953.23	672.00	281.23	3.390	Alert
20,350.00	10,560.00	20,070.00	10,200.00	147.64	147.62	67.79	9,739.34	1,216.62	953.22	670.66	282.56	3.373	Alert
20,400.00	10,560.00	20,120.00	10,200.00	148.34	148.32	67.79	9,789.34	1,216.36	953.22	669.32	283.90	3.358	Alert
20,450.00	10,560.00	20,170.00	10,200.00	149.05	149.02	67.79	9,839.34	1,216.10	953.22	667.98	285.24	3.342	Alert
20,500.00	10,560.00	20,220.00	10,200.00	149.75	149.73	67.79	9,889.34	1,215.83	953.22	666.64	286.57	3.326	Alert
20,550.00	10,560.00	20,270.00	10,200.00	150.46	150.43	67.79	9,939.33	1,215.57	953.21	665.30	287.91	3.311	Alert
20,600.00	10,560.00	20,320.00	10,200.00	151.17	151.13	67.79	9,989.33	1,215.31	953.21	663.96	289.25	3.295	Alert
20,650.00	10,560.00	20,370.00	10,200.00	151.87	151.84	67.79	10,039.33	1,215.05	953.21	662.62	290.59	3.280	Alert
20,700.00	10,560.00	20,420.00	10,200.00	152.58	152.54	67.79	10,089.33	1,214.79	953.20	661.28	291.92	3.265	Alert
20,750.00	10,560.00	20,470.00	10,200.00	153.28	153.25	67.79	10,139.33	1,214.53	953.20	659.94	293.26	3.250	Alert

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36_25 State Fed Com 235H - Wellbore #1 - Permit Plan 1

Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
20,800.00	10,560.00	20,520.00	10,200.00	153.99	153.95	67.79	10,189.33	1,214.26	953.20	658.60	294.60	3.236	Alert
20,823.96	10,560.00	20,543.95	10,200.00	154.33	154.29	67.79	10,213.29	1,214.14	953.20	657.96	295.24	3.229	Alert

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36-25 State Fed Com 230H - Wellbore #1 - Permit Plan 1

Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
5,650.00	5,644.38	5,978.12	5,925.28	19.78	22.45	142.46	-129.90	-1,364.56	1,498.41	1,457.82	40.59	36.912	
5,700.00	5,694.18	6,027.76	5,973.95	19.96	22.66	142.48	-131.93	-1,355.05	1,492.43	1,451.48	40.95	36.441	
5,750.00	5,743.97	6,077.40	6,022.63	20.14	22.88	142.50	-133.96	-1,345.53	1,486.45	1,445.14	41.32	35.978	
5,800.00	5,793.77	6,127.04	6,071.31	20.31	23.09	142.51	-135.99	-1,336.02	1,480.47	1,438.79	41.68	35.522	
5,850.00	5,843.56	6,176.68	6,119.98	20.49	23.31	142.53	-138.02	-1,326.51	1,474.49	1,432.45	42.04	35.075	
5,900.00	5,893.36	6,226.31	6,168.66	20.67	23.53	142.54	-140.05	-1,316.99	1,468.51	1,426.11	42.40	34.634	
5,950.00	5,943.16	6,275.95	6,217.34	20.85	23.74	142.56	-142.08	-1,307.48	1,462.53	1,419.77	42.76	34.201	
6,000.00	5,992.95	6,325.59	6,266.01	21.03	23.96	142.58	-144.11	-1,297.97	1,456.55	1,413.42	43.12	33.775	
6,050.00	6,042.75	6,375.23	6,314.69	21.21	24.18	142.59	-146.14	-1,288.45	1,450.57	1,407.08	43.49	33.356	
6,100.00	6,092.54	6,424.87	6,363.37	21.38	24.39	142.61	-148.17	-1,278.94	1,444.59	1,400.74	43.85	32.944	
6,150.00	6,142.34	6,474.51	6,412.04	21.56	24.61	142.63	-150.20	-1,269.42	1,438.61	1,394.39	44.21	32.538	
6,200.00	6,192.13	6,524.15	6,460.72	21.74	24.83	142.64	-152.23	-1,259.91	1,432.63	1,388.05	44.58	32.138	
6,250.00	6,241.93	6,573.79	6,509.40	21.92	25.05	142.66	-154.26	-1,250.40	1,426.65	1,381.71	44.94	31.745	
6,300.00	6,291.72	6,623.43	6,558.07	22.10	25.27	142.68	-156.29	-1,240.88	1,420.67	1,375.36	45.30	31.358	
6,350.00	6,341.52	6,673.07	6,606.75	22.28	25.48	142.70	-158.32	-1,231.37	1,414.69	1,369.02	45.67	30.977	
6,400.00	6,391.32	6,722.71	6,655.43	22.46	25.70	142.72	-160.35	-1,221.86	1,408.71	1,362.67	46.03	30.602	
6,450.00	6,441.11	6,772.35	6,704.10	22.64	25.92	142.73	-162.38	-1,212.34	1,402.73	1,356.33	46.40	30.233	
6,500.00	6,490.91	6,821.99	6,752.78	22.82	26.14	142.75	-164.41	-1,202.83	1,396.75	1,349.99	46.76	29.869	
6,550.00	6,540.70	6,871.62	6,801.46	23.00	26.36	142.77	-166.44	-1,193.32	1,390.77	1,343.64	47.13	29.511	
6,600.00	6,590.50	6,921.26	6,850.13	23.18	26.58	142.79	-168.47	-1,183.80	1,384.79	1,337.30	47.49	29.158	
6,650.00	6,640.29	6,970.90	6,898.81	23.36	26.80	142.81	-170.50	-1,174.29	1,378.81	1,330.95	47.86	28.811	
6,700.00	6,690.09	7,020.54	6,947.49	23.54	27.02	142.83	-172.53	-1,164.77	1,372.83	1,324.61	48.22	28.469	
6,750.00	6,739.88	7,070.18	6,996.16	23.72	27.23	142.84	-174.56	-1,155.26	1,366.85	1,318.27	48.59	28.131	
6,800.00	6,789.68	7,119.82	7,044.84	23.90	27.45	142.86	-176.59	-1,145.75	1,360.88	1,311.92	48.95	27.799	
6,850.00	6,839.48	7,169.46	7,093.52	24.09	27.67	142.88	-178.62	-1,136.23	1,354.90	1,305.58	49.32	27.471	
6,900.00	6,889.27	7,219.10	7,142.19	24.27	27.89	142.90	-180.65	-1,126.72	1,348.92	1,299.23	49.69	27.149	
6,950.00	6,939.07	7,268.74	7,190.87	24.45	28.11	142.92	-182.68	-1,117.21	1,342.94	1,292.89	50.05	26.831	
7,000.00	6,988.86	7,318.38	7,239.55	24.63	28.33	142.94	-184.71	-1,107.69	1,336.96	1,286.54	50.42	26.517	
7,050.00	7,038.66	7,368.02	7,288.23	24.81	28.55	142.96	-186.74	-1,098.18	1,330.99	1,280.20	50.79	26.208	
7,100.00	7,088.45	7,417.66	7,336.90	24.99	28.77	142.98	-188.77	-1,088.67	1,325.01	1,273.86	51.15	25.903	
7,150.00	7,138.25	7,467.30	7,385.58	25.18	28.99	143.00	-190.80	-1,079.15	1,319.03	1,267.51	51.52	25.602	
7,200.00	7,188.04	7,516.93	7,434.26	25.36	29.21	143.02	-192.83	-1,069.64	1,313.05	1,261.17	51.89	25.306	
7,250.00	7,237.84	7,566.57	7,482.93	25.54	29.43	143.04	-194.86	-1,060.12	1,307.08	1,254.82	52.25	25.014	
7,300.00	7,287.64	7,616.21	7,531.61	25.72	29.65	143.06	-196.89	-1,050.61	1,301.10	1,248.48	52.62	24.726	
7,350.00	7,337.43	7,665.85	7,580.29	25.90	29.88	143.08	-198.92	-1,041.10	1,295.12	1,242.13	52.99	24.441	
7,400.00	7,387.23	7,715.49	7,628.96	26.09	30.10	143.11	-200.95	-1,031.58	1,289.15	1,235.79	53.36	24.161	
7,450.00	7,437.02	7,765.13	7,677.64	26.27	30.32	143.13	-202.98	-1,022.07	1,283.17	1,229.45	53.72	23.884	
7,500.00	7,486.82	7,814.77	7,726.32	26.45	30.54	143.15	-205.01	-1,012.56	1,277.19	1,223.10	54.09	23.611	
7,550.00	7,536.61	7,864.41	7,774.99	26.64	30.76	143.17	-207.04	-1,003.04	1,271.22	1,216.76	54.46	23.342	
7,600.00	7,586.41	7,914.05	7,823.67	26.82	30.98	143.19	-209.07	-993.53	1,265.24	1,210.41	54.83	23.076	
7,650.00	7,636.20	7,963.69	7,872.35	27.00	31.20	143.21	-211.10	-984.02	1,259.27	1,204.07	55.20	22.814	
7,700.00	7,686.00	8,013.33	7,921.02	27.19	31.42	143.24	-213.13	-974.50	1,253.29	1,197.73	55.56	22.555	
7,750.00	7,735.79	8,062.97	7,969.70	27.37	31.64	143.26	-215.16	-964.99	1,247.32	1,191.38	55.93	22.300	
7,800.00	7,785.59	8,112.61	8,018.38	27.55	31.87	143.28	-217.19	-955.47	1,241.34	1,185.04	56.30	22.048	
7,850.00	7,835.39	8,162.25	8,067.05	27.74	32.09	143.31	-219.22	-945.96	1,235.37	1,178.70	56.67	21.799	
7,900.00	7,885.18	8,211.88	8,115.73	27.92	32.31	143.33	-221.25	-936.45	1,229.39	1,172.35	57.04	21.553	
7,950.00	7,934.98	8,261.52	8,164.41	28.10	32.53	143.35	-223.28	-926.93	1,223.42	1,166.01	57.41	21.311	
8,000.00	7,984.77	8,311.16	8,213.08	28.29	32.75	143.38	-225.31	-917.42	1,217.44	1,159.67	57.78	21.071	
8,050.00	8,034.57	8,360.80	8,261.76	28.47	32.98	143.40	-227.34	-907.91	1,211.47	1,153.32	58.15	20.835	
8,100.00	8,084.36	8,410.44	8,310.44	28.65	33.20	143.42	-229.37	-898.39	1,205.50	1,146.98	58.52	20.601	
8,150.00	8,134.16	8,460.08	8,359.11	28.84	33.42	143.45	-231.40	-888.88	1,199.52	1,140.64	58.88	20.371	
8,200.00	8,183.95	8,509.72	8,407.79	29.02	33.64	143.47	-233.43	-879.37	1,193.55	1,134.29	59.25	20.143	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36-25 State Fed Com 230H - Wellbore #1 - Permit Plan 1 — **Offset Site Error:** 0.00 ft

Survey Program: 0-MWD+HDGM — **Offset Well Error:** 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
8,250.00	8,233.75	8,559.36	8,456.47	29.21	33.86	143.50	-235.46	-869.85	1,187.58	1,127.95	59.62	19.918	
8,300.00	8,283.55	8,609.00	8,505.14	29.39	34.09	143.52	-237.49	-860.34	1,181.60	1,121.61	59.99	19.696	
8,350.00	8,333.34	8,658.64	8,553.82	29.58	34.31	143.55	-239.52	-850.82	1,175.63	1,115.27	60.36	19.476	
8,400.00	8,383.14	8,708.28	8,602.50	29.76	34.53	143.58	-241.55	-841.31	1,169.66	1,108.93	60.73	19.259	
8,450.00	8,432.93	8,757.92	8,651.17	29.94	34.75	143.60	-243.58	-831.80	1,163.69	1,102.58	61.10	19.045	
8,500.00	8,482.73	8,807.56	8,699.85	30.13	34.98	143.63	-245.61	-822.28	1,157.71	1,096.24	61.47	18.833	
8,550.00	8,532.52	8,857.19	8,748.53	30.31	35.20	143.65	-247.64	-812.77	1,151.74	1,089.90	61.84	18.624	
8,600.00	8,582.32	8,906.83	8,797.20	30.50	35.42	143.68	-249.67	-803.26	1,145.77	1,083.56	62.21	18.417	
8,650.00	8,632.11	8,956.47	8,845.88	30.68	35.64	143.71	-251.70	-793.74	1,139.80	1,077.22	62.58	18.213	
8,700.00	8,681.91	9,006.11	8,894.56	30.87	35.87	143.74	-253.73	-784.23	1,133.83	1,070.88	62.95	18.011	
8,750.00	8,731.71	9,055.75	8,943.23	31.05	36.09	143.76	-255.76	-774.72	1,127.86	1,064.54	63.32	17.812	
8,800.00	8,781.50	9,105.39	8,991.91	31.24	36.31	143.79	-257.79	-765.20	1,121.89	1,058.20	63.69	17.614	
8,850.00	8,831.30	9,155.03	9,040.59	31.42	36.54	143.82	-259.82	-755.69	1,115.92	1,051.86	64.06	17.419	
8,900.00	8,881.09	9,204.67	9,089.26	31.61	36.76	143.85	-261.85	-746.17	1,109.95	1,045.51	64.43	17.227	
8,950.00	8,930.89	9,254.31	9,137.94	31.79	36.98	143.88	-263.88	-736.66	1,103.98	1,039.17	64.80	17.036	
9,000.00	8,980.68	9,303.95	9,186.62	31.98	37.20	143.91	-265.91	-727.15	1,098.01	1,032.84	65.17	16.848	
9,050.00	9,030.48	9,353.59	9,235.29	32.16	37.43	143.94	-267.94	-717.63	1,092.04	1,026.50	65.54	16.661	
9,100.00	9,080.27	9,403.23	9,283.97	32.35	37.65	143.97	-269.97	-708.12	1,086.07	1,020.16	65.91	16.477	
9,150.00	9,130.07	9,452.87	9,332.65	32.54	37.87	144.00	-272.00	-698.61	1,080.10	1,013.82	66.28	16.295	
9,200.00	9,179.87	9,502.51	9,381.33	32.72	38.10	144.03	-274.03	-689.09	1,074.13	1,007.48	66.65	16.115	
9,250.00	9,229.66	9,552.14	9,430.00	32.91	38.32	144.06	-276.06	-679.58	1,068.17	1,001.14	67.02	15.937	
9,300.00	9,279.46	9,601.78	9,478.68	33.09	38.54	144.09	-278.09	-670.07	1,062.20	994.80	67.40	15.761	
9,350.00	9,329.27	9,651.41	9,527.34	33.28	38.77	144.07	-280.12	-660.55	1,056.08	988.32	67.77	15.584	
9,400.00	9,379.13	9,700.96	9,575.94	33.46	38.99	144.02	-282.15	-651.06	1,049.46	981.32	68.14	15.402	
9,450.00	9,429.04	9,750.49	9,624.50	33.64	39.21	143.95	-284.08	-641.57	1,042.31	973.80	68.51	15.215	
9,500.00	9,478.98	9,799.93	9,673.00	33.82	39.43	144.01	-283.05	-632.10	1,034.63	965.77	68.86	15.024	
9,550.00	9,528.95	9,848.58	9,720.47	34.00	39.63	144.29	-277.89	-622.86	1,026.46	957.25	69.20	14.832	
9,600.00	9,578.94	9,895.87	9,766.05	34.18	39.82	144.75	-268.96	-614.01	1,017.85	948.32	69.53	14.638	
9,650.00	9,628.93	9,941.34	9,809.05	34.35	39.98	145.40	-256.79	-605.68	1,008.92	939.07	69.86	14.443	
9,700.00	9,678.93	9,984.61	9,848.97	34.52	40.12	-87.79	-242.02	-597.96	999.99	929.82	70.17	14.250	
9,750.00	9,728.93	10,025.38	9,885.49	34.69	40.25	-86.80	-225.33	-590.92	991.57	921.08	70.49	14.067	
9,800.00	9,778.93	10,063.50	9,918.49	34.86	40.36	-85.72	-207.37	-584.57	983.85	913.05	70.80	13.897	
9,850.00	9,828.93	10,098.90	9,948.04	35.03	40.45	-84.60	-188.72	-578.90	977.02	905.93	71.09	13.743	
9,900.00	9,878.93	10,131.63	9,974.31	35.20	40.53	-83.45	-169.86	-573.87	971.29	899.92	71.37	13.610	
9,950.00	9,928.93	10,161.79	9,997.54	35.38	40.60	-82.32	-151.15	-569.43	966.83	895.22	71.60	13.503	
10,000.00	9,978.93	10,189.52	10,018.02	35.55	40.66	-81.21	-132.88	-565.53	963.81	892.02	71.79	13.425	
10,050.00	10,028.90	10,215.73	10,036.57	35.72	40.70	-79.98	-114.70	-562.01	962.11	890.19	71.92	13.377	
10,100.00	10,078.54	10,241.87	10,054.23	35.88	40.75	-79.04	-95.72	-558.66	961.26	889.26	71.99	13.352	
10,134.60	10,112.51	10,259.94	10,065.93	35.99	40.78	-78.38	-82.14	-556.44	961.09	889.09	72.00	13.348 CC	
10,150.00	10,127.49	10,267.97	10,071.00	36.04	40.79	-78.09	-75.98	-555.49	961.12	889.12	72.00	13.349	
10,200.00	10,175.37	10,294.05	10,086.86	36.19	40.83	-77.12	-55.50	-552.50	961.61	889.67	71.94	13.366	
10,250.00	10,221.81	10,320.11	10,101.77	36.33	40.86	-76.17	-34.31	-549.70	962.62	890.79	71.83	13.402	
10,300.00	10,266.47	10,350.00	10,117.70	36.45	40.89	-75.11	-9.20	-546.72	964.05	892.35	71.69	13.447	
10,350.00	10,309.00	10,372.21	10,128.69	36.57	40.91	-74.31	9.99	-544.67	965.76	894.32	71.44	13.519	
10,400.00	10,349.08	10,400.00	10,141.40	36.68	40.94	-73.40	34.59	-542.32	967.70	896.49	71.20	13.590	
10,450.00	10,386.41	10,424.31	10,151.55	36.77	40.96	-72.63	56.60	-540.45	969.75	898.84	70.91	13.675	
10,500.00	10,420.70	10,450.00	10,161.27	36.85	40.98	-71.88	80.31	-538.68	971.83	901.21	70.62	13.761	
10,550.00	10,451.68	10,476.44	10,170.17	36.92	40.99	-71.18	105.15	-537.07	973.88	903.53	70.34	13.844	
10,600.00	10,479.13	10,500.00	10,177.15	36.98	41.01	-70.60	127.62	-535.83	975.80	905.75	70.05	13.929	
10,650.00	10,502.84	10,528.59	10,184.39	37.04	41.02	-70.03	155.24	-534.56	977.54	907.70	69.84	13.997	
10,700.00	10,522.62	10,550.00	10,188.93	37.11	41.03	-69.64	176.15	-533.78	979.07	909.46	69.61	14.064	
10,750.00	10,538.32	10,580.76	10,194.09	37.18	41.04	-69.24	206.46	-532.93	980.28	910.77	69.50	14.104	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36-25 State Fed Com 230H - Wellbore #1 - Permit Plan 1

Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM

Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
10,800.00	10,549.83	10,600.00	10,196.51	37.26	41.05	-69.01	225.54	-532.56	981.24	911.84	69.40	14.140	
10,850.00	10,557.06	10,632.96	10,199.18	37.36	41.06	-68.82	258.39	-532.21	981.76	912.35	69.42	14.143	
10,900.00	10,559.94	10,659.06	10,199.98	37.46	41.07	-68.76	284.47	-532.19	981.98	912.50	69.48	14.133	
10,950.00	10,560.00	10,704.64	10,200.00	37.57	41.10	-68.76	330.05	-532.43	981.98	912.34	69.64	14.102	
11,000.00	10,560.00	10,754.64	10,200.00	37.69	41.13	-68.76	380.05	-532.69	981.98	912.16	69.82	14.064	
11,050.00	10,560.00	10,804.64	10,200.00	37.83	41.17	-68.76	430.05	-532.95	981.99	911.95	70.03	14.021	
11,100.00	10,560.00	10,854.64	10,200.00	37.98	41.23	-68.76	480.05	-533.21	981.99	911.72	70.27	13.974	
11,150.00	10,560.00	10,904.64	10,200.00	38.16	41.30	-68.76	530.05	-533.48	981.99	911.46	70.54	13.922	
11,200.00	10,560.00	10,954.64	10,200.00	38.33	41.37	-68.76	580.05	-533.74	981.99	911.17	70.83	13.864	
11,250.00	10,560.00	11,004.64	10,200.00	38.53	41.47	-68.76	630.05	-534.00	982.00	910.85	71.15	13.802	
11,300.00	10,560.00	11,054.64	10,200.00	38.73	41.57	-68.76	680.05	-534.26	982.00	910.51	71.49	13.736	
11,350.00	10,560.00	11,104.64	10,200.00	38.95	41.70	-68.76	730.04	-534.52	982.00	910.14	71.86	13.666	
11,400.00	10,560.00	11,154.64	10,200.00	39.18	41.83	-68.76	780.04	-534.78	982.00	909.76	72.25	13.592	
11,450.00	10,560.00	11,204.64	10,200.00	39.42	41.99	-68.76	830.04	-535.05	982.01	909.34	72.67	13.514	
11,500.00	10,560.00	11,254.64	10,200.00	39.67	42.15	-68.76	880.04	-535.31	982.01	908.90	73.11	13.433	
11,550.00	10,560.00	11,304.64	10,200.00	39.94	42.34	-68.76	930.04	-535.57	982.01	908.44	73.57	13.348	
11,600.00	10,560.00	11,354.64	10,200.00	40.21	42.54	-68.76	980.04	-535.83	982.01	907.96	74.06	13.260	
11,650.00	10,560.00	11,404.64	10,200.00	40.51	42.76	-68.76	1,030.04	-536.09	982.02	907.45	74.57	13.169	
11,700.00	10,560.00	11,454.64	10,200.00	40.80	42.99	-68.76	1,080.04	-536.36	982.02	906.92	75.10	13.076	
11,750.00	10,560.00	11,504.64	10,200.00	41.11	43.24	-68.76	1,130.04	-536.62	982.02	906.37	75.65	12.980	
11,800.00	10,560.00	11,554.64	10,200.00	41.43	43.50	-68.76	1,180.04	-536.88	982.03	905.80	76.23	12.883	
11,850.00	10,560.00	11,604.64	10,200.00	41.76	43.77	-68.76	1,230.04	-537.14	982.03	905.20	76.83	12.783	
11,900.00	10,560.00	11,654.64	10,200.00	42.10	44.06	-68.76	1,280.04	-537.40	982.03	904.59	77.44	12.681	
11,950.00	10,560.00	11,704.64	10,200.00	42.45	44.36	-68.76	1,330.04	-537.66	982.03	903.96	78.08	12.578	
12,000.00	10,560.00	11,754.64	10,200.00	42.80	44.68	-68.76	1,380.04	-537.93	982.04	903.30	78.73	12.473	
12,050.00	10,560.00	11,804.64	10,200.00	43.18	45.00	-68.76	1,430.04	-538.19	982.04	902.63	79.41	12.367	
12,100.00	10,560.00	11,854.64	10,200.00	43.55	45.34	-68.76	1,480.03	-538.45	982.04	901.94	80.10	12.260	
12,150.00	10,560.00	11,904.64	10,200.00	43.94	45.69	-68.76	1,530.03	-538.71	982.04	901.23	80.81	12.153	
12,200.00	10,560.00	11,954.64	10,200.00	44.33	46.05	-68.76	1,580.03	-538.97	982.05	900.51	81.54	12.044	
12,250.00	10,560.00	12,004.64	10,200.00	44.73	46.41	-68.76	1,630.03	-539.23	982.05	899.77	82.28	11.935	
12,300.00	10,560.00	12,054.64	10,200.00	45.14	46.79	-68.76	1,680.03	-539.50	982.05	899.01	83.04	11.826	
12,350.00	10,560.00	12,104.64	10,200.00	45.56	47.18	-68.76	1,730.03	-539.76	982.05	898.23	83.82	11.716	
12,400.00	10,560.00	12,154.64	10,200.00	45.99	47.58	-68.76	1,780.03	-540.02	982.06	897.44	84.61	11.607	
12,450.00	10,560.00	12,204.64	10,200.00	46.42	47.98	-68.76	1,830.03	-540.28	982.06	896.64	85.42	11.497	
12,500.00	10,560.00	12,254.64	10,200.00	46.86	48.40	-68.76	1,880.03	-540.54	982.06	895.82	86.24	11.387	
12,550.00	10,560.00	12,304.64	10,200.00	47.31	48.82	-68.76	1,930.03	-540.81	982.06	894.98	87.08	11.278	
12,600.00	10,560.00	12,354.64	10,200.00	47.76	49.25	-68.76	1,980.03	-541.07	982.07	894.14	87.93	11.169	
12,650.00	10,560.00	12,404.64	10,200.00	48.23	49.68	-68.76	2,030.03	-541.33	982.07	893.27	88.80	11.060	
12,700.00	10,560.00	12,454.64	10,200.00	48.69	50.13	-68.76	2,080.03	-541.59	982.07	892.40	89.67	10.952	
12,750.00	10,560.00	12,504.64	10,200.00	49.17	50.58	-68.76	2,130.03	-541.85	982.07	891.51	90.56	10.844	
12,800.00	10,560.00	12,554.64	10,200.00	49.65	51.04	-68.76	2,180.03	-542.11	982.08	890.61	91.47	10.737	
12,850.00	10,560.00	12,604.64	10,200.00	50.14	51.50	-68.76	2,230.02	-542.38	982.08	889.70	92.38	10.631	
12,900.00	10,560.00	12,654.64	10,200.00	50.62	51.97	-68.76	2,280.02	-542.64	982.08	888.78	93.31	10.525	
12,950.00	10,560.00	12,704.64	10,200.00	51.12	52.45	-68.76	2,330.02	-542.90	982.09	887.84	94.24	10.421	
13,000.00	10,560.00	12,754.64	10,200.00	51.63	52.93	-68.76	2,380.02	-543.16	982.09	886.90	95.19	10.317	
13,050.00	10,560.00	12,804.64	10,200.00	52.14	53.42	-68.76	2,430.02	-543.42	982.09	885.94	96.15	10.214	
13,100.00	10,560.00	12,854.64	10,200.00	52.65	53.91	-68.76	2,480.02	-543.69	982.09	884.97	97.12	10.112	
13,150.00	10,560.00	12,904.64	10,200.00	53.17	54.41	-68.76	2,530.02	-543.95	982.10	883.99	98.10	10.011	
13,200.00	10,560.00	12,954.64	10,200.00	53.69	54.92	-68.76	2,580.02	-544.21	982.10	883.01	99.09	9.911	
13,250.00	10,560.00	13,004.64	10,200.00	54.22	55.42	-68.76	2,630.02	-544.47	982.10	882.01	100.09	9.812	
13,300.00	10,560.00	13,054.64	10,200.00	54.75	55.94	-68.76	2,680.02	-544.73	982.10	881.01	101.10	9.714	
13,350.00	10,560.00	13,104.64	10,200.00	55.29	56.46	-68.76	2,730.02	-544.99	982.11	879.99	102.11	9.618	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36-25 State Fed Com 230H - Wellbore #1 - Permit Plan 1 — Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM — Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
13,400.00	10,560.00	13,154.64	10,200.00	55.83	56.98	-68.76	2,780.02	-545.26	982.11	878.97	103.14	9.522	
13,450.00	10,560.00	13,204.64	10,200.00	56.38	57.51	-68.76	2,830.02	-545.52	982.11	877.94	104.17	9.428	
13,500.00	10,560.00	13,254.64	10,200.00	56.92	58.05	-68.76	2,880.02	-545.78	982.11	876.90	105.21	9.334	
13,550.00	10,560.00	13,304.64	10,200.00	57.48	58.58	-68.76	2,930.01	-546.04	982.12	875.85	106.27	9.242	
13,600.00	10,560.00	13,354.64	10,200.00	58.04	59.13	-68.76	2,980.01	-546.30	982.12	874.80	107.32	9.151	
13,650.00	10,560.00	13,404.64	10,200.00	58.60	59.67	-68.76	3,030.01	-546.57	982.12	873.73	108.39	9.061	
13,700.00	10,560.00	13,454.64	10,200.00	59.16	60.22	-68.76	3,080.01	-546.83	982.12	872.67	109.46	8.972	
13,750.00	10,560.00	13,504.64	10,200.00	59.73	60.77	-68.76	3,130.01	-547.09	982.13	871.59	110.54	8.885	
13,800.00	10,560.00	13,554.64	10,200.00	60.30	61.33	-68.76	3,180.01	-547.35	982.13	870.51	111.62	8.799	
13,850.00	10,560.00	13,604.64	10,200.00	60.88	61.89	-68.76	3,230.01	-547.61	982.13	869.42	112.72	8.713	
13,900.00	10,560.00	13,654.64	10,200.00	61.46	62.46	-68.76	3,280.01	-547.87	982.14	868.32	113.82	8.629	
13,950.00	10,560.00	13,704.64	10,200.00	62.04	63.02	-68.76	3,330.01	-548.14	982.14	867.22	114.92	8.546	
14,000.00	10,560.00	13,754.64	10,200.00	62.62	63.59	-68.76	3,380.01	-548.40	982.14	866.11	116.03	8.464	
14,050.00	10,560.00	13,804.64	10,200.00	63.21	64.17	-68.76	3,430.01	-548.66	982.14	864.99	117.15	8.384	
14,100.00	10,560.00	13,854.64	10,200.00	63.80	64.74	-68.76	3,480.01	-548.92	982.15	863.87	118.27	8.304	
14,150.00	10,560.00	13,904.64	10,200.00	64.39	65.32	-68.76	3,530.01	-549.18	982.15	862.75	119.40	8.226	
14,200.00	10,560.00	13,954.64	10,200.00	64.99	65.91	-68.76	3,580.01	-549.45	982.15	861.62	120.53	8.148	
14,250.00	10,560.00	14,004.64	10,200.00	65.59	66.49	-68.76	3,630.01	-549.71	982.15	860.48	121.67	8.072	
14,300.00	10,560.00	14,054.64	10,200.00	66.19	67.08	-68.76	3,680.00	-549.97	982.16	859.34	122.82	7.997	
14,350.00	10,560.00	14,104.64	10,200.00	66.79	67.67	-68.76	3,730.00	-550.23	982.16	858.19	123.97	7.923	
14,400.00	10,560.00	14,154.64	10,200.00	67.40	68.27	-68.76	3,780.00	-550.49	982.16	857.04	125.12	7.850	
14,450.00	10,560.00	14,204.64	10,200.00	68.01	68.86	-68.76	3,830.00	-550.75	982.16	855.88	126.28	7.778	
14,500.00	10,560.00	14,254.64	10,200.00	68.62	69.46	-68.76	3,880.00	-551.02	982.17	854.72	127.44	7.707	
14,550.00	10,560.00	14,304.64	10,200.00	69.23	70.07	-68.76	3,930.00	-551.28	982.17	853.56	128.61	7.637	
14,600.00	10,560.00	14,354.64	10,200.00	69.85	70.67	-68.76	3,980.00	-551.54	982.17	852.39	129.78	7.568	
14,650.00	10,560.00	14,404.64	10,200.00	70.47	71.28	-68.76	4,030.00	-551.80	982.17	851.22	130.96	7.500	
14,700.00	10,560.00	14,454.64	10,200.00	71.09	71.89	-68.76	4,080.00	-552.06	982.18	850.04	132.14	7.433	
14,750.00	10,560.00	14,504.64	10,200.00	71.71	72.50	-68.76	4,130.00	-552.32	982.18	848.86	133.32	7.367	
14,800.00	10,560.00	14,554.64	10,200.00	72.33	73.11	-68.76	4,180.00	-552.59	982.18	847.67	134.51	7.302	
14,850.00	10,560.00	14,604.64	10,200.00	72.96	73.72	-68.76	4,230.00	-552.85	982.18	846.48	135.70	7.238	
14,900.00	10,560.00	14,654.64	10,200.00	73.58	74.34	-68.76	4,280.00	-553.11	982.19	845.29	136.90	7.175	
14,950.00	10,560.00	14,704.64	10,200.00	74.21	74.96	-68.76	4,330.00	-553.37	982.19	844.09	138.10	7.112	
15,000.00	10,560.00	14,754.64	10,200.00	74.84	75.58	-68.76	4,379.99	-553.63	982.19	842.89	139.30	7.051	
15,050.00	10,560.00	14,804.64	10,200.00	75.48	76.20	-68.76	4,429.99	-553.90	982.20	841.69	140.51	6.990	
15,100.00	10,560.00	14,854.64	10,200.00	76.11	76.83	-68.76	4,479.99	-554.16	982.20	840.48	141.71	6.931	
15,150.00	10,560.00	14,904.64	10,200.00	76.75	77.46	-68.76	4,529.99	-554.42	982.20	839.27	142.93	6.872	
15,200.00	10,560.00	14,954.64	10,200.00	77.39	78.09	-68.76	4,579.99	-554.68	982.20	838.06	144.14	6.814	
15,250.00	10,560.00	15,004.64	10,200.00	78.03	78.72	-68.76	4,629.99	-554.94	982.21	836.84	145.36	6.757	
15,300.00	10,560.00	15,054.64	10,200.00	78.67	79.35	-68.76	4,679.99	-555.20	982.21	835.62	146.58	6.701	
15,350.00	10,560.00	15,104.64	10,200.00	79.31	79.98	-68.76	4,729.99	-555.47	982.21	834.40	147.81	6.645	
15,400.00	10,560.00	15,154.64	10,200.00	79.95	80.62	-68.76	4,779.99	-555.73	982.21	833.18	149.04	6.590	
15,450.00	10,560.00	15,204.64	10,200.00	80.60	81.25	-68.76	4,829.99	-555.99	982.22	831.95	150.27	6.537	
15,500.00	10,560.00	15,254.64	10,200.00	81.25	81.89	-68.76	4,879.99	-556.25	982.22	830.72	151.50	6.483	
15,550.00	10,560.00	15,304.64	10,200.00	81.89	82.53	-68.76	4,929.99	-556.51	982.22	829.49	152.73	6.431	
15,600.00	10,560.00	15,354.64	10,200.00	82.54	83.17	-68.76	4,979.99	-556.78	982.22	828.25	153.97	6.379	
15,650.00	10,560.00	15,404.64	10,200.00	83.20	83.81	-68.76	5,029.99	-557.04	982.23	827.01	155.21	6.328	
15,700.00	10,560.00	15,454.64	10,200.00	83.85	84.46	-68.76	5,079.99	-557.30	982.23	825.77	156.46	6.278	
15,750.00	10,560.00	15,504.64	10,200.00	84.50	85.10	-68.76	5,129.98	-557.56	982.23	824.53	157.70	6.228	
15,800.00	10,560.00	15,554.64	10,200.00	85.15	85.75	-68.76	5,179.98	-557.82	982.23	823.28	158.95	6.180	
15,850.00	10,560.00	15,604.64	10,200.00	85.81	86.40	-68.76	5,229.98	-558.08	982.24	822.04	160.20	6.131	
15,900.00	10,560.00	15,654.64	10,200.00	86.47	87.05	-68.76	5,279.98	-558.35	982.24	820.79	161.45	6.084	
15,950.00	10,560.00	15,704.64	10,200.00	87.13	87.70	-68.76	5,329.98	-558.61	982.24	819.54	162.71	6.037	

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36-25 State Fed Com 230H - Wellbore #1 - Permit Plan 1 — Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM — Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
16,000.00	10,560.00	15,754.64	10,200.00	87.78	88.35	-68.76	5,379.98	-558.87	982.24	818.28	163.96	5.991	
16,050.00	10,560.00	15,804.64	10,200.00	88.45	89.00	-68.76	5,429.98	-559.13	982.25	817.02	165.22	5.945	
16,100.00	10,560.00	15,854.64	10,200.00	89.11	89.66	-68.76	5,479.98	-559.39	982.25	815.77	166.48	5.900	
16,150.00	10,560.00	15,904.64	10,200.00	89.77	90.31	-68.76	5,529.98	-559.66	982.25	814.51	167.75	5.856	
16,200.00	10,560.00	15,954.64	10,200.00	90.43	90.97	-68.76	5,579.98	-559.92	982.26	813.24	169.01	5.812	
16,250.00	10,560.00	16,004.64	10,200.00	91.10	91.63	-68.76	5,629.98	-560.18	982.26	811.98	170.28	5.769	
16,300.00	10,560.00	16,054.64	10,200.00	91.76	92.28	-68.76	5,679.98	-560.44	982.26	810.71	171.55	5.726	
16,350.00	10,560.00	16,104.64	10,200.00	92.43	92.94	-68.76	5,729.98	-560.70	982.26	809.45	172.82	5.684	
16,400.00	10,560.00	16,154.64	10,200.00	93.10	93.60	-68.76	5,779.98	-560.96	982.27	808.18	174.09	5.642	
16,450.00	10,560.00	16,204.64	10,200.00	93.76	94.27	-68.76	5,829.98	-561.23	982.27	806.91	175.36	5.601	
16,500.00	10,560.00	16,254.64	10,200.00	94.43	94.93	-68.76	5,879.97	-561.49	982.27	805.63	176.64	5.561	
16,550.00	10,560.00	16,304.64	10,200.00	95.10	95.59	-68.76	5,929.97	-561.75	982.27	804.36	177.92	5.521	
16,600.00	10,560.00	16,354.64	10,200.00	95.77	96.26	-68.76	5,979.97	-562.01	982.28	803.08	179.19	5.482	
16,650.00	10,560.00	16,404.64	10,200.00	96.44	96.92	-68.76	6,029.97	-562.27	982.28	801.80	180.47	5.443	
16,700.00	10,560.00	16,454.64	10,200.00	97.12	97.59	-68.76	6,079.97	-562.53	982.28	800.52	181.76	5.404	
16,750.00	10,560.00	16,504.64	10,200.00	97.79	98.25	-68.76	6,129.97	-562.80	982.28	799.24	183.04	5.366	
16,800.00	10,560.00	16,554.64	10,200.00	98.46	98.92	-68.76	6,179.97	-563.06	982.29	797.96	184.33	5.329	
16,850.00	10,560.00	16,604.64	10,200.00	99.14	99.59	-68.76	6,229.97	-563.32	982.29	796.68	185.61	5.292	
16,900.00	10,560.00	16,654.64	10,200.00	99.81	100.26	-68.76	6,279.97	-563.58	982.29	795.39	186.90	5.256	
16,950.00	10,560.00	16,704.64	10,200.00	100.49	100.93	-68.76	6,329.97	-563.84	982.29	794.11	188.19	5.220	
17,000.00	10,560.00	16,754.64	10,200.00	101.17	101.60	-68.76	6,379.97	-564.11	982.30	792.82	189.48	5.184	
17,050.00	10,560.00	16,804.64	10,200.00	101.85	102.27	-68.76	6,429.97	-564.37	982.30	791.53	190.77	5.149	
17,100.00	10,560.00	16,854.64	10,200.00	102.52	102.95	-68.76	6,479.97	-564.63	982.30	790.24	192.07	5.114	
17,150.00	10,560.00	16,904.64	10,200.00	103.20	103.62	-68.76	6,529.97	-564.89	982.31	788.94	193.36	5.080	
17,200.00	10,560.00	16,954.64	10,200.00	103.88	104.30	-68.76	6,579.96	-565.15	982.31	787.65	194.66	5.046	
17,250.00	10,560.00	17,004.64	10,200.00	104.56	104.97	-68.76	6,629.96	-565.41	982.31	786.36	195.95	5.013	
17,300.00	10,560.00	17,054.64	10,200.00	105.24	105.65	-68.76	6,679.96	-565.68	982.31	785.06	197.25	4.980	Alert
17,350.00	10,560.00	17,104.64	10,200.00	105.93	106.32	-68.76	6,729.96	-565.94	982.32	783.76	198.55	4.947	Alert
17,400.00	10,560.00	17,154.64	10,200.00	106.61	107.00	-68.76	6,779.96	-566.20	982.32	782.47	199.85	4.915	Alert
17,450.00	10,560.00	17,204.64	10,200.00	107.29	107.68	-68.76	6,829.96	-566.46	982.32	781.17	201.15	4.883	Alert
17,500.00	10,560.00	17,254.64	10,200.00	107.97	108.36	-68.76	6,879.96	-566.72	982.32	779.87	202.46	4.852	Alert
17,550.00	10,560.00	17,304.64	10,200.00	108.66	109.03	-68.76	6,929.96	-566.99	982.33	778.56	203.76	4.821	Alert
17,600.00	10,560.00	17,354.64	10,200.00	109.34	109.71	-68.76	6,979.96	-567.25	982.33	777.26	205.07	4.790	Alert
17,650.00	10,560.00	17,404.64	10,200.00	110.03	110.39	-68.76	7,029.96	-567.51	982.33	775.96	206.37	4.760	Alert
17,700.00	10,560.00	17,454.64	10,200.00	110.71	111.07	-68.76	7,079.96	-567.77	982.33	774.65	207.68	4.730	Alert
17,750.00	10,560.00	17,504.64	10,200.00	111.40	111.76	-68.76	7,129.96	-568.03	982.34	773.35	208.99	4.700	Alert
17,800.00	10,560.00	17,554.64	10,200.00	112.09	112.44	-68.76	7,179.96	-568.29	982.34	772.04	210.30	4.671	Alert
17,850.00	10,560.00	17,604.64	10,200.00	112.77	113.12	-68.76	7,229.96	-568.56	982.34	770.73	211.61	4.642	Alert
17,900.00	10,560.00	17,654.64	10,200.00	113.46	113.80	-68.77	7,279.96	-568.82	982.34	769.42	212.92	4.614	Alert
17,950.00	10,560.00	17,704.64	10,200.00	114.15	114.49	-68.77	7,329.95	-569.08	982.35	768.11	214.23	4.585	Alert
18,000.00	10,560.00	17,754.64	10,200.00	114.84	115.17	-68.77	7,379.95	-569.34	982.35	766.80	215.55	4.558	Alert
18,050.00	10,560.00	17,804.64	10,200.00	115.53	115.86	-68.77	7,429.95	-569.60	982.35	765.49	216.86	4.530	Alert
18,100.00	10,560.00	17,854.64	10,200.00	116.22	116.54	-68.77	7,479.95	-569.87	982.35	764.18	218.17	4.503	Alert
18,150.00	10,560.00	17,904.64	10,200.00	116.91	117.23	-68.77	7,529.95	-570.13	982.36	762.87	219.49	4.476	Alert
18,200.00	10,560.00	17,954.64	10,200.00	117.60	117.91	-68.77	7,579.95	-570.39	982.36	761.55	220.81	4.449	Alert
18,250.00	10,560.00	18,004.64	10,200.00	118.29	118.60	-68.77	7,629.95	-570.65	982.36	760.24	222.13	4.423	Alert
18,300.00	10,560.00	18,054.64	10,200.00	118.98	119.29	-68.77	7,679.95	-570.91	982.37	758.92	223.44	4.396	Alert
18,350.00	10,560.00	18,104.64	10,200.00	119.67	119.98	-68.77	7,729.95	-571.17	982.37	757.60	224.76	4.371	Alert
18,400.00	10,560.00	18,154.64	10,200.00	120.37	120.66	-68.77	7,779.95	-571.44	982.37	756.29	226.08	4.345	Alert
18,450.00	10,560.00	18,204.64	10,200.00	121.06	121.35	-68.77	7,829.95	-571.70	982.37	754.97	227.40	4.320	Alert
18,500.00	10,560.00	18,254.64	10,200.00	121.75	122.04	-68.77	7,879.95	-571.96	982.38	753.65	228.73	4.295	Alert
18,550.00	10,560.00	18,304.64	10,200.00	122.45	122.73	-68.77	7,929.95	-572.22	982.38	752.33	230.05	4.270	Alert

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36-25 State Fed Com 230H - Wellbore #1 - Permit Plan 1 — Offset Site Error: 0.00 ft

Survey Program: 0-MWD+HDGM — Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
18,600.00	10,560.00	18,354.64	10,200.00	123.14	123.42	-68.77	7,979.95	-572.48	982.38	751.01	231.37	4.246	Alert
18,650.00	10,560.00	18,404.64	10,200.00	123.83	124.11	-68.77	8,029.94	-572.75	982.38	749.69	232.70	4.222	Alert
18,700.00	10,560.00	18,454.64	10,200.00	124.53	124.80	-68.77	8,079.94	-573.01	982.39	748.37	234.02	4.198	Alert
18,750.00	10,560.00	18,504.64	10,200.00	125.22	125.50	-68.77	8,129.94	-573.27	982.39	747.04	235.35	4.174	Alert
18,800.00	10,560.00	18,554.64	10,200.00	125.92	126.19	-68.77	8,179.94	-573.53	982.39	745.72	236.67	4.151	Alert
18,850.00	10,560.00	18,604.64	10,200.00	126.62	126.88	-68.77	8,229.94	-573.79	982.39	744.39	238.00	4.128	Alert
18,900.00	10,560.00	18,654.64	10,200.00	127.31	127.57	-68.77	8,279.94	-574.05	982.40	743.07	239.33	4.105	Alert
18,950.00	10,560.00	18,704.64	10,200.00	128.01	128.27	-68.77	8,329.94	-574.32	982.40	741.74	240.65	4.082	Alert
19,000.00	10,560.00	18,754.64	10,200.00	128.71	128.96	-68.77	8,379.94	-574.58	982.40	740.42	241.98	4.060	Alert
19,050.00	10,560.00	18,804.64	10,200.00	129.40	129.65	-68.77	8,429.94	-574.84	982.40	739.09	243.31	4.038	Alert
19,100.00	10,560.00	18,854.64	10,200.00	130.10	130.35	-68.77	8,479.94	-575.10	982.41	737.76	244.64	4.016	Alert
19,150.00	10,560.00	18,904.64	10,200.00	130.80	131.04	-68.77	8,529.94	-575.36	982.41	736.44	245.97	3.994	Alert
19,200.00	10,560.00	18,954.64	10,200.00	131.50	131.74	-68.77	8,579.94	-575.62	982.41	735.11	247.31	3.972	Alert
19,250.00	10,560.00	19,004.64	10,200.00	132.20	132.43	-68.77	8,629.94	-575.89	982.41	733.78	248.64	3.951	Alert
19,300.00	10,560.00	19,054.64	10,200.00	132.89	133.13	-68.77	8,679.94	-576.15	982.42	732.45	249.97	3.930	Alert
19,350.00	10,560.00	19,104.64	10,200.00	133.59	133.82	-68.77	8,729.94	-576.41	982.42	731.12	251.30	3.909	Alert
19,400.00	10,560.00	19,154.64	10,200.00	134.29	134.52	-68.77	8,779.93	-576.67	982.42	729.79	252.64	3.889	Alert
19,450.00	10,560.00	19,204.64	10,200.00	134.99	135.22	-68.77	8,829.93	-576.93	982.43	728.45	253.97	3.868	Alert
19,500.00	10,560.00	19,254.64	10,200.00	135.69	135.91	-68.77	8,879.93	-577.20	982.43	727.12	255.31	3.848	Alert
19,550.00	10,560.00	19,304.64	10,200.00	136.39	136.61	-68.77	8,929.93	-577.46	982.43	725.79	256.64	3.828	Alert
19,600.00	10,560.00	19,354.64	10,200.00	137.10	137.31	-68.77	8,979.93	-577.72	982.43	724.46	257.98	3.808	Alert
19,650.00	10,560.00	19,404.64	10,200.00	137.80	138.01	-68.77	9,029.93	-577.98	982.44	723.12	259.31	3.789	Alert
19,700.00	10,560.00	19,454.64	10,200.00	138.50	138.70	-68.77	9,079.93	-578.24	982.44	721.79	260.65	3.769	Alert
19,750.00	10,560.00	19,504.64	10,200.00	139.20	139.40	-68.77	9,129.93	-578.50	982.44	720.45	261.99	3.750	Alert
19,800.00	10,560.00	19,554.64	10,200.00	139.90	140.10	-68.77	9,179.93	-578.77	982.44	719.12	263.33	3.731	Alert
19,850.00	10,560.00	19,604.64	10,200.00	140.60	140.80	-68.77	9,229.93	-579.03	982.45	717.78	264.67	3.712	Alert
19,900.00	10,560.00	19,654.64	10,200.00	141.31	141.50	-68.77	9,279.93	-579.29	982.45	716.44	266.00	3.693	Alert
19,950.00	10,560.00	19,704.64	10,200.00	142.01	142.20	-68.77	9,329.93	-579.55	982.45	715.11	267.34	3.675	Alert
20,000.00	10,560.00	19,754.64	10,200.00	142.71	142.90	-68.77	9,379.93	-579.81	982.45	713.77	268.68	3.657	Alert
20,050.00	10,560.00	19,804.64	10,200.00	143.41	143.60	-68.77	9,429.93	-580.08	982.46	712.43	270.02	3.638	Alert
20,100.00	10,560.00	19,854.64	10,200.00	144.12	144.30	-68.77	9,479.93	-580.34	982.46	711.09	271.37	3.620	Alert
20,150.00	10,560.00	19,904.64	10,200.00	144.82	145.00	-68.77	9,529.92	-580.60	982.46	709.75	272.71	3.603	Alert
20,200.00	10,560.00	19,954.64	10,200.00	145.53	145.70	-68.77	9,579.92	-580.86	982.46	708.42	274.05	3.585	Alert
20,250.00	10,560.00	20,004.64	10,200.00	146.23	146.40	-68.77	9,629.92	-581.12	982.47	707.08	275.39	3.568	Alert
20,300.00	10,560.00	20,054.64	10,200.00	146.93	147.11	-68.77	9,679.92	-581.38	982.47	705.74	276.73	3.550	Alert
20,350.00	10,560.00	20,104.64	10,200.00	147.64	147.81	-68.77	9,729.92	-581.65	982.47	704.40	278.08	3.533	Alert
20,400.00	10,560.00	20,154.64	10,200.00	148.34	148.51	-68.77	9,779.92	-581.91	982.47	703.05	279.42	3.516	Alert
20,450.00	10,560.00	20,204.64	10,200.00	149.05	149.21	-68.77	9,829.92	-582.17	982.48	701.71	280.76	3.499	Alert
20,500.00	10,560.00	20,254.64	10,200.00	149.75	149.91	-68.77	9,879.92	-582.43	982.48	700.37	282.11	3.483	Alert
20,550.00	10,560.00	20,304.64	10,200.00	150.46	150.62	-68.77	9,929.92	-582.69	982.48	699.03	283.45	3.466	Alert
20,600.00	10,560.00	20,354.64	10,200.00	151.17	151.32	-68.77	9,979.92	-582.96	982.49	697.69	284.80	3.450	Alert
20,650.00	10,560.00	20,404.64	10,200.00	151.87	152.02	-68.77	10,029.92	-583.22	982.49	696.34	286.15	3.434	Alert
20,700.00	10,560.00	20,454.64	10,200.00	152.58	152.73	-68.77	10,079.92	-583.48	982.49	695.00	287.49	3.417	Alert
20,750.00	10,560.00	20,504.64	10,200.00	153.28	153.43	-68.77	10,129.92	-583.74	982.49	693.66	288.84	3.402	Alert
20,800.00	10,560.00	20,554.64	10,200.00	153.99	154.14	-68.77	10,179.92	-584.00	982.50	692.31	290.18	3.386	Alert
20,823.96	10,560.00	20,578.59	10,200.00	154.33	154.47	-68.77	10,203.87	-584.13	982.50	691.67	290.83	3.378	Alert, ES, SF

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Offset Design Sec. 36-T23S-R31E - Todd 36B State 20H (Offset) - Wellbore #1 - Wellbore #1 — Offset Site Error: 0.00 ft

Survey Program: 100-GYRO-NS-CT, 8402-MWD+IGRF — Offset Well Error: 0.50 ft

Reference Measured Depth (ft)	Reference Vertical Depth (ft)	Offset Measured Depth (ft)	Offset Vertical Depth (ft)	Semi Major Axis Reference (ft)	Semi Major Axis Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
8,000.00	7,984.77	13,787.20	9,024.31	28.29	116.64	-62.75	204.49	1,269.15	1,488.14	1,377.37	110.76	13.436	
8,050.00	8,034.57	13,793.05	9,024.37	28.47	116.76	-62.43	199.05	1,271.31	1,452.27	1,339.38	112.89	12.864	
8,100.00	8,084.36	13,798.76	9,024.42	28.65	116.89	-62.11	193.75	1,273.41	1,417.24	1,302.16	115.08	12.315	
8,150.00	8,134.16	13,804.31	9,024.47	28.84	117.01	-61.80	188.58	1,275.45	1,383.11	1,265.79	117.32	11.789	
8,200.00	8,183.95	13,809.73	9,024.51	29.02	117.12	-61.50	183.54	1,277.45	1,349.96	1,230.34	119.61	11.286	
8,250.00	8,233.75	13,815.02	9,024.54	29.21	117.24	-61.21	178.62	1,279.39	1,317.85	1,195.90	121.95	10.807	
8,300.00	8,283.55	13,820.18	9,024.57	29.39	117.35	-60.92	173.82	1,281.28	1,286.87	1,162.56	124.31	10.352	
8,350.00	8,333.34	13,825.21	9,024.59	29.58	117.46	-60.64	169.14	1,283.13	1,257.10	1,130.40	126.70	9.922	
8,400.00	8,383.14	13,830.13	9,024.61	29.76	117.57	-60.36	164.56	1,284.93	1,228.62	1,099.53	129.10	9.517	
8,450.00	8,432.93	13,834.93	9,024.62	29.94	117.67	-60.10	160.10	1,286.68	1,201.54	1,070.06	131.48	9.138	
8,500.00	8,482.73	13,839.61	9,024.62	30.13	117.77	-59.83	155.74	1,288.40	1,175.94	1,042.10	133.84	8.786	
8,550.00	8,532.52	13,838.90	9,024.66	30.31	117.76	-59.87	156.41	1,288.15	1,151.97	1,015.91	136.06	8.467	
8,600.00	8,582.32	13,842.58	9,024.68	30.50	117.84	-59.67	152.99	1,289.50	1,129.67	991.39	138.28	8.169	
8,650.00	8,632.11	13,846.30	9,024.71	30.68	117.92	-59.46	149.53	1,290.87	1,109.16	968.75	140.41	7.900	
8,700.00	8,681.91	13,850.05	9,024.74	30.87	118.00	-59.25	146.04	1,292.25	1,090.55	948.14	142.41	7.658	
8,750.00	8,731.71	13,853.85	9,024.76	31.05	118.08	-59.04	142.51	1,293.65	1,073.92	929.67	144.26	7.444	
8,800.00	8,781.50	13,857.69	9,024.79	31.24	118.17	-58.82	138.94	1,295.07	1,059.39	913.46	145.92	7.260	
8,850.00	8,831.30	13,861.57	9,024.83	31.42	118.25	-58.61	135.33	1,296.50	1,047.02	899.65	147.38	7.104	
8,900.00	8,881.09	13,865.49	9,024.86	31.61	118.34	-58.39	131.69	1,297.95	1,036.91	888.31	148.59	6.978	
8,950.00	8,930.89	13,869.45	9,024.90	31.79	118.42	-58.16	128.01	1,299.41	1,029.11	879.56	149.55	6.881	
9,000.00	8,980.68	13,873.46	9,024.94	31.98	118.51	-57.94	124.29	1,300.89	1,023.68	873.46	150.22	6.814	
9,050.00	9,030.48	13,877.51	9,024.98	32.16	118.60	-57.71	120.52	1,302.39	1,020.66	870.05	150.60	6.777	
9,087.24	9,067.56	13,880.55	9,025.01	32.30	118.66	-57.54	117.70	1,303.51	1,019.98	869.29	150.69	6.769	CC, ES, SF
9,100.00	9,080.27	13,881.60	9,025.02	32.35	118.69	-57.48	116.72	1,303.90	1,020.06	869.38	150.68	6.770	
9,150.00	9,130.07	13,885.74	9,025.07	32.54	118.78	-57.25	112.88	1,305.44	1,021.90	871.44	150.46	6.792	
9,200.00	9,179.87	13,889.92	9,025.12	32.72	118.87	-57.02	108.99	1,306.99	1,026.15	876.21	149.94	6.844	
9,250.00	9,229.66	13,894.16	9,025.17	32.91	118.96	-56.78	105.06	1,308.56	1,032.79	883.65	149.14	6.925	
9,300.00	9,279.46	13,898.44	9,025.22	33.09	119.05	-56.54	101.08	1,310.14	1,041.78	893.70	148.08	7.035	
9,350.00	9,329.27	13,902.62	9,025.28	33.28	119.14	-56.42	97.20	1,311.69	1,053.14	906.38	146.77	7.176	
9,400.00	9,379.13	13,906.32	9,025.32	33.46	119.22	-56.39	93.77	1,313.07	1,067.05	921.82	145.23	7.347	
9,450.00	9,429.04	13,920.58	9,025.37	33.64	119.53	-56.44	90.88	1,314.22	1,083.42	939.69	143.73	7.538	
9,500.00	9,478.98	13,917.82	9,025.41	33.82	119.47	-56.53	88.32	1,315.25	1,102.14	960.41	141.73	7.776	
9,550.00	9,528.95	13,915.61	9,025.44	34.00	119.43	-56.70	86.27	1,316.07	1,123.10	983.47	139.63	8.043	
9,600.00	9,578.94	13,916.04	9,025.46	34.18	119.43	-56.93	84.74	1,316.69	1,146.17	1,008.66	137.51	8.335	
9,650.00	9,628.93	13,917.15	9,025.48	34.35	119.46	-57.23	83.71	1,317.10	1,171.23	1,035.88	135.35	8.654	
9,700.00	9,678.93	13,917.91	9,025.49	34.52	119.48	68.71	83.01	1,317.38	1,198.04	1,064.89	133.15	8.998	
9,750.00	9,728.93	13,918.68	9,025.50	34.69	119.49	68.75	82.30	1,317.67	1,226.31	1,095.37	130.94	9.365	
9,800.00	9,778.93	13,919.45	9,025.51	34.86	119.51	68.79	81.58	1,317.95	1,255.93	1,127.19	128.75	9.755	
9,850.00	9,828.93	13,920.23	9,025.53	35.03	119.53	68.84	80.86	1,318.24	1,286.82	1,160.24	126.57	10.167	
9,900.00	9,878.93	13,921.02	9,025.54	35.20	119.54	68.88	80.13	1,318.54	1,318.87	1,194.44	124.44	10.599	
9,950.00	9,928.93	13,921.81	9,025.55	35.38	119.56	68.93	79.39	1,318.84	1,352.02	1,229.67	122.35	11.050	
10,000.00	9,978.93	13,922.62	9,025.56	35.55	119.58	68.98	78.64	1,319.14	1,386.18	1,265.86	120.32	11.521	
10,050.00	10,028.90	13,921.94	9,025.55	35.72	119.56	65.51	79.27	1,318.88	1,420.86	1,302.57	118.30	12.011	
10,100.00	10,078.54	13,917.02	9,025.48	35.88	119.46	61.03	83.84	1,317.05	1,455.17	1,338.96	116.21	12.521	
10,150.00	10,127.49	13,907.75	9,025.34	36.04	119.25	56.67	92.44	1,313.60	1,488.82	1,374.74	114.09	13.050	

Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Reference Depths are relative to RKB @ 3533.50ft
Offset Depths are relative to Offset Datum
Central Meridian is -104.333334

Coordinates are relative to: Todd 36-25 State Fed Com 234H
Coordinate System is US State Plane 1983, New Mexico Eastern Zone
Grid Convergence at Surface is: 0.32°



Company:	WCDSC Permian NM	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Project:	Eddy County (NAD 83 NM Eastern)	**TVD Reference:**	RKB @ 3533.50ft
Reference Site:	Sec. 36-T23S-R31E	**MD Reference:**	RKB @ 3533.50ft
Site Error:	0.00 ft	**North Reference:**	Grid
Reference Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Well Error:	0.50 ft	**Output errors are at**	2.00 sigma
Reference Wellbore	Wellbore #1	**Database:**	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	**Offset TVD Reference:**	Offset Datum

Reference Depths are relative to RKB @ 3533.50ft
Offset Depths are relative to Offset Datum
Central Meridian is -104.333334

Coordinates are relative to: Todd 36-25 State Fed Com 234H
Coordinate System is US State Plane 1983, New Mexico Eastern Zone
Grid Convergence at Surface is: 0.32°



WCDSC Permian NM

Eddy County (NAD 83 NM Eastern)
Sec. 36-T23S-R31E
Todd 36-25 State Fed Com 234H

Wellbore #1

Plan: Permit Plan 1

Standard Planning Report - Geographic

04 October, 2018

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3533.50ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3533.50ft
Site:	Sec. 36-T23S-R31E	**North Reference:**	Grid
Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Project	Eddy County (NAD 83 NM Eastern)		
Map System:	US State Plane 1983	**System Datum:**	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Sec. 36-T23S-R31E				
Site Position:		**Northing:**	461,801.03 usft	**Latitude:**	32.268172
From:	Map	**Easting:**	724,712.45 usft	**Longitude:**	-103.740050
Position Uncertainty:	0.00 ft	**Slot Radius:**	13-3/16 "	**Grid Convergence:**	0.32 °

Well	Todd 36-25 State Fed Com 234H					
Well Position	**+N/-S**	0.00 ft	**Northing:**	456,874.57 usft	**Latitude:**	32.254575
	+E/-W	0.00 ft	**Easting:**	728,350.82 usft	**Longitude:**	-103.728369
Position Uncertainty		0.50 ft	**Wellhead Elevation:**		**Ground Level:**	3,508.50 ft

Wellbore	Wellbore #1				
Magnetics	**Model Name**	**Sample Date**	**Declination (°)**	**Dip Angle (°)**	**Field Strength (nT)**
	IGRF2015	10/1/2018	6.89	60.05	47,806.45535565

Design	Permit Plan 1				
Audit Notes:					
Version:		**Phase:**	PROTOTYPE	**Tie On Depth:**	0.00
Vertical Section:	**Depth From (TVD) (ft)**	**+N/-S (ft)**	**+E/-W (ft)**	**Direction (°)**	
	0.00	0.00	0.00	1.86	

Plan Survey Tool Program **Date** 10/4/2018

	Depth From (ft)	Depth To (ft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	20,823.96	Permit Plan 1 (Wellbore #1)	MWD+HDGM	
				OWSG MWD + HDGM	

Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,414.68	5.18	125.96	4,414.11	-11.01	15.17	1.25	1.25	0.00	125.96	
9,312.50	5.18	125.96	9,291.91	-270.83	373.36	0.00	0.00	0.00	0.00	
9,658.07	0.00	0.00	9,637.00	-280.00	386.00	1.50	-1.50	0.00	180.00	
10,008.11	0.00	0.00	9,987.04	-280.00	386.00	0.00	0.00	0.00	0.00	
10,908.11	90.00	359.70	10,560.00	292.95	383.03	10.00	10.00	0.00	359.70	PBHL - Todd 36-25 St
20,823.96	90.00	359.70	10,560.00	10,208.67	331.67	0.00	0.00	0.00	0.00	PBHL - Todd 36-25 St

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3533.50ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3533.50ft
Site:	Sec. 36-T23S-R31E	**North Reference:**	Grid
Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
100.00	0.00	0.00	100.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
200.00	0.00	0.00	200.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
300.00	0.00	0.00	300.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
400.00	0.00	0.00	400.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
500.00	0.00	0.00	500.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
600.00	0.00	0.00	600.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
700.00	0.00	0.00	700.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
800.00	0.00	0.00	800.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
900.00	0.00	0.00	900.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
1,000.00	0.00	0.00	1,000.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
1,100.00	0.00	0.00	1,100.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
1,200.00	0.00	0.00	1,200.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
1,300.00	0.00	0.00	1,300.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
1,400.00	0.00	0.00	1,400.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
1,500.00	0.00	0.00	1,500.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
1,600.00	0.00	0.00	1,600.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
1,700.00	0.00	0.00	1,700.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
1,800.00	0.00	0.00	1,800.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
1,900.00	0.00	0.00	1,900.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
2,000.00	0.00	0.00	2,000.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
2,100.00	0.00	0.00	2,100.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
2,200.00	0.00	0.00	2,200.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
2,300.00	0.00	0.00	2,300.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
2,400.00	0.00	0.00	2,400.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
2,500.00	0.00	0.00	2,500.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
2,600.00	0.00	0.00	2,600.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
2,700.00	0.00	0.00	2,700.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
2,800.00	0.00	0.00	2,800.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
2,900.00	0.00	0.00	2,900.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
3,000.00	0.00	0.00	3,000.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
3,100.00	0.00	0.00	3,100.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
3,200.00	0.00	0.00	3,200.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
3,300.00	0.00	0.00	3,300.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
3,400.00	0.00	0.00	3,400.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
3,500.00	0.00	0.00	3,500.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
3,600.00	0.00	0.00	3,600.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
3,700.00	0.00	0.00	3,700.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
3,800.00	0.00	0.00	3,800.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
3,900.00	0.00	0.00	3,900.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
4,000.00	0.00	0.00	4,000.00	0.00	0.00	456,874.57	728,350.82	32.254575	-103.728369
4,100.00	1.25	125.96	4,099.99	-0.64	0.88	456,873.93	728,351.70	32.254573	-103.728366
4,200.00	2.50	125.96	4,199.94	-2.56	3.53	456,872.01	728,354.35	32.254568	-103.728358
4,300.00	3.75	125.96	4,299.79	-5.76	7.94	456,868.81	728,358.76	32.254559	-103.728343
4,400.00	5.00	125.96	4,399.49	-10.24	14.12	456,864.33	728,364.94	32.254547	-103.728323
4,414.68	5.18	125.96	4,414.11	-11.01	15.17	456,863.56	728,365.99	32.254545	-103.728320
4,500.00	5.18	125.96	4,499.09	-15.53	21.41	456,859.04	728,372.23	32.254532	-103.728300
4,600.00	5.18	125.96	4,598.68	-20.84	28.73	456,853.73	728,379.54	32.254517	-103.728276
4,700.00	5.18	125.96	4,698.27	-26.14	36.04	456,848.43	728,386.86	32.254503	-103.728253
4,800.00	5.18	125.96	4,797.86	-31.45	43.35	456,843.12	728,394.17	32.254488	-103.728229
4,900.00	5.18	125.96	4,897.45	-36.75	50.67	456,837.82	728,401.48	32.254473	-103.728206
5,000.00	5.18	125.96	4,997.04	-42.06	57.98	456,832.51	728,408.80	32.254459	-103.728182
5,100.00	5.18	125.96	5,096.63	-47.36	65.29	456,827.21	728,416.11	32.254444	-103.728159
5,200.00	5.18	125.96	5,196.22	-52.67	72.60	456,821.90	728,423.42	32.254429	-103.728135
5,300.00	5.18	125.96	5,295.81	-57.97	79.92	456,816.60	728,430.73	32.254414	-103.728112

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3533.50ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3533.50ft
Site:	Sec. 36-T23S-R31E	**North Reference:**	Grid
Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
5,400.00	5.18	125.96	5,395.41	-63.28	87.23	456,811.29	728,438.05	32.254400	-103.728088
5,500.00	5.18	125.96	5,495.00	-68.58	94.54	456,805.99	728,445.36	32.254385	-103.728064
5,600.00	5.18	125.96	5,594.59	-73.89	101.86	456,800.68	728,452.67	32.254370	-103.728041
5,700.00	5.18	125.96	5,694.18	-79.19	109.17	456,795.38	728,459.99	32.254356	-103.728017
5,800.00	5.18	125.96	5,793.77	-84.50	116.48	456,790.07	728,467.30	32.254341	-103.727994
5,900.00	5.18	125.96	5,893.36	-89.80	123.80	456,784.77	728,474.61	32.254326	-103.727970
6,000.00	5.18	125.96	5,992.95	-95.11	131.11	456,779.46	728,481.93	32.254312	-103.727947
6,100.00	5.18	125.96	6,092.54	-100.41	138.42	456,774.16	728,489.24	32.254297	-103.727923
6,200.00	5.18	125.96	6,192.13	-105.71	145.74	456,768.85	728,496.55	32.254282	-103.727899
6,300.00	5.18	125.96	6,291.72	-111.02	153.05	456,763.55	728,503.87	32.254268	-103.727876
6,400.00	5.18	125.96	6,391.32	-116.32	160.36	456,758.24	728,511.18	32.254253	-103.727852
6,500.00	5.18	125.96	6,490.91	-121.63	167.67	456,752.94	728,518.49	32.254238	-103.727829
6,600.00	5.18	125.96	6,590.50	-126.93	174.99	456,747.63	728,525.80	32.254223	-103.727805
6,700.00	5.18	125.96	6,690.09	-132.24	182.30	456,742.33	728,533.12	32.254209	-103.727782
6,800.00	5.18	125.96	6,789.68	-137.54	189.61	456,737.02	728,540.43	32.254194	-103.727758
6,900.00	5.18	125.96	6,889.27	-142.85	196.93	456,731.72	728,547.74	32.254179	-103.727735
7,000.00	5.18	125.96	6,988.86	-148.15	204.24	456,726.41	728,555.06	32.254165	-103.727711
7,100.00	5.18	125.96	7,088.45	-153.46	211.55	456,721.11	728,562.37	32.254150	-103.727687
7,200.00	5.18	125.96	7,188.04	-158.76	218.87	456,715.80	728,569.68	32.254135	-103.727664
7,300.00	5.18	125.96	7,287.64	-164.07	226.18	456,710.50	728,577.00	32.254121	-103.727640
7,400.00	5.18	125.96	7,387.23	-169.37	233.49	456,705.20	728,584.31	32.254106	-103.727617
7,500.00	5.18	125.96	7,486.82	-174.68	240.81	456,699.89	728,591.62	32.254091	-103.727593
7,600.00	5.18	125.96	7,586.41	-179.98	248.12	456,694.59	728,598.94	32.254077	-103.727570
7,700.00	5.18	125.96	7,686.00	-185.29	255.43	456,689.28	728,606.25	32.254062	-103.727546
7,800.00	5.18	125.96	7,785.59	-190.59	262.75	456,683.98	728,613.56	32.254047	-103.727523
7,900.00	5.18	125.96	7,885.18	-195.90	270.06	456,678.67	728,620.87	32.254032	-103.727499
8,000.00	5.18	125.96	7,984.77	-201.20	277.37	456,673.37	728,628.19	32.254018	-103.727475
8,100.00	5.18	125.96	8,084.36	-206.51	284.68	456,668.06	728,635.50	32.254003	-103.727452
8,200.00	5.18	125.96	8,183.95	-211.81	292.00	456,662.76	728,642.81	32.253988	-103.727428
8,300.00	5.18	125.96	8,283.55	-217.12	299.31	456,657.45	728,650.13	32.253974	-103.727405
8,400.00	5.18	125.96	8,383.14	-222.42	306.62	456,652.15	728,657.44	32.253959	-103.727381
8,500.00	5.18	125.96	8,482.73	-227.73	313.94	456,646.84	728,664.75	32.253944	-103.727358
8,600.00	5.18	125.96	8,582.32	-233.03	321.25	456,641.54	728,672.07	32.253930	-103.727334
8,700.00	5.18	125.96	8,681.91	-238.34	328.56	456,636.23	728,679.38	32.253915	-103.727311
8,800.00	5.18	125.96	8,781.50	-243.64	335.88	456,630.93	728,686.69	32.253900	-103.727287
8,900.00	5.18	125.96	8,881.09	-248.95	343.19	456,625.62	728,694.01	32.253885	-103.727263
9,000.00	5.18	125.96	8,980.68	-254.25	350.50	456,620.32	728,701.32	32.253871	-103.727240
9,100.00	5.18	125.96	9,080.27	-259.56	357.82	456,615.01	728,708.63	32.253856	-103.727216
9,200.00	5.18	125.96	9,179.87	-264.86	365.13	456,609.71	728,715.94	32.253841	-103.727193
9,300.00	5.18	125.96	9,279.46	-270.16	372.44	456,604.40	728,723.26	32.253827	-103.727169
9,312.50	5.18	125.96	9,291.91	-270.83	373.36	456,603.74	728,724.17	32.253825	-103.727166
9,400.00	3.87	125.96	9,379.13	-274.88	378.95	456,599.69	728,729.76	32.253814	-103.727148
9,500.00	2.37	125.96	9,478.98	-278.08	383.35	456,596.49	728,734.17	32.253805	-103.727134
9,600.00	0.87	125.96	9,578.94	-279.74	385.64	456,594.83	728,736.46	32.253800	-103.727127
9,658.07	0.00	0.00	9,637.00	-280.00	386.00	456,594.57	728,736.82	32.253799	-103.727125
9,700.00	0.00	0.00	9,678.93	-280.00	386.00	456,594.57	728,736.82	32.253799	-103.727125
9,800.00	0.00	0.00	9,778.93	-280.00	386.00	456,594.57	728,736.82	32.253799	-103.727125
9,900.00	0.00	0.00	9,878.93	-280.00	386.00	456,594.57	728,736.82	32.253799	-103.727125
10,000.00	0.00	0.00	9,978.93	-280.00	386.00	456,594.57	728,736.82	32.253799	-103.727125
10,008.11	0.00	0.00	9,987.04	-280.00	386.00	456,594.57	728,736.82	32.253799	-103.727125
10,009.70	0.16	359.70	9,988.63	-280.00	386.00	456,594.57	728,736.82	32.253799	-103.727125
KOP @ 10010' MD, 50' FSL, 1280' FEL									
10,100.00	9.19	359.70	10,078.54	-272.65	385.96	456,601.92	728,736.78	32.253820	-103.727125
10,200.00	19.19	359.70	10,175.37	-248.17	385.84	456,626.40	728,736.65	32.253887	-103.727125

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3533.50ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3533.50ft
Site:	Sec. 36-T23S-R31E	**North Reference:**	Grid
Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
10,300.00	29.19	359.70	10,266.47	-207.24	385.62	456,667.33	728,736.44	32.253999	-103.727125
10,340.84	33.27	359.70	10,301.38	-186.07	385.51	456,688.50	728,736.33	32.254058	-103.727125
FTP @ 10341' MD, 100' FSL, 1280' FEL									
10,400.00	39.19	359.70	10,349.08	-151.12	385.33	456,723.45	728,736.15	32.254154	-103.727125
10,500.00	49.19	359.70	10,420.70	-81.51	384.97	456,793.06	728,735.79	32.254345	-103.727125
10,600.00	59.19	359.70	10,479.13	-0.52	384.55	456,874.05	728,735.37	32.254568	-103.727125
10,700.00	69.19	359.70	10,522.62	89.39	384.09	456,963.96	728,734.90	32.254815	-103.727125
10,800.00	79.19	359.70	10,549.83	185.48	383.59	457,060.05	728,734.41	32.255079	-103.727125
10,900.00	89.19	359.70	10,559.94	284.84	383.07	457,159.41	728,733.89	32.255352	-103.727125
10,908.11	90.00	359.70	10,560.00	292.95	383.03	457,167.52	728,733.85	32.255374	-103.727125
11,000.00	90.00	359.70	10,560.00	384.84	382.56	457,259.41	728,733.37	32.255627	-103.727124
11,100.00	90.00	359.70	10,560.00	484.84	382.04	457,359.41	728,732.85	32.255902	-103.727124
11,200.00	90.00	359.70	10,560.00	584.84	381.52	457,459.41	728,732.34	32.256177	-103.727124
11,300.00	90.00	359.70	10,560.00	684.84	381.00	457,559.40	728,731.82	32.256452	-103.727124
11,400.00	90.00	359.70	10,560.00	784.84	380.48	457,659.40	728,731.30	32.256726	-103.727124
11,500.00	90.00	359.70	10,560.00	884.84	379.97	457,759.40	728,730.78	32.257001	-103.727124
11,600.00	90.00	359.70	10,560.00	984.83	379.45	457,859.40	728,730.26	32.257276	-103.727124
11,700.00	90.00	359.70	10,560.00	1,084.83	378.93	457,959.40	728,729.75	32.257551	-103.727123
11,800.00	90.00	359.70	10,560.00	1,184.83	378.41	458,059.40	728,729.23	32.257826	-103.727123
11,900.00	90.00	359.70	10,560.00	1,284.83	377.89	458,159.40	728,728.71	32.258101	-103.727123
12,000.00	90.00	359.70	10,560.00	1,384.83	377.38	458,259.39	728,728.19	32.258376	-103.727123
12,100.00	90.00	359.70	10,560.00	1,484.83	376.86	458,359.39	728,727.67	32.258651	-103.727123
12,200.00	90.00	359.70	10,560.00	1,584.83	376.34	458,459.39	728,727.16	32.258926	-103.727123
12,300.00	90.00	359.70	10,560.00	1,684.82	375.82	458,559.39	728,726.64	32.259200	-103.727123
12,400.00	90.00	359.70	10,560.00	1,784.82	375.30	458,659.39	728,726.12	32.259475	-103.727122
12,500.00	90.00	359.70	10,560.00	1,884.82	374.79	458,759.39	728,725.60	32.259750	-103.727122
12,600.00	90.00	359.70	10,560.00	1,984.82	374.27	458,859.38	728,725.08	32.260025	-103.727122
12,700.00	90.00	359.70	10,560.00	2,084.82	373.75	458,959.38	728,724.57	32.260300	-103.727122
12,800.00	90.00	359.70	10,560.00	2,184.82	373.23	459,059.38	728,724.05	32.260575	-103.727122
12,900.00	90.00	359.70	10,560.00	2,284.82	372.71	459,159.38	728,723.53	32.260850	-103.727122
13,000.00	90.00	359.70	10,560.00	2,384.82	372.20	459,259.38	728,723.01	32.261125	-103.727121
13,100.00	90.00	359.70	10,560.00	2,484.81	371.68	459,359.38	728,722.50	32.261399	-103.727121
13,200.00	90.00	359.70	10,560.00	2,584.81	371.16	459,459.38	728,721.98	32.261674	-103.727121
13,300.00	90.00	359.70	10,560.00	2,684.81	370.64	459,559.37	728,721.46	32.261949	-103.727121
13,400.00	90.00	359.70	10,560.00	2,784.81	370.12	459,659.37	728,720.94	32.262224	-103.727121
13,500.00	90.00	359.70	10,560.00	2,884.81	369.61	459,759.37	728,720.42	32.262499	-103.727121
13,600.00	90.00	359.70	10,560.00	2,984.81	369.09	459,859.37	728,719.91	32.262774	-103.727121
13,700.00	90.00	359.70	10,560.00	3,084.81	368.57	459,959.37	728,719.39	32.263049	-103.727120
13,800.00	90.00	359.70	10,560.00	3,184.80	368.05	460,059.37	728,718.87	32.263324	-103.727120
13,900.00	90.00	359.70	10,560.00	3,284.80	367.53	460,159.36	728,718.35	32.263598	-103.727120
14,000.00	90.00	359.70	10,560.00	3,384.80	367.02	460,259.36	728,717.83	32.263873	-103.727120
14,100.00	90.00	359.70	10,560.00	3,484.80	366.50	460,359.36	728,717.32	32.264148	-103.727120
14,200.00	90.00	359.70	10,560.00	3,584.80	365.98	460,459.36	728,716.80	32.264423	-103.727120
14,300.00	90.00	359.70	10,560.00	3,684.80	365.46	460,559.36	728,716.28	32.264698	-103.727119
14,400.00	90.00	359.70	10,560.00	3,784.80	364.94	460,659.36	728,715.76	32.264973	-103.727119
14,500.00	90.00	359.70	10,560.00	3,884.80	364.43	460,759.36	728,715.24	32.265248	-103.727119
14,600.00	90.00	359.70	10,560.00	3,984.79	363.91	460,859.35	728,714.73	32.265523	-103.727119
14,700.00	90.00	359.70	10,560.00	4,084.79	363.39	460,959.35	728,714.21	32.265797	-103.727119
14,800.00	90.00	359.70	10,560.00	4,184.79	362.87	461,059.35	728,713.69	32.266072	-103.727119
14,900.00	90.00	359.70	10,560.00	4,284.79	362.35	461,159.35	728,713.17	32.266347	-103.727119
15,000.00	90.00	359.70	10,560.00	4,384.79	361.84	461,259.35	728,712.65	32.266622	-103.727118
15,100.00	90.00	359.70	10,560.00	4,484.79	361.32	461,359.35	728,712.14	32.266897	-103.727118
15,200.00	90.00	359.70	10,560.00	4,584.79	360.80	461,459.34	728,711.62	32.267172	-103.727118
15,300.00	90.00	359.70	10,560.00	4,684.78	360.28	461,559.34	728,711.10	32.267447	-103.727118

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3533.50ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3533.50ft
Site:	Sec. 36-T23S-R31E	**North Reference:**	Grid
Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
15,400.00	90.00	359.70	10,560.00	4,784.78	359.76	461,659.34	728,710.58	32.267722	-103.727118
15,500.00	90.00	359.70	10,560.00	4,884.78	359.25	461,759.34	728,710.06	32.267996	-103.727118
15,566.81	90.00	359.70	10,560.00	4,951.59	358.90	461,826.15	728,709.72	32.268180	-103.727118
Cross Section @ 15567' MD, 0' FSL, 1280' FEL									
15,600.00	90.00	359.70	10,560.00	4,984.78	358.73	461,859.34	728,709.55	32.268271	-103.727118
15,700.00	90.00	359.70	10,560.00	5,084.78	358.21	461,959.34	728,709.03	32.268546	-103.727117
15,800.00	90.00	359.70	10,560.00	5,184.78	357.69	462,059.34	728,708.51	32.268821	-103.727117
15,900.00	90.00	359.70	10,560.00	5,284.78	357.17	462,159.33	728,707.99	32.269096	-103.727117
16,000.00	90.00	359.70	10,560.00	5,384.77	356.66	462,259.33	728,707.47	32.269371	-103.727117
16,100.00	90.00	359.70	10,560.00	5,484.77	356.14	462,359.33	728,706.96	32.269646	-103.727117
16,200.00	90.00	359.70	10,560.00	5,584.77	355.62	462,459.33	728,706.44	32.269921	-103.727117
16,300.00	90.00	359.70	10,560.00	5,684.77	355.10	462,559.33	728,705.92	32.270195	-103.727116
16,400.00	90.00	359.70	10,560.00	5,784.77	354.58	462,659.33	728,705.40	32.270470	-103.727116
16,500.00	90.00	359.70	10,560.00	5,884.77	354.07	462,759.32	728,704.88	32.270745	-103.727116
16,600.00	90.00	359.70	10,560.00	5,984.77	353.55	462,859.32	728,704.37	32.271020	-103.727116
16,700.00	90.00	359.70	10,560.00	6,084.77	353.03	462,959.32	728,703.85	32.271295	-103.727116
16,800.00	90.00	359.70	10,560.00	6,184.76	352.51	463,059.32	728,703.33	32.271570	-103.727116
16,900.00	90.00	359.70	10,560.00	6,284.76	352.00	463,159.32	728,702.81	32.271845	-103.727116
17,000.00	90.00	359.70	10,560.00	6,384.76	351.48	463,259.32	728,702.29	32.272120	-103.727115
17,100.00	90.00	359.70	10,560.00	6,484.76	350.96	463,359.32	728,701.78	32.272394	-103.727115
17,200.00	90.00	359.70	10,560.00	6,584.76	350.44	463,459.31	728,701.26	32.272669	-103.727115
17,300.00	90.00	359.70	10,560.00	6,684.76	349.92	463,559.31	728,700.74	32.272944	-103.727115
17,400.00	90.00	359.70	10,560.00	6,784.76	349.41	463,659.31	728,700.22	32.273219	-103.727115
17,500.00	90.00	359.70	10,560.00	6,884.75	348.89	463,759.31	728,699.70	32.273494	-103.727115
17,600.00	90.00	359.70	10,560.00	6,984.75	348.37	463,859.31	728,699.19	32.273769	-103.727114
17,700.00	90.00	359.70	10,560.00	7,084.75	347.85	463,959.31	728,698.67	32.274044	-103.727114
17,800.00	90.00	359.70	10,560.00	7,184.75	347.33	464,059.30	728,698.15	32.274319	-103.727114
17,900.00	90.00	359.70	10,560.00	7,284.75	346.82	464,159.30	728,697.63	32.274594	-103.727114
18,000.00	90.00	359.70	10,560.00	7,384.75	346.30	464,259.30	728,697.11	32.274868	-103.727114
18,100.00	90.00	359.70	10,560.00	7,484.75	345.78	464,359.30	728,696.60	32.275143	-103.727114
18,200.00	90.00	359.70	10,560.00	7,584.75	345.26	464,459.30	728,696.08	32.275418	-103.727114
18,300.00	90.00	359.70	10,560.00	7,684.74	344.74	464,559.30	728,695.56	32.275693	-103.727113
18,400.00	90.00	359.70	10,560.00	7,784.74	344.23	464,659.30	728,695.04	32.275968	-103.727113
18,500.00	90.00	359.70	10,560.00	7,884.74	343.71	464,759.29	728,694.52	32.276243	-103.727113
18,600.00	90.00	359.70	10,560.00	7,984.74	343.19	464,859.29	728,694.01	32.276518	-103.727113
18,700.00	90.00	359.70	10,560.00	8,084.74	342.67	464,959.29	728,693.49	32.276793	-103.727113
18,800.00	90.00	359.70	10,560.00	8,184.74	342.15	465,059.29	728,692.97	32.277067	-103.727113
18,900.00	90.00	359.70	10,560.00	8,284.74	341.64	465,159.29	728,692.45	32.277342	-103.727112
19,000.00	90.00	359.70	10,560.00	8,384.73	341.12	465,259.29	728,691.93	32.277617	-103.727112
19,100.00	90.00	359.70	10,560.00	8,484.73	340.60	465,359.28	728,691.42	32.277892	-103.727112
19,200.00	90.00	359.70	10,560.00	8,584.73	340.08	465,459.28	728,690.90	32.278167	-103.727112
19,300.00	90.00	359.70	10,560.00	8,684.73	339.56	465,559.28	728,690.38	32.278442	-103.727112
19,400.00	90.00	359.70	10,560.00	8,784.73	339.05	465,659.28	728,689.86	32.278717	-103.727112
19,500.00	90.00	359.70	10,560.00	8,884.73	338.53	465,759.28	728,689.34	32.278992	-103.727112
19,600.00	90.00	359.70	10,560.00	8,984.73	338.01	465,859.28	728,688.83	32.279266	-103.727111
19,700.00	90.00	359.70	10,560.00	9,084.73	337.49	465,959.27	728,688.31	32.279541	-103.727111
19,800.00	90.00	359.70	10,560.00	9,184.72	336.97	466,059.27	728,687.79	32.279816	-103.727111
19,900.00	90.00	359.70	10,560.00	9,284.72	336.46	466,159.27	728,687.27	32.280091	-103.727111
20,000.00	90.00	359.70	10,560.00	9,384.72	335.94	466,259.27	728,686.75	32.280366	-103.727111
20,100.00	90.00	359.70	10,560.00	9,484.72	335.42	466,359.27	728,686.24	32.280641	-103.727111
20,200.00	90.00	359.70	10,560.00	9,584.72	334.90	466,459.27	728,685.72	32.280916	-103.727111
20,300.00	90.00	359.70	10,560.00	9,684.72	334.38	466,559.27	728,685.20	32.281191	-103.727110
20,400.00	90.00	359.70	10,560.00	9,784.72	333.87	466,659.26	728,684.68	32.281465	-103.727110
20,500.00	90.00	359.70	10,560.00	9,884.71	333.35	466,759.26	728,684.16	32.281740	-103.727110

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Todd 36-25 State Fed Com 234H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3533.50ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3533.50ft
Site:	Sec. 36-T23S-R31E	**North Reference:**	Grid
Well:	Todd 36-25 State Fed Com 234H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
20,600.00	90.00	359.70	10,560.00	9,984.71	332.83	466,859.26	728,683.65	32.282015	-103.727110
20,700.00	90.00	359.70	10,560.00	10,084.71	332.31	466,959.26	728,683.13	32.282290	-103.727110
20,743.96	90.00	359.70	10,560.00	10,128.67	332.08	467,003.22	728,682.90	32.282411	-103.727110
LTP @ 20744' MD, 100' FNL, 1280' FEL									
20,800.00	90.00	359.70	10,560.00	10,184.71	331.79	467,059.26	728,682.61	32.282565	-103.727110
20,823.95	90.00	359.70	10,560.00	10,208.66	331.67	467,083.21	728,682.49	32.282631	-103.727110
PBHL; 20' FNL, 1280' FEL									
20,823.96	90.00	359.70	10,560.00	10,208.67	331.67	467,083.21	728,682.49	32.282631	-103.727110

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL - Todd 36-25 State	0.00	0.00	0.00	10,208.67	331.67	467,083.21	728,682.49	32.282631	-103.727110
- plan misses target center by 10214.05ft at 0.00ft MD (0.00 TVD, 0.00 N, 0.00 E)									
- Point									

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	Local Coordinates +E/-W (ft)	Comment
10,009.70	9,988.63	-280.00	386.00	KOP @ 10010' MD, 50' FSL, 1280' FEL
10,340.84	10,301.38	-186.07	385.51	FTP @ 10341' MD, 100' FSL, 1280' FEL
15,566.81	10,560.00	4,951.59	358.90	Cross Section @ 15567' MD, 0' FSL, 1280' FEL
20,743.96	10,560.00	10,128.67	332.08	LTP @ 20744' MD, 100' FNL, 1280' FEL
20,823.95	10,560.00	10,208.66	331.67	PBHL; 20' FNL, 1280' FEL

Devon Energy

WELL DETAILS: Todd 36-25 State Fed Com 234H

RKB @ 3533.50ft
3508.50

Northing	Easting	Latitude	Longitude
456874.57	728350.82	32.254575	-103.728369

SECTION DETAILS Permit Plan 1

	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	VSect	Annotation
	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	4000.00	0.00	0.00	4000.00	0.00	0.00	0.00	0.00	
	4414.68	5.18	125.96	4414.11	-11.01	15.17	1.25	-10.51	
	9312.50	5.18	125.96	9291.91	-270.83	373.36	0.00	-258.56	
5	9658.07	0.00	0.00	9637.00	-280.00	386.00	1.50	-267.32	
6	10008.11	0.00	0.00	9987.04	-280.00	386.00	0.00	-267.32	
7	10908.11	90.00	359.70	10560.00	292.95	383.03	10.00	305.23	
8	20823.96	90.00	359.70	10560.00	10208.67	331.67	0.00	10214.05	PBHL: 20' FNL, 1280' FEL



devon

Commitment Runs Deep



Design Plan
Operation and Maintenance Plan
Closure Plan

SENM - Closed Loop Systems
June 2010

I. Design Plan

Devon uses MI SWACO closed loop system (CLS). The MI SWACO CLS is designed to maintain drill solids at or below 5%. The equipment is arranged to progressively remove solids from the largest to the smallest size. Drilling fluids can thus be reused and savings is realized on mud and disposal costs. Dewatering may be required with the centrifuges to insure removal of ultra fine solids.

The drilling location is constructed to allow storm water to flow to a central sump normally the cellar. This insures no contamination leaves the drilling pad in the event of a spill. Storm water is reused in the mud system or stored in a reserve fluid tank farm until it can be reused. All lubricants, oils, or chemicals are removed immediately from the ground to prevent the contamination of storm water. An oil trap is normally installed on the sump if an oil spill occurs during a storm.

A tank farm is utilized to store drilling fluids including fresh water and brine fluids. The tank farm is constructed on a 20 ml plastic lined, bermed pad to prevent the contamination of the drilling site during a spill. Fluids from other sites may be stored in these tanks for processing by the solids control equipment and reused in the mud system. At the end of the well the fluids are transported from the tank farm to an adjoining well or to the next well for the rig.

Prior to installing a closed-loop system on site, the topsoil, if present, will be stripped and stockpiled for use as the final cover or fill at the time of closure.

Signs will be posted on the fence surrounding the closed-loop system unless the closed-loop system is located on a site where there is an existing well, that is operated by Devon.

II. Operations and Maintenance Plan

Primary Shakers: The primary shakers make the first removal of drill solids from the drilling mud as it leaves the well bore. The shakers are sized to handle maximum drilling rate at optimal screen size. The shakers normally remove solids down to 74 microns.

Mud Cleaner: The Mud Cleaner cleans the fluid after it leaves the shakers. A set of hydrocyclones are sized to handle 1.25 to 1.5 times the maximum circulating rate. This ensures all the fluid is being processed to an average cut point of 25 microns. The wet discharged is dewatered on a shaker equipped with ultra fine mesh screens and generally cut at 40 microns.



Centrifuges: The centrifuges can be one or two in number depending on the well geometry or depth of well. The centrifuges are sized to maintain low gravity solids at 5% or below. They may or may not need a dewatering system to enhance the removal rates. The centrifuges can make a cut point of 8-10 microns depending on bowl speed, feed rate, solids loading and other factors.

The centrifuge system is designed to work on the active system and be flexible to process incoming fluids from other locations. This set-up is also dependant on well factors.

Dewatering System: The dewatering system is a chemical mixing and dosing system designed to enhance the solids removal of the centrifuge. Not commonly used in shallow wells. It may contain pH adjustment, coagulant mixing and dosing, and polymer mixing and dosing. Chemical flocculation binds ultra fine solids into a mass that is within the centrifuge operating design. The

dewatering system improves the centrifuge cut point to infinity or allows for the return of clear water or brine fluid. This ability allows for the ultimate control of low gravity solids.

Cuttings Boxes: Cuttings boxes are utilized to capture drill solids that are discarded from the solids control equipment. These boxes are set upon a rail system that allows for the removal and replacement of a full box of cuttings with an empty one. They are equipped with a cover that insures no product is spilled into the environment during the transportation phase.

Process Tank: (Optional) The process tank allows for the holding and process of fluids that are being transferred into the mud system. Additionally, during times of lost circulation the process tank may hold active fluids that are removed for additional treatment. It can further be used as a mixing tank during well control conditions.

Sump and Sump Pump: The sump is used to collect storm water and the pump is used to transfer this fluid to the active system or to the tank for to hold in reserve. It can also be used to collect fluids that may escape during spills. The location contains drainage ditches that allow the location fluids to drain to the sump.

Reserve Fluids (Tank Farm): A series of frac tanks are used to replace the reserve pit. These are steel tanks that are equipped with a manifold system and a transfer pump. These tanks can contain any number of fluids used during the drilling process. These can include fresh water, cut brine, and saturated salt fluid. The fluid can be from the active well or reclaimed fluid from other locations. A 20 ml liner and berm system is employed to ensure the fluids do not migrate to the environment during a spill.

If a leak develops, the appropriate division district office will be notified within 48 hours of the discovery and the leak will be addressed. Spill prevention is accomplished by maintaining pump packing, hoses, and pipe fittings to insure no leaks are occurring. During an upset condition the source of the spill is isolated and repaired as soon as it is discovered. Free liquid is removed by a diaphragm pump and returned to the mud system. Loose topsoil may be used to stabilize the spill and the contaminated soil is excavated and placed in the cuttings boxes. After the well is finished and the rig has moved, the entire location is scrapped and testing will be performed to determine if a release has occurred.

All trash is kept in a wire mesh enclosure and removed to an approved landfill when full. All spent motor oils are kept in separate containers and they are removed and sent to an approved recycling center. Any spilled lubricants, pipe

dope, or regulated chemicals are removed from soil and sent to landfills approved for these products.

These operations are monitored by Mi Swaco service technicians. Daily logs are maintained to ensure optimal equipment operation and maintenance. Screen and chemical use is logged to maintain inventory control. Fluid properties are monitored and recorded and drilling mud volumes are accounted for in the mud storage farm. This data is kept for end of well review to insure performance goals are met. Lessons learned are logged and used to help with continuous improvement.

A MI SWACO field supervisor manages from 3-5 wells. They are responsible for training personnel, supervising installations, and inspecting sites for compliance of MI SWACO safety and operational policy.

III. Closure Plan

A maximum 340' X 340' caliche pad is built per well. All of the trucks and steel tanks fit on this pad. All fluid cuttings go to the steel tanks to be hauled by various trucking companies to an agency approved disposal.

A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Devon proposes using a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 5000 (5M) psi.

- Wellhead will be installed by wellhead representatives.
- If the welding is performed by a third party, the wellhead representative will monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- Wellhead representative will install the test plug for the initial BOP test.
- Wellhead company will install a solid steel body pack-off to completely isolate the lower head after cementing intermediate casing. After installation of the pack-off, the pack-off and the lower flange will be tested to 5M, as shown on the attached schematic. Everything above the pack-off will not have been altered whatsoever from the initial nipple up. Therefore the BOP components will not be retested at that time.
- If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head will be cut and top out operations will be conducted.
- Devon will pressure test all seals above and below the mandrel (but still above the casing) to full working pressure rating.
- Devon will test the casing to 0.22 psi/ft or 1500 psi, whichever is greater, as per Onshore Order #2.

After running the 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 5M will be installed on the wellhead system and will undergo a 250 psi low pressure test followed by a 5,000 psi high pressure test. The 5,000 psi high and 250 psi low test will cover testing requirements a maximum of 30 days, as per Onshore Order #2. If the well is not complete within 30 days of this BOP test, another full BOP test will be conducted, as per Onshore Order #2.

After running the 9-5/8' intermediate casing with a mandrel hanger, the 13-5/8" BOP/BOPE system with a minimum rating of 5M will already be installed on the wellhead.

The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 5,000 psi WP.

Devon's proposed wellhead manufactures will be FMC Technologies, Cactus Wellhead, or Cameron.


7-1/16" 10M
1-13/16" 10M
1-13/16" 10M
11" 5M
13-5/8" 5M
2-1/16" 5M
2-1/16" 5M
13-3/8" Casing
9-5/8" Casing
5-1/2" Casing

Devon Energy
APD VARIANCE DATA

OPERATOR NAME: Devon Energy

1. SUMMARY OF Variance:

Devon Energy respectfully requests approval for the following additions to the drilling plan:

1. Potential utilization of a spudder rig to pre-set surface casing.

2. Description of Operations

1. A spudder rig contractor may move in their rig to drill the surface hole section and pre-set surface casing on this well.
    a. After drilling the surface hole section, the rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
    b. Rig will utilize fresh water based mud to drill surface hole to TD.
2. The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
3. A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wingvalves.
    a. A means for intervention will be maintained while the drilling rig is not over the well.
4. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
5. Drilling operation will be performed with the big rig. At that time an approved BOP stack will be nippled up and tested on the wellhead before drilling operations commences on each well.
    a. The BLM will be contacted / notified 24 hours before the big rig moves back on to the pad with the pre-set surface casing.
6. Devon Energy will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
7. Once the rig is removed, Devon Energy will secure the wellhead area by placing a guard rail around the cellar area.

Devon Energy, Todd 36-25 State Fed Com 234H

1. Geologic Formations

TVD of target	10560	Pilot hole depth	N/A
MD at TD:	20823	Deepest expected fresh water:	

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Rustler	812		
Salado	1147		
Base of Salt	4446		
Delaware	4507		
L Brushy Canyon	8057		
Bone Spring	8387		
Leonard 'A'	8487		
Leonard 'B'	8972		
Leonard 'C'	9137		
2nd BSPG Lime	9872		
2nd BSPG Sand	10037		
L 2nd BSPG Sand	10546		
Landing Point	10560		

*H2S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (PPF)	Grade	Conn.
	From	To				
17.5"	0	837	13.375"	48	H-40	STC
12.25"	0	6000	9.625"	40	J-55	BTC
8.75"	0	TD	5.5"	17	P-110	BTC
BLM Minimum Safety Factor				Collapse: 1.125	Burst: 1.00	Tension: 1.6 Dry 1.8 Wet

- All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h Must have table for contingency casing
- Rustler top will be validated via drilling parameters (i.e. reduction in ROP) and surface casing setting depth revised accordingly if needed.
- Variance is requested for collapse rating on intermediate casing. Operator will keep pipe full while running casing. No losses are expected in subsequent hole section.
- Int casing shoe will be selected based on drilling data, gamma, and flows experienced while drilling. Setting depth with be revised accordingly if needed.
- A variance is requested to wave the centralizer requirement for the intermediate and production casing strings if drilling conditions dictate

Devon Energy, Todd 36-25 State Fed Com 234H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

3. Cementing Program (3-String Primary Design)

Casing	# Sks	TOC	Wt. (lb/gal)	H_20 (gal/sk)	Yld (ft3/sack)	Slurry Description
Surface	873	Surf	13.2	6.33	1.33	Lead: Class C Cement + additives
Int	757	Surf	9	20.6	1.94	Lead: Class C Cement + additives
	196	500' above shoe	13.2	6.42	1.33	Tail: Class H / C + additives
Production	460	500' tieback	9	20.6	1.94	Lead: Class H / C + additives
	1882	KOP	13.2	5.31	1.6	Tail: Class H / C + additives

If a DV tool is ran the depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. Slurry weights will be adjusted based on estimated fracture gradient of the formation. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. If cement is not returned to surface during the primary cement job on the surface casing string, a planned top job will be conducted immediately after completion of the primary job.

Casing String	% Excess
Surface	100%
Intermediate	50%
Production	10%

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
Int 1	13-5/8"	3M	Annular	X	50% of rated working pressure
			Blind Ram		3M
			Pipe Ram		
			Double Ram	X	
			Other*		
Production	13-5/8"	5M	Annular (5M)	X	50% of rated working pressure
			Blind Ram		5M
			Pipe Ram		
			Double Ram	X	
			Other *		
			Annular		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other *		

5. Mud Program

6. Depth		Type	Weight (ppg)	Vis	Water Loss
From	To				
0	837	FW	8.5 – 9.0	28-34	N/C
837	6000	Brine	10 – 10.5	28-34	N/C
6000	TD	WBM	8.5 – 9.0	28-34	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring

6. Logging and Testing Procedures

Logging, Coring and Testing.	
X	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned		Interval
	Resistivity	
	Density	
X	CBL	Production casing
X	Mud log	KOP to TD

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	4937 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
N	H2S is present
Y	H2S Plan attached

8. Other facets of operation

Is this a walking operation? Potentially

1. If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
2. The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
3. The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially

1. Spudder rig will move in and drill surface hole.
    a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.
2. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
3. The wellhead will be installed and tested once the 10 ¾" surface casing is cut off and the WOC time has been reached.
4. A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
5. Spudder rig operations is expected to take 4-5 days per well on a multi well pad.
6. The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
7. Drilling operations will be performed with the drilling rig. At that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
    a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

Attachments

_x_ Directional Plan

___ Other, describe

Continental CONTITECH

Fluid Technology

ContiTech Beattie Corp.
Website: www.contitechbeattie.com

Monday, June 14, 2010

RE: Drilling & Production Hoses
Lifting & Safety Equipment

To Helmerich & Payne,

A Continental ContiTech hose assembly can perform as intended and suitable for the application regardless of whether the hose is secured or unsecured in its configuration. As a manufacturer of High Pressure Hose Assemblies for use in Drilling & Production, we do offer the corresponding lifting and safety equipment, this has the added benefit of easing the lifting and handling of each hose assembly whilst affording hose longevity by ensuring correct handling methods and procedures as well as securing the hose in the unlikely event of a failure; but in no way does the lifting and safety equipment affect the performance of the hoses providing the hoses have been handled and installed correctly it is good practice to use lifting & safety equipment but not mandatory

Should you have any questions or require any additional information/clarifications then please do not hesitate to contact us.

ContiTech Beattie is part of the Continental AG Corporation and can offer the full support resources associated with a global organization.

Best regards,

Robin Hodgson
Sales Manager
ContiTech Beattie Corp

ContiTech Beattie Corp,
11535 Brittmoore Park Drive,
Houston, TX 77041
Phone: +1 (832) 327-0141
Fax: +1 (832) 327-0148
www.contitechbeattie.com

RIG 212

PHOENIX

QUALITY DOCUMENT

PHOENIX RUBBER INDUSTRIAL LTD.

6728 Szeged, Budapesti út 10. Hungary • H-6701 Szeged, P. O. Box 152
Phone: (3662) 566-737 • Fax: (3662) 566-738

SALES & MARKETING: H-1092 Budapest, Ráday u. 42-44. Hungary • H-1440 Budapest, P. O. Box 26
Phone: (361) 456-4200 • Fax: (361) 217-2972, 456-4273 • www.taurusemerge.hu

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE					CERT. N°: 552
PURCHASER: Phoenix Beattie Co.					P.O. N°: 1519FA-871
PHOENIX RUBBER order N°: 170466		HOSE TYPE: 3" ID		Choke and Kill Hose	
HOSE SERIAL N°: 34128		NOMINAL / ACTUAL LENGTH:		11,43 m	
W.P. 68,96 MPa	10000 psi	T.P. 103,4 MPa	15000 psi	Duration: 60	min.

Pressure test with water at ambient temperature

See attachment. (1 page)

↑ 10 mm = 10 Min.

→ 10 mm = 25 MPa

COUPLINGS

Type	Serial N°	Quality	Heat N°
3" coupling with	720 719	AISI 4130	C7626
4 1/16" Flange end		AISI 4130	47357

API Spec 16 C
Temperature rate:"B"

All metal parts are flawless

WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.

Date:	Inspector	Quality Control
29. April. 2002.		PHOENIX RUBBER Industrial Ltd. Hose Inspection and Verification Dept.

VERIFIED TRUE COPY
PHOENIX RUBBER C.C.



PHOENIX RUBBER
Industrial Ltd.
Hose Inspection and
Certification Dept.

VERIFIED TRUE CO
PHOENIX RUBBER I.C.

APD ID: 10400035010 **Submission Date:** 10/10/2018

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Well Type: OIL WELL **Well Work Type:** Drill

Highlighted data reflects the most recent changes

Show Final Text

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

TODD_36_25_STATE_FED_COM_234H_EX_ACCESS_RD_20181010071930.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT **Row(s) Exist?** NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

TODD_36_25_STATE_FED_COM_234H_ACCESS_RD_20181010071949.pdf

New road type: COLLECTOR,RESOURCE

Length: 46 Feet **Width (ft.):** 30

Max slope (%): 6 **Max grade (%):** 4

Army Corp of Engineers (ACOE) permit required? NO

ACOE Permit Number(s):

New road travel width: 20

New road access erosion control: n/a

New road access plan or profile prepared? NO

New road access plan attachment:

Access road engineering design? NO

Access road engineering design attachment:

Access surfacing type: GRAVEL

Access topsoil source: BOTH

Access surfacing type description:

Access onsite topsoil source depth: 6

Offsite topsoil source description: n/a

Onsite topsoil removal process: See attached Interim reclamation diagram.

Access other construction information:

Access miscellaneous information:

Number of access turnouts: **Access turnout map:**

Drainage Control

New road drainage crossing: CULVERT

Drainage Control comments: n/a

Road Drainage Control Structures (DCS) description: n/a

Road Drainage Control Structures (DCS) attachment:

Access Additional Attachments

Additional Attachment(s):

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

Todd_36_25_State_Fed_Com_234H_OneMileBuffer_WA017432176_20181010072010.pdf

Existing Wells description:

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? DEFER

Estimated Production Facilities description: Wells will go to Todd 36 CTB 2 . Please refer to CTB plat.

Section 5 - Location and Types of Water Supply

Water Source Table

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Water source use type: OTHER **Water source type:** OTHER

Describe type: STIMULATION

Source latitude: **Source longitude:**

Source datum:

Water source permit type: OTHER

Source land ownership: FEDERAL

Water source transport method: PIPELINE

Source transportation land ownership: STATE

Water source volume (barrels): 230000 **Source volume (acre-feet):** 29.645412

Source volume (gal): 9660000

Water source and transportation map:

TODD_36_25_STATE_FED_COM_233H_234H_235H_water_x_map_20181009092522.pdf

Water source comments: The attached Water Transfer Map is a proposal only and the final route and documentation will be provided by a Devon contractor prior to installation. When available Devon will always follow existing disturbance.
New water well? NO

New Water Well Info

Well latitude: **Well Longitude:** **Well datum:**

Well target aquifer:

Est. depth to top of aquifer(ft): **Est thickness of aquifer:**

Aquifer comments:

Aquifer documentation:

Well depth (ft): **Well casing type:**

Well casing outside diameter (in.): **Well casing inside diameter (in.):**

New water well casing? **Used casing source:**

Drilling method: **Drill material:**

Grout material: **Grout depth:**

Casing length (ft.): **Casing top depth (ft.):**

Well Production type: **Completion Method:**

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Construction Materials description: Dirt fill and caliche will be used to construct well pad. See attached map.

Construction Materials source location attachment:

Todd_36_Wellpad_3_Caliche_Map_20181010072227.pdf

Section 7 - Methods for Handling Waste

Waste type: COMPLETIONS/STIMULATION

Waste content description: Flow back water during completion operations.

Amount of waste: 3000 barrels

Waste disposal frequency : One Time Only

Safe containment description: n/a

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Various disposal locations in Lea and Eddy counties.

Waste type: PRODUCED WATER

Waste content description: n/a

Amount of waste: 1000 barrels

Waste disposal frequency : Daily

Safe containment description: n/a

Safe containmant attachment:

Waste disposal type: ON-LEASE INJECTION **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Multiple methods for handling waste will be utilized. Via trucking, Dvn owned disposal system and or third party pipeline take away.

Waste type: FLOWBACK

Waste content description: n/a

Amount of waste: 1500 barrels

Waste disposal frequency : Daily

Safe containment description: n/a

Safe containmant attachment:

Waste disposal type: ON-LEASE INJECTION **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Various disposal locations in Lea and Eddy counties.

Waste type: DRILLING

Waste content description: Water Based Cuttings

Amount of waste: 2005 barrels

Waste disposal frequency : Daily

Safe containment description: n/a

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: All cuttings will disposed of at R360, Sundance, or equivalent.

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.) **Reserve pit width (ft.)**

Reserve pit depth (ft.) **Reserve pit volume (cu. yd.)**

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? NO

Description of cuttings location

Cuttings area length (ft.) **Cuttings area width (ft.)**

Cuttings area depth (ft.) **Cuttings area volume (cu. yd.)**

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

TODD_36_25_STATE_FED_COM_234H_RIGLAYOUT_20181010072309.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance **Multiple Well Pad Name:** TODD 36 WELLPAD

Multiple Well Pad Number: 3

Recontouring attachment:

Drainage/Erosion control construction: All areas disturbed shall be reclaimed as early and as nearly as practicable to their original condition or their final land use and shall be maintained to control dust and minimize erosion to the extent practicable.
Drainage/Erosion control reclamation: Topsoils and subsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns. The disturbed area then shall be reseeded in the first favorable growing season.

Well pad proposed disturbance (acres): 3.471
Road proposed disturbance (acres): 0.22
Powerline proposed disturbance (acres): 0.044
Pipeline proposed disturbance (acres): 0.637
Other proposed disturbance (acres): 5.165
Total proposed disturbance: 9.537

Well pad interim reclamation (acres): 2.018
Road interim reclamation (acres): 0
Powerline interim reclamation (acres): 0
Pipeline interim reclamation (acres): 0
Other interim reclamation (acres): 0
Total interim reclamation: 2.018

Well pad long term disturbance (acres): 1.641
Road long term disturbance (acres): 0.22
Powerline long term disturbance (acres): 0.044
Pipeline long term disturbance (acres): 0.637
Other long term disturbance (acres): 5.165
Total long term disturbance: 7.707

Disturbance Comments:

Reconstruction method: Operator will use Best Management Practices"BMP" to mechanically recontour to obtain the desired outcome.
Topsoil redistribution: Topsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns.
Soil treatment: Topsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns.
Existing Vegetation at the well pad:

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road:

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline:

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances:

Existing Vegetation Community at other disturbances attachment:

Non native seed used?

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project?

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation?

Seed harvest description:

Seed harvest description attachment:

Seed Management

Seed Table

Seed type:

Seed source:

Seed name:

Source name:

Source address:

Source phone:

Seed cultivar:

Seed use location:

PLS pounds per acre:

Proposed seeding season:

Seed Summary	
Seed Type	**Pounds/Acre**

Total pounds/Acre:

Seed reclamation attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Operator Contact/Responsible Official Contact Info

First Name: JACOB **Last Name:** OCHOA

Phone: (575)748-9934 **Email:** JACOB.OCHOA@DVN.COM

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: Maintain weeds on an as need basis.

Weed treatment plan attachment:

Monitoring plan description: Monitor as needed.

Monitoring plan attachment:

Success standards: n/a

Pit closure description: n/a

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland: **USFS Ranger District:**

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Disturbance type: EXISTING ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland: **USFS Ranger District:**

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland: **USFS Ranger District:**

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

Disturbance type: PIPELINE

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland: **USFS Ranger District:**

Section 12 - Other Information

Right of Way needed? NO **Use APD as ROW?**

ROW Type(s):

ROW Applications

SUPO Additional Information: FLOWLINES ARE ALL BURIED ELECTRIC LINES CTB- revised to show center point of the CTB calls from the section lines 3/26/2019
Use a previously conducted onsite? NO

Previous Onsite information:

Other SUPO Attachment

Pay.gov___Receipt_20181010094343.pdf
EL8245_TODD_36_CTB_2_EL_P_20190319124838.PDF
EL8249_TODD_36_WP_3_EL_P_20190319124845.PDF
AA000145925_TODD_36_CTB_2_P_R2_20190326074535.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: TODD 36-25 STATE FED COM **Well Number:** 234H

TODD_36_WP_3_TO_CTB_2_FL_P_all_buried_lines_4_2_2019_20190402061420.pdf

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



DEVON ENERGY PRODUCTION COMPANY, L.P.
TODD 36-25 STATE FED COM 234H
LOCATED 330 FT. FROM THE SOUTH LINE
AND 1666 FT. FROM THE EAST LINE OF
SECTION 36, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

0 1000 2000

HORIZON ROW LLC		Drawn for: devon
DEVON ENERGY PRODUCTION CO., L.P.		
Drawn by: CHRIS MAAS	Date: 09/20/2018	

EXHIBIT "A"

ACCESS ROAD PLAT
SECTION 36, T23S–R31E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



30' EASEMENT AREA = 0.032 ACRE(S)
46.36 FEET OR 2.81 RODS

0+00.0 P.O.B./EXISTING ACCESS ROAD
0+03.9 EDGE OF ROAD
0+11.6 EXISTING FLOW LINE
0+16.3 POWER LINE
0+46.3 P.O.E./TODD 36 WELLPAD 3

SEE THE ATTACHED LEGAL DESCRIPTION

Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision; this survey meets the minimum standards for surveying in New Mexico.

NEW MEXICO 22404 PROFESSIONAL SURVEYOR

B.L. Laman PLS #22404
Date Signed: 09-23-2018
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70837
Employee of Horizonrow, LLC

0 1000 2000

HORIZON ROW LLC	DEVON ENERGY PRODUCTION COMPANY, L.P.		LINE NUMBER:
Drawn for: devon	TODD 36 WELLPAD 3 ACCESS ROAD		WBS NUMBER:
	PROPOSED 30' EASEMENT ON THE PROPERTY OF BUREAU OF LAND MANAGEMENT SECTION 36, T23S–R31E, N.M.P.M.		SCALE: 1" = 1000'
			REVISIONS:
Drawn by: CHRIS MAAS	Date: 07/07/2018		SURVEY DATE: 6/30/18

SECTION 36, T23S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

ACCESS ROAD PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southeast quarter (SE ¼) of Section 36, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 1" iron pipe w/BC for the east quarter corner of Section 36, T23S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence S 45°28'13" W a distance of 3031.10' to the **Point of Beginning** of this easement having coordinates of Northing=457067.69, Easting=727843.19 feet and continuing the following course;

Thence S 08°21'32" E a distance of 46.36' to the **Point of Ending** having coordinates of Northing=457021.82, Easting=727849.93 feet from said point a 2" iron pipe w/BC for the southeast corner of Section 36, T23S-R31E bears S 77°49'11" E a distance of 2218.65', covering **46.36' or 2.81 rods** and having an area of **0.032 acres**.

NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman PLS 22404
Date Signed: 09/23/2018
Horizon Row, LLC
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizon Row, LLC

PLAT

One Mile Radius Map

TODD 36-25 STATE FED COM 234H
WA017432176

devon

This map is for illustrative purposes only and is neither a legally recorded map nor a survey and is not intended to be used as one. Devon makes no warranty,representation, or guarantee of any kind regarding this map.

USA Contiguous Equidistant Conic
Datum: North American 1983
Created by: FME Server
Map is current as of 10/4/2018

N

Miles
0 0.3
1 inch = 0.44 miles

TODD 36B STATE 20H
Nearest wellbore to SHL: 1235 ft.

ALDABRA 25 FED 7H
Nearest wellbore to BHL: 393 ft.

- ○ Unknown SHL
- • Active SHL
- ○ Inactive SHL
- × BHL



TODD 36-25 STATE FED COM

233H/234H/235H

devon

This map is for illustrative purposes only and is neither a legally recorded map nor survey and is not intended to be used as one. Devon makes no warranty, representation, or guarantee of any kind regarding this map.

WGS_1984_Web_Mercator_Auxiliary_Sphere
Prepared by: _User
Map is current as of: 08-Oct-2018

N

Miles
0 0.28 0.56 1.12 1:56,913


TODD 36 WELLPAD 3
CALICHE MAP
CALICHE PIT
TOTAL DISTANCE=2.55 MILES
TODD 36 WELLPAD 3

Devon Energy - Well Pad
Rig Location Layout
Safety Equipment Location



Pay.gov

Receipt

Your payment is submitted

Pay.gov Tracking ID: 26CPORR8
Agency Tracking ID: 75591612551
Form Name: Bureau of Land Management (BLM) Application for Permit to Drill (APD) Fee
Application Name: BLM Oil and Gas Online Payment

Payment Information

Payment Type: Bank account (ACH)
Payment Amount: $30,150.00
Transaction Date: 10/10/2018 11:31:45 AM EDT
Payment Date: 10/11/2018
Company: DEVON ENERGY PRODUCTION CO., L.P.
APD IDs: 10400034900, 10400035010, 10400035068
Lease Numbers: NMNM0544986, NMNM0544986, NMNM0544986
Well Numbers: 233H, 234H, 235H
Note: You will need your Pay.gov Tracking ID to complete your APD transaction in AFMSS II. Please ensure you write this number down upon completion of payment.

Account Information

Account Holder Name: Devon Energy Production Company, L.P.
Routing Number: 061000052
Account Number: **********9892

Email Confirmation Receipt

Confirmation Receipts have been emailed to:
JENNY.HARMS@DVN.COM
jeff.walla@dvn.com
lisa.othon@dvn.com

EXHIBIT "A"
PAGE 1 of 4

ELECTRIC LINE PLAT
SECTION 36, T23S–R31E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



30' EASEMENT AREA = 0.210 ACRE(S)
304.65 FEET OR 18.46 RODS

SEE THE ATTACHED LEGAL DESCRIPTION

Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

STATION TABLE

0+00.0 P.O.B./TODD 36 PRIMARY ELECTRIC LINE
2+14.7 EXISTING FLOW LINE
3+04.7 P.O.E./TODD 36 CTB 2

0 1000 2000

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

B.L. LAMAN NEW MEXICO 22404 PROFESSIONAL SURVEYOR

B.L. Laman PLS #22404
Date Signed: 09-07-2018
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizonrow, LLC

HORIZON ROW LLC	DEVON ENERGY PRODUCTION COMPANY, L.P.		LINE NUMBER: EL8245
Drawn for: devon	TODD 36 CTB 2 ELECTRIC LINE		WBS NUMBER: XX-129865.01.SLC
			SCALE: 1" = 1000'
	PROPOSED 30' EASEMENT ON THE PROPERTY OF BUREAU OF LAND MANAGEMENT SECTION 36, T23S–R31E, N.M.P.M.		REVISIONS:
Drawn by: Jesus Rivero	Date: 07/03/2018		SHEET: 1 OF 4

SECTION 36, T23S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

ELECTRIC LINE PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southeast quarter (SE ¼) of Section 36, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 2" iron pipe w/BC for the southeast corner of Section 36, T23S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence N 76°04'36" W a distance of 2597.66' to the **Point of Beginning** of this easement having coordinates of Northing=457178.77, Easting=727497.30 feet and continuing the following courses;

Thence N 00°00'00" W a distance of 289.65' to an angle point;

Thence N 90°00'00" E a distance of 15.00' to the **Point of Ending** having coordinates of Northing=457468.42, Easting=727512.30 feet from said point a 1" iron pipe w/BC for the east quarter corner of Section 36, T23S-R31E bears N 55°18'24" E a distance of 3030.51', covering **304.65' or 18.46 rods** and having an area of **0.210 acres**.

NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

B.L. Laman PLS 22404
Date Signed: 09/07/2018
Horizon Row, LLC
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizon Row, LLC

EXHIBIT "A"
PAGE 3 of 4



QUAD MAP

SECTION 36, T23S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC	Drawn for: devon		LINE NUMBER: EL8245
DEVON ENERGY PRODUCTION CO., L.P.			WBS NUMBER: XX-129865.01.SLC
PROPOSED 30' EASEMENT			SCALE: 1" = 1000'
Drawn by: Jesus Rivero	Date: 07/03/2018		REVISIONS:
			SHEET: 3 OF 4

EXHIBIT "A"
PAGE 4 of 4



AERIAL MAP

SECTION 36, T23S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC	Drawn for: devon		LINE NUMBER: EL8245
DEVON ENERGY PRODUCTION CO., L.P.			WBS NUMBER: XX-129865.01.SLC
PROPOSED 30' EASEMENT			SCALE: 1" = 1000'
Drawn by: Jesus Rivero	Date: 07/03/2018		REVISIONS:
			SHEET: 4 OF 4

EXHIBIT "A"
PAGE 1 of 4

ELECTRIC LINE PLAT
SECTION 36, T23S–R31E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



30' EASEMENT AREA = 0.044 ACRE(S)
63.45 FEET OR 3.85 RODS

SEE THE ATTACHED LEGAL DESCRIPTION

Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

NEW MEXICO 22404 PROFESSIONAL SURVEYOR

B.L. Laman PLS #22404
Date Signed: 09-07-2018
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizonrow, LLC

STATION TABLE

0+00.0	P.O.B./TODD 36 PRIMARY ELECTRIC LINE
0+14.2	EDGE OF LEASE ROAD
0+21.1	CENTERLINE LEASE ROAD
0+27.4	EDGE OF LEASE ROAD
0+36.0	EXISTING FLOWLINE
0+49.6	EXISTING POWER LINE
0+63.5	P.O.E./TODD 36 WELLPAD 3

0 1000 2000

HORIZON ROW LLC
Drawn for: devon
Drawn by: Jesus Rivero
Date: 07/03/2018

DEVON ENERGY PRODUCTION COMPANY, L.P.
TODD 36 WELLPAD 3
ELECTRIC LINE
PROPOSED 30' EASEMENT
ON THE PROPERTY OF
BUREAU OF LAND MANAGEMENT
SECTION 36, T23S–R31E, N.M.P.M.

LINE NUMBER: EL8249
WBS NUMBER: XX-129865.01.SLC
SCALE: 1" = 1000'
REVISIONS:
SHEET: 1 OF 4

SECTION 36, T23S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

ELECTRIC LINE PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southeast quarter (SE ¼) of Section 36, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 1" iron pipe w/BC for the east quarter corner of Section 36, T23S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence S 39°23'26" W a distance of 2724.67' to the **Point of Beginning** of this easement having coordinates of Northing=457087.61, Easting=728274.94 feet and continuing the following courses;

Thence S 00°00'00" E a distance of 63.45' to the **Point of Ending** having coordinates of Northing=457024.16, Easting=728274.94 feet from said point a 2" iron pipe w/BC for the southeast corner of Section 36, T23S-R31E bears S 74°54'05" E a distance of 1806.04', covering **63.45' or 3.85 rods** and having an area of **0.044 acres**.

NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

B.L. Laman PLS 22404
Date Signed: 09/07/2018
Horizon Row, LLC
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizon Row, LLC



QUAD MAP

SECTION 36, T23S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC	Drawn for:		LINE NUMBER: EL8249
DEVON ENERGY PRODUCTION CO., L.P.		devon	WBS NUMBER: XX-129865.01.SLC
PROPOSED 30' EASEMENT			SCALE: 1" = 1000'
Drawn by: Jesus Rivero	Date: 07/03/2018		REVISIONS:
			SHEET: 3 OF 4



AERIAL MAP

SECTION 36, T23S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC	Drawn for: devon		LINE NUMBER: EL8249
DEVON ENERGY PRODUCTION CO., L.P.			WBS NUMBER: XX-129865.01.SLC
PROPOSED 30' EASEMENT			SCALE: 1" = 1000'
Drawn by: Jesus Rivero	Date: 07/03/2018		REVISIONS:
			SHEET: 4 OF 4

TODD 36 CTB 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE SOUTHEAST QUARTER (SE/4)
SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, NEW MEXICO
SHEET 1 OF 6



DESCRIPTION

BEING A SURFACE SITE EASEMENT LYING IN THE SOUTHEAST QUARTER (SE/4) OF SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST N.M.P.M., EDDY COUNTY, NEW MEXICO.

BEGINNING AT THE SOUTHEAST CORNER OF SAID SITE EASEMENT, WHERE A 2" IRON PIPE W/BC FOR THE SOUTHEAST CORNER OF SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST N.M.P.M. BEARS S 68°23'12" E, A DISTANCE 2211.85';

THENCE S 90°00'00" W, A DISTANCE 450.00 FEET TO THE SOUTHWEST CORNER OF THIS EASEMENT;
THENCE N 00°00'00" W, A DISTANCE 500.00 FEET TO THE NORTHWEST CORNER OF THIS EASEMENT;
THENCE N 90°00'00" E, A DISTANCE 450.00 FEET TO THE NORTHEAST CORNER OF THIS EASEMENT;
THENCE S 00°00'00" E, A DISTANCE 500.00 FEET TO THE SOUTHEAST CORNER OF THIS EASEMENT, TO THE POINT OF BEGINNING; CONTAINING 5.165 ACRES.

GENERAL NOTES:

1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A CENTRAL BATTERY.

2.) All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS/No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

B.L. Laman PLS #22404
Horizonrow, LLC
Date Signed: 03-21-2019
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizonrow, LLC

B.L. LAMAN — NEW MEXICO — 22404 — PROFESSIONAL SURVEYOR

DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF NM-128 AND RED ROAD HEAD NORTH ON RED ROAD FOR 0.09 MILES. TURN RIGHT ONTO AN ACCESS ROAD AND HEAD NORTHEAST FOR 0.07 MILES TO THE POINT OF BEGINNING OF THE PROPOSED TODD 36 WELLPAD 1 ACCESS ROAD. LEAVE THE EXISTING ACCESS ROAD AND HEAD NORTH AND EAST ON THE PROPOSED TODD 36 WELLPAD 1 ACCESS ROAD FOR 0.19 MILES TO THE SAME EXISTING ACCESS ROAD AND THEN HEAD EAST FOR 0.40 MILES TO THE POINT OF BEGINNING OF THE PROPOSED TODD 36 CTB 3 ACCESS ROAD. HEAD NORTH AND EAST ALONG THE PROPOSED TODD 36 CTB 3 ACCESS ROAD FOR 0.21 MILES TO THE POINT OF BEGINNING OF THE PROPOSED TODD 36 CTB 2 ACCESS ROAD. TURN RIGHT AND HEAD SOUTH 115' TO THE NORTH CENTER POINT OF THE TODD 36 CTB 2.

0 300 600

HORIZON ROW LLC Drawn for: devon Drawn by: CHRIS MAAS Date: 07/06/2018	DEVON ENERGY PRODUCTION COMPANY, L.P. TODD 36 CTB 2 SURVEY PLAT SHOWING A CTB ON THE PROPERTY OF THE BUREAU OF LAND MANAGEMENT	SITE NUMBER: AA000145925 WBS NUMBER: SCALE: 1" = 300' REVISIONS: DATE OF SURVEY: 6/22/18

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF NM-128 AND RED ROAD HEAD NORTH ON RED ROAD FOR 0.09 MILES. TURN RIGHT ONTO AN ACCESS ROAD AND HEAD NORTHEAST FOR 0.07 MILES TO THE POINT OF BEGINNING OF THE PROPOSED TODD 36 WELLPAD 1 ACCESS ROAD. LEAVE THE EXISTING ACCESS ROAD AND HEAD NORTH AND EAST ON THE PROPOSED TODD 36 WELLPAD 1 ACCESS ROAD FOR 0.19 MILES TO THE SAME EXISTING ACCESS ROAD AND THEN HEAD EAST FOR 0.40 MILES TO THE POINT OF BEGINNING OF THE PROPOSED TODD 36 CTB 3 ACCESS ROAD. HEAD NORTH AND EAST ALONG THE PROPOSED TODD 36 CTB 3 ACCESS ROAD FOR 0.21 MILES TO THE POINT OF BEGINNING OF THE PROPOSED TODD 36 CTB 2 ACCESS ROAD. TURN RIGHT AND HEAD SOUTH 115' TO THE NORTH CENTER POINT OF THE TODD 36 CTB 2.

0 1000 2000

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

Drawn by: CHRIS MAAS

Date: 07/06/2018

Drawn for: devon

EXHIBIT "A"

ACCESS ROAD PLAT
SECTION 36, T23S–R31E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



30' EASEMENT AREA = 0.248 ACRE(S)
359.67 FEET OR 21.80 RODS

0+00.0 P.O.B./EXISTING ACCESS ROAD
0+09.7 EDGE OF ROAD
0+15.0 TODD 36 PRIMARY ELECTRIC LINE
3+12.1 TODD 36 CTB 3 ACCESS ROAD
3+59.7 P.O.E./TODD 36 CTB 2

SEE THE ATTACHED LEGAL DESCRIPTION

Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

NEW MEXICO 22404 PROFESSIONAL SURVEYOR

B.L. Laman PLS #22404
Date Signed: 12-27-2018
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizonrow, LLC

0 1000 2000

HORIZON ROW LLC Drawn for: devon	DEVON ENERGY PRODUCTION COMPANY, L.P. TODD 36 CTB 2 ACCESS ROAD	LINE NUMBER: 7660159R WBS NUMBER: SCALE: 1" = 1000'
Drawn by: CHRIS MAAS Date: 07/06/2018	PROPOSED 30' EASEMENT ON THE PROPERTY OF BUREAU OF LAND MANAGEMENT SECTION 36, T23S–R31E, N.M.P.M.	REVISIONS: CMAAS 12/10/18 DATE OF SURVEY: 12/6/18

SECTION 36, T23S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

ACCESS ROAD PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southeast quarter (SE ¼) of Section 36, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 2" iron pipe w/BC for the southeast corner of Section 36, T23S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence N 75°31'30" W a distance of 2070.98' to the **Point of Beginning** of this easement having coordinates of Northing=457071.37, Easting=728013.39 feet and continuing the following courses;

Thence N 00°38'31" W a distance of 312.07' to an angle point;

Thence N 90°00'00" W a distance of 47.60' to the **Point of Ending** having coordinates of Northing=457383.42, Easting=727962.30 feet from said point a 1" iron pipe w/BC for the east quarter corner of Section 36, T23S-R31E bears N 48°26'39" E a distance of 2728.45', covering **359.67' or 21.80 rods** and having an area of **0.248 acres**.

NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

B.L. Laman PLS 22404
Date Signed: 12/27/2018
Horizon Row, LLC
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizon Row, LLC

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
PLAN VIEW



0 100 200

SHEET 5 OF 6

EARTHWORK QUANTITIES FOR
TODD 36 CTB 2

CUT	FILL	NET
4,836 CY	4,836 CY	0 CY

EARTHWORK QUANTITIES ARE ESTIMATED

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

Drawn by: CHRIS MAAS

Date: 07/06/2018

Drawn for: devon

SECTION 36, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
CROSS SECTIONS







SCALE 1" = 100' HORIZONTAL
SCALE 1" = 10' VERTICAL

SHEET 6 OF 6

EARTHWORK QUANTITIES FOR
TODD 36 CTB 2

CUT	FILL	NET
4,836 CY	4,836 CY	0 CY

EARTHWORK QUANTITIES ARE ESTIMATED

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

Drawn by: CHRIS MAAS

Date: 07/06/2018

Drawn for:

devon

EXHIBIT "A"
PAGE 1 of 4

8" COMPOSITE PIPE
SECTION 36, T23S–R31E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

All flowlines are buried



0+00.0 P.O.B./TODD 36 WELLPAD 3
0+14.5 POWER LINE
0+30.4 FLOWLINE
0+36.3 EDGE OF ROAD
0+42.6 C/L ROAD
0+49.5 EDGE OF ROAD
4+09.4 TODD 36 CTB 3 ELECTRIC LINE
9+25.0 P.O.E./TODD 36 CTB 2

30' EASEMENT AREA = 0.637 ACRE(S)
924.99 FEET OR 56.06 RODS

SEE THE ATTACHED LEGAL DESCRIPTION

Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman PLS #22404
Date Signed: 09-27-2018
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizonrow, LLC

0 1000 2000

HORIZON ROW LLC Drawn for: devon	DEVON ENERGY PRODUCTION COMPANY, L.P. TODD 36 WELLPAD 3 TO CTB 2 FLOWLINE	LINE NUMBER: 7660144F WBS NUMBER: XX-129865.01.SLC SCALE: 1" = 1000'
Drawn by: CHRIS MAAS Date: 09/27/2018	PROPOSED 30' EASEMENT ON THE PROPERTY OF BUREAU OF LAND MANAGEMENT SECTION 36, T23S–R31E, N.M.P.M.	REVISIONS: DATE OF SURVEY: 9/26/18

SECTION 36, T23S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southeast quarter (SE ¼) of Section 36, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 2" iron pipe w/BC for the southeast corner of Section 36, T23S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence N 74°31'36" W a distance of 1764.24' to the **Point of Beginning** of this easement having coordinates of Northing=457024.39, Easting=728318.34 feet and continuing the following courses;

Thence N 00°01'04" W a distance of 244.98' to an angle point;

Thence N 90°00'00" W a distance of 580.96' to an angle point;

Thence N 00°00'00" W a distance of 99.05' to the **Point of Ending** having coordinates of Northing=457368.42, Easting=727737.30 feet from said point a 2" iron pipe w/BC for the southwest corner of Section 36, T23S-R31E bears S 74°16'40" W a distance of 3113.45', covering **924.99' or 56.06 rods** and having an area of **0.637 acres**.

NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

B.L. Laman PLS 22404
Date Signed: 09/27/2018
Horizon Row, LLC
P.O. Box 548, Dry Creek, La.
(903) 388-3045 70637
Employee of Horizon Row, LLC



QUAD MAP

SECTION 36, T23S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

All flowlines are buried

HORIZON ROW LLC		Drawn for: devon	LINE NUMBER: 7660144F
DEVON ENERGY PRODUCTION CO., L.P. PROPOSED 30' EASEMENT			WBS NUMBER: XX-129865.01.SLC
			SCALE: 1" = 1500'
			REVISIONS:
Drawn by: CHRIS MAAS	Date: 09/27/2018		DATE OF SURVEY: 9/27/18



AERIAL MAP

SECTION 36, T23S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

All flowlines are buried

HORIZON ROW LLC		Drawn for: devon	LINE NUMBER: 7660144F
DEVON ENERGY PRODUCTION CO., L.P. PROPOSED 30' EASEMENT			WBS NUMBER: XX-129865.01.SLC
			SCALE: 1" = 1500'
			REVISIONS:
Drawn by: CHRIS MAAS	Date: 09/27/2018		DATE OF SURVEY: 9/27/18

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner: **PWD disturbance (acres):**

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner: **PWD disturbance (acres):**

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:

AFMSS

U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data Report

04/23/2019

Bond Information

Federal/Indian APD: FED

BLM Bond number: CO1104

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: