		Expires: January 31, 2018 Expires: January 31, 2018 NMNM100549 6. If Indian, Allottee or Tribe Name					
•	SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.						
	<u></u>	7. If Unit or CA/Agro	eement, Name and/or N				
	1. Type of Well	8. Well Name and No HH SO 8 5 FED					
	2. Name of Operator CONTACT: LAURA BECERRA CHEVRON USA INCORPORATED E-Mail: LBECERRA@CHEVRON.COM					.9. API Well No. 30-015-45987-00-X1	
	3a. Address 6301 DEAUVILLE BLVD MIDLAND, TX 79706			3b. Phone No. (include area code) Ph: 432-687-7665		10. Field and Pool or Exploratory Area PURPLE SAGE-WOLFCAMP (GAS	
			., R., M., or Survey Description	1)		11. County or Parish,	, State
	Sec 17 T26S R2 32.047600 N Lat					EDDY COUNT	Y, NM
	12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA						
	TYPE OF SUBM	AISSION		ТҮРЕ	OF ACTION		
	🛛 Notice of Intent	t	🗖 Acidize	Deepen	Product	ion (Start/Resume)	UWater Shut-Of
			Alter Casing	🗖 Hydraulic Fracturii	ng 🔲 Reclama	ation	 Well Integrity Other Surface Disturbance
	□ Subsequent Rep		Casing Repair	New Construction	🗖 Recomp		
	Final Abandonr	nent Notice	 Change Plans Convert to Injection 	Plug and Abandon Plug Back	Tempor Water D	arily Abandon Disnosal	
	If the proposal is to a Attach the Bond und	deepen direction: ler which the wor	eration: Clearly state all pertine ally or recomplete horizontally, k will be performed or provide	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/	rting date of any pre- casured and true ve BIA. Required sub	roposed work and appro rtical depths of all perti- psequent reports must be	nent markers and zones filed within 30 days
	If the proposal is to c Attach the Bond und following completion testing has been com determined that the s	deepen directions ler which the wor n of the involved spleted. Final At site is ready for f	eration: Clearly state all pertine ally or recomplete horizontally, k will be performed or provide operations. If the operation re bandonment Notices must be fil inal inspection.	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or r ed only after all requirements, inc	arting date of any p easured and true ve BIA. Required sub recompletion in a r cluding reclamation	roposed work and appro rtical depths of all pertin osequent reports must be new interval, a Form 316 n, have been completed	nent markers and zones e filed within 30 days 50-4 must be filed once and the operator has
-	If the proposal is to a Attach the Bond und following completion testing has been com determined that the s Chevron USA re- to 24'x619' and to The secondary a each well. The se	deepen direction: ler which the wor n of the involved pleted. Final At site is ready for f spectfully req o add a temper access is need econdary acc	eration: Clearly state all pertine ally or recomplete horizontally, k will be performed or provide operations. If the operation re pandonment Notices must be fil inal inspection. uests authorization to ext orary 24'x909' access roa ded to safely enter and ex ess road is temporary and	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or ed only after all requirements, including end the existing service roa to the HH SO 8 5 FED 00 to the HH SO 8 5 FED 00 to the pad during the fracking d will be reclaimed after the	rting date of any prasured and true ve BIA. Required sub recompletion in a ri- cluding reclamation ad from 24'x212 04 well pad. ng operations o a fracking	roposed work and appropriate the sequent reports must be new interval, a Form 316 n, have been completed of Accepted for the formation of the second	nent markers and zones. 2 filed within 30 days 50-4 must be filed once and the operator has 50-4 must be filed once and the operator has 50-5 multiple of the second
	If the proposal is to c Attach the Bond und following completion testing has been com determined that the s Chevron USA re- to 24'x619' and to The secondary a each well. The se operations are co Certified IR plat i	deepen direction: ler which the woin of the involved pleted. Final At site is ready for f spectfully req o add a tempo access is need econdary acc omplete. s attached. T	eration: Clearly state all pertine ally or recomplete horizontally, k will be performed or provide operations. If the operation re bandonment Notices must be fil inal inspection. uests authorization to ext orary 24'x909' access roa ded to safely enter and ex ess road is temporary and his request applies to the	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or ed only after all requirements, including end the existing service roa to the HH SO 8 5 FED 00 to the HH SO 8 5 FED 00 to the pad during the fracking d will be reclaimed after the	rting date of any prasured and true ve BIA. Required sub recompletion in a ri- cluding reclamation ad from 24'x212 04 well pad. ng operations o a fracking	roposed work and appropriate the sequent reports must be new interval, a Form 316 n, have been completed of Accepted for the formation of the second	nent markers and zones. 2 filed within 30 days 50-4 must be filed once and the operator has 50-4 must be filed once and the operator has 50-5 multiple of the second
	If the proposal is to a Attach the Bond und following completion testing has been com determined that the s Chevron USA re- to 24'x619' and to The secondary a each well. The se	deepen direction: ler which the woin of the involved pleted. Final At site is ready for f spectfully req o add a tempo access is need econdary acc complete. s attached. T 004 1H - 30-0 004 2H - 30-0	eration: Clearly state all pertine ally or recomplete horizontally, k will be performed or provide operations. If the operation re pandonment Notices must be fil inal inspection. uests authorization to ext orary 24'x909' access roa ded to safely enter and ex ess road is temporary and his request applies to the 015-45987 015-45988	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or r ed only after all requirements, inc end the existing service roa id to the HH SO 8 5 FED 00 sit the pad during the frackin d will be reclaimed after the approved APDs for the foll	rting date of any prasured and true ve BIA. Required sub recompletion in a ri- cluding reclamation ad from 24'x212 04 well pad. Ing operations of fracking	roposed work and appropriate the sequent reports must be the interval, a Form 316 and the sequent reports must be the interval, a Form 316 and the sequent reports must be the interval, a Form 316 and the sequent reports and the sequent reports must be the sequent reports must be the interval, a Form 316 and the sequent reports and the sequent reports must be the s	nent markers and zones. e filed within 30 days 60-4 must be filed once and the operator has HED FOR APPROVAL
	If the proposal is to c Attach the Bond und following completion testing has been com determined that the s Chevron USA rea to 24'x619' and to The secondary a each well. The se operations are co Certified IR plat i HH SO 8 5 FED HH SO 8 5 FED HH SO 8 5 FED HH SO 8 5 FED	deepen direction: ler which the woin on of the involved spleted. Final At site is ready for f spectfully req o add a tempo access is need econdary acc omplete. s attached. T 004 1H - 30-0 004 2H - 30-0 004 3H - 30-0	aration: Clearly state all pertine ally or recomplete horizontally, 'k will be performed or provide operations. If the operation re- bandonment Notices must be fil- inal inspection. uests authorization to ext orary 24'x909' access roa ded to safely enter and ex- ess road is temporary and his request applies to the 015-45987 015-45988 015-45989	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or ed only after all requirements, including end the existing service roa to the HH SO 8 5 FED 00 to the HH SO 8 5 FED 00 to the pad during the fracking d will be reclaimed after the	rting date of any prasured and true ve BIA. Required sub recompletion in a ri- cluding reclamation ad from 24'x212 04 well pad. Ing operations of fracking	roposed work and appropriate the sequent reports must be the sequent reports and the sequent reports must be the sequence of the s	hent markers and zones. te filed within 30 days 50-4 must be filed once and the operator has HED FOR APPROVAL
-	If the proposal is to c Attach the Bond und following completion testing has been com determined that the s Chevron USA re- to 24'x619' and the The secondary a each well. The se operations are co Certified IR plat i HH SO 8 5 FED HH SO 8 5 FED	deepen direction: ter which the woin of the involved pleted. Final At site is ready for f spectfully req o add a temper access is need econdary acc complete. s attached. T 004 1H - 30-0 004 2H - 30-0 004 3H - 30-0 the foregoing is	eration: Clearly state all pertine andoment Notices must be fil inal inspection. Uests authorization to ext brary 24'x909' access roa led to safely enter and ex ess road is temporary and his request applies to the 015-45987 015-45988 015-45989 015-45989 015-45989 015-45980 01	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or r ed only after all requirements, inc end the existing service roa id to the HH SO 8 5 FED 00 sit the pad during the frackin d will be reclaimed after the approved APDs for the foll	rting date of any prasured and true ve BIA. Required sub recompletion in a ri- cluding reclamation ad from 24'x212 04 well pad. Ing operations of a fracking well of the carlsbad	roposed work and appropriate a period of all period sequent reports must be new interval, a Form 316 n, have been completed of Accepted for feet for feet set and the second set of the second s	nent markers and zones. the filed within 30 days 50-4 must be filed once and the operator has EXAMPLE FOR TED FOR APPROVAL L CONSERVAT
	If the proposal is to c Attach the Bond und following completion testing has been com determined that the s Chevron USA rea to 24'x619' and to The secondary a each well. The se operations are co Certified IR plat i HH SO 8 5 FED HH SO 8 5 FED HH SO 8 5 FED HH SO 8 5 FED	deepen direction: ler which the word on of the involved spleted. Final At site is ready for f spectfully req o add a temper access is need econdary acc complete. s attached. T 004 1H - 30-0 004 2H - 30-0 004 3H - 30-0 the foregoing is corr	eration: Clearly state all pertine ally or recomplete horizontally, rk will be performed or provide operations. If the operation re pandonment Notices must be fil inal inspection. uests authorization to ext orary 24'x909' access roa led to safely enter and ex ess road is temporary and his request applies to the 015-45987 015-45988 015-45989 015-45989 015-45980 015	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or r ed only after all requirements, including end the existing service roa id to the HH SO 8 5 FED 00 sit the pad during the fracking d will be reclaimed after the approved APDs for the foll sector COM 480235 verified by the BLM V ISA INCORPORATED, sent feets approved JUANA MEDRANC	rting date of any prasured and true ve BIA. Required sub recompletion in a ri- cluding reclamation ad from 24'x212 04 well pad. Ing operations of a fracking well of the carlsbad	roposed work and appropriate a sequent reports must be the interval, a Form 316 and the interval, a Form 316 and the been completed for the sequent reports must be a system (19JM0093SE)	nent markers and zones. te filed within 30 days 50-4 must be filed once and the operator has HED FOR HED FOR APPROVAL L CONSERVAT RTESIA DISTRICT
	If the proposal is to c Attach the Bond und following completion testing has been com determined that the s Chevron USA rei to 24'x619' and to The secondary a each well. The se operations are co Certified IR plat i HH SO 8 5 FED HH SO 8 5 FED HH SO 8 5 FED HH SO 8 5 FED HH SO 8 5 FED	deepen direction: ler which the word on of the involved spleted. Final At site is ready for f spectfully req o add a temper access is need econdary acc complete. s attached. T 004 1H - 30-0 004 2H - 30-0 004 3H - 30-0 \mathcal{M} (corr the foregoing is	eration: Clearly state all pertine andoment Notices must be fil inal inspection. Uests authorization to ext brary 24'x909' access roa led to safely enter and ex ess road is temporary and his request applies to the 015-45987 015-45988 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45980 015-45980 015-45980 015-45980 015-45980 015-45980 015-45980 015-45980 015-45980 015-45980 015-45980 015-45980 015-45980 015-45987 015-45980 01	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or ed only after all requirements, including end the existing service roa id to the HH SO 8 5 FED 00 tit the pad during the frackin d will be reclaimed after the approved APDs for the foll approved APDs for the fol	Arting date of any pressured and true ve BIA. Required sub recompletion in a re- cluding reclamation ad from 24'x212 D4 well pad. Ing operations of a fracking forwing wells N S Well Information to the Carlsbad O on 08/23/2019 (roposed work and appropriate a sequent reports must be the interval, a Form 316 and the interval, a Form 316 and the been completed for the sequent reports must be a system (19JM0093SE)	nent markers and zones. the filed within 30 days 50-4 must be filed once and the operator has HED FOR HED FOR APPROVAL CONSERVAT RTESIA DISTRICT DCT 17 2019
	If the proposal is to c Attach the Bond und following completion testing has been com determined that the s Chevron USA rei to 24'x619' and to The secondary a each well. The se operations are co Certified IR plat i HH SO 8 5 FED HH SO 8 5 FED	deepen direction. ler which the word on of the involved upleted. Final At site is ready for f spectfully req o add a temper access is need econdary acc complete. s attached. T 004 1H - 30-C 004 2H - 30-C 004 3H - 30-C	eration: Clearly state all pertine ally or recomplete horizontally, 'k will be performed or provide operations. If the operation re- bandonment Notices must be fil- inal inspection. uests authorization to ext orary 24'x909' access road led to safely enter and ex- ess road is temporary and his request applies to the 015-45987 015-45988 015-45989	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or ed only after all requirements, including end the existing service roa id to the HH SO 8 5 FED 00 tit the pad during the frackin d will be reclaimed after the approved APDs for the foll approved APDs for the fol	rting date of any prasured and true ve BIA. Required sub recompletion in a model cluding reclamation ad from 24'x212 04 well pad. Ing operations of a fracking cowing wighting well information to the Carlsbad o on 08/23/2019 (ULATORY SPE 8/2019	roposed work and appro ritical depths of all perti- ssequent reports must be new interval, a Form 316 a, have been completed of Accepted for feed SEE ATTACH IDITIONS OF MM OF System (19JM0093SE) ECIALIST	nent markers and zones. te filed within 30 days 50-4 must be filed once and the operator has HED FOR HED FOR APPROVAL CONSERVAT RTESIA DISTRICT DCT 17 2019
	If the proposal is to c Attach the Bond und following completion testing has been com determined that the s Chevron USA rei to 24'x619' and to The secondary a each well. The se operations are co Certified IR plat i HH SO 8 5 FED HH SO 8 5 FED	deepen direction. ler which the word on of the involved upleted. Final At site is ready for f spectfully req o add a temper access is need econdary acc complete. s attached. T 004 1H - 30-C 004 2H - 30-C 004 3H - 30-C	eration: Clearly state all pertine ally or recomplete horizontally, 'k will be performed or provide operations. If the operation re- bandonment Notices must be fil- inal inspection. uests authorization to ext orary 24'x909' access road led to safely enter and ex- ess road is temporary and his request applies to the 015-45987 015-45988 015-45989	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or ed only after all requirements, inclu- end the existing service roa to to the HH SO 8 5 FED 00 tit the pad during the frackin d will be reclaimed after the approved APDs for the foll A80235 verified by the BLM V ISA INCORPORATED, sent essing by JUANA MEDRANC Title REG	rting date of any prasured and true ve BIA. Required sub recompletion in a model cluding reclamation ad from 24'x212 04 well pad. Ing operations of a fracking cowing wighting well information to the Carlsbad o on 08/23/2019 (ULATORY SPE 8/2019	roposed work and appro ritical depths of all perti- ssequent reports must be new interval, a Form 316 a, have been completed of Accepted for feed SEE ATTACH IDITIONS OF MM OF System (19JM0093SE) ECIALIST	nent markers and zones. te filed within 30 days 60-4 must be filed once and the operator has HED FOR APPROVAL CONSERVAT RTESIA DISTRICT DCT 17 2019
	If the proposal is to c Attach the Bond und following completion testing has been com determined that the s Chevron USA re- to 24'x619' and to The secondary a each well. The se operations are cc Certified IR plat i HH SO 8 5 FED HH SO 8 5 FED	deepen direction. ler which the woin on of the involved pleted. Final At- spectfully req o add a tempo- inccess is needer econdary accomplete. s attached. T 004 1H - 30-0 004 2H - 30-0 004 3H - 30-0 004 3H - 30-0 the foregoing is Corr D LAURA BE (Electronic S (Electronic S	eration: Clearly state all pertine ally or recomplete horizontally, rk will be performed or provide operations. If the operation re bandonment Notices must be fil inal inspection. uests authorization to ext brary 24'x909' access road led to safely enter and ex- ess road is temporary and his request applies to the 015-45987 015-45988 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45989 015-45987 015-45989 015-45987 015-45987 015-45988 015-45987 0	nt details, including estimated sta give subsurface locations and me the Bond No. on file with BLM/ sults in a multiple completion or ed only after all requirements, inclu- end the existing service roa do to the HH SO 8 5 FED 00 it the pad during the frackin d will be reclaimed after the approved APDs for the foll approved APDs for the foll ap	rting date of any prasured and true ve BIA. Required sub recompletion in a model cluding reclamation ad from 24'x212 04 well pad. Ing operations of a fracking cowing wighting well information to the Carlsbad o on 08/23/2019 (ULATORY SPE 8/2019	roposed work and appro ritical depths of all perti- ssequent reports must be new interval, a Form 316 a, have been completed of Accepted for feed SEE ATTACH IDITIONS OF MM OF System (19JM0093SE) ECIALIST	nent markers and zones. te filed within 30 days 60-4 must be filed once and the operator has HED FOR APPROVAL CONSERVAT RTESIA DISTRICT DCT 17 2019

•

Additional data for EC transaction #480235 that would not fit on the form

32. Additional remarks, continued

i

HH SO I	8 5 FED 004 4H - 30-015-45990
HH SO 8	8 5 FED 004 5H - 30-015-45991
HH SO 8	8 5 FED 004 6H - 30-015-45992

PECOS DISTRICT SURFACE USE CONDITIONS OF APPROVAL

OPERATOR'S NAME: CHEVRON USA INCORPORATED LEASE NO: NMNM100549 LOCATION: EDDY

HH SO 8 5 FED 004 1H

Surface Hole Location: 783' FNL & 1584' FEL, NWNE, Section 17, T. 26 S., R. 27 E. Bottom Hole Location: 280' FNL & 750' FEL, Section 5, T. 23 S., R. 29 E.

HH SO 8 5 FED 004 2H

Surface Hole Location: 783' FNL & 1559' FEL, NWNE, Section 17, T. 26 S., R. 27 E. Bottom Hole Location: 280' FNL & 1590' FEL, Section 5, T. 23 S., R. 29 E.

HH SO 8 5 FED 004 3H

Surface Hole Location: 783' FNL & 1534' FEL, NWNE, Section 17, T. 26 S., R. 27 E. Bottom Hole Location: 280' FNL & 1170' FEL, Section 5, T. 23 S., R. 29 E.

HH SO 8 5 FED 004 4H

Surface Hole Location: 783' FNL & 1509' FEL, NWNE, Section 17, T. 26 S., R. 27 E. Bottom Hole Location: 280' FNL & 330' FEL, Section 5, T. 23 S., R. 29 E.

HH SO 8 5 FED 004 5H

Surface Hole Location: 783' FNL & 1484' FEL, NWNE, Section 17, T. 26 S., R. 27 E. Bottom Hole Location: 280' FNL & 330' FEL, Section 5, T. 23 S., R. 29 E.

HH SO 8 5 FED 004 6H

Surface Hole Location: 783' FNL & 1459' FEL, NWNE, Section 17, T. 26 S., R. 27 E. Bottom Hole Location: 280' FNL & 1254' FEL, Section 5, T. 23 S., R. 29 E.

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

 General Provisions Permit Expiration Archaeology, Paleontology, and Historical Sites Noxious Weeds Special Requirements
Cave/Karst
Hydrology
Special Status Plant Species Habitat
Construction
Notification
Topsoil
Closed Loop System
Federal Mineral Material Pits
Well Pads
Roads
☐ Road Section Diagram
Well Structures & Facilities
Pipelines
Final Abandonment & Reclamation

Ð

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Cave/Karst Surface Mitigation

The following stipulations will be applied to minimize impacts during construction, drilling and production:

Construction:

General Construction:

- No blasting
- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, cave passages, or voids are penetrated during construction, and no additional construction shall occur until clearance has been issued by the Authorized Officer.
- All linear surface disturbance activities will avoid sinkholes and other karst features to lessen the possibility of encountering near surface voids during construction, minimize changes to runoff, and prevent untimely leaks and spills from entering the karst drainage system.
- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

Pad Construction:

- The pad will be constructed and leveled by adding the necessary fill and caliche no blasting.
- The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.
- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g., caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised

(i.e. an access road crossing the berm cannot be lower than the berm height).

• Following a rain event, all fluids will vacuumed off of the pad and hauled off-site and disposed at a proper disposal facility.

Tank Battery Construction:

- The pad will be constructed and leveled by adding the necessary fill and caliche no blasting.
- All tank battery locations and facilities will be lined and bermed.
- The liner should be at least 20 mil in thickness and installed with a 4 oz. felt backing, or equivalent, to prevent tears or punctures.
- Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

Road Construction:

- Turnout ditches and drainage leadoffs will not be constructed in such a manner as to alter the natural flow of water into or out of cave or karst features.
- Special restoration stipulations or realignment may be required if subsurface features are discovered during construction.

Buried Pipeline/Cable Construction:

• Rerouting of the buried line(s) may be required if a subsurface void is encountered during construction to minimize the potential subsidence/collapse of the feature(s) as well as the possibility of leaks/spills entering the karst drainage system.

Powerline Construction:

- Smaller powerlines will be routed around sinkholes and other karst features to avoid or lessen the possibility of encountering near surface voids and to minimize changes to runoff or possible leaks and spills from entering karst systems.
- Larger powerlines will adjust their pole spacing to avoid cave and karst features.
- Special restoration stipulations or realignment may be required if subsurface voids are encountered.

Surface Flowlines Installation:

• Flowlines will be routed around sinkholes and other karst features to minimize the possibility of leaks/spills from entering the karst drainage system.

Leak Detection System:

• A method of detecting leaks is required. The method could incorporate gauges to measure loss, situating values and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present.

- A leak detection plan will be submitted to BLM that incorporates an automatic shut off system (see below) to minimize the effects of an undesirable event that could negatively sensitive cave/karst resources.
- Well heads, pipelines (surface and buried), storage tanks, and all supporting equipment should be monitored regularly after installation to promptly identify and fix leaks.

Automatic Shut-off Systems:

 Automatic shut off, check values, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and groundwater concerns:

Closed Loop System:

- A closed loop system using steel tanks will be utilized during drilling no pits
- All fluids and cuttings will be hauled off-site and disposed of properly at an authorized site

Rotary Drilling with Fresh Water:

• Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

Directional Drilling:

• The kick off point for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

Lost Circulation:

- ALL lost circulation zones between surface and the base of the cave occurrence zone will be logged and reported in the drilling report.
- If a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, regardless of the type of drilling machinery used, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

Abandonment Cementing:

- Additional plugging conditions of approval may be required upon well abandonment in high and medium karst potential occurrence zones.
- The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

Pressure Testing:

- The operator will perform annual pressure monitoring on all casing annuli and reported in a sundry notice.
- If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

<u>Hydrology</u>

The entire well pad(s) will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. The compacted berm shall be constructed at a minimum of 12 inches with impermeable mineral material (e.g. caliche). Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion. Stockpiling of topsoil is required. The top soil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control. If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

When crossing ephemeral drainages the pipeline(s) will be buried to a minimum depth of 48 inches from the top of pipe to ground level. Erosion control methods such as gabions and/or rock aprons should be placed on both up and downstream sides of the pipeline crossing. In addition, curled (weed free) wood/straw fiber wattles/logs and/or silt fences should be placed on the downstream side for sediment control during construction and maintained until soils and vegetation have stabilized. Water bars should be placed within the ROW to divert and dissipate surface runoff. A pipeline access road is not permitted to cross these ephemeral drainages. Traffic should be diverted to a preexisting route. Additional seeding may be required in floodplains and drainages to restore energy dissipating vegetation.

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Any water erosion that may occur due to the construction of overhead electric line and during the life of the power line will be quickly corrected and proper measures will be taken to prevent future erosion. A power pole should not be placed drainages or floodplains and must span across the features at a distance away that would not promote further erosion.

SPECIAL STATUS PLANT SPECIES (SSPS)

Vehicles and equipment will be kept on existing roads and approved surfaces only, and will avoid travel across undisturbed surfaces; workers will be instructed not to park off the roads or ROW in undisturbed areas.

Alterations to project design and additions of project components will require SSPS surveys and re-analysis of impacts if those project elements intersect SSPS suitable habitat.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed thirty (30) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: $\underline{400'} + 100' = 200'$ lead-off ditch interval $\underline{4\%}$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 $\frac{1}{2}$ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production

equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the Grant and attachments, including stipulations, survey plat(s) and/or map(s), shall be on location during construction. BLM personnel may request to review a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, Holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC § 2601 *et seq.* (1982) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant (*see* 40 CFR, Part 702-799 and in particular, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193). Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. Holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms

are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. § 9601, *et seq.* or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, *et seq.*) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way Holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way Holder on the Right-of-Way. This provision applies without regard to whether a release is caused by Holder, its agent, or unrelated third parties.

4. Holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. Holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of Holder including, but not limited to: construction, operation, maintenance, and termination of the facility;
- b. Activities of other parties including, but not limited to:
 - (1) Land clearing
 - (2) Earth-disturbing and earth-moving work
 - (3) Blasting
 - (4) Vandalism and sabotage;
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of Holder, regardless of fault. Upon failure of Holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he/she deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of Holder. Such action by the Authorized Officer shall not relieve Holder of any responsibility as provided herein.

6. All construction and maintenance activity shall be confined to the authorized

right-of-way width of <u>20</u> feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline shall be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline shall be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity shall be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation shall be allowed unless approved in writing by the Authorized Officer.

8. Holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky of duney areas, the pipeline shall be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of <u>24</u> inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than

routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines shall be less than or equal to 4 inches and a working pressure below 125 psi.

STANDARD STIPULATIONS FOR BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 <u>et seq.</u> (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section

102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, <u>et seq</u>. or the Resource Conservation and Recovery Act, 42 U.S.C.6901, <u>et seq</u>.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-ofway.

6. The pipeline will be buried with a minimum cover of <u>36</u> inches between the top of the pipe and ground level.

7. The maximum allowable disturbance for construction in this right-of-way will be <u>30</u> feet:

- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed **20** feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
- Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed <u>30</u> feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving*)

ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.)

• The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)

8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately <u>6</u> inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

(X) seed mixture 1	() seed mixture 3
() seed mixture 2	() seed mixture 4
() seed mixture 2/LPC	() Aplomado Falcon Mixture

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 1 for Loamy Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed shall be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed shall be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture shall be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed shall be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre shall be doubled. The seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species	<u>lb/acre</u>
Plains lovegrass (Eragrostis intermedia)	0.5
Sand dropseed (Sporobolus cryptandrus)	1.0
Sideoats grama (Bouteloua curtipendula)	5.0
Plains bristlegrass (Setaria macrostachya)	2.0
*Pounds of pure live seed:	

Pounds of seed **x** percent purity **x** percent germination = pounds pure live seed