

RECEIVED

Form 3160-3
(June 2015)

DEC 04 2019

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
DISTRICT 7 - ARTESIA O.C.D.

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No. NMNM120904	
6. If Indian, Allottee or Tribe Name	
7. If Unit or CA Agreement, Name and No.	
8. Lease Name and Well No. THOROUGHbred-10-3.FED 621H 326523	
9. API Well No. 30-015-46478	
10. Field and Pool, or Exploratory PURPLE SAGE / WOLFCAMP GAS	
11. Sec., T. R. M. or Blk. and Survey or Area SEC 10 / T26S / R31E / NMP	
12. County or Parish EDDY	13. State NM
14. Distance in miles and direction from nearest town or post office*	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 220 feet	16. No of acres in lease 200
17. Spacing Unit dedicated to this well 240	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 1876 feet	19. Proposed Depth 11325 feet / 18695 feet
20. BLM/BIA Bond No. in file FED: NMB000801	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3242 feet	22. Approximate date work will start* 05/27/2020
23. Estimated duration 45 days	
24. Attachments	
The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)	
1. Well plat certified by a registered surveyor. 2. A Drilling Plan. 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).	4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). 5. Operator certification. 6. Such other site specific information and/or plans as may be requested by the BLM.
25. Signature (Electronic Submission)	Name (Printed/Typed) Jenny Harms / Ph: (405)552-6560
Title Regulatory Compliance Professional	Date 06/27/2019
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Christopher Walls / Ph: (575)234-2234
Title Petroleum Engineer	Office CARLSBAD
Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached.	
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.	

APPROVED WITH CONDITIONS
Approval Date: 11/25/2019

Need
GQP?

RWP 12-10-19

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not

hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

- Thoroughbred 10-3 Fed Com 621H (Pad 1)
220 FSL, 380 FWL Section 10, T.26., R. 31E.
- Thoroughbred 10-3 Fed Com 711H (Pad 1)
220 FSL, 350 FWL Section 10, T.26., R. 31E.
- Thoroughbred 10-3 Fed Com 731H (Pad 1)
220 FSL, 410 FWL Section 10, T.26., R. 31E.
- Thoroughbred 10-3 Fed Com 712H (Pad 2)
220 FSL, 1470 FWL Section 10, T.26., R. 31E.
- Thoroughbred 10-3 Fed Com 332H (Pad 2)
220 FSL, 1500 FWL Section 10, T.26., R. 31E.
- Thoroughbred 10-3 Fed Com 732H (Pad 2)
220 FSL, 1530 FWL Section 10, T.26., R. 31E.

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
 - Phantom Banks SMA
 - Hydrology
 - Range
 - Karst
- Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- Road Section Diagram**
- Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- Interim Reclamation**
- Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Phantom Banks SMA

Surface disturbance will not be allowed within up to 200 meters of active heronries or by delaying activity for up to 120 days, or a combination of both.

Hydrology:

The entire well pad(s) will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. The compacted berm shall be constructed at a minimum of 12 inches with impermeable mineral material (e.g. caliche). Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion. Stockpiling of topsoil is required. The top soil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control. If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

When crossing ephemeral drainages the pipeline(s) will be buried to a minimum depth of 48 inches from the top of pipe to ground level. Erosion control methods such as gabions and/or rock aprons should be placed on both up and downstream sides of the pipeline crossing. In addition, curled (weed free) wood/straw fiber wattles/logs and/or silt fences should be placed on the downstream side for sediment control during construction and maintained until soils and vegetation have stabilized. Water bars should be placed within the ROW to divert and dissipate surface runoff. A pipeline access road is not permitted to cross these ephemeral drainages. Traffic should be diverted to a preexisting route. Additional seeding may be required in floodplains and drainages to restore energy dissipating vegetation.

Prior to pipeline installation/construction a leak detection plan will be developed. The method(s) could incorporate gauges to detect pressure drops, siting valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Any water erosion that may occur due to the construction of overhead electric line and during the life of the power line will be quickly corrected and proper measures will be taken to prevent future erosion. A power pole should not be placed in drainages, playas, wetlands, riparian areas, or floodplains and must span across the features at a distance away that would not promote further erosion.

Livestock Watering Requirement

Any damage to structures that provide water to livestock throughout the life of the well, caused by operations from the well site, must be immediately corrected by the operator. The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

Fence Requirement

Where entry is granted across a fence line, the fence must be braced and tied off on both sides of the passageway with H-braces prior to cutting. Once the work is completed, the fence will be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

The operator must contact the allotment holder prior to construction to identify the location of the pipeline. The operator must take measures to protect the pipeline from compression or other damages. If the pipeline is damaged or compromised in any way near the proposed project as a result of oil and gas activity, the operator is responsible for repairing the pipeline immediately. The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

During construction, the proponent shall minimize disturbance to existing fences, water lines, troughs, windmills, and other improvements on public lands. The proponent is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the grazing permittee/allottee prior to disturbing any range improvement projects. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

CONSTRUCTION MITIGATION

In order to mitigate the impacts from construction activities on cave and karst resources, the following Conditions of Approval will apply to this APD or project:

- In the event that any underground voids are encountered during construction activities, construction activities will be halted and the BLM will be notified immediately.
- No blasting – the pad and roads will be constructed and leveled by adding the necessary fill and caliche.
- All pads will be bermed to minimize the impact of any spilled contaminants

DRILLING MITIGATION

Federal regulations and standard Conditions of Approval applied to all APDs require that adequate measures are taken to prevent contamination to the environment. Due to the extreme sensitivity of the cave and karst resources in this project area, the following additional Conditions of Approval will be added to this APD.

To prevent cave and karst resource contamination the following will be required.

- Closed mud system using steel tanks - all fluids and cuttings will be hauled off-site and disposed of properly
- Rotary drilling with fresh water where cave or karst features are expected to prevent contamination of freshwater aquifers.
- Directional drilling is only allowed at depths greater than 100 feet below the cave occurrence zone to prevent additional impacts resulting from directional drilling.
- Lost circulation zones will be logged and reported in the drilling report so BLM can assess the situation and work with the operator on corrective actions.
- Additional drilling, casing, and cementing procedures to protect cave zones and fresh water aquifers. See drilling COAs.

PRODUCTION MITIGATION

In order to mitigate the impacts from production activities and due to the nature of karst terrane, the following Conditions of Approval will apply to this APD:

- Tank battery locations and facilities will be bermed and lined with a 20 mil thick permanent liner that has a 4 oz. felt backing, or equivalent, to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.
- Development and implementation of a leak detection system to provide an early alert to operators when a leak has occurred.
- Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

RESIDUAL AND CUMULATIVE MITIGATION

- The operator will perform annual pressure monitoring on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be taken to correct the problem to the BLM's approval.

PLUGGING AND ABANDONMENT MITIGATION

- Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C.6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.
6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.
7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:
 - Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
 - Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
 - The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)
8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.
9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.
11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- | | |
|--|--|
| <input type="checkbox"/> seed mixture 1 | <input type="checkbox"/> seed mixture 3 |
| <input checked="" type="checkbox"/> seed mixture 2 | <input type="checkbox"/> seed mixture 4 |
| <input type="checkbox"/> seed mixture 2/LPC | <input type="checkbox"/> Aplomado Falcon Mixture |

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates “Standard Environmental Colors” – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder’s name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches that are not otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or

other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.

5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the

Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species	lb/acre
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sand love grass (<i>Eragrostis trichodes</i>)	1.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

12/02/2019

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Jenny Harms

Signed on: 06/27/2019

Title: Regulatory Compliance Professional

Street Address: 333 West Sheridan Avenue

City: Oklahoma City **State:** OK

Zip: 73102

Phone: (405)552-6560

Email address: jennifer.harms@dvn.com

Field Representative

Representative Name: Ray vaz

Street Address: 333 WEST SHERIDAN AVE

City: OKLAHOMA CITY **State:** OK

Zip: 73102

Phone: (575)748-1871

Email address: ray.vaz@dvn.com



APD ID: 10400043121

Submission Date: 06/27/2019

Highlighted data reflects the most recent changes

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHBRED 10-3 FED

Well Number: 621H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - General

APD ID: 10400043121

Tie to previous NOS?

Submission Date: 06/27/2019

BLM Office: CARLSBAD

User: Jenny Harms

Title: Regulatory Compliance Professional

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM120904

Lease Acres: 200

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: DEVON ENERGY PRODUCTION COMPANY LP

Operator letter of designation:

Operator Info

Operator Organization Name: DEVON ENERGY PRODUCTION COMPANY LP

Operator Address: 333 West Sheridan Avenue

Zip: 73102

Operator PO Box:

Operator City: Oklahoma City State: OK

Operator Phone: (800)583-3866

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: THOROUGHBRED 10-3 FED

Well Number: 621H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: PURPLE SAGE

Pool Name: WOLFCAMP

Is the proposed well in an area containing other mineral resources? NATURAL GAS,OIL,POTASH

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHbred 10-3 FED

Well Number: 621H

Is the proposed well in an area containing other mineral resources? NATURAL GAS,OIL,POTASH

Is the proposed well in a Helium production area? N Use Existing Well Pad? YES New surface disturbance? N

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: Number: 1

Well Class: HORIZONTAL

THOROUGHbred 10 WELLPAD

Number of Legs:

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town:

Distance to nearest well: 1876 FT

Distance to lease line: 220 FT

Reservoir well spacing assigned acres Measurement: 240 Acres

Well plat: THOROUGHbred_10_3_FED_COM_621H_WL_P_C102_SIGNED_5_3_2019_20190904091510.pdf

Well work start Date: 05/27/2020

Duration: 45 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number: 7226

Reference Datum:

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
SHL Leg #1	220	FSL	380	FWL	26S	31E	10	Aliquot SWS W	32.050728	-103.7734279	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 120904	324 2	0	0	
KOP Leg #1	50	FSL	790	FWL	26S	31E	10	Aliquot SWS W	32.050258	-103.772107	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 120904	- 751 0	107 65	107 52	
PPP Leg #1-1	330	FSL	890	FWL	26S	31E	10	Aliquot SWS W	32.0510328	-103.7717819	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 120904	- 800 4	113 66	112 46	


Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHBRED 10-3 FED

Well Number: 621H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
EXIT Leg #1	231 0	FSL	890	FWL	26S	31E	3	Aliquot NWS W	32.07113 05	- 103.7717 509	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 089057	- 808 3	186 95	113 25	
BHL Leg #1	231 0	FSL	890	FWL	26S	31E	3	Aliquot NWS W	32.07113 05	- 103.7717 509	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 089057	- 808 3	186 95	113 25	

**SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
SITE MAP**



NOTE: LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1983 (NAD83). LISTED NEW MEXICO STATE PLANE EAST COORDINATES ARE GRID (NAD83). BASIS OF BEARING AND DISTANCES USED ARE NEW MEXICO STATE PLANE EAST COORDINATES MODIFIED TO THE SURFACE. ELEVATION VALUES ARE NAVD88.

012 60 120 240
SCALE 1" = 120'

DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF CR. 1 (ORLA HWY.) & MONSANTO ROAD, GO SOUTH ON CR. 1 APPROX. 4.2 MILES TO A CALICHE ROAD (PIPELINE ROAD), TURN RIGHT (WEST) AND GO APPROX. 5.2 MILES TO A "T" INTERSECTION, TURN LEFT AND GO SOUTH APPROX. 1.0 MILE, TURN RIGHT AND GO WEST APPROX. 0.25 MILE TO THE SOUTHWEST CORNER OF AN EXISTING WELLPAD AND A ROAD SURVEY, TURN RIGHT AND FOLLOW ROAD SURVEY NORTH APPROX. 0.2 MILE, TURN LEFT AND GO WEST APPROX. 0.2 MILE, TURN LEFT AND GO SOUTH APPROX. 0.1 MILE TO THE NORTHEAST PAD CORNER FOR THIS LOCATION.


**DEVON ENERGY PRODUCTION COMPANY, L.P.
THOROUGHBRED 10-3 FED COM 621H
LOCATED 220 FT. FROM THE SOUTH LINE
AND 380 FT. FROM THE WEST LINE OF
SECTION 10, TOWNSHIP 26 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO**

MAY 3, 2019

SURVEY NO. 7226


MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 **CARLSBAD, NEW MEXICO**

SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 INTERIM SITE BUILD PLAN



 DENOTES INTERIM PAD RECLAMATION AREA

 DENOTES GRADING SITE RECLAMATION AREA




2.032± ACRES INTERIM PAD RECLAMATION AREA
 3.590± ACRES GRADING SITE RECLAMATION AREA
 2.413± ACRES NON-RECLAIMED AREA
 8.035± ACRES THOROUGHNBRED 10 WELLPAD 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
THOROUGHNBRED 10-3 FED COM 621H
 LOCATED 220 FT. FROM THE SOUTH LINE
 AND 380 FT. FROM THE WEST LINE OF
 SECTION 10, TOWNSHIP 26 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

MAY 3, 2019

SURVEY NO. 7226

SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL PHOTO



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
FEB. 2019


DEVON ENERGY PRODUCTION COMPANY, L.P.
THOROUGHbred 10-3 FED COM 621H
LOCATED 220 FT. FROM THE SOUTH LINE
AND 380 FT. FROM THE WEST LINE OF
SECTION 10, TOWNSHIP 26 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

MAY 3, 2019

SURVEY NO. 7226

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
FEB. 2019

DEVON ENERGY PRODUCTION COMPANY, L.P.
THOROUGHbred 10-3 FED COM 621H
LOCATED 220 FT. FROM THE SOUTH LINE
AND 380 FT. FROM THE WEST LINE OF
SECTION 10, TOWNSHIP 26 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

MAY 3, 2019

SURVEY NO. 7226

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

PLAN VIEW

THOROUGHbred
10 CTB 1

STAKED ACCESS ROAD

PROPOSED 114 L.F.
ACCESS ROAD

PROPOSED 320 L.F.
PAD ACCESS ROAD

LIMITS OF
EARTHWORK
3:1 SLOPE (TYP.)


LIMITS OF
EARTHWORK
3:1 SLOPE (TYP.)



DEVON ENERGY PRODUCTION COMPANY, L.P.
PAD GRADING AND CROSS SECTIONS
FOR THOROUGHbred 10-3 FED COM 621H
SECTION 10, TOWNSHIP 26 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

CUT	FILL	NET
22526 CU. YD	19297 CU. YD	3229 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED



MAY 3, 2019


MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

301 SOUTH CANAL
(575) 234-3341


SHEET 1-2
SURVEY NO. 7226

CROSS-SECTIONS


SECTION A-A'



SECTION B-B'



SECTION C-C'



0 12 60 120 240
 SCALE 1" = 120' - 1" = 20' VER

DEVON ENERGY PRODUCTION COMPANY, L.P.
 PAD GRADING AND CROSS SECTIONS
FOR THOROUGHBRED 10-3 FED COM 621H
 SECTION 10, TOWNSHIP 26 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

CUT	FILL	NET
22526 CU. YD	19297 CU. YD	3229 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED


MAY 3, 2019
MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
 (575) 234-3341

SHEET 2-2
 SURVEY NO. 7226


ACCESS ROAD PLAT

PAD ACCESS ROAD FOR THOROUGHREAD 10-3 FED COM 711H, 621H, 731H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 3, 2019



SEE NEXT SHEET (2-2) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSPE EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS _____ DAY OF MAY 2019

(Handwritten signature of Filimon F. Jaramillo)

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

FILIMON F. JARAMILLO, SLS. 12797

SURVEY NO. 7226

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SHEET: 1-2

ACCESS ROAD PLAT

PAD ACCESS ROAD FOR THOROUGHREAD 10-3 FED COM 711H, 621H, 731H

**DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 3, 2019**

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S55°03'41"W, A DISTANCE OF 802.59 FEET;
THENCE N89°44'48"E A DISTANCE OF 189.64 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N44°42'52"E A DISTANCE OF 50.00 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N00°15'28"W A DISTANCE OF 80.30 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE WEST QUARTER CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N23°10'17"W, A DISTANCE OF 2273.13 FEET;

SAID STRIP OF LAND BEING 319.94 FEET OR 19.39 RODS IN LENGTH, CONTAINING 0.220 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 319.94 L.F. 19.39 RODS 0.220 ACRES

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-2

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 3RD DAY OF MAY 2019

[Signature]
FILIMON F. JARAMILLO, PLS. 12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 7226

301 SOUTH CANAL
(575) 234-3341



APD ID: 10400043121

Submission Date: 06/27/2019

Highlighted data reflects the most recent changes

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHbred 10-3 FED

Well Number: 621H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	UNKNOWN	3242	0	0	OTHER, ALLUVIUM : Surface	NONE	N
2	RUSTLER	1903	1338	1338	SANDSTONE	NONE	N
3	TOP SALT	1591	1651	1651	SALT	NONE	N
4	BASE OF SALT	-601	3842	3842	SALT	NONE	N
5	LAMAR	-840	4082	4082	SANDSTONE	NATURAL GAS,OIL	N
6	BELL CANYON	-860	4102	4102	SANDSTONE	NATURAL GAS,OIL	N
7	CHERRY CANYON	-1810	5052	5052	SANDSTONE	NATURAL GAS,OIL	N
8	BRUSHY CANYON	-3100	6342	6342	SANDSTONE	NATURAL GAS,OIL	N
9	BONE SPRING LIME	-4758	8000	8000	LIMESTONE,SANDSTONE	NATURAL GAS,OIL	N
10	BONE SPRING	-5780	9022	9022	SANDSTONE	NATURAL GAS,OIL	N
11	BONE SPRING 2ND	-6420	9662	9662	SANDSTONE	NATURAL GAS,OIL	N
12	BONE SPRING LIME	-6970	10212	10212	LIMESTONE	NATURAL GAS,OIL	N
13	BONE SPRING 3RD	-7680	10922	10922	SANDSTONE	NATURAL GAS	N
14	WOLFCAMP	-8086	11327	11327	SANDSTONE	NATURAL GAS,OIL	Y
15	STRAWN	-10580	13822	13822	LIMESTONE	NATURAL GAS,OIL	N

Section 2 - Blowout Prevention

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHbred 10-3 FED

Well Number: 621H

Pressure Rating (PSI): 5M

Rating Depth: 11110

Equipment: BOP/BOPE will be installed per Onshore Oil & Gas Order #2 requirements prior to drilling below surface casing, a BOP/BOPE system with the above minimum rating will be installed on the wellhead system. BOP/BOPE will be tested by an independent service company per Onshore Oil & Gas Order #2 requirements and MASP (Maximum Anticipated Surface Pressure) calculations. If the system is upgraded, all the components installed will be functional and tested.

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.

Testing Procedure: A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Choke Diagram Attachment:

5M_BOPE__CK_20190406162412.pdf

BOP Diagram Attachment:

5M_BOPE__CK_20190408073802.pdf

Pressure Rating (PSI): 5M

Rating Depth: 11325

Equipment: BOP/BOPE will be installed per Onshore Oil & Gas Order #2 requirements prior to drilling below intermediate casing, a BOP/BOPE system with the above minimum rating will be installed on the wellhead system. BOP/BOPE will be tested by an independent service company per Onshore Oil & Gas Order #2 requirements and MASP (Maximum Anticipated Surface Pressure) calculations. If the system is upgraded, all the components installed will be functional and tested.

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.

Testing Procedure: A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Choke Diagram Attachment:

5M_BOPE__CK_20190627144730.pdf

BOP Diagram Attachment:

5M_BOPE__CK_20190627144856.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHbred 10-3 FED

Well Number: 621H

Section 3 - Casing

1	Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE		17.5	13.375	NEW	API	N	0	1443	0	1443	-6965	-8031	1443	H-40	48	ST&C	1.12	1	BUOY	1.6	BUOY	1.6
2	INTERMED LATE		9.875	7.625	NEW	API	N	0	10929	0	10929	-6965	-12965	10929	P-110	29.7	OTHER - Flushmax III	1.12	1	BUOY	1.6	BUOY	1.6
3	PRODUCTI ON		6.75	5.5	NEW	API	N	0	18696	0	11325	-6965	-17514	18696	P-110	20	OTHER - Vam SG	1.12	1	BUOY	1.6	BUOY	1.6

Casing Attachments

Casing ID: 1 String Type: SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Surf_Csg_Ass_20190406163130.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHBRED 10-3 FED

Well Number: 621H

Casing Attachments

Casing ID: 2 String Type: INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Int_Csg_Ass_20190406163257.pdf

Casing ID: 3 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Prod_Csg_Ass_20190406163405.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1443	1082.7	1.44	13.2	1559.1	50	C	Class C + adds

INTERMEDIATE	Lead		0	6929	717.5	3.27	9	2346.3	30	C	Class C + Adds
INTERMEDIATE	Tail		6929	10929	783	1.44	13.2	1127.6	30	C	Class C + Adds
PRODUCTION	Lead		8765	10765	63	3.27	9	205.8	10	TUNED	Class C + adds

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHBRED 10-3 FED

Well Number: 621H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Tail		1076 5	1869 6	506	1.44	13.2	728.6	10	H	(50:50) Clas H Cement: Poz (Fly Ash) + 0.5% bwoc HALAD-344 + 0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2% bwoc Bentonite

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Describe the mud monitoring system utilized: PVT/Pason/Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
1092 9	1132 5	OIL-BASED MUD	10	10.5				2			
1443	1092 9	OTHER : DBE / Cut Brine	10	10.5				2			
0	1443	OTHER : FW Gel	8.5	9							

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHBRED 10-3 FED

Well Number: 621H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Will run GRMWD from TD to from KOP. Cement bond logs will be run in vertical to determine top of cement. Stated logs run will be in the completion report and submitted to the BLM.

List of open and cased hole logs run in the well:

CALIPER,CBL,DS,GR,MUDLOG

Coring operation description for the well:

N/A

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 6183

Anticipated Surface Pressure: 3691.5

Anticipated Bottom Hole Temperature(F): 159

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

Thoroughbred_10_3_Fed_Com_621H_H2S_20190627145629.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Devon_Thoroughbred_10_3_FED_COM_621H_AC_Report_Permit_Plan_1_20190627145837.pdf

Devon_Thoroughbred_10_3_FED_COM_621H_Permit_Plan_1_20190627145838.pdf

Devon_Thoroughbred_10_3_Fed_Com_621H_Plot_Permit_Plan_1_20190627145838.pdf

Thoroughbred_10_3_Fed_Com_621H_Permit_Plan_1_20190627145839.pdf

Other proposed operations facets description:

Multi-Bowl Verbiage 5M

Multi-Bowl Wellhead 5M

Closed-Loop Design Plan

Gas Capture Plan

Spudder Rig

Other proposed operations facets attachment:

Spudder_Rig_Info_20190314132650.pdf

Clsd_Loop_20190314132649.pdf

MB_Wellhd_10M_13.375_7.625_5.5_20190510092941.pdf

5.5_20_P110_EC_VAMSG_20190510092825.pdf

7.625_29.70_P110_Flushmax_20190510092838.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHBRED 10-3 FED

Well Number: 621H

MB_Wellhd_5M_13.375_8.625_20190627145907.pdf

MB_Wellhd_10M_13.375_7.625_5.5__20190627145909.pdf

Pay.gov___Confirmation_621H_711H_731H_20190627145922.pdf

MB_Verb_5M_20190904092118.pdf

Other Variance attachment:

Co_flex_20190314132801.pdf

Casing Assumptions and Load Cases

Surface

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Surface Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Displace to Gas	Formation Pore Pressure	Dry gas from next casing point

Surface Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Surface Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	3 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Intermediate

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Intermediate Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Fracture @ Shoe	Formation Pore Pressure	Dry gas

Intermediate Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Intermediate Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Production

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Production Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Fluid in hole (water or produced water) + test psi
Tubing Leak	Formation Pore Pressure	Packer @ KOP, leak below surface 8.6 ppg packer fluid
Stimulation	Formation Pore Pressure	Max frac pressure with heaviest frac fluid

Production Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC.	None
Cementing	Wet cement weight	Water (8.33ppg)

Production Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Surface

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Surface Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Displace to Gas	Formation Pore Pressure	Dry gas from next casing point

Surface Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Surface Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	3 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Intermediate

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Intermediate Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Fracture @ Shoe	Formation Pore Pressure	Dry gas

Intermediate Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Intermediate Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Production

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Production Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Fluid in hole (water or produced water) + test psi
Tubing Leak	Formation Pore Pressure	Packer @ KOP, leak below surface 8.6 ppg packer fluid
Stimulation	Formation Pore Pressure	Max frac pressure with heaviest frac fluid

Production Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC.	None
Cementing	Wet cement weight	Water (8.33ppg)

Production Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A



**Devon Energy Center
333 West Sheridan Avenue
Oklahoma City, Oklahoma 73102-5015**

Hydrogen Sulfide (H₂S) Contingency Plan



For

Thoroughbred 10-3 Fed Com 621H

**Sec-10 T-26S R-31E
220' FSL & 380' FWL
LAT. = 32.0507280' N (NAD83)
LONG = 103.7734279' W**

Eddy County NM

Thoroughbred 10-3 Fed Com 621H
 This is an open drilling site. H₂S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H₂S, including warning signs, wind indicators and H₂S monitor.



**Assumed 100 ppm ROE = 3000' (Radius of Exposure)
 100 ppm H₂S concentration shall trigger activation of this plan.**

Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crews should then block the entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are no homes or buildings in or near the ROE.

Assumed 100 ppm ROE = 3000'

100 ppm H₂S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE.
- Be equipped with H₂S monitors and air packs in order to control the release.
- Use the “buddy system” to ensure no injuries occur during the response
- Take precautions to avoid personal injury during this operation.
- Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- Have received training in the
 - Detection of H₂S, and
 - Measures for protection against the gas,
 - Equipment used for protection and emergency response.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCED and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H ₂ S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO ₂	2.21 Air = 1	2 ppm	N/A	1000 ppm

Contacting Authorities

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER)

Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE (H₂S) TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H₂S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan.

II. HYDROGEN SULFIDE TRAINING

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H₂S.

1. Well Control Equipment

- A. Flare line
- B. Choke manifold – Remotely Operated
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
- D. Auxiliary equipment may include if applicable: annular preventer and rotating head.
- E. Mud/Gas Separator

2. Protective equipment for essential personnel:

30-minute SCBA units located at briefing areas, as indicated on well site diagram, with escape units available in the top doghouse. As it may be difficult to communicate audibly while wearing these units, hand signals shall be utilized.

3. H₂S detection and monitoring equipment:

Portable H₂S monitors positioned on location for best coverage and response. These units have warning lights which activate when H₂S levels reach 10 ppm and audible sirens which activate at 15 ppm. Sensor locations:

- Bell nipple
- Possum Belly/Shale shaker
- Rig floor
- Choke manifold
- Cellar

Visual warning systems:

- A. Wind direction indicators as shown on well site diagram
- B. Caution/ Danger signs shall be posted on roads providing direct access to locations. Signs will be painted a high visibility yellow with black lettering of sufficient size to be reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

4. Mud program:

The mud program has been designed to minimize the volume of H₂S circulated to surface. Proper mud weight, safe drilling practices and the use of H₂S scavengers will minimize hazards when penetrating H₂S bearing zones.

5. Metallurgy:

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold lines, and valves shall be H₂S trim.
- B. All elastomers used for packing and seals shall be H₂S trim.

6. Communication:

- A. Company personnel have/use cellular telephones in the field.
- B. Land line (telephone) communications at Office

7. Well testing:

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safety and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H₂S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

Devon Energy Corp. Company Call List		
Drilling Supervisor – Basin – Mark Kramer		405-823-4796
EHS Professional – Laura Wright		405-439-8129
Agency Call List		
Lea County (575)	Hobbs	
	Lea County Communication Authority	393-3981
	State Police	392-5588
	City Police	397-9265
	Sheriff's Office	393-2515
	Ambulance	911
	Fire Department	397-9308
	LEPC (Local Emergency Planning Committee)	393-2870
	NMOCD	393-6161
	US Bureau of Land Management	393-3612
	Eddy County (575)	Carlsbad
State Police		885-3137
City Police		885-2111
Sheriff's Office		887-7551
Ambulance		911
Fire Department		885-3125
LEPC (Local Emergency Planning Committee)		887-3798
US Bureau of Land Management		887-6544
NM Emergency Response Commission (Santa Fe)		(505) 476-9600
24 HR		(505) 827-9126
National Emergency Response Center		(800) 424-8802
National Pollution Control Center: Direct For Oil Spills		(703) 872-6000
		(800) 280-7118
Emergency Services		
Wild Well Control		(281) 784-4700
Cudd Pressure Control		(915) 699-0139 (915) 563-3356
Halliburton		(575) 746-2757
B. J. Services		(575) 746-3569
Give GPS position:		Native Air – Emergency Helicopter – Hobbs (TX & NM)
	Flight For Life - Lubbock, TX	(806) 743-9911
	Aerocare - Lubbock, TX	(806) 747-8923
	Med Flight Air Amb - Albuquerque, NM	(575) 842-4433
	Lifeguard Air Med Svc. Albuquerque, NM	(800) 222-1222
	Poison Control (24/7)	(575) 272-3115
	Oil & Gas Pipeline 24 Hour Service	(800) 364-4366
	NOAA – Website - www.nhc.noaa.gov	

Prepared in conjunction with
Dave Small



WCDSC Permian NM

Eddy County (NAD 83 NM Eastern)

Sec 10-T26S-R31E

Thoroughbred 10-3 Fed Com 621H

Wellbore #1

Plan: Permit Plan 1

Standard Planning Report - Geographic

20 June, 2019

Planning Report - Geographic

Database:	EDM r5000.141_Prod US	Local Co-ordinate Reference	Well Thoroughbred 10-3 Fed Com 621H
Company:	WCDCS Permian NM	TVD Reference:	RKB @ 3266.50ft
Project:	Eddy County (NAD 83 NM Eastern)	MD Reference:	RKB @ 3266.50ft
Site:	Sec 10-T26S-R31E	North Reference:	Grid
Well:	Thoroughbred 10-3 Fed Com 621H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Project	Eddy County (NAD 83 NM Eastern)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Sec 10-T26S-R31E				
Site Position:		Northing:	382,457.83 usft	Latitude:	32.039419
From:	Map	Easting:	0.00 usft	Longitude:	-106.080279
Position Uncertainty:	0.00 ft	Slot Radius:	13-3/16 "	Grid Convergence:	-0.93 °

Well	Thoroughbred 10-3 Fed Com 621H					
Well Position	+N/-S	0.00 ft	Northing:	382,642.63 usft	Latitude:	32.050728
	+E/-W	0.00 ft	Easting:	714,807.10 usft	Longitude:	-103.773428
Position Uncertainty		0.50 ft	Wellhead Elevation:		Ground Level:	3,241.50 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
			(°)	(°)	(nT)
	IGRF2015	6/17/2019	6.82	59.85	47,610.19324261

Design	Permit Plan 1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(ft)	(ft)	(ft)	(°)
	0.00	0.00	0.00	3.71

Plan Survey Tool Program	Date	6/19/2019		
Depth From	Depth To	Survey (Wellbore)	Tool Name	Remarks
(ft)	(ft)			
1	0.00	18,693.32 Permit Plan 1 (Wellbore #1)	MWD+HDGM	OWSG MWD + HDGM

Plan Sections										
Measured			Vertical							
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Dogleg	Build	Turn	TFO	Target
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(°/100usft)	(°/100usft)	(°/100usft)	(°)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2,750.00	0.00	0.00	2,750.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
3,094.90	3.45	112.52	3,094.69	-3.97	9.59	1.00	1.00	0.00	112.52	
10,185.26	3.45	112.52	10,172.21	-167.35	403.61	0.00	0.00	0.00	0.00	
10,415.19	0.00	0.00	10,402.00	-170.00	410.00	1.50	-1.50	0.00	180.00	
10,765.23	0.00	0.00	10,752.04	-170.00	410.00	0.00	0.00	0.00	0.00	

Planning Report - Geographic

Database:	EDM r5000.141_Prod US	Local Co-ordinate Reference	Well Thoroughbred 10-3 Fed Com 621H
Company:	WCDSC Permian NM	TVD Reference:	RKB @ 3266.50ft
Project:	Eddy County (NAD 83 NM Eastern)	MD Reference:	RKB @ 3266.50ft
Site:	Sec 10-T26S-R31E	North Reference:	Grid
Well:	Thoroughbred 10-3 Fed Com 621H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N-S (ft)	+E-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude	
0.00	0.00	0.00	0.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
100.00	0.00	0.00	100.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
200.00	0.00	0.00	200.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
300.00	0.00	0.00	300.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
400.00	0.00	0.00	400.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
500.00	0.00	0.00	500.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
600.00	0.00	0.00	600.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
700.00	0.00	0.00	700.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
800.00	0.00	0.00	800.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
900.00	0.00	0.00	900.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
1,000.00	0.00	0.00	1,000.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
1,100.00	0.00	0.00	1,100.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
1,200.00	0.00	0.00	1,200.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
1,300.00	0.00	0.00	1,300.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
1,400.00	0.00	0.00	1,400.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
1,500.00	0.00	0.00	1,500.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
1,600.00	0.00	0.00	1,600.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
1,700.00	0.00	0.00	1,700.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
1,800.00	0.00	0.00	1,800.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
1,900.00	0.00	0.00	1,900.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
2,000.00	0.00	0.00	2,000.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
2,100.00	0.00	0.00	2,100.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
2,200.00	0.00	0.00	2,200.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
2,300.00	0.00	0.00	2,300.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
2,400.00	0.00	0.00	2,400.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
2,500.00	0.00	0.00	2,500.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
2,600.00	0.00	0.00	2,600.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
2,700.00	0.00	0.00	2,700.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
2,750.00	0.00	0.00	2,750.00	0.00	0.00	382,642.63	714,807.10	32.050728	-103.773428	
2,800.00	0.50	112.52	2,800.00	-0.08	0.20	382,642.54	714,807.30	32.050728	-103.773427	
2,900.00	1.50	112.52	2,899.98	-0.75	1.81	382,641.88	714,808.91	32.050726	-103.773422	
3,000.00	2.50	112.52	2,999.92	-2.09	5.04	382,640.54	714,812.13	32.050722	-103.773412	
3,094.90	3.45	112.52	3,094.69	-3.97	9.59	382,638.65	714,816.68	32.050717	-103.773397	
3,100.00	3.45	112.52	3,099.78	-4.09	9.87	382,638.54	714,816.97	32.050717	-103.773396	
3,200.00	3.45	112.52	3,199.60	-6.40	15.43	382,636.23	714,822.52	32.050710	-103.773378	
3,300.00	3.45	112.52	3,299.42	-8.70	20.98	382,633.93	714,828.08	32.050704	-103.773361	
3,400.00	3.45	112.52	3,399.24	-11.00	26.54	382,631.62	714,833.64	32.050697	-103.773343	
3,500.00	3.45	112.52	3,499.06	-13.31	32.10	382,629.32	714,839.19	32.050691	-103.773325	
3,600.00	3.45	112.52	3,598.88	-15.61	37.66	382,627.02	714,844.75	32.050685	-103.773307	
3,700.00	3.45	112.52	3,698.70	-17.92	43.21	382,624.71	714,850.31	32.050678	-103.773289	
3,800.00	3.45	112.52	3,798.51	-20.22	48.77	382,622.41	714,855.87	32.050672	-103.773271	
3,900.00	3.45	112.52	3,898.33	-22.53	54.33	382,620.10	714,861.42	32.050665	-103.773253	
4,000.00	3.45	112.52	3,998.15	-24.83	59.88	382,617.80	714,866.98	32.050659	-103.773235	
4,100.00	3.45	112.52	4,097.97	-27.13	65.44	382,615.49	714,872.54	32.050653	-103.773217	
4,200.00	3.45	112.52	4,197.79	-29.44	71.00	382,613.19	714,878.09	32.050646	-103.773199	
4,300.00	3.45	112.52	4,297.61	-31.74	76.56	382,610.89	714,883.65	32.050640	-103.773182	
4,400.00	3.45	112.52	4,397.43	-34.05	82.11	382,608.58	714,889.21	32.050633	-103.773164	
4,500.00	3.45	112.52	4,497.25	-36.35	87.67	382,606.28	714,894.77	32.050627	-103.773146	
4,600.00	3.45	112.52	4,597.07	-38.66	93.23	382,603.97	714,900.32	32.050620	-103.773128	
4,700.00	3.45	112.52	4,696.88	-40.96	98.78	382,601.67	714,905.88	32.050614	-103.773110	
4,800.00	3.45	112.52	4,796.70	-43.26	104.34	382,599.37	714,911.44	32.050608	-103.773092	
4,900.00	3.45	112.52	4,896.52	-45.57	109.90	382,597.06	714,916.99	32.050601	-103.773074	
5,000.00	3.45	112.52	4,996.34	-47.87	115.46	382,594.76	714,922.55	32.050595	-103.773056	
5,100.00	3.45	112.52	5,096.16	-50.18	121.01	382,592.45	714,928.11	32.050588	-103.773038	

Planning Report - Geographic

Database:	EDM r5000.141_Prod US	Local Co-ordinate Reference	Well Thoroughbred 10-3 Fed Com 621H
Company:	WCDSC Permian NM	TVD Reference:	RKB @ 3266.50ft
Project:	Eddy County (NAD 83 NM Eastern)	MD Reference:	RKB @ 3266.50ft
Site:	Sec 10-T26S-R31E	North Reference:	Grid
Well:	Thoroughbred 10-3 Fed Com 621H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
5,200.00	3.45	112.52	5,195.98	-52.48	126.57	382,590.15	714,933.67	32.050582	-103.773020
5,300.00	3.45	112.52	5,295.80	-54.78	132.13	382,587.84	714,939.22	32.050576	-103.773003
5,400.00	3.45	112.52	5,395.62	-57.09	137.68	382,585.54	714,944.78	32.050569	-103.772985
5,500.00	3.45	112.52	5,495.44	-59.39	143.24	382,583.24	714,950.34	32.050563	-103.772967
5,600.00	3.45	112.52	5,595.25	-61.70	148.80	382,580.93	714,955.89	32.050556	-103.772949
5,700.00	3.45	112.52	5,695.07	-64.00	154.36	382,578.63	714,961.45	32.050550	-103.772931
5,800.00	3.45	112.52	5,794.89	-66.31	159.91	382,576.32	714,967.01	32.050544	-103.772913
5,900.00	3.45	112.52	5,894.71	-68.61	165.47	382,574.02	714,972.57	32.050537	-103.772895
6,000.00	3.45	112.52	5,994.53	-70.91	171.03	382,571.71	714,978.12	32.050531	-103.772877
6,100.00	3.45	112.52	6,094.35	-73.22	176.58	382,569.41	714,983.68	32.050524	-103.772859
6,200.00	3.45	112.52	6,194.17	-75.52	182.14	382,567.11	714,989.24	32.050518	-103.772842
6,300.00	3.45	112.52	6,293.99	-77.83	187.70	382,564.80	714,994.79	32.050511	-103.772824
6,400.00	3.45	112.52	6,393.81	-80.13	193.26	382,562.50	715,000.35	32.050505	-103.772806
6,500.00	3.45	112.52	6,493.62	-82.43	198.81	382,560.19	715,005.91	32.050499	-103.772788
6,600.00	3.45	112.52	6,593.44	-84.74	204.37	382,557.89	715,011.47	32.050492	-103.772770
6,700.00	3.45	112.52	6,693.26	-87.04	209.93	382,555.59	715,017.02	32.050486	-103.772752
6,800.00	3.45	112.52	6,793.08	-89.35	215.48	382,553.28	715,022.58	32.050479	-103.772734
6,900.00	3.45	112.52	6,892.90	-91.65	221.04	382,550.98	715,028.14	32.050473	-103.772716
7,000.00	3.45	112.52	6,992.72	-93.96	226.60	382,548.67	715,033.69	32.050467	-103.772698
7,100.00	3.45	112.52	7,092.54	-96.26	232.16	382,546.37	715,039.25	32.050460	-103.772680
7,200.00	3.45	112.52	7,192.36	-98.56	237.71	382,544.06	715,044.81	32.050454	-103.772663
7,300.00	3.45	112.52	7,292.18	-100.87	243.27	382,541.76	715,050.37	32.050447	-103.772645
7,400.00	3.45	112.52	7,391.99	-103.17	248.83	382,539.46	715,055.92	32.050441	-103.772627
7,500.00	3.45	112.52	7,491.81	-105.48	254.39	382,537.15	715,061.48	32.050435	-103.772609
7,600.00	3.45	112.52	7,591.63	-107.78	259.94	382,534.85	715,067.04	32.050428	-103.772591
7,700.00	3.45	112.52	7,691.45	-110.09	265.50	382,532.54	715,072.59	32.050422	-103.772573
7,800.00	3.45	112.52	7,791.27	-112.39	271.06	382,530.24	715,078.15	32.050415	-103.772555
7,900.00	3.45	112.52	7,891.09	-114.69	276.61	382,527.94	715,083.71	32.050409	-103.772537
8,000.00	3.45	112.52	7,990.91	-117.00	282.17	382,525.63	715,089.27	32.050402	-103.772519
8,100.00	3.45	112.52	8,090.73	-119.30	287.73	382,523.33	715,094.82	32.050396	-103.772501
8,200.00	3.45	112.52	8,190.55	-121.61	293.29	382,521.02	715,100.38	32.050390	-103.772484
8,300.00	3.45	112.52	8,290.36	-123.91	298.84	382,518.72	715,105.94	32.050383	-103.772466
8,400.00	3.45	112.52	8,390.18	-126.21	304.40	382,516.41	715,111.49	32.050377	-103.772448
8,500.00	3.45	112.52	8,490.00	-128.52	309.96	382,514.11	715,117.05	32.050370	-103.772430
8,600.00	3.45	112.52	8,589.82	-130.82	315.51	382,511.81	715,122.61	32.050364	-103.772412
8,700.00	3.45	112.52	8,689.64	-133.13	321.07	382,509.50	715,128.17	32.050358	-103.772394
8,800.00	3.45	112.52	8,789.46	-135.43	326.63	382,507.20	715,133.72	32.050351	-103.772376
8,900.00	3.45	112.52	8,889.28	-137.74	332.19	382,504.89	715,139.28	32.050345	-103.772358
9,000.00	3.45	112.52	8,989.10	-140.04	337.74	382,502.59	715,144.84	32.050338	-103.772340
9,100.00	3.45	112.52	9,088.92	-142.34	343.30	382,500.29	715,150.39	32.050332	-103.772322
9,200.00	3.45	112.52	9,188.73	-144.65	348.86	382,497.98	715,155.95	32.050325	-103.772305
9,300.00	3.45	112.52	9,288.55	-146.95	354.41	382,495.68	715,161.51	32.050319	-103.772287
9,400.00	3.45	112.52	9,388.37	-149.26	359.97	382,493.37	715,167.07	32.050313	-103.772269
9,500.00	3.45	112.52	9,488.19	-151.56	365.53	382,491.07	715,172.62	32.050306	-103.772251
9,600.00	3.45	112.52	9,588.01	-153.86	371.09	382,488.76	715,178.18	32.050300	-103.772233
9,700.00	3.45	112.52	9,687.83	-156.17	376.64	382,486.46	715,183.74	32.050293	-103.772215
9,800.00	3.45	112.52	9,787.65	-158.47	382.20	382,484.16	715,189.30	32.050287	-103.772197
9,900.00	3.45	112.52	9,887.47	-160.78	387.76	382,481.85	715,194.85	32.050281	-103.772179
10,000.00	3.45	112.52	9,987.29	-163.08	393.31	382,479.55	715,200.41	32.050274	-103.772161
10,100.00	3.45	112.52	10,087.10	-165.39	398.87	382,477.24	715,205.97	32.050268	-103.772144
10,185.26	3.45	112.52	10,172.21	-167.35	403.61	382,475.28	715,210.70	32.050262	-103.772128
10,200.00	3.23	112.52	10,186.92	-167.68	404.40	382,474.95	715,211.50	32.050261	-103.772126
10,300.00	1.73	112.52	10,286.83	-169.33	408.40	382,473.29	715,215.49	32.050257	-103.772113
10,400.00	0.23	112.52	10,386.81	-169.99	409.97	382,472.64	715,217.07	32.050255	-103.772108

Planning Report - Geographic

Database:	EDM r5000.141_Prod US	Local Co-ordinate Reference	Well Thoroughbred 10-3 Fed Com 621H
Company:	WCDSC Permian NM	TVD Reference:	RKB @ 3266.50ft
Project:	Eddy County (NAD 83 NM Eastern)	MD Reference:	RKB @ 3266.50ft
Site:	Sec 10-T26S-R31E	North Reference:	Grid
Well:	Thoroughbred 10-3 Fed Com 621H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N-S (ft)	+E-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
10,415.19	0.00	0.00	10,402.00	-170.00	410.00	382,472.63	715,217.10	32.050255	-103.772108
10,500.00	0.00	0.00	10,486.81	-170.00	410.00	382,472.63	715,217.10	32.050255	-103.772108
10,600.00	0.00	0.00	10,586.81	-170.00	410.00	382,472.63	715,217.10	32.050255	-103.772108
10,700.00	0.00	0.00	10,686.81	-170.00	410.00	382,472.63	715,217.10	32.050255	-103.772108
10,765.23	0.00	0.00	10,752.04	-170.00	410.00	382,472.63	715,217.10	32.050255	-103.772108
10,800.00	3.54	16.75	10,786.79	-168.97	410.31	382,473.66	715,217.40	32.050258	-103.772107
10,900.00	13.72	16.75	10,885.53	-154.62	414.63	382,488.00	715,221.72	32.050297	-103.772092
11,000.00	23.90	16.75	10,980.06	-123.79	423.91	382,518.84	715,231.00	32.050382	-103.772062
11,100.00	34.08	16.75	11,067.42	-77.45	437.85	382,565.18	715,244.95	32.050509	-103.772016
11,200.00	44.26	16.75	11,144.85	-17.05	456.03	382,625.58	715,263.13	32.050675	-103.771957
11,211.90	45.47	16.75	11,153.28	-9.02	458.45	382,633.61	715,265.55	32.050697	-103.771949
11,300.00	53.78	12.33	11,210.32	55.90	475.12	382,698.53	715,282.22	32.050875	-103.771894
11,400.00	63.38	8.33	11,262.41	139.76	490.25	382,782.39	715,297.35	32.051105	-103.771843
11,500.00	73.06	4.96	11,299.48	231.88	500.90	382,874.51	715,307.99	32.051358	-103.771808
11,600.00	82.80	1.93	11,320.37	329.37	506.72	382,971.99	715,313.81	32.051626	-103.771787
11,673.79	90.00	359.78	11,325.00	402.95	507.81	383,045.58	715,314.90	32.051828	-103.771782
11,700.00	90.00	359.78	11,325.00	429.16	507.71	383,071.79	715,314.80	32.051901	-103.771782
11,800.00	90.00	359.78	11,325.00	529.16	507.33	383,171.79	715,314.42	32.052175	-103.771782
11,900.00	90.00	359.78	11,325.00	629.16	506.94	383,271.79	715,314.04	32.052450	-103.771781
12,000.00	90.00	359.78	11,325.00	729.16	506.56	383,371.78	715,313.65	32.052725	-103.771781
12,100.00	90.00	359.78	11,325.00	829.16	506.17	383,471.78	715,313.27	32.053000	-103.771781
12,200.00	90.00	359.78	11,325.00	929.16	505.79	383,571.78	715,312.88	32.053275	-103.771780
12,300.00	90.00	359.78	11,325.00	1,029.16	505.41	383,671.78	715,312.50	32.053550	-103.771780
12,400.00	90.00	359.78	11,325.00	1,129.15	505.02	383,771.78	715,312.12	32.053825	-103.771779
12,500.00	90.00	359.78	11,325.00	1,229.15	504.64	383,871.78	715,311.73	32.054100	-103.771779
12,600.00	90.00	359.78	11,325.00	1,329.15	504.25	383,971.78	715,311.35	32.054375	-103.771778
12,700.00	90.00	359.78	11,325.00	1,429.15	503.87	384,071.78	715,310.96	32.054649	-103.771778
12,800.00	90.00	359.78	11,325.00	1,529.15	503.49	384,171.78	715,310.58	32.054924	-103.771777
12,900.00	90.00	359.78	11,325.00	1,629.15	503.10	384,271.78	715,310.20	32.055199	-103.771777
13,000.00	90.00	359.78	11,325.00	1,729.15	502.72	384,371.78	715,309.81	32.055474	-103.771777
13,100.00	90.00	359.78	11,325.00	1,829.15	502.33	384,471.77	715,309.43	32.055749	-103.771776
13,200.00	90.00	359.78	11,325.00	1,929.15	501.95	384,571.77	715,309.04	32.056024	-103.771776
13,300.00	90.00	359.78	11,325.00	2,029.15	501.57	384,671.77	715,308.66	32.056299	-103.771775
13,400.00	90.00	359.78	11,325.00	2,129.15	501.18	384,771.77	715,308.28	32.056574	-103.771775
13,500.00	90.00	359.78	11,325.00	2,229.15	500.80	384,871.77	715,307.89	32.056849	-103.771774
13,600.00	90.00	359.78	11,325.00	2,329.15	500.41	384,971.77	715,307.51	32.057123	-103.771774
13,700.00	90.00	359.78	11,325.00	2,429.14	500.03	385,071.77	715,307.12	32.057398	-103.771773
13,800.00	90.00	359.78	11,325.00	2,529.14	499.65	385,171.77	715,306.74	32.057673	-103.771773
13,900.00	90.00	359.78	11,325.00	2,629.14	499.26	385,271.77	715,306.36	32.057948	-103.771773
14,000.00	90.00	359.78	11,325.00	2,729.14	498.88	385,371.77	715,305.97	32.058223	-103.771772
14,100.00	90.00	359.78	11,325.00	2,829.14	498.49	385,471.76	715,305.59	32.058498	-103.771772
14,200.00	90.00	359.78	11,325.00	2,929.14	498.11	385,571.76	715,305.21	32.058773	-103.771771
14,300.00	90.00	359.78	11,325.00	3,029.14	497.73	385,671.76	715,304.82	32.059048	-103.771771
14,400.00	90.00	359.78	11,325.00	3,129.14	497.34	385,771.76	715,304.44	32.059322	-103.771770
14,500.00	90.00	359.78	11,325.00	3,229.14	496.96	385,871.76	715,304.05	32.059597	-103.771770
14,600.00	90.00	359.78	11,325.00	3,329.14	496.57	385,971.76	715,303.67	32.059872	-103.771770
14,700.00	90.00	359.78	11,325.00	3,429.14	496.19	386,071.76	715,303.29	32.060147	-103.771769
14,800.00	90.00	359.78	11,325.00	3,529.14	495.81	386,171.76	715,302.90	32.060422	-103.771769
14,900.00	90.00	359.78	11,325.00	3,629.14	495.42	386,271.76	715,302.52	32.060697	-103.771768
15,000.00	90.00	359.78	11,325.00	3,729.14	495.04	386,371.76	715,302.13	32.060972	-103.771768
15,100.00	90.00	359.78	11,325.00	3,829.13	494.65	386,471.76	715,301.75	32.061247	-103.771767
15,200.00	90.00	359.78	11,325.00	3,929.13	494.27	386,571.75	715,301.37	32.061522	-103.771767
15,300.00	90.00	359.78	11,325.00	4,029.13	493.89	386,671.75	715,300.98	32.061796	-103.771766
15,400.00	90.00	359.78	11,325.00	4,129.13	493.50	386,771.75	715,300.60	32.062071	-103.771766

Planning Report - Geographic

Database:	EDM r5000.141_Prod US	Local Co-ordinate Reference:	Well Thoroughbred 10-3 Fed Com 621H
Company:	WCDSC Permian NM	TVD Reference:	RKB @ 3266.50ft
Project:	Eddy County (NAD 83 NM Eastern)	MD Reference:	RKB @ 3266.50ft
Site:	Sec 10-T26S-R31E	North Reference:	Grid
Well:	Thoroughbred 10-3 Fed Com 621H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
15,500.00	90.00	359.78	11,325.00	4,229.13	493.12	386,871.75	715,300.21	32.062346	-103.771766
15,600.00	90.00	359.78	11,325.00	4,329.13	492.73	386,971.75	715,299.83	32.062621	-103.771765
15,700.00	90.00	359.78	11,325.00	4,429.13	492.35	387,071.75	715,299.45	32.062896	-103.771765
15,800.00	90.00	359.78	11,325.00	4,529.13	491.97	387,171.75	715,299.06	32.063171	-103.771764
15,900.00	90.00	359.78	11,325.00	4,629.13	491.58	387,271.75	715,298.68	32.063446	-103.771764
16,000.00	90.00	359.78	11,325.00	4,729.13	491.20	387,371.75	715,298.29	32.063721	-103.771763
16,100.00	90.00	359.78	11,325.00	4,829.13	490.81	387,471.75	715,297.91	32.063996	-103.771763
16,200.00	90.00	359.78	11,325.00	4,929.13	490.43	387,571.75	715,297.53	32.064270	-103.771762
16,300.00	90.00	359.78	11,325.00	5,029.13	490.05	387,671.74	715,297.14	32.064545	-103.771762
16,400.00	90.00	359.78	11,325.00	5,129.13	489.66	387,771.74	715,296.76	32.064820	-103.771762
16,500.00	90.00	359.78	11,325.00	5,229.12	489.28	387,871.74	715,296.37	32.065095	-103.771761
16,600.00	90.00	359.78	11,325.00	5,329.12	488.89	387,971.74	715,295.99	32.065370	-103.771761
16,700.00	90.00	359.78	11,325.00	5,429.12	488.51	388,071.74	715,295.61	32.065645	-103.771760
16,800.00	90.00	359.78	11,325.00	5,529.12	488.13	388,171.74	715,295.22	32.065920	-103.771760
16,900.00	90.00	359.78	11,325.00	5,629.12	487.74	388,271.74	715,294.84	32.066195	-103.771759
17,000.00	90.00	359.78	11,325.00	5,729.12	487.36	388,371.74	715,294.45	32.066470	-103.771759
17,100.00	90.00	359.78	11,325.00	5,829.12	486.97	388,471.74	715,294.07	32.066744	-103.771759
17,200.00	90.00	359.78	11,325.00	5,929.12	486.59	388,571.74	715,293.69	32.067019	-103.771758
17,300.00	90.00	359.78	11,325.00	6,029.12	486.21	388,671.73	715,293.30	32.067294	-103.771758
17,400.00	90.00	359.78	11,325.00	6,129.12	485.82	388,771.73	715,292.92	32.067569	-103.771757
17,500.00	90.00	359.78	11,325.00	6,229.12	485.44	388,871.73	715,292.53	32.067844	-103.771757
17,600.00	90.00	359.78	11,325.00	6,329.12	485.06	388,971.73	715,292.15	32.068119	-103.771756
17,700.00	90.00	359.78	11,325.00	6,429.12	484.67	389,071.73	715,291.77	32.068394	-103.771756
17,800.00	90.00	359.78	11,325.00	6,529.11	484.29	389,171.73	715,291.38	32.068669	-103.771755
17,900.00	90.00	359.78	11,325.00	6,629.11	483.90	389,271.73	715,291.00	32.068944	-103.771755
18,000.00	90.00	359.78	11,325.00	6,729.11	483.52	389,371.73	715,290.61	32.069218	-103.771755
18,100.00	90.00	359.78	11,325.00	6,829.11	483.14	389,471.73	715,290.23	32.069493	-103.771754
18,200.00	90.00	359.78	11,325.00	6,929.11	482.75	389,571.73	715,289.85	32.069768	-103.771754
18,300.00	90.00	359.78	11,325.00	7,029.11	482.37	389,671.73	715,289.46	32.070043	-103.771753
18,400.00	90.00	359.78	11,325.00	7,129.11	481.98	389,771.72	715,289.08	32.070318	-103.771753
18,500.00	90.00	359.78	11,325.00	7,229.11	481.60	389,871.72	715,288.69	32.070593	-103.771752
18,600.00	90.00	359.78	11,325.00	7,329.11	481.22	389,971.72	715,288.31	32.070868	-103.771752
18,695.76	90.00	359.78	11,325.00	7,424.87	480.85	390,067.48	715,287.94	32.071131	-103.771751

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL - Thoroughbred 1t - hit/miss target - Shape	0.00	0.00	0.00	7,424.74	480.95	390,067.35	715,288.05	32.071131	-103.771751
- plan misses target center by 7440.30ft at 0.00ft MD (0.00 TVD, 0.00 N, 0.00 E)									
- Point									

Devon Energy

WELL DETAILS: Thoroughbred 10-3 Fed Com 621H




RKB @ 3266.50ft

3241.50

Northing 382642.63 Easting 714807.10 Latitude 32.050728 Longitude -103.773428

SECTION DETAILS Permit Plan 1

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	Vsect	Annotation
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
750.00	0.00	0.00	2750.00	0.00	0.00	0.00	0.00	
094.90	3.45	112.52	3094.69	-3.97	9.59	1.00	-3.35	
185.26	3.45	112.52	10172.21	-167.35	403.61	0.00	-140.92	
415.19	0.00	0.00	10402.00	-170.00	410.00	1.50	-143.15	
765.23	0.00	0.00	10752.04	-170.00	410.00	0.00	-143.15	KOP @ 10765' MD, 50' FSL, 790' FWL
211.90	45.47	16.75	11153.28	-9.02	458.45	10.18	20.63	
573.79	90.00	359.78	11325.00	402.95	507.81	10.18	434.93	
695.76	90.00	359.78	11325.00	7424.87	480.65	0.00	7440.42	PBHL & LTP @ 18696' MD, 2310' FSL, 890' FWL

Thoroughbred 10-3 Fed Com 621H

2. Casing Program (Primary Design)

Hole Size	Casing Interval		Csg. Size	Wt (PPF)	Grade	Conn	Min SF Collapse	Min SF Burst	Min SF Tension
	From	To							
17 1/2	0	1443 TVD	13 3/8	48.0	H40	STC	1.125	1.25	1.6
9 7/8	0	10929 TVD	7 5/8	29.7	P110	Flushmax III	1.125	1.25	1.6
6 3/4	0	TD	5 1/2	20.0	P110	Vam SG	1.125	1.25	1.6
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

- All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 IILB.1.h Must have table for contingency casing.
- Rustler top will be validated via drilling parameters (i.e. reduction in ROP) and surface casing setting depth revised accordingly if needed.
- A variance is requested for collapse rating on intermediate casing. Operator will keep pipe full while running casing.
- Int casing shoe will be selected based on drilling data/gamma, setting depth with be revised accordingly if needed.
- A variance is requested to wave the centralizer requirement for the Intermediate casing and production casing.
- A variance is requested to set intermediate casing in the curve if hole conditions dictate that a higher shoe strength is required.

Casing Program (Alternative Design)

Hole Size	Casing Interval		Csg. Size	Wt (PPF)	Grade	Conn	Min SF Collapse	Min SF Burst	Min SF Tension
	From	To							
17 1/2	0	1443 TVD	13 3/8	48.0	H40	STC	1.125	1.25	1.6
9 7/8	0	10929 TVD	8 5/8	32.0	P110	TLW	1.125	1.25	1.6
7 7/8	0	TD	5 1/2	17.0	P110	BTC	1.125	1.25	1.6
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

- All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 IILB.1.h Must have table for contingency casing.
- Rustler top will be validated via drilling parameters (i.e. reduction in ROP) and surface casing setting depth revised accordingly if needed.
- A variance is requested for collapse rating on intermediate casing. Operator will keep pipe full while running casing.
- Int casing shoe will be selected based on drilling data/gamma, setting depth with be revised accordingly if needed.
- A variance is requested to wave the centralizer requirement for the Intermediate casing and production casing.
- Variance requested to drill 10.625" hole instead of 9.875" for intermediate 1, the 8.625" connection will change from TLW to BTC.
- A variance is requested to set intermediate casing in the curve if hole conditions dictate that a higher shoe strength is required.

Thoroughbred 10-3 Fed Com 621H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

3. Cementing Program (Primary Design)

Casing	# Sks	TOC	Wt. (lb/gal)	Yld (ft ³ /sack)	Slurry Description
Surface	1083	Surf	13.2	1.44	Lead: Class C Cement + additives
Int 1	718	Surf	9	3.27	Lead: Class C Cement + additives
	783	4000' above shoe	13.2	1.44	Tail: Class H / C + additives
Int 1 Two Stage w/ DV @ TVD of Delaware	856	Surf	9	3.27	1st stage Lead: Class C Cement + additives
	93	500' above shoe	13.2	1.44	1st stage Tail: Class H / C + additives
	425	Surf	9	3.27	2nd stage Lead: Class C Cement + additives
	93	500' above DV	13.2	1.44	2nd stage Tail: Class H / C + additives
Int 1 Intermediate Squeeze	As Needed	Surf	9	1.44	Squeeze Lead: Class C Cement + additives
	718	Surf	9	3.27	Lead: Class C Cement + additives
	783	4000' above shoe	13.2	1.44	Tail: Class H / C + additives
Production	63	8765	9.0	3.3	Lead: Class H / C + additives
	506	10765	13.2	1.4	Tail: Class H / C + additives

If a DV tool is ran the depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. Slurry weights will be adjusted based on estimated fracture gradient of the formation. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. If cement is not returned to surface during the primary cement job on the surface casing string, a planned top job will be conducted immediately after completion of the primary job.

Casing String	% Excess
Surface	50%
Intermediate 1	30%
Intermediate 1 (Two Stage)	25%
Prod	10%

3. Cementing Program (Alternative Design)

Casing	# Sks	TOC	Wt. ppg	Yld (ft3/sack)	Slurry Description
Surface	1083	Surf	13.2	1.44	Lead: Class C Cement + additives
Int 1	485	Surf	9	3.27	Lead: Class C Cement + additives
	465	4000' above shoe	13.2	1.44	Tail: Class H / C + additives
Int 1 Two Stage w DV @ ~4500	503	Surf	9	3.27	1st stage Lead: Class C Cement + additives
	55	500' above shoe	13.2	1.44	1st stage Tail: Class H / C + additives
	313	Surf	9	3.27	2nd stage Lead: Class C Cement + additives
	55	500' above DV	13.2	1.44	2nd stage Tail: Class H / C + additives
Int 1 Intermediate Squeeze	As Needed	Surf	13.2	1.44	Squeeze Lead: Class C Cement + additives
	485	Surf	9	3.27	Lead: Class C Cement + additives
	465	4000' above shoe	13.2	1.44	Tail: Class H / C + additives
Int 1 (10.625" Hole Size)	668	Surf	9	3.27	Lead: Class C Cement + additives
	768	4000' above shoe	13.2	1.44	Tail: Class H / C + additives
Production	117	8765	9.0	3.3	Lead: Class H / C + additives
	1050	10765	13.2	1.4	Tail: Class H / C + additives

If a DV tool is ran the depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. Slurry weights will be adjusted based on estimated fracture gradient of the formation. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. If cement is not returned to surface during the primary cement job on the surface casing string, a planned top job will be conducted immediately after completion of the primary job.

Casing String	% Excess
Surface	50%
Intermediate 1	30%
Intermediate 1 (Two Stage)	25%
Prod	10%

4. Pressure Control Equipment (Three String Design)

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
Int 1	13-58"	5M	Annular	X	50% of rated working pressure
			Blind Ram	X	5M
			Pipe Ram		
			Double Ram	X	
			Other*		
Production	13-5/8"	5M	Annular (5M)	X	50% of rated working pressure
			Blind Ram	X	5M
			Pipe Ram		
			Double Ram	X	
			Other*		
			Annular (5M)		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		
N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.				
Y	A variance is requested to run a 5 M annular on a 10M system				

5. Mud Program (Three String Design)

Section	Type	Weight (ppg)
Surface	FW Gel	8.5-9
Intermediate	DBE / Cut Brine	10-10.5
Production	OBM	10-10.5

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well - vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain.
	Coring? If yes, explain.

Additional logs planned	Interval
Resistivity	Int. shoe to KOP
Density	Int. shoe to KOP
X CBL	Production casing
X Mud log	Intermediate shoe to TD
PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH pressure at deepest TVD	6183
Abnormal temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered measured values and formations will be provided to the BLM.

N	H ₂ S is present
Y	H ₂ S plan attached.

8. Other facets of operation

Is this a walking operation? Potentially

- 1 If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
- 2 The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
- 3 The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially

- 1 Spudder rig will move in and batch drill surface hole.
 - a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.,
- 2 After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
- 3 The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
- 4 A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
- 5 Spudder rig operations is expected to take 4-5 days per well on a multi-well pa.
- 6 The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 7 Drilling operations will be performed with drilling rig. A that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

Attachments

- X Directional Plan
 Other, describe

Devon Energy
APD VARIANCE DATA

OPERATOR NAME: Devon Energy

1. SUMMARY OF Variance:


Devon Energy respectfully requests approval for the following additions to the drilling plan:

1. Potential utilization of a spudder rig to pre-set surface casing.

2. Description of Operations

1. A spudder rig contractor may move in their rig to drill the surface hole section and pre-set surface casing on this well.
 - a. After drilling the surface hole section, the rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
 - b. Rig will utilize fresh water based mud to drill surface hole to TD.
2. The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
3. A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wingvalves.
 - a. A means for intervention will be maintained while the drilling rig is not over the well.
4. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
5. Drilling operation will be performed with the big rig. At that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The BLM will be contacted / notified 24 hours before the big rig moves back on to the pad with the pre-set surface casing.
6. Devon Energy will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
7. Once the rig is removed, Devon Energy will secure the wellhead area by placing a guard rail around the cellar area.

EXHIBIT "A"
 PAGE 1 of 4
 ELECTRIC LINE PLAT
 SECTION 10, T26S-R31E, N.M.P.M.
 EDDY COUNTY, NEW MEXICO




30' EASEMENT AREA = 0.582 ACRE(S)
 845.76 FEET OR 51.26 RODS

SEE THE ATTACHED LEGAL DESCRIPTION
 Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.


- 0+00.0 P.O.B./THOROUGHbred 10 PRIMARY ELECTRIC LINE
- 1+51.2 THOROUGHbred 10 CTB 1 ACCESS ROAD
- 8+11.1 THOROUGHbred 10 WELLPAD 2 ELECTRIC LINE
- 8+45.8 P.O.E./THOROUGHbred 10 WELLPAD 1

LINE	BEARING	DISTANCE
L1	S 00°03'01" E	811.11'
L1	S 89°39'32" W	34.65'

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect the actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman PLS #22404
 Date Signed: 06-05-2019
 P.O. Box 548, Dry Creek, LA
 (903) 388-3045 70637
 Employee of Horizonrow, LLC



HORIZON ROW LLC

Drawn for:

Drawn by: JESUS RIVERO Date: 05/16/2019

DEVON ENERGY PRODUCTION COMPANY, L.P.
 THOROUGHbred 10 WELLPAD 1 ELECTRIC LINE
 PROPOSED 30' EASEMENT ON THE PROPERTY OF BUREAU OF LAND MANAGEMENT SECTION 10, T26S-R31E, N.M.P.M.

LINE NUMBER: ELB324
WBS NUMBER: XX-130173.01.SLC
SCALE: 1" = 1000'
REVISIONS:
SURVEY DATE: 05/13/19

**SECTION 10, T26S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO**

ELECTRIC LINE PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southwest quarter (SW ¼) of Section 10, Township 26 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 1" iron pipe w/BC found for the west quarter corner of Section 10, T26S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence S 36°02'45" E a distance of 1602.85' to the **Point of Beginning** of this easement having coordinates of Northing=383789.88, Easting=715359.44 feet and continuing the following courses;

Thence S 00°03'01" E a distance of 811.11' to an angle point;

Thence S 89°39'32" W a distance of 34.65' to the **Point of Ending** having coordinates of Northing=382978.57, Easting=715325.51 feet in Section 10, T26S-R31E, N.M.P.M., Eddy County, New Mexico, from said point a 2" iron pipe w/BC for the southwest corner of Section 10, T26S-R31E, bears S 58°06'40" W a distance of 1056.74, covering **845.76' or 51.26 rods** and having an area of **0.582 acre**.

NOTES:


Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.


B.L. Laman PLS#22404
Horizon Row, LLC
Date Signed: 02/11/2018
P.O. Box 548, Dry Creek, LA 70637
(903) 388-3045
Employee of Horizon Row, LLC



EXHIBIT "A"
PAGE 3 of 4



QUAD MAP

SECTION 10, T26S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:
JESUS RIVERO

Date: 05/16/2019

Drawn for:



LINE NUMBER:
EL8324


WBS NUMBER:
XX-130173.01.SLC

SCALE:
1" = 2000'

REVISIONS:

SURVEY DATE:
05/14/2019

EXHIBIT "A"
PAGE 4 of 4



AERIAL MAP

SECTION 10, T26S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:
JESUS RIVERO

Date: 05/16/2019

Drawn for:



LINE NUMBER:
EL8324

WBS NUMBER:
XX-130173.01.SLC

SCALE:
1" = 2000'


REVISIONS:

SURVEY DATE:
05/14/2019

THOROUGHBRED 10 CTB 1 (AA000253631)

DEVON ENERGY PRODUCTION COMPANY, L.P.
 IN THE N/2 SW/4 SW/4 OF
 SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

JUNE 10, 2019



DESCRIPTION

A CERTAIN PIECE OR PARCEL OF LAND AND REAL ESTATE LYING IN BUREAU OF LAND MANAGEMENT LAND IN THE N/2 SW/4 SW/4 OF SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO.

BEGINNING AT THE SOUTHWEST CORNER OF THE PARCEL, WHENCE THE SOUTHWEST CORNER OF SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S16°21'07\"W, A DISTANCE OF 699.70 FEET;
 THENCE N00°16'04\"W A DISTANCE OF 499.99 FEET TO THE NORTHWEST CORNER OF THE PARCEL;
 THENCE N89°35'50\"E A DISTANCE OF 500.07 FEET TO THE NORTHEAST CORNER OF THE PARCEL;
 THENCE S00°15'03\"E A DISTANCE OF 500.02 FEET TO THE SOUTHEAST CORNER OF THE PARCEL;
 THENCE S89°36'04\"W A DISTANCE OF 499.93 FEET TO THE SOUTHWEST CORNER OF THE PARCEL, THE POINT OF BEGINNING;
 CONTAINING 5.739 ACRES MORE OR LESS.

GENERAL NOTES

- 1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A CENTRAL TANK BATTERY
- 2.) BASIS OF BEARING IS NEW MEXICO STATE PLANE EAST ZONE MODIFIED TO THE SURFACE (NAD83), COORDINATES ARE NAD 83. ELEVATIONS ARE NAVD 88

DRIVING DIRECTIONS: FROM THE INTERSECTION OF CR. 1 (ORLA HWY.) & MONSANTO ROAD, GO SOUTH ON CR. 1 APPROX. 4.2 MILES TO A CALICHE ROAD (PIPELINE/ROSS ROAD). TURN RIGHT (WEST) AND GO APPROX. 5.2 MILES TO A T INTERSECTION, TURN LEFT AND GO SOUTH APPROX. 1.0 MILE, TURN RIGHT AND GO WEST APPROX. 0.25 MILE TO THE SOUTHWEST CORNER OF AN EXISTING WELLPAD AND A ROAD SURVEY, TURN RIGHT AND FOLLOW ROAD SURVEY NORTH APPROX. 0.2 MILE, TURN LEFT AND GO WEST APPROX. 0.2 MILE, TURN LEFT AND GO SOUTH APPROX 0.1 MILE, TURN RIGHT AND GO WEST 185' TO THE SOUTHEAST PAD CORNER FOR THIS LOCATION.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 10th DAY OF JUNE 2019

(Signature of Filmon F. Jaramillo)
 FILMON F. JARAMILLO, PLS. #2797
 301 SOUTH CANAL
 (875) 234-3341

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

SHEET: 1-3


MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO SURVEY NO. 6714

THOROUGHbred 10 CTB 1 (AA000253631)

DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE N/2 SW/4 SW/4 OF
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JUNE 10, 2019

QUAD MAP



SHEET: 2-3

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO

SURVEY NO. 6714

(575) 234-3341


THOROUGHbred 10 CTB 1 (AA000253631)

DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE N/2 SW/4 SW/4 OF
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JUNE 10, 2019

AERIAL PHOTO

SECTION 10
T. 26 S., R. 31 E.
BUREAU OF LAND
MANAGEMENT LAND



THOROUGHbred
10 CTB 1

THOROUGHbred
10 WELLPAD 1


0 250 500 750
SCALE 1" = 500'

SHEET: 3-3

SURVEY NO. 6714

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

PLAN VIEW



0 12 60 120 240
SCALE 1" = 120'

THOROUGHbred
10 WELLPAD 1
DEVON ENERGY PRODUCTION COMPANY, L.P.
PAD ELEVATIONS AND CROSS SECTIONS
FOR THOROUGHbred 10 CTB 1
SECTION 10, TOWNSHIP 26 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

CUT	FILL	NET
12355 CU. YD	27425 CU. YD	15070 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED


JUNE 10, 2019

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO


SHEET 1-2
SURVEY NO. 6714

CROSS-SECTIONS


SECTION A-A'



SECTION B-B'



SECTION C-C'



0 12 60 120 240
SCALE 1" = 120' - 1" = 20' VER

DEVON ENERGY PRODUCTION COMPANY, L.P.
PAD ELEVATIONS AND CROSS SECTIONS
FOR THOROUGHbred 10 CTB 1
SECTION 10, TOWNSHIP 26 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

CUT	FILL	NET
12355 CU. YD	27425 CU. YD	15070 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED


JUNE 10, 2019

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341


SHEET 2-2
SURVEY NO. 6714

ACCESS ROAD PLAT
ACCESS ROAD FOR THOROUGHbred 10 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 10, 2019



SEE NEXT SHEET (2-2) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 12th DAY OF JUNE 2019

FILIMON F. JARAMILLO, P.S. 12797

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

SURVEY NO. 6714

SHEET: 1-2

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

301 SOUTH CANAL
 (575) 234-3341

ACCESS ROAD PLAT
ACCESS ROAD FOR THOROUGHbred 10 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 10, 2019

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S45°17'24"W, A DISTANCE OF 980.67 FEET;
THENCE N89°52'58"E A DISTANCE OF 185.22 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTH QUARTER CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S69°25'51"E, A DISTANCE OF 1911.47 FEET;

SAID STRIP OF LAND BEING 185.22 FEET OR 11.23 RODS IN LENGTH, CONTAINING 0.128 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 185.22 L.F. 11.23 RODS 0.128 ACRES

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-2

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (575) 234-3341

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.


IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 10th DAY OF JUNE 2019

FILIMON F. JARAMILLO, PLS 12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6714

EXHIBIT "A"
 PAGE 1 of 4
 ELECTRIC LINE PLAT
 SECTION 10, T26S-R31E, N.M.P.M.
 EDDY COUNTY, NEW MEXICO




30' EASEMENT AREA = 2.238 ACRE(S)
 3249.64 FEET OR 196.95 RODS

SEE THE ATTACHED LEGAL DESCRIPTION
 Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

- 0+00.0 P.O.B./XCEL TO SNAPPING 11 FED 1H LATERAL BATTERY CONNECT
- 0+31.1 EOG PIPELINE
- 0+48.9 FLOWLINE
- 0+55.6 EDGE OF ROAD
- 0+67.6 C/L ROAD
- 0+80.6 EDGE OF ROAD
- 1+04.2 FLOWLINE
- 19+27.8 THOROUGHBRED 10 CTB 2 ELECTRIC LINE
- 26+90.4 THOROUGHBRED WELLPAD 1 & 2 ELECTRIC LINE
- 32+49.6 P.O.E./THOROUGHBRED 10 CTB 1 ELECTRIC LINE

LINE	BEARING	DISTANCE
L1	S 89°35'05"	W 3249.64'

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman
 Date Signed: 06-05-2019
 571 STATE STREET, JASPER, TX.
 (409) 202-5111 75951
 Employee of Horizonrow, LLC



HORIZON ROW LLC

Drawn for:

Drawn by: JESUS RIVERO Date: 05/16/2016

DEVON ENERGY PRODUCTION COMPANY, L.P.
 THOROUGHBRED 10 PRIMARY ELECTRIC LINE
 PROPOSED 30' EASEMENT ON THE PROPERTY OF BUREAU OF LAND MANAGEMENT SECTION 10, T26S-R31E, N.M.P.M.

LINE NUMBER: ELB322
WBS NUMBER: XX-130173.01.SLC
SCALE: 1" = 1000'
REVISIONS:
SURVEY DATE: 05/13/19

**SECTION 10, T26S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO**

ELECTRIC LINE PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southeast quarter (SE ¼) and the southwest quarter (SW ¼) of Section 10, Township 26 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 2" iron pipe w/BC found for the southeast corner of Section 10, T26S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence N 51°49'40" W a distance of 2186.57' to the **Point of Beginning** of this easement having coordinates of Northing=383809.38, Easting=718049.74 feet and continuing the following courses;

Thence S 89°35'05" W a distance of 3249.64' to the **Point of Ending** having coordinates of Northing=383785.83, Easting=714800.19 feet in Section 10, T26S-R31E, N.M.P.M., Eddy County, New Mexico, from said point a 1" iron pipe w/BC for the west quarter corner of Section 10, T26S-R31E, bears N 16°27'08" W a distance of 1355.53, covering **3249.64' or 196.95 rods** and having an area of **2.238 acre**.

NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman PLS#22404

Date Signed: 06-05-2019

Horizon Row, LLC


571 State Street Jasper, Tx

(409) 202-5111 75951

Employee of Horizon Row, LLC



EXHIBIT "A"
PAGE 3 of 4



QUAD MAP

SECTION 10, T26S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:
JESUS RIVERO

Date: 05/16/2019

Drawn for:



LINE NUMBER:
EL8322


WBS NUMBER:
XX-1.30173.01.SLC

SCALE:
1" = 2000'


REVISIONS:

SURVEY DATE:
05/13/2019

FLOWLINE PLAT
THOROUGHbred 10 PAD 1 TO THE THOROUGHbred 10 CTB 1 BURIED FLOWLINE
DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 16, 2019



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 16 DAY OF MAY 2019

12797
 FILMON F. JARAMILLO
 PROFESSIONAL SURVEYOR

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

SURVEY NO. 7283

SHEET: 1-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

FLOWLINE PLAT

THOROUGHbred 10 PAD 1 TO THE THOROUGHbred 10 CTB 1 BURIED FLOWLINE

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 16, 2019

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.; WHENCE THE SOUTHWEST CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S24°18'04"W, A DISTANCE OF 517.23 FEET;

THENCE N00°13'55"W A DISTANCE OF 130.13 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;

THENCE N89°36'52"E A DISTANCE OF 134.96 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;

THENCE N00°13'38"W A DISTANCE OF 70.06 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE WEST QUARTER CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N10°12'34"W, A DISTANCE OF 2025.66 FEET;

SAID STRIP OF LAND BEING 335.15 FEET OR 20.31 RODS IN LENGTH, CONTAINING 0.231 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 335.15 L.F. 20.31 RODS 0.231 ACRES

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 16th DAY OF MAY 2019

(Signature of Filmon F. Jaramillo)
FILMON F. JARAMILLO, SURVEYOR NO. 12797
201 SOUTH CANAL
(575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.


SHEET: 2-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEY NO. 7283

FLOWLINE PLAT
THOROUGHbred 10 PAD 1 TO THE THOROUGHbred 10 CTB 1 BURIED FLOWLINE

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 16, 2019



SHEET: 3-4


SURVEY NO. 7283

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

FLOWLINE PLAT

THOROUGHbred 10 PAD 1 TO THE THOROUGHbred 10 CTB 1 BURIED FLOWLINE

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 16, 2019



NM T26S R31E

SHEET: 4-4

SURVEY NO. 7283

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341


S10, T26S, R31E
 EDDY COUNTY, STATE OF NEW MEXICO
 BUREAU OF LAND MANAGEMENT LAND
 335.15 L.F.
 20.31 RODS

OWNERSHIP

PLAN ON AERIAL




1" = 100' HOR




POINT	STATION	ELEV.
B.O.L.	0+00	3236.0
E.O.L.	3+35.2	3240.5
HP	3+35.2	3240.5
CP	0+00	3236.0

EASEMENT


N.T.S.



STATIONING



PROFILE



1" = 10' VER

LEGEND

- CENTERLINE
- - - EASEMENT
- SECTION LINE
- QUARTER LINE
- EXISTING PIPELINE
- EXISTING POWER LINE
- EXISTING FENCE LINE
- 5' CONTOUR LINE

PIPE SPECIFICATIONS AND TEST REQUIREMENTS									
FROM	TO	LN. FT.	O.D.	W.T.	GRADE	D.P.	TEST PRESS. PSI	SM. DUR. HR.	

BILL OF MATERIAL	

X-RAY REQUIREMENTS

1. All pipe joints shall be radiographed in accordance with the requirements of the American Society of Mechanical Engineers (ASME) Section VIII, Division 1, Subsection (1) for the design stress intensity factor (DSIF) of 1.0.

2. All pipe joints shall be radiographed in accordance with the requirements of the American Society of Mechanical Engineers (ASME) Section VIII, Division 1, Subsection (1) for the design stress intensity factor (DSIF) of 1.0.

3. All pipe joints shall be radiographed in accordance with the requirements of the American Society of Mechanical Engineers (ASME) Section VIII, Division 1, Subsection (1) for the design stress intensity factor (DSIF) of 1.0.

RECORD


APPROVED FOR CONSTRUCTION
 MAY 16, 2019

**DEVON ENERGY
 PRODUCTION
 COMPANY, L.P.**

THOROUGHBRED 10 PAD 1 TO THE
 THOROUGHBRED 10 CTR 1 BURIED
 FLOWLINE

MAY 16, 2019

EXHIBIT "A"
 PAGE 1 of 4
 ELECTRIC LINE PLAT
 SECTION 10, T26S-R31E, N.M.P.M.
 EDDY COUNTY, NEW MEXICO





30' EASEMENT AREA = 0.135 ACRE(S)
 195.94 FEET OR 11.88 RODS

0+00.0 P.O.B./THOROUGHbred 10 PRIMARY ELECTRIC LINE
 1+95.9 P.O.E./THOROUGHbred 10 CTB 1

LINE	BEARING	DISTANCE
L1	S 00°24'55" E	195.94'

SEE THE ATTACHED LEGAL DESCRIPTION
 Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman
 PLS #22404
 Date Signed: 06-05-2019
 P.O. Box 548, Dry Creek, LA
 (903) 388-3045 70637
 Employee of Horizonrow, LLC

HORIZON ROW LLC
 Drawn for:
devon
 Drawn by: JESUS RIVERO
 Date: 05/18/2019

DEVON ENERGY PRODUCTION COMPANY, L.P.	LINE NUMBER: ELB328
THOROUGHbred 10 CTB 1 ELECTRIC LINE	WBS NUMBER: XX-130173.01.SLC
PROPOSED 30' EASEMENT ON THE PROPERTY OF BUREAU OF LAND MANAGEMENT	SCALE: 1" = 1000'
SECTION 10, T26S-R31E, N.M.P.M.	REVISIONS:
	SURVEY DATE: 05/13/19

**SECTION 10, T26S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO**

ELECTRIC LINE PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southwest quarter (SW ¼) of Section 10, Township 26 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 1" iron pipe w/BC found for the west quarter corner of Section 10, T26S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence S 16°27'08" E a distance of 1355.53' to the **Point of Beginning** of this easement having coordinates of Northing=383785.83, Easting=714800.19 feet and continuing the following courses;

Thence S 00°24'55" E a distance of 195.94' to the **Point of Ending** having coordinates of Northing=383785.93, Easting=714800.19 feet in Section 10, T26S-R31E, N.M.P.M., Eddy County, New Mexico, from said point a 2" iron pipe w/BC for the southwest corner of Section 10, T26S-R31E, bears S 17°42'15" W a distance of 1227.71, covering **195.94' or 11.88 rods** and having an area of **0.135 acre**.

NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman PLS#22404

Date Signed: 06-05-2019

Horizon Row, LLC


P.O. Box 548, Dry Creek, LA

(903) 388-3045 70637

Employee of Horizon Row, LLC



EXHIBIT "A"
PAGE 3 of 4



QUAD MAP

SECTION 10, T26S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:
JESUS RIVERO

Date: 05/16/2019

Drawn for:



LINE NUMBER:
EL8328


WBS NUMBER:
XX-130173.01.SLC

SCALE:
1" = 2000'

REVISIONS:

SURVEY DATE:
05/13/2019

EXHIBIT "A"
PAGE 4 of 4



AERIAL MAP

SECTION 10, T26S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED '30' EASEMENT

Drawn by:
JESUS RIVERO

Date: 05/16/2019

Drawn for:



LINE NUMBER:
EL8328

WBS NUMBER:
XX-130173.01.SLC

SCALE:
1" = 2000'


REVISIONS:

SURVEY DATE:
05/13/2019


ACCESS ROAD PLAT (7600228R)

PRIMARY ACCESS ROAD FOR THOROUGHbred 10 WELLPADS & CTBS

DEVON ENERGY PRODUCTION COMPANY, L.P.
 CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
 SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 JUNE 10, 2019



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 10th DAY OF JUNE 2019

(Signature)
 FILIMON F. JARAMILLO, 12797

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

SURVEY NO. 6933

SHEET: 1-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT (7600228R)

PRIMARY ACCESS ROAD FOR THOROUGHBRED 10. WELLPADS & CTBS

**DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 10, 2019**

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

MAIN ROAD.

BEGINNING AT A POINT WITHIN THE SE/4 SW/4 OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTH QUARTER CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S87°53'58"E, A DISTANCE OF 567.26 FEET;
THENCE N44°59'39"W A DISTANCE OF 49.57 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N00°16'01"W A DISTANCE OF 1115.75 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N45°07'27"W A DISTANCE OF 49.64 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE S89°52'32"W A DISTANCE OF 1113.41 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE S44°54'48"W A DISTANCE OF 49.56 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE S00°07'41"E A DISTANCE OF 497.52 FEET THE TERMINUS OF THIS CENTERLINE SURVEY; WHENCE THE SOUTHWEST CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S51°57'27"W, A DISTANCE OF 1120.17 FEET;

SAID STRIP OF LAND BEING 2875.44 FEET OR 174.27 RODS IN LENGTH, CONTAINING 1.980 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SW/4	1914.03 L.F.	116.00 RODS	1.318 ACRES
SW/4 SW/4	961.41 L.F.	58.27 RODS	0.662 ACRES

LATERAL ROAD

BEGINNING AT A POINT WITHIN THE SE/4 SW/4 OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTH QUARTER CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S47°30'49"E, A DISTANCE OF 1784.20 FEET;
THENCE S44°58'09"W A DISTANCE OF 35.33 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE S00°07'10"E A DISTANCE OF 503.61 FEET THE TERMINUS OF THIS CENTERLINE SURVEY; WHENCE THE SOUTH QUARTER CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S63°12'29"E, A DISTANCE OF 1500.76 FEET;

SAID STRIP OF LAND BEING 538.94 FEET OR 32.66 RODS IN LENGTH, CONTAINING 0.371 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SW/4	261.02 L.F.	15.82 RODS	0.180 ACRES
SW/4 SW/4	277.92 L.F.	16.84 RODS	0.191 ACRES

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 10th DAY OF JUNE 2019

[Signature]
FILMON F. JARAMILLO PLS. 12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6933

GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.


SHEET: 2-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT (7600228R)

PRIMARY ACCESS ROAD FOR THOROUGHbred 10 WELLPADS & CTBS


DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 10, 2019



ACCESS ROAD PLAT (7600228R)

PRIMARY ACCESS ROAD FOR THOROUGHbred 10 WELLPADS & CTBS


DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 10, 2019



FLOWLINE PLAT (7600249F)

BURIED FLOWLINE FROM THOROUGHbred 10 WELLPAD 2 TO THOROUGHbred 10 CTB 3

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2019



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 06 DAY OF AUGUST 2019

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

FILIMON F. JARAMILLO, SLS 12797

SURVEY NO. 7464

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (575) 234-3341

SHEET: 1-4

FLOWLINE PLAT (7600249F)

BURIED FLOWLINE FROM THOROUGHbred 10 WELLPAD 2 TO THOROUGHbred 10 CTB 3

**DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2019**

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S66°42'14"W, A DISTANCE OF 1466.22 FEET;

BEGINNING AT A POINT WITHIN THE SE/4 SW/4 OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S66°42'14"W, A DISTANCE OF 1466.22 FEET;
THENCE N00°16'47"W A DISTANCE OF 16.18 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N89°38'49"E A DISTANCE OF 698.57 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N80°57'39"E A DISTANCE OF 628.24 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE S89°33'50"E A DISTANCE OF 1080.56 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHEAST CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S67°44'27"E, A DISTANCE OF 1723.85 FEET;

SAID STRIP OF LAND BEING 2423.55 FEET OR 146.88 RODS IN LENGTH, CONTAINING 1.669 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SW/4	1345.55 L.F.	81.55 RODS	0.927 ACRES
SW/4 SE/4	1078.00 L.F.	65.33 RODS	0.742 ACRES

20' TEMPORARY WORK SPACE
BEING A TEMPORARY WORK SPACE TWENTY FEET IN WIDTH LYING ON THE LEFT SIDE AND ADJOINING THE LEFT SIDE OF THE ABOVE DESCRIBED STRIP OF LAND 30 FEET WIDE, HAVING A TOTAL AREA OF 1.136 ACRES.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS _____ DAY OF AUGUST 2019

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 7464

GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSF EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

FILIMON F. JARAMILLO, PLS. 12797
301 SOUTH CANAL
(575) 234-3341

FLOWLINE PLAT (7600249F)

BURIED FLOWLINE FROM THOROUGHbred 10 WELLPAD 2 TO THOROUGHbred 10 CTB 3


DEVON ENERGY PRODUCTION COMPANY, L.P.

CENTERLINE SURVEY OF A PIPELINE CROSSING

SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

AUGUST 6, 2019



SHEET: 3-4


SURVEY NO. 7464

MADRON SURVEYING, INC. 301 SOUTH CANAL (576) 234-3341 CARLSBAD, NEW MEXICO

FLOWLINE PLAT (7600249F)

BURIED FLOWLINE FROM THOROUGHbred 10 WELLPAD 2 TO THOROUGHbred 10 CTB 3


DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2019



THOROUGHbred 10 CTB 3 (AA000289612)

DEVON ENERGY PRODUCTION COMPANY, L.P.
 IN THE W/2 SE/4 SE/4 & E/2 SW/4 SW/4 OF
 SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

JULY 1, 2019



LEGEND
 ● SET NAIL

DESCRIPTION

A CERTAIN PIECE OR PARCEL OF LAND AND REAL ESTATE LYING IN BUREAU OF LAND MANAGEMENT LAND IN THE W/2 SE/4 SE/4 & E/2 SW/4 SW/4 OF SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

BEGINNING AT THE SOUTHEAST CORNER OF THE PARCEL, WHENCE THE SOUTHEAST CORNER OF SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S59°38'11\"E, A DISTANCE OF 1270.47 FEET;
 THENCE S89°35'08\"W A DISTANCE OF 500.04 FEET TO THE SOUTHWEST CORNER OF THE PARCEL;
 THENCE N00°33'02\"W A DISTANCE OF 500.05 FEET TO THE NORTHWEST CORNER OF THE PARCEL;
 THENCE N89°35'04\"E A DISTANCE OF 500.04 FEET TO THE NORTHEAST CORNER OF THE PARCEL;
 THENCE S00°33'04\"E A DISTANCE OF 500.05 FEET TO THE SOUTHEAST CORNER OF THE PARCEL, THE POINT OF BEGINNING;
 CONTAINING 5.740 ACRES MORE OR LESS.

GENERAL NOTES

- 1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A CENTRAL TANK BATTERY
- 2.) BASIS OF BEARING IS NEW MEXICO STATE PLANE EAST ZONE MODIFIED TO THE SURFACE (NAD83), COORDINATES ARE NAD 83, ELEVATIONS ARE NAVD 88

DRIVING DIRECTIONS: FROM STATE HWY. 128 & CR. 1 (ORLA), GO SOUTH ON CR. 1 10.4 MILES, TURN RIGHT ON CALICHE ROAD (ROSS/PIPELINE RD) AND GO WEST 5.23 MILES, TURN LEFT AND GO SOUTH 0.88 MILES TO A ROAD SURVEY AND FOLLOW FLAGS EAST 190' TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 1ST DAY OF JULY 2019

(Signature of Filimon F. Jaramillo)
 FILIMON F. JARAMILLO, SURVEYOR
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 (575) 234-3341

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

SURVEY NO. 6716

SHEET: 1-3


MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

THOROUGHbred 10 CTB 3 (AA000289612)

DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE W/2 SE/4 SE/4 & E/2 SW/4 SW/4 OF
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JULY 1, 2019

QUAD MAP



SHEET: 2-3

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO

SURVEY NO. 6716

(575) 234-3341

THOROUGHbred 10 CTB 3 (AA000289612)


DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE W/2 SE/4 SE/4 & E/2 SW/4 SW/4 OF
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JULY 1, 2019


AERIAL PHOTO

SECTION 10
T. 26 S., R. 31 E.
BUREAU OF LAND
MANAGEMENT LAND

THOROUGHbred
10 CTB 3



THOROUGHbred
10 WELLPAD 4




SCALE 1" = 300'

SHEET: 3-3

SURVEY NO. 6716

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341


PLAN VIEW



I, FILMON F. JARAMILLO, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY AND THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.



DEVON ENERGY PRODUCTION COMPANY, L.P.
 PAD ELEVATIONS AND CROSS SECTIONS
 FOR THOROUGHbred 10 CTB 3
 SECTION 10, TOWNSHIP 26 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO



CUT	FILL	NET
7070 CU. YD	4562 CU. YD	2508 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED

FILMON F. JARAMILLO, PLS. (10123)


MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
 (575) 234-3341

JULY 1, 2019


SHEET 1-2
 SURVEY NO. 6716

CROSS-SECTIONS


SECTION A-A'



SECTION B-B'



SECTION C-C'



I, FILIMON F. JARAMILLO, NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

[Handwritten Signature]
 FILIMON F. JARAMILLO, REGISTERED PROFESSIONAL SURVEYOR
 DATE: 7/1/2019

DEVON ENERGY PRODUCTION COMPANY, L.P.
PAD ELEVATIONS AND CROSS SECTIONS
FOR THOROUGHbred 10 CTB 3
 SECTION 10, TOWNSHIP 26 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

012 60 120 240
 SCALE 1" = 120' - 1" = 20' VER

CUT	FILL	NET
7070 CU. YD	4562 CU. YD	2508 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED


JULY 1, 2019
MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
 (575) 234-3341

SHEET 2-2
 SURVEY NO. 6716

ACCESS ROAD PLAT

ACCESS ROAD FOR THOROUGHbred 10 CTB 3

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JULY 1, 2019



SEE NEXT SHEET (2-2) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 1ST DAY OF JULY 2019

(Signature of Filmon F. Jaramillo)
 FILMON F. JARAMILLO, S.S. 12797
 301 SOUTH CANAL, CARLSBAD, NEW MEXICO (575) 234-3341

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

SHEET: 1-2

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEY NO. 6716

ACCESS ROAD PLAT
ACCESS ROAD FOR THOROUGHBRED 10 CTB 3

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JULY 1, 2019

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SE/4 OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTH QUARTER CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S52°10'05"W, A DISTANCE OF 1118.26 FEET;
THENCE N89°27'25"E A DISTANCE OF 189.98 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHEAST CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S67°16'39"E, A DISTANCE OF 1730.89 FEET;

SAID STRIP OF LAND BEING 189.98 FEET OR 11.51 RODS IN LENGTH, CONTAINING 0.131 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SE/4 189.98 L.F. 11.51 RODS 0.131 ACRES


GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 1ST DAY OF JULY 2019


12797


MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SHEET: 2-2

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEY NO. 6716

EXHIBIT "A"
 PAGE 1 of 4
 ELECTRIC LINE PLAT
 SECTION 10, T26S-R31E, N.M.P.M.
 EDDY COUNTY, NEW MEXICO



30' EASEMENT AREA = 0.149 ACRE(S)
 216.57' FEET OR 13.13 RODS


0+00.0 P.O.B./SHETLAND 11 PRIMARY ELECTRIC LINE
 1+66.0 SHETLAND 11 PRIMARY ACCESS ROAD
 2+16.6 P.O.E./THOROUGHBRED 10 CTB 3

LINE	BEARING	DISTANCE
L1	S 00°24'55" E	216.57'

SEE THE ATTACHED LEGAL DESCRIPTION

Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman
 Date Signed: 06-05-2019
 P.O. Box 548, Dry Creek, LA
 (903) 388-3045 70637
 Employee of Horizonrow, LLC

HORIZON ROW LLC

Drawn for:

Drawn by: JESUS RIVERO Date: 05/21/2019

DEVON ENERGY PRODUCTION COMPANY, L.P.
 THOROUGHBRED 10 CTB 3
 ELECTRIC LINE
 PROPOSED 30' EASEMENT
 ON THE PROPERTY OF
 BUREAU OF LAND MANAGEMENT
 SECTION 10, T26S-R31E, N.M.P.M.

LINE NUMBER:
 ELB330
 WBS NUMBER:
 XX-130173.01.SLC
 SCALE:
 1" = 1000'
 REVISIONS:
 SURVEY DATE:
 05/14/19

**SECTION 10, T26S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO**

ELECTRIC LINE PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southeast quarter (SE ¼) of Section 10, Township 26 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 1" iron pipe w/BC found for the east quarter corner of Section 10, T26S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence S 46°46'37" W a distance of 1918.63' to the **Point of Beginning** of this easement having coordinates of Northing=383811.52, Easting=718344.93 feet and continuing the following courses;

Thence S 00°24'55" E a distance of 216.57' to the **Point of Ending** having coordinates of Northing=383594.96, Easting=718346.50 feet in Section 10, T26S-R31E, N.M.P.M., Eddy County, New Mexico, from said point a 2" iron pipe w/BC for the southeast corner of Section 10, T26S-R31E, bears S 51°21'39" E a distance of 1820.81, covering **216.57' or 13.13 rods** and having an area of **0.149 acre**.

NOTES:


Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.


B.L. Laman PLS#22404
Horizon Row, LLC
Date Signed: 06/05/2019
P.O. Box 548, Dry Creek, LA 70637
(903) 388-3045
Employee of Horizon Row, LLC



EXHIBIT "A"
PAGE 3 of 4



QUAD MAP

SECTION 10, T26S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:
JESUS RIVERO

Date: 05/16/2019

Drawn for:



LINE NUMBER:
ELB330


WBS NUMBER:
XX-130173.01.SLC

SCALE:
1" = 2000'

REVISIONS:

SURVEY DATE:
05/14/2019

EXHIBIT "A"
PAGE 4 of 4



AERIAL MAP

SECTION 10, T26S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:
JESUS RIVERO

Date: 05/16/2019

Drawn for:



LINE NUMBER:
EL8330

WBS NUMBER:
XX-130173.01.SLC

SCALE:
1" = 2000'


REVISIONS:

SURVEY DATE:
05/14/2019


FLOWLINE PLAT (7600248F)

BURIED FLOWLINE FROM THOROUGHbred 10 WELLPAD 1 TO THOROUGHbred 10 CTB 3

DEVON ENERGY PRODUCTION COMPANY, L.P.
 CENTERLINE SURVEY OF A PIPELINE CROSSING
 SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 AUGUST 6, 2019



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS _____ DAY OF AUGUST 2019

(Signature of Filimon F. Jaramillo)
 12797

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

SHEET: 1-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO SURVEY NO. 7463

FILIMON F. JARAMILLO, PLS. 12797
 301 SOUTH CANAL
 (575) 234-3341

FLOWLINE PLAT (7600248F)

BURIED FLOWLINE FROM THOROUGHbred 10 WELLPAD 1 TO THOROUGHbred 10 CTB 3

**DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2019**

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S20°26'46"W, A DISTANCE OF 609.09 FEET;
THENCE N00°56'00"E A DISTANCE OF 30.57 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N89°21'34"E A DISTANCE OF 1830.70 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N80°46'46"E A DISTANCE OF 628.90 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE S89°56'04"E A DISTANCE OF 1080.63 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHEAST CORNER OF SAID SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S66°49'15"E, A DISTANCE OF 1736.41 FEET;

SAID STRIP OF LAND BEING 3570.80 FEET OR 216.41 RODS IN LENGTH, CONTAINING 2.459 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4	1150.53 L.F.	69.73 RODS	0.792 ACRES
SE/4 SW/4	1343.05 L.F.	81.40 RODS	0.925 ACRES
SW/4 SE/4	1077.22 L.F.	65.29 RODS	0.742 ACRES

20' TEMPORARY WORK SPACE

BEING A TEMPORARY WORK SPACE TWENTY FEET IN WIDTH LYING ON THE LEFT SIDE AND ADJOINING THE LEFT SIDE OF THE ABOVE DESCRIBED STRIP OF LAND 30 FEET WIDE, HAVING A TOTAL AREA OF 1.662 ACRES.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF AUGUST 2019

(Handwritten signature of Filmon F. Jaramillo)
FILMON F. JARAMILLO, PLS. 12797
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
(575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 7463

GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.


SHEET: 2-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

FLOWLINE PLAT (7600248F)

BURIED FLOWLINE FROM THOROUGHbred 10 WELLPAD 1 TO THOROUGHbred 10 CTB 3

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2019



FLOWLINE PLAT (7600248F)

BURIED FLOWLINE FROM THOROUGHbred 10 WELLPAD 1 TO THOROUGHbred 10 CTB 3


DEVON ENERGY PRODUCTION COMPANY, L.P.

CENTERLINE SURVEY OF A PIPELINE CROSSING

SECTION 10, TOWNSHIP 26 SOUTH, RANGE 31 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

AUGUST 6, 2019





APD ID: 10400043121

Submission Date: 06/27/2019

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHBRED 10-3 FED

Well Number: 621H

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHBRED 10-3 FED

Well Number: 621H

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD disturbance (acres):

PWD surface owner:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHbred 10-3 FED

Well Number: 621H

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: THOROUGHBRED 10-3 FED

Well Number: 621H

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment: