5-07-670



RESUBMITTAL

OCT 0 2 2007

Expires March 31, 2007	
Lease Serial No NMLC 069627	

If Indian, Allotee or Tribe Name

5

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER If Unit or CA Agreement, Name and No **V** DRILL REENTER la Type of work NMNM 71016 8 Lease Name and Well No. Type of Well Oil Well Gas Well Single Zone Multiple Zone Poker Lake Unit #250 Name of Operator BEPCO, L. P. 3b Phone No. (include area code) Address P. O. Box 2760 10 Field and Pool, or Exploratory Midland, TX 79702 432-683-2277 Nash Draw (Delaware, BS, Avalon) 11 Sec, T R M or Blk and Survey or Area Location of Well (Report location clearly and in accordance with any State requirements *) SENE, UL H, 1400' FNL, 990' FEL, Lat 32.191944, Lon 103.915306 Sec 30, T24S, R30E Mer NMP At proposed prod zone Same 12 County or Parish 13 State 14 Distance in miles and direction from nearest town or post office* 14 miles east of Malaga NM Eddy Distance from proposed 16 No of acres in lease 17 Spacing Unit dedicated to this well 990 location to nearest property or lease line, ft 1922 (Also to nearest drig unit line, if any) 20 BLM/BIA Bond No on file 19 Proposed Depth 18 Distance from proposed location* to nearest well, drilling, completed, 7800' MD, 7800' TVD 644 NM 2204 applied for, on this lease, ft 22 Approximate date work will start* Elevations (Show whether DF, KDB, RT, GL, etc.) 23 Estimated duration 3161' GL 10/01/2007 12 days 24. Attachments The following, completed in accordance with the requirements of Onshore Oil and Gas Order No 1, shall be attached to this form 1 Well plat certified by a registered surveyor Bond to cover the operations unless covered by an existing bond on file (see Item 20 above) 2 A Drilling Plan 3 A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office) Such other site specific information and/or plans as may be required by the authorized officer 25 Name (Printed/Typed) Annette Childers Administrative Assistant Name (Printed Sped) Don Peterson Approved by (Signatur S Don Peterson Title Office

If earthen pits are used in association with the drilling of this well, an OCD pit permit must be obtained prior to pit construction.

ant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to

APPROVAL FOR TWO YEARS

ke it a crime for any person knowingly and willfully to make to any department or agency of the United itions as to any matter within its jurisdiction

Carlsbad Controlled Water Basin

SEE ATTACHED FOR **CONDITIONS OF APPROVAL** APPROVAL SUBJECT TO **GENERAL REQUIREMENTS** AND SPECIAL STIPULATIONS ATTACHED

DISTRICT I 1625 N. French Dr., Hobbe, NM 88240 DISTRICT II 811 South First, Artesia, NM 88210

State of New Mexico

Rnergy, Minerals and Natural Resources Department

Form C-102 Revised March 17, 1999

Submit to Appropriate District Office

State Lease - 4 Copies Fee Lease - 3 Copies

DISTRICT III 1000 Rio Brazos Rd., Aztec, NM 87410

DISTRICT IV 2040 South Pacheco, Santa Fe, NM 87505

OIL CONSERVATION DIVISION


2040 South Pacheco Santa Fe, New Mexico 87504-2088

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API	Number	Pool Code				Pool Name				
30-015-34	1420		475	45	Nas	Nash Draw (Delaware, Bone Spring, Avalon Sd)				
Property	Code			,000	Property Nam	ie		Well Nu	Well Number	
001796				Р	OKER LAKE	UNIT		25	250	
OGRID N	0.				Operator Nam	ie		Elevat	ion	
001801			BEPCO, L.P.					616	6161' 3/6]	
Surface Location										
UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County	
Н	30	24 S	30 E		1400	NORTH	990	EAST	EDDY	
Bottom Hole Location If Different From Surface										
UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County	
Dedicated Acres Joint or Infill Consolidation Code Order No.										

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



DISTRICT I 1925 M. French Br., Hobbs, RM 96240

State of New Mexico Energy, Minerals and Natural Resources Department

Form C-102 Revised March 17, 1999

DISTRICT II 811 South First, Artesia, NM 88210

Submit to Appropriate District Office

State Lease - 4 Copies
Foo Lease - 3 Copies

DISTRICT III 1000 Rio Brazos Rd., Aztec, NN 67410

OIL CONSERVATION DIVISION

2040 South Pacheco

☐ AMENDED REPORT

DISTRICT IV 2040 South Pecheco, Santa Fe, NH 87505

LOT 4

40.38 ACRES

40.00 ACRES

WELL LOCATION AND ACREAGE DEDICATION PLAT

Santa Fe, New Mexico 87504-2088

H 30 24-S 30-E 1400 NORTH 990 EAST E Bottom Hole Location If Different From Surface	API Number			Pool Code			Pool Name					
Dedicated Acres John or Infill Consolidation Code Drder No. LOT 1 40.28 ACRES DASS ENTERPRISES PRODUCTION COMPANY BASS ENTERPRISES PRODUCTION COMPANY 3161 Surface Location UL or lot No. Section Township Range Lot Idn Feet from the North/South line Peet from the East/Vest line C EAST E Bottom Hole Location if Different From Surface UL or lot No. Section Township Range Lot Idn Feet from the North/South line Feet from the East/Vest line C Ea	Property	Property Code		l	F							
Surface Location UL or lot No. Section Township Range Lot Idn Feet from the North/South line Feet from the East/Vest line C 1400 NORTH 990 EAST E Bottom Hole Location If Different From Surface UL or lot No. Section Township Range Lot Idn Feet from the North/South line Feet from the East/Veet line C Dedicated Acres Joint or Infill Consolidation Code Drder No. C	OGRID N	D.	 								Elevation	
UL or lot No. Section Hole Location If Different From Surface Bottom Hole Location If Different From Surface UL or lot No. Section Township Range Lot ldn Feet from the North/South line Feet from the East/West line C			<u> </u>	BASS E	ENTERPI	PRISES PRODUCTION COMPANY 316			3161	P4-2		
Bottom Hole Location If Different From Surface Ul or lot No. Section Township Range Lot Idn Feet from the North/South line Feet from the East/West line C				Surface Location								
Bottom Hole Location If Different From Surface Ul or lot No. Section Township Range Lot Idn Feet from the North/South line Feet from the East/West line C Dedicated Acres Joint or Infill Consolidation Code Order No. I C NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATE OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION LOT 1 40.00 ACRES 40.00 ACRES 40.00 ACRES 40.00 ACRES 3151.8 3165.9 LATA N32*1131.8 LONG N003*20155.7 Date SURVEYOR CERTIFICATION SURVEYOR CERTIFICATION	UL or lot No.	Section	Township	Pange	Lot kin	Feet from t	h•	North/South line	Feet from the	1 1	County	
Dedicated Acres Joint or Infill Consolidation Code Order No. NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATE OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION LOT 1 40.00 ACRES 40.00 ACRES 40.00 ACRES 3158.9 3170.3 3158.9 3170.3 3158.9 3170.3 3158.9 3170.3 3158.9 3170.3 3158.9 3170.3 SIGNATURE W.R. DANNELS Printed Name DIVISION DRILLING SUPT. TILE J. LAN, N32-1/31 IX, LONG, W103-30-55. THE DATE DIVISION DRILLING SUPT. TILE J. LAN, N32-1/31 IX, LONG, W103-30-55. THE DATE SURVEYOR CERTIFICATION SURVEYOR CERTIFICATION	Н	30	24-S	30-E		1400		NORTH	990	EAST	EDDY	
Dedicated Acres Joint or Infill Consolidation Code Order No. NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATE OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION OPERATOR CERTIFICATION I hereby cortify the the information consisted herein is true and complete to best of my involedge and tellar. LOT 2 40.00 ACRES J151.8 J160.00 ACRES J160.00 ACRES SURVEYOR CERTIFICATION SIGNATURE DIVISION DRILLING SUPT. Title SURVEYOR CERTIFICATION SURVEYOR CERTIFICATION				Bottom	Hole Lo	cation If D	iffer	ent From Sur	face			
NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATE OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION OPERATOR CERTIFICATION I hereby certify the the toform contained herein is true and complete to best of my knowledge and belief. W.R. DANNELS Printed Name DIVISION DRILLING SUPT. TILL A0.31 ACRES 160.00 ACRES SURVEYOR CERTIFICATION SURVEYOR CERTIFICATION	UL or lot No.	Section	Township	Range	Lot Idn	Feet from t	he	North/South line	Feet from the	East/West line	County	
NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATE OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION OPERATOR CERTIFICATION I hereby certify the the toform contained herein is true and complete to best of my knowledge and belief. W.R. DANNELS Printed Name DIVISION DRILLING SUPT. TILL A0.31 ACRES 160.00 ACRES SURVEYOR CERTIFICATION SURVEYOR CERTIFICATION			<u> </u>	<u> </u>	<u> </u>					L	<u> </u>	
NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATE OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION OPERATOR CERTIFICATION I hereby certify the the fuform contained hervin is true and complete the best of my knowledge and bestef. A0.28 ACRES J158.9 3170.3 OPERATOR CERTIFICATION I hereby certify the the fuform contained hervin is true and complete the best of my knowledge and bestef. W.R. DANNELS Printed Name DIVISION DRILLING SUPT. TILLE J26.05 Date SURVEYOR CERTIFICATION SURVEYOR CERTIFICATION	-	Joint o	or haffin Co	msolidation	Code 0	rder No.						
LOT 1 40.00 ACRES LOT 2 40.00 ACRES LOT 2 40.00 ACRES LOT 2 40.00 ACRES LOT 2 40.00 ACRES LAT N32 1/31 IX LONG W103 20/55.1 LOT 2 160.00 ACRES LOT 2 160.00 ACRES SURVEYOR CERTIFICATION OPERATOR CERTIFICATION I hereby certify the the inform constained herein is true and complete the best of my knowledge and belief. W.R. DANNELS Printed Name DIVISION DRILLING SUPT. Title SURVEYOR CERTIFICATION SURVEYOR CERTIFICATION		1										
LOT 1 40.28 ACRES 40.00 ACRES 3158.9 3170.3 OPERATOR CERTIFICATION I hereby certify the the inform contained herein is true and complete the best of my knowledge and belief. WR. DANNELS Printed Name DIVISION DRILLING SUPT. Title 160.00 ACRES SURVEYOR CERTIFICATION	NO ALLO	WABLE 1								EEN CONSOLIDA	ATED	
LOT 1 40.28 ACRES 40.00 ACRES 3158.9 3170.3 1 hereby certify the the inform constained herein is true and complete the best of my knowledge and belief. WR. DANNELS Printed Name DIVISION DRILLING SUPT. Title 160.00 ACRES 160.00 ACRES SURVEYOR CERTIFICATION			OK A I	NUN-STAN	DARD U	NII HAS BE	RN 1	APPROVED BY	HR DIVISION			
LOT 1 40.28 ACRES 40.00 ACRES 3158.9 3170.3 LOT 2 40.00 ACRES 40.00 ACRES 3151.8 3165.9 LATANS2*1/31.0° LONG DRIOS*9455.7 Date contained herein is true and complete to best of my knowledge and belief. W.R. DANNELS Printed Name DIVISION DRILLING SUPT. Title S/26/05 Date SURVEYOR CERTIFICATION		1						1	OPERATO	OR CERTIFICAT	TON	
LOT 1 40.28 ACRES 40.00 ACRES 3158.9 3170.3 LOT 2 40.00 ACRES 50 3170.3 W.R. DANNELS Printed Name DIVISION DRILLING SUPT. Title 5/26/05 Date SURVEYOR CERTIFICATION		1						į	I Aereb	y certify the the in	formation	
40.28 ACRES 40.00 ACRES 3158.9 3170.3 W.R. DANNELS Printed Name DIVISION DRILLING SUPT. Table 160.00 ACRES 160.00 ACRES SURVEYOR CERTIFICATION	LOT	1 !					;	_	1 1	_	rte to the	
LOT 2 40.00 ACRES 40.00 ACRES 40.00 ACRES 40.00 ACRES 160.00 ACRES Signature WR. DANNELS Printed Name DIVISION DRILLING SUPT. Title SIGNATURE SIGNATURE WR. DANNELS Printed Name DIVISION DRILLING SUPT. Title SIGNATURE SURVEYOR CERTIFICATION			40.00	ACRES	İ			54				
LOT 2 40.00 ACRES 40.00 ACRES 40.00 ACRES 160.00 ACRES W.R. DANNELS Printed Name DIVISION DRILLING SUPT. Title SZ6/05 Date SURVEYOR CERTIFICATION		Ì				3158.	 .9	3170.3	Att		. ^ ^	
LOT 2 40.00 ACRES 40.00 ACRES 40.00 ACRES 160.00 ACRES W.R. DANNELS Printed Name DIVISION DRILLING SUPT. Title SZ6/05 Date SURVEYOR CERTIFICATION		1					<u> </u> -	-	Stepature	703/1	עשוט	
LOT 2 40.00 ACRES 40.00 ACRES 40.00 ACRES 160.00 ACRES Printed Name DIVISION DRILLING SUPT. Title SIRVEYOR CERTIFICATION							*	A 330	ヨ Γ	V.R. DANNELS		
LOT 2 40.00 ACRES LAT, N32 131.br LONG. W103 94 55.1 160.00 ACRES Title SIRVEYOR CERTIFICATION		į			\		1					
40.31 ACRES LAT. N32 1/31 br LONG. W103 94 55.1 Date 160.00 ACRES SURVEYOR CERTIFICATION	LOT	2 I				3151.	.8	3765.9		ON DRILLING SU	PT.	
160.00 ACRES SURVEYOR CERTIFICATION	· · ·		40.00 A	ACRES				LAX N32 1731.0	nue S/	26/05		
		i					1/ 1/2	2NG. 7V103*54'55.1	Date	4/55		
I hereby certify that the well lecation a						160.00	ACR	ES \	SURVEYO	OR CERTIFICAT	ION	
		1					1		1 4			
on this plat was plotted from field not act wil surveys made by me or und		1					İ		11	•	notes of under my	
LOT 3 40.00 ACRES supervisor, and that the same is tru	LOT:	3	40.00 A	ACRES			ļ		11 -		true and	
40.35 ACRES JULY 27, 2005	40.35 ACI	RES					1			ULY 27 2005		
Date Survey		ĺ										
		<u> </u>				160.00	ACR	es	Signature & Professional	Sal Telopo		

Surface casing to be set into the Rustler below all fresh water sands.


Production casing will be cemented using Zone Seal cement.

Drilling Procedure, BOP Diagram, Anticipated tops and surface plans attached.

This well is located outside the Secretary's Potash area and outside the R-111 Potash area. There are no potash leases within 1 mile of the location.

This well is an unorthodox location.

BEPCO, L.P., at P. O. Box 2760, Midland, TX, 79702 is a subsidiary of BEPCO, L.P., 201 Mail Street, Ft. Worth, TX, 76102. Bond No. NM 2204 (Nationwide).



EIGHT POINT DRILLING PROGRAM BASS ENTERPRISES PRODUCTION CO.

NAME OF WELL: Poker Lake Unit #250

LEGAL DESCRIPTION - SURFACE: 1400' FNL & 990' FEL, Section 30, T-24-S, R-30-E, Eddy County, New Mexico.

POINT 1: ESTIMATED FORMATION TOPS

(See No. 2 Below)

POINT 2: WATER, OIL, GAS AND/OR MINERAL BEARING FORMATIONS

Anticipated Formation Tops: KB 3178' (est)

GL 3161'

FORMATION	ESTIMATED TOP FROM KB	ESTIMATED SUBSEA TOP	BEARING
T/Rustler	Not Present		
T/Salt	361'	+2800'	Barren
T/Ramsey Sand	3419'	-268'	Oil/Gas
T/Lwr Brushy Canyon "8" A	6991'	-3830'	Oil/Gas
TD	7800'	-4639'	

POINT 3: CASING PROGRAM

TYPE	HOLE SIZE	<u>INTERVALS</u>	<u>PURPOSE</u>	CONDITION
16"	20"	0'- 40'	Conductor	Contractor Discretion
11-3/4", 42#,H-40, ST&C	14-3/4"	0'- 351'	Surface	New
8-5/8", 32#, J-55, LT&C	11"	0'- 3435'	Intermediate	New *
5-1/2", 15.5#, J-55, LT&C	7-7/8"	0' -6300'	Production	New
5-1/2", 17#, J-55, LT&C	7-7/8"	6300' -7800'	Production	New

^{*}If there is no flowing sand or Loss Circulation this string will not be run.

CASING DESIGN SAFETY FACTORS:

TYPE	<u>TENSION</u>	COLLAPSE	BURST
11-3/4", 42#, H-40, ST&C	20.83	6.37	5.64
8-5/8", 32#, J-55, LT&C	3.38	1.42	1.14
5-1/2", 15.5#, J-55, LT&C	1.77	1.29	1.37
5-1/2", 17#, J-55, LT&C	11.62	1.32	1.52

DESIGN CRITERIA AND CASING LOADING ASSUMPTIONS:

SURFACE CASING

Tension A 1.6 design factor utilizing the effects of buoyancy (9.2 ppg).

Collapse A 1.0 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the

casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

Burst

A 1.3 design factor with a surface pressure equal to the fracture gradient at setting depth less a gas gradient to the surface. Internal burst force at the shoe will be fracture pressure a that depth. Backup pressure will be formation pore pressure. In all cases a conservative fracture pressure will be used such that it represents the upper limit of potential fracture resistance up to a 1.0 psi/ft gradient. The effects of tension on burst will not be utilized.

PROTECTIVE CASING

Tension A 1.6 design factor utilizing the effects of buoyancy (10 ppg).

Collapse A 1.0 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the casing will be run (0.52 psi/ft). The effects of axial load on collapse will be considered.

In the case of development drilling, collapse design should be analyzed using internal evacuation equal to 1/3 the proposed total depth of the well. This criterion will be used when there is absolutely no potential of the protective string being used as a production casing string.

Burst A 1.0 surface design factor and a 1.3 downhole design factor with a surface pressure equivalent to the

fracture gradient at setting depth less a gas gradient to the surface. Internal burst force at the shoe will be fracture pressure at that depth. Back pressure will be formation pore pressure. In all cases a conservative fracture pressure will be used such that it represents the upper limit of potential fracture resistance up to a

1.0 psi/ft gradient.

PRODUCTION CASING

Tension A 1.6 design factor utilizing the effects of buoyancy (9.2 ppg).

Collapse A 1.0 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the

casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

Burst A 1.25 design factor with anticipated maximum tubing pressure (3731 psig) on top of the maximum

anticipated packer fluid gradient. Backup on production strings will be formation pore pressure. The

effects of tension on burst will not be utilized.


POINT 4: PRESSURE CONTROL EQUIPMENT (SEE ATTACHED DIAGRAM)

The blowout preventer equipment will be as shown in Diagram #2 and will consist of a double ram type preventer (3000 psi WP) and a bag type (Hydril) annular preventer (3000 psi WP). The same BOPE will be installed on the surface casinghead and will be on all subsequent casing strings. The BOP stack, choke, kill lines, kelly cocks, inside BOP, etc. when installed on the surface casinghead will be hydro-tested to 1000 psig by the independent tester. The BOPE when rigged up on the intermediate casing spool will be tested to 3000 psig by independent tester. (As per Onshore Oil & Gas Order No 2 – 3000 psig system) In addition to the high pressure test, a low pressure (200 psig) test will be required.

These tests will be performed:

- a) Upon installation
- b) After any component changes
- c) Fifteen days after a previous test
- d) As required by well conditions

A function test to insure that the preventers are operating correctly will be performed on each trip.



POINT 5: MUD PROGRAM

DEPTH	MUD TYPE	<u>WEIGHT</u>	_FV	PV_	YP_	FL	Ph
0' - 351'	FW Spud Mud	8.5 - 9.2	38-70	NC	NC	NC	10.0
351' - 3435'	Brine Water	9.8 -10.2	28-30	NC	NC	NC	9.5 - 10.5**
3435' - 6000'	FW	8.8 - 9.2	30-34	NC	NC	NC	9.5 – 10.5**
6000' - 6900'	FW/Starch	8.8 - 9.2	30-34	8	2	<100 cc	9.5 - 10.5**
6900' - TD	FW/Starch	8.8 - 9.2	30-34	8	2	<25 cc	9.5 - 10.5**

^{**} If there is no intermediate casing set @ 3380', the drilling fluid will be 10 ppg BW to 5600' where it will be converted to BW/Diesel with properties as follows: 8.8 – 9 ppg, 32 – 40 funnel secs vis, YP2, PV 8, FL 25 cc or less, Ph 9.5 – 10.

NOTE: May increase vis for logging purposes only.

POINT 6: TECHNICAL STAGES OF OPERATION

A) TESTING

None anticipated.

B) LOGGING

GR-CNL-LDT-AIT from TD to base of Salt (+/- 3300'). GR-CNL-CAL from base of Salt to surface.

C) CONVENTIONAL CORING

None anticipated.

D) CEMENT *

INTERVAL SURFACE:	AMOUNT SKS	FT OF FILL	ТҮРЕ	GALS/SK	<u>PPG</u>	FT ³ /SK
Tail 0' – 351' (100% excess circ to surface)	250	351	Class C + 2% S1	6.34	14.8	1.34
PRODUCTION: Stage 2 Lead 0 - 4900' (50% excess circ to surface)	1162	4900	50/50 Poz C + 10% D20 + 0.02% D46 + 0.125 pps D130 + 5% D44	14.71	11.9	2.50
Tail 4900' - 5000' (50% excess)	55	100	Class C + 1% D13	6.32	14.8	1.34
DV Tool @ ± 5000'						
Stage 1 Lead 5000' - 6000' (50% excess)	105	1000	CemCrete 39/31 + 2% D53 + 0.05 gps D604AM + 0.03 gps M45 + 2 pps D24 + 0.04 gps D801	9.88	10.2	2.47

INTERVAL Tail 6000' - 7800' (50% excess)	AMOUNT <u>SKS</u> 228	FT OF FILL 1800	TYPE CemCrete 39/31 + 2% D53 + 0.05 gps D604AM + 0.03 gps M45 + 2 pps D24 + 0.04 gps D801	<u>GALS/SK</u> 7.34	<u>PPG</u> 10.5	FT ³ /SK 2.10
* INTERMEDIATE (if re Lead 0' - 3185' (100% excess Circ to surface)	equired): 700	3185	50/50 Poz C + 10% D20 + 0.02% D46 + 0.125 pps D130 + 5% D44	14.71	11.9	2.50
Tail 3185' – 3435' (100% excess)	115	250	Class "C" + 1% CaCl ₂	6.34	14.8	1.34

E) DIRECTIONAL DRILLING

No directional services anticipated.

POINT 7: ANTICIPATED RESERVOIR CONDITIONS

Normal pressures are anticipated throughout Delaware section. A BHP of 3731 psi (max) or MWE of 8.7 ppg is expected. Lost circulation may exist in the Delaware Section from 3419-7200'. No H_sS is anticipated.

POINT 8: OTHER PERTINENT INFORMATION

A) Auxiliary Equipment

Upper and lower kelly cocks. Full opening stab in valve on the rig floor.

B) Anticipated Starting Date

Upon approval


12 days drilling operations

14 days completion operations

GEG/mac August 29, 2007

BEPCO, L. P. 3-M WP BOPE WITH 3-M WP ANNULAR

3 M CHOKE MANIFOLD EQUIPMENT-CONFIGURATION MAY VARY



THE FOLLOWING CONSTITUTE MINIMUM BLOWOUT PREVENTER REQUIREMENTS

- A. One double gate Blowout preventer with lower pipe rams and upper blind rams, all hydraulically controlled.
- B. Opening on preventers between rams to be flanged, studded or clamped and at least two inches in diameter.
- C. All connections from operating manifold to preventers to be all steel hose or tube a mininum of one inch in diameter.
- D. The available closing pressure shall be at least 15% in excess of that required with suffficient volume to operate (close, open, and re-close) the preventers.
- E. All connections to and from preventers to have a pressure rating equivalent to that of the BOPs.
- F. Manual controls to be installed before drilling cement plug.
- G. Valve to control flow through drill pipe to be located on rig floor.
- H. Chokes must be adjustable. Choke spool may be used between rams.

DIAGRAM 2

MULTI-POINT SURFACE USE PLAN

NAME OF WELL: Poker Lake Unit #250

LEGAL DESCRIPTION - SURFACE: 1400 FNL & 990' FEL, Section 30, T-24-S, R-30-E, Eddy County, New Mexico.

POINT 1: EXISTING ROADS

A) Proposed Well Site Location:

See Exhibit A and Survey Plats

B) Existing Roads:

From Carlsbad, New Mexico, go 8 miles south on Highway 285 to Highway 31. Turn north and go 7 miles on Highway 31. Turn east on Highway 128 and go 4 miles to Rawhide Road (located between mile markers 4 and 5). Go south for 10.2 miles stay on main road to second windmill, turn south for 0.3 miles, to road to Poker Lake Unit #238 then to proposed road to Poker Lake Unit #250.

C) Existing Road Maintenance or Improvement Plan:

See Exhibit B and Survey Plats.

POINT 2: NEW PLANNED ACCESS ROUTE

A) Route Location:

Approximately 750' of new road is required.

B) Width

12'

C) Maximum Grade

Grade to match existing topography or as per BLM requirements.

D) Turnout Ditches

Spaced per BLM requirements.

E) Culverts, Cattle Guards, and Surfacing Equipment

If required, culverts and cattle guards will be set per BLM Specs.

POINT 3: LOCATION OF EXISTING WELLS

Exhibit A indicates existing wells within the surrounding area.

A) No existing facilities are located within one mile which are owned or controlled by lessee/operator:

Closest Oil/Gas production facilities are located at Poker Lake Unit #213 wellsite. Poker Lake Unit #213 is located 1 ½ miles north of proposed well.

B) New Facilities in the Event of Production:

At this time the location of new production facilities have not been finalized. After drilling & completion of this well (Poker Lake Unit #250) a sundry notice will be submitted covering installation of production facilities and flowlines.

C) Rehabilitation of Disturbed Areas Unnecessary for Production:

Following flowline construction, those access areas required for continued production will be graded to provide drainage and minimize erosion. The areas unnecessary for use will be graded to blend in with the surrounding topography (see Point 10)

POINT 5: LOCATION AND TYPE OF WATER SUPPLY

A) Location and Type of Water Supply

Fresh water will be hauled from Johnson Station 50 miles east of Carlsbad, New Mexico or other commercial facilities. Brine water will be hauled from commercial facilities

B) Water Transportation System

Water hauling to the location will be over the existing and proposed roads.

POINT 6: SOURCE OF CONSTRUCTION MATERIALS

A) Materials

Exhibit B shows location of caliche source.

B) Land Ownership

Federally Owned.

C) Materials Foreign to the Site

No construction materials foreign to this area are anticipated for this drill site.

D) Access Roads

See Exhibit B.

POINT 7: METHODS FOR HANDLING WASTE MATERIAL

Page 3

A) Cuttings

Cuttings will be contained in the reserve pit.

B) Drilling Fluids

Drilling fluids will be contained in the reserve pit.

C) Produced Fluids

Water production will be contained in the reserve pit.

Hydrocarbon fluid or other fluids that may be produced during testing will be retained in test tanks. Prior to cleanup operations, any hydrocarbon material in the reserve pit will be removed by skimming or burning as the situation would dictate.

D) Sewage

Current laws and regulations pertaining to the disposal of human waste will be complied with.

E) Garbage

Portable containers will be utilized for garbage disposal during the drilling of this well.

F) Cleanup of Well Site

Upon release of the drilling rig, the surface of the drilling pad will be graded to accommodate a completion rig if electric log analysis indicate potential productive zones. The reserve pit will be fenced and bird netted. The fence will be maintained until the pit is backfilled. Reasonable cleanup will be performed prior to the final restoration of the site.

POINT 8: ANCILLARY FACILITIES

None required.

POINT 9: WELL SITE LAYOUT

A) Rig Orientation and Layout

Exhibit "D" shows the dimensions of the well pad and reserve pits, and the location of major rig components. Only minor leveling of the well site will be required. No significant cuts or fills will be necessary.

POINT 9: WELL SITE LAYOUT - Cont'd...

Page 4

B) Locations of Pits and Access Road

See Exhibits "B", "C" & "D".

C) Lining of the Pits

The reserve pit will be lined with plastic.

POINT 10: PLANS FOR RESTORATION OF THE SURFACE

A) Reserve Pit Cleanup

The pits will be fenced immediately after construction and shall be maintained until they are backfilled. Previous to backfill operations, any hydrocarbon material on the pits' surfaces shall be removed. The fluids and solids contained in the pits shall be backfilled with soil excavated from the site and soil adjacent to the reserve pits. The restored surface of the pits shall be contoured to prevent impoundment of surface water flow. Water-bars will be constructed as needed to prevent excessive erosion. Topsoil, as available, shall be placed over the restored surface in a uniform layer. The area will be seeded according to the Bureau of Land Management stipulations during the appropriate season following restoration.

B) Restoration Plans - Production Developed

The reserve pits will be backfilled and restored as described above under Item A. In addition, those areas not required for production will be graded to blend with the surrounding topography. Topsoil, as available, will be placed upon those areas and seeded. The portion of the site required for production will be graded to minimize erosion and provide access during inclement conditions. Following depletion and abandonment of the site, restoration procedures will be those that follow under Item C.

C) Restoration Plans - No Production Developed

The reserve pits will be restored as described above. With no production developed, the entire surface disturbed by construction of the well site will be restored. The site will be contoured to blend with the surrounding topography and provide drainage of surface water. The topsoil, as available, shall be replaced in a uniform layer and seeded according to the Bureau of Land Management's stipulations.

D) Rehabilitation's Timetable

Upon completion of drilling operations, the initial cleanup of the site will be performed as soon as weather and site conditions allow economic execution of the work.

POINT 11: OTHER INFORMATION

Page 5

A) Terrain

Relatively flat.

B) Soil

Caliche and sand.

C) Vegetation

Sparse, primarily grasses and mesquite with very little grass.

D) Surface Use

Primarily grazing.

E) Surface Water

There are no ponds, lakes, streams or rivers within several miles of the wellsite.

F) Water Wells

There is one water well located within 1 mile of the proposed well. This well is approximately 5000' North of the proposed well.

G) Residences and Buildings

None in the immediate vicinity.

H) Historical Sites

None observed.

I) Archeological Resources

An archeological survey will be obtained for this area. Before any construction begins, a full and complete archeological survey will be submitted to the Bureau of Land Management. Any location or construction conflicts will be resolved before construction begins.

J) Surface Ownership

The well site is on federally owned land.

- K) Well signs will be posted at the drilling site.
- L) Open Pits

All pits containing liquid or mud will be fenced and bird-netted.

POINT 12: OPERATOR'S FIELD REPRESENTATIVE

Page 6

(Field personnel responsible for compliance with development plan for surface use).

DRILLING

William R. Dannels

Box 2760

Midland, Texas 79702

(432) 683-2277

PRODUCTION

Mike Waygood

3104 East Green Street

Carlsbad, New Mexico 88220

(505) 887-7329

Michael L. Lyon

Box 2760

Midland, Texas 79702

(432) 683-2277

Date

GEG/mac

Gary E. Gerhard

OPERATOR CERTIFICATION

I hereby certify that I, or persons under my direct supervision have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in the plan are, to the best of my knowledge, true and correct; and that the work associated with operations proposed herein will be performed by BEPCO, L.P. and it's contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filling of a false statement.

8/29/07 Date Gary E. Gerhard

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 2 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (505) 361-2822

- 1. A Hydrogen Sulfide (H2S) Drilling Plan is N/A.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
- 3. When floor controls are required, (3M or Greater) controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

B. CASING

- 1. The 11.75 inch surface casing shall be set above the salt @ approximately 351 feet and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with a surface log readout will be used or a cement bond log shall be run to verify the top of the cement.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement).

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial action will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 8.625 inch contingency intermediate casing is:
 - Cement to surface. If cement does not circulate see B.1.a-d above.
- 3. The minimum required fill of cement behind the 5.5 inch production casing is:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office.
- 4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. The appropriate BLM office shall be notified a minimum of 2 hours in advance for a representative to witness the tests.
 - a. The tests shall be done by an independent service company.
 - b. The results of the test shall be reported to the appropriate BLM office.
 - c. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
 - d. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. HAZARDS

1. Our geologist has indicated that there is potential for lost circulation in the Delaware and the Bone Springs.

Engineering can be reached @ 505-706-2779 for variances.

FWright: 9/6/07 (date)