

OCD-ARTESIA

ATS-09-489

LM

# Split Estate

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

RECEIVED

OCT 13 2009

FORM APPROVED  
OMB No. 1004-0137  
Expires March 31, 2007

NM OCD ARTESIA

5 Lease Serial No  
NMNM-122617

6 If Indian, Allottee or Tribe Name

## APPLICATION FOR PERMIT TO DRILL OR REENTER

1a Type of work- <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		7 If Unit or CA Agreement, Name and No	
1b Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		8, Lease Name and Well No. Tamano Federal #1	
2 Name of Operator Mack Energy Corporation		9 API Well No. 30-015-37321	
3a Address P.O. Box 960 Artesia, NM 88211-0960		3b Phone No. (include area code) (575)748-1288	
10 Field and Pool, or Exploratory Maljamar; Grayburg San Andres		11 Sec, T R M or Blk and Survey or Area Sec. 35 T17S R31E	
4 Location of Well (Report location clearly and in accordance with any State requirements*) At surface 1278 FSL & 200 FWL, Sec. 36 T17S R31E At proposed prod zone 355 FSL & 330 FWL, Sec. 35 T17S R31E		12 County or Parish Eddy	
14. Distance in miles and direction from nearest town or post office* 8 miles east of Loco Hills, NM		13 State NM	
15. Distance from proposed* location to nearest property or lease line, ft (Also to nearest drlg unit line, if any) 200		16 No. of acres in lease 640	
18 Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft 50'		20 BLM/BIA Bond No on file NMB000286	
21 Elevations (Show whether DF, KDB, RT, GL, etc ) 3810' GR		22 Approximate date work will start* 9/10/09	
		23 Estimated duration 20 days	

## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form

- |  |   |
|--|---|
| 1 Well plat certified by a registered surveyor   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above),   |
| 2 A Drilling Plan  | 5 Operator certification  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office) | 6 Such other site specific information and/or plans as may be required by the authorized officer. |

25 Signature <i>Jerry W. Sherrell</i>	Name (Printed/Typed) Jerry W. Sherrell	Date 8/10/09
Title Production Clerk		
Approved by (Signature) <i>/s/ Don Peterson</i>	Name (Printed/Typed)	Date <b>OCT 2 2009</b>
Title <b>FIELD MANAGER</b>	Office <b>CARLSBAD FIELD OFFICE</b>	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon  
Conditions of approval, if any, are attached

**APPROVAL FOR TWO YEARS**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction

\*(Instructions on page 2)

Well becomes Orthodox @ 4,400' MD & 4,152' TVD

Roswell Controlled Water Basin

Approval Subject to General Requirements  
& Special Stipulations Attached

SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

OCD Artesia

FORM APPROVED  
Budget Bureau No 1004-0135  
Expires March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals

**SUBMIT IN TRIPLICATE**

1 Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		5 Lease Designation and Serial No <b>NMNM-122617</b>
2 Name of Operator <b>Mack Energy Corporation</b>		6 If Indian, Allottee or Tribe Name
3 Address and Telephone No <b>P.O. Box 960 Artesia, NM 88211-0960 (575)748-1288</b>		7 If Unit or CA, Agreement Designation
4 Location of Well (Footage, Sec, T R, M or Survey Description) <b>SL 1250 FSL &amp; 200 FWL, Sec. 36 T17S R31E BHL 355 FSL &amp; 330 FWL, Sec. 35 T17S R31E</b>		8 Well Name and No <b>Tamano Federal #1</b>
		9 API Well No
		10 Field and Pool, or Exploratory Area <b>Maljamar; Grayburg-San Andres</b>
		11 County or Parish, State <b>Eddy, NM</b>

**12 CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> Other <b>Move Location</b>
	<input checked="" type="checkbox"/> Change of Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

13 Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)\*

Mack Energy Corporation proposes to move the surface location for this well from 1120 FSL & 200 FWL Sec. 36 T17S R31E, 130' north. The new footages for this location are 1250 FSL & 200 FWL Sec. 36 T17S R31E.

14 I hereby certify that the foregoing is true and correct

Signed *Don Peterson* Title Production Clerk Date 9/16/09

(This space for Federal or State office use)

Approved by /s/ Don Peterson Title FIELD MANAGER Date OCT 2 2009

Conditions of approval, if any

**CARLSBAD FIELD OFFICE**

Title 18 U S C Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction

\*See Instruction on Reverse Side

DISTRICT I  
1625 N. FRENCH DR., HOBBS, NM 88240

DISTRICT II  
1301 W. GRAND AVENUE, ARTESIA, NM 88210

DISTRICT III  
1000 RIO BRAZOS RD., AZTEC, NM 87410

DISTRICT IV  
11885 S. ST. FRANCIS DR., SANTA FE, NM 87505

State of New Mexico  
Energy, Minerals and Natural Resources Department

OIL CONSERVATION DIVISION  
11885 SOUTH ST. FRANCIS DR.  
Santa Fe, New Mexico 87505

Form C-102  
Revised October 12, 2005  
Submit to Appropriate District Office  
State Lease - 4 Copies  
Fee Lease - 3 Copies

WELL LOCATION AND ACREAGE DEDICATION PLAT

☐ AMENDED REPORT

API Number <b>30-015-37321</b>	Pool Code <b>43329</b> ✓	Pool Name <b>Maljamar; Grayburg-San Andres</b> ✓
Property Code <b>37871</b>	Property Name <b>TAMANO FEDERAL</b>	Well Number <b>1</b>
OGRID No. <b>013837</b>	Operator Name <b>MACK ENERGY CORPORATION</b>	Elevation <b>3815'</b>


Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	36	17-S	31-E		1250	SOUTH	200	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	35	17-S	31-E		355	SOUTH	330	WEST	EDDY
Dedicated Acres <b>160</b>	Joint or Infill	Consolidation Code	Order No.						

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED  
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



OPERATOR CERTIFICATION

I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division

*Jerry W. Sherrell* 9/16/09  
Signature Date

Jerry W. Sherrell  
Printed Name


SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

*Ronald J. Eidson* 9-15-09  
Date Surveyed 3239  
Signature & Seal of Professional Surveyor  
RONALD J. EIDSON  
SEPTEMBER 30 2009  
LA  
09.11.0783


Certificate No. GARY G. EIDSON 12641  
RONALD J. EIDSON 3239

**SECTION 36, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.**  
 EDDY COUNTY NEW MEXICO



**DIRECTIONS TO LOCATION**

FROM THE INTERSECTION OF U.S. HWY #82 AND ST. HWY. #529 (BERMUDA RD.), GO SOUTHEAST APPROX. 3.8 MILES ON ST. HWY. #529. TURN RIGHT AND GO SOUTH APPROX. 0.65 MILES. TURN RIGHT AND GO WEST APPROX. 1.0 MILE TO THE CONCHO ANTELOPE ST. #6 WELL PAD. THIS LOCATION IS APPROX. 350 FEET SOUTHWEST.




PROVIDING SURVEYING SERVICES  
 SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
 412 N. DAL PASO  
 HOBBS, N.M. 88240  
 (575) 393-3117

**MACK ENERGY CORPORATION**

TAMANO FEDERAL #1 WELL  
 LOCATED 1250 FEET FROM THE SOUTH LINE  
 AND 200 FEET FROM THE WEST LINE OF SECTION 36,  
 TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.,  
 EDDY COUNTY, NEW MEXICO

Survey Date: 9/3/09	Sheet 1 of 1 Sheets
W.O. Number: 09.11.0783	Dr By: LA
Date: 9/14/09	09110783
	Scale: 1"=100'

# VICINITY MAP



SCALE: 1" = 2 MILES

SEC. 36 TWP. 17-S RGE. 31-E

SURVEY N.M.P.M.


COUNTY EDDY STATE NEW MEXICO

DESCRIPTION 1250' FSL & 200' FWL


ELEVATION 3815'

OPERATOR MACK ENERGY CORPORATION

LEASE TAMANO FEDERAL



# LOCATION VERIFICATION MAP



SCALE: 1" = 2000'

CONTOUR INTERVAL:  
MALJAMAR, N.M. - 10'

SEC. 36 TWP. 17-S RGE. 31-E

SURVEY \_\_\_\_\_ N.M.P.M.

COUNTY EDDY STATE NEW MEXICO


DESCRIPTION 1250' FSL & 200' FWL

ELEVATION 3815'

OPERATOR MACK ENERGY CORPORATION

LEASE TAMANO FEDERAL

U.S.G.S. TOPOGRAPHIC MAP  
MALJAMAR, N.M.



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
Budget Bureau No 1004-0135  
Expires March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals

**SUBMIT IN TRIPLICATE**

1 Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2 Name of Operator

Mack Energy Corporation

3 Address and Telephone No

P.O. Box 960 Artesia, NM 88211-0960 (575)748-1288

4 Location of Well (Footage, Sec, T, R, M or Survey Description)

SL 1250 FSL & 200 FWL, Sec. 36 T17S R31E  
BHL 355 FSL & 330 FWL, Sec. 35 T17S R31E

5 Lease Designation and Serial No

NMNM-122617

6 If Indian, Allottee or Tribe Name

7 If Unit or CA, Agreement Designation

8 Well Name and No

Tamano Federal #1

9 API Well No

10 Field and Pool, or Exploratory Area

Maljamar; Grayburg-San Andres

11 County or Parish, State

Eddy, NM

12 CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent  
☐ Subsequent Report  
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment  
☐ Recompletion  
☐ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☒ Other Reclamation Variance

☒ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form)

13 Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)\*

Mack Energy Corporation is requesting a variance for future reclamation of this well site. The surface location for this well are 1250 FSL & 200 FWL Sec. 36 T17S R31E. The north edge of this location will be built over an existing reserve pit area for the Antelope State #6.

We are requesting approval to leave caliche in place that will be covering the existing pit area, during interim and final reclamation of this location. This is clearly outlined on attached plat.

14 I hereby certify that the foregoing is true and correct

Signed

*Garry A. Sherrill*

Title

Production Clerk

Date

9/16/09

(This space for Federal or State office use)

Approved by

*/s/ James A. Amos*

for

Title

FIELD MANAGER

Date

SEP 29 2009

Conditions of approval, if any

CARLSBAD FIELD OFFICE

Title 18 U S C Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction

\*See Instruction on Reverse Side

DISTRICT I  
1625 N. FRENCH DR., HOBBS, NM 88240

DISTRICT II  
1301 W. GRAND AVENUE, ARTESIA, NM 88210

DISTRICT III  
1000 RIO BRAZOS RD., AZTEC, NM 87410

DISTRICT IV  
11885 S. ST. FRANCIS DR., SANTA FE, NM 87505

State of New Mexico  
Energy, Minerals and Natural Resources Department

OIL CONSERVATION DIVISION  
11885 SOUTH ST. FRANCIS DR.  
Santa Fe, New Mexico 87505

Form C-102

Revised October 12, 2005

Submit to Appropriate District Office

State Lease - 4 Copies

Fee Lease - 3 Copies

WELL LOCATION AND ACREAGE DEDICATION PLAT

☐ AMENDED REPORT

API Number	Pool Code 43329	Pool Name Maljamar; Grayburg-San Andres
Property Code	Property Name TAMANO FEDERAL	Well Number 1
OGRID No. 013837	Operator Name MACK ENERGY CORPORATION	Elevation 3815'

Surface Location


UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	36	17-S	31-E		1250	SOUTH	200	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	35	17-S	31-E		355	SOUTH	330	WEST	EDDY

Dedicated Acres 160	Joint or Infill	Consolidation Code	Order No.
------------------------	-----------------	--------------------	-----------

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED  
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



OPERATOR CERTIFICATION

I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division

*Jerry W. Sherrell* 9/16/09  
Signature Date

Jerry W. Sherrell  
Printed Name

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

*Ronald J. Eidson* 9-15-09  
Date Surveyed 9-15-09  
Signature & Seal of Professional Surveyor  
09.11.0783


Certificate No. GARY G. EIDSON 12641  
RONALD J. EIDSON 3239



# SECTION 36, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.


EDDY COUNTY


NEW MEXICO



## DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF U.S. HWY. #82 AND ST. HWY. #529 (BERMUDA RD.), GO SOUTHEAST APPROX. 3.8 MILES ON ST. HWY. #529. TURN RIGHT AND GO SOUTH APPROX. 0.65 MILES. TURN RIGHT AND GO WEST APPROX. 1.0 MILE TO THE CONCHO ANTELOPE ST. #6 WELL PAD. THIS LOCATION IS APPROX. 350 FEET SOUTHWEST.





PROVIDING SURVEYING SERVICES  
SINCE 1946


**JOHN WEST SURVEYING COMPANY**

412 N. DAL PASO  
HOBBS, N.M. 88240  
(575) 393-3117

## MACK ENERGY CORPORATION


TAMANO FEDERAL #1 WELL  
LOCATED 1250 FEET FROM THE SOUTH LINE  
AND 200 FEET FROM THE WEST LINE OF SECTION 36,  
TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO

Survey Date. 9/3/09	Sheet 1 of 1 Sheets
W.O. Number: 09.11.0783	Dr By: LA
Date 9/14/09	09110783
	Scale: 1"=100'



PROVIDING SURVEYING SERVICES  
SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
412 N. DAL PASO  
HOBBS, N.M. 88240  
(575) 393-3117

# LOCATION VERIFICATION MAP



SCALE: 1" = 2000'

CONTOUR INTERVAL:  
MALJAMAR, N.M. - 10'

SEC. 36 TWP. 17-S RGE. 31-E

SURVEY N.M.P.M.

COUNTY EDDY STATE NEW MEXICO


DESCRIPTION 1250' FSL & 200' FWL

ELEVATION 3815'

OPERATOR MACK ENERGY CORPORATION

LEASE TAMANO FEDERAL

U.S.G.S. TOPOGRAPHIC MAP  
MALJAMAR, N.M.



## DRILLING PROGRAM

### 1. Geologic Name of Surface Formation

Quaternary

### 2. Estimated Tops of Important Geologic Markers:

Yates	2195'
Queen	2250'
San Andres	4175'
Delaware	5600'

### 3. Estimated Depths of Anticipated Fresh Water, Oil and Gas:

Water Sand	150'	Fresh Water
Grayburg	3650'	Oil/Gas
San Andres	4175'	Oil/Gas
Delaware	5600'	Oil/Gas

No other formations are expected to give up oil, gas or fresh water in measurable quantities. Setting 13 3/8" casing to ~~800'~~ and circulating cement back to surface will protect the surface fresh water sand. Salt Section will be protected by setting 9 5/8" casing to 2200' and circulating cement back to surface. Any shallower zones above TD, which contain commercial quantities of oil and/or gas, will have cement circulated across them by cementing 7" casing @ 4200', sufficient cement will be pumped back to surface.

### 4. Casing Program: See COA

Hole Size	Interval	OD Casing	Wt, Grade, Jt, cond, collapse/burst/tension
	950'		
17 1/2"	0- <del>800'</del>	13 3/8"	48#, H-40, ST&C, New, 1.892/3.295/3.460
12 1/4"	0-2200'	9 5/8"	36#, J-55, ST&C, New, 1.731/11.733/11.733
8 3/4"	0-4250'	7"	26# HCP-110,LT&C,New, 3.460/33.167/33.167
6 1/8"	3100-9010'	4 1/2"	11.6# HCP-110,LT&C,New, 1.946/3.509/3.563

### 5. Cement Program: See COA

13 3/8" Surface Casing: Class C, Lead 600sx, 11.8#, yield 2.46 tail 200sx, 14.8#, yield 1.34  
9 5/8" Intermediate Casing: Class C, lead 500sx 11.8#, yield 2.46, tail 200sx, 14.8# yield 1.34  
7" Intermediate Casing: Class C, lead 250sx, 11.8#, yield 2.46, tail 200sx, 14.8#, yield 1.34.  
4 1/2" Production Casing: Liner hanger @ 3100' set with Peak isolation packers.

### 6. Minimum Specifications for Pressure Control:

The blowout preventer equipment (BOP) shown in Exhibit #9 will consist of a double ram-type (3000 psi WP) minimum preventer. This unit will be hydraulically operated and the ram type preventer will be equipped with blind rams on top of 4 1/2" drill pipe rams on bottom. ~~The BOP will be nipped up on the 13 3/8" surface casing and tested to 1000~~ *See COA* ~~psi using the rig pump and used continuously until TD is reached.~~ All BOP's and accessory equipment will be tested to 2000 psi before drilling out of intermediate casing. Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment (Exhibit #10) will include a Kelly cock and floor safety valve and choke lines and choke manifold (Exhibit #11) with a minimum 3000 psi WP rating.

**7. Types and Characteristics of the Proposed Mud System:**

The well will be drilled to TD with a combination of brine, cut brine and polymer mud system. The applicable depths and properties of this system are as follows:

*See COA*

DEPTH	TYPE	WEIGHT	VISCOSITY	WATERLOSS
0- <del>800</del> <i>950</i> '	Fresh Water	9.4	28	N.C.
<del>800</del> -2200'	Brine	10.2	30	N.C.
2200'-TD	Cut Brine	9.5	29	N.C.

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept at the well site at all times.

**8. Auxiliary Well Control and Monitoring Equipment:**

- A. Kelly cock will be kept in the drill string at all times.
- B. A full opening drill pipe-stabbing valve with proper drill pipe connections will be on the rig floor at all times.

**9. Logging, Testing and Coring Program: *See COA***

- A. The electric logging program will consist of GR-Dual Laterolog, Spectral Density, Dual Spaced Neutron, CSNG Log from T.D. to 9 5/8 casing shoe.
- B. Drill Stem test is not anticipated.
- C. No conventional coring is anticipated.
- D. Further testing procedures will be determined at TD.

**10. Abnormal Conditions, Pressures, Temperatures and Potential Hazards:**


No abnormal pressures or temperatures are anticipated. The estimated bottom hole at TD is 120 degrees and estimated maximum bottom hole pressure is 2100 psig. Low levels of Hydrogen sulfide have been monitors in producing wells in the area, so H2S may be present while drilling of the well; a plan is attached to the Drilling program. No major loss of circulation zones has been reported in offsetting wells.

**11. Anticipated Starting Date and Duration of Operations:**

Road and location work will not begin until approval has been received from the BLM. The anticipated spud date is September 10, 2009. Once commenced, the drilling operation should be finished in approximately 20 days. If the well is productive, an additional 30 days will be required for completion and testing before a decision is made to install permanent facilities.

**1. Well Site Layout:**

- A. The drill pad layout, with elevations staked by John West Engineering, is shown in Exhibit #6. Dimensions of the pad are shown. Topsoil, if available, will be stockpiled per BLM specifications. Because the pad is almost level no major cuts will be required.
- B. Diagram below shows the proposed orientation of the location. No permanent living facilities are planned, but a temporary foreman/toolpusher's trailer will be on location during the drilling operations.



*Exhibit #6*



## **Mack Energy**

Eddy County

Tamano Federal

#1H

OH

Plan: Plan #2

## **Pathfinder X & Y Planning Report**

07 August, 2009

# **PATHFINDER**



# Pathfinder Energy Services

## Pathfinder X & Y Planning Report



**Company:** Mack Energy  
**Project:** Eddy County  
**Site:** Tamano Federal  
**Well:** #1H  
**Wellbore:** OH  
**Design:** Plan #2

**Local Co-ordinate Reference:** Well #1H  
**TVD Reference:** WELL @ 3828.00ft (18' KB)  
**MD Reference:** WELL @ 3828.00ft (18' KB)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Database:** Midland Database

**Project:** Eddy County

**Map System:** US State Plane 1927 (Exact solution)  
**Geo Datum:** NAD 1927 (NADCON CONUS)  
**Map Zone:** New Mexico East 3001

**System Datum:** Mean Sea Level

**Site:** Tamano Federal

<b>Site Position:</b>	<b>Map</b>	<b>Northing:</b>	650,324.300 ft	<b>Latitude:</b>	32° 47' 12.562 N
<b>From:</b>		<b>Easting:</b>	654,535.000 ft	<b>Longitude:</b>	103° 49' 49.750 W
<b>Position Uncertainty:</b>	0 00 ft	<b>Slot Radius:</b>	"	<b>Grid Convergence:</b>	0.27 °

**Well:** #1H

<b>Well Position</b>	<b>+N-S</b>	0 00 ft	<b>Northing:</b>	650,324.300 ft	<b>Latitude:</b>	32° 47' 12.562 N
	<b>+E-W</b>	0.00 ft	<b>Easting:</b>	654,535.000 ft	<b>Longitude:</b>	103° 49' 49.750 W
<b>Position Uncertainty</b>		0 00 ft	<b>Wellhead Elevation:</b>	ft	<b>Ground Level:</b>	3 810 00 ft

**Wellbore:** OH

<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination</b> (°)	<b>Dip Angle</b> (°)	<b>Field Strength</b> (nT)
	IGRF200510	08/06/2009	7 96	60 72	49,138

**Design:** Plan #2

**Audit Notes:**

**Version:** **Phase:** -PLAN **Tie On Depth:** 0.00

<b>Vertical Section:</b>	<b>Depth From (TVD)</b> (ft)	<b>+N-S</b> (ft)	<b>+E-W</b> (ft)	<b>Direction</b> (°)
	0.00	0.00	0 00	261.15

**Survey Tool Program** Date 08/07/2009

<b>From</b> (ft)	<b>To</b> (ft)	<b>Survey (Wellbore)</b>	<b>Tool Name</b>	<b>Description</b>
0 00	9,010 23	Plan #2 (OH)	MWD	MWD - Standard





# Pathfinder Energy Services

## Pathfinder X & Y Planning Report



Company: Mack Energy  
Project: Eddy County  
Site: Tamano Federal  
Well: #1H  
Wellbore: OH  
Design: Plan #2

Local Co-ordinate Reference: Well #1H  
TVD Reference: WELL @ 3828.00ft (18' KB)  
MD Reference: WELL @ 3828.00ft (18' KB)  
North Reference: Grd  
Survey Calculation Method: Minimum Curvature  
Database: Midland Database

### Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
0.00	0 00	0.00	0.00	-3,828.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
100.00	0 00	0.00	100.00	-3,728.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
200.00	0 00	0.00	200.00	-3,628.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
300.00	0 00	0.00	300.00	-3,528.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
400.00	0.00	0.00	400.00	-3,428.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
500.00	0 00	0.00	500.00	-3,328.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
600.00	0 00	0.00	600.00	-3,228.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
700.00	0 00	0.00	700.00	-3,128.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
800.00	0.00	0.00	800.00	-3,028.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
900.00	0.00	0.00	900.00	-2,928.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
1,000.00	0 00	0.00	1,000.00	-2,828.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
1,100.00	0.00	0.00	1,100.00	-2,728.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
1,200.00	0 00	0.00	1,200.00	-2,628.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
1,300.00	0.00	0.00	1,300.00	-2,528.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
1,400.00	0 00	0.00	1,400.00	-2,428.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
1,500.00	0 00	0.00	1,500.00	-2,328.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
1,600.00	0.00	0.00	1,600.00	-2,228.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
1,700.00	0.00	0.00	1,700.00	-2,128.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
1,800.00	0.00	0.00	1,800.00	-2,028.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
1,900.00	0 00	0.00	1,900.00	-1,928.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
2,000.00	0 00	0.00	2,000.00	-1,828.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
2,100.00	0 00	0.00	2,100.00	-1,728.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
2,200.00	0.00	0.00	2,200.00	-1,628.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
2,300.00	0.00	0.00	2,300.00	-1,528.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
2,400.00	0.00	0.00	2,400.00	-1,428.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
2,500.00	0 00	0.00	2,500.00	-1,328.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
2,600.00	0.00	0.00	2,600.00	-1,228.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00



# Pathfinder Energy Services

## Pathfinder X & Y Planning Report



Company: Mack Energy  
Project: Eddy County  
Site: Tamano Federal  
Well: #1H  
Wellbore: OH  
Design: Plan #2

Local Co-ordinate Reference: Well #1H  
TVD Reference: WELL @ 3828.00ft (18' KB)  
MD Reference: WELL @ 3828.00ft (18' KB)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Database: Midland Database

### Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
2,700.00	0.00	0.00	2,700.00	-1,128.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
2,800.00	0.00	0.00	2,800.00	-1,028.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
2,900.00	0.00	0.00	2,900.00	-928.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
3,000.00	0.00	0.00	3,000.00	-828.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
3,100.00	0.00	0.00	3,100.00	-728.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
3,179.00	0.00	0.00	3,179.00	-649.00	0.00	0.00	0.00	0.00	650,324.30	654,535.00
KOP-3179.00°MD,0.00°INC,0.00°AZI,3179.00°TVD										
3,200.00	1.12	254.00	3,200.00	-628.00	-0.06	-0.20	0.20	5.35	650,324.24	654,534.80
3,300.00	6.47	254.00	3,299.74	-528.26	-1.88	-6.56	6.77	5.35	650,322.42	654,528.44
3,400.00	11.82	254.00	3,398.43	-429.57	-6.26	-21.84	22.54	5.35	650,318.04	654,513.16
3,500.00	17.17	254.00	3,495.22	-332.78	-13.16	-45.90	47.38	5.35	650,311.14	654,489.10
3,600.00	22.52	254.00	3,589.24	-238.76	-22.52	-78.52	81.05	5.35	650,301.78	654,456.48
3,700.00	27.87	254.00	3,679.69	-148.31	-34.25	-119.43	123.28	5.35	650,290.05	654,415.57
3,800.00	33.22	254.00	3,765.78	-62.22	-48.25	-168.27	173.69	5.35	650,276.05	654,366.73
3,900.00	38.57	254.00	3,846.76	18.76	-64.41	-224.61	231.85	5.35	650,259.89	654,310.39
4,000.00	43.92	254.00	3,921.92	93.92	-82.57	-287.96	297.24	5.35	650,241.73	654,247.04
4,100.00	49.27	254.00	3,990.61	162.61	-102.59	-357.78	369.30	5.35	650,221.71	654,177.22
4,200.00	54.62	254.00	4,052.23	224.23	-124.29	-433.44	447.40	5.35	650,200.01	654,101.56
4,300.00	59.97	254.00	4,106.24	278.24	-147.47	-514.30	530.87	5.35	650,176.83	654,020.70
4,400.00	65.32	254.00	4,152.17	324.17	-171.95	-599.65	618.96	5.35	650,152.35	653,935.35
4,500.00	70.67	254.00	4,189.63	361.63	-197.49	-688.74	710.93	5.35	650,126.81	653,846.26
4,600.00	76.02	254.00	4,218.28	390.28	-223.89	-780.80	805.95	5.35	650,100.41	653,754.20
4,700.00	81.37	254.00	4,237.87	409.87	-250.91	-875.02	903.21	5.35	650,073.39	653,659.98
4,800.00	86.72	254.00	4,248.24	420.24	-278.31	-970.60	1,001.86	5.35	650,045.99	653,564.40
4,861.32	90.00	254.00	4,250.00	422.00	-295.21	-1,029.51	1,062.68	5.35	650,029.09	653,505.49
EOC-4861.32°MD,90.00°INC,254.00°AZI,4250.00°TVD,5.35°DLS, 1062.68°VS, -295.21°N, -1029.51°E										
4,900.00	90.00	254.77	4,250.00	422.00	-305.62	-1,066.76	1,101.09	2.00	650,018.68	653,468.24



# Pathfinder Energy Services

## Pathfinder X & Y Planning Report



Company: Mack Energy  
Project: Eddy County  
Site: Tamano Federal  
Well: #1H  
Wellbore: OH  
Design: Plan #2

Local Co-ordinate Reference: Well #1H  
TVD Reference: WELL @ 3828.00ft (18' KB)  
MD Reference: WELL @ 3828.00ft (18' KB)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Database: Midland Database

### Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
5,000.00	90.00	256.77	4,250.00	422.00	-330.19	-1,163.69	1,200.64	2.00	649,994.11	653,371.31
5,100.00	90.00	258.77	4,250.00	422.00	-351.37	-1,261.42	1,300.46	2.00	649,972.93	653,273.58
5,200.00	90.00	260.77	4,250.00	422.00	-369.12	-1,359.82	1,400.43	2.00	649,955.18	653,175.18
5,300.00	90.00	262.77	4,250.00	422.00	-383.43	-1,458.79	1,500.42	2.00	649,940.87	653,076.21
5,338.10	90.00	263.54	4,250.00	422.00	-387.97	-1,496.62	1,538.50	2.00	649,936.33	653,038.38
5,400.00	90.00	263.54	4,250.00	422.00	-394.94	-1,558.12	1,600.34	0.00	649,929.36	652,976.88
5,500.00	90.00	263.54	4,250.00	422.00	-406.20	-1,657.49	1,700.25	0.00	649,918.10	652,877.51
5,600.00	90.00	263.54	4,250.00	422.00	-417.46	-1,756.85	1,800.17	0.00	649,906.84	652,778.15
5,700.00	90.00	263.54	4,250.00	422.00	-428.71	-1,856.22	1,900.08	0.00	649,895.59	652,678.78
5,800.00	90.00	263.54	4,250.00	422.00	-439.97	-1,955.58	1,999.99	0.00	649,884.33	652,579.42
5,900.00	90.00	263.54	4,250.00	422.00	-451.23	-2,054.94	2,099.91	0.00	649,873.07	652,480.06
6,000.00	90.00	263.54	4,250.00	422.00	-462.49	-2,154.31	2,199.82	0.00	649,861.81	652,380.69
6,100.00	90.00	263.54	4,250.00	422.00	-473.75	-2,253.67	2,299.73	0.00	649,850.55	652,281.33
6,200.00	90.00	263.54	4,250.00	422.00	-485.01	-2,353.04	2,399.65	0.00	649,839.29	652,181.96
6,300.00	90.00	263.54	4,250.00	422.00	-496.27	-2,452.40	2,499.56	0.00	649,828.03	652,082.60
6,400.00	90.00	263.54	4,250.00	422.00	-507.52	-2,551.77	2,599.47	0.00	649,816.78	651,983.23
6,500.00	90.00	263.54	4,250.00	422.00	-518.78	-2,651.13	2,699.39	0.00	649,805.52	651,883.87
6,600.00	90.00	263.54	4,250.00	422.00	-530.04	-2,750.49	2,799.30	0.00	649,794.26	651,784.51
6,700.00	90.00	263.54	4,250.00	422.00	-541.30	-2,849.86	2,899.21	0.00	649,783.00	651,685.14
6,800.00	90.00	263.54	4,250.00	422.00	-552.56	-2,949.22	2,999.12	0.00	649,771.74	651,585.78
6,900.00	90.00	263.54	4,250.00	422.00	-563.82	-3,048.59	3,099.04	0.00	649,760.48	651,486.41
7,000.00	90.00	263.54	4,250.00	422.00	-575.08	-3,147.95	3,198.95	0.00	649,749.22	651,387.05
7,100.00	90.00	263.54	4,250.00	422.00	-586.34	-3,247.31	3,298.86	0.00	649,737.96	651,287.69
7,200.00	90.00	263.54	4,250.00	422.00	-597.59	-3,346.68	3,398.78	0.00	649,726.71	651,188.32
7,300.00	90.00	263.54	4,250.00	422.00	-608.85	-3,446.04	3,498.69	0.00	649,715.45	651,088.96
7,400.00	90.00	263.54	4,250.00	422.00	-620.11	-3,545.41	3,598.60	0.00	649,704.19	650,989.59
7,500.00	90.00	263.54	4,250.00	422.00	-631.37	-3,644.77	3,698.52	0.00	649,692.93	650,890.23



# Pathfinder Energy Services

## Pathfinder X & Y Planning Report



Company: Mack Energy  
Project: Eddy County  
Site: Tamano Federal  
Well: #1H  
Wellbore: OH  
Design: Plan #2

Local Co-ordinate Reference: Well #1H  
TVD Reference: WELL @ 3828.00ft (18' KB)  
MD Reference: WELL @ 3828.00ft (18' KB)  
North Reference: Grd  
Survey Calculation Method: Minimum Curvature  
Database: Midland Database

### Targets

#### Target Name

- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)		
PBHL(Tamano#1H)	0 00	0 00	4,250.00	-801.40	-5,145.40	649,522.900	649,389.600	32° 47' 4.870 N	103° 50' 50.066 W
- plan hits target									
- Point									

### Casing Points

Measured Depth	Vertical Depth	Name	Casing Diameter	Hole Diameter
(ft)	(ft)		(")	(")
4,328.14	4,120.00	7"	7	8-3/4

### Plan Annotations

Measured Depth	Vertical Depth	Local Coordinates		Comment
(ft)	(ft)	+N/-S	+E/-W	
(ft)	(ft)	(ft)	(ft)	
3,179.00	3,179.00	0.00	0.00	KOP-3179.00'MD,0.00°INC,0.00°AZI,3179.00'TVD
4,861.32	4,250.00	-295.21	-1,029.51	EOC-4861.32'MD,90.00°INC,254.00°AZI,4250.00'TVD,5.35°DLS, 1062
9,010.23	4,250.00	-801.40	-5,145.40	BHL-9010.23'MD,90.00°INC,263.54°AZI, 4250.00'TVD, 5207.43°VS, -81

Checked By: \_\_\_\_\_ Approved By: \_\_\_\_\_ Date: \_\_\_\_\_



Project: Eddy County  
Site: Tamano Federal  
Well: #1H  
Wellbore: OH  
Plan: Plan #2 (#1H/OH)



Azimuths to Grid North  
True North: -0.27°  
Magnetic North: 7.69°

Magnetic Field  
Strength 49138.0snT  
Dip Angle 60.72°  
Date: 08/06/2009  
Model: IGRF200510





PROJECT DETAILS Eddy County  
Geodetic System: US State Plane 1927 (Exact solution)  
Datum: NAD 1927 (NADCON CONUS)  
Ellipsoid: Clarke 1866  
Zone: New Mexico East 3001  
System Datum: Mean Sea Level  
Local North: Grid

WELL DETAILS #1H						
Ground Elevation 3810.00						
RKB Elevation WELL @ 3828.00R (18' KB)						
Rig Name 18' KB						
+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Slot
0.00	0.00	650324.300	654535.000	32° 47' 12.562 N	103° 49' 49.750 W	

SECTION DETAILS									
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec Target
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2	3179.00	0.00	0.00	3179.00	0.00	0.00	0.00	0.00	0.00
3	4861.32	90.00	254.00	4250.00	-295.21	-1029.51	5.35	254.00	1062.68
4	5338.10	90.00	263.54	4250.00	-387.97	-1496.62	2.00	90.00	1538.50
5	9010.23	90.00	263.54	4250.00	-801.40	-5145.40	0.00	0.00	5207.44 PBHL(Tamano#1H)

WELLBORE TARGET DETAILS				
Name	TVD	+N/-S	+E/-W	Shape
PBHL(Tamano#1H)	4250.00	-801.40	-5145.40	Point

West(-)/East(+) (200 ft/in)



Plan Plan #2 (#1H/OH)			
Created By	Nate Bingham	Date	13 10, August 07 2009
Checked		Date	

Attached to Form 3160-3  
Mack Energy Corporation  
Tamano Federal #1  
SL 1120 FSL & 200 FWL, Unit M, Sec. 36 T17S R31E  
BHL 355 FSL & 330 FWL, Unit M, Sec. 35 T17S R31E  
Eddy County, NM

---

**NOTES REGARDING THE BLOWOUT PREVENTERS**

**Tamano Federal #1  
Eddy County, New Mexico**

1. Drilling nipple to be so constructed that it can be removed without use of a welder through rotary table opening, with minimum I.D. equal to preventer bore.
2. Wear ring to be properly installed in head.
3. Blow out preventer and all fittings must be in good condition, 2000 psi WP minimum.
4. All fittings to be flanged.
5. Safety valve must be available on rig floor at all times with proper connections, valve to be full 2000 psi WP minimum.
6. All choke and fill lines to be securely anchored especially ends of choke lines.
7. Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
8. Kelly cock on Kelly.
9. Extension wrenches and hands wheels to be properly installed.
10. Blow out preventer control to be located as close to driller's position as feasible.
11. Blow out preventer closing equipment to include minimum 40-gallon accumulator, two independent sources of pump power on each closing unit installation all API specifications.


**Mack Energy Corporation**  
**Minimum Blowout Preventer Requirements**  
 3000 psi Working Pressure  
 3 MWP  
 EXHIBIT #10

**Stack Requirements**

NO	Items	Min. I D	Min Nominal
1	Flowline		2"
2	Fill up line		2"
3	Drilling nipple		
4	Annular preventer		
5	Two single or one dual hydraulically operated rams		
6a	Drilling spool with 2" min. kill line and 3" min choke line outlets		2" Choke
6b	2" min. kill line and 3" min. choke line outlets in ram. (Alternate to 6a above)		
7	Valve Gate Plug	3 1/8	
8	Gate valve-power operated	3 1/8	
9	Line to choke manifold		3"
10	Valve Gate Plug	2 1/16	
11	Check valve	2 1/16	
12	Casing head		
13	Valve Gate Plug	1 13/16	
14	Pressure gauge with needle valve		
15	Kill line to rig mud pump manifold		2"

**OPTIONAL**

16	Flanged Valve	1 13/16	
----	---------------	---------	--



**CONTRACTOR'S OPTION TO FURNISH:**

1. All equipment and connections above bradenhead or casinghead. Working pressure of preventers to be 2000 psi minimum.
2. Automatic accumulator (80 gallons, minimum) capable of closing BOP in 30 seconds or less and, holding them closed against full rated working pressure.
3. BOP controls, to be located near drillers' position.
4. Kelly equipped with Kelly cock.
5. Inside blowout preventer or its equivalent on derrick floor at all times with proper threads to fit pipe being used.
6. Kelly saver-sub equipped with rubber casing protector at all times.
7. Plug type blowout preventer tester
8. Extra set pipe rams to fit drill pipe in use on location at all times.
9. Type RX ring gaskets in place of Type R

**MEC TO FURNISH:**

1. Bradenhead or casing head and side valves.
2. Wear bushing. If required.

**GENERAL NOTES:**

1. Deviations from this drawing may be made only with the express permission of MEC's Drilling Manager
2. All connections, valves, fittings, piping, etc., subject to well or pump pressure must be flanged (suitable clamp connections acceptable) and have minimum working pressure equal to rated working pressure of preventers up through choke valves must be full opening and suitable for high pressure mud service.
3. Controls to be of standard design and each marked, showing opening and closing position
4. Chokes will be positioned so as not to hamper or delay changing of choke beans

- Replaceable parts for adjustable choke, or bean sizes, retainers, and choke wrenches to be conveniently located for immediate use
5. All valves to be equipped with hand-wheels or handles ready for immediate use.
6. Choke lines must be suitably anchored.
7. Handwheels and extensions to be connected and ready for use
8. Valves adjacent to drilling spool to be kept open. Use outside valves except for emergency.
9. All seamless steel control piping (2000 psi working pressure) to have flexible joints to avoid stress. Hoses will be permitted.
10. Casinghead connections shall not be used except in case of emergency.
11. Does not use kill line for routine fill up operations

# Mack Energy Corporation


Exhibit #11

## MINIMUM CHOKE MANIFOLD

3,000, 5,000, and 10,000 PSI Working Pressure

3M will be used

3 MWP - 5 MWP - 10 MWP



Mud Pit

Reserve Pit

\* Location of separator optional

Below Substructure

### Minimum requirements

No.		3,000 MWP			5,000 MWP			10,000 MWP		
		I.D.	Nominal	Rating	I.D.	Nominal	Rating	I.D.	Nominal	Rating
1	Line from drilling Spool		3"	3,000		3"	5,000		3"	10,000
2	Cross 3" x 3" x 3" x 2"			3,000			5,000			
2	Cross 3" x 3" x 3" x 2"									10,000
3	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000
4	Valve Gate Plug	1 13/16		3,000	1 13/16		5,000	1 13/16		10,000
4a	Valves (1)	2 1/16		3,000	2 1/16		5,000	2 1/16		10,000
5	Pressure Gauge			3,000			5,000			10,000
6	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000
7	Adjustable Choke (3)	2"		3,000	2"		5,000	2"		10,000
8	Adjustable Choke	1"		3,000	1"		5,000	2"		10,000
9	Line		3"	3,000		3"	5,000		3"	10,000
10	Line		2"	3,000		2"	5,000		2"	10,000
11	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000
12	Line		3"	1,000		3"	1,000		3"	2,000
13	Line		3"	1,000		3"	1,000		3"	2,000
14	Remote reading compound Standpipe pressure gauge			3,000			5,000			10,000
15	Gas Separator		2' x 5'			2' x 5'			2' x 5'	
16	Line		4"	1,000		4"	1,000		4"	2,000
17	Valve Gate Plug	3 1/8		3,000	3 1/8		5,000	3 1/8		10,000

(1) Only one required in Class 3M

(2) Gate valves only shall be used for Class 10 M

(3) Remote operated hydraulic choke required on 5,000 psi and 10,000 psi for drilling


### EQUIPMENT SPECIFICATIONS AND INSTALLATION INSTRUCTION

- All connections in choke manifold shall be welded, studded, flanged or Cameron clamp of comparable rating.
- All flanges shall be API 6B or 6BX and ring gaskets shall be API RX or BX Use only BX for 10 MWP.
- All lines shall be securely anchored
- Chokes shall be equipped with tungsten carbide seats and needles, and replacements shall be available.
- alternate with automatic chokes, a choke manifold pressure gauge shall be located on the rig floor in conjunction with the standpipe pressure gauge
- Line from drilling spool to choke manifold should be as straight as possible Lines downstream from chokes shall make turns by large bends or 90 degree bends using bull plugged tees



# Mack Energy Corporation

## MANIFOLD SCHEMATIC



**Mack Energy Corporation  
Onshore Order #6  
Hydrogen Sulfide Drilling Operation Plan**

**I. HYDROGEN SULFIDE TRAINING**

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H<sub>2</sub>S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H<sub>2</sub>S on metal components. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H<sub>2</sub>S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H<sub>2</sub>S zone (within 3 days or 500 feet) and weekly H<sub>2</sub>S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan. The concentrations of H<sub>2</sub>S of wells in this area from surface to TD are low enough that a contingency plan is not required.

## II. H2S SAFETY EQUIPMENT AND SYSTEMS

Note: All H2S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonable expected to contain H2S.

### 1. Well Control Equipment:

- A. Flare line.
- B. Choke manifold.
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
- D. Auxiliary equipment may include if applicable: annular preventer & rotating head.

### 2. Protective equipment for essential personnel:

- A. Mark II Survive air 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

### 3. H2S detection and monitoring equipment:

- A. 1 portable H2S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 PPM are reached.

### 4. Visual warning systems:

- A. Wind direction indicators as shown on well site diagram (Exhibit #8).
- B. Caution/Danger signs (Exhibit #7) shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.

### 5. Mud program:

- A. The mud program has been designed to minimize the volume of H2S circulated to surface. Proper mud weight, safe drilling practices and the use of H2S scavengers will minimize hazards when penetrating H2S bearing zones.

**6. Metallurgy:**

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H<sub>2</sub>S service.
- B. All elastomers used for packing and seals shall be H<sub>2</sub>S trim.

**7. Communication:**

- A. Radio communications in company vehicles including cellular telephone and 2-way radio.
- B. Land line (telephone) communication at Office.

**8. Well testing:**

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safely and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will *not* be flowed to the surface. All drill-stem-testing operations conducted in an H<sub>2</sub>S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

**EXHIBIT #7**

**WARNING**  
**YOU ARE ENTERING AN H<sub>2</sub>S**  
**AUTHORIZED PERSONNEL ONLY**


- 1. BEARDS OR CONTACT LENSES NOT ALLOWED**
- 2. HARD HATS REQUIRED**
- 3. SMOKING IN DESIGNATED AREAS ONLY**
- 4. BE WIND CONSCIOUS AT ALL TIMES**
- 5. CHECK WITH MACK ENERGY FOREMAN AT OFFICE**

**MACK ENERGY CORPORATION**

**1-575-748-1288**

DRILLING LOCATION H<sub>2</sub>S SAFETY EQUIPMENT

Exhibit # 8



- ▽ H<sub>2</sub>S Monitors with alarms at the bell nipple
- Wind Direction Indicators
- △ Safe Briefing areas with caution signs and breathing equipment min 150 feet from

**Mack Energy Corporation Call List, Eddy County**

<b>Artesia (575)</b>	<b>Cellular</b>	<b>Office</b>	<b>Home</b>
Jim Krogman.....	746-5515.....	748-1288.....	746-2674
Lonnie Archer.....	746-7889.....	748-1288.....	365-2998
Donald Archer.....	748-7875.....	748-1288.....	748-2287
Chris Davis.....	746-7132.....	748-1288.....	
Kevin Garrett.....	746-7423.....	748-1288.....	

**Agency Call List (575)****Artesia**

State Police.....	746-2703
City Police.....	746-2703
Sheriff's Office.....	746-9888
Ambulance.....	911
Fire Department.....	746-2701
LEPC (Local Emergency Planning Committee).....	746-2122
NMOCD.....	748-1283

**Carlsbad**

State Police.....	885-3137
City Police.....	885-2111
Sheriff's Office.....	887-7551
Ambulance.....	911
Fire Department.....	885-2111
LEPC (Local Emergency Planning Committee).....	887-3798
Bureau of Land Management.....	887-6544
New Mexico Emergency Response Commission.....	(505)476-9690
24 Hour.....	(505)827-9126
National Emergency Response Center (Washington).....	(800)424-8802

**Emergency Services**

Boots & Coots IWC.....	1-800-256-9688 or (281)931-8884
Cudd pressure Control.....	(915)699-0139 or (915)563-3356
Halliburton.....	746-2757
B. J. Services.....	746-3569
Flight For Life-Lubbock, TX.....	(806)743-9911
Aerocare-Lubbock, TX.....	(806)747-8923
Med Flight Air Amb-Albuquerque, NM.....	(505)842-4433
Lifeguard Air Med Svc. Albuquerque, NM.....	(505)272-3115

# SURFACE USE AND OPERATING PLAN

## 1. Existing & Proposed Access Roads

- A. The well site and elevation plat for the proposed well is shown in Exhibit #1. It was staked by John West Engineering, Hobbs, NM.
- B. All roads to the location are shown in Exhibit below. The existing lease roads are illustrated and are adequate for travel during drilling and production operations. Upgrading existing roads prior to drilling well will be done where necessary.
- C. Directions to Location: From the intersection of Hwy #82 and St. Hwy #529. Go SE on 529 3.8 miles, turn right/south .6 mile, turn right/west 1.0 mile to Antelope St #6, follow proposed road survey, location is 165' southeast to location.
- D. Routine grading and maintenance of existing roads will be conducted as necessary to maintain their condition as long as any operations continue on this lease.




Exhibit #4

## **2. Proposed Access Road:**

Exhibit #3 shows the 165' of new access road to be constructed. The road will be constructed as follows:

- A. The Maximum width of the running surface will be 14'. The road will be crowned and ditched and constructed of 6" rolled and compacted caliche. Ditches will be at 3:1 slope and 4 feet wide. Water will be diverted where necessary to avoid ponding, prevent erosion, maintain good drainage, and to be consistent with local drainage patterns.
- B. The average grade will be less than 1%.
- C. No turnouts are planned.
- D. No culverts, cattleguard, gates, low water crossings or fence cuts are necessary.
- E. Surfacing material will consist of native caliche. Caliche will be obtained from the nearest BLM approved caliche pit.
- F. The proposed access road as shown in Exhibit #3 has been centerline flagged by John West Engineering, Hobbs, New Mexico.

## **3. Location of Existing Wells & Proposed flow lines for New Wells:**

Exhibit #4 shows all existing wells within a one-mile radius of this well. Proposed flow lines, will stay on location, TB at the #1 well.

## **4. Location of Existing and/or Proposed Facilities:**

- A. Mack Energy Corporation does not operate a production facility on this lease.
- B. If the well is productive, contemplated facilities will be as follows:
  - 1) San Andres Completion: Will be sent to the Tamano Federal TB located at the #1 well. The Facility is shown in Exhibit #5.
  - 2) The tank battery and facilities including all flow lines and piping will be installed according to API specifications.
  - 3) Any additional caliche will be obtained from a BLM approved caliche pit. Any additional construction materials will be purchased from contractors.
  - 4) It will be necessary to run electric power if this well is productive. Power will be run by CVE and they will send in a separate plan for power.



**7. Methods of Handling Water Disposal:**

- A. Drill cuttings not retained for evaluation purposes will be disposed into the steel tanks and hauled to an approved facility.
- B. Drilling fluids will be contained in steel tanks using a closed loop system.
- C. Water produced from the well during completion may be disposed into a steel tank. After the well is permanently placed on production, produced water will be collected in tanks (fiberglass) until pumped to an approved disposal system.
- D. Garbage produced during drilling or completion operations will be collected and hauled to an approved landfill. All water and fluids will be disposed of into an approved facility. No toxic waste or hazardous chemicals will be produced by this operation.
- E. After the rig is moved out and the well is either completed or abandoned, all waste materials will be cleaned up within 30 days. In the event of a dry hole only a dry hole marker will remain.

**8. Plans for Restoration of the Surface:**

- A. Upon completion of the proposed operations, if the well is completed, any additional caliche required for facilities will be obtained from a BLM approved caliche pit.
- B. In the event of a dry hole. Topsoil removed from the drill site will be used to recontour the area to its original natural level and reseeded as per BLM specifications.

**9. Surface Ownership:**

The well site is located entirely on State surface. We have notified the SLO and obtained ROW for the impending operations. According to SLO the leasee is Williams & Son Cattle Co., P.O. Box 30, Maljamar, NM 88264.

**10. Other Information:**

- A. The area around the well site is grassland and the topsoil is sandy. The vegetation is native scrub grass with sagebrush.
- B. There is no permanent or live water in the immediate area.
- C. A Cultural Resources Examination has been requested and will be forwarded to your office in the near future.

**11. Lessee's and Operator's Representative:**

The Mack Energy Corporation representative responsible for assuring compliance with the surface use plan is as follows:


Jerry W. Sherrell  
Mack Energy Corporation  
P.O. Box 960  
Artesia, NM 88211-0960  
Phone (575) 748-1288 (office)

## APD CERTIFICATION

I hereby certify that I, or person under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this APD, are to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by Mack Energy Corporation and its contractors and subcontractors in conformity with this plan and the terms and conditions which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Date: 8-10-09

Signed: \_\_\_\_\_

  
Jerry W. Sherrell

## PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Mack Energy Corp
LEASE NO.:	NM 122617
WELL NAME & NO.:	1 Tamano Federal
SURFACE HOLE FOOTAGE:	1250' FSL & 200' FWL
BOTTOM HOLE FOOTAGE:	355' FSL & 330' FWL
LOCATION:	Section 36, T. 17 S., R 31 E., NMPM
COUNTY:	Eddy County, New Mexico

### TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
  - Lesser Prairie-Chicken
  - Ground-level Abandoned Well Marker
  - V-door: Northeast
- ☐ **Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
  - Casing Depth Change
  - H2S Requirements, Onshore Order #6
  - Logging Requirements
- ☒ **Production (Post Drilling)**
  - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment/Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## **V. SPECIAL REQUIREMENT(S)**

### **Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken:**

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

**Ground-level Abandoned Well Marker to avoid raptor perching:** Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

**The V-door will be northeast so that no topsoil from the caliche pit will be disturbed to the south of the location.**

## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5972 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall stockpile the topsoil of the well pad. The topsoil shall not be used to backfill the reserve pit and will be used for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

If the operator elects to surface the access road and/or well pad, mineral materials extracted during construction of the reserve pit may be used for surfacing the well pad and access road and other facilities on the lease.

Payment shall be made to the BLM prior to removal of any additional federal mineral materials from any site other than the reserve pit. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

## **F. ON LEASE ACCESS ROADS**

### **Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed thirty (30) feet.

### **Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

### **Crowning**


Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

### **Ditching**

Ditching shall be required on both sides of the road.

### **Turnouts**


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:



### **Drainage**

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### **Formula for Spacing Interval of Lead-off Ditches**

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

#### **Culvert Installations**

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

#### **Cattleguards**

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.



**Fence Requirement**


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

**Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Figure 1 – Cross Sections and Plans For Typical Road Sections



## VII. DRILLING

### A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

1. A Hydrogen Sulfide (H<sub>2</sub>S) Drilling Plan should be activated 500 feet prior to drilling into the **Grayburg** formation. **As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the CAL/GR/N well log run from TD to surface will be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**
5. **Well must be produced at an orthodox location.**

### B. CASING

**Changes to the approved APD casing and cement program require submitting a sundry and receiving approval prior to work. Failure to obtain approval prior to work will result in an Incident of Non-Compliance being issued.**

**Centralizers required on surface casing per Onshore Order 2.III.B.1.f.**

**Wait on cement (WOC) time for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.**

**No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.**

**Possible water and brine flows in the Salado and Artesia Groups.**

**Possible lost circulation in the Grayburg and San Andres**

1. The **13-3/8 inch** surface casing shall be set **at approximately 950 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt)** and cemented to the surface. **Fresh water to be used to setting depth.**
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with a surface log readout will be used or a cement bond log shall be run to verify the top of the cement.
  - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9-5/8 inch** intermediate casing is:  
☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.
3. The minimum required fill of cement behind the **7 inch** intermediate casing is:  
☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.
4. Cement not required on the **4-1/2" casing. Packer system being used.**

5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

#### **C. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M) psi. Operator installing a 3M, but only testing to 2M.**
3. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. The tests shall be done by an independent service company.
  - b. The results of the test shall be reported to the appropriate BLM office.
  - c. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
  - d. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.
  - e. **Effective November 1, 2008, no variances will be granted on reduced pressure tests on the surface casing and BOP/BOPE. Onshore Order 2 requirements will be in effect.**

#### **D. DRILL STEM TEST**

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

**CRW 090909**

## **VIII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the east side of the well pad to allow for maximum interim recontouring and revegetation of the west side of the well location as soon as possible.

#### **Containment Structures**

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

#### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color  
Shale Green, Munsell Soil Color Chart # 5Y 4/2

## **IX. INTERIM RECLAMATION**

If the well is a producer, interim reclamation shall be conducted on the well site in accordance with the orders of the Authorized Officer. The operator shall submit a Sundry Notices and Reports on Wells (Notice of Intent), Form 3160-5, prior to conducting interim reclamation.

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

The operators should work with BLM surface management specialists to devise the best strategies to reduce the size of the location. Any reductions should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

## Seed Mixture for LPC Sand/Shinnery Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

\*\*Four-winged Saltbush 5lbs/A

\* This can be used around well pads and other areas where caliche cannot be removed.

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



## **X. FINAL ABANDONMENT & REHABILITATION REQUIREMENTS**

Upon abandonment of the well and/or when the access road is no longer in service the Authorized Officer shall issue instructions and/or orders for surface reclamation and restoration of all disturbed areas.

Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

On private surface/federal mineral estate land the reclamation procedures on the road and well pad shall be accomplished in accordance with the private surface land owner agreement.