OCD-ARTESIA

		_				
orRECEIVED	UNITED DEPARTMENT O			FORM APPROVED OMB No 1001- 0137		
MAY 07 2010	BUREAU OF LANI			F	expires July 31, 2010	
NMOCD ARTESIA DRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.					No NMLC028793A ottee, or Fribe Name	
SUBMIT IN TRIPLICATE - Other Instructions on page 2					Agreement Name and/or No	
Type of Well Gas Well	X Other	wiw		NMNM88525X 8 Well Name and No		
2 Name of Operator Marbob Energy Corporation				9 API Well No	rch Keely Unit #98	
3a Address PO Bo		3b Phone No anclude area code)			2/364 30-015- 21366	
Artesia, NM 88211-0227 (575) 748-3303			48-3303	10 Field and Pool, or Exploratory Area		
4 Location of Well (I-ootuge, Sec., T	, R , M , or Survey Description)				Jackson; SR-Q-Grbg-SA	
1650 FSL 760 FEL, Sec. 19-T17S-R30E, Unit I					arish, State Eddy Co., NM	
12. CHECK APPROF	PRIATE BOX(S) TO IND	ICATE NATURE OF	NOTICE, REPOI	RT, OR OTHE	R DATA	
TYPE OF SUBMISSION	TYPE OF ACTION					
X Notice of Intent	Acidize	Deepen	Production (S	Start/ Resume)	Water Shut-off	
	Altering Casing	Fracture Treat	Reclamation		Well Integrity	
Subsequent Report	Casing Repair	New Construction	Recomplete		Other	
	Change Plans	X Plug and Abandon	Temporarily /	∆bandon		
Final Abandonment Notice	Convert to Injection	Plug Back	Water Dispos	·		
Attach the Bond under which the following completion of the invol	ctionally or recomplete horizont work will performed or provid- ved operations. If the operation Abandonment Notice shall be	ally, give subsurface location the Bond No on file with results in a multiple complete	ns and measured and the BLM/ BIA Requestion or recompletion	I true vertical dept uned subsequent r in a new interval,	k and approximate duration thereof ths or pertinent markers and sands reports shall be filed within 30 days a Form 3160-4 shall be filed once en completed, and the operator has	

Marbob Energy Corporation proposes to plug & abandon this well.

(See detailed procedure and wellbore schematics attached)

SEE ATTACHED FOR CONDITIONS OF APPROVAL

RECLAMATION PROCEDURE ATTACHED

14. Thereby certify that the foregoing is true and correct					
Name (Pymted Typed)	1				
	Fitle				
Diana, J. Briggs	1,,,,,	Production Manager			
		1 roduction manager			
Signature I I M M M M M M M M M M M M M M M M M	Date		,		
	1	V D D D WILLIAM	1		
TING ADA OF CODE ACED	FDAL OD OT				
THIS SPACE FOR FED	ERAL OR STA	TE OFFIGE USENUVLU			
Approved by	Title	MAX C 2HM -=			
Conditions of approval, if any are attached. Approval of this notice does not warra	ant or	MAY 6 2010° -	1		
certify that the applicant holds legal or equitable title to those rights in the subject.		Int Dunkin Minkley	Ī		
		/s// Dustin Winkler	!		
	reon	11	1		
Fifle 18 U.S.C. Section 1001 AND Fifle 43 U.S.C. Section 1212, make it a crim	me for any person k	TO STINDING IN A SAME OF THE STILL OF THE ST	gency of the United		
States any false, fictitious or fraudulent statements or representations as to any matter	r within its imisdiction	P CARL SRAD FIELD DEFICE			
		E CARLODAU FIELU UPFILE	 		

BKU 98 1650' fsl, 760' fel Unit I, Sec. 19, T17S, R30E Eddy Co., NM API 30-015-21366 Plug and Abandonment Procedure 15 Apr 10

RECEIVED
APR 1 5 2010

LKBC.

Basic Data:

8-5/8" @ 495' 100 sx. Calc TOC @ 240' Assuming 13" Hole. 4-1/2" @ 3410' 600 sx. TOC 1210' Temp Survey.

Old squeezed casing leaks in 4-1/2" 60-150'. New casing leaks in 4-1/2" 120-233'.

Top Salt = 480', Base Salt = 955'

Grayburg and San Andres are part of a single pooled interval and don't need to be separated when well is plugged.

<u>Note:</u> Notify BLM inspectors in Carlsbad (575-361-2822) at least 24 hrs. before starting plugging operation. Class "C" cement will be used (14.8 ppg, 1.32 cfps, 6.3 gwps).

Procedure:


- 1. Pick up a work string and run bit and scraper to 2500' if necessary.
- 2. Install packoff, run gauge ring to 2500' if necessary and set CIBP at 2500'. Shoot 8 squeeze holes at 1005' (50' below base salt) and 545' (50' below 8-5/8" shoe).
- 3. RIH with tubing to CIBP at 2500', tag plug, set a few points weight onto plug to make sure it won't move, spot 25 sx. Class "C" with 2% CaCl2 on top of CIBP, pull up to 2000', circulate 30 bbls of 9 ppg brine mixed with 25 sx per 100 bbls of salt gel into well, TOOH with tubing and pick up a packer.
- 4. RIH with packer to 800', establish injection rate into perfs at 1005' (50' below base of salt, open valve on 4-1/2" x 8-5/8" annulus), pump 50 sx Class "C" with 2% CaCl2, flush cement to packer, TOOH with packer and RIH open-ended and tag cement. If can't inject into perfs at 1005', POOH with packer, RIH open-ended to 1260', spot 30 sx. Class "C" with 2% CaCl2, pull tubing to 300', WOC couple of hours and RIH and tag plug. Plug needs to be 895' or shallower. Respot plug if necessary.
- 5. RIH with packer to 380', establish injection rate into perfs at 545' (50' below 8-5/8" shoe, open valve on 4-1/2" x 8-5/8" annulus), pump 50 sx Class "C" with 2% CaCl2, flush cement to packer, TOOH with packer, WOC couple of hours and RIH open-ended and tag cement. Plug needs to be 430' or shallower. Respot plug if necessary.
- 6. RIH with open-ended tubing to 250', fill 4-1/2" with approx. 20 sx. Class "C" with 2% CaCl2, POOH with tubing, tie onto 4.5" casing, pump cement down 4-1/2" and up 4-1/2" x 8-5/8" annulus until cement circulates to surface, close 4-1/2" x 8-5/8" annulus and pump cement down 4-1/2" and attempt to circulate to surface outside the 8-5/8" casing. Have extra cement available in case needed (should take


- approx. 130 sx. to fill 4-1/2", 4-1/2" x 8-5/8" annulus and 8-5/8" x open hole annulus from 200' to surface).
- 7. Cut wellhead and casings off 3' below ground level and remove. Weld plate onto 8-5/8" stub. Weld a 4" diameter dry hole marker onto plate such that 4' of it is above ground level. The following information needs to be placed on the marker:

Marbob Energy, BKU 98, 1650' fsl, 760' fel, Unit I, Sec. 19, T17S, R30E, 30-015-21366 Date well plugged

8. Cut off anchors, and reclaim location per BLM specs.

Kbc/bku 98 plug





Marbob Energy Corperation

NMLC-028793A: Burch Keely Unit #98

API: 30-015-21366

Eddy County, New Mexico

RE: Plugging and Abandonment Procedure, Conditions of Approval

H2S monitoring equipment to be on location.

- 1. OK
- 2. OK
- 3. OK (Perfs)
- 4. OK (BOS)
- 5. OK (Casing shoe TOS)
- 6. Perforations needed Otherwise OK (Surface)
- 7. Verify cement to surface in all annuluses. Ground Level Dry Hole Marker required in this area Requirements attached.
- 8. OK
- 9. Submit subsequent report, with details.

See attached standard COA.

DHW 042910

BUREAU OF LAND MANAGEMENT

Carlsbad Field Office 620 East Greene Street Carlsbad, New Mexico 88220 575-234-5972

Permanent Abandonment of Federal Wells Conditions of Approval

Failure to comply with the following Conditions of Approval may result in a Notice of Incidents of Noncompliance (INC) in accordance with 43 CFR 3163.1.

1. Plugging operations shall commence within <u>ninety (90)</u> days from the approval date of this Notice of Intent to Abandon.

If you are unable to plug the well by the 90th day provide this office, prior to the 90th day, with the reason for not meeting the deadline and a date when we can expect the well to be plugged. Failure to do so will result in enforcement action.

The rig used for the plugging procedure cannot be released and moved off without the prior approval of the authorized officer. Failure to do so may result in enforcement action.

- 2. <u>Notification:</u> Contact the appropriate BLM office at least 24 hours prior to the commencing of any plugging operations. For wells in Chaves and Roosevelt County, call 575-627-0272; Eddy County, call 575-361-2822; Lea County, call 575-393-3612.
- 3. <u>Blowout Preventers</u>: A blowout preventer (BOP), as appropriate, shall be installed before commencing any plugging operation. The BOP must be installed and maintained as per API and manufacturer recommendations. The minimum BOP requirement is a 2M system for a well not deeper than 9,090 feet; a 3M system for a well not deeper than 13,636 feet; and a 5M system for a well not deeper than 22,727 feet.
- 4. <u>Mud Requirement:</u> Mud shall be placed between all plugs. Minimum consistency of plugging mud shall be obtained by mixing at the rate of 25 sacks (50 pounds each) of gel per 100 barrels of **brine** water. Minimum nine (9) pounds per gallon.
- 5. Cement Requirement: Sufficient cement shall be used to bring any required plug to the specified depth and length. Any given cement volumes on the proposed plugging procedure are merely estimates and are not final. Unless specific approval is received, no plug except the surface plug shall be less than 25 sacks of cement. In lieu of a cement plug in a cased hole, a bridge plug set within 50 feet to 100 feet above the perforations shall be capped with 25 sacks of cement. If a bailer is used to cap this plug, 35 feet of cement shall be sufficient. Any plug that requires a tag will have a minimum WOC time of 4 hours.

Unless otherwise specified in the approved procedure, the cement plug shall consist of either Neat Class "C", for up to 7,500 feet of depth or Neat Class "H", for deeper than 7,500 feet plugs.

- 6. <u>Dry Hole Marker</u>: All casing shall be cut-off at the base of the cellar or 3 feet below final restored ground level (whichever is deeper). The BLM is to be notified when the wellhead is cut off to verify that cement is to surface in the casing and all annuluses. The well bore shall then be capped with a 4-inch pipe, 10-feet in length, 4 feet above ground and embedded in cement. The following information shall be permanently inscribed on the dry hole marker: well name and number, name of the operator, lease serial number, surveyed location (quarter-quarter section, section, township and range or other authorized survey designation acceptable to the authorized officer such as metes and bounds).
- 7. <u>Subsequent Plugging Reporting:</u> Within 30 days after plugging work is completed, file one original and five copies of the Subsequent Report of Abandonment, Form 3160-5 to BLM. The report should give in detail the manner in which the plugging work was carried out, the extent (by depths) of cement plugs placed, and the size and location (by depths) of casing left in the well. **Show date well was plugged.**
- 8. <u>Trash:</u> All trash, junk and other waste material shall be contained in trash cages or bins to prevent scattering and will be removed and deposited in an approved sanitary landfill. Burial on site is not permitted.

Following the submission and approval of the Subsequent Report of Abandonment, surface restoration will be required. See attached reclamation procedure.

DHW 112309



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Carlsbad Field Office 620 E. Greene St. Carlsbad, New Mexico 88220-6292 www.blm.gov/nm



In Reply Refer To: 1310

Interim Reclamation Procedures

Reclamation Objective: Oil and gas development is one of many uses of the public lands and resources. While development may have a short- or long-term effect on the land, successful reclamation can ensure the effect is not permanent. During the life of the development, all disturbed areas not needed for active support of production operations should undergo "interim" reclamation in order to minimize the environmental impacts of development on other resources and uses.

Interim reclamation consists of minimizing the footprint of disturbance by reclaiming all portions of the well site not needed for production operations. The portions of the cleared well site not needed for operational and safety purposes are recontoured to a final or intermediate contour that blends with the surrounding topography as much as possible. Sufficient level area remains for setup of a workover rig and to park equipment. Topsoil is respread over areas not needed for all-weather operations. Production facilities should be clustered to maximize the opportunity for interim reclamation. In order to inspect and operate the well or complete workover operations, it may be necessary to drive, park, and operate on restored, interim vegetation within the previously disturbed area. This is generally acceptable provided damage is repaired and reclaimed following use.

To reduce final reclamation costs; maintain healthy, biologically active topsoil; and to minimize habitat, visual, and forage loss during the life of the well, all salvaged topsoil should be spread over the area of interim reclamation, rather than stockpiled.

- 1. The Application for Permit to Drill or Reenter (APD, Form 3160-3), Surface Use Plan of Operations must include adequate measures for stabilization and reclamation of disturbed lands. Oil and Gas operators must plan for reclamation, both interim and final, up front in the APD process as per Onshore Oil and Gas Order No. 1.
- 2. For wells and/or access roads not having an approved plan, or an inadequate plan for surface reclamation (either interim or final reclamation), the operator must submit a proposal describing the procedures for reclamation. For interim reclamation, the appropriate time for submittal would be when filing the Well Completion or Recompletion Report and Log (Form 3160-4). Interim reclamation is to be completed within 6 months of well completion.

- 3. If you have an approved Surface Use Plan of Operation and/or an approved Sundry Notice, you are free to proceed with interim reclamation as per approved APD or Sundry Notice. If you have issues or concerns, contact a BLM specialist to assist you. It would be in your interest to have a BLM specialist look at the location and access road prior to the removal of reclamation equipment to ensure that it meets BLM objectives. Upon conclusion submit a Form 3160-5, Subsequent Report of Reclamation. This will prompt a specialist to inspect the location to verify work was completed as per approved plans.
- 4. The approved Subsequent Report of Reclamation will be your notice that the native soils, contour and seedbed have been reestablished. If the BLM objectives have not been met the operator will be notified and corrective actions may be required.
- 5. It is the responsibility of the operator to monitor these locations and/or access roads until such time as the operator feels that the BLM objective has been met.

If there are any questions, please feel free to contact any of the following specialists:

Jim Amos Supervisory Environmental Protection Specialist 575-234-5909, 575-361-2648 (Cell)

Terry Gregston Environmental Protection Specialist 575-234-5958

Bobby Ballard Environmental Protection Specialist 575-234-2230

Randy Rust Environmental Protection Specialist 575-234-5943

Linda Denniston Environmental Protection Specialist 575-234-5974

Jennifer Van Curen Environmental Protection Specialist 575-234-5905

Justin Frye Environmental Protection Specialist 575-234-5922 Cody Layton Natural Resource Specialist 575-234-5959

Trishia Bad Bear Natural Resource Specialist 575-393-3612

Todd Suter Surface Protection Specialist 575-234-5987

Doug Hoag Civil Engineering Technician 575-234-5979