

Submit 1 Copy To Appropriate District
Office
District I
1625 N French Dr., Hobbs, NM 88240
District II
1301 W Grand Ave., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S St Francis Dr., Santa Fe, NM
87505

State of New Mexico
Energy, Minerals and Natural Resources

Form C-103
October 13, 2009

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

WELL API NO. 30-015-28327
5. Indicate Type of Lease STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>
6. State Oil & Gas Lease No. L-1897
7. Lease Name or Unit Agreement Name NDDUP Unit
8. Well Number 4
9. OGRID Number 025575
10. Pool name or Well Dagger Draw; Upper Penn, North

RECEIVED
JUN - 8 2010
NMOC D ARTESIA

SUNDRY NOTICES AND REPORTS ON WELLS
(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)

1. Type of Well: Oil Well ☒ Gas Well ☐ Other ☐

2. Name of Operator
Yates Petroleum Corporation

3. Address of Operator
105 South Fourth Street, Artesia, NM 88210

4. Well Location
Unit Letter D : 660 feet from the North line and 660 feet from the West line
Section 16 Township 19S Range 25E NMPM Eddy County

11. Elevation (Show whether DR, RKB, RT, GR, etc.)
3517'GR

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:

PERFORM REMEDIAL WORK ☐ PLUG AND ABANDON ☒
TEMPORARILY ABANDON ☐ CHANGE PLANS ☐
PULL OR ALTER CASING ☐ MULTIPLE COMPL ☐
DOWNHOLE COMMINGLE ☐

SUBSEQUENT REPORT OF:

REMEDIAL WORK ☐ ALTERING CASING ☐
COMMENCE DRILLING OPNS. ☐ P AND A ☐
CASING/CEMENT JOBS ☐

**Notify OGD 24 hrs. prior
to any work done.**

OTHER: ☐

OTHER: ☐

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 19.15.7.14 NMAC. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

Yates Petroleum Corporation plans to plug and abandon this well as follows:

1. NU BOP. Rig up any safety equipment as needed. No casing recovery will be attempted.
2. Set a CIBP at 7719' with 35' cement on top. This will place a plug over open Canyon perforations.
3. Spot a 160' cement plug from 5447'-5607'. This will leave a plug across Wolfcamp top.
4. Spot a 140' cement plug from 3357'-3497'. This will leave a plug across Bone Spring top.
5. Spot a 120' cement plug from 2128'-2248'. This will leave a plug across Glorieta top.
6. Spot a 150' cement plug from 1055'-1205'. WOC and tag plug, reset if necessary. This will leave a plug across surface casing shoe.
7. Spot a 100' cement plug to surface. WOC and tag plug, reset if necessary. This will leave a 100' surface plug.
8. Remove all surface equipment and weld dry hole marker per regulations.

Due to the volume of wells we currently have plans to plug, both State/Fee and Federal, Yates Petroleum respectfully requests a time frame of 1 year to have commenced plugging operations and for this notice of intent to be in affect

*** Required O.V. Tool Cmt Plug 6262'-6362'**

Spud Date:

Rig Release Date:

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Tina Huerta TITLE Regulatory Compliance Supervisor DATE June 2, 2010

Type or print name Tina Huerta E-mail address: tinah@yatespetroleum.com PHONE: 575-748-4168

For State Use Only

APPROVED BY: [Signature] TITLE DATE 6/14/2010

Conditions of Approval (if any):

Approval Granted providing work
is complete by 6/14/2011

WELL NAME: NDDUP #4 FIELD: Dagger Draw
 LOCATION: 660' FNL & 660' FWL of Section 16-19S-25E Eddy Co., NM
 GL: 3,517' ZERO: _____ KB: _____
 SPUD DATE: 2/5/95 COMPLETION DATE: 3/10/95
 COMMENTS: API No.: 30-015-28327
(Formerly Aparejo APA State Com #1)


CASING PROGRAM

9-5/8" 40		1,155'
7" 26# N80	624'	
7" 26# J55 (SB)	185'	
7" 26# J-55 (V)	2,510'	
7" 23# J-55 (V)	3,748'	
7" 26# J-555 (V)	1,203'	8,270'

Before

TOPS

SA 726'
 Glorieta 2,198'
 BS 3,447'
 WC 5,557'
 Canyon 7,652'



Not to Scale


1/28/10
 DC/Hill

WELL NAME: NDDUP #4 **FIELD:** Dagger Draw
LOCATION: 660' FNL & 660' FWL of Section 16-19S-25E Eddy Co., NM
GL: 3,517' **ZERO:** _____ **KB:** _____
SPUD DATE: 2/5/95 **COMPLETION DATE:** 3/10/95
COMMENTS: API No.: 30-015-28327
(Formerly Aparejo APA State Com #1)

CASING PROGRAM

9-5/8" 40		1,155'
7" 26# N80	624'	
7" 26# J55 (SB)	185'	
7" 26# J-55 (V)	2,510'	
7" 23# J-55 (V)	3,748'	
7" 26# J-555 (V)	1,203'	8,270'

14-3/4" Hole



100' Surface plug
0-100'

150' plug from 1,055-1,205'
across shoe

9-5/8" @ 1,155' w/
1100' sx cmt (Circ)

120' plug from 2,128-2,248'
across Glorieta

140' plug from 3,357-3,497'
across BS

160' plug from 5,447-5,607'
across WC

DV Tool @ 6,312'

** - Required D.V. Tool
CMT- Plug. 6262'-6362'*

CIBP @ 7,719' 35' cmt

Canyon Perfs:
7,769-7,833'; 7,711-7,731'; 7,711-7,833'

TD: 8,056'

7" @ 8,270'
1st Stage: 450 sx
2nd Stage: 900 sx (Circ)

After

TOPS	
SA	726'
Glorieta	2,198'
BS	3,447'
WC	5,557'
Canyon	7,652'

Not to Scale
 1/28/10
 DC/Hill