

11-150

OCD-ARTESIAForm 3160-3
(April 2004)**R-111-POTASH**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**APPLICATION FOR PERMIT TO DRILL OR REENTER**FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007**Split Estate****EAM 249**

1a. Type of work: ☒ DRILL ☐ REENTER		5. Lease Serial No. NMNM-0405444A;	
1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone		6. If Indian, Allottee or Tribe Name	
2. Name of Operator Devon Energy Production Company, LP		7. If Unit or CA Agreement, Name and No.	
3a. Address 20 North Broadway Oklahoma City, Oklahoma City 73102-8260		8. Lease Name and Well No. Aldabra 27 Fed Com 8H	
3b. Phone No. (include area code) 405-228-8699		9. API Well No. 30-015-38632	
4. Location of Well (Report location clearly and in accordance with any State requirements.) At surface SW/4 SW/4 85 FSL & 420 FWL Unit M PP:85 FSL & 420 FWL At proposed prod. zone NE/4 SE/4 2600 FSL & 350 FEL Unit I SEC 22 T23S R31E		10. Field and Pool, or Exploratory Ingle Wells; Avalon Shale	
11. Sec., T. R. M. or Blk. and Survey or Area SEC 26 T23S R31E		12. County or Parish Eddy County	
13. State NM		14. Distance in miles and direction from nearest town or post office* Approximately 22 miles east of Loving, NM.	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 200'		16. No. of acres in lease 1960 Acres	
17. Spacing Unit dedicated to this well 240 Acres		18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. See Attached Map	
19. Proposed Depth 16,973' MD 8960' TVD		20. BLM/BIA Bond No. on file CO-1104	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3452' GL		22. Approximate date work will start*	
23. Estimated duration 45 days		24. Attachments	

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature <i>Judy A. Barnett</i>	Name (Printed/Typed) Judy A. Barnett	Date 12/06/2010
---	---	--------------------

Approved by (Signature) /s/ Jesse J. Juen	Name (Printed/Typed) /s/ Jesse J. Juen	Date MAR 11 2011
Title STATE DIRECTOR	Office NM STATE OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

OCD CONDITION OF APPROVAL of Drilling:
Intent to drill ONLY --- CANNOT produce until the Non-Standard
Location has been approved by OCD Santa Fe office.

CARLSBAD CONTROLLED WATER BASIN**SEE ATTACHED FOR
CONDITIONS OF APPROVAL****APPROVAL SUBJECT TO
GENERAL REQUIREMENTS
AND SPECIAL STIPULATIONS
ATTACHED**

DRILLING PROGRAM

Devon Energy Production Company, LP

Aldabra 27 Fed Com 8H

Surface Location: 85' FSL & 420' FWL, Unit M, Sec 26 T23S R31E, Eddy, NM

Bottom Hole Location: 2600' FSL & 350' FEL, Unit I, Sec 22 T23S R31E, Eddy, NM

1. Geologic Name of Surface Formation

a. Quaternary

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas:

a. Quaternary	180'	Fresh Water
b. Rustler Dol	619'	
c. Salado Salt	939'	
d. Castile	2889'	
e. Base of Salt	4085'	
f. Lamar	4317'	Oil
g. Bell Canyon	4354'	Oil
h. Cherry Canyon	5254'	Oil
i. Brushy Canyon	6512'	Oil
j. 1 st Bone Spring LM	9710'	Oil/Gas
k. Top Avalon Shale	8260'	Oil/Gas
l. 1 st Bone Spring SS	9868'	Oil/Gas
m. 2 nd Bone Spring LM	9710'	Oil/Gas
n. 2 nd Bone Spring SS	9868'	Oil/Gas
o. 2 nd Bone Spring Lower Sd	11,094'	Oil/Gas
p. Wolfcamp	11,527'	Oil/Gas
Total Depth	16,973'	

No other formations are expected to yield oil, gas or fresh water in measurable volumes. The surface fresh water sands will be protected by setting 13 3/8" casing at 725' and circulating cement back to surface. Fresh water sands will be protected by setting 9 5/8" casing at 4375' and circulating cement to surface. The Bone Spring intervals will be isolated by setting 5 1/2" casing to total depth and circulating cement above the base of the 9 5/8" casing.

Casing Program:

<u>Hole Size</u>	<u>Hole Interval</u>	<u>OD Csg</u>	<u>Casing Interval</u>	<u>Weight</u>	<u>Collar</u>	<u>Grade</u>
17 1/2"	0-725'	13 3/8"	0'-725'	48#	ST&C	H-40
12 1/4"	725-4375'	9 5/8"	0'-4375'	40#	LT&C	J-55
8 3/4"	4375-7500'	5 1/2"	0'-7500'	20#	LT&C	HCP-110
8 3/4"	7500-16,973'	5 1/2"	7500-16,973'	17#	BT&C	HCP-110

An 8-3/4" pilot hole will be drilled to 11,600' MD and plugged back to KOP. The cement plug details are included below in the "Cementing Program".

Design Parameter Factors:

<u>Casing Size</u>	<u>Collapse Design Factor</u>	<u>Burst Design Factor</u>	<u>Tension Design Factor</u>
13 3/8"	2.27	5.10	9.25
9 5/8" 40#	1.13	1.74	2.97
5 1/2" 20# LTC	2.13	3.03	1.55
5 1/2" 17# BTC	1.77	2.53	3.42

3.

Cement Program:

13 3/8" Surface

** See COA - Wait on Cement time*
Lead: 500 sacks Class C Cement + 2% bwoc Calcium Chloride + 0.125 lbs/sack Cello Flake + 4% bwoc Bentonite + 81.4% Fresh Water, 13.5 ppg **Yield:** 1.75 cf/sk **TOC @ surface**
Tail: 250 sacks Class C Cement + 2% bwoc Calcium Chloride + 0.125 lbs/sack Cello Flake + 56.3% Fresh Water, 14.8 ppg **Yield:** 1.35 cf/sk

9 5/8" Intermediate

Lead: 1,200 sacks (35:65) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.125 lbs/sack Cello Flake + 6% bwoc Bentonite + 107.8% Fresh Water, 12.5 ppg **Yield:** 2.04 cf/sk **TOC @ surface**
Tail: 300 sacks (60:40) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.125 lbs/sack Cello Flake + 0.4% bwoc Sodium Metasilicate + 4% bwoc MPA-5 + 64.7% Water, 13.8 ppg **Yield:** 1.37 cf/sk

5 1/2" Production

*See COA
For DV-TOOL
& Cement*

1st Stage

Lead: 560 sacks (35:65) Poz (Fly Ash):Class H Cement + 5% bwow Sodium Chloride + 0.3% bwoc CD-32 + 0.5% bwoc FL-25 + 2% bwoc Bentonite + 0.6% bwoc Sodium Metasilicate + 0.5% bwoc FL-52A + 102.5% Fresh Water, 12.5 ppg **Yield:** 2.01 cf/sk
Tail: 2,200 sacks (50:50) Poz (Fly Ash):Class H Cement + 1% bwow Sodium Chloride + 0.2% bwoc R-3 + 0.125 lbs/sack Cello Flake + 0.5% bwoc BA-10A + 4% bwoc MPA-5 + 58.3% Fresh Water, 14.2 ppg **Yield:** 1.28 cf/sk

DV TOOL at 6,000'

2nd Stage

Lead: 325 sacks Class C Cement + 1% bwow Calcium Chloride + 0.125 lbs/sack Cello Flake + 157.8% Fresh Water, 11.4 ppg **Yield:** 2.88 cf/sk
Tail: 100 sacks (60:40) Poz (Fly Ash):Class C Cement + 1% bwow Sodium Chloride + 0.2% bwoc R-3 + 0.125 lbs/sack Cello Flake + 0.5% bwoc BA-10A + 4% bwoc MPA-5 + 63.2% Fresh Water, 13.8 ppg **Yield:** 1.37cf/sk

~~**DV TOOL at 3,000'**~~

3rd Stage

Lead: 375 sacks Class C Cement + 1% bwow Calcium Chloride + 0.125 lbs/sack Cello Flake + 157.8% Fresh Water, 11.4 ppg **Yield:** 2.91 cf/sk **TOC @ surface**
Tail: 100 sacks (60:40) Poz (Fly Ash):Class C Cement + 1% bwow Sodium Chloride + 0.2% bwoc R-3 + 0.125 lbs/sack Cello Flake + 0.5% bwoc BA-10A + 4% bwoc MPA-5 + 63.2% Fresh Water, 13.8 ppg **Yield:** 1.37cf/sk

8-3/4" Pilot Hole Plugs

See COA

Plug 1: 200 sacks Class H Cement, 15.6 ppg, 1.18 cf/sk
Top of Plug: 11,100'
Bottom of Plug: 11,600' (Pilot Hole TD)

500'

Plug 2: 300 sacks Class H Cement, 18.0 ppg, 0.89 cf/sk
Top of Plug: 8,392' (KOP)
Bottom of Plug: 8,900'

508'

The above cement volumes could be revised pending the caliper measurement from the open hole logs. All casing is new and API approved.

Pressure Control Equipment:

** See COA -*

The BOP system used to drill the intermediate hole will consist of a 13-5/8" 3M Triple Ram and Annular preventer. The BOP system will be tested as per BLM Onshore Oil and Gas Order No. 2 as a 3M system prior to drilling out the surface casing shoe.

The BOP system used to drill the production hole will consist of a 13-5/8" 3M Triple Ram and Annular preventer. The BOP system will be tested as per BLM Onshore Oil and Gas Order No. 2 as a 3M system prior to drilling out the intermediate casing shoe.

The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 3,000 psi WP.

Devon requests a variance to use a flexible line with flanged ends between the BOP and the choke manifold (choke line). The line will be kept as straight as possible with minimal turns.

Proposed Mud Circulation System

<u>Depth</u>	<u>Mud Wt.</u>	<u>Visc</u>	<u>Fluid Loss</u>	<u>Type System</u>
0' - 725'	8.4-9.0	30-34	NC	FW
725' - 4375'	9.8-10.0	28-32	NC	Brine
4375' - 16,973'	8.6-9.0	28-32	NC	FW

The necessary mud products for weight addition and fluid loss control will be on location at all times.

4. Auxiliary Well Control and Monitoring Equipment:

- A Kelly cock will be in the drill string at all times.
- A full opening drill pipe stabbing valve having the appropriate connections will be on the rig floor at all times.
- Hydrogen Sulfide detection equipment will be in operation after drilling out the 13 3/8" casing shoe until the 5 1/2" casing is cemented. Breathing equipment will be on location upon drilling the 13 3/8" shoe until total depth is reached.

5. Logging, Coring, and Testing Program:

- Drill stem tests will be based on geological sample shows.
- If a drill stem test is anticipated; a procedure, equipment to be used and safety measures will be provided via sundry notice to the BLM.
- The open hole electrical logging program will be:
 - Total Depth to Intermediate Casing
Ray. Compensated Neutron - Z Density log with Gamma Ray and Caliper.
 - Total Depth to Surface
Compensated Neutron with Gamma Ray
 - No coring program is planned
 - Additional testing will be initiated subsequent to setting the 5 1/2" production casing. Specific intervals will be targeted based on log evaluation, geological sample shows and drill stem tests.

6. **Potential Hazards:**

- a. No abnormal pressures or temperatures are expected. There is no known presence of H₂S in this area. If H₂S is encountered the operator will comply with the provisions of Onshore Oil and Gas Order No. 6. No lost circulation is expected to occur. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. Estimated BHP 4200 psi and Estimated BHT 140°. No H₂S is anticipated to be encountered.

7. **Anticipated Starting Date and Duration of Operations:**

- a. Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon after BLM approval and as soon as a rig will be available. Move in operations and drilling is expected to take 32 days. If production casing is run then an additional 30 days will be needed to complete well and construct surface facilities and/or lay flow lines in order to place well on production. Depending on rig availability, Devon may set the surface casing using an Ashton Oilfield Services rig. The rig plat is attached. This rig will be used only to set the surface casing and will leave the location once the surface casing has been run and cemented. Another rig will drill the remainder of the wellbore. The reasons for using the smaller rig to set surface are: rig availability and economics.

See X
COA X

The BLM will be contacted 24 hours prior to commencing drilling operations. The surface casing will be run and cemented back to surface as per the approved APD. The well will be secured with a cap welded onto the surface casing. Another rig will be on location to drill the remainder of the wellbore within 60 days after the Ashton rig has left the location.



Devon Energy, Inc.

Eddy County

Aldabra "27" Fed

#8H

OH

Plan: Plan #1

Pathfinder X & Y Planning Report

11 November, 2010



A Schlumberger Company



Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Plan: Plan #1 (#8H/OH)

PROJECT DETAILS: Eddy County
Geodetic System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone: New Mexico Eastern Zone
System Datum: Mean Sea Level
Local North: Grid



Azimuths to Grid North
True North: -0.31°
Magnetic North: 7.43°

Magnetic Field
Strength: 48716.0snT
Dip Angle: 60.23°
Date: 11/11/2010
Model: IGRF200510



A Schlumberger Company

West(-)/East(+) (200 ft/in)

SECTION DETAILS										
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2	8392.00	0.00	0.00	8392.00	0.00	0.00	0.00	0.00	0.00	
3	9074.47	78.47	282.56	8880.24	86.72	-389.18	11.50	282.56	126.56	
4	9747.56	90.00	359.69	8960.00	570.95	-773.07	11.50	87.39	647.94	Heal TGT(ALD#8)
5	16972.63	90.00	359.69	8960.00	7795.92	-811.72	0.00	0.00	7838.06	PBHL TGT(ALD#8)


WELL DETAILS: #8H

Ground Elevation: 3452.20
RK9 Elevation: WELL @ 3477.20ft (25' KB Correction)
Rig Name: 25' KB Correction

+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Slot
0.00	0.00	461866.520	719854.610	32° 16' 6.331 N	103° 45' 20.753 W	

WELLBORE TARGET DETAILS (MAP CO-ORDINATES)

Name	TVD	+N/-S	+E/-W	Northing	Easting	Shape
Heal TGT(ALD#8)	8960.00	570.95	-773.07	462437.470	719081.540	Point
PBHL TGT(ALD#8)	8960.00	7795.92	-811.72	469662.440	719042.890	Point



Plan: Plan #1 (#8H/OH)

Created By: Nate Bingham Date: 14:54, November 11 2010



Pathfinder
Pathfinder X & Y Planning Report



Company: Devon Energy, Inc.
Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #8H
TVD Reference: WELL @ 3477.20ft (25' KB Correction)
MD Reference: WELL @ 3477.20ft (25' KB Correction)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: Midland Database

Project	Eddy County		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Aldabra "27" Fed		
Site Position:		Northing:	461,950.580 ft
From:	Map	Easting:	714,427.100 ft
Position Uncertainty:	2.00 ft	Slot Radius:	6-1/8 "
		Latitude:	32° 16' 7.447 N
		Longitude:	103° 46' 23.961 W
		Grid Convergence:	0.30 °

Well		#8H				
Well Position	+N/-S	0.00 ft	Northing:	461,866.520 ft	Latitude:	32° 16' 6.331 N
	+E/-W	0.00 ft	Easting:	719,854.610 ft	Longitude:	103° 45' 20.753 W
Position Uncertainty	0.00 ft		Wellhead Elevation:	ft	Ground Level:	3,452.20 ft

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	11/11/10	7.73	60.23	48,716

Design	Plan #1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(ft)	(ft)	(ft)	(°)
	0.00	0.00	0.00	354.06

Survey Tool Program	Date	11/11/10		
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description
0.00	16,972.63	Plan #1 (OH)	Pathfinder	Pathfinder MWD



Pathfinder
Pathfinder X & Y Planning Report



Company: Devon Energy, Inc.
Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #8H
TVD Reference: WELL @ 3477.20ft (25' KB Correction)
MD Reference: WELL @ 3477.20ft (25' KB Correction)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: Midland Database

Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
0.00	0.00	0.00	0.00	-3,477.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
100.00	0.00	0.00	100.00	-3,377.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
200.00	0.00	0.00	200.00	-3,277.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
300.00	0.00	0.00	300.00	-3,177.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
400.00	0.00	0.00	400.00	-3,077.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
500.00	0.00	0.00	500.00	-2,977.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
600.00	0.00	0.00	600.00	-2,877.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
700.00	0.00	0.00	700.00	-2,777.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
800.00	0.00	0.00	800.00	-2,677.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
900.00	0.00	0.00	900.00	-2,577.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
1,000.00	0.00	0.00	1,000.00	-2,477.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
1,100.00	0.00	0.00	1,100.00	-2,377.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
1,200.00	0.00	0.00	1,200.00	-2,277.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
1,300.00	0.00	0.00	1,300.00	-2,177.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
1,400.00	0.00	0.00	1,400.00	-2,077.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
1,500.00	0.00	0.00	1,500.00	-1,977.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
1,600.00	0.00	0.00	1,600.00	-1,877.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
1,700.00	0.00	0.00	1,700.00	-1,777.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
1,800.00	0.00	0.00	1,800.00	-1,677.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
1,900.00	0.00	0.00	1,900.00	-1,577.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
2,000.00	0.00	0.00	2,000.00	-1,477.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
2,100.00	0.00	0.00	2,100.00	-1,377.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
2,200.00	0.00	0.00	2,200.00	-1,277.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
2,300.00	0.00	0.00	2,300.00	-1,177.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
2,400.00	0.00	0.00	2,400.00	-1,077.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
2,500.00	0.00	0.00	2,500.00	-977.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
2,600.00	0.00	0.00	2,600.00	-877.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61



Pathfinder
Pathfinder X & Y Planning Report

PATHFINDER
A Schlumberger Company

Company: Devon Energy, Inc.
Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #8H
TVD Reference: WELL @ 3477.20ft (25' KB Correction)
MD Reference: WELL @ 3477.20ft (25' KB Correction)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: Midland Database

Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
2,700.00	0.00	0.00	2,700.00	-777.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
2,800.00	0.00	0.00	2,800.00	-677.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
2,900.00	0.00	0.00	2,900.00	-577.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
3,000.00	0.00	0.00	3,000.00	-477.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
3,100.00	0.00	0.00	3,100.00	-377.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
3,200.00	0.00	0.00	3,200.00	-277.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
3,300.00	0.00	0.00	3,300.00	-177.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
3,400.00	0.00	0.00	3,400.00	-77.20	0.00	0.00	0.00	0.00	461,866.52	719,854.61
3,500.00	0.00	0.00	3,500.00	22.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
3,600.00	0.00	0.00	3,600.00	122.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
3,700.00	0.00	0.00	3,700.00	222.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
3,800.00	0.00	0.00	3,800.00	322.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
3,900.00	0.00	0.00	3,900.00	422.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
4,000.00	0.00	0.00	4,000.00	522.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
4,100.00	0.00	0.00	4,100.00	622.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
4,200.00	0.00	0.00	4,200.00	722.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
4,300.00	0.00	0.00	4,300.00	822.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
4,400.00	0.00	0.00	4,400.00	922.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
4,500.00	0.00	0.00	4,500.00	1,022.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
4,600.00	0.00	0.00	4,600.00	1,122.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
4,700.00	0.00	0.00	4,700.00	1,222.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
4,800.00	0.00	0.00	4,800.00	1,322.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
4,900.00	0.00	0.00	4,900.00	1,422.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
5,000.00	0.00	0.00	5,000.00	1,522.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
5,100.00	0.00	0.00	5,100.00	1,622.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
5,200.00	0.00	0.00	5,200.00	1,722.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
5,300.00	0.00	0.00	5,300.00	1,822.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61



Pathfinder
Pathfinder X & Y Planning Report

PATHFINDER
A Schlumberger Company

Company: Devon Energy, Inc.
Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #8H
TVD Reference: WELL @ 3477.20ft (25' KB Correction)
MD Reference: WELL @ 3477.20ft (25' KB Correction)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: Midland Database

Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
5,400.00	0.00	0.00	5,400.00	1,922.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
5,500.00	0.00	0.00	5,500.00	2,022.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
5,600.00	0.00	0.00	5,600.00	2,122.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
5,700.00	0.00	0.00	5,700.00	2,222.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
5,800.00	0.00	0.00	5,800.00	2,322.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
5,900.00	0.00	0.00	5,900.00	2,422.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
6,000.00	0.00	0.00	6,000.00	2,522.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
6,100.00	0.00	0.00	6,100.00	2,622.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
6,200.00	0.00	0.00	6,200.00	2,722.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
6,300.00	0.00	0.00	6,300.00	2,822.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
6,400.00	0.00	0.00	6,400.00	2,922.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
6,500.00	0.00	0.00	6,500.00	3,022.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
6,600.00	0.00	0.00	6,600.00	3,122.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
6,700.00	0.00	0.00	6,700.00	3,222.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
6,800.00	0.00	0.00	6,800.00	3,322.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
6,900.00	0.00	0.00	6,900.00	3,422.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
7,000.00	0.00	0.00	7,000.00	3,522.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
7,100.00	0.00	0.00	7,100.00	3,622.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
7,200.00	0.00	0.00	7,200.00	3,722.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
7,300.00	0.00	0.00	7,300.00	3,822.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
7,400.00	0.00	0.00	7,400.00	3,922.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
7,500.00	0.00	0.00	7,500.00	4,022.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
7,600.00	0.00	0.00	7,600.00	4,122.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
7,700.00	0.00	0.00	7,700.00	4,222.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
7,800.00	0.00	0.00	7,800.00	4,322.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
7,900.00	0.00	0.00	7,900.00	4,422.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
8,000.00	0.00	0.00	8,000.00	4,522.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61



Pathfinder
Pathfinder X & Y Planning Report



Company: Devon Energy, Inc.
Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #8H
TVD Reference: WELL @ 3477.20ft (25' KB Correction)
MD Reference: WELL @ 3477.20ft (25' KB Correction)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: Midland Database

Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
8,100.00	0.00	0.00	8,100.00	4,622.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
8,200.00	0.00	0.00	8,200.00	4,722.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
8,300.00	0.00	0.00	8,300.00	4,822.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
8,392.00	0.00	0.00	8,392.00	4,914.80	0.00	0.00	0.00	0.00	461,866.52	719,854.61
8,400.00	0.92	282.56	8,400.00	4,922.80	0.01	-0.06	0.02	11.50	461,866.53	719,854.55
8,425.00	3.79	282.56	8,424.98	4,947.78	0.24	-1.07	0.35	11.50	461,866.76	719,853.54
8,450.00	6.67	282.56	8,449.87	4,972.67	0.73	-3.29	1.07	11.50	461,867.25	719,851.32
8,475.00	9.54	282.56	8,474.62	4,997.42	1.50	-6.73	2.19	11.50	461,868.02	719,847.88
8,500.00	12.42	282.56	8,499.16	5,021.96	2.54	-11.38	3.70	11.50	461,869.06	719,843.23
8,525.00	15.29	282.56	8,523.43	5,046.23	3.84	-17.22	5.60	11.50	461,870.36	719,837.39
8,550.00	18.17	282.56	8,547.37	5,070.17	5.40	-24.25	7.88	11.50	461,871.92	719,830.36
8,575.00	21.04	282.56	8,570.91	5,093.71	7.23	-32.43	10.55	11.50	461,873.75	719,822.18
8,600.00	23.92	282.56	8,594.01	5,116.81	9.31	-41.76	13.58	11.50	461,875.83	719,812.85
8,625.00	26.79	282.56	8,616.60	5,139.40	11.63	-52.21	16.98	11.50	461,878.15	719,802.40
8,650.00	29.67	282.56	8,638.63	5,161.43	14.21	-63.75	20.73	11.50	461,880.73	719,790.86
8,675.00	32.54	282.56	8,660.03	5,182.83	17.01	-76.35	24.83	11.50	461,883.53	719,778.26
8,700.00	35.42	282.56	8,680.76	5,203.56	20.05	-89.99	29.26	11.50	461,886.57	719,764.62
8,725.00	38.29	282.56	8,700.76	5,223.56	23.31	-104.62	34.02	11.50	461,889.83	719,749.99
8,750.00	41.16	282.56	8,719.99	5,242.79	26.79	-120.22	39.09	11.50	461,893.31	719,734.39
8,775.00	44.04	282.56	8,738.39	5,261.19	30.47	-136.73	44.46	11.50	461,896.99	719,717.88
8,800.00	46.91	282.56	8,755.91	5,278.71	34.34	-154.13	50.12	11.50	461,900.86	719,700.48
8,825.00	49.79	282.56	8,772.53	5,295.33	38.41	-172.36	56.05	11.50	461,904.93	719,682.25
8,850.00	52.66	282.56	8,788.18	5,310.98	42.65	-191.38	62.24	11.50	461,909.17	719,663.23
8,875.00	55.54	282.56	8,802.84	5,325.64	47.05	-211.15	68.66	11.50	461,913.57	719,643.46
8,900.00	58.41	282.56	8,816.46	5,339.26	51.61	-231.61	75.32	11.50	461,918.13	719,623.00
8,925.00	61.29	282.56	8,829.02	5,351.82	56.31	-252.70	82.18	11.50	461,922.83	719,601.91
8,950.00	64.16	282.56	8,840.47	5,363.27	61.14	-274.39	89.23	11.50	461,927.66	719,580.22



Pathfinder
Pathfinder X & Y Planning Report



Company: Devon Energy, Inc.
Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #8H
TVD Reference: WELL @ 3477.20ft (25' KB Correction)
MD Reference: WELL @ 3477.20ft (25' KB Correction)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: Midland Database

Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
8,975.00	67.04	282.56	8,850.80	5,373.60	66.09	-296.61	96.45	11.50	461,932.61	719,558.00
9,000.00	69.91	282.56	8,859.97	5,382.77	71.15	-319.31	103.83	11.50	461,937.67	719,535.30
9,025.00	72.79	282.56	8,867.97	5,390.77	76.30	-342.42	111.35	11.50	461,942.82	719,512.19
9,050.00	75.66	282.56	8,874.76	5,397.56	81.53	-365.90	118.99	11.50	461,948.05	719,488.71
9,074.47	78.47	282.56	8,880.24	5,403.04	86.72	-389.18	126.56	11.50	461,953.24	719,465.43
9,100.00	78.62	285.55	8,885.31	5,408.11	92.80	-413.45	135.11	11.50	461,959.32	719,441.16
9,125.00	78.80	288.48	8,890.20	5,413.00	99.97	-436.89	144.68	11.50	461,966.49	719,417.72
9,150.00	79.00	291.40	8,895.02	5,417.82	108.34	-459.95	155.39	11.50	461,974.86	719,394.66
9,175.00	79.23	294.32	8,899.74	5,422.54	117.87	-482.57	167.21	11.50	461,984.39	719,372.04
9,200.00	79.49	297.23	8,904.35	5,427.15	128.56	-504.69	180.13	11.50	461,995.08	719,349.92
9,225.00	79.78	300.14	8,908.85	5,431.65	140.36	-526.26	194.11	11.50	462,006.88	719,328.35
9,250.00	80.09	303.04	8,913.22	5,436.02	153.25	-547.23	209.10	11.50	462,019.77	719,307.38
9,275.00	80.42	305.94	8,917.46	5,440.26	167.20	-567.53	225.08	11.50	462,033.72	719,287.08
9,300.00	80.78	308.83	8,921.54	5,444.34	182.18	-587.13	242.00	11.50	462,048.70	719,267.48
9,325.00	81.17	311.72	8,925.46	5,448.26	198.14	-605.96	259.83	11.50	462,064.66	719,248.65
9,350.00	81.57	314.59	8,929.21	5,452.01	215.04	-623.99	278.51	11.50	462,081.56	719,230.62
9,375.00	82.00	317.47	8,932.79	5,455.59	232.85	-641.17	298.00	11.50	462,099.37	719,213.44
9,400.00	82.44	320.33	8,936.17	5,458.97	251.51	-657.45	318.25	11.50	462,118.03	719,197.16
9,425.00	82.91	323.19	8,939.36	5,462.16	270.99	-672.79	339.20	11.50	462,137.51	719,181.82
9,450.00	83.39	326.05	8,942.34	5,465.14	291.22	-687.16	360.82	11.50	462,157.74	719,167.45
9,475.00	83.89	328.90	8,945.11	5,467.91	312.17	-700.52	383.04	11.50	462,178.69	719,154.09
9,500.00	84.40	331.74	8,947.67	5,470.47	333.77	-712.84	405.80	11.50	462,200.29	719,141.77
9,525.00	84.93	334.58	8,949.99	5,472.79	355.98	-724.07	429.05	11.50	462,222.50	719,130.54
9,550.00	85.46	337.41	8,952.09	5,474.89	378.73	-734.21	452.73	11.50	462,245.25	719,120.40
9,575.00	86.01	340.24	8,953.94	5,476.74	401.98	-743.21	476.79	11.50	462,268.50	719,111.40
9,600.00	86.57	343.07	8,955.56	5,478.36	425.66	-751.06	501.15	11.50	462,292.18	719,103.55
9,625.00	87.14	345.89	8,956.93	5,479.73	449.71	-757.74	525.76	11.50	462,316.23	719,096.87



Pathfinder
Pathfinder X & Y Planning Report

PATHFINDER
A Schlumberger Company

Company: Devon Energy, Inc.
Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #8H
TVD Reference: WELL @ 3477.20ft (25' KB Correction)
MD Reference: WELL @ 3477.20ft (25' KB Correction)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: Midland Database

Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
9,650.00	87.72	348.71	8,958.05	5,480.85	474.07	-763.23	550.56	11.50	462,340.59	719,091.38
9,675.00	88.30	351.52	8,958.92	5,481.72	498.68	-767.52	575.48	11.50	462,365.20	719,087.09
9,700.00	88.88	354.34	8,959.54	5,482.34	523.48	-770.60	600.47	11.50	462,390.00	719,084.01
9,725.00	89.47	357.15	8,959.90	5,482.70	548.40	-772.45	625.45	11.50	462,414.92	719,082.16
9,747.56	90.00	359.69	8,960.00	5,482.80	570.95	-773.07	647.94	11.50	462,437.47	719,081.54
Heal TGT(ALD#8)										
9,800.00	90.00	359.69	8,960.00	5,482.80	623.39	-773.35	700.13	0.00	462,489.91	719,081.26
9,900.00	90.00	359.69	8,960.00	5,482.80	723.39	-773.89	799.65	0.00	462,589.91	719,080.72
10,000.00	90.00	359.69	8,960.00	5,482.80	823.39	-774.42	899.16	0.00	462,689.91	719,080.19
10,100.00	90.00	359.69	8,960.00	5,482.80	923.39	-774.96	998.68	0.00	462,789.91	719,079.65
10,200.00	90.00	359.69	8,960.00	5,482.80	1,023.39	-775.49	1,098.20	0.00	462,889.91	719,079.12
10,300.00	90.00	359.69	8,960.00	5,482.80	1,123.39	-776.03	1,197.71	0.00	462,989.91	719,078.58
10,400.00	90.00	359.69	8,960.00	5,482.80	1,223.38	-776.56	1,297.23	0.00	463,089.90	719,078.05
10,500.00	90.00	359.69	8,960.00	5,482.80	1,323.38	-777.10	1,396.74	0.00	463,189.90	719,077.51
10,600.00	90.00	359.69	8,960.00	5,482.80	1,423.38	-777.63	1,496.26	0.00	463,289.90	719,076.98
10,700.00	90.00	359.69	8,960.00	5,482.80	1,523.38	-778.17	1,595.78	0.00	463,389.90	719,076.44
10,800.00	90.00	359.69	8,960.00	5,482.80	1,623.38	-778.70	1,695.29	0.00	463,489.90	719,075.91
10,900.00	90.00	359.69	8,960.00	5,482.80	1,723.38	-779.23	1,794.81	0.00	463,589.90	719,075.38
11,000.00	90.00	359.69	8,960.00	5,482.80	1,823.38	-779.77	1,894.33	0.00	463,689.90	719,074.84
11,100.00	90.00	359.69	8,960.00	5,482.80	1,923.37	-780.30	1,993.84	0.00	463,789.89	719,074.31
11,200.00	90.00	359.69	8,960.00	5,482.80	2,023.37	-780.84	2,093.36	0.00	463,889.89	719,073.77
11,300.00	90.00	359.69	8,960.00	5,482.80	2,123.37	-781.37	2,192.87	0.00	463,989.89	719,073.24
11,400.00	90.00	359.69	8,960.00	5,482.80	2,223.37	-781.91	2,292.39	0.00	464,089.89	719,072.70
11,500.00	90.00	359.69	8,960.00	5,482.80	2,323.37	-782.44	2,391.91	0.00	464,189.89	719,072.17
11,600.00	90.00	359.69	8,960.00	5,482.80	2,423.37	-782.98	2,491.42	0.00	464,289.89	719,071.63
11,700.00	90.00	359.69	8,960.00	5,482.80	2,523.37	-783.51	2,590.94	0.00	464,389.89	719,071.10
11,800.00	90.00	359.69	8,960.00	5,482.80	2,623.36	-784.05	2,690.46	0.00	464,489.88	719,070.56



Pathfinder
Pathfinder X & Y Planning Report



Company: Devon Energy, Inc.
Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #8H
TVD Reference: WELL @ 3477.20ft (25' KB Correction)
MD Reference: WELL @ 3477.20ft (25' KB Correction)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: Midland Database

Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
11,900.00	90.00	359.69	8,960.00	5,482.80	2,723.36	-784.58	2,789.97	0.00	464,589.88	719,070.03
12,000.00	90.00	359.69	8,960.00	5,482.80	2,823.36	-785.12	2,889.49	0.00	464,689.88	719,069.49
12,100.00	90.00	359.69	8,960.00	5,482.80	2,923.36	-785.65	2,989.01	0.00	464,789.88	719,068.96
12,200.00	90.00	359.69	8,960.00	5,482.80	3,023.36	-786.19	3,088.52	0.00	464,889.88	719,068.42
12,300.00	90.00	359.69	8,960.00	5,482.80	3,123.36	-786.72	3,188.04	0.00	464,989.88	719,067.89
12,400.00	90.00	359.69	8,960.00	5,482.80	3,223.36	-787.26	3,287.55	0.00	465,089.88	719,067.35
12,500.00	90.00	359.69	8,960.00	5,482.80	3,323.35	-787.79	3,387.07	0.00	465,189.87	719,066.82
12,600.00	90.00	359.69	8,960.00	5,482.80	3,423.35	-788.33	3,486.59	0.00	465,289.87	719,066.28
12,700.00	90.00	359.69	8,960.00	5,482.80	3,523.35	-788.86	3,586.10	0.00	465,389.87	719,065.75
12,800.00	90.00	359.69	8,960.00	5,482.80	3,623.35	-789.40	3,685.62	0.00	465,489.87	719,065.21
12,900.00	90.00	359.69	8,960.00	5,482.80	3,723.35	-789.93	3,785.14	0.00	465,589.87	719,064.68
13,000.00	90.00	359.69	8,960.00	5,482.80	3,823.35	-790.47	3,884.65	0.00	465,689.87	719,064.14
13,100.00	90.00	359.69	8,960.00	5,482.80	3,923.35	-791.00	3,984.17	0.00	465,789.87	719,063.61
13,200.00	90.00	359.69	8,960.00	5,482.80	4,023.34	-791.54	4,083.68	0.00	465,889.86	719,063.07
13,300.00	90.00	359.69	8,960.00	5,482.80	4,123.34	-792.07	4,183.20	0.00	465,989.86	719,062.54
13,400.00	90.00	359.69	8,960.00	5,482.80	4,223.34	-792.61	4,282.72	0.00	466,089.86	719,062.00
13,500.00	90.00	359.69	8,960.00	5,482.80	4,323.34	-793.14	4,382.23	0.00	466,189.86	719,061.47
13,600.00	90.00	359.69	8,960.00	5,482.80	4,423.34	-793.68	4,481.75	0.00	466,289.86	719,060.93
13,700.00	90.00	359.69	8,960.00	5,482.80	4,523.34	-794.21	4,581.27	0.00	466,389.86	719,060.40
13,800.00	90.00	359.69	8,960.00	5,482.80	4,623.34	-794.75	4,680.78	0.00	466,489.86	719,059.86
13,900.00	90.00	359.69	8,960.00	5,482.80	4,723.33	-795.28	4,780.30	0.00	466,589.85	719,059.33
14,000.00	90.00	359.69	8,960.00	5,482.80	4,823.33	-795.82	4,879.81	0.00	466,689.85	719,058.79
14,100.00	90.00	359.69	8,960.00	5,482.80	4,923.33	-796.35	4,979.33	0.00	466,789.85	719,058.26
14,200.00	90.00	359.69	8,960.00	5,482.80	5,023.33	-796.89	5,078.85	0.00	466,889.85	719,057.72
14,300.00	90.00	359.69	8,960.00	5,482.80	5,123.33	-797.42	5,178.36	0.00	466,989.85	719,057.19
14,400.00	90.00	359.69	8,960.00	5,482.80	5,223.33	-797.96	5,277.88	0.00	467,089.85	719,056.65
14,500.00	90.00	359.69	8,960.00	5,482.80	5,323.33	-798.49	5,377.40	0.00	467,189.85	719,056.12



Pathfinder
Pathfinder X & Y Planning Report



Company: Devon Energy, Inc.
Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #8H
TVD Reference: WELL @ 3477.20ft (25' KB Correction)
MD Reference: WELL @ 3477.20ft (25' KB Correction)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: Midland Database

Planned Survey

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	TVDSS (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Northing (ft)	Easting (ft)
14,600.00	90.00	359.69	8,960.00	5,482.80	5,423.32	-799.03	5,476.91	0.00	467,289.84	719,055.58
14,700.00	90.00	359.69	8,960.00	5,482.80	5,523.32	-799.56	5,576.43	0.00	467,389.84	719,055.05
14,800.00	90.00	359.69	8,960.00	5,482.80	5,623.32	-800.10	5,675.94	0.00	467,489.84	719,054.51
14,900.00	90.00	359.69	8,960.00	5,482.80	5,723.32	-800.63	5,775.46	0.00	467,589.84	719,053.98
15,000.00	90.00	359.69	8,960.00	5,482.80	5,823.32	-801.17	5,874.98	0.00	467,689.84	719,053.44
15,100.00	90.00	359.69	8,960.00	5,482.80	5,923.32	-801.70	5,974.49	0.00	467,789.84	719,052.91
15,200.00	90.00	359.69	8,960.00	5,482.80	6,023.32	-802.24	6,074.01	0.00	467,889.84	719,052.37
15,300.00	90.00	359.69	8,960.00	5,482.80	6,123.31	-802.77	6,173.53	0.00	467,989.83	719,051.84
15,400.00	90.00	359.69	8,960.00	5,482.80	6,223.31	-803.31	6,273.04	0.00	468,089.83	719,051.30
15,500.00	90.00	359.69	8,960.00	5,482.80	6,323.31	-803.84	6,372.56	0.00	468,189.83	719,050.77
15,600.00	90.00	359.69	8,960.00	5,482.80	6,423.31	-804.38	6,472.08	0.00	468,289.83	719,050.23
15,700.00	90.00	359.69	8,960.00	5,482.80	6,523.31	-804.91	6,571.59	0.00	468,389.83	719,049.70
15,800.00	90.00	359.69	8,960.00	5,482.80	6,623.31	-805.45	6,671.11	0.00	468,489.83	719,049.16
15,900.00	90.00	359.69	8,960.00	5,482.80	6,723.31	-805.98	6,770.62	0.00	468,589.83	719,048.63
16,000.00	90.00	359.69	8,960.00	5,482.80	6,823.30	-806.52	6,870.14	0.00	468,689.82	719,048.09
16,100.00	90.00	359.69	8,960.00	5,482.80	6,923.30	-807.05	6,969.66	0.00	468,789.82	719,047.56
16,200.00	90.00	359.69	8,960.00	5,482.80	7,023.30	-807.59	7,069.17	0.00	468,889.82	719,047.02
16,300.00	90.00	359.69	8,960.00	5,482.80	7,123.30	-808.12	7,168.69	0.00	468,989.82	719,046.49
16,400.00	90.00	359.69	8,960.00	5,482.80	7,223.30	-808.66	7,268.21	0.00	469,089.82	719,045.95
16,500.00	90.00	359.69	8,960.00	5,482.80	7,323.30	-809.19	7,367.72	0.00	469,189.82	719,045.42
16,600.00	90.00	359.69	8,960.00	5,482.80	7,423.30	-809.73	7,467.24	0.00	469,289.82	719,044.88
16,700.00	90.00	359.69	8,960.00	5,482.80	7,523.29	-810.26	7,566.75	0.00	469,389.81	719,044.35
16,800.00	90.00	359.69	8,960.00	5,482.80	7,623.29	-810.80	7,666.27	0.00	469,489.81	719,043.81
16,900.00	90.00	359.69	8,960.00	5,482.80	7,723.29	-811.33	7,765.79	0.00	469,589.81	719,043.28
16,972.63	90.00	359.69	8,960.00	5,482.80	7,795.92	-811.72	7,838.06	0.00	469,662.44	719,042.89

PBHL TGT(ALD#8)



Pathfinder
Pathfinder X & Y Planning Report



Company: Devon Energy, Inc.
Project: Eddy County
Site: Aldabra "27" Fed
Well: #8H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference: Well #8H
TVD Reference: WELL @ 3477.20ft (25' KB Correction)
MD Reference: WELL @ 3477.20ft (25' KB Correction)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: Midland Database

Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
PBHL TGT(ALD#8) - plan hits target center - Point	0.00	0.00	8,960.00	7,795.92	-811.72	469,662.440	719,042.890	32° 17' 23.518 N	103° 45' 29.720 W
Heal TGT(ALD#8) - plan hits target center - Point	0.00	0.00	8,960.00	570.95	-773.07	462,437.470	719,081.540	32° 16' 12.022 N	103° 45' 29.721 W

Checked By: _____ Approved By: _____ Date: _____

NOTES REGARDING BLOWOUT PREVENTERS

Devon Energy Production Company, LP


Aldabra 27 Fed Com 8H

Surface Location: 85' FSL & 420' FWL, Unit M, Sec 26 T23S R31E, Eddy, NM


Bottom Hole Location: 2600' FSL & 350' FEL, Unit I, Sec 22 T23S R31E, Eddy, NM

1. Drilling nipple will be constructed so it can be removed mechanically without the aid of a welder. The minimum internal diameter will equal BOP bore.
2. Wear ring will be properly installed in head.
3. Blowout preventer and all associated fittings will be in operable condition to withstand a minimum 3000 psi working pressure.
4. All fittings will be flanged.
5. A full bore safety valve tested to a minimum 3000 psi WP with proper thread connections will be available on the rotary rig floor at all times.
6. All choke lines will be anchored to prevent movement.
7. All BOP equipment will be equal to or larger in bore than the internal diameter of the last casing string.
8. Will maintain a kelly cock attached to the kelly.
9. Hand wheels and wrenches will be properly installed and tested for safe operation.
10. Hydraulic floor control for blowout preventer will be located as near in proximity to driller's controls as possible.
11. All BOP equipment will meet API standards and include a minimum 40 gallon accumulator having two independent means of power to initiate closing operation.


13-5/8" x 3,000 psi BOP Stack



13-5/8" 3M BOPE & Closed Loop Equipment Schematic



New





Fluid Technology

ContiTech Beattie Corp.
Website: www.contitechbeattie.com

Monday, June 14, 2010

RE: Drilling & Production Hoses
Lifting & Safety Equipment

To Helmerich & Payne,

A Continental ContiTech hose assembly can perform as intended and suitable for the application regardless of whether the hose is secured or unsecured in its configuration. As a manufacturer of High Pressure Hose Assemblies for use in Drilling & Production, we do offer the corresponding lifting and safety equipment, this has the added benefit of easing the lifting and handling of each hose assembly whilst affording hose longevity by ensuring correct handling methods and procedures as well as securing the hose in the unlikely event of a failure; but in no way does the lifting and safety equipment affect the performance of the hoses providing the hoses have been handled and installed correctly. It is good practice to use lifting & safety equipment but not mandatory.


Should you have any questions or require any additional information/clarifications then please do not hesitate to contact us.


ContiTech Beattie is part of the Continental AG Corporation and can offer the full support resources associated with a global organization.

Best regards,


Robin Hodgson
Sales Manager
ContiTech Beattie Corp

ContiTech Beattie Corp,
11535 Brittmoore Park Drive,
Houston, TX 77041
Phone: +1 (832) 327-0141
Fax: +1 (832) 327-0148
www.contitechbeattie.com



QUALITY CONTROL INSPECTION AND TEST CERTIFICATE						CERT. N°: 1713	
PURCHASER: ContiTech Beattie Co.						P.O. N°: 002808	
CONTITECH ORDER N°: 426127			HOSE TYPE: 3" ID Choke and Kill Hose				
HOSE SERIAL N°: 53622			NOMINAL / ACTUAL LENGTH: 10,67 m				
W.P. 68,96 MPa		10000 psi	T.P. 103,4 MPa		15000 psi	Duration: 60 min.	
Pressure test with water at ambient temperature							
See attachment. (1 page)							
↑ 10 mm = 10 Min. → 10 mm = 25 MPa							
COUPLINGS Type		Serial N°		Quality		Heat N°	
3" coupling with 4 1/16" Flange end		5503 2029		AISI 4130 AISI 4130		N1590P 27566	
INFOCHIP INSTALLED						API Spec 16 C Temperature rate:"B"	
All metal parts are flawless				Hose conform to NACE MR 01-75			
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER INSPECTED AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.							
STATEMENT OF CONFORMITY: We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.							
COUNTRY OF ORIGIN HUNGARY/EU							
Date: 25. August. 2008	Inspector		Quality Control ContiTech Rubber Industrial Kft. Quality Control Dept.  				

HARTMANN &



Confitech Rubber
Industrial Kft.
Quality Control Dept.
(2)

DISTRICT I --- CHECKLIST FOR INTENTS TO DRILL

Operator DEVON ENERGY PROD CO LP OGRID # 6137
 38560 Well Name & # ALDABRAA 27 FED COM # 8 H Surface Type (F) (S) (P)
 Location: UL 23, Sect 27, Township 23 s, RNG 31 e, Sub-surface Type (F) (S) (P)
23 31

A. Date C101 rec'd / / C101 reviewed / /

B. 1. Check mark, Information is OK on Forms:

OGRID X, BONDING FED PROP CODE X WELL # 4, SIGNATURE

2. Inactive Well list as of: 3/30/11 # wells 1499 # Inactive wells 3

a. District Grant APD but see number of inactive wells:

No letter required X; Sent Letter to Operator , to Santa Fe

3. Additional Bonding as of: 3/30/11

a. District Denial because operator needs addition bonding:

No Letter required X; Sent Letter to Operator , To Santa Fe

b. District Denial because of Inactive well list and Financial Assurance:

No Letter required X; Sent Letter to Operator , To Santa Fe

C. C102 YES , NO , Signature

1. Pool WILDCAT; BONE SHINE Code 96403

a. Dedicated acreage 240, What Units 22: IP 27: AHIP

b. SUR. Location Standard : Non-Standard Location X

c. Well shares acres: Yes , No , # of wells plus this well # #7

2. 2nd. Operator in same acreage, Yes , No X

Agreement Letter , Disagreement letter

3. Intent to Directional Drill Yes X, No

a. Dedicated acreage 240, What Units 22: IP 27: AHIP

b. Bottomhole Location Standard , Non-Standard Bottomhole X

4. Downhole Commingle: Yes , No X

a. Pool #2 , Code , Acres

Pool #3 , Code , Acres

Pool #4 , Code , Acres

5. POTASH Area Yes , No FED

D. Blowout Preventer Yes X, No

E. H2S Yes X, No Part of FED

F. C144 Pit Registration Yes , No X need

G. Does APD require Santa Fe Approval:

1. Non-Standard Location: Yes X, No , NSL #

2. Non-Standard Proration: Yes , No X, NSP #

3. Simultaneous Dedication: Yes , No X, SD #

Number of wells Plus #

4. Injection order Yes , No X; PMX # or WFX #

5. SWD order Yes , NO X; SWD #

6. DHC from SF ; DHC-HOB ; Holding

7. OCD Approval Date / /

API #30-015--38632

8. Reviewers KD