


RECEIVED


SEP 13 1996

OIL CON. DIV.  
PAGE 9



13-3/8", 54#, H-40 @ 238'  
w/250 sx cement

8-5/8", 24#, K-55 @ 1000'  
w/765 sx cement



Approximate top of cement 4170'

*3/8 holes in 2 3/8 EUE (3 Holes)  
@ 4700, 4685, + 4670  
(6-28-96)*

Perforations  
Upper-Wolfcamp 4670-4716  
*260*

DV Tool @ 5000'  
Cemented upper stage through DV  
Tool @ 5000' w/250 sx cement

2" EUE, 4.7#, J-55 tubing  
set @ 7026'

Approximate top of cement 6600'

Otis Sliding Sleeve  
1 jt above packer @ 6994'

4 1/2", 10.5# & 11.6#, K-55 @ 7210'  
w/200 sx cement

4 1/2" Otis Retrievmatic  
Packer @ 7026' w/On-Off  
tool above packer  
1.875 Profile

*2 3/8 Bridge Plug set (6-28-96)*

Atoka perforations 7100-7116'

TOTAL DEPTH 7215'

SCHMATIC DRAWING  
BEARD OIL COMPANY  
MANI AD \* 1